



Local Project Administration

Certification Course Manual & Reference Guide

February 2005

Construction Administration

Construction Project Finalization

STATE OF MAINE DEPARTMENT OF TRANSPORTATION

TRANSPORTATION BUILDING



AUGUSTA, MAINE 04333-0016



JOHN G, MELROSE Commissioner

March 30, 2002

Re: Project # STP-4217(10)X

Allan Haggan
Assistant Program Manager
Maine Department of Transportation
Augusta, Maine 04333

Dear Allan:

On March 1, 2002 a Preconstruction Conference for the Limerick project was held at the Scarborough Division Office. The following attended:

Jim Ferguson, MDOT
Robert Libby, Limerick Water & Sewer
Rick Paraschak, MDOT
John Cleveland, Consultant
Joyce Noel, MDOT
Tom Shaw, Gorham Sand & Gravel
Holly Anderson, MDOT
Jim Shaw, Gorham Sand & Gravel
Christa Boucher, MDOT
Scott Doucette, Gorham Sand & Gravel
Eric Shepherd, MDOT

Peter Brown, MDOT
Brent Chesley, Wyman & Simpson, Inc.
Tim Sawtelle, Dirigo Eng.
Russ Welch, Wyman & Simpson, Inc.
Joanne Andrews, Selectman
Don Ettinger, HNTB
Martha Hamilton, Selectman
Chris Cucco, HNTB
Kenneth Laughlin, Selectman
Jerry Quirion, MDOT
Scott Doucette, Gorham Sand & Gravel

The following items were discussed:

 Tom Shaw asked if the DOT would consider raising the proposed grade of the drainage in the area where the existing water and sewer had already been replaced.
 He expressed concern that there would be many areas of conflict with the water services and the water main if we did not redesign the drainage in the area of the hill. Tom also stated that he was concerned that damage might occur to the water main while blasting and removing ledge to install the new storm drainage.

Tom expressed that he felt that the depth of the proposed drainage as shown on the plan was unusually deep, unlike the standards that he had experienced on other

rojects.

I said that the depths of the drainage as shown were within the perimeters of standard design used by the DOT. I also stated that we would do everything possible to eliminate conflicts with the sewer and water main; but water services in most cases would have to be moved in the event of a conflict with the new drainage. I also explained that the ledge was shown on the plans and that care would have to be exercised in order to prevent damage to the existing utilities; in some cases ledge may have to be removed by means other than blasting.

Tom asked who would be paying for the relocation of the utilities and if damage occurred while blasting, who would pay for that.

I stated that in the event that a conflict could not be avoided and the utility needed to be moved, the utility would be responsible. I also stated that damage, as the result of blasting was the responsibility of the Contractor.

I said that during the design phase care was given to design the system to avoid as many conflicts as possible.

This topic was discussed in great length and it was agreed that the DOT would look at a proposal from Gorham Sand & Gravel to raise the drainage, if after further review within the Department and HNTB, raising the drainage would not reduce its effectiveness or cause a detrimental effect to the base.

- 2. Russ Welch said that Wyman & Simpson were in the process of reviewing the feasibility of proposing the use of precast deck panels on the bridge.
- 3. I informed Gorham Sand & Gravel that Ron Taylor of Inland Fisheries and Wildlife had contacted me and requested that I ask if they would be interested in building the boat ramp and other associated work using Limerick project bid prices. I told them I would provide them with a set of plans and to please notify me of their decision.
- 4. Addendum#1: Discussed all items affected by the addendum. The issue of the Sediment Tank Unit Testing Procedure was the item that was of most concern to Gorham Sand & Gravel. Joyce Noel noted that she would like to see the testing requirements changed and remove the Contract Payment Retention clause.
- 5. Submittals: The Emergency Contact List, Schedule of Work, Soil Erosion & Water Pollution Control Plan were discussed. The Contractor was provided with a blank copy of the Emergency Contact List to fill out their numbers. I stated that the S.E.& W.P. Plan would need to be accepted and implemented prior to any soil disturbance on the project. The QC Plans for both Concrete and Pavement were said to be in the makings. I noted that the Concrete QC plan would have to be accepted prior to any concrete being used and that the Paving QC Plan needed to be approved before

holding the Prepaving Conference. I asked that the Contactor review the requirements for all necessary item submittals and to note their time allowances.

- 6. Performance Ratings: Discussed the Departments usage of the Contractors performance reviews. I noted that I needed to get them a copy.
- 7. Progress Meetings: Discussed that meetings would be held on a bi-weekly basis as needed to discuss any concerns the Contractor or other involved parties may have in regard to the progress of the project.

The following items in the Special Provisions were reviewed.

- 1. Instream Work: Instream work is allowed from 7/15 to 9/30.
- Temporary Pavement: Discussed Special Provision requirement that Contractor replace pavement after installing drainage in areas that carry traffic with a minimum of 3 inches of acceptable hot or cold bituminous mixture.
 Tom Shaw asked if they could use reclaim instead of hot or cold bituminous mixture. I stated that my experience in the past with reclaim was that it did not hold up as good as what was required by the contract and that it would not be accepted as a substitute. I did note that the contract required the drainage trenches be patched on a daily basis, but I would allow them to wait till Friday of each week if they so desired.
- 3. 106.3.4 Storage: Discussed that the Contractor should not use private property for storage without the written permission of the Owner and that they were required to furnish copies if requested by the Department.
- 4. Section 107: Noted that all drainage, paved drives, sidewalks and bridgework are to be complete at the time of winter suspension and that the specified contract completion date is June 6, 2003.
- 5. Section 203: Discussed the utilization requirements of salvaged pavement.
- 6. Section 304: Discussed the surcharge requirements of the contract.
- 7. Section 525 (Dry Laid Retaining Wall): Reviewed entire section, with specific notation of the construction requirements that state the wall shall be built by a skilled craftsperson, that the stones shall be cleaned and that care shall be taken to expose weathered faces.
- 8. Section 615: Discussed loam requirements, that the Department may require the Contractor to test the loam. Also the placing requirements were discussed.
- 9. Section 637: Dust control of the project was discussed. I stated that the abutters along the project put up with a lot during the construction and that I felt we needed to do a good job controlling dust so that it did not get out of control. I noted that as required

by this contract failure to maintain dust control for the duration of the project could result in a project shutdown until dust is under control again.

10. Section 652: Discussed that the contract requires that a minimum roadway width of 22 feet for two-way traffic and a minimum of 11 feet for one-way traffic be maintained. Also noted was that no material or equipment is to be stored within 10 feet of the established travel lanes.

Sincerely,

Jim Ferguson

MDOT Project Resident


CC: Contractor

J. Noel


H. Anderson

File

PROJECT RECORD KEEPING MANUAL







Maine Department of Transportation
February 2005



TABLE OF CONTENTS

SECTION 10	8 MEASUREMENT AND PAYMENT	
108.1		4
108.2	Quantities for Progress Payments	
108.21	Using the Progress Estimate Form – Paper Copy	
108.22	Using the Progress Estimate Form - Field Manager	Ŕ
108.3	Quantities for Final Payment.	8
.00.0	qualities for a main aymonia	.0
Section 109	Contract Modifications, Work Orders and Resident Work	Orc
109.1	General	11
109.2	Conditions Requiring Work Orders	11
109.3	Contents of the Work Order	11
109.4	Resident's Work Orders	12
109.5	Work Orders Requiring Supervisor Approval	12
109.6	Work Orders Requiring Federal Approval	
109.7	Method of Payment for the Work	
Section 200		
201.5	Clearing, Tree and Stump Removal	14
202.5	Removal of Structures, Obstructions, and Pavement	
203.5	Excavation	
203.6	Borrow	20
206.5	Structural Excavation	23
Section 300	Bases	
	Aggregate Base and Subbase	25
	309 Recycled Pavement.	
007.00	500 Hodysted Fuvernont.	21
<u>Section 400</u> 401.5 ⊢	Hot Mix Asphalt Pavement Iot Mix Asphalt Pavement	28
Section 500	Structures	
	oundation Piles	29
	Structural Concrete	
	Reinforcing Steel	
504.5 S	Structural Steel	32
	hear Connectors	
	Railings	
507.5 N	Aembrana Waterproofing	30 27
500.5 N	Iembrane Waterproofingtructural Plate Pipes and Arches	٥/ ٥٥
510.5 5	pecial Detour	39
511.5 0	Cofferdams	40
513.5 5	lope Protection	41
	rotective Coatings for Concrete Surfaces	
	lehabilitation of Structural Concrete	
	xpansion Devices, Non-Modular	
523.5 P	ot Bearings	45
525.5 G	iranite Masonry	46
526.5 C	oncrete Barrier	47
Section 600	Miscellaneous Construction	
	604.5 & 605.5 Pipe Culverts, Storm Drains, Manholes, Catch Basins and	
000.0, 0	Underdrains	48
606.5 G	aurdrail	49
		50

TABLE OF CONTENTS CONT'

610.5 Stone Fill, Riprap, Slope Blanket and Stone Ditch	
615.5, 618.5 Loam and Seeding	
626.5 Foundations, Conduit and Junction Boxes	
631.5 Hand Labor & Equipment Rental	. 54
0 11 000 B 11 (B 1 1B 1 10)	
Section 900 Preparation of Project Records and Closeout	
900.1 General	55
Section 901 Preparation of Project Records	
902.1 General	55
902.2 Project Diary	55
902.3 Final Quantity Book	
902.4 Construction Book	
902.5 Drainage Book	56
902.6 Inspectors Diary	. 57
902.7 Final Quantity Computation Book	
902.8 Testing File	57
902.9 Miscellaneous Project Records	58
Section 902 Review, Closeout & Final Payment	
902.0 General	58
902.1 Review	
902.2 Closeout.	
902.3 Final Payment	
Appendix A Sample Project Documentation	
Sample Project Diary Entries	63
Sample Final Quantity Entries	65
Sample Construction Book Entries	80
Sample Inspectors Diary	89
Appendix B Sample Memo and Forms	
Sample Time Charge Report	06
Sample Right of Way Encroachment Memo.	90
Sample Waste Dump Authorization	
Sample Daily Report of Equipment Rental Form	
Sample Review Guidelines;	99
Overlay Projects	100
Full Construction Projects	
Bridge Projects	
Sample Onsite Review Guidelines	
Sample Contractor Evaluation.	
Sample Accident Report	
Sample Payroll Interview	

SECTION 108 - MEASUREMENT AND PAYMENT

108.1 General.

This Section describes, in general, Departmental policies and acceptable methods for measuring and computing contract quantities for progress and final payments. Divisions 200 through 600 and 900 of this Manual explain in more detail, the requirements and procedures to follow.

There are two systems in use and acceptable to the Department for documenting and measuring quantities for payment: the traditional "paper" method, the computer software program Field Manager - Field Book and Field Pad method. Residents are encouraged to use the software program when feasible.

If the Resident chooses to use the paper method, they will have the following project records; a Final Quantity Book, a Final Quantity Computations Book, a Project Diary, Testing file and a Construction Book. Other fieldbooks may be required, such as a Drainage Book, depending on the complexity of the project. If Field Manager is used, the project records will consist of an Item History to Date instead of the Final Quantity Book, a Daily Diary, and Inspectors' Daily Reports. The Inspector's Daily Report is needed to generate progress estimate quantities. A Construction Book is almost always necessary; it is policy of the Department and good record practice that original field measurements must be entered in a bound fieldbook or PDA. The Final Quantity Computations Book may or may not required, depending on the extent of computations needed to figure quantities.

Division 900 of this Manual explains further, and in more detail, project records required. It is suggested that you study Division 900 before proceeding beyond Sections 108 and 109.

For anyone needing training in the use of Field Manager, the Contracts Section will provide instruction in the application of this software program. You should contact the Contracts Section either directly or through your Supervisor for help.

108.2 Quantities for Progress Payments

After the formalities of contract award have been completed, the Contracts Section will initiate the first payment, which is Mobilization. The Resident will receive either a paper copy of the first estimate paid or an electronic transfer, depending on whether or not Field Manager is being used. The Resident should advise the Contracts Section, preferably before the contract is awarded, whether their will use paper or Field Manager to make progress payments. The Department encourages the use of Field Manager.

It is important to our highway and bridge contractors that they receive prompt and full payment of all monies due them for work satisfactorily performed. Unnecessary delay in paying the Contractor increases his or her cost of doing business, and these costs are ultimately passed on to the Department in the form of higher bid prices on future contracts. The Contractor is to be paid, on each progress estimate, the full estimated value of the work satisfactorily completed. The Resident should not hold payment of money due the Contractor other than what is sufficient to cover work still remaining to be done under a particular item. Quantities should be current to the end of the pay period, particularly for hot mix asphalt items because of the time-dependent nature of the asphalt escalator price adjustment Specifications. If a significant overpayment or underpayment is detected following the submission of a progress estimate, an additional estimate correcting the error should be submitted to the Contracts Section immediately. Section 108.2 of the Specifications further explains procedures for making progress payments

Contract Specifications require the Department to pay the Contractor a minimum of once a month, but it is policy to make a progress payment every two weeks. The Resident will determine the quantities or the Contractor may submit, as allowed in Section 108.2, a requisition for payment. The Resident will review the figures submitted by the Contractor and so note in the project records. The estimate will then be forwarded to the Contracts Section, either electronically or on a paper copy, for payment. The Contracts Section will process the progress estimate for payment minus a retent. This retained amount is based upon Section 108.3 of the Specifications.

Quantities for progress payment will be estimated with the help of the following guidelines:

Quantities paid by the unit: Progress estimates can be based on a percent of the estimated quantity or on actual field measurements of the work done to date. The Resident is cautioned not to pay too high a percent of the estimated quantity without first checking the Engineer's Estimate for accuracy.

Quantities paid lump sum: The Resident may pay a percent of the bid price, as work progresses; amount paid is dependent on amount of work done. Contract Specifications will state, for some items paid lump sum, what portion to pay as work progresses.

Quantities paid load count: Whether by weight or by volume, quantity to date can be readily determined from daily totals entered in the Final Quantity Book/Item History to Date.

Quantities paid by the hour or force account: Hourly work items and force account work are determined from Daily Reports of Labor and Equipment Rental.

Regardless of the methods used to arrive at quantities for progress payments, the Resident will keep on file the notes and measurements used to document payments.. These records may be needed to explain to Auditors and to the Contractor how Quantities were determined.

108.21 Using the Progress Estimate Form - Paper Copy

Estimates must be made out on the computerized print-out generated by the Contracts Section. The first form the Resident will receive will be labeled "Payment Voucher Summary" number 0001, and it will show partial payment for Item 659.10 - Mobilization. The Resident will also receive, at the same time, "Progress Estimate" number 0002. Present policy is to fax the completed estimate form to the Contracts Section for processing The resulting "Payment Voucher Summary" and the next "Progress Estimate" will be sent to the Resident as e-mail attachments.

Tracking of funding allocations requires separate cost figures for highway and bridge expenditures, for what is federally participating and federally non-participating, and for town and utility reimbursements. Each category of funds is designated by a number as, for example: 0001 for highway, 0002 for bridge. Categories are assigned by the Project Manager. Work done under the original contract items or added to the project, whether unit price, lump sum or force account, must be coded to the correct category, i.e., highway, bridge, non-participating, etc.

<u>Progress Estimate. Final Quantity Estimate or Final Estimate.</u> During the progress of work, the Resident will place a checkmark on the "Progress Estimate" line. When the project is closed out with the Contracts Section, the "Final Quantity Estimate" line will be checked and the words "Final Quantity Estimate" will be written on the "Comment" line in the upper right-hand corner of the estimate. The Final Estimate will be made out by the Contracts Section when the retent is released and paid off.

<u>Pay Period Ending – Year, Month, Day.</u> The date, entered by the Resident, should be the end date for the period the work has been done. This end date will be as current with the work as is practicable; it will be the middle and/or the last day of the month and not the first day of the next month for the purposes of figuring asphalt escalator price adjustments.

<u>New Items.</u> This section is used to make modifications to the contract, such as: items from one Pin to another Pin under the same contract, new items added by contract modification paid by agreed unit price, lump sum or force account, categories added, or work made non-participating.

Modifications are made as follows:

Catg #: Enter the appropriate four digit category number.

<u>Item # (Or None):</u> The item number can be obtained from the Bid Item Dictionary located at http://www.maine.gov/mdot/contractor-consultant-information/item_dictionary_english.htm. If the item does not appear in the Dictionary, print the word "None" in its place, and write a very brief description of the item or work order in the "Description" column.

<u>Authorized Quantity:</u> Enter the estimated quantity shown on the Work Order. If there is no work order, enter the actual quantity.

Quantity to Date: Enter the quantity you want to pay at this time. Figures can be carried to two decimal places.

Unit Price: Enter the unit price shown on the Work Order, or defined in the contract or in the Specifications.

<u>RWO/EWO:</u> Enter the Work Order or a Resident's Work Order number. To move an existing bid item from one Pin to another Pin on the same contract, use the same item number and use RWO/EWO zero. Items that are to be added to the Schedule of items through existing mechanisms in the contract without a RWO/EXO, such as; rock excavation, structural excavation-major structures-below grade and HMA pay adjustment, can be added by writing SS, standard Specifications, in lieu of a RWO/EXO number.

Description: Enter a description only if "None" was entered as the Item #.

Changes to lump sum items will be done as separate line item entries under the <u>New Items</u> section described above. The lump sum item originally in the contract will show a zero quantity for payment and will be reentered under New Items with the new price.

The "New Item" procedure, or more pertinently, contract modification, will be processed by the computer and print it in the body of the next estimate at the end of the appropriate code section or in a newly coded section.

Specifications provide a mechanism for paying for certain items added to the contract without the need of a price quote from the Contractor. The following is a list of items commonly used and how to pay for them

To Pay For	Use Item	<u>Un</u>	it Price
Rock Excavation	203.20 ComExc	6	X Bid
Struct. Rock Excavation - Drainage	203.20 Com Exc	16	X Bid
Excavation for Slope Blanket	203.20 Com Exc	2	X Bid
Struct Rock Excavation - Major Str	206.082 Str Ea Exc - Major Sit	6	X Bid
Str Ea Exc - Major Str, Below Grade	206.082 Str Ea Exc - Major Str	1 ½	X Bid
Str Rock Exc - Mjr Str, Below Grade	206.092 Str RockExc - Mjr Str	1 ½	X Bid
Aggr Sub Crse - For Foundations	304.10 Aggr Subbase Crse - Grav	2	X Bid
Aggr Sub Crse - Slope Blanket	304.10 Aggr Subbase Crse - Grav	2	X Bid

<u>Stockpiled Materials.</u> This section is used by the Resident to pay for stockpiled materials. Section 108.4 of the Specifications allows for the payment of non-perishable materials stored for future use on the project.

Departmental policy is as follows:

- 1. Partial payments may be made for certain materials delivered to the project but not yet incorporated into the work
- 2. Payment will be shown on the progress estimate as a separate line item entry.
- 3. Materials will not be paid until the Contractor furnishes the Resident with copies of receipted bills.
- 4. As the stockpiled material is incorporated into the project and paid under the bid item, the stockpiled quantity should be reduced proportionally.
- 5. When work involving the stockpiled item is complete, that portion remaining in the stockpile, if any, shall be reduced to a "0" quantity on the progress estimate.

Payment for a stockpiled item is entered on the progress estimate as follows:

<u>Category No.:</u> Enter the appropriate four digit category number. Refer to New Items above, if necessary. <u>Item No:</u> Enter the same item number as shown for the pay item in the contract.

Quantity To Date: Enter the quantity, typically 1, or a portion of 1. Figures can be carried to two decimal places.

<u>Unit Price:</u> The unit price for payment under the stockpiled item is determined from receipted bills. The unit price shall equal the dollar amount shown on receipted bills divided by the quantity.

RWO/EWO: MA, material allowance, shall be used designate this item as allowable stockpile payment After the first estimate is processed with the above information, the stockpiled item will appear in the body of the next estimate directly following the item as originally bid.

Retent Modification. This line is used by the Contracts Section to control the retent status of the Project.

<u>Body of the Estimate.</u> The Resident fills in only the "Quantity to Date" column of this section for each item that has changed since the previous estimate. The total quantity to date may be an increase or a decrease from the previous estimate. Entries will be made in red ink.

Quantities will be entered as follows: whole numbers to the left of the decimal point and tenths and hundredths, if required, to the right of the decimal point. Quantities or percentages can be entered to three decimal places. Numbers are free read; for example, 2 is the same as 2.0 or 2.00.

For quantities with a unit of Lump Sum, show the quantity for progress payment from 0.01 to 1.00. Be careful to place the number on the correct side of the decimal point, i.e., whole numbers to the left and tenths/hundreths to the right.

For items with a unit of Each, show the quantity as a decimal, for example, for a Field Office, 0.33 or 0.67 or 1.00.

If you are adding a Lump Sum item by work order, enter the quantity for payment as 1 L.S. and not 100% L.S. If payment shows as 100% LS, the mistake of paying 100 times the L.S. price can result.

108.22 Using the Progress Estimate Form - Field Manager.

Progress estimates may also be submitted to the Contracts Section electronically, using the Field Manager construction management software program.

To use Field Manager, the Resident must import the database file of his or her project to the Field Manager program. This file will be obtained from the Contracts Section, either by network transfer or by floppy disk. If a Resident is using Field Manager solely for the generation of progress estimates, it will be necessary to generate an IDR (Inspector's Daily Report) posting the quantities for each item that needs to be paid, prior to each progress estimate submittal.

Once the IDRs' have been generated and saved, the next estimate can be added. After adding and before generating the next estimate, it should be checked for accuracy. When the Resident is confident in its accuracy, their then generates it.

When an estimate is generated, a file is automatically created in the "outbox" folder of the "fieldmgr" folder, which is accessed by using "Windows Explorer" or "My Computer". This file should then be transferred to the appropriate project folder located on the Network Neighborhood at Dotaugl/\$com-Cons/Field ManagerProjects for processing by the Contracts Section. If network connections are not possible, the file can be transferred by using a floppy disk.

When the Contracts Section receives the file, it is then processed in the Transport System and a "turnaround" file is created. This file is then picked up by the Resident, as described above, and imported back to the Field Manager program before the next estimate can be generated.

108.3 Quantities for Payment

Method of measurement and payment for items in the contract and for extra work are grouped as follows:

- 1. Plan Quantities.
- 2. Lump Sum Quantities.
- 3. Measured Quantities.

Specifications, under Sections "Method of Measurement" and "Basis of Payment" state how items in the contract are to be paid.

<u>Plan Quantities.</u> Quantity for final payment will be the figure shown in the Schedule of Items as defined in the contract Specifications or as mutually agreed to by the Resident and the Contractor.

If the Specifications state, that for some items, final payment will be based on the quantity shown in the

Schedule of Items, more commonly referred to as the "plan quantity", that figure will be paid whether the amount is estimated correctly or not. It may be altered only if a design change is made in the field. Example items are: granular borrow backfill and structural excavation for bridge abutments, granular borrow backfill for multi-plate pipes, and shoulder rehabilitation.

Final payment can also be based on plan quantity by agreement between the Resident and the Contractor. Examples are: common excavation and gravel. For such an agreement to take place, two conditions have to be met: (1) the estimated quantity must be reasonably accurate and (2) work done under the item must be to the same limits as shown in the Engineer's Estimate. Reasonably accurate is defined as the Estimate being within five percent of the true figure. The Resident must check the Estimate before proposing the agreement. Errors and changes to limits of work will be taken into consideration and corrections made.

Payment based on "plan quantity" will be documented by notes of inspection and acceptance entered in the project records.

<u>Lump Sum Quantities. Some</u> items in the contract will be designated lump sum for payment as defined in the Specifications. Examples are: field office, structural concrete, and maintenance of traffic. "Lump sum" quantities are documented by notes of inspection and acceptance recorded in the project records.

<u>Measured Quantities.</u> Payment for some items in the contract will be determined from measurements and computations of the actual work done. Sources for measured quantities can be: surface area measurements, three-dimensional volume measurements, average end area measurements, delivery slip measurements, weight measurements, hourly measurements, and force account measurements.

Surface Area Measurements. By Specifications, some items in the contract will be measured and paid based on surface areas. Examples are: clearing, butt joints, shoulder rehab, cold recycled-in-place pavement, and rehabilitation of structural concrete deck slab. Measurements and any sketches will be entered in a bound fieldbook; these can be taken in the field or scaled off the plans or a combination of both. Computations will be done in the same fieldbook or in the Final Quantity Computations Book.

Volume Measurements. Items measured by volume will be specified in the Contract. Examples are: common excavation, borrow, gravel, and concrete. Volumes can be figured using three dimensional field measurements, such as for roadway undercuts, or trench boulders. For large quantities, the average end area method will be used to figure earth excavation, rock excavation, and borrow. Any basic route survey textbook will explain in detail the average end area method. "Typical factors" will be used for figuring aggregate subbase course - gravel. Computer programs are available from the Survey Section to compute borrow and excavation.

If the Resident chooses to figure their own quantities rather than having the Survey Technicians do this, they must consider correcting between stations on curves as on ramps, for example. Also, it must be remembered that the average end area method is not usually accurate between any two stations, particularly if the areas cross sectioned differ considerably. This method is only accurate when at least three cross-sectional, areas are used to compute a quantity.

Load Count Measurements, by Volume: Items paid load count will be identified by Special Provision in the Contract. In addition, Specifications allow load count Measurement up to specified maximum limits. Load count is used when it is not practical to measure the quantities by cross-section or by three dimensions.

When materials are measured by load count, the following rules apply

- a) A delivery slip must accompany each load.
- b) The slip must be of a printed format and it must be serially pre-numbered.
- c) It will contain the project number, item description, and truck number.
- d) It must be issued by the truck driver or Foreman present at the site and signed by him or her.
- e) The Inspector or Ticket Taker must witness every load dumped and as evidence, will sign the slip. Partial loads will be noted as: "3/4 full", for example.

Volume need not be shown on the slip but the Inspector will measure every truck body and enter measurements in a bound fieldbook, signed and dated. The Correct shrinkage factors will be applied when the quantities are figured for payment. Borrow and excavation measured load Count are reduced 10 percent; gravel is reduced 20 percent; concrete, riprap, and loam are measured on a "yard for yard" basis, i.e., no shrinkage or swellage is applied. Refer to the Specifications under the appropriate items for swellage and shrinkage factors.

Load Count Measurements, by Weight: Specifications require that hot mix asphalt items be measured by weight. A delivery slip will accompany each truckload of *mix* delivered to the job. Slips will contain the following information:

- a) Slips will be serially pre-numbered.
- b) Weight of each batch and total weight of the load will show on the slip if the plant weigh system is computerized. If not, only the total weight of the load needs to be shown, and the slip must be signed by a certified weigh master.
- c) The Paving Contractor's name must appear at the heading, in print.
- d) Every slip will be signed by the Ticket Taker.
- e) A Cover slip showing the day's total will be made out and signed by the Contractor's Representative and the Resident.

All weigh slips for hot mix asphalt must be kept in the Resident's office for the duration of the project. When the Resident submits their records to the Contracts Section for final review and close-out, delivery slips may be discarded but the Cover slips will remain with the project records.

The Testing Technician will do some check weighing to verify the accuracy of the scales. Check weighing procedures are explained in Division 100, Section 108, of the Specifications.

Hourly Work Items. Extra work, unforeseen, is sometimes measured and paid by the hour. This work can be paid by using the hourly bid items in the contract, by force account or by a combination of both. Section 109.07, of the Specifications and Section 109 of this Manual explain in detail, rules covering extra work. The Daily Report of Labor and Equipment Rental will be used to document the hours of labor and equipment, and materials used. Authorization for the work by the Resident or by Contract Modification and description will be noted in the Remarks portion of the Report which will be signed by both the Inspector or the Resident and the Contractor's Foreman or Superintendent.

This Section, Quantities for Final Payment, is intended to describe only in general, methods used to measure and pay final quantities. The Resident will refer to Divisions 200 through 600 and 900 for more detailed discussion of the requirements for field documentation, measurement, and payment.

SECTION 109 - WORK ORDERS AND CONTRACT MODIFICATIONS

109.1 General.

Specifications require the Contractor, as directed by the Resident, to perform extra or unforeseen work added to the contract a supplemental agreement, in the form of a work order or contract modification, will be written to authorize and to document the added work.

109.2 Conditions Requiring Work Orders and Contract Modifications.

Work Orders will be initiated and written by the Department, normally by the Resident, and will be signed by the Resident. All Contract Modifications, except those initiated by standard Specifications ie; rock excavation & Quality Assurance Pay Adjustments, will require the signature of the Contractor and may also require the signature of administrative personnel within the Department, as explained further in the next Section. A work order/contract modification will be written when the following conditions are present on the project:

- 1. Changes in Specifications.
- 2. Substitution of materials.
- 3. Changes in Testing Requirements.
- 4, Changes or extra work within the scope of the contract.
- 5. Changes in design beyond the scope of the contract.
- 6. Changes that result in an increase or decrease of 25 percent or more in major items of the contract. A major item is one that exceeds 10 percent of the original contract amount, as awarded. These changes may result in an increase or decrease in unit bid prices. Section 109.1.2 defines a major change.
- 7. Changes in deadline dates, completion dates, or time extensions not covered elsewhere.
- 8. Additional driveways, copy to Right of Way team member.
- 9. Municipal Government, County Government, or other State Agency request for additional work or change in proposed work. If the Agency involved requests additional work, it will be required to pay the nonfederal share. The Work Order will clearly state what portion will be paid by the Agency and will be signed by a responsible person from that Agency.

109.3 Contents of the Work Order and Contract Modification.

The following information will be included in the content of the Work Order:

- Description and location of work.
- 2. Reason for the change or for the added work.
- 3. Method of payment, ie existing bid items, contractor quoted work, force account, and benefits to the project.
- 4. Procedures to be followed by the Contractor. Time constraints, Special Provisions, and Supplemental Specifications are to be made part of the Work Order, as applicable.
- 5. Price quotations, if required on Contractor Letterhead.
- 6. Time extensions and reasons for the extra time, if needed. A time extension is not granted unless the work directly affects the Contractor's progress, known as the "critical path".
- 7 Right-of-way acquisitions or easements if needed.

- 8. Cost estimates. The Resident will include with the Work Order, his or her estimate of the cost of doing the work, whether it is done by unit price, lump sum, or force account. The Resident should arrive at the cost estimate independently of the Contractor's figures as much as possible. It should be more than just a review of the Contractor's numbers. An excellent source of historical data is the MDOT Bid History by items, which is located at http://dot0dta1asora14.mdot.w2k.state.me.us;7778/freeprod/pBidHistEnglish.display.
- 9. Approvals and signatures. The Contractor's signature shall be on all Work Order; it signifies thier concurrence with performing and payment of the work.. A work order is a supplemental agreement and is not legally part of the original contract unless it contains the signatures of both parties. Work orders not considered to be Residents' Work Orders will be submitted to the Resident's Supervisor for his or her approval and signature. Section 109.4-Resident's Work Orders and 109.5 Work Orders Requiring Supervisor Approval explain further, and in more detail under what conditions work orders are needed.
- 10. Federal participation. All work orders on federally funded projects must be designated "participating" or "non-participating", i.e., whether or not Federal funds will be expended in the costs involved. In general, the FHW A will participate in the cost of all work orders except when an outside agency such as a Town, County, or a private developer requests the work, or the work is beyond the scope of the contract and is of no direct benefit to the project. Conditions under which FHW A approval is needed are outlined in Section 109.6 of this Manual and what approvals are required,

109.4 Resident's Work Orders.

The Department has authorized the Resident to execute certain work orders at the project level without the approval of their Supervisor, but subject to the following limitations:

- Each work order is limited to \$10,000.00, not to exceed a cumulative cost of 3 percent of the awarded contract amount.
- 2. The Resident's authority is limited to construction of the project as intended and designed and does not extend beyond the original scope of the contract.

In addition to the above limitations, the requirements of Section 109.3-Contents of the Work Order will apply, as applicable.

109.5 Work Orders Requiring Supervisor Approval.

The following types of changes are considered to be beyond the limits of the Resident's authority to approve and therefore must be submitted to the Supervisor for concurrence and signature:

- 1. Changes in geometric design of the project or structural design of bridges, including foundations, and culverts greater than 1.8 m. in diameter.
- 2. Revision of typical plan cross-sections.
- 3. The addition, deletion, or relocation of any bridge or other structure which affects the function or intent of the approved design.
- 4. Changes in Right-of Way
- 5. The addition of work outside project limits. An exception is work necessary for erosion control, in which case the property owner's permission is needed and put in writing.
- 6. Changes that alter contract Specifications or other requirements of the contract.
- 7. Changes that will affect the safety and operation of traffic other than what is allowed under the terms of the contract.
- 8. Changes that result in an increase or decrease of 25 percent or more in major items of the contract. A major item is one that exceeds 10 percent of the awarded contract amount. These

changes may result in increases or decreases in bid prices. Section 109.1.2, Division 100 of the Specifications - Green Cover, defines a major change.

- 9. Changes that exceed \$10,000.00 in cost and result in negotiated prices or payment by force account.
- 10. Changes which may require modification to previously approved environmental permits.
- 11. Quality Control/Quality Assurance provisions added to the contract.
- 12. Significant changes in completion dates or other time constraints, if not addressed as part of other work orders.

All of the above situations, the Resident can obtain verbal approval from his or her Supervisor before the Contractor does the work, and will follow up by a signed work order. The Supervisor's approval will be noted on the Work Order.

109.6 Work Orders Requiring Federal Approval.

Every construction season, the Federal Highway Administration will designate certain federally funded projects as "Direct Involvement" projects. On these jobs the FHW A will be involved in the design and construction more so than on other projects, and will do on-site visits on a regular basis. The Resident should ask thier Supervisor or the Designer if his or her job is a Direct Involvement project.

Types of work orders described in Section 109.5 - Work Orders Requiring Supervisor Approval will also need concurrence from the FHW A on Direct Involvement projects. The Resident can obtain Federal approval verbally and so note on the Work Order; this can be done by phone or when the FHWA Engineer visits the project, preferably prior to the work being done. Details of the conversation such as name of the FHW A Engineer and date the conversation took place should be recorded on the Work Order. A copy of the Work Order should be mailed to the FHW A for documentation. Copies of all Resident's Work Orders should also be sent to the FHW A prior to project completion.

109.7 Method of Payment for the Work.

The Specifications, Section 109.7 - Equitable Adjustments to Compensation, specifies that payment for extra work will be made by any one or a combination of the following methods:

- 1. Agreed Unit Prices.
- 2. Lump Sum.
- 3. Force Account.

Agreed Unit Price includes miscellaneous extras such as, but not limited to: labor, materials, equipment, supervision, overtime, travel time, benefits, small tools, transportation, profit, overhead, and other incidental items of work.

Lump Sum is all inclusive and includes extraneous items such as: profit, overhead, regular and overtime labor, supervision, benefits, materials, equipment, and miscellaneous small tools.

If agreement cannot be reached between the Contractor and the Resident on methods 1 or 2, the Contractor must accept payment on a force account basis. Reference is made to Specifications, Sections 109.3 - Extra Work and 109.7.2 - Basis of Payment.

Force Account should be used only when either of the following conditions are present:

1. The extent of the work is difficult to predict, and therefore the cost cannot be estimated with any degree of

accuracy.

2. The Resident and the Contractor cannot come to an agreement on unit prices *or* lump sum prices. Sections 109.7.3, 109.7.4, and 109.7.5 of Division 100 - Specifications, explain in detail how to calculate payment made by force account.

The following is a brief summary of the contents of the Sections noted above:

Materials:

actual cost supported by receipted bills plus 15 percent mark-up

Labor:

payroll cost for regular and overtime plus 90 percent for laborers and foremen directly

involved in the work.

Equipment:

"Blue Book" rates, available from the Contracts and Specifications Section.

Mark-Ups: The Prime Contractor is allowed a 5 percent mark-up on a subcontractor's bill for profit and handling of paperwork. When force account work is involved, a 90 percent mark-up is allowed on payroll labor rates and a 15 percent mark-up is allowed on materials. No further mark-ups are permitted.

Regardless which method is used to pay for extra work, whether agreed unit prices, lump sum, or force account, estimating the cost before the work is done is necessary. The Resident should have an idea of what the work will cost before the Contractor submits their price. The figures will be submitted to the Supervisor with the Work Order; other documentation such as receipted bills and price quotes, will remain in the Resident's project files. Back-up documentation and cost estimates for Resident's Work Orders will be kept in the project files on site also.

Division 200 - Earthwork

201.5 Clearing, Tree and Stump Removal- Field Documentation. Measurement. and Payment.

This Section describes the recordkeeping necessary to document and measure clearing and the removal of single trees and stumps.

Field Documentation.

Project Diary, Inspector's Diary/Inspector's Daily Report: The Resident or Inspector will keep notes describing the subcontractor's clearing and selective clearing operations; equipment, personnel, and station to station limits of work will be noted. Workers and equipment need not be recorded every day unless there are frequent changes.

The Contractor, or more commonly the clearing subcontractor, will take the clearing limits from the plans and flag them in the field. If the Resident makes substantial changes or if the limits are not shown on the plans, a clearing list will be made up by the Resident and a copy given to the Contractor. For sample Inspector Diary entry, ref pg 90

Measurement and Payment.

Final quantity for payment can be plan quantity providing the estimated quantity is accurate and work is done as estimated. The Resident will adjust the plan quantity, upward or downward, according to changes made in the field.

Should the Resident find it necessary to establish new limits for the entire job, final pay quantity will be figured from these revised limits flagged in the field. A list of new limits will be made part of the project records.

Whether the Resident makes final payment based on plan quantity or based on a list of revised clearing limits, he/she must substantiate final payment by notes stating that clearing has been completed and accepted to limits flagged. These notes will be made in the Final Quantity Book or in the Construction Book.

Single trees and stumps required to be removed outside clearing areas will be field counted and entered directly in the Final Quantity Book for payment. All measurements will be signed and dated.

Final quantity for payment will be entered in the Final Quantity Book and labeled as such; reference to measurements, clearing limits flagged, and statements of inspection will be made as necessary. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

<u>202.5 Removal of Structures, Obstructions, Pavement - Field Documentation, Measurement and Payment.</u>

This Section describes the recordkeeping necessary to document and measure the removal of structures, pavement, and other existing structures designated to be removed under pay items in Section 202.

Field Documentation.

Project Diary, Inspector's Diary/Inspector's Daily Report: The Resident or Inspector will keep notes describing, for example, demolition of buildings, removal of bridge superstructures and substructures, removal of pavement and other obstructions for which there is a pay item in the contract. Station to station limits of work done by the Contractor, if appropriate, and disposal will be noted. Disposal usually consists of hauling materials to a waste dump, turning over to a State or Town Official, or stockpiling for future use.

The Contractor may need a permit to dispose of certain building materials off the project. The Resident should review the special Provisions of the Contract and contact the Environmental Services Section in Augusta for advice regarding permits.

Special Provisions of the Contract may require that certain components of the existing bridge become property of the State or the Town. The Resident should obtain the signature of the individual receiving such materials.

Measurement and Payment.

Final quantity for payment will be entered in the Final Quantity Book arid labeled as such.

For items to be paid lump sum, the Resident will make reference to notes in the Project Diary that document progress of work. A statement of final inspection and acceptance will be made in the Final Quantity Book.

For items to be paid by the unit, such as removal of existing concrete, reference will be made to field measurements. These measurements will be entered in a Construction Book or directly in the Final Quantity Book; all measurements will be signed and dated.

For items to be paid plan quantity, such as removing existing pavement, the estimated quantity must be accurately figured and the actual work limits must be the same as those shown in the Engineer's Estimate. The Resident may have to adjust the Estimate to reflect field changes. As for lump sum items, the Resident will make references to Diary notes verifying that work has been done as estimated. These notes may be made directly in the Final Quantity Book. If the plan quantity is a "throw-in" quantity, i.e., has no basis other than a guess, the work in question will have to be field measured.

Removal of curb, fence, and guardrail will be incidental to the work in general. No separate payment will be made unless there exists specific pay items in the contract for these items.

All calculations and data entries must signed, dated and checked; the checker must sign and date their work.

203.5 Excavation - Field Documentation, Measurement, and Payment.

This section describes the recordkeeping necessary to document and measure excavation. It is recommended that you read Division 900 - Project Records of this Manual to better acquaint yourself with project recordkeeping in general.

Field Documentation.

Project Diary, Inspector's Diary/Inspector's Daily Report. By Specifications, the Contractor is required to place usable excavation within the slopes of the embankment;

no excavation can be hauled off the project without the Resident's approval. It is their responsibility to determine what material can be used on the job, or can be wasted, or stockpiled for future use. This becomes particularly important on a "borrow job" as the amount of wasted excavation directly affects the amount of borrow required. A project is a "borrow job" when material from off the project is required to meet the fill requirements of the contract.

The Resident, or the Inspector if one is assigned to cover excavation items, will keep daily notes of the Contractor's activities relative to earth and rock excavation. It is the Resident's option, whether or not the Inspector is to keep a Diary or Daily Report. The Resident may prefer to have all daily documentation entered directly in the Project Diary. Entries will be made documenting station to station limits of material excavated and locations where placed. It is important to record such information as: material directed to be placed within the core of the embankment or in waste storage areas within embankment limits, or to be stockpiled for future use on the project, or hauled to waste dumps off the job.

Circumstances surrounding the hauling of excavation off the project must be explained, particularly if the project is a borrow job. Material suitable to be placed in the embankment, but wasted without the Resident's permission will be deducted from borrow. Likewise, material only suitable to be placed in waste storage areas outside the core of the embankment, but wasted without permission will also be deducted from borrow. Excess excavation, not required for embankment construction, will be hauled off the project and disposed in waste dumps or other locations approved by the Resident. Excavation that the Contractor stockpiles away from the job for future use on the project will or will not be measured for a second payment, depending on whether or not the Resident has allowed stockpiling. Section 203 of the Specifications, Basis of Payment, allows payment for the rehandling of excavation when it is not possible for the Contractor to do otherwise.

Added undercuts, changes in ditches either in grade or offset, changes in backslopes such as flattening, changes in excavation limits to the approaches, and changes in drives must also be noted and measured for payment.

Grade Check Book. It is a requirement of the Department that the Resident or Inspector spot check the Contractor's grading operations to assure that fine-grading is done within construction tolerances stated in the Specifications. It is recommended although not a requirement, that a "Grade Check Book" be made part of the project records. This book will serve as a convenient and ready reference for checking sub grade, sidewalks, ditches, and backslopes on mainline and side roads, and also for keeping tract of what areas the Contractor has fine-graded and what areas have been spot checked. This book should be set up prior to the start of excavation and borrow operations so that the Resident, when in the process of figuring offsets and grades, will discover possible errors in the plans and will also become familiar with the geometrics of the job before work begins.

Whether or not the Resident uses a Grade Check Book, some written documentation must be entered in the project records that the Contractor's fine-grading operations have been checked and approved. These entries may be made in the Project Diary, Inspector's Diary, Daily Report, directly in the Final Quantity Book, or in the Grade Check Book if there is one.

For sample project diary documentation ref page 64, Final Quantity Entries ref page 65 & 66 and Construction Book entries ref page 80,82,85,88 & 92.

Measurement and Payment

Final quantity for payment can be the figure shown in the Schedule of Items in the contract, more frequently called the "plan quantity". The Resident may pay plan quantity as final payment but the following two conditions must be met: the quantity estimated, i.e., the Engineer's Estimate, must be reviewed for accuracy and considered reasonably accurate, and the limits of excavation in the field must approximate those estimated.

Frequently the plan quantity must be adjusted, upward or downward, because of changes made in the field and also because of increases or decreases in quantity of rock excavation estimated. The Engineer's Estimate must be reviewed to assure that rock is not included in the quantity of earth figured. Changes will be measured and recorded directly in the Final Quantity Book or in the Construction Book. Types of changes are described under Field Documentation, above. The Final Quantity Book and the Construction Book are described in Division 900, Section 901.3 of this Manual.

Field changes and added work will be measured by load count, by length, width, and depth, or by original and final cross-sections. Load count will be reduced by 10 percent to arrive at a quantity equivalent to what would be measured in its original position. Computations may be done in the Final Quantity Book, in the Construction Book, or on computation sheets that are part of the Final Quantity Computations Book. If the Resident uses the computer program "Field Manager", the Item History to Date will be generated in lieu of a Final Quantity Book.

Wasting of excavation without the Resident's permission will be measured and deducted from borrow. Measurement will be by load count or by length, width, and depth. Load count excavation will be reduced to 90 percent for deduction purposes; excavation measured in-place off the project will be deducted at 100 percent of quantity so measured.

Muck and grubbing excavated beyond limits shown on the plans will not be measured for payment unless the Resident has authorized a change in the limits. Lateral excavation limits for muck excavation are determined by the intersection of the bottom of the excavation and a l: 1 slope line drawn down from the finish shoulder break. Borrow placed in over excavated areas will not be deducted unless the excavation beyond lateral limits is deliberate or due to negligence by the Contractor.

All pay quantities will be entered in the Final Quantity Book and referenced to the source document; the final pay quantity will be so labeled. A chain of referencing from the

Final Quantity Book to the original record is always needed. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

Rock Excavation: Unlike earth excavation, it is usually the case that the actual quantity of rock excavated will not agree with the Engineer's Estimate. Since soundings are normally taken some distance apart, original ledge cross-sections drawn on the plans do not accurately describe top of ledge, particularly where there is earth overburden. Abrupt changes in elevations are not always detected and also, boulders may be mistaken for solid ledge. This lack of detailed information results in errors in the estimated quantity, and therefore the "plan quantity" cannot be used to make final payment. If earth is paid plan quantity, it must be adjusted according to actual quantity or rock paid.

Rock has to be re-sectioned before removal; but, if the Contractor does not want to strip ledge prior to blasting, top of ledge elevations can be determined, by recording from a known elevation, depth the drill rig has to go before hitting solid rock. Section 203.04 General, requires that the Contractor remove overburden before original cross-sections are taken; it is the Resident's prerogative, therefore, whether or not to allow the Contractor to leave the earth in place before blasting.

Quantity of ledge for payment will be figured from "new" originals to the design cross- section if rock is removed to the construction limits described in Section 203.05 of the Specifications. No payment will be made for rock removed beyond the design cross-sections unless the Resident has directed a change in design. Section 203.18 Method of Measurement, Specifications, defines pay limits. Quantities will be computed by the average end area method. A computer program is available from the Augusta Office, Survey, to figure ledge quantities. Print-outs will be made part of the Final Quantity Computations Book.

Boulders, concrete, solidly mortared masonry, all defined in Section 203.01(b), and small quantities of rock

such as ledge nubbles, will be measured by three dimensions. Boulders encountered at sub grade during excavation operations will be measured as rock excavation and the portion estimated to be above sub grade will be deducted from earth excavation. A "pay" boulder is defined in Section 203.1(b) referred to above.

The situation may arise where ledge is not measured in its original position but is measured load count or in its final location as riprap or rock fill. The quantity so measured will be reduced to 75 percent to determine the amount of rock excavation for payment, the reason being that ledge swells after it is excavated. Measurements and sketches if needed for clarification will be entered in a bound field book, which would be the Construction Book or the Final Quantity Book.

If the job is bid "unclassified", the Resident should make note of the elevation of actual top of ledge where backs lopes are designed on a Y4: 1. In deep ledge cuts, pay limits of earth overburden have to be adjusted depending on the elevation of the ledge.

If the Contractor wastes rock without the Resident's permission and the result is an increase in the amount of borrow needed to meet the fill requirements of the contract, the quantity of rock wasted will be deducted from borrow at 100 percent of the quantity so measured. All measurements and load counts will be entered in a bound field book.

All quantities for payment will be entered in the Final Quantity Book and referenced to the source document. There must always be a trail of reference from the Final Quantity Book to the original record. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work. The final quantity for payment must be labeled as such and signed, checked, and dated.

203.6 Borrow - Field Documentation, Measurement, and Payment.

This section describes the recordkeeping necessary to document and measure borrow required to meet the fill requirements of the contract.

Field Documentation.

Project Diary, Inspector's Diary/Inspector's Daily Report: Specifications, Section 203.03, Unauthorized Use of Materials, and Section 203.04 General, require that no excavation suitable for embankment construction be hauled off the project. The Resident or the Inspector is to make note of wasted excavation and the nature of it, since the more excavation the Contractor removes from the project, whether authorized or not, the more borrow is needed to construct the embankments.

The Resident or the Inspector will keep daily notes in the Project Diary or the Inspector's Diary/Daily Report relative to the Contractor's operations. Name of the pit that borrow is being hauled from and station to station limits it is being placed, whether in the core of the embankment or in waste storage areas. These areas, which are beyond the 1: 1 slope from the finish shoulder break, are to be reserved for the placement of grubbings or other excavation not suitable for constructing the core of the embankment. The Contractor should not be allowed to place borrow in these areas if there is waste excavation available.

Ideally, the Contractor should complete all excavation operations prior to hauling borrow to the project. If the/she places borrow on the job before all excavation is complete, the Resident should advise the Contractor that he/she is doing so at the risk of having some borrow deducted from the final pay quantity at a later time. As stated previously, no excavation is to be removed from the project if it can be placed either in the core of the embankment or in waste storage areas. The case may arise, usually because traffic has to be maintained on the existing road, where borrow has to hauled to the job before excavation is complete. The result is that good excavation is wasted; in this situation the Contractor is not penalized. Discussions relating to these matters must be noted in the Diaries.

Borrow diverted for the Contractor's own use must be documented as well; materials used to maintain a haul road or town road, or to grade the equipment yard is all to be deducted from borrow if the material comes from a sectioned pit.

Grade Check Book. As stated previously under Section 203.5 - Excavation, documentation of subgrade checks is a requirement of the Department, whether the operation is in a cut or in a fill. Refer to Section 203.5, Grade Check Book, for further discussion of grade checks.

For sample final quantity book entries ref page 67, for construction book entries ref page 82 and for inspectors diary entries ref page 90 & 91

Measurement and Payment

Borrow: While common excavation can be paid plan quantity, borrow cannot. An exception is when the plans require backfill behind abutments and around multi-plate pipes to be granular borrow or gravel borrow. Specifications, Section 203, Method of Measurement, allow backfill around bridge structures to be paid plan quantity.

When the Designer estimates the quantity of borrow required for the project, he/she makes assumptions that may or may not be representative of what actually happens in the field, particularly on bridge projects. Quantity of excavation estimated to be available for fills is, to some extent, guesswork. Some of the excavation mayor may not be suitable for embankment construction or a situation may exist on the job that makes excavation not available in a timely manner; an example would be traffic maintenance on the existing roadway. The result is that the actual quantity of borrow used on the job is usually not what is estimated.

For these reasons, final quantity of borrow must be determined from actual measurements. The Resident will use the following methods or a combination thereof:

Cross Sections. By Standard Specifications, the contract bid price for borrow is based on the material being

measured in its original position, i.e., in the pit. When measured any other way, the quantity must be adjusted as explained below. Original cross-sections are taken in the pit after the Contractor has stripped the surface and before excavating and hauling operations begin. The Survey Crew should flag the pit limits to alert the equipment operators not to remove material beyond the outer limits of the original cross-sections. Final sections will be taken after the pit has been graded and before grubbings, loam, or other material that can support a growth of grass has been spread. Specifications, Division 105.8.6, addresses pit rehabilitation.

Borrow pushed up and beyond the edge of pit at its perimeter will be deducted from the overall quantity measured for payment. The Survey Section uses a "total station" computer program to take cross-sections and to compute quantities; a print-out of each cross-section is available.

Load Count. It is frequently not practical to figure borrow quantities by cross-sectioning the source. Since nearly all borrow pits are commercial pits and therefore are available to the public, it is nearly impossible for the Contractor to guarantee or even assure the Resident that all material taken out of a sectioned pit will be hauled to the job.

Load count, providing the total quantity measured is less than 5000 cm, offers an alternative to the cross-sectional method. There are two problems common to load counted material: trucks not being fully loaded and drivers reporting more trips than what they actu~ly haul. For these reasons, it is advisable to assign an inspector or ticket taker to witness and to collect delivery slips for every load hauled. If, because of lack of personnel, this cannot be done, the Resident or Inspector assigned must do a random check of the Contractor's hauling operations. The Resident should do a "time study", i.e., determine how long it takes for a driver, or more than one, to make a round trip from the pit to the site, and also to visually observe if the trucks are fully loaded.

Section 203.18, Method of Measurement, Specifications, requires that borrow by load count must be reduced to 90 percent of the quantity so measured.

In-Place Measure. A third method of measuring borrow is to compute the quantity in its final position, more commonly called "in-place-measure". This method is particularly suited to bridge projects. The procedure to follow is to figure the total quantity in the embankment from the design template to original ground or to bottom of grubbing limits. The excavation placed in the fill would be deducted from the total embankment and the resulting figure would be swelled 15 percent for final payment.

If earth excavation that is placed in fills is measured in its original position, it will be shrunk 15 percent before being deducted from the total embankment quantity. If it is measured in its final position, i.e., in the embankment, it will be deducted at 100 percent of the quantity so measured. If it is measured load count, it will be shrunk 25 percent before deduction.

If rock excavation that is placed in fills is measured in its original position, it will be swelled 33 percent before being deducted from the total embankment quantity. If it measured in its final position or by load count, it will be deducted at 100 percent of the quantity so measured.

Borrow Deductions. When the Resident computes the final pay quantity of borrow, he/she must determine if any of the material should be excluded from payment.

Unless directed by the Resident, all usable excavation will be placed in the core of the embankment and all waste excavation will be placed in waste storage areas, either as shown on the plan cross-sections or as directed in the field. Only excess excavation can be hauled offsite. Borrow diverted for the Contractor's own use or placed in unauthorized areas will be at their expense. Specifications, Section 203.18 - Method of Measurement, states that material placed outside the embankment will not be eligible for payment.

For deduction purposes, the following situations are to be considered:

Borrow is placed ahead of excavation operations which results in a surplus of excavation: Common excavation and rock excavation wasted will be swelled 15 percent before deduction; reference is made to Section 203.04.

Excavation is hauled off the job instead of being placed in the embankment and then later replaced with borrow because of convenience and ease of operation to the Contractor: The quantity of excavation that could have been placed in the embankment will be deducted from borrow at 100 percent of the quantity so measured.

Excavation is placed in the embankment beyond the design template in concentrated areas as opposed to being distributed throughout all fills, thus creating "fat" slopes: Earth and rock excavation placed beyond the

pay limits defined in Section 203.18 - Method of Measurement, Specifications - 6", will be deducted from borrow at 100 percent of the quantity so measured.

Borrow is placed in embankments beyond the design template, the result being "fat" slopes: Quantity placed beyond the pay limits defined in Section 203.18 will be deducted from borrow. Deduction will be made at 100 percent of the quantity so measured.

Borrow is diverted for the Contractor's own use: Material used to dress the Contractor's equipment yard or a waste dump, or to upgrade a haul road or town road will not be included for payment. Deduction will be made at 115 percent of the quantity so measured; refer to Section 203.03 - Unauthorized Use of Materials, Specifications.

Final quantity for payment will be entered in the Final Quantity Book. Subtotals, and deductions making up the final quantity for payment will be entered in the Final Quantity Book and referenced back to source. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

206.5 Structural Excavation - Field Documentation, Measurement, and Payment.

This Section describes the recordkeeping necessary to document and measure the excavation of earth and rock required to install culverts, bridge abutments, and other structures.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report, Drainage Book, and Construction Book: The Resident or Inspector will keep notes describing the Contractor's excavation operations required for the installation of drainage, bridges, and other structures. These notes will describe location and final disposition of the material, whether on the job or off the job.

Documentation of installation of culverts, underdrain, catch basins, and manholes will be entered in the Project Diary. If the drainage is extensive, a Drainage Book should be set up prior to the work being done and all notes pertaining to drainage work will be entered in the Drainage Book. Reference is made to Division 900 of this Manual for further explanation of the Drainage Book. Undercutting to provide a stable foundation, bedding, excavating rock, and material used to maintain traffic will be noted and measured for payment.

Documentation of construction of bridge abutments, pier footings, wingwalls, retaining walls, multiplate pipes, and other major structures will be entered in the Project Diary or Construction Book. The Construction Book will be used if layout and/or field measurements and sketches are required. Typical measurements would be for rock excavation and undercutting. Division 900 of this Manual explains the Construction Book and how it is used.

Documentation of installation of other miscellaneous minor structures will be entered in the Project Diary or the Construction Book. The Construction Book will be used if layout and measurements for removal of rock or unstable foundation material are required.

For sample construction book entries ref page 84 & 86 and for inspectors diary entries ref page 89,90,91 & 93.

Measurement and Payment.

Drainage and Minor Structures: In areas of full width construction and reconstruction of shoulders, excavation for culverts, catch basins, and other minor structures is incidental from sub grade down to 12" below the flow line of the pipe or bottom of the base. Excavation required below that point for stable foundation or change in grade will be paid under the item "Structural Earth Excavation-Below Grade". That quantity will not be paid plan quantity; this figure is a "throw-in" and is not necessarily based on work anticipated to be done. Quantity for payment must be field measured. Measurements and sketches will be entered in the Drainage Book, signed and dated. Depth will be as directed by the Resident and width will be the limits defined in Section 206.04 of the Specifications and sheet #605(1) of the Standard Details for underdrain.

Rock excavation for drainage and other minor structures will be the quantity actually excavated to the pay limits defined in Section 206.04 of the Specifications. Measurements and sketches will be entered in the Drainage Book, signed and dated.

Bedding material will be computed to depth authorized beginning at the flow line of the pipe or bottom of the base in the case of catch basins; width will be as defined in the Specifications.

Major Structures: Section 206.04 of the Specifications states that final payment for earth excavated for bridge abutments and piers will be the quantity shown on the plans unless the structure is founded on ledge. In this case payment for earth and rock removed would be based on field measurements. Since top of ledge shown on the plans is not accurate, new ledge originals would be needed. Original cross-sections will be taken at right angles to the centerline of bearing at close intervals.

Quantity of earth will be figured vertically from original ground or roadway sub grade to top of ledge and horizontally to pay limits shown on the plans or to 18" beyond the footing. If actual top of ledge is lower than the elevation shown on the plans, earth excavated below that elevation will be paid at I 1/2 times the bid price for structural earth excavation. Typically, elevation of top of ledge is shown on the plans as, for example: 26 +/-. Such a designation would be interpreted to mean that only earth excavated below elevation 25 would be paid at I 1/2 times the price. Another example would be: if the elevation shown were 26.0+/-, earth excavated below 25.9 would be paid at 1 1/2 times the price. Likewise, if the elevation of bottom of footing is lowered due to change in design, excavation below, the original elevation shown would also be paid at 1 1/2 times the price.

If the plans call for excavating into ledge for the footing, the Contractor is allowed a pay tolerance of up to 12"

below the elevation of the bottom of the footing. Rock excavated and concrete placed below the 12" tolerance will not be paid. If the Resident directs the Contractor to remove rock below bottom of footing elevation because of a change in design or because of the soft nature of the ledge, it will be paid at 1 ½ times the bid price for structural rock excavation.

"Pay" boulders, defined in Section 203.0l(b) of the Specifications, that are found partly within the excavation limits for drainage and major structures will be measured and computed for payment as follows: that portion estimated to be within the structural excavation pay lines will be paid as such and the remainder will be paid as common rock excavation.

There will be no payment for rehandling structural excavation; the bid price includes excavating, rehandling as many times as necessary, and placing in its final position, whether it be in the embankment, waste storage areas, or off the project.

Final quantities of structural earth excavation-below grade and structural rock excavation will be entered in the Final Quantity Book and labeled as such. References will be made, as appropriate, to the Drainage Book or Construction Book for measurements and computations.

All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

Division 300 - Bases

304.5 Aggregate Base and Subbase - Field Documentation. Measurement. and Payment.

This Section describes the recordkeeping necessary to document and measure aggregate base and subbase on the project.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes describing the Contractor's aggregate base and subbase operations. Information recorded will be: name of pit the material is coming from, station to station limits where it is placed, and whether placed in one lift or two lifts.

The Resident is responsible for quality assurance testing; he/she must assure that a Technician from the Department is available to do the testing required. Tests the Contractor may take are not to be counted toward the total number needed; these tests are to be considered as quality control for the Contractor's benefit only. Reference is made to Division 900, Section 901.4, of this Manual for further discussion of "Minimum Testing requirements".

Gravel can fail gradation or density or both. Corrective action directed by the Resident will be documented; more compactive effort may be required or material failing in gradation may have to be removed.

Sections 304.03 and 304.04 of the Specifications requires the Contractor to place the material in two lifts, but he/she can be allowed to place it in one. Gravel placed in one lift must meet density requirements full depth and therefore the lower portion of the one lift will be tested. If it fails, the Contractor must take whatever action necessary to attain passing density full depth.

Grade Check Book: The Department requires that the Resident or Inspector do random checks of sub grade and top of gravel to assure that the Contractor is placing gravel within construction tolerances. Checks should be done between stations as well as on station. Reference is made to Division 900, Section 901.3 and to Division 200, Section 203.5 for further discussion of the Grade Check book.

For sample project diary entries ref page 64, for final quantity book entries ref page 69, for construction book entries ref page 81 & 82 and for inspectors diary entries ref page 91 & 92.

Measurement and Payment.

Final quantity for aggregate base and subbase can be figured by anyone or a combination of the following methods:

Plan Quantity. Quantity for payment can be plan quantity providing the Resident reviews Engineer's Estimate for accuracy and the work is done to the limits estimated. It is often the situation that side streets and mainline approaches and drives are changed to match field conditions; the Estimate should be adjusted to meet these field conditions as necessary. Payment by plan quantity shall be documented by written agreement in the form of a Resident's Work Order. The agreement should state that the plan quantity will be adjusted upward or downward if changes are made in the field. Changes will be measured by three dimensions or load count described below.

In-Place Measurement. If the estimated quantity has no basis, commonly referred to as a "throw in" figure, gravel for the project will have to be refigured. Typical factors should be used for mainline travelway and shoulders where possible. Three dimensional measurements and/or plan dimensions can be used for drives, approaches and intersection areas. Gravel used to backfill undercut areas or to provide bedding for drainage can also be measured and computed by three dimensions to limits authorized. For drainage, depth will be figured from flow line of the pipe and width will be figured to the lateral pay limits defined in Section 206.04 of the Specifications.

Load Count. Gravel can be measured load count if: there is not a large quantity involved and the work involves mostly traffic maintenance or matching into, existing material. By Specifications, gravel measured load count will be reduced 20 percent for payment to arrive at an equivalent quantity measured in its final position. Refer to Section 304.06 of the Specifications for clarification.

Final quantity for payment will be entered in the Final Quantity Book and labeled as such. Reference will be made to grade checks, measurements, load count delivery slips, and computations in the project records, as necessary. Measurements and delivery slip totals must be entered in a bound book which can be the Final Quantity Book or the Construction Book. Reference is made to Division 900, Section 901.3 of this Manual for further discussion of field books. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

307, 309 & 310 Recycled Pavement - Field documentation. Measurement, and Payment.

This Section describes the recordkeeping necessary to document and measure the recycling of existing pavement.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes describing the Contractor's operations on the road and in the plant.

Full Depth Recycled Pavement. Field notes will include weather conditions, station to station limits of work, and description of equipment used: pulverizer, grader/spreader, rollers. The Inspector will also document inspection procedures and check measurements of work done, such as: depth of grinding operations, cross-slope, and density of the finished product. Any added aggregate or recycled pavement used as necessary to restore cross-slope will also be noted, tested, and measured for payment if required.

Plant Mixed Recycled Pavement, Foamed Asphalt & CIP require a QC/QA plan to be submitted. Field notes will be the same as for recycled pavement with additional documentation regarding plant inspections.

For sample final quantity book entries ref page 70.

Method of Measurement.

Final quantity of recycled pavement can be figured by either of the two following methods:

Plan Quantity. Quantity for payment can be "plan quantity" providing the estimated quantity shown in the Schedule of Items is reasonably accurate and work is done to the limits estimated. Payment by plan quantity should be documented by written agreement such as a memo or Resident's Work Order, between the Resident and the Contractor.

The agreement must stipulate that the plan quantity will be adjusted upward or downward if changes are made in the field. Quantities paid "plan quantity" will be documented by notes of inspection and acceptance entered in the Project Diary, or directly in the Final Quantity Book.

In-Place Measurement. If the estimated quantity is not figured accurately enough to pay as a final figure, the final pay quantity will be determined from field measurements, or will be refigured from the plans, or a combination of both. Length will be distance between stations and width will be field measured Frequency of width measurements will depend on road width consistency. All measurements, and sketches if required, will be recorded in a Construction Book or directly in the final Quantity Book and signed and dated. Irregularly shaped areas such as ramp and side street approaches and intersections will be broken down into basic geometric shapes and measured by length and width. Dimensions taken from the plans land corresponding notes of inspection and acceptance also recorded in a Construction Book or the Final Quantity Book.

Added Material. If specified in the contract, material added to maintain cross-slope in areas not designated on the plans or in the construction notes will be paid separately under the item used. Measurement will be by load count reduced by 20 percent for final payment. Every load will be documented by a delivery slip that has been signed and dated at the point of delivery by the Resident or Inspector. Daily totals will be entered in the Final Quantity Book. Refer to Section 304.06 - Method of Measurement of the Specifications and Special Provisions for further explanation of shrinkage factors.

The Special Provisions, Section 108 should also be reviewed for the incorporation of Asphalt Pay Adjustment and the procedure how to determine the adjustment.

Final Quantity. Final quantity for payment will be entered in the Final Quantity Book and so labeled. References will be made to statements of inspection and acceptance, plan dimensions, field measurements, and delivery slips, as necessary. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

Division 400 – Pavements

401.5 Hot Mix Asphalt Pavement - Field Documentation. Measurement, and Payment.

This Section describes the recordkeeping necessary to document and measure hot mix asphalt placed on the project.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report, Paving Report, Tally Sheet, Test and Data Reports: The Resident or Paving Inspector will document on a daily basis, the Contractor's paving operations. He/she will keep notes regarding: station to station limits of paving, inspection problems, observations regarding quality control, equipment, personnel, weather, and temperatures. It is strongly suggested that the Paving Inspector use the Paving Report. This document has a preprinted format that serves as a reminder to record all of this information. This report is to be filled in on a daily basis, prior to the start of the next day. Ticket taker will keep a tally of all loads delivered by noting delivery slip number, the location where placed and sign the delivery slip upon delivery. The primary purpose of the Truck Tally Sheet is to control the yield and to determine which loads are involved if a problem area develops. If the Resident can isolate the loads, he/she can correlate the questionable material with specific batching data on record in the plant and in this way the cause for the bad mix may be determined.

Contract Specifications state that quality of mix will be controlled by following the "QC/QA" requirements of Sections 401 and 106 of the Specifications. The Contractor will provide quality control by testing and inspection and will propose their quality control procedures by submitting a Quality Control Plan to the Resident for Departmental approval. Specifications, Section 401 outline the basic requirements of the Plan and also procedures for quality assurance testing that the Department will perform.

Section 401 of the Special Provisions defines the quality control and quality assurance requirements at three levels: Methods A, B, and C. Method A provides for pay incentives and disincentives. Method B provides for disincentives only. Quality control and quality assurance procedures are the same for Methods A and B.

Method C is used for mixes with quantities less than 250 tons, sidewalks, drives, and other mixes behind the curb that are generally referred to as "hand-placed". Quality control requirements are not as stringent as for Methods A and B. Section 401 defines the types and frequencies of QA tests to be taken.

Special Provision, Section 403, designates which method is to be used for a particular pavement item, usually based on quantity. To better understand quality control, quality assurance, and Methods A, B, and C, the contents of Specifications - Section 401 and Special Provision - Section 403 should be thoroughly read by the Resident and the Paving Inspector before paving operations begin. All quality control records and quality assurance records will be filed together in the Testing File daily.

For sample final quantity book entries ref page 71 and for inspectors diary entries ref page 93.

Measurement and Payment.

The delivery slip for each load of hot mix asphalt delivered to the project will be signed at the point of delivery by the Resident, Inspector or Ticket Taker. Daily total quantities for each pay item will be documented by a cover slip signed by the Contractor's Representative and the Resident or Inspector, and will be entered in the Final Quantity Book; all entries will be signed and dated. Delivery slips will be kept in the Resident's field office until the records are submitted to the Project Review Unit for final review. At that time the weigh slips may be discarded, but the cover slips will be kept as part of the project records.

Occasionally a load will be split between two pay items. Quantities will be determined by fractions noted on the slip, example: "pay 1/3 load as hand-placed". A rejected load will be documented by a note on the slip stating the reason such as: segregation, dry load, or low temperature.

Check weighing to verify the accuracy of the scales will be done twice during every five days of production. Section 401.085 of the Specifications explains the check weighing procedures.

Pay factor computations for incentives, disincentives, and penalties will be part of the Testing File but final cost figures will be entered in the Final Quantity Book with the digits 01 and descriptions added to the pertinent pay item number, for example: 403.20801 Incentive-HMA-9.5 mm.

Final quantity for payment will be figured in the Final Quantity Book from daily totals. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

Division 500 – Structures

501.5 Foundation Piles - Field Documentation. Measurement. and Payment.

This Section describes the recordkeeping required to document the installation and measurement of foundation piles.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Pile Driving Inspector will keep notes describing the Contractor's pile driving operations; personnel, equipment, working hours, and which abutment or pier being worked will be recorded.

The Resident will make a note in the Project Diary of the following: approval of the pile driving equipment, approval of driving procedures, approval of driving hammer, inspection and approval of pipe piles before Contractor places concrete. Sections 501.03 - Equipment and 501.04 - Driving Procedures and Tolerances of the Specifications address, in detail, equipment and driving of piles.

The Resident will document static and dynamic load testing. Static load testing: approval of testing procedures and the results will be recorded in the Project diary. Dynamic load testing: a report of test results will be submitted to the Resident and placed in the Testing File. Specifications, Section 501.07 - Pile Testing and Acceptance explains the requirements of load testing.

Pile tips and pile splicing procedures must be approved by the Resident. Notes will be made in the Project diary. Reference is made to Section 501.09 of the Specifications.

The Resident or the Pile Driving Inspector will complete the following records and make them part of the Final Quantity Computations Book:

Pile Layout Diagram. The layout diagram is a sketch of the outline of the foundation and the batter, identification, and location of each pile by number.

Pile Driving Report. This report identifies each pile driven by number, location, driving length, pay length, and cut-off length. It also gives the type of hammer and other data pertinent to the operation. This report must be kept current with the work and must be signed by the Inspector.

Report of Record Pile. This report is a driving log of a pile; it is an indication of the energy required and the resistance encountered during the driving operation. Two record piles are required for each foundation unit. These reports must also be signed and dated.

For sample project diary entries ref page 87 and for inspectors diary entries ref page 94.

Measurement and Payment.

Foundation Piles. Payment for piles furnished will be based on quantities ordered in writing by the Resident. Cut-off piles in excess of 10 feet for each piece will become property of the Department. A Special Provision in the Contract will designate how the excess will be disposed.

Payment for piles installed will be determined from pay lengths shown on the Pile Driving Report; pay length is the difference between the driving length and the cut-off length. In the case of pipe piles, there is no payment for concrete in them.

Splices and Tips. These will be recorded for payment on the Pile Driving Report.

Loading Tests. These tests will be paid per each; reference will be made to appropriate Diary notes and test results for documentation of quantities paid.

All final quantities for payment for piles delivered, piles driven, load tests, splices, and tips will be entered in the Final Quantity Book. References to documentation of quantities will be made to pile driving reports, to test results, and to entries in the Project Diary or Inspector's Diary for statements of approval. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

502.5 Structural Concrete - Field Documentation Measurement and Payment.

This Section describes the recordkeeping necessary to document and measure concrete for major and minor structures.

Field Documentation. -

Project Diary, inspector's Diary/Daily Report: The Resident or inspector will keep notes describing the Contractor's pre-placement and placement activities, such as: excavation and preparation for erection of forms and installation of reinforcing steel. Equipment, personnel, weather, temperatures, and location of work site will be recorded also.

It is policy of the Department that the Inspector document in writing the inspection and approval of forms and reinforcing steel before a concrete placement. The Contractor is also required to do a "dry run" with the screed machine before the deck placement. The Inspector will note their observations during the dry run and also measure and record thickness of the deck slab as the concrete is placed. Notes can be entered in the Project Diary or Inspector's Diary or directly in the Final Quantity Book.

Concrete for sign bases, light bases, traffic signal bases, and other minor structures will be documented by Inspector's statements verifying that placement of forms, steel cages or mesh, anchor rods, and conduit have been checked and accepted.

For sample final quantity book entries ref page 72 & 73, for construction book entries ref page 84 and for inspectors diary entries ref page 89.

Measurement and Payment.

Final quantity for payment will be lump sum or by the cubic meter computed in-place as specified in the Schedule of Items in the Contract Book.

Lump Sum. This method of payment is specified in the bid schedule if the dimensions of the structure, be it abutment, pier, or deck, are clearly defined and not subject to change in the field. Final quantity for payment will be entered in the Final Quantity Book as "Lump Sum" and reference will be made to inspection and approval of forms, dry run of screed machine, check of the slab thickness, as appropriate.

Cubic Meter. Concrete paid by the unit is usually specified when the dimensions of the structure are not clearly identified, as when the footing is on ledge, or when the work consists of extending an existing abutment or placing a new footing on dry laid granite. In this situation, concrete is measured by delivery slip. The Inspector will sign the slip when the concrete is delivered to the site and he/she will also note amount wasted if any. The note will say, for example: "wasted !!4 cu meter", Quantity of concrete wasted shall be co-signed by the Contractor's Representative to show agreement with the amount in question. Delivery slip daily totals will be entered in the Final Quantity Book. The concrete may also be measured in-place providing a sufficient number of field measurements are taken; measurements will be entered in the Construction Book. All delivery slip totals and field measurements will be signed and dated.

Seal Concrete. When the item Structural Concrete - Placed Under Water, also known as "seal concrete", is bid by the cubic meter, and the distribution slab above it, part of the item Structural Concrete - Piers or Abutments, is also bid by the cubic meter, the following shall apply:

- Top of seal is below plan elevation: Quantity of distribution slab is figured from plan measurements for payment and the difference between the plan measured quantity and the delivery slip quantity is paid as seal concrete. Presumably the delivery slip quantity for the distribution slab will be greater than the plan measured quantity.
- 2. Top of seal is above plan elevation: Quantity of distribution slab is determined from delivery slips for payment and the difference between the plan measured quantity and the delivery slip quantity is paid as seal concrete. Presumably in this case, the delivery slip quantity for the distribution slab will be less than the plan measured quantity.

To determine whether top of seal is above or below plan elevation, check shots will have to be taken to determine the approximate elevation of the seal.

Occasionally the Schedule of Items will specify concrete to be paid by the cubic meter as opposed to lump

sum even though the dimensions of the substructure are clearly shown on the plans and will not change in the field. In this situation the concrete can be paid plan quantity providing the estimated amount is figured to the same degree of accuracy as it would be for final payment. The Resident will check the calculations and so note in the Final Quantity Book.

Where a footing is founded on ledge, concrete placed more than 12" below the designated bottom elevation of the footing will not be included in the pay quantity of concrete figured in-place. Likewise, if the concrete is figured by load count, quantity below the 12" line will be figured in-place and deducted from the total delivery slip quantity.

Since final ledge cross-sections will have already been taken to figure structural rock excavation, these same cross-sections will be used to compute quantity of concrete for payment or to figure quantity for deduction.

If the item "concrete fill" is added to the contract by work order, the lateral pay limits of the fill must be specified in the work order and the final quantity must reflect a deduction or non-payment for concrete placed beyond pay limits.

Contract Specifications stipulate that quality of concrete will be controlled by following the "QC/QA" requirements of Sections 502 and 1 06 of the Specifications. The Contractor will propose their quality control procedures by submitting a Quality Control Plan to the Department for approval. The Contractor will do quality control testing and the Resident will do quality assurance testing.

There are basically three levels of QC/QA: Method A, Method B, and "Non-QC/QA"; Special Provisions will specify the method for each item. Method A provides for incentives and disincentives; Method B provides for disincentives only. The Non-QC/QA method is used when the concrete in question must only meet the minimum quality standards in the Specifications. Examples are: armored joint repairs, surface repairs to wingwalls, bridge decks, abutments, piers, or box culverts, and modifications to concrete endposts. Cylinder breaks below what is allowed in the Specifications will be reason for either rejection of the concrete, or negotiation of a price credit. Quality control and quality assurance are explained in detail in Sections 106 and 502 of the Specifications.

Final quantity for payment will be entered in the Final Quantity Book: References will be made to source documentation, such as: Final Quantity Computations Book, delivery slips, form checks, and reinforcing steel checks. Delivery slip quantities and form checks, and re-steel checks will be entered in the Construction Book or directly in the Final Quantity Book.

Quality control records, quality assurance records, and pay factor computations will be filed in the Testing File for each day's placement. Incentive and disincentive computations and cost figures will be entered in the Final Quantity Book with digits 01 and descriptions added to the pertinent pay item number, for example: 502.2101 Incentive-Str Conc Abuts & Ret Walls. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

503.5 Reinforcing Steel - Field documentation Measurement and Payment.

This section describes the recordkeeping necessary to document and measure reinforcing steel delivered and placed in the structure.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes describing the Contractor's progress on this item; also to be noted are crew, equipment, weather, and location work is taking place, i.e., abutment, footing, pier, deck, or sign base.

When the steel is delivered, the Resident/Inspector will inspect the material for condition and proper storage. He/she will record inspection and acceptance in the Project Diary or directly in the Final Quantity Book. Delivery invoices will be kept as part of the project records.

When the Contractor places the re-steel, the Resident/Inspector will inspect for bar size, length, splice assembly, and proper positioning within the forms. He/she will document acceptance of reinforcing steel and splices by notes entered in the Project Diary or directly in the Final Quantity Book. Inspection will also be noted in the project records for re-steel placed in minor structures, such as traffic signal bases, sign bases, or concrete sidewalks.

Measurement and Payment.

Quantity for payment of reinforcing steel delivered and placed will be the quantity shown on the Steel Schedule in the contract plans, checked and corrected as necessary.

Final quantities of re-steel will be entered in the Final Quantity Book, signed and dated. Reference will be made to the Steel Schedule, computations in the Final Quantity Computations Book, and to statements of inspection and acceptance in the Project Diary or other project records.

Final quantity of splices will be entered in the Final Quantity Book. Reference will be made to the plans for the number paid; additional splices requested by the Contractor and approved by the Resident will not be measured for payment. Reference will also be made to Project Diary entries for documentation of splices installed and accepted.

Steel mesh placed in sidewalks, sign bases and traffic signal bases will not be measured for payment but is included in the bid price per unit. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

504.5 Structural Steel - Field Documentation. Measurement. and Payment.

This Section describes the recordkeeping necessary to document payment, delivery, and erection of structural steel.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will record, on a daily basis, the Contractor's progress in the erection of structural steel. He/she will keep notes regarding, but not limited to: the installation of beams, splices, diaphragms, and bearing assemblies. Crew, equipment, weather, and location, i.e., which span, girder, or abutment being worked on and lot numbers of materials will be noted.

Documentation for payment will be as follows:

<u>Fabrication and Delivery.</u> When the steel is brought on the job, the Resident and or Inspector will identify and record which girders, braces, bearing assemblies, and other hardware are delivered, and he/she will inspect for fabricating and shipping defects. Items to consider are:

- 1. Full bearing of bearing stiffeners.
- 2. Web buckles in welded girders within tolerance.
- 3. Welds in proper locations.
- 4. Burrs and roughness removed.
- 5. No loose or scaly rust in splice areas.

Notes will be made in the Project Diary or directly in the Final Quantity Book, signed and dated.

The Department will perform through the services of a private Testing Agency, shop and mill inspection of structural steel fabrication. The Fabrication Engineer will forward a copy of the Inspection Reports to the Resident. In addition, the Inspector should become familiar with the many other details of inspection explained in Section 504.4 of this Manual.

Erection. The following tests will be done and documented in the project records at the time steel is erected:

Rotational Capacity Test. Specifications, Sections 504.28 and 713.02 require that a "rotational capacity" be done on two sets of nuts, bolts, and washers in every lot delivered to the project. This test determines the compatibility of the components. The results will be noted in the Project Diary or directly in the Final Quantity Book.

Bolt Tension Test. Specifications require the Contractor to install and test bolt tension in girder splice connections and diaphragm/cross-brace connections using the following methods:

- Calibrated Wrench Method. If the Contractor makes use of a calibrated torque wrench to do QC testing, the Resident or Inspector will use the Calibrated Wrench Method to perform QA testing. Ten percent of all bolts or a minimum of two bolts per connection in all girder splices will be checked and noted on the splice inspection diagram.
- 2. Turn of the Nut Method. If the Contractor uses this method, the Inspector will witness the tightening of all bolts in the girder splices and so note on the splice inspection diagram. This inspection procedure should be verified weekly with a calibrated torque wrench. For diaphragm and cross-brace connections, the Inspector will observe the Contractor doing the turn of the nut method is acceptable; other test procedures are not required.
- 3. DTI Method. The DTI method of installation will be checked by the Inspector with a "feeler gauge". The Inspector will further verify the accuracy of the feeler gauge by checking bolt tension with a calibrated torque wrench on a weekly basis.
- 4. Inspection of Tension Control Bolts. The Inspector will inspect the bolts to verify that the spline has been snapped off. A spot check with the calibrated torque wrench will be done every week as required for methods noted above.

Departmental policy requires that the Inspector verify bolt tension in girder splices and cross-brace and diaphragm connections. Any of the above methods will be used and the results will be recorded in the Project Diary, Construction Book, or in the Final Quantity Book. On a multi-span structure, a splice layout diagram is suggested to keep account, on a daily basis, of which splices have been checked and accepted; notes will be made directly on the diagram. This sheet will become part of the project records. An overview of the structural steel layout, such as the one found in the contract plans may be used.

Measurement and Payment.

Final quantity for payment will be entered in the Final Quantity Book; references will be made to field inspections, rotational capacity tests, bolt tension tests, and other notes of inspection. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

505.5 Shear Connectors - Field documentation. Measurement. and Payment.

This Section describes the recordkeeping necessary to document and measure for payment, stud welded shear connectors.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes documenting the Contractor's progress on this item; crew, equipment, and location of work, i.e., which span and which girder, will be noted. Field welding will be done by a prequalified welder, as required under Section 504.49 of the Specifications.

The Resident or Inspector will inspect all shear connectors to assure an acceptable 360 degree weld and will also perform the "bend test" described in Section 505.04 of the Specifications. These inspection procedures will be recorded in the Project Diary or directly in the Final Quantity Book.

Measurement and Payment.

Quantity for payment, lump sum, will be recorded in the Final Quantity Book, signed and dated. Reference will be made to statements of inspection and acceptance in the project records. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

507.5 Railings - Field Documentation. Measurement. and Payment.

This Section describes the recordkeeping necessary to document and measure for payment, the installation of bridge railing.

Field Documentation

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes documenting the Contractor's progress on this item. Crew, equipment, and location of work will be noted, for example: which span if a multi-span structure, and which side, left or right, will be recorded.

Measurement and Payment.

If the item is paid lump sum, notes of inspection and acceptance will be made in the Project Diary or directly in the Final Quantity Book. If the item is paid plan quantity, the Resident will check the accuracy of the computations and will refigure the quantity from the plans if necessary. He/she will also make entries in the Project Diary or Final Quantity Book relative to inspection and acceptance. If the item is paid by the unit, field measurements will be entered in the Construction Book or the Final Quantity Book, signed and dated.

Final quantity for payment will be entered in the Final Quantity Book, and referenced to source documentation, such as: field measurements, plan calculations, or statements of inspection and acceptance, as appropriate. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

508.5 Membrane Waterproofing - Field Documentation. Inspection and Payment.

This Section describes the recordkeeping required to document and measure the installation of membrane waterproofing on bridge decks.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes describing the Contractor's preparation and installation of membrane waterproofing on bridge decks. Crew, equipment, weather conditions, and temperatures will be noted. Manufacturers' names of primer, membrane, and mastic will be recorded and verified with the Department's Approved List before approval for use. Acceptance of the item after work is completed will be recorded in the Project Diary.

For sample inspectors diary entries ref page 93

Measurement and Payment.

Final quantity for payment will be lump sum entered in the Final Quantity Book. Reference will be made to notes of inspection and final acceptance. All calculations and data entries must be signed, dated, and checked; the checker must sign and their entries.

509.5 Structural Plat Pipe and Arches-Field documentation, Measurement and Payment.

This Section describes the recordkeeping required to document and measure the assembly and installation of structural plate pipes and pipe arches.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes describing the Contractor's progress of the installation of the structural plate pipe. Notes will be made regarding, but not limited to: assembly in the dry or in the trench, excavation, bedding, torque checks, stream diversion, cofferdams, and backfilling. Crew, equipment, and weather will also be noted.

To document payment for the item, the Resident/Inspector will inspect and note acceptance of bedding and will check the tension in 10 % of the bolts using a calibrated torque wrench. Bolts are to be torqued to 100-300 ft-lbs. A wrench should be available from the Contractor.

For sample inspectors diary entries ref page 94.

Measurement and Payment

Final quantity for payment will be lump sum and will be entered in the Final Quantity Book, signed and dated. Reference will be made to notes in the Project Diary that document inspection and acceptance of bedding and the checking of bolt tension. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

There is no separate payment for excavation. Sections 206.01 (a) and 206.04(a) of the Specifications state that payment for excavation is incidental to the price bid for the structure. The quantity of granular borrow for payment will be that shown on the plans; reference is made to Section 203.18, second paragraph, of the Specifications.

510.5 Special Detour - Field Documentation. Measurement. and Payment.

This Section describes the recordkeeping required to document and measure for payment the installation of a detour on the project.

Field Documentation.

Project Diary, Inspector's Diary/Inspector's Daily Report: The Resident or Inspector will keep notes describing the Contractor's progress in the construction of the detour. The Inspector must be familiar with the contract Specifications, Section 510, to assure that the detour has been designed and constructed according to plan. Acceptance, maintenance, satisfactory removal, and clean-up of the site will be noted. Crew, equipment, and weather conditions will also be recorded.

Measurement and Payment.

Final quantity for payment will be lump sum and will be entered in the Final Quantity Book, signed, and dated. Reference will be made to notes of inspection, acceptance, and disposal recorded in the project records. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

Departmental policy is: If, during removal of the detour, the Contractor uses some of the excavation as permanant fill and if the use of this excavation does not cause a waste of usable excavation elsewhere on the project, the material in question will be measured and paid as common borrow.

511.5 Cofferdams - Field Documentation. Measurement. and Payment.

This Section describes the recordkeeping required to document and measure the installation, maintenance, and removal of cofferdams.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep a record describing the inspection and acceptance Contractor's work and submittal, approval and adherence to their Water Pollution Control Plan. Type and size of cofferdam, type of pumping operations and adequacy of the sedimentation basin and sedimentation control will be noted.

For sample final quantity book entries ref page 76, inspectors diary entries ref page 93 & 94.

Measurement and Payment.

Final Quantity Book: Final quantity for payment, lump sum, will be entered in the Final Quantity Book, signed and dated. References will be made to Project Diary entries that document acceptance of the item. The item is not accepted until the removal and clean-up of the cofferdam(s), Sedimentation Basin(s), and pump(s) has been disposed in a manner satisfactory to the Resident. Payment is made regardless of the extent of work required to build the cofferdam. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

513.05 Slope Protection - Field Documentation, Measurement. and Payment.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes describing the Contractor's progress on this item. Preparation for placing concrete or crushed stone as called for on the plans, i.e., setting grades, excavating as necessary, compacting the slope, as well as crew, equipment and weather will be recorded.

Measurement and Payment.

Final Quantity Book: Final quantity for payment will be entered in the Final Quantity Book and referenced to field measurements or plan dimensions. Measurements and calculations will be entered in the Construction Book, signed and dated. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

515.5 Protective Coating for Concrete, Surfaces - Field Documentation. Measurement. and Payment.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will record the Contractor's work activities on this item such as surface preparation and condition before applications, note the name of manufacturers material being used, verification of the material with the Departments Approved Product list, application rate of each coat, and notes of inspection and acceptance, crew, equipment, time of each application and weather conditions will also be documented.

Measurement and Payment.

Final Quantity Book: Final quantity for payment will be by the square meter or lump sum. Total units will be computed from field measurements or from dimensions scaled from the plans. Measurements, dimensions, and calculations will be entered in the Construction Book and the total transferred to the Final Quantity Book. Lump sum will be entered directly in the Final Quantity Book.

Final quantity for payment will be signed and dated. References will be made to measurements, calculations, and notes of inspection and final acceptance. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

518.5 Rehabilitation of Structural Concrete - Field Documentation. Measurement. and Payment.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will keep notes describing the Contractor's activities on this item; crew, equipment, weather conditions, location of work, i.e., which lane and which span if appropriate, will be recorded. Also to be documented are: name brand of patching material, bonding grout, and verification of the material with the Departments Approved Product list.

Measurement and Payment.

Final Quantity Book: Final quantity for payment will be determined from field measurements recorded in the Construction Book, signed and dated. Rehabilitation of Structural Concrete can involve one or a combination of three items: above re-steel, to re- steel, or below re-steel. If these items overlap in area, the item involving the largest surface area should be measured first and should be all encompassing, i.e., include the other items. These other items should then be measured after and deducted from the largest area. This method of measurement will avoid confusion and result in greater accuracy.

The final quantity will be entered in the Final Quantity Book and referred to field measurements in the Construction Book. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

520.5 Expansion Devices. Non-Modular- Field Documentation, Measurement. and Payment.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will make notes regarding: type of seal used, whether gland or compression, manufacturer's name, preparation of surface areas prior to installation, name of lubricant or sealant, and other Specifications requirements. Crew, equipment, weather conditions and temperatures will also be recorded.

Measurement and Payment.

Final Quantity Book: Final quantity for payment will be entered in the Final Quantity Book by the unit. Reference will be made to appropriate Diary entries that document inspection and acceptance. All calculations and data entries must be signed, dated and checked; the checker must sign and date their entries.

523.5 Pot Bearings - Field Documentation. Measurement. and Payment.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will inspect and note approval of: 1) when the bearings have been delivered to the site and properly stored 2) when the bearing area has been prepared; 3) when the holes are drilled and the anchor bolts grouted in place 3) note the manufactures name and verification of grout on the Department Approved product list 3) when the preformed pads, plates, and bearings are set; and 4) when the temperature adjustments have been made and the sole plates are welded to the girders. Any or all of these steps may be combined along with a final acceptance of the work.

Approved shop drawings, shop inspection reports and test results will be forwarded to the Resident by the Fabrication Engineer in advance of delivery of the bearing assemblies to the site.

Measurement and Payment.

Final Quantity Book: Final quantity for payment bid and measured by the unit for each assembly will be entered in the Final Quantity Book. References will be made to notes of inspection and acceptance of seating areas and test results for the grout. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

525.5 Granite Masonry - Field Documentation. Measurement. and Payment.

Field Documentation.

Project Diary, Inspector's Dairy/Daily Report: The Resident or Inspector will note inspection and acceptance of granite stones, anchors, mortar, and caulking material. He/she will also inspect and note the Contractor is preparing the areas prior to setting the stones.

Measurement and Payment.

Final Quantity Book: Final quantity for payment will be calculated from field measurements or plan dimensions recorded in the Construction Book. Final quantity will be entered in the Final Quantity Book, signed, dated, and referred to notes of inspection and acceptance in the Project Diary. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

526.5 Concrete Barrier - Field Documentation Measurement and Payment

Field Documentation.

Project Diary, Inspector's Diary/Daily Report: The Resident or Inspector will note when the type of barrier installed, the inspection and acceptance of forms and re-steel. Sometimes this item is pre-cast. In this situation, refer to the inspection reports written by the Inspector at the plant at the time the barriers were cast. When it is necessary to reset, a note of a spot check of the dimensions for plan conformity and will also inspect for location as shown in the traffic control plan or other contract documents.

Measurement and Payment.

Final Quantity Book: Final quantity for payment will be lump sum or by the meter.

If the Temporary Concrete Barrier is measured and paid by the linear foot, measure the total length acceptable and enter it directly in the Final Quantity Book. If the item is measured and paid Lump Sum, enter the "Lump Sum" in the Final Quantity Book.

Permanent Concrete Barrier Type II, IIIa, and IIIb will be measured for payment by Lump Sum complete in place and entered directly in the Final Quantity Book.

Permanent Transition Concrete Barrier will be measured by each barrier connecting bridge rail to guardrail complete in place and entered directly in the Inspectors Daily Report or the Final Quantity Book.

The final figure will be entered in the Final Quantity Book, signed, dated, and referenced to Diary entries for inspection and acceptance and to field measurements recorded in the Construction Book if the item is measured by the unit. All calculations and data entries will be signed, date, and checked; the checker will sign and date their work.

Division 600 – Miscellaneous Construction

603.5 Pipe Culverts and Storm Drains 604.5 Manholes and Catch Basins 605.5 Underdrain

Field Documentation

Drainage Book, Construction Book: The Resident or Inspector will keep drainage installation notes in the Drainage Book if the drainage is extensive, or in a Construction Book. If the drainage is a minor item in the contract. Section 901.3 - Field Books in Division 900, of this Manual describes in more detail the contents of these fieldbooks.

The Resident or Inspector should note the inspection of the material as it arrives on the project to insure that the material meets specifications, fits the application and is free of damage from delivery. The installation notes should include the inspection of line and location, grade, special connections, bedding & backfill material and compactive effort.

The Resident or Inspector will note the placement of any excavated material that is not used for backfilling. Excavated material should not be wasted unless there is no possible use for it on the project.

For sample project diary entries ref page 63 and for inspectors diary entries ref page 90 & 91.

Measurement and Payment

Excavation to install drainage is incidental to the item except for rock and excavation "below grade", defined in the Specifications. If a boulder or a concrete obstruction measuring two cubic meters or more is encountered in the excavation, that portion within the limits of the trench is paid as structural rock and the portion outside the limits is paid as common rock excavation. Portions within and outside the trench limits can be estimated in fractions, example " 1/2 boulder outside trench".

In a "full construction" area, if a portion of the boulder or concrete is above subgrade, that quantity will be paid as rock excavation and deducted from common excavation.

Underdrain special connections (elbows, wyes or tees) will be counted and 3 feet added per connection to the overall length of the run of pipe.

After acceptance of the catch basin or manhole, the height from floor to top of grate should be measured and recorded for final payment. Units up 2.5 meters [8 ft] will be 1 each. One fifth of a unit [one eighth of a unit] will be added for each additional 0.5 meters [1 ft] over 2.5 meters [8 ft] measured to the nearest 0.5 meters [1 ft]. Rebuild, alter and adjust items are measured as 1 each.

Section 206.5 in Division 200 of this Manual further describes structural excavation for drainage.

Final Quantity Book: Final quantity for payment will be by the linear measurement. The final figure will be entered in the Final Quantity Book, signed, dated, and referenced to Diary entries for inspection and acceptance and to field measurements recorded in the Construction Book if the item is measured by the unit. All calculations and data entries will be signed, date, and checked; the checker will sign and date their work.

606.5 Guard Rail - Field Documentation. Measurement. and Payment.

Field Documentation

Project Diary, Inspector's Diary/Daily Report, Guardrail Book: The Resident or Inspector will document the Contractor's progress on guard rail items. If guardrail work on the project is extensive and if several items are involved, for example: remove, modify, and reset, or adjust, or remove and reset, the Resident should set up a "Guardrail Book". Each run of guardrail to be worked on will be entered in this book primarily by location, i.e., station to station, left or right, and further identified by type of work to be done, whether remove, modify, and reset, or adjust, etc. As a run is completed and accepted, it will be so noted by the Inspector and dated.

All of the above documentation can be entered in the Construction Book if guardrail is not a major item in the contract.

Measurement and Payment

Final Quantity Book: Final quantity for payment will be entered in the Final Quantity Book, signed, dated, and referenced to source documentation in the Guardrail Book, or in the Construction Book for lesser quantities. Final quantities will be field measured or figured from station to station. All calculations and data entries must be signed, dated, and checked; the checker must sign their entries.

609.5 Curbing- Field Documentation. Measurement. and Payment.

Field Documentation

Project Diary, Inspector's Diary/Daily Report, or Construction Book: The Resident or Inspector will note the Contractor's progress on these items; approximate station to station limits of work, crew, equipment will be recorded and notes of inspection and acceptance.

Notes of inspection will include, in the case of vertical curbing, the condition of the curbing when it arrives on the project to insure size and tolerance specification. Notes will also include the bedding and backfill material and line and grade.

Field measurements will be entered directly in the Final Quantity Book or in the Construction Book after the curb is complete, accepted and installed. If the curbing is extensive, the Resident should set up a "Curb Book" or at least dedicate a part of the Construction Book before the Contractor begins work. The location of each item of curb, i.e., "new", "reset", or "circular", and terminal, should be identified by sketches, station to station limits, left or right shall be noted.

Final Quantity Book: Final quantity for payment will be entered in the Final Quantity Book, signed, dated, and referenced to measurements.

For sample project diary entries ref page 64.

Measurement and Payment

No separate payment is made for excavation to install curb, whether new or reset. Excavation is incidental to the curb item or to roadway excavation. There is no payment to remove existing curb; only curb that is reset is measured for payment. Removal of existing curb that is not used is incidental to other items in the contract.

All calculations and data entries will be signed, dated, and checked; the checker must sign and date their work.

610.5 Stone Fill. Rip Rap, Blanket. and Stone Ditch Protection.

Field Documentation

Project Diary, Inspector's Diary/Daily Report, Construction Book: The Resident or Inspector will make notes documenting progress of work on these items. They will record source of material, whether rock from within the excavation limits on the project, pit tailings, or rock quarry.

Measurements, sketches, and computations will be recorded in the Construction Book or directly in the Final Quantity Book.

Final Quantity Book: Final quantity for payment will be entered in the Final Quantity Book, signed, dated, and referenced to measurements and calculations. Quantities will be determined from surface area measurements to limits authorized by the Resident and to depths shown on the plans.

If riprap or stone fill is placed under water or on rough, irregular ground as required by the Resident or called for on the plans, quantity for payment can be measured by delivery slip with no reduction in volume. Reference is made to Section 610.05 of the Specifications.

Measurement and Payment

If the source of material is rock excavation, there will be no deduction from borrow, even though rock excavation is designated for use in the embankment, i.e., even though the project is a "borrow" job. Specifications, Division 100, Section 104.3.13 allows the use of ledge for items designated under this Section without deduction from borrow.

There will be no payment for excavation beyond the face of riprap, stone ditch protection, and stone blanket; only the excavation from original ground to face of the finished slope is allowed, i.e., excavation is incidental to riprap where rock is actually placed. More detailed explanation is given in Section 610 of the Specifications. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

615.5 Loam. 616.5 Sod. 618.5 Seed. 619.5 Mulch - Field Documentation. Measurement. and Payment.

These Sections describe the recordkeeping necessary to document and measure for payment loam, sod, seed, and mulch placed on the project.

Field Documentation.

Project Diary, Inspector's diary/Daily Report: The Resident or Inspector will keep notes describing the Contractor's loam, sod, seed, and mulch operations. They will record location of areas worked, personnel, equipment, and weather conditions. Depth of loam will be spot checked and recorded; loading of the hydroseeder with seed, lime, fertilizer, and mulch will also be documented.

Contract Specifications require that, at the Resident's directive, a second seeding be applied within 60 calendar days of the first seeding at the Contractor's expense if there is no acceptable growth of grass at the first seeding. The Resident must notify the Contractor before the end of the 60-day period for the Specifications requirements to remain valid. Reference is made to seed Specifications in the Contract Book for further clarification.

Measurement and Payment.

Final quantity for payment will be plan quantity or the quantity determined from measurements.

Plan Quantity. Specifications state that final payment for seed and mulch will be based on the quantities shown in the Schedule of Items if estimated areas agree within 15 percent of actual areas. A review and check of the Engineer's Estimate for reasonableness is an acceptable way to verify the quantity shown in the Schedule of Items. The plan quantity will be adjusted, upward or downward, if changes are made in the field.

Measurements. If the plan quantity is inaccurately figured or has no basis, i.e., is a "throw in" amount, quantities of seed and mulch will be determined from field measurements or from dimensions scaled off the plans.

The accuracy and frequency of measurements will depend on the project. On a rural overlay job, station-to-station limits and typical widths scaled off the plans or field measured are acceptable. On an urban job, areas will be divided into common shapes and field measured by length and width.

Loam and sod will be field measured. Field measurements and scaled measurements will be entered in the Construction Book, signed, and dated. Final pay quantity will be entered in the Final Quantity Book and labeled as such, signed and dated; references will be made to source documentation such as measurements and loading of the hydroseeder. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their entries.

626.5 Foundations. Conduit, and Junction Boxes for Highwav Signing. Lighting, and Signals - Field Documentation. Measurement. and Payment.

Field Documentation.

Project Diary, Inspector's Diary/Daily Report, Sign Book: The Resident or Inspector will keep notes regarding the Contractor's progress of work on the installation of foundations, poles, signs, lights, and traffic signals. The Resident or Inspector will document inspection and approval of forms, re-steel or steel wire mesh, anchor rods, and conduit in the foundation units.

The Resident or Inspector should keep a log of foundations installed, lengths of conduit buried, junction boxes sign locations, signal support poles and light pole foundations and documented in an Inspectors Diary or Construction book

If the project is primarily a signing or lighting job, the Resident should set up a "Sign Book" before the Contractor begins work. Signs will be identified in this book by location. The Resident or Inspector will note type of sign required and will record when the foundation is placed, when the poles, signs and lights are erected, and length of conduit and wiring installed. As noted above, inspection and acceptance of forms, resteel, anchor rods, and conduits will be recorded; other pertinent information will be noted as required.

Measurement and Payment.

Final Quantity Book: Final quantity for foundations, junction boxes, conduit, and wiring will be entered under the appropriate items in the Final Quantity Book. Reference will be made to field counts or field measurements. The Sign Book can be eliminated if signing and lighting are not a major portion of the contract; measurements and documentation can be entered directly in the Final Quantity Book or in the Construction Book. All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

629.5 Hand Labor 631.5 Equipment Rental Field Documentation. Measurement. and Payment.

Field Documentation.

Daily Report of Labor and Equipment Rental: The Resident will use this form to document hours for payment. Approval for hourly work, if not bid items, will be in writing by Work Order, and verbally by the Resident if bid items are involved. A detailed explanation of the work performed, inspected and accepted, and reference to the pertinent work order or "authorization by the Resident" should be noted in the Remarks section of the Report.

For sample project diary entries ref page 63, for final quantity book entries ref page 77, for inspectors diary entries ref page 90 & 91, and for a sample DREW from ref page 98

Measurement and Payment.

Whereas payment for hourly work often is extra and unforeseen and therefore authorized by work order, the Resident should refer to Division 100 of this Manual and the Specifications for explanation of price determination for labor and equipment.

Section 109 of this Manual further explains the circumstances under which a Work Order is required.

Specifications, Section 629, allow payment for overtime labor under the following circumstances:

- A. When the Resident requires the work to be done during the Contractor's normal overtime hours.
- B.. When the Resident directs the Contractor to do the work within a limited period of time and overtime is necessary to complete the work.
- C. When the work is of an emergency nature and overtime is required.

Final Quantity Book: Final quantities for payment will be entered under the appropriate hourly items as bid, and will be signed, dated and referred to Daily Reports of Labor and Equipment Rental.

All calculations and data entries must be signed, dated, and checked; the checker must sign and date their work.

<u>Division 900 – Project Record and Closeout</u>

This Division explains how the Resident is to prepare project records for close-out and final payment.

Section	<u>Title</u>
901	Preparation of Project Records
902	Review, Close-out, Final Payment

SECTION 901 - PREPARATION OF PROJECT RECORDS

<u>901.1 General</u> This Section describes the requirements for preparation of the project records by the Resident for final review. Field record-keeping and testing procedures for the individual pay items are explained in the appropriate sections of this Manual.

Project Records. Project records are grouped as follows:

Section	<u>Title</u>
901.2	Project Diary
901.3	Final Quantity Book
901.4	Construction Book
901.5	Drainage Book
901.6	Inspectors Diary
901.7	Final Quantity Computation Book
901.8	Testing File
901.9	Miscellaneous Records

901.2 Contents of a Project Diary

Every job must have a Project Diary, or, in the case of Field Manager, a Daily Diary or a combination Daily Diary and Inspector's Daily Report. The Project Diary is intended to give the reader a general accounting of the Contractor's and subcontractors' day by day activities such as: pay items worked and ,locations, source and disposition of excavation, borrow, gravel, and pavement grindings, All Directives given to the Contractor and non-routine matters must be recorded as well. Examples are: Traffic Accidents, the Contractor adherance to traffic maintenance and erosion control, disregarding contract Specifications, not staffing the job appropriately to complete work within required time limits, and other issues that could result in contractor claims. Matters dealing with town officials, utilities, developers, and other abutters should also be recorded. Information recorded in the Project Diary/Daily Diary should be factual and pertinent information; personal opinions and speculative remarks should not be included.

Examples of a project Diary template and typical boilerplate entries are located in Appendix A pgs 89 through 94.

901.3 Contents of a Final Quantity Book

Final Quantity Book/Item History to Date: The Final Quantity Book, or Item History to Date if the job is set up using Field Manager, is the mainspring of the project records. Every bid item originally in the contract and all work orders involving additional payment must be entered in this book; no job can be paid off without it.

Funding of a contract is sometimes divided into several funding sources, which usually result in pay items being grouped under different categories and PINs within the contract. The Final Quantity Book must be organized to reflect the different categories and pin numbers. PINs and categories will show on the first progress estimate, but if the Resident needs this information before the first estimate is issued, the Contracts Section will provide it.

A reference trail from the final pay quantity to the original documentation, whether it is notes of inspection and acceptance, measurements, or computations, must always be provided. It is suggested that the Resident and their inspectors enter original documentation and calculations to the extent feasible, directly in the Final Quantity Book

Urban full construction or reconstruction projects usually involve the town, sewer/water districts or other utilities. A formal agreement called a Municipal Agreement or a City- State Agreement drawn up between the parties will stipulate payment responsibilities and other contractual responsibilities. These agreements will frequently make the Town or the Utility District liable for a share of the project cost. The Resident should have a copy of these agreements; there may be several and they are available from the Project Manager. Items involved will normally show as a category in the progress estimate, but if not, they still need to be entered as a separate entity in the Final Quantity Book.

The Final Quantity Book/Item History to Date will have no more than one item per page. Item number, description, and estimated quantity will be entered at the top of the page. Final pay quantity will be entered at the bottom and so labeled. All entries in the Final Quantity Book must be signed, dated, and checked; the checker must sign and date each entry as well. All final quantitites in the Item History to Date must also be signed, dated, and checked, and the checker must sign and date the entries. Signatures in the Item History to Date may be signed manually or an electronic signature can be used.

Examples of Final Book entries are located in Appendix A pgs 65 through 79.

901.4 Contents of a Construction Book

Construction Book: This book is a catch-all; whether the Resident uses Field Manager or the conventional method of keeping project records, i.e., field books, a "construction book" is handy to have and usually necessary. Complex field measurements, field data, or sketches that must be recorded before that work is buried and cannot be easily recorded in the Final Quantity Book/Item History to Date can be entered in the Construction Book.

Typically, measurements for riprap, loam, seed, mulch, undercuts, top of ledge elevations, boulders, gravel used for traffic maintenance, grade checks on concrete forms and drainage systems, and layout in general will be entered in the Construction Book.

One form of a Construction book is referred to as a Grade Check Book. On a large, full construction project a grade check book should be set up prior to the work being done. This book will provide the Inspector with a handy tool to use for checking subgrade, top of gravel ("fine-grading"), ditches and backslopes. A copy may be given to the Contractor's grade foreman for them to use. The Contractor's foreman is in effect performing a Quality Control activity and the Department's Inspector is performing a Quality Assurance activity by checking, at random, the Contractor's grading accuracy.

Examples of a Construction Book entries are located in Appendix a pgs 80 through 88.

Examples of a Grade Check Book entries are located in Appendix a pgs 81 and 83.

901.5 Contents of a Drainage Book

Drainage Book: If a job has a large quantity of drainage, such as on a complex urban project, documentation of drainage installations should be entered in a separate book called a Drainage Book. This book should be organized before the work is done; each run of pipe and each catch basin or manhole would have its own page or pages.

As the work progresses, inspector's notes and measurements would be entered under the appropriate run: length of pipe and catch basins installed, gravel used for traffic maintenance, undercutting and bedding material used, ledge removed, riprap at pipe iniets or outlets, or utilities encountered, could be part of the daily entries. Quantities for payment would then be summarized in this book and transferred into the Final Quantity Book/Item History to Date.

Examples of Drainage Book entries are located in Appendix a pgs 84, 86, 90 & 91.

901.6 Contents of an Inspectors Diary

Inspector's Diaryl1nspector's Daily Report: If a job is staffed by more than one inspector, the Resident may want the inspectors to keep diaries. This diary would contain the same boilerplate information as the Project Diary but would have a more detailed accounting of the Contractor's activities and progress of work. The Inspector's observation notes and some measurements may also be recorded. Again, only pertinent and factual information should be included; no personal opinions or speculative statements should be included.

Examples of an Inspectors Diary entries are located in Appendix a pgs 89 through 94.

901.7 Contents of a Final Quantity Computations Book.

This book contains all computations that support pay quantities and that are done on 8 ½ by 11 sheets or other loose sheets. These computations may be done manually or may be computer generated. Whether the Resident uses the conventional paper method or the software program Field Manager, a Final Quantity Computations Book will be needed, as necessary. Dimensions, measurements, and computer data used in the computations must be referenced to source, whether it is plans or field measurements. All calculations and data entries must be signed, dated, and checked; the checker must also sign and date all calculations and data entries.

Computation sheets will be filed by pay item, beginning with the lowest numbered. Example: Item 201 - Clearing. A summary sheet will precede the computations for each pay item. Totals shown on each summary sheet will be transferred to the appropriate pay item in the Final Quantity Book. The pages of each item should be numbered consecutively. Computation sheets will be bound together in a red binder, titled in one inch lettering: Project Number, Project Identification Number (PIN), Town, and Final Quantity Computations Book.

Daily Reports of Hourly Work and Flagger Reports should be filed in the Final Quantity Computations Book, located as items 629-631, and item 652, respectively. Following the item computation sheets is a copy of all Extra Work Orders, and Resident's Work Orders. A list of plotting rolls and plans, and a list of field books is also required. Index tabs will be used to locate each pay item or list.

901.8 Content of the Testing File.

The Minimum Testing Requirements, also known as the "Minimums", specify the frequencies and types of tests to be taken of materials used on the project. The Minimums are determined by the Materials Section in Bangor, and are available at the following network: Network Neighborhood/DOTBGRI/Shared/Minimums. General testing requirements will be found in each Section of this Manual. The Minimums may vary from these general testing requirements to meet the needs of each particular project. The Northern Area Acceptance Testing Supervisor issues the "Minimums" for all projects; he will e-mail the requirements to the Resident. Alternately, the "Minimums" are available at the above noted address.

Exhibit 20 is a sample set of Minimum Testing Requirements.

The Resident is to use the list of Minimum Testing Requirements as a guide to test job materials. The minimum number of any particular test should not be less than the listed requirement without justifiable reason. Changes are to be explained by memo filed with the item involved. The most frequently seen change is a decrease in the number of densities required. However, due to changes in material sources, borderline materials, or work being done in several small sections (mostly on urban projects), more tests than the minimum may be necessary. The Resident must use his discretion to determine when more tests are necessary. The Resident must also explain the outcome of failing materials, i.e., removed and replaced, or accepted on the basis of substantial conformance.

If a contract contains Acceptance Methods that allow pay adjustments for hot bituminous pavement and for concrete, the Contractor's QC test data and the Engineer's Q A test data will be filed together for each day such testing is performed under the pertinent item. Pay adjustment computations will also be flied with the test data. These calculations will be done by the Resident and checked by someone knowledgeable in the

calculation of pay adjustments. The Contractor should be given the opportunity to review the adjustments before the Resident submits the project records to the Contracts Section for review.

The Testing File documents the quality of materials incorporated into the project. Reports and related data will be filed chronologically with the most recent on top and will be grouped and tabbed by pay item in the same order as shown on the list of Minimum Testing Requirements, a copy of which must be included in the front. The Testing File will be bound by a black acco-press binder and with the following information on white labels: Testing File, Project No., PIN, and Town. Index tabs will be used to separate and identify the items.

901.9 Miscellaneous Project Records

Project files consist of job records exclusive of final quantity computations, field books, and test data, turned in to the Contracts Section at the completion of the project. The following types of records should be grouped and submitted in manila envelopes: general correspondence, right-of-way records, utility records, submittals (shop drawings), permits, payrolls, payroll interviews, delivery slips, and cover slips. The envelopes should be labeled with the project number, town, and contents. Work orders, flagger reports, and daily work reports become part of the Final Quantity Computations Testing File. The preliminary engineering file, known also as "PE" file, the engineer's estimate and one copy of the bid book (Special Provisions) should also be turned in with the project records. Extra copies of the proposal book, delivery slips for hot mix asphalt, and progress estimates, vouchers, and estimate computations may be discarded before the project records are submitted for final review. The most recent progress estimate must be kept, as it will be used to prepare the Final Quantity Estimate during final review.

SECTION 902 - Review, Closeout and Final Payment

This Section describes the procedure the Resident is to follow when project records are submitted to the Project Review Unit of the Contracts Section for final review and close-out of the project.

902.1 General

The purpose of the final review is to assure that both the quality and quantity of materials and work performed by the Contractor are tested and documented according to Departmental policy and procedure.

After the job records have been assembled as described in Section 901, the Resident will contact the Project Review Unit and make an appointment to submit the records for final review. This should take place within 60 calendar days of physical completion of the project. Physical completion is described in Section 107.9, Division 100, of the Specifications.

902.2 Review

The Resident and someone in the Contracts Section, the "Reviewer", will go over the project records together to assure that the final quantities for payment are substantiated by field measurements and other original documentation as required. A project review checklist, copy following, is to be used as a guide. Also at this time, the Testing File will be reviewed to verify that materials have been tested according to the list of Minimum Testing Requirements and Departmental policy.

Pages 99 through 102 are sample final review checklists and page 103 is a sample on-site review checklist.

Work and materials that are not documented and tested in accordance with Departmental policy may require additional tests, measurements, or field documentation, or may be shown as ,"non-participating" on the Final Quantity Estimate, that is, ineligible for Federal funds.

As part of the review, the Final Quantity Estimate will be made out and labeled as such used to make progress payments, the Resident should contact the Project Review Unit, prior to submitting records for review, so that a paper copy of the most recent progress estimate can be prepared. This estimate will then be used to make out the Final Quantity Estimate. Every project must have a paper copy of the Final Quantity Estimate as part of the final contract documents.

Quantities to be billed to Towns, Sewer & Water Districts, Utility Companies, Developers, and Abutters are to be summarized and forwarded to the Bureau of Finance & Administration. Municipal Agreements, discussed under section 901.3 are to be reviewed and billings done accordingly. The Reviewer and the Resident will prepare together, at the time of final review, the bills to be sent; the Reviewer will present these bills to the

Bureau of Finance and Administration.

It is sometimes the case, that it is necessary to go back to the job to do repair work or to make changes after the project has been completed and the Contractor has been released from further obligations. By FHW A agreement, work done after project completion that involves a change in design is participating. Work that consists of restoring to original condition as designed would be considered maintenance work and not eligible for Federal Funds.

It may be done by the original Contractor or a Contractor on an active project nearby, by Town forces, or Maintenance Division forces, depending upon costs and the availability of crews and equipment. Transfer of costs from the active project to the project involved, payments to the Town, and transfer of funds to the Maintenance Division will be done by the Contracts Section with the assistance of the Resident. A work order will be required to document costs and payment procedure.

In addition to the Final Quantity Estimate, the following final documents are also required:

Time Charge Report: This report shows the required contract completion date and actual completion date. The Resident will discuss time overruns with their supervisor and document resolution of such overrun by a memo to the Project Review Unit, whether it is a time extension or assessment of liquidated damages. A meeting with the Contractor may be required in the process. Exhibit 25 is a sample Time Charge Report.

Right-of-Way Encroachment Memo: This memo lists kind and location of encroachments within the right-of-way, only if new right-of-way is taken. Pre-existing encroachments need not be reported. Page 97 is a sample Right-of-Way Encroachment memo.

Contractor Evaluation: This form is an evaluation of the Contractor's performance during construction of the project. It must be completed and signed by the Resident and co-signed by the Contractor's' Superintendent. Page 105 is a sample Contractor Evaluation packet.

Explanation of Overruns and Underruns: Written explanations of overruns and underruns are no longer required when final records are submitted for review. Significant quantity overruns and underruns will be discussed at the final team meeting. The final team meeting will be coordinated by the Resident With the Project Manager. Minutes of the meeting will be written by the Resident and distributed to team members and functional managers.

The Resident should complete the above three documents prior to final review; these documents are available from the Contracts Section in Augusta. The Final Quantity Estimate will be made out during the final review process.

Two brief reports, in the form of memos to the project file and usually one page each in length, will be written by the Reviewer. One memo addresses final quantities and the other addresses testing of materials. The "Final Quantities" memo states that project records have been reviewed and properly substantiate quantities of work incorporated into the job, with exceptions if any. The "Testing Memo" states that the testing records have been reviewed and properly substantiate the quality of materials incorporated into the project, and again, exceptions are noted, if any. Secondary documentation and explanations are made part of the memos when there are exceptions.

It may be the situation that, at the completion of final review, there remains contractor issues that are unresolved, usually: potential liquidated damages, disagreement over pay factors for hot-mix asphalt or concrete, or contractor claims. The Resident likely will be called on to help settle these items by meeting in Augusta with their Supervisors and with the Contractor; this will be done before the Project Review Unit makes final payment and the project is closed out.

902.3 Close-Out and Final Payment.

A project cannot be closed out until all outstanding issues are resolved on the project and final payment is made.

Following the final review, the Contracts Section will send a copy of final quantities to the Contractor with a cover letter stating that the final quantities are included and what final documents are to be submitted arid issues remaining to be settled before final payment can be made. Contractor's final documents are:

- Certificate of Materials, Section 700 Specifications.
- 2. "Buy America" Statement, Appendix A, Section 3, Buy America, Div 100, Specifications.
- 3. Letter" All Bills Paid", Subs 1 0 1.2, Definitions-Closeout Documentation, Div-100, Specifications.

4. FHWAForm "PR-47" on projects with full Federal oversight over \$1 million in estimated cost - Division 100,

Section 101.2 - Closeout Documentation of Division 100, Specifications, discusses the above listed documents. Contractor Evaluation Forms, and PR-47 Forms are available from the Contracts Section.

Contractors will not generally submit the "All Bills Paid" letter until they have seen the Final Quantity Estimate and have settled all items of contention with the Department, liquidated damages being the most frequent one.

A portion of the monies withheld from the Contractor (the "retent") may be paid at the time of final review or prior to it, depending on the status of the job. If there are no liquidated damages, no claims or disagreements with quantities, or no remaining work to be done in the field (such as clean-up), most of the retent may be paid. A fixed amount will be held pending the receipt of final documents.

After the Contractor submits the final documents to the Project Review Unit and all issues have been settled, final payment is made. This payment includes final adjustments, and also the remainder of the retent. When the "Final Estimate" is paid, the project records are filed with the Program. The Bureau of Finance and Administration will continue the close-out process by issuing the last check to the Contractor, and working with the FHW A for reimbursement for the Federal share of the project.

APPENDIX A

SAMPLE DOCUMENTATION

MOOT: BILL BITTERMAN, RESIDENT MAH: 6:00AM TO 5:00 PM 1 SOURCES 2 LARGE EXC. 1 5 TOWN VIB ROLLER 1 ARE 1 LABORERS 2 LARGE EXC. 1 5 TOWN VIB ROLLER 1 LABORERS 2 LARGE EXC. 1 5 TOWN VIB ROLLER 1 LASTINGS TREE REMOVAL SERVICES ITEMS 682 361 AND 656.75 MICO AND SERVIC INSPECTED AND ACCEPTED FOR THE WEEK ITEM 201, 23 SINGLE TREE THE CORNERS OF TIM CALV PIPE ITEM 603 159 INSTALLED 12" OPT I CALV PIPE ITEM 603 159 INSTALLED 12" OPT I CALV PIPE ITEM 604 997 ITEM 604 997 ITEM 604 997 ITEM 603 159 MAH MULCHED ALL DISTURBED AREAS COMPLAINT FROM BILL SIMPSON, PROJ SUPT ABOUT DELAYS FROM UTILITIES NOT SHOWN ON PLANS AS WELL AS SLOW PRODUCTION, HE THEY WILL KEEP RECORDS COMPLAINT FROM BILL SIMPSON, OP LANS AS WELL AS SLOW PRODUCTION, HE THEY WILL KEEP RECORDS COMPLAINT FROM BILL SIMPSON OF LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW ALTERMATE WAS ALSO REQUESTED INFORMATION ON LANS AS WELL AS SLOW BELLERED BY: BILL BITTERMAN 6-12-02	6/12/2002 FRIDAY	FRIDAY	•	SUNNY 80'S
6:00AM TO 5:00 PM 6:00AM TO 5:00 PM 1 SUPR 1 SUPR 1 SUPRES 2 TRUCKS 2 TRUCKS 2 LARGE EXC. 1 5 TON VIB ROLLER 1 D6 DOZER 2 LAMPION GRADER 1 D6 DOZER 2 LAMPION GRADER 2 LAMPION GRADER 1 D6 DOZER 2 LAMPION GRADER 2 LASTALLED 12" OPT III CULV PIPE 1 INSTALLED 12" OPT III CULV PIPE 2 LASTALLED AT STA 12-56 RT 2 LASTALLED 12" OPT III CULV PIPE 2 LASTALLED ALSO STUMP CHIPPER 3 STUMP CHIPPER 4 LASTALLED ALSO STUMP CHIPPER 4 LASTALLES NOT SHOWN ON PLANS AS WELL AS SI 4 CUTION. HE THEY WILL KEEP RECORDS FOR POSSETRI 2 CUTION. HE THEY WILL KEEP RECORDS FOR POSSETRI 3 LASTALES NOT SHOWN ON PLANS AS WELL AS SI 4 LASTALSO REQUESTED INFORMATION ON PLANS BY WELL AS SI 4 LASTALSO REQUESTED INFORMATION ON PLANS BY WELL AS SI 4 LASTALSO REQUESTED INFORMATION ON PLANS BY SILL BITTERMAN 6-12-02	MDOT:	BILL BITTERMAN, BILLY BOB BENNE	2	
6:00AM TQ 5:00 PM 1 SUPT 1 SUPT 2 TRUCKS 2 LARGE EXC. 1 5 TON VIB ROLLER 1 APE 1 D6 DOZER 201.23 SINGLE TREE 1 D6 DOZER 201.23 SINGLE TREE 1 D7 TILL CULV PIPE 1 D6 TILL CARDED TO GRIND E ALL DE TREE ALL DESTURBED AREAS 1 D6 TOT TILL CULV PIPE 1 D6 TILL BATTON ON PLANS AS WELL AS SILL BATTER AND PLANS AS WELL				
1 SUPT 5 WORKERS 2 LARGE EXC. 1 D TON VIB ROLLER 1 D D DOZER 1 D D D D D D D D D D D D D D D D D D D	M&H:		¥	
5 WORKERS 2 LARGE EKC. 1 5 TON VIB ROLLER 1 APE 1 D6 DOZER 201.23 SINGLE TREE 1 HASTINGS CUT AND REMOVED SINGLE TREE AND SEWPC IN PREET AND RT 4 1 D6.23 SINGLE TREE 1 D6 DOZER 201.23 SINGLE TREE 1 HASTINGS CUT AND REMOVED SINGLE TREE AND RT 4 1 D6.23 SINGLE TREE 1 HASTINGS CUT AND REMOVED SINGLE TREE AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE CORNER OF PINE STREET AND RT 4 1 THE THEY WILL KEEP RECORDS FOR POSSIBLE OF THE PROJECT 2+5G TO 45+75 1 THE HAS ALSO REQUESTED INFORMATION ON THE WORK AT THE OTHER END OF THE PROJECT 2+5G TO 45+75			╁	SOR
2 LARGE EKC. 1 5 TON VIB ROLLER 1 D6 DOZER 201.23 STREE REMOVAL SERVICES 201.23 STNGLE TREE 1 HASTINGS CUT AND REMOVED STNGLE TREE 1 HASTINGS CUT AND REMOVED STNGLE TREE 201.23 STNGLE TREE 201.23 STNGLE TREE 201.23 STNGLE TREE 201.24 STNGLE TREE 201.25 STNGLE TREE 201.25 STNGLE TREE 201.25 STNGLE TREE 201.26 STNGLE TREE 201.27 STNGLE TREE 201.28 STNGLE TREE 201.28 STNGLE TREE 201.29 STNGLE TREE 201.20 S		5 WORKERS	2 TRUCKS	
1 APE 1 D6 DOZÉR 201. E3 SINGLE TRÉE 1 HASTINGS CUT AND RÉMOVED SINGLE TRÉE A HASTINGS CUT AND RÉMOVED SINGLE TREÉ A THE CORNER OF PINÉ STREET AND RT 4 1 D6 D3. 159 1 D8 TALLED 12" OPT II CULV PIPE 1 INSTALLED AT STA 12+56 RT 1 MSTALLED AT STA 12+56 RT 2+56 TO 45+75 1 ME HAS ALSO REQUESTED INFORMATION ON NATE WORK AT THE OTHER END OF THE PROJECT 2+56 TO 45+75 1 D6 BY : BILL BITTERMAN 6-12-02		2 LARGE EXC.		IB ROLLER
1 D6 DOZÉR INGS TREE REMOVAL SERVICES 5 652.361 AND 656.75 AND SEWPC INSPECTED AND ACCEPTED FOR THE W 201.23 SINGLE TREE HASTINGS CUT AND REMOVED SINGLE TREE A THE CORNER OF PINE STREET AND RT 4 603.159 12" OPT III CULV PIPE INSTALLED 12" OPT III CULV PIPE INSTALLED AT STA 12.56 RT 604.097 6' B1-C CATCH BASIN INSTALLED ALL DISTURBED AREAS AUCHED AS A LOS AUCHED AND A LAND		1 APE		ON GRADER
S 652.361 AND 656.75 AND SEWPC INSPECTED AND ACCEPTED FOR THE W 201. 23 SINGLE TREE HASTINGS CUT AND REMOVED SINGLE TREE HASTINGS CUT AND REMOVED SINGLE TREE THE CORNER OF PINE STREET AND RT 4 THE CORNER OF PINE STREET AND RT 12-55 INSTALLED 12" OPT III CULV PIPE INSTALLED 12" OPT III CULV PIPE INSTALLED AT STA 12-56 RT STUMP CHIPPER HASTINGS USED STUMP CHIPPER HASTINGS USED STUMP CHIPPER HASTINGS USED STUMP CHIPPER LAINT FROM BILL SIMPSON, PROJ SUPT ABOUT DEI CITION. HE THEY WILL KEEP RECORDS FOR POSSIBL CULL HE HAS ALSO REQUESTED INFORMATION ON NATE WORK AT THE OTHER END OF THE PROJECT 2-50 TO 45-75 RED BY: BILL BITTERMAN \$-12-02				
AND SEWPC INSPECTED AND ACCEPTED FOR THE W 201.23 SINGLE TREE HASTINGS CUT AND REMOVED SINGLE TREE HASTINGS CUT AND REMOVED SINGLE TREE HASTINGS CUT AND REMOVED SINGLE TREE THE CORNER OF PINE STREET AND RT 4 THE CORNER OF PINE STREET AND RT 4 603.159 INSTALLED 12" OPT III CULV PIPE INSTALLED AT STA 12+56 RT AINT FROM BILL SIMPSON, PROJ SUPT ABOUT DEI UTILITIES NOT SHOWN ON PLANS AS WELL AS SI CITION. HE THEY WILL KEEP RECORDS FOR POSSIBL CHASTINGS USED STURPER END OF THE PROJECT 2+50 TO 45+75 RED BY: BILL BITTERMAN 6-12-02	HASTINGS		RVICES	
AND SEWPC INSPECTED AND ACCEPTED FOR THE WAND SEWPC INSPECTED AND ACCEPTED FOR THE WASTINGS CUT AND REMOVED SINGLE TREE HASTINGS CUT AND REMOVED SINGLE TREE AND RT 4 THE CORNER OF PINE STREET AND RT 4 INSTALLED 12" OPT III CULV PIPE INSTALLED AT STA 12+56 RT AULCHED ALL DISTURBED AREAS AUCHCHED ALL DISTURBED AREAS AUCHCHER AND ALL AREAS AUCHCHER AND ALL AREAS AUCHCHER AND ALL ALL AREAS AUCHCHER AND ALL ALL AREAS AUCHCHER AND ALL ALL ALL ALL ALL ALL ALL ALL ALL AL	1	0 361 AND 656 75		
201. 23 SINGLE TREE HASTINES CUT AND REMOVED SINGLE TREE A THE CORNER OF PINE STREET AND RT 4 THE CORNER OF PINE STREET AND RT 4 INSTALLED 12" OPT III CULV PIPE INSTALLED AT STA 12+56 RT INSTALLED AT STA 12+56 RT HASTINGS USED STUMP CHIPPER TO GRIND 2 HASTINGS USED STUMP CHIPPER TO GRIND ON THE PROJECT 2+50 TO 45+75 RED BY: BILL BITTERMAN 6-12-02		SEWPC INSPECTED	AND ACCEPTE	D FOR THE WEEK
HASTINGS CUT AND REMOVED SINGLE TREE A THE CORNER OF PINE STREET AND RT 4 THE CORNER OF PINE STREET AND RT 4 103.159 12" OPT III CULV PIPE INSTALLED 12" OPT III CULV PIPE AT STA 12-56 604.097 604.097 61 BILL BITTERMAN 6-12-02	TTFM 201	PR STNGIF TREE		
THE CORNER OF PINE STREET AND RT 4 103.159 12" OPT III CULV PIPE 1NSTALLED 12" OPT III CULV PIPE AT STA 12-50 104.097 604.097 61.2 1NSTALLED AT STA 12-56 RT 1NSTALLED AT STA 12-56 RT 1NSTALLED AT STA 12-68 RT HASTINGS USED STUMP CHIPPER TO GRIND 2 1NULCHED ALL DISTURBED AREAS 1AINT FROM BILL SIMPSON, PROJ SUPT ABOUT DEI 1NTLITIES NOT SHOWN ON PLANS AS WELL AS SI 1NTLITIES NOT SHOWN ON PLANS AS WELL SHOWN ON P		HASTINGS CUT	VD REMOVED S	
603.159 12" OPT III CULV PIPE INSTALLED 12" OPT II CULV PIPE AT STA 12-55 604.097 61.2 INSTALLED AT STA 12-56 RT INSTALLED AT STA 12-56 RT ALSTINGS USED STUMP CHIPPER TO GRIND 2 HASTINGS USED STUMP CHIPPER TO GRIND 2 HE HAS ALSO REQUESTED INFORMATION ON WATE WORK AT THE OTHER END OF THE PROJECT 2-50 TO 45-75 RED BY: BILL BITTERMAN 6-12-02		THE CORNER OF P.	INE STREET A	JD RT 4
INSTALLED 12" OPT I CULV PIPE AT STA 12-56 604.097 60.097 6. B1-C CATCH BASIN INSTALLED AT STA 12-56 RT 631.2 HASTINGS USED STUMP CHIPPER TO GRIND 2 HASTINGS USED STUMP CHIPPER TO GRIND 2 MULCHED ALL DISTURBED AREAS MULCHED AREAS MULCHED ALL DISTURBED AREAS MULCHED AR			TITI CULV PIP	10.
604.097 6' B1-C CATCH BASIN INSTALLED AT STA 12+56 RT 631.2 HASTINGS USED STUMP CHIPPER TO GRIND 2 HULCHED ALL DISTURBED AREAS AINT FROM BILL SIMPSON, PROJ SUPT ABOUT DEI UTILITIES NOT SHOWN ON PLANS AS WELL AS SL CTION. HE THEY WILL KEEP RECORDS FOR POSSIBL CTION. HE HAS ALSO REQUESTED INFORMATION ON NATE WORK AT THE OTHER END OF THE PROJECT C+50 TO 45+75 RED BY: BILL BITTERMAN 6-12-02		STALLED	T I CULV PIPE	AT STA 12-56
631.2 INSTALLED AT STA 12+56 RT 631.2 HASTINGS USED STUMP CHIPPER TO GRIND 2 NULCHED ALL DISTURBED AREAS AINT FROM BILL SIMPSON, PROJ SUPT ABOUT DEI UTILITIES NOT SHOWN ON PLANS AS WELL AS SI UTILITIES NOT SHOWN ON PLANS AS SERVED ON PLANS AS SERV	107 H2TT	190	140000000000000000000000000000000000000	
HASTINGS USED STUMP CHIPPER TO GRIND 2 CHED ALL DISTURBED AREAS WELL SILL BITTERMAN 6-12-02	TIEM DOG.	78/07/1/1/1/1	CAICH BASIN	
HASTINGS USED STUMP CHIPPER TO GRIND 2 CHED ALL DISTURBED AREAS VIT FROM BILL SIMPSON, PROJ SUPT ABOUT DEI LITTES NOT SHOWN ON PLANS AS WELL AS SL TON. HE THEY WILL KEEP RECORDS FOR POSSIBL THAS ALSO REQUESTED INFORMATION ON TE WORK AT THE OTHER END OF THE PROJECT TO 45+75 BY: BILL BITTERMAN 6-12-02			7	
HASTINGS USED STUMP CHIPPER TO GRIND 2 CHED ALL DISTURBED AREAS VT FROM BILL SIMPSON, PROJ SUPT ABOUT DEI LITTES NOT SHOWN ON PLANS AS WELL AS SL TON. HE THEY WILL KEEP RECORDS FOR POSSTBL IS HAS ALSO REQUESTED INFORMATION ON TE WORK AT THE OTHER END OF THE PROJECT TO TO 45+75 BY: BILL BITTERMAN 6-12-02	ITEM 631.	2 STUMP	CHIPPER	
VIT FROM BILL SIMPSON, PROJ SUPT ABOUT SILITIES NOT SHOWN ON PLANS AS WELL AS TON. HE THEY WILL KEEP RECORDS FOR POSS E HAS ALSO REQUESTED INFORMATION ON TE WORK AT THE OTHER END OF THE PROJEC TO 45-75 BY: BILL BITTERMAN 6-12-02		USED	STUMP CHIPPER	TO GRIND 2
NT FROM BILL SIMPSON, PROJ SUPT ABOUT LITTES NOT SHOWN ON PLANS AS WELL AS TON. HE THEY WILL KEEP RECORDS FOR POSS E HAS ALSO REQUESTED INFORMATION ON TE WORK AT THE OTHER END OF THE PROJEC TO 45.75 BY: BILL BITTERMAN 6-12-02	M&H MULC	HED ALL DISTURBE	D AREAS	
NT FROM BILL SIMPSON, PROJ SUPT ABOUT ILITIES NOT SHOWN ON PLANS AS WELL AS ION. HE THEY WILL KEEP RECORDS FOR POSS IE HAS ALSO REQUESTED INFORMATION ON TE WORK AT THE OTHER END OF THE PROJECT OF TO 45+75 BY: BILL BITTERMAN 6-12-02			ı	
	COMPLAIN	T FROM BILL SIMP	SON PROJ SU	PT ABOUT DELAYS
E HAS ALSO REQUESTED INFORMATION ON TE WORK AT THE OTHER END OF THE PROJECT TO 45+75 BY: BILL BITTERMAN 6-12-02	PROM UTIL	TITLE NOT SHOW	N ON PLANS A	S WELL AS SLOW
TE WORK AT THE OTHER O TO 45+75 BY: BILL BITTERMAN 6-	PRODUCTION OF THE PROPULATION OF	IN. HE I HEY WILL	٦,	FOR FOSS.
TE WORK ATT THE OTHER TO TO 45+75 BY: BILL BITTERMAN 6-	CLAIM. HE	HAS ALSO REQUE	STED INFORM	4 TION ON
17:54 O 1 0 43:75	ALTERNATI		HER END OF T	HE PROJECT
BY: BILL	DC+74 MIS	10 42+/2		
8V : BILL				
BY: BILL				
		BILL	IN 6-12-02	

MDOT: PERSON CONTRACTOR FEQUEN WORKI WORKI NORKI PROJECT ACTIVIT: PROJECT	RESON	EL ENT G HOURS G HOURS GENT ENT G HOURS WHER LOCATION & LIABLE CONTRISUB AND DISPOSITION OF NNY EXCANATION
ERED 8)	SOURCE AND DIS NON-ROUTINE A CONTR CONTR C. CONTR THE J D. ANYTH CONTR	SOURCE AND DISPOSITION OF GRAVEL AND BORROW A: CONTRACTORS' NON ADHERANCE TO CONTRACT SPEC'S: MTCD'S & SEWPC CONTRACT SPEC'S: MTCD'S & SEWPC CONTRACTOR SINABEQUETLY STAFFING THE JOB FOR THE TYPE OF WORK C: CONTRACTOR IS INABEQUETLY STAFFING THE JOB FOR THE TYPE OF WORK CONTRACTOR CLAIMS E: ANY DISCUSIONS WITH TOWN OFFICIALS. UTILITIES, DEVELOPERS AND ABUTTERS E: TRAFFIC ACCIDENTS & OTHER HAZARDS E: TRAFFIC ACCIDENTS & OTHER HAZARDS

6/16/02	MONDAY			FAIR 60'S	(m)
MDOT:	BILL BITTE	FRMAN, RE	RESIDENT		\$
	BILLY BOB BENNET, INSPECTOR	BENNET, I	NSPECTOR		
M&H:	6:00AM TO 5:00 PM	5:00 PM			
	1 SUPT		1 COMPRES	SOR	
	5 WORKERS		2 TRUCKS		
	2 LARGE EXC.	ic.	1 5 TON V	5 TON VIB ROLLER	
	1 APE		1 CHAMPIC	CHAMPION GRADER	
ITEM 304.	ITEM 304.10 , STA 3+DO TO 4+25	XX TO 4+25			
	AFTER PLAK	CING/COMP	ACTING LO	AFTER PLACING/COMPACTING LOWER LAYER	
OF ASC GRAVEL,	AVEL, THE	THE SUBGRADE	MATERIAL	BEGAN TO	
PUMPING 1	NTO THE L	OWER ASC	GRAVEL LI	PUMPING INTO THE LOWER ASC GRAVEL LIFT. THE RESIDENT	SENT
DIRECTED	THE CONTR	ACTOR TO	EXCAVATE	AND REMOVE	
THE CONT	AMINATED (SRAVEL. RO	ADWAY ST	THE CONTAMINATED GRAVEL. ROADWAY STABILIZATION	
GEOTEXTI	E WAS THE	N PLACED	ON THE SU	E WAS THEN PLACED ON THE SUB-GRADE SURFACE	FACE
BEFORE PL	BEFORE PLACING ASC GRAVEL. THIS WORK	GRAVEL. T	IIS WORK	WILL BE PAID	
UNDER ITE	-M 203.20 G	OMMON EX	C AND 304	10 ASC-GRAVEL	ŒL.
REF TO BG	OK 4 PAGES	5 THROUG	H 7 FOR F	REF TO BOOK 4 PAGES 5 THROUGH 7 FOR FIELD MEASUREMENTS	MENTS
ROADWAY	STABILIZA	TION GEOT	EXTILE WI	STABILIZATION GEOTEXTILE WILL BE PAID	
PER RESID	ENTS WORK	ORDER #1	(AMOCO 2	OOG INSTALLE	(0)
THEOE WA	441 4000	F 100 F	000 1000	1, 7, 401	
וחבאה שא	CTT O OF IT 10 00 11 / WELL OF I	יייייייייייייייייייייייייייייייייייייי		I CODAY AL	
514 2+25	47 10:00 AM +/-	1 +/- VEH	VEHICLE NO 1		ER
PLAIE NO	4356 JJ) REAR-ENDED	AR-ENDED	VEHICLE NO 2 (CHEV)	O 2 (CHEVY S	5-10
PLATE NO	763784 I) W	HICH WAS	STOPPED	763784 I) WHICH WAS STOPPED FOR FLAGGER	
EU KNUWL	CS WILHIN	IHE WORK	ZUNE. TH	E ACCIDENT	WAS
INVESTIG	INVESTIGATED BY JOEL RAMICH	FL RAMICH	OF THE FA	OF THE FARMINGTON	
POLICE DE	T. ALL SIGN	NS WERE O	P AND TRA	POLICE DEPT. ALL STANS WERE UP AND TRAFFIC CONTROL	7,
DEVICES N	VERE SATIS	-ACTORY.	EFER TO d	REFER TO GORRESPONDENCE	VCE
	-	THE POLICE	ACCIDENT	REPORT	
COMPLETE	ACCIDEN	REPORT A	VD FORWA	REPORT AND FORWARDED TO THE MOOT	MDOT
LEGAL DEPT	7.				

					- Inches
ENTERED BY : BILL	Y: BILL BI	BITTERMAN 06-16-02	6-16-02		

FAIR 70'S	IN, RESIDENT INET, INSPECTOR	O PM 1 COMPRESSOR 2 TRUCKS 1 5 TON VIB ROLLER	LLERS, 1 PAVER, 12 TRUCKS, 1 SERVICE CK & 1 BOBCAT. 1 FOREMAN, 7 SKILLED, 12 UNSKILLED, NA WORKERS	AND ACCEPTED STA 22+00 TO 35+25 REAN AT STA 22+00 TO 35+25	CALL FROM BILL COBURN-FABRICATION INSPECTOR RE: CONRETE CURBING. BILL HAD SOME CONCERNS ABOUT THE PERMABILITY. HE WILL VIST GAGNE THEIR VEAZIE TOMORROW AND WILL E-MAIL ME THE RESULTS OF THE TEST IF THERE IS A PROBLEM, REFER TO CORRES. FILE FOR RECORD.	1 1001.51	STA 2+00 TO 12+00, PIKES RECLAIMER ON PROJECT, STA 2+00 TO STA 5+00 TO REMOVE PVMT IN FULL EXCAVATION AREA, LOADER PLACING MAT'L IN TRUCKS TO BE STOCKPILED ON SITE AND PLACED AS ASE AT A LATER DATE. TO BE PAID AS COMMON EXC AND ASE. RECLAIMED STA 5+00 TO 12+00, GRADED AND COMPACTED, TO BE PAID AS 307. DENNY DOYLE, MOOT, ON SITE TO TEST 307 COMPACTION ENTERED BY: BILL BITTERMAN 6-17-02
6/17/02 MONDAY	MDOT: BILL BITTERMAN, R BILLY BOB BENNET,	M&H: 6:00AM TO 6:00 PM 1 SUPT 5 WORKERS 2 LARGE EXC.	SUB: PIKE IND, 4 ROLLERS, 1 PAIL TRUCK, 1 WATER TRUCK & 1 BOBC. PERSONNEL: 1 SUPT, 1 FOREMAN, 2 LABORERS & 2 QC/QA WORKERS	FINEGRADE COMPLETE AND ACCE ITEM 403 207 PAVING OPERATIONS BEGAN AT	CALL FROM BILL COBURN-FABRICATION INSPECTOR RE: CONRETE CURBING. BILL HAD SOME CONCERNS THE PERMABILITY. HE WILL VIST GAGNE THEIR VE. TOMORROW AND WILL E-MAIL ME THE RESULTS OF TEST IF THERE IS A PROBLEM, REFER TO CORRES. F RECORD.	STA 2+00 TO 5+00, EXCES. REMOVED AND TAKEN TO . ITEM 203.20	STA 2+00 TO 12+00, PIKES RECLAIMER ON PRO TO STA 5+00 TO REMOVE PVANT IN FULL EXCAL LOADER PLACING MAT"L IN TRUCKS TO BE STO SITE AND PLACED AS ASG AT A LATER DATE. COMMON EXC AND A\$G. RECLAIMED STA 5+00 GRADED AND COMPACTED, TO BE PAID AS 307. DENNY DOYLE, MDOT ON SITE TO TEST 307 of ENTERED BY: BILL BITTERMAN 6-17-02

NOTE: THE ENGINEERS ESITIMATE WAS REVIEWED AND APPEARS TO BE REASONABLE AND ACCURATE. REF: RWO NO 1; CONTRACTOR ASREED TO PLAN QTY PAYMENT RULS ANY ADDITIONAL EXCANATION CUTSIDE OF EXCANATION LIMITS OR AS DIRECTED. BK 3 P6 1 BK 3 P6 1 BK 3 P6 1 BK 3 P6 1 BK 4 P6 X BK 4 P6 X BK 4 P6 X	202.20	COMMON	COMMON EXCAVALION	>		$\mathbb{E}\left[\mathbb{E}\left[$
NOTE: THE ENGINEER'S ESTIMATE WAS REVIEWED AND APPEARS TO BE REASONABLE AND ACCURATE. REF: RWO NO 1; CONTRACTOR ASREED TO FLAN QTY PAYMENT PLUS ANY ADDITTONAL EXCAVATION OUTSIDE OF EXCAVATION LIMITS OR AS DIRECTED. BK 3 PG 1 BK 3 PG 1 BK 3 PG 1 BK 4 PG X BK 6	REF					
REF: RWO WO 1; CONTRACTOR ASREED TO PLAN QTY PAYMENT PLUS ANY ADDITIONAL EXCANATION OUTSIDE OF EXCANATION LIMITS OR AS DIRECTED. BK 3 PE 1 BK 3 PE 1 BK 3 PE 1 BK 4 PE X BK 6 PE X BK 6 PE X BK 7 PE X B	NOTE: THE APPEARS T	ENGINEER O BE REAS	S ESTIMAT ONABLE AN	E WAS REV D ACCURATI	<i>TEWED AN</i> E.	
PAYMENT RUSS ANY ADDITIONAL EXCAVATION OUTSIDE OF EXCAVATION LIMITS OR AS DIRECTED. BK 3 PE 1 BK 3 PE 1 BK 3 PE 2 BK 4 PE X BK 5 PE X BK	REF: RWO	NO 1; CON	TRACTOR A	GREED TO A	LAN OTY	
OF EXCAVÁTION LIMITS OR AS DIRECTED. BK 3 P6 1 BK 3 P6 1 BK 4 P6 X BK 4 P6	PAYMENT !	LUS ANY A	DDITIONAL	. EXCAVATI	ON OUTSIL	<u></u>
3 P6 1 3 P6 1 3 P6 1 3 DUCT ROCK EXC, BK 4 P6 3 4 P6 X 4 P6 X	OF EXCAV	ITION LIMI	TS OR 45	DIRECTED.		
3 P6 1 3 P6 1 5 VCT ROCK EXC, BK 4 P6 3 5 VCT ROCK EXC, BK 3 P6 6 4 P6 X			2	FOR SUBGR	ADE CHECKS	
3 P6 1 3 P6 1 9UCT ROCK EXC, BK 4 P6 9UCT ROCK EXC, BK 3 P6 4 P6 X				-		
EXC, 8K 4 P6 EXC, 8K 3 P6	BK 3 PG 1					
EXC, 8K 4 P6 EXC, 8K 3 P6	BK 3 PG 1	i.				
EXC. BK	DEDUCT RO	EXC	4 PG			
	DEDUCT RO	EXC.	١.	•		
	BK 4 PG X					
	a de la constantina della cons					

\$12.00		37478	•																
600 CY @	ENT	888				888													
	400.	× 009		744.44 ~	813.11 ~	811.65	800.00 \$	67.000		1-08-02	3								
COMMON EXCAVATION	ì	009		144.44	68.67 ~	-1.46 ~	-11.39	7.00	: 800.006 CY	ENTERED RY : RTI RITTERMAN 11-08-02		. 60							
COMMON &	71.0	21+00		21+25		17.00	17.00	2/1-27	EINAL PAY QUANTITY: 800.06 C	V : RTI I RT		V: ABC 1-2							
202.20	723	15+00		20+00	16+25	16+50	20.01		EINAL PAY	FNTFRED A		CHECKED BY: ABC 1-2-03							

\$12.00		DATE	8/20/2002	8/12/2002	8/12/2002															
600 CY @	ENT	88	888	888	888															
	ACC.	QTY	11.59~	14.05~	28.65 ~				1-08-02											
VATTON		QT7	11.59~	2.46 ~	14.6 V			24.64 CY	BITTERMAN 1		> 3									
ROCK EXCAVATION		STA	17+80		22+20			CUANTITY	BILL	0 0 0 0	. ABC 1-C-									
203.21		STA	17+50	16+50	21+25			FINAL PAY QUANTITY:	ENTERED BY :	טוובערה מעי ייסק ז סי	בשברצבה ש									

(E)				Ē		5 & SPEC	1									•						
	TEWEN AND		LAN QTY	EXCAVATION OUTSIDE		7	$\overline{}$															
	TE WAS DEL	APPEARS TO BE REASONABLE AND ACCURATE.	1 7371		Z N .	COMPLETE	AVATION (C	BK 4 PG 2 MAINTENACE OF TRAFFIC											:			
	S ESTIMA	NABLE AN	TRACTOR A	PAYMENT PLUS ANY ADDITIONAL	TS OR 45	MULTI PLATE BACKFILL	TONAL EXC.	CE OF TRAF		i												
	FNGTNEE	O BE REAS	NO 1; CON	LUS ANY A	TION LIM.	MULTI PLAT	FOR ADDIT.	NAINTENA														
	REF NOTE: THI	APPEARS T	REF: RWO	PAYMENT !	OF EXCAV.	BK 4 PG 2 ,	BK 4 PG 2	BK 4 PG 2,														

	Smith's		Атеѕ							
	accord to plan/spec, waste hauled to		waste hauled to		-					
	lan/spec, wa	1 1 1 1	1 1 1 1							
	accord to pl	#1 PAGE 5	completed accord to plan/spec,	#1 PAGE 8						
	Completed waste area	REF TO INSP DIARY #1 PAGE 5 DIRECT ENT.	completed c waste area	REF TO INSP DIARY #1						
REF.	DIRECT EN	REF TO II		REF TO II						

@ \$3.00/ft		DATE	6/20/2002	6/20/2002	6/20/2002	6/20/2002	6/21/2002	6/21/2002	6/26/2002	6/27/2002	6/27/2002	6/27/2002	6/27/2002	6/27/2002	6/27/2002	7/1/2002		>	202	70-1									
1500 FEET	ENT	BY	888	888	888	888	888	888	888	888	888	888	888	888	888	888		: 1790 FT	M4N 11 0	0-11 1/1/1/	1-2-03								
	ACC.	LENGTH	125' ~	220'~	~,08Z	320'~	445'~	~,509	1040,~	1140'~	1265'~	~,0671	1315'~	1365'~	1465'~	1790'~		QUANTITY	20 AU 11 IN MATTER 111 OF 02	דרר מדוור	CHECKED BY: BWD1-2-03								
211.2 INSLOPE EXCAVATION		LENGTH	125'~	95, ~	~ ,09	40, ~	125' ~	160' ~	432,~	100,~	125'~	25' ~	25' ~	20, ~	100,0	325' ~	E	FINAL PAY	ENTEDEN RV .	•	~ CHECK								
INSLOPE B		STA	3+25RT	5+00RT	6+00RT	6+75RT	9+50RT	11+90RT	12+0017	22+50RT	24+50RT	25+55RT	26+75RT	28+25RT	29+50RT	30+00LT			ENIT										
211.2		STA	2+00RT	4+05FT	5+40RT	6+35RT	8+25RT	10+80RT	1+001	21+50RT	23+25RT	25+35RT	26+50RT	27+75 RT	28+50RT	21+00LT													

•		
1		
•		
•		
1		
ī.		
1		
3		
1		
8		
8		
8		
1		
1		
1		
ı		
1		
l		
2		
ı		
1		
1		
ı		
l		
3		
1		
•		
1		

3	DATE															
ACC. ENT																
ACC.	000	8	669,44			7-08-02										
	009		69.44		669.44 CY	TERMAN 11		25						i		
	21+00		21+25		FINAL PAY QUANTITY: 669.44 C	ENTERED BY : BILL BATTERMAN 11-08-02	, ,	CHECKED BY: ABC 1-C-US								
	15+00		20+02		INAL PAY	NTERED BY	100000	HECKED BY								

(E)			2-32																				
	EWED AND	REF: RWO NO 1; CONTRACTOR AGREED TO PLAN QTY PAYMENT PLUS ANY ADDITIONAL EXCAVATION OUTSIDE OF EXCAVATION LIMITS OR AS DIRECTED.	BK 3 PG 4 THRU 16 FOR FINEFRADE CHECKS ADDITION MATL USED IN DRIVES. REF INSP DIARY PG 22-32																				
•	REF NOTE: THE ENGINEERS ESTIMATE WAS REVIEWED AND APPEARS TO BE REASONABLE AND ACCURATE.	REF: RWO NO 1; CONTRACTOR AGREED TO PLAN QTY PAYMENT PLUS ANY ADDITIONAL EXCAVATION OUTS OF EXCAVATION LIMITS OR AS DIRECTED.	S REF INSP																				
	S ESTIMAT	TRACTOR A	BK 3 PG 4 THRU 16 FOR FINEFRADE CHECKS ADDITION MATL USED IN DRIVES REF INS																				
\$16.00/CY	E ENGINEER O BE REAS	NO 1: CON LUS ANY A	THRU 16 F																				
600 CY @ \$16.00/CY	REF NOTE: TH APPEARS 1	REF: RWO PAYMENT . OF EXCAV.	BK 3 PG 4																				
	MEROMANA SEMILIPANS (DANIE A REAL SE SEMILIPANS A SEMILIP	MECHECOLO (SALUTO) SE SOLUTION DE SOLUTION DE SALUTO (SALUTO)			e Po turi su m eso	A Mark Mark Speed	ika kacasans	**************************************	· · · · · · · · · · · · · · · · · · ·				***************************************	(1944) (194	SATUS PROPERTY.	580425 039 (54)	ercento)(c)	nitidatema na	wanca is 2	and the second	:#:erbs:wa	State of the	######################################
QTY	5489 37489										!												

(5) (30)					
REF					
NOTE: THE	ENGINEER	S ESTIMAT	NOTE: THE ENGINEERS ESTIMATE WAS REVIEWED APPEADS TO RE DEASONABLE AND ACCIDATE	TEWED AND	
עני באאט ז	שר ארעס	אישבר איא	מרכינים ב		
REF: RWO	NO 1: CON	TRACTOR A	CNI	LAN QTY	ļ
OF EXCAVA	TION LIMI	OF EXCAVATION LIMITS OR AS		EXCAVATION CUISIDE IRECTED.	الد
REF CONSTRUCTION BK 3,	RUCTION	3K 3, PG 10	12 FOR FI	PG 10-12 FOR FINEGRADE CHECKS	FCKS
•			_		

			1	F	
STA	STA	AREA	ACC. LENGTH	EN!	DATE
30+50	58+75	7,525	27,525	888	
			:		
AL PAY	FINAL PAY QUANTITY: 27,525 S	(: 27,525 S			
			,		
TERED !	ENTERED BY : BILL BITTERMAN 11-08-02	TTERMAN .	1-08-02		
CVEN	CUECVEN BV. 405 1 2 02	20			
בערה ב	7-1 200 . /	3			
			:		
		_			
		:			
	_	-			

					AC 28										Managaran (a					WENT ST	*****			an a	
	ACCUM	M.L.	1,856.25 ~		1,300.00 4,951.75 ~		1,649.25 ~ 6,601.00 ~	1,540.50 4 8,141.50 >		8,141.50 ~		(TINE)				TCIPATING)									
		M.L.	1,856.25	1,795.50~	1,300.00		1,649.25	1,540.50~		>		(PARTICIPATING)				(NON-PAR									
.5 MM	ACCUM	QTY	1,856.25	13,651.75	5,253.00	109.50 \$ 6,362.50	1,649.25 \$ 8,011,75	9, 792.25	10,756.00	10756.50	> *	ME	1 00 02	70-90-1		> <u>SN</u>	1-08-02								
SPHALT, 1		QTY	1,856.25	1,795.50	1,601.25	1,109.50	1,649.25	1,780.50	963.75~		230 50	: 10,756.00	TTEDM 4A1	ICKMAN	03 ~	230.50 TONS	TERMAN !	2 %							
403.208 HOT MIX ASPHALT, 12.5 MM		DATE	8/4/2002	8/5/2002	8/6/2002	8/7/2002	8/16/2002	8/17/2002	8/18/2002		37487	FINAL PAN QUANTITY: 10,756,00 MG	10 / 170 . 7	י פורר פו	1: ABC 1-2	QUANTITY	V : BILL BI	1. 4RC 1_2							
403.208	COVER	ON dITS	3456	3457	3458	3460	3461	3466	3469	TOTALS	3470	EINAL PAY	ENTEDEN BY . DTI . DTITEDHAM 14 00 02	CIVICACU B	CHECKED BY: ABC 1-2-03	FINAL PAY	ENTERED BY : BILL BITTERMAN 11-08-02	CHECKEN BY: 4RC 1-2-03							

9																		87												
,)			20	20	02 *	05	202	202	200			_		_	ļ		1	0716	+	+	-	<u> </u>		+	 	<u> </u>			+	
) } }	NATE	7,40	2002/5/8	8/6/2002	8/7/2002	8/8/2002	2002/11/8	8/18/2002	2002/61/8						077		l)	IE TO BE					:							
	FAIT BV	CIA! D)	888	888	888	888	888	888	888						4 PAGE 23FOR			MAPLE LANE												
	ON TO!	70,100	1	1	1	1	2	5	2	>					ARY BK 4 P			VE MIX ON	≥											
	ACCUM	, , ,			. '	1,410.75			2614.50	2614 50	20.1.20				ECTORS DI	BREAKDOWN		" NON-PARTICIPATING	FARMINGTON											
	SHLDR	*			301.25 ×	1,109.50		240.00 ~	963.75 ~						* REF INS	BREAKDOW		A-NON-PA	TOWN OF											

\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		FOR F.Q. CALCULATIONS	ION 502	TEEL CHECKS	TEBL CHECKS	TEBL CHECKS	теві снескз										
1.5. 250 CY @ \$\$25.00/CY		F.Q. COMP SECTION 502 FOR	PROJECT TESTING FILE SECTION 502	BK 5 PG 10 FOR FORMS/RE-STEBL CHECKS	BK 5 PG 1D FOR FORMS/RE-STEEL CHECKS	PG 11 FOR FORMS/RE-STEEL	5 PG 11 FOR FORMS/RE-STEBL										
RETAINING WALLS.	DATE REF	F.Q.	PROJ	5/17/2002 BK 5	5/19/2002 BK 5	6/2/2002 BK 5	6/4/2002 BK 5							Target and the state of the sta			

	ENT BY	888	888		
ENTS AND	ACCUM	18.35	43.77		
502.21 STRUCTURAL CONCRETE, ABUTMENTS AND	QTV (CY)	18.35~	17.39	1-08-02	
AL CONCRE		ENT FTG	NT FTG	2.18 CV	
STRUCTUR	LOCATION	N. ABUTMENT S. ABUTMENT BREASTWALL	S. ABUTMENT FTG	BKEASI WALL Y QUANTITY: 52.18 CY BY: ABC 1-2-03 V	
502.21	DATE	5/17/2002 N. ABUTMENT FT6 5/19/2002 S. ABUTMENT BREASTWALL	6/2/2002	ENTERED BY: BILL BITTE CHECKED BY: ABC 1-2-03	

TAINING	ENT BY	888	888						
502.22 STRUCTUAL CONCRETE, ABUTMENTS AND RETAINING	ACCUM 1	9.56 1	20.07 1						
E, ABUTME	QTY (CY)	9.56	10.51				1-08-02		
L CONCRET		ENT FTG	INT FT6			: 20.07 CY	TTERMAN .		
STRUCTUA	LOCATION	N. ABUTMENT FTG	S. ABUTMENT FTG			QUANTITY: 20.07 CY	<i>Y : BILL BI</i> <i>Y: ABC 1-2</i>		
502.22	DATE	5/2/2002	5/20/2002			FINAL PAY	ENTERED BY : BILL BITTERMAN CHECKED BY: ABC 1-2-03		

KET					
BK 3 PAGE	2	BK 2 for no	tes of inspe	for nates of inspection and acceptance	ceptance
BK 3 PAGE 8	8				
BK 3 PAGE 9	6				
BK 3 PAGE 10	10				
BK 3 PAGE 11	11				
BK 3 PAGE 12	12				
BK 3 PAGE 12	12				
BK 3 PAGE 12	12	+			
				;	

IVERED	DATE		3/7/2003																		
RICATED AND DEL	UM ENT		1563 888	4088	5463	8838	8401	10926	12176	13586				1-08-02		:					
TNG STEEL, FAB	LBS ACCUM	587	1563	2525	1375	1375	1563	2525	1250	1410	:		: 13,536 lbs	BITTERMAN 11-0	-03						
503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	LOCATION		N ABUT FTG	N ABUT BRST WALL	N ABUT WEST WING	N ABUT EAST WING	S ABUT FTG	S ABUT BRST WALL	S ABUT WEST WING	S ABUT EAST WING			FINAL PAY QUANTITY:	ENTERED BY : BILL BI	CHECKED BY: ABC 1-2-03						

	200,000				
, DEC					
KET:					
FOR NOTES OF INSPECTION REF INSP. DIARY PG 8-12	S OF INSPE	CTION REF	INSP. DIA	RY PG 8-12	
TORQUE CHECKS BK 4 PG 32	IECKS BK 4	P6 32			
			Visiting		
					The state of the s
					The second secon

			•		
	•				

			H	93				The state of the s					
ARCH		TODAY DAMAGE DUE		S IS ACCEPTED									
STEEL STRUCTURAL PLATE PIPE ARCH		PIPE DELIVERED ON PROJECT TODAY AND FOUND TO BE FREE ANY DAMAGE TO DELIVERY.	TEEL P	SPEC. AND	N/S	11-08-02							
UCTURAL P		VERED ON F VD TO BE FI SRY.	EXISTING.	GRADE AND	K: 1 LUMP SUM	TTERMAN .	-03						
STEEL STA			REMOVED INSTALLE	PER LINE, GRADE AS OF THIS DAY.	FINAL PAY QUANTITY:	ENTERED BY : BILL BITTERMAN	CHECKED BY: ABC 1-2-03						
509.12	DATE	7/18/2002	7/23/2002		FINAL PAY	ENTERED E	снескер в						

	DATE:																			
	ENT	BY	888	888	888															
									1-08-02											
X	DATE	REMOVED			7/22/2002		0,10	277	TERMAN	03										
511.07 COFFERDAM							3444	CAINITIA	V : BILL BI	1: ABC 1-2										
511.07	DATE	INSTALLED	7/19/2002	7/20/2002			ETA 141 04W	LIVAL PAY WANTILY: 1 LS	ENTERED BY : BILL BITTERMAN 11-08-02	CHECKED BY: ABC 1-2-03										

4 112 132 152 156, REF CONTRACT MOD #5 156, REF CONTRACT MOD #5	INSP DIARY BK4 PAGE 4 INSP DIARY BK 4 PAGE 12 INSP DIARY BK 4 PAGE 13 INSP DIARY BK 4 PAGE 22 INSP DIARY BK 4 PAGE 55 INSP DIARY BK 4 PAGE 55 INSP DIARY BK 4 PAGE 56
REF CONTRACT REF CONTRACT	
REF CONTRACT	
REF CONTRACT REF CONTRACT	
NET CONTRACT	
	1
	ŀ
	1
	- 1
T THE REST OF THE PARTY OF THE	

			6.		2	2		2																		
OSI.12 ALL PORPUSE EXCAVA OR (INCL OPERALOR)		DATE	7/1/2002	2002/9/2	7/16/2002	7/25/2002	8/5/2002	8/12/2002											į							
CK (INCL	ENT	BY	888	888	888	888	888	888			>	1-08-02														
マイデンくコ コイ	ACCUM	HRS	2 ~	12 ~	15~	23 ~	33 ~	41 ~	41 ~		: 41 HKS	TTERMAN.	-03 ~													
- WO 1	NO OF	HRS	7 2	10 ~	3 <	8 <	10 ~	8 <			COANILIX	ENTERED BY : BILL BATTERMAN	ABC 1-2													
	DREW	NO.	I	2	E	5	9	8	TOTAL	110	FINAL PAY	ENTERED B	CHECKED BY:													

\odot																				
@ \$65.00																				••••••
50 EA @							į		11 III										:	

		DATE	0/27/2002	10/05/2002	10/10/2008	10/25/2002	11/5/2002	11/20/2002	12/5/2002													
	ENT	ВУ	999	BAR	888	BBB	NABA >		888	>		>	2-10-02									
		REF	ATDECT EAT	-		*	BK 3 PGF XX	DIRECT ENT	DIRECT ENT	66 DRUMS		: 66 EA	BITTERMAN	-03 ~								
		EA	2	22	22	36	99	25	30	AMOUNT		QUANTITY:	BY : BT// BT	BY: ABC 1-2								
	DATE	COUNTED	0-27-01	10-15-01	10-30-01	10-25-01	11-05-01	11-10-01	11-17-01	MAXIMUM		FINAL PAY	ENTERED BY	CHECKED BY								

-	
-	

2																							
EROSION AND WATER POLLUTION	8/8/2002	3/15/2002	8/22/2002	3/29/2002	9/6/2002	9/10/2002	9/11/2002	0/13/2002	9/20/2002		~ 000 o	1-08-02											
656.75 TEMP SOIL EROSION A	דואסורכוורם	O.K.				TO REMARKS	REF TO REMARKS	70			FINAL PAY QUANTITY: 1 LS OF \$20,000	ENTERED BY : BILL BITTERMAN 11	CHECKED BY: ABC 1-2-03 V										

ION	1 L.S. @ \$20,000
	REMARKS MIKE CLARK, OES, REVISED AND APPROVED SEWPCP, PAY 10%
	PAID 50%
	V DEDCUT \$100 FOR NON COMP TO PLAN, REF TO CORRESPENCE
	✓ DEDCUT \$100 FOR NON COMP TO PLAN, REF TO CORRESPENCE DATED 9/11/02 AND AROJECT DIARY PAGE 70
	NOTE: THE DEDUCTIONS ARE MADE UNDER SAME ITEM #

									***************************************	Matrices	umaket		MINISTER STATE	MARKE AND A	**************		**************************************			eranana				SAME No.	dan kerin		LA HANNE		Kana da	XXIII SERVI
		3411001	VOLUME		487.5		2925	1107	6.794	3900 CF		144,44 CV	The second secon						18"				Van aandy-upper saansaansaansaansa ja			uning.				
	RED ENDS)	CAICTU	TEING! H		22		75	100	63	IME =		11							NFPTH = 1	ı										
>	1+25 (TAPE	ADEA CE	אאנא טר	0		39		39	0	TOAL VOLUME	1	72/(006E) = NC	Ś		1-08-02															
COMMON EXCAVATION	20+00 TO 2	NEDTU	מברות	0		1.5'		1.5'	0			TOTAL VOLUME FOR THIS SECTION	QTY = 144.44 CY		I LEKMAN I	03	3													
COMMON	XC STA	W/1 W/2		0 0		24' 28'		.82 .42	0 0		50	UME FOR T			X : BILL BA	V. 40C 4 2	7: ABC 1-C													
202.20	COMMON EXC STA 20+00 TO 21+25 (TAPERED ENDS) FROST HEAVE APEA	SECTION		1		2	(3	4		ITEM 202.	TOTAL VO	ITEM 304.104 ASG		ENIEREU BY : BILL BAI I ERMAN 11-08-02	CHECKEN	CHECKEU BY: ABC 1-2-03													

											***************************************						117											
		DWAY ELEV	VOLUME	ζ λ	21	33.6	10.5	11.2	76.3 CV	.		V 79 89		TRUCK MEASUREMENTS		WITH AS	3 5	76.3 CV	10.5		86.8 CY	***************************************	69.44 CV					
**************************************		REGRADING ENTRANCE TO MATCH NEW ROADWAY ELEV	VOLUME	VOL/LOAD	10.5	11.2	10.5	11.2	TOTAL		QTY REDUCTION	9776 3) =	1	TRUCK MEA		DETI IDNIEN	AI LOAD BY	TOTAL	TRK #117			REDUCTION	L		1-08-02			
	752	TO MATC	NO OF	104DS	2	3	1	7			T.M. QTY			#4 PAGE 60 FOR		D FXC ANIN						T.M. OTY			BITTERMAN 1.	03		
	COMMON EXC STA 16+25 L	. ENTRANC	χ		117	120	117	120				P TOTAL OTY		800K #4 PA		CK DEMOVE	WITH ONE						104 TOTAL		BY : BILL BI	/: ABC 1-2-03		
202 30	COMMON E	REGRADINE			37530	37530	10/2/2002	10/2/2001	The second secon			ITEM 202		REFER TO B	100 11	NOTE: TPICK	WITH ONE ADDIT					The second secon	ITEM 304.1		ENTERED B	CHECKED BY:		

			••••	_
77	<i>T</i>	574		RIGHT
16'	12'	س	12,	,91
-2%	-2%	15+00	-2.0%	-2%
75"	74"	12	24"	24.75"
-2%	-1 50%	15+50	-2 0%	-2%
24.25"	23.25"	21"	24"	24.75"
			-	
-2%	-1.0%	16+00	-2.0%	-2%
23.5"	22.5"	21"	24"	24.75"
-2%	-0.50%	16+50	-2 0%	-2%
22.75"	21.75"	21"	24"	24.75"
è	100	50	80,0	à
27-	+1.0%	1/400	-2.0%	-7%
20.5"	19.5"	21"	24"	24.75"
-2%	+2.5%	17+50	-3.0%	-3.0%
18.5"	17.5"	12	25.25"	26.75"
-2%	+4.0%	18+00	-4.0%	-4.0%
16.25"	15.25"	21"	26.25"	28.75"
-2%	+4.0%	18+50	-4.0%	-4.0%
16.25"	15.25"	21"	26.25"	28.75"
-2%	+2.5%	19,00	-3.0%	-3.0%
18.5"	17.5"	21"	25.25"	26.75"
80	+1 0%	19+50	-2 0%	-2%
20.5"	19.5"	21"	24"	24.75"
-2%	-0.5%	20+00	-2.0%	-2%
22.75"	21.75"	27."	24"	24.75"
-2%	-1.5%	20-50	-2.0%	-2%
24.25"	23.25"	12	24"	24.75"
-2%	-2.0%	21-00	-2.0%	-2%
75"	24"	12	24"	24.75"

RIGHT	12' 16'		9 78	94.		1	2-,	₩ 2						\d≥	1	1	Dā	НЭ	20)- <u>{</u>		1		TO TO				1	.KE	78) 23)	
STA	ښ	15+00			15+50			16+00		16+50		17:00		17+50			18+00		18+50		00+61		19+50		20+00		20+50			21+00	
LEFT	12'					:																									- To 10

ОАТЕ	37470	37470	37470	37470	
ENT	888	888	888	888	

MENTS	MEASUREMENTS QTY M3	J.XWXH 3,93X2.21X1.22=10.6 WTMIS HOTST = 1.22X 46X 2= 112	UCK #417 = 10.6-	LXWXH (2.21X1,22±10,6	2=.112	101AL FOR TRUCK #03 = 10.6 112 = 10.5	3 STANTH 12-0 OF	MINUS HOIST = 1.22X, 46X, 2=.112	TOTAL FOR TRUCK #d32 = 10.6-,112 = 8.9		S. HOIST = 1.22X. 46X. 2=.112	TOTAL FOR TRUCK #08 = 10.6 112 = 8.9		7.1-2-03			
TRUCK MEASUREMENTS	MEASUREA	3,93X2.21X1.2.	TOTAL FOR	LXWXH K2.21X1.22	ST = 1.22	TOTAL FO	LXWXH	MINUS HC	TOTAL FO	НХМХ1	S. 83XC. 11X1. 14 MINUS HOIST	TOTAL FO		CHECKED BY: ABC 1-2			
TRUCK ME.	TRUCK	M# H #017		M# H #03	MINUS HOI		M# H #032			<i>₩</i> # <i>H</i>	\$00			CHECKED B			

	16,	+	Z	ro-z	7-8	888	18		<i>'S</i>	DON	FB4	701		+	•	20)-£-	.8	88	7 1	8	LNA	5:	120	IVE	97	01	378	אש פ	110
RIGHT		37 8	9VM	1 1	1			- 1	1 1		1 1	03	- 1	HJ				- 1	1 1	l i			- 1	1		l I		ZCKF		
-	12′					:																								,
574	5	32.67	15+50		16+00		16-50		17.00	_	17+50		18+00			18+50		19.00			19.50		20100			20+50		21.00	3	

HT	16'	-2%	4"	-2%	4"	-2%	4"	-2%	##	-2%	4"	-3.0%	5.25"	-4.0%	6.75"	-4.0%	6.75"	-3.0%	5.25"	-2%	4"	-2%	4"	-2%	4"	-2%	"4"
RIGHT	12'	-2.0%	3"	-2.0%	3"	-2.0%	3"	-2 0%	3"	-2.0%	3"	-3.0%	4.25"	-4.0%	5.75"	-4.0%	5.75"	-3.0%	4.25"	-2.0%	3"	-2.0%	3"	-2.0%	3"	-2.0%	3"
574	Ę.	15+00	,,0	15+50	,,0	16+00	,,,	16+50	0	17.00	21"	17+50	0	18+00	"0	18+50	,,0	19+00	,,0	19+50	,,0	20+00	0,,,	20+50	,,,	21+00	<u>"e</u>
7-	12,	-2%	3"	-1.50%	2.25"	-1.0%	1.5"	-0 50%	75"	+1.0%	-1.5"	+2.5%	-3.5"	+4.0%	-5.75"	+4.0%	-5.75"	+2.5%	-3.5"	+1.0%	-1.5"	-0.5%	0.75"	-1.5%	2.25"	-2 0%	3"
TEET	,91	-2%	4"	-2%	3.25"	-2%	23.5"	200	1.75"	-2%	-0.5"	-2%	-2.5"	-2%	-4.75"	-2%	-4.75"	-2%	-2.5"	-2%	-0.5"	-2%	1.75"	-2%	3.25"	-2%	""

					(5)	
			4' 8		AREA INCL	Š
$^-\mathbb{F}-$	ABUT	F7 <i>6</i>	1230 7230			
		100				
		0		,	19931	EN
		2		,50		
			_			
		3	4		•	
		100				
		12.	7 7			
		AVE				
			14		A COLUMN TO THE PARTY OF THE PA	
	*	= 1.5				
		7	2			
					A TOTAL AND A	
ITEM 206. 092		T				
	F LEDGE ABC	IE PLAN I	V OF 8.5			
11		21.5 X 5.	5' (18" PAY L	(LIMIT) =	201.0 CF	
VOLUME = 201	201.0 / 27 =	7.44.07	>			
ITEM 000.00.	STRUCT	ROCK BELO	ROCK BELOW PLAN ELEV	, TO BE PAID	4ID	
1.5 TIME 206.092						
VOLUME OF LE	F LEDGE BEL	E LEDGE BELOW PLAN	ELEV OF 8.5'	5' 54 CE / 27 -	5000	
VOLUME = (0.5)			- 122.			
ITEM 502.22 C	CONCRET	22 CONCRETE UNDERWATER	4TER		And the state of t	
OTY PLACED ON LEDGE TO PLAN ELEV	SLIP NO	TO PLAN	5LEV = 6.5 CY	>		
					Salara Mariana Maria	
MEASURED/CALCULATED BY:BILL	LCULATE		BITTERMAN 6	8-30-02		
CHECKED BY: ABC 1-2-03	4BC 1-2-	> <				

3 3.8 71 7.5 6.6 1.5 1.2 1.3 1.2 1.2 1.3 1.2 1.2 1.3 1.2 1.3 1.2 1.3 1.2 1.3 1		20	+/,	7.0	1	KEMUVAL SCOTI LOCI
19.3 19.3 19.3 12.0 7.3 1.2 1		BS	Н	FS	ELEV	DEPTH BELON
12.0 7.3 1.2 12.3 7.0 1.5 13.3 1.2 13.3 7.0 1.5 14.3 7.2 1.3 15.5 6.8 1.9 15.5 6.8 1.9 15.5 6.8 1.9 15.5 6.8 1.9 15.5 6.8 1.9 15.5 6.8 1.9 15.5 6.8 1.9 15.5 6.8 1.9 15.5 6.8 1.9 15.5 6.8 15.5 7.1 1	1#3		19.3′			FTG ELEV 8.5'
12.0 7.3 1.2 1.2 1.2 1.3 1.5						
206. DR2 STRUCT EARTH EXC-MAJOR STRUCT VOLUME = 15/12-14) X 4' X 1.5' = 78 CF/27 = 2.89 206. DR2 STRUCT EARTH EXC-MAJOR STRUCT VOLUME = 2.89 X 1.15 (SWELL) = 3.32 CV 206. DR2 STRUCT ROCK EXC-MAJOR STRUCT FLEGE ELEVATIONS 8 8.4 10.5' 8 8.4 10.5' 8 8.4 10.5' 9 8.2 10.1' 9 8.2 10.1' 9 9.2 7 8.4 10.5' 8 8.4 10.5' 8 8.4 10.5' 9 8.7 11.1' 5 8 8.8 10.5' 8 8.8 10.5' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.3' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.2 10.1' 9 9.3'	7			12.0	7.3	1.2'
12.1 7.2 1.3	2			12.3	7.0	1.5'
12.5 6.8 1.9	3			12.1	7.2	1.3'
208. DB2 STRUCT EARTH EXC-MAJOR STRUCT VOLUME = .5(12+14) X 4' X 1.5' = 78 GF/27 = 2.89 203.25 GRAVEL BORROW VOLUME = 2.89 X 1.15 (SWELL) = 3.32 CV VOLUME = 2.89 X 1.15 (SWELL) = 3.32 CV 206. DB2 STRUCT ROCK EXC-MAJOR STRUCT 8	4			12.5	6.8	1.9'
1.56. DB2 STRUCT EARTH EXC-MAJOR STRUCT 1.60. DB2 STRUCT ROCK EXC-MAJOR STRUCT 1.60. DB3 TRUCT 1.60. DB3						
206. DB2 STRUCT EARTH EXC-MAJOR STRUCT VOLUME = .5(12+14) X 4' X 1.5' = 78 CF/27 = 2.89 203. 25 GRAVEL BORROW VOLUME = 2.89 X 1.15 (SWELL) = 3.32 CV 206. D92 STRUCT ROCK EXC-MAJOR STRUCT BS HI FS ELEV 3 3.8 19.3' 10.0 9.3' 6 8.8 10.5' 7 8.4 10.9' 8 8.4 10.9' 8 8.4 10.9' 9.2 10.1' 9.2 10.1' 9.2 10.1' 5 8 8.4 10.9' 8 8.8 10.5' 7 9.1 + 2(10.1+10.5) + 10.9 + 11.1)/8 = 10.2' 7 9.1 + 2(10.1+10.5) + 10.9 + 11.1)/8 = 10.2' 7 9.2 10.1' 9.3 3.8 19.3' 12.3 7.0 9.4 12.2 7.1' 9.5 12.3 7.0 9.7 12.2 7.1' 9.7 12.3 7.0	SAGE L	EPTH OF U	NDERCUT B	ELOW ELEV	8.5'	
206. 082 STRUCT EARTH EXC-MAJOR STRUCT VOLUME = .5(12+14) X 4' X 1.5' = 78 CF/27 = 2.89 203.25 GRAVEL BORROW VOLUME = 2.89 X 1.15 (SWELL) = 3.32 CY 206. 092 STRUCT ROCK EXC-MAJOR STRUCT 8						
203.25 GRAVEL BORROW 206.092 STRUCT ROCK EXCMAJOR STRUCT 706.092 STRUCT ROCK EXCMAJOR STRUCT 85 HI 85 HI 10.2 9.1' 6 8.8 10.5' 7 8.4 10.5' 8 8.4 10.9' 8 8.4 10.9' 9 1.1.1' FLEGE WEIGHTED AVERAGE ELEVATION 9 3.8 19.3' 10.2 9.1' 7 8.4 10.5 8 8.7 10.1' 8 8.8 10.5 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 3.1' 9 2 10.1' 9 3.7' 9 3.8 10.5' 7 8.4 10.5' 8 8.7 10.5' 9 1.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 2 10.1' 9 3.1' 9 2 10.1' 9 3.1' 9 2 10.1' 9 3.1' 9 2 10.1' 9 3.	206.	D82 STRUCT		-MAJOR	TRUCT	
203. 25 GRAVEL BORROW VOLUME = 2.89 X 1.15 (SWELL) = 3. 206. 092 STRUCT ROCK EXC-MAJOR STRU BS HI FS EL BS HI FS ELEVATION FLEDGE WEIGHTED AVERAGE ELEVATION OF LEDGE ELEVATIONS BS HI FS ELEVATION 9.2 8.4 8.4 8.4 8.4 8.4 8.4 8.4 8		VOLUME =	.5(12+14) >	(4' X 1.5'	= 78 CF/27	= 2.89
206. D92 STRUCT ROCK EXCMAJOR STRUM F LEDGE ELEVATIONS 8	203	OF GDAVE	WODDOW/			
FS ELL 10.0 10.2 9.2 9.2 8.8 8.4 8.4 8.2 8.4 8.2 8.4 8.2 8.4 8.2 12.3 12.3 12.3 12.2 12.2 12.2 12.2 12.2 12.2 12.2 12.3			2.89 X 1.1	= (SWELL) =		***************************************
FS ELL 10.0 10.2 9.2 8.8 8.4 8.4 8.2 8.4 8.7 8.7 8.7 8.7 8.7 8.7 8.7 8.7						
FS EL 10.0 10.2 9.2 8.8 8.4 8.2 8.7 8.7 8.7 12.2 12.2 12.2 12.2 12.2 12.2 12.2 12.2 12.2 12.2	1 206.	092 STRUCT			RUCT	
FS EL 10.0 10.2 9.2 8.8 8.4 8.4 8.7 8.7 8.7 8.8 8.4 8.2 8.7 8.7 8.8 8.4 8.2 8.2 8.2 8.2 12.3 12.3 12.2 12.0 12.1 12.2 12.2 12.2 12.2 12.3	2		7,001			
F.S. CEL 10.0 10.2 9.2 8.8 8.4 8.4 8.2 8.7 8.7 8.7 12.3 12.3 12.3 12.3 12.2 12.0 12.1	77 75		SW2T	Ų	ì	
10.0 10.2 9.2 8.8 8.4 8.4 8.2 8.7 12.3 12.3 12.3 12.3 12.2 12.0 12.1 12.3			H1		ELEV	
9.2 8.8 8.4 8.2 8.2 8.2 8.2 8.2 8.2 8.2 8.2	۵,	3.8	19.3	10.0	9.3.	
9.2 8.8 8.4 8.2 8.2 8.7 8.7 8.7 8.7 8.7 8.7 8.7 8.8 8.7 8.7	41			10.2	9.1'	
8.8 8.4 8.2 8.2 6E ELEVATION 9 + 11.1)/8 = 1 12.3 12.2 12.2 12.2 12.2 12.2 12.2 12.2 12.3	5			9.2	10.1'	***************************************
8.4 8.2 6E ELEVATION 9 + 11.1)/8 = 1 12.3 12.2 12.2 12.0 12.1 12.2 12.2 12.2 12.3	9			8.8	10.5	
6E ELEVATION 9 + 11.1)/8 = 1 7 + 11.1)/8 = 1 12.3 12.2 12.0 12.1 12.2 12.2 12.3	7			8.4	10.9'	
OF LEGGE WEIGHTED AVERAGE ELEVATION 3 + 9.1 + 2(10.1+10.5) + 10.9 + 11.1)/8 = 10.2' 7 OM OF LEGGE ELEVATIONS 8 A 19.3' 12.3 7.0 4 12.2 7.1' 5 12.2 7.1' 6 12.1 7.2' 7 12.2 7.1 8 12.3 7.0 9 12.3 7.0 12.3 7.0	8			8.2	11.1'	
OF LEDGE WEIGHTED AVERAGE ELEVATION 3 + 9.1 + 2(10.1+10.5) + 10.9 + 11.1)/8 = 10.2' COM OF LEDGE ELEVATIONS BS HI FS ELEV 3 3.8 19.3' 12.3 7.0 4 12.0 7.3' 5 12.0 7.3' 6 12.1 7.2' 7 12.2 7.1 8 12.3 7.0 OM OF LEDGE WEIGHTED AVERAGE ELEVATION						
3 + 9.1 + 2(10.1+10.5) + 10.9 + 11.1)/8 = 10.2' 70M OF LEDGE ELEVATIONS 3 3.8 19.3' 12.3 7.0 4 12.2 7.1' 5 12.0 7.3' 6 12.1 7.2' 7 12.2 7.1 8 12.3 7.0 12.3 7.0	OF LE	рбе Weigh	TED AVERA	GE ELEVAT		
TOM OF LEDGE ELEVATIONS 3 3.8 19.3' 12.3 7.0 4 19.3' 12.2 7.1' 5 12.0 7.3' 6 12.1 7.2' 7 12.2 7.1 8 12.3 7.0 TOM OF LEDGE WEIGHTED AVERAGE ELEVATION	3+9.	1 + 2(10.1+	10.5) + 10.	+	= 10.	
3 3.8 HI FS ELEV 3 3.8 19.3' 12.3 7.0 4 12.2 7.1' 5 12.0 7.3' 6 12.1 7.2' 7 12.2 7.1 8 12.2 7.1 9 12.2 7.1 12.2 7.1 12.2 7.1 12.3 7.0	OW C	F LEDGE EL	EVATIONS			
		88	HI	FS	ELEV	
	3		19.3'	12.3	7.0	
	4			12.2	7.1'	:
	5			12.0	7.3'	
	9			12.1	7.2'	
	_			12.2	7.1	
	8			12.3	7.0	
	TOM O	IF LEDGE W		VERAGE ELE	VATION	
+ 7. 1 + 2(7.3+7.2) + 7.1 + 7.0)/8 = 7.	(7.0 + 7.		2) + 7.1 +	٧.	16	

7.TON = (2)+ $X_2(Y_1-Y_3)+X_3(Y_2-Y_4)+X_4(Y_3-Y_1)$ 7.TON AT 17 + 60 DIFFERENCE DOUBLE AREA X Y OF Y'S + 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0						(و
TION AT 17 + 60 X X Y $OFY'S$ $+$ $ 0$ $+5$ $+2$ $0.25-2$ 24 $ 1.5$ $0.25-1.5$ $0.25-2$ 24 $0.25-2$ $0.35-1.5$ $0.$	AREA OF 3 .5((X,1 (Y,4)	$\frac{8ECTION}{(-Y_2)+X_2(Y)}$	<u> </u>	\ ∾	3-71	
Note	ADEA OF	LA LACTTORI AT	1			
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	מארת כן	ייי איייייי		DIFFERENCE	lu.	AREA
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	POINT	×	٨	OF Y'S	ıL	
12 +2 0-1.5=-1.5 7.5 7.5 1.2 1.2 1.2 1.3 0 1.5-0=2 24 \checkmark 0 0 0 0 0 43.5 \checkmark -7.5 0.0 0 0 0 0 43.5 \checkmark -7.5 0 0 0 0 0 0 0 0 0.15=-1.5 19.5 \checkmark 0 0 0 0 0.15=-1.5 19.5 \checkmark 0 0 0 0.15=-1.5 19.5 \checkmark 0 0 0 0 0.15=-1.5 19.5 \checkmark 0 0 0 0 0.15=-1.5 19.5 \checkmark 0 0 0 0 0 0 0.15=-1.5 19.5 \checkmark 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			0	0-2=-2		0
112 +1.5	2		7+			7.5 V
+13 0 1.5-0=1.5 19.5 \\ 0 0 0 0 43.5 \\ 0 0 0 43.5 \\	es.		+1.5	2-0-2		
0 0 0 0 0 43.5 c	4		0	1.5-0-1.5	19.5~	
TTON AT 17+ 80 TOTAL =+43.5-7.5=36 \ AREA = 36 X.5 = 18 \$F \ AREA = 1.5 \ 0.5 = 1.5 \ AREA = 1.5 \ 0.5 = 1.5 \ AREA = 1.5 \ 0.5 = 1.5 \ AREA = 1.5 \ 0.5 = 2.5 \ AREA = 23 X.5 = 11.5 \$F \ AREA = 14.75 \ 12 \ 17 \ AREA = 177 \ AREA = 177 \ AREA = 177 \ AREA = 18 \ AREA = 2.5 \ AREA = 2.5 \ AREA = 1.5 \ AREA = 1.75 \ AREA = 1.75 \ AREA = 1.5 \ AREA = 1.5 \ AREA = 1.75 \ AREA = 1.	1	_	0	0		0
TION AT 17+80 X X X Y X Y X Y X X					43.5 ~	-7.5 ~
TION AT 17+80 X Y OF $V'S$ $+$ 0 0 $0.1.5=.15$ $+$ 0 0 $0.1.5=.15$ $+$ 0 0 $0.1.5=.15$ $+$ 0 0 $0.1.5=.15$ 0 0 $0.1.5=.5$ 0 0 $0.1.5=.5$ 0 0 $0.1.5=.5$ 0 0 $0.1.5=.5$ 0 0 $0.1.5=.5$ 0 0 $0.1.5=.5$ 0 0 $0.1.5=.5$ 0 0 $0.1.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 $0.5=.5$ 0 0 $0.5=.5$ 0 0 0 0 0 0 0 0 0 0				ŀ	3.5-7.5-36	>
TION AT 17+ 80 X X Y $OF Y'S$ $+$ $ 0$ 0 $0.1.5=-1.5$ 1.5 $0.5=-1.5$ 1.5 $0.5=-5$ 1.5 $0.5=-5$ 1.5 0.5 $0.5=-5$ 1.5 0.5 $0.5=-5$ 0.5 0.5 $0.5=-5$ 0.5 0.5 $0.5=-5$ 0.5 0.5 $0.5=-5$ 0.5 0.5 $0.5=-5$ 0.5 0.5 $0.5=-5$ 0.5 0.5 $0.5=-5$ 0.5				11	X.5 = 18 SF	i I
X						
X Y OF Y'S + O'	AREA OF S	ECTION AT				
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$				DIFFERENCE	3 78000	AREA
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	POINT	×	٨	OF Y'S	+	1
5 1.5 $0.5=5$ 2.5 12 0.5 $1.5-0=1.5$ $18 \checkmark$ 2.5 13 0 $3.5-0=5$ $3.5 \checkmark$ 0 0 0 0 0 0 0 0 0 0 0 ANERACA ANERACE 0 0 0 AREA LENGTH VOLUME 0 SF FT CF 0 0 $9 \checkmark$ $10 \checkmark$ $90 \checkmark$ 0 11.5 0 0 0 0 0 11.5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 11.5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 11.5 0 0 0 0 0 0 0 0	1		0	0-1.5=-1.5		>
12 0.5 1.5-0=1.5 18 \checkmark 13 0 .5-0=.5 7.5 \checkmark 0 0 0 0 0 25.5 \checkmark 2.5 COCK REMOVED SF FT CF 0 9 \checkmark 10 \checkmark 90 \checkmark 11.5 11.5 COCK REMOVED ANERAGE ANERAGE 11.5 \checkmark 12 \checkmark 177 \checkmark 11.5 0 0 9 \checkmark 10 \checkmark 90 \checkmark 11.5 11.5 \checkmark 12 \checkmark 177 \checkmark 11.5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	2		1.5	05=5		2.5 ~
13 0 .5-0=.5 7.5 \ 0 0 0 0 0 0 0 25.5 \times 2.5 5 25.5 \times 2.5	E		0.5	1.5-0-1.5		
0 0 0 0 0 25.5 v 2.5 TOTAL =+25.5-2.5= 28 v ROCK REMOVED AREA AREA LENGTH VOLUME SF FT CF 0 9 v 10 v 90 v 11.5 11.5 COTAL VOLUME = 313/27 = 11.59 CV v	4		0	.5-0-5		
### STOTAL =+25.5-2.5= 28	1		0	0		0
ROCK REMOVED AREA = 23 X . 5 = 11.5 SF AVERAGE AREA LENGTH VOLUME SF					25.5 ~	
ROCK REMOVED AREA AREA LENGTH VOLUME 5F 5F FT CF 0 9 \ldot 10 \ldot 90 \ldot \text{ 11.5} 11.5 0 TOTAL VOLUME = 313/27 = 11.59 CY					7	>
ROCK REMOVED AREA AREA LENGTH VOLUME SF SF FT CF 0 9 \ldots 10 \ldots 90 \ldots 11.5 5.75 \ldots 8 \ldots 46 \ldots 0 707AL VOLUME = 313/27 = 11.59 CY					;	
ROCK REMOVED ANERAGE LENGTH VOLUME SF SF FT CF 0 9 10 \sqrt{90				23	.5 = 11.5	- 1
AREA AREA LENGTH VOLUME SF SF FT CF 0 9 \ldots 10 \ldots 90 \ldots 11.5 11.5 8 \ldots 46 \ldots 0 707AL VOLUME = 313/27 = 11.59 CY	VOLUME O	F ROCK REA	OVED			
AREA LENGTH VOLUME SF FT CF 0 9 \ldots 10 \ldots 90 \ldots 18 14.75 \ldots 12 \ldots 177 \ldots 11.5 5.75 \ldots 8 \ldots 46 \ldots 0 TOTAL VOLUME = 313/27 = 11.59 CY			AVERAGE			
SF FT CF 0 9 \ldots 10 \ldots 90 \ldots 18 14.75 \ldots 12 \ldots 177 \ldots 11.5 5.75 \ldots 8 \ldots 46 \ldots 0 TOTAL VOLUME = 313/27 = 11.59 CY	STA	AREA	AREA	LENGTH	NOLUME	
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$		SF	SF	FT	£	
11.5 5.75	17+50	0				
11.5 14.75 \checkmark 12 \checkmark 177 \checkmark 11.5 0 46 \checkmark 0 TOTAL VOLUME = 313/27 = 11.59 CY					~ <i>06</i>	
11.5 $5.75 \checkmark 12 \checkmark 177 \checkmark$ 0 $707AL\ VOLUME = 313/27 = 11.59\ CY$	17+60	18				
11.5 5.75			14.75~		^ <i>∐I</i>	
0 $TOTAL\ VOLUME = 313/27 = 11.59\ CV$	17+72	11.5				
0 TOTAL VOLUME = 313/27 = 11.59 CV			5.75 ~	- 1		
TOTAL VOLUME = 313/27 = 11.59 CV	17+80	ı				
		5	TAL VOLUM			5
						1


	17+00					2				.5')	PT 4 (13',0')			>	>	>	>					PT 4 (13',0')			>	>	>	>		
	VG AT STA		END	STA 17+80		9 AND 17+72				PT 3 (12', 1		21 51/	רברג	,0	2.0′	1.5'	0,				5')		FIFV		0	1.5′	.5"	0		
	REMOVING ROCK ABOVE SUBGRADE STARTING					STA 17+60		RADE				55	2	5.5	3.5	4.0	5.5		ADE		PT 3 (12'		F.S		5.5	4.0	5.0	5.5	1-08-02	
VATTON	VE SUBGRAL					TAKEN AT	90	ICTS SUBG	,			777	5.5					72	CTS SUBGA				HI	5.5					BITTERMAN	-03 ~
203.21 ROCK EXCAVATION	ROCK ABO					TWO SECTIONS WERE	T STA 17+	O ELEV DE	PT 2 (5' 2')			BC	5.5					IT STA 17+72	ELEV DEP	2 (5', 1.5')			8.5	}						V: ABC 1-2
203.21	REMOVING	PLAN		BEGIN	STA 17+00	TWO SECT	SECTION	NOTE: ZERO ELEV DEPICTS SUBGRADE			PT 1 (0',0')	TRM	- SE	PT 1	PT 2	PT 3	PT 4	SECTION A		PT		PT 1 (0',0')	TMB = 56		PT 1	PT2	PT 3	PT 4	ENTERED BY : BILL	CHECKED BY: ABC 1-2-03

					ا
	TOP	BOTTOM		416	
STA	1EDGE	1EDGE	AREA	AREA L'	VOLUME
(BEGIN OF	ROCK EXC)				
10+85	0	9.6	0		
				.25 X 5	1.25 V
10+90	10.0	9.6	0.5		
				.875 X 10	8.75 ~
11+00	10.2	9.7	1.25		
				1.25 X 10	12.5 ~
11+10	10.4	6.6	1.25	1 1	
				1.5 X 10	15 ~
11+20	10.5	9.6	1.75		
				2.13 X 10	21.3 ~
11+30	10.8	9.8	2,5		- [1
				2.75 X 10	27.5 ~
11+40	10.9	9.7	w	25 × 10	25 5
11+50	106	80	2	1	1
				1.63 X 10	16.3 V
11+60	10.4	9.6	1.25		
				1.5 X 10	15 ~
11+70	10.5	9.8	1.75		
				1.5 X 10	15 <
11+80	10.2	9.7	1.25		- 1
				.875 X 10	8.75 ~
11+90	10	8.6	0.5		ļ
			,	.25 X 5	1.25 ~
	0	9.6	0		
(END OF R	RDCK EXC)				
			TOTAL VOLUME	LUME =	16/.6 CF ~
NOTE: ALL	FINAL ROCK FLEV		ABOVE THE FLOW LINE	I- JNIT MO	I FT
PAY LIMIT		10.4	10.01		
ITEM 206. D7	20				
	OTAL	VOLUME = 167	6/27=6.2	<i>\$</i>	
				1	
MEASURED &	& CALCULATE) BY :	BILL BITTER	BITTERMAN 11-08	-02
1					

70.00.0	-				
		אוטדו עלער עלער אינו אינו אינו אינו אינו אינו אינו אינו	2017	בלא זע אלב	1 YPE C
	FROM STA	FROM STA 10+80 TO 11+90	11+90		
	TRENCH PA	TRENCH PAY WIDTH = DIA	DIA + 18"	"= 30" = 2.5"	> ,6
700 00	טיייי בו בוי				
	ארע ברבע.			!	
	ВМ	BS	HI	FS	ELEV
	#3 = 23.5	4.5	19.0		
STA					
10+90				9.0	10.0 ~
11+00				8.8	10.2 ~
01+11				8.6	10.4 ~
11+20				8.5	10.5 ~
11+30				8.2	10.8 ~
11+40				8.1	10.9 ~
11+50				8.4	10.6 ~
11+60				8.6	10.4 ~
11+70				8.5	10.5 ~
11+80				8.8	10.2 V
11+90				Ø	10 <
OTTOM C	BOTTOM OF ROCK ELEVATIONS	VATIONS			
	BM	88	HI	FS	ELEV
	#3 = 23.5	4.2	19.3'		
STA					
10+85				9.7	> 9.6
10+90				9.6	9.7 ~
11+00				9.4	> 6.6
11+10				9.5	<i>> 8.6 ✓</i>
1+20				9.5	9.8 ~
11+30				9.4	× 6.6
11+40				9.6	2.7 ~
11+50				9.5	> 8.6
11+60				9.4	> 6.6
11+70				9.5	9.8 <
11+80				9.6	2.7 <
11+90				9.5	> 8.6
11+95				9.7	> 9.6

5				5,#1	**************************************												
4	3			5 THE BEAN	A 10 DEGREE SKEW						20						
3	35	JTMENT		IE SAME A	10 DEGRE				452.9'	445.9'	RMAN 5-7-						
2		NORTH ABUTMENT	STREAM	IRE NOT T	ARE HAVE A 10				FLIVERED =	TI	 BILL BITTE	>					
1				PILE #'S	ALL PILES				86: PILES DELIVERED	61: PILES I	COMPS BY	48C 8-08-02					-
PILE NO:				NOTE: THE PILE #'S					ITEM 501.8	ITEM 501. 861: PILES IN PLACE	MEASURED/COMPS BY BILL BITTERMAN 5-7-02	CHFCK BY:					

(-)						
1 AREAS' WERE MEASURED WITH A PLANIMETER	VOLUME (CY)		3.6 <		20	
RED WITH	TIONS LENGTH (FT)	25	15	>	BILL BITTERMAN 8/20/02 -03	
ERE MEASU	CROSS SECTIONS AVERAGE LENG	2.9	6.5 1.9 TOTAL	14.6 CV	311L BITTER -03	
E1 AREAS' W	ADJACENT AREA	5.8	3.8	21 TOTAL	MEASURED/CALC BY: BILL CHECKED BY: ABC 1-2-03	
17EM 203. 21	FROM THE	21+25	21+75	ITEM 203.	CHECKED 6	



TIEM 206, 082 COMPLETED EXCAVATION AT THE NORTH ABUTMENT SECTION, UPSTREAM OF CENTERLINE, DEWATERED AREA, CLEANED OFF LEDGE, AND PLACE 12, 2 CY OF CONCRETE AREA, CLEANED OFF LEDGE, AND PLACE 12, 2 CY OF CONCRETE WAS SPILLED BEVONDTHE FORMS AND WILL, NOT BE PAID FOR. THE REMAINING CONCRETE WAS PLACED IN THIS SECTION TO THE ELEV OF THE BOTTOM THE FOOTING SHOWN ON THE PLANS. SECTION CURED WITH WATER AND CONT'D WETTED AND SELECTED AND SISSUES WERE BROUGHT TO MY ATTERN SOLVED. SEVENCE DECICES AND SISSUES WERE BROUGHT TO MY ATTERN SOLVED. TIEM 206 DRZ ALL EXCAVATED MATERIAL WAS DETERMINED TO BE UNUSABLE AND WAS SUPER, AND WERE ALL ISSUES WERE RESOLVED. TIEM 206 DRZ ALL EXCAVATED AND SEWPC DEVICES ARE INPLACE AND IN GOOD WORKING CONDITION AT THE END OF THE DAY ENTERRED BY: BILL BITTERMAN 7 16-02	7/16/2002		:	SUNNY 10 S	S	2)
COMPLETED EXCAVATION AT THE NORTH ABUTHENT SECTION, UPSTREAM OF CENTERLINE, DEWATERED AREA, CLEANED OFF LEDGE, AND PLACE 12. & CY OF CONCRETE WAS SPILLED BEYONDTHE FORMS AND WILL NOT BE PAID FOR THE REMAINING CONCRETE WAS PLACED IN THIS SECTION TO THE ELEW OF THE BOTTOM THE FOOTING SHOWN ON THE PLANS. SECTION CURED WITH WATER AND CONT'D WETTED BILL SIMPSON, OES CONSULTANT ON -SITE TO REVIEW SEWE DEFICES AND 3 ISSUES WERE BROUGHT TO MY ATTENTION, AND WERE DIRECTED IMMEDIATELY TO JEFF SIMPSON, WAS SUPER. AND WERE ALL ISSUES WERE RESOLVED. TIEM 206. DB2 ALL EXCAVATED MATERIAL WAS DETERMINED TO BE UNUSABLE AND WAS TAKEN TO THE SMITH WASTE ARE UNUSABLE AND WAS TAKEN TO THE SMITH WASTE ARE IN GOOD WORKING CONDITION AT THE END OF THE DAY ENTERED BY: BILL BITTERMAN 7-16-02	ITEM 206.	282				
AREA, CLEANED OFF LEDGE, AND PLACE 12. & CV OF CONCRETE ITEM 502. 26 PLACED 10 82 CY OF GONCRETE FILL, 1.25 CY OF CONCRETE WAS SPILLED BEYONOTHE FORM\$ AND WILL NOT BE PAID FOR. THE REMAINING CONCRETE WAS PLACED IN THIS SECTION TO THE ELEV OF THE BOTTOM THE FOOTING SHOWN ON THE PLANS. SECTION CURED WITH WATER AND ON THE PLANS. SECTION CURED WITH WATER AND CONTRESS WERE BROUGHT TO MY SEWPC DEVICES AND 3 ISSUES WERE BROUGHT TO MY ATTEM 200. DES GONSULTANT ON -SITE TO REVIEW SEWPC DEVICES AND 3 ISSUES WERE BROUGHT TO MY ATTEM 200. DES WERE RESOLVED. ITEM 622. 36 AND 656. 75 ALL MICD'S AND SEWPC DEVICES ARE INPLACE AND IN GOOD WORKING CONDITION AT THE END OF THE DAY IN GOOD WORKING CONDITION AT THE END OF THE DAY IN GOOD WORKING CONDITION AT THE END OF THE DAY IN GOOD WORKING CONDITION AT THE END OF THE DAY IN GOOD WORKING CONDITION AT THE END OF THE DAY IN GOOD WORKING CONDITION AT THE END OF THE DAY	COMPLETEL	EXCAVAT.	ON AT THE	S NORTH OF CENTER		ATERED
PLACED 10 82 CY OF CONCRETE FILL, 1.25 CY OF CONCRETE WAS SPILLED BEYOND THE FORMS AND WILL NOT BE PAID FOR. THE REMAINING CONCRETE WAS PLACED IN THIS SECTION TO THE ELEW OF THE BOTTOM THE FOOTING SHOWN ON THE PLANS. SECTION CURED WITH WATER AND CON'TO WETTED AND CON'TO WETTED SEWED DEVICES AND 3 ISSUES WERE BROUGHT TO MY ATTENITION, AND WERE DIRECTED IMMEDIATELY TO JEFF SIMPSON, WAS SUPER. AND WERE ALL ISSUES WERE RESOLVED. ITEM 206, 582 ALL EXCAUATED MATERIAL WAS DETERMINED TO BE UNIVERSITE AND SEWPC DEVICES ARE INPLACE AND IN GOOD WORKING CONDITION AT THE END OF THE DAY ENTERED 8Y: BILL BITTERMAN 7-16-02	AREA, CLE	ANED OFF L	EDGE, AND	PLACE 12.	CY OF CO	VCRETE
PLACED 10 82 CY OF CONCRETE FILL, 1.25 CY OF CONCRETE WAS SPILIED BEYONDTHE FORMS AND WILL NOT BE PAID FOR. THE REMAINING CONCRETE WAS PLACED IN THIS SECTION TO THE ELEV OF THE BOTTOM THE FOOTING SHOWN TO THE ELEV OF THE BOTTOM THE FOOTING SHOWN TO THE ELEV OF THE BOTTOM THE FOOTING SHOWN TO THE ELEV OF THE BOTTOM THE PLACE AND CONT'D WETTED BILL SIMPSON, OES CONSULTANT ON -SITE TO REVIEW SEWPC DEVICES AND 3 ISSUES WERE BROUGHT TO MY ATTENTION, AND WERE DIRECTED IMMEDIATELY TO JEFF SIMPSON, WAS SUPER. AND WERE ALL ISSUES WERE RESOLVED. ITEM 206. DR2 ALL EXCAVATED MATERIAL WAS DETERMINED TO BE UNUSABLE AND WAS TAKEN TO THE SMITH WASTE ARE UNUSABLE AND WORKING CONDITION AT THE END OF THE DAY IN GOOD WORKING CONDITION AT THE END OF THE DAY ENTERED BY: BILL BITTERMAN 7-16-02	ITEM 502.	92		i i		
WAS SPILIED BEYONDTHE FORMS AND WILL NOT BE PAID FOR. THE REMAINING CONCRETE WAS PLACED IN THIS SECTION TO THE ELEV OF THE BOTTOM THE FOOTING SHOWN ON THE PLANS. SECTION CURED WITH WATER AND CON TO WETTED AND CON TO WETTED SEWPC DEVICES AND 3 ISSUES WERE BROUGHT TO MY ATTENTION, AND WERE DIRECTED IMMEDIATELY TO JEFF SIMPSON, WAS SUPER. AND WERE ALL ISSUES WERE RESOLVED. ITEM 206. DB2 ALL EXCAVATED MATERIAL WAS DETERMINED TO BE UNUSABLE AND WAS TAKEN TO THE SMITH WASTE AREA IN GOOD WORKING CONDITION AT THE END OF THE DAY IN GOOD WORKING CONDITION AT THE END OF THE DAY ENTERED BY: BILL BITTERMAN 7-16-02	PLACED 10.	82 CY OF C	ONCRETE F	ILL, 1.25 C	Y OF CONC	SETE
FCR. THE REMAINING CONCRETE WAS PLACED IN THIS SECTION TO THE ELEV OF THE BOTTOM THE FOOTING SHOWN ON THE PLANS. SECTION CURED WITH WATER AND CONT'D WETTED BILL SIMPSON, OES CONSULTANT ON -SITE TO REVIEW SEWPC DEVICES AND 3 ISSUES WERE BROUGHT TO MY ATTENTION, AND WERE DIRECTED IMMEDIATELY TO JEFF SIMPSON, WAS SUPER. AND WERE ALL ISSUES WERE RESOLVED. ITEM 206. DB2 ALL EXCAVATED MATERIAL WAS DETERMINED TO BE UNUSABLE AND WAS TAKEN TO THE SMITH WASTE AREA IN GOOD WORKING CONDITION AT THE END OF THE DAY ENTERED BY: BILL BITTERMAN 7-16-02	WAS SPILL	ED BEYONE	THE FORM	S AND WILL	NOT BE P	4ID
SHOWN ON THE PLANS. SECTION CURED WITH WATER AND CONT'D WETTED SEURC DEVICES AND 3 ISSUES WERE BROUGHT TO MY ATTENTION, AND WERE DIRECTED IMMEDIATELY TO JEFF SIMPSON, WAS SUPER. AND WERE ALL ISSUES WERE RESQLIVED. ITEM 206. DR2 ALL EXCAVATED MATERIAL WAS DETERMINED TO BE UNUSABLE AND WAS TAKEN TO THE SMITH WASTE AREA UNUSABLE AND 656.75 ITEM 652.36 AND 656.75 IN 600D WORKING CONDITION AT THE END OF THE DAY ENTERED 87: BILL BITTERMAN 7-16-02	SECTION 1	PEMAININE TO THE FLE	V OF THE B	WAS PLAC	ED IN THIS E FOOTING	
	SHOWN O	V THE PLAN	IS. SECTIO	V CURED W	ITH WATER	
	AND CON	ט מבווב				
	BILL SIMP	SON, OES G	ONSULTAN	T ON -SIT	E TO REVIE	×
	SEWPC DE	TICES AND	3 ISSUES	VERE BROU	SHT TO MY	
	ATTENTIO	N, AND WE	RE DIRECT	D IMMEDI	TELY TO	
DETERMINED TO BE THE SMITH WASTE A AT THE END OF THE 16-02	VERE RES	SUN, WAS	SUPER. AN) WEKE ALL	155UE5	
DETERMINED TO BE THE SMITH WASTE A AT THE END OF THE -16-02	ITEM 206.	282				
THE SMITH WASTE A ARE INPLACE AND AT THE END OF THE 16-02	ALL EXCAN	ام		DETERMIN	38 OT 0	
S ARE INPLACE AND AT THE END OF THE -16-02	UNUSABLE	AND WAS		THE SMITH	WASTE	EA
AT THE END OF THE 16-02						
S ARE INPLACE AND AT THE END OF THE -16-02	ITEM 652.	36 AND 656	.75			
AT THE END OF THE -16-02	ALL MTCD	S AND SEN	PC DEVICE	S ARE INPL.		
TERMAN 7	IN 6000	VORKING C	ONDITION	AT THE EN		Z Z
TERMAN 7						
	ENTERED B	Y: BILL BI	TERMAN 7	-16-02		

	SUB	NOIL	BORROW	•	70 	on To Early	LIGNMENT		STAFFING		47		TOWN OFFICIALS.	4TERS	ZARDS			1				
WEATHER	BLE CONTR	SOURCE AND DISPOSITION OF ANY EXCAVATION			CONTRACTORS' NON ADHERANCE TO CONTRACT SPEC'S: MICD'S & SEWPC	TO CLE (NEW)	IE: RELOCATIONS, CHANGES IN ALIGNMENT		SEQUETLY S	PE OF WORK	O POTENTIAL		TH TOWN D	VITUATIES DEVELOPRES AND ABUTTERS	TRAFFIC ACCIDENTS & OTHER HAZARDS							
	LOCATION & LIA	TTON OF A	SOURCE AND DISPOSITION OF GRAVEL AND		CONTRACTIORS' NON CONTRACT SPEC'S: M	Kof TVRS G	TTONS, CI	מ ארוייטאא	CONTRACTOR IS XNADEQUETLY S	OR THE YN		CONTRACTOR CLAIMS	WEIONS WI	DEVELOPE	CCIDENTS							
	ABER,	ND DISPOS	ND DISPOS	NON-ROUTINE ACTIVITIES	CONTRACT	MACTOR	IE: RELOC	CINDERLUI	CONTRACT	THE/JOB \	ANYTHINE	CONTRACT	ANVIOLER	र्णम्याम्	TRAFFIC A						2776	24.n
DAY	ACTIVITIES: I TTEM NUMBER				¥ (j j			9		D:	-			6:						CATEDOR N. MARIE	AY . INAMIC
DATE	PROJECT ,																				CATTERE	בואובאנה

6	9			E PIPE	INE,	ATED		IS PIPE	LAY.	SIDENT			4DE	ROPOSED		4.7"			S															
2,0	0	N III	Q)	48' OF 12" CORR. POLYETHYLENE PIPE	PIPE WAS INSTALLED PER LI	7	H 8" LIFT	T BELOW THIS PIPE	NING BLUE d	THIS UNDERCUT WAS APPROVED BY THE RESIDENT			BELOW GRADE	-T.		1 5+23.5/5=24.7"	H SIDE)=42		X40'/27=5.5		CUT			MUST BE		1								
SINN 7018	SOINIVY V.	CULVERT PIPE OPTION	12" CMP AN	2" CORR. PC	WAS INST	ACKFILLED N	AND COMPACTED EACH 8" LIFT	THERE WAS ALSO AN UNDERCUT	SE UNDERL	S APPROVED		MENTS	HRTH EXC			27	7 + 15"(EAC		7"-12")X(15"+12"+15")X40'/27=5.	REORROW			; ;	IN PLACE		15 - 6 33	0.00	6-7-02						
		CULVERT ,	w		4+75. PIPE	ID SPEC. BA		45 ALSO AI	ΦF UNSTAB	SERCUT WA		T MEASUREMENTS	STRUCT EA	WAS UNDE	Æ	DEPTH =22.	MAX WIDTH-PIPE DI		1 7"-12"X(1	GRANULAR	D TO BACK	V =5.5 CY		BORROW MEASUREED	BY 15%	N-5571	\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \	BITTERMAN				**********		
EDTAAV	LKIDAY	603.159	REMOVED	INSTALLED	AT STA 12+75.	GRADE AND SPEC.	MATERIAL	THERE W	BECAUSE	THIS UND	ENGINEER	UNDERCUT	206.061	THE PIPE	FLOW LIN	AVERAGE	MAX WID	LENGTH =	QTY = (24.	203.25		TOTAL QT		BORROW ,	SWELLED BY 15%	TO 141 OT	30,00	BY: BILL B.						
10/2/7	70///0	ITEM											ITEM							ITEM								ENTERED I						

		THE							N/T.						/LAR			DAT I	6							OMESSAGES
FAIR 50'S		DISCOVERED THAT THE	W ON THE	DO NOT	EXISTING SLOPES	GUARDRAIL	- 4, 1, 0 on	ETEL N STANES MATCH BOTALT MITTHENTS	LOTIO (MT)	DIRECTED THE CONTRACTOR TO REMOVE 9 SINGLE TREES	IRING LIMITS		OVERALL		VERY SERIOUS HAZARD TO VEHICULAR		7773	27.7	BE PAID WITH EXISTING	BID ITEMS (MANPOWER AND EQUIPMENT RENTAL TIME)						
			ES ARE NOT AS SHOWN ON THE	21+35 LEFT	GNS, EXIST	ARE STEEPER AND INFRINGE ON DETAILED GUARDRAIL PLACEMENT.		CONTRACTOR TO REMOVE & STUMPS AND TO	שעונע	REMOVE 9	OUTSIDE OF THE CLE	O ACTUAL B.	SIGHT DISTANCE, AND OVERALL	.s.	STOUS HAZA		0 744 07 0		L BE PAID N	ULPMENT RI	7-17-02					
		WHILE PERFORMING INSLOPE WORK,	PES ARE NC	1 20+00 TO	DEPICT ACTUAL FIELD CONDITIONS,	VFRINGE OF	700 0100			RACTOR TO	OUTSIDE	DYAL DUE TO		1 ° 1	_				AND SHAPING BACKSLOPES WILL	YER AND EG	TERMAN					
//1//2002 TUESDAY	02	RFORMING	BACK SLO	X-SECTIONS AT STA	CTUAL FIEL	PER AND II IT.			י בערבי	THE CONT	THESES TREES WERE	BUT REQUIRED REMO	MATCH POINTS AND .	POOR CONDITION OF	THE 9 TREES POSED A		TIZIN TEXTORISE STATES	יאבר אבישט	ING BACKS	S (MANFON	BY: BILL BT					
7/17/2005	ITEM 211.20	WHILE PE	EXISTINE	X-SECTIC	DEPICT A	ARE STEEP PLACEMEN	A TO COTE OF	CIT DACK	THE R O W	DIRECTED	THESES 1	BUT REQU	MATCH PC	POOR CON	THE 9 TRE	ואאון אני	0.000	SI CMIT OF	AND SHAL	BID IIEM	ENTERED					

┰
တ

S		0	> 4	INAGE							
SUNNY 70'S	ITE TODAY IED	IW NO. 3, 1	MRS SMITH. MRS SMITH BROUGHT TO OUR ATTENTION THAT THE WATER RUNOFF FROM THE ROAD COLLECTS NEAR HER HOUSE AND ASKED THE MDOT TAKE REMOVE A	IN HER LAWN TO ALLOW FOR BETTER DRAINAGE SPOT WAS LOCATED WITHIN THE ROW 13	COMPACTED	. 1 1 1	TEST				
	ARRIVED AT THE SITE ALL PIPE IS CERTIFIED	REF TO DREW NO.	THE ROAD	OW FOR B	IE PROJECT		TODAY TO	-10-02			
	\\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\	S OF APE, K	TH BROUG JOFF FROM ASKED TH	WN TO ALL	SED ON TH	TO 15+50	V РРОЈЕСТ	TERMAN 9-			
FRIDAY	CONTRACTOR OPTION III, A	USED 2 HRS OF APE,	MATER RUHOUSE AND	IN HER LAWN TO ALLOW FOR BETTER SPOT WAS LOCATED WITHIN THE ROW 83	22 DRUMS USED ON THE PROJECT 10 D TO PI ACF ASCGRAVEL TN WELL	N ST 12+00	WEISNER ON PROJECT ONS	BIT			
9/10/2002 FRIDAY	ITEM 603.159 CONTRACTOR WITH THE OPTION III, ASHTO M-294 STAMP	ITEM 631.12 USED 2 HRS OF APE, REF TO DREW NO. 3, CREATE A BETTER SWAIF THROUGH THE PROPERTY OF	MITT		COUNTED RE DRUMS USED ON THE PROJECT ITEM 304 10 CONTINIED TO PLACE ASC60 A VELL CONTINIED TO PLACE ASC60 A VELL	LIFTS FROM ST 12+00 TO 15+50	NOTE: D. WEI.	ENTERED BY: BILL			

603.09 CB STA 33+28 RT INSTALLED B' PRECAST CB WITH 2' SUMP LORGE CONCRETE STRUCTURE IN ORDER TO INSTALL CB SUMP. SEE OPPOSITE PAGE FOR PAY DEPTH 4 QIV'S BACKFILLED WITH STONE FOR CB REDDING. QUISIDE GB = 4' DIAMETER CUTSIDE GB = 4' DIAMETER CUTSIDE GB = 4' DIAMETER CUTSIDE GB = 4' DIAMETER CONTRIDE WITH HOE RAM TO REMOYE CONCRETE BACKFILLED WITH EXCANATED MATERIAL. AND COMPACTED EACH LIFT. ALL WORK DONE ACCRODING TO PLANS 4 SPEC. AND COMPACTED EACH LIFT. ALL WORK DONE ACCRODING TO PLANS 4 SPEC. ITEM 203 D' STRUCTURAL ROCK EXCANATION BOTTOM OF SUMP CONCRETE STRUCTURE TO INSTALL CB SUMP BOTTOM OF SUMP CONCRETE STRUCTURE TBM # 5 BS HI F FS BOTTOM OF SUMP CONCRETE STRUCTURE AVERAGE ELEV OF TOP OF BURIED CONCRETE = 95.45' BOTTOM OF UNDERCUT ELEV = 89.5' DEPTH OF CONCRETE REMOYED WIDTH OF CONCRETE REMOYED WIDTH OF CONCRETE REMOYED WIDTH OF CONCRETE REMOYED WILDTH OF CONCRETE REMOYED WILDTH OF CONCRETE REMOYED WILDTH OF CONCRETE REMOYED WILDTH OF CONCRETE REMOYED ENTERED BY: BILL BITTERMAN 66-08-02 CHECKED BY: BILL BITTERMAN 66-08-02 CHECKED BY: BILL BITTERMAN 66-08-02 CHECKED BY: BILL BITTERMAN 66-08-02	6/8/2001	6/8/2001 TUESDAY SUNNY 70\S	(E)
TH 2' SUMP TH 2' SUMP TO A PORTICIO TO REA PAY DEPT TO PLANS & SP TO PLA	603.09	CB STA 33+28 RT	
CONCRETE = 9			
TIN ORDER TO. FOR PAY DEPT NE FOR CB BEP NE FOR CB BEP NO VED A NO		FOR EXISTING 24" CIP. REMOVED A PORTION	7F A
FOR PAY DEPTONE FOR CB BEE L AND USED A MATERIAL, OPLANS & SP TION TE STRUCTURE ELEV. 95.7 \		LARGE CONCRETE STRUCTURE IN ORDER TO IN	
NE FOR CB BEE L AND USED A MATERIAL, ANTERIAL, OPLANS & SP TION TE STRUCTURE ELEV. 96 \rightarrow 95.7 \rightar		CB SUMP. SEE OPPOSITE PAGE FOR PAY DEPTH	थर
1 AND USED A MATERIAL, TO PLANS & SP TONCRETE STRUCTURE ELEV. 95.7 \ 95.		QTY'S BACKFILLED WITH STONE FOR CB BEDD	NG.
1. AND USED A MATERIAL, MATERIAL, TO PLANS & SP TO PLANS &		OUTSIDE &B = 4' DIAMETER	
10VE CONCRET MATERIAL TO PLANS & SP TO PLANS & S		EXCAVATED 18" OUTSIDE WALL AND USED A 2	35
######################################		B'HOE WITH HOE RAM TO REMOVE CONCRETE	
TION TE STRUCTURE = 90.5' FROM FLEV. 96 \(95.7 \\ 95.7 \\ 95.1 \\ 95.7 \\		BACKFILLED WITH EXCAVATED MATERIAL,	
TION TE STRUCTURE = 90.5' FROM 1ED CONCRETE ELEV. 95.7 \		AND COMPACTED EACH LIFT.	
TION TE STRUCTURE = 90.5' FROM, IED CONCRETE ELEV. 95.7 \ 95		8	
### STRUCTURE			
= 90.5' FROM! = 90.5' FROM! ELEV. 96 \\ 95.7 \	ITEM 203.	07 STRUCTURAL ROCK EXCAVATION	
20.5' FROM. IED CONCRETE ELEV. 96 \(95.7 \\ 95.1 \\ 95.1 \\ 95.1 \\ 95.7 \\			
1ED CONCRETE ELEV. 96 \ 95.7 \ 95.1 \ 95.1 \ 95.4 \ 95.4 \ 95.4 \ 69.5 \ 7			
1ED CONCRETE ELEV. 96 \ 95.7 \ 95.7 \ 95.1 \ 95.4 \ 95.4 \ 60 \ \text{CONCRETE} = 9. \ \text{6} \(\)		90.5' FROM	4NS <
1ED CONCRETE ELEV. 96 \\ 95.7 \\ 95.7 \\ 95.1 \\ 95.1 \\ 95.4			
96 \\ 95.7 \\ 95.7 \\ 95.7 \\ 95.1 \\ 95.1 \\ 95.4 \\ 95.4 \\ 60 \		AVERAGE ELEV OF TOP OF BURIED CONCRETE	
96 \\ 95.7 \\ 95.7 \\ 95.7 \\ 95.1 \\ 95.4 \\ 89.5' \\ 6 \\ 6 \\ 6 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7		BS HI FS	
96 \ 95.7 \ 95.7 \ 95.1 \ 95.4 \ 60 \ 95.4 \ 89.5 \ \(101.5	3.5 105 ~	
95.7 \ 95.1 \ 95.1 \ 95.1 \ 95.4 \ 89.5' \ 6 \ 7 \ 7 \ 7 \ = 2.4;		> %	OF CONC
95.1 \$\sigma 95.1 \$\sigma 95.4 \$\sigma 95.4 \$\cdot 95.4 \$\sigma 95.4 \$		95.7 ~	OF CONC
95 V CONCRETE = 9, 89.5' 5 = 95.45-89.5' V		95.1~	OF CONC
CONCRETE = 95.45' 89.5' 595.45-89.5 = 5.95' CF / 27 = 2.42 CV \		95 V	OF CONC
69.5' 89.5' -95.45-89.5 = 5.95' 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			
89.5' =95.45-89.5 = 5.95' 0 0 0 0 0 0 0 0 0 0 0 0 0			
0 =95.45-89.5 = 5.95'		BOTTOM OF UNDERCUT ELEV = 89.5'	
0 -95.45-89.5 = 5.95'			***************************************
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		u	92,
G 127 = 2.42 CV		WIDTH OF CONCRETE REMOVED	
GF / 27 = 2.42 CV		= 4' + 2(1.5') = 7' \	
GF / 27 = 2.42 CY			
GF / 27 = 2.42 CY	ITEM 203.	DT STRUCT ROCK EXCAVATION	
ENTERED BY: BILL BITTERMAN \$6-08-02 CHECKED BY: ABC 1-2-03	VOLUME	3.14 X (7/2)2 X 5,95 = 65.42 CF / 27 =	
CHECKED BY: ABC 1-2-03 V	CATTEREN	V. 57: 1 211150448 04 08 02	
	CHECKED	7: BILL BAI 1 EKMAN WO-WO-WE Y: ABC 1-2-03 V	

	700	5	407				>	>		>	0											•		4		
	CE 4 DENATA	١	THE CONTRACT	RROW			1	T = 87.5'	!	ENT	I FKEE/=90 -0					1.63 CV V	_	>		11-08-02						
	V CT COTES TO !!	THE CONTRACTOR OF EU TO USE	L BF PATO AT	PRICE OF 203.35 GRANULAR BORROW	VOLUME OF GRANULAR BORROW	anns vivos so morrada so visis	יר ביוער שיי	ELEV OF BOTTOM OF UNDERCUT		NOERCUT FOR PAYMENT	92.00 -4 (CUNC) - 12 (FIRS) FI	20T	>			25) / 27 = 4.	000	1.15 = 5.32 CY		BATTERMAN	ABC 1-2-03					
	ILAR BORROW	CONTRACTOR OF	THE BEDOING WILL BE PAID	OF 203.35 6	IE OF GRANI	TE DOTTO	100 J	JF BOTTOM		IRE UNDERC	-4 (CONC) -	DEPTH OF UNDER CUT	.87.5 = 3.25'	15	ĩ	(3.14 X (7/2)2 X 3.	7	= 4.03 X		ED BY : BILL	BY:	******				
203.	GRANULAR	ישבי כי	THE B	PRICE	NOTON	בו בו י	ברבג	ELEV (1	MEASURE	92.00	DEPTH	90.75-87.5	 3411101		(3.14		SWELL		ENTERED	CHECK					-
ITEM																										

TITEM 202. 20 CONTRACTOR IS MILLING EXISTING PAVEMENT AND STOCKPILING MAT'L AT APROVED STAGING AREA TO BE USED LATER AS ASG GRAVEL. CONTRACTOR IS EXCAVATING MAT'L FROM STA 12-00. QTY TO BE MEASURED PLAN QTY. REF TO BK 3 PG 2 FOR SUBGRADE CHECK AND CONTRACTOR IS BACKFILLING EXC AREAS WITH MAT'L FROM THE ALLISON PIT AND PLACING AND CONTRACTOR IS BACKFILLING EXC AREAS WITH MAT'L FROM THE ALLISON PIT AND PLACING AND COMPACTING IN LIFTS FROM STA 15 + 00 TO STA 21-00. MILLINGS WAS USED TO PLACE THE FINAL LIFT QTY IS TO BE MEASURE PLAN QTY REF TO BK 3 PG 3 FCR FINEGRADE CHECKS ITEM 203. 21 ROCK WAS REMOVED FROM STA 16+50 FILED MESSURED VOLUME = 4,5'X 3.3' X 4' = 59.4 CF / Z7 = 2.2 CY ITEM 202. 20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202. 2 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202. 2 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202. 2 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202. 2 DEDUCT ROCK QTY OF 1.5-02	202.2				OV VAINIOS	5
CONTRACTOR IS MILL AND STOCKPILING MA AREA TO BE USED LA CONTRACTOR IS EXCA STA 15+00 TO 21+00. QTY. REF TO BK 3 PG CONTRACTOR IS BACK MAT'L FROM THE ALL COMPACTING IN LIFT STA 21+00. MILLINGS FINAL LIFT. QTY IS TO STA 21+00. MILLINGS FINAL LIFT. QTY IS TO CONTRACTOR IS BACK MAT'L FROM THE ALL STA 21+00. MILLINGS FINAL LIFT. QTY IS TO ROCK WAS REMOVED FIELD MEASURED VOLUME = 4.5'X 3.3'. DEDUCT ROCK QTY OF		0				
AND STOCKPILING MA AREA TO BE USED LA CONTRACTOR IS EXCA STA 15-00 TO 21-00. QTY. REF TO BK 3 PG CONTRACTOR IS BACK WASTE AREA. COMPACTING IN LIFT STA 21-00. MILLINGS FINAL LIFT.QTY IS TO STA 21-00. MILLINGS FINAL LIFT.QTY IS TO COMPACTING IN LIFT STA 21-00. MILLINGS FINAL LIFT.QTY IS TO COMPACTING IN LIFT STA 21-00. MILLINGS FINAL LIFT.QTY IS TO DEDUCT ROCK QTY OF DEDUCT ROCK QTY OF DEDUCT ROCK QTY OF DEDUCT ROCK QTY OF SED BY: BILL BITTERMAN 6		CONTRACT	OR IS MILL	ING EXIST	ING PAVEME	'N
AREA TO BE USED LA CONTRACTOR IS EXCA STA 15+00 TO 21+00. QTY. REF TO BK 3 PG CONTRACTOR IS TAKI WASTE AREA. CONTRACTOR IS BACK MAT'L FROM THE ALL COMPACTING IN LIFT STA 21+00. MILLINGS FINAL LIFT. QTY IS T REF TO BK 3 PG 3 FO FIELD MEASURED VOLUME = 4.5'X 3.3' DEDUCT ROCK QTY OF SED BY: BILL BITTERMAN 6		AND STOC	'W GNITIAX	IT'L AT APP	ROVED STAE	FINE
CONTRACTOR IS EXCE STA 15+00 TO 21+00 QTY. REF TO BK 3 PG CONTRACTOR IS TAKE WASTE AREA. 304. 104 CONTRACTOR IS BACK MAT'L FROM THE ALL COMPACTING IN LIFT STA 21+00. MILLINGS FINAL LIFT. QTY IS TO REF TO BK 3 PG 3 FO FIELD MEASURED VOLUME = 4.5'X 3.3'. DEDUCT ROCK QTY OF DEDUCT ROCK QTY OF		AREA TO B	E USED LA	TER AS ASE	GRAVEL.	
STA 15+0C TO 21+0O QTY. REF TO BK 3 PE CONTRACTOR IS TAKE WASTE AREA. 304.104 MAT'L FROM THE ALL COMPACTINE IN LIFT STA 21+0C. MILLINGS FINAL LIFT QTY IS TO REF TO BK 3 PE 3 FO FIELD MEASURED VOLUME = 4.5'X 3.3'. DEDUCT ROCK QTY OF DEDUCT ROCK QTY OF SED BY: BILL BITTERMAN 6		CONTRACT	OS IS EXC	IVATING M.	AT'L FROM	
QTY. REF TO BK 3 PE CONTRACTOR IS TAKI WASTE AREA. 304 104 CONTRACTOR IS BACK MAT'L FROM THE ALL COMPACTING IN LIFT STA 21+0C. MILLINGS FINAL LIFT. QTY IS TO REF TO BK 3 PG 3 FO FIELD MEASURED VOLUME = 4.5'X 3.3'. 202.20 DEDUCT ROCK QTY OF DEDUCT ROCK QTY OF DEDUCT ROCK QTY OF SED BY: BILL BITTERMAN 6		STA 15+00	TO 21+00.	QTY TO 8	- MEASURED	PLAN
CONTRACTOR IS TAKE WASTE AREA. 304 104 CONTRACTOR IS BACK MAT'L FROM THE ALL COMPACTING IN LIFT STA 21+0C. MILLINGS FINAL LIFT. QTY IS TO REF TO BK 3 PG 3 FO FIELD MEASURED VOLUME = 4.5'X 3.3'. 202.20 DEDUCT ROCK QTY OF			TO BK 3 PG		GRADE CHEC	Z AND
WASTE AREA. 304. 104 CONTRACTOR IS BACKFILLING EXC AREAS W MAT'L FROM THE ALLISON PIT AND PLACIN COMPACTING IN LIFTS FROM STA 15 + 00: STA 21+00. MILLINGS WAS USED TO PLACE FINAL LIFT. QTY IS TO BE MEASURE PLAN OR BEFT TO BK 3 PG 3 FOR FINEGRADE CHECKS 203. 21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 202. 20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM RED BY: BILL BITTERMAN 6-15-02		CONTRACT	OR IS TAK	ING MAT'L	TO THE SMI	TH'S
304. 104 CONTRACTOR IS BACKFILLING EXC AREAS W MAT'L FROM THE ALLISON PIT AND PLACIN COMPACTING IN LIFTS FROM STA 15 + 00 : STA 21+02. MILLINGS WAS USED TO PLACE FINAL LIFT QIY IS TO BE MEASURE PLAN OR REF TO BK 3 PG 3 FCR FINEGRADE CHECKS ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59. 4 CF / 27 = DEDUCT ROCK QTY OF 1.46 CY FROM ITEM AREA BY : BILL BITTERMAN 6-15-02		WASTE AR	EA.			
203. 20 SED BY: BILL BITTERMAN 6-15-02						
CONTRACTOR IS BACKFILLING EXC AREAS W MAT'L FROM THE ALLISON PIT AND PLACIN COMPACTING IN LIFTS FROM STA 15 + 00 : STA 21+02. MILLING\$ WAS USED TO PLACE FINAL LIFT.QTY IS TO BE MEASURE PLAN O REF TO BK 3 PG 3 FCR FINEGRADE CHECKS 203. 21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = DEDUCT ROCK QTY OF 1.46 CY FROM ITEM RED BY: BILL BITTERMAN 6-15-02	304	8				
MAT'L FROM THE ALLISON PIT AND PLACING COMPACTING IN LIFTS FROM 574 15 + 00 : STA 21+00. MILLING\$ WAS USED TO PLACE FINAL LIFT.QTV IS TO BE MEASURE PLAN G REF TO BK 3 PG 3 FCR FINEGRADE CHECKS 203.21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 202.20 DEDUCT ROCK QTV OF 1.46 CV FROM ITEM A DEDUCT ROCK QTV OF 1.46 CV FROM ITEM A DEDUCT ROCK QTV OF 1.5-02		CONTRACT	OR IS BACK	FILLING EX	C AREAS W	HLI
COMPACTING IN LIFTS FROM ST4 15 + 00: STA 21+00. MILLING\$ WAS USED TO PLACE FINAL LIFT.QTV IS TO BE MEASURE PLAN G REF TO BK 3 PG 3 FCR FINEGRADE CHECKS 203.21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 202.20 DEDUCT ROCK QTV OF 1.46 CV FROM ITEM A SED BY: BILL BITTERMAN 6-15-02		MAT'L FRO	M THE ALL	ISON PIT	ND PLACING	AND
STA 21+00. MILLINGS WAS USED TO PLACE THE FINAL LIFT. QTY IS TO BE MEASURE PLAN QTY REF TO BK 3 PG 3 FOR FINEGRADE CHECKS 203.21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5 °X 3.3 °X 4' = 59.4 °CF / 27 = 2.2 202.20 DEDUCT ROCK QTY OF 1.46 °CY FROM ITEM 202.		COMPACTI	NG TN I TET	S FROM ST	4 15 + 00 TO	2
FINAL LIFT. QTY IS TO BE MEASIRE PLAN QTY REF TO BK 3 PG 3 FOR FINEGRADE CHECKS 203.21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 2.2 202.20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202.		574 21+00	MTITNE	WAS 115E	TO 01 4CE	THE
203.21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 2.2 202.20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202.		CTA 141 1 TE	.1 P	2000000	0 1 4 1 O	1
203.21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEA SURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 2.2 202.20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202.		דואשר רדג		O BE MEAS	שבו גרשוא פ	4
203.21 ROCK WAS REMOVED FROM STA 16+50 FIELD MEA SURED VOLUME = 4.5 ° X 3.3 ° X 4 ° = 59.4 ° C F / 27 = 2.2 202.20 DEDUCT ROCK QTY OF 1.46 ° CY FROM ITEM 202. SED 8 Y : BILL BITTERMAN 6-15-02	1	REF TO BK	3 PG	R FINEGRA	SE CHECKS	
AS REMOVED FROM STA 16+50 EASURED = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 2.2 ROCK QTY OF 1.46 CY FROM ITEM 202.						
ROCK WAS REMOVED FROM STA 16+50 FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 2.2 202.20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202. RED BY: BILL BITTERMAN 6-15-02	203.	1				
FIELD MEASURED VOLUME = 4.5'X 3.3' X 4' = 59.4 CF / 27 = 2.2 202.20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202. SED BY: BILL BITTERMAN 6-15-02		ROCK WAS	REMOVED .		16+50	
202.20 202.20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202. RED BY: BILL BITTERMAN 6-15-02		FIELD MEA	SURED			
202. 20 DEDUCT ROCK QTY OF 1.46 CY FROM ITEM 202. RED BY: BILL BITTERMAN 6-15-02		VOLUME =	6.	lt.	CF / 27 =	20%
202. 20 DEDUCT ROCK QTY OF RED BY: BILL BITTERMAN 6				l		
DEDUCT ROCK QTY OF RED BY: BILL BITTERMAN 6	202	0				
BITTERMAN 6		DEDITIET RO	CK OTY OF		OM TTEM PO	72.2
BITTERMAN 6		2000	io com voc			
BITTERMAN 6						
BITTERMAN 6						
BITTERMAN 6						
ENTERED BY: BILL BITTERMAN 6-15-02						
BITTERMAIN 6	1					
	TERED BY		TTERMAN O	-15-02		
	 					

VACINOM OTIZE		CONTRACTIC	AND DOWN.	SEDIMENTA	SIDE OF BR	NIEENS WOD	CONTRACTIC	WASTE ARE	ITEM 509.12	CONTRACTO DIDE ADOL	THE BOLTS	CHECK ON B				ITEM 203.21	ROCK WAS	FIELD MEAS	VOLUME = 5		ITEM 202.20	DEDUCT ROL		TTEM 204 DK1	DIRECTED CONTRACTO	EXISTING UTILITY, TH	PLAN.	FIELD MEASURE FROM	DETH BELOW FLOWLIN	WIDTH = 2.5'	LENGTH = 45'	Q17 = (6.3-1 FA) LAM		ENTERED BY : BILL BIT	
SUNNY 70 S	0070	THO A DENSITIES ARE EXCUDED FROM	L PLACED ON THE	W.V.	SELF AGREED THAT		WIN /2000 = 3.000 TONS		SLIP #3458 QTY OF 1601.25 TONS FOR ITEM 403.208		ISTALL MEMBRANE	OT BLASTED" USING A	ACK STEEL PELLETS.	BLASTED COMPLETED AND FREE OF LATANCE.	BY THE CONTRACTOR USING	. MOISURE MASTER	HE READINGS	STA 1+009 1.5 M RT. AND STA		STON RAYBOND 713		IOAN EASYPAVE	ALED WITH MASTIC	IS AKE ON THE MOO!									New York Control of the Control of t		
6/10/2002 MONDAY	ITEM 403.208	BOTH ARE METHOD A DENSITIES AR	1. 1	THE VARIABLE WIDTH SHOULDERS OF	MIKE SMITH, PAVING SUPT. AND MYSELF AGREED THAT		ML = (7,100' X 12' X 2) / 9 X 110#/5Y/IN /2000 = 3,000 TONS	1, GOLL DB F - 3,000 T = 301.25 TONS	REF COVER SLIP #3458 QTY OF 1601.	TTEM 508 43	AD ROSSI ON SITE TO INSTALL MEMBRANE	ON BRIDGE DECK. THE DECK WAS "SHOT BLASTED" USING A	BLASTRAC MACHINE USING SMALL BLACK STEEL PELLETS.	THE DECK WAS BLASTED COMPLETED	3 MOISTURE READING WERE TAKEN BY THE CONTRACTOR USING	A SOVEREIGN PORTABLE ELECTRONIC MOISURE MASTER	WITH RESULTS OF 3.2, 3.2 & 3.3., TI	T STA 1+005, CL.		MED	1	ROSSI PLACED 32.4 SM OF ROYSTON 10AN EASYPAVE	MEMBRANE AND ALL EDGES WERE SEALED WITH MASTIC	X 6	APPROVED FRODUCT LEST										

37110	MONDAY	SUNNY 70'S
ITEM 511.0	07 CONTRACTION INSTAULTING UPSTREAM	
	AND DOWNSTREAM COFFERDAMS, BUILDING	ILDINS
	SEDIMENTATION BASINS ON DOWNSTREAM	TREAM
	SIDE OF BRIDGE ON EXISTING LOGGING. THE	NG. THE
	CONTRACTOR WAS NOTIFIEDTHAT THE BASIN	IE BASIN
	NEEDS MORE BALES PER EROSION CON	VTROL PLAN.
	IS TAKING MAT'L	TO THE SMITH'S
	WASTE AREA.	
TTEM 500	70	
3	CONTRACTOR HAS FINISHED FRECTING	91
	PIPE ARCH THIS A.M. AND STARTED TIGHTENING	TIGHTENING
	THE BOLTS WITH COMPRESSOR. PERFO	PERFORMED TORQUE
	CHECK ON BOLTS	
200 11 11		
11 CM 203.4	ROCK WAS REMOVED FROM STA 16+50	
	SURED	
ANALYZANIA SPIRAL SPIRA	VOLUME = 5' X 3.3' X 4' = 66 CF / 27	= 2.44 CV
ITEM 202.20	0	
	DEDUCT ROCK QTY OF 2.44 CY FROM ITEM	TEM 202.2
ITEM 206.061	61	
DIRECTED	CONTRACTOR TO UNDERCUT UD TO AVOID	OID
EXISTING UTILITY,	VIILITY, THE UTILITY IS NOT LOCATED AS	ED AS PER
PLAN.		
FIELD MEA.	FIELD MEASURE FROM FLOW LINE	Advisor of the state of the sta
ретн вегом	W FLOWLINE =AVG P.5 FT	
WIDTH = 2	ريار الارارية	
QTY = (2.5-1	' PAY LIMIT) X 2.5' X 45' / 27 =	6.25 CV
ENTERED &	BY : BILL BITTERMAN 8-7-02	

TO DOWNSTREAM		BASIN.			
509.12					
SPO	SPOT CHECKED	KED TORQU	TORQUE ON BOLT		AFTER PIPE WAS
. NI	THE GR	OUND AND	IN THE GROUND AND RE-TORQUE	E AND FOUND	UND TO
1 38	VITHI	BE WITHIN SPECIFICATIONS.	ATIONS.		
652.86					
MTC	D ARE	OF FOR TH	$\boldsymbol{\mathcal{E}}$	ID WAS CLO	DSED
THI	THIS AM	O TRAFFIC	ALL DETG	ALL DETGUR SIGNS	WERE PUT
INT	O PLAG	E THIS MC	INTO PLACE THIS MORNING AS	PER PLAN.	
ITEM 652.812 AND 546.301	4ND 52	6.301			
7/2	E III B	TYPE III BARICADES .	IN PLACE A	IN PLACE AND TEMP CONC	DNC
BAR	BARRIERS	PUT IN PLA	PUT IN PLACE BEHIND TYPE III	TII 3dKL	
131	PER PLA	IN ON THE	AS PER PLAIN ON THE NORTH ANDOVER ROAD	DOVER ROA	q
ENT	ERING	AND EXTT	ING THE W	DRK AREA N	VEAR
THE	MULT	PLATE.	THE MULTIPLATE.		
_					
_					
ENTERED BY: B.	BILL BI	TERMAN 8-06-02	-06-02		

37109 MONDAY

ITEM 511.07

APPENDIX B

EXAMPLE MEMO'S AND FORMS

Maine Department of Transportation - Contracts Division Time Charge Report

Project No.	9999	
Town/City	augusta	Calculated By: B. Bitterman
Contractor:	Contractor	Checked By: J.Keamy

Contract Time Charges

Calendar Day Ba	sis		Completion Dat	e Basis
Time Charge Started	6/5/2004	Required C	ompletion Date	10/27/2004
Time Charge Suspended		Actual Com	pletion Date	11/16/2004
Time Charge Resumed		Days Beyor	nd Completion Date	18 days
Time Charge Terminated	6/20/2004	Days Added	d by WOs	12 days
Days Beyond	0	Days subjectiquidated I		6 days
Days added by W.O.s		Elquidatou	Damagoo	- o days
Days subjected to Liquidated Damages	0			
EWO # DAYS 3 1	EWO#	DAYS	EWO#	DAYS
5 3				
<u> </u>		•		

Remarks:

....... DO NOT WRITE BELOW THIS LINE TO BE COMPLETED BY AUGUSTA OFFICE

7) Time Extensions (g+h)				Days
g. D.O.T. Approval		Da	te:	Days
h. Other explain)		Da	te:	 Days
8) Underrun		7		Days
9) Overrun				Days
10) Liquidated Damages	\$	per day	=	\$
Use separate report for each	h type of tim	e charge		

Signed:



STATE OF MAINE DEVARTMENT OF TRANSPORTATION 16 STATE HOUSE STATION AUGUSTA, MAINE 04333-0016

DAVID A. COLE

Example No 1; Memo free of Encroachments

Project 009999.00 - Augusta

ENGINEERS STATEMENT OF RIGHT OF WAY ENCROACHMENT

The above mentioned project was inspected on Fehruary 9, 2005 and appears to be free of all Right of Way Encroachments.

3/1 Bett_

Bill Bitterman Resident Engineer

Example No 2; Memo with Encroachments

Project 009999.00 - Augusta

ENGINEERS STATEMENT OF RIGHT OF WAY ENCROACHMENT

The above mentioned project was inspected on February 9, 2005 and appears to be free of all Right of Way Encroachments with the following exceptions:

- 1. Sta. 18+576 LT. Easy Self Storage sign on post.
- 2. Sta 22:320 LT. Granite Mailbox post.

Bill Bitterman Resident Engineer

BA BIL



THE MAINE DEPARTMENT OF TRANSPORTATION IS AN AFFIRMATIVE ACTION , EQUAL OPPORTUNELY EMPLOYER

Maine Department of Transportation - Contracts Division Waste Area Permit

Project No:	· · · · · · · · · · · · · · · · · · ·	
Upon receipt of written permission from		
	(Property Owner)	
(Contractor)	is authorized to place waster material from this project at	
(comusion)	in accordance with Sections 104.3.2 & 203.06 & 211.08,	
(Description of Waste Area)		
State of Maine, Department of Transportation, Standa Revisions of December 2002.	ard Specifications Highways and Bridges,	
maintained between the near edge of the waste area at the entrance to the waste area in a wooded area exce	rea, a screen of trees (min. width of 30m (100 ft) shall be and the Right of Way or Construction Limit Line. If the width eeds 5m (16ft), this entrance shall be replanted with trees hall extend for a length of 30m (100ft) along the entrance roa	
All waste areas and entrances to the waste are other earthly material that will support growth of grass.	ea shall be uniformly graded to drain, loamed or covered with s, seeded and hay mulched.	ı
All trees which are damaged, uprooted or other have had waste material placed around them to the ex	erwise moved as a result of the waste material, and trees whick at they will die, shall be cut and removed.	ch
Grading, Loaming, Seeding and Hay Mulching items in the contract.	shall not be paid directly, but shall be incidental to other	
The contractor is responsible for relocating and Environmental Protection Regulations, Chapter 404 (S	d disposing of waste, in accordance with the Department of Storage and Disposal of Inert Fill).	
	Approval: Project Resident	
	Agreed:	
	Contractor's Bancasantativa	

*original copy to Contractor and additional copy for Resident's file.

MAINE DEPARTENT OF TRANSPORTATION DAILY REPORT OF EQUIPMENT RENTAL

TOWN	Augusta	REPORT No.	12
PROJECT NUMBER:	9999	AUTHORIZATION	Residents Directive
CONTRACTOR	M&H	DATE	Thursday, August 21, 2004

LABOR

ITEM NO.	CLASS	RATE	TIME	TOTAL
				0
	Hand Labor	\$35	6	210
	A Character and a second of the Committee of the Park Boy of Pillians South Hillians and a strong of a second of the Committee of the Committe			0
				0
				0
				0
	are en mente en	hin 1990 5 And White W.	e di Mariadiologia e e e e	0
S. procession and notice of the security of the second			TOTAL	210

EQUIPMENT RENTAL

ITEM NO.	TYPE	RATE	TIME	TOTAL
				0
631.12	APE	\$100	6	600
631.15	Earth Roller (Inc. Op)	\$75	2	150
631.172	Truck Large, (Inc. Op)	\$55	6	330
				0
				0
				0
12 h Turk 2010 2010 2010			TOTAL.	1080

MATERIAL

QUANTITY	DESCRIPTION	RATE	TOTAL
			0
			0
			0
			0
			0
			0
			0
		TOTAL	0

SUMMARY					
TOTAL LABOR	\$210.00				
TOTAL EQUIPMENT	\$1,080.00				
TOTAL MATERIAL	\$0.00				
TOTAL THIS REPORT	\$1,290.00				
PREVIOUS REPORT					
TOTAL DATE	\$2,580.00				

APPROVED:	APPROVED:	
RESIDENT		CONTRACTOR REPRESENTATIVE

DESCRIPTION OF WORK:

Worked performed as directed at Sta 5+40 to 5+70 RT at the entrance to Bittermans Gas-n-Go. The Entrance was re-graded to insure drainage from the parking lot to the new Catch Basin at Sta 5+28 RT.

RESIDENT:	PROJ. NO	
DATE: REVIEWED BY:	TOWN/BRIDGE:	
CLOSEOUT REVIE	W GUIDLELINES FOR OVERLAY PROJE	CTS
LABOR COMPLIANCE		
Verify that employees are paid at	wages not less than those contained in applicable wage decision	
Verify receipt of hourly breakdown	for fringe benefits from Contractor	
Review documented employee int	erviews by appropriate MDOT personnel - Notify supervisor if missing	
Reviewer check of certified payrol	ls for accuracy	
Has Wage Rate Compliance O	fficer been notified of any problems?	
PROJECT DIARY	•	
	crew, equipment, weather, contractor and state personnel	
Time charge report		
MTCD and maint of Erosion Contr	ol items, weekly notes:	
Description of work done by item		
Other entries relating to contacts,	claims and other potential problems	
FINAL QUANTITY BOOK		
Book set up same as progress es		
	ocumented, and referenced to Proj Diary	
	Order & references proper documentation (check engineers est)	
•	naximum), receipted bills of mat'l + 15%, specialty 15%	
	eferenced to construction book entries	
- •	cipality, DOT Maintenance or utility company	
QC/QA incentive/disincentive calc		
GENERAL DOCUMENTATION REG		
	ts, sta to sta, limits, signed, checked	
	e, inspec & accept documented in Pro diary, Final Quantity Book / Reports of Extra Work, receipted bills for specialty work and mat'l	
Participating	7 Reports of Extra Work, receipted bills for specialty work and matt	
, .	nd/or Supervisor if required	
	ects with Federal Oversight	
Copy to Finals Folder		
PAVEMENT ITEMS		
·····	igned, dated and entered in Final Quantity Book	· · · · · · · · · · · · · · · · · · ·
Tack coat delivery invoices, refere		*-
Daily reports of Extra Work		
Flaggers certified		
QC/QA test file		
Asphalt esclator for recycling if 10	8 Special Provision	
<u>DRAINAGE</u>		
Drainage diary & installaion notes	and layout notes, sta to sta & offsets documented	
Ledge removal quantity measured	1	
MISCELLANEOUS ITEMS		
Have appropriate DBE letters a	and reports been completed	
Waste area Authorizations		
Contractor E-vals		
ROW Encroachment letter		
QC/QA for any fill and base mater		
Hourly equipment rental items ent	ered on DREWS	
Third party billing		
Notes:		
Notes:		

	PROJ. NO.	
RESIDE		
CLOS	EQUIT REVIEW GUIDELINES FOR FULL CONSTRUCTION PROJ	ECTS
LABOR	COMPLIANCE	
	Verify that employees are paid at wages not less than those contained in applicable wage decision	
	Verify receipt of hourly breakdown for fringe benefits from Contractor	
	Review documented employee interviews by appropriate MDOT - Notify supervisor if missing	
	Reviewer check of certified payrolls for accuracy	·
	Has Wage Rate Compliance Officer been notified of any problems?	L
PROJEC	<u>T DIARY</u>	
	Daily entries showing working hrs, crew, equipment, weather, contractor and state personnel	
	Time charge report	
	MTCD and maint of Erosion Control items, weekly notes:	
	Description of work done by item Other entries relating to contacts, claims and other potential problems	
	Other entries relating to contacts, claims and other potential problems	
FINAL Q	<u>UANTITY BOOK</u>	,
	Book set up same as progress estimates	
	Extra work entered, agreed unit prices and ref to Proj Diary or written documentation	<u> </u>
	Plan quantity per RWO references documentation (check engineers est) Force Account Blue Book rates, receipted bill mat'l + 15%	
	Quantities checked, signed, and references construction books	
	Billings quantites: DOT to City, maintenance or utilities	
	QC/QA incentive/disincentive calculated	
	Copy to Finals Folder for scanning	
CENED	N. DOCUMENTATION REQUIREMENTS	
GENERA	AL DOCUMENTATION REQUIREMENTS Unit price Item, field measurements, sta to sta, limits, signed, checked	F
	LS Item ref to record of work done, inspec & accept documented in Pro diary, Final Quantity Book	
	Force Account Items, doc by Daily Reports of Extra Work, receipted bills for specialty work and mat'l	
	Contract Modifications (Change Orders - Resident Work Orders) - signed, Part & non Part	
	Approval by Design and/or Supervisor if required	
	Copy to FHWA on projects with Federal Oversight	
EXCAVA	ATION AND BORROW	
	Source and Final placement noted in Project Diary (Pit author and waste areas)	
	Checks on-subgrade, finegrade, ditch and backslopes	
	Field changes documented by measurements	
AGGRE	GATE BASE AND SUBBASE	
AGGIL	Finegrade checks, field measurements of drives and other changes	
	QC/QA gradation and compaction	
<u>DRAINA</u>		
	Drainage diary notes and layout notes, sta to sta & offsets	
	Ledge removal measured	
PAVEME	NT ITEMS	
	Delivery, Cover and Tack slips totals signed, dated and entered in FQB (certificate of analysis)	
	QC/QA test file	
MISCEL	LANEOUS	
	Flaggers certified	
	Waste area Authorizations	
	Contractor E-vals	
	ROW Encroachment letter	
	Hourly equipment rental items entered on DREWS & signed	
	Third party billing	<u></u>
	REVIEWERS' NAME: DATE:	

NESIDEI		
DATE:	TOWN	
O.T.		
	LOSEOUT REVIEW GUIDELINES FOR BRIDGE PROJECTS	
LABOR (<u>COMPLIANCE</u>	
	Verify that employees are paid at wages not less than those contained in applicable wage decision	
	Verify receipt of hourly breakdown for fringe benefits from Contractor	
	Review documented employee interviews by appropriate MDOT - Notify supervisor if missing	
	Reviewer check of certified payrolls for accuracy	
	Has Wage Rate Compliance Officer been notified of any problems?	
<u>PROJEC</u>	<u>PT DIARY</u>	
	Daily entries showing working hrs, crew, equipment, weather, contractor and state personnel	
	Time charge report and ROW encroachment letter	
	MTCD and maint of Erosion Control items, weekly notes:	
	Description of work done by item	
	Other entries relating to contacts, claims and other potential problems	
FINAL Q	UANTITY BOOK	
	Book set up same as progress estimates	
	Extra work entered, agreed unit prices and ref to Proj Diary or written documentation	
	Plan quantity per RWO references documentation (check with Engineers est.)	
	Force Account Blue Book rates, receipted bill mat'l + 15%, specialty 15%	
	Quantities checked, signed, and references construction books	
	Billings quantites: DOT to City, maintenance or utilities	
CENEDA	QC/QA incentive/disincentive calculated	L
GENERA	AL DOCUMENTATION REQUIREMENTS	
	Item by unit, field measurements, sta to sta, limits, signed, checked	
	item by LS, ref to record of work done, inspection and acceptance, in Proj diary, FQB	
	Item force account, documented by DREWS, receipted bills for specialty work and mat'l CO's, EWO's and RWO:	
	Approval by Design and/or Supervisor if required	
	Copy to Finals Folder for scanning Copy to FHWA on projects with Folderal Oversight	
BRIDGE	Copy to FHWA on projects with Federal Oversight	
<u>DNIDGE</u>		
	Pile reports, layouts, record piles Forms and re-steel checks, summary sheets, elev requirements	
	Structural steel, inspection and acceptance, torque checks, calibrations, rotational capacity	
	shear commectors, bent test and weld inspection	
	Painting, coat thickness:	
		L
BRIDGE .	APPROACH WORK	
	Roadway excavation, waste site, grade checks	
	Base mat'l, source, QC/QA, finegrading	
<u>DRAINA (</u>		
	Drainage diary and installation notes and layout notes, sta to sta & offsets	
	Ledge removal measured	
<u>PAVEME</u>	<u>ENT ITEMS</u>	
	Delivery, Cover and Tack slips totals signed, dated and entered in FBQ (certificate of analysis)	
	Flaggers certified	
	QC/QA test file	
MISC:		
	Contractor E-vals, Waste Area authorization	
	Third party billing	
	REVIEWERS' NAME: DATE:	

NOTES

RESIDENT:	
DATE:	
REVIEWED BY:	



rnos. No	•			
	-			
TOWN/BR	IDGE			
TOWNDE	IDUL.		 	

REVIEW GUIDELINES FOR ONSITE REVIEWS

Wage Rate Posters & Presentation of Wage-Hour Outline & EEO Outline Copy of applicable wage decision available Are payrolls and certifications received within the 7 days allowed If not received within allowable time, what action taken to correct Verify that employees are paid correct wages Verify receipt of hourly breakdown for fringe benefits from Contractor Reviewer spot check of certified payrolls for accuracy Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? FIELD BOOKS Signatures, weather, working day number, contract hours, personnel, Eqpmnt, State Personnel, survey notes identified, crew names & duties CLEARING Measuring referenced to source Inspection of limits after work done. If paid plan qty, verify work done according to plan EXCAVATION Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10%					
Copy of applicable wage decision available Are payrolls and certifications received within the 7 days allowed If not received within allowable time, what action taken to correct Verify that employees are paid correct wages Verify receipt of hourly breakdown for fringe benefits from Contractor Reviewer spot check of certified payrolls for accuracy Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? Dates	LABOR COMPLIANCE			Dates	
Are payrolis and certifications received within the 7 days allowed If not received within allowable time, what action taken to correct Verify that employees are paid correct wages Verify receipt of hourly breakdown for fringe benefits from Contractor Reviewer spot check of certified payrolis for accuracy Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? FIELD BOOKS Signatures, weather, working day number, contract hours, personnel, Eqpmnt, State Personnel, survey notes identified, crew names & duties CLEARING Measuring referenced to source Inspection of limits after work done. If paid plan qty, verify work done according to plan EXCAVATION Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500° check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Length of pipe measured or documented. Unliquate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth		Wage-Hour Outline & EEO Outline			
If not received within allowable time, what action taken to correct Verify that employees are paid correct wages Verify receipt of hourly breakdown for fringe benefits from Contractor Reviewer spot check of certified payrolls for accuracy Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? FIELD BOOKS Signatures, weather, working day number, contract hours, personnel, Eqpmnt, State Personnel, survey notes identified, crew names & duties CLEARING Measuring referenced to source Inspection of limits after work done. If paid plan qty, verify work done according to plan EXCAVATION Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements ip swell 15%, fruck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w0 rock ex minor struct pay 16 times common ex/ rock w0 rock major struct pay 6 times struct earth	<u> </u>				
Verify that employees are paid correct wages Verify receipt of hourly breakdown for fringe benefits from Contractor Reviewer spot check of certified payrolls for accuracy Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? Dates	Are payrolls and certifications received w	thin the 7 days allowed			
Verify receipt of hourly breakdown for fringe benefits from Contractor Reviewer spot check of certified payrolis for accuracy Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? Dates	If not received within allowable time, what	action taken to correct			
Verify receipt of hourly breakdown for fringe benefits from Contractor Reviewer spot check of certified payrolis for accuracy Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? Dates	Verify that employees are paid correct wa	ges			
Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? Dates	Verify receipt of hourly breakdown for frin	ge benefits from Contractor			
Document & review employee interviews by appropriate MDOT personnel Has Wage Rate Compliance Officer been notified of any problems? Dates	Reviewer spot check of certified payrolls	or accuracy			
Signatures, weather, working day number, contract hours, personnel, Eqpmnt, State Personnel, survey notes identified, crew names & duties	Document & review employee interviews	by appropriate MDOT personnel			
Signatures, weather, working day number, contract hours, personnel, Eqpmnt, State Personnel, survey notes identified, crew names & duties CLEARING	Has Wage Rate Compliance Officer b	een notified of any problems?			
Signatures, weather, working day number, contract hours, personnel, Eqpmnt, State Personnel, survey notes identified, crew names & duties CLEARING					
Eqpmnt, State Personnel, survey notes identified, crew names & duties CLEARING			Dates		
Measuring referenced to source Inspection of limits after work done. If paid plan qty, verify work done according to plan EXCAVATION Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w0 rock ex minor struct pay 16 times common ext rock w0 rock major struct pay 6 times struct earth Dates					
Measuring referenced to source Inspection of limits after work done. If paid plan qty, verify work done according to plan Dates Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth	Eqpmnt, State Personnel, survey note	es identified, crew names & duties			
Measuring referenced to source Inspection of limits after work done. If paid plan qty, verify work done according to plan Dates Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth	CLEARING		Dates		
Inspection of limits after work done. If paid plan qty, verify work done according to plan EXCAVATION				T	
If paid plan qty, verify work done according to plan			<u> </u>		
Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements :ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth		rding to plan		1 1	
Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth	pana pian 43, tom, nom acite acce			†	
Source and final placement noted in diary Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth					
Embankment core staked out, waste storage areas designated/owner sign Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth Dates Dates			Dates		
Design changes in backslopes. Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth					
Documentation of excavation limits in backslopes and ditches Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth		storage areas designated/owne <u>r sign</u>		_	
Grubbing, undercuts, muck excavation, measured, documented If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10%. BORROW					
If paid plan, verify accuracy of estimate & work done to plan excavation by truck measure reduce 10% BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE					
BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth Dates Dates					
BORROW Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth Dates		e & work done to plan			
Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth	excavation by truck measure reduce 10%				
Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth		W-11-4			
Source and final placement noted in diary. Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth					
Pit rehabilitation. Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth Dates	<u>BORROW</u>		Dates		
Location of pit described, layout shown Final cross-section or statement of inspection plus 500' check section measurements :ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth Dates		liary.			
Final cross-section or statement of inspection plus 500' check section measurements: ip swell 15%, truck measure deduct 10%, & check Engineers est STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth Dates	Pit rehabilitation.				
STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth Dates					
STRUCTURAL EXCAVATION AND DRAINAGE Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth Dates	Final cross-section or statement of ins	spection plus 500' check section			
Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE Dates	measurements :ip swell 15%, truck measure d	educt 10%, & check Engineers est			
Culverts: drainage installation notes regarding backfill, line and grade Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE Dates					
Bedding, width and depth measurement for undercut Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE Dates			Dates		
Length of pipe measured or documented. Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE Dates					
Catch Basins: diameter of hole measured for undercut Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE Dates					
Multiplate: depth of bedding, width of excavation, disposition of over- Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE Dates					
Compensation for over-excavation if a borrow job rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE Dates					
rock w/0 rock ex minor struct pay 16 times common ex/ rock w/0 rock major struct pay 6 times struct earth GRAVEL BASE SUBBASE Dates	•				
GRAVEL BASE SUBBASE Dates	•				
	rock w/0 rock ex minor struct pay 16 times con	nmon ex/ rock w/0 rock major struct pay 6 times	struct earth		
	CDAVEL BASE SUBBASE		Datas		
Chaver checks, and under a not or draver checks for Hallinge. Not 1040s 1 1 1		val chacks for mainling, side reads	Dates	1	
truck measure reduce 20% & check Engineers est & how to measure plan or truck measure		· · · · · · · · · · · · · · · · · · ·	L		

Maine Department of Transportation Contractor's Performance Rating

ৡ The computer program for contractor evaluation will provide numerical analysis and rating প্র CHECK APPROPRIATE ITEMS. DO NOT SCORE ITEMS WHICH DO NOT APPLY

The preliminary report shall be completed by the Resident Engineer, discussed with the Superintendent and Project Manager at a project closeout meeting and forwarded to the Construction Engineer/Program Manager. The Resident Engineer shall assure that the rating reflects the contractor's performance demonstrated by the Contractor on the contract indicated. Below Standard or Inadequate performance shall be sufficiently documented in the project records and SO NOTED ON THIS FORM. The Resident Engineer shall complete the review of the Preliminary Contractor's Performance Pating no later than ten (10) calendar days after the rating period ends. Contained in each category listed are items, (1, 2, 3, etc.) that reflect areas of performance the Contractor demonstrated in completing the terms and conditions of the contract. The Resident Engineer using the PATING DESCHPTICNS ATTACHED shall rate items. Rate each item on its own and for this contract only without any averaging of one item against another or any tempering up or down because performance on some other contract. The Resident Engineer should use those personnel that actively participated in the inspection of the work and/or the administration of the contract to assist in rating the Contractor's performance.

PINI ·

Date

Contractor:									
Address:							·		
Town:		Prime:							
	Project Type		Resident Engineer:						
Bridge Construction			Project Manager:						
Highway Constr	uction				Project Start Date:				
Paving				Project Completion Date:					
Marine Constru	otion			Contract Amount \$					
Buildings	Subcontract A	mour	nt\$						
Traffic Signals an	d/or Lighting			Annual		T ype of Report Interim Type:	Final		
Quality of Work	Cooperation	Prosecution Progress	&	Policies, Procedures Regulations	&	Procedural & Administrative	Total Score		
Sgnatures							·		
MDOT Resident Engineer		Contractor's Superintendent					_		
	uction Engineer/ Manager	- Adm	inis	strator/Proj	ect N	Manager			

MAINE DEPARTMENT OF TRANSPORTATION CONTRACTOR'S PERFORMANCE RATING

		na i iiv	∽			
CATEGORIES AND ITEMS	EXCELENT	ABOVE STANDARD	STANDARD	BELOW STANDARD	INADEQUATE	PLI II L NCE
QUALITY OF WORK						
1. Contractor Quality Control						
2. Workmanship						×
Compliance with Contract Requirements						
4. Adequacy of Personnel						
5. Contractor Engineering and Survey Layout						
COOPERATION						
1. Partnering (Team Building)						
2. Attitude (Cooperation)						
PROSECUTION & PROG	RESS		<u></u>	<u></u>	<u> I</u>	
1. Adherence to Progress Schedule						
2. Compliance with Environmental Regulations		2922		-		
Compliance with Traffic Regulations						
4. Compliance with Safety Regulations						
5. Adequacy of Equipment						
IMPLEMENTATION OF POLICIES, PROCEDURES			OCAL			
1. Compliance with Labor Standards		TATIONS			1	
and EEO Requirements						
2. Compliance with DBE Requirements						
3. Compliance with OJF Requirements						
PROCEDURAL/ADMINIS	TRATIVE			1 · · · · · · · · · · · · · · · · · · ·		
1. Adequacy of Supervision						
Adequacy of Subcontractor Management						
Managaman						

MDOT Labor Interview Questionnaire							
(1) Project #		(2) Town		(3) County			
(4) Prime Contrac	etor		(5)	Subcontractor			
(6) Employee	(7) Social Secu	7) Social Security # (8) Classifi		(9) Wage Rate	(10) Fringe		
(11) Are you satisfied	d that you are paid an	nd classified correc	tly?		1		
□ Yes	<i>□</i> No		If answer	r is no, please explain bel	ow		
İ							
i							
(12) Is any money de	educted from your pa	u except Income To	ıx. Social Secu	ity or Court Ordered Dec	hiction?		
□ Yes □ N		rswer is yes, please					
					-		
		atot same					
(13) Signature	of employee						
(14) Is permission gi	um to dimelas to	nomployer the	amnation in +L	e etatament?			
(14) 15 permission gi	осн о шошуе ю уош	i engwyer, we try	ગ તાલાલ ા લ છે.	is statement !			
	Yes	□ No					
(15) Interviewers con	mmante						
(15) Therviewers con	mmerus						
(16) Interviewer's Si	gnature						

State of Maine - Department of Transportation FRINGE BENEFIT STATEMENT October 26, 2004 CONTRACTOR/SUBCONTRACTOR CONTRACT NUMBER FEDERAL AID PROJECT # DATE TO: RESIDENT ENGINEER/LABOR COMPLIANCE OFFICER BUSINESS ADDRESS The following information (as shown on wage rate determinations) paid to or on behalf of employees in various crafts or classifications is used to check payrolls or applied to force account work on the above contract. THIS FORM MUST BE COMPLETED AND SUBMITTED WITH THE FIRST CERTIFED PAYROLL, OR WHEN THERE HAVE BEEN ANY CHANGES. NAME AND ADDRESS OF PLAN, FRINGE BENEFIT HOURLY AMOUNT **CLASSIFICATION** FUND, OR PROGRAM Effective Date Vacation \$ Health & Welfare \$_____ Pension \$____ Travel Pay Apprentice/ Training \$_ CLASSIFICATION FRINGE BENEFIT HOURLY AMOUNT NAME AND ADDRESS OF PLAN, FUND, OR PROGRAM Effective Date Vacation \$

Welfare \$

Pension \$_____

Training \$_____

Other \$

FRINGE BENEFIT HOURLY AMOUNT

Welfare \$

Pension \$_____

Training \$_____

Other \$_____

NAME AND ADDRESS OF PLAN,

FUND, OR PROGRAM

Health &

Apprentice/

Vacation \$__

Apprentice/

Travel Pay

CLASSIFICATION

Effective Date

Travel Pay