

Special Condition
for
Third Party Inspection Program

THIRD-PARTY INSPECTION PROGRAM

1.0 THE PURPOSE OF THE THIRD-PARTY INSPECTION

As a condition of this permit, the Maine Department of Environmental Protection (MDEP) requires the permit applicant to retain the services of a third-party inspector to monitor compliance with MDEP permit conditions during construction. The objectives of this condition are as follows:

- 1) to ensure that all construction and stabilization activities comply with the permit conditions and the MDEP-approved drawings and specifications,
- 2) to ensure that field decisions regarding erosion control implementation, stormwater system installation, and natural resource protection are based on sound engineering and environmental considerations, and
- 3) to ensure communication between the contractor and MDEP regarding any changes to the development's erosion control plan, stormwater management plan, or final stabilization plan.

This document establishes the inspection program and outlines the responsibilities of the permit applicant, the MDEP, and the inspector.

2.0 SELECTING THE INSPECTOR

At least 30 days prior to starting any construction activity on the site, the applicant will submit the names of at least two inspector candidates to the MDEP. Each candidate must meet the minimum qualifications listed under section 3.0. The candidates may not be employees, partners, or contracted consultants involved with the permitting of the project or otherwise employed by the same company or agency. The MDEP will have 15 days from receiving the names to select one of the candidates as the inspector or to reject both candidates. If the MDEP rejects both candidates, then the MDEP shall state the particular reasons for the rejections. In this case, the applicant may either dispute the rejection to the Director of the Bureau of Land and Water Quality or start the selection process over by nominating two, new candidates.

3.0 THE INSPECTOR'S QUALIFICATIONS

Each inspector candidate nominated by the applicant shall have the following minimum qualifications:

- 1) a degree in an environmental science or civil engineering, or other demonstrated expertise,
- 2) a practical knowledge of erosion control practices and stormwater hydrology,
- 3) experience in management or supervision on large construction projects,
- 4) the ability to understand and articulate permit conditions to contractors concerning erosion control or stormwater management,
- 5) the ability to clearly document activities being inspected,
- 6) appropriate facilities and, if necessary, support staff to carry out the duties and responsibilities set forth in section 6.0 in a timely manner, and
- 7) no ownership or financial interest in the development other than that created by being retained as the third-party inspector.

4.0 INITIATING THE INSPECTOR'S SERVICES

The applicant will not formally and finally engage for service any inspector under this permit condition prior to MDEP approval or waiver by omission under section 2.0. No clearing, grubbing, grading, filling, stockpiling, or other construction activity will take place on the development site until the applicant retains the MDEP-approved inspector for service.

5.0 TERMINATING THE INSPECTOR'S SERVICES

The applicant will not terminate the services of the MDEP-approved inspector at any time between commencing construction and completing final site stabilization without first getting written approval to do so from the MDEP.

6.0 THE INSPECTOR'S DUTIES AND RESPONSIBILITIES

The inspector's work shall consist of the duties and responsibilities outlined below.

- 1) Prior to construction, the inspector will become thoroughly familiar with the terms and conditions of the state-issued site permit, natural resources protection permit, or both.
- 2) Prior to construction, the inspector will become thoroughly familiar with the proposed construction schedule, including the timing for installing and removing erosion controls, the timing for constructing and stabilizing any basins or ponds, and the deadlines for completing stabilization of disturbed soils.
- 3) Prior to construction, the inspector will become thoroughly familiar with the project plans and specifications, including those for building detention basins, those for installing the erosion control measures to be used on the site, and those for temporarily or permanently stabilizing disturbed soils in a timely manner.
- 4) During construction, the inspector will monitor the contractor's installation and maintenance of the erosion control measures called for in the state permit(s) and any additional measures the inspector believes are necessary to prevent sediment discharge to off-site properties or natural resources. This direction will be based on the approved erosion control plan, field conditions at the time of construction, and the natural resources potentially impacted by construction activities.
- 5) During construction, the inspector will monitor the contractor's construction of the stormwater system, including the construction and stabilization of ditches, culverts, detention basins, water quality treatment measures, and storm sewers.
- 6) During construction, the inspector will monitor the contractor's installation of any stream or wetland crossings.
- 7) During construction, the inspector will monitor the contractor's final stabilization of the project site.
- 8) During construction, the inspector will keep logs recording any rain storms at the site, the contractor's activities on the site, discussions with the contractor(s), and possible violations of the permit conditions.
- 9) During construction, the inspector will inspect the project site at least once a week and before and after any significant rain event. The inspector will photograph all protected natural resources both before and after construction and will photograph all areas of non-compliance. All photographs will be identified with, at a minimum the date the photo was taken, the location and the name of the individual taking the photograph.
Note: the frequency of these inspections as contained in this condition can be varied to best address the particular project needs.
- 10) During construction, the inspector will prepare and submit weekly (*or other frequency*) inspection reports to the MDEP.

- 11) During construction, the inspector will notify the designated person at the MDEP immediately of any significant non-compliance issues.

7.0 INSPECTION REPORTS

The inspector will submit weekly written reports (*or at another designated frequency*), including photographs of potential violations, on a form provided by the Department to the designated person at the MDEP. Each report will be due at the MDEP by the Friday (*or other designated day*) following the inspection week (Monday through Sunday).

The weekly report will summarize construction activities and events on the site for the previous week as outlined below.

- 1) The report will state the name of the development, its permit number(s), and the start and end dates for the inspection week (Monday through Sunday).
- 2) The report will state the date(s) and time(s) when the inspector was on the site making inspections.
- 3) The report will state the date(s) and approximate duration(s) of any rainfall events on the site for the week.
- 4) The report will identify and describe any erosion problems that resulted in sediment leaving the property or sediment being discharged into a wetland, brook, stream, river, lake, or public storm sewer system. The report will describe the contractor's actions to repair any damage to other properties or natural resources, actions to eliminate the erosion source, and actions to prevent future sediment discharges from the area.
- 5) The report will list the buildings, roads, parking lots, detention basins, stream crossings or other features open to construction for the week, including those features or areas actively worked and those left unworked (dormant).
- 6) For each area open to construction, the report will list the date of initial soil disturbance for the area.
- 7) For each area open to construction, the report will note which areas were actively worked that week and which were left dormant for the week. For those areas actively worked, the report will briefly state the work performed in the area that week and the progress toward final stabilization of the area -- e.g. "grubbing in progress", "grubbing complete", "rough grading in progress", "rough grading complete", "finish grading in progress", "finish grading complete", "permanent seeding completed", "area fully stable and temporary erosion controls removed", etc.
- 8) For each area open to construction, the report will list the erosion and sedimentation control measures installed, maintained, or removed during the week.
- 9) For each erosion control measure in-place, the report will note the condition of the measure and any maintenance performed to bring it to standard.