

STATE OF MAINE DEPARTMENT OF TRANSPORTATION 16 STATE HOUSE STATION AUGUSTA, MAINE 04333-0016

DAVID A. COLE

May 05, 2003

Subject: Stetson / Carmel

Project No. STP-1009(200)X / BR-1007(900)X

Pin No. 10092.00 / 10079.00 **Bid Amendment No. 3**

Dear Sir/Ms.:

Please make the following changes to your bid package.

- 1) In the "Schedule of Items" please change the quantity for item # 206.061 "Structural Earth Excavation-Drainage and Minor Structures, Below Grade" from 555.000 M3 to now read 540.000 M3.
- **2)** On the plan sheets for Project Number STP-1009(200) X please delete in its entirety Item # 206.061 "Structural Earth Excavation-Drainage and Minor Structures, Below Grade" with a quantity of 15 M3.

Make these changes in pen and ink.

3) The following is the response to a recent RFI.

Question: Is the excavation for the box culverts incidental or paid for as Structural Excavation?

Response: The excavation for the box culverts is incidental to the box culvert pay item down to 300 mm below the structure. The box culvert in Carmel has granular borrow 600 mm below the invert. The structural excavation pay item is to pay for the excavation of the additional 300 mm below what is covered under the box culvert pay item. <u>See changes above.</u>

Consider these changes prior to submitting your bid on May 07, 2003.

Sincerely,

Bruce R. Carter Contracts Engineer

Buce R. Contes

