



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

February 2, 2004
Subject: Bethel, Woodstock
and Oxford
Project No. NH-1144(400)E,
STP-1209(100)X
Amendment No. 1

Dear Sir/Ms.:

Please make the following change to your bid package.

- 1) Replace the Special Provision, Section 603, Headwall (Remove and Dispose) one page dated December 30, 2003 with the attached Special Provision, Section 603, Headwall (Remove and Dispose) dated January 30, 2004.
- 2) In the Construction Notes for PIN 011444.00 page 1 of 2, Item 606.165 15 inch RCP Class 3, please change in pen and ink, the extension for station 144+08 rt. to now read 144+08 lt.

Consider these changes prior to submitting your bid on February 11, 2004.

Sincerely,

Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SPECIAL PROVISION
SECTION 603
HEADWALL
(Remove and Dispose)

Description This work shall consist of the removal and disposal of all or part of existing headwalls, as indicated in the contract.

CONSTRUCTION REQUIREMENTS

General Where a secure connection of an extension can be made to the existing pipe and headwall the headwall may remain in place as long as it is removed to a minimum elevation 300 mm (1 foot) below the grade of the 4:1 inslope. If the previous requirements can not be met then the existing headwall shall be removed in its entirety. The final decision to partially or completely remove the headwall shall be made by the Resident. All headwall material removed shall become the property of the Contractor.

Method of Measurement Headwall, Remove and Dispose, will be measured by each.

Basis of Payment The quantity of Headwall, Remove and Dispose, will be paid for at the contract unit price per each.

Payment will made under:

| <u>Pay Item</u> | <u>Pay Unit</u> |
|--------------------------------------|-----------------|
| 603.748 Headwall, Remove and Dispose | Each |