



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

May 19, 2004
Subject: South Windham & Gorham
Project No. BH-A017 (000)X
PIN 10170.00
Bid Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to your Bid Package:

Delete "Special Provision Section 502 Structural Concrete (QC/QA Acceptance Methods)" dated September 16, 2003 one page, and replace with the attached one page entitled "Special Provision Section 502 Structural Concrete (QC/QA Acceptance Methods)" dated May 19, 2004.

Please make the following change in pen and ink to the Plan Sheets:

On sheet 2 of 46 entitled "Estimated Quantities" add the following note # 28 to the General Construction Notes:

28. The Contractor shall be responsible for placing temporary pavement on the box beams or leveling slab during times that permanent pavement is unavailable. Temporary pavement shall be removed and the surface prepared as directed by the Resident prior to placing final pavement. All labor, materials, and other incidentals related to the placing and removal of this temporary pavement shall be incidental to related contract items.

Consider these changes prior to submitting your bid on May 26, 2004.

Sincerely,

Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SPECIAL PROVISION
SECTION 502
 STRUCTURAL CONCRETE
 (QC/QA Acceptance Methods)

CLASS OF CONCRETE	ITEM NUMBER	DESCRIPTION	P	METHOD
A	502.21	Structural Concrete Abut. & Ret.Walls	\$550	A
S	502.22	Structural Concrete Abut. & Ret.Walls (UW)		B
A	502.23	Structural Concrete Piers	\$550	A
S	502.24	Structural Concrete Piers (UW)		B
A	502.25	Structural Concrete Superstructure Slab	\$550	A
A	502.31	Structural Concrete Approach Slab		B
LP	502.49	Structural Concrete Curbs & Sidewalks	\$650	A
LP	526.323	Texas Classic Rail	\$650	A

P values listed above reflect the price per cubic meter (M³) for all pay adjustment purposes.