

## STATE OF MAINE DEPARTMENT OF TRANSPORTATION 16 STATE HOUSE STATION AUGUSTA, MAINE 04333-0016

DAVID A. COLE
COMMISSIONER

November 17, 2003 Subject: Project STP-1071(100)X PIN 10171 Windham Bid Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to your Bid Package:

In the General Notes on the plans, add the following note in pen and ink:

"Dredge Material (See MDOT Standard Specifications 101.2) is regulated as a Special Waste. 38 cubic meters [50 yd³] or less of Dredge Material Beneficially Used in the area adjacent to and draining into the dredged water body is exempt from regulation. The Contractor shall ensure that all Dredge Material is placed into the fill areas specified by MDOT. No more than 38 cubic meters [50 yd³] of Dredge Material may be excavated without authorization from the Resident."

Add the attached Special Provision 203 - Dredge Materials dated 10/28/03.

Replace the 1 page Schedule of Items dated 10-15-03 with the attached 2 page Schedule of Items dated 11-17-03

Consider these changes prior to submitting your bid on November 19, 2003.

Sincerely,

Bruce R. Carter
Contracts Engineer



## SPECIAL PROVISION <u>SECTION 203</u> EXCAVATION AND EMBANKMENT (Dredge Materials)

<u>Description</u> Dredge Material (See MDOT Standard Specifications 101.2) is regulated as a Special Waste.

38 cubic meters [50 yd³] or less of Dredge Material Beneficially Used in the area adjacent to and draining into the dredged water body is exempt from regulation. The Dredge Material quantity from the Black Brook Bridge site is expected to be less than 38 cubic meters [50 yd³].

## CONSTRUCTION REQUIREMENTS

<u>Management and Disposal</u> The contractor shall Beneficially Use all Dredge Material excavated at the Black Brook Bridge Project as construction fill to reshape the side slopes in the area adjacent to and draining into the dredged water body. No more than 38 cubic meters [50 yd<sup>3</sup>] of Dredge Material may be excavated.

<u>Method of Measurement:</u> Dredge Material will be measured by the cubic meter [cubic yard] of material removed.

**Basis of Payment:** Dredge Material Beneficially Used will be paid for at the contract unit price bid for Structural Excavation.

Payment shall be full compensation for excavating, dewatering, managing, transporting, placing, and compacting.

Payment will be made under:

Pay Item 206.061 Structural Earth Excavation Pay Unit cubic meter [yd³]

SCHEDULE OF ITEMS REVISED:

CONTRACT ID: 010171.00 PROJECT(S): STP-1017(100)X

INE	ITEM	•	PROX.			BID A	
NO   DE	SCRIPTION					DOLLARS	
	SEC	CTION 0001	BRIDGE I	TEMS			
0010 EXCAVAT	STRUCTURAL EAF TION - DRAINAGE TOR STRUCTURES, GRADE	Ì	38.000	       	     	       	       
	STRUCTURAL E CULVERT INVER	   RT  LUMP 		  LUMP 	     	   	     
503.12  0030 FABRIC	REINFORCING STE	EEL,  RED    KG	2440.000	     	     	   	     
503.13  0040 PLACING	REINFORCING STE		2440.000	   	     	   	     
511.07  0050 	COFFERDAM: 1	  LUMP 		  LUMP 	     	   	   
511.07     	COFFERDAM: 2	  LUMP 		  LUMP 	     	   	     
610.09  0070  	HAND LAID RIPRA	AP      M3	20.000	   	     	   	   
652.39   0080   CONTROI 	WORK ZONE TRAFE	FIC    LUMP 		  LUMP 	     	   	   
0090 EROSION	TEMPORARY SOIL AND WATER ON CONTROL	  LUMP 		  LUMP 	     	   	   
659.10  0100  	MOBILIZATION	•		  LUMP 	     	     	     

MAINE DEPARTMENT OF TRANSPORTATION PAGE: 2
DATE: 031117

SCHEDULE OF ITEMS REVISED:

CONTRACT ID: 010171.00 PROJECT(S): STP-1017(100)X