



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

June 25, 2004
Subject: Patten & Crystal
Project No: STP-1020(010)X
PIN: 10200.10
Bid Amendment No. 1

Dear Sir/Ms.:

Please make the following change to your Bid Package:

Add the attached one page, entitled "Special Provision Section 203 Excavation and Embankment (Dredge Materials)" dated 22 June 2004.

Please make the following change to the Plan Sheets:

On Plan Sheet No. 7 of 175 add the following to the General Notes:

46. Dredge Material (See MDOT Standard Specifications § 101.2) is regulated as a Special Waste. Fifty cubic yards or less of Dredge Material Beneficially Used in the area adjacent to and draining into the dredged water body is exempt from Beneficial Use Permits. The Contractor shall ensure that all Dredge Material is placed into the fill areas specified by MDOT. No more than fifty cubic yards (38 cubic meters) of Dredge Material may be excavated without authorization from the Engineer.

Make this change in pen and ink.

Consider these changes prior to submitting your bid on June 30, 2004.

Sincerely,

FOR
Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SPECIAL PROVISION
SECTION 203
EXCAVATION AND EMBANKMENT
(Dredge Materials)

Description: Dredge Material (See MDOT Standard Specifications § 101.2) is regulated as a Special Waste.

Fifty cubic yards or less of Dredge Material Beneficially Used in the area adjacent to and draining into the dredged water body is exempt from Beneficial Use Permits. The Dredge Material quantity from the culvert work associated with the Patten-Crystal (PIN 10200.10) Project is expected to be less than 50 cubic yards (38 cubic meters).

CONSTRUCTION REQUIREMENTS

Management and Disposal: The contractor shall Beneficially Use all Dredge Material excavated at the PIN 10200.10 Project in the area adjacent to and draining into the dredged water body. No more than 38 cubic meters (50 cubic yards) of Dredge Material may be excavated.

Method of Measurement: Dredge Material will be measured by the cubic meter of material removed.

Basis of Payment: Payment for Dredge Material Beneficially Used will be incidental to Pay Item 534.71 "Precast Concrete Box Culvert".

Payment shall be full compensation for excavation, dewatering, managing, transporting, and placement.