



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

November 6, 2003
Subject: Project STP-1021(400)X
PIN 10214.00
Windham
Bid Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to your Bid Package:

Add the attached 1 page Typical Section for side roads and drives.

Make the following changes by pen and ink:

In the General Notes, sheet 7 of 32:

Note 4. Change to read;

“All residential entrances shall be constructed with one (1) foot of ASCG and two (2) inches of Hot Mix Asphalt.

All Side Roads shall be constructed with 20 inches of ASCG and four (4) inches of Hot Mix Asphalt.”

Delete Notes 16,19,34,35, and 45.

Note 22. Add the following at the end of the note;

“All test pits to identify utility facilities shall be completed by the respective utility company.”

Note 46. Change to read;

“All water main pipes, underdrain, and drainage structures designated on plans or as directed by the Resident shall be removed to limits shown or limits as directed by Resident. Removal shall include all items necessary to complete the removal of water main, including any additional backfill material and compaction of the material. Any remaining sections authorized to remain shall be plugged with brick



PRINTED ON RECYCLED PAPER


and mortar. No separate payment shall be made for any of this work and payment shall be considered incidental to contract.”

In the Sub-Basin Bowl Detail, sheet 7 of 32:

Delete all references to traps and extend the outlet pipes to the basin.

Consider these changes prior to submitting your bid on November 12, 2003.

Sincerely,


for Bruce R. Carter
Contracts Engineer

