



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

August 24, 2004
Subject: Monroe
Project No. BH-1153(300)X
Pin No. 11053.00
Bid Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to your bid package:


Delete in its entirety the "Schedule of Items" 4 pages dated 040728 and replace with the new attached "Schedule of Items" 4 pages dated 040824.

The Department has received the following Request for information:

- Q) How many Bridge Post are there?
- R) There are 4 concrete posts on each side of the bridge.
- Q) Is the Remove and Reset rail 3b?
- R) The Remove and Reset Guardrail is for the area where the Catch Basin is to be installed

Consider these changes prior to submitting your bid on August 25, 2004.

Sincerely,


Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

THE MAINE DEPARTMENT OF TRANSPORTATION IS AN AFFIRMATIVE ACTION - EQUAL OPPORTUNITY EMPLOYER

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 1

SCHEDULE OF ITEMS

DATE: 040824

REVISED:

CONTRACT ID: 011053.00

PROJECT(S): BH-1105(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 BRIDGE ITEMS

0010	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	348.000 SY				
0020	202.30 REMOVING EXISTING CONCRETE WEARING SURFACE	LUMP	LUMP			
0030	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	20.000 CY				
0040	403.210 HOT MIX ASPHALT 9.5 MM HMA	50.000 T				
0050	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	60.000 T				
0060	409.15 BITUMINOUS TACK COAT APPLIED	10.000 G				
0070	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0080	502.704 DRAINAGE SYSTEM (DOWNSPOUTS, THROUGHES, ETC.)	LUMP	LUMP			
0090	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0100	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 7.9 IN.	113.000 SF				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

SCHEDULE OF ITEMS

DATE: 040824

REVISED:

CONTRACT ID: 011053.00

PROJECT(S): BH-1105(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 7.9 IN.	38.000 SF				
0120	604.244 CATCH BASIN TYPE F4	1.000 EA				
0130	606.18 GUARDRAIL TYPE 3B - DOUBLE RAIL	70.000 LF				
0140	606.35 GUARDRAIL DELINEATOR POST	4.000 EA				
0150	606.36 GUARDRAIL REMOVED AND RESET	40.000 LF				
0160	606.48 SINGLE GALVANIZED STEEL POST	16.000 EA				
0170	606.78 LOW VOLUME GUARDRAIL ENDS - TYPE 3	2.000 EA				
0180	609.31 CURB TYPE 3	130.000 LF				
0190	610.08 PLAIN RIPRAP	1.000 CY				
0200	615.07 LOAM	10.000 CY				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 3

SCHEDULE OF ITEMS

DATE: 040824

REVISED:

CONTRACT ID: 011053.00

PROJECT(S): BH-1105(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	1.000 UN				
0220	620.54 STABILIZATION GEOTEXTILE	3.000 SY				
0230	629.05 HAND LABOR, STRAIGHT TIME	8.000 HR				
0240	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	8.000 HR				
0250	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				
0260	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR				
0270	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	16.000 HR				
0280	639.19 FIELD OFFICE TYPE B	1.000 EA				
0290	652.38 FLAGGER	200.000 HR				
0300	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0310	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 4

SCHEDULE OF ITEMS

DATE: 040824

REVISED:

CONTRACT ID: 011053.00

PROJECT(S): BH-1105(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					