



JOHN ELIAS BALDACCI  
GOVERNOR

STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

DAVID A. COLE  
COMMISSIONER

August 3, 2004  
Subject: Newcastle  
Project No. STP-1124(700)X  
PIN 11247.00  
**Bid Amendment No. 2**

Dear Sir/Ms.:

The Department has received the following Requests for Information:

**Q)** The Plan calls for a 4' Diameter Pump Station with Dual Pump, however the Duplex Sanitary Pump Station detail calls for a 6' ID pump station. Could you clarify 4' or 6'?

**R)** 4' diameter pump station is acceptable.

**Q)** I can't read the Pump Modal on the Spec Drawings, can you verify?

**R)** Pump is a Myers ME3 1/3 HP or equal.

**Q)** What do you require for a control Panel? Power?

**R)** Power hook up is at existing panel in the existing restroom building.

**Q)** The Cross Section on site plan prepared by S.W. Cole calls for : Remove existing soil down to a minimum depth of 50"....could you clarify what is meant by 50" depth of 50," do they mean 50" below TBM or 50" below existing grade?

**R)** Removal of 50" of existing soil, this is measured from the high point of existing grade. This means that 1.5' of soil will be removed under the finished grade of the chambers.




PRINTED ON RECYCLED PAPER

**Q) What is a Bid Bond Validation Number?**

**R) Disregard Bid Bond Validation Number.**

Consider this information prior to submitting your bid on August 4, 2004.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford". The signature is fluid and cursive, with the first name "Scott" and last name "Bickford" clearly distinguishable.

Scott Bickford  
Contracts & Specifications Engineer