

STATE OF MAINE DEPARTMENT OF TRANSPORTATION 16 STATE HOUSE STATION AUGUSTA, MAINE 04333-0016

DAVID A. COLE

May 12, 2003 Subject: Dixfield Project No. NH-4329(40)E PIN 4329.40 **Bid Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to your bid package.

- 1) Delete in its entirety the "Schedule of Items" 4 pages dated 030402, and replace with the new attached "Schedule of Items' 4 pages dated 030509.
- 2) Please add the attached 1 page Special Provision Section 621 "Planting Season" dated 5/09/03.
- **3)** In Special Provision Section 652 "Maintenance of Traffic", Please add the following statement; "Road Access Maintenance: Minimum road width shall be maintained during working hours to accommodate emergency vehicles, a 12' 0" width shall be maintained during non-working hours.

Make this change in pen and ink.

- 4) Please add the following notes to the Plan Sheets.
 - **a.)** On sheet # 2 of 8 entitled "Materials and Quantities" delete in its entirety Item # 610.07 Stone Fill (Roadway) with a total quantity of 50 CY
 - **b.)** Add Item # 203.26 "Gravel Borrow" with a quantity of 35CY at Pole 19 and 15 CY at Upstream Culvert with a total of 50 CY.
 - **c.**) On sheet # 2 of 8 entitled "Materials and Quantities", "Under Item Number "621.54 Deciduous Shrubs 18" 24" " the "Pole 19" site plant quantities shall be categorized as follows: 1310 plants are identified by type and size on page 4 "Pole 19 Site Restoration Plan." 925 *Salix discolor Pussy Willow* (621.54) shall be used for the bioengineering on this site. Upstream Culvert site: 290 plants are identified by type and size on page 7 "Culvert Site Restoration Plan." 145 *Salix discolor Pussy Willow* (621.54) shall be used for the bioengineering on this site. Downstream Culvert site: 180 *Salix discolor Pussy Willow* (621.54) shall be used for the bioengineering on this site."



d.) On Plan Sheet # 3 of 8 please add the following as note # 7. "Temporary construction access to the Pole 19 site shall be provided by the Contractor. Access road will be to the east of Pole 19 and run north to the South Branch of the Sandy River. The specific location is to be determined at Pre-Construction meeting."

Make these changes in pen and ink.

- 5) The following is provided for informational purposes.
 - **a.)** All plant materials for this project shall be containerized. Quantities shall not change

Consider these changes prior to submitting your bid on May 14, 2003.

Sincerely,

Bruce R. Carter Contracts Engineer

Buce R. Contes

MAINE DEPARTMENT OF TRANSPORTATION

SCHEDULE OF ITEMS

PAGE: 1 DATE: 030509

REVISED:

CONTRACT ID: 004329.40 PROJECT(S): NH-4329(40)E

| CONTRACTOR | : | |
|------------|---|--|
|------------|---|--|

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY | UNIT PRICE | | | | |
|--------------|---|------------------|---------------|---------------|--|--|--|
| | | AND UNITS | DOLLARS CTS | DOLLARS CTS | | | |
| | SECTION 0001 MITIGATION ITEMS | | | | | | |
| 0010 | 201.11 CLEARING | 0.25 | 0 | | | | |
| 0020 | 203.20 COMMON EXCAVATION | 780.00 | 0 | | | | |
| 0030 | 203.25 GRANULAR BORROW | 60.00 | 0 | | | | |
| 0040 | 203.26 GRAVEL BORROW | 50.00 | 0 | | | | |
| 0050 | 603.911 60" X 38" RCP ELLIPTICAI CULVERT PIPE | 40.00 | 0 | | | | |
| 0060 | 606.17 GUARDRAIL TYPE 3B - SINGLE RAIL | 75.00 LF | 0 | | | | |
| 0070 | 606.35 GUARDRAIL DELINEATOR POST | 4.00 EA | 0 | | | | |
| 0080 | 606.78 LOW VOLUME GUARDRAIL ENDS - TYPE 3 | 4.00 EA | 0 | | | | |
| 0090 | 610.09 HAND LAID RIPRAP - CULVERT PROTECTION | 32.00 CY | 0 | | | | |
| 0100 | 610.10 VEGETATED RIPRAP | 105.00 | 0 | | | | |

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2 DATE: 030509 SCHEDULE OF ITEMS REVISED:

CONTRACT ID: 004329.40 PROJECT(S): NH-4329(40)E

| CONTRACTOR : | |
|--------------|--|
|--------------|--|

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY | UNIT PRICE | | | |
|--------------|---|---------------------|------------|-----------|--|-----|
| NO | DESCRIPTION | AND UNITS | DOLLARS | I . | | CTS |
| | 610.18 STONE DITCH PROTECTION | 30.00 | 0 | | | |
| | 610.21 RIVER STONES - RIFFLES | 45.00 | 0 | | | |
| 0130 | 615.07 LOAM | 145.00 CY | 0 | | | |
| | 618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY | 14.00 UN | 0 | | | |
| | 619.1201 MULCH - PLAN QUANTITY | 14.00 UN | 0 | | | |
| 0160 | 619.1401 EROSION CONTROL | 125.00 | 0 | | | |
| | 620.58 EROSION CONTROL GEOTEXTILE | 80.00 SY | 0 | | | |
| 0180 | 621.01 EVERGREEN TREES (8 INCH - 12 INCH) | 139.00 EA | 0 | | | |
| 0190 | 621.245 LARGE DECIDUOUS TREES (2 FOOT - 3 FOOT) GROUP A | 111.00 EA | 0 | | | |
| 0200 | 621.54 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP A | 2850.00 EA | 0 | | | |
| | 621.80 ESTABLISHMENT PERIOD | LUMP | LUMP | | | |

MAINE DEPARTMENT OF TRANSPORTATION

SCHEDULE OF ITEMS

PAGE: 3 DATE: 030509 REVISED:

CONTRACT ID: 004329.40 PROJECT(S): NH-4329(40)E

CONTRACTOR :

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE | | BID AMOUNT | |
|--------------|---|----------------------------------|------------|-----|------------|-----|
| | | | DOLLARS | CTS | DOLLARS | CTS |
| | 629.05 HAND LABOR, STRAIGHT TIME | 89.000 | | | | |
| | 631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR) | 82.000 HR |) | | | |
| 0240 | 631.172 TRUCK - LARGE (INCLUDING OPERATOR) | 67.000 |) | | | |
| | 631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR) | 14.000 |) | | | |
| 0260 | 637.071 DUST CONTROL | LUMP | LUMP | | | |
| 0270 | 652.34 CONE | 20.000 |) | | | |
| | 652.35 CONSTRUCTION SIGNS | 100.000 |) | | | |
| | 652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES | LUMP | LUMP | | | |
| 0300 | 652.38 FLAGGER | 16.000 |) | | | |
| 0310 | 656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL | LUMP | LUMP | | | |
| 0320 | 659.10 MOBILIZATION | LUMP | LUMP | | | |
| | SECTION 0001 TOTAL | | | | | |

PAGE: 4 DATE: 030509 MAINE DEPARTMENT OF TRANSPORTATION

REVISED: SCHEDULE OF ITEMS

CONTRACT ID: 004329.40 PROJECT(S): NH-4329(40)E

CONTRACTOR:

| LINE | ITEM | APPROX. | UNIT PRICE | BID AMOUNT | |
|------|-------------|--------------------|---------------|---------------|--|
| NO | DESCRIPTION | QUANTITY AND UNITS | DOLLARS CTS | DOLLARS CTS | |
| | TOTAL BID | | | | |

Dixfield PIN 4329.40 Date: 5/09/03

Special Provision 621 Planting Season

621.0020 Planting Time; Add the following Statement

Plant installation time for bioengineering material will be determined by the Contractor's schedule, as approved by the Resident inspector.