



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

May 18, 2004
Subject: Gorham & Windham
Project No. STP-7852(00)X
PIN 7852.00
Bid Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to your bid package:

On the "Notice to Contractors" sixth paragraph, delete the forth sentence and replace with the following:

"Questions received after 12:00 Noon of Thursday, May 27, 2004 will not be answered."

Add the attached one page entitled "Special Provision Section 203 Excavation and Embankment (Dredge Materials)" dated 17 MAY 2004.

Please make the following change in pen and ink to the Plan Sheets:

On plan sheet No. 2 of 16 entitled "Quantities and Notes" add the following Note No. 16 to the "General Construction Notes":

16. Dredge Material (See MDOT Standard Specifications § 101.2) is regulated as a Special Waste. Fifty cubic yards or less of Dredge Material Beneficially Used in the area adjacent to and draining into the dredged water body is exempt from Beneficial Use Permits. The Contractor shall ensure that all Dredge Material is placed into the fill areas specified by MDOT. No more than fifty cubic yards (38 cubic meters) of Dredge Material may be excavated without authorization from the Resident.

Consider these changes prior to submitting your bid on June 2, 2004.

Sincerely,

Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

GORHAM & WINDHAM—7852.00
GAMBO FALLS BRIDGE (0266)
17 MAY 2004

SPECIAL PROVISION
SECTION 203
EXCAVATION AND EMBANKMENT
(Dredge Materials)

Description: Dredge Material (See MDOT Standard Specifications § 101.2) is regulated as a Special Waste.

Fifty cubic yards or less of Dredge Material Beneficially Used in the area adjacent to and draining into the dredged water body is exempt from Beneficial Use Permits. The Dredge Material quantity from the Gambo Falls Bridge site is expected to be less than 50 cubic yards (38 cubic meters).

CONSTRUCTION REQUIREMENTS

Management and Disposal: The contractor shall Beneficially Use all Dredge Material excavated at the Gambo Falls Bridge Project in the area adjacent to and draining into the dredged water body. No more than 38 cubic meters (50 cubic yards) of Dredge Material may be excavated.

Method of Measurement: Dredge Material will be measured by the cubic meter of material removed.

Basis of Payment: Dredge Material Beneficially Used will be paid for at the contract unit price bid for Structural Earth Excavation – Major Structures.

Payment shall be full compensation for excavation, dewatering, managing, transporting, and placement.

Payment will be made under:

<u>Pay Item</u>		<u>Pay Unit</u>
206.082	Structural Earth Excavation – Major Structures	cubic meter