STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

July 20, 2004
Subject: **Prospect - Verona**
Project #: **BR-7965(51)X**
PIN: **7965.51**
Bid Amendment #2

Dear Sir/Ms.:

Please make the following change to your Bid Package:

Delete "Special Provision Section 104, General Rights and Responsibilities - Limits on Subcontracting" one page dated February 27, 2004.

The Department has received the following Questions:

Q) Can blown ledge be screened and used as Choke Stone?

A) *Choke Stone can be blown ledge if it meets the gradation requirements.*

Q) On sheet 8 of 86 - Construction Notes - Available Rock Fill Waste Areas discuss an optional rock waste area. Is the Contractor required to fill this area?

A) *The Contractor is not required to fill the optional rock waste fill area. It is delineated as a possible location for waste.*

Q) Please clarify Special Provision Section 105, General Scope of Work - Maintenance During Winter Construction. Where will one Contractor's responsibility begin and another's end? Does this include all existing Rte 1, the existing bridge, and Rte 174 within the Project limits?

A) *As long as the detour is complete and paved, and any disturbed areas are repaired to the satisfaction of the Project Manager, the Department will be responsible for winter maintenance. Other Projects will not work within the existing roadway until 2006.*

PRINTED ON RECYCLED PAPER

THE MAINE DEPARTMENT OF TRANSPORTATION IS AN AFFIRMATIVE ACTION - EQUAL OPPORTUNITY EMPLOYER

Q) Will clearing, site prep, erosion control, etc. be required in the areas of the rock stockpile site, in MDOT designated areas, or offsite at the Cary Pit location? If yes, how will this be paid for? The plans note that the stockpiles will be "measured in-place." How will the stockpiles quantities be measured? Will the material be placed to a specific cross-section or not?

A) *Clearing, site preparation, erosion control, etc. will be required under this Contract in the areas of the rock stockpiles onsite, in the MDOT designated areas, and offsite at the Cary Pit location. Clearing in the designated areas will be paid for at the Contract unit price for clearing. Clearing for waste disposable shall be considered incidental. Site preparation and erosion control shall be considered incidental to the related contract items. The stockpiles in Verona and the Cary Pit will be piled at no particular elevation and paid for by truck count and/or field estimate. The other designated areas will be placed to a yet to be determined cross-section.*

Q) The cross-sections do not list the Cut/Fill quantities. Is it possible to get the station quantities?

A) *See the attached Cut/Fill computations.*

Consider this change and the information provided prior to submitting your bid on July 21, 2004.

Sincerely,

Scott C. Bickford
Contracts & Specifications Engineer.

SUBJECT

FILL AREAS

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
10+00	0			20+00	0		
	0	**30**	**0**		**0**	**30**	**0**
10+30	0			20+30	0		
	0	**20**	**0**		**0**	**20**	**0**
10+50	0			20+50	0		
	0	**37.75**	**0**		**0**	**50**	**0**
10+88	0			21+00	0		
	0	**5**	**0**		**0**	**50**	**0**
10+93	0			21+50	0		
	2.465	**25**	**2.3**		**0**	**50**	**0**
11+18	4.93			22+00	0		
	4.93	**0.01**	**0**		**0**	**50**	**0**
11+18	4.93			22+50	0		
	5.23	**24.99**	**4.8**		**0**	**50**	**0**
11+43	5.53			23+00	0		
	2.765	**8.94**	**0.9**		**0**	**50**	**0**
11+52	0			23+50	0		
	0	**6.06**	**0**		**0**	**50**	**0**
11+58	0			24+00	0		
	0	**10**	**0**		**0**	**50**	**0**
11+68	0			24+50	0		
	0	**19.1**	**0**		**0**	**50**	**0**
11+87	0			25+00	0		
					0	**50**	**0**
				25+50	0		
					0	**50**	**0**
				26+00	0		
					0	**50**	**0**
				26+50	0		
					0	**50**	**0**
30+00	0.89			27+00	0		
	2.34	**11.25**	**1**		**0**	**50**	**0**
30+11	3.79			27+50	0		
	4.235	**12.5**	**2**		**0**	**42.36**	**0**
30+24	4.68			27+92	0		
	4.025	**11.25**	**1.7**				
30+35	3.37						
	5.295	**15**	**2.9**				
30+50	7.22			1+40	0		
	3.61	**50**	**6.7**		**0**	**10**	**0**
31+00	0			1+50	0		
	0	**50**	**0**		**0**	**15**	**0**
31+50	0			1+65	0		
	0.755	**50**	**1.4**				
32+00	1.51						
	9.03	**50**	**16.7**				
32+50	16.55						
	11.265	**50**	**20.9**				
33+00	5.98						
	5.535	**50**	**10.3**				
33+50	5.09						
	5.555	**50**	**10.3**				
34+00	6.02						
	8.195	**50**	**15.2**				
34+50	10.37						
	5.185	**13.45**	**2.6**				
34+63	0						
	Totals:	650.3	99.7		Totals:	817.36	0

-

99.7 Cu.Yds.

SUBJECT

GRUBBING IN FILL

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
10+00	4.55			20+00	5.07		
	2.275	**30**	**2.5**		**2.535**	**30**	**2.8**
10+30	0			20+30	0		
	0	**20**	**0**		**0**	**20**	**0**
10+50	0			20+50	0		
	0.5	**37.75**	**0.7**		**0**	**50**	**0**
10+88	1			21+00	0		
	7.94	**5**	**1.5**		**0**	**50**	**0**
10+93	14.88			21+50	0		
	18.195	**25**	**16.8**		**0**	**50**	**0**
11+18	21.51			22+00	0		
	21.51	**0.01**	**0**		**0**	**50**	**0**
11+18	21.51			22+50	0		
	13.26	**24.99**	**12.3**		**0**	**50**	**0**
11+43	5.01			23+00	0		
	2.505	**8.94**	**0.8**		**0**	**50**	**0**
11+52	0			23+50	0		
	0	**6.06**	**0**		**0**	**50**	**0**
11+58	0			24+00	0		
	0	**10**	**0**		**0**	**50**	**0**
11+68	0			24+50	0		
	0	**19.1**	**0**		**0**	**50**	**0**
11+87	0			25+00	0		
					0	**50**	**0**
				25+50	0		
					0	**50**	**0**
				26+00	0		
					0	**50**	**0**
				26+50	0		
					0	**50**	**0**
30+00	4.58			27+00	0		
	5.98	**11.25**	**2.5**		**0**	**50**	**0**
30+11	7.38			27+50	0		
	10.56	**12.5**	**4.9**		**0**	**42.36**	**0**
30+24	13.74			27+92	0		
	18.175	**11.25**	**7.6**				
30+35	22.61						
	19.415	**15**	**10.8**				
30+50	16.22			1+40	0		
	8.11	**50**	**15**		**0**	**10**	**0**
31+00	0			1+50	0		
	1.6	**50**	**3**		**0**	**15**	**0**
31+50	3.2			1+65	0		
	11.185	**50**	**20.7**				
32+00	19.17						
	20.48	**50**	**37.9**				
32+50	21.79						
	21.855	**50**	**40.5**				
33+00	21.92						
	21.96	**50**	**40.7**				
33+50	22						
	22.015	**50**	**40.8**				
34+00	22.03						
	22.195	**50**	**41.1**				
34+50	22.36						
	11.18	**13.45**	**5.6**				
34+63	0						
	Totals:	650.3	305.7		Totals:	817.36	2.8

-

308.5 Cu.Yds.

SUBJECT UNCLASSIFIED EXCAVATION

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
357+00	0			366+00	2111.25		
	13.26	**50**	**24.6**		**1571.76**	**21.22**	**1235.3**
357+50	26.52			366+21	1032.27		
	40.205	**42.02**	**62.6**		**533.605**	**28.78**	**568.8**
357+92	53.89			366+50	34.94		
	56.535	**7.98**	**16.7**		**92.29**	**11.73**	**40.1**
358+00	59.18			366+62	149.64		
	97.22	**50**	**180**		**150.6**	**38.27**	**213.5**
358+50	135.26			367+00	151.56		
	269.495	**50**	**499.1**				
359+00	403.73						
	543.525	**20**	**402.6**				
359+20	683.32						
	1015.71	**30**	**1128.6**				
359+50	1348.1						
	1767.2	**40**	**2618.1**				
359+90	2186.3						
	2255.895	**10**	**835.5**				
360+00	2325.49						
	2488.42	**20**	**1843.3**				
360+20	2651.35						
	2912.115	**17**	**1833.6**				
360+37	3172.88						
	3235.52	**13**	**1557.8**				
360+50	3298.16						
	3849.45	**50**	**7128.6**				
361+00	4400.74						
	4924.725	**40**	**7295.9**				
361+40	5448.71						
	5566.755	**10**	**2061.8**				
361+50	5684.8						
	6268.99	**50**	**11609.2**				
362+00	6853.18						
	7307.17	**50**	**13531.8**				
362+50	7761.16						
	8193.45	**50**	**15173.1**				
363+00	8625.74						
	8892.575	**50**	**16467.7**				
363+50	9159.41						
	9166.735	**20**	**6790.2**				
363+70	9174.06						
	9082.11	**30**	**10091.2**				
364+00	8990.16						
	8842.59	**50**	**16375.2**				
364+50	8695.02						
	7834.745	**50**	**14508.8**				
365+00	6974.47						
	6490.9	**25**	**6010.1**				
365+25	6007.33						
	5503.765	**25**	**5096.1**				
365+50	5000.2						
	4732.495	**10.26**	**1798.3**				
365+60	4464.79						
	3880.705	**19.74**	**2837.2**				
365+80	3296.62						
	2703.935	**20**	**2002.9**				
366+00	2111.25						
	Totals:	900	149780.6		Totals:	100	2057.7

151838.3 Cu.Yds.