STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

July 20, 2004
Subject: **Prospect - Verona**
Project #: **BR-7965(51)X**
PIN: **7965.51**
Bid Amendment #3

Dear Sir/Ms.:

The Cut/Fill sheets provided in Bid Amendment #2 were incomplete. Attached is the complete set.

Consider this information provided prior to submitting your bid on July 21, 2004.

Sincerely,

Scott C. Bickford
Contracts & Specifications Engineer.

PRINTED ON RECYCLED PAPER

THE MAINE DEPARTMENT OF TRANSPORTATION IS AN AFFIRMATIVE ACTION - EQUAL OPPORTUNITY EMPLOYER

SUBJECT **FILL AREAS**

SUMMARY SHEET

PAGE NO.	DESCRIPTION	PAGE TOTAL
2	357+00 TO 367+00 ROCK CUT	487.6 cy
3	367+00 TO 369+58 PROSPECT ROCK FILL	11089.3 cy
4	388+46 TO 359+00 VERONA ROCK FILL	36543.8 cy
5	1+40, 10+00, 20+00, 30+00 DRIVES	99.7 cy

TOTAL 48220.4 cy

SAY 48,300 CY

SUBJECT **FILL AREAS**

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
357+00	0			366+00	5.03		
	13.96	**50**	**25.9**		**12.17**	**21.22**	**9.6**
357+50	27.92			366+21	19.31		
	32.3	**42.02**	**50.3**		**26.24**	**28.78**	**28**
357+92	36.68			366+50	33.17		
	37.215	**7.98**	**11**		**16.585**	**11.73**	**7.2**
358+00	37.75			366+62	0		
	45.36	**50**	**84**		**0**	**38.27**	**0**
358+50	52.97			367+00	0		
	52.04	**50**	**96.4**				
359+00	51.11						
	47	**20**	**34.8**				
359+20	42.89						
	23.78	**30**	**26.4**				
359+50	4.67						
	4.67	**40**	**6.9**				
359+90	4.67						
	4.67	**10**	**1.7**				
360+00	4.67						
	4.67	**20**	**3.5**				
360+20	4.67						
	4.67	**17**	**2.9**				
360+37	4.67						
	4.67	**13**	**2.2**				
360+50	4.67						
	4.395	**50**	**8.1**				
361+00	4.12						
	4.125	**40**	**6.1**				
361+40	4.13						
	4.125	**10**	**1.5**				
361+50	4.12						
	4.12	**50**	**7.6**				
362+00	4.12						
	4.575	**50**	**8.5**				
362+50	5.03						
	5.03	**50**	**9.3**				
363+00	5.03						
	5.03	**50**	**9.3**				
363+50	5.03						
	5.03	**20**	**3.7**				
363+70	5.03						
	5.03	**30**	**5.6**				
364+00	5.03						
	5.03	**50**	**9.3**				
364+50	5.03						
	5.03	**50**	**9.3**				
365+00	5.03						
	5.025	**25**	**4.7**				
365+25	5.02						
	5.025	**25**	**4.7**				
365+50	5.03						
	5.03	**10.26**	**1.9**				
365+60	5.03						
	4.9	**19.74**	**3.6**				
365+80	4.77						
	4.9	**20**	**3.6**				
366+00	5.03						
	Totals:	900	442.8		Totals:	100	44.8

-

487.6 Cu.Yds.

SUBJECT

FILL AREAS

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
367+21	0						
	75.965	**17.56**	**49.4**				
367+38	151.93						
	356.07	**11.66**	**153.8**				
367+50	560.21						
	968.295	**14.36**	**515**				
367+64	1376.38						
	1586.19	**32.92**	**1934**				
367+97	1796						
	1782.89	**2.72**	**179.6**				
368+00	1769.78						
	1810.305	**3.81**	**255.5**				
368+04	1850.83						
	2178.81	**14.15**	**1141.9**				
368+18	2506.79						
	2675.12	**8.27**	**819.4**				
368+26	2843.45						
	2928.91	**3.81**	**413.3**				
368+30	3014.37						
	3083.51	**5.52**	**630.4**				
368+36	3152.65						
	3008.535	**9.96**	**1109.8**				
368+46	2864.42						
	2715.09	**4.48**	**450.5**				
368+50	2565.76						
	2285.87	**7.97**	**674.8**				
368+58	2005.98						
	1836.02	**4.54**	**308.7**				
368+63	1666.06						
	1558.23	**4.8**	**277**				
368+67	1450.4						
	1320.625	**9.19**	**449.5**				
368+77	1190.85						
	1042.545	**23.5**	**907.4**				
369+00	894.24						
	898.855	**3.71**	**123.5**				
369+04	903.47						
	822.61	**4.12**	**125.5**				
369+08	741.75						
	570.5	**17.17**	**362.8**				
369+25	399.25						
	218.17	**25**	**202**				
369+50	37.09						
	18.545	**8**	**5.5**				
369+58	0						
	Totals:	237.22	11089.3		Totals:	0	0

-

11089.3 Cu.Yds.

SUBJECT

FILL AREAS

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
388+41	0						
	46.08	**4.81**	**8.2**				
388+46	92.16						
	429.065	**14.1**	**224.1**				
388+60	765.97						
	1278.235	**9.9**	**468.7**				
388+70	1790.5						
	2848.735	**30**	**3165.3**				
389+00	3906.97						
	4479.35	**15.96**	**2647.8**				
389+16	5051.73						
	5128.175	**12**	**2279.2**				
389+28	5204.62						
	5054.915	**10**	**1872.2**				
389+38	4905.21						
	4817.66	**5.04**	**899.3**				
389+43	4730.11						
	4693.03	**7**	**1216.7**				
389+50	4655.95						
	4462.825	**4.96**	**819.8**				
389+55	4269.7						
	4176.055	**0.01**	**1.5**				
389+55	4082.41						
	4181.605	**35.78**	**5541.4**				
389+91	4280.8						
	4143.205	**9.25**	**1419.4**				
390+00	4005.61						
	3398.26	**50**	**6293.1**				
390+50	2790.91						
	2203.89	**50**	**4081.3**				
391+00	1616.87						
	1489.235	**40**	**2206.3**				
391+40	1361.6						
	1317.005	**10**	**487.8**				
391+50	1272.41						
	819.63	**50**	**1517.8**				
392+00	366.85						
	346.605	**13**	**166.9**				
392+13	326.36						
	276.005	**37**	**378.2**				
392+50	225.65						
	190.79	**50**	**353.3**				
393+00	155.93						
	130.675	**50**	**242**				
393+50	105.42						
	84.465	**50**	**156.4**				
394+00	63.51						
	54.92	**20**	**40.7**				
394+20	46.33						
	34.47	**30**	**38.3**				
394+50	22.61						
	18.79	**10**	**7**				
394+60	14.97						
	7.485	**40**	**11.1**				
395+00	0						
	Totals:	658.81	36543.8		Totals:	0	0

36543.8 Cu.Yds.

SUBJECT

FILL AREAS

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
10+00	0			20+00	0		
	0	**30**	**0**		**0**	**30**	**0**
10+30	0			20+30	0		
	0	**20**	**0**		**0**	**20**	**0**
10+50	0			20+50	0		
	0	**37.75**	**0**		**0**	**50**	**0**
10+88	0			21+00	0		
	0	**5**	**0**		**0**	**50**	**0**
10+93	0			21+50	0		
	2.465	**25**	**2.3**		**0**	**50**	**0**
11+18	4.93			22+00	0		
	4.93	**0.01**	**0**		**0**	**50**	**0**
11+18	4.93			22+50	0		
	5.23	**24.99**	**4.8**		**0**	**50**	**0**
11+43	5.53			23+00	0		
	2.765	**8.94**	**0.9**		**0**	**50**	**0**
11+52	0			23+50	0		
	0	**6.06**	**0**		**0**	**50**	**0**
11+58	0			24+00	0		
	0	**10**	**0**		**0**	**50**	**0**
11+68	0			24+50	0		
	0	**19.1**	**0**		**0**	**50**	**0**
11+87	0			25+00	0		
					0	**50**	**0**
				25+50	0		
					0	**50**	**0**
				26+00	0		
					0	**50**	**0**
				26+50	0		
					0	**50**	**0**
30+00	0.89			27+00	0		
	2.34	**11.25**	**1**		**0**	**50**	**0**
30+11	3.79			27+50	0		
	4.235	**12.5**	**2**		**0**	**42.36**	**0**
30+24	4.68			27+92	0		
	4.025	**11.25**	**1.7**				
30+35	3.37						
	5.295	**15**	**2.9**				
30+50	7.22			1+40	0		
	3.61	**50**	**6.7**		**0**	**10**	**0**
31+00	0			1+50	0		
	0	**50**	**0**		**0**	**15**	**0**
31+50	0			1+65	0		
	0.755	**50**	**1.4**				
32+00	1.51						
	9.03	**50**	**16.7**				
32+50	16.55						
	11.265	**50**	**20.9**				
33+00	5.98						
	5.535	**50**	**10.3**				
33+50	5.09						
	5.555	**50**	**10.3**				
34+00	6.02						
	8.195	**50**	**15.2**				
34+50	10.37						
	5.185	**13.45**	**2.6**				
34+63	0						
	Totals:	650.3	99.7		Totals:	817.36	0

-

99.7 Cu.Yds.

SUBJECT GRUBBING IN FILL

SUMMARY SHEET

PAGE NO.	DESCRIPTION	PAGE TOTAL
2	357+00 TO 367+00 ROCK CUT	221.7 cy
3	367+00 TO 367+50 PROSPECT FILL	5.2 cy
4	391+50 TO 395+00 VERONA FILL	203.0 cy
5	1+40, 10+00, 20+00, 30+00 DRIVES	308.5 cy

TOTAL 738.4 cy

say 740 cy

SUBJECT GRUBBING IN FILL

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
357+00	0			366+00	0		
	9.61	**50**	**17.8**		**8.41**	**21.22**	**6.6**
357+50	19.22			366+21	16.82		
	21.155	**42.02**	**32.9**		**18.075**	**28.78**	**19.3**
357+92	23.09			366+50	19.33		
	23.67	**7.98**	**7**		**9.665**	**11.73**	**4.2**
358+00	24.25			366+62	0		
	26.065	**50**	**48.3**		**0**	**38.27**	**0**
358+50	27.88			367+00	0		
	27.36	**50**	**50.7**				
359+00	26.84						
	26.93	**20**	**19.9**				
359+20	27.02						
	13.51	**30**	**15**				
359+50	0						
	0	**40**	**0**				
359+90	0						
	0	**10**	**0**				
360+00	0						
	0	**20**	**0**				
360+20	0						
	0	**17**	**0**				
360+37	0						
	0	**13**	**0**				
360+50	0						
	0	**50**	**0**				
361+00	0						
	0	**40**	**0**				
361+40	0						
	0	**10**	**0**				
361+50	0						
	0	**50**	**0**				
362+00	0						
	0	**50**	**0**				
362+50	0						
	0	**50**	**0**				
363+00	0						
	0	**50**	**0**				
363+50	0						
	0	**20**	**0**				
363+70	0						
	0	**30**	**0**				
364+00	0						
	0	**50**	**0**				
364+50	0						
	0	**50**	**0**				
365+00	0						
	0	**25**	**0**				
365+25	0						
	0	**25**	**0**				
365+50	0						
	0	**10.26**	**0**				
365+60	0						
	0	**19.74**	**0**				
365+80	0						
	0	**20**	**0**				
366+00	0						
	Totals:	900	191.6		Totals:	100	30.1

221.7 Cu.Yds.

SUBJECT

GRUBBING IN FILL

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
367+21	0						
	4.8	**17.56**	**3.1**				
367+38	9.6						
	4.8	**11.66**	**2.1**				
367+50	0						
	Totals:	29.22	5.2		Totals:	0	0

-

5.2 Cu.Yds.

SUBJECT

GRUBBING IN FILL

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
391+50	0						
	17.825	**50**	**33**				
392+00	35.65						
	20.675	**87**	**66.6**				
391+13	5.7						
	6.45	**137**	**32.7**				
392+50	7.2						
	6.935	**50**	**12.8**				
393+00	6.67						
	6.655	**50**	**12.3**				
393+50	6.64						
	9.73	**50**	**18**				
394+00	12.82						
	11.75	**20**	**8.7**				
394+20	10.68						
	9.455	**30**	**10.5**				
394+50	8.23						
	7.8	**10**	**2.9**				
394+60	7.37						
	3.685	**40**	**5.5**				
395+00	0						
	Totals:	524	203		Totals:	0	0

203 Cu.Yds.

SUBJECT

GRUBBING IN FILL

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
10+00	4.55			20+00	5.07		
	2.275	**30**	**2.5**		**2.535**	**30**	**2.8**
10+30	0			20+30	0		
	0	**20**	**0**		**0**	**20**	**0**
10+50	0			20+50	0		
	0.5	**37.75**	**0.7**		**0**	**50**	**0**
10+88	1			21+00	0		
	7.94	**5**	**1.5**		**0**	**50**	**0**
10+93	14.88			21+50	0		
	18.195	**25**	**16.8**		**0**	**50**	**0**
11+18	21.51			22+00	0		
	21.51	**0.01**	**0**		**0**	**50**	**0**
11+18	21.51			22+50	0		
	13.26	**24.99**	**12.3**		**0**	**50**	**0**
11+43	5.01			23+00	0		
	2.505	**8.94**	**0.8**		**0**	**50**	**0**
11+52	0			23+50	0		
	0	**6.06**	**0**		**0**	**50**	**0**
11+58	0			24+00	0		
	0	**10**	**0**		**0**	**50**	**0**
11+68	0			24+50	0		
	0	**19.1**	**0**		**0**	**50**	**0**
11+87	0			25+00	0		
					0	**50**	**0**
				25+50	0		
					0	**50**	**0**
				26+00	0		
					0	**50**	**0**
				26+50	0		
					0	**50**	**0**
30+00	4.58			27+00	0		
	5.98	**11.25**	**2.5**		**0**	**50**	**0**
30+11	7.38			27+50	0		
	10.56	**12.5**	**4.9**		**0**	**42.36**	**0**
30+24	13.74			27+92	0		
	18.175	**11.25**	**7.6**				
30+35	22.61						
	19.415	**15**	**10.8**				
30+50	16.22			1+40	0		
	8.11	**50**	**15**		**0**	**10**	**0**
31+00	0			1+50	0		
	1.6	**50**	**3**		**0**	**15**	**0**
31+50	3.2			1+65	0		
	11.185	**50**	**20.7**				
32+00	19.17						
	20.48	**50**	**37.9**				
32+50	21.79						
	21.855	**50**	**40.5**				
33+00	21.92						
	21.96	**50**	**40.7**				
33+50	22						
	22.015	**50**	**40.8**				
34+00	22.03						
	22.195	**50**	**41.1**				
34+50	22.36						
	11.18	**13.45**	**5.6**				
34+63	0						
	Totals:	650.3	305.7		Totals:	817.36	2.8

-

308.5 Cu.Yds.

SUBJECT UNCLASSIFIED EXCAVATION

SUMMARY SHEET

PAGE NO.	DESCRIPTION	PAGE TOTAL
2	357+00 TO 367+00 ROCK CUT	151838.3 cy
3	367+00 TO 367+50 PROSPECT FILL	237.4 cy
4	394+00 TO 395+00 VERONA ROCK FILL	439.3 cy
5	1+40, 10+00, 20+00, 30+00 DRIVES	4918.2 cy
6	DRAINAGE - PAGE 1	38.1 cy
7	DRAINAGE - PAGE 2	42.1 cy
8	DRAINAGE - PAGE 3	33.3 cy

TOTAL ***157546.7*** *cy*

say 158,000 cy

SUBJECT UNCLASSIFIED EXCAVATION

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
357+00	0			366+00	2111.25		
	13.26	**50**	**24.6**		**1571.76**	**21.22**	**1235.3**
357+50	26.52			366+21	1032.27		
	40.205	**42.02**	**62.6**		**533.605**	**28.78**	**568.8**
357+92	53.89			366+50	34.94		
	56.535	**7.98**	**16.7**		**92.29**	**11.73**	**40.1**
358+00	59.18			366+62	149.64		
	97.22	**50**	**180**		**150.6**	**38.27**	**213.5**
358+50	135.26			367+00	151.56		
	269.495	**50**	**499.1**				
359+00	403.73						
	543.525	**20**	**402.6**				
359+20	683.32						
	1015.71	**30**	**1128.6**				
359+50	1348.1						
	1767.2	**40**	**2618.1**				
359+90	2186.3						
	2255.895	**10**	**835.5**				
360+00	2325.49						
	2488.42	**20**	**1843.3**				
360+20	2651.35						
	2912.115	**17**	**1833.6**				
360+37	3172.88						
	3235.52	**13**	**1557.8**				
360+50	3298.16						
	3849.45	**50**	**7128.6**				
361+00	4400.74						
	4924.725	**40**	**7295.9**				
361+40	5448.71						
	5566.755	**10**	**2061.8**				
361+50	5684.8						
	6268.99	**50**	**11609.2**				
362+00	6853.18						
	7307.17	**50**	**13531.8**				
362+50	7761.16						
	8193.45	**50**	**15173.1**				
363+00	8625.74						
	8892.575	**50**	**16467.7**				
363+50	9159.41						
	9166.735	**20**	**6790.2**				
363+70	9174.06						
	9082.11	**30**	**10091.2**				
364+00	8990.16						
	8842.59	**50**	**16375.2**				
364+50	8695.02						
	7834.745	**50**	**14508.8**				
365+00	6974.47						
	6490.9	**25**	**6010.1**				
365+25	6007.33						
	5503.765	**25**	**5096.1**				
365+50	5000.2						
	4732.495	**10.26**	**1798.3**				
365+60	4464.79						
	3880.705	**19.74**	**2837.2**				
365+80	3296.62						
	2703.935	**20**	**2002.9**				
366+00	2111.25						
	Totals:	900	149780.6		Totals:	100	2057.7

151838.3 Cu.Yds.

UNCLASSIFIED EXCAVATION

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
367+00	151.56						
	193.085	**20.78**	**148.6**				
367+21	234.61						
	128.81	**17.56**	**83.8**				
367+38	23.01						
	11.505	**11.66**	**5**				
367+50	0						
	Totals:	50	237.4		Totals:	0	0

237.4 Cu.Yds.

UNCLASSIFIED EXCAVATION

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
394+00	0						
	81.515	**20**	**60.4**				
394+20	163.03						
	165.095	**30**	**183.4**				
394+50	167.16						
	172.43	**10**	**63.9**				
394+60	177.7						
	88.85	**40**	**131.6**				
395+00	0						
	Totals:	100	439.3		Totals:	0	0

439.3 Cu.Yds.

UNCLASSIFIED EXCAVATION

Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)	Station	Area (S.F.)	Length (Ft)	Volume (C.Y.)
10+00	64.04			20+00	62.78		
	62.11	**30**	**69**		**82.505**	**30**	**91.7**
10+30	60.18			20+30	102.23		
	57.185	**20**	**42.4**		**120.68**	**20**	**89.4**
10+50	54.19			20+50	139.13		
	42.335	**37.75**	**59.2**		**157.955**	**50**	**292.5**
10+88	30.48			21+00	176.78		
	63.585	**5**	**11.8**		**191.83**	**50**	**355.2**
10+93	96.69			21+50	206.88		
	79.355	**25**	**73.5**		**204.01**	**50**	**377.8**
11+18	62.02			22+00	201.14		
	62.02	**0.01**	**0**		**247.595**	**50**	**458.5**
11+18	62.02			22+50	294.05		
	32.355	**24.99**	**29.9**		**302.01**	**50**	**559.3**
11+43	2.69			23+00	309.97		
	1.345	**8.94**	**0.4**		**246.02**	**50**	**455.6**
11+52	0			23+50	182.07		
	0	**6.06**	**0**		**139.535**	**50**	**258.4**
11+58	0			24+00	97		
	0	**10**	**0**		**113.455**	**50**	**210.1**
11+68	0			24+50	129.91		
	0	**19.1**	**0**		**99.565**	**50**	**184.4**
11+87	0			25+00	69.22		
					85.87	**50**	**159**
				25+50	102.52		
					94.645	**50**	**175.3**
				26+00	86.77		
					60.42	**50**	**111.9**
				26+50	34.07		
					32.265	**50**	**59.8**
30+00	11.03			27+00	30.46		
	7.055	**11.25**	**2.9**		**81.65**	**50**	**151.2**
30+11	3.08			27+50	83.76		
	5.705	**12.5**	**2.6**		**54.495**	**42.36**	**85.5**
30+24	8.33			27+92	25.23		
	9.535	**11.25**	**4**				
30+35	10.74						
	6.915	**15**	**3.8**				
30+50	3.09			1+40	162.75		
	54.175	**50**	**100.3**		**154.37**	**10**	**57.2**
31+00	105.26			1+50	145.99		
	72.64	**50**	**134.5**		**157.665**	**15**	**87.6**
31+50	40.02			1+65	169.34		
	30.835	**50**	**57.1**				
32+00	21.65						
	11.43	**50**	**21.2**				
32+50	1.21						
	4.59	**50**	**8.5**				
33+00	7.97						
	7.79	**50**	**14.4**				
33+50	7.61						
	9.525	**50**	**17.6**				
34+00	11.44						
	18.95	**50**	**35.1**				
34+50	26.46						
	19.27	**13.45**	**9.6**				
34+63	12.08						
	Totals:	650.3	697.8		Totals:	817.36	4220.4

4918.2 Cu.Yds.