



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

March 12, 2004
Subject: Salem TWP
Project No. BR-8973(00)X
PIN 8973.00
Bid Amendment No. 2

Dear Sir/Ms.:

Please make the following changes to your bid package:

Delete the "Schedule of Items" dated 040219 seven pages total, and replace with the attached "Schedule of Items" dated 040312 seven pages total.

Delete the first page of the "Contract Agreement, Offer & Award" with a completion date of **October 9, 2004** (both copies) two pages total, and replace with the attached "Contract Agreement, Offer & Award" with a completion date of **June 1, 2005** (both copies) two pages total.

Delete "Special Provision Section 107 Prosecution and Progress (Contract Time)" dated October 28, 2003 one page and replace with the attached "Special Provision Section 107 Prosecution and Progress (Contract Time)" dated March 12, 2004 one page.

Delete "Special Provision Section 502 Structural Concrete (QC/QA Acceptance Methods)" dated September 29, 2003 page 1 of 1 and replace with the attached "Special Provision Section 502 Structural Concrete (QC/QA Acceptance Methods)" dated March 10, 2004 page 1 of 1.

Please make the following changes to the Plan Sheets:

On page 2 of 29 entitled "Estimated Quantities" add the following to the Estimated Quantities list:

403.211, Hot Mix Asphalt (shimming) 100 Megagrams
409.15, Bituminous Tack Coat, Applied 1000 Liters



PRINTED ON RECYCLED PAPER

On page 2 of 29 entitled "Estimated Quantities" add the following note to the General Construction Notes:

20. Existing substructure units are to be removed to 300 mm below finished grade.

Make these changes in pen and ink.

Consider these changes prior to submitting your bid on March 17, 2004.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford", written in a cursive style.

Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008973.00

PROJECT(S): BR-8973(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE DOLLARS CTS	BID AMOUNT DOLLARS CTS
SECTION 0001 BRIDGE ITEMS				
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP	
0020	203.20 COMMON EXCAVATION	2090.000		
		M3		
0030	203.24 COMMON BORROW	450.000		
		M3		
0040	203.25 GRANULAR BORROW	205.000		
		M3		
0050	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	95.000		
		M3		
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2150.000		
		M3		
0070	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	320.000		
		MG		
0080	403.208 HOT MIX ASPHALT 12.5 MM, SURFACE	225.000		
		MG		
0090	403.210 HOT MIX ASPHALT 9.5 MM NOMINAL MAX SIZE	60.000		
		MG		
0100	403.211 HOT MIX ASPHALT (SHIM)	100.000		
		MG		

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008973.00

PROJECT(S): BR-8973(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT APPLIED	1000.000 L				
0120	501.231 DYNAMIC LOADING TEST	1.000 EA				
0130	501.50 STEEL H-BEAM PILES 132 KG/M, DELIVERED	270.000 M				
0140	501.501 STEEL H-BEAM PILES 132 KG/M, IN PLACE	270.000 M				
0150	501.90 PILE TIPS	8.000 EA				
0160	501.91 PILE SPLICES	4.000 EA				
0170	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0180	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0190	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0200	502.45 STRUCTURAL CONCRETE APPROACH SLABS	16.000 M3				
0210	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008973.00

PROJECT(S): BR-8973(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	4200.000 KG				
0230	503.13 REINFORCING STEEL, PLACING	4200.000 KG				
0240	503.17 MECHANICAL WELDED SPLICE	64.000 EA				
0250	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0260	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0270	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0280	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0290	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0300	511.07 COFFERDAM: ABUTMENT NO. 1	LUMP	LUMP			
0310	511.07 COFFERDAM: ABUTMENT NO. 2	LUMP	LUMP			
0320	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008973.00

PROJECT(S): BR-8973(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	120.000 M2				
0340	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0350	603.17 450 MM CULVERT PIPE OPTION I	9.000 M				
0360	605.09 150 MM UNDERDRAIN TYPE B	100.000 M				
0370	605.11 300 MM UNDERDRAIN TYPE C	60.000 M				
0380	606.17 GUARDRAIL TYPE 3B - SINGLE RAIL	31.000 M				
0390	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0400	606.35 GUARDRAIL DELINEATOR POST	6.000 EA				
0410	606.76 MODIFIED ECCENTRIC LOADER TERMINAL	4.000 EA				
0420	610.08 PLAIN RIPRAP	360.000 M3				
0430	610.18 STONE DITCH PROTECTION	40.000 M3				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008973.00

PROJECT(S): BR-8973(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	613.319 EROSION CONTROL BLANKET	50.000 M2				
0450	615.0701 LOAM - PLAN QUANTITY	90.000 M3				
0460	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	8.000 UN				
0470	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	10.000 UN				
0480	619.1201 MULCH - PLAN QUANTITY	18.000 UN				
0490	619.1401 EROSION CONTROL MIX	180.000 M3				
0500	621.195 MEDIUM DECIDUOUS TREE (45 MM - 50 MM CALIPER) GROUP A	6.000 EA				
0510	621.273 LARGE DECIDUOUS TREE (50 MM - 65 MM CALIPER) GROUP A	3.000 EA				
0520	621.546 DECIDUOUS SHRUBS (600 MM - 900 MM) GROUP A	18.000 EA				
0530	621.552 DECIDUOUS SHRUBS (900 MM - 1200 MM) GROUP A	12.000 EA				
0540	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	870.000 M				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008973.00

PROJECT(S): BR-8973(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0560	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0570	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0580	637.071 DUST CONTROL	LUMP	LUMP			
0590	639.19 FIELD OFFICE TYPE B	1.000 EA				
0600	652.312 TYPE III BARRICADE	6.000 EA				
0610	652.33 DRUM	10.000 EA				
0620	652.34 CONE	20.000 EA				
0630	652.35 CONSTRUCTION SIGNS	50.000 M2				
0640	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0650	652.38 FLAGGER	160.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008973.00

PROJECT(S): BR-8973(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0670	659.101 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (Department), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and

_____ a corporation or other legal entity organized under the laws of the State of Maine, with its principal place of business located at _____

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, PIN No. **8973.00**, for the **BRIDGE REPLACEMENT** in **SALEM TWP**, County of **FRANKLIN**, Maine. The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before **June 1, 2005**. Further, the Department may deduct from moneys otherwise due the Contractor, not as a penalty, but as Liquidated Damages in accordance with Sections 107.7 and 107.8 of the State of Maine Department of Transportation Standard Specifications, Revision of December 2002.

C. Price.

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (Department), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and

_____ a corporation or other legal entity organized under the laws of the State of Maine, with its principal place of business located at _____

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, PIN No. **8973.00**, for the **BRIDGE REPLACEMENT** in **SALEM TWP**, County of **FRANKLIN**, Maine. The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before **June 1, 2005**. Further, the Department may deduct from moneys otherwise due the Contractor, not as a penalty, but as Liquidated Damages in accordance with Sections 107.7 and 107.8 of the State of Maine Department of Transportation Standard Specifications, Revision of December 2002.

C. Price.

SPECIAL PROVISION
SECTION 107
PROSECUTION AND PROGRESS
(Contract Time)

The Base course of pavement must be complete on both lanes of the bridge and approaches on or before November 15th, 2004. Should the contractor opt to pave the surface course in the spring the contractor shall construct the base course to match the surface at each end and shall ramp the thickness of it down to its design thickness over a length of 10 meters, and the contractor will be required to mill that 10 meter length down to allow for the proper thickness of surface course to be placed in the spring, and base course should be paved to the berm line behind the guardrail. When final paving is done in the spring the surface course should be carried only to the face of rail in guardrail sections. This work shall be considered incidental to related paving items. No additional payment shall be made for milling. The contractor will be assessed supplemental liquidated damages of \$2500.00 per day for each day beyond the base course paving completion date for which the base course pavement is not complete. These liquidated damages will be in addition to those specified in Standard Specification section 107.7.2

Guardrail and bridge rail must be installed prior to December 1st, 2004. The contractor will be assessed supplemental liquidated damages of \$2500.00 per day for each day beyond the guardrail and bridge rail completion date for which the guardrail and bridge rail is not complete. These liquidated damages will be in addition to those specified in Standard Specification section 107.7.2

The specified contract completion date is June 1st, 2005.

SPECIAL PROVISION
SECTION 502
STRUCTURAL CONCRETE
(QC/QA Acceptance Methods)

CLASS OF CONCRETE	ITEM NUMBER	DESCRIPTION	P	METHOD
A	502.26	Struc. Conc. Superstructure Slab (Class A)	\$680	A
LP	502.49	Structural Concrete Curbs & Sidewalks		B
A	502.219	Structural Concrete Abutments and Retaining walls	\$680	A
A	502.45	Structural Concrete Approach Slab		B

P values listed above reflect the price per cubic meter for all pay adjustment purposes.