



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLI
COMMISSIONER

June 24, 2003
Subject: Guilford & Dover-Foxcroft
Project No. STP-9200(20)X;
STP-1060(200)X
PIN 9200.20 & 10602.00
Bid Amendment No. 1

Dear Sir/Ms.:

Please make the following change to your bid package.

1) On the cover of the contract book, under Project No., delete STP-1050(200) X, and replace with STP-1060(200) X.

Make this change in pen and ink.

2) Delete page 4 of the "Schedule of Items" dated 030612 and replace with the new attached page 4 of the "Schedule of Items" dated 030623.

3) Delete page 1 of 1 of the "Special Provision, Section 309, entitled Full Depth Recycled Pavement (with foamed asphalt), Mix Design" dated 6/13/03 and replace with the new attached page 1 of 1 "Special Provision, Section 309, Full Depth Recycled Pavement (with foamed asphalt), Mix Design" dated 6/23/03.

Consider these changes prior to submitting your bid on July 2, 2003.

Sincerely,

Bruce R. Carter
Contracts Engineer



PRINTED ON RECYCLED PAPER

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 4

SCHEDULE OF ITEMS

DATE: 030623

REVISED:

CONTRACT ID: 009200.20

PROJECT(S): STP-9200(20)X
STP-1060(200)X

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE | | BID AMOUNT | |
|------------|---|----------------------------------|------------|-----|------------|-----|
| | | | DOLLARS | CTS | DOLLARS | CTS |
| 0320 | 606.754 WIDEN SHOULDER FOR 350 END TREATMENT | 3.000 EA | | | | |
| 0330 | 606.79 GUARDRAIL 350 FLARED TERMINAL | 3.000 EA | | | | |
| 0340 | 609.31 CURB TYPE 3 | 1023.000 M | | | | |
| 0350 | 609.441 CURBING REMOVED AND STACKED | 182.000 M | | | | |
| 0360 | 610.08 PLAIN RIPRAP | 45.000 M3 | | | | |
| 0370 | 610.16 HEAVY RIPRAP | 20.000 M3 | | | | |
| 0380 | 610.18 STONE DITCH PROTECTION | 110.000 M3 | | | | |
| 0390 | 613.319 EROSION CONTROL BLANKET | 2720.000 M2 | | | | |
| 0400 | 615.0701 LOAM - PLAN QUANTITY | 736.000 M3 | | | | |
| 0410 | 618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY | 75.000 UN | | | | |

SPECIAL PROVISION
SECTION 309
FULL DEPTH RECYCLED PAVEMENT
(with foamed asphalt)

Mix Design

The Full Depth Recycled Asphalt Pavement on this project will be treated with the following material proportions:

| | |
|--|-------|
| PG 64-28 asphalt binder | 2.5 % |
| Water needed to ensure proper foaming | 3 % |
| Portland cement (Type I or II) | 1.5 % |
| 1.5 inches of crusher dust applied during initial reclaiming | |

The optimum moisture content for compaction shall be determined by the Department using samples obtained from the pulverized material prior to addition of the foamed asphalt, by means of AASHTO T 180, Method D.

The Department will compensate the Contractor in accordance with Section 109.7.5 - Force Account, paragraph B. Materials, if the Departments mix design requirements for Full Depth Recycled Pavement with Foam Asphalt exceeds the 2.5 percent for added asphalt, or the 1.5 percent for added Portland cement. Adjustments in water content exceeding the initial targets shall not be paid for directly, but shall be incidental to Item 309.36.