

ADDENDUM NO. 3

State of Maine Cultural Building Asbestos Abatement & Mechanical Upgrades
Phase 2: Mechanical Upgrades & Museum Abatement
230 State Street
Augusta, ME

February 17, 2022

From: Wood
Environment & Infrastructure Solutions
511 Congress Street
Portland, Maine 04101

To: Prospective Bidders

This Addendum forms a part of the Contract Documents and modifies the original bidding documents dated January 7, 2022, as noted below. Bidder shall acknowledge receipt of this Addendum in the space provided on the Contractor Bid Form, failure to do so may subject the bidder to disqualification.

PERTAINING TO REQUEST FOR INFORMATION QUESTIONS

Responses to RFIs received from 2/1 through 2/10 are included with this addendum.

PERTAINING TO SPECIFICATIONS

1. Section 00 11 13 Notice to Contractors for Email
 - a) DELETE section in its entirety, ADD the Section 00 11 13 Notice to Contractors for Email attached to this addendum.
2. Section 011000 Summary.
 - a) DELETE section in its entirety, ADD the Section 011000 Summary attached to this addendum.
3. Section 017900 Demonstration and Training
 - a) DELETE section in its entirety, ADD the Section 017900 Demonstration and Training attached to this addendum.
4. Section 019113 General Commissioning Requirements.
 - a) DELETE section in its entirety, ADD the Section 019113 General Commissioning Requirements attached to this addendum.
5. Section 024119 Selective Demolition
 - a) DELETE section in its entirety, ADD the Section 024119 Selective Demolition attached to this addendum.

6. Section 230800 Commissioning of HVAC.

- a) DELETE section in its entirety, ADD the Section 230800 Commissioning of HVAC attached to this addendum.

PERTAINING TO THE DRAWINGS

DELETE sheets listed below and ADD drawings attached to this addendum.

1. Drawing GI004B:
 - a) Added Bid Alternate #5 to deduct the scope for abatement and associated demolition of the 4th floor Mechanical Room 416 in its entirety.
2. Drawing GC100B:
 - a) Revised contractor access dates
3. Drawing GC101B:
 - a) Revised contractor access dates
4. Drawing GC102B:
 - a) Revised contractor access dates
5. Drawing GC103B:
 - a) Revised contractor access dates
6. Drawing GC104B:
 - a) Revised contractor access dates
7. Drawing GC105B:
 - a) Revised contractor access dates
8. Drawing AD105:
 - a) Removed rigid insulation at loading dock roof overhang (New Keynote 47).
9. Drawing AD109:
 - a) Removed existing soffit at roof overhang.
10. Drawing AE122:
 - a) Revised Diffuser layout per mechanical revisions
11. Drawing AE124:
 - a) Revised Diffuser layout per mechanical revisions
12. Drawing AE129:
 - a) Added new soffit at roof overhang
13. Drawing AE202:
 - a) Revised Elevation
14. Drawing AE203:
 - a) Revised Elevation
15. Drawing AE301:
 - a) Revised overhang details
16. Drawing AE312:
 - a) Change spray-applied fireproofing to rigid board fireproofing

17. Drawing AE512:
 - a) Deleted detail
 - b) Revised elevations
18. Drawing AE513:
 - a) Deleted details
19. Drawing AE621:
 - a) Added window type
20. Drawing AK105:
 - a) Changed rigid board fireproofing to spray-applied fireproofing at loading dock overhang.
21. Drawing AK107:
 - a) Changed rigid board fireproofing to spray-applied fireproofing at exterior soffit.
22. Drawing M-001:
 - a) Changes to Piping Symbols.
 - b) Added General Note.
23. Drawing MH101:
 - a) Corrected Slot Diffuser Tags
24. Drawing MH102:
 - a) Added note to Roof Plan clarifying construction of exterior ductwork.
 - b) Revised diffusers in 322, 323.
25. Drawing MH104:
 - a) Revised diffusers in Revised diffusers in 330, 333, 336, 340, 341, 342.
 - b) Reconfigured ductwork in 334.
26. Drawing MH105:
 - a) Clarified location of low mounted R-5 gills in Cars & Boats, 140.
27. Drawing MH-106:
 - a) Ductwork SA main size increased at vertical chase next to Stair 7.
28. Drawing MH-107:
 - a) Ductwork SA mains sizes increased at vertical chase next to Stair 7.
 - b) Tagged Exhaust duct riser.
29. Drawing MH-108:
 - a) Ductwork SA mains sizes increased at vertical chase next to Stair 7 and into Mech Room 416.
 - b) Fire-smoke dampers shown on all duct penetrations into vertical chase next to Stair 7.
 - c) Diffuser tags updated in Hall 413, Men 415, Women 414.
30. Drawing M-302:
 - a) Made changes to Section: "A1 AHU-1,2,3 SECTION"
 - b) Made changes to Section: "B1 AHU-1,3 SECTION"
31. Drawing M-401:
 - a) Made changes to Part Plan: "D2 MUSEUM – FOURTH LEVEL MECHANICAL 416 LOWER DUCTWORK PART PLAN"
 - b) Added Refrigerant Monitor and Thermostats in Part Plan: "MUSEUM FOURTH LEVEL MECHANICAL 416 LOWER PIPING PART PLAN".
32. Drawing M-402:

- a) Increased Supply Air Duct sizes and modified AHU connections in Part Plan: “D2 MUSEUM – FOURTH LEVEL MECHANICAL 416 UPPER DUCTWORK PART PLAN”
33. Drawing M-403:
- a) Modified HWS and HWR piping sizes in Part Plan: “D4 MECHANICAL ROOM B5 PIPING PART PLAN”
 - b) Added Refrigerant Monitor and Thermostat in Part Plan: “A4 ARCHIVE-THIRD LEVEL MECHANICAL 348 PIPING PART PLAN”.
34. Drawing M-404:
- a) Added Refrigerant Monitor and Thermostat in Part Plan: “A4 LIBRARY-THIRD LEVEL MECHANICAL 315 PIPING PART PLAN”.
35. Drawing M-601:
- a) Revised Supply Air Diffuser Schedule.
 - b) Revised Return, Transfer & Exhaust Grille Schedule.
36. Drawing M-602:
- a) Revised Air Separator Schedule.
37. Drawing M-603:
- a) Added MERV13 to FCU-05-05 to Fan Coil Unit Schedule.
38. Drawing M-604:
- a) Revised Pump Schedule operating points.
 - b) Revised Heat Exchanger Schedule operating points.
 - c) Revised Expansion Tank Schedule design points.
39. Drawing M-605:
- a) Added Note 12 to Air Handling Unit Schedule.
40. Drawing M-706:
- a) Added Duct Pressure Sensor to Control Diagram: “E1 ERV-1,2,3 CONTROL DIAGRAM”
 - b) Added Duct Pressure Sensor to Control Diagram: “D1 ERV-4 CONTROL DIAGRAM”
 - c) Added Sensors to Control Diagram “A1 AHU-4 CONTROL DIAGRAM”
 - d) Made changes to Control Diagram “D4 AHU-3 CONTROL DIAGRAM”
 - e) Made changes to Control Diagram “A4 AHU-1, 2 CONTROL DIAGRAM”
41. Drawing M-707:
- a) Revised Sequence of Operation
42. Drawing M-708:
- a) Revised Sequence of Operation
43. Drawing M-709
- a) Revised Sequence of Operation

END OF ADDENDUM NO. 3

State of Maine Cultural Building Asbestos Abatement & Mechanical Upgrades
Phase 2: Mechanical Upgrades & Museum Abatement
Pre-Bid Questions

Question No.	Discipline	Question	Date Received	Response
18	Architectural	It looks like the spec 088000 - Glazing sections 3.8, 3.9, 3.10 has many glass types listed but only partially described. Glass types are not outlined anywhere within the plans other than vision glass or "opaque" glass/spandrel. Will this be clarified?	2/1/2022	Glass Types are to be 1 inch insulated glazing – clear and ¼" black spandrel glass. Tempered as per code requirements
19	Architectural	Will a stand-alone mock-up be required for this project regarding storefront and curtainwall as the spec lays out? (see 084413-1.6-A, 084113-1.6-A)	2/1/2022	the intent of the mock up was to build one in place as part of the work , to then be the standard
20	Architectural	Will a laboratory mock-up and test report for storefront (084113) and curtainwall (084431) truly be required? These systems have been generally tested in labs and have reports readily available as an alternative.	2/1/2022	Manufacturers tests reports are satisfactory
21	General	When will the selected GC be able to start work? I had March/April in my notes for a 15 month total duration to complete by the stated June 2023, but would like to confirm.	2/2/2022	Refer to Specification sections and Drawings issued with addendum No. 3 for clarification.
22	Structural	We are having difficulty finding a AISC certified steel fabricator to bid the work. We are asking that the AISC certification requirement be	2/3/2022	AISC Certification requirements are to remain.
23	Architectural	What are the opening tag, door material, frame material, or frame type for the first unknown opening on door schedule?	2/3/2022	Door schedule has been revised and was issued with addendum No. 2
24	Architectural	What are the locations of openings 230, 240, 244, 245, 246, 247, 248, and 260 on the floor plans?	2/3/2022	Door schedule has been revised and was issued with addendum No. 2
25	Architectural	What do door types 79, 152, G, H, J, and K indicate on openings 126b, 137a, 137b, 137c, 137d, 233, 234a, 234b, 245, 246, 247, 348a, 356, and 434?	2/3/2022	Door schedule has been revised and was issued with addendum No. 2
26	Architectural	What is the door material for openings 126b, 245, 246, 247, 248, 260, 356, and 434?	2/3/2022	Door schedule has been revised and was issued with addendum No. 2
27	Architectural	What are the frame material and frame types for openings 126a, 126b, 137a, 137b, 137c, 137d, 230, 240, 245, 246, 247, 248, 260, 315, 348b, 248c, 356, and 434?	2/3/2022	Door schedule has been revised and was issued with addendum No. 2
28	Architectural	Door Schedule list both HM and STL doors. Are they the same? Only types A and B are drawn Other type are listed on the schedule. Seven doors do not list a type. Fire rating listed as 1 or 2. Is that hours?	2/4/2022	Door schedule has been revised and was issued with addendum No. 2

Question No.	Discipline	Question	Date Received	Response
29	Architectural	Item 32 on the façade elevations calls for patching and repairing of the cracked/damaged cementitious coating and paint finish. Is there an assumed quantity of repair that has been dedicated to this item? I know the actual stucco repair will be a small portion of the actual SF, however do we assume we be re-coating the entire areas?	2/10/2022	Please include a 2500 sqft allowance for the patching and repairing of cementitious coating. Additionally, provide a unit price for any additional area needing repair. Repaired areas to be re-coated to the extent of the nearest adjacent edge or reveal, to be verified in the field with the Architect.
30	General	What are the chances of getting into the building one day next week for an additional site visit? Maybe Thursday the 17th?	2/10/2022	All site visits have to be scheduled with Jill Instasi of Maine's Bureau of General Services. Please coordinate the desired time with Jill so that Museum staff can provide an escort.

revised 27 April 2021

00 11 13
Notice to Contractors

Cultural Building Asbestos Abatement & Mechanical Upgrades - Phase 2: Mechanical Upgrades & Museum Abatement
PT 3108

The Phase 2 project work consists of asbestos abatement throughout selected areas of the Cultural Building in Augusta, ME, including abatement of asbestos containing materials (ACM) and contaminated materials; and limited removal of the mechanical system components, electrical and fire alarm fixtures and devices, and architectural features to support the abatement work. The work consists of partial renovatoin throughout the entire building, including areas previously abated under separate contract. Upgrades include replacement of the mechanical system, electrical and architectural upgrades necessitated by the abatement and mechanical work, minor structural repairs, and other Work included in the Contract Documents. The work also includes protection of identified exhibits within the Museum galleries to protect the collections and facilitate the abatement and construction activities.

The cost of the work is approximately \$ 9,200,000. The work to be performed under this contract shall be completed on or before the Final Completion date of **15 November 2023**.

1. Submit bids on a completed Contractor Bid Form, plus bid security when required, all scanned and included as an attachment to an email with the subject line marked "**Bid for Cultural Building Asbestos Abatement & Mechanical Upgrades - Phase 2: Mechanical Upgrades and Museum Abatement**" and addressed to the Bid Administrator at: BGS.Architect@Maine.gov, so as to be received no later than **2:00:00 p.m. on February 24, 2022**.

Bid submissions will be opened and read aloud at the time and date noted above at the Bureau of General Services office, accessible as a video conference call. Those who wish to participate in the call must submit a request for access to Jill.Instasi@Maine.gov.

Any bid received after the noted time will not be considered a valid bid and will remain unopened. Any bid submitted by any other means will not be considered a valid bid. The Bid Administrator may require the Bidder to surrender a valid paper copy of the bid form or the bid security document in certain circumstances.

Questions on the bid opening process shall be addressed to the Bid Administrator: Jill Instasi, Bureau of General Services, 77 State House Station, Augusta, Maine 04333-0077, Jill.Instasi@Maine.gov.

2. The bid shall be submitted on the Contractor Bid Form (section 00 41 13) provided in the Bid Documents. The Owner reserves the right to accept or reject any or all bids as may best serve the interest of the Owner.
3. Bid security *is required* on this project.
If noted above as required, the Bidder shall include a satisfactory Bid Bond (section 00 43 13) or a certified or cashier's check for 5% of the bid amount with the completed bid form submitted to the Owner. The Bid Bond form is available on the BGS website.
4. Performance and Payment Bonds *are required* on this project.
If noted above as required, the selected Contractor shall furnish a 100% contract Performance Bond (section 00 61 13.13) and a 100% contract Payment Bond (section 00 61 13.16) in the contract amount to cover the execution of the Work. Bond forms are available on the BGS website.

00 11 13
Notice to Contractors

5. Filed Sub-bids *are not required* on this project.
6. There *are no* Pre-qualified General Contractors on this project.
If Pre-qualified General Contractors are identified for this project, the name of each company, with their city and state, are listed below.
7. An on-site pre-bid conference *will* be conducted for this project.
If a pre-bid conference is scheduled, it is *mandatory* for General Contractors and optional for Subcontractors and suppliers. Contractors who arrive late or leave early for a mandatory meeting may be prohibited from participating in this meeting and bidding. *Pre-bid conference #1 will be conducted Wednesday, January 19, 2022, at 10:00 a.m. at the Cultural Building, 230 State Street, Augusta, ME 04333. Pre-bid conference #2 will be conducted Tuesday, February 1, 2022, at 9:00 a.m. at the Cultural Building. Those in attendance for conference #1 are not required to attend conference #2. Requests for Information shall be submitted by email to lorrie.picard@woodplc.com by 2:00 PM on February 10, 2022.*
8. Bid Documents - full sets only - will be available on or about *January 14, 2022* and may be obtained *electronically or as printed sets purchased at cost* from:
Xpress Copy Plan Room
17 Westfield Street
Portland, ME 04101
(207) 775-2444
<https://www.xpressplanroom.com>
9. Bid Documents may be examined at:

<i>AGC Maine</i>	<i>Construction Summary</i>
<i>188 Whitten Road</i>	<i>734 Chestnut Street</i>
<i>Augusta, ME 04330</i>	<i>Manchester, NH 03104</i>
<i>Phone 207-622-4741 Fax 207-622-1625</i>	<i>Phone 603-627-8856 Fax 603-627-4524</i>

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

- 1. Project information.
- 2. Work covered by Contract Documents.
- 3. Construction milestones.
- 4. Work performed by Owner.
- 5. Work under Owner's separate contracts.
- 6. Owner-furnished/Contractor-installed (OFCI) products.
- 7. Owner-furnished/Owner-installed (OFOI) products.
- 8. Contractor's use of site and premises.
- 9. Coordination with occupants.
- 10. Work restrictions.
- 11. Specification and Drawing conventions.
- 12. Miscellaneous provisions.
- ~~12.~~13. Commissioning.

- B. Related Requirements:

- 1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.
- 2. Section 017300 "Execution" for coordination of Owner-installed products.

1.3 PROJECT INFORMATION

- A. Project Identification: Cultural Building Asbestos Abatement and Mechanical Upgrades – Phase 2: Mechanical Upgrades & Museum Abatement.

- 1. Project Location: 230 State Street, Augusta, Maine.

- B. Owner: State of Maine, Bureau of General Services.

- 1. Owner's Representative: Jill Instasi, State of Maine Bureau of General Services, Sewall Street, 77 SHS, 4th Floor, Augusta, ME 04333 Phone: (207) 624-7341 jill.intasi@maine.gov.
- 2. BGS Project No. PT 3108.

- C. Architect: Wood Environment & Infrastructure Solutions, Inc., 511 Congress Street, Suite 200, Portland, ME 04101 Phone: (207) 775-5401, Fax: (207) 772-4762.
- D. Web-Based Project Software: Contractor, may, at their discretion, use project software for purposes of managing communication and documents during the construction stage.

1.4 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of Project is defined by the Contract Documents and includes, but is not limited to, the following:
 - 1. The Cultural Building houses the State of Maine's three cultural agencies, Maine State Archives, Maine State Museum, and Maine State Library. The facility provides space for storage, maintenance, display, and public access to a large collection of artifacts which tell the story of the State of Maine, as well as administrative office space. The design and construction of upgrades to the Cultural Building are intended to protect occupants and visitors from exposure to hazardous materials, to improve the safety of the collections with appropriate climate control, and it improve the efficiency and functionality of the mechanical systems.

The Cultural Building is located at 230 State Street, Augusta, Maine. Construction of the five-story building, which is approximately 157,200 total square feet (SF), was completed in 1971. The third floor atrium was added in 1987. Other than minor renovation in administrative offices and building out or changing of the Museum exhibits, minimal renovation has occurred since the original construction.

The facility is built into a sloped site such that the third floor main entrance at the north atrium is located at grade, with the side sloping down to the south elevation of the Museum and first floor at grade. Exterior walls consist of cast-in-place concrete, precast concrete panels, concrete masonry infill, and glass curtain walls. The exterior is finished with exterior stone cladding in places. The structure is comprised of a steel frame supporting concrete waffle deck and steel form deck. The interior spaces are open to structure in storage areas and have a variety of ceiling systems suspended in the administrative spaces and Museum exhibit galleries.

The project will provide for partial renovation to the Cultural building including abatement of asbestos containing materials, replacement of the mechanical system, electrical and architectural upgrades necessitated by the abatement and mechanical work, and minor structural repairs. The project also includes protection of identified exhibits within the Museum galleries to protect the collections and facilitate the abatement and construction activities.

The Museum exhibits remaining in the Cultural Building during construction contain highly sensitive historic collections and require special care while navigating the galleries before protection systems are installed; during construction of protection systems; and for the duration of abatement and construction activities. An exhibit protection work plan, a preinstallation meeting, and integrated mockups are required by other Division 01 Specification Sections prior to construction of exhibit protection. During abatement and construction activities, daily reports are required with photographic documentation through vision panels in protection enclosures. Following abatement activities and receipt

of clearance for each area containing exhibits, exhibit protection enclosures will be unsealed to allow the Owner to enter the enclosures and check on the protected exhibits prior to resealing the enclosures for the duration of remaining construction activities.

- B. Type of Contract: Project will be constructed utilizing a single prime contract.

1.5 CONSTRUCTION MILESTONES

- A. Construct the Work in accordance with the following schedule:

1. Construction Phase:

- a. Commencement of Construction: Work on this phase shall commence within 7 days after Notice to Proceed.
- b. Museum Exhibit Protection Punchlist: Following completion of constructing exhibit protection and prior to commencement of abatement activities.
- c. Museum Abatement Punchlist: Following completion of abatement activities for a given area and receipt of clearance and prior to resealing exhibit protection enclosures in the respective area for subsequent construction activities.
- d. ~~Beneficial Occupancy (Library and Archives): April 1, 2023. Substantial Completion: Within 345 days of Commencement of Construction.~~
- e. ~~Beneficial Occupancy (Museum): October 1, 2023.~~
- f. ~~Final Completion Date: November 15, 2023.~~
- d. —

2. Commissioning Phase:

- a. ~~Commissioning shall be completed prior to beneficial occupancy. Commencement of Construction: Work on this phase shall comment upon completion of previous phase.~~
- b. ~~Substantial Completion: Within 30 days.~~

- B. Before commencing Work of each phase, submit an updated copy of Contractor's construction schedule, showing the sequence, commencement and completion dates for all phases of the Work.

1.6 WORK PERFORMED BY OWNER

- A. Cooperate fully with Owner, so work may be carried out smoothly, without interfering with or delaying Work under this Contract or work by Owner. Coordinate the Work of this Contract with work performed by Owner.
- B. Preceding Work: Owner will perform the following construction operations at Project site. Those operations are scheduled to be substantially complete before Work under this Contract begins.
 1. Removal and storage of furniture and equipment from the areas of Work unless otherwise noted on the Drawings or observed during the pre-bid walk in areas identified for Contractor access prior to ~~May 31, 2022~~ August 15, 2022. In areas identified for

Contractor access prior to ~~May 31, 2022~~August 15, 2022, furniture and equipment remaining at the time of the pre-bid walk shall be assumed to remain during construction; limited rearrangement or movement of remaining furniture and equipment within the space required to complete the Work shall be coordinated with the Owner.

- C. Concurrent Work: Owner will perform the following construction operations at Project site. Those operations will be conducted simultaneously with Work under this Contract and are planned to be complete by ~~May 30, 2022~~August 14, 2022; completion of those operations is contingent on completion of concurrent work under separate contract at the Center Building, noted in the following section.

1. Removal and storage of furniture, equipment, and collections from the areas of Work identified for Contractor access starting ~~May 31, 2022~~August 15, 2022, unless otherwise noted on the Drawings or specified herein. Furniture, equipment, and collections on the fifth level of the Museum observed during the pre-bid walk shall be assumed to remain during construction; the Owner will move items off perimeter walls to facilitate the Work prior to Contractor access to the space. Limited rearrangement or movement of remaining furniture and equipment within the space required to complete the Work shall be coordinated with the Owner.

1.7 WORK UNDER OWNER'S SEPARATE CONTRACTS

- A. Work with Separate Contractors: Cooperate fully with Owner's separate contractors, so work on those contracts may be carried out smoothly, without interfering with or delaying Work under this Contract or other contracts. Coordinate the Work of this Contract with work performed under Owner's separate contracts.
- B. Preceding Work: Owner has awarded separate contract(s) for the following construction operations at Project site. Those operations may be substantially complete or may be partially conducted simultaneously with Work under this Contract.
1. Cultural Building Asbestos Abatement and Mechanical Upgrades – Phase 1: To EnviroVantage, Inc. for Work including asbestos abatement, mechanical system demolition, and architectural finish demolition in the Library and Archives sections of the building.
- C. Concurrent Work: Owner has awarded separate contract(s) for the following construction operations at the Center Building, AMHI Campus, Hospital Street, Augusta. Those operations will be conducted simultaneously with Work under this Contract and are planned to be substantially complete on ~~March 25, 2022~~June 3, 2022.
1. Center Building Renovation for Temporary Storage: For Work to prepare temporary storage space at the Center Building for the Owner to remove additional Museum collections from the Cultural Building prior to Contractor access to Museum spaces in the Cultural Building.

1.8 OWNER-FURNISHED/CONTRACTOR-INSTALLED (OFCI) PRODUCTS

- A. Owner's Responsibilities: Owner will furnish products indicated and perform the following, as applicable:
1. Provide to Contractor Owner-reviewed Product Data.
 2. Provide for delivery of Owner-furnished products to Project site.
 3. Upon delivery, inspect delivered items.
 - a. If Owner-furnished products are damaged, defective, or missing, arrange for replacement.
 4. Obtain manufacturer's inspections, service, and warranties.
 5. Inform Contractor of earliest available delivery date for Owner-furnished products.
- B. Contractor's Responsibilities: The Work includes the following, as applicable:
1. Designate delivery dates of Owner-furnished products in Contractor's construction schedule, utilizing Owner-furnished earliest available delivery dates.
 2. Review Owner-reviewed Product Data, noting discrepancies and other issues in providing for Owner-furnished products in the Work.
 3. Receive, unload, handle, store, protect, and install Owner-furnished products.
 4. Make building services connections for Owner-furnished products.
 5. Protect Owner-furnished products from damage during storage, handling, and installation and prior to Substantial Completion.
 6. Repair or replace Owner-furnished products damaged following receipt.
- C. Owner-Furnished/Contractor-Installed (OFCI) Products:
1. Temporary Wireless Fire Alarm Devices: For use by contractor during construction when a portion(s) of the building fire alarm system is disabled or removed to facilitate the Work.

1.9 OWNER-FURNISHED/OWNER-INSTALLED (OFOI) PRODUCTS

- A. The Owner will furnish and install products indicated.
- B. Owner-Furnished/Owner-Installed (OFOI) Products:
1. Data Loggers: Owner shall furnish and install a data logger, that measures temperature and humidity, for the Museum spaces and exhibits identified below. Contractor shall provide Owner access to install data loggers following construction of exhibit protection and prior to sealing protection enclosures for abatement. Data loggers shall be installed such that they are visible through viewing ports in the exhibit protection enclosures. Data loggers subject to daily photographic documentation by the Contractor shall be located in the following Museum spaces and exhibits; the Owner may place additional data loggers that require no action from the Contractor:
 - a. Cars N Boats Gallery 240, in the space containing exhibits below the protection platform.

- b. Exhibit #2.18 (Blacksmith Shop, in Made in Maine Gallery 238), within the exhibit below the sloped ceiling being worked overhead.
 - c. Exhibit #3.11 (St. Mary Hull, in Lumbering Gallery 390), within the space below the exhibit being worked overhead.
 - d. Exhibit #3.01 (Mural, in Museum Lobby 373).
2. Temporary Space Heaters: Owner has furnished and installed temporary space heaters throughout the building for the 2021 to 2022 heating season to maintain minimum temperatures of 55 degrees Fahrenheit. Owner will remove temporary space heaters at the completion of the 2021 to 2022 heating season.
 3. Portable Dehumidification Units: Owner has furnished and installed portable dehumidification units, connected to building drainable system, throughout the building to maintain relative humidity below 65 percent. Owner will remove portable dehumidification units at the completion of the project.
 4. Owner shall provide and install data cabling in Contractor-installed raceways.

1.10 CONTRACTOR'S USE OF SITE AND PREMISES

- A. Restricted Use of Site: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section. Use of site to be coordinated with Owner's Representative.
- B. Limits on Use of Site: Limit use of Project site to Work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
 1. Limits on Use of Site: Confine construction operations to work areas as illustrated in the Drawings.
 2. Driveways, Walkways and Entrances: Except as shown on the Drawings, keep driveways and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or for storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- C. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.
- D. Condition of Existing Grounds: Maintain portions of existing grounds, landscaping, and hardscaping affected by construction operations throughout construction period. Repair damage caused by construction operations.

1.11 COORDINATION WITH OCCUPANTS

- A. Partial Owner Occupancy: Owner will occupy the Museum areas during the initial stages of construction; dates and extents of occupancy and restricted contractor access to those areas are

shown on the Drawings. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's operations. Maintain existing exits unless otherwise indicated.

1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and authorities having jurisdiction.
2. Provide signage and barricades at access points to restricted areas occupied by the Owner or outside the limit of Work.
3. Provide not less than 72 hours' notice to Owner of activities that will affect Owner's operations.

1.12 WORK RESTRICTIONS

- A. Comply with restrictions on construction operations.
 1. Comply with limitations on use of public streets, work on public streets, rights of way, and other requirements of authorities having jurisdiction.
- B. On-Site Work Hours: Limit work to between 7:00 a.m. to 6:00 p.m., Monday through Friday, unless otherwise indicated. Work hours may be modified to meet Project requirements if approved by Owner and authorities having jurisdiction.
 1. Weekend and Holiday Hours: As coordinated with the Owner.
 2. Hours for Utility Shutdowns: As coordinated with the Owner.
 3. Hours for Operations Creating Loud Noise Levels: 8:00 a.m. and 5:00 pm.
- C. Existing Utility Interruptions: Do not interrupt utilities serving facilities unless permitted under the following conditions and then only after arranging for temporary utility services according to requirements indicated:
 1. Notify Owner not less than two days in advance of proposed utility interruptions.
 2. Obtain Owner's written permission before proceeding with utility interruptions.
- D. Smoking and Controlled Substance Restrictions: Use of tobacco products, alcoholic beverages, and other controlled substances on Owner's property is not permitted.
- E. Employee Identification: Provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.
- F. Employee Screening: Comply with Owner's requirements for background screening of Contractor personnel working on Project site. Require personnel to use identification tags at all times. Utilize the Background Check Application attached to this section. State requirements forbid people with felony convictions from working on this project.

1.13 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
 2. Text Color: Text used in the Specifications, including units of measure, manufacturer and product names, and other text may appear in multiple colors or underlined as part of a hyperlink; no emphasis is implied by text with these characteristics.
 3. Hypertext: Text used in the Specifications may contain hyperlinks. Hyperlinks may allow for access to linked information that is not residing in the Specifications. Unless otherwise indicated, linked information is not part of the Contract Documents.
 4. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 00 Contracting Requirements: General provisions of the Contract, including General and Supplementary Conditions, apply to all Sections of the Specifications.
- C. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- D. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:
1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
 2. Abbreviations: Materials and products are identified by abbreviations scheduled on Drawings and published as part of the U.S. National CAD Standard.
 3. Keynoting: Materials and products may be identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

SECTION 017900 - DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
 - 1. Instruction in operation and maintenance of systems, subsystems, and equipment.
 - 2. Demonstration and training video recordings.

1.3 INFORMATIONAL SUBMITTALS

- A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.
 - 1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.
- B. Qualification Data: For facilitator or instructor.
- C. Attendance Record: For each training module, submit list of participants and length of instruction time.
- D. Evaluations: For each participant and for each training module, submit results and documentation of performance-based test.

1.4 CLOSEOUT SUBMITTALS

- A. Demonstration and Training Video Recordings: Submit two copies within seven days of end of each training module.
 - 1. Identification: On each copy, provide an applied label with the following information:
 - a. Name of Project.
 - b. Name and address of videographer.
 - c. Name of Architect.

- d. Name of Construction Manager.
 - e. Name of Contractor.
 - f. Date of video recording.
2. Transcript: Prepared in PDF electronic format. Include a cover sheet with same label information as the corresponding video recording and a table of contents with links to corresponding training components. Include name of Project and date of video recording on each page.
 3. At completion of training, submit complete training manual(s) for Owner's use prepared in same paper and PDF file format required for operation and maintenance manuals specified in Section 017823 "Operation and Maintenance Data."

1.5 QUALITY ASSURANCE

- A. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.
- B. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Section 014000 "Quality Requirements," experienced in operation and maintenance procedures and training.
- C. Videographer Qualifications: A professional videographer who is experienced photographing demonstration and training events similar to those required.
- D. ~~Preinstruction Conference:~~ Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." ~~Review methods and procedures related to demonstration and training including, but not limited to, the following:~~
 1. ~~Inspect and discuss locations and other facilities required for instruction.~~
 2. ~~Review and finalize instruction schedule and verify availability of educational materials, instructors' personnel, audiovisual equipment, and facilities needed to avoid delays.~~
 3. ~~Review required content of instruction.~~
 4. ~~For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.~~

1.6 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.
- C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data have been reviewed and approved by Architect.

1.7 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:
 - 1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
 - a. System, subsystem, and equipment descriptions.
 - b. Performance and design criteria if Contractor is delegated design responsibility.
 - c. Operating standards.
 - d. Regulatory requirements.
 - e. Equipment function.
 - f. Operating characteristics.
 - g. Limiting conditions.
 - h. Performance curves.
 - 2. Documentation: Review the following items in detail:
 - a. Emergency manuals.
 - b. Systems and equipment operation manuals.
 - c. Systems and equipment maintenance manuals.
 - d. Product maintenance manuals.
 - e. Project Record Documents.
 - f. Identification systems.
 - g. Warranties and bonds.
 - h. Maintenance service agreements and similar continuing commitments.
 - 3. Emergencies: Include the following, as applicable:
 - a. Instructions on meaning of warnings, trouble indications, and error messages.
 - b. Instructions on stopping.
 - c. Shutdown instructions for each type of emergency.
 - d. Operating instructions for conditions outside of normal operating limits.
 - e. Sequences for electric or electronic systems.
 - f. Special operating instructions and procedures.
 - 4. Operations: Include the following, as applicable:
 - a. Startup procedures.
 - b. Equipment or system break-in procedures.
 - c. Routine and normal operating instructions.
 - d. Regulation and control procedures.
 - e. Control sequences.
 - f. Safety procedures.
 - g. Instructions on stopping.

- h. Normal shutdown instructions.
 - i. Operating procedures for emergencies.
 - j. Operating procedures for system, subsystem, or equipment failure.
 - k. Seasonal and weekend operating instructions.
 - l. Required sequences for electric or electronic systems.
 - m. Special operating instructions and procedures.
5. Adjustments: Include the following:
- a. Alignments.
 - b. Checking adjustments.
 - c. Noise and vibration adjustments.
 - d. Economy and efficiency adjustments.
6. Troubleshooting: Include the following:
- a. Diagnostic instructions.
 - b. Test and inspection procedures.
7. Maintenance: Include the following:
- a. Inspection procedures.
 - b. Types of cleaning agents to be used and methods of cleaning.
 - c. List of cleaning agents and methods of cleaning detrimental to product.
 - d. Procedures for routine cleaning.
 - e. Procedures for preventive maintenance.
 - f. Procedures for routine maintenance.
 - g. Instruction on use of special tools.
8. Repairs: Include the following:
- a. Diagnosis instructions.
 - b. Repair instructions.
 - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - d. Instructions for identifying parts and components.
 - e. Review of spare parts needed for operation and maintenance.
- 1.8 PREPARATION
- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."
 - B. Set up instructional equipment at instruction location.

1.9 INSTRUCTION

- A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.
- B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
 - 1. Architect will furnish an instructor to describe basis of system design, operational requirements, criteria, and regulatory requirements.
 - 2. Owner will furnish an instructor to describe Owner's operational philosophy.
 - 3. Owner will furnish Contractor with names and positions of participants.
- C. Scheduling: Provide instruction at mutually agreed-on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.
 - 1. Schedule training with Owner with at least seven days' advance notice.
- D. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.
- E. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

1.10 DEMONSTRATION AND TRAINING VIDEO RECORDINGS

- A. General: Engage a qualified commercial videographer to record demonstration and training video recordings. Record each training module separately. Include classroom instructions and demonstrations, board diagrams, and other visual aids, but not student practice.
 - 1. At beginning of each training module, record each chart containing learning objective and lesson outline.
- B. Digital Video Recordings: Provide high-resolution, digital video in MPEG format, produced by a digital camera with minimum sensor resolution of 12 megapixels and capable of recording in full HD modewith vibration reduction technology.
 - 1. Submit video recordings on CD-ROM or thumb drive.
 - 2. File Hierarchy: Organize folder structure and file locations according to Project Manual table of contents. Provide complete screen-based menu.
 - 3. File Names: Utilize file names based on name of equipment generally described in video segment, as identified in Project specifications.
 - 4. Contractor and Installer Contact File: Using appropriate software, create a file for inclusion on the equipment demonstration and training recording that describes the following for each Contractor involved on the Project, arranged according to Project Manual table of contents:

- a. Name of Contractor/Installer.
 - b. Business address.
 - c. Business phone number.
 - d. Point of contact.
 - e. Email address.
- C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to adequately cover area of demonstration and training. Display continuous running time.
1. Film training session(s) in segments not to exceed 15 minutes.
 - a. Produce segments to present a single significant piece of equipment per segment.
 - b. Organize segments with multiple pieces of equipment to follow order of Project Manual table of contents.
 - c. Where a training session on a particular piece of equipment exceeds 15 minutes, stop filming and pause training session. Begin training session again upon commencement of new filming segment.
- D. Light Levels: Verify light levels are adequate to properly light equipment. Verify equipment markings are clearly visible prior to recording.
1. Furnish additional portable lighting as required.
- E. Narration: Describe scenes on video recording by audio narration by microphone while video recording is recorded. Include description of items being viewed.
- F. Transcript: Provide a transcript of the narration. Display images and running time captured from videotape opposite the corresponding narration segment.
- G. Preproduced Video Recordings: Provide video recordings used as a component of training modules in same format as recordings of live training.

PART 2 - PRODUCTS

PART 3 - EXECUTION

END OF SECTION 017900

SECTION 019113 - GENERAL COMMISSIONING REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. General requirements for coordinating and scheduling commissioning activities.
2. Commissioning meetings.
3. Commissioning reports.
4. Use of commissioning process test equipment, instrumentation, and tools.
5. Construction checklists, including, but not limited to, installation checks, startup, performance tests, and performance test demonstration.
6. Commissioning tests and commissioning test demonstration.
7. Adjusting, verifying, and documenting identified systems and assemblies.

- B. Related Requirements:

1. Section 011000 "Summary" for Commissioning Authority responsibilities.
2. Section 013300 "Submittal Procedures" for submittal procedure requirements for commissioning process.
3. Section 017700 "Closeout Procedures" for Certificate of Construction-Phase Commissioning Process Completion submittal requirements.
4. Section 017823 "Operation and Maintenance Data" for preliminary operation and maintenance data submittal requirements.
5. Section 230800 "Commissioning of HVAC" for technical commissioning requirements for HVAC.

1.3 DEFINITIONS

- A. Acceptance Criteria: Threshold of acceptable work quality or performance specified for a commissioning activity, including, but not limited to, construction checklists, performance tests, performance test demonstrations, commissioning tests, and commissioning test demonstrations.
- B. Basis-of-Design Document: A document prepared by Architect that records concepts, calculations, decisions, and product selections used to comply with Owner's Project Requirements and to suit applicable regulatory requirements, standards, and guidelines.
- C. Commissioning Authority: An independent testing agency hired by the Contractor~~An entity engaged by Owner~~, and identified in Section 011000 "Summary," to evaluate Commissioning-Process Work.

- D. Commissioning Plan: A document, prepared by Commissioning Authority, that outlines the organization, schedule, allocation of resources, and documentation of commissioning requirements.
- E. Commissioning: A quality-focused process for verifying and documenting that the facility and its systems and assemblies are installed, and tested to comply with Owner's Project Requirements. The requirements specified here are limited to the construction phase commissioning activities.
- F. Construction-Phase Commissioning-Process Completion: The stage of completion and acceptance of commissioning process when resolution of deficient conditions and issues discovered during commissioning process and retesting until acceptable results are obtained has been accomplished. Owner-Commissioning Authority will establish in writing the date construction-phase commissioning-process completion is achieved. See Section 017700 "Closeout Procedures" for Certificate of Construction-Phase Commissioning Process Completion submittal requirements.
 - 1. Commissioning process is complete when the Work specified of this Section and related Sections has been completed and accepted, including, but not limited to, the following:
 - a. Completion of tests and acceptance of test results.
 - b. Resolution of issues, as verified by retests performed and documented with acceptance of retest results.
 - c. Comply with requirements in Section 017900 "Demonstration and Training."
 - d. Completion and acceptance of submittals and reports.
- G. Owner's Project Requirements: A document that details the functional requirements of a project and the expectations of how it will be used and operated, including Project goals, measurable performance criteria, cost considerations, benchmarks, success criteria, and supporting information. This document is prepared either by the Owner or for the Owner by the Architect or Commissioning Authority.
- H. Owner's Witness: Commissioning Authority, Owner's Project Manager, or Architect-designated witness authorized to authenticate test demonstration data and to sign completed test data forms.
- I. "Systems," "Assemblies," "Subsystems," "Equipment," and "Components": Where these terms are used together or separately, they shall mean "as-built" systems, assemblies, subsystems, equipment, and components.
- J. Test: Performance tests, performance test demonstrations, commissioning tests, and commissioning test demonstrations.

1.4 COMPENSATION

- A. If Architect or Engineer, Commissioning Authority, other Owner's witness, or Owner's staff perform additional services or incur additional expenses due to actions of Contractor listed below, Contractor shall compensate Owner for such additional services and expenses.
 - 1. Failure to provide timely notice of commissioning activities schedule changes.
 - 2. Failure to meet acceptance criteria for test demonstrations.

1.5 COMMISSIONING TEAM

A. Members Appointed by Contractor(s):

1. Commissioning Coordinator: A person or entity employed by Contractor to manage, schedule, and coordinate commissioning process.
2. Project superintendent and other employees that Contractor may deem appropriate for a particular portion of the commissioning process.
3. Subcontractors, installers, suppliers, and specialists that Contractor may deem appropriate for a particular portion of the commissioning process.
4. Appointed team members shall have the authority to act on behalf of the entity they represent.

B. Commissioning Agency Members Hired by Contractor:

- 4.1. Commissioning Authority, plus consultants that Commissioning Authority may deem appropriate for a particular portion of the commissioning process.

B.C. Members Appointed by Owner:

- ~~1. Commissioning Authority, plus consultants that Commissioning Authority may deem appropriate for a particular portion of the commissioning process.~~
- 2.1. Owner representative(s), facility operations and maintenance personnel, plus other employees, separate contractors, and consultants that Owner may deem appropriate for a particular portion of the commissioning process.
- 3.2. Engineer, plus employees and consultants that Architect may deem appropriate for a particular portion of the commissioning process.

1.6 INFORMATIONAL SUBMITTALS

- A. Comply with requirements in Section 013300 "Submittal Procedures" for submittal procedure general requirements for commissioning process.
- B. Commissioning Plan Information:
 1. List of ~~Contractor-appointed~~Commissioning Authority commissioning team members to include specific personnel and subcontractors performing the various commissioning requirements.
 2. Schedule of commissioning activities, integrated with the Construction Schedule. Comply with requirements in Section 013200 "Construction Progress Documentation" for the Construction Schedule general requirements for commissioning process.
 3. Contractor personnel and subcontractors participating in each test.
 4. List of instrumentation required for each test to include identification of parties that will provide instrumentation for each test.
- C. Commissioning schedule.
- D. Two-week look-ahead schedules.

E. Commissioning Coordinator Letter of Authority:

1. Within 10 days after approval of Commissioning Coordinator qualifications, submit a letter of authority for Commissioning Coordinator, signed by a principal of Contractor's firm. Letter shall authorize Commissioning Coordinator to do the following:
 - a. Make inspections required for commissioning process.
 - b. Coordinate, schedule, and manage commissioning process of Contractor, subcontractors, and suppliers.
 - c. Obtain documentation required for commissioning process from Contractor, subcontractors, and suppliers.
 - d. Report issues, delayed resolution of issues, schedule conflicts, and lack of cooperation or expertise on the part of members of the commissioning team.

F. List test instrumentation, equipment, and monitoring devices. Include the following information:

1. Make, model, serial number, and application for each instrument, equipment, and monitoring device.
2. Brief description of intended use.
3. Calibration record showing the following:
 - a. Calibration agency, including name and contact information.
 - b. Last date of calibration.
 - c. Range of values for which calibration is valid.
 - d. Certification of accuracy.
 - e. Certification for calibration equipment traceable to NIST.
 - f. Due date of the next calibration.

G. Test Reports:

1. Pre-Startup Report: Prior to startup of equipment or a system, submit signed, completed construction checklists.
2. Test Data Reports: At the end of each week in which tests are conducted, submit test data for tests performed.
3. Commissioning Issue Reports: Daily, at the end of each week in which tests are conducted, submit commissioning issue reports for tests for which acceptable results were not achieved.
4. Weekly Progress Report: Weekly, at the end of each week in which tests are conducted, submit a progress report.
5. Data Trend Logs: Submit data trend logs at the end of the trend log period.
6. System Alarm Logs: Weekly, at the start of days following a day in which tests were performed, submit printout of log of alarms that occurred since the last log was printed.

H. Construction Checklists:

1. Material checks.
2. Installation checks.
3. Startup procedures test reports, where required.

1.7 CLOSEOUT SUBMITTALS

A. Commissioning Report:

1. At Construction-Phase Commissioning Completion, include the following:
 - a. Pre-startup reports.
 - b. Approved test procedures.
 - c. Test data forms, completed and signed.
 - d. Progress reports.
 - e. Commissioning issue report log.
 - f. Commissioning issue reports showing resolution of issues.
 - g. Correspondence or other documents related to resolution of issues.
 - h. Other reports required by commissioning process.
 - i. List unresolved issues and reasons they remain unresolved and should be exempted from the requirements for Construction-Phase Commissioning Completion.
 - j. Report shall include commissioning work of Contractor.

B. Request for Certificate of Construction-Phase Commissioning Process Completion.

C. Operation and Maintenance Data: For proprietary test equipment, instrumentation, and tools to include in operation and maintenance manuals.

1.8 QUALITY ASSURANCE

A. Commissioning Coordinator Qualifications:

1. Documented experience commissioning systems of similar complexity to those contained in these documents on other projects of similar scope and complexity.
2. Certification of commissioning-process expertise. The following certifications are acceptable. Owner reserves the right to accept or reject certifications as evidence of qualification.
 - a. Certified Commissioning Authority, by AABC Commissioning Group (ACG).
 - b. Commissioning-Process Management Professional, by American Society of Heating, Refrigerating and Air-Conditioning Engineers.
 - c. Certified Commissioning Professional, by Building Commissioning Association.

B. Calibration Agency Qualifications: Certified by The American Association for Laboratory Accreditation that the calibration agency complies with minimum requirements of ISO/IEC 17025.

PART 2 - PRODUCTS

2.1 TEST EQUIPMENT, INSTRUMENTATION, AND TOOLS

- #### A. Test equipment and instrumentation required to perform the commissioning process shall remain the property of Contractor unless otherwise indicated.

- B. Test equipment and instrumentation required to perform commissioning process shall comply with the following criteria:
1. Be manufactured for the purpose of testing and measuring tests for which they are being used and have an accuracy to test and measure system performance within the tolerances required to determine acceptable performance.
 2. Calibrated and certified.
 - a. Calibration performed and documented by a qualified calibration agency according to national standards applicable to the tools and instrumentation being calibrated. Calibration shall be current according to national standards or within test equipment and instrumentation manufacturer's recommended intervals, whichever is more frequent, but not less than within six months of initial use on Project. Calibration tags shall be permanently affixed.
 - b. Repair and recalibrate test equipment and instrumentation if dismantled, dropped, or damaged since last calibrated.
 3. Maintain test equipment and instrumentation.
 4. Use test equipment and instrumentation only for testing or monitoring Work for which they are designed.

2.2 PROPRIETARY TEST EQUIPMENT, INSTRUMENTATION, AND TOOLS

- A. Proprietary test equipment, instrumentation, and tools are those manufactured or prescribed by tested equipment manufacturer and required for work on its equipment as a condition of equipment warranty, or as otherwise required to service, repair, adjust, calibrate, or perform work on its equipment.
1. Identify proprietary test equipment, instrumentation, and tools required in the test equipment identification list submittal.
 2. Proprietary test equipment, instrumentation, and tools shall become the property of Owner at Substantial Completion.

2.3 REPORT FORMAT AND ORGANIZATION

A. General Format and Organization:

1. Bind report in three-ring binders.
2. Label the front cover and spine of each binder with the report title, volume number, project name, Contractor's name, and date of report.
3. Record report on compact disk **or USB thumb drive**.
4. Electronic Data: Portable document format (PDF); a single file with outline-organized bookmarks for major and minor tabs and tab contents itemized for specific reports.

B. Commissioning Report:

1. Include a table of contents and an index to each test.
2. Include major tabs for each Specification Section.
3. Include minor tabs for each test.

4. Within each minor tab, include the following:
 - a. Test specification.
 - b. Pre-startup reports.
 - c. Approved test procedures.
 - d. Test data forms, completed and signed.
 - e. Commissioning issue reports, showing resolution of issues, and documentation related to resolution of issues pertaining to a single test. Group data forms, commissioning issue reports showing resolution of issues, and documentation related to resolution of issues for each test repetition together within the minor tab, in reverse chronological order (most recent on top).

PART 3 - EXECUTION

3.1 PREPARATION

- A. Review preliminary construction checklists and preliminary test procedures and data forms.

3.2 CONSTRUCTION CHECKLISTS

- A. Construction checklists cannot modify or conflict with the Contract Documents.
- B. Create construction checklists based on actual systems and equipment to be included in Project.
- C. Material Checks: Compare specified characteristics and approved submittals with materials as received. Include factory tests and other evaluations, adjustments, and tests performed prior to shipment if applicable.
 1. Service connection requirements, including configuration, size, location, and other pertinent characteristics.
 2. Included optional features.
 3. Installation Checks:
 - a. Location according to Drawings and approved Shop Drawings.
 - b. Configuration.
 - c. Compliance with manufacturers' written installation instructions.
 - d. Attachment to structure.
 - e. Access clearance to allow for maintenance, service, repair, removal, and replacement without the need to disassemble or remove other equipment or building elements. Access coordinated with other building elements and equipment, including, but not limited to, ceiling and wall access panels, in a manner consistent with OSHA fall-protection regulations and safe work practices.
 - f. Utility connections are of the correct characteristics, as applicable.
 - g. Correct labeling and identification.
 - h. Startup Checks: Verify readiness of equipment to be energized. Include manufacturer's standard startup procedures and forms.

- D. Startup: Perform and document initial operation of equipment to prove that it is installed properly and operates as intended according to manufacturer's standard startup procedures, at minimum.
- E. Performance Tests:
 - 1. Functional Performance Tests (FPT): Test and evaluate performance of systems under a full range of operating conditions and loads.

3.3 GENERAL EXECUTION REQUIREMENTS

- A. Schedule and coordinate the commissioning process with the Construction Schedule.
- B. Perform activities identified in construction checklists, including tests, and document results of actions as construction proceeds.
- C. Perform test demonstrations for Owner's witness. Unless otherwise indicated, demonstrate tests for 100 percent of work to which the test applies.
- D. Report test data and commissioning issue resolutions.
- E. Schedule personnel to participate in and perform Commissioning-Process Work.
- F. Installing contractors' commissioning responsibilities include, but are not limited to, the following:
 - 1. Operating the equipment and systems ~~they install~~ during functional tests.
 - 2. In addition, installing contractors may be required to assist in tests of equipment and systems with which their work interfaces.

3.4 COMMISSIONING COORDINATOR RESPONSIBILITIES

- A. Management and Coordination: Manage, schedule, and coordinate commissioning process, including, but not limited to, the following:
 - 1. Coordinate with subcontractors on their commissioning responsibilities and activities.
 - ~~2. Obtain, assemble, and submit commissioning documentation.~~
 - ~~3.2.~~ Attend periodic on-site commissioning meetings. Comply with requirements in Section 013100 "Project Management and Coordination."
 - ~~4.3.~~ ~~Develop and maintain the commissioning schedule.~~ Integrate commissioning schedule into the Construction Schedule. Update Construction Schedule at specified intervals.
 - ~~5. Review and comment on preliminary test procedures and data forms.~~
 - ~~6. Report inconsistencies and issues in system operations.~~
 - ~~7.4.~~ Verify that equipment startup tests have been successfully completed ~~and results comply with acceptance criteria~~, and that equipment and systems are ready before scheduling test demonstrations.
 - ~~8. Direct and coordinate test demonstrations.~~
 - ~~9.5.~~ Coordinate witnessing of test demonstrations by Owner's witness.

- ~~10. Coordinate and manage training. Be present during training sessions to direct video recording, present training, and direct the training presentations of others. Comply with requirements in Section 017900 "Demonstration and Training."~~
- ~~11. Prepare and submit specified commissioning reports.~~
- ~~12. Track commissioning issues until resolution and retesting is successfully completed.~~
- ~~13. Retain original records of Commissioning-Process Work, organized as required for the commissioning report. Provide Owner's representative access to these records on request.~~
- ~~14. Assemble and submit commissioning report.~~

3.5 COMMISSIONING AUTHORITY RESPONSIBILITIES

A. Lead and perform the commissioning process, including, but not limited to:

1. Obtain, assemble, and submit commissioning documentation.
2. Schedule and lead periodic on-site commissioning meetings. Comply with requirements in Section 013100 "Project Management and Coordination."
3. Develop and maintain the Commissioning Schedule. Coordinate Commissioning Schedule into the Construction Schedule with the Contractor and the Owner. Update the Commissioning Schedule as required – at least monthly.
4. Review and comment on preliminary test procedures and data forms submitted by the Contractor.
5. Report inconsistencies and issues in system operations.
6. Direct and coordinate test demonstrations.
7. Coordinate witnessing of test demonstrations by Owner's witness.
8. Track commissioning issues until resolution and retesting is successfully completed.
9. Retain original records of Commissioning-Process Work, organized as required for the commissioning report. Provide Owner's Representative access to these records on request.
10. Assemble and submit commissioning report.

3.5.3.6 COMMISSIONING FUNCTIONAL TESTING

- A. Quality Control: Construction checklists, including tests, are quality-control tools designed to improve the functional quality of Project. Test demonstrations evaluate the effectiveness of Contractor's quality-control process.
- B. ~~Owner's witness will be present to witness commissioning work requiring the signature of an owner's witness, including, but not limited to, test demonstrations.~~ Owner's project manager will coordinate attendance by Owner's witness with Contractor's published Commissioning Schedule. Owner's witness will provide no labor or materials in the commissioning work. The only functions of Owner's witness will be to observe and comment on the progress and results of commissioning process and sign any commissioning forms requiring the signature of an Owner's witness.
- C. Construction Checklists (Pre-Functional Test Checklists):
 1. Complete construction checklists as Work is completed.
 2. Distribute construction checklists to installing contractors before they start work.
 3. Installers:

- a. Verify installation using approved construction checklists as Work proceeds.
 - b. Complete and sign construction checklists weekly for work performed during the preceding week.
4. Provide Commissioning Authority access to completed construction checklists.
- D. Installation Compliance Issues: Record as an installation compliance issue Work found to be incomplete, inaccessible, at variance with the Contract Documents, nonfunctional, or that does not comply with construction checklists. Record installation compliance issues on the construction checklist at the time they are identified. Record corrective action and how future Work should be modified before signing off the construction checklist.
- ~~E. Pre-Startup Audit: Prior to executing startup procedures, review completed installation checks to determine readiness for startup and operation. Report conditions, which, if left uncorrected, adversely impact the ability of systems or equipment to operate satisfactorily or to comply with acceptance criteria. Prepare pre-startup report for each system.~~

F.E. Functional Test Procedures and Test Data Forms:

1. Test procedures shall define the step-by-step procedures to be used to execute tests and test demonstrations.
2. Test procedures shall be specific to the make, model, and application of the equipment and systems being tested.
3. Completed test data forms are the official records of the test results.
4. Commissioning Authority will provide to Contractor preliminary test procedures and test data forms for performance tests and commissioning tests after approval of Product Data, Shop Drawings, and preliminary operation and maintenance manual.
5. Review preliminary test procedures and test data forms, and provide comments within 14 days of receipt from Commissioning Authority. Review shall address the following:
 - a. Equipment protection and warranty issues, including, but not limited to, manufacturers' installation and startup recommendations, and operation and maintenance instructions.
 - b. Applicability of the procedure to the specific software, equipment, and systems approved for installation.
6. After Contractor has reviewed and commented on the preliminary test procedures and test data forms, Commissioning Authority will revise and reissue the approved revised test procedures and test data forms marked "Approved for Testing."
7. Use only approved test procedures and test data forms marked "Approved for Testing" to perform and document tests and test demonstrations.

G.F. Performance of Functional Tests:

1. Perform Functional Testing of all HVAC equipment unless otherwise indicated.
2. Notify Owner's witness at least three days in advance of each functional test.
 - a. Failure of Owner's witness to be present for agreed-on schedule of test demonstration shall not delay Contractor. If Owner's witness fails to attend a scheduled test, Contractor shall proceed with the scheduled test.

3. Perform and complete each step of the approved test procedures in the order listed.
4. Record data observed during performance of tests on approved data forms at the time of test performance and when the results are observed.
5. Record test results that are not within the range of acceptable results on commissioning issue report forms in addition to recording the results on approved test procedures and data forms according to the "Commissioning Compliance Issues" Paragraph in this Article.
6. On completion of a test, sign the completed test procedure and data form. Tests for which test procedures and data forms are incomplete, not signed, or which indicate performance that does not comply with acceptance criteria will be rejected. Tests for which test procedures and data forms are rejected shall be repeated and results resubmitted.
7. False load test requirements are specified in related sections.
 - a. Where false load testing is specified, provide temporary equipment, power, controls, wiring, piping, valves, and other necessary equipment and connections required to apply the specified load to the system. False load system shall be capable of steady-state operation and modulation at the level of load specified. Equipment and systems permanently installed in this work may be used to create the temporary false load using control overrides, schedule adjustments, or setpoint adjustments as long as the systems and equipment are not damaged or degraded and space temperature and humidity are not adversely affected. After the test is complete, the overrides shall be removed and the systems shall revert to normal operation.

H.G. Deferred Tests:

1. Deferred Test List: Identify proposed deferred tests or other tests approved for deferral until specified seasonal or other conditions are available. When approved, deferred tests may be completed after the date of Construction-Phase Commissioning Completion. Identify proposed deferred tests as follows:
 - a. Identify deferred tests by number and title.
 - b. Provide a target schedule for completion of deferred tests.
2. Schedule and coordinate deferred tests. Schedule deferred tests when specified conditions are available. ~~Notify Architect and Commissioning Authority at least three working days (minimum) in advance of tests.~~
3. Where deferred tests are specified, coordinate participation of necessary personnel and of Architect, Commissioning Authority, and Owner's witness. Schedule deferred tests to minimize occupant and facility impact. ~~Obtain Architect's approval of the proposed schedule.~~

H.H. Delayed Tests:

1. Delayed Test List: Identify proposed delayed tests. Obtain Owner approval of proposed delayed tests, including proposed schedule of completion of each delayed test, before submitting request for Certificate of Construction-Phase Commissioning Process Completion. Include the following in the request for Certificate of Construction-Phase Commissioning Process Completion:
 - a. Identify delayed tests by test number and title.

- b. Written approval of proposed delayed tests, including approved schedule of completion of delayed tests.
2. Schedule and coordinate delayed tests. Schedule delayed tests when conditions that caused the delay have been rectified. ~~Notify Architect and Commissioning Authority at least three working days (minimum) in advance of tests.~~
3. Where delayed tests are approved, coordinate participation of necessary personnel and of Architect, Commissioning Authority, and Owner's witness. Schedule delayed tests to minimize occupant and facility impact. ~~Obtain Architect's approval of the proposed schedule.~~

H.I. Commissioning Compliance Issues:

1. Test results that are not within the range of acceptable results are commissioning compliance issues.
2. Track and report commissioning compliance issues until resolution and retesting are successfully completed.
3. If a test demonstration fails, determine the cause of failure. Direct timely resolution of issue and then repeat the demonstration. If the issue can be quickly corrected (such as changing a setpoint, tuning a control loop, etc.) then the Contractor shall immediately make the correction and the test shall be repeated until proper operation is verified.~~If a test demonstration must be repeated due to failure caused by Contractor work or materials, reimburse Owner for billed costs for the participation in the repeated demonstration.~~
4. Test Results: If a test demonstration fails to meet the acceptance criteria and cannot be immediately corrected, perform the following:
 - a. Complete a commissioning compliance issue report form promptly on discovery of test results that do not comply with acceptance criteria.
 - b. Submit commissioning compliance issue report form within 24 hours of the test.
 - c. Determine the cause of the failure.
 - d. Establish responsibility for corrective action if the failure is due to conditions found to be Contractor's responsibility.
5. Commissioning Compliance Issue Report: Provide a commissioning compliance issue report for each issue. Do not report multiple issues on the same commissioning compliance issue report.
 - a. Exception: If an entire class of devices is determined to exhibit the identical issue, they may be reported on a single commissioning compliance issue report. (For example, if all return-air damper actuators that are specified to fail to the open position are found to fail to the closed position, they may be reported on a single commissioning issue report. If a single commissioning issue report is used for multiple commissioning compliance issues, each device shall be identified in the report, and the total number of devices at issue shall be identified.
 - b. Complete and submit Part 1 of the commissioning compliance issue report immediately when the condition is observed.
 - c. Record the commissioning compliance issue report number and describe the deficient condition on the data form.
 - d. Resolve commissioning compliance issues promptly. Complete and submit Part 2 of the commissioning compliance issue report when issues are resolved.

6. Diagnose and correct failed test demonstrations as follows:
 - a. Perform diagnostic tests and activities required to determine the fundamental cause of issues observed.
 - b. Record each step of the diagnostic procedure prior to performing the procedure. Update written procedure as changes become necessary.
 - c. Record the results of each step of the diagnostic procedure.
 - d. Record the conclusion of the diagnostic procedure on the fundamental cause of the issue.
 - e. Determine and record corrective measures.
 - f. Include diagnosis of fundamental cause of issues in commissioning compliance issue report.

7. Retest:
 - a. Schedule and repeat the complete test procedure for each test demonstration for which acceptable results are not achieved. Obtain signature of Owner's witness on retest data forms. Repeat test demonstration until acceptable results are achieved. Except for issues that are determined to result from design errors or omissions, or other conditions beyond Contractor's responsibility, compensate Owner for direct costs incurred as the result of repeated test demonstrations to achieve acceptable results.
 - b. For each repeated test demonstration, submit a new test data form, marked "Retest."

8. Do not correct commissioning compliance issues during test demonstrations.
 - a. Exceptions will be allowed if the cause of the issue is obvious and resolution can be completed in less than five minutes. If corrections are made under this exception, note the deficient conditions on the test data form and issue a commissioning compliance issue report. A new test data form, marked "Retest," shall be initiated after the resolution has been completed.

3.63.7 COMMISSIONING MEETINGS

- A. Commissioning Authority will schedule and conduct commissioning meetings. Comply with requirements in Section 013100 "Project Management and Coordination."

3.73.8 SEQUENCING

- A. Sequencing of Commissioning Verification Activities: For a particular material, item of equipment, assembly, or system, perform the following in the order listed unless otherwise indicated:
 1. Construction Checklists:
 - a. Material checks.
 - b. Installation checks.

~~e. Startup, as appropriate. Some startup may depend on component performance. Such startup may follow component performance tests on which the startup depends.~~

d.c. Performance Tests:

- 1) Static tests, as appropriate.
- 2) Component performance tests. Some component performance tests may depend on completion of startup. Such component performance tests may follow startup.
- 3) Equipment and assembly performance tests.
- 4) System performance tests.
- 5) Intersystem performance tests.

2. Commissioning tests.

- B. Before performing commissioning tests, verify that materials, equipment, assemblies, and systems are delivered, installed, started, and adjusted to perform according to construction checklists.
- C. Verify readiness of materials, equipment, assemblies, and systems by performing tests prior to performing test demonstrations. Notify Architect if acceptable results cannot be achieved due to conditions beyond Contractor's control or responsibility.
- D. Commence tests as soon as installation checks for materials, equipment, assemblies, or systems are satisfactorily completed. Tests of a particular system may proceed prior to completion of other systems, provided the incomplete work does not interfere with successful execution of test.

3.83.9 SCHEDULING

- A. Commence commissioning process as early in the construction period as possible.
- B. Commissioning Schedule: Integrate commissioning activities into Construction Schedule. See Section 013200 "Construction Progress Documentation."
 1. Include detailed commissioning activities in monthly updated Construction Schedule and short-interval schedule submittals.
 2. Schedule the start date and duration for the following commissioning activities:
 - a. Submittals.
 - b. Preliminary operation and maintenance manual submittals.
 - c. Installation checks.
 - d. Startup, where required.
 - e. Performance tests.
 - f. Performance test demonstrations.
 - g. Commissioning tests.
 - h. Commissioning test demonstrations.
 3. Schedule shall include a line item for each installation check, startup, and test activity specific to the equipment or systems involved.

4. Determine milestones and prerequisites for commissioning process. Show commissioning milestones, prerequisites, and dependencies in monthly updated critical-path-method construction schedule and short-interval schedule submittals.
- C. Two-Week Look-Ahead Commissioning Schedule:
1. Two weeks prior to the beginning of tests, submit a detailed two-week look-ahead schedule. Thereafter, submit updated two-week look-ahead schedules weekly for the duration of commissioning process.
 2. Two-week look-ahead schedules shall identify the date, time, beginning location, Contractor personnel required, and anticipated duration for each startup or test activity.
 3. Use two-week look-ahead schedules to notify and coordinate participation of Owner's witnesses.
- D. Owner's Witness Coordination:
1. Coordinate Owner's witness participation via Architect.
 2. Notify Architect of commissioning schedule changes at least ~~{two}~~ **<Insert number>** ~~five~~ work days in advance for activities requiring the participation of Owner's witness.

3.93.10 COMMISSIONING REPORTS

- A. Test Reports:
1. Pre-startup reports include observations of the conditions of installation, organized into the following sections:
 - a. Equipment Model Verification: Compare contract requirements, approved submittals, and provided equipment. Note inconsistencies.
 - b. Preinstallation Physical Condition Checks: Observe physical condition of equipment prior to installation. Note conditions including, but not limited to, physical damage, corrosion, water damage, or other contamination or dirt.
 - c. Preinstallation Component Verification Checks: Verify components supplied with the equipment, preinstalled or field installed, are correctly installed and functional. Verify external components required for proper operation of equipment correctly installed and functional. Note missing, improperly configured, improperly installed, or nonfunctional components.
 - d. Summary of Installation Compliance Issues and Corrective Actions: Identify installation compliance issues and the corrective actions for each. Verify that issues noted have been corrected.
 - e. Evaluation of System Readiness for Startup: For each item of equipment for each system for which startup is anticipated, document in summary form acceptable to Owner completion of equipment model verification, preinstallation physical condition checks, preinstallation component verification checks, and completion of corrective actions for installation compliance issues.
 2. Test data reports include the following:

- a. "As-tested" system configuration. Complete record of conditions under which the test was performed, including, but not limited to, the status of equipment, systems, and assemblies; temporary adjustments and settings; and ambient conditions.
 - b. Data and observations, including, but not limited to, data trend logs, recorded during the tests.
 - c. Signatures of individuals performing and witnessing tests.
 - d. Data trend logs accumulated overnight from the previous day of testing.
3. Commissioning Compliance Issue Reports: Report as commissioning compliance issues results of tests and test demonstrations that do not comply with acceptance criteria. Report only one issue per commissioning compliance issue report. Use sequentially numbered facsimiles of commissioning compliance issue report form included in this Section, or other form approved by Owner. Distribute commissioning compliance issue reports to parties responsible for taking corrective action. Identify the following:
- a. Commissioning compliance issue report number. Assign unique, sequential numbers to individual commissioning compliance issue reports when they are created, to be used for tracking.
 - b. Action distribution list.
 - c. Report date.
 - d. Test number and description.
 - e. Equipment identification and location.
 - f. Briefly describe observations about the performance associated with failure to achieve acceptable results. Identify the cause of failure if apparent.
 - g. Diagnostic procedure or plan to determine the cause (include in initial submittal)
 - h. Diagnosis of fundamental cause of issues as specified below (include in resubmittal).
 - i. Fundamental cause of unacceptable performance as determined by diagnostic tests and activities.
 - j. When issues have been resolved, update and resubmit the commissioning issue report forms by completing Part 2. Identify resolution taken and the dates and initials of the persons making the entries.
 - k. Schedule for retesting.
4. Weekly progress reports include information for tests conducted since the preceding report and the following:
- a. Completed data forms.
 - b. Equipment or system tested, including test number, system or equipment tag number and location, and notation about the apparent acceptability of results.
 - c. Activities scheduled but not conducted per schedule.
 - d. Commissioning compliance issue report log.
 - e. Schedule changes for remaining Commissioning-Process Work, if any.
5. Data trend logs shall be initiated and running prior to the time scheduled for the test demonstration.
- a. Trend log data format shall be multiple data series graphs. Where multiple data series are trend logged concurrently, present the data on a common horizontal time axis. Individual data series may be presented on a segmented vertical axis to avoid interference of one data series with another, and to accommodate different axis

- scale values. Graphs shall be sufficiently clear to interpret data within the accuracy required by the acceptance criteria.
- b. Attach to the data form printed trend log data collected during the test or test demonstration.
 - c. Record, print out, and attach to the data form operator activity during the time the trend log is running. During the time the trend log is running, operator intervention not directed by the test procedure invalidates the test results.
6. System Alarm Logs: Record and print out a log of alarms that occurred since the last log was printed. Evaluate alarms to determine if the previous day's work resulted in any conditions that are not considered "normal operation."
- a. Conditions that are not considered "normal operation" shall be reported on a commissioning issue report attached to the alarm log. Resolve as necessary. The intent of this requirement is to discover control system points or sequences left in manual or disabled conditions, equipment left disconnected, set points left with abnormal values, or similar conditions that may have resulted from failure to fully restore systems to normal, automatic control after test completion.

3.103.11 CERTIFICATE OF CONSTRUCTION-PHASE COMMISSIONING PROCESS COMPLETION

- A. When Contractor considers that construction-phase commissioning process, or a portion thereof which Owner agrees to accept separately, is complete, Contractor shall prepare and submit to Owner and Commissioning Authority through Architect a comprehensive list of items to be completed or corrected. Failure to include an item on such list does not alter Contractor's responsibility to complete commissioning process.
- B. On receipt of Contractor's list, Commissioning Authority will make an inspection to determine whether the construction-phase commissioning process or designated portion thereof is complete. If Commissioning Authority's inspection discloses items, whether included on Contractor's list, which is not sufficiently complete as defined in "Construction-Phase Commissioning Process Completion" Paragraph in the "Definitions" Article, Contractor shall, before issuance of the Certificate of Construction-Phase Commissioning Process Completion, complete or correct such items on notification by Commissioning Authority. In such case, Contractor shall then submit a request for another inspection by Commissioning Authority to determine construction-phase commissioning process completion.
- C. Contractor shall promptly correct deficient conditions and issues discovered during commissioning process. Costs of correcting such deficient conditions and issues, including additional testing and inspections, the cost of uncovering and replacement, and compensation for Architect's and Commissioning Authority's services and expenses made necessary thereby, shall be at Contractor's expense.
- D. When construction-phase commissioning process or designated portion is complete, Commissioning Authority will prepare a Certificate of Construction-Phase Commissioning Process Completion that shall establish the date of completion of construction-phase commissioning process. Certificate of Construction-Phase Commissioning Process Completion shall be submitted prior to requesting inspection for determining date of Substantial Completion.

END OF SECTION 019113

SECTION 024119 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Demolition and removal of selected portions of building or structure.
2. Demolition and removal of selected site elements.
3. Salvage of existing items to be reused or recycled.

B. Related Requirements:

1. Section 011000 "Summary" for restrictions on use of the premises, Owner-occupancy requirements, and phasing requirements.
2. Section 017300 "Execution" for cutting and patching procedures.
3. Section 013516 "Alteration Project Procedures" for general protection and work procedures for alteration projects.
4. Section 022600 "Asbestos Abatement."

1.2 DEFINITIONS

- A. Remove: Detach items from existing construction and dispose of them off-site unless indicated to be salvaged or reinstalled.
- B. Remove and Salvage: Detach items from existing construction, in a manner to prevent damage, and store.
- C. Remove and Reinstall: Detach items from existing construction, in a manner to prevent damage, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Leave existing items that are not to be removed and that are not otherwise indicated to be salvaged or reinstalled.
- E. Dismantle: To remove by disassembling or detaching an item from a surface, using gentle methods and equipment to prevent damage to the item and surfaces; disposing of items unless indicated to be salvaged or reinstalled.

1.3 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition waste becomes property of Contractor.
- B. Historic items, relics, antiques, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, and other items of interest or value to Owner that may be uncovered during demolition remain the property of Owner.

1. Carefully salvage in a manner to prevent damage and promptly return to Owner.

1.4 PREINSTALLATION MEETINGS

- A. Predemolition Conference: Conduct conference at Project site and/or online.
 1. Inspect and discuss condition of construction to be selectively demolished.
 2. Review structural load limitations of existing structure.
 3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
 4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
 5. Review areas where existing construction is to remain and requires protection.

1.5 INFORMATIONAL SUBMITTALS

- A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.
- B. Submit fire alarm drawings indicating wiring runs between all devices shown on the construction plans. Plans will be used by contractor during the new work phase to re-install devices removed and salvaged during Phase 1 and Phase 2 demolition and reconnect them to the existing loops, providing new conduit and wiring where existing was removed during Phase 1 and Phase 2 demolition~~install new devices and reconnect them to the existing loops~~. Submitted plans must be approved prior to any fire alarm device, conduit, or wiring being removed.
- C. Qualification Data: For refrigerant recovery technician.
- D. Proposed Protection Measures: Submit report, including Drawings, that indicates the measures proposed for protecting individuals and property, for dust control and, for noise control. Indicate proposed locations and construction of barriers.
- E. Schedule of Selective Demolition Activities: Indicate the following:
 1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's building manager's on-site operations are uninterrupted.
 2. Interruption of utility services. Indicate how long utility services will be interrupted.
 3. Coordination for shutoff, capping, and continuation of utility services.
 4. Use of elevator and stairs.
 5. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.
- F. Predemolition Photographs or Video: Show existing conditions of adjoining construction, including finish surfaces, that might be misconstrued as damage caused by salvage and demolition operations. Comply with Section 013233 "Photographic Documentation." Submit before Work begins.

- G. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.
- H. Warranties: Documentation indicating that existing warranties are still in effect after completion of selective demolition.

1.6 CLOSEOUT SUBMITTALS

- A. Inventory: Submit a list of items that have been removed and salvaged.

1.7 QUALITY ASSURANCE

- A. Refrigerant Recovery Technician Qualifications: Certified by an EPA-approved certification program.

1.8 FIELD CONDITIONS

- A. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- B. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- C. Hazardous Materials: Present in buildings and structures to be selectively demolished. A report on the presence of hazardous materials is on file for review and use. Examine report to become aware of locations where hazardous materials are present.
 - 1. Hazardous material remediation is specified elsewhere in the Contract Documents.
 - 2. Do not disturb hazardous materials or items suspected of containing hazardous materials except under procedures specified elsewhere in the Contract Documents.
 - 3. Owner will provide material safety data sheets for suspected hazardous materials that are known to be present in buildings and structures to be selectively demolished because of building operations or processes performed there.
- D. Storage or sale of removed items or materials on-site is not permitted.
- E. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
 - 1. Maintain fire-protection facilities in service during selective demolition operations.

1.9 COORDINATION

- A. Arrange selective demolition schedule so as not to interfere with Owner's operations.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI/ASSP A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Review Project Record Documents of existing construction or other existing condition and hazardous material information provided by Owner. Owner does not guarantee that existing conditions are same as those indicated in Project Record Documents.
- B. Engage a professional engineer to perform an engineering survey of condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective building demolition operations.
 - 1. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.
- C. Verify that hazardous materials have been remediated before proceeding with building demolition operations.
- D. Survey of Existing Conditions: Record existing conditions by use of measured drawings and preconstruction photographs or video.
 - 1. Inventory and record the condition of items to be removed and salvaged.

3.2 PREPARATION

- A. Refrigerant: Before starting demolition, remove refrigerant from mechanical equipment according to 40 CFR 82 and regulations of authorities having jurisdiction.

3.3 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.
- B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off utility services and mechanical/electrical systems serving areas to be selectively demolished.

1. Arrange to shut off utilities with utility companies and Owner's representative.
2. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
3. Disconnect, demolish, and remove fire-suppression systems, plumbing, and HVAC systems, equipment, and components indicated on Drawings to be removed.
 - a. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
 - b. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material and leave in place.
 - c. Equipment to Be Removed: Disconnect and cap services and remove equipment.
 - d. Equipment to Be Removed and Reinstalled: Disconnect and cap services and remove, clean, and store equipment; when appropriate, reinstall, reconnect, and make equipment operational.
 - e. Equipment to Be Removed and Salvaged: Disconnect and cap services and remove equipment and deliver to Owner.
 - f. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.
 - g. Ducts to Be Abandoned in Place: Cap or plug ducts with same or compatible ductwork material and leave in place.

3.4 PROTECTION

- A. Temporary Protection: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
 2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
 3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
 4. Cover and protect furniture, furnishings, and equipment that have not been removed.
 5. Comply with requirements for temporary enclosures, dust control, heating, and cooling specified in Section 015000 "Temporary Facilities and Controls."
- B. Temporary Shoring: Design, provide, and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
 1. Strengthen or add new supports when required during progress of selective demolition.
- C. Remove temporary barricades and protections where hazards no longer exist.

3.5 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
 2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction.
 3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
 5. Maintain fire watch during and for at least 1/2 hour after flame-cutting operations.
 6. Maintain adequate ventilation when using cutting torches.
 7. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
 8. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
 9. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
 10. Dispose of demolished items and materials promptly.
- B. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
- C. Removed and Salvaged Items:
1. Clean salvaged items.
 2. Pack or crate items after cleaning. Identify contents of containers.
 3. Store items in a secure area until delivery to Owner.
 4. Transport items to Owner's storage area designated by Owner.
 5. Protect items from damage during transport and storage.
- D. Removed and Reinstalled Items:
1. Clean and repair items to functional condition adequate for intended reuse.
 2. Pack or crate items after cleaning and repairing. Identify contents of containers.
 3. Protect items from damage during transport and storage.
 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.
- E. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable,

protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete.

3.6 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

- A. Concrete: Demolish in sections. Cut concrete full depth at junctures with construction to remain and at regular intervals using power-driven saw, and then remove concrete between saw cuts.
- B. Masonry: Demolish in small sections. Cut masonry at junctures with construction to remain, using power-driven saw, and then remove masonry between saw cuts.
- C. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, and then break up and remove.
- D. Resilient Floor Coverings: Remove floor coverings and adhesive according to recommendations in RFCI's "Recommended Work Practices for the Removal of Resilient Floor Coverings."
- E. Roofing: Remove no more existing roofing than what can be covered in one day by new roofing and so that building interior remains watertight and weathertight.
 - 1. Remove existing roof membrane, flashings, copings, and roof accessories.
 - 2. Remove existing roofing system down to substrate.

3.7 DISPOSAL OF DEMOLISHED MATERIALS

- A. Remove demolition waste materials from Project site and dispose of them in an EPA-approved construction and demolition waste landfill acceptable to authorities having jurisdiction. and recycle or dispose of them according to applicable laws and regulations.
 - 1. Do not allow demolished materials to accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
 - 3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
- B. Burning: Do not burn demolished materials.

3.8 CLEANING

- A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 024119

SECTION 230800 - COMMISSIONING OF HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes Cx process requirements for the following HVAC systems, assemblies, and equipment:
 - 1. Heat generation systems.
 - 2. Cooling generation systems.
 - 3. Central-station air-handling systems.
 - 4. Air, steam, and hydronic distribution systems.
 - 5. Heating and cooling terminal and unitary equipment.
 - 6. HVAC controls.
 - 7. TAB verification.
- B. Related Requirements:
 - 1. For construction checklists, comply with requirements in various Division 23 Sections specifying HVAC systems, system components, equipment, and products.

1.3 DEFINITIONS

- A. BAS: Building automation system.
- B. Cx: Commissioning, as defined in Section 019113 "General Commissioning Requirements."
- C. CxA: Commissioning Authority, as defined in Section 019113 "General Commissioning Requirements."
- D. "Systems," "Assemblies," "Subsystems," "Equipment," and "Components": Where these terms are used together or separately, they mean "as-built" systems, assemblies, subsystems, equipment, and components.
- E. TAB: Testing, adjusting, and balancing.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For BAS and HVAC testing technician.

B. Construction Checklists:

1. Draft Cx plan, including draft construction checklists to be prepared by CxA under Section 019113 "General Commissioning Requirements." Div. 23 Subcontractor is to review Construction Checklist in accordance with requirements in Section 019113 "General Commissioning Requirements" and ASHRAE 202 and to resolve any issues with the CxA.
2. Cx plan, including material, installation, and performance construction checklists for systems, assemblies, subsystems, equipment, and components relating to BAS and HVAC to be part of the Cx process and in accordance with requirements in Section 019113 "General Commissioning Requirements and ASHRAE 202."

C. Test Equipment and Instruments: For all test equipment and instruments to be used in conducting Cx tests by Div. 23 Subcontractor, provide the following:

1. Equipment/instrument identification number.
2. Planned Cx application or use.
3. Manufacturer, make, model, and serial number.
4. Calibration history, including certificates from agencies that calibrate the equipment and instrumentation.
5. Equipment manufacturers' proprietary instrumentation and tools. For each instrument or tool, identify the following:
 - a. Instrument or tool identification number.
 - b. Equipment schedule designation of equipment for which the instrument or tool is required.
 - c. Manufacturer, make, model, and serial number.
 - d. Calibration history, including certificates from agencies that calibrate the instrument or tool, where appropriate.

1.5 QUALITY ASSURANCE

A. HVAC Testing Technician Qualifications: Technicians to perform HVAC Construction Checklist verification tests, functional tests, and Cx test demonstrations shall have the following minimum qualifications:

1. Vocational school four-year-program graduate or a Bachelor or Associate's degree in mechanical engineering with coursework related to HVAC systems, air conditioning, Controls, or similar field. Degree may be offset by three years' experience in servicing mechanical systems in the HVAC industry. Generally, required knowledge includes BAS, HVAC systems, electrical concepts, building operations, and application and use of tools and instrumentation to measure performance of HVAC equipment, assemblies, and systems.
2. Commissioning certification from AABC(ACG), NEBB, BCCB (Building Commissioning Certification Board), ASHRAE, or similar professional organization.

B. Testing Equipment and Instrumentation Quality and Calibration:

1. Capable of testing and measuring performance within the specified acceptance criteria.

2. Be calibrated at manufacturer's recommended intervals with current calibration tags permanently affixed to the instrument being used.
3. Be maintained in good repair and operating condition throughout duration of use on Project.
4. Be recalibrated/repared if dropped or damaged in any way since last calibrated.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 Cx PROCESS:

- A. The Cx process shall be designed to test the performance of each HVAC system in actual operating conditions to verify and document that the HVAC systems function as designed in accordance with the specified sequences of operation.
- B. Perform Cx process in accordance with Section 019113 "General Commissioning Requirements" for BAS and HVAC and in accordance with the following:
 1. ASHRAE 202.
 2. Commissioning standards acceptable to the authority having jurisdiction.

3.2 CONSTRUCTION CHECKLISTS

- A. ~~The Commissioning Authority shall prepare~~Prepare preliminary detailed construction checklists (Prefunctional Test Checklists) for each BAS and HVAC system, assembly, subsystem, equipment, and component required to be commissioned, as detailed in ASHRAE 202.
 1. Submit preliminary construction checklists to ~~CxA-Contractor~~ and Designer for review.
 2. When review comments have been resolved, the CxA will provide final construction checklists marked "Approved for Use, (date)."
 3. Use only construction checklists, marked "Approved for Use, (date)" when performing tests. Mark construction checklists in the appropriate place, as indicated Project events are completed and provide pertinent details and other information.
- B. Systems required to be commissioned:
 1. VRF systems including temperature control function, heat recovery functions, and controls.
 2. Air-handling systems, including the following:
 - a. Supply and return air fans, motors, and drives.
 - b. Automatic and gravity dampers.
 - c. ~~Heating and cooling devices.~~Hot water/glycol heating coils.
 - d. Humidification and dehumidification devices.
 - e. Air filters.
 - f. Interlock between air-handling system and fire/smoke alarm system.

~~f.g. VRF cooling coils.~~

3. Air duct systems, including the following:
 - a. VAV boxes and their heating coils.
 - ~~a.b. Motorized dampers.~~
4. Steam and hydronic distribution systems, including the following:
 - a. Steam distribution piping systems and steam traps.
 - b. Cooling coil condensate~~Condensate~~ piping systems, including condensate pumps and all accessories.
 - c. Hydronic piping systems and accessories.
 - d. Pumps and accessories.
 - e. Heat Exchangers.
 - f. Meters and gauges.
 - ~~g. Heat tracing.~~
5. Heating and cooling terminal and unitary equipment, including the following:
 - a. Unit heaters.
 - b. ~~Fan-coil units.~~Convectors.
 - c. Finned-tube radiation.
6. TAB Verification:
 - a. Airflow.
 - b. Water flow.
- ~~7. Documentation:~~
 - ~~a. Mechanical systems manuals.~~
 - ~~b. Documentation of required commissioning.~~

3.3 Cx TESTING PREPARATION

- A. Certify that HVAC instrumentation and control systems have been completed and calibrated, point-to-point checkout has been successfully completed, and systems are operating in accordance with their design sequence of operation, Contract Documents, and approved submittals. Certify that all sensors are operating within specified accuracy and all systems are set to and maintaining set points as required by the design documents.
- B. Certify that TAB procedures have been completed and that TAB reports have been submitted, discrepancies corrected, and corrective work approved.
- C. Set systems, subsystems, and equipment into operating mode to be tested in accordance with approved test procedures (e.g., normal shutdown, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).

3.4 Cx TEST CONDITIONS

- A. Perform tests using design conditions, whenever possible.
 - 1. Simulated conditions may, with approval of Engineer of Record, be imposed using an artificial load when it is impractical to test under design conditions. Set simulated conditions as directed by CxA, and document simulated conditions and methods of simulation. After tests, return configurations and settings to normal operating conditions.
 - 2. Cx test procedures may direct that set points be altered when simulating conditions is impractical.
 - 3. Cx test procedures may direct that sensor values be altered when design or simulating conditions and altering ~~setpoints~~set points are impractical.
- B. If tests cannot be completed because of a deficiency outside the scope of the HVAC system, document the deficiency and report it to Architect. After deficiencies are resolved, reschedule tests.
- C. If seasonal testing is specified, complete appropriate initial performance tests and documentation, and schedule seasonal tests.

3.5 Cx TESTS COMMON TO HVAC SYSTEMS

- A. Measure capacities and effectiveness of systems, assemblies, subsystems, equipment, and components, including operational and control functions, to verify compliance with acceptance criteria.
- B. Test systems, assemblies, subsystems, equipment, and components for operating modes, interlocks, control responses, responses to abnormal or emergency conditions, and response in accordance with acceptance criteria.
- C. Coordinate schedule with, and perform Cx activities at the direction of, CxA.
- D. Provide technicians, instrumentation, tools, and equipment to perform and document the following:
 - 1. Cx Construction Checklist verification tests.
- E. The mechanical contractor and ATC contractors shall provide technicians as needed to support the Functional Testing process, make corrections to equipment, control programming and tuning found to be faulty or performing poorly during functional testing.

3.6 HEATING CONTROL SYSTEM Cx TESTS

3.6A. Heating system control refers to both the glycol/water system and the hot water system.

A.B. Heating-Water Supply Temperature Control:

- 1. Prerequisites: Installation verification of the following:
 - a. Startup of steam to hot-water converter.

- b. Startup of heating-water pump(s).
 - c. TAB of heating-water flow and pressure.
 - d. Input Device: Heating-water supply temperature; thermostat.
 - e. Output Device: Control valve.
 - f. Display the following at the operator's workstation:
 - 1) Heating-water supply temperature.
 - 2) Heating-water supply temperature setpoint ~~set-point~~.
 - 3) Control-valve position(s).
2. Scope: Heating-water system.
 3. Purpose: Control of heating-water supply temperature at input device.
 4. Conditions of the Test:
 - a. Minimum heating-water flow.
 - b. Midrange Heating-Water Flow: 50 to 60 percent of maximum.
 - c. Maximum heating-water flow.
 5. Acceptance Criteria: Under all conditions, heating-water supply temperature is within plus or minus 2.0 deg F of set point.

B.C. Heating-Water Supply Temperature Reset:

1. Prerequisites: Installation verification of the following:
 - a. Startup of steam to hot-water converter.
 - b. Startup of heating-water pump(s).
 - c. TAB of heating-water flow and pressure.
 - d. Input Device: Heating-water supply temperature; thermostat.
 - e. Input Device: Outdoor-air temperature; outdoor-air sensor.
 - f. Output Device: Control valve.
 - g. Display the following at the operator's workstation:
 - 1) Outdoor-air temperature.
 - 2) Heating-water supply temperature.
 - 3) Heating-water supply temperature set point.
 - 4) Control-valve position.
2. Scope: Heating-water system.
3. Purpose: Control of heating-water supply temperature at heating-water supply temperature input device in response to variable outdoor-air temperature input; outdoor-air sensor.
4. Conditions of the Test: Outdoor-air temperature input value may be overridden for this test.
 - a. Low Temperature: Outdoor-air temperature between minus 20 and 0 deg F.
 - b. Midrange Temperature: Outdoor-air temperature between 30 and 45 deg F.
 - c. High Temperature: Outdoor-air temperature above 65 deg F.

5. Acceptance Criteria: Heating-water supply temperature resets in straight-line relationship with outdoor-air temperature for the following reset schedule. Under all conditions, heating-water supply temperature is within 2.0 deg F of set point.
 - a. 195 deg F heating water when outdoor-air temperature is minus 3 deg F.
 - b. 130 deg F heating water when outdoor-air temperature is 65 deg F.
 - c. Under all conditions, heating-water supply temperature is within plus or minus 2.0 deg F of set point.

C.D. Control Primary Circulating Pump(s):

1. Prerequisites: Installation verification of the following:
 - a. Startup of heating-water pump(s).
 - b. Input Device: Outdoor-air temperature; outdoor-air sensor.
 - c. Output Device: Heating-water pump; DDC system command to starter relay.
 - d. Display the following at the operator's workstation:
 - 1) Outdoor-air temperature.
 - 2) Operating status of primary circulating pump(s).
2. Scope: Heating-water pump(s) and associated controls.
3. Purpose: On-off control of heating-water pump(s) in response to variable outdoor-air temperature input; outdoor-air sensor.
4. Conditions of the Test:
 - a. High Temperature: Outdoor-air temperature above 65 deg F.
 - b. Low Temperature: Outdoor-air temperature below 65 deg F.
5. Acceptance Criteria:
 - a. High Temperature: Pump(s) are off when outside-air temperature is above 65 deg F.
 - b. Low Temperature: Pump(s) are on when outside-air temperature is below 65 deg F.

3.7 TERMINAL UNIT EQUIPMENT Cx TESTS

A. VAV Terminal Air Units with Coils:

1. Prerequisites: Installation verification of the following:
 - a. Occupancy Output Device: DDC system binary output.
 - b. Room Temperature Input Device: Room thermostat.
 - c. Room Temperature Output Device: Electronic damper actuators and control-valve operators.
 - d. Display the following at the operator's workstation:
 - 1) Room/area served.
 - 2) Room occupied/unoccupied.

- 3) Room temperature indication.
 - 4) Room temperature set point.
 - 5) Room temperature set point, occupied.
 - 6) Room temperature set point, unoccupied.
 - 7) Air-damper position as percentage open.
 - 8) Control-valve position as percentage open.
2. Scope: VAV terminal air units with hydronic coils in supply-air systems, and associated controls.
 3. Purpose:
 - a. Occupancy-dependent room temperature set-point reset.
 - b. Room temperature control.
 4. Conditions of the Test:
 - a. Cx Test Demonstration Sampling Rate: 10 percent of each model/size unit.
 - b. Temperature Control - Occupied: Start with the room unoccupied. Occupy the room and observe the change to occupied status. Observe temperature control until room temperature is stable at occupied ~~setpoint~~ ~~set-point~~, plus or minus 1.0 deg F.
 - c. Temperature Control - Unoccupied: Start with the room occupied. Vacate the room and observe the change to unoccupied status. Observe temperature control until room temperature is stable at unoccupied ~~setpoint~~ ~~set-point~~, plus or minus 1.0 deg F.
 5. Acceptance Criteria:
 - a. Temperature Control - Occupied:
 - 1) Control system status changes from "occupied" to "unoccupied" after the specified time.
 - 2) Room temperature is stable at occupied set point, plus or minus 1.0 deg F within 10 minutes of occupancy. Room temperature does not overshoot or undershoot set point by more than 2.0 deg F during transition.
 - b. Temperature Control - Unoccupied:
 - 1) Control system status changes from "unoccupied" to "occupied" after five minutes of continuous occupancy.
 - 2) Room temperature is stable at unoccupied set point, plus or minus 1.0 deg F within 30 minutes of occupancy.

3.8 AIR-HANDLING SYSTEM Cx TESTS

3.8A. Each of the air-handling systems include some (but not all) of the following devices. Cx shall test the equipment and control sequences applicable to each AHU.

A.B. Supply Fan(s) Variable-Volume Control:

1. Prerequisites: Installation verification of the following:

- a. Volume-Control Input Device: Static-pressure transmitter sensing supply-duct static pressure referenced to conditioned-space static pressure.
 - b. Volume-Control Output Device: DDC system analog output to modulating damper actuator. Set variable-speed drive to minimum speed when fan is stopped.
 - c. High-Pressure Input Device: Static-pressure transmitter sensing supply-duct static pressure referenced to static pressure outside the duct.
 - d. High-Pressure Output Device: DDC system binary output ~~to~~.
 - e. Display the following at the operator's workstation:
 - 1) Supply-fan-discharge static-pressure indication.
 - 2) Supply-fan-discharge static-pressure set point.
 - 3) Supply-fan airflow rate.
 - 4) Supply-fan speed.
2. Scope: VAV supply fan units and associated controls.
 3. Purpose:
 - a. Supply-air discharge static pressure control.
 - b. Response to excess supply-air discharge static pressure condition.
 4. Conditions of the Test:
 - a. Minimum supply-air flow.
 - b. Midrange Supply-Air Flow: 50 to 60 percent of maximum.
 - c. Maximum supply-air flow.
 - d. Excess supply-air discharge static pressure.
 5. Acceptance Criteria:
 - a. At all supply-air flow rates, and during changes in supply-air flow, discharge air static pressure is at ~~setpoint~~ ~~set point~~ plus or minus 2 percent.
 - b. Fan stops and an alarm is initiated at the operator's workstation when supply-air discharge static pressure is at the excess static pressure, plus or minus 2 percent.

B-C. Air-Handler Outside-Air Control:

1. Prerequisites: Installation verification of the following:
 - a. Output Device: DDC system analog output to modulating damper actuator(s).
 - b. Outside air flow measuring device.
 - c. Supply-Air Temperature Input Device: Duct-mounted temperature sensor.
 - d. Cooling Reset Input Device: Outdoor- and return-air, duct-mounted thermostats.
 - e. Display the following at the operator's workstation:
 - 1) Mixed-air-temperature indication.
 - 2) Mixed-air-temperature ~~setpoint~~ ~~set point~~.
 - 3) Mixed-air damper position.
2. Scope: Air handler with mixed-air control and associated controls.
3. Purpose:

- a. Occupied time control.
 - b. Minimum damper position control.
 - c. Outside Air control in response to CO₂ concentration (Demand Controlled Ventilation).
 - d. Heating reset control.
 - e. Supply-air temperature control.
 - f. Mixed-air temperature control.
 - g. Cooling reset control.
 - h. Unoccupied time control.
4. Conditions of the Test:
- a. Occupied Time Control: Start in unoccupied schedule. Advance to occupied schedule time.
 - b. Minimum Outdoor Damper Position Control: Command system to occupied mode to verify the outside air dampers open to the minimum damper position as balanced. Override CO₂ above baseline concentration and observe outside air damper position.
 - c. Heating Reset Control: Create a call for heating. Raise room thermostat set point to a value 2.0 deg F above current space temperature and observe system response.
 - d. Cooling Reset Control: Create a call for cooling. Lower room thermostat set point to a value 2.0 deg F below current space temperature and observe system response.
 - e. Unoccupied Time Control: Advance to unoccupied schedule time and verify system enters unoccupied mode.
5. Acceptance Criteria:
- a. Occupied Time Control: Mixed-air control is active in occupied mode.
 - b. Minimum Damper Position Control: Controller positions outdoor-air dampers to minimum position.
 - c. Heating Reset Control: Controller sets outdoor-air dampers to minimum position, then modulates the heating coil valve open to maintain space temperature at set point, plus or minus 1.0 deg F.
 - d. Cooling Reset Control: Controller sets outdoor-air dampers to minimum position when outdoor-air enthalpy exceeds return-air enthalpy.
 - e. Unoccupied Time Control: Controller positions outdoor- and relief-air dampers closed and return-air dampers open.
 - f. Control Data Trend Log: Data verify control in accordance with sequence of control.

3.9 ERV AND DOAS UNIT C_x TESTS

A. ERV supply fan(s) constant volume controls.

B. DOAS supply fan(s) constant volume control.

C. When Outside Air is Warm and Humid: DOAS unit dehumidification, liquid subcooling, and hot gas reheat control.

£D. When Outside Air is Cold and Dry: DOAS unit hot water heating control and humidifier control.

END OF SECTION 230800

CODE SUMMARY

THE DESIGN OF THIS PROJECT CONFORMS TO THE FOLLOWING APPLICABLE CODES AND GOVERNMENT REQUIREMENTS:

INTERNATIONAL BUILDING CODE (IBC), 2015 AS AMENDED BY CHAPTER 3 OF THE MAINE UNIFORM BUILDING AND ENERGY CODE (MUBEC)
INTERNATIONAL EXISTING BUILDING CODE (IEBC), 2015 AS AMENDED BY CHAPTER 4 OF THE MUBEC; ADOPTS CHAPTERS 1-16 AND APP A-C BY REFERENCE
INTERNATIONAL ENERGY CONSERVATION CODE (IECC), 2009 AS AMENDED BY CHAPTER 6 OF THE MUBEC
AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR CONDITIONING ENGINEERS (ASHRAE) STANDARDS ADOPTED AS AMENDED BY MUBEC CHAPTER 3 - IBC, CHAPTER 4: IEBC AND CHAPTER 6 - IECC
STATE OF MAINE RULES OF THE STATE FIRE MARSHAL (ME RSFM)
STATE OF MAINE - ASBESTOS REMOVAL
AUGUSTA CODE OF ORDINANCES - PART III GENERAL LEGISLATION


PROJECT DATA

BUILDING AREA: BASEMENT 4,313 SF, FIRST LEVEL 43,364 SF, SECOND LEVEL 44,801 SF, THIRD LEVEL 44,065 SF, FOURTH LEVEL 16,892 SF, FIFTH LEVEL 7,370 SF, TOTAL AREA 161,205 SF
BUILDING HEIGHT: 71 FT
NUMBER OF STORIES: 5 STORIES
FIRE PROTECTION: PARTIALLY SPRINKLERED
BUILDING OCCUPANCIES: IBC, GROUP A-3 ASSEMBLY, GROUP B BUSINESS, GROUP S-1 STORAGE, GROUP F-1 FACTORY
CONSTRUCTION TYPE: TYPE I-B
PROPOSED WORK: ASBESTOS ABATEMENT, MECHANICAL SYSTEM UPGRADES WITH RELATED WORK, ELECTRICAL ROOM WALL REPLACEMENT
ACCESSIBILITY: THE PROJECT IS CONSIDERED AN ALTERATION IN ACCORDANCE WITH... THE COST OF WHICH IS LESS THAN 75% OF THE REPLACEMENT COST OF THE COMPLETED FACILITY...


DELEGATED DESIGN

DELEGATED DESIGN SCOPE OF WORK
CONTRACTOR SHALL PROVIDE DELEGATED DESIGN SERVICES FOR THE PROTECTIVE PLATFORMS AND ENCLOSURES WITHIN THE MUSEUM EXHIBIT AREAS AS DEFINED ON THE DRAWINGS. REFER TO THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR EXHIBIT PROTECTION.
STRUCTURAL REQUIREMENTS
ARCHITECTURAL REQUIREMENTS
OTHER REQUIREMENTS

LEGEND



HAZ MAT LEGEND



ABBREVIATIONS

Table of abbreviations including A/E ARCHITECT/ENGINEER, ACT ACUSTICAL CEILING TILE, ADA AMERICANS WITH DISABILITIES ACT, AFF ABOVE FINISHED FLOOR, ALUM ALUMINUM, APC ACOUSTICAL PANEL CEILING, BAT BATTEN, BD BOARD, BITUM BITUMINOUS, BLDG BUILDING, BOT BOTTOM, BS BOTH SIDES, CAB CABINET, CD CONSTRUCTION DOCUMENTS, CF CONTRACTOR FURNISHED, CF/CI CONTRACTOR FURNISHED/CONTRACTOR INSTALLED, CF/GI CONTRACTOR FURNISHED/GOVERNMENT INSTALLED, CF/OI CONTRACTOR FURNISHED/OWNER INSTALLED, CJ CAST-IN-PLACE CONSTRUCTION JOINT OR CONTROL JOINT, CL CEILING, CLR CLEAR, CMU CONCRETE MASONRY UNIT, COL COLUMN, CONC CONCRETE, CONT CONTINUE, COORD COORDINATE, CT CERAMIC TILE, D DEPTH, DBL DOUBLE, DEG DEGREE, DEMO DEMOLITION, DET DETAIL, DIA DIAMETER, DIM DIMENSION, DOC DOCUMENT, DWG DRAWING, (E) EXISTING, E EAST, EFS EXTERIOR FINISH SYSTEM, EIFS EXTERIOR INSULATION AND FINISH SYSTEM, EJ EXPANSION JOINT, EL ELEVATION, ELEV ELEVATOR, EQ EQUAL, EQUI EQUIPMENT, ET CETERA OR AND SO FORTH, EXIST EXISTING, FD FLOOR DRAIN, FDN FOUNDATION, FE FIRE EXTINGUISHER, FEC FIRE EXTINGUISHER CABINET, FF EL FINISH FLOOR ELEVATION, FF/FE FINISH FLOOR AND EQUIPMENT, FIN FLR FIN FLOOR, FIXT FIXTURE, FLASH FLASHING, FLR FIN FLOOR FINISH, FT FOOT OR FEET, FTG FOOTING, GA GAGE OR GYPSUM ASSOCIATION, GALV GALVANIZED, GC GENERAL CONTRACTOR, GSB GYPSUM SHEATHING BOARD, GYP GYPSUM, CYP BD GYPSUM BOARD, H HIGH, HAZ MAT HAZARDOUS MATERIALS, HM HOLLOW METAL, HORIZ HORIZONTAL, HT HEIGHT, IBC INTERNATIONAL BUILDING CODE, ID INSIDE DIAMETER, IDENTIFICATION OR INTERIOR DESIGN, INCL INCLUDED, INFO INFORMATION, INSUL INSULATION, INT INTERIOR, JAN JANITOR, JAN CLO JANITOR CLOSET, J-BOX JUNCTION BOX, L ANGLE, LAM LAMINATE, LAV LAVATORY, LF LINEAR FEET (FOOT), LLH LONG LEG HORIZONTAL, LLV LONG LEG VERTICAL, LT GA LIGHT GAGE, LOUVER LOUVER, LVR LAYER, MAINT MAINTENANCE, MATL MATERIAL, MAX MAXIMUM, MECH MECHANICAL, MEMB MEMBRANE, MEZZ MEZZANINE, MFR MANUFACTURER, MFR REC MANUFACTURER'S RECOMMENDATION, MISC MISCELLANEOUS, MO MASONRY OPENING, MTL METAL, N NORTH, NA NOT APPLICABLE, NFPA NATIONAL FIRE PROTECTION ASSOCIATION, NIC NOT IN CONTRACT, NO NUMBER, OC ON CENTER, ODD OUTSIDE DIAMETER, OF/CI OWNER FURNISHED/CONTRACTOR INSTALLED, OF/OI OWNER FURNISHED/OWNER INSTALLED, OPP OPPOSITE, OPT OPTIONAL, OSHA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION, PART PARTIAL, PLAM PLASTIC LAMINATE, PLBG PLUMBING, PLYWD PLYWOOD, PR PAIR, PREFAB PREFABRICATE, PT PAINT OR PRESSURE TREATED, PTN PARTITION, QA QUALITY ASSURANCE, QC QUALITY CONTROL, QT QUARRY TILE, R RADIUS, RB RUBBER BASE OR RESILIENT BASE, RCP REFLECTED CEILING PLAN, RD ROOF DRAIN, REF REFERENCE OR REFRIGERATOR, REQ REQUIRE, REQD REQUIRED, RESIL RESILIENT, REV REVISION, RM ROOM, RO ROUGH OPENING, SAT SUSPENDED ACOUSTICAL TILE, SCHED SCHEDULE, SECT SECTION, SF SQUARE FOOT (FEET), SHT SHEET, SIM SIMILAR, SK SKETCH, SPEC SPECIFICATION, SQ IN SQUARE INCH, SST STAINLESS STEEL, STC SOUND TRANSMISSION CLASS STANDARD, STD STEEL, STOR STORAGE, STRUCT STRUCTURAL, SUSP SUSPENDED, SUSP CLG SUSPENDED CEILING SYMBOL, T&G TONGUE AND GROOVE, TEMP TEMPORARY, THK THICKNESS, THRU THROUGH, TO TOP OF, TO FDN TOP OF FOUNDATION, TOB TOP OF BEAM, TOM TOP OF MASONRY, TOP TOP OF PARAPET, TOS TOP OF STEEL, TYP TYPICAL, UFC UNIFORM FIRE CODE, UNO UNLESS NOTED OTHERWISE, VAR VARIES OR VARIATION, VBS VINYL BASE, VCT VINYL COMPOSITION TILE, VERT VERTICAL, VIF VERIFY IN FIELD, VTR VENT THROUGH ROOF, W WEST OR WIDE, WI WITH, W/O WITHOUT, WOOD WOOD, WD WIDE FLANGE, WT WEIGHT, X BRACE CROSS BRACE, YD YARD

PHASE 2 - PROJECT DESCRIPTION

RENOVATION OF THE CULTURAL BUILDING TO REMOVE ASBESTOS CONTAINING MATERIALS AND TO UPGRADE THE MECHANICAL SYSTEMS, ARCHITECTURAL FEATURES, BUILDING SYSTEMS AND DEVICES THROUGHOUT SHALL BE REMOVED AND REINSTALLED TO ACCOMMODATE THE ASBESTOS ABATEMENT ACTIVITIES. ARCHITECTURAL, STRUCTURAL, ELECTRICAL AND BUILDING AUTOMATION SYSTEMS MODIFICATIONS ARE INCLUDED AS NECESSARY TO SUPPORT THE MECHANICAL SYSTEM UPGRADES.
THE PROJECT INCLUDES PROVIDING PROTECTIVE ENCLOSURES FOR PROTECTION OF EXHIBITS REMAINING IN PLACE DURING THE WORK. EXHIBIT PROTECTION SHALL BE CONSTRUCTED PRIOR TO ASBESTOS ABATEMENT ACTIVITIES AND REMAIN IN PLACE FOR THE DURATION OF THE RENOVATION ACTIVITIES.
THE EXISTING BUILDING IS APPROXIMATELY 161,205 SF ON FIVE FLOORS AND A PARTIAL BASEMENT. THE INTERIOR SPACES INCLUDE MUSEUM EXHIBITS, ARCHIVES STORAGE, LIBRARY STACKS, PUBLIC LIBRARY SPACE, PUBLIC RESEARCH SPACE, MEETING SPACE, SEPARATE ADMINISTRATIVE SPACE FOR ALL THREE CULTURAL AGENCIES, A WORKSHOP, A MAILROOM, A LOADING DOCK, AND GENERAL STORAGE. ASBESTOS CONTAINING MATERIAL IS PRESENT THROUGHOUT MUCH OF THE BUILDING, INCLUDING SPRAY-APPLIED FIRE-PROOFING.

GENERAL NOTES

- 1. ALL WORK INCLUDED IN THIS CONTRACT SHALL CONFORM TO ALL STATE, NATIONAL AND OTHER CODES AND ORDINANCES WHICH APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES TO THE ARCHITECT. THE CONTRACTOR SHALL PROCEED WITH THE WORK ONLY AFTER THE DISCREPANCIES HAVE BEEN RESOLVED AND APPROVED BY THE ARCHITECT AND OWNER.
3. THE CONTRACTOR SHALL PROTECT EXISTING SYSTEMS AND SURFACES TO REMAIN. ALL DAMAGE RESULTING FROM THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR REPLACED AS APPROVED BY THE ARCHITECT AT NO ADDITIONAL COST TO THE OWNER.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS WHICH ARE REQUIRED FOR THE SATISFACTORY COMPLETION OF WORK.
5. THE CONTRACTOR SHALL PROVIDE BARRICADES AT ALL WORK AREAS TO PREVENT PERSONNEL FROM ENTERING AREAS OF WORK.
6. THE CONTRACTOR SHALL COORDINATE THE TIMING AND SEQUENCE OF WORK WITH THE OWNER.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND DISPOSAL OF ALL DEMOLITION MATERIALS UNLESS NOTED TO SALVAGE AND TURN OVER TO THE OWNER.
8. COORDINATE CLEANING OF THE WORK AREA WITH ALL APPLICABLE CITY, STATE AND FEDERAL REGULATIONS.
9. EXECUTE WORK IN A CAREFUL AND ORDERLY MANNER WITH LEAST POSSIBLE DISTURBANCE TO THE PUBLIC AND BUILDING OCCUPANTS.
10. DIMENSIONS OF ALL REPLACEMENT MATERIALS SHALL MATCH EXISTING MATERIAL DIMENSIONS, UNLESS NOTED OTHERWISE.

ADDITIVE BID ALTERNATES


- BID ALTERNATE 1: ELECTRICAL: REMOVE EXISTING GENERATOR AND TRANSFER SWITCH. MAINTAIN EXISTING FEEDERS. PROVIDE REPLACEMENT GENERATOR AND TRANSFER SWITCH. CONNECT EXISTING FEEDERS.
BID ALTERNATE 2: REPLACE EXTERIOR DOORS, WINDOWS AND GLAZING SYSTEMS
ARCHITECTURAL: REMOVE EXTERIOR DOORS, WINDOW ASSEMBLIES, AND BLINDS. SALVAGE EXISTING BLINDS FOR REINSTALLATION. PREPARE OPENINGS TO RECEIVE NEW ASSEMBLIES. PROVIDE REPLACEMENT THERMALLY BROKEN WINDOW ASSEMBLIES. REINSTALL SALVAGED BLINDS IN SAME LOCATION AS EXISTING. PROVIDE REPLACEMENT THERMALLY BROKEN CURTAIN WALL SYSTEM. PROVIDE REPLACEMENT INSULATED EXTERIOR ENTRY DOOR ASSEMBLY AT LOADING DOCK.
BID ALTERNATE 3: EXTERIOR VENEER SURFACE REPAIR & JOINT REPOINTING
ARCHITECTURAL: RAKE OUT AND REPOINT GRANITE PANEL HARD JOINTS. RAKE OUT AND REPOINT GRANITE PANEL SOFT SEALANT JOINTS. RAKE OUT AND REPOINT LIMESTONE PANEL HARD JOINTS. RAKE OUT AND REPOINT CONCRETE PANEL SOFT SEALANT JOINTS. RAKE OUT AND REPOINT SURFACE/MATERIAL TRANSITIONS.
BID ALTERNATE 4: EXTERIOR SURFACE CLEANING AND PRESERVATION
ARCHITECTURAL: CLEAN AND PRESERVE LIMESTONE PANELS OF STAINING AND DEGRADATION. PATCH AND REPAIR CRACKED AND DAMAGED CEMENTITIOUS COATING ON CONCRETE SURFACES.
BID ALTERNATE 5: DEDUCT THE SCOPE FOR ABATEMENT AND ASSOCIATED HAZARDOUS MATERIAL DEMOLITION OF FOURTH FLOOR MECHANICAL ROOM 416 IN ITS ENTIRETY.
HAZARDOUS MATERIAL DEMOLITION: REMOVE EXISTING MECHANICAL EQUIPMENT AND ASSOCIATED PIPING, CONTROLS AND DUCTWORK. REMOVE EXISTING LIGHT FIXTURES AND CEILING MOUNTED DEVICES. REMOVE EXISTING CEILING COVERING.
HAZARDOUS ABATEMENT: REMOVE ACM CONTAINING SPRAY-ON FIREPROOFING

WOOD logo, STATE OF MAINE BUREAU OF GENERAL SERVICES, ELIZABETH HUCKKIS, LICENSED ARCHITECT, No. 4338, PHASE 2 - ISSUED FOR BID JANUARY 7, 2022, STATE OF MAINE CULTURAL BUILDING ASBESTOS ABATEMENT & MECHANICAL UPGRADES, PROJECT NO. 3618208720, PROJECT MANAGER: KFM, A/E OF RECORD: EAH, DESIGNED BY: TCM, DRAWN BY: JLR, SHEET TITLE: GENERAL INFORMATION, SHEET ID: G1004B


NOT FOR CONSTRUCTION

SITE ACCESS NOTES:

- SITE ACCESS PLANS ARE CONCEPTUAL IN NATURE AND DO NOT RELIEVE THE CONTRACTOR OF THE PREPARING SITE SPECIFIC PHASING PLANS FOR IMPLEMENTATION OF THE FULL SCOPE OF WORK DEFINED BY THE CONTRACT DOCUMENTS. (REFER TO SPECIFICATION SECTION 01 21 GENERAL CONDITIONS AND 013300 CONSTRUCTION PROGRESS DOCUMENTATION GENERAL REQUIREMENTS FOR CONTRACTOR PHASING RESPONSIBILITY) CONTRACTOR TO SUBMIT FULLY DEVELOPED PHASING PLANS SHOWING FULL SEQUENCE OF CONSTRUCTION.
- A. CONTRACTOR SHALL TAKE WHATEVER STEPS ARE NECESSARY TO PREVENT THE INTERRUPTION OF THE OWNER'S OPERATIONS IN THE OCCUPIED COMPONENTS OF THE BUILDING. SEE DIVISION 01 SPECIFICATIONS FOR COORDINATION/NOTIFICATION REQUIREMENTS.
 - B. REFER TO THE FOLLOWING SPECIFICATIONS FOR GENERAL REQUIREMENTS
 - 1. SECTION 011000 - SUMMARY.
 - 2. SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION.
 - 3. SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS.
 - 4. SECTION 022600 - ASBESTOS ABATEMENT.
 - C. CONTRACT WORK MAY BE SCHEDULED TO OCCUR.
 - 1. WEEKENDS AND HOLIDAYS MAY BE AVAILABLE FOR CONTRACT WORK OF PHASES SHOWN IF PERMITTED BY AND COORDINATED WITH THE OWNERS CONTRACTING OFFICER
 - D. ISOLATE EACH AREA OF ABATEMENT WITH DUST PARTITION AND THE PROVISION OF NEGATIVE AIR PRESSURIZATION. FOLLOW REQUIREMENTS DEFINED IN 022600 ASBESTOS ABATEMENT. REFERENCED SPECIFICATIONS AS WELL AS STATE AND FEDERAL GUIDELINES.
 - E. CONTRACTOR SHALL COORDINATE MECHANICAL, ELECTRICAL, AND PLUMBING (MEP) IMPACTS. CONTRACTOR IS RESPONSIBLE FOR COORDINATING SYSTEM TEMPORARY CONNECTIONS, SHUTDOWNS AND OTHER IMPACTS WITH OWNER'S REPRESENTATIVE.
 - F. REFER TO DEMOLITION AND NEW PLANS FOR ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL WORK INVOLVED WITH PROJECT.
 - G. CONTRACTOR SHALL NOT IMPAIR THE OWNER'S ACCESS AND USE OF THE LOADING DOCK AREA.
 - H. CONTRACTOR SHALL NOT IMPAIR OWNER'S USE AND ACCESS TO THE FRONT ENTRANCE AREA TO EVACUATE THIRD FLOOR EXHIBIT MATERIALS THROUGH THIS AREA.
 - I. MAINTAIN ACCESS TO FIRE LANES FOR EMERGENCY SERVICES. PROVIDE KNOX BOX WITH GATE KEYS TO OWNER, CAPITAL POLICE AND EMERGENCY SERVICES.
 - J. CONTRACTORS TO COORDINATE BUILDING ACCESS WITH OWNER AND OTHER CONTRACTORS.



STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314



2/17/2022


CURRENT ISSUE STATUS:
 PHASE 2 - ISSUED FOR BID
 JANUARY 7, 2022

PROJECT:
 STATE OF MAINE CULTURAL BUILDING
 ASBESTOS ABATEMENT & MECHANICAL UPGRADES

NO.	DATE	REVISION ISSUE DESCRIPTION
B	02-17-2022	ADDENDUM NO. 3
A	01-07-2022	ISSUED FOR BID


PROJECT NO: 3618208720
 PROJECT MANAGER: KFM
 A/E OF RECORD: EAH
 DESIGNED BY: TCM
 DRAWN BY: BEB
 SHEET TITLE:
 BASEMENT LEVEL ACCESS PLAN
 SHEET ID:
 GC100B


NOT FOR CONSTRUCTION



- CONTRACTOR ACCESS STARTING UPON NOTICE TO PROCEED
- CONTRACTOR ACCESS LIMITED TO ESCORT BY OWNER ONLY
- CONTRACTOR ACCESS SHARED WITH OWNER BETWEEN NOTICE TO PROCEED AND 8/15/22. CONTRACTOR ACCESS 8/15/22 AND BEYOND.
- CONTRACTOR ACCESS STARTING 5/15/22
- CONTRACTOR ACCESS STARTING 8/15/22

A1 BASEMENT LEVEL ACCESS PLAN
 3/32" = 1'-0"





SITE ACCESS NOTES:

SITE ACCESS PLANS ARE CONCEPTUAL IN NATURE AND DO NOT RELIEVE THE CONTRACTOR OF THE PREPARING SITE SPECIFIC PHASING PLANS FOR IMPLEMENTATION OF THE FULL SCOPE OF WORK DEFINED BY THE CONTRACT DOCUMENTS. (REFER TO SPECIFICATION SECTION 01 21 GENERAL CONDITIONS AND 013300 CONSTRUCTION PROGRESS DOCUMENTATION GENERAL REQUIREMENTS FOR CONTRACTOR PHASING RESPONSIBILITY) CONTRACTOR TO SUBMIT FULLY DEVELOPED PHASING PLANS SHOWING FULL SEQUENCE OF CONSTRUCTION.

A. CONTRACTOR SHALL TAKE WHATEVER STEPS ARE NECESSARY TO PREVENT THE INTERRUPTION OF THE OWNER'S OPERATIONS IN THE OCCUPIED COMPONENTS OF THE BUILDING. SEE DIVISION 01 SPECIFICATIONS FOR COORDINATION/NOTIFICATION REQUIREMENTS.

B. REFER TO THE FOLLOWING SPECIFICATIONS FOR GENERAL REQUIREMENTS

- SECTION 011000 - SUMMARY
- SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION
- SECTION 016000 - TEMPORARY FACILITIES AND CONTROLS
- SECTION 022600 - ASBESTOS ABATEMENT

C. CONTRACT WORK MAY BE SCHEDULED TO OCCUR

- WEEKENDS AND HOLIDAYS MAY BE AVAILABLE FOR CONTRACT WORK OF PHASES SHOWN IF PERMITTED BY AND COORDINATED WITH THE OWNER'S CONTRACTING OFFICER

D. ISOLATE EACH AREA OF ABATEMENT WITH DUST PARTITION AND THE PROVISION OF NEGATIVE AIR PRESSURIZATION. FOLLOW REQUIREMENTS DEFINED IN 022600 ASBESTOS ABATEMENT. REFERENCED SPECIFICATIONS AS WELL AS STATE AND FEDERAL GUIDELINES.

E. CONTRACTOR SHALL COORDINATE MECHANICAL, ELECTRICAL, AND PLUMBING (MEP) IMPACTS. CONTRACTOR IS RESPONSIBLE FOR COORDINATING SYSTEM TEMPORARY CONNECTIONS, SHUTDOWNS AND OTHER IMPACTS WITH OWNER'S REPRESENTATIVE.

F. REFER TO DEMOLITION AND NEW PLANS FOR ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL WORK INVOLVED WITH PROJECT.

G. CONTRACTOR SHALL NOT IMPAIR THE OWNER'S ACCESS AND USE OF THE LOADING DOCK AREA.

H. CONTRACTOR SHALL NOT IMPAIR OWNER'S USE AND ACCESS TO THE FRONT ENTRANCE AREA TO EVACUATE THIRD FLOOR EXHIBIT MATERIALS THROUGH THIS AREA.

I. MAINTAIN ACCESS TO FIRE LANES FOR EMERGENCY SERVICES. PROVIDE KNX BOX WITH GATE KEYS TO OWNER, CAPITAL POLICE AND EMERGENCY SERVICES.

J. CONTRACTORS TO COORDINATE BUILDING ACCESS WITH OWNER AND OTHER CONTRACTORS.

	CONTRACTOR ACCESS STARTING UPON NOTICE TO PROCEED
	CONTRACTOR ACCESS LIMITED TO ESCORT BY OWNER ONLY
	CONTRACTOR ACCESS SHARED WITH OWNER BETWEEN NOTICE TO PROCEED AND 8/15/22. CONTRACTOR ACCESS 8/15/22 AND BEYOND.
	CONTRACTOR ACCESS STARTING 5/15/22
	CONTRACTOR ACCESS STARTING 8/15/22

A1 FIRST LEVEL ACCESS PLAN
 3/32" = 1'-0"
 0 8' 16' 24'
 PLAN NORTH

wood.
 Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 772-9931 F: (207) 772-9926 www.woodgroup.com

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314


ELIZABETH HUCKINS
 No. 4338
 ARCHITECT
 STATE OF MAINE
 2/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum, 250 State Street, Augusta, ME 04333-0083

PROJECT NO.	3618208720
PROJECT MANAGER:	KFM
A/E OF RECORD:	EAH
DESIGNED BY:	TCM
DRAWN BY:	BEB
SHEET TITLE:	FIRST LEVEL ACCESS PLAN
SHEET ID:	GC101B

NOT FOR CONSTRUCTION



SITE ACCESS NOTES:

SITE ACCESS PLANS ARE CONCEPTUAL IN NATURE AND DO NOT RELIEVE THE CONTRACTOR OF THE PREPARING SITE SPECIFIC PHASING PLANS FOR IMPLEMENTATION OF THE FULL SCOPE OF WORK DEFINED BY THE CONTRACT DOCUMENTS. (REFER TO SPECIFICATION SECTION 01 71 GENERAL CONDITIONS AND 013300 CONSTRUCTION PROGRESS DOCUMENTATION GENERAL REQUIREMENTS FOR CONTRACTOR PHASING RESPONSIBILITY) CONTRACTOR TO SUBMIT FULLY DEVELOPED PHASING PLANS SHOWING FULL SEQUENCE OF CONSTRUCTION.

A. CONTRACTOR SHALL TAKE WHATEVER STEPS ARE NECESSARY TO PREVENT THE INTERRUPTION OF THE OWNER'S OPERATIONS IN THE OCCUPIED COMPONENTS OF THE BUILDING. SEE DIVISION 01 SPECIFICATIONS FOR COORDINATION/NOTIFICATION REQUIREMENTS.

B. REFER TO THE FOLLOWING SPECIFICATIONS FOR GENERAL REQUIREMENTS

- SECTION 011000 - SUMMARY
- SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION
- SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS
- SECTION 022600 - ASBESTOS ABATEMENT

C. CONTRACT WORK MAY BE SCHEDULED TO OCCUR

- WEEKENDS AND HOLIDAYS MAY BE AVAILABLE FOR CONTRACT WORK OF PHASES SHOWN IF PERMITTED BY AND COORDINATED WITH THE OWNER'S CONTRACTING OFFICER

D. ISOLATE EACH AREA OF ABATEMENT WITH DUST PARTITION AND THE PROVISION OF NEGATIVE AIR PRESSURIZATION. FOLLOW REQUIREMENTS DEFINED IN 022600 ASBESTOS ABATEMENT. REFERENCED SPECIFICATIONS AS WELL AS STATE AND FEDERAL GUIDELINES.

E. CONTRACTOR SHALL COORDINATE MECHANICAL, ELECTRICAL, AND PLUMBING (MEP) IMPACTS. CONTRACTOR IS RESPONSIBLE FOR COORDINATING SYSTEM TEMPORARY CONNECTIONS, SHUTDOWNS AND OTHER IMPACTS WITH OWNER'S REPRESENTATIVE.






F. REFER TO DEMOLITION AND NEW PLANS FOR ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL WORK INVOLVED WITH PROJECT.

G. CONTRACTOR SHALL NOT IMPAIR THE OWNER'S ACCESS AND USE OF THE LOADING DOCK AREA.


H. CONTRACTOR SHALL NOT IMPAIR OWNER'S USE AND ACCESS TO THE FRONT ENTRANCE AREA TO EVACUATE THIRD FLOOR EXHIBIT MATERIALS THROUGH THIS AREA.


I. MAINTAIN ACCESS TO FIRE LANES FOR EMERGENCY SERVICES. PROVIDE KNOX BOX WITH GATE KEYS TO OWNER, CAPITAL POLICE AND EMERGENCY SERVICES.

J. CONTRACTORS TO COORDINATE BUILDING ACCESS WITH OWNER AND OTHER CONTRACTORS.

-  CONTRACTOR ACCESS STARTING UPON NOTICE TO PROCEED
-  CONTRACTOR ACCESS LIMITED TO ESCORT BY OWNER ONLY
-  CONTRACTOR ACCESS SHARED WITH OWNER BETWEEN NOTICE TO PROCEED AND 8/15/22. CONTRACTOR ACCESS 8/15/22 AND BEYOND.
-  CONTRACTOR ACCESS STARTING 5/15/22
-  CONTRACTOR ACCESS STARTING 8/15/22


A1 SECOND LEVEL ACCESS PLAN
3/32" = 1'-0"





Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 775-9931 F: (207) 772-9262 www.woods.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314



2/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES

NO.	DATE	REVISION/ISSUE DESCRIPTION
B	02-17-2022	ADDENDUM NO. 3
A	01-07-2022	ISSUED FOR BID
REV		

PROJECT NO: 3618208720

PROJECT MANAGER: KFM

A/E OF RECORD: EAH

DESIGNED BY: TCM


DRAWN BY: BEB

NOT FOR CONSTRUCTION

SHEET TITLE:
SECOND LEVEL ACCESS PLAN

SHEET ID:
GC102B

WOOD ENVIRONMENT & INFRASTRUCTURE SOLUTIONS, INC. 2022. ALL RIGHTS RESERVED. THIS DOCUMENT IS THE PROPERTY OF WOOD ENVIRONMENT & INFRASTRUCTURE SOLUTIONS, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM WOOD ENVIRONMENT & INFRASTRUCTURE SOLUTIONS, INC.



SITE ACCESS NOTES:

SITE ACCESS PLANS ARE CONCEPTUAL IN NATURE AND DO NOT RELIEVE THE CONTRACTOR OF THE PREPARING SITE SPECIFIC PHASING PLANS FOR IMPLEMENTATION OF THE FULL SCOPE OF WORK DEFINED BY THE CONTRACT DOCUMENTS. (REFER TO SPECIFICATION SECTION 01 21 GENERAL CONDITIONS AND 013300 CONSTRUCTION PROGRESS DOCUMENTATION GENERAL REQUIREMENTS FOR CONTRACTOR PHASING RESPONSIBILITY) CONTRACTOR TO SUBMIT FULLY DEVELOPED PHASING PLANS SHOWING FULL SEQUENCE OF CONSTRUCTION.

A. CONTRACTOR SHALL TAKE WHATEVER STEPS ARE NECESSARY TO PREVENT THE INTERRUPTION OF THE OWNER'S OPERATIONS IN THE OCCUPIED COMPONENTS OF THE BUILDING. SEE DIVISION 01 SPECIFICATIONS FOR COORDINATION/NOTIFICATION REQUIREMENTS.

B. REFER TO THE FOLLOWING SPECIFICATIONS FOR GENERAL REQUIREMENTS

- SECTION 011000 - SUMMARY
- SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION
- SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS
- SECTION 022600 - ASBESTOS ABATEMENT

C. CONTRACT WORK MAY BE SCHEDULED TO OCCUR

- WEEKENDS AND HOLIDAYS MAY BE AVAILABLE FOR CONTRACT WORK OF PHASES SHOWN IF PERMITTED BY AND COORDINATED WITH THE OWNER'S CONTRACTING OFFICER

D. ISOLATE EACH AREA OF ABATEMENT WITH DUST PARTITION AND THE PROVISION OF NEGATIVE AIR PRESSURIZATION. FOLLOW REQUIREMENTS DEFINED IN 022600 ASBESTOS ABATEMENT REFERENCED SPECIFICATIONS AS WELL AS STATE AND FEDERAL GUIDELINES.

E. CONTRACTOR SHALL COORDINATE MECHANICAL, ELECTRICAL AND PLUMBING (MEP) IMPACTS. CONTRACTOR IS RESPONSIBLE FOR COORDINATING SYSTEM TEMPORARY CONNECTIONS, SHUTDOWNS AND OTHER IMPACTS WITH OWNER'S REPRESENTATIVE.


F. REFER TO DEMOLITION AND NEW PLANS FOR ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL WORK INVOLVED WITH PROJECT.

G. CONTRACTOR SHALL NOT IMPAIR THE OWNER'S ACCESS AND USE OF THE LOADING DOCK AREA.


H. CONTRACTOR SHALL NOT IMPAIR OWNER'S USE AND ACCESS TO THE FRONT ENTRANCE AREA TO EVACUATE THIRD FLOOR EXHIBIT MATERIALS THROUGH THIS AREA.

I. MAINTAIN ACCESS TO FIRE LANES FOR EMERGENCY SERVICES. PROVIDE KNOX BOX WITH GATE KEYS TO OWNER, CAPITAL POLICE AND EMERGENCY SERVICES.

J. CONTRACTORS TO COORDINATE BUILDING ACCESS WITH OWNER AND OTHER CONTRACTORS.



A1 THIRD LEVEL ACCESS PLAN
3/32" = 1'-0"



wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 752-9931 F: (207) 752-9932 www.woodgroup.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314

ELIZABETH HUCKKIS
No. 4338
STATE OF MAINE
2/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: EAH
DESIGNED BY: TCM
DRAWN BY: BEB


SHEET TITLE:
THIRD LEVEL ACCESS PLAN

SHEET ID:
GC103B

NOT FOR CONSTRUCTION

GENERAL PHASING NOTES:

- SITE ACCESS PLANS ARE CONCEPTUAL IN NATURE AND DO NOT RELIEVE THE CONTRACTOR OF THE PREPARING SITE SPECIFIC PHASING PLANS FOR IMPLEMENTATION OF THE FULL SCOPE OF WORK DEFINED BY THE CONTRACT DOCUMENTS. (REFER TO SPECIFICATION SECTION 01 21 GENERAL CONDITIONS AND 013300 CONSTRUCTION PROGRESS DOCUMENTATION GENERAL REQUIREMENTS FOR CONTRACTOR PHASING RESPONSIBILITY) CONTRACTOR TO SUBMIT FULLY DEVELOPED PHASING PLANS SHOWING FULL SEQUENCE OF CONSTRUCTION.
- A. CONTRACTOR SHALL TAKE WHATEVER STEPS ARE NECESSARY TO PREVENT THE INTERRUPTION OF THE OWNER'S OPERATIONS IN THE OCCUPIED COMPONENTS OF THE BUILDING. SEE DIVISION 01 SPECIFICATIONS FOR COORDINATION/NOTIFICATION REQUIREMENTS.
 - B. REFER TO THE FOLLOWING SPECIFICATIONS FOR GENERAL REQUIREMENTS
 - 1. SECTION 011000 - SUMMARY.
 - 2. SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION.
 - 3. SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS.
 - 4. SECTION 022600 - ASBESTOS ABATEMENT.
 - C. CONTRACT WORK MAY BE SCHEDULED TO OCCUR.
 - 1. WEEKENDS AND HOLIDAYS MAY BE AVAILABLE FOR CONTRACT WORK OF PHASES SHOWN IF PERMITTED BY AND COORDINATED WITH THE OWNER'S CONTRACTING OFFICER.
 - D. ISOLATE EACH AREA OF ABATEMENT WITH DUST PARTITION AND THE PROVISION OF NEGATIVE AIR PRESSURIZATION. FOLLOW REQUIREMENTS DEFINED IN 022600 ASBESTOS ABATEMENT. REFERENCED SPECIFICATIONS AS WELL AS STATE AND FEDERAL GUIDELINES.
 - E. CONTRACTOR SHALL COORDINATE MECHANICAL, ELECTRICAL, AND PLUMBING (MEP) IMPACTS. CONTRACTOR IS RESPONSIBLE FOR COORDINATING SYSTEM TEMPORARY CONNECTIONS, SHUTDOWNS AND OTHER IMPACTS WITH OWNER'S REPRESENTATIVE.
 - F. REFER TO DEMOLITION AND NEW PLANS FOR ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL WORK INVOLVED WITH PROJECT.
 - G. CONTRACTOR SHALL NOT IMPAIR THE OWNER'S ACCESS AND USE OF THE LOADING DOCK AREA.
 - H. CONTRACTOR SHALL NOT IMPAIR OWNER'S USE AND ACCESS TO THE FRONT ENTRANCE AREA TO EVACUATE THIRD FLOOR EXHIBIT MATERIALS THROUGH THIS AREA.
 - I. MAINTAIN ACCESS TO FIRE LANES FOR EMERGENCY SERVICES. PROVIDE KNOX BOX WITH GATE KEYS TO OWNER, CAPITAL POLICE AND EMERGENCY SERVICES.
 - J. CONTRACTORS TO COORDINATE BUILDING ACCESS WITH OWNER AND OTHER CONTRACTORS.



	CONTRACTOR ACCESS STARTING UPON NOTICE TO PROCEED
	CONTRACTOR ACCESS LIMITED TO ESCORT BY OWNER ONLY
	CONTRACTOR ACCESS SHARED WITH OWNER BETWEEN NOTICE TO PROCEED AND 8/15/22. CONTRACTOR ACCESS 8/15/22 AND BEYOND.
	CONTRACTOR ACCESS STARTING 5/15/22
	CONTRACTOR ACCESS STARTING 8/15/22

A1 FOURTH LEVEL ACCESS PLAN
 3/32" = 1'-0"
 0 8' 16' 24'
 PLAN NORTH

wood.
 Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 772-2900 F: (207) 772-2926 www.woodgroup.com

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314

ELIZABETH HUCKINS
 No. 4338
 ARCHITECT
 STATE OF MAINE
 2/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022


STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum, 250 State Street, Augusta, ME 04333-2083

PROJECT NO.	3618208720
PROJECT MANAGER:	KFM
A/E OF RECORD:	EAH
DESIGNED BY:	TCM
DRAWN BY:	BEB
SHEET TITLE:	FOURTH LEVEL ACCESS PLAN
SHEET ID:	GC104B

NOT FOR CONSTRUCTION

SITE ACCESS NOTES:

- SITE ACCESS PLANS ARE CONCEPTUAL IN NATURE AND DO NOT RELIEVE THE CONTRACTOR OF THE PREPARING SITE SPECIFIC PHASING PLANS FOR IMPLEMENTATION OF THE FULL SCOPE OF WORK DEFINED BY THE CONTRACT DOCUMENTS. (REFER TO SPECIFICATION SECTION 01 21 GENERAL CONDITIONS AND 013300 CONSTRUCTION PROGRESS DOCUMENTATION GENERAL REQUIREMENTS FOR CONTRACTOR PHASING RESPONSIBILITY) CONTRACTOR TO SUBMIT FULLY DEVELOPED PHASING PLANS SHOWING FULL SEQUENCE OF CONSTRUCTION.
- A. CONTRACTOR SHALL TAKE WHATEVER STEPS ARE NECESSARY TO PREVENT THE INTERRUPTION OF THE OWNER'S OPERATIONS IN THE OCCUPIED COMPONENTS OF THE BUILDING. SEE DIVISION 01 SPECIFICATIONS FOR COORDINATION/NOTIFICATION REQUIREMENTS.
 - B. REFER TO THE FOLLOWING SPECIFICATIONS FOR GENERAL REQUIREMENTS
 - 1. SECTION 011000 - SUMMARY.
 - 2. SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION.
 - 3. SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS.
 - 4. SECTION 022600 - ASBESTOS ABATEMENT.
 - C. CONTRACT WORK MAY BE SCHEDULED TO OCCUR.
 - 1. WEEKENDS AND HOLIDAYS MAY BE AVAILABLE FOR CONTRACT WORK OF PHASES SHOWN IF PERMITTED BY AND COORDINATED WITH THE OWNERS CONTRACTING OFFICER
 - D. ISOLATE EACH AREA OF ABATEMENT WITH DUST PARTITION AND THE PROVISION OF NEGATIVE AIR PRESSURIZATION. FOLLOW REQUIREMENTS DEFINED IN 022000 ASBESTOS ABATEMENT. REFERENCED SPECIFICATIONS AS WELL AS STATE AND FEDERAL GUIDELINES.
 - E. CONTRACTOR SHALL COORDINATE MECHANICAL, ELECTRICAL, AND PLUMBING (MEP) IMPACTS. CONTRACTOR IS RESPONSIBLE FOR COORDINATING SYSTEM TEMPORARY CONNECTIONS, SHUTDOWNS AND OTHER IMPACTS WITH OWNER'S REPRESENTATIVE.
 - F. REFER TO DEMOLITION AND NEW PLANS FOR ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL WORK INVOLVED WITH PROJECT.
 - G. CONTRACTOR SHALL NOT IMPAIR THE OWNER'S ACCESS AND USE OF THE LOADING DOCK AREA.
 - H. CONTRACTOR SHALL NOT IMPAIR OWNER'S USE AND ACCESS TO THE FRONT ENTRANCE AREA TO EVACUATE THIRD FLOOR EXHIBIT MATERIALS THROUGH THIS AREA.
 - I. MAINTAIN ACCESS TO FIRE LANES FOR EMERGENCY SERVICES. PROVIDE KNOX BOX WITH GATE KEYS TO OWNER, CAPITAL POLICE AND EMERGENCY SERVICES.
 - J. CONTRACTORS TO COORDINATE BUILDING ACCESS WITH OWNER AND OTHER CONTRACTORS.



STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314




ELIZABETH HUCKINS
 No. 4338
 STATE OF MAINE
 2/17/2022

CURRENT ISSUE STATUS:
 PHASE 2 - ISSUED FOR BID
 JANUARY 7, 2022

PROJECT:
 STATE OF MAINE CULTURAL BUILDING
 ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum, 250 State Street, Augusta, ME 04333-0083

NO.	DATE	REVISION/ISSUE DESCRIPTION
B	02-17-2022	ADDENDUM NO. 3
A	01-07-2022	ISSUED FOR BID
REV		


PROJECT NO: 3618208720
 PROJECT MANAGER: KFM
 A/E OF RECORD: EAH
 DESIGNED BY: TCM
 DRAWN BY: BEB
 SHEET TITLE:
 FIFTH LEVEL & ROOF ACCESS PLAN
 SHEET ID:
 GC105B



	CONTRACTOR ACCESS STARTING UPON NOTICE TO PROCEED
	CONTRACTOR ACCESS LIMITED TO ESCORT BY OWNER ONLY
	CONTRACTOR ACCESS SHARED WITH OWNER BETWEEN NOTICE TO PROCEED AND 8/15/22. CONTRACTOR ACCESS 8/15/22 AND BEYOND.
	CONTRACTOR ACCESS STARTING 5/15/22
	CONTRACTOR ACCESS STARTING 8/15/22

A1 FIFTH LEVEL & ROOF ACCESS PLAN
 3/32" = 1'-0"
 PLAN NORTH

NOT FOR CONSTRUCTION



A1 MUSEUM - FIRST LEVEL DEMOLITION PLAN
 1/8" = 1'-0"
 0 4' 8' 16'
 PLAN NORTH

- ### NOTES
- SEE SHEET A-001 FOR DEMOLITION GENERAL NOTES AND LEGEND
 - THE CONTRACTOR SHALL MAINTAIN THE EXISTING STRUCTURAL AND FIREPROOFING INTEGRITY OF THE ENTIRE BUILDING EXCEPT WHERE OTHERWISE NOTED.
 - UPON DISCOVERY OF HAZARDOUS MATERIALS ENCOUNTERED DURING CONSTRUCTION OTHER THAN THAT IDENTIFIED IN THE PROJECT SCOPE, NOTIFY THE DESIGNER AND OWNER IMMEDIATELY AND AWAIT FURTHER INSTRUCTIONS. THE WORK AREA SHALL BE COMPLETELY SEALED OFF DURING ABATEMENT.
 - WORK INCLUDED IN THE CONTRACT IS ILLUSTRATED IN BOLD DASHED LINE WORK. EXISTING CONDITIONS TO REMAIN IS ILLUSTRATED IN LIGHT LINE WORK. UNLESS NOTED OTHERWISE, BOLD-DASHED ITEMS INDICATED SUCH AS: PARTITIONS, DOORS, WINDOWS, EQUIPMENT, ETC. ARE TO BE REMOVED.
 - WHERE THE TERM "REMOVE" IS USED, THE CONTRACTOR SHALL REMOVE FROM THE SITE AND LEGALLY DISPOSE OF.
 - WHERE THE TERM "REUSE" IS USED, THE CONTRACTOR SHALL REUSE THE EQUIPMENT ON THIS PROJECT OR RETURN TO THE OWNER. STORE SALVAGEABLE MATERIALS IN A LOCATION AS DIRECTED BY THE OWNER.
 - WHERE THE TERM "REMOVE AND REINSTALL" IS USED, THE CONTRACTOR IS TO DETACH ITEMS FROM EXISTING CONSTRUCTION, PREPARE THEM FOR REUSE, AND REINSTALL THEM WHERE INDICATED.
 - WHERE THE TERM "EXISTING TO REMAIN" IS USED, THE EXISTING ITEMS OF CONSTRUCTION ARE NOT TO BE REMOVED.
 - SEE HAZMAT REFLECTED CEILING DEMOLITION PLANS (HD1XXX) FOR CEILING DEMOLITION WORK.
 - SEE ENGINEERING DRAWINGS FOR THE REMOVAL OF SPECIFIC STRUCTURAL, MECHANICAL, ELECTRICAL, PLUMBING AND FIRE ALARM SYSTEMS.
 - REINSTALLED EQUIPMENT AND DEVICES ARE TO BE CLEANED OF ALL FOREIGN MATERIAL. REPLACE EQUIPMENT OR DEVICES WHICH ARE DEFECTIVE OR DAMAGED DURING RELOCATION.
 - WHEREVER MECHANICAL, ELECTRICAL, AND PLUMBING DEVICES ARE REMOVED, ALL PIPING AND/OR CONDUITS THAT ARE ABANDONED SHALL BE CAPPED OFF BELOW THE FLOOR, INSIDE THE WALLS, OR ABOVE THE CEILING UNLESS NOTED OTHERWISE. MECHANICAL/ELECTRICAL CONTRACTOR TO REMOVE ALL UNUSED WIRING TO PANEL BOXES. PATCH AND REPAIR FINISHES TO MATCH SURROUNDING FINISHES.
 - REMOVE WALL BASE IN AREAS WHERE FLOORING IS BEING REMOVED.
 - FLOORS AND WALLS: WHERE WALLS OR PARTITIONS THAT ARE REMOVED EXTEND ONE FINISHED AREA INTO ANOTHER, PATCH AND REPAIR FLOOR AND WALL SURFACES IN THE NEW SPACE TO PROVIDE AN EVEN SURFACE OF UNIFORM FINISH, COLOR, TEXTURE, AND APPEARANCE.
 - PATCH FLOOR/FINISH AT LOCATIONS WHERE RADIATOR PIPING HAS BEEN REMOVED.

- ### KEYED NOTES
- REMOVE PORTION OF WALL
 - REMOVE DOOR, FRAME, AND HARDWARE
 - REMOVE EXISTING LOUVER AND EXISTING SCREEN, WHERE OCCURS
 - REMOVE FRAMED GLAZING SYSTEM. REMOVE GWB AND FRAMING AT SPANDREL LOCATION
 - REMOVE LUMBER RACK
 - TEMPORARILY SUPPORT TOILET COMPARTMENTS FOR ABATEMENT ACTIVITY.
 - REMOVE PORTION OF WALL AS REQUIRED FOR ACCESS TO MECHANICAL DUCTS AND PIPING
 - REMOVE RIGID INSULATION AT STEEL FRAMING.

ADDITIVE BID ALTS

SEE SHEET G004B FOR FURTHER BID ALTERNATE INFORMATION

- BID ALTERNATE 2:** REPLACE EXTERIOR DOORS, WINDOWS AND GLAZING SYSTEMS

KEY PLAN

REV	DATE	DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID
		REVISION ISSUE DESCRIPTION

PROJECT NO:	3618208720
PROJECT MANAGER:	KFM
A/E OF RECORD:	EAH
DESIGNED BY:	TCM
DRAWN BY:	JLR
SHEET TITLE:	MUSEUM - FIRST LEVEL DEMOLITION PLAN
SHEET ID:	AD105

Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 742-9931 F: (207) 742-9266 www.woodsolutions.com


STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314

ELIZABETH HUCKINS
 No. 4338
 2/17/2022


PHASE 2 - ISSUED FOR BID
 JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
 ASBESTOS ABATEMENT & MECHANICAL UPGRADES

NOT FOR CONSTRUCTION



D1 LIBRARY - ATRIUM LEVEL CEILING PLAN
1/8" = 1'-0"



A1 LIBRARY - THIRD LEVEL CEILING PLAN
1/8" = 1'-0"

- ### NOTES
- SEE SHEET A-001 FOR SYMBOLS, LEGENDS AND GENERAL NOTES
 - CENTER CEILING GRID IN SPACE UNLESS NOTED OTHERWISE
 - CENTER NEW EQUIPMENT AND DEVICES IN CEILING TILE UNLESS NOTED OTHERWISE
 - REINSTALL SUSPENDED CEILING TILE REMOVED FOR INSULATION UPGRADES, MECHANICAL, ELECTRICAL, AND TELECOMMUNICATIONS WORK. IF TILES OR CEILING SYSTEM ARE DAMAGED DURING WORK, REPLACE IN KIND.
 - COORDINATE WITH MECHANICAL AND ELECTRICAL REQUIREMENTS FOR LOCATION OF ACCESS PANELS. LOCATIONS SHALL BE REVIEWED AND APPROVED BY THE OWNER.
 - CEILING HEIGHT SHALL BE 9'-0" AFF UNO.
 - "OPEN" REFERS TO OPEN TO STRUCTURE ABOVE.
 - IN AREAS NOTED TO PAINT EXPOSED STRUCTURE OVERHEAD, PAINT STRUCTURE, EQUIPMENT AND FIREPROOFING WHERE OCCURS.

- ### KEYED NOTES
- 52 2' X 2' SUSPENDED ACOUSTIC PANEL CEILING SYSTEM, FACTORY WHITE UNO
 - 55 SUSPENDED METAL FRAMED CEILING WITH 5/8" GYPSUM BOARD FINISH, PAINTED
 - 56 METAL FRAMED SOFFIT WITH 5/8" GYPSUM BOARD FINISH, PAINTED



STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314

ELIZABETH HUCKINS
No. 4338
STATE OF MAINE
2/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

PROJECT:
STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: EAM
DESIGNED BY: TCM
DRAWN BY: JLR


SHEET TITLE:
LIBRARY - THIRD AND ATRIUM LEVEL REFLECTED CEILING PLANS

SHEET NO:
AE122


wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 752-9931 F: (207) 752-9932 www.woodeng.com

MADE AND DATED UNDER THE PROFESSIONAL SEAL AND LICENSE OF THE ARCHITECT AS SHOWN ON THESE PLANS. THE SEAL AND LICENSE OF THE ARCHITECT ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM.

NOT FOR CONSTRUCTION



D1 ARCHIVES - ATRIUM LEVEL CEILING PLAN
1/8" = 1'-0"




A1 ARCHIVES - THIRD LEVEL CEILING PLAN
1/8" = 1'-0"


- ### NOTES
- SEE SHEET A-001 FOR SYMBOLS, LEGENDS AND GENERAL NOTES
 - CENTER CEILING GRID IN SPACE UNLESS NOTED OTHERWISE
 - CENTER NEW EQUIPMENT AND DEVICES IN CEILING TILE UNLESS NOTED OTHERWISE
 - REINSTALL SUSPENDED CEILING TILE REMOVED FOR INSULATION UPGRADES, MECHANICAL, ELECTRICAL, AND TELECOMMUNICATIONS WORK. IF TILES OR CEILING SYSTEM ARE DAMAGED DURING WORK, REPLACE IN KIND.
 - COORDINATE WITH MECHANICAL AND ELECTRICAL REQUIREMENTS FOR LOCATION OF ACCESS PANELS. LOCATIONS SHALL BE REVIEWED AND APPROVED BY THE OWNER.
 - CEILING HEIGHT SHALL BE 9'-0" AFF UNO.
 - "OPEN" REFERS TO OPEN TO STRUCTURE ABOVE.
 - IN AREAS NOTED TO PAINT EXPOSED STRUCTURE OVERHEAD, PAINT STRUCTURE, EQUIPMENT AND FIREPROOFING WHERE OCCURS.

KEYED NOTES

- 2' X 2' SUSPENDED ACOUSTIC PANEL CEILING SYSTEM, FACTORY WHITE UNO


KEY PLAN





Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 752-9931 F: (207) 752-9932 www.woods.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314



ELIZABETH HUCKLEBS
No. 4338
2/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-2083

REV	DATE	REVISION DESCRIPTION
B	02-17-2022	ADDENDUM NO. 3
A	01-07-2022	ISSUED FOR BID

PROJECT NO:	3618208720
PROJECT MANAGER:	KFM
A/E OF RECORD:	EAH
DESIGNED BY:	TCM
DRAWN BY:	JLR
SHEET TITLE:	ARCHIVES - THIRD AND ATRIUM LEVEL REFLECTED CEILING PLANS
SHEET ID:	AE124


NOT FOR CONSTRUCTION

NOTES


- SEE SHEET A-001 FOR SYMBOLS, LEGENDS AND GENERAL NOTES
- CENTER CEILING GRID IN SPACE UNLESS NOTED OTHERWISE
- CENTER NEW EQUIPMENT AND DEVICES IN CEILING TILE UNLESS NOTED OTHERWISE
- REINSTALL SUSPENDED CEILING TILE REMOVED FOR INSULATION UPGRADES, MECHANICAL, ELECTRICAL, AND TELECOMMUNICATIONS WORK. IF TILES OR CEILING SYSTEM ARE DAMAGED DURING WORK, REPLACE IN KIND
- COORDINATE WITH MECHANICAL AND ELECTRICAL REQUIREMENTS FOR LOCATION OF ACCESS PANELS. LOCATIONS SHALL BE REVIEWED AND APPROVED BY THE OWNER.
- CEILING HEIGHT SHALL BE 9'-0" AFF UNO.
- "OPEN" REFERS TO OPEN TO STRUCTURE ABOVE.
- IN AREAS NOTED TO PAINT EXPOSED STRUCTURE OVERHEAD, PAINT STRUCTURE, EQUIPMENT AND FIREPROOFING WHERE OCCURS.

KEYED NOTES


57 METAL FRAMED SOFFIT WITH 5/8" EXTERIOR - GRADE GYPSUM BOARD FINISH, PAINTED



A1 MUSEUM - FIFTH LEVEL REFLECTED CEILING PLAN
1/8" = 1'-0"



KEY PLAN



STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314



LICENSED ARCHITECT
ELIZABETH HUCKINS
No. 4338
2/17/2022

CURRENT ISSUE STATUS:
PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022
PROJECT:
STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-2083

REV	REVISION ISSUE DESCRIPTION	DATE
B	ADDENDUM NO. 3	02-17-2022
A	ISSUED FOR BID	01-07-2022

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: EAH
DESIGNED BY: TCM
DRAWN BY: JLR
SHEET TITLE:
MUSEUM - FIFTH LEVEL REFLECTED CEILING PLAN


SHEET ID:
AE129

NOT FOR CONSTRUCTION

wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 742-9931 F: (207) 742-9932 www.woodage.com

SCALE AND DATE: THIS DRAWING COPY, PROVIDED BY THE OFFICE, MAY BE UTILIZED FOR BIDDING OR CONSTRUCTION PURPOSES. CONSULT THE ORIGINAL DRAWING FOR ANY CHANGES.


NO. 2022-01-07-2022 - AE Cultural Building Mechanical Upgrades 2022-01-07-2022_AE129.rvt




D1 SOUTH ELEVATION - MUSEUM
3/32" = 1'-0"

- KEYED NOTES**
- BID ALT 2 - REPLACEMENT OF NON-THERMALLY BROKEN WINDOW / WINDOW WALL ASSEMBLIES WITH THERMALLY BROKEN STOREFRONT ASSEMBLIES. SEE SHEET AE621.
 - BID ALT 2 - REPLACEMENT OF NON-THERMALLY BROKEN WINDOW / WINDOW WALL ASSEMBLIES WITH THERMALLY BROKEN CURTAINWALL ASSEMBLIES. SEE SHEET AE622.
 - PENINSULA LOCATION - REMOVE EXISTING PANEL AND ADJACENT PANELS INTERSECTING WITH BEVELED EDGES - RESET ALL 3 SIDES, SO AS TO RESET/ REALIGN MITTERED EDGE AND ANCHORING. SEE E1/AE701.
 - REMOVE EXISTING PANELS - USE CARE REMOVING EXISTING PANELS SO AS TO PRESERVE FOR OTHER AS NEEDED CONDITIONS - RETAIN BY OWNER. CLEAN / CLEAR EXPOSED AREAS. PREP TO RECEIVE NEW PANEL(S). RESET / REALIGN, SET AND ANCHOR, IN SO FAR AS PRACTICAL WITH ADJACENT EDGES OF UNDISTURBED PANELS. MATCH EXISTING MORTAR / SEALANT & ROD JOINTS, RAKE AND REPOINT - SEE E5 & D5/AE531. AS ADDITIONAL REFERENCE SEE E1/AE701.
 - RAKE OUT AND REPOINT GRANITE PANEL 1/4" MORTAR JOINTS - REFER TO DETAIL E5/AE531
 - RAKE OUT AND REPOINT GRANITE PANEL 3/4" ROD AND SEALANT JOINTS - SEE F5/AE531
 - RAKE OUT AND REPOINT LIMESTONE PANEL 1/4" MORTAR JOINTS - SEE F5/AE531
 - RAKE OUT AND REPOINT LIMESTONE PANEL 3/4" ROD AND SEALANT JOINTS - SEE F5/AE531
 - RAKE OUT AND REPOINT CONCRETE PANEL ROD AND SEALANT JOINTS - SEE D5/AE531
 - RAKE OUT AND REPOINT SURFACE MATERIAL TRANSITIONS (REFER TO GENERAL NOTE #5 AND PHOTO DETAIL # E1/AE701)
 - CLEAN LIMESTONE PANELS, IN SO FAR AS PRACTICAL AND CARE, REMOVE ANY AND ALL STAINING.
 - PATCH AND REPAIR CRACKED AND DAMAGED CEMENTITIOUS COATING ON CONCRETE SURFACES - PAINT FINISH
 - REMOVE DAMAGED PANEL - REPLACE WITH NEW PANEL - SET / MATCH ALIGN WITH EXISTING AND REPOINT.
 - NEW EIFS WALL SYSTEM - SEE ELEVATIONS FOR CONTROL JOINTS
 - NEW SOFFIT - MATCH EXISTING COLOR/TEXTURE AND JOINERY - SEE WALL SECTION A4/AE301.
 - RAKE AND REPOINT ROD AND SEALANT JOINTS AT SCUPPERS - SEE B1/AE531
 - RESERVED

- BID ALTERNATES**
- SEE SHEET G1004B FOR FURTHER BID ALTERNATE INFORMATION
- BID ALTERNATE 2: REPLACE EXTERIOR FENESTRATION
 - BID ALTERNATE 3: HARD SURFACE REPAIR : LIMESTONE, CONCRETE, GRANITE
 - BID ALTERNATE 4: HARD SURFACE CLEANING : LIMESTONE, CONCRETE, GRANITE



A1 SOUTH ELEVATION LIBRARY & ARCHIVES
3/32" = 1'-0"



wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 749-9001 F: (207) 742-9262 www.woodgroup.com

LeMessurier.

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314

REGISTERED ARCHITECT
DANIEL C. MORENO
No. 2409


PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

PROJECT: STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-0083


REV	DATE	REVISION / ISSUE DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: DCM
DESIGNED BY: PDG
DRAWN BY: GJM
SHEET TITLE: EXTERIOR ELEVATIONS
SHEET ID: AE202

NOT FOR CONSTRUCTION



D1 EAST ELEVATION
 3/32" = 1'-0"
 0 8' 16' 24'



A1 WEST ELEVATION
 3/32" = 1'-0"
 0 8' 16' 24'

NOTES

KEYED NOTES

21. BID ALT 2 - REPLACEMENT OF NON-THERMALLY BROKEN WINDOW / WINDOW WALL ASSEMBLIES WITH THERMALLY BROKEN STOREFRONT ASSEMBLIES. SEE SHEET AE21.
22. BID ALT 2 - REPLACEMENT OF NON-THERMALLY BROKEN WINDOW / WINDOW WALL ASSEMBLIES WITH THERMALLY BROKEN CURTAINWALL ASSEMBLIES. SEE SHEET AE22.
23. PENINSULA LOCATION - REMOVE EXISTING PANEL AND ADJACENT PANELS INTERSECTING WITH BEVELED EDGES - RESET ALL 3 SIDES. SO AS TO RESET/ REALIGN MITTERED EDGE AND ANCHORING. SEE E1/AE701.
24. REMOVE EXISTING PANELS - USE CARE REMOVING EXISTING PANELS SO AS TO PRESERVE FOR OTHER AS NEEDED CONDITIONS - RETAIN BY OWNER. CLEAN / CLEAR EXPOSED AREAS. PREP TO RECEIVE NEW PANEL(S). RESET / REALIGN, SET AND ANCHOR. IN SO FAR AS PRACTICAL WITH ADJACENT EDGES OF UNDISTURBED PANELS. MATCH EXISTING MORTAR, SEALANT & ROD JOINTS, RAKE AND REPOINT - SEE E5 & D5/AE531. AS ADDITIONAL REFERENCE SEE E1/AE701.
25. RAKE OUT AND REPOINT GRANITE PANEL 1/4" MORTAR JOINTS - REFER TO DETAIL E5/AE531
26. RAKE OUT AND REPOINT GRANITE PANEL 3/4" ROD AND SEALANT JOINTS - SEE F5/AE531
27. RAKE OUT AND REPOINT LIMESTONE PANEL 1/4" MORTAR JOINTS - SEE E5/AE531
28. RAKE OUT AND REPOINT LIMESTONE PANEL 3/4" ROD AND SEALANT JOINTS - SEE F5/AE531
29. RAKE OUT AND REPOINT CONCRETE PANEL ROD AND SEALANT JOINTS - SEE D5/AE531
30. RAKE OUT AND REPOINT SURFACE MATERIAL TRANSITIONS (REFER TO GENERAL NOTE #5 AND PHOTO DETAIL # E1/AE701)
31. CLEAN LIMESTONE PANELS, IN SO FAR AS PRACTICAL AND CARE. REMOVE ANY AND ALL STAINING.
32. PATCH AND REPAIR CRACKED AND DAMAGED CEMENTITIOUS COATING ON CONCRETE SURFACES - PAINT FINISH
33. REMOVE DAMAGED PANEL - REPLACE WITH NEW PANEL - SET / MATCH ALIGN WITH EXISTING AND REPOINT.
34. NEW EIFS WALL SYSTEM - SEE ELEVATIONS FOR CONTROL JOINTS
35. NEW SOFFIT - MATCH EXISTING COLOR/TEXTURE AND JOINERY - SEE WALL SECTION A4/AE301.
36. RAKE OUT AND REPOINT ROD AND SEALANT JOINTS AT SCUPPERS - SEE B1/AE531
37. RESERVED

BID ALTERNATES

- SEE SHEET G1004B FOR FURTHER BID ALTERNATE INFORMATION
2. **BID ALTERNATE 2:**
REPLACE EXTERIOR FENESTRATION
 3. **BID ALTERNATE 3:**
HARD SURFACE REPAIR: LIMESTONE, CONCRETE, GRANITE
 4. **BID ALTERNATE 4:**
HARD SURFACE CLEANING: LIMESTONE, CONCRETE, GRANITE

wood.
 Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 775-2601 F: (207) 772-7246 www.woodgroup.com

LeMessurier.

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEAWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314


DANIEL C. MORENO
 No. 2409
 02/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES

REV	DATE	DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID
REV		REVISION ISSUE DESCRIPTION


PROJECT NO: 3618208720
 PROJECT MANAGER: KFM
 A/E OF RECORD: DCM
 DESIGNED BY: PDG
 DRAWN BY: GJN
 SHEET TITLE: EXTERIOR ELEVATIONS
 SHEET ID: AE203




NOT FOR CONSTRUCTION

NOTE

1. SEE A-001 FOR GENERAL NOTES, LEGENDS AND SYMBOLS



D1 BUILDING SECTION
3/8" = 1'-0"
0 2' 4' 6'




A1 BUILDING SECTION
1/4" = 1'-0"
0 2' 4' 6'

wood.

Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 752-9931 F: (207) 752-9932 www.woodsolutions.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314



2/17/2022


CURRENT ISSUE STATUS:
PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022
PROJECT:
STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-2083

REV	DATE	REVISION ISSUE DESCRIPTION
B	02-17-2022	ADDENDUM NO. 3
A	01-07-2022	ISSUED FOR BID


PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: EAH
DESIGNED BY: TCM
DRAWN BY: JLR
SHEET TITLE:
PARTIAL BUILDING SECTIONS
SHEET ID:
AE312

NOT FOR CONSTRUCTION


WOODSOLUTIONS.COM




D1 SECTION
3" = 1'-0"




D2 SCIENCE LAB 406 - A
3/8" = 1'-0"




D4 SCIENCE LAB 406 - B
3/8" = 1'-0"




D6 SCIENCE LAB 406 - C
3/8" = 1'-0"




B1 CEILING SUPPORT w/ CHANNEL AND COVER TRIM
1 1/2" = 1'-0"




B2 SECTION
1 1/2" = 1'-0"



A1 SECTION DETAIL @ SOFFIT
1 1/2" = 1'-0"



A2 CORNER SOFFIT @ FIRST FLOOR
1 1/2" = 1'-0"



A5 ENCAPSULATION WALL DETAIL
1 1/2" = 1'-0"

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314




ELIZABETH HUCKINS
No. 4338
2/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022
STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES

PROJECT NO.	3618208720
PROJECT MANAGER:	KFM
A/E OF RECORD:	EAM
DESIGNED BY:	TCM
DRAWN BY:	SMB
SHEET TITLE:	INTERIOR DETAILS
SHEET ID:	AE512


NOT FOR CONSTRUCTION

wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 775-9931 F: (207) 772-9262 www.woodeng.com




D1 ENCAPSULATION WALL
1 1/2" = 1'-0"


PERMANENT, SOLID BARRIERS TO BE CONSTRUCTED FROM EXISTING CEILING SURFACES TO FLOOR DECK ABOVE TO ISOLATE AREAS NOT INCLUDED IN THE OVERALL ABATEMENT WORK. SEE ARCHITECTURAL DRAWINGS FOR ADDITIONAL INFORMATION. IN ADDITION TO SOLID BARRIERS, AIR-TIGHT POLYETHYLENE (POLY) BARRIERS (COMPRISED OF A MINIMUM OF TWO LAYERS OF SIX-MIL POLY) SHALL BE INSTALLED. WARNING SIGNS (OSHA 1910.1001 (J)(4)(II)) SHALL BE POSTED AT EIGHT-FOOT INTERVALS ON THE EXPOSED SURFACE OF THE BARRIERS




C1 ENCAPSULATION WALL
1 1/2" = 1'-0"




A1 ENCAPSULATION WALL
1 1/2" = 1'-0"



C3 GUARDRAIL DETAIL
1 1/2" = 1'-0"



C5 HANDRAIL DETAIL
1 1/2" = 1'-0"




A3 UNISTRUT GRID DETAIL
1 1/2" = 1'-0"

wood.

Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 775-9991 F: (207) 775-9992 www.woodpe.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314



2/17/2022

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES


REV	DATE	DESCRIPTION
B	02-17-2022	ADDENDUM NO. 3
A	01-07-2022	ISSUED FOR BID

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: EAH
DESIGNED BY: TCM
DRAWN BY: SMB
SHEET TITLE: INTERIOR DETAILS

SHEET ID: AE513

NOT FOR CONSTRUCTION


WOOD ENVIRONMENT & INFRASTRUCTURE SOLUTIONS, INC. 2022



- ### NOTES
- SEE SHEET A - 001 FOR SYMBOLS, LEGENDS AND GENERAL NOTES.
 - ALL FLOOR CONSTRUCTION AND ASSOCIATED SECONDARY MEMBERS SHALL RECEIVE A FIRE-RESISTANCE RATING OF 2 HOURS UNLESS NOTED OTHERWISE.
 - ALL ROOF CONSTRUCTION AND ASSOCIATED SECONDARY MEMBERS SHALL RECEIVE A FIRE-RESISTANCE RATING OF 1 HOUR UNLESS NOTED OTHERWISE.
 - ALL BEARING WALLS AND PRIMARY STRUCTURAL FRAMES SHALL RECEIVE A FIRE-RESISTANCE RATING OF 2 HOURS UNLESS NOTED OTHERWISE.

○ ADDITIVE BID ALTS

- ### LEGEND
- [Solid Grey] SPRAY APPLIED FIREPROOFING ON STEEL ONLY
 - [Diagonal Hatching] SPRAY APPLIED FIREPROOFING ON STEEL AND DECKING
 - [Cross-hatching] EXISTING SPRAY APPLIED FIREPROOFING
 - [Vertical Hatching] 3" MINERAL FIBER-BOARD ON DECK AND STEEL
 - [Grid Hatching] EXISTING ASBESTOS CONTAINING SPRAY APPLIED FIREPROOFING TO REMAIN



A1 MUSEUM - THIRD LEVEL FIREPROOFING PLAN
 1/8" = 1'-0"
 0 4' 8' 16'
 PLAN NORTH

WOOD ENVIRONMENT & INFRASTRUCTURE SOLUTIONS, INC.
 11 CONGRESS ST., SUITE 200, PORTLAND, ME 04101
 P: (207) 752-9931 F: (207) 752-9932 WWW.WOOD-ES.COM

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314

CURRENT ISSUE STATUS: PHASE 2 - ISSUED FOR BID
 JANUARY 7, 2022

PROJECT: STATE OF MAINE CULTURAL BUILDING
 ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-0083

REV	DATE	REVISION ISSUE DESCRIPTION
A	02-17-2022	ADDENDUM NO. 3

PROJECT NO: 3618208720
 PROJECT MANAGER: KFM
 A/E OF RECORD: EAH
 DESIGNED BY: TCM
 DRAWN BY: JLR
 SHEET TITLE: MUSEUM - THIRD LEVEL FIREPROOFING PLAN
 SHEET ID: AK107

NOT FOR CONSTRUCTION

ABBREVIATIONS


@	AT	EXIST	EXISTING	NC	NORMALLY CLOSED, NOISE CRITERIA
A	AMP	EXT	EXPANSION TANK	NEC	NATIONAL ELECTRICAL CODE NFPA 70
ABS	ACRYLONITRILE BUTADIENE STYRENE PLASTIC	EXP	EXPANSION	NG	NATURAL GAS
ABV	ABOVE	F	FAN, DEGREES FAHRENHEIT	NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
AC	AIR CONDITIONING, AIR COMPRESSOR	FA	FRESH AIR	NIFRA	NOT IN CONTRACT
ADA	AMERICANS WITH DISABILITIES ACT	FAI	FRESH AIR INTAKE	NO	NORMALLY OPEN, NUMBER
AD	ACCESS DOOR	FBG	FURNISHED BY GOVERNMENT	NO2	NITROGEN DIOXIDE
AF	AIR FILTER	FC	FLEX CONNECTION	NTS	NOT TO SCALE
AFF	ABOVE FINISHED FLOOR	FCO	FLOOR CLEANOUT	OA	OUTSIDE AIR
AHM	AIR FLOW MEASURING STATION	FD	FIRE DAMPER, FLOOR DRAIN	OAF	OUTSIDE AIR FILTER, OUTSIDE AIR FAN
AHU	AIR HANDLING UNIT	FF	FINISH FLOOR	OAI	OUTSIDE AIR INTAKE
AL	ACOUSTICAL LINER	FX	FIXTURE	OAT	OUTSIDE AIR TEMPERATURE
AMB	AMBIENT	FLA	FULL LOAD AMPS	OBVD	OPPOSED BLADE VOLUME DAMPER
AP	ACCESS PANEL	FLR	FLOOR	OD	OUTSIDE DIAMETER
APD	AIR PRESSURE DROP	FOB	FLAT ON BOTTOM	OED	OPEN ENDED DUCT
APPROX	APPROXIMATELY	FOT	FLAT ON TOP	OS&Y	OUTSIDE STEM AND YOKE
AS	AIR SEPARATOR	FS	FLOAT SWITCH	P	PUMP, PITCH
ASME	AMERICAN SOCIETY OF MECHANICAL ENGINEERS	FSD	FIRE-SMOKE DAMPER	PC	PUMPED CONDENSATE
ASSY	ASSEMBLY	FT	FEET	PD	PRESSURE DROP
ATC	AUTOMATIC TEMPERATURE CONTROL	FZ	FREEZE/STAT	PLMB	PLUMBING
ATT	ACOUSTICAL ATTENUATOR	G	GAS	PRESS	PRESSURE
AV	AUTOMATIC VENT	GA	GAUGE	PRV	PRESSURE REDUCING VALVE
BDD	BACKDRAFT DAMPER	GAL	GALLONS	PSIG	POUNDS PER SQUARE INCH GAUGE
BFP	BACKFLOW PREVENTER	GALV	GALVANIZED	PT	PRESSURE TREATED
BHP	BRAKE HORSEPOWER	GC	GENERAL CONTRACTOR	PVC	POLYVINYL CHLORIDE
BLDG	BUILDING	GMU	GLYCOL MAKEUP UNIT	QTY	QUANTITY
BOD	BOTTOM OF DUCT	GPP	GLYCOL RETURN	(R)	REMOVE
BTUH	BTU PER HOUR	GPH	GALLONS PER HOUR	R	RADIUS, RETURN
CA	CENTERLINE	GPM	GALLONS PER MINUTE	RA	RETURN AIR
CA	COMPRESSED AIR	GR	GENERAL PURPOSE	RAD	RADIATOR
CAP	CAPACITY	GRH	GRAVITY RELIEF HOOD	RAF, RF	RETURN AIR FAN
CC	COOLING COIL	GHWR	GLYCOL HOT WATER RETURN	RAT	RETURN AIR TEMPERATURE
CD	CONDENSATE DRAIN	GHWS	GLYCOL HOT WATER SUPPLY	REL	RELIEF
CF	CUBIC FEET	GV	GATE VALVE	REQD	REQUIRED
CFM	CUBIC FEET PER MINUTE	GSM	GALVANIZED SHEET METAL	RET	RETURN
CH	CHILLER	GYP	GYPSPUM WALLBOARD	RH	RELATIVE HUMIDITY
CHWR	CHILLED WATER RETURN	HC	HEATING COIL	RI	REFRIGERANT LIQUID
CHWS	CHILLED WATER SUPPLY	HOA	HANDS-OFF-AUTOMATIC	RLA	RATED LOAD AMPS
CLG	CEILING	HOR	HORIZONTAL	RM	ROOM
CO	CLEAN OUT, CARBON MONOXIDE	HPS	HORSEPOWER, HIGH PRESSURE	RPM	REVOLUTIONS PER MINUTE
COL	COLUMN	HR	HOUR	RS	REFRIGERANT SUCTION
CONC	CONCRETE	HT	HEIGHT	RTU	ROOFTOP UNIT
COND	CONDENSATE	HUMID	HUMIDIFIER, HUMIDITY	S	SUPPLY DIFFUSER
CONN	CONNECTION	HV	HEATING AND VENTILATING/CONDITIONING	SA	SUPPLY AIR
CONT	CONTINUATION	HVAC	HEATING, VENTILATING AND AIR	SCH	SCHEDULE
CONV	CONVECTOR	HW	HOT WATER	SCR	SCREEN
CP	CONTROL PANEL, CONDENSATE PUMP	HWR	HOT WATER RETURN	SD	SMOKE DAMPER
CPT	CONDENSATE PUMP TRAP	HWS	HOT WATER SUPPLY	SF	SQUARE FOOT
CSA	CANADIAN STANDARDS ASSOCIATION	HX	HEAT EXCHANGER	SIM	SIMILAR
CU	CONDENSING UNIT	HERTZ	HERTZ	SM	SHEET METAL AND AIR CONDITIONING CONTRACTOR'S NATIONAL ASSOCIATION
CUH	CABINET UNIT HEATER	HZ	HERTZ	SOV	SHUT OFF VALVE
CV	CONTROL VALVE	IDR	INSIDE DIAMETER	SP	STATIC PRESSURE
CV	CONTROL VALVE RATING	IN	INCHES	SPH	STATIC PRESSURE HIGH LIMIT
CVT	CONSTANT VOLUME AIR TERMINAL	IND	INDIRECT WASTE	SPL	STATIC PRESSURE LOW LIMIT
CW	COLD WATER	KW	KILOWATT	SPL	STATIC PRESSURE LOW LIMIT
CWR	COLD WATER RETURN	L	LENGTH, LOUVER	SPS	STATIC PRESSURE SENSOR
CWS	COLD WATER SUPPLY	LAT	LEAVING AIR TEMPERATURE	SQ	SQUARE
D	DRAIN	LD	LIQUEFIED PETROLEUM	SS	STAINLESS STEEL
(D)	ITEMS TO BE DEMOLISHED	LDB	LEAVING DRY BULB	STL	STEEL
DB	DECIBELS	LF	LINEAR FEET	SUP	SUPPLY
DB	DRY BULB	LG	LONG	T	TEMPERATURE SENSOR, THERMOSTAT
DC	DRY COOLER	LOC	LOCATION, LOCATED	TC	TOTAL COOLING
DDC	DIRECT DIGITAL CONTROL	LQ	LIQUEFIED PROPANE	TEMP	TEMPERATURE
DIA	DIAMETER	LPR	LOW PRESSURE RETURN	THK	THICK, THICKNESS
DIFF	DIFFERENTIAL DIFFUSER	LPS	LOW PRESSURE STEAM (15 PSI OR LESS)	TG	TRANSFER GRILLE
DISCH	DISCHARGE	LRA	LOCKED ROTOR AMPS	TRANS	TRANSITION
DN	DOWN	LS	LINE SET (REFRIG)	TSP	TOTAL STATIC PRESSURE
DOM	DOMESTIC	LVG	LEAVING	TYP	TYPICAL
DP	DIFFERENTIAL PRESSURE	LWB	LEAVING WET BULB	UH	UNIT HEATER
DWG	DRAWING	LWT	LEAVING WATER TEMPERATURE	UNO	UNLESS NOTED OTHERWISE
DWGS	DRAWINGS	M	MECHANICAL	V	VENT
E	ELECTRICAL, EXHAUST	MANUF	MANUFACTURER	VAV	VARIABLE AIR VOLUME
(E)	EXISTING TO REMAIN	MAX	MAXIMUM	VD	VOLUME DAMPER
EA	EXHAUST AIR	MAX PD	MAXIMUM PRESSURE DROP	VEL	VELOCITY
EAT	ENTERING AIR TEMPERATURE	MBH	1000 BTU PER HOUR	VFD	VARIABLE FREQUENCY DRIVE
EC	ELECTRICAL CONTRACTOR	MBU	1000 BTU	VRF	VARIABLE REFRIGERANT FLOW
EDR	EQUIVALENT DIRECT RADIATION	MCA	MAXIMUM CIRCUIT AMPS	VTR	VENT THROUGH ROOF
EER	ENERGY EFFICIENT RATIO	MCC	MOTOR CONTROL CENTER	W	WIDTH, WATT
EF	EXHAUST FAN	MD	MOTORIZED DAMPER	W/	WITH
EFF	EFFICIENCY	MECH	MECHANICAL	WB	WET BULB
ELEC	ELECTRIC, ELECTRICAL	MEZZ	MEZZANINE	WC	WATER COLUMN
ELEV	ELEVATION	MFG	MANUFACTURER	WCO	WALL CLEANOUT
ENT	ENTERING	MIN	MINIMUM, MINUTES	WF	WALL FAN
EPM	ETHYLENE PROPYLENE DIENE MEMBRANE	MLS	MAIN LINE SET (REFRIG)	WG	WATER GAUGE
EQUIP	EQUIPMENT	mm	MILLIMETERS	WH	WATER HEATER
ESP	EXTERNAL STATIC PRESSURE	MNTD	MOUNTED	WMS	WIRE MESH SCREEN
ET	EXPANSION TANK	MOC	MAXIMUM OVERCURRENT PROTECTION	WPD	WATER PRESSURE DROP
EUH	ELECTRIC UNIT HEATER	MUA	MAKE-UP AIR		
EVAP	EVAPORATOR	MUW	MAKE-UP WATER		
EW	ELECTRIC WATER COOLER	N/A	NOT APPLICABLE		
EWT	ENTERING WATER TEMPERATURE	NATL	NATURAL		
EXH	EXHAUST				

GENERAL SYMBOLS


	DETAIL NUMBER		GPM
	DRAWING WHERE DETAIL IS DRAWN		KEY NOTE (NUMBER)
	DETAIL NUMBER		REVISION (LETTER)
	SYMBOL PER ABBREVIATION LIST		CONNECT TO EXISTING
	EQUIPMENT SEQUENCE NUMBER		LIMIT OF DEMOLITION
	NOTE		
	DIFFUSER, REGISTER OR GRILLE SEQUENCE NUMBER		
	OPM		
	NOTE		
	FINTUBE DESIGNATION		
	MBH		
	LENGTH OF ACTIVE FIN TUBE		

MODELED DUCTWORK LEGEND

	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR ROUND DUCT RISE		RETURN AIR ROUND DUCT RISE		EXHAUST AIR ROUND DUCT RISE
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR ROUND DUCT DROP		RETURN AIR ROUND DUCT DROP		EXHAUST AIR ROUND DUCT DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR RADIUS ELBOW RISE		RETURN AIR RADIUS ELBOW RISE		EXHAUST AIR RADIUS ELBOW RISE
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR RADIUS ELBOW DROP		RETURN AIR RADIUS ELBOW DROP		EXHAUST AIR RADIUS ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR RADIUS ELBOW RISE		RETURN AIR RADIUS ELBOW RISE		EXHAUST AIR RADIUS ELBOW RISE
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW RISE		RETURN AIR MITERED ELBOW RISE		EXHAUST AIR MITERED ELBOW RISE
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW RISE		RETURN AIR MITERED ELBOW RISE		EXHAUST AIR MITERED ELBOW RISE
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED ELBOW DROP		EXHAUST AIR MITERED ELBOW DROP
	24"x24" SA		24"x24" RA		24"x24" EA
	SUPPLY AIR MITERED ELBOW DROP		RETURN AIR MITERED EL		






D1 LIBRARY - SECOND LEVEL DUCTWORK PLAN
1/8" = 1'-0"
PLAN NORTH



A1 LIBRARY - FIRST LEVEL DUCTWORK PLAN
1/8" = 1'-0"
PLAN NORTH


- NOTES**
- SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
 - WHERE DUCTWORK PASSES THROUGH A FLOOR SLAB, PROVIDE A FIRE DAMPER UNLESS OTHERWISE NOTED.
 - WHERE DUCTWORK IS EXPOSED, IT SHALL BE DOUBLE WALL, SPIRAL SEAMED FLAT OVAL OR ROUND.



PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: SMM
DESIGNED BY: SMM
DRAWN BY: BAL




REV	DATE	REVISION DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID
REV		REVISION ISSUE DESCRIPTION

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: SMM
DESIGNED BY: SMM
DRAWN BY: BAL


SHEET TITLE:
LIBRARY - FIRST AND SECOND LEVEL DUCTWORK PLANS

SHEET ID:
MH101

NOT FOR CONSTRUCTION



D1 ARCHIVES - ROOF DUCTWORK PLAN
1/8" = 1'-0"
PLAN NORTH




A1 ARCHIVES - THIRD LEVEL DUCTWORK PLAN
1/8" = 1'-0"
PLAN NORTH

NOTES

- SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.

KEYED NOTES

- DUCT THROUGH (E) OPENING IN BEAM
- ARCHITECTURAL TO PROVIDE CURBS



wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 745-9001 F: (207) 742-9000 www.woodeng.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314




PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-0083

NO.	DATE	REVISION / ISSUE DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID
REV		REVISION ISSUE DESCRIPTION

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: SMM
DESIGNED BY: SMM
DRAWN BY: BAL
SHEET TITLE: ARCHIVES - THIRD LEVEL AND ROOF DUCTWORK PLAN
SHEET ID: MH104

NOT FOR CONSTRUCTION



A1 MUSEUM - FIRST LEVEL DUCTWORK PLAN
 1/8" = 1'-0"
 0 4' 8' 16'
 PLAN NORTH


NOTES

- SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
- COORDINATE LOCATION OF SLOT DIFFUSERS IN CARS AND BOATS GALLERY WITH EXHIBIT ITEMS TO ALLOW UNIMPEDED AIRFLOW TO THE FLOOR.
- WHERE DUCTWORK IS EXPOSED, IT SHALL BE DOUBLE WALL, SPIRAL SEAMED FLAT OVAL OR ROUND.

KEYED NOTES

- DUCT THROUGH (E) OPENING IN BEAM
- DIRECT RETURN

KEY PLAN



wood.
 Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 745-9001 F: (207) 742-9268 www.woodeng.com

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314



PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum, 250 State Street, Augusta, ME 04333-0083


REVISION	DATE	DESCRIPTION
B	02-17-2022	ADDENDUM NO. 3
A	01-07-2022	ISSUED FOR BID
REV		REVISION ISSUE DESCRIPTION

PROJECT NO: 3618208720
 PROJECT MANAGER: KFM
 A/E OF RECORD: SMM
 DESIGNED BY: SMM
 DRAWN BY: BAL

SHEET TITLE:
MUSEUM - FIRST LEVEL DUCTWORK PLAN
 SHEET ID:
MH105

NOT FOR CONSTRUCTION

M:\300\2022\02\03\A1_MUSEUM - FIRST LEVEL DUCTWORK PLAN.dwg




NOTES

- SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
- COORDINATE LOCATION OF SLOT DIFFUSERS IN CARS AND BOATS GALLERY WITH EXHIBIT ITEMS TO ALLOW UNIMPEDED AIRFLOW TO THE FLOOR.
- WHERE DUCTWORK IS EXPOSED, IT SHALL BE DOUBLE WALL, SPIRAL SEAMED FLAT OVAL OR ROUND.


KEYED NOTES

- DUCT PASSES THROUGH EXISTING OPENING IN BEAM.
- 3-HR RATED FIRE DAMPER
- 3-HR RATED FIRE DAMPER

KEY PLAN



A1 MUSEUM - SECOND LEVEL DUCTWORK PLAN
1/8" = 1'-0"



wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 775-3001 F: (207) 772-9262 www.woodgroup.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314



PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022
STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-0083


CURRENT ISSUE STATUS:
PROJECT:
DATE

REV	REVISION ISSUE DESCRIPTION	DATE
C	ADDENDUM NO. 3	02-17-2022
B	ADDENDUM NO. 2	02-08-2022
A	ISSUED FOR BID	01-07-2022

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: SMM
DESIGNED BY: SMM
DRAWN BY: BAL
SHEET TITLE:
MUSEUM - SECOND LEVEL DUCTWORK PLAN

SHEET ID:
MH106

NOT FOR CONSTRUCTION



A1 MUSEUM - THIRD LEVEL DUCTWORK PLAN
 1/8" = 1'-0"
 PLAN NORTH


NOTES

1. SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.

KEYED NOTES


- 1. DUCT PASSES THROUGH EXISTING OPENING IN BEAM.
- 2. PROVIDE 2-HR SHAFT RATED ENCLOSURE AROUND THE EXHAUST DUCT FROM THE VERTICAL SHAFT TO PENETRATION OF THE FOURTH FLOOR SLAB ABOVE.

KEY PLAN



wood.
 Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 745-9001 F: (207) 742-9262 www.woodeng.com

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314



PHASE 2 - ISSUED FOR BID
 JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
 ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum, 250 State Street, Augusta, ME 04333-0083


REV	DATE	REVISION DESCRIPTION
B	02-17-2022	ADDENDUM NO. 3
A	01-07-2022	ISSUED FOR BID
		REVISION ISSUE DESCRIPTION

PROJECT NO: 3618208720
 PROJECT MANAGER: KFM
 A/E OF RECORD: SMM
 DESIGNED BY: SMM
 DRAWN BY: BAL
 SHEET TITLE:
 MUSEUM - THIRD LEVEL DUCTWORK PLAN

SHEET ID:
MH107

NOT FOR CONSTRUCTION

M:\300\2022\02\03\146_Cultural Building Mechanical Upgrade\10102022_MH_107.dwg




NOTES

- SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.

KEYED NOTES

- DIRECT RETURN
- DUCT PASSES THROUGH EXISTING OPENING IN BEAM.
- REBALANCE EXISTING DIFFUSER TO 240 CFM
- REBALANCE EXISTING DIFFUSER TO 70 CFM
- REBALANCE EXISTING DIFFUSER TO 50 CFM
- REBALANCE EXISTING DIFFUSER TO 140 CFM
- REBALANCE EXISTING DIFFUSER TO 225 CFM

KEY PLAN



A1 MUSEUM - FOURTH LEVEL DUCTWORK PLAN
 1/8" = 1'-0"
 0 4' 8' 16'
 PLAN NORTH

wood.
 Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 775-3001 F: (207) 772-9262 www.woodgroup.com

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-314


STATE OF MAINE
 STEVEN M. MARTE
 217-0022
 7148
 LICENSED PROFESSIONAL ENGINEER

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022



STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum, 250 State Street, Augusta, ME 04333-0083

PROJECT NO.	3618208720
PROJECT MANAGER:	KFM
A/E OF RECORD:	SMM
DESIGNED BY:	SMM
DRAWN BY:	BAL
SHEET TITLE:	MUSEUM - FOURTH LEVEL DUCTWORK PLAN
SHEET ID:	MH108


NOT FOR CONSTRUCTION



D2 MUSEUM - FOURTH LEVEL MECHANICAL 416 LOWER DUCTWORK PART PLAN
1/4" = 1'-0"



A3 MUSEUM - FOURTH LEVEL MECHANICAL 416 LOWER PIPING PART PLAN
1/4" = 1'-0"



NOTES

- SEE SHEET M-301 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
- DUCTWORK, PIPING, AND EQUIPMENT SHALL BE ROUTED TO PROVIDE MIN. 6'-8" CLEARANCE ALONG ACCESS PATHS IN MECHANICAL ROOMS.
- SEE FLOW DIAGRAMS ON M-705 AND PIPING DETAILS ON M-502, M-503 AND M-504 FOR DETAILED PIPING CONNECTIONS, VALVES AND ACCESSORIES.
- PROVIDE DRAIN PAN FOR CU's AND ROUTE 1" CONDENSATE TO NEAREST FLOOR DRAIN.

KEYED NOTES

- FIRE DAMPER AT SLAB PENETRATION

wood.

Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 742-9001 F: (207) 742-9002 www.woodeng.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314



PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022
STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-0083

REV	DATE	DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID
		REVISION ISSUE DESCRIPTION

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: SMM
DESIGNED BY: SMM
DRAWN BY: BAL
SHEET TITLE:
MECHANICAL PART PLANS
SHEET ID:
M-401

NOT FOR CONSTRUCTION

NOTES

- SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
- DUCTWORK, PIPING, AND EQUIPMENT SHALL BE ROUTED TO PROVIDE MIN. 6" CLEARANCE ALONG ACCESS PATHS IN MECHANICAL ROOMS.
- SEE FLOW DIAGRAMS ON M-705 AND PIPING DETAILS ON M-502, M-503 AND M-504 FOR DETAILED PIPING CONNECTIONS, VALVES AND ACCESSORIES.
- PROVIDE DRAIN PAN FOR CU'S AND ROUTE 1" CONDENSATE TO NEAREST FLOOR DRAIN.

wood.
 Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 742-9001 F: (207) 742-9006 www.woodgroup.com

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314




CURRENT ISSUE STATUS:
 PHASE 2 - ISSUED FOR BID
 JANUARY 7, 2022

PROJECT:
 STATE OF MAINE CULTURAL BUILDING
 ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum, 250 State Street, Augusta, ME 04333-0083



REV	DATE	REVISION ISSUE DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID

PROJECT NO: 3618208720
 PROJECT MANAGER: KFM
 A/E OF RECORD: SMM
 DESIGNED BY: SMM
 DRAWN BY: BAL
 SHEET TITLE:
 MECHANICAL PART PLANS
 SHEET ID:
M-402


NOT FOR CONSTRUCTION




D2 MUSEUM - FOURTH LEVEL MECHANICAL 416 UPPER DUCTWORK PART PLAN
 1/4" = 1'-0"




A1 MUSEUM - FOURTH LEVEL MECHANICAL 416 UPPER PIPING PART PLAN
 1/4" = 1'-0"




M:\3618208720\3618208720_04_Cultural Building Mechanical Upgrade\012022_MP_402.dwg




D1 MECHANICAL ROOM B5 DUCTWORK PLAN
1/4" = 1'-0"



D4 MECHANICAL ROOM B5 PIPING PART PLAN
1/4" = 1'-0"



A1 ARCHIVES - THIRD LEVEL MECHANICAL 348 DUCTWORK PART PLAN
1/4" = 1'-0"



A4 ARCHIVE - THIRD LEVEL MECHANICAL 348 PIPING PART PLAN
1/4" = 1'-0"

- NOTES**
- SEE SHEET M-301 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
 - DUCTWORK, PIPING, AND EQUIPMENT SHALL BE ROUTED TO PROVIDE MIN. 6'-6" CLEARANCE ALONG ACCESS PATHS IN MECHANICAL ROOMS.
 - SEE FLOW DIAGRAMS ON M-705 AND PIPING DETAILS ON M-502, M-503 AND M-504 FOR DETAILED PIPING CONNECTIONS, VALVES AND ACCESSORIES.
 - PROVIDE DRAIN PAN FOR CU'S AND ROUTE 1" CONDENSATE TO NEAREST FLOOR DRAIN.

- KEYED NOTES**
- 48"x30" OA UP
 - 48"x30" EA UP
 - FIRE DAMPER AT SLAB PENETRATION
 - EXISTING CONCRETE PAD
 - FIRE DAMPER AT FLOOR PENETRATION

wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 742-9001 F: (207) 742-9002 www.woodeng.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-3141

STEVEN M. MARTIN
2/17/2022
7148
LICENSED PROFESSIONAL ENGINEER

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 250 State Street, Augusta, ME 04333-0083

REV	DATE	DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: SMM
DESIGNED BY: SMM
DRAWN BY: BAL
SHEET TITLE: MECHANICAL PART PLANS
SHEET ID: M-403

NOT FOR CONSTRUCTION

NOTES

- SEE SHEET M-301 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
- DUCTWORK, PIPING, AND EQUIPMENT SHALL BE ROUTED TO PROVIDE MIN. 6'-6" CLEARANCE ALONG ACCESS PATHS IN MECHANICAL ROOMS.
- SEE FLOW DIAGRAMS ON M-705 AND PIPING DETAILS ON M-502, M-503 AND M-504 FOR DETAILED PIPING CONNECTIONS, VALVES AND ACCESSORIES.
- PROVIDE DRAIN PAN FOR CUs AND ROUTE 1" CONDENSATE TO NEAREST FLOOR DRAIN.

KEYED NOTES

- 48"x30" OA UP
- 48"x30" EA UP
- FIRE DAMPER AT SLAB PENETRATION
- FIRE DAMPER AT FLOOR PENETRATION

wood.

Environment & Infrastructure Solutions, Inc.
 1 Congress St., Suite 200, Portland, ME 04101
 P: (207) 745-3001 F: (207) 742-6262 www.woodsolutions.com

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-3141




PHASE 2 - ISSUED FOR BID
 JANUARY 7, 2022
 PROJECT: STATE OF MAINE CULTURAL BUILDING
 ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum, 250 State Street, Augusta, ME 04333-0083


PROJECT NO:	3618208720
PROJECT MANAGER:	KFM
A/E OF RECORD:	SMM
DESIGNED BY:	SMM
DRAWN BY:	BAL
SHEET TITLE:	
REVISION NO.	DATE
B ADDENDUM NO. 3	02-17-2022
A ISSUED FOR BID	01-07-2022
REV	REVISION ISSUE DESCRIPTION

MECHANICAL PART PLANS
 SHEET ID:
M-404

NOT FOR CONSTRUCTION



A1 LIBRARY - THIRD LEVEL MECHANICAL 315 DUCTWORK PART PLAN
 1/4" = 1'-0"



A4 LIBRARY - THIRD LEVEL MECHANICAL 315 PIPING PART PLAN
 1/4" = 1'-0"

GRAVITY VENTILATOR SCHEDULE

TAG	SERVICE	AIRFLOW (CFM)	THROAT VELOCITY (FPM)	PRESSURE DROP (IN. WG)	DUCT CONNECTION SIZE (IN)	BASIS OF DESIGN MFG & MODEL	NOTES
GV-1	INTAKE; ERV-1	7500	839	0.1	36X36	GREENHECK FGI-36X36	1, 2

NOTES:
 1. PROVIDE WITH INTEGRAL BIRDSCREEN.
 2. PROVIDE WITH MIN. 12" TALL MANUFACTURER FURNISHED ROOF CURB.
 3. INSTALL CONTROL DAMPER, D-14, IN ROOF CURB.
 4. 12" BASE.

GLYCOL MAKE-UP UNIT SCHEDULE

TAG	LOCATION	SERVES	TANK MATERIAL	TANK SIZE (GALLONS)	PUMP TYPE	FLUID	FLOW (GPM)	HEAD (PSIG)	PUMP			POWER			BASIS OF DESIGN			NOTES	
										CONTROL	MHP	RPM	VOLTS	PHASE	HZ	MANUFACTURER	MODEL	WEIGHT (LB)	
GMU-1	MECHANICAL B-5	GLYCOL SYSTEM	HDPE	50	ROTARY VANE	30% PG	1.8	70	BMS	1/3	1,760	110	1	60	WESSELS	GMPD-23050	153	1, 2, 3, 4	

NOTES:
 1. PROVIDE TWIN PUMP UNIT WITH PRESSURE SWITCH AND ALTERNATING CONTROL.
 2. PROVIDE RELAY CONTACT FOR CONTROL THROUGH BMS SYSTEM.
 3. PROVIDE PRESSURE REDUCING VALVE SET TO MINIMUM SYSTEM PRESSURE.
 4. PROVIDE HOA CONTROL.

FAN SCHEDULE

TAG	LOCATION	FAN TYPE	SYSTEM TYPE	DRIVE TYPE	AIRFLOW (CFM)	ESP (IN WG)	MOTOR SIZE (HP)	SPEED (RPM)	ELECTRICAL		MFR	MODEL NUMBER	WEIGHT (LBS)	NOTES
										V/PHz	FLA (A)			
SF-1	4TH FLOOR ROOF	FILTERED ROOF SUPPLY	SUPPLY	BELT	4,000	0.50	2	775	480/3/60	3.4	GREENHECK	SAF-115	260	1, 2

NOTES:
 1. PROVIDE MANUFACTURER FURNISHED MIN 18 INCH HIGH ROOF CURB.
 2. NEMA 1 DISCONNECT SWITCH LOCATED WITHIN FAN HOUSING.

VALVE SCHEDULE

TAG	SERVICE	TYPE	DOMESTIC CONNECTION SIZE (INCH)		MAX. FLOW RATE (GPM)	MAX. OPERATING PRESSURE (PSI)	TEMPERATURE (°F)		BASIS OF DESIGN		NOTES
				INLET	OUTLET		FROM WH	TO PLUMBING FIXTURES	MFG	MODEL	
MV-1	DOMESTIC WATER	THERMOSTATIC MIXING VALVE	1.5	1.5	24	125	140	105	WATTS	LFN SERIES	1, 2

NOTES:
 1. LEAD FREE BRASS BODY CONSTRUCTION.
 2. RATED FOR POTABLE HOT WATER SERVICE.

BRANCH CIRCUIT CONTROLLER SCHEDULE

TAG	SERVES	NUMBER OF PORTS	CONNECTED CAPACITY TO BC (MBH)	ELECTRICAL			BASIS OF DESIGN		NOTES
				VOLTS	PHASE	HZ	MITSUBISHI MODEL		
BCC-1	CU-1	12	153	208	1	60	TCMBM1012JA11N4	1, 2	
BCC-2	CU-2	16	311	208	1	60	TCMBM1016JA11N4	1, 2	
BCC-3	CU-3	16	195	208	1	60	TCMBM1016JA11N4	1, 2	
BCC-5	CU-5	16	175	208	1	60	TCMBM1016JA11N4	1, 2	
BCC-6	CU-6	8	74	208	1	60	TCMBM1016JA11N4	1, 2	
BCC-7	CU-7	16	191	208	1	60	TCMBM1016KA11N4	1, 2	
BCC-7-1	CU-7	8	84	208	1	60	TCMS0108KB11N4	1, 2	

NOTES:
 1. PROVIDE WITH DIAMONDBACK BALL VALVES BV-SERIES, 700 PSIG WORKING PRESSURE, FULL PORT, 410A RATED.
 2. COORDINATE WITH MANUFACTURER FOR MAXIMUM ALLOWABLE INDOOR UNIT CAPACITY FOR SUB BC CONTROLLER.

LOUVER SCHEDULE

TAG	LOCATION	SERVES	AIRFLOW DIRECTION	CFM	DEPTH (INCH)	WIDTH (INCH)	HEIGHT (INCH)	FACE AREA SQ FT	FREE AREA SQ FT	BLADE TYPE	ANGLE	APD (IN WC)	BASIS OF DESIGN		NOTES
													MFG	MODEL	
L-1A	ARCHIVES MECH RM	CU-4	EXHAUST	9,200	6	108	48	36.00	256	21.72	424	0.02	GREENHECK	ESD-635	1, 2
L-1B	ARCHIVES MECH RM	CU-4	INTAKE	9,200	6	108	48	36.00	256	21.72	424	0.02	GREENHECK	ESD-635	1, 2
L-2A	ARCHIVES MECH RM	CU-5	EXHAUST	14,850	6	108	48	36.00	413	21.72	684	0.06	GREENHECK	ESD-635	1, 2
L-2B	ARCHIVES MECH RM	CU-5	INTAKE	14,850	6	108	48	36.00	413	21.72	684	0.06	GREENHECK	ESD-635	1, 2
L-3A	ARCHIVES MECH RM	ERV-2	EXHAUST	3,105	6	108	48	36.00	86	21.72	143	0.00	GREENHECK	ESD-635	1, 2
L-3B	ARCHIVES MECH RM	ERV-2	INTAKE	3,450	6	108	48	36.00	96	21.72	159	0.00	GREENHECK	ESD-635	1, 2
L-4A	LIBRARY MECH RM	CU-1 & ...	EXHAUST	14,150	6	108	48	36.00	393	21.72	651	0.06	GREENHECK	ESD-635	1, 2
L-4B	LIBRARY MECH RM	CU-1 & ...	INTAKE	14,150	6	108	48	36.00	393	21.72	651	0.06	GREENHECK	ESD-635	1, 2
L-5A	LIBRARY MECH RM	CU-2	EXHAUST	14,150	6	108	48	36.00	393	21.72	651	0.06	GREENHECK	ESD-635	1, 2
L-5B	LIBRARY MECH RM	CU-2	INTAKE	14,150	6	108	48	36.00	393	21.72	651	0.06	GREENHECK	ESD-635	1, 2
L-6A	LIBRARY MECH RM	CU-3	EXHAUST	14,800	6	108	48	36.00	411	21.72	681	0.06	GREENHECK	ESD-635	1, 2
L-6B	LIBRARY MECH RM	CU-3	INTAKE	14,800	6	108	48	36.00	411	21.72	681	0.06	GREENHECK	ESD-635	1, 2
L-7	MUSEUM MECH RM	CU-7	EXHAUST	14,850	6	82	76	43.28	343	38.76	383	0.02	GREENHECK	ESD-635	1, 2
L-8	MUSEUM MECH RM	CU-6	EXHAUST	6,000	6	82	76	43.28	139	21.56	278	0.01	GREENHECK	ESD-635	1, 2
L-9	MUSEUM MECH RM	CU-7	INTAKE	14,850	6	82	76	43.28	343	38.76	383	0.02	GREENHECK	ESD-635	1, 2
L-10	MUSEUM MECH RM	CU-6	INTAKE	6,000	6	82	76	43.28	139	21.56	278	0.01	GREENHECK	ESD-635	1, 2
L-11	MUSEUM MECH RM	ERV-3	INTAKE	5,600	6	82	76	43.28	129	38.76	144	0.02	GREENHECK	ESD-635	1, 2
L-12	MUSEUM MECH RM	-	-	-	-	-	-	-	-	-	-	-	-	-	1, 2, 3
L-13	LIBRARY MECH RM	ERV-1	EXHAUST	6,795	6	120	48	40.00	170	23.75	286	0.02	GREENHECK	ESD-635	1, 2

NOTES:
 1. FABRICATE LOUVER OF EXTRUDED ALUMINUM BLADES AND FRAME WITH KYMAR FINISH.
 2. PROVIDE LOUVER WITH 1/2 INCH MESH STAINLESS STEEL BIRD SCREEN.
 3. BLANK OFF AND INSULATE LOUVER FROM THE INSIDE.

AIR SEPARATOR SCHEDULE

TAG	SERVICE	TYPE	CASING MATERIAL	CONNECTION SIZE (INCH)	FLUID	FLOW RATE (GPM)	PRESSURE DROP (FT WC)	BASIS OF DESIGN			NOTES
								MFG & MODEL	DRY WEIGHT (LBS)	FLOODED WEIGHT (LBS)	
AS-1	GLYCOL LOOP	AIR & DIRT SEPARATOR	CARBON STEEL	4.00	30% PG	235	1.31	TACO 4904ADH-125	130	190	1-5
AS-2	HOT WATER LOOP	AIR & DIRT SEPARATOR	CARBON STEEL	2.50	WATER	65	1.54	TACO 4902ADH-125	105	146	1-5

NOTES:
 1. PROVIDE WITH INTEGRAL STRAINER.
 2. PROVIDE WITH FLANGED PIPE CONNECTIONS.
 3. DESIGNED AND CONSTRUCTED PER ASME.
 4. PROVIDE WITH HIGH CAPACITY AUTOMATIC AIR VENT.
 5. PROVIDE FACTORY INSTALLED BLOW DOWN VALVE.

FAN COIL UNIT SCHEDULE

TAG	COND. UNIT	LOCATION	UNIT TYPE	INLET	DISCH	FILTERS	SUPPLY AIR (CFM)	AIR FLOW		ESP (IN WC)	FAN DRIVE		AIR				ELECTRICAL			BASIS OF DESIGN		NOTES			
								OUTSIDE AIR	% OF SA		TYPE	CONTROL	MODE	ENTERING DB/WB (°F)	LEAVING DB/WB (°F)	TMBH	SMBH	VOLTS	PHASE	HZ	MCA	MCCB	MITSUBISHI MODEL	WEIGHT (LBS)	
FCU-01-01	CU-1	OPEN STACKS 101	CEILING CONCEALED	HORI	HORI	-	1342	645	48%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	55/52.7	40.4	30.2	208	1	60	4.2	15	TPEFYP048MH142A	86	1-4
FCU-01-02	CU-1	LIBRARY CLOSED STACKS 109	CEILING CONCEALED	HORI	HORI	-	777	610	39%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	54.4/52.4	23.7	17.5	208	1	60	2.4	15	TPEFYP027MH142A	124	1-4
FCU-01-03	CU-1	MAIL 108	CEILING CONCEALED	HORI	HORI	MERV13	600	118	10%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	55/45.4	15.8	12.9	208	1	60	1.6	15	TPEFYP018MA143A	58	1-4
FCU-01-04	CU-1	PRELIMINARY PROCESS 111	CEILING CONCEALED	HORI	HORI	MERV13	494	127	13%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	55/52	13.2	10.7	208	1	60	1.5	15	TPEFYP015MA143A	58	1-4
FCU-01-05	CU-1	CORRIDOR 119	CEILING CONCEALED	HORI	HORI	MERV13	300	24	4%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	55/54	5.3	5.3	208	1	60	1.1	15	TPEFYP006MA143A	49	1-4
FCU-01-06	CU-1	WORKSHOP 121	CEILING CONCEALED	HORI	HORI	MERV13	300	351	59%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	51.7/50.1	5.3	5.3	208	1	60	1.1	15	TPEFYP006MA143A	49	1-4
FCU-01-07	CU-1	WORKSHOP 122	CEILING CONCEALED	HORI	HORI	MERV13	300	140	23%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	58/52.7	5.3	5.3	208	1	60	1.1	15	TPEFYP006MA143A	49	1-4
FCU-01-08	CU-1	OPEN STACKS 101	CEILING CONCEALED	HORI	HORI	-	883	349	20%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	55/51.9	23.7	19.2	208	1	60	2.9	15	TPEFYP027MA144A	67	1-4
FCU-02-01	CU-2	OPEN LIBRARY STACKS 217	CEILING CONCEALED	HORI	HORI	-	1,306	525	20%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	51.5/49.5	38.5	30.1	208	1	60	4.4	15	TPEFYP048MA144A	86	1-4
FCU-02-02	CU-2	FL2, LIBRARY	CEILING CONCEALED	HORI	HORI	-	1,306	525	20%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	51.5/49.5	38.5	30.1	208	1	60	4.4	15	TPEFYP048MA144A	86	1-4
FCU-02-03	CU-2	OPEN LIBRARY STACKS 217	CEILING CONCEALED	HORI	HORI	-	300	118	20%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	50/49	6.4	5.7	208	1	60	1.1	15	TPEFYP008MA143A	49	1-4
FCU-02-05	CU-2	OPEN LIBRARY STACKS 217	CEILING CONCEALED	HORI	HORI	-	300	118	20%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	50/49	6.4	5.7	208	1	60	1.1	15	TPEFYP008MA143A	49	1-4
FCU-02-06	CU-2	OPEN LIBRARY STACKS 217	CEILING CONCEALED	HORI	HORI	-	300	119	20%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	50/49	6.4	5.7	208	1	60	1.1	15	TPEFYP008MA143A	49	1-4
FCU-02-07	CU-2	OPEN LIBRARY STACKS 217	CEILING CONCEALED	HORI	HORI	-	371	168	23%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	50/49	9.7	7.5	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-02-08	CU-2	LIBRARY WEST	CEILING CONCEALED	HORI	HORI	-	1,271	606	24%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	50/49	28.8	25.3	208	1	60	4.3	15	TPEFYP036MA144A	84	1-4
FCU-02-09	CU-2	OPEN STAIR	CEILING CONCEALED	HORI	HORI	-	300	136	23%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	55/51	6.4	5.7	208	1	60	1.1	15	TPEFYP008MA143A	49	1-4
FCU-02-10	CU-2	CIRC OFFICE	CEILING CONCEALED	HORI	HORI	-	600	84	7%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.1	15.3	12.8	208	1	60	1.6	15	TPEFYP018MA143A	58	1-4
FCU-02-11	CU-2	REF OFFICE	CEILING CONCEALED	HORI	HORI	-	600	68	6%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/52.7	15.3	12.8	208	1	60	2.9	15	TPEFYP018MA144A	58	1-4
FCU-02-12	CU-2	CONFERENCE ROOM 211	CEILING CONCEALED	HORI	HORI	MERV13	371	75	10%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	54.8/52.3	10.2	7.8	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-02-13	CU-2	LIBRARIAN	CEILING CONCEALED	HORI	HORI	MERV13	494	51	5%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/52.9	12.7	10.6	208	1	60	2.9	15	TPEFYP015MA144A	58	1-4
FCU-02-14	CU-2	CONFERENCE ROOM 224	CEILING CONCEALED	HORI	HORI	-	1,412	265																	

FAN COIL UNIT SCHEDULE

TAG	COND. UNIT	LOCATION	UNIT			AIR FLOW			FAN		AIR				ELECTRICAL				BASIS OF DESIGN		NOTES				
			TYPE	INLET	DISCH.	FILTERS	SUPPLY AIR (CFM)	OUTSIDE AIR (CFM)	ESP (IN WC)	TYPE	CONTROL	MODE	ENTERING DBWB (°F)	LEAVING DBWB (°F)	TMBH	SMBH	VOLTS	PHASE	H2	MCA		MOCP	MITSUBISHI MODEL	WEIGHT (LBS)	
																									% OF SA
FCU-04-06	CU-4	COURT FILES ARCHIVAL 218 SOUTH	CEILING CONCEALED	HORI	HORI	MERV13	1,165	582	25%	0.6	DIRECT	VARIABLE SPEED	COOLING	70/58	50.2/48.3	30.8	25.8	208	1	60	3.5	15	TPEFYP036MA143A	86	1-4
FCU-04-07	CU-4	COURT FILES ARCHIVAL 218 NORTH	CEILING CONCEALED	HORI	HORI	MERV13	1,165	449	19%	0.6	DIRECT	VARIABLE SPEED	HEATING	66.0	67.3	28.7	-	208	1	60	3.5	15	TPEFYP036MA143A	86	1-4
FCU-04-08	CU-4	ELECTRICAL SERVICE ENTRANCE	WALL MOUNTED	HORI	HORI	WASHABLE	297	0	0%	N/A	DIRECT	VARIABLE SPEED	COOLING	70/58	50/48.3	30.8	25.8	208	1	60	0.2	15	TPKFYP012LM140A	25	1-4
FCU-04-09	CU-4	IT 235	WALL MOUNTED	HORI	HORI	WASHABLE	297	0	0%	N/A	DIRECT	VARIABLE SPEED	HEATING	66.0	95.0	9.7	-	208	1	60	0.2	15	TPKFYP012LM140A	25	1-4
FCU-05-01	CU-5	BREAK 330	CEILING CONCEALED	HORI	HORI	--	371	85	11%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	52.5/50.7	10.3	7.8	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-05-02	CU-5	OFFICE 333 (ARCHIVIST OFFICE)	CEILING CONCEALED	HORI	HORI	MERV13	371	29	4%	0.6	DIRECT	VARIABLE SPEED	HEATING	68.0	89.4	9.2	-	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-05-03	CU-5	OFFICE 337	CEILING CONCEALED	HORI	HORI	MERV13	371	36	5%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.9	10.3	7.8	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-05-04	CU-5	OFFICE 338 (DIRECTOR OFFICE)	CEILING CONCEALED	HORI	HORI	MERV13	371	36	5%	0.6	DIRECT	VARIABLE SPEED	HEATING	68.0	88.0	9.2	-	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-05-05	CU-5	OFFICE 340	CEILING CONCEALED	HORI	HORI	MERV13	300	8	1%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/54	6.9	6.0	208	1	60	1.8	15	TPEFYP008MA144A	47	1-4
FCU-05-06	CU-5	DARKROOM 357	CEILING CONCEALED	HORI	HORI	--	494	122	12%	0.6	DIRECT	VARIABLE SPEED	HEATING	68.0	95.0	6.1	-	208	1	60	1.5	15	TPEFYP015MA143A	58	1-4
FCU-05-07	CU-5	DIGITAL ARCHIVES 361	CEILING CONCEALED	HORI	HORI	--	600	79	7%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.8	15.5	12.9	208	1	60	2.9	15	TPEFYP018MA144A	58	1-4
FCU-05-08	CU-5	OFFICE 35	CEILING CONCEALED	HORI	HORI	--	371	15	2%	0.6	DIRECT	VARIABLE SPEED	HEATING	68.0	95.0	9.2	-	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-05-09	CU-5	RECORDS MANAGEMENT 354	CEILING CONCEALED	HORI	HORI	--	300	67	11%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.9	6.9	6.0	208	1	60	1.8	15	TPEFYP008MA144A	47	1-4
FCU-05-10	CU-5	CONFERENCE 351	CEILING CONCEALED	HORI	HORI	--	371	131	18%	0.6	DIRECT	VARIABLE SPEED	HEATING	68.0	95.0	9.2	-	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-05-11	CU-5	RESEARCH 350	CEILING CONCEALED	HORI	HORI	--	1,165	218	9%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.4	31.0	26.3	208	1	60	3.5	15	TPEFYP036MA143A	86	1-4
FCU-05-12	CU-5	CORRIDOR	CEILING CONCEALED	HORI	HORI	--	300	16	3%	0.6	DIRECT	VARIABLE SPEED	HEATING	68.0	94.7	27.2	-	208	1	60	1.1	15	TPEFYP006MA143A	49	1-4
FCU-05-13	CU-5	ARCHIVES LOBBY	CEILING CONCEALED	HORI	HORI	--	371	187	25%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/54.4	5.2	5.2	208	1	60	1.1	15	TPEFYP006MA143A	49	1-4
FCU-06-01	CU-6	CONSERVATION LAB 408	CEILING CONCEALED	HORI	HORI	MERV13	671	101	8%	1.0	DIRECT	VARIABLE SPEED	HEATING	68.0	87.9	4.6	-	208	1	60	1.2	15	TPEFYP012MA143A	49	1-4
FCU-06-02	CU-6	COLLECTION STORAGE 431	CEILING CONCEALED	HORI	HORI	MERV13	600	135	11%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	54.9/54.4	18.2	14.4	208	1	60	2.1	15	TPEFYP024MH142A	100	1-4
FCU-06-03	CU-6	SCIENCE LAB 406	CEILING CONCEALED	HORI	HORI	MERV13	300	31	5%	0.6	DIRECT	VARIABLE SPEED	HEATING	68.0	95.0	20.0	-	208	1	60	2.9	15	TPEFYP018MA144A	58	1-4
FCU-06-04	CU-6	INCOMING COLLECTIONS 403	CEILING CONCEALED	HORI	HORI	MERV13	883	179	10%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55.0/53.8	13.7	12.1	208	1	60	1.8	15	TPEFYP008MA144A	47	1-4
FCU-07-01	CU-7	OFFICE 513	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	390	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	95.0	6.7	-	208	1	60	2.9	15	TPEFYP024MA144A	67	1-4
FCU-07-02	CU-7	OFFICE 502	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	307	0	0%	0.0	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.7	11.7	8.7	208	1	60	0.4	15	TPLFYP015FM140A	37	1-4
FCU-07-03	CU-7	OFFICE 503	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	307	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	94.1	10.5	-	208	1	60	0.3	15	TPLFYP006BM140F	38	1-4
FCU-07-04	CU-7	SEMINAR 504	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	335	0	0%	0.0	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.4	4.7	4.6	208	1	60	0.3	15	TPLFYP006BM140F	38	1-4
FCU-07-05	CU-7	OFFICE 505	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	315	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	90.0	4.1	-	208	1	60	0.3	15	TPLFYP006BM140F	38	1-4
FCU-07-06	CU-7	OFFICE 506	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	390	0	0%	0.0	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.2	6.3	5.6	208	1	60	0.3	15	TPLFYP008FM140A	34	1-4
FCU-07-07	CU-7	OFFICE 507	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	307	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	86.7	5.6	-	208	1	60	0.3	15	TPLFYP008FM140A	34	1-4
FCU-07-08	CU-7	CONFERENCE 508	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	460	0	0%	0.0	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.28	11.7	8.7	208	1	60	0.4	15	TPLFYP015FM140A	37	1-4
FCU-07-09	CU-7	OFFICE 510	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	460	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	95.0	10.5	-	208	1	60	0.4	15	TPLFYP015FM140A	37	1-4
FCU-07-10	CU-7	RECEPTION 511	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	280	0	0%	0.0	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.9	14.1	10.5	208	1	60	0.5	15	TPLFYP018FM140A	37	1-4
FCU-07-11	CU-7	OFFICE 514	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	315	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	94.8	8.3	-	208	1	60	0.5	15	TPLFYP018FM140A	37	1-4
FCU-07-12	CU-7	OFFICE 515	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	315	0	0%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.7	9.4	7.1	208	1	60	0.3	15	TPLFYP012FM140A	37	1-4
FCU-07-13	CU-7	CONFERENCE 516	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	390	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	94.8	8.3	-	208	1	60	0.3	15	TPLFYP012FM140A	37	1-4
FCU-07-14	CU-7	OFFICE 518	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	307	0	0%	0.0	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.2	6.3	5.6	208	1	60	0.3	15	TPLFYP008FM140A	34	1-4
FCU-07-15	CU-7	OFFICE 519	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	390	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	86.7	5.6	-	208	1	60	0.3	15	TPLFYP008FM140A	34	1-4
FCU-07-16	CU-7	STORAGE 520	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	307	0	0%	0.0	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.28	11.7	8.7	208	1	60	0.4	15	TPLFYP015FM140A	37	1-4
FCU-07-17	CU-7	CORRIDOR 521	CEILING CONCEALED	HORI	HORI	--	300	181	30%	0.6	DIRECT	VARIABLE SPEED	HEATING	68.0	95.0	12.4	-	208	1	60	0.5	15	TPLFYP018FM140A	37	1-4
FCU-07-18	CU-7	RESEARCH 522	CEILING CONCEALED	HORI	HORI	--	600	181	15%	0.6	DIRECT	VARIABLE SPEED	COOLING	74/62	55/53.9	14.1	10.5	208	1	60	0.5	15	TPLFYP018FM140A	37	1-4
FCU-07-19	CU-7	COLLECTION STORAGE 530	CEILING CASSETTE (FOUR-WAY)	HORI	HORI	WASHABLE	307	0	0%	0.0	DIRECT	VARIABLE SPEED	HEATING	68.0	84.2	4.1	-	208	1	60	0.3	15	TPLFYP006BM140F	38	1-4

NOTES:
 1. REFRIGERANT SHALL BE R-410A.
 2. SEE MECHANICAL FLOOR PLANS FOR LOCATIONS
 3. TAG NUMBERS INCLUDE ASSOCIATED CONDENSING UNIT: FCU - CONDENSING UNIT NUMBER - FAN COIL UNIT NUMBER
 4. PROVIDE INTEGRAL CONDENSATE PUMP

NOTES

1. SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.

wood.

Environment & Infrastructure Solutions, Inc.
 611 Congress St., Suite 220, Portland, ME 04101
 P: (207) 755-9941 F: (207) 755-1492 www.wood-ei.com

STATE OF MAINE
 BUREAU OF GENERAL SERVICES
 111 SEWALL STREET, 4TH FLOOR
 AUGUSTA, MAINE 04333-0077
 (207) 624-7314



CURRENT ISSUE STATUS:
 PHASE 2 - ISSUED FOR BID
 JANUARY 7, 2022
 PROJECT:
 STATE OF MAINE CULTURAL BUILDING
 ASBESTOS ABATEMENT & MECHANICAL UPGRADES
 Maine State Museum 230 State Street, Augusta, ME 04333-0083

NO.	DATE	DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-09-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID
REV		REVISION ISSUE DESCRIPTION

PROJECT NO: 3618208720
 PROJECT MANAGER: KFM
 A/E OF RECORD: SMM
 DESIGNED BY: SML
 DRAWN BY: STR

SHEET TITLE:
 MECHANICAL SCHEDULES

SHEET ID:
 M-603

NOT FOR CONSTRUCTION

EXPANSION TANK SCHEDULE

TAG	SERVICE	TYPE	CASING MATERIAL	CONNECTION SIZE (INCH)	PRESSURE RATING (PSI)	FLUID	SYSTEM VOLUME (GAL)		TEMPERATURE (°F)		CALCULATED SYSTEM EXPANSION VOLUME (GAL)	TANK VOLUME REQUIRED (GAL)	TANK VOLUME (GAL)	ACCEPTANCE VOLUME (GAL)	TANK DIMENSIONS (INCH)		BASIS OF DESIGN		WEIGHT (LBS)	NOTES		
							MIN	MAX	MIN	MAX					DIAMETER	HEIGHT	MFG	MODEL			TANK	W/FLUID
ET-1	WATER / GLYCOL LOOP	BLADDER	STEEL	1.50	125	30% PG WATER	630	40	80	40	180	25.5	60	79	79	24	59.0	TACO	CA-300-125	320	978	1-5
ET-2	HEATING HOT WATER	BLADDER	STEEL	1.00	125	100% WATER	194	40	80	40	180	5.2	12	23	23	20	32.0	TACO	CA-90-125	120	312	1-5
ET-3	DOMESTIC HOT WATER	BLADDER	STEEL	0.75	150	100% WATER	100	40	125	40	180	2.7	7	8	5	14	24.8	TACO	PAX30-150	90	127	1-6

- NOTES:
 1. FABRICATE TANK PER ASME SECTION VIII.
 2. TANK TO BE PRESSURIZED TO FACTORY STANDARD PRE-CHARGE (12 PSIG) WITH COMPRESSED AIR - SEE DETAIL.
 3. PROVIDE BLADDER FAILURE SWITCH.
 4. PROVIDE WITH SIGHT GLASS.
 5. PRECHARGE WITH AIR TO MINIMUM PRESSURE SCHEDULED.
 6. STAINLESS STEEL CONNECTION AND CORROSION RESISTANT CONSTRUCTION FOR POTABLE WATER SERVICE.

WATER HEATER SCHEDULE

TAG	SERVICE	DOMESTIC WATER			HOT WATER HEAT EXCHANGER			TEMPERATURE		TANK DIMENSIONS		BASIS OF DESIGN		WEIGHT		NOTES	
		TANK SIZE	CONNECTION SIZE (INCH)	FLOW RATE	PRESSURE DROP	SURFACE AREA	CAPACITY	EWT	LWT	DIAMETER	HEIGHT	MFG	MODEL	TANK	FILLED		
WH-1	DOMESTIC WATER	78	1.5	1.5	24	10.0	68	360	170	140	23.5	72.0	HTP	SSU-80CN	175	651	1, 2, 3, 4

- NOTES:
 1. TANK RATED FOR 150 PSI WORKING PRESSURE. PROVIDE COMMERCIAL UNIT WITH DOUBLE HEAT EXCHANGER.
 2. PROVIDE WITH THERMOSTATIC MIXING VALVE TO REDUCE DHW SUPPLY TEMPERATURE TO 105°F.
 3. TANK INSULATED WITH MINIMUM 2 INCH THICK FOAM WITH PLASTIC JACKET.
 4. PROVIDE TEMPERATURE AND PRESSURE RELIEF VALVE.

FIN TUBE RADIATOR SCHEDULE

TAG	SERVES	TYPE	ENCLOSURE			HEATING ELEMENT			HOT WATER COIL			BASIS OF DESIGN		NOTES							
			TOP	GRILL	HEIGHT	TUBE MATERIAL	FIN DIAMETER	FIN HEIGHT	FIN DEPTH	FIN/FT	ROWS	FLUID	EWT (°F)		LWT (°F)	WPD (FT OF H2O)					
FT-1	LIBRARY UNDER ATRIUM	ARCHITECTURAL	FLAT	BAR GRILL	24	5.56	1,690	COPPER	1	4	4	40	2	WATER	170	150	6.5	0.2	STERLING	JDVB-24	1,2,3

- NOTES:
 1. STANDARD STEEL CASING WITH BAKED ENAMEL FINISH IN COLOR TO BE SELECTED BY ARCHITECT.
 2. MOUNTING HEIGHT 4 INCH A.F.F.
 3. CABINET CASING: 16 GAUGE COLD ROLLED STEEL, EXTRUDED ALUMINUM BAR GRILL.

DOAS CONDENSING UNIT SCHEDULE

TAG	SERVES	TYPE	FAN		COMPRESSOR		CAPACITY		ELECTRICAL			BASIS OF DESIGN		NOTES						
			QUANTITY	DRIVE TYPE	MOTOR HP	POWER	HEATING	COOLING	VOLTS	PHASE	HZ	FLA AMPS	MCA AMPS		MFS AMPS					
CU-DOAS-1	DOAS-1	4	DIRECT	1.5	2	23	150	N/A	402.5	227.8	460	3	60	52.6	58.4	80	ADDISON	MCOA 360 C4	1,978	1,2,3,4,6,7
CU-DOAS-2	DOAS-2	2	DIRECT	1.5	2	10	62	N/A	171.1	98.0	460	3	60	22.6	25	30	ADDISON	MCOA 150 B2	1,293	1,2,3,5,6,7
CU-DOAS-3	DOAS-3	2	DIRECT	1.5	2	18	125	N/A	311.1	173.9	460	3	60	39	43.5	60	ADDISON	MCOA 240 B2	1,930	1,2,3,4,6,7

- NOTES:
 1. FUSED DISCONNECT WITH 65K SCCR - SEE ELECTRICAL DRAWINGS
 2. REFRIGERANT SHALL BE R410A
 3. PROVIDE WITH INTERNAL HOT GAS BYPASS
 4. PROVIDE WITH DUAL SCROLL DUAL CIRCUIT WITH LEAD CIRCUIT VFD
 5. PROVIDE WITH SINGLE DIGITAL SCROLL AND SINGLE SCROLL/DUAL CIRCUIT
 6. PROVIDE WITH SIGHT GLASS
 7. PROVIDE CONDENSER FANS WITH EC MOTORS

DUCTED DESICANT DEHUMIDIFIER SCHEDULE

TAG	SERVES	AIR STREAMS	AIR FLOW										FILTER (1)	ROTOR TYPE	DEHUMID CAPACITY LB/HR	ELECTRICAL			BASIS OF DESIGN			NOTES									
			CFM	OUTSIDE AIR CFM	% OF SA	EXTERNAL IN WC	TOTAL IN WC	BLOWER HP	ENTERING		LEAVING					MERV	THICKNESS INCH	HEATER KW	VOLTS	PHASE	HZ		FLA AMPS	RLA AMPS	MFG	MODEL	WEIGHT (LBS)				
DH-1	RM 110	HVAC AIR FLOW	450	45	10%	2.0	4.2	1.5	50.0	37.5	25.0%	13.2	65.0	43.3	7.6	7.0	8	1	SILICA GEL DESICCANT	1.8	9.0	460	3	60	15.4	8.6	STULZ	DESICAIR DEZ-450-40	330	1, 2	
		REACTIVATION AIR FLOW	150	N/A	N/A	0.8	3.2	0.3	70	58.5	50	54.4	N/A	N/A	N/A	N/A	8	1													

- NOTES:
 1. FILTRATION IS THE SAME FOR BOTH AIR STREAMS.
 2. PROVIDE UNIT MOUNTED DISCONNECT SWITCH

REVERSE OSMOSIS WATER TREATMENT EQUIPMENT

TAG	SERVES	WATER FLOW			CARBON FILTER/WATER SOFTENER		REVERSE OSMOSIS			ELECTRICAL		ACCESSORIES		BOD		NOTES						
		OUTPUT GAL/DAY	CONTINUOUS GPM	DISCHARGE PSIG	TEMPERATURE DEG F	BRINE TANK QUANTITY	CARBON FILTER TANKS QUANTITY	CF/TANK	PRE-FILTER	RO CARTRIDGES	RECOVERY RATE	VOLTS	PHASE	MCCP AMPS	BLADDER TANK GALLONS		DELIVERY PUMP HP					
RO-1	H-1, 2, 3	1,000	6	30	45-77	2	24	2	1.0	5 MICRON	3	41%	208	1	20	30	6	60	3/4	WATER CONTROL CORPORATION	H-1000-MTM1T-CW	1, 2, 3, 4

- NOTES:
 1. INTERLOCK TO RUN WITH HUMIDIFIERS
 2. PROVIDE COMPLETE SKID MOUNTED SYSTEM
 3. ALL DOWNSTREAM CONNECTIONS SHALL BE MADE WITH PLASTIC PIPE (NO COPPER)
 4. PROVIDE ULTRA-LOW ENERGY RO MEMBRANE CARTRIDGES FOR USE WITH COLD WATER.

UNIT HEATER SCHEDULE

TAG	SERVES	TYPE	HEATING			AIR		HOT WATER			FAN			POWER			BASIS OF DESIGN		NOTES											
			MBH	EAT (°F)	LAT (°F)	SA CFM	DISCHARGE	THROW (FT)	MOUNTING HEIGHT (FT)	FLUID	EWT (°F)	LWT (°F)	WPD (FT WC)	CONNECTIONS (INCH)	FAN TYPE	DIAMETER (INCH)	DRIVE	RPM		HP	VOLTS	PH	MCA (AMPS)	MCCP (AMPS)	TRANE MODEL	DIAMENSIONS (INCH) W D H	WEIGHT (LBS)			
UH-1	BS MECHANICAL ROOM	HORIZONTAL	18	60	81	815	HORIZONTAL	22	9	WATER	170	140	1.2	0.1	1-1/4	PROPELLER	13.50	DIRECT	1,550	1/20	120	1	2.6	15	60-S	24.00	17.00	17.00	55	1
UH-2	LOADING DOCK	HORIZONTAL	97	60	89	3,299	HORIZONTAL	40	15	30% PG	170	140	6.8	0.4	1-1/2	PROPELLER	19.75	DIRECT	1,100	1/4	120	1	4.5	15	230-S	39.38	23.00	32.25	190	1
UH-3	LIBRARY MECHANICAL ROOM	VERTICAL	135	40	70	4,430	DOWN	12	12	30% PG	170	140	9.5	1.0	2	PROPELLER	25.25	DIRECT	1,100	1/2	120	1	6.8	15	280-P	37.50	37.50	15.25	135	1
UH-4	LIBRARY MECHANICAL ROOM	VERTICAL	139	40	71	4,430	DOWN	12	12	30% PG	170	140	9.8	1.0	2	PROPELLER	25.25	DIRECT	1,100	1/2	120	1	6.8	15	280-P	37.50	37.50	15.25	135	1
UH-5	LIBRARY MECHANICAL ROOM	VERTICAL	139	40	71	4,430	DOWN	12	12	30% PG	170	140	9.8	1.0	2	PROPELLER	25.25	DIRECT	1,100	1/2	120	1	6.8	15	280-P	37.50	37.50	15.25	135	1
UH-6	LIBRARY MECHANICAL ROOM	VERTICAL	100	40	63	4,162	DOWN	12	12	30% PG	170	140	7.0	0.8	2	PROPELLER	25.25	DIRECT	1,100	1/4	120	1	4.5	15	252-P	37.50	37.50	15.13	135	1
UH-7	LIBRARY MECHANICAL ROOM	VERTICAL	100	40	63	4,162	DOWN	12	12	30% PG	170	140	7.0	0.8	2	PROPELLER	25.25	DIRECT	1,100	1/4	120	1	4.5	15	252-P	37.50	37.50	15.13	135	1
UH-8	ARCHIVES MECHANICAL ROOM	VERTICAL	128	40	70	4,162	DOWN	12	12	30% PG	170	140	9.0	0.8	2	PROPELLER	25.25	DIRECT	1,100	1/4	120	1	4.5	15	252-P	37.50	37.50	15.13	135	1
UH-9	ARCHIVES MECHANICAL ROOM	VERTICAL	153	40	69	5,210	DOWN	12	12	30% PG	170	140	10.8	1.3	2	PROPELLER	25.25	DIRECT	1,140	3/4	480	3	2.0	15	336-P	37.50	37.50	16.75	135	1
UH-10	ARCHIVES WATER ENTRANCE...	HORIZONTAL	12	60	74	815	HORIZONTAL	22	9	30% PG	170	140	0.8	0.1	1-1/4	PROPELLER	13.50	DIRECT	1,550	1/20	120	1	2.6	15	60-S	24.00	17.00	17.00	55	1
UH-11	MUSEUM MECHANICAL ROOM	HORIZONTAL	75	40	71	2,380	HORIZONTAL	40	14	30% PG	170	140	5.3	1.2	1-1/2	PROPELLER	19.75	DIRECT	1,100	1/8	120	1	2.9	15	168-S	33.75	22.00	26.25	145	1
UH-12	MUSEUM MECHANICAL ROOM	HORIZONTAL	158	40	74	4,480	HORIZONTAL	50	15	30% PG	170	140	11.1	1.2	1-1/2	PROPELLER	25.25	DIRECT	1,100	1/2	120	1	6.8	15	320-S	52.13	25.00	32.25	190	1
UH-13	MUSEUM MECHANICAL ROOM	HORIZONTAL	40	40	65	1,535	HORIZONTAL	28	9	30% PG	170	140	2.8	0.2	1-1/4	PROPELLER	16.75	DIRECT	1,100	1/8	120	1	2.1	15	100-S	26.75	18.75	20.25	85	1

- NOTES:
 1. ACTUAL MBH IS THE CATALOG MBH RATED FOR ENTERING AIR TEMPERATURE (EAT) AND ENTERING AND LEAVING WATER TEMPERATURE LISTED.

PUMP SCHEDULE

TAG	SERVICE	TYPE	FLUID	CASING MATERIAL	FLOW GPM	HEAD FT H2O	EFFICIENCY	CONNECTION		IMPELLER DIAMETER (INCH)	MOTOR			POWER		BASIS OF...		WEIGHT (LBS.)	NOTES			
								TYPE	DISCHARGE (INCH)		CONTROL	HP	RPM	BHP	VOLTS	PHASE	HZ			MFG	MODEL	
P-1	GLYCOL LOOP TO DOAS, AHU'S, UHS	BASE MOUNTED END SUCTION	30% PROPYLENE GLYCOL / WATER	CAST IRON	235	45	77%	FLANGES	3	2-1/2	7.75	VFD	5	1,760	3.58	480	3	60	TACO	2510C	542	1,2,3,4,5
P-2	GLYCOL LOOP TO DOAS, AHU'S, UHS	BASE MOUNTED END SUCTION	30% PROPYLENE GLYCOL / WATER	CAST IRON	235	45	77%	FLANGES	3	2-1/2	7.75	VFD	5	1,760	3.58	480	3	60	TACO	2510C	542	1,2,3,4,5
P-3	100% WATER LOOP TO VAV'S, CONVECTORS	BASE MOUNTED END SUCTION	100% WATER	CAST IRON	65	39	67%	FLANGES	2	1-1/4	7.25	VFD	2	1,760	0.96	480	3	60	TACO	1207D	226	1,2,3,4,5
P-4	100% WATER LOOP TO VAV'S, CONVECTORS	BASE MOUNTED END SUCTION	100% WATER	CAST IRON	65	39	67%	FLANGES	2	1-1/4	7.25	VFD	2	1,760	0.96	480	3	60	TACO	1207D	226	1,2,3,4,5
P-5	RECIRCULATION HOT WATER	INLINE	100% WATER	COMPOSITE	5	11	-	UNION	1	1	-	ECM	1/40	1,590-4,830	-	115	1	60	TACO	006e3	3.5	6

- NOTES:
 1. PROVIDE SELF-SENSING SPEED CONTROL AND BACNET INTERFACE FOR BAS.
 2. VFD PROVIDED BY PUMP MANUFACTURER WITH INTEGRAL POWER DISCONNECT SWITCH
 3. PROVIDE FLANGES TO MATCH PUMP TO PIPE SIZE.
 4. PROVIDE WITH 1/4 INCH NPT PRESSURE GAUGE PORTS.
 5. PROVIDE WITH SUCTION DIFFUSER WITH STRAINER SIZED TO MATCH INLET PIPE AND PUMP SUCTION.
 6. DOMESTIC HOT WATER CIRCULATION PUMP FOR OPEN LOOP POTABLE WATER SERVICE WITH 3 SPEED CONTROL.

HUMIDIFIER SCHEDULE

TAG	SERVES	AIRFLOW CFM	DUCT SIZE INCHES	DUCT VELOCITY FPM	ENTERING AIR			LEAVING AIR			CAPACITY		DISPERSION TUBES		NON-WETTING DISTANCE INCH	CONTROL	POWER			MFG	STEAM GENERATOR MODEL	DISPERSION TUBE MODEL	OPERATING WEIGHT (LBS)	NOTES						
					TEMPERATURE °F	HUMIDITY %	TEMPERATURE °F	HUMIDITY %	INLET WATER GPH	LOAD LB/HR	OUTPUT LB/HR	LENGTH INCH	INLET INCH	OUTLET INCH			ROWS	VOLTS	PHASE						HZ	KW	FLA	MCCP		
H-1	DOAS-1	7,550	36x24	1,258	68.0	49.7	24.7	68.6	55.3	40%	11.5	95.0	102.0	40.0	2.0	2.0	1	20	SSR SEQUENCING	480	3	60	34	40.9	60	DRISTEEM	VAPORMIST VM-34	SINGLE TUBE	160	1, 2, 3, 4, 5, 6
H-2	DOAS-2	3,450	30x16	1,035	68.0	49.7	24.8	68.6	55.3	40%	5.3	43.6	48.0	34.0	2.0	2.0	1													

AIR HANDLING UNIT SCHEDULE

TAG	SERVES	AIR FLOW				FAN										FILTERS				COILS																	
		SUPPLY AIR MAX (CFM)	MINIMUM OUTSIDE AIR (CFM)	FAN		STATIC PRESSURE		DRIVE		WHEEL		MOTOR		MERV	DEPTH (INCH)	APD (IN WC)	AREA (SF)	AIR				FLUID				COIL		CAPACITY									
				SERVICE	ESP (IN WC)	TOTAL (IN WC)	TYPE	CONTROL	DESIGN (HZ)	TYPE	NUMBER OF FANS	DIAMETER (INCH)	RPM					BHP EACH	MHP EACH	NOMINAL RPM	TYPE	EAT °F	LAT °F	APD (IN WC)	FLUID	EWT (°F)	LWT (°F)	FLOW (GPM)	WPD (FT)	AREA (SF)	ROWS	TOTAL MBH	SENS MBH				
AHU-1	EXHIBIT LEVELS 1 & 2	6,600	2,110	RETURN	1.50	1.92	DIRECT	VFD	62	PLENUM AIRFOIL	1	20.00	1,455	3.9	5.0	1,800	PRE	8	2	0.65	13.44	VRF COOLING	72.0	62.0	54.0	52.7	0.42	R-410A	N/A	N/A	N/A	N/A	13.4	4	144	161	118
				SUPPLY	2.00	4.61	DIRECT	VFD	76	PLENUM AIRFOIL	1	20.00	2,248	7.6	10.0	1,800	FINAL	15	12	0.83	13.44	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
AHU-2	EXHIBIT LEVEL 3	4,700	1,230	RETURN	1.50	1.80	DIRECT	VFD	73	PLENUM AIRFOIL	1	18.25	2,140	3.0	5.0	1,800	PRE	8	2	0.67	8.67	VRF COOLING	72.0	62.0	55.0	53.5	0.70	R-410A	N/A	N/A	N/A	N/A	10	4	158	131	88
				SUPPLY	2.00	4.76	DIRECT	VFD	79	PLENUM AIRFOIL	1	18.25	2,341	5.6	7.5	1,800	FINAL	15	12	0.62	18.89	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
AHU-3	EXHIBIT LEVEL 4	4,400	980	SUPPLY	2.00	4.68	DIRECT	VFD	69	PLENUM AIRFOIL	1	22.25	2,026	9.5	10.0	1,800	PRE	8	2	0.63	18.89	VRF COOLING	72.0	63.0	55.0	53.5	0.76	R-410A	N/A	N/A	N/A	N/A	6.1	4	163	84	56
AHU-4	ATRIUM	7,500	770	SUPPLY	1.50	3.42	DIRECT	VFD	60	PLENUM AIRFOIL	1	20.00	2,042	6.3	7.5	1,800	PRE	8	2	0.01	-	DX COOLING	76.2	63.4	51.2	51.0	0.35	R-410A	N/A	N/A	N/A	N/A	17.4	4	15	209	191
																	FINAL	14	4	0.82	-	HYDRONIC HEATING	64.5	N/A	95.0	N/A	0.39	30% GLYCOL	170	140	16.3	0.50	17.4	2	12	233	N/A

AIR HANDLING UNIT SCHEDULE (CONTINUED)

TAG	SERVES	ARRANGEMENT		ELECTRICAL						BASIS OF DESIGN			NOTES	
		ACCESS SIDE	BASE RAIL HEIGHT (INCH)	POWER SUPPLY			CURRENT			MFG	MODEL	WEIGHT (LBS)		
				LOAD	VOLTS	PHASE	HZ	FLA (AMPS)	MCA (AMPS)					MOCAP (AMPS)
AHU-1	EXHIBIT LEVELS 1 & 2	LEFT	6	UNIT	480	3	60	22.20	25.70	35	TRANE	CSAA014	2,814	1, 2, 3, 4, 6, 7, 8, 9, 10, 11
				LIGHTS	120	1	60	2.61	3.26	15				
				RECEPTACLE	120	1	60	8.00	10.00	15				
				LEV	208	1	60	0.06	--	15				
				LEV	208	1	60	0.06	--	15				
				UNIT	480	3	60	19.20	21.95	30				
AHU-2	EXHIBIT LEVEL 3	LEFT	6	LIGHTS	120	1	60	2.61	3.26	15	TRANE	CSAA010	2,449	1, 2, 3, 4, 6, 7, 8, 9, 10, 11
				RECEPTACLE	120	1	60	8.00	10.00	15				
				LEV	208	1	60	0.06	--	15				
				LEV	208	1	60	0.06	--	15				
				UNIT	480	3	60	8.20	10.25	30				
				LIGHTS	120	1	60	2.61	3.26	15				
AHU-3	EXHIBIT LEVEL 4	LEFT	6	RECEPTACLE	120	1	60	8.00	10.00	15	TRANE	CSAA008	1,540	1, 2, 3, 4, 6, 7, 8, 9, 10, 11
				LEV	208	1	60	0.06	--	15				
				UNIT	480	3	60	40.80	44.00	50				
AHU-4	ATRIUM	-	6	UNIT	480	3	60	40.80	44.00	50	TRANE	OADG017F3	3,130	1, 2, 3, 4, 5, 8, 9, 10, 11

- NOTES:
 1. PROVIDE FACTORY WIRE LED MARINE TYPE LIGHTS IN FAN SECTIONS WITH LIGHT SWITCH & CONVENIENCE OUTLET ON OUTSIDE OF UNIT CASING.
 2. PROVIDE 115 VOLT 15 AMP CIRCUIT FOR UNIT LIGHTS & CONVENIENCE OUTLET.
 3. PROVIDE UNIT MOUNTED VFDs.
 4. MID-LIFE FILTER PRESSURE DROP LISTED FOR FILTERS AND USED FOR FAN PERFORMANCE RATING.
 5. ROOFTOP UNIT WITH INTEGRAL COOLING COMPRESSORS AND CONDENSERS.
 6. PROVIDE INLET BELL AND PERFORATED PANELS ON FAN SECTIONS TO REDUCE NOISE.
 7. PROVIDE LEV KIT AND REFRIGERANT CIRCUITING TO MATCH VRF CONDENSING UNIT. REQUIRES DEDICATED 208V/1PH CIRCUIT.
 8. PROVIDE WITH DUCT MOUNTED SMOKE DETECTOR.
 9. PROVIDE WITH CONDENSATE OVERFLOW SWITCH.
 10. PROVIDE UNIT MANUFACTURER'S CURBS WITH MINIMUM 21 INCH HIGH HORIZONTAL DISCHARGE CURB EXTENSION. CURBS SHALL BE GALVANIZED STEEL WITH 1 INCH THICK FOIL FACED INSULATION.
 11. PROVIDE ELL MODULATION OUTSIDE AIR DAMPER.
 12. PROVIDE MEZONETER AIRFLOW MEASURING TAPS IN THE FAN WITH TRANSDUCERS TO CONVERT DIFFERENTIAL PRESSURE TO CFM.

VAV BOX SCHEDULE

TAG	SERVES	DESCRIPTION	INLET DIAMETER (INCH)	DESIGN AIRFLOW		MAX APD (IN WC)	# COIL ROWS	CAPACITY (MBH)	FLOW (GPM)	EAT (DEG F)	LAT (DEG F)	EWT (DEG F)	LWT (DEG F)	MAX WPD (FT HD)	BASIS OF DESIGN		NOTES
				MAX (CFM)	MIN (CFM)										MFG	MODEL	
VAV 1-1	AHU-1, FLOORS 1 & 2 INTERIOR	SINGLE DUCT VAV TERMINAL BOX	12	1,300	650	0.2	1	27.6	2.8	65	85.0	170	150	4.3	TRANE	VCWF	1,2,3,4,5,7
VAV 1-2	AHU-1, FLOORS 1 & 2 NORTHWEST	SINGLE DUCT VAV TERMINAL BOX	8	600	300	0.2	1	14.9	1.5	65	88.0	170	150	6	TRANE	VCWF	1,2,3,4,5,6,7
VAV 1-3	AHU-1, FLOORS 1 & 2 SOUTHWEST	SINGLE DUCT VAV TERMINAL BOX	10	800	400	0.2	2	23.6	2.4	65	92.3	170	150	2	TRANE	VCWF	1,2,3,4,5,6,7
VAV 1-4	AHU-1, FLOORS 1 & 2 SOUTH	SINGLE DUCT VAV TERMINAL BOX	14	2,050	1,030	0.2	1	31.7	3.2	65	79.3	170	150	4	TRANE	VCWF	1,2,3,4,5,6,7
VAV 1-5	AHU-1, FLOORS 1 & 2 WEST	SINGLE DUCT VAV TERMINAL BOX	14	1,850	930	0.2	1	48.0	4.8	65	89.0	170	150	6.5	TRANE	VCWF	1,2,3,4,5,6,7
VAV 2-1	AHU-2, FLOOR 3 INTERIOR	SINGLE DUCT VAV TERMINAL BOX	10	1,000	500	0.01	1	26.1	2.6	65	85.0	170	150	3.9	TRANE	VCWF	1,2,3,4,5,7
VAV 2-2	AHU-2, FLOOR 3 EAST	SINGLE DUCT VAV TERMINAL BOX	10	900	450	0.2	2	26.0	2.6	65	91.7	170	150	2	TRANE	VCWF	1,2,3,4,5,6,7
VAV 2-3	AHU-2, FLOOR 3 SOUTH	SINGLE DUCT VAV TERMINAL BOX	12	1,600	--	0.3	1	22.0	2.2	65	77.7	170	150	4	TRANE	VCWF	1,2,3,4,5,6,7
VAV 2-4	AHU-2, FLOOR 3 WEST	SINGLE DUCT VAV TERMINAL BOX	12	1,200	600	0.2	1	34.0	3.4	65	91.2	170	150	7	TRANE	VCWF	1,2,3,4,5,6,7

- NOTES:
 1. PROVIDE WITH 3/8" CLOSED CELL INSULATION
 2. CONTROLS ACTUATORS AND SENSORS BY MECHANICAL AND CONTROLS CONTRACTOR.
 3. CONTRACTOR TO VERIFY "HAND" OF UNIT PRIOR TO ORDER
 4. REFER TO CONTROLS DRAWINGS FOR CONTROL POINTS AND EQUIPMENT.
 5. PROVIDE UNIT-MOUNTED DISCONNECT.
 6. REPEAT PROVIDED BY 100% HYDRONIC WATER.
 7. BOXES SHALL BE SELECTED FOR MAX. NC OF 20

CONVECTOR SCHEDULE

TAG	SERVES	TYPE	REQ. MBH	HOT WATER COIL				BASIS OF DESIGN			NOTES			
				FLUID	EWT (°F)	LWT (°F)	FLOW (GPM)	WPD (FT H2O)	MFG	MODEL		DIMENSIONS (INCHES)		
						L	D	H						
CONV-1	STAIR 2, FLOOR 1, LIB	RECESSED, WALL MOUNTED	8.47	WATER	170	150	0.85	0.2	STERLING	FWG-A	52	6	32	1,2,3,4,5,6,7,8,9
CONV-2	STAIR 6, FLOOR 1, EXHIBIT	RECESSED, WALL MOUNTED	8.40	30% PG	170	150	0.88	0.2	STERLING	FWG-A	52	6	32	1,2,3,4,5,6,7,8,9
CONV-3	STAIR 1, FLOOR 2, LIB	RECESSED, WALL MOUNTED	8.18	WATER	170	150	0.82	0.1	STERLING	FWG-A	44	8	32	1,2,3,4,5,6,7,8,9
CONV-4	STAIR 4, FLOOR 3, ARCHIVE	RECESSED, WALL MOUNTED	8.18	WATER	170	150	0.82	0.1	STERLING	FWG-A	44	8	32	1,2,3,4,5,6,7,8,9
CONV-5	STAIR 5, FLOOR 3, ARCHIVE	RECESSED, WALL MOUNTED	8.18	WATER	170	150	0.82	0.1	STERLING	FWG-A	44	8	32	1,2,3,4,5,6,7,8,9
CONV-6	STAIR 7, FLOOR 3, EXHIBIT	RECESSED, WALL MOUNTED	11.46	WATER	170	150	1.15	0.2	STERLING	FWG-A	60	8	32	1,2,3,4,5,6,7,8,9

- NOTES:
 1. STANDARD MFR CASING COLOR SELECTION TO BE APPROVED BY ARCHITECT.
 2. UNIT SHALL HAVE A BOTTOM DISCHARGE.
 3. PROVIDE INSULATION ON BACK OF CONVECTOR.
 4. CABINET CASING: FRONT 1/8 GAUGE, SIDES AND BACK: 20 GAUGE.
 5. HTG ELEMENT: 1/2" CU TUBE, 0.01" AL FINIS.
 6. UNIT SHALL HAVE OPPOSITE END CONNECTIONS.
 7. UNIT SHALL HAVE LOUVERED AIR VENTS.
 8. UNIT SHALL HAVE ACCESS DOORS, WITH Allen-KEY.
 9. UNIT SHALL HAVE FACTORY APPLIED FINISH.

CONDENSING UNIT SCHEDULE

TAG	SERVES	# OF MODULES	CONDENSER AIR FLOW				CAPACITY		COOLING EFFICIENCY IEER / EER	HEATING OUTDOOR TEMP DEG F	COOLING OUTDOOR TEMP DEG F	REFRIGERANT CHARGE PER MODULE			ELECTRICAL PER MODULE			BASIS OF DESIGN		NOTES	
			# FANS	TOTAL CFM	ESP IN WC	COOLING MBH	HEATING MBH	FACTORY LBS				FIELD ADDED LBS	TOTAL LBS	VOLTS	PHASE	HZ	MCA AMPS	MOCAP AMPS	MITSUBISHI MODEL		WEIGHT LBS
CU-1	FIRST FLOOR LIBRARY	1	2	9,200	0.32	129	112	25.9 / 11.6	33.6	88.0	24	63.1	87	460	3	60	20	30	TURYP1444AN40AN	715	1-5
CU-2	SECOND FLOOR LIBRARY	2	4	19,100	0.32	254	247	24.25 / 10.55	33.6	88.0	24	95.8	120	460	3	60	20	30	TURYP2894BN40AN	1,364	1-5
CU-3	THIRD FLOOR LIBRARY	2	4	14,800	0.32	171	176	27.5 / 12.7	33.6	88.0	11	52.7	63	460	3	60	15	20	TURYP1924BN40AN	1,222	1-5
CU-4	FIRST/SECOND FLOOR ARCHIVES	1	2	9,200	0.32	128	121	27.5 / 12.9	33.6	88.0	23	40.1	63	460	3	60	21	35	TUHYE1444AN40AN	715	1-5
CU-5	THIRD FLOOR ARCHIVES	1	2	14,850	0.32	151	133	23.55 / 10.8	33.6	88.0	24	57.0	81	460	3	60	28	40	TURYP1684AN40AN	774	1-5
CU-6	FOURTH FLOOR MUSEUM	1	1	6,000	0.32	56	62	26.5 / 13.9	33.6	88.0	11	42.5	54	460	3	60	11	15	TURYP0724AN40AN	552	1-5
CU-7	FIFTH FLOOR MUSEUM	1	2	14,850	0.32	144	132	23.55 / 11.0	33.6	88.0	24	69.7	93	460	3	60	28	40	TURYP1684AN40AN	774	1-5
CU-8	AHU-1	2	4	13,400	0	185	112	28.15 / 13	-7.5	95.0	22	20.0	42	460	3	60	15	20	TUHYP1924BN40AN	1,210	1-3,5
CU-9	AHU-2	2	4	13,400	0	185	112	28.15 / 13	-7.5	95.0	22	20.0	42	460	3	60	15	20	TUHYP1924BN40AN	1,210	1-3,5
CU-10	AHU-3	1	2	6,700	0	95	57	29.4 / 14	-7.5	95.0	22	8.7	30	460	3	60	15	20	TUHYP064AN40AN	605	1-3,5

- NOTES:
 1. TWO DIRECT DRIVE CONDENSER FANS SHALL BE INVERTER CONTROLLED AND BRUSHLESS DC MOTOR.
 2. PROVIDE WITH PANEL HEATER KIT
 3. USES R-410A AS REFRIGERANT.
 4. PROVIDE WITH EXTERNAL STATIC PRESSURE OPTION.
 5. DISCONNECT SWITCH(ES) BY DIV 26

CONTROL DAMPERS SCHEDULE

TAG	LOCATION	SERVES	MATERIAL	TYPE	BLADE ACTION	AIRFLOW		NUMBER OF DAMPERS	DEPTH (INCH)	WIDTH (INCH)	HEIGHT (INCH)	APD (IN WC)	BASIS OF DESIGN		NOTES	
						DIRECTION	AIRFLOW PER DAMPER (CFM)						TOTAL AIRFLOW (CFM)	MFG		MODEL
D-1A	LIBRARY MECH 315	CU-1	ALUMINUM	INSULATED AIRFOIL	PARALLEL	EXHAUST	9,200	9,200	1	5	48	30	0.07	GREENHECK	ICD-45	1, 2, 3, 4
D-1B	LIBRARY MECH 315	CU-1	ALUMINUM	INSULATED AIRFOIL	PARALLEL	INTAKE	9,200	9,200	1	5	48</					

SEQUENCE OF OPERATION

1.1 GENERAL

- A. THE BUILDING AUTOMATION SYSTEM (BAS) SHALL CONTROL ALL THE HVAC SYSTEMS IN ACCORDANCE WITH THE DRAWINGS AND POINTS LISTS.
- B. REFER TO SPECIFICATION 230923 FOR DESCRIPTION OF CONTROL SYSTEM INTEGRATION WITH THE STATE OF MAINE BUILDING CONTROL CENTER (BCC) WHICH USES THE HONEYWELL ENTERPRISE BUILDING INTEGRATOR (EBI) SYSTEM.
- C. THE INTENT IS TO PROVIDE ALL NEW BAS SYSTEM COMPONENTS IN THE MAINE CULTURAL BUILDING TO INCLUDE SENSORS, CONTROL WIRING, CONDUIT, CONTROLLERS, ACTUATORS, ETC.
- D. THE GRAPHIC SCREENS SHALL BE UPDATED TO INCORPORATE GRAPHIC CONTROL AND MONITORING OF ALL HVAC EQUIPMENT FOR A COMPLETE CONTROL SYSTEM.
- E. THE HVAC SYSTEMS SHALL BE AVAILABLE 24 HOURS PER DAY, 7 DAYS PER WEEK.
- F. PUMPS SHALL BE PROVEN ON USING A CURRENT TRANSFORMER (CT) ON THE POWER SUPPLY TO THE PUMP FROM THE VFD. CT SETPOINT SHALL BE 10% LESS THAN THE CURRENT MEASURED AT MINIMUM PUMP SPEED.
- G. FAIL SAFE POSITIONS ARE POSITIONS THAT DEVICES WILL GO TO WHEN DE-ENERGIZED: NO = NORMALLY OPEN, NC = NORMALLY CLOSED.
- H. ALL LISTED SETPOINTS SHALL BE ADJUSTABLE AT THE BAS WORKSTATION WITHOUT PROGRAMMING.
- I. ALL TEMPERATURES LISTED ARE IN DEGREES FAHRENHEIT (°F).
- J. ADJUSTABLE (ADJ) MEANS THAT THE SETPOINT OR SCHEDULE CAN BE CHANGED USING THE BAS WORKSTATION GRAPHICS WITHOUT PROGRAMMING.
- K. SUPPLY AND RETURN AIRFLOW SHALL BE MEASURED IN CFM USING PIEZOMETER TAPS AND TRANSDUCER PROVIDED BY AHU MANUFACTURER IN AHU SUPPLY AND RETURN FANS.
- L. OUTSIDE AIRFLOW SHALL BE MEASURED IN CFM USING FLOW MEASURING DAMPERS PROVIDED IN AIR MIXING SECTION OF AHU-1, AHU-2, AHU-3.

1.2 SCHEDULES

- A. PROVIDE AN ADJUSTABLE OCCUPANCY SCHEDULE IN THE GRAPHICS FOR EACH SYSTEM TO SWITCH HVAC EQUIPMENT BETWEEN OCCUPIED AND UNOCCUPIED MODES. SCHEDULES SHALL BE ADJUSTABLE WITHOUT PROGRAMMING USING THE BAS WORKSTATION.
 - 1. OCCUPIED HOURS SHALL BE EASILY ADJUSTABLE AT THE BAS WORKSTATION. INITIAL SCHEDULE SHALL BE 7 DAYS A WEEK FROM 7 AM TO 5 PM, OR AS DIRECTED BY STATE OF MAINE PERSONNEL.
 - 2. PROVIDE OPTIMUM START ALGORITHM TO SWITCH THE SYSTEM TO THE OCCUPIED SETPOINTS AT THE LATEST TIME POSSIBLE SO THAT SPACE TEMPERATURE REACHES THE OCCUPIED TEMPERATURE SETPOINT AT THE SCHEDULED OCCUPANCY TIME. VENTILATION SYSTEMS SHALL REMAIN OFF UNTIL THE SCHEDULED OCCUPIED HOURS.
 - 3. PROVIDE THE CAPABILITY TO PROGRAM OR ADJUST OCCUPIED HOURS FOR SPECIAL EVENTS AT THE BAS WORKSTATION.
 - 4. PROVIDE THE CAPABILITY TO PROGRAM OR ADJUST UNOCCUPIED HOURS FOR UP TO ONE YEAR FOR HOLIDAYS OR OTHER PERIODS WHEN THE BUILDING WILL BE CLOSED.

1.3 USER PERMISSIONS AND REMOTE ACCESS

- A. PROVIDE MULTIPLE LEVELS OF USER ACCESS WITH THE FOLLOWING ACCESS LEVELS AS A MINIMUM:
 - 1. FULL ACCESS: OPERATOR CAN ASSIGN USER NAMES, PASSWORDS, ADJUST ALL SETPOINTS AND SCHEDULES, AND OVERRIDE CONTROL POINTS.
 - 2. NORMAL USER ACCESS: OPERATOR CAN ADJUST ALL SETPOINTS AND SCHEDULES.
 - 3. LOW LEVEL ACCESS: OPERATOR CAN SEE THE GRAPHICS DISPLAY AND OBSERVE SYSTEM OPERATION BUT DOES NOT HAVE ACCESS TO MAKE ANY CHANGES.
- B. PROVIDE THE CAPABILITY FOR AUTHORIZED USERS TO LOG IN TO THE BAS SYSTEM FROM A REMOTE COMPUTER USING THEIR USERNAME AND PASSWORD. REMOTE ACCESS SHALL SHOW THE GRAPHICS DISPLAY AND ALLOW MODIFICATIONS TO SETPOINTS AND SCHEDULES FOR USERS WITH NORMAL OR FULL ACCESS.

1.4 THERMOSTATS

- A. THE OCCUPIED SPACE TEMPERATURE SETPOINT SHALL BE BASED ON THE DESIGN CONDITIONS SCHEDULE IN THE DRAWINGS. WHERE THE SPACE TEMPERATURE SETPOINT IS NOT OTHERWISE INDICATED, THE INITIAL SETPOINT SHALL BE 75°F COOLING (ADJUSTABLE), HEATING SETPOINT SHALL BE 5°F LOWER (ADJUSTABLE), FOR A 5°F DEADBAND.

- B. OCCUPIED SETPOINT SHALL BE OCCUPANT ADJUSTABLE, EXCEPT WHERE NOTED OTHERWISE. LIMIT ADJUSTMENT TO A MINIMUM OF 70°F AND A MAXIMUM OF 76°F COOLING. OCCUPIED SETPOINT SHALL NOT BE OCCUPANT ADJUSTABLE IN THE LEVEL 1 AND 2 ARCHIVES SPACES.
- C. UNOCCUPIED SETPOINT SHALL BE 62°F HEATING, 62°F COOLING (ADJUSTABLE AT THE BAS WORKSTATION). UNOCCUPIED SETPOINT SHALL BE THE SAME AS OCCUPIED SETPOINT IN THE LEVEL 1 AND 2 ARCHIVES SPACES.
- D. OVERRIDE BUTTON ON THE THERMOSTAT SHALL OVERRIDE THE SYSTEM TO OCCUPIED MODE FOR 2 HOURS (ADJUSTABLE).

1.5 VARIABLE REFRIGERANT FLOW (VRF) SYSTEMS

- A. GENERAL
 - 1. EACH VARIABLE REFRIGERANT FLOW SYSTEM AND ITS VARIOUS COMPONENTS (FAN COILS, BRANCH CIRCUIT CONTROLLERS, LEV KITS, AND CONDENSING UNITS) SHALL BE CONTROLLED BY THE VRF SYSTEM VENDOR'S CONTROL SYSTEM USING ITS OWN INTERNAL SAFETIES AND CONTROL SEQUENCES TO MAINTAIN SPACE TEMPERATURE SETPOINT.
 - 2. VRF CONTROLLERS SHALL COMMUNICATE WITH THE BAS OVER BACNET TO MONITOR EQUIPMENT STATUS AND ADJUST SETPOINTS FROM THE BAS WORKSTATION.
 - 3. SPACE TEMPERATURE AND SPACE TEMPERATURE SETPOINT SHALL BE INTEGRATED INTO THE BAS GRAPHICS. SETPOINT ADJUSTMENT SHALL BE AVAILABLE TO USER LEVEL 2 OR HIGHER AT THE BAS WORKSTATION.

B. VRF OUTDOOR UNITS INSTALLED INDOORS

- 1. WHERE VRF OUTDOOR UNITS ARE INSTALLED IN MECHANICAL ROOMS, EACH OUTDOOR UNIT SHALL HAVE ONE OR MORE OUTSIDE AIR DAMPERS, EXHAUST AIR DAMPERS, AND RETURN AIR DAMPERS.
- 2. WHEN OUTDOOR AIR TEMPERATURE IS AT OR ABOVE THE MECHANICAL ROOM TEMPERATURE SETPOINT (MRTS) (INITIALLY 40 DEG F +/- 5 DEG F, ADJUSTABLE), THE OUTSIDE AIR DAMPERS AND EXHAUST AIR DAMPERS SHALL BE OPEN WHILE THE RETURN AIR DAMPERS ARE CLOSED.
- 3. WHEN OUTDOOR AIR TEMPERATURE IS BELOW THE MECHANICAL ROOM TEMPERATURE SETPOINT, THE OUTDOOR AIR DAMPERS AND EXHAUST AIR DAMPERS SHALL BE CLOSED AND THE RETURN AIR DAMPERS SHALL OPEN. THE UNIT HEATERS SHALL OPERATE TO MAINTAIN SPACE TEMPERATURE AT THE MECHANICAL ROOM TEMPERATURE SETPOINT.
- 4. REFRIGERANT MONITORING: PROVIDE AND INSTALL A REFRIGERANT MONITORING DEVICE TO DETECT R-410a LOCATED WITHIN 12 INCHES ABOVE THE LOWEST FLOOR LEVEL IN EACH OF THE THREE MECHANICAL ROOMS: 315, 348, 416.
 - a. IF DETECTED REFRIGERANT CONCENTRATION RISES ABOVE 50 PPM (ADJUSTABLE), OVERRIDE THE OUTSIDE AIR AND EXHAUST AIR DAMPERS OPEN TO DILUTE REFRIGERANT. ACTIVATE ALARM BELL AND WARNING LIGHT LOCATED JUST ABOVE THE ROOM ACCESS DOORS, AND GENERATE A CRITICAL ALARM AT THE BAS WORKSTATION.
 - b. WHEN REFRIGERANT CONCENTRATION DROPS BELOW 10 PPM FOR 5 MINUTES (ADJUSTABLE), SILENCE THE ALARM AND ALLOW OUTSIDE AIR AND EXHAUST AIR DAMPERS TO CLOSE IF OUTSIDE AIR TEMPERATURE IS BELOW THE MECHANICAL ROOM TEMPERATURE SETPOINT.

1.6 VENTILATION SYSTEMS

A. SCHEDULE

- 1. VENTILATION SYSTEMS SHALL BE SET TO OCCUPIED MODE WHENEVER ANY OF THE SERVED VRF AND AHU SYSTEMS ARE IN OCCUPIED MODE.
- 2. VENTILATION SYSTEMS SHALL DEFAULT TO UNOCCUPIED MODE WHENEVER ALL OF THE SERVED VRF AND AHU SYSTEMS ARE IN UNOCCUPIED MODE.

B. ENERGY RECOVERY VENTILATOR (ERV): ERV-1, ERV-2, ERV-3

- 1. OCCUPIED MODE
 - a. THE OUTSIDE AIR DAMPER AND EXHAUST AIR DAMPER SHALL OPEN AND THE ERV SUPPLY AND EXHAUST FANS SHALL START AT LOW SPEED, THEN RAMP UP TO NORMAL FAN SPEED NEEDED TO SUPPLY SCHEDULED OUTSIDE AIR (SAME AIRFLOW AS THE ASSOCIATED DOAS UNIT) AND EXHAUST AIR, AS MEASURED AND SET BY THE TAB CONTRACTOR.

- b. THE ERV FANS SHALL RUN CONTINUOUSLY TO SUPPLY MINIMUM OUTSIDE AIR TO THE ASSOCIATED DOAS UNITS.
- c. THE ERV 30% PROPYLENE GLYCOL / HOT WATER PRE-HEAT COIL CONTROL VALVE SHALL MODULATE TO MAINTAIN ENTERING AIR TEMPERATURE (EAT) TO THE HEAT EXCHANGER CORE OF 20 DEG F (ADJUSTABLE).
- d. WHEN OUTSIDE AIR IS COLDER THAN 10 DEG F, THE HEATING COIL CONTROL VALVE MINIMUM POSITION SHALL BE 10% OPEN (ADJUSTABLE).

2. UNOCCUPIED MODE

- a. ERV FANS SHALL BE OFF AND THE OUTSIDE AIR DAMPER AND EXHAUST AIR DAMPER SHALL BE CLOSED. THE HEATING COIL CONTROL VALVE SHALL CLOSE.
- b. WHEN OUTSIDE AIR IS COLDER THAN 20 DEG F, THE HEATING COIL CONTROL VALVE SHALL MODULATE TO MAINTAIN SPACE TEMPERATURE DOWNSTREAM OF THE HEATING COIL AT THE HX CORE EAT SETPOINT (20 DEG F).

3. ALARMS

- A. LOW ENTERING AIR TEMPERATURE
 - 1) IF ENTERING AIR TEMP TO THE HEAT EXCHANGER CORE DROPS BELOW 15 DEG F (ADJ) FOR 10 MINUTES (ADJ), GENERATE AN ALARM.
 - 2) IF ENTERING AIR TEMP TO THE HEAT EXCHANGER CORE DROPS BELOW 15 DEG F (ADJ) FOR 30 MINUTES (ADJ), SHUT DOWN THE ERV, THE ASSOCIATED DOAS, EXHAUST AIR DAMPERS, AND RETURN AIR DAMPERS.

B. DIRTY FILTERS

- 1) PROVIDE FILTER DIFFERENTIAL PRESSURE (DP) SENSOR FOR ERV OUTSIDE AIR AND RETURN AIR FILTERS. STATUS OF FILTER DP SENSORS SHALL BE INDICATED ON THE GRAPHICS ON THE BAS WORKSTATION.
- 2) WHEN PRESSURE DROP ACROSS THE FILTER EXCEEDS 1.0 IN WC (ADJUSTABLE) INDICATING FILTERS NEED TO BE CHANGED, GENERATE ALARM ON THE BAS WORKSTATION.

- C. WIRE DUCT SMOKE DETECTORS TO SHUT OFF THE ERV FANS, CLOSE ITS OUTSIDE AIR AND EXHAUST DAMPERS, SET THE ASSOCIATED DOAS TO UNOCCUPIED MODE, AND GENERATE AN ALARM ON THE BAS AND FIRE ALARM SYSTEM IF SMOKE IS DETECTED IN THE SUPPLY AIR OR RETURN AIR.

D. HIGH STATIC PRESSURE

- 1) WHEN SUPPLY OR EXHAUST FAN PRESSURE SENSOR DETECTS PRESSURE HIGHER THAN 1 INCH WC (ADJUSTABLE), SHUT DOWN ERV AND ASSOCIATED DOAS AND GENERATE AN ALARM ON THE BAS WORKSTATION.

C. ENERGY RECOVERY VENTILATOR: ERV-4

- 1. OCCUPIED MODE
 - a. THE OUTSIDE AIR DAMPER AND EXHAUST AIR DAMPER SHALL OPEN AND THE ERV-4 FANS SHALL START AT LOW SPEED, RAMP UP TO SPEED SET BY BALANCER, THEN RUN CONTINUOUSLY TO SUPPLY OUTSIDE AIR AND EXHAUST TO THE BASEMENT SPACES SERVED.
 - b. HEATING COIL HC-3 CONTROL VALVE SHALL MODULATE TO MAINTAIN SPACE TEMPERATURE AT SETPOINT.

2. UNOCCUPIED MODE

- a. ERV-4 FANS SHALL BE OFF AND THE OUTSIDE AIR DAMPER AND EXHAUST AIR DAMPER SHALL BE CLOSED. HC-3 CONTROL VALVE SHALL CLOSE.
- b. IF SPACE TEMPERATURE RISES OR FALLS MORE THAN 10 DEG F FROM SETPOINT, ERV-4 SHALL RUN IN OCCUPIED MODE AND HC-3 SHALL MODULATE TO MAINTAIN SPACE TEMPERATURE AT SETPOINT +/- 5 DEG F.

3. ALARMS

- a. FREEZE PROTECTION
 - 1) IF THE DISCHARGE AIR TEMPERATURE IS BELOW 40 DEG F (ADJ) FOR MORE THAN 5 MINUTES, GENERATE ALARM.

- b. HIGH DISCHARGE AIR TEMPERATURE
 - 1) IF THE DISCHARGE AIR TEMPERATURE IS ABOVE 100 DEG F (ADJ) FOR MORE THAN 5 MINUTES, GENERATE ALARM.

D. DEDICATED OUTSIDE AIR SYSTEM (DOAS): DOAS-1, DOAS-2, DOAS-3

1. OCCUPIED MODE

- a. EACH DOAS UNIT SHALL START AND RUN CONTINUOUSLY WHENEVER ITS ASSOCIATED ERV RUNS.
- b. THE DOAS SUPPLY FAN SHALL START AT LOW SPEED THEN RAMP UP TO FAN SPEED REQUIRED TO PROVIDE THE SCHEDULED OUTSIDE AIRFLOW AS DETERMINED DURING BALANCING. THE DOAS FANS SHALL RUN CONTINUOUSLY TO SUPPLY MINIMUM OUTSIDE AIR TO AHU-1, AHU-2, AND AHU-3.
- c. THE DOAS SHALL BE CONTROLLED BY ITS OWN INTEGRAL CONTROLLER SUBJECT TO ITS OWN INTERNAL SAFETIES AND CONTROL SEQUENCES TO MAINTAIN A CONSTANT LEAVING AIR TEMPERATURE (LAT) OF 70 DEG F (ADJ).
- d. DEHUMIDIFICATION: THE DOAS CONTROLLER SHALL SEQUENCE TWO STAGES OF COOLING, MODULATE THE FIRST STAGE OF COOLING, PROVIDE LIQUID SUBCOOLING REHEAT, AND MODULATE HOT GAS REHEAT TO MAINTAIN LEAVING AIR TEMPERATURE OF 70 DEG F (ADJ) AT A DEWPOINT OF 51 DEG F.
- e. HEATING: THE DOAS HEATING COIL CONTROL VALVE SHALL MODULATE TO MAINTAIN LEAVING AIR TEMPERATURE 2 DEG F LOWER THAN THE LAT SETPOINT (ADJUSTABLE). THE HEATING COIL SHALL BE LOCKED OUT WHENEVER THE DX SYSTEM IS RUNNING.
- f. HUMIDIFICATION: ELECTRIC HUMIDIFIER ASSOCIATED WITH EACH DOAS UNIT SHALL START AND MODULATE STEAM OUTPUT TO MAINTAIN SUPPLY AIR FROM DOAS UNIT AT 40% RELATIVE HUMIDITY (RH) (ADJUSTABLE). THE HUMIDIFIER SHALL BE LOCKED OUT WHENEVER THE DX COOLING SYSTEM IS RUNNING OR THE ASSOCIATED DOAS IS OFF.

2. UNOCCUPIED MODE

- a. DOAS SUPPLY FAN, COMPRESSORS, CONDENSER FANS SHALL TURN OFF. THE HEATING COIL CONTROL VALVE SHALL CLOSE AND THE ASSOCIATED HUMIDIFIER SHALL BE OFF.

3. ALARMS

- A. LOW ENTERING AIR TEMPERATURE
 - 1) IF ENTERING AIR TEMP DROPS BELOW 40 DEG F (ADJ) FOR 10 MINUTES (ADJ), GENERATE ALARM AT THE BAS WORKSTATION.
- B. HIGH LEAVING AIR TEMPERATURE
 - 1) IF LEAVING AIR TEMPERATURE IS ABOVE 75 DEG F (ADJ) FOR 10 MINUTES (ADJ), GENERATE ALARM AT THE BAS WORKSTATION.
- C. LOW LEAVING AIR TEMPERATURE
 - 1) IF LEAVING AIR TEMPERATURE IS BELOW 60 DEG F (ADJ) FOR 10 MINUTES (ADJ), GENERATE ALARM AT THE BAS WORKSTATION.
- D. LOW LEAVING AIR HUMIDITY
 - 1) IF LEAVING AIR RELATIVE HUMIDITY IS LESS THAN 30% AT 72 DEG F (ADJUSTABLE) FOR 10 MINUTES (ADJUSTABLE), GENERATE ALARM AT THE BAS WORKSTATION.
- E. HIGH LEAVING AIR HUMIDITY
 - 1) COOLING MODE: IF LEAVING AIR CALCULATED DEWPOINT EXCEEDS 55 DEG F (ADJUSTABLE) FOR 10 MINUTES (ADJUSTABLE), GENERATE ALARM AT THE BAS WORKSTATION.
 - 2) HEATING MODE: IF LEAVING AIR HUMIDITY EXCEEDS 50% RH AT 72 DEG F (ADJUSTABLE) FOR 10

MINUTES (ADJUSTABLE) SHUT OFF HUMIDIFIER AND GENERATE ALARM AT THE BAS WORKSTATION.

F. FILTER MONITORING

- 1) PROVIDE PRE-FILTER AND FINAL FILTER DIFFERENTIAL PRESSURE SENSORS. FILTER DIFFERENTIAL PRESSURES SHALL BE DISPLAYED AT THE BAS WORKSTATION.
- 2) GENERATE AN ALARM AT THE BAS WORKSTATION IF FILTER DP EXCEEDS 1.0 INCH WC (ADJUSTABLE).

G. CONDENSATE OVERFLOW SWITCH

- 1) PROVIDE CONDENSATE OVERFLOW SWITCH OPTION WITH DOAS. RELAY STATUS OF SWITCH TO BAS WORKSTATION.
- 2) WHEN CONDENSATE OVERFLOW SWITCH TRIPS, GENERATE ALARM AT THE BAS WORKSTATION.

2. SUPPLY AIR STATIC PRESSURE RESET CONTROL

- a. SUPPLY FAN MAXIMUM SPEED IS CONTROLLED TO MAINTAIN DUCT STATIC PRESSURE AT THE SETPOINT DETERMINED DURING BALANCING.
- b. POLL THE STATUS OF THE ASSOCIATED VAV BOX DAMPERS. IF ALL VAV DAMPERS ARE LESS THAN 75% OPEN (ADJUSTABLE), FAN STATIC SETPOINT SHALL BE REDUCED 0.25 INCH WC (ADJUSTABLE). AFTER 10 MINUTES (ADJUSTABLE) REPEAT THIS PROCESS UNTIL AT LEAST ONE VAV BOX DAMPER IS 80% OPEN (ADJUSTABLE) OR MORE.

3. VENTILATION CONTROL

- a. THE MIXING BOX MEASURING OUTSIDE AIR DAMPERS (TRAQ) SHALL MODULATE TO MAINTAIN OUTSIDE AIR FLOW FROM DOAS-03 AT THE UNIT SCHEDULED OUTSIDE AIR CFM SETPOINT.
- b. THE GENERAL EXHAUST DAMPER FROM THE RA SHALL BE OPENED.
- 4. SUPPLY AIR TEMPERATURE CONTROL
 - a. DURING OCCUPIED MODE, THE VRF COOLING COIL AND THE ASSOCIATED CONDENSING UNIT SHALL MODULATE TO MAINTAIN DISCHARGE AIR TEMPERATURE AT THE RESET SETPOINT.
- 5. SUPPLY AIR TEMPERATURE RESET
 - a. SUPPLY AIR TEMPERATURE SETPOINT SHALL INITIALLY BE SET TO 55 DEG F (ADJUSTABLE).
 - b. SUPPLY AIR TEMPERATURE SETPOINT SHALL BE RESET FROM 55 DEG F UP TO A MAXIMUM OF 65 DEG F (ADJUSTABLE) AS RETURN AIR TEMPERATURE VARIES FROM 75 DEG F (ADJUSTABLE) TO 70 DEG F (ADJUSTABLE) AS NEEDED TO MAINTAIN SPACE TEMPERATURE IN ALL SERVED VAV ZONES AT SETPOINT WITHOUT REHEAT.

C. UNOCCUPIED MODE

- 1. THE SUPPLY FAN AND THE RETURN FAN SHALL BE OFF, THE MIXING BOX OUTSIDE AIR DAMPER AND THE GENERAL EXHAUST DAMPER FROM THE RA SHALL BE CLOSED.
- 2. IF ANY ASSOCIATED VAV ZONE DROPS BELOW ITS UNOCCUPIED HEATING TEMPERATURE SETPOINT, OR RISES ABOVE ITS UNOCCUPIED COOLING TEMPERATURE SETPOINT, THE SUPPLY AIR FAN SHALL START AND RAMP UP TO 75% SPEED (ADJUSTABLE). THE RETURN AIR FAN SHALL MODULATE TO MAINTAIN RA AIRFLOW AT THE AHU INLET PER THE FOLLOWING EQUATION: RA CFM = SA CFM.
- a. THE OUTSIDE AIR DAMPERS AND THE EXHAUST AIR DAMPERS SHALL REMAIN CLOSED.
 - a. THE ASSOCIATED VAV BOX DAMPERS AND HEATING COILS SHALL MODULATE ACCORDING TO THE VAV BOX CONTROL SEQUENCE TO COOL OR HEAT ALL SERVED SPACES TO THEIR UNOCCUPIED TEMPERATURE SETPOINT.
- b. IF ALL SERVED SPACES ARE NOT AT THE UNOCCUPIED TEMPERATURE SETPOINT AFTER 20 MINUTES (ADJUSTABLE), THE SUPPLY FAN SPEED SHALL BE INCREASED TO MAXIMUM (AS SET DURING BALANCING). THE RETURN FAN SHALL MODULATE TO MAINTAIN RA CFM = SA CFM.
- c. THE OUTSIDE AIR DAMPERS AND EXHAUST AIR DAMPERS SHALL REMAIN CLOSED.
- c. WHEN ALL SPACES ARE WITHIN THEIR UNOCCUPIED TEMPERATURE SETPOINTS, THE SUPPLY AIR FAN AND RETURN AIR FAN SHALL STOP AND NORMAL UNOCCUPIED MODE SHALL RESUME.

3. UNOCCUPIED OVERRIDE

- a. WHEN THE UNOCCUPIED OVERRIDE BUTTON ON ANY OF THE VAV BOX THERMOSTATS IS PRESSED FOR ONE SECOND OR MORE, AHU-1, AHU-2, AHU-3, AND DOAS-3 SHALL START AND RUN IN OCCUPIED MODE FOR 2 HOURS (ADJUSTABLE), THEN SWITCH BACK TO UNOCCUPIED MODE. PRESSING ANY OF THE OVERRIDE BUTTONS WHILE THE SYSTEM IS RUNNING IN OVERRIDE MODE SHALL RESET THE OCCUPIED MODE RUN TIME.

D. ALARMS

- 1. FAN STATUS-COMMAND
 - a. IF THE FAN STATUS DIFFERS FROM THE COMMAND FOR 15 SECONDS, GENERATE ALARM AT THE BAS WORKSTATION.
- 2. DIRTY FILTERS
 - a. IF THE DIFFERENTIAL PRESSURE SENSOR ACROSS THE PRE-FILTERS EXCEEDS 0.75 INCH (ADJUSTABLE) FOR 5 MINUTES WHEN AIRFLOW EXCEEDS 80%, GENERATE ALARM AT THE BAS WORKSTATION.
 - b. IF THE DIFFERENTIAL PRESSURE SENSOR ACROSS THE FINAL FILTERS EXCEEDS 1.0 IN WC (ADJUSTABLE) FOR 5 MINUTES WHEN AIRFLOW EXCEEDS 80%, GENERATE ALARM AT THE BAS WORKSTATION.
- 3. WIRE DUCT SMOKE DETECTORS TO SHUT DOWN THE ASSOCIATED AHU SUPPLY AND RETURN FANS AND DOAS-3 AND GENERATE AN ALARM ON THE BAS AND FIRE ALARM SYSTEM IF SMOKE IS DETECTED IN THE SUPPLY AIR OR RETURN AIR.
- 4. AUTOMATIC FAULT DETECTION AND DIAGNOSTICS (AFDD)
 - a. AFDD CONDITIONS ARE EVALUATED CONTINUOUSLY AND SEPARATELY FOR EACH OPERATING AHU.
 - b. THE FOLLOWING VALUES SHALL BE CONTINUOUSLY CALCULATED BY THE AFDD ROUTINES FOR EACH AHU:
 - 1) FIVE MINUTE ROLLING AVERAGES WITH 1-MINUTE SAMPLING TIME OF THE FOLLOWING POINT VALUES: OPERATOR SHALL HAVE THE ABILITY TO ADJUST THE AVERAGING WINDOW AND SAMPLING PERIOD OF EACH POINT INDEPENDENTLY.
 - a) SUPPLY AIR TEMPERATURE
 - b) MIXED AIR TEMPERATURE



NO.	DATE	REVISION / ISSUE DESCRIPTION
C.	02-17-2022	ADDENDUM NO. 3
B.	02-08-2022	ADDENDUM NO. 2
A.	01-07-2022	ISSUED FOR BID
REV		REVISION ISSUE DESCRIPTION

c) RETURN AIR TEMPERATURE
d) OUTDOOR AIR TEMPERATURE
e) DUCT STATIC PRESSURE
f) COOLING COIL LEAVING AIR TEMPERATURE

1.9 AIR HANDLING UNIT AHU-3
A. AHU-3 IS A SINGLE ZONE VAV AIR HANDLING UNIT WITH A 30% PROPYLENE GLYCOL HEATING COIL AND A VRF COOLING COIL.
B. OCCUPIED MODE
1. THE SUPPLY FAN SHALL RUN CONTINUOUSLY WHENEVER THE UNIT IS IN OCCUPIED MODE.
2. SUPPLY FAN SPEED CONTROL SETTINGS
a. PROVIDE RAMP FUNCTION TO PREVENT CHANGES IN FAN SPEED OF MORE THAN 10% PER MINUTE
b. MAXIMUM FAN SPEED SHALL BE THE SCHEDULED SUPPLY AIRFLOW.
c. MINIMUM FAN SPEED SHALL BE 40% OF MAXIMUM SPEED (ADJUSTABLE).
3. SUPPLY AIR TEMPERATURE AND SUPPLY FAN SPEED CONTROL
a. PROVIDE RAMP FUNCTION TO PREVENT CHANGES IN SUPPLY AIR TEMPERATURE OF MORE THAN 0.5 DEG PER MINUTE.
b. AT MAX COOLING, FAN SPEED SHALL BE AT MAXIMUM AND VRF COOLING COIL SHALL MODULATE TO MAINTAIN DISCHARGE AIR TEMPERATURE OF 55 DEG F (ADJ).
c. UPON A DROP IN SPACE TEMPERATURE, FAN SPEED SHALL RAMP DOWN TOWARD MINIMUM FLOW.
d. UPON A CONTINUED DROP IN SPACE TEMPERATURE AFTER FAN IS AT MINIMUM FLOW, SUPPLY AIR TEMPERATURE SHALL BE RESET FROM A MINIMUM DISCHARGE AIR TEMPERATURE OF 75 DEG F (ADJ) UP TO A MAXIMUM OF 90 DEG F (ADJ).
e. UPON A CONTINUED DROP IN SPACE TEMPERATURE, FAN SHALL CONTINUE AT MINIMUM SPEED AND VRF COOLING COIL SHALL MODULATE OFF.
f. UPON A CONTINUED DROP IN SPACE TEMPERATURE BELOW HEATING SETPOINT, THE HEATING COIL CONTROL VALVE SHALL MODULATE OPEN TO MAINTAIN DISCHARGE AIR TEMPERATURE OF 75 DEG F (ADJ).
g. UPON A CONTINUED DROP IN SPACE TEMPERATURE AFTER FAN IS AT MINIMUM FLOW, SUPPLY AIR TEMPERATURE SHALL BE RESET FROM A MINIMUM DISCHARGE AIR TEMPERATURE OF 75 DEG F (ADJ) UP TO A MAXIMUM OF 90 DEG F (ADJ).
h. UPON A CONTINUED DROP IN SPACE TEMPERATURE AFTER DISCHARGE AIR TEMPERATURE IS AT MAXIMUM OF 90 DEG F (ADJ), THE FAN SPEED SHALL MODULATE TO MAXIMUM AIRFLOW AS NEEDED TO MAINTAIN SPACE TEMPERATURE AT SETPOINT.
4. VENTILATION CONTROL
a. DURING OCCUPIED MODE, THE AIR FLOW MEASURING OUTDOOR AIR DAMPER SHALL MODULATE TO MAINTAIN THE SCHEDULED MINIMUM OUTDOOR AIRFLOW AS MEASURED AT THE AIRFLOW MEASURING MIXED AIR DAMPERS (TRAQ). THE RETURN AIR DAMPER IS MECHANICALLY LINKED TO OPERATE INVERSELY TO THE OUTSIDE AIR DAMPER.
b. THE EXHAUST DAMPER FROM THE RA SHALL BE OPEN.
C. UNOCCUPIED MODE
1. THE SUPPLY FAN SHALL BE OFF, THE MIXING BOX OUTSIDE AIR DAMPER SHALL BE CLOSED AND THE RETURN AIR DAMPER FULLY OPEN, AND THE GENERAL EXHAUST DAMPER FROM THE RA SHALL BE CLOSED.
2. IF SPACE TEMPERATURE DROPS BELOW ITS UNOCCUPIED HEATING TEMPERATURE SETPOINT, OR RISES ABOVE ITS UNOCCUPIED COOLING TEMPERATURE SETPOINT, THE SUPPLY AIR FAN SHALL START AND RAMP UP TO 75% SPEED (ADJUSTABLE). THE OUTSIDE AIR DAMPERS AND EXHAUST DAMPERS SHALL REMAIN CLOSED AND THE RETURN AIR DAMPERS SHALL REMAIN OPEN.
a. COOLING: THE UNIT VRF COOLING COIL SHALL MODULATE TO MAINTAIN SUPPLY AIR TEMPERATURE AT MINIMUM.
b. HEATING: THE UNIT HEATING COIL SHALL MODULATE TO MAINTAIN SUPPLY AIR TEMPERATURE AT MAXIMUM.

IF THE VALVE POSITION IS 0% FOR 15 MINUTES, DISCHARGE AIR TEMP IS 5 DEG F OR MORE ABOVE AHU SUPPLY TEMP AND THE FAN SERVING THE ZONE IS PROVEN ON, GENERATE ALARM.

IF THE SPACE HAS NOT REACHED THE UNOCCUPIED TEMPERATURE SETPOINT AFTER 20 MINUTES (ADJUSTABLE), THE SUPPLY FAN SPEED SHALL BE INCREASED TO MAXIMUM (AS SET DURING BALANCING) UNTIL THE SPACE IS AT THE UNOCCUPIED SETPOINT. THE OUTSIDE AIR DAMPER SHALL REMAIN CLOSED.

WHEN ALL SPACES ARE WITHIN THEIR UNOCCUPIED TEMPERATURE SETPOINTS, THE SUPPLY AIR FAN SHALL STOP.

UNOCCUPIED OVERRIDE
a. WHEN THE UNOCCUPIED OVERRIDE BUTTON ON THE SPACE THERMOSTAT IS PRESSED FOR ONE SECOND OR MORE, AHU-1, AHU-2, AHU-3, AND DOAS-3 SHALL START AND RUN IN OCCUPIED MODE FOR 2 HOURS (ADJUSTABLE), THEN SWITCH BACK TO UNOCCUPIED MODE. PRESSING THE OVERRIDE BUTTON WHILE THE SYSTEM IS RUNNING IN OVERRIDE MODE SHALL RESET THE OCCUPIED MODE RUN TIME.

ALARMS
1. FAN STATUS-COMMAND
a. IF THE FAN STATUS DIFFERS FROM THE COMMAND FOR 15 SECONDS, GENERATE ALARM.
2. DIRTY FILTER
a. IF THE DIFFERENTIAL PRESSURE SENSOR ACROSS THE PRE-FILTERS EXCEEDS 0.75 INCH (ADJUSTABLE) FOR 5 MINUTES WHEN AIRFLOW EXCEEDS 80%, GENERATE ALARM AT THE BAS WORKSTATION.
b. IF THE DIFFERENTIAL PRESSURE SENSOR ACROSS THE FINAL FILTERS EXCEEDS 1.0 IN WC (ADJUSTABLE) FOR 5 MINUTES WHEN AIRFLOW EXCEEDS 80%, GENERATE ALARM AT THE BAS WORKSTATION.
3. WIRE DUCT SMOKE DETECTORS TO SHUT DOWN THE AHU-3 SUPPLY FAN AND DOAS-3 AND GENERATE AN ALARM ON THE BAS AND FIRE ALARM SYSTEM IF SMOKE IS DETECTED IN THE RETURN AIR.
E. AUTOMATIC FAULT DETECTION AND DIAGNOSTICS (AFDD)
1. AFDD CONDITIONS ARE EVALUATED CONTINUOUSLY AND SEPARATELY FOR EACH OPERATING AHU.
2. THE FOLLOWING VALUES SHALL BE CONTINUOUSLY CALCULATED BY THE AFDD ROUTINES FOR EACH AHU:
a. FIVE MINUTE ROLLING AVERAGES WITH 1-MINUTE SAMPLING TIME OF THE FOLLOWING POINT VALUES. OPERATOR SHALL HAVE THE ABILITY TO ADJUST THE AVERAGING WINDOW AND SAMPLE PERIOD OF EACH POINT INDEPENDENTLY.
1) SUPPLY AIR TEMPERATURE
2) MIXED AIR TEMPERATURE
3) RETURN AIR TEMPERATURE
4) OUTDOOR AIR TEMPERATURE
5) DUCT STATIC PRESSURE
6) COOLING COIL ENTERING AIR TEMPERATURE
7) COOLING COIL LEAVING AIR TEMPERATURE
3. THE INTERNAL AFDD VARIABLES SHOWN BELOW SHALL BE DEFINED FOR EACH AHU. ALL PARAMETERS ARE ADJUSTABLE BY THE OPERATOR WITH INITIAL VALUES AS FOLLOWS:
a. TEMP RISE ACROSS SUPPLY FAN = 2 DEG F
b. TEMP ERROR THRESHOLD FOR SUPPLY, RETURN, AND OUTSIDE AIR TEMP SENSOR = 2 DEG F
c. TEMP ERROR THRESHOLD FOR MIXED AIR TEMP SENSOR = 5 DEG F
d. AIRFLOW ERROR THRESHOLD = 30%
e. VFD SPEED ERROR THRESHOLD = 5%
f. DUCT STATIC PRESSURE ERROR THRESHOLD = 0.1"
g. COOLING COIL ENTERING/LEAVING TEMP SENSOR ERROR = 2 DEG F
h. TIME IN MINUTES THAT A FAULT MUST PERSIST BEFORE TRIGGERING AN ALARM = 30 MIN.
4. THE FOLLOWING FAULT CONDITIONS SHALL BE ANALYZED:
a. DUCT STATIC PRESSURE TOO LOW WITH FAN AT FULL SPEED

MIXED AIR TEMP TOO LOW OR TOO HIGH, SHOULD BE BETWEEN RA TEMP AND OA TEMP
SUPPLY AIR TEMP TOO HIGH; SHOULD BE LESS THAN MIXED AIR TEMP
SUPPLY AIR TEMP TOO LOW IN HEATING; SHOULD BE HIGHER THAN MIXED AIR TEMP
TEMPERATURE DROPS ACROSS INACTIVE COOLING COIL
TEMPERATURE RISE ACROSS INACTIVE HEATING COIL
EVALUATION OF FAULT CONDITIONS SHALL BE SUSPENDED WHEN AHU IS NOT RUNNING OR FOR 30 MINUTES AFTER A CHANGE IN OPERATING MODE (I.E. UNOCCUPIED TO OCCUPIED MODE)

WHEN AHU-3 IS ON IN OCCUPIED MODE OR DURING UNOCCUPIED HEATING, HEATING COIL CONTROL VALVE SHALL MODULATE OPEN, SUBJECT TO A MAXIMUM DISCHARGE AIR TEMPERATURE OF 90 DEG F (ADJUSTABLE), TO MAINTAIN SPACE TEMPERATURE AT SETPOINT.
1. HIGH DISCHARGE AIR TEMPERATURE
a. IF THE DISCHARGE AIR TEMPERATURE IS ABOVE 100 DEG F (ADJ) FOR MORE THAN 5 MINUTES, GENERATE ALARM.

ROOFTOP AIR HANDLING UNIT AHU-4
A. AHU-4 IS A SINGLE ZONE VAV AIR HANDLING UNIT WITH A 30% PROPYLENE GLYCOL HEATING COIL AND DX COOLING COIL.
B. OCCUPIED MODE
1. THE SUPPLY FAN SHALL RUN CONTINUOUSLY WHENEVER THE UNIT IS IN OCCUPIED MODE.
2. SUPPLY FAN SPEED CONTROL SETTINGS
a. PROVIDE RAMP FUNCTION TO PREVENT CHANGES IN FAN SPEED OF MORE THAN 10% PER MINUTE
b. MAXIMUM FAN SPEED SHALL BE THE SCHEDULED SUPPLY AIRFLOW.
c. MINIMUM FAN SPEED SHALL BE 40% OF MAXIMUM SPEED (ADJUSTABLE).
3. SUPPLY AIR TEMPERATURE AND SUPPLY FAN SPEED CONTROL
a. UNIT CONTROLLER SHALL MODULATE INTEGRAL DX COOLING, PROPYLENE GLYCOL COIL HEATING CONTROL VALVE, FAN SPEED, AND OUTSIDE AIR DAMPERS IN SEQUENCE TO MAINTAIN SPACE TEMPERATURE AT SETPOINT.
b. SUPPLY AIR TEMPERATURE SHALL BE RESET FROM A MINIMUM DISCHARGE AIR TEMPERATURE OF 55 DEG F (ADJUSTABLE) UP TO A MAXIMUM OF 95 DEG F (ADJUSTABLE).
c. IF RETURN AIR HUMIDITY RISES ABOVE 50% RELATIVE HUMIDITY AT 75 DEG F (ADJUSTABLE), COOLING COIL DISCHARGE TEMPERATURE SHALL BE SET TO 55 DEG F (ADJUSTABLE) AND THE INTEGRAL HOT GAS REHEAT COIL SHALL MODULATE TO MAINTAIN SUPPLY AIR TEMPERATURE AT THE RESET SETPOINT.
4. VENTILATION CONTROL
a. THE OUTDOOR AIR DAMPER SHALL MODULATE TO MINIMUM POSITION DETERMINED DURING BALANCING TO PROVIDE THE SCHEDULED MINIMUM OUTSIDE AIRFLOW. THE RETURN AIR DAMPER IS MECHANICALLY LINKED TO OPERATE INVERSELY TO THE OUTSIDE AIR DAMPER.
b. ECONOMIZER CONTROL: WHEN OUTSIDE AIR ENTHALPY IS LESS THAN RETURN AIR ENTHALPY, THE OUTSIDE AIR DAMPERS SHALL MODULATE OPEN AND THE RETURN AIR DAMPERS SHALL CLOSE IN PROPORTION TO HELP MAINTAIN SPACE TEMPERATURE AT SETPOINT (FREE COOLING). DX COOLING SHALL BE AVAILABLE DURING ECONOMIZER OPERATION IF NEEDED. EXHAUST AIR SHALL BE RELIEVED THROUGH THE UNIT BAROMETRIC RELIEF DAMPERS.
c. DEMAND CONTROLLED (CO2) VENTILATION: THE OUTSIDE AIR DAMPERS SHALL MODULATE OPEN AND THE RETURN AIR DAMPERS SHALL CLOSE IN PROPORTION TO MAINTAIN RA CO2 BELOW 850 PPM (ADJUSTABLE). DX COOLING OR HOT WATER HEATING SHALL BE AVAILABLE IF NEEDED TO MAINTAIN SPACE TEMPERATURE AT SETPOINT WITH ADDITIONAL VENTILATION AIR.

EXHAUST AIR SHALL BE RELIEVED THROUGH THE UNIT BAROMETRIC RELIEF DAMPERS.

UNOCCUPIED MODE
1. THE SUPPLY FAN SHALL BE OFF, THE MIXING BOX OUTSIDE AIR DAMPER SHALL BE CLOSED AND THE RETURN AIR DAMPER FULLY OPEN.
2. WHEN THE SUPPLY FAN IS OFF, THE HOT WATER CONTROL VALVE SHALL MODULATE TO MAINTAIN INTERNAL UNIT TEMPERATURE (CLOSEST TEMPERATURE SENSOR TO HW COIL) AT 60 DEG F (ADJUSTABLE).
3. IF SPACE TEMPERATURE DROPS BELOW ITS UNOCCUPIED HEATING TEMPERATURE SETPOINT, THE SUPPLY AIR FAN SHALL START AND RAMP UP TO 75% SPEED (ADJUSTABLE). THE OUTSIDE AIR DAMPERS SHALL REMAIN CLOSED AND THE RETURN AIR DAMPERS SHALL REMAIN OPEN.
a. THE UNIT HEATING COIL SHALL MODULATE TO MAINTAIN SUPPLY AIR TEMPERATURE AT MAXIMUM.
b. IF THE SPACE HAS NOT REACHED THE UNOCCUPIED TEMPERATURE SETPOINT, THE OUTSIDE AIR DAMPERS (ADJUSTABLE), THE SUPPLY FAN SPEED SHALL BE INCREASED TO MAXIMUM (AS SET DURING BALANCING) UNTIL THE SPACE IS AT THE UNOCCUPIED SETPOINT. THE OUTSIDE AIR DAMPER SHALL REMAIN CLOSED.
c. WHEN THE SPACE ARE WITHIN THEIR UNOCCUPIED TEMPERATURE SETPOINTS, THE SUPPLY AIR FAN SHALL STOP.
4. UNOCCUPIED OVERRIDE
a. WHEN THE UNOCCUPIED OVERRIDE BUTTON ON THE SPACE THERMOSTAT IS PRESSED FOR ONE SECOND OR MORE, AHU-4 SHALL START AND RUN IN OCCUPIED MODE FOR 2 HOURS (ADJUSTABLE), THEN SWITCH BACK TO UNOCCUPIED MODE. PRESSING THE OVERRIDE BUTTON WHILE THE SYSTEM IS RUNNING IN OVERRIDE MODE SHALL RESET THE OCCUPIED MODE RUN TIME.

ALARMS
1. FAN STATUS-COMMAND
a. IF THE FAN STATUS DIFFERS FROM THE COMMAND FOR 15 SECONDS, GENERATE ALARM.
2. DIRTY FILTER
a. IF THE DIFFERENTIAL PRESSURE SENSOR ACROSS THE PRE-FILTERS EXCEEDS 0.75 INCH (ADJUSTABLE) FOR 5 MINUTES WHEN AIRFLOW EXCEEDS 80%, GENERATE ALARM AT THE BAS WORKSTATION.
b. IF THE DIFFERENTIAL PRESSURE SENSOR ACROSS THE FINAL FILTERS EXCEEDS 1.0 IN WC (ADJUSTABLE) FOR 5 MINUTES WHEN AIRFLOW EXCEEDS 80%, GENERATE ALARM AT THE BAS WORKSTATION.
3. WIRE DUCT SMOKE DETECTORS TO SHUT DOWN THE AHU-4 SUPPLY FAN AND FIRE ALARM SYSTEM IF SMOKE IS DETECTED IN THE RETURN AIR.
4. LOW TEMPERATURE DETECTION (FREEZESTAT)
A. AUTOMATIC RESET FREEZESTAT LOCATED IMMEDIATELY DOWNSTREAM OF THE HOT WATER HEATING COIL SHALL SET THE UNIT TO UNOCCUPIED MODE (FANS OFF AND OA DAMPERS CLOSED), OVERRIDE THE HEATING COIL VALVE TO 50% OPEN (ADJUSTABLE), AND GENERATE AN ALARM IF ANY PART OF THE AIRSTREAM DROPS BELOW 20 DEG F (ADJUSTABLE).
B. FREEZESTAT SHALL AUTOMATICALLY RESET AFTER 5 MINUTES (ADJUSTABLE) AND THE UNIT SHALL RESTART AND REVERT TO NORMAL OPERATION.
C. IF THE FREEZESTAT TRIPS MORE THAN 3 TIMES WITHIN 30 MINUTES (ADJUSTABLE), THE UNIT SHALL BE LOCKED OUT IN UNOCCUPIED MODE AND A CRITICAL ALARM SHALL BE DISPLAYED AT THE BAS WORKSTATION.

STAIR CONVECTORS / FIN TUBED RADIATOR
A. HEATING COIL CONTROL VALVE SHALL MODULATE TO MAINTAIN SPACE TEMPERATURE AT SETPOINT.

DEHUMIDIFIER
A. DH-1 SHALL OPERATE CONTINUOUSLY 24/7 SUBJECT TO ITS OWN CONTROLS TO MAINTAIN COLD ROOM

SPACE HUMIDITY AT 30% RH AT 50 DEG F (ADJUSTABLE) (DEWPOINT 21.2 DEG F).
B. THE EXISTING REFRIGERATION UNIT SHALL OPERATE CONTINUOUSLY ON ITS OWN CONTROL TO MAINTAIN COLD ROOM TEMPERATURE AT SETPOINT.

4TH FLOOR CONSERVATION LAB PAINT BOOTH:
SF-1, HC-1, D-8
A. UPON A RELAY SIGNAL INDICATING THE PAINT BOOTH EXHAUST FAN IS ON, THE OUTSIDE AIR DAMPER SHALL OPEN AND THE SUPPLY FAN SHALL TURN ON IN SEQUENCE.
B. WHEN THE SUPPLY FAN IS ON, THE HEATING COIL CONTROL VALVE SHALL MODULATE TO MAINTAIN LEAVING AIR TEMPERATURE OF 68 DEG F (ADJ).
C. UPON A RELAY SIGNAL INDICATING THE PAINT BOOTH EXHAUST FAN IS OFF, THE SUPPLY FAN SHALL TURN OFF AND THE OUTSIDE AIR DAMPER SHALL CLOSE IN SEQUENCE.
D. WHEN THE SUPPLY FAN IS OFF, THE HEATING COIL CONTROL VALVE SHALL CLOSE.
E. WHEN THE SUPPLY FAN IS OFF AND OUTSIDE AIR TEMPERATURE IS LESS THAN 20 DEG F, THE HEATING COIL CONTROL VALVE SHALL MODULATE TO MAINTAIN DUCT TEMPERATURE DOWNSTREAM OF COIL AT 60 DEG F (ADJUSTABLE).
F. ALARMS
1. FREEZE PROTECTION
a. IF THE DISCHARGE AIR TEMPERATURE IS BELOW 30 DEG F (ADJ) FOR MORE THAN 5 MINUTES, GENERATE ALARM, TURN OFF SUPPLY FAN, AND CLOSE OUTSIDE AIR DAMPER.
2. HIGH DISCHARGE AIR TEMPERATURE
a. IF THE DISCHARGE AIR TEMPERATURE IS ABOVE 100 DEG F (ADJ) FOR MORE THAN 5 MINUTES, GENERATE ALARM.
3. FAN STATUS-COMMAND
a. IF THE FAN STATUS DIFFERS FROM THE COMMAND FOR 15 SECONDS, GENERATE ALARM.

1ST FLOOR WORKSHOP PAINT BOOTH: HC-2, D-9
A. UPON A RELAY SIGNAL INDICATING THE PAINT BOOTH EXHAUST FAN IS ON, THE OUTSIDE AIR DAMPER SHALL OPEN.
B. WHEN THE OUTSIDE AIR DAMPER IS OPEN, THE HEATING COIL CONTROL VALVE SHALL MODULATE TO MAINTAIN LEAVING AIR TEMPERATURE OF 68 DEG F (ADJ).
C. UPON A RELAY SIGNAL INDICATING THE PAINT BOOTH EXHAUST FAN IS OFF, THE OUTSIDE AIR DAMPER SHALL CLOSE AND THE HEATING COIL CONTROL VALVE SHALL CLOSE.
D. ALARMS
1. FREEZE PROTECTION
a. IF THE DISCHARGE AIR TEMPERATURE IS BELOW 30 DEG F (ADJ) FOR MORE THAN 5 MINUTES, GENERATE ALARM AND CLOSE OUTSIDE AIR DAMPER.
2. HIGH DISCHARGE AIR TEMPERATURE
a. IF THE DISCHARGE AIR TEMPERATURE IS ABOVE 100 DEG F (ADJ) FOR MORE THAN 5 MINUTES, GENERATE ALARM
3. DAMPER STATUS-COMMAND
a. IF THE FAN STATUS DIFFERS FROM THE COMMAND FOR 15 SECONDS, GENERATE ALARM.

EXISTING PAINT BOOTH EXHAUST FANS
A. EXISTING EXHAUST FANS SERVING 1ST AND 4TH FLOOR PAINT BOOTHS HAVE MANUAL CONTROLS LOCATED IN THEIR RESPECTIVE SPACES.
B. PROVIDE GRAPHIC AND FAN STATUS MONITORING CAPABILITIES AT BAS WORKSTATION.

UNIT HEATERS
A. THE UNIT HEATER CONTROL VALVE SHALL MODULATE TO MAINTAIN SPACE TEMPERATURE SETPOINT.
B. THE UNIT HEATER FAN SHALL RUN ANY TIME THE HEATING COIL CONTROL VALVE IS OPEN.
C. THE FAN SHALL CONTINUE TO RUN FOR 15 MINUTES (ADJ) AFTER THE HEATING COIL HAS CLOSED.

HOT WATER PLANT
A. BOTH INDEPENDENT HOT WATER PLANTS (100% WATER PLANT AND 30% PROPYLENE GLYCOL / WATER PLANT) SHALL USE THE SAME SEQUENCE OF OPERATION BUT HAVE SEPARATE TEMPERATURE RESET SETPOINTS.
B. PLANT ENABLE/DISABLE
1. THE DEFAULT SCHEDULE SHALL BE 24/7
2. ENABLE THE PLANT WHEN OUTSIDE AIR TEMPERATURE IS LESS THAN 50 DEG F (ADJ)
3. DISABLE THE PLANT WHEN OUTSIDE AIR TEMPERATURE IS GREATER THAN OR EQUAL TO 65 DEG F (ADJ)

wood.
Environment & Infrastructure Solutions, Inc.
1 Congress St., Suite 200, Portland, ME 04101
P: (207) 775-9001 F: (207) 772-9000 www.woodeng.com

STATE OF MAINE
BUREAU OF GENERAL SERVICES
111 SEWALL STREET, 4TH FLOOR
AUGUSTA, MAINE 04333-0077
(207) 624-7314

STATE OF MAINE
STEVEN M. MARTELL
MAJESTIC
7148
LICENSED PROFESSIONAL ENGINEER

PHASE 2 - ISSUED FOR BID
JANUARY 7, 2022

STATE OF MAINE CULTURAL BUILDING
ASBESTOS ABATEMENT & MECHANICAL UPGRADES
Maine State Museum, 280 State Street, Augusta, ME 04333-0083

REV	DATE	DESCRIPTION
C	02-17-2022	ADDENDUM NO. 3
B	02-08-2022	ADDENDUM NO. 2
A	01-07-2022	ISSUED FOR BID

PROJECT NO: 3618208720
PROJECT MANAGER: KFM
A/E OF RECORD: SMF
DESIGNED BY: SMM
DRAWN BY: BAL
SHEET TITLE:
SEQUENCE OF OPERATIONS
SHEET ID:
M-708

NOT FOR CONSTRUCTION

NO. 300 (01/2022) © 2022, ME Contract Bidder Mechanical Design/2022/01/2022/01/2022/01/2022

