SPECIFICATIONS

221 STATE STREET
Building Renovations
Augusta, Maine

Prepared For:

State of Maine
Bureau of General Services
Division of Planning, Design & Construction
111 Sewall Street
77 State House Station
Augusta, Maine 04333

BGS Project No. 3143

December 16, 2025

Prepared By:

OAK POINT ASSOCIATES
architecture
engineering
planning

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

00 11 13	NOTICE TO CONTRACTORS FOR EMAIL BID
00 21 13	INSTRUCTIONS TO BIDDERS
00 31 26	EXISTING HAZARDOUS MATERIAL INFORMATION
00 41 13	CONTRACTOR BID FORM
00 43 13	CONTRACTOR BID BOND
00 52 13	CONTRACT AGREEMENT
00 61 13.13	CONTRACTOR PERFORMANCE BOND
00 61 13.16	CONTRCTOR PAYMENT BOND
00 62 76	BGS APPLICATION FOR PAYMENT
00 63 46	CONSTRUCTION CHANGE DIRECTIVE
00 63 63	CHANGE ORDER
00 71 00	DEFINITIONS
00 72 13	GENERAL CONDITIONS
00 73 46	WAGE DETERMINATION SCHEDULE

DIVISION 01 - GENERAL REQUIREMENTS

011000	SUMMARY
012100	ALLOWANCES
012200	UNIT PRICES
012500	SUBSTITUTION PROCEDURES
012600	CONTRACT MODIFICATION PROCEDURES
012900	PAYMENT PROCEDURES
013100	PROJECT MANAGEMENT AND COORDINATION
013200	CONSTRUCTION PROGRESS DOCUMENTATION
013233	PHOTOGRAPHIC DOCUMENTATION
013300	SUBMITTAL PROCEDURES
013516	ALTERATION PROJECT PROCEDURES
014000	QUALITY REQUIREMENTS
014200	REFERENCES
014339	MOCKUPS
014535	SPECIAL INSPECTIONS
015000	TEMPORARY FACILITIES AND CONTROLS
015639	TEMPORARY TREE AND PLANT PROTECTION
016000	PRODUCT REQUIREMENTS
017300	EXECUTION
017419	CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
017700	CLOSEOUT PROCEDURES
017823	OPERATION AND MAINTENANCE DATA
017839	PROJECT RECORD DOCUMENTS
017900	DEMONSTRATION AND TRAINING

DIVISION 02 - EXISTING CONDITIONS

024119	SELECTIVE DEMOLITION
028200	ASBESTOS REMEDIATION
028300	LEAD, CHROMIUM, AND CADMIUM REMEDIATION
028400	PCB REMEDIATION
028416	HANDLING OF LIGHTING BALLASTS AND LAMPS CONTAINING PCBS AND MERCURY

DIVISION 03 - CONCRETE
030130 MAINTENANCE OF CAST-IN-PLACE CONCRETE
031000 CONCRETE FORMING AND ACCESSORIES
032000 CONCRETE REINFORCING
033000 CAST-IN-PLACE CONCRETE

DIVISION 04 - MASONRY
040110 MASONRY CLEANING
040120.63 BRICK MASONRY REPAIR
040120.64 BRICK MASONRY REPOINTING
040140.61 STONE REPAIR
042200 UNIT MASONRY
047200 CAST STONE MASONRY

DIVISION 05 – METALS
051200 STRUCTURAL STEEL FRAMING
053100 STEEL DECKING
055000 METAL FABRICATIONS
055213 PIPE AND TUBE RAILINGS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES
061000 ROUGH CARPENTRY
061600 SHEATHING
064116 PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS
066400 PLASTIC PANELING

DIVISION 07 - THERMAL AND MOISTURE PROTECTION
070150.19 PREPARATION FOR REROOFING
071326 SELF-ADHERING SHEET WATERPROOFING
072100 THERMAL INSULATION
072119 FOAMED-IN-PLACE INSULATION
072600 VAPOR RETARDERS
074293 SOFFIT PANELS
075419 POLYVINYL-CHLORIDE (PVC) ROOFING
076200 SHEET METAL FLASHING AND TRIM
077100 ROOF SPECIALTIES
077200 ROOF ACCESSORIES
078413 PENETRATION FIRESTOPPING
078443 JOINT FIRESTOPPING
079100 PREFORMED JOINT SEALANTS
079200 JOINT SEALANTS
079219 ACOUSTICAL JOINT SEALANTS

DIVISION 08 - OPENINGS
081113 HOLLOW METAL DOORS AND FRAMES
081116.13 INTERIOR ALUMINUM DOORS AND WINDOWS
081416 FLUSH WOOD DOORS
083113 ACCESS DOORS AND FRAMES
083323 OVERHEAD COILING DOORS
084113 ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
084413 GLAZED ALUMINUM CURTAIN WALLS

087100 DOOR HARDWARE
087113 POWER DOOR OPERATORS
088000 GLAZING
088813 FIRE RATED GLAZING
089119 FIXED LOUVERS

DIVISION 09 - FINISHES
092216 NON-STRUCTURAL METAL FRAMING
092900 GYPSUM BOARD
093013 CERAMIC TILING
095113 ACOUSTICAL PANEL CEILINGS
096513 RESILIENT BASE AND ACCESSORIES
096519 RESILIENT TILE FLOORING
096723 RESINOUS FLOORING
096813 TILE CARPETING
099123 INTERIOR PAINTING
099600 HIGH-PERFORMANCE COATINGS
099726 CEMENTITIOUS COATINGS

DIVISION 10 - SPECIALTIES
101423.16 ROOM-IDENTIFICATION PANEL SIGNAGE
102113.13 METAL TOILET COMPARTMENTS
102239 FOLDING PANEL PARTITIONS
102800 TOILET, BATH, AND LAUNDRY ACCESSORIES
104413 FIRE PROTECTION CABINETS
104416 FIRE EXTINGUISHERS
105113 METAL LOCKERS
108213 ROOF SCREENS

DIVISION 11 - EQUIPMENT
111313 LOADING DOCK BUMPERS
113013 RESIDENTIAL APPLIANCES

DIVISION 12 - FURNISHINGS
122413 ROLLER WINDOW SHADES
123661.16 SOLID SURFACING COUNTERTOPS

DIVISION 14 - CONVEYING EQUIPMENT
142410 HYDRAULIC ELEVATOR - MODERNIZATION

DIVISION 21 - FIRE SUPPRESSION
210517 SLEEVES AND SLEEVE SEALS FOR FIRE-SUPPRESSION PIPING
210518 ESCUTCHEONS FOR FIRE-SUPPRESSION PIPING
210523 GENERAL-DUTY VALVES FOR WATER-BASED FIRE-SUPPRESSION PIPING
210529 HANGERS AND SUPPORTS FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT
210553 IDENTIFICATION FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT
211000 WATER-BASED FIRE-SUPPRESSION SYSTEMS
211119 FIRE DEPARTMENT CONNECTIONS

DIVISION 22 - PLUMBING

220513 COMMON MOTOR REQUIREMENTS FOR PLUMBING EQUIPMENT
220517 SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING
220518 ESCUTCHEONS FOR PLUMBING PIPING
220519 METERS AND GAGES FOR PLUMBING PIPING
220523.12 BALL VALVES FOR PLUMBING PIPING
220523.14 CHECK VALVES FOR PLUMBING PIPING
220529 HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT
220553 IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT
220593 TESTING, ADJUSTING, AND BALANCING FOR PLUMBING
220719 PLUMBING PIPING INSULATION
220800 COMMISSIONING OF PLUMBING
221116 DOMESTIC WATER PIPING
221119 DOMESTIC WATER PIPING SPECIALTIES
221123.21 INLINE, DOMESTIC-WATER PUMPS
221316 SANITARY WASTE AND VENT AND RADON PIPING
221319 SANITARY WASTE PIPING SPECIALTIES
221319.13 SANITARY DRAINS
221329 SANITARY SEWERAGE PUMPS
221413 STORM DRAINAGE PIPING
221423 STORM DRAINAGE PIPING SPECIALTIES
223300 ELECTRIC, DOMESTIC-WATER HEATERS
224200 COMMERCIAL PLUMBING FIXTURES
224600 SECURITY PLUMBING FIXTURES
224716 PRESSURE WATER COOLERS

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

230513 COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT
230517 SLEEVES AND SLEEVE SEALS FOR HVAC PIPING
230518 ESCUTCHEONS FOR HVAC PIPING
230519 METERS AND GAUGES FOR HVAC PIPING
230523.12 BALL VALVES FOR HVAC PIPING
230523.13 BUTTERLY VALVES FOR HVAC PIPING
230523.15 GATE VALVES FOR HVAC PIPING
230529 HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT
230548.13 VIBRATION CONTROLS FOR HVAC
230553 IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT
230593 TESTING, ADJUSTING, AND BALANCING FOR HVAC
230713 DUCT INSULATION
230719 HVAC PIPING INSULATION
230800 COMMISSIONING OF HVAC
230923 DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC
230923.11 CONTROL VALVES
230923.12 CONTROL DAMPERS
230923.14 FLOW INSTRUMENTS
230923.16 GAS INSTRUMENTS

230923.19 MOISTURE INSTRUMENTS
230923.23 PRESSURE INSTRUMENTS
230923.27 TEMPERATURE INSTRUMENTS
230923.53 VARIABLE-FREQUENCY MOTOR CONTROLLERS
231123 NATURAL-GAS PIPING
232113 HYDRONIC PIPING
232116 HYDRONIC PIPING SPECIALTIES
232123 HYDRONIC PUMPS
233113 METAL DUCTS
233300 AIR DUCT ACCESSORIES
233346 FLEXIBLE DUCTS
233600 AIR TERMINAL UNITS
233713.13 AIR DIFFUSERS
233713.23 REGISTERS AND GRILLES
235123 GAS VENTS
235216 CONDENSING BOILERS
235700 HEAT EXCHANGERS FOR HVAC
236423.13 AIR-COOLED, REVERSIBLE, SCROLL WATER CHILLERS
237343.16 OUTDOOR, SEMI-CUSTOM AIR-HANDLING UNITS
238126 SPLIT-SYSTEM AIR-CONDITIONERS
238219 FAN COIL UNITS
238229 RADIATORS
238236 FINNED-TUBE RADIATION HEATERS
238239.13 CABINET UNIT HEATERS
238239.16 PROPELLER UNIT HEATERS

DIVISION 26 - ELECTRICAL
260010 SUPPLEMENTAL REQUIREMENTS FOR ELECTRICAL
260513 MEDIUM-VOLTAGE CABLES
260519 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES
260523 CONTROL-VOLTAGE ELECTRICAL POWER CABLES
260526 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
260529 HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
260533.13 CONDUITS FOR ELECTRICAL SYSTEMS
260533.16 BOXES AND COVERS FOR ELECTRICAL SYSTEMS
260533.23 SURFACE RACEWAYS FOR ELECTRICAL SYSTEMS
260536 CABLE TRAYS FOR ELECTRICAL SYSTEMS
260543 UNDERGROUND DUCTS AND RACEWAYS FOR ELECTRICAL SYSTEMS
260544 SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING
260553 IDENTIFICATION FOR ELECTRICAL SYSTEMS
260573 POWER SYSTEM STUDIES
260800 COMMISSIONING OF ELECTRICAL SYSTEMS
260923 LIGHTING CONTROL DEVICES
260943.23 RELAY-BASED LIGHTING CONTROLS
261219 PAD-MOUNTED, LIQUID-FILLED, MEDIUM-VOLTAGE TRANSFORMERS
262213 LOW-VOLTAGE DISTRIBUTION TRANSFORMERS
262413 SWITCHBOARDS

262416 PANELBOARDS
262713 ELECTRICITY METERING
262726 WIRING DEVICES
262813 FUSES
262816 ENCLOSED SWITCHES AND CIRCUIT BREAKERS
263213.13 DIESEL-ENGINE-DRIVEN GENERATOR SETS
263600 TRANSFER SWITCHES
264113 LIGHTNING PROTECTION FOR STRUCTURES
264313 SURGE PROTECTIVE DEVICES FOR LOW-VOLTAGE ELECTRICAL POWER CIRCUITS
265000 LIGHTING
APPENDIX BGS ELECTRICAL REQUIREMENTS 2025

DIVISION 27 - COMMUNICATIONS
271100 COMMUNICATIONS EQUIPMENT ROOM FITTINGS
271323 COMMUNICATIONS OPTICAL FIBER BACKBONE CABLING
271513 COMMUNICATIONS COPPER HORIZONTAL CABLING
275119 SOUND MASKING SYSTEMS

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY
281000 ACCESS CONTROL
281400 ACCESS CONTROL SYSTEM HARDWARE
281500 INTEGRATED ACCESS CONTROL HARDWARE DEVICES
282000 VIDEO SURVEILLANCE
283100 INTRUSION DETECTION
284621.11 ADDRESSABLE FIRE-ALARM SYSTEMS
APPENDIX BGS WIRING APPENDIX SET 2025

DIVISION 31 - EARTHWORK
311000 SITE CLEARING
312000 EARTH MOVING
312319 DEWATERING

DIVISION 32 - EXTERIOR IMPROVEMENTS
321216 ASPHALT PAVING
321373 CONCRETE PAVING JOINT SEALANTS
321723 PAVEMENT MARKINGS
323113 CHAIN LINK FENCES AND GATES
329115 SOIL PREPARATION (PERFORMANCE SPECIFICATIONS)
329200 TURF AND GRASSES

DIVISION 33 - UTILITIES
333115 SITE SANITARY SEWERAGE PIPING
334200 STORMWATER CONVEYANCE

END

00 11 13
Notice to Contractors

221 State Street Building Renovations BGS Project No. 3143

The project includes renovations to the existing 221 State Street building and the connector to the adjacent HETL building. The scope of work includes exterior building envelope, roofing, interiors, structural, mechanical, fire protection, electrical, IT, utilities, and civil/site renovations.

The contract shall designate the Substantial Completion Date on or before *31 December 2027*, and the Contract Final Completion Date on or before *18 February 2028*.

1. Submit bids on a completed Contractor Bid Form (section 00 41 13), provided in the Bid Documents, include bid security when required, and scan each item as an attachment to an email addressed to: BGS.Architect@Maine.gov, so as to be received no later than **1:30 p.m.** on ***Thursday, January 22, 2026***. The email subject line shall be marked "**3143 Bid for *221 State Street Building Renovations***". Bid submissions will be opened at **2:00 p.m.** on the date noted above, accessible as a video conference call. Conference links are available on the BGS website at BGS.Architect@Maine.gov. Any bid received after the noted time will not be considered a valid bid and will remain unopened. Any bid submitted by any other means will not be considered a valid bid. In certain circumstances, the Bureau of General Services may require the Bidder to surrender a valid paper copy of the bid form or the bid security document. The Owner reserves the right to accept or reject any or all bids as may best serve the interest of the Owner.

2. Questions and comments on the *bid opening process* shall be addressed to: Kirsten Haskell, Division of Planning, Design & Construction, Bureau of General Services, 77 State House Station, Augusta, Maine 04333-0077, BGS.Architect@Maine.gov.

3. Questions and comments regarding the *project* design specifications or drawings shall be directed in writing to the Consultant during the bid period prior to the question and comment deadline of 5:00 p.m. on *Friday, January 9, 2026*.

   Oak Point Associates
   Jeff Luy
   jbluy@oakpoint.com

4. ☒ Bid security is required on this project.
   The Bidder shall include a satisfactory Bid Bond (section 00 43 13) or a certified or cashier's check for 5% of the bid amount with the completed bid form submitted to the Owner. The Bid Bond form is available on the BGS website.

   or

   ☐ Bid security is <u>not</u> required on this project.

00 11 13
Notice to Contractors

5. ☒ Performance and Payment Bonds are required on this project.
   If noted above as required, or if any combination of Base Bid and Alternate Bids amounts selected in the award of the contract exceeds $125,000.00, the selected Contractor shall furnish a 100% contract Performance Bond (section 00 61 13.13) and a 100% contract Payment Bond (section 00 61 13.16) in the contract amount to cover the execution of the Work. Bond forms are available on the BGS website.
   or
   ☐ Performance and Payment Bonds are not required on this project.

6. Filed Sub-bids *are not required* on this project.

7. ☐ Pre-qualified General Contractors are utilized on this project.
   insert the company name, city and state for each
   or
   ☒ Pre-qualified General Contractors are not utilized on this project.

8. ☒ An on-site pre-bid conference (☒ *mandatory* or ☐ *optional*) will be conducted for this project. The pre-bid conference is intended for General Contractors. Subcontractors and suppliers are welcome to attend. Contractors who arrive late or leave early for a mandatory meeting may be prohibited from participating in this meeting and bidding.
   10:00 a.m., Tuesday, January 6, 2026
   State Street Entrance Lobby

   or
   ☐ An on-site pre-bid conference will not be conducted for this project.

9. Bid Documents - full sets only - will be available on or about *Tuesday, Decenber 16, 2025* and may be obtained from:
   The BGS Website
   https://www.maine.gov/dafs/bgs/business-opportunities

00 21 13
Instructions to Bidders

1. Bidder Requirements

1.1 A bidder is a Contractor which is evidently qualified, or has been specifically pre-qualified by the Bureau of General Services, to bid on the proposed project described in the Bid Documents.

1.2 Contractors and Subcontractors bidding on projects that utilize Filed Sub-bids shall follow the requirements outlined in these Bid Documents for such projects. See Section 00 22 13 for additional information.

1.3 Contractors and Subcontractors are not eligible to bid on the project when their access to project design documents prior to the bid period distribution of documents creates an unfair bidding advantage. Prohibited access includes consultation with the Owner or with design professionals engaged by the Owner regarding cost estimating, constructability review, or project scheduling. This prohibition to bid applies to open, competitive bidding or pre-qualified contractor bidding or Filed Sub-bidding. The Bureau may require additional information to determine if the activities of a Contractor constitute an unfair bidding advantage.

1.4 Each bidder is responsible for becoming thoroughly familiar with the Bid Documents prior to submitting a bid. The failure of a bidder to review evident site conditions, to attend available pre-bid conferences, or to receive, examine, or act on addenda to the Bid Documents shall not relieve that bidder from any obligation with respect to their bid or the execution of the work as a Contractor.

1.5 Prior to the award of the contract, General Contractor bidders or Filed Sub-bidders may be required to provide documented evidence to the Owner or the Bureau showing compliance with the provisions of this section, their business experience, financial capability, or performance on previous projects.

1.6 The selected General Contractor bidder will be required to provide proof of insurance before a contract can be executed.

1.7 Contracts developed from this bid shall not be assigned, sublet or transferred without the written consent of the Owner.

1.8 By submitting a bid the Contractor attests that it has not been declared ineligible to bid on State of Maine projects. The Director of the Bureau of General Services may disallow award of this contract to any Contractor if there is evidence that the Contractor or any of its Subcontractors, through their own fault, have been terminated, suspended for cause, debarred from bidding, agreed to refrain from bidding as part of a settlement, have defaulted on a contract, or had a contract completed by another party.

1.9 The Contractor attests that it is not presently indicted for or otherwise criminally or civilly charged by a Federal, State or local government entity with commission of any of the following offenses and has not within a three-year period preceding this bid been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction, or contract under a public transaction, violation of Federal or State anti-trust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property.

1.10 The Contractor shall not make any award or permit any award (subgrant or contract) at any tier to any party which is debarred or suspended or is otherwise excluded from or ineligible for participation in Federal assistance programs or State of Maine projects.

2. Authority of Owner

2.1 The Owner reserves the right to accept or reject any or all bids as may best serve the interest of the Owner.

2.2 Subject to the Owner's stated right to accept or reject any or all bids, the Contractor shall be selected on the basis of the lowest dollar value of an acceptable Base Bid, or any combination of Base Bid plus Alternate Bids, as well as other limited cost modifications the Owner determines may best serve the interests of the Owner. An acceptable bid is a duly submitted bid from a responsive and responsible bidder.

2.3 The Owner reserves the right to require Bid Bonds or Performance and Payment Bonds for any project of any contract value.

3. Submitting Bids and Bid Requirements

3.1 Each bid shall be submitted on the forms provided in the Bid Documents.

3.2 Each bid shall be valid for a period of thirty calendar days following the Project bid closing date and time. The bid expiration date may be extended in unusual circumstances by mutual consent of the Bidder and the Owner. The bid amount shall not be modified due to the bid expiration date extension.

3.3 Any provision contained in a bid which shows cost escalation, or any modification of schedule or other requirements shall not be accepted. Such a provision causes the bid to be invalid, or, at the discretion of the Owner and BGS, that element of the bid submission may be disregarded for the purpose of awarding the contract without that provision.

3.4 Bidders shall include a Bid Bond or other approved bid security with the bid form submitted to the Owner when the bid form indicates such bid security is required. The bond value shall be 5% of the bid amount. The form of bond is shown in section 00 43 13.

3.5 Bidders recognize that inclusion of contract bonds and the cost of those bonds is dependent on the awarded contract dollar value. Therefore, a Base Bid, or any combination of Base Bid plus Alternate Bids, as well as other limited cost modifications, resulting in a contract award shall include the cost of Performance and Payment Bonds in the submitted bid amount when the construction contract value is over $125,000.00. Similarly, the cost of Performance and Payment Bonds is excluded in the submitted bid amount when the construction contract value is $125,000.00 or less unless bonds are specifically required by the Bid Documents. When required for the project, the selected Contractor shall provide these bonds before a contract can be executed, pursuant to 14 M.R.S.A., Section 871, Public Works Contractors' Surety Bond Law of 1971, subsection 3. The form of bonds is shown in section 00 61 13.13 and 00 61 13.16.

3.6 Bidders may modify bids in writing, by the same means as the original bid submission, prior to the bid closing time. Such written amendments shall not disclose the amount of the initial bid. If so disclosed, the entire bid is considered invalid.

3.7 Bidders implicitly acknowledge all Addenda issued when they submit the bid form. By usual practice the Consultant shall not issue Addenda less than 72 hours prior to the bid closing time, to allow ample time for bidders to incorporate the information. However, some information, such as extending the bid due date and time, may be issued with shorter notice. Addenda shall be issued to all companies who are registered holders of Bid Documents.

3.8 A bid may be withdrawn without penalty if a written request by the bidder is presented to the Owner prior to the bid closing time. Such written withdrawal requests are subject to verification as required by the Bureau.

A bid may be withdrawn without penalty after the bid closing time if, in the determination of the Bureau, evidence provided by the Contractor shows an apparent unintended error such as a miscalculation, or an erroneous number on estimating documents, was the cause of an inaccurate bid. The Bureau may allow withdrawal in consideration of the bid bond or, without utilizing a bid bond, if the Bureau considers documented evidence provided by the Contractor shows factual errors had been made on the bid form.

3.9 In the event State of Maine Offices unexpectedly close on the published date of a public bid opening in the location of that bid opening, prior to the time of the scheduled deadline, the new deadline for the public bid opening will be the following business day at the originally scheduled hour of the day, at the original location. Official closings are posted on the State of Maine government website.

3.10 The Owner may require, in a Notice of Intent to Award letter to the apparent low bidder, a Schedule of Values, Project Schedule, and List of Subcontractors and Suppliers as both a demonstration of capability of the Bidder and as a condition of award.

3.11 Projects which require a State of Maine wage determination will include that schedule as part of the Bid Documents. See section 00 73 46, if such rates are required.

3.12 Projects which require compliance with the Davis-Bacon Act are subject to the regulations contained the Code for Federal Regulations and the federal wage determination which is made a part of the Bid Documents. See section 00 73 46, if such rates are required.

3.13 The Owner is exempt from the payment of Maine State sales and use taxes as provided in 36 M.R.S. §1760 (1). The Contractor and Subcontractors shall not include taxes on exempt items in the construction contract.

DOCUMENT 003126 - EXISTING HAZARDOUS MATERIAL INFORMATION

PART 1 - GENERAL

1.1 EXISTING HAZARDOUS MATERIAL INFORMATION

A. This Document with its referenced attachments is part of the Procurement and Contracting Requirements for the Project. They provide Owner's information for Bidders' convenience and are intended to supplement rather than serve in lieu of Bidders' own investigations. They are made available for Bidders' convenience and information. This Document and its attachments are not part of the Contract Documents.

B. Existing asbestos and PCB reports for the Project listed below are available for viewing at the office of the Owner:

1. Asbestos Identification Survey DHHS Building, Augusta, Maine, URS Corporation, May 16, 2002.
2. Limited Asbestos Identification Survey-Former DHHS Offices-221 State Street-Augusta, Maine; CES Inc.; December 16, 2019.
3. Polychlorinated Biphenyl Caulk/Glazing Screening-Former DHHS Offices-221 State Street-Augusta, Maine; CES Inc., January 2, 2020
4. Limited Asbestos Materials Inspection-Former DHS and Current HETL Buildings-Augusta, Maine; SME Engineers, November 11, 2022.
5. PCB Assessment in Exterior Building Materials and Soil-Health and Environmental Testing Laboratory and Connector-221 State Street-Augusta, Maine; SME Engineers, January 2024.

C. The contractor must assume all painted surfaces contain lead paint and follow Maine EPA guidelines for removal and demolition.

D. Related Requirements:

1. Division 02 Sections for abatement of hazardous materials.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF DOCUMENT 003126

00 41 13
Contractor Bid Form

221State Street Building Renovations BGS project number

Bid Form submitted by: *email only to email address below*

Bid Administrator:
Kirsten Haskell BGS.Architect@Maine.gov
Bureau of General Services
111 Sewall Street, Cross State Office Building, 4th floor
77 State House Station
Augusta, Maine 04333-0077

Bidder:

Signature: _____

Printed name and title: _____

Company name: _____

Mailing address: _____

City, state, zip code: _____

Phone number: _____

Email address: _____

State of incorporation, if a corporation: _____

List of all partners, if a partnership: _____

The Bidder agrees, if the Owner offers to award the contract, to provide any and all bonds and certificates of insurance, as well as Schedule of Values, Project Schedule, and List of Subcontractors and Suppliers if required by the Owner, and to sign the designated Construction Contract within twelve calendar days after the date of notification of such acceptance, except if the twelfth day falls on a State of Maine government holiday or other closure day, or a Saturday, or a Sunday, in which case the aforementioned documents must be received before 12:00 noon on the first available business day following the holiday, other closure day, Saturday, or Sunday.

As a guarantee thereof, the Bidder submits, together with this bid, a bid bond or other acceptable instrument as and if required by the Bid Documents.

00 41 13
Contractor Bid Form

1. The Bidder, having carefully examined the *221 State Street Building Renovations* Project Manual dated *Tuesday, December 16, 2025*, prepared by *Oak Point Associates*, as well as Specifications, Drawings, and any Addenda, the form of contract, and the premises and conditions relating to the work, proposes to furnish all labor, equipment and materials necessary for and reasonably incidental to the construction and completion of this project for the **Base Bid** amount of:

$ _____ .00

2. Allowances *are included* on this project.
Bid amount above includes the following Allowances

1	*Brick Repointing*	$ *65,000*.00
2	*Brick Repair*	$ *35,000*.00
3	*Concrete Foundation Wall Spall Repair*	$ *45,000*.00
4	*Additional Discovered ACM Pipe Insulation*	$ *85,000*.00
5	*Additional Discovered Mechanical and Electrical Piping and Conduit Removals*	*$125,000*.00
6.	*Hydraulic Elevator Plunger Assembly Hole*	*$ 50,000.00*
7.	*Hydraulic Elevator Plunger Assembly, Casing, and Casing Liner*	*$ 90,000.00*

3. Unit Prices *are included* on this project.
Any dollar amount line below that is left blank by the Bidder shall be read as a bid of **$0.00**. *Note:* ***ADD and DEDUCT unit prices cannot differ by more than 20%.***

		UNIT	ADD	DEDUCT
1	*Unit Price No. 1: Brick Repointing*	SF	$_____	$_____
2	*Unit Price No. 2: Brick Repair*	SF	$_____	$_____
3	*Unit Price No. 3: Concrete Foundation Wall Spall Repair*	SF	$_____	$_____
4	*Unit Price No. 4: Additional Discovered ACM Pipe Insulation*	LF	$_____	$_____

4. Bid security *is required* on this project.
If noted above as required, or if the Base Bid amount exceeds $125,000.00, the Bidder shall include with this bid form a satisfactory Bid Bond (section 00 43 13) or a certified or cashier's check for 5% of the bid amount with this completed bid form submitted to the Owner.

5. Filed Sub-bids *are not required* on this project.
If noted above as required, the Bidder shall include with this bid form a list of each Filed Sub-bidder selected by the Bidder on the form provided (section 00 41 13F).

00 43 13
Contractor Bid Bond

Bond No.: **insert bond number**

We, the undersigned, ***insert company name of Contractor***, ***select type of entity*** of ***insert name of municipality*** in the State of ***insert name of state*** as principal, and ***insert name of surety*** as Surety, are hereby held and firmly bound unto ***select title of obligee*** in the penal sum of ***five percent of the bid amount***, for the payment of which, well and truly to be made, we hereby jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns, signed this ***insert date, i.e.: 8th*** day of ***select month***, ***select year***, which is the same date as that of the first specified bid due date, or subsequent bid due date revised by addendum.

The condition of the above obligation is such that whereas the principal has submitted to the Owner, or State of Maine, to a certain bid, attached hereto and hereby made a part hereof, to enter into a contract in writing, for the construction of ***insert name of project as designated in the contract documents***

Now therefore:

If said bid shall be rejected, or, in the alternate,

If said bid shall be accepted and the principal shall execute and deliver a contract in the form of contract attached hereto, properly completed in accordance with said bid, and shall furnish a bond for the faithful performance of said contract, and for the payment of all persons performing labor or furnishing material in connection therewith, and shall in all other respects perform the agreement created by the acceptance of said bid, then this obligation shall be void.

Otherwise, the same shall remain in force and effect- it being expressly understood and agreed that the liability of the Surety for any and all claims hereunder shall, in no event, exceed the penal amount of this obligation as herein stated.

The Surety, for value received hereby stipulates and agrees that the obligation of said Surety and its bonds shall be in no way impaired or affected by any extension of the time within which the Obligee may accept such bid and said Surety does hereby waive notice of any such extension.

SAMPLE

[Fillable bond forms may be downloaded from the Bureau of General Services website.]

00 43 13
Contractor Bid Bond

In witness whereof, the principal and the Surety have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereto affixed and these presents to be signed by their proper officers, the day and year first set above.

Signed and sealed this ***insert date, i.e.: 8th*** day of ***select month***, ***select year***, which is the same date as that of the first specified bid due date, or subsequent bid due date revised by addendum.

Contractor

(Signature)

insert name and title

insert company name

insert address
insert city state zip code

Surety

(Signature)

insert name and title

insert company name

insert address
insert city state zip code

If Contractor is a partnership, all partners shall execute the bond. A power of attorney document indicating that it still is in full force and effect shall be provided by the person executing this bond.

SAMPLE

[Fillable bond forms may be downloaded from the Bureau of General Services website.]

AdvantageME CT# _____

State of Maine
CONSTRUCTION CONTRACT

Large Construction Project

This form is used when the Contract value is $50,000 or greater.
The Project Manual, Specifications and Drawings, and any Addenda are considered part of this Contract.

Agreement entered into by and between the ***contracting entity name*** hereinafter called the ***Owner*** and ***Contractor company name*** hereinafter called the ***Contractor***.

BGS Project No.: ***number assigned by BGS*** Other Project No.: _____

For the following Project: ***title of project as shown on bid documents*** at ***facility or campus name***, ***municipality***, Maine.

The Specifications and the Drawings have been prepared by ***Consultant firm name***, acting as Professional-of-Record and named in the documents as the Consultant Architect or Engineer.

The *Owner* and *Contractor* agree as follows:

ARTICLE 1 COMPENSATION AND PAYMENTS

1.1 The Owner shall pay the Contractor to furnish all labor, equipment, materials and incidentals necessary for the construction of the Work described in the Specifications and shown on the Drawings the Contract Amount as shown below.

Base Bid	*$0.00*
Alternate Bid number and name or "no Alternates"	*$0.00*
Alternate Bid number and name or "no Alternates"	*$0.00*
Alternate Bid number and name or "no Alternates"	*$0.00*
Alternate Bid number and name or "no Alternates"	*$0.00*
Alternate Bid number and name or "no Alternates"	*$0.00*
Total Contract Amount	***$0.00***

1.2 The Contractor's requisition shall contain sufficient detail and supporting information for the Owner to evaluate and support the payment requested.

1.2.1 Payments are due and payable twenty-five working days from the date of receipt of a Contractor requisition which is approved by the Owner.

1.2.2 Provisions for late payments are governed by 5 M.R.S. Chapter 144, *Payment of Invoices Received from Business Concerns*, and interest shall be calculated at 1% per month.

ARTICLE 2 COMMENCEMENT AND COMPLETION DATES

2.1 The Work of this Contract shall commence no sooner than the date this document is executed by the approval authority, or a subsequent date designated in the contract documents.

2.2 The Substantial Completion Date shall be _____.

SAMPLE

2.3 The Work of this Contract shall be completed on or before the Contract Final Completion Date of _____.

2.4 The Contract Expiration Date shall be _____. (This date is the Owner's deadline for internal management of contract accounts. The Contract Expiration Date does not directly relate to any contract obligation of the Contractor.)

ARTICLE 3 INELIGIBLE BIDDER

3.1 By signing this contract the Contractor attests that it has not been declared ineligible to bid on State of Maine projects. The Bureau of General Services may disallow award of this contract to any Contractor if there is evidence that the Contractor or any of its Subcontractors, through their own fault, have been terminated, suspended for cause, debarred from bidding, agreed to refrain from bidding as part of a settlement, have defaulted on a contract, or had a contract completed by another party.

3.2 By signing this contract the Contractor attests that it is not presently indicted for or otherwise criminally or civilly charged by a Federal, State or local government entity with commission of any of the following offenses and has not within a three-year period preceding this bid been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction, or contract under a public transaction, violation of Federal or State anti-trust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property.

3.3 The Contractor shall not make any award or permit any award (subgrant or contract) at any tier to any party which is debarred or suspended or is otherwise excluded from or ineligible for participation in Federal assistance programs or State of Maine projects.

ARTICLE 4 CONTRACTOR'S RESPONSIBILITIES

4.1 On this project, the Contractor ***shall*** furnish the Owner the appropriate contract bonds in the amount of 100% of the Contract Sum. Contract bonds are mandated if the Contract Sum exceeds $125,000, or if bonds are specifically required by the Contract Documents.

4.2 The Contractor shall comply with all laws, codes and regulations applicable to the Work.

4.3 The Contractor shall acquire all permits and third-party approvals applicable to the Work not specifically identified as provided by the Owner. Costs for Contractor-provided permits and third-party approvals shall be included in the Contract Sum identified in Section 1.1 above.

4.4 The Contractor shall remain an independent agent for the duration of this Contract, shall not become an employee of the State of Maine, and shall assure that no State employee will be compensated by, or otherwise benefit from, this Contract.

4.5 The Contractor shall be responsible for any design cost, construction cost, or other cost incurred on the Project to the extent caused by the negligent acts, errors or omissions of the Contractor or their Subcontractors in the performance of Work under this Contract.

SAMPLE

ARTICLE 5 OWNER'S RESPONSIBILITIES

5.1 The Owner shall provide full information about the objectives, schedule, constraints and existing conditions of the project. The Owner has established a budget with reasonable contingencies that meets the project requirements.

5.2 By signing this contract, the Owner attests that all State of Maine procurement requirements for this contract have been met, including the solicitation of competitive bids.

ARTICLE 6 INSTRUMENTS OF SERVICE

6.1 The Contractor's use of the drawings, specifications and other documents known as the Consultant's Instruments of Service is limited to the execution of the Contractor's scope of work of this project unless the Contractor receives the written consent of the Owner and Consultant for use elsewhere.

ARTICLE 7 MISCELLANEOUS PROVISIONS

7.1 This Contract shall be governed by the laws of the State of Maine.

7.2 The Owner and Contractor, respectively, bind themselves, their partners, successors, assigns and legal representatives to this Contract. Neither party to this Contract shall assign the Contract as a whole without written consent of the other party, which consent the Owner may withhold without cause.

7.3 Notwithstanding any other provision of this Agreement, if the Owner does not receive sufficient funds to fund this Agreement or funds are de-appropriated, or if the Owner does not receive legal authority from the Maine State Legislature or Maine Courts to expend funds intended for this Agreement, then the Owner is not obligated to make payment under this Agreement; provided, however, the Owner shall be obligated to pay for services satisfactorily performed prior to any such non-appropriation in accordance with the termination provisions of this Agreement. The Owner shall timely notify the Contractor of any non-appropriation and the effective date of the non-appropriation.

ARTICLE 8 CONTRACT DOCUMENTS

8.1 The Project Manual, Specifications and Drawings, and any Addenda, together with this agreement, form the contract. Each element is as fully a part of the Contract as if hereto attached or herein repeated.

8.2 Specifications: ***indicate date of issuance of project manual***

8.3 Drawings: ***note here or attach each sheet number and title***

8.4 Addenda: ***note each addenda number and date, or "none"***

SAMPLE

BGS Project No.: _____

The Contract is effective as of the date executed by the approval authority.

OWNER	**CONTRACTOR**
Signature *Date* *name and title* *name of contracting entity* *address* *telephone* *email address*	*Signature* *Date* *name and title* *name of contractor company* *address* *telephone* *email address* *Vendor Number*

Indicate the names of the review and approval individuals appropriate to the approval authority.

select proper approval authority	
Reviewed by:	**Approved by:**
Signature *Date* *insert name*	*Signature* *Date* *John Kenney, P.E.*
Project Manager/ Contract Administrator	*Director, Planning Design and Construction Division (PDCD)*

SAMPLE

00 61 13.13
Contractor Performance Bond

Bond No.: **insert bond number**

We, the undersigned, ***insert company name of Contractor***, ***select type of entity*** of ***insert name of municipality*** in the State of ***insert name of state*** as principal, and ***insert name of surety*** as Surety, are hereby held and firmly bound unto ***select title of obligee*** in the penal sum of the Contract Price $ ***insert the Contract Price in numbers*** for the payment of which, well and truly to be made, we hereby jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns.

The condition of the above obligation is such that if the principal shall promptly and faithfully perform the contract entered into this ***insert date, i.e.: 8th*** day of ***select month***, ***select year***, which is the same date as that of the notice of intent to award letter, or in the absence of such a letter, not later than the date the Owner signs the construction contract, for the construction of ***insert name of project as designated in the contract documents***, then this obligation shall be null and void.

Otherwise, the same shall remain in force and effect- it being expressly understood and agreed that the liability of the Surety for any and all claims hereunder shall, in no event, exceed the penal amount of this obligation as herein stated.

The Surety, for value received hereby stipulates and agrees that the obligation of said Surety and its bonds shall be in no way impaired or affected by any extension of the time which the Obligee may accept during the performance of the contract and said Surety does hereby waive notice of any such extension.

SAMPLE

[Fillable bond forms may be downloaded from the Bureau of General Services website.]

00 61 13.13
Contractor Performance Bond

In witness whereof, the principal and the Surety have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereto affixed and these presents to be signed by their proper officers, the day and year first set above.

Signed and sealed this ***insert date, i.e.: 8th*** day of ***select month***, ***select year***, which is the same date as that of the notice of intent to award letter, or in the absence of such a letter, not later than the date the Owner signs the construction contract.

Contractor

_____

(Signature)

insert name and title

insert company name

insert address
insert city state zip code

Surety

_____

(Signature)

insert name and title

insert company name

insert address
insert city state zip code

If Contractor is a partnership, all partners shall execute the bond. A power of attorney document indicating that it still is in full force and effect shall be provided by the person executing this bond.

SAMPLE

[Fillable bond forms may be downloaded from the Bureau of General Services website.]

00 61 13.16
Contractor Payment Bond

Bond No.: **insert bond number**

We, the undersigned, ***insert company name of Contractor***, ***select type of entity*** of ***insert name of municipality*** in the State of ***insert name of state*** as principal, and ***insert name of surety*** as Surety, are hereby held and firmly bound unto ***select title of obligee*** in the penal sum of the Contract Price $ ***insert the Contract Price in numbers*** for the use and benefit of claimants, defined as an entity having a contract with the principal or with a subcontractor of the principal for labor, materials, or both labor and materials, used or reasonably required for use in the performance of the contract, for the payment of which, well and truly to be made, we hereby jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns.

The condition of the above obligation is such that if the principal shall promptly satisfy all claims and demands incurred for all labor and materials, used or required by the principal in connection with the work described in the contract entered into this ***insert date, i.e.: 8th*** day of ***select month***, ***select year***, which is the same date as that of the notice of intent to award letter, or in the absence of such a letter, not later than the date the Owner signs the construction contract, for the construction of ***insert name of project as designated in the contract documents***, and shall fully reimburse the obligee for all outlay and expense with said obligee may incur in making good any default of said principal, then this obligation shall be null and void.

Otherwise, the same shall remain in force and effect- it being expressly understood and agreed that the liability of the Surety for any and all claims hereunder shall, in no event, exceed the penal amount of this obligation as herein stated.

The Surety, for value received hereby stipulates and agrees that the obligation of said Surety and its bonds shall be in no way impaired or affected by any extension of the time which the Obligee may accept during the performance of the contract and said Surety does hereby waive notice of any such extension.

SAMPLE

[Fillable bond forms may be downloaded from the Bureau of General Services website.]

00 61 13.16
Contractor Payment Bond

In witness whereof, the principal and the Surety have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereto affixed and these presents to be signed by their proper officers, the day and year first set above.

Signed and sealed this ***insert date, i.e.: 8th*** day of ***select month***, ***select year***, which is the same date as that of the notice of intent to award letter, or in the absence of such a letter, not later than the date the Owner signs the construction contract.

Contractor

_____

(Signature)

insert name and title

insert company name

insert address
insert city state zip code

Surety

_____

(Signature)

insert name and title

insert company name

insert address
insert city state zip code

If Contractor is a partnership, all partners shall execute the bond. A power of attorney document indicating that it still is in full force and effect shall be provided by the person executing this bond.

SAMPLE

[Fillable bond forms may be downloaded from the Bureau of General Services website.]

Form revision date: 25 Sept 2025

AdvantageME CT#

State of Maine
CONSTRUCTION CONTRACT
Application for Payment

Enter Project name
Enter location / school / campus

Enter Contractor Company name
address
city state zip code

Application Number: 1
Period Start Date: 19-May-2025
Period End Date: 30-Jun-2025
BGS Project No.: BGS #
Other Project No.: Other # or n/a

1	Original Contract Amount			$0
2	Net of Change Orders to Date	(from table below)		$0
3	Contract Sum to Date	(line 1 plus or minus line 2)		$0
4	Total Completed and Stored to Date	(column G on Continuation Sheet)		$0
5a	5% Retainage of Completed Work	(columns D + E x 5%	$0	
5b	5% Retainage of Stored Materials	(column F x 5%)	$0	
5c	Total Retainage	(column I)		$0
6	Total Earned Less Retainage	(line 4 minus line 5c)		$0
7	Less Previous Approved Applications for Payment	(line 6 from previous Application)		$0
8	Current Payment Due	(line 6 minus line 7)		**$0**
9	Balance to Finish, Including Retainage	(line 3 minus line 6)	$0	

Change Order Summary	Additions	Deductions	
Total Changes Approved in Previous Months	$0	$0	
Total Changes Approved this Month	$0	$0	
Subtotals	$0	$0	
Net of Change Orders to Date			$0

The undersigned Contractor certifies that to the best of the Contractor's knowledge, information, and belief the Work covered by this Application for Payment has been completed in accordance with the Contract Documents, that all amounts have been paid by the Contractor for Work for which the previous Certificates for Payment were issued and payments received from the Owner, and that current payment shown herein is now due.

Contractor
Type company name here
Type person's name, title here

---
signature date

In accordance with the Contract Documents, based on on-site observations and the data comprising this Application, the Consultant certifies to the Owner that to the best of the Consultant's knowledge, information, and belief the Work has progressed as indicated, the quality of the Work is in accordance with the Contract Documents, and the Contractor is entitled to payment of the Amount Certified.

Amount Certified_____

Consultant (Architect or Engineer)
Type firm name here
Type person's name, title here

---
signature date

Owner
Type contracting entity name here
Type person's name, title here

---
signature date

Owner's Rep / other - clear this text if not used
Type entity name here
Type person's name, title here

---
signature date

Bureau of General Services / Other - clear this text if not used
Type entity name here
Type person's name, title here

---
signature date

Bureau of General Services
Type entity name here
Type person's name, title here

---
signature date

Form revision date: 25 Sept 2025

State of Maine
CONSTRUCTION CONTRACT
Application for Payment - Base Contract Work

Application Number: 1
Period Start Date: 19-May-2025
Period End Date: 30-Jun-2025
BGS Project No.: BGS #
Other Project No.: Other # or n/a

Enter Project name

Enter Contractor Company name

A	B	C	D	E	F	G		H	I
Item No.	Description of Work	Scheduled Value	Work Completed From Previous Application (Previous D + E)	Work Completed From This Period	Total Stored Materials (Not in D or E)	Total Completed and Stored to Date (D + E + F)	Percent Complete (G ÷ C)	Balance to Finish (C - G)	Retainage 5%
1	Enter Description of Work Item	$0	$0	$0	$0	$0	0.0%	$0	$0

Form revision date: 25 Sept 2025

State of Maine
CONSTRUCTION CONTRACT
Application for Payment - Change Orders and Totals

Application Number: 1
Period Start Date: 19-May-2025
Period End Date: 30-Jun-2025
BGS Project No.: BGS #
Other Project No.: Other # or n/a

Enter Project name

Enter Contractor Company name

A	B	C	D	E	F	G		H	I
Item No.	Description of Work	Scheduled Value	Work Completed From Previous Application (Previous D + E)	Work Completed From This Period	Total Stored Materials (Not in D or E)	Total Completed and Stored to Date (D + E + F)	Percent Complete (G ÷ C)	Balance to Finish (C - G)	Retainage 5%
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
		$0	$0	$0	$0	$0	0.0%	$0	$0
	Total Change Order Work	$0	$0	$0	$0	$0	0.0%	$0	$0
	Total Base Contract Work	$0	$0	$0	$0	$0	0.0%	$0	$0
	Grand Total	$0	$0	$0	$0	$0	0.0%	$0	$0

revised 05 April 2021

State of Maine
CONSTRUCTION CONTRACT
Construction Change Directive

Project name
location / school / campus

Contractor Company name
address
city state zip code

C. C. D. Number: **1**
CP (Change Proposal) Number 1
Issue Date of this Document: 31-Oct-2021

BGS Project No.: n
Other Project No.: x

CCD Item	Type name of CCD item here		
Description of Work	Type brief description here of work scope here.		
Reason or Necessity of Work	Type brief justification for change here.		
Method of Compensation	Select from drop down box…	**Projected Total Cost**	$0
Supporting Documentation	is attached	**Projected Calendar Days***	0

** Calendar Days refers to Contract Final Completion Date only.*
Fully describe the scope of work of the CCD item in the table above and on attached drawings and specifications as necessary.
Indicate the reason for the work, and the estimated schedule and cost impacts.
This CCD records the order to do the work. The documented actual final time and cost changes are subject to approval in a subsequent Change Order process.

Consultant (Architect or Engineer)
Type firm name here
Type person's name, title here
signature date

Contractor
Type company name here
Type person's name, title here
signature date

Owner
Type contracting entity name here
Type person's name, title here
signature date

Owner's Rep
Type entity name here
Type person's name, title here
signature date

Bureau of General Services
Division of Planning, Design & Construction
Type person's name, title here
signature date

State of Maine
CONSTRUCTION CONTRACT
Change Order

Project name
location / school / campus

Change Order: **1**

Issue Date of this Document: 21-Aug-2025

Contractor Company name
address
city state zip code

BGS Project No.: n
Other Project No.: x

Cost Change *Show Deduct as a negative number, e.g.: "-$850".*

	Add	Deduct	Total
Net Amount of this Change Order	$0	$0	
Net Amount of Previous Change Orders	$0	$0	
Net of Change Orders to Date	$0	$0	$0
Original Contract Amount			$0
Revised Contract Amount			**$0**

Time Change *Show Deduct as a negative number, e.g.: "-8".*

	Add	Deduct	Total
Net Calendar Days Adjusted by this Change Order	0	0	
Net Calendar Days Adjusted by Previous Change Orders	0	0	
Net of Change Orders to Date	0	0	0
Original Contract Final Completion Date			30-Apr-2027
Revised Contract Final Completion Date*			**30-Apr-2027**

Consultant (Architect or Engineer)
Type firm name here
Type person's name, title here

---
signature date

Contractor
Type company name here
Type person's name, title here

---
signature date

Owner
Type contracting entity name here
Type person's name, title here

---
signature date

Owner' Representative / Delete if not used
Type entity name here
Type person's name, title here

---
signature date

Project Manager / Delete if not used
Type entity name here
Type person's name, title here

---
signature date

Bureau of General Services
Division of Planning, Design & Construction
Type person's name, title here

---
signature date

Attach the "List of Change Order Items" sheet, plus all supporting documentation for each Change Order Item.

Substantial Completion Date: the deadline for first beneficial use by Owner, as certified by Consultant. 4-May-2027
** **Contract Final Completion Date** : the Contractor's final completion deadline for contract work.* 30-Apr-2027
Contract Expiration Date: the Owner's deadline for internal management of contract accounts; 31-Dec-2027
Contract Expiration Date does not directly relate to any contract obligation of the Contractor.

revised 25 June 2025

State of Maine Change Order

List of Change Order Items

Project name **C. O. Number: 1**

Contractor Company name

Item No.	CP No.	Item Name	Reason Code	Calendar Days*	Cost
1	1	Enter Item Name		0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
				0	$0
			Totals	**0**	**$0**

Reason Codes

EO Error or omission of Consultant
UC Unforeseen job site condition
OC Owner-generated change
RC Regulatory authority-generated change
CC Contractor-generated change

** Calendar Days shows Contract Final Completion Date impact only.*

Attach this sheet to the BGS "Change Order" cover sheet (with cost and time summaries, and signatures). Attach a "Details" sheet, and other supporting documentation, for each Change Order Item listed above.

revised 25 June 2025

State of Maine Change Order

Details of Change Order Item

Project name
location / school / campus

Contractor Company name
address
city state zip code

Change Order	**1**
Item Number	**1**
CP (Change Proposal) Number	**1**
Issue Date of this Document:	21-Aug-2025
BGS Project No.:	n
Other Project No.:	x

Item Name	Add item name from List of Items sheet			
Description of Work	Briefly describe scope of work			
Reason or Necessity of Work	Briefly describe reason or necessity for work change			
Cost Breakdown	Work by Subcontractor only	Work by Sub *and* Contractor	Work by Contractor only	
Subcontractor base cost	$0	$0		
Subcontractor markup	$0	$0		
Contractor base cost		$0	$0	
Contractor markup	$0	$0	$0	
Subtotal	$0	$0	$0	
Compensation	lump sum		**Total Cost**	**$0**
Initiated by	Contractor		**Calendar Days***	0
	CC		**Supporting Documentation**	is not needed

EO — *Error or omission of Consultant*
UC — *Unforeseen job site condition*
OC — *Owner-generated change*
RC — *Regulatory authority-generated change*
CC — *Contractor-generated change*

** Calendar Days shows Contract Final Completion Date impact only.*

Consultant (Architect or Engineer)
Type firm name here
Type person's name, title here

signature date

Contractor
Type company name here
Type person's name, title here

signature date

Owner
Type contracting entity name here
Type person's name, title here

signature date

Owner' Representative / Delete if not used
Type entity name here
Type person's name, title here

signature date

Project Manager / Delete if not used
Type entity name here
Type person's name, title here

signature date

Bureau of General Services
Division of Planning, Design & Construction
Type person's name, title here

signature date

00 71 00
Definitions

1. Definitions

1.1 *Addendum*: A document issued by the Consultant that amends the Bid Documents. Addenda shall not be issued less than seventy-two hours prior to the specified bid opening time.

1.2 *Allowance*: A specified dollar amount for a particular scope of work or service included in the Work that is identified in the Bid Documents and included in each Bidder's Bid. The Contractor shall document expenditures for an Allowance during the Project. Any unused balance shall be credited to the Owner. The Contractor is responsible for notifying the Owner of anticipated expenses greater than the specified amount and the Owner is responsible for those additional expenses.

1.3 *Alternate Bid*: The Contractor's written offer of a specified dollar amount, submitted on the Bid Form, for the performance of a particular scope of work described in the Bid Documents. The Owner determines the low bidder based on the sum of the base Bid and any combination of Alternate Bids that the Owner selects.

1.4 *Architect*: A Consultant acting as, or supporting, the Professional-of-Record who is responsible for the design of the Project. Equivalent to "Consultant" in State of Maine contract forms.

1.5 *Architectural Supplemental Instruction (ASI)*: A written instruction from the Architect for the purpose of clarification of the Contract Documents. An ASI does not alter the Contract Price or Contract Time. ASIs may be responses to RFIs and shall be issued by the Architect in a timely manner to avoid any negative impact on the Schedule of the Work.

1.6 *Bid*: The Contractor's written offer of a specified dollar amount or amounts, submitted on a form included in the Bid Documents, for the performance of the Work. A Bid may include bonds or other requirements. A base Bid is separate and distinct from Alternate Bids, being the only cost component necessary for the award of the contract, and representing the minimum amount of Work that is essential for the functioning of the Project.

1.7 *Bid Bond*: The security designated in the Bid Documents, furnished by Bidders as a guaranty of good faith to enter into a contract with the Owner, should a contract be awarded to that Bidder.

1.8 *Bidder*: Any business entity, individual or corporation that submits a bid for the performance of the work described in the Bid Documents, acting directly or through a duly authorized representative. See also *Responsive and Responsible Bidder*.

1.9 *Bid Documents*: The drawings, procurement and contracting requirements, general requirements, and the written specifications -including all addenda, that a bidder is required to reference in the submission of a bid.

1.10 *Bureau*: The State of Maine Bureau of General Services, or BGS, in the Department of Administrative and Financial Services.

1.11 *Calendar days*: Consecutive days, as occurring on a calendar, taking into account each day of the week, month, year, and any religious, national or local holidays. Calendar days are used for changes in Contract Time.

1.12 *Certificate of Substantial Completion*: A document developed by the Consultant that describes the final status of the Work and establishes the date that the Owner may use the facility for its intended purpose. The Certificate of Substantial Completion may also include a provisional list of items - a "punch list" - remaining to be completed by the Contractor. The Certificate of Substantial Completion identifies the date from which the project warranty period commences.

1.13 *Certificate of Occupancy*: A document developed by a local jurisdiction such as the Code Enforcement Officer that grants permission to the Owner to occupy a building.

1.14 *Change Order (CO)*: A document that modifies the contract and establishes the basis of a specific adjustment to the Contract Price or the Contract Time, or both. Change Orders may address correction of omissions, errors, and document discrepancies, or additional requirements. Change Orders should include all labor, materials and incidentals required to complete the work described. A Change Order is not valid until signed by the Contractor, Owner and Consultant and approved by the Bureau.

1.15 *Change Order Proposal (COP) (see also Proposal)*: Contract change proposed by the Contractor regarding the contract amount, requirements, or time. The Contractor implements the work of a COP after it is accepted by all parties. Accepted COPs are incorporated into the contract by Change Order.

1.16 *Clerk of the Works*: The authorized representative of the Consultant on the job site. Clerk of the Works is sometimes called the Architect's representative.

1.17 *Construction Change Directive (CCD)*: A written order prepared by the Consultant and signed by the Owner and Consultant, directing a change in the Work prior to final agreement with the Contractor on adjustment, if any, in the Contract Price or Contract Time, or both.

1.18 *Contract*: A written agreement between the Owner and the successful bidder which obligates the Contractor to perform the work specified in the Contract Documents and obligates the Owner to compensate the Contractor at the mutually accepted sum, rates or prices.

1.19 *Contract Bonds (also known as Payment and Performance Bonds)*: The approved forms of security, furnished by the Contractor and their surety, which guarantee the faithful performance of all the terms of the contract and the payment of all bills for labor, materials and equipment by the Contractor.

1.20 *Contract Documents*: The drawings and written specifications (including all addenda), Standard General Conditions, and the contract (including all Change Orders subsequently incorporated in the documents).

1.21 *Contract Expiration Date*: Date determined by the Owner as a deadline for internal management of contract accounts. This allows time after the Contract Final Completion Date for processing the final Requisition for Payment. The Contract Expiration Date does not directly relate to any contract obligation of the Contractor.

1.22 *Contract Final Completion Date*: Point of time when the Work is fully completed in compliance with the Contract Documents, as certified by the Consultant. Final payment to the Contractor is due upon Final Completion of the Project.

1.23 *Contract Price*: The dollar amount of the construction contract, also called *Contract Sum*.

1.24 *Contract Time*: The designated duration of time to execute the Work of the contract, with a specific date for completion.

1.25 *Contractor*: Also called the "General Contractor" or "GC" the individual or entity undertaking the execution of the general contract work under the terms of the contract with the Owner, acting directly or through a duly authorized representative. The Contractor is responsible for the means, methods and materials utilized in the execution and completion of the Work.

1.26 *Consultant*: The Architect or Engineer acting as Professional-of-Record for the Project. The Consultant is responsible for the design of the Project.

1.27 *Drawings*: The graphic and pictorial portion of the Contract Documents showing the design, location and dimensions of the Work, generally including plans, elevations, sections, details, schedules, and diagrams.

1.28 *Engineer*: A Consultant acting as, or supporting, the Professional-of-Record who is responsible for the design of the Project. Equivalent to “Consultant” in State of Maine contract forms.

1.29 *Filed Sub-bid*: The designated major Subcontractor's (or, in some cases, Contractor’s) written offer of a specified dollar amount or amounts, submitted on a form included in the Bid Documents, for the performance of a particular portion of the Work. A Filed Sub-bid may include bonds or other requirements.

1.30 *General Requirements*: The on-site overhead expense items the Contractor provides for the Project, typically including, but not limited to, building permits, construction supervision, Contract Bonds, insurance, field office, temporary utilities, rubbish removal, and site fencing. Overhead expenses of the Contractor's general operation are not included. Sometimes referred to as the Contractor's General Conditions.

1.31 *Owner*: The State agency which is represented by duly authorized individuals. The Owner is responsible for defining the scope of the Project and compensation to the Consultant and Contractor.

1.32 *Owner’s Representative*: The individual or entity contracted by the Owner to be an advisor and information conduit regarding the Project.

1.33 *Overhead*: General and administrative expenses of the Contractor’s principal and branch offices, including payroll costs and other compensation of Contractor employees, deductibles paid on any insurance policy, charges against the Contractor for delinquent payments, and costs related to the correction of defective work, and the Contractor’s capital expenses, including interest on capital used for the work.

1.34 *Performance and Payment Bonds (also known as Contract Bonds)*: The approved forms of security, furnished by the Contractor and their surety, which guarantee the faithful performance of all the terms of the contract and the payment of all bills for labor, materials and equipment by the Contractor.

1.35 *Post-Bid Addendum*: Document issued by the Consultant that defines a potential Change Order prior to signing of the construction contract. The Post-Bid Addendum allows the Owner to negotiate

contract changes with the Bidder submitting the lowest valid bid, only if the negotiated changes to the Bid Documents result in no change or no increase in the bid price.

A Post-Bid Addendum may also be issued after a competitive construction Bid opening to those Bidders who submitted a Bid initially, for the purpose of rebidding the Project work without re-advertising.

1.36 *Project*: The construction project proposed by the Owner to be constructed according to the Contract Documents. The Project, a public improvement, may be tied logistically to other public improvements and other activities conducted by the Owner or other contractors.

1.37 *Proposal (see also Change Order Proposal)*: The Contractor's written offer submitted to the Owner for consideration containing a specified dollar amount or rate, for a specific scope of work, and including a schedule impact, if any. A proposal shall include all costs for overhead and profit. The Contractor implements the work of a Proposal after it is accepted by all parties. Accepted Proposals are incorporated into the contract by Change Order.

1.38 *Proposal Request (PR)*: An Owner's written request to the Contractor for a Change Order Proposal.

1.39 *Punch List*: A document that identifies the items of work remaining to be done by the Contractor at the Close Out of a Project. The Punch List is created as a result of a final inspection of the work only after the Contractor attests that all of the Work is in its complete and permanent status.

1.40 *Request For Information (RFI)*: A Contractor's written request to the Consultant for clarification, definition or description of the Work. RFIs shall be presented by the Contractor in a timely manner to avoid any negative impact on the Schedule of the Work.

1.41 *Request For Proposal (RFP)*: An Owner's written request to the Contractor for a Change Order Proposal.

1.42 *Requisition for Payment*: The document in which the Contractor certifies that the Work described is, to the best of the Contractor's knowledge, information and belief, complete and that all previous payments have been paid by the Contractor to Subcontractors and suppliers, and that the current requested payment is now due. See *Schedule of Values.*

1.43 *Responsive and Responsible Bidder*: A bidder who complies, when submitting a bid on a given project, with the following *responsive* standards, as required by the Bid Documents:
- submits specific qualifications to bid the project, if required;
- attends mandatory pre-bid conferences, if required;
- submits a bid prior to the close of the bid period;
- submits a complete bid form;
- submits a bid without indications of intent contrary to the stated requirements;
- submits other materials and information, such as bid security, as required;

and, meets the following minimums regarding these *responsible* standards:
- sustains a satisfactory record of project performance;
- maintains a permanent place of business in a known physical location;
- possesses the financial means for short- and long-term operations;
- possesses the appropriate technical experience and capabilities;
- employs adequate personnel and subcontractor resources;

maintains the equipment needed to perform the work;
complies with the proposed implementation schedule;
complies with the insurance and bonding requirements;
provides post-construction warranty coverage;
and other criteria which can be considered relevant to the contract.

1.44 *Retainage*: The amount, calculated at five percent (5%) of the contract value or a scheduled value, that the Owner shall withhold from the Contractor until the work or portion of work is declared substantially complete or otherwise accepted by the Owner. The Owner may, if requested, reduce the amount withheld if the Owner deems it desirable and prudent to do so. (See Title 5 M.R.S.A., Section 1746.)

1.45 *Sample*: A physical example provided by the Contractor which illustrates materials, equipment or workmanship and establishes standards by which the Work will be judged.

1.46 *Schedule of the Work*: The document prepared by the Contractor and approved by the Owner that specifies the dates on which the Contractor plans to begin and complete various parts of the Work, including dates on which information and approvals are required from the Owner.

1.47 *Schedule of Values*: The document prepared by the Contractor and approved by the Owner before the commencement of the Work that specifies the dollar values of discrete portions of the Work equal in sum to the contract amount. The Schedule of Values is used to document progress payments of the Work in regular (usually monthly) requisitions for payment. See *Requisition for Payment*.

1.48 *Shop Drawings*: The drawings, diagrams, schedules and other data specially prepared for the Work by the Contractor or a Subcontractor, manufacturer, supplier or distributor to illustrate some portion of the Work.

1.49 *Specifications*: The portion of the Contract Documents consisting of the written requirements of the Work for materials, equipment, systems, standards, workmanship, and performance of related services.

1.50 *Subcontractor*: An individual or entity undertaking the execution of any part of the Work by virtue of a written agreement with the Contractor or any other Subcontractor. Also, an individual or entity retained by the Contractor or any other Subcontractor as an independent contractor to provide the labor, materials, equipment or services necessary to complete a specific portion of the Work.

1.51 *Substantial Completion Date*: Point of time when the Work or a designated portion of the Work is sufficiently complete in compliance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended purpose without unscheduled disruption. Substantial Completion is documented by the date of the Certificate of Substantial Completion signed by the Owner and the Contractor.

1.52 *Superintendent*: The representative of the Contractor on the job site, authorized by the Contractor to receive and fulfill instructions from the Consultant.

1.53 *Surety*: The individual or entity that is legally bound with the Contractor and Subcontractor to insure the faithful performance of the contract and for the payment of the bills for labor, materials and equipment by the Contractor and Subcontractors.

1.54 *Work*: The construction and services, whether completed or partially completed, including all labor, materials, equipment and services provided or to be provided by the Contractor and Subcontractors to fulfill the requirements of the Project as described in the Contract Documents.

00 72 13
General Conditions

Table of Contents of this General Conditions Section

1. Preconstruction Conference 2
2. Intent and Correlation of Contract Documents 2
3. Additional Drawings and Specifications 3
4. Ownership of Contract Documents 3
5. Permits, Laws, and Regulations 3
6. Taxes 4
7. Labor and Wages 4
8. Indemnification 5
9. Insurance Requirements 5
10. Contract Bonds 6
11. Patents and Royalties 7
12. Surveys, Layout of Work 7
13. Record of Documents 7
14. Allowances 8
15. Shop Drawings 8
16. Samples 8
17. Substitutions 8
18. Assignment of Contract 9
19. Separate Contracts 9
20. Subcontracts 10
21. Contractor-Subcontractor Relationship 10
22. Supervision of the Work 11
23. Observation of the Work 11
24. Consultant's Status 12
25. Management of the Premises 12
26. Safety and Security of the Premises 13
27. Changes in the Work 14
28. Correction of the Work 15
29. Owner's Right to do Work 16
30. Termination of Contract and Stop Work Action 16
31. Delays and Extension of Time 17
32. Payments to the Contractor 18
33. Payments Withheld 19
34. Liens 19
35. Workmanship 19
36. Close-out of the Work 20
37. Date of Completion and Liquidated Damages 21
38. Dispute Resolution 21

1. Preconstruction Conference

1.1 The Contractor shall, upon acceptance of a contract and prior to commencing work, schedule a preconstruction conference with the Owner and Consultant. The purpose of this conference is as follows.

1.1.1 Introduce all parties who have a significant role in the Project, including:
Owner (State agency or other contracting entity)
Owner's Representative
Consultant (Architect or Engineer)
Subconsultants
Clerk-of-the-works
Contractor (GC)
Superintendent
Subcontractors
Other State agencies
Construction testing company
Commissioning agent
Special Inspections agent
Bureau of General Services (BGS);

1.1.2 Review the responsibilities of each party;

1.1.3 Review any previously-identified special provisions of the Project;

1.1.4 Review the Schedule of the Work calendar submitted by the Contractor to be approved by the Owner and Consultant;

1.1.5 Review the Schedule of Values form submitted by the Contractor to be approved by the Owner and Consultant;

1.1.6 Establish routines for Shop Drawing approval, contract changes, requisitions, et cetera;

1.1.7 discuss jobsite issues;

1.1.8 Discuss Project close-out procedures;

1.1.9 Provide an opportunity for clarification of Contract Documents before work begins; and

1.1.10 Schedule regular meetings at appropriate intervals for the review of the progress of the Work.

2. Intent and Correlation of Contract Documents

2.1 The intent of the Contract Documents is to describe the complete Project. The Contract Documents consist of various components; each component complements the others. What is shown as a requirement by any one component shall be inferred as a requirement on all corresponding components.

2.2 The Contractor shall furnish all labor, equipment and materials, tools, transportation, insurance, services, supplies, operations and methods necessary for, and reasonably incidental to, the construction and completion of the Project. Any work that deviates from the Contract Documents which appears to be required by the exigencies of construction or by inconsistencies in the Contract Documents, will be determined by the Consultant and authorized in writing by the Consultant, Owner and the Bureau prior to execution. The Contractor shall be responsible for requesting clarifying information where the intent of the Contract Documents is uncertain.

2.3 The Contractor shall not utilize any apparent error or omission in the Contract Documents to the disadvantage of the Owner. The Contractor shall promptly notify the Consultant in writing of such errors or omissions. The Consultant shall make any corrections or clarifications necessary in such a situation to document the true intent of the Contract Documents.

3. Additional Drawings and Specifications

3.1 Upon the written request of the Contractor, the Owner shall provide, at no expense to the Contractor, up to five sets of printed Drawings and Specifications for the execution of the Work.

3.2 The Consultant shall promptly furnish to the Contractor revised Drawings and Specifications, for the area of the documents where those revisions apply, when corrections or clarifications are made by the Consultant. All such information shall be consistent with, and reasonably inferred from, the Contract Documents. The Contractor shall do no work without the proper Drawings and Specifications.

4. Ownership of Contract Documents

4.1 The designs represented on the Contract Documents are the property of the Consultant. The Drawings and Specifications shall not be used on other work without consent of the Consultant.

5. Permits, Laws, and Regulations

5.1 The Owner is responsible for obtaining any zoning approvals or other similar local project approvals necessary to complete the Work, unless otherwise specified in the Contract Documents.

5.2 The Owner is responsible for obtaining Maine Department of Environmental Protection, Maine Department of Transportation, or other similar state government project approvals necessary to complete the Work, unless otherwise indicated in the Contract Documents.

5.3 The Owner is responsible for obtaining any federal agency project approvals necessary to complete the Work, unless otherwise indicated in the Contract Documents.

5.4 The Owner is responsible for obtaining all easements for permanent structures or permanent changes in existing facilities.

5.5 The Contractor is responsible for obtaining and paying for all permits and licenses necessary for the implementation of the Work. The Contractor shall notify the Owner of any delays, variance or restrictions that may result from the issuing of permits and licenses.

5.6 The Contractor shall comply with all ordinances, laws, rules and regulations and make all required notices bearing on the implementation of the Work. In the event the Contractor observes disagreement between the Drawings and Specifications and any ordinances, laws, rules and regulations, the Contractor shall promptly notify the Consultant in writing. Any necessary changes shall be made as provided in the contract for changes in the work. The Contractor shall not perform any work knowing it to be contrary to such ordinances, laws, rules and regulations.

5.7 The Contractor shall comply with local, state and federal regulations regarding construction safety and all other aspects of the Work.

5.8 The Contractor shall comply with the Maine Code of Fair Practices and Affirmative Action, 5 M.R.S. §784 (2).

6. Taxes

6.1 The Owner is exempt from the payment of Maine State sales and use taxes as provided in 36 M.R.S. §1760 (1). The Contractor and Subcontractors shall not include taxes on exempt items in the construction contract.

6.2 Section 1760 further provides in subsection 61 that sales to a construction contractor or its subcontractor of tangible personal property that is to be physically incorporated in, and become a permanent part of, real property for sale to or owned by the Owner, are exempt from Maine State sales and use taxes. Tangible personal property is defined in 36 M.R.S. §1752 (17).

6.3 The Contractor may contact Maine Revenue Services, 24 State House Station, Augusta, Maine 04333 for guidance on tax exempt regulations authorized by 36 M.R.S. §1760 and detailed in Rule 302 (18-125 CMR 302).

7. Labor and Wages

7.1 The Contractor shall conform to the labor laws of the State of Maine, and all other laws, ordinances, and legal requirements affecting the work in Maine.

7.2 The Consultant shall include a wage determination document prepared by the Maine Department of Labor in the Contract Documents for state-funded contracts in excess of $50,000. The document shows the minimum wages required to be paid to each category of labor employed on the project.

7.3 On projects requiring a Maine wage determination, the Contractor shall submit monthly payroll records to the Owner ("the contracting agency") showing the name and occupation of all workers and all independent contractors employed on the project. The monthly submission must also include the Contractor's company name, the title of the project, hours worked, hourly rate or other method of remuneration, and the actual wages or other compensation paid to each person.

7.4 The Contractor shall not reveal, in the payroll records submitted to the Owner, personal information regarding workers and independent contractors, other than the information described above. Such information shall not include Social Security number, employee identification number, or employee address or phone number, for example.

7.5 The Contractor shall conform to Maine statute (39-A M.R.S. §105-A (6)) by providing to the Workers' Compensation Board a list of all subcontractors and independent contractors on the job site and a record of the entity to whom that subcontractor or independent contractor is directly contracted and by whom that subcontractor or independent contractor is insured for workers' compensation purposes.

7.6 The Contractor shall enforce strict discipline and good order among their employees at all times, and shall not employ any person unfit or unskilled to do the work assigned to them.

7.7 The Contractor shall promptly pay all employees when their compensation is due, shall promptly pay all others who have billed and are due for materials, supplies and services used in the Work, and shall promptly pay all others who have billed and are due for insurance, workers compensation coverage, federal and state unemployment compensation, and Social Security

charges pertaining to this Project. Before final payments are made, the Contractor shall furnish to the Owner affidavits that all such payments described above have been made.

7.8 The Contractor may contact the Maine Department of Labor, 54 State House Station, Augusta, Maine 04333 for guidance on labor issues.

7.9 The Contractor may contact the Maine Workers' Compensation Board, 27 State House Station, Augusta, Maine 04333 for guidance on workers' compensation issues.

8. Indemnification

8.1 The Contractor shall indemnify and hold harmless the Owner and its officers and employees from and against any and all damages, liabilities, and costs, including reasonable attorney's fees, and defense costs, for any and all injuries to persons or property, including claims for violation of intellectual property rights, to the extent caused by the negligent acts or omissions of the Contractor, its employees, agents, officers or subcontractors in the performance of work under this Agreement. The Contractor shall not be liable for claims to the extent caused by the negligent acts or omissions of the Owner or for actions taken in reasonable reliance on written instructions of the Owner.

8.2 The Contractor shall notify the Owner promptly of all claims arising out of the performance of work under this Agreement by the Contractor, its employees or agents, officers or subcontractors.

8.3 This indemnity provision shall survive the termination of the Agreement, completion of the project or the expiration of the term of the Agreement.

9. Insurance Requirements

9.1 The Contractor shall provide, with each original of the signed Contract, an insurance certificate or certificates acceptable to the Owner and BGS. The Contractor shall submit insurance certificates to the Owner and BGS at the commencement of this Contract and at policy renewal or revision dates. The certificates shall identify the project name and BGS project number, and shall name the Owner as certificate holder and as additional insured for general liability and automobile liability coverages. The submitted forms shall contain a provision that coverage afforded under the insurance policies will not be canceled or materially changed unless at least ten days prior written notice by registered letter has been given to the Owner and BGS.

9.2 The Owner does not warrant or represent that the insurance required herein constitutes an insurance portfolio which adequately addresses all risks faced by the Contractor or its Subcontractors. The Contractor is responsible for the existence, extent and adequacy of insurance prior to commencement of work. The Contractor shall not allow any Subcontractor to commence work until all similar insurance required of the Subcontractor has been confirmed by the Contractor.

9.3 The Contractor shall procure and maintain primary insurance for the duration of the Project and, if written on a Claims-Made basis, shall also procure and maintain Extended Reporting Period (ERP) insurance for the period of time that any claims could be brought. The Contractor shall ensure that all Subcontractors they engage or employ will procure and maintain similar insurance

in form and amount acceptable to the Owner and BGS. At a minimum, the insurance shall be of the types and limits set forth herein protecting the Contractor from claims which may result from the Contractor's execution of the Work, whether such execution be by the Contractor or by those employed by the Contractor or by those for whose acts they may be liable. All required insurance coverages shall be placed with carriers authorized to conduct business in the State of Maine by the Maine Bureau of Insurance.

9.3.1 The Contractor shall have Workers' Compensation insurance for all employees on the Project site in accordance with the requirements of the Workers' Compensation law of the State of Maine. Minimum acceptable limits for Employer's Liability are:

Bodily Injury by Accident.....$500,000
Bodily Injury by Disease.....$500,000 Each Employee
Bodily Injury by Disease.....$500,000 Policy Limit

9.3.2 The Contractor shall have Commercial General Liability insurance providing coverage for bodily injury and property damage liability for all hazards of the Project including premise and operations, products and completed operations, contractual, and personal injury liabilities. The policy shall include collapse and underground coverage as well as explosion coverage if explosion hazards exist. Aggregate limits shall apply on a location or project basis. Minimum acceptable limits are:

General aggregate limit.....$2,000,000
Products and completed operations aggregate $1,000,000
Each occurrence limit.....$1,000,000
Personal injury aggregate.....$1,000,000

9.3.3 The Contractor shall have Automobile Liability insurance against claims for bodily injury, death or property damage resulting from the maintenance, ownership or use of all owned, non-owned and hired automobiles, trucks and trailers. Minimum acceptable limit is:

Any one accident or loss $500,000

9.3.4 For the portion of a project which is new construction, the Contractor shall procure and maintain Builder's Risk insurance naming the Owner, Contractor, and any Subcontractor as insureds as their interest may appear. Covered causes of loss form shall be all Risks of Direct Physical Loss, endorsed to include flood, earthquake, transit and sprinkler leakage where sprinkler coverage is applicable. Unless specifically authorized in writing by the Owner, the limit of insurance shall not be less than the initial contract amount, for the portion of the project which is new construction, and coverage shall apply during the entire contract period and until the work is accepted by the Owner.

9.3.5 The Contractor shall have Owner's Protective Liability insurance for contract values $50,000 and above, naming the Owner as the Named Insured. Minimum acceptable limits are:

General aggregate limit.....$2,000,000
Each occurrence limit.....$1,000,000

10. Contract Bonds

10.1 When noted as required in the Bid Documents, the Contractor shall provide to the Owner a Performance Bond and a Payment Bond, or "contract bonds", upon execution of the contract. Each bond value shall be for the full amount of the contract and issued by a surety company authorized to do business in the State of Maine as approved by the Owner. The bonds shall be

executed on the forms furnished in the Bid Documents. The bonds shall allow for any subsequent additions or deductions of the contract.

10.2 The contract bonds shall continue in effect for one year after final acceptance of the contract to protect the Owner's interest in connection with the one year guarantee of workmanship and materials and to assure settlement of claims for the payment of all bills for labor, materials and equipment by the Contractor.

11. Patents and Royalties

11.1 The Contractor shall, for all time, secure for the Owner the free and undisputed right to the use of any patented articles or methods used in the Work. The expense of defending any suits for infringement or alleged infringement of such patents shall be borne by the Contractor. Awards made regarding patent suits shall be paid by the Contractor. The Contractor shall hold the Owner harmless regarding patent suits that may arise due to installations made by the Contractor, and to any awards made as a result of such suits.

11.2 Any royalty payments related to the work done by the Contractor for the Project shall be borne by the Contractor. The Contractor shall hold the Owner harmless regarding any royalty payments that may arise due to installations made by the Contractor.

12. Surveys, Layout of Work

12.1 The Owner shall furnish all property surveys unless otherwise specified.

12.2 The Contractor is responsible for correctly staking out the Work on the site. The Contractor shall employ a competent surveyor to position all construction on the site. The surveyor shall run the axis lines, establish correct datum points and check each line and point on the site to insure their accuracy. All such lines and points shall be carefully preserved throughout the construction.

12.3 The Contractor shall lay out all work from dimensions given on the Drawings. The Contractor shall take measurements and verify dimensions of any existing work that affects the Work or to which the Work is to be fitted. The Contractor is solely responsible for the accuracy of all measurements. The Contractor shall verify all grades, lines, levels, elevations and dimensions shown on the Drawings and report any errors or inconsistencies to the Consultant prior to commencing work.

13. Record of Documents

13.1 The Contractor shall maintain one complete set of Contract Documents on the jobsite, in good order and current status, for access by the Owner and Consultant.

13.2 The Contractor shall maintain, continuously updated, complete records of Requests for Information, Architectural Supplemental Instructions (or equivalent), Information Bulletins, supplemental sketches, Change Order Proposals, Change Orders, Shop Drawings, testing reports, et cetera, for access by the Owner and Consultant.

14. Allowances

14.1 The Contract Price shall include all allowances described in the Contract Documents. The Contractor shall include all overhead and profit necessary to implement each allowance in their Contract Price.

14.2 The Contractor shall not be required to employ parties for allowance work against whom the Contractor has a reasonable objection. In such a case, the Contractor shall notify the Owner in writing of their position and shall propose an alternative party to complete the work of the allowance.

15. Shop Drawings

15.1 The Contractor shall administer Shop Drawings prepared by the Contractor, Subcontractors, suppliers or others to conform to the approved Schedule of the Work. The Contractor shall verify all field measurements, check and authorize all Shop Drawings and schedules required by the Work. The Contractor is the responsible party and contact for the Contractor's work as well as that of Subcontractors, suppliers or others who provide Shop Drawings.

15.2 The Consultant shall review and acknowledge Shop Drawings, with reasonable promptness, for general conformity with the design concept of the project and compliance with the information provided in the Contract Documents.

15.3 The Contractor shall provide monthly updated logs containing: requests for information, information bulletins, supplemental instructions, supplemental sketches, change order proposals, change orders, submittals, testing and deficiencies.

15.4 The Contractor shall make any corrections required by the Consultant, and shall submit a quantity of corrected copies as may be needed. The acceptance of Shop Drawings or schedules by the Consultant shall not relieve the Contractor from responsibility for deviations from Drawings and Specifications, unless the Contractor has called such deviations to the attention of the Consultant at the time of submission and secured the Consultant’s written approval. The acceptance of Shop Drawings or schedules by the Consultant does not relieve the Contractor from responsibility for errors in Shop Drawings or schedules.

16. Samples

16.1 The Contractor shall furnish for approval, with reasonable promptness, all samples as directed by the Consultant. The Consultant shall review and approve such samples, with reasonable promptness, for general conformity with the design concept of the project and compliance with the information provided in the Contract Documents. The subsequent work shall be in accord with the approved samples.

17. Substitutions

17.1 The Contractor shall furnish items and materials described in the Contract Documents. If the item or material specified describes a proprietary product, or uses the name of a manufacturer, the term “or approved equal” shall be implied, if it is not included in the text. The specific item or material specified establishes a minimum standard for the general design, level of quality, type, function, durability, efficiency, reliability, compatibility, warranty coverage, installation factors

and required maintenance. The Drawing or written Specification shall not be construed to exclude other manufacturers products of comparable design, quality, and efficiency.

17.2 The Contractor may submit detailed information about a proposed substitution to the Consultant for consideration. Particular models of items and particular materials which the Contractor asserts to be equal to the items and materials identified in the Contract Documents shall be allowed only with written approval by the Consultant. The request for substitution shall include a cost comparison and a reason or reasons for the substitution.

17.3 The Consultant may request additional information about the proposed substitution. The approval or rejection of a proposed substitution may be based on timeliness of the request, source of the information, the considerations of minimum standards described above, or other considerations. The Consultant should briefly state the rationale for the decision. The decision shall be considered final.

17.4 The duration of a substitution review process can not be the basis for a claim for delay in the Schedule of the Work.

18. Assignment of Contract

18.1 The Contractor shall not assign or sublet the contract as a whole without the written consent of the Owner. The Contractor shall not assign any money due to the Contractor without the written consent of the Owner.

19. Separate Contracts

19.1 The Owner reserves the right to create other contracts in connection with this Project using similar General Conditions. The Contractor shall allow the Owner's other contractors reasonable opportunity for the delivery and storage of materials and the execution of their work. The Contractor shall coordinate and properly connect the Work of all contractors.

19.2 The Contractor shall promptly report to the Consultant and Owner any apparent deficiencies in work of the Owner's other contractors that impacts the proper execution or results of the Contractor. The Contractor’s failure to observe or report any deficiencies constitutes an acceptance of the Owner's other contractors work as suitable for the interface of the Contractor’s work, except for latent deficiencies in the Owner's other contractors work.

19.3 Similarly, the Contractor shall promptly report to the Consultant and Owner any apparent deficiencies in their own work that would impact the proper execution or results of the Owner's other contractors.

19.4 The Contractor shall report to the Consultant and Owner any conflicts or claims for damages with the Owner's other contractors and settle such conflicts or claims for damages by mutual agreement or arbitration, if necessary, at no expense to the Owner.

19.5 In the event the Owner's other contractors sue the Owner regarding any damage alleged to have been caused by the Contractor, the Owner shall notify the Contractor, who shall defend such proceedings at the Contractor's expense. The Contractor shall pay or satisfy any judgment that may arise against the Owner, and pay all other costs incurred.

20. Subcontracts

20.1 The Contractor shall not subcontract any part of this contract without the written permission of the Owner.

20.2 The Contractor shall submit a complete list of named Subcontractors and material suppliers to the Consultant and Owner for approval by the Owner prior to commencing work. The Subcontractors named shall be reputable companies of recognized standing with a record of satisfactory work.

20.3 The Contractor shall not employ any Subcontractor or use any material until they have been approved, or where there is reason to believe the resulting work will not comply with the Contract Documents.

20.4 The Contractor, not the Owner, is as fully responsible for the acts and omissions of Subcontractors and of persons employed by them, as the Contractor is for the acts and omissions of persons directly or indirectly employed by the Contractor.

20.5 Neither the Contract Documents nor any Contractor-Subcontractor contract shall indicate, infer or create any direct contractual relationship between any Subcontractor and the Owner.

21. Contractor-Subcontractor Relationship

21.1 The Contractor shall be bound to the Subcontractor by all the obligations in the Contract Documents that bind the Contractor to the Owner.

21.2 The Contractor shall pay the Subcontractor, in proportion to the dollar value of the work completed and requisitioned by the Subcontractor, the approved dollar amount allowed to the Contractor no more than seven days after receipt of payment from the Owner.

21.3 The Contractor shall pay the Subcontractor accordingly if the Contract Documents or the subcontract provide for earlier or larger payments than described in the provision above.

21.4 The Contractor shall pay the Subcontractor for completed and requisitioned subcontract work, less retainage, no more than seven days after receipt of payment from the Owner for the Contractor's approved Requisition for Payment, even if the Consultant fails to certify a portion of the Requisition for Payment for a cause not the fault of the Subcontractor.

21.5 The Contractor shall not make a claim for liquidated damages or penalty for delay in any amount in excess of amounts that are specified by the subcontract.

21.6 The Contractor shall not make a claim for services rendered or materials furnished by the Subcontractor unless written notice is given by the Contractor to the Subcontractor within ten calendar days of the day in which the claim originated.

21.7 The Contractor shall give the Subcontractor an opportunity to present and to submit evidence in any progress conference or disputes involving subcontract work.

21.8 The Contractor shall pay the Subcontractor a just share of any fire insurance payment received by the Contractor.

21.9 The Subcontractor shall be bound to the Contractor by the terms of the Contract Documents and assumes toward the Contractor all the obligations and responsibilities that the Contractor, by those documents, assumes toward the Owner.

21.10 The Subcontractor shall submit applications for payment to the Contractor in such reasonable time as to enable the Contractor to apply for payment as specified.

21.11 The Subcontractor shall make any claims for extra cost, extensions of time or damages, to the Contractor in the manner provided in these General Conditions for like claims by the Contractor to the Owner, except that the time for the Subcontractor to make claims for extra cost is seven calendar days after the receipt of Consultant's instructions.

22. Supervision of the Work

22.1 During all stages of the Work the Contractor shall have a competent superintendent, with any necessary assistant superintendents, overseeing the project. The superintendent shall not be reassigned without the consent of the Owner unless a superintendent ceases to be employed by the Contractor due to unsatisfactory performance.

22.2 The superintendent represents the Contractor on the jobsite. Directives given by the Consultant or Owner to the superintendent shall be as binding as if given directly to the Contractor's main office. All important directives shall be confirmed in writing to the Contractor. The Consultant and Owner are not responsible for the acts or omissions of the superintendent or assistant superintendents.

22.3 The Contractor shall provide supervision of the Work equal to the industry's highest standard of care. The superintendent shall carefully study and compare all Contract Documents and promptly report any error, inconsistency or omission discovered to the Consultant. The Contractor may not necessarily be held liable for damages resulting directly from any error, inconsistency or omission in the Contract Documents or other instructions by the Consultant that was not revealed by the superintendent in a timely way.

23. Observation of the Work

23.1 The Contractor shall allow the Owner, the Consultant and the Bureau continuous access to the site for the purpose of observation of the progress of the work. All necessary safeguards and accommodations for such observations shall be provided by the Contractor.

23.2 The Contractor shall coordinate all required testing, approval or demonstration of the Work. The Contractor shall give sufficient notice to the appropriate parties of readiness for testing, inspection or examination.

23.3 The Contractor shall schedule inspections and obtain all required certificates of inspection for inspections by a party other than the Consultant.

23.4 The Consultant shall make all scheduled observations promptly, prior to the work being concealed or buried by the Contractor. If approval of the Work is required of the Consultant, the Contractor shall notify the Consultant of the construction schedule in this regard. Work concealed or buried prior to the Consultant's approval may need to be uncovered at the Contractor's expense.

23.5 The Consultant may order reexamination of questioned work, and, if so ordered, the work must be uncovered by the Contractor. If the work is found to conform to the Contract Documents, the Owner shall pay the expense of the reexamination and remedial work. If the work is found to not conform to the Contract Documents, the Contractor shall pay the expense, unless the defect in the work was caused by the Owner's Contractor, whose responsibility the reexamination expense becomes.

23.6 The Bureau shall periodically observe the Work during the course of construction and make recommendations to the Contractor or Consultant as necessary. Such recommendations shall be considered and implemented through the usual means for changes to the Work.

24. Consultant's Status

24.1 The Consultant represents the Owner during the construction period, and observes the work in progress on behalf of the Owner. The Consultant has authority to act on behalf of the Owner only to the extent expressly provided by the Contract Documents or otherwise demonstrated to the Contractor. The Consultant has authority to stop the work whenever such an action is necessary, in the Consultant's reasonable opinion, to ensure the proper execution of the contract.

24.2 The Consultant is the interpreter of the conditions of the contract and the judge of its performance. The Consultant shall favor neither the Owner nor the Contractor, but shall use the Consultant's powers under the contract to enforce faithful performance by both parties.

24.3 In the event of the termination of the Consultant's employment on the project prior to completion of the work, the Owner shall appoint a capable and reputable replacement. The status of the new Consultant relative to this contract shall be that of the former Consultant.

25. Management of the Premises

25.1 The Contractor shall place equipment and materials, and conduct activities on the premises in a manner that does not unreasonably hinder site circulation, environmental stability, or any long term effect. Likewise, the Consultant's directions shall not cause the use of premises to be impeded for the Contractor or Owner.

25.2 The Contractor shall not use the premises for any purpose other than that which is directly related to the scope of work. The Owner shall not use the premises for any purpose incompatible with the proposed work simultaneous to the work of the Contractor.

25.3 The Contractor shall enforce the Consultant's instructions regarding information posted on the premises such as signage and advertisements, as well as activities conducted on the premises such as fires, and smoking.

25.4 The Owner may occupy any part of the Project that is completed with the written consent of the Contractor, and without prejudice to any of the rights of the Owner or Contractor. Such use or occupancy shall not, in and of itself, be construed as a final acceptance of any work or materials.

26. Safety and Security of the Premises

26.1 The Contractor shall designate, and make known to the Consultant and the Owner, a safety officer whose duty is the prevention of accidents on the site.

26.2 The Contractor shall continuously maintain security on the premises and protect from unreasonable occasion of injury all people authorized to be on the job site. The Contractor shall also effectively protect the property and adjacent properties from damage or loss.

26.3 The Contractor shall take all necessary precautions to ensure the safety of workers and others on and adjacent to the site, abiding by applicable local, state and federal safety regulations. The Contractor shall erect and continuously maintain safeguards for the protection of workers and others, and shall post signs and other warnings regarding hazards associated with the construction process, such as protruding fasteners, moving equipment, trenches and holes, scaffolding, window, door or stair openings, and falling materials.

26.4 The Contractor shall restore the premises to conditions that existed prior to the start of the project at areas not intended to be altered according to the Contract Documents.

26.5 The Contractor shall protect existing utilities and exercise care working in the vicinity of utilities shown in the Drawings and Specifications or otherwise located by the Contractor.

26.6 The Contractor shall protect from damage existing trees and other significant plantings and landscape features of the site which will remain a permanent part of the site. If necessary or indicated in the Contract Documents, tree trunks shall be boxed and barriers erected to prevent damage to tree branches or roots.

26.7 The Contractor shall repair or replace damage to the Work caused by the Contractor's or Subcontractor's forces, including that which is reasonably protected, at the expense of the responsible party.

26.8 The Contractor shall not load, or allow to be loaded, any part of the Project with a force which imperils personal or structural safety. The Consultant may consult with the Contractor on such means and methods of construction, however, the ultimate responsibility lies with the Contractor.

26.9 The Contractor shall not jeopardize any work in place with subsequent construction activities such as blasting, drilling, excavating, cutting, patching or altering work. The Consultant must approve altering any structural components of the project. The Contractor shall supervise all construction activities carried out by others on site to ensure that the work is neatly done and in a manner that will not endanger the structure or the component parts.

26.10 The Contractor may act with their sole discretion in emergency situations that potentially effect health, life or serious damage to the premises or adjacent properties, to prevent such potential loss or injury. The Contractor may negotiate with the Owner for compensation for expenses due to such emergency work.

26.11 The Contractor and Subcontractors shall have no responsibility for the identification, discovery, presence, handling, removal or disposal of, or exposure of persons to, hazardous materials in any form at the project site. The Contractor shall avoid disruption of any hazardous materials or toxic substances at the project site and promptly notify the Owner in writing on the occasion of such a discovery.

26.12 The Contractor shall keep the premises free of any unsafe accumulation of waste materials caused by the work. The Contractor shall regularly keep the spaces "broom clean". See the Close-out of the Work provisions of this section regarding cleaning at the completion of the project.

27. Changes in the Work

27.1 The Contractor shall not proceed with extra work without an approved Change Order or Construction Change Directive. A Change Order which has been properly signed by all parties shall become a part of the contract.

27.2 A Change Order is the usual document for directing changes in the Work. In certain circumstances, however, the Owner may utilize a Construction Change Directive to direct the Contractor to perform changes in the Work that are generally consistent with the scope of the project. The Owner shall use a Construction Change Directive only when the normal process for approving changes to the Work has failed to the detriment of the Project, or when agreement on the terms of a Change Order cannot be met, or when an urgent situation requires, in the Owner's judgment, prompt action by the Contractor.

27.3 The Consultant shall prepare the Construction Change Directive representing a complete scope of work, with proposed Contract Price and Contract Time revisions, if any, clearly stated.

27.4 The Contractor shall promptly carry out a Construction Change Directive which has been signed by the Owner and the Consultant. Work thus completed by the Contractor constitutes the basis for a Change Order. Changes in the Contract Price and Contract Time shall be as defined in the Construction Change Directive unless subsequently negotiated with some other terms.

27.5 The method of determining the dollar value of extra work shall be by:
- .1 an estimate of the Contractor accepted by Owner as a lump sum, or
- .2 unit prices named in the contract or subsequently agreed upon, or
- .3 cost plus a designated percentage, or
- .4 cost plus a fixed fee.

27.6 The Contractor shall determine the dollar value of the extra work for both the lump sum and cost plus designated percentage methods so as not to exceed the following rates. The rates include all overhead and profit expenses.
- .1 Contractor - for any work performed by the Contractor's own forces, up to 20% of the cost;
- .2 Subcontractor - for work performed by Subcontractor's own forces, up to 20% of the cost;
- .3 Contractor - for work performed by Contractor's Subcontractor, up to 10% of the amount due the Subcontractor.

27.7 The Contractor shall keep and provide records as needed or directed for the cost plus designated percentage method. The Consultant shall review and certify the appropriate amount which

includes the Contractor's overhead and profit. The Owner shall make payments based on the Consultant's certificate.

27.8 Cost reflected in Change Orders shall be limited to the following: cost of materials, cost of delivery, cost of labor (including Social Security, pension, Workers' Compensation insurance, and unemployment insurance), and cost of rental of power tools and equipment. Labor cost may include a pro-ratio share of a foreman's time only in the case of an extension of contract time granted due to the Change Order.

27.9 Overhead reflected in Change Orders shall be limited to the following: bond premium, supervision, wages of clerks, time keepers, and watchmen, small tools, incidental expenses, general office expenses, and all other overhead expenses directly related to the Change Order.

27.10 The Contractor shall provide credit to the Owner for labor, materials, equipment and other costs but not overhead and profit expenses for those Change Order items that result in a net value of credit to the contract.

27.11 The Owner may change the scope of work of the Project without invalidating the contract. The Owner shall notify the Contractor of a change of the scope of work for the Owner's Contractors, which may affect the work of this Contractor, without invalidating the contract. Change Orders for extension of the time caused by such changes shall be developed at the time of directing the change in scope of work.

27.12 The Consultant may order minor changes in the Work, not involving extra cost, which is consistent with the intent of the design or project.

27.13 The Contractor shall immediately give written notification to the Consultant of latent conditions discovered at the site which materially differ from those represented in the Drawings or Specifications, and which may eventually result in a change in the scope of work. The Contractor shall suspend work until receiving direction from the Consultant. The Consultant shall promptly investigate the conditions and respond to the Contractor's notice with direction that avoids any unnecessary delay of the Work. The Consultant shall determine if the discovered conditions warrant a Change Order.

27.14 The Contractor shall, within ten calendar days of receipt of the information, give written notification to the Consultant if the Contractor claims that instructions by the Consultant will constitute extra cost not accounted for by Change Order or otherwise under the contract. The Consultant shall promptly respond to the Contractor's notice with direction that avoids any unnecessary delay of the Work. The Consultant shall determine if the Contractor's claim warrants a Change Order.

28. Correction of the Work

28.1 The Contractor shall promptly remove from the premises all work the Consultant declares is non-conforming to the contract. The Contractor shall replace the work properly at no expense to the Owner. The Contractor is also responsible for the expenses of others whose work was damaged or destroyed by such remedial work.

28.2 The Owner may elect to remove non-conforming work if it is not removed by the Contractor within a reasonable time, that time defined in a written notice from the Consultant. The Owner may elect to store removed non-conforming work not removed by the Contractor at the Contractor's expense. The Owner may, with ten days written notice, dispose of materials which the Contractor does not remove. The Owner may sell the materials and apply the net proceeds, after deducting all expenses, to the costs that should have been borne by the Contractor.

28.3 The Contractor shall remedy any defects due to faulty materials or workmanship and pay for any related damage to other work which appears within a period of one year from the date of substantial completion, and in accord with the terms of any guarantees provided in the contract. The Owner shall promptly give notice of observed defects to the Contractor and Consultant. The Consultant shall determine the status of all claimed defects. The Contractor shall perform all remedial work without unjustifiable delay in either the initial response or the corrective action.

28.4 The Consultant may authorize, after a reasonable notification to the Contractor, an equitable deduction from the contract amount in lieu of the Contractor correcting non-conforming or defective work.

29. Owner's Right to do Work

29.1 The Owner may, using other contractors, correct deficiencies attributable to the Contractor, or complete unfinished work. Such action shall take place only after giving the Contractor three days written notice, and provided the Consultant approves of the proposed course of action as an appropriate remedy. The Owner may then deduct the cost of the remedial work from the amount due the Contractor.

29.2 The Owner may act with their sole discretion when the Contractor is unable to take action in emergency situations that potentially effect health, life or serious damage to the premises or adjacent properties, to prevent such potential loss or injury. The Owner shall inform the Contractor of the emergency work performed, particularly where it may affect the work of the Contractor.

30. Termination of Contract and Stop Work Action

30.1 The Owner may, owing to a certificate of the Consultant indicating that sufficient cause exists to justify such action, without prejudice to any other right or remedy and after giving the Contractor and the Contractor’s surety seven days written notice, terminate the employment of the Contractor. At that time the Owner may take possession of the premises and of all materials,

tools and appliances on the premises and finish the work by whatever method the Owner may deem expedient. Cause for such action by the Owner includes:

.1 the contractor is adjudged bankrupt, or makes a general assignment for the benefit of its creditors, or

.2 a receiver is appointed due to the Contractor's insolvency, or

.3 the Contractor persistently or repeatedly refuses or fails to provide enough properly skilled workers or proper materials, or

.4 the Contractor fails to make prompt payment to Subcontractors or suppliers of materials or labor, or

.5 the Contractor persistently disregards laws, ordinances or the instructions of the Consultant, or is otherwise found guilty of a substantial violation of a provision of the Contract Documents.

30.2 The Contractor is not entitled, as a consequence of the termination of the employment of the Contractor as described above, to receive any further payment until the Work is finished. If the unpaid balance of the contract amount exceeds the expense of finishing the Work, including compensation for additional architectural, managerial and administrative services, such balance shall be paid to the Contractor. If the expense of finishing the Work exceeds the unpaid balance, the Contractor shall pay the difference to the Owner. The Consultant shall certify the expense incurred by the Contractor's default. This obligation for payment shall continue to exist after termination of the contract.

30.3 The Contractor may, if the Work is stopped by order of any court or other public authority for a period of thirty consecutive days, and through no act or fault of the Contractor or of anyone employed by the Contractor, with seven days written notice to the Owner and the Consultant, terminate this contract. The Contractor may then recover from the Owner payment for all work executed, any proven loss and reasonable profit and damage.

30.4 The Contractor may, if the Consultant fails to issue a certificate for payment within seven days after the Contractor's formal request for payment, through no fault of the Contractor, or if the Owner fails to pay to the Contractor within 30 days after submission of any sum certified by the Consultant, with seven days written notice to the Owner and the Consultant, stop the Work or terminate this Contract.

31. Delays and Extension of Time

31.1 The completion date of the contract shall be extended if the work is delayed by changes ordered in the work which have approved time extensions, or by an act or neglect of the Owner, the Consultant, or the Owner's Contractor, or by strikes, lockouts, fire, flooding, unusual delay in transportation, unavoidable casualties, or by other causes beyond the Contractor's control. The Consultant shall determine the status of all claimed causes.

31.2 The contract shall not be extended for delay occurring more than seven calendar days before the Contractor's claim made in writing to the Consultant. In case of a continuing cause of delay, only one claim is necessary.

31.3 The contract shall not be extended due to failure of the Consultant to furnish drawings if no schedule or agreement is made between the Contractor and the Consultant indicating the dates

which drawings shall be furnished and fourteen calendar days has passed after said date for such drawings.

31.4 This article does not exclude the recovery of damages for delay by either party under other provisions in the Contract Document.

32. Payments to the Contractor

32.1 As noted under *Preconstruction Conference* in this section, the Contractor shall submit a Schedule of Values form, before the first application for payment, for approval by the Owner and Consultant. The Consultant may direct the Contractor to provide evidence that supports the correctness of the form. The approved Schedule of Values shall be used as a basis for payments.

32.2 The Contractor shall submit an application for each payment ("Requisition for Payment") on a form approved by the Owner and Consultant. The Consultant may require receipts or other documents showing the Contractor's payments for materials and labor, including payments to Subcontractors.

32.3 The Contractor shall submit Requisitions for Payment as the work progresses not more frequently than once each month, unless the Owner approves a more frequent interval due to unusual circumstances. The Requisition for Payment is based on the proportionate quantities of the various classes of work completed or incorporated in the Work, in agreement with the actual progress of the Work and the dollar value indicated in the Schedule of Values.

32.4 The Consultant shall verify and certify each Requisition for Payment which appears to be complete and correct prior to payment being made by the Owner. The Consultant may certify an appropriate amount for materials not incorporated in the Work which have been delivered and suitably stored at the site. The Contractor shall submit bills of sale, insurance certificates, or other such documents that will adequately protect the Owner's interests prior to payments being certified.

32.5 In the event any materials delivered but not yet incorporated in the Work have been included in a certified Requisition for Payment with payment made, and said materials thereafter are damaged, deteriorated or destroyed, or for any reason whatsoever become unsuitable or unavailable for use in the Work, the full amount previously allowed shall be deducted from subsequent payments unless the Contractor satisfactorily replaces said material.

32.6 The Contractor may request certification of an appropriate dollar amount for materials not incorporated in the Work which have been delivered and suitably stored away from the site. The Contractor shall submit bills of sale, insurance certificates, right-of-entry documents or other such documents that will adequately protect the Owner's interests. The Consultant shall determine if the Contractor's documentation for the materials is complete and specifically designated for the Project. The Owner may allow certification of such payments.

32.7 Subcontractors may request, and shall receive from the Consultant, copies of approved Requisitions for Payment showing the amounts certified in the Schedule of Values.

32.8 Certified Requisitions for Payment, payments made to the Contractor, or partial or entire occupancy of the project by the Owner shall not constitute an acceptance of any work that does

not conform to the Contract Documents. The making and acceptance of the final payment constitutes a waiver of all claims by the Owner, other than those arising from unsettled liens, from faulty work or materials appearing within one year from final payment or from requirements of the Drawings and Specifications, and of all claims by the Contractor, except those previously made and still unsettled.

33. Payments Withheld

33.1 The Owner shall retain five percent of each payment due the Contractor as part security for the fulfillment of the contract by the Contractor. The Owner may make payment of a portion of this "retainage" to the Contractor temporarily or permanently during the progress of the Work. The Owner may thereafter withhold further payments until the full amount of the five percent is reestablished. The Contractor may deposit with the Maine State Treasurer certain securities in place of retainage amounts due according to Maine Statute (5 M.R.S. §1746).

33.2 The Consultant may withhold or nullify the whole or a portion of any Requisitions for Payment submitted by the Contractor in the amount that may be necessary, in his reasonable opinion, to protect the Owner from loss due to any of the following:

.1 defective work not remedied;
.2 claims filed or reasonable evidence indicating probable filing of claims;
.3 failure to make payments properly to Subcontractors or suppliers;
.4 a reasonable doubt that the contract can be completed for the balance then unpaid;
.5 liability for damage to another contractor.

The Owner shall make payment to the Contractor, in the amount withheld, when the above circumstances are removed.

34. Liens

34.1 The Contractor shall deliver to the Owner a complete release of all liens arising out of this contract before the final payment or any part of the retainage payment is released. The Contractor shall provide with the release of liens an affidavit asserting each release includes all labor and materials for which a lien could be filed. Alternately, the Contractor, in the event any Subcontractor or supplier refuses to furnish a release of lien in full, may furnish a bond satisfactory to the Owner, to indemnify the Owner against any lien.

34.2 In the event any lien remains unsatisfied after all payments to the Contractor are made by the Owner, the Contractor shall refund to the Owner all money that the latter may be compelled to pay in discharging such lien, including all cost and reasonable attorney's fees.

35. Workmanship

35.1 The Contractor shall provide materials, equipment, and installed work equal to or better than the quality specified in the Contract Documents and approved in submittal and sample. The installation methods shall be of the highest standards, and the best obtainable from the respective trades. The Consultant's decision on the quality of work shall be final.

35.2 The Contractor shall know local labor conditions for skilled and unskilled labor in order to apply the labor appropriately to the Work. All labor shall be performed by individuals well skilled in their respective trades.

35.3 The Contractor shall perform all cutting, fitting, patching and placing of work in such a manner to allow subsequent work to fit properly, whether that be by the Contractor, the Owner's Contractors or others. The Owner and Consultant may advise the Contractor regarding such subsequent work. Notwithstanding the notification or knowledge of such subsequent work, the Contractor may be directed to comply with this standard of compatible construction by the Consultant at the Contractor's expense.

35.4 The Contractor shall request clarification or revision of any design work by the Consultant, prior to commencing that work, in a circumstance where the Contractor believes the work cannot feasibly be completed at the highest quality, or as indicated in the Contract Documents. The Consultant shall respond to such requests in a timely way, providing clarifying information, a feasible revision, or instruction allowing a reduced quality of work. The Contractor shall follow the direction of the Consultant regarding the required request for information.

35.5 The Contractor shall guarantee the Work against any defects in workmanship and materials for a period of one year commencing with the date of the Certificate of Substantial Completion, unless specified otherwise for specific elements of the project. The Work may also be subdivided in mutually agreed upon components, each defined by a separate Certificate of Substantial Completion.

36. Close-out of the Work

36.1 The Contractor shall remove from the premises all waste materials caused by the work. The Contractor shall make the spaces “broom clean” unless a more thorough cleaning is specified. The Contractor shall clean all windows and glass immediately prior to the final inspection, unless otherwise directed.

36.2 The Owner may conduct the cleaning of the premises where the Contractor, duly notified by the Consultant, fails to adequately complete the task. The expense of this cleaning may be deducted from the sum due to the Contractor.

36.3 The Contractor shall participate in all final inspections and acknowledge the documentation of unsatisfactory work, customarily called the "punch list", to be corrected by the Contractor. The Consultant shall document the successful completion of the Work in a dated Certificate of Substantial Completion, to be signed by Owner, Consultant, and Contractor.

36.4 The Contractor shall not call for final inspection of any portion of the Work that is not completely and permanently installed. The Contractor may be found liable for the expenses of individuals called to final inspection meetings prematurely.

36.5 The Contractor and all major Subcontractors shall participate in the end-of-warranty-period conference, typically scheduled close to one year after the Substantial Completion date.

37. Date of Completion and Liquidated Damages

37.1 The Contractor may make a written request to the Owner for an extension or reduction of time, if necessary. The request shall include the reasons the Contractor believes justifies the proposed completion date. The Owner may grant the revision of the contract completion date if the Work was delayed due to conditions beyond the control and the responsibility of the Contractor. The Contractor shall not conduct unauthorized accelerated work or file delay claims to recover alleged damages for unauthorized early completion.

37.2 The Contractor shall vigorously pursue the completion of the Work and notify the Owner of any factors that have, may, or will affect the approved Schedule of the Work. The Contractor may be found responsible for expenses of the Owner or Consultant if the Contractor fails to make notification of project delays.

37.3 The Project is planned to be done in an orderly fashion which allows for an iterative submittal review process, construction administration including minor changes in the Work and some bad weather. The Contractor shall not file delay claims to recover alleged damages on work the Consultant determines has followed the expected rate of progress.

37.4 The Consultant shall prepare the Certificate of Substantial Completion which, when signed by the Owner and the Contractor, documents the date of Substantial Completion of the Work or a designated portion of the Work. The Owner shall not consider the issuance of a Certificate of Occupancy by an outside authority a prerequisite for Substantial Completion if the Certificate of Occupancy cannot be obtained due to factors beyond the Contractor's control.

37.5 Liquidated Damages may be deducted from the sum due to the Contractor for each calendar day that the Work remains uncompleted after the completion date specified in the Contract or an approved amended completion date. The dollar amount per day shall be calculated using the Schedule of Liquidated Damages table shown below.

If the original contract amount is:	The per day Liquidated Damages shall be:
Less than $100,000	$250
$100,000 to less than $2,000,000	$750
$2,000,000 to less than $10,000,000	$1,500
$10,000,000 and greater	$1,500 plus $250 for each $2,000,000 over $10,000,000

38. Dispute Resolution

38.1 Mediation

38.1.1 A dispute between the parties which arises under this Contract which cannot be resolved through informal negotiation, shall be submitted to a neutral mediator jointly selected by the parties.

38.1.2 Either party may file suit before or during mediation if the party, in good faith, deems it to be necessary to avoid losing the right to sue due to a statute of limitations. If suit is filed before good faith mediation efforts are completed, the party filing suit shall agree to stay all proceedings in the lawsuit pending completion of the mediation process, provided such stay is without prejudice.

38.1.3 In any mediation between the Owner and the Consultant, the Owner has the right to consolidate related claims between Owner and Contractor.

38.2 Arbitration

38.2.1 If the dispute is not resolved through mediation, the dispute shall be settled by arbitration. The arbitration shall be conducted before a panel of three arbitrators. Each party shall select one arbitrator; the third arbitrator shall be appointed by the arbitrators selected by the parties. The arbitration shall be conducted in accordance with the Maine Uniform Arbitration Act (MUAA), except as otherwise provided in this section.

38.2.2 The decision of the arbitrators shall be final and binding upon all parties. The decision may be entered in court as provided in the MUAA.

38.2.3 The costs of the arbitration, including the arbitrators' fees shall be borne equally by the parties to the arbitration, unless the arbitrator orders otherwise.

38.2.4 In any arbitration between the Owner and the Consultant, the Owner has the right to consolidate related claims between Owner and Contractor.

00 73 46
Wage Determination Schedule

PART 1- GENERAL

1.1 Related Documents
A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specifications Sections, apply to this Section.

1.2 Summary
A. This Section includes the wage determination requirements for Contractors as issued by the State of Maine Department of Labor Bureau of Labor Standards or the United States Department of Labor.

1.3 Requirements
A. Conform to the wage determination schedule for this project which is shown on the following page.

PART 2 - PRODUCTS (not used)

PART 3 - EXECUTION (not used)

THIS DOCUMENT MUST BE CLEARLY POSTED AT ALL CONSTRUCTION SITES FUNDED IN PART WITH STATE FUNDS

State of Maine
Department of Labor
Bureau of Labor Standards
Augusta, Maine 04333-0045
Telephone (207) 623-7906

Wage Determination - In accordance with 26 MRS §1301 et. seq., this is a determination by the Bureau of Labor Standards, of the fair minimum wage rate to be paid to laborers and workers employed on the below titled project.

2026 Fair Minimum Wage Rates – Building 2 Kennebec County (other than 1 or 2 family homes)

Occupational Title	Minimum Wage	Minimum Benefit	Total
Brickmasons and Blockmasons	$43.91	$28.47	$72.38
Bulldozer Operator	$30.62	$5.38	$36.00
Carpenter	$27.87	$4.58	$32.45
Cement Masons and Concrete Finisher	$27.44	$0.87	$28.31
Construction and Maintenance Painters	$29.16	$3.32	$32.48
Construction Laborer	$25.32	$2.04	$27.36
Conveyor Operators and Tenders	$30.17	$13.77	$43.94
Crane and Tower Operators	$40.43	$8.63	$49.06
Crushing Grinding and Polishing Machine Operators	$26.15	$3.24	$29.39
Earth Drillers - Except Oil and Gas	$25.04	$3.77	$28.81
Electrical Power - Line Installer and Repairers	$48.12	$15.63	$63.75
Electricians	$36.22	$19.40	$55.62
Elevator Installers and Repairers	$67.34	$39.76	$107.10
Excavator Operator	$34.12	$6.49	$40.61
Fence Erectors	$30.90	$2.18	$33.08
Flaggers	$21.39	$0.86	$22.25
Floor Layers - Except Carpet/Wood/Hard Tiles	$29.00	$8.65	$37.65
Glaziers	$37.00	$6.60	$43.60
Hazardous Materials Removal Workers	$24.12	$1.60	$25.72
Heating and Air Conditioning and Refrigeration Mechanics and Installers	$34.53	$5.29	$39.82
Heavy and Tractor - Trailer Truck Drivers	$29.13	$3.98	$33.11
Highway Maintenance Workers	$23.30	$1.14	$24.44
Industrial Machinery Mechanics	$29.97	$6.74	$36.71
Industrial Truck and Tractor Operators	$24.61	$4.21	$28.82
Insulation Worker - Mechanical	$27.35	$6.05	$33.40
Light Truck or Delivery Services Drivers	$26.79	$5.14	$31.93
Loading Machine and Dragline Operators	$29.71	$4.79	$34.50
Millwrights	$35.99	$10.52	$46.51
Mobile Heavy Equipment Mechanics - Except Engines	$30.67	$5.10	$35.77
Operating Engineers and Other Equipment Operators	$39.74	$3.67	$43.41
Paving Surfacing and Tamping Equipment Operators	$30.74	$10.67	$41.41
Pile-Driver Operators	$37.15	$3.12	$40.27
Pipe/Steam/Sprinkler Fitter	$31.38	$8.02	$39.40
Pipelayers	$28.75	$3.64	$32.39
Plumbers	$31.30	$6.35	$37.65
Radio Cellular and Tower Equipment Installers	$34.72	$5.63	$40.35
Reinforcing Iron and Rebar Workers	$32.94	$25.00	$57.94
Riggers	$31.25	$7.68	$38.93
Roofers	$22.93	$4.35	$27.28
Sheet Metal Workers	$27.85	$6.44	$34.29
Structural Iron and Steel Workers	$28.22	$4.33	$32.55
Tapers	$29.16	$5.64	$34.80
Telecommunications Equipment Installers and Repairers - Except Line Installers	$43.59	$21.08	$64.67
Telecommunications Line Installers and Repairers	$28.49	$5.29	$33.78
Tile and Marble Setters	$28.91	$5.46	$34.37

Welders are classified as the trade to which welding is incidental (e.g. welding structural steel is Structural Iron and Steel Worker)

Apprentices – The minimum wage rates for registered apprentices are the rates recognized in the sponsorship agreement for registered apprentices working in the pertinent classification.

For any other specific trade on this project not listed above, contact the Bureau of Labor Standards for further clarification.

Title 26 §1310 requires that a clearly legible statement of all fair minimum wage and benefits rates to be paid the several classes of laborers, workers and mechanics employed on the construction on the public work must be kept posted in a prominent and easily accessible place at the site by each contractor and subcontractor subject to sections 1304 to 1313.

Appeal – Any person affected by the determination of these rates may appeal to the Commissioner of Labor by filing a written notice with the Commissioner stating the specific grounds of the objection within ten (10) days from the filing of these rates.

A true copy

Attest: Scott R. Cotnoir
Scott R. Cotnoir
Wage & Hour Director
Bureau of Labor Standards

Supersedes 02-03-2025
Effective 01-10-2026

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Project information.
2. Work covered by Contract Documents.
3. Contractor's use of site and premises.
4. Work restrictions.
5. Specification and Drawing conventions.
6. Miscellaneous provisions.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.
2. Section 017300 "Execution" for coordination of Owner-installed products.

1.2 DEFINITIONS

A. Work Package: A group of specifications, drawings, and schedules prepared by the design team to describe a portion of the Project Work for pricing, permitting, and construction.

1.3 PROJECT INFORMATION

A. Project Identification: 221 State Street, Building Renovations, Augusta, Maine.

1. Project Location: 221 State Street, Augusta, Maine 04330.

B. Owner: State of Maine, Bureau of General Services, 77 State House Station, Augusta, Maine 04333.

1. Owner's Representative: Brian Keezer, Bureau Director, (207) 624-7371.

C. Architect: Oak Point Associates, 231 Main Street, Biddeford, Maine 04005.

1. Architect's Representative: Jeffrey Luy, AIA, (207) 283-0193.

D. Web-Based Project Software: Project software will be used for purposes of managing communication and documents during the construction stage.

1. See Section 013100 "Project Management and Coordination" for requirements for using web-based Project software.

1.4 WORK COVERED BY CONTRACT DOCUMENTS

A. The Work of Project is defined by the Contract Documents and includes, but is not limited to, the following:

1. Renovation of the 221 State Street Building and attached elevator/stair connector, including roofing, windows, doors, envelope repairs, interior partitions, ceilings and finishes, mechanical, electrical, and fire protection systems and devices, site and parking lot improvements, structural upgrades, commissioning, and associated work indicated in the Contract Documents.

B. Type of Contract:

1. Project will be constructed under a single prime contract.

1.5 CONTRACTOR'S USE OF SITE AND PREMISES

A. Unrestricted Use of Site: Contractor shall have full use of Project site for construction operations during construction period. Contractor's use of Project site is limited only by Owner's right to perform work or to retain other contractors on portions of Project.

B. Limits on Use of Site: Limit use of Project site to Work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.

1. Limits on Use of Site: Confine construction operations to 221 State Street building and attached stair/elevator connector. Work does not include the adjacent attached unoccupied lab building.

C. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.

D. Condition of Existing Grounds: Maintain portions of existing grounds, landscaping, and hardscaping affected by construction operations throughout construction period. Repair damage caused by construction operations.

1.6 WORK RESTRICTIONS

A. Comply with restrictions on construction operations.

1. Comply with limitations on use of public streets, work on public streets, rights of way, and other requirements of authorities having jurisdiction.

B. On-Site Work Hours: Limit work to between 6:00 a.m. to 6:00 p.m., Monday through Friday, unless otherwise indicated. Work hours may be modified to meet Project requirements if approved by Owner and authorities having jurisdiction.

C. Existing Utility Interruptions: Do not interrupt utilities serving other facilities unless permitted under the following conditions and then only after arranging for temporary utility services according to requirements indicated:

1. Notify Owner not less than seven days in advance of proposed utility interruptions.
2. Obtain Owner's written permission before proceeding with utility interruptions.

D. Nonsmoking Building: Smoking is not permitted within the building or within **25 feet** of entrances, operable windows, or outdoor-air intakes.

E. Smoking and Controlled Substance Restrictions: Use of tobacco products, alcoholic beverages, and other controlled substances on Owner's property is not permitted.

F. Employee Identification: Provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.

G. Employee Screening: Comply with Owner's requirements for drug and background screening of Contractor personnel working on Project site.

1. Maintain list of approved screened personnel with Owner's representative.

1.7 SPECIFICATION AND DRAWING CONVENTIONS

A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:

1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.

B. Division 00 Contracting Requirements: General provisions of the Contract, including General and Supplementary Conditions, apply to all Sections of the Specifications.

C. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.

D. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:

1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
2. Abbreviations: Materials and products are identified by abbreviations scheduled on Drawings and published as part of the U.S. National CAD Standard.

PART 2 - PRODUCTS (Not Used)
s

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 012100 - ALLOWANCES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements governing allowances.

B. Types of allowances include the following:

1. Contingency allowances.

C. Related Requirements:

1. Section 012200 "Unit Prices" for procedures for using unit prices, including adjustment of quantity allowances when applicable.
2. Section 012600 "Contract Modification Procedures" for procedures for submitting and handling Change Orders.

1.2 DEFINITIONS

A. Allowance: A quantity of work or dollar amount included in the Contract, established in lieu of additional requirements, used to defer selection of actual materials and equipment to a later date when direction will be provided to Contractor. If necessary, additional requirements will be issued by Change Order.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Submit proposals for purchase of products or systems included in allowances in the form specified for Change Orders.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Submit invoices or delivery slips to show actual quantities of materials delivered to the site for use in fulfillment of each allowance.

C. Submit time sheets and other documentation to show labor time and cost for installation of allowance items that include installation as part of the allowance.

D. Coordinate and process submittals for allowance items in same manner as for other portions of the Work.

1.5 CONTINGENCY ALLOWANCES

A. Use the contingency allowance only as directed by Architect for Owner's purposes and only by Change Orders that indicate amounts to be charged to the allowance.

B. Contractor's overhead, profit, and related costs for products and equipment under the contingency allowance are included in the allowance and are not part of the Contract Sum. These costs include delivery, installation, taxes, insurance, equipment rental, and similar costs.

C. At Project closeout, credit unused amounts remaining in the contingency allowance to Owner by Change Order.

1.6 ADJUSTMENT OF ALLOWANCES

A. Allowance Adjustment: To adjust allowance amounts, prepare a Change Order proposal based on the difference between purchase amount and the allowance, multiplied by final measurement of work-in-place where applicable. If applicable, include reasonable allowances for cutting losses, tolerances, mixing wastes, normal product imperfections, required maintenance materials, and similar margins.

1. Include installation costs in purchase amount only where indicated as part of the allowance.
2. If requested, prepare explanation and documentation to substantiate distribution of overhead costs and other markups.
3. Submit substantiation of a change in scope of Work, if any, claimed in Change Orders related to unit-cost allowances.
4. Owner reserves the right to establish the quantity of work-in-place by independent quantity survey, measure, or count.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine products covered by an allowance promptly on delivery for damage or defects. Return damaged or defective products to manufacturer for replacement.

3.2 PREPARATION

A. Coordinate materials and their installation for each allowance with related materials and installations to ensure that each allowance item is completely integrated and interfaced with related work.

3.3 SCHEDULE OF ALLOWANCES

A. Allowance No. 1: Brick Repointing. Contingency Allowance: Include a contingency allowance of $65,000 for deteriorated mortar joint removal, as specified in Section 040120.64 “Brick Masonry Repointing" and details provided on sheet AE502. Note that this allowance is in addition to Base Bid area quantity required in "Unit Prices-Allowances Schedule" shown on sheet G-002.

1. Unit of Measurement: Square feet of brick with joints to be repointed
2. Coordinate allowance adjustment with unit price requirements in Section 012200 “Unit Prices.”

B. Allowance No. 2: Brick Repair. Contingency Allowance: Include a contingency allowance of $35,000 to remove cracked and spalled brick and provide toothed-in brick to match existing, as specified in Section 040120.63 “Brick Masonry Repair" and details provided on sheet AE502. Note that this allowance is in addition to Base Bid area quantity required in "Allowances-Unit Prices Schedule" shown on sheet G-002.

1. Unit of Measurement: Square feet of brick to be repaired.
2. Coordinate allowance adjustment with unit price requirements in Section 012200 “Unit Prices.”

C. Allowance No. 3: Concrete Foundation Wall Spall Repair. Contingency Allowance: Include a contingency allowance of $45,000 to repair spalls in exterior face of exposed concrete foundation walls, as specified in Section 030130 "Maintenance of Cast-In-Place Concrete" and details provided on sheet AE502. Note that this allowance is in addition to Base Bid area quantity required in "Allowances-Unit Prices Schedule" shown on sheet G-002.

1. Unit of Measurement: Square feet of concrete up to 3 inches in depth to be repaired.
2. Coordinate allowance adjustment with unit price requirements in Section 012200 “Unit Prices.”

D. Allowance No. 4: Additional Discovered ACM Pipe Insulation. Contingency Allowance: Include a contingency allowance of $85,000 for removal and disposal of additional discovered hazardous asbestos containing material pipe insulation. Note that this allowance is in addition to base bid requirements for hazardous materials removals and disposal shown on bid documents.

1. Unit of Measurement: Lineal feet of 3" diameter ACM pipe insulation to be removed.
2. Coordinate allowance adjustment with unit price requirements in Section 012200 "Unit Prices.”

E. Allowance No. 5: Additional Discovered Mechanical and Electrical Piping and Conduit Removals. Contingency Allowance: Include a contingency allowance of $125,000 for removal and disposal of additional discovered mechanical and electrical piping, conduit and wiring, including under slab piping. Note that this allowance is in addition to base bid requirements for mechanical and electrical removals and disposal shown on bid documents.

1. Unit of Measurement: Lineal feet.

F. Allowance No. 6: Hydraulic Elevator Plunger Assembly Hole. Contingency Allowance: Include a contingency allowance of $50,000 for drilling a new hole in existing elevator pit. Note that this allowance is in addition to base bid elevator modernization requirements as specified in section 142410 "Hydraulic-Elevator Modernization".

1. Unit of Measurement: Lump Sum.

G. Allowance No. 7: Hydraulic Elevator Plunger Assembly, Casing, and Casing Liner. Contingency Allowance: Include a contingency allowance of $90,000 for removal and provision of hydraulic plunger assembly, cylinder casing and PVC casing liner. Note that this allowance is in addition to base bid elevator modernization requirements as specified in section 142410 "Hydraulic-Elevator Modernization".

1. Unit of Measurement: Lump Sum.

END OF SECTION

SECTION 012200 - UNIT PRICES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for unit prices.

B. Related Requirements:

1. Section 012100 "Allowances" for procedures for using unit prices to adjust contingency allowances.
2. Section 012600 "Contract Modification Procedures" for procedures for submitting and handling Change Orders.

1.2 DEFINITIONS

A. Unit price is an amount incorporated into the Agreement, applicable during the duration of the Work as a price per unit of measurement for materials, equipment, or services, or a portion of the Work, added to or deducted from the Contract Sum by appropriate modification, if the scope of Work or estimated quantities of Work required by the Contract Documents are increased or decreased.

1.3 PROCEDURES

A. Unit prices include all necessary material, plus cost for delivery, installation, insurance, applicable taxes, overhead, and profit.

B. Measurement and Payment: See individual Specification Sections for work that requires establishment of unit prices. Methods of measurement and payment for unit prices are specified in those Sections.

C. Owner reserves the right to reject Contractor's measurement of work-in-place that involves use of established unit prices and to have this work measured, at Owner's expense, by an independent surveyor acceptable to Contractor.

D. List of Unit Prices: A schedule of unit prices is included in Part 3. Specification Sections referenced in the Part 3 "Schedule of Unit Prices" Article contain requirements for materials described under each unit price.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF UNIT PRICES

A. Unit Price No.1: Brick Repointing

1. Description: Removal and repointing of unsound or deteriorated exterior brick mortar joints in accordance with Section 04120.64 “Brick Masonry Repointing”
2. Unit of Measurement: Square Feet of brick masonry with joints to be repointed.
3. Contingency Allowance: Coordinate unit price with allowance adjustment requirements in Section 012100 “Allowances.”

B. Unit Price No.2: Brick Repair

1. Description: Removal and provision of matching brick at cracked, spalled, or deteriorated exterior brick and removal and patching of abandoned metal anchor holes in accordance with Section 04120.63 “Brick Masonry Repair” and drawing details.
2. Unit of Measurement: Square Feet of brick masonry to be removed and replaced with new.
3. Contingency Allowance: Coordinate unit price with allowance adjustment requirements in Section 012100 “Allowances.”

C. Unit Price No.3: Concrete Foundation Wall Spall Repair

1. Description: Repair of exposed exterior concrete foundation wall cracks in accordance with Section 030130 “Maintenance of Cast-In-Place Concrete” and drawing details.
2. Unit of Measurement: Square Feet of concrete cracks/spalls to be repaired.
3. Contingency Allowance: Coordinate unit price with allowance adjustment requirements in Section 012100 “Allowances.”

D. Unit Price No. 4: Additional Discovered Asbestos Containing Material Pipe Insulation

1. Description: Removal and disposal of additional discovered hazardous asbestos containing material pipe insulation. Note that this allowance is in addition to base bid requirements for hazardous materials removals and disposal shown on bid documents.
2. Unit of Measurement: Lineal feet of 3" diameter ACM pipe insulation to be removed.
3. Contingency Allowance: Coordinate unit price with allowance adjustment requirements in Section 012100 "Unit Allowances".

END OF SECTION

SECTION 012500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for substitutions.

B. Related Requirements:

1. Section 00 72 13 “General Conditions.”
2. Section 012100 "Allowances" for products selected under an allowance.
3. Section 012300 "Alternates" for products selected under an alternate.
4. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.2 DEFINITIONS

A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents.

1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required to meet other Project requirements but may offer advantage to Contractor or Owner.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Substitution Requests: Submit documentation identifying product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Substitution Request Form: Use form acceptable to Architect.
2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:

a. Statement indicating why specified product or fabrication or installation method cannot be provided, if applicable.
b. Coordination of information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.
c. Detailed comparison of significant qualities of proposed substitutions with those of

the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes, such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.

d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
e. Samples, where applicable or requested.
f. Certificates and qualification data, where applicable or requested.
g. List of similar installations for completed projects, with project names and addresses as well as names and addresses of architects and owners.
h. Material test reports from a qualified testing agency, indicating and interpreting test results for compliance with requirements indicated.
i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
j. Detailed comparison of Contractor's construction schedule using proposed substitutions with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
k. Cost information, including a proposal of change, if any, in the Contract Sum.
l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents, except as indicated in substitution request, is compatible with related materials and is appropriate for applications indicated.
m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.

3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.4 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.5 PROCEDURES

A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

1.6 SUBSTITUTIONS

A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.

1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:

a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
b. Substitution request is fully documented and properly submitted.
c. Requested substitution will not adversely affect Contractor's construction schedule.
d. Requested substitution has received necessary approvals of authorities having jurisdiction.
e. Requested substitution is compatible with other portions of the Work.
f. Requested substitution has been coordinated with other portions of the Work.
g. Requested substitution provides specified warranty.
h. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

B. Substitutions for Convenience:

1. Not allowed.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

B. Related Requirements:

1. Section 00 72 13 “General Conditions.”
2. Section 012500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.
3. Section 013100 "Project Management and Coordination" for requirements for forms for contract modifications provided as part of web-based Project management software.

1.2 MINOR CHANGES IN THE WORK

A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on Architect’s standard form.

1.3 PROPOSAL REQUESTS

A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.

1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
2. Within 10 business days after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.

    a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    c. Include costs of labor and supervision directly attributable to the change.
    d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
    e. Quotation Form: Use forms acceptable to Architect.

B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.

1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
7. Proposal Request Form: Use form acceptable to Architect.

1.4 ADMINISTRATIVE CHANGE ORDERS

A. Allowance Adjustment: See Section 012100 "Allowances" for administrative procedures for preparation of Change Order Proposal for adjusting the Contract Sum to reflect actual costs of allowances.

B. Unit-Price Adjustment: See Section 012200 "Unit Prices" for administrative procedures for preparation of Change Order Proposal for adjusting the Contract Sum to reflect measured scope of unit-price work.

1.5 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Change Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor.

1.6 CONSTRUCTION CHANGE DIRECTIVE

A. Construction Change Directive: Architect may issue a Construction Change Directive. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.

1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.

B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.

1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

B. Related Requirements:

1. Section 00 72 13 “General Conditions.”
2. Section 012100 "Allowances" for procedural requirements governing the handling and processing of allowances.
3. Section 012200 "Unit Prices" for administrative requirements governing the use of unit prices.
4. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
5. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.2 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.3 SCHEDULE OF VALUES

A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.

1. Coordinate line items in the schedule of values with items required to be indicated as separate activities in Contractor's construction schedule.
2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.

B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.

1. Identification: Include the following Project identification on the schedule of values:

a. Project name and location.
b. Owner's name.
c. Owner's Project number.
d. Name of Architect.
e. Architect's Project number.

f. Contractor's name and address.
g. Date of submittal.

2. Arrange schedule of values consistent with format of AIA Document G703.
3. Arrange the schedule of values in tabular form, with separate columns to indicate the following for each item listed:

a. Related Specification Section or division.
b. Description of the Work.
c. Name of subcontractor.
d. Name of manufacturer or fabricator.
e. Name of supplier.
f. Change Orders (numbers) that affect value.
g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent. Round dollar amounts to whole dollars, with total equal to Contract Sum.

1) Labor.
2) Materials.
3) Equipment.

4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
5. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.

a. Differentiate between items stored on-site and items stored off-site.

6. Allowances: Provide a separate line item in the schedule of values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.
7. Overhead Costs, Proportional Distribution: Include total cost and proportionate share of general overhead and profit for each line item.
8. Temporary Facilities: Show cost of temporary facilities and other major cost items that are not direct cost of actual work-in-place as separate line items.
9. Closeout Costs. Include separate line items under Contractor and principal subcontracts for Project closeout requirements in an amount totaling five percent of the Contract Sum and subcontract amount.
10. Schedule of Values Revisions: Revise the schedule of values when Change Orders or Construction Change Directives result in a change in the Contract Sum. Include at least one separate line item for each Change Order and Construction Change Directive.

1.4 APPLICATIONS FOR PAYMENT

A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments, as certified by Architect and paid for by Owner.

B. Payment Application Times: The date for each progress payment is indicated in the Owner/Contractor Agreement. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.

C. Payment Application Times: Submit Application for Payment to Architect at each monthly requisition meeting. The period covered by each Application for Payment is one month, ending on the last day of the month.

1. Submit draft copy of Application for Payment seven days prior to due date for review by Architect.

D. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.

1. Other Application for Payment forms proposed by the Contractor may be acceptable to Architect and Owner. Submit forms for approval with initial submittal of schedule of values.

E. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.

1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.

F. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.

1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment for stored materials.
2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
3. Provide summary documentation for stored materials indicating the following:

a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.

G. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt. One copy shall include waivers of lien and similar attachments if required.

1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.

H. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from subcontractors, sub-subcontractors, and suppliers for construction period covered by the previous application.

1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
2. When an application shows completion of an item, submit conditional final or full waivers.
3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
4. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
5. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.

I. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:

1. List of subcontractors.
2. Schedule of values.
3. Contractor's construction schedule (preliminary if not final).
4. Combined Contractor's construction schedule (preliminary if not final) incorporating Work of multiple contracts, with indication of acceptance of schedule by each Contractor.
5. Products list (preliminary if not final).
6. Sustainable design action plans, including preliminary project materials cost data.
7. Schedule of unit prices.
8. Submittal schedule (preliminary if not final).
9. List of Contractor's staff assignments.
10. List of Contractor's principal consultants.
11. Copies of building permits.
12. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
13. Initial progress report.
14. Report of preconstruction conference.
15. Certificates of insurance and insurance policies.
16. Performance and payment bonds.
17. Data needed to acquire Owner's insurance.

J. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.

1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.

a. Complete administrative actions, submittals, and Work preceding this application, as described in Section 017700 "Closeout Procedures."

2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.

K. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:

1. Evidence of completion of Project closeout requirements.
2. Certification of completion of final punch list items.
3. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
4. Updated final statement, accounting for final changes to the Contract Sum.
5. AIA Document G706.
6. AIA Document G706A.
7. AIA Document G707.
8. Evidence that claims have been settled.
9. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
10. Final liquidated damages settlement statement.
11. Proof that taxes, fees, and similar obligations are paid.
12. Waivers and releases.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative provisions for coordinating construction operations on Project, including, but not limited to, the following:

1. General coordination procedures.
2. Coordination drawings.
3. RFIs.
4. Digital project management procedures.
5. Web-based Project management software package.
6. Project meetings.

B. Related Requirements:

1. Section 013200 "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
2. Section 017300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
3. Section 017700 "Closeout Procedures" for coordinating closeout of the Contract.
4. Section 019113 "General Commissioning Requirements" for coordinating the Work.

1.2 DEFINITIONS

A. RFI: Request for Information. Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:

1. Name, address, telephone number, and email address of entity performing subcontract or supplying products.
2. Number and title of related Specification Section(s) covered by subcontract.
3. Drawing number and detail references, as appropriate, covered by subcontract.

C. Key Personnel Names: Within 15 days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses, cellular telephone numbers, and e-mail addresses. Provide names, addresses, and telephone numbers of individuals assigned as alternates in the absence of individuals assigned to Project.

1. Post copies of list in Project meeting room, in temporary field office, in web-based Project software directory, and in prominent location in built facility. Keep list current at all times.

1.4 GENERAL COORDINATION PROCEDURES

A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations included in different Sections that depend on each other for proper installation, connection, and operation.

1. Schedule construction operations in sequence required to obtain the best results, where installation of one part of the Work depends on installation of other components, before or after its own installation.
2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
3. Make adequate provisions to accommodate items scheduled for later installation.

B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.

1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.

C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:

1. Preparation of Contractor's construction schedule.
2. Preparation of the schedule of values.
3. Installation and removal of temporary facilities and controls.
4. Delivery and processing of submittals.
5. Progress meetings.
6. Preinstallation conferences.
7. Project closeout activities.
8. Startup and adjustment of systems.

1.5 COORDINATION DRAWINGS

A. Coordination Drawings, General: Prepare coordination drawings for all areas of the project according to requirements in this Section and individual sections. Coordination is required to facilitate integration of products and materials fabricated or installed by more than one entity and with the existing structure.

1. Content: Project-specific information, drawn accurately to a scale large enough to indicate and resolve conflicts. Do not base coordination drawings on standard printed data. Include the following information, as applicable:

a. Use applicable Drawings as a basis for preparation of coordination drawings. Prepare sections, elevations, and details as needed to describe relationship of various systems and components.

b. Coordinate the addition of trade-specific information to coordination drawings in a sequence that best provides for coordination of the information and resolution of conflicts between installed components before submitting for review.
c. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, plumbing, fire protection, kitchen, and electrical systems.
d. Indicate space requirements for routine maintenance and for anticipated replacement of components during the life of the installation.
e. Show location and size of access doors required for access to concealed dampers, valves, and other controls.
f. Indicate required installation sequences.
g. Indicate dimensions shown on Drawings. Specifically note dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternative sketches to Architect indicating proposed resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.

B. Coordination Drawing Organization: Organize coordination drawings as follows:

1. Floor Plans and Reflected Ceiling Plans: Show architectural and structural elements, and mechanical, plumbing, fire-protection, fire-alarm, kitchen, and electrical Work. Show locations of visible ceiling-mounted devices relative to acoustical ceiling grid. Supplement plan drawings with section drawings where required to adequately represent the Work.
2. Plenum Space: Indicate subframing for support of ceiling and wall systems, mechanical and electrical equipment, and related Work. Locate components within plenums to accommodate layout of light fixtures and other components indicated on Drawings. Indicate areas of conflict between light fixtures and other components. Indicate elevations of all components.
3. Mechanical Rooms: Provide coordination drawings for mechanical rooms showing plans and elevations of mechanical, plumbing, fire-protection, fire-alarm, and electrical equipment.
4. Structural Penetrations: Indicate penetrations and openings required for all disciplines.
5. Slab Edge and Embedded Items: Indicate slab edge locations and sizes and locations of embedded items for metal fabrications, sleeves, anchor bolts, bearing plates, angles, door floor closers, slab depressions for floor finishes, curbs and housekeeping pads, and similar items.
6. Mechanical and Plumbing Work: Show the following:

    a. Sizes and bottom elevations of ductwork, piping, and conduit runs, including insulation, bracing, flanges, and support systems.
    b. Dimensions of major components, such as dampers, valves, diffusers, access doors, cleanouts, air handlers, terminal units, boiler plant equipment, control panels, and electrical distribution equipment.
    c. Fire-rated enclosures around ductwork, where required.

7. Electrical Work: Show the following:

    a. Runs of vertical and horizontal conduit 1-1/4 inches in diameter and larger.
    b. Light fixture, exit light, emergency battery pack, smoke detector, and other fire-alarm locations, including dimensions.

c. Panel board, switch board, switchgear, transformer, busway, generator, and motor-control center locations, including dimensions.
d. Location and dimensions of pull boxes and junction boxes, dimensioned from column center lines.

8. Fire-Protection System: Show the following:

a. Locations and dimensions of standpipes, mains piping, branch lines, pipe drops, and sprinkler heads.

9. Review: Architect will review coordination drawings to confirm that in general the Work is being coordinated, but not for the details of the coordination, which are Contractor's responsibility. If Architect determines that coordination drawings are not being prepared in sufficient scope or detail, or are otherwise deficient, Architect will so inform Contractor, who shall make suitable modifications and resubmit.

C. Coordination Digital Data Files: Prepare coordination digital data files according to the following requirements:

1. File Preparation Format: Same digital data software program, version, and operating system as original Drawings.
2. File Submittal Format: Submit or post coordination drawing files using format same as file preparation format and PDF format.

1.6 REQUEST FOR INFORMATION (RFI)

A. General: Immediately on discovery of the need for additional information, clarification, or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.

1. Architect will return without response those RFIs submitted to Architect by other entities controlled by Contractor.
2. Coordinate and submit RFIs in a prompt manner to avoid delays in Contractor's work or work of subcontractors.

B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:

1. Project name.
2. Owner name.
3. Owner's Project number.
4. Name of Architect.
5. Architect's Project number.
6. Date.
7. Name of Contractor.
8. RFI number, numbered sequentially.
9. RFI subject.
10. Specification Section number and title and related paragraphs, as appropriate.
11. Drawing number and detail references, as appropriate.
12. Field dimensions and conditions, as appropriate.

13. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
14. Contractor's signature.
15. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.

    a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.

C. RFI Forms: Software-generated form with substantially the same content as indicated above, acceptable to Architect.

1. Attachments shall be electronic files in PDF format.

D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.

1. The following Contractor-generated RFIs will be returned without action:

    a. Requests for approval of submittals.
    b. Requests for approval of substitutions.
    c. Requests for approval of Contractor's means and methods.
    d. Requests for coordination information already indicated in the Contract Documents.
    e. Requests for adjustments in the Contract Time or the Contract Sum.
    f. Requests for interpretation of Architect's actions on submittals.
    g. Incomplete RFIs or inaccurately prepared RFIs.

2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt by Architect of additional information.
3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."

    a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 5 days of receipt of the RFI response.

E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Use software log that is part of web-based Project management software. Include the following:

1. Project name.
2. Name and address of Contractor.
3. Name and address of Architect.
4. RFI number, including RFIs that were returned without action or withdrawn.
5. RFI description.
6. Date the RFI was submitted.
7. Date Architect's response was received.

8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.

F. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within three days if Contractor disagrees with response.

1.7 DIGITAL PROJECT MANAGEMENT PROCEDURES

A. Use of Architect's Digital Data Files: Digital data files of Architect's CAD drawings will be provided by Architect for Contractor's use during construction.

1. Digital data files may be used by Contractor in preparing coordination drawings, Shop Drawings, and Project Record Drawings.
2. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to Contract Drawings.
3. Digital Drawing Software Program: Contract Drawings are available in AutoCAD 2022.
4. Contractor shall execute a data licensing agreement in the form of Agreement form acceptable to Owner and Architect.

    a. Subcontractors and other parties granted access by Contractor to Architect's digital data files shall execute a data licensing agreement in the form of Agreement acceptable to Owner and Architect.

5. The following digital data files will be furnished for each appropriate discipline:

    a. Floor plans.
    b. Reflected ceiling plans.

B. Web-Based Project Management Software Package: Provide, administer, and use web-based Project management software package for purposes of hosting and managing Project communication and documentation until Final Completion.

1. Web-based Project management software includes, at a minimum, the following features:

    a. Compilation of Project data, including Contractor, subcontractors, Architect, Architect's consultants, Owner, and other entities involved in Project. Include names of individuals and contact information.
    b. Access control for each entity for each workflow process, to determine entity's digital rights to create, modify, view, and print documents.

    c. Document workflow planning, allowing customization of workflow between project entities.
    d. Creation, logging, tracking, and notification for Project communications required in other Specification Sections, including, but not limited to, RFIs, submittals, Minor Changes in the Work, Construction Change Directives, and Change Orders.
    e. Track status of each Project communication in real time, and log time and date when responses are provided.
    f. Procedures for handling PDFs or similar file formats, allowing markups by each entity. Provide security features to lock markups against changes once submitted.
    g. Processing and tracking of payment applications.

h. Processing and tracking of contract modifications.
i. Creating and distributing meeting minutes.
j. Document management for Drawings, Specifications, and coordination drawings, including revision control.
k. Management of construction progress photographs.
l. Mobile device compatibility, including smartphones and tablets.

2. Provide up to seven Project management software user licenses for use of Owner, Architect, and Architect's consultants.
3. At completion of Project, provide digital archive in format that is readable by common desktop software applications in format acceptable to Architect. Provide data in locked format to prevent further changes.
4. Basis-of-Design Product: Subject to compliance with requirements, provide ProCore Technologies, Inc. or comparable product by one of the following:

C. PDF Document Preparation: Where PDFs are required to be submitted to Architect, prepare as follows:

1. Assemble complete submittal package into a single indexed file, incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
2. Name file with submittal number or other unique identifier, including revision identifier.
3. Certifications: Where digitally submitted certificates and certifications are required, provide a digital signature with digital certificate on where indicated.

1.8 PROJECT MEETINGS

A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.

1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times a minimum of seven days prior to meeting.
2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days of the meeting.

B. Preconstruction Conference: Schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.

1. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
2. Agenda: Discuss items of significance that could affect progress, including the following:

a. Responsibilities and personnel assignments.
b. Tentative construction schedule.
c. Phasing.

d. Critical work sequencing and long lead items.
e. Designation of key personnel and their duties.
f. Lines of communications.
g. Use of web-based Project software.
h. Procedures for processing field decisions and Change Orders.
i. Procedures for RFIs.
j. Procedures for testing and inspecting.
k. Procedures for processing Applications for Payment.
l. Distribution of the Contract Documents.
m. Submittal procedures.
n. Preparation of Record Documents.
o. Use of the premises and existing building.
p. Work restrictions.
q. Working hours.
r. Owner's occupancy requirements.
s. Responsibility for temporary facilities and controls.
t. Procedures for moisture and mold control.
u. Procedures for disruptions and shutdowns.
v. Construction waste management and recycling.
w. Parking availability.
x. Office, work, and storage areas.
y. Equipment deliveries and priorities.
z. First aid.
aa. Security.
bb. Progress cleaning.

3. Minutes: Contractor will record and distribute meeting minutes.

C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity when required by other Sections and when required for coordination with other construction.

1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:

a. Contract Documents.
b. Options.
c. Related RFIs.
d. Related Change Orders.
e. Purchases.
f. Deliveries.
g. Submittals.
h. Review of mockups.
i. Possible conflicts.
j. Compatibility requirements.
k. Time schedules.
l. Weather limitations.

m. Manufacturer's written instructions.
n. Warranty requirements.
o. Compatibility of materials.
p. Acceptability of substrates.
q. Temporary facilities and controls.
r. Space and access limitations.
s. Regulations of authorities having jurisdiction.
t. Testing and inspecting requirements.
u. Installation procedures.
v. Coordination with other work.
w. Required performance results.
x. Protection of adjacent work.
y. Protection of construction and personnel.

3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.

D. Project Closeout Conference: Schedule and conduct a project closeout conference, at a time convenient to Owner and Architect, but no later than 30 days prior to the scheduled date of Substantial Completion.

1. Conduct the conference to review requirements and responsibilities related to Project closeout.
2. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the meeting. Participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
3. Agenda: Discuss items of significance that could affect or delay Project closeout, including the following:

a. Preparation of Record Documents.
b. Procedures required prior to inspection for Substantial Completion and for final inspection for acceptance.
c. Procedures for completing and archiving web-based Project software site data files.
d. Submittal of written warranties.
e. Requirements for preparing operations and maintenance data.
f. Requirements for delivery of material samples, attic stock, and spare parts.
g. Requirements for demonstration and training.
h. Preparation of Contractor's punch list.
i. Procedures for processing Applications for Payment at Substantial Completion and for final payment.
j. Submittal procedures.
k. Owner's partial occupancy requirements.
l. Installation of Owner's furniture, fixtures, and equipment.
m. Responsibility for removing temporary facilities and controls.

4. Minutes: Contractor will record and distribute meeting minutes.

E. Progress Meetings: Conduct progress meetings at biweekly intervals.

1. Coordinate dates of meetings with preparation of payment requests.
2. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.

    a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.

        1) Review schedule for next period.

    b. Review present and future needs of each entity present, including the following:

        1) Interface requirements.
        2) Sequence of operations.
        3) Status of submittals.
        4) Deliveries.
        5) Off-site fabrication.
        6) Access.
        7) Site use.
        8) Temporary facilities and controls.
        9) Progress cleaning.
        10) Quality and work standards.
        11) Status of correction of deficient items.
        12) Field observations.
        13) Status of RFIs.
        14) Status of Proposal Requests.
        15) Pending changes.
        16) Status of Change Orders.
        17) Pending claims and disputes.
        18) Documentation of information for payment requests.

4. Minutes: Contractor will record and distribute the meeting minutes to each party present and to parties requiring information.

    a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting, where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

F. Coordination Meetings: Conduct Project coordination meetings at regular intervals. Project coordination meetings are in addition to specific meetings held for other purposes, such as progress meetings and preinstallation conferences.

1. Attendees: Each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meetings shall be familiar with Project and authorized to conclude matters relating to the Work.
2. Agenda: Review and correct or approve minutes of the previous coordination meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.

    a. Combined Contractor's Construction Schedule: Review progress since the last coordination meeting. Determine whether each contract is on time, ahead of schedule, or behind schedule, in relation to combined Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
    b. Schedule Updating: Revise combined Contractor's construction schedule after each coordination meeting, where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with report of each meeting.
    c. Review present and future needs of each contractor present, including the following:

        1) Interface requirements.
        2) Sequence of operations.
        3) Status of submittals.
        4) Deliveries.
        5) Off-site fabrication.
        6) Access.
        7) Site use.
        8) Temporary facilities and controls.
        9) Work hours.
        10) Hazards and risks.
        11) Progress cleaning.
        12) Quality and work standards.
        13) Status of RFIs.
        14) Proposal Requests.
        15) Change Orders.
        16) Pending changes.

3. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:

1. Startup construction schedule.
2. Contractor's Construction Schedule.
3. Construction schedule updating reports.
4. Site condition reports.
5. Unusual event reports.

B. Related Requirements:

1. Section 012900 "Payment Procedures" for schedule of values and requirements for Applications for Payment.
2. Section 014000 "Quality Requirements" for schedule of tests and inspections.

1.2 DEFINITIONS

A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction Project. Activities included in a construction schedule consume time and resources.

1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
2. Predecessor Activity: An activity that precedes another activity in the network.
3. Successor Activity: An activity that follows another activity in the network.

B. Cost Loading: The allocation of the schedule of values for completing an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum.

C. Event: The starting or ending point of an activity.

D. Resource Loading: The allocation of labor and equipment necessary for completing an activity as scheduled.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Format for Submittals: Submit required submittals in the following format:

1. Working electronic copy of schedule file.
2. PDF file.

C. Startup construction schedule.

D. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.

E. Construction Schedule Updating Reports: Submit with Applications for Payment.

F. Site Condition Reports: Submit at time of discovery of differing conditions.

G. Unusual Event Reports: Submit at time of unusual event.

H. Qualification Data: For scheduling consultant.

1.4 COORDINATION

A. Coordinate Contractor's Construction Schedule with the schedule of values, list of subcontracts, submittal schedule, progress reports, payment requests, and other required schedules and reports.

1. Secure time commitments for performing critical elements of the Work from entities involved.
2. Coordinate each construction activity in the network with other activities, and schedule them in proper sequence.

1.5 CONTRACTOR'S CONSTRUCTION SCHEDULE

A. Computer Scheduling Software: Prepare schedules using current version of a program that is capable of managing construction schedules.

B. Time Frame: Extend schedule from date established for commencement of the Work to date of Final Completion.

1. Contract completion date to not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.

C. Activities: Treat each floor or separate area as a separate numbered activity for each main element of the Work. Comply with the following:

1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
2. Procurement Activities: Include procurement process activities for the following long lead-time items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with submittal schedule.

4. Commissioning Time: Include no fewer than 15 days for commissioning.
5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
6. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and Final Completion.

D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.

1. Work Restrictions: Show the effect of the following items on the schedule:

   a. Coordination with existing construction.
   b. Uninterruptible services.
   c. Seasonal variations.
   d. Environmental control.

2. Construction Areas: Identify each major area of construction for each major portion of the Work. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities to provide for the following:

   a. Structural completion.
   b. Temporary enclosure and space conditioning.
   c. Permanent space enclosure.
   d. Completion of mechanical installation.
   e. Completion of electrical installation.
   f. Substantial Completion.

E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and Final Completion.

F. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:

1. Unresolved issues.
2. Unanswered Requests for Information.
3. Rejected or unreturned submittals.
4. Notations on returned submittals.
5. Pending modifications affecting the Work and the Contract Time.

G. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.

1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
3. As the Work progresses, indicate Final Completion percentage for each activity.

H. Distribution: Distribute copies of approved schedule to Architect, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.

1. Post copies in Project meeting rooms and temporary field offices.
2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

1.6 REPORTS

A. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

B. Unusual Event Reports: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, responses by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.

1. Submit unusual event reports directly to Owner within one day of an occurrence. Distribute copies of report to parties affected by the occurrence.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 013233 - PHOTOGRAPHIC DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for the following:

1. Preconstruction photographs.
2. Concealed Work photographs.
3. Periodic construction photographs.
4. Final Completion construction photographs.

B. Related Requirements:

1. Section 017700 "Closeout Procedures" for submitting photographic documentation as Project Record Documents at Project closeout.
2. Section 017900 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.
3. Section 024119 "Selective Demolition" for photographic documentation before selective demolition operations commence.

1.2 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Key Plan: Submit key plan of Project site and building with notation of vantage points marked for location and direction of each photograph. Indicate elevation or story of construction. Include same information as corresponding photographic documentation.

C. Digital Photographs: Submit image files within three days of taking photographs.

1. Submit photos by uploading to web-based Project management software site. Include copy of key plan indicating each photograph's location and direction.
2. Identification: Provide the following information with each image description in web-based Project management software site:

a. Name of Project.
b. Name and contact information for photographer.
c. Name of Architect.
d. Name of Contractor.
e. Date photograph was taken.
f. Description of location, vantage point, and direction.
g. Unique sequential identifier keyed to accompanying key plan.

1.3 FORMATS AND MEDIA

A. Digital Photographs: Provide color images in JPG format, produced by a digital camera with minimum sensor size of 12 megapixels, and at an image resolution of not less than 3200 by 2400 pixels. Use flash in low light levels or backlit conditions.

B. Digital Images: Submit digital media as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.

C. Metadata: Record accurate date and time from camera.

D. File Names: Name media files with date and Project area and sequential numbering suffix.

1.4 CONSTRUCTION PHOTOGRAPHS

A. Photographer: Engage a qualified photographer to take construction photographs.

B. General: Take photographs with maximum depth of field and in focus.

1. Maintain key plan with each set of construction photographs that identifies each photographic location.

C. Preconstruction Photographs: Before commencement of the Work, take photographs of Project site and surrounding properties, including existing items to remain during construction, from different vantage points, as directed by Architect.

1. Flag construction limits before taking construction photographs.
2. Take 50 photographs to show existing conditions adjacent to property before starting the Work.
3. Take 50 photographs of existing buildings either on or adjoining property, to accurately record physical conditions at start of construction.
4. Take additional photographs as required to record settlement or cracking of adjacent structures, pavements, and improvements.

D. Concealed Work Photographs: Before proceeding with installing work that will conceal other work, take photographs sufficient in number, with annotated descriptions, to record nature and location of concealed Work, including, but not limited to, the following:

1. Underground utilities.
2. Underslab services.
3. Piping.
4. Electrical conduit.
5. Waterproofing and weather-resistant barriers.

E. Periodic Construction Photographs: Take 20 photographs weekly. Select vantage points to show status of construction and progress since last photographs were taken.

F. Final Completion Construction Photographs: Take 100 photographs after date of Substantial Completion for submission as Project Record Documents. Architect will inform photographer of desired vantage points.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Submittal schedule requirements.
2. Administrative and procedural requirements for submittals.

B. Related Requirements:

1. Section 00 72 13 “General Conditions.”
2. Section 012900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.
3. Section 013100 "Project Management and Coordination" for submitting coordination drawings and subcontract list and for requirements for web-based Project software.
4. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
5. Section 013233 "Photographic Documentation" for submitting preconstruction photographs, periodic construction photographs, and Final Completion construction photographs.
6. Section 014000 "Quality Requirements" for submitting test and inspection reports, and schedule of tests and inspections.
7. Section 017700 "Closeout Procedures" for submitting closeout submittals and maintenance material submittals.
8. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
9. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
10. Section 017900 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.

1.2 DEFINITIONS

A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."

B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."

1.3 SUBMITTAL SCHEDULE

A. Submittal Schedule: Submit, as an action submittal, a list of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
2. Final Submittal Schedule: Submit concurrently with the first complete submittal of Contractor's construction schedule.

    a. Submit revised submittal schedule as required to reflect changes in current status and timing for submittals.

3. Format: Arrange the following information in a tabular format:

    a. Scheduled date for first submittal.
    b. Specification Section number and title.
    c. Submittal Category: Action; informational.
    d. Name of subcontractor.
    e. Description of the Work covered.
    f. Scheduled date for Architect's final release or approval.

1.4 SUBMITTAL FORMATS

A. Submittal Information: Include the following information in each submittal:

1. Project name.
2. Date.
3. Name of Architect.
4. Name of Contractor.
5. Name of firm or entity that prepared submittal.
6. Names of subcontractor, manufacturer, and supplier.
7. Unique submittal number, including revision identifier. Include Specification Section number with sequential alphanumeric identifier and alphanumeric suffix for resubmittals.
8. Category and type of submittal.
9. Submittal purpose and description.
10. Number and title of Specification Section, with paragraph number and generic name for each of multiple items.
11. Drawing number and detail references, as appropriate.
12. Indication of full or partial submittal.
13. Location(s) where product is to be installed, as appropriate.
14. Other necessary identification.
15. Remarks.
16. Signature of transmitter.

B. Options: Identify options requiring selection by Architect.

C. Deviations and Additional Information: On each submittal, clearly indicate deviations from requirements in the Contract Documents, including minor variations and limitations; include relevant additional information and revisions, other than those requested by Architect on previous submittals. Indicate by highlighting on each submittal or noting on attached separate sheet.

D. Electronic Submittals: Prepare submittals as PDF package, incorporating complete information into each PDF file. Name PDF file with submittal number.

E. Submittals Utilizing Web-Based Project Software: Prepare submittals as PDF files or other format indicated by Project management software.

1.5 SUBMITTAL PROCEDURES

A. Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.

1. Email: Prepare submittals as PDF package and transmit to Architect by sending via email. Include PDF transmittal form. Include information in email subject line as requested by Architect.

    a. Architect will return annotated file. Annotate and retain one copy of file as a digital Project Record Document file.

2. Web-Based Project Management Software: Prepare submittals in PDF form, and upload to web-based Project management software website. Enter required data in web-based software site to fully identify submittal.

B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.

1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
4. Coordinate transmittal of submittals for related parts of the Work specified in different Sections, so processing will not be delayed because of need to review submittals concurrently for coordination.

    a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.

C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.

1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
3. Resubmittal Review: Allow 15 days for review of each resubmittal.
4. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 21 days for initial review of each submittal.

D. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.

1. Note date and content of previous submittal.
2. Note date and content of revision in label or title block, and clearly indicate extent of revision.
3. Resubmit submittals until they are marked with Reviewed notation from Architect's action stamp.

E. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.

F. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with Reviewed notation from Architect's action stamp.

1.6 SUBMITTAL REQUIREMENTS

A. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.

1. If information must be specially prepared for submittal because standard published data are unsuitable for use, submit as Shop Drawings, not as Product Data.
2. Mark each copy of each submittal to show which products and options are applicable.
3. Include the following information, as applicable:

    a. Manufacturer's catalog cuts.
    b. Manufacturer's product specifications.
    c. Standard color charts.
    d. Statement of compliance with specified referenced standards.
    e. Testing by recognized testing agency.
    f. Application of testing agency labels and seals.
    g. Notation of coordination requirements.
    h. Availability and delivery time information.

4. For equipment, include the following in addition to the above, as applicable:

    a. Wiring diagrams that show factory-installed wiring.
    b. Printed performance curves.
    c. Operational range diagrams.
    d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.

5. Submit Product Data before Shop Drawings, and before or concurrently with Samples.

B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data unless submittal based on Architect's digital data drawing files is otherwise permitted.

1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:

a. Identification of products.
b. Schedules.
c. Compliance with specified standards.
d. Notation of coordination requirements.
e. Notation of dimensions established by field measurement.
f. Relationship and attachment to adjoining construction clearly indicated.
g. Seal and signature of professional engineer if specified.

C. Samples: Submit Samples for review of type, color, pattern, and texture for a check of these characteristics with other materials.

1. Transmit Samples that contain multiple, related components, such as accessories together in one submittal package.
2. Identification: Permanently attach label on unexposed side of Samples that includes the following:

a. Project name and submittal number.
b. Generic description of Sample.
c. Product name and name of manufacturer.
d. Sample source.
e. Number and title of applicable Specification Section.
f. Specification paragraph number and generic name of each item.

3. Email Transmittal: Provide PDF transmittal. Include digital image file illustrating Sample characteristics and identification information for record.
4. Web-Based Project Management Software: Prepare submittals in PDF form, and upload to web-based Project software website. Enter required data in web-based software site to fully identify submittal.
5. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.

a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.

6. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units, showing the full range of colors, textures, and patterns available.

a. Number of Samples: Submit one full set of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.

D. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:

1. Type of product. Include unique identifier for each product indicated in the Contract Documents or assigned by Contractor if none is indicated.
2. Manufacturer and product name, and model number if applicable.
3. Number and name of room or space.
4. Location within room or space.

E. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.

F. Design Data: Prepare and submit written and graphic information indicating compliance with indicated performance and design criteria in individual Specification Sections. Include list of assumptions and summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Number each page of submittal.

G. Certificates:

1. Certificates and Certifications Submittals: Submit a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity. Provide a notarized signature where indicated.
2. Installer Certificates: Submit written statements on manufacturer's letterhead, certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
3. Manufacturer Certificates: Submit written statements on manufacturer's letterhead, certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
4. Material Certificates: Submit written statements on manufacturer's letterhead, certifying that material complies with requirements in the Contract Documents.
5. Product Certificates: Submit written statements on manufacturer's letterhead, certifying that product complies with requirements in the Contract Documents.
6. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of AWS B2.1/B2.1M on AWS forms. Include names of firms and personnel certified.

H. Test and Research Reports:

1. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for substrate preparation and primers required.
2. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.

3. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
4. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
5. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
6. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:

    a. Name of evaluation organization.
    b. Date of evaluation.
    c. Time period when report is in effect.
    d. Product and manufacturers' names.
    e. Description of product.
    f. Test procedures and results.
    g. Limitations of use.

1.7 DELEGATED DESIGN SERVICES

A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

    1. If criteria indicated are insufficient to perform services or certification required, submit a written request for additional information to Architect.

B. Delegated Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF file and three paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.

    1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

1.8 CONTRACTOR'S REVIEW

A. Action Submittals and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.

B. Contractor's Approval: Indicate Contractor's approval for each submittal with a uniform approval stamp. Include name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

1. Architect will not review submittals received from Contractor that do not have Contractor's review and approval.

1.9 ARCHITECT'S REVIEW

A. Action Submittals: Architect will review each submittal, indicate corrections or revisions required, and return.

1. PDF Submittals: Architect will indicate, via markup on each submittal, the appropriate action.
2. Submittals by Web-Based Project Management Software: Architect will indicate, on Project management software website, the appropriate action.

B. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.

C. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.

D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.

E. Architect will return without review submittals received from sources other than Contractor.

F. Submittals not required by the Contract Documents will be returned by Architect without action.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services

PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	012100	**ALLOWANCES**																
		Proposal for Purchase of Products/Systems																
		Invoices/Delivery Slips																
		Time Sheets & Other Documentation																
		Allowance Items																
	012500	**SUBSTITUTION PROCEDURES**																
		Substitution Requests																
	013100	**PROJECT MANAGEMENT AND COORDINATION**																
		Subcontract List																
		Key Personnel Names																
	013200	**CONSTRUCTION PROGRESS DOCUMENTATION**																
		Startup Construction Schedule																
		Contractor's Construction Schedule																
		Construction Scheduling Updating Reports																
		Site Condition Reports																
		Unusual Event Reports																
		Qualification Data																
	013233	**PHOTOGRAPHIC DOCUMENTATION**																
		Key Plan																
		Digital Photographs																
	013300	**SUBMITTAL PROCEDURES**																
		Product Data																
		Shop Drawings																
		Samples for Initial Selection																
		Qualification Statements																
		Welding Certificates																
		Material Test Reports																
		Product Test Reports																
		Preconstruction Test Reports																
		Compatibility Test Reports																
		Design Data																
		Field Test Reports																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Installer Certificates																
		Manufacturer Certificates																
		Wiring diagrams																
	013516	**ALTERATION PROJECT PROCEDURES**																
		Preconstruction Documentation																
		Fire-Prevention Plan																
	014000	**QUALITY REQUIREMENTS**																
		Contractor Quality-Control Plan																
		Qualification Data																
		Contractor's Statement of Responsibility																
		Testing Agency Qualifications																
		Schedule of Tests and Inspections																
		Reports																
		Permits, Licenses, and Certificates																
	014339	**MOCKUPS**																
		Shop Drawings																
	014535	**SPECIAL INSPECTIONS**																
		Preconstruction Submittals																
		Test Reports																
		Certificates																
	015000	**TEMPORARY FACILITIES AND CONTROLS**																
		Site Utilization Plan																
		Implementation and Termination Schedule																
		Project Identification and Temporary Signs																
		Erosion- and Sedimentation-Control Plan																
		Fire-Safety Program																
		Moisture- and Mold-Protection Plan																
		Dust- and HVAC-Control Plan																
	015639	**TEMPORARY TREE AND PLANT PROTECTION**																
		Product Data																
		Tree-Pruning Schedule																
		Maintenance Recommendations																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Qualification Statements																
		Certification																
		Maintenance Recommendations																
		Existing Conditions																
		Quality-Control Program																
	017300	**EXECUTION**																
		Utilities and Mechanical and Electrical Systems																
		Landfill Receipts																
	017419	**CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL**																
		Landfill and Incinerator Disposal Records																
		Qualification Statements																
		Statement of Refrigerant Recovery																
		Refrigerant Recovery																
	017700	**CLOSEOUT PROCEDURES**																
		Product Data																
		Contractor's List of Incomplete Items																
		Certified List of Incomplete Items																
		Certificates of Release																
		Certificate of Insurance																
		Field Report																
		Schedule of Maintenance Material Items																
	017823	**OPERATION AND MAINTENANCE DATA**																
		Operation and Maintenance Manuals																
		Initial Manual Submittal																
		Final Manual Submittal																
	017839	**PROJECT RECORD DOCUMENTS**																
		Recor Drawings																
		Record Specifications																
		Record Prodouct Data																
		Miscellaneous Record Submittals																
	017900	**DEMONSTRATION AND TRAINING**																
		Instruction Program																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Qualification Data																
		Attendance Record																
		Evaluations																
		Demonstration and Training Video Recordings																
	019113	**GENERAL COMMISSIONING REQUIREMENTS**																
		Commissioning Plan Information																
		Commissioning Schedule																
		Two-Week Look-Ahead Schedule																
		Commissioning Coordinator Letter of Authority																
		Commissioning Coordinator Qualification Data																
		Test Instrumentation, Equipment, and Monitoring Devices																
		Test Reports																
		Construction Checklists																
		Commissioning Report																
		Request for Certificate of Construction-Phase Commissioning Process Completion																
		Operation and Maintenance Data																
	019119.43	**EXTERIOR ENCLOSURE COMMISSIONING**																
		Qualification Data																
		Construction Checklists																
		Cx Process Submissions																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
	024119	**SELECTIVE DEMOLITION**																
		Qualification Statements																
		Survey of Existing Conditions																
		Proposed Protection Measures																
		Schedule of Selective Demolition Activities																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Statement of Refrigerant Recovery																
		Warranties																
		Inventory																
	028200	**ASBESTOS REMEDIATION**																
		Test Reports																
		Certificates																
		Permits and Licenses																
		Notifications																
		Respirator Program Records																
		Rental Equipment																
	028300	**LEAD, CHROMIUM, AND CADMIUM REMEDIATION**																
		Preconstruction Submittals																
		Product Data																
		Test Reports																
		Manifest																
		Turn-In Documents or Weight Tickets																
	028416	**HANDLING OF LIGHTING BALLASTS AND LAMPS CONTAINING PCBS AND MERCURY**																
		Certificate Qualifications of CIH																
		Transporter Certification of Waste Activities																
		Certification of Decontamination																
		Certificate of Disposal and/or Recyling																
	030130	**MAINTENANCE OF CAST-IN-PLACE CONCRETE**																
		Product Data																
		Qualification Data																
		Material Certificates																
		Product Test Reports																
	031000	**CONCRETE FORMING AND ACCESSORIES**																
		Product Data																
		Qualification Data																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Field Quality-Control Reports																
	032000	**CONCRETE REINFORCING**																
		Product Data																
		Shop Drawings																
		Construction Joint Layout																
		Qualification Statements																
		Field Quality-Control Reports																
	033000	**CAST-IN-PLACE CONCRETE**																
		Product Data																
		Shop Drawings																
		Design Mixtures																
		Qualification Data																
		Material Certificates																
		Material Test Reports																
		Research Reports																
		Field Quality-Control Reports																
	040110	**MASONRY CLEANING**																
		Product Data																
		Material Certificates																
		Chemical Cleaning Materials																
		Qualification Data																
		Cleaning Program																
		Preconstruction Test Reports																
	040120.63	**BRICK MASONRY REPAIR**																
		Product Data																
		Samples for Initial Selection																
		Samples for Verification																
	040120.64	**BRICK MASONRY REPOINTING**																
		Product Data																
		Samples for Verification																
	040140.61	**STONE REPAIR**																
		Product Data																
		Samples for Verification																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	042000	**UNIT MASONRY**																
		Product Data																
		Shop Drawings																
		Samples for Verification																
		List of Materials																
		Material Certificates																
		Qualification Statements																
		Mix Designs																
		Statement of Compressive Strength of Masonry																
		Cold-Weather and Hot-Weather Procedures																
	047200	**CAST STONE MASONRY**																
		Product Data																
		Shop Drawings																
		Samples for Verification																
		Qualification Data																
		Material Test Reports																
	051200	**STRUCTURAL STEEL FRAMING**																
		Product Data																
		Shop Drawings																
		Welding Procedure Specifications																
		Welding Certificates																
		Paint Compatibility Certificates																
		Mill Test Reports																
		Product Test Reports																
		Survey of Existing Conditions																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
	053100	**STEEL DECKING**																
		Product Data																
		Shop Drawings																
		Welding Certificates																
		Product Certificates																
		Test and Evaluation Reports																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Field Quality-Control Reports																
		Qualification Statements																
	055000	**METAL FABRICATIONS**																
		Product Data																
		Shop Drawings																
		Certificates (Welding & Paint Compatibility)																
		Research Reports																
	055213	**PIPE AND TUBE RAILINGS**																
		Product Data																
		Shop Drawings																
		Samples for Initial Selection																
		Samples for Verification																
		Delegated Design Submittal																
		Qualification Data																
		Welding Certificates																
		Paint Compatibility Certificates																
		Product Test Reports																
		Research Reports																
	061000	**ROUGH CARPENTRY**																
		Product Data																
		Material Certificates																
	061600	**SHEATHING**																
		Product Data																
		Shop Drawings																
		Qualification Data																
		Product Certificates																
		Product Test Reports																
		Evaluation Reports																
		Field Quality-Control Reports																
	064116	**PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS**																
		Product Data																
		Shop Drawings																
		Qualification Data																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	066400	**PLASTIC PANELING**																
		Product Data																
	071326	**SELF-ADHERING SHEET WATERPROOFING**																
		Product Data																
		Field Quality-Control Reports																
		Qualification Statements																
		Sample Warranties																
	072100	**THERMAL INSULATION**																
		Product Data																
		Installer's Certification																
		Product Test Reports																
		Research Reports																
	072119	**FOAMED-IN-PLACE INSULATION**																
		Product Data																
		Product Test Reports																
		Qualification Statements																
	072600	**VAPOR RETARDERS**																
		Product Data																
		Product Test Reports																
	074293	**SOFFIT PANELS**																
		Product Data																
		Samples for Verification																
		Qualification Data																
		Product Test Reports																
		Maintenance Data																
	075419	**POLYVINYL-CHLORIDE (PVC) ROOFING**																
		Product Data																
		Shop Drawings																
		Samples for Verification																
		Wind-Uplift-Resistance Submittal																
		Manufacturer's Certificates																
		Qualification Data																
		Product Test Reports																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Field Quality-Control Reports																
		Sample Warranties																
		Maintenance Data																
	076200	**SHEET METAL FLASHING AND TRIM**																
		Product Data																
		Shop Drawings																
		Samples for Verification																
		Qualification Statements																
		Sample Warranties																
		Maintenance Data																
	077100	**ROOF SPECIALTIES**																
		Product Data																
		Shop Drawings																
		Samples for Verification																
		Product Certificates																
		Qualification Statements																
		Product Test Reports																
		Sample Warranties																
		Maintenance Data																
	077200	**ROOF ACCESSORIES**																
		Product Data																
		Shop Drawings																
		Delegated Design Submittals																
		Coordination Drawings																
		Qualification Statements																
		Delegated Design Engineer Qualifications																
		Operation and Maintenance Data																
	078413	**PENETRATION FIRESTOPPING**																
		Product Data																
		Product Schedule																
		Qualification Data																
		Listed System Designs																
		Installer Certificates																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	078443	**JOINT FIRESTOPPING**																
		Product Data																
		Product Schedule																
		Qualification Data																
		Listed System Designs																
		Installer Certificates																
	079100	**PREFORMED JOINT SEALS**																
		Product Data																
		Samples for Verification																
		Preformed Joint Seal Schedule																
		Test and Evaluation Reports																
		Sample Warranties																
	079200	**JOINT SEALANTS**																
		Product Data																
		Samples for Verification																
		Joint-Sealant Schedule																
		Field Quality-Control Reports																
		Sample Warranties																
		Manufacturer's Special Warranties																
		Installer's Special Warranties																
	079219	**ACOUSTICAL JOINT SEALANTS**																
		Product Data																
		Product Test Reports																
	081113	**HOLLOW METAL DOORS AND FRAMES**																
		Product Data																
		Shop Drawings																
		Product Schedule																
		Qualification Data																
		Product Test Reports																
		Oversize Construction Certification																
		Field Quality-Control Reports																
		Record Documents																
	081116.13	**INTERIOR ALUMINUM DOORS AND WINDOWS**																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Product Data																
		Shop Drawings																
		Samples for Initial Selection																
		Samples for Verification																
		Product Schedule																
		Oversize Fire-Rated Construction Certification																
		Maintenance Data																
	081416	**FLUSH WOOD DOORS**																
		Product Data																
		Shop Drawings																
		Samples for Initial Selection																
		Samples for Verification																
		Sample Warranty																
	083113	**ACCESS DOORS AND FRAMES**																
		Product Data																
		Samples																
		Product Schedule																
		Qualification Statements																
		Record Documents																
	083323	**OVERHEAD COILING DOORS**																
		Product Data																
		Shop Drawings																
		Samples																
		Maintenance Data																
	084113	**ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS**																
		Product Data																
		Shop Drawings																
		Samples for Initial Selection																
		Samples for Verification																
		Entrance Door Hardware Schedule																
		Delegated Design Submittals																
		Energy Performance Certificates																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services

PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Product Test Reports																
		Field Quality-Control Reports																
		Quality-Control Program																
		Qualification Statements																
		Delegated Design Engineer Qualifications																
		Sample Warranties																
		Operation and Maintennace Data																
		Maintenance Data for Structural Sealant																
	084413	**GLAZED ALUMINUM CURTAIN WALLS**																
		Product Data																
		Shop Drawings																
		Samples for Initial Selection																
		Samples for Verification																
		Fabrication Sample																
		Delegated Design Submittal																
		Qualification Data																
		Energy Performance Certificates																
		Product Test Reports																
		Field Quality-Control Reports																
		Sample Warranties																
		Maintenance Data																
		Maintenance Data for Structural Sealant																
	087100	**DOOR HARDWARE**																
		Product Data																
		Shop Drawings																
		Samples																
		Door Hardware Schedule																
		Keying Schedules																
		Product Certificates																
		Product Test Reports																
		Sample Warranty																
		Maintenance Data																
		Schedules																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	087113	**POWER DOOR OPERATORS**																
		Product Data																
		Shop Drawings																
		Samples																
		Qualification Data																
		Field Quality-Control Reports																
		Sample Warranties																
		Maintenance Data																
	088000	**GLAZING**																
		Product Data																
		Glass Samples																
		Glazing Schedule																
		Delegated Design Submittal																
		Qualification Data																
		Product Certificates																
		Product Test Reports																
		Preconstruction Adhesion & Compatibility Test Report																
		Sample Warranties																
	088813	**FIRE-RATED GLAZING**																
		Product Data																
		Glass Samples																
		Glazing Schedule																
		Qualification Data																
		Product Certificates																
		Sample Warranties																
	089119	**FIXED LOUVERS**																
		Product Data																
		Shop Drawings																
		Samples																
		Delegated Design Submittals																
		Product Test Reports																
		Sample Warranties																
	092216	**NON-STRUCTURAL METAL FRAMING**																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services

PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Product Data																
		Product Certificates																
		Evaluation Reports																
	09200	**GYPSUM BOARD**																
		Product Data																
		Samples for Verification																
	093013	**CERAMIC TILING**																
		Product Data																
		Qualification Data																
	095113	**ACOUSTICAL PANEL CEILINGS**																
		Product Data																
		Coordination Drawings																
		Maintenance Data																
	096513	**ACOUSTICAL PANEL CEILINGS**																
		Product Data																
	096519	**RESILIENT TILE FLOORING**																
		Product Data																
		Sustainable Design Submittals																
		Qualification Data																
		Maintenance Data																
	096723	**RESINOUS FLOORING**																
		Product Data																
		Samples																
		Qualification Data																
		Maintenance Data																
	096813	**TILE CARPETING**																
		Product Data																
		Qualification Statements																
		Sample Warranties																
		Maintenance Data																
	099123	**INTERIOR PAINTING**																
		Product Data																
		Product Schedule																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	099600	**HIGH-PERFORMANCE COATINGS**																
		Product Data																
		Samples for Initial Selection																
		Samples for Verification																
		Product List																
		Extra Materials (Coatings)																
	099726	**CEMENTITIOUS COATINGS**																
		Product Data																
		Samples for Verification																
		Material Certificates																
		Product Test Reports																
		Extra Materials																
	102113.13	**METAL TOILET COMPARTMENTS**																
		Product Data																
		Shop Drawings																
		Samples for Initial Selection																
		Operation and Maintenance Data																
	102239	**FOLDING PANEL PARTITIONS**																
		Product Data																
		Shop Drawings																
		Samples for Verification																
		Setting Drawings																
		Coordination Drawings																
		Qualification Data																
		Seismic Qualification Certificates																
		Product Test Reports																
		Field Quality-Control Reports																
		Sample Warranty																
		Operation and Maintenance Data																
	102800	**TOILET, BATH, AND LAUNDRY ACCESSORIES**																
		Product Data																
		Product Schedule																
		Sample Warranty																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services

PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Maintenance Data																
	104413	**FIRE PROTECTION CABINETS**																
		Product Data																
		Shop Drawings																
		Samples																
		Product Schedule																
		Maintenance Data																
	104416	**FIRE EXTINGUISHERS**																
		Product Data																
		Product Schedule																
		Warranty																
		Operation and Maintenance Data																
	105113	**METAL LOCKERS**																
		Product Data																
		Shop Drawings																
		Qualification Data																
		Sample Warranty																
		Maintenance Data																
	108213	**ROOF SCREENS**																
		Product Data																
		Shop Drawings																
		Selection Samples																
		Design Calculations																
		Manufacturer's Certificates																
		Welders Certificates																
		Warranties																
	111313	**LOADING DOCK BUMPERS**																
		Product Data																
		Shop Drawings																
	113013	**RESIDENTIAL APPLIANCES**																
		Product Data																
		Sustainable Design Submittals																
		Operation and Maintenance Data																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	122413	**ROLLER WINDOW SHADES**																
		Product Data																
		Shop Drawings																
		Product Schedule																
		Qualification Data																
		Operation and Maintenance Data																
	123661.16	**SOLID SURFACING COUNTERTOPS**																
		Product Data																
		Shop Drawings																
		Qualification Data																
		Maintenance Data																
	1424100	**HYDRAULIC ELEVATOR - MODERNIZATION**																
		Shop Drawings																
		Samples																
		Name of Mfr, Type/Style of Applicable Data																
		Construction Drawings																
		Vibration Isolating Foundations																
		Dimensioned Drawings																
		Cut Sheets or Drawings																
		Certificates																
	210517	**SLEEVES AND SLEEVE SEALS FOR FIRE-SUPPRESSION PIPING**																
		Product Data																
		Field Quality-Control Reports																
	210518	**ESCUTCHEONS FOR FIRE-SUPPRESSION PIPING**																
		Product Data																
	210523	**GENERAL-DUTY VALVES FOR WATER-BASED FIRE-SUPPRESSION PIPING**																
		Product Data																
	210529	**HANGERS AND SUPPORTS FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT**																
		Product Data																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Welding Certificates																
	210553	**IDENTIFICATION FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT**																
		Product Data																
	211000	**WATER-BASED FIRE-SUPPRESSION SYSTEMS**																
		Product Data																
		Shop Drawings																
		Delegated Design Submittals																
		Coordination Drawings																
		Qualification Data																
		Design Data																
		Welding Certificates																
		Field Test Reports																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
		Extra Materials (Sprinkler Cabinets, System Control Valves)																
	211119	**FIRE DEPARTMENT CONNECTIONS**																
		Product Data																
	220517	**SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING**																
		Product Data																
	220518	**ESCUTCHEONS FOR PLUMBING PIPING**																
		Product Data																
	220519	**METERS AND GAGES FOR PLUMBING PIPING**																
		Product Data																
		Product Certificates																
		Operation and Maintenance Data																
	220523.12	**BALL VALVES FOR PLUMBING PIPING**																
		Product Data																
	220523.14	**CHECK VALVES FOR PLUMBING PIPING**																
		Product Data																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	220529	**HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT**																
		Product Data																
		Shop Drawings																
		Welding Certificates																
	220553	**IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT**																
		Product Data																
		Equipment Label Schedule																
		Valve Numbering Scheme																
		Valve Schedules																
	220593	**TESTING ADJUSTING AND BALANCING FOR PLUMBING**																
		Qualification Data																
		Contract Documents Examination Report																
		Strategies and Procedures Plan																
		System Readiness Checklist																
		Examination Report																
		Certified TAB Reports																
		Sample Report Forms																
		Instrument Calibration Reports																
	220719	**PLUMBING PIPING INSULATION**																
		Product Data																
		Insulation Schedule																
		Qualification Data																
		Field Quality-Control Reports																
	220800	**COMMISSIONING OF PLUMBING**																
		Qualification Data																
		Construction Checklists																
		Test Equipment and Instruments																
	221116	**DOMESTIC WATER PIPING**																
		Product Data																
		Piping Layouts																
		System Purging and Disinfecting Activities																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Report																
		Field Quality-Control Reports																
	221119	**DOMESTIC WATER PIPING SPECIALTIES**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
	221123.21	**INLINE DOMESTIC WATER PUMPS**																
		Product Data																
		Equipment Cut Sheets																
		Operation and Maintenance Data																
	221316	**SANITARY WASTE AND VENT PIPING**																
		Product Data																
		Piping Schedule																
		Piping Layouts																
		Field Quality-Control Reports																
	221319	**SANITARY WASTE PIPING SPECIALTIES**																
		Product Data																
	221319.13	**SANITARY DRAINS**																
		Product Data																
	221329	**SANITARY SEWERAGE PUMPS**																
		Product Data																
		Shop Drawings																
		Operation and Maintenance Data																
	221413	**STORM DRAINAGE PIPING**																
		Product Data																
		Piping Schedule																
		Piping Laouts																
		Field Quality-Control Reports																
	221423	**STORM DRAINAGE PIPING SPECIALTIES**																
		Product Data																
		Drain Cut Sheets																
	223300	**ELECTRIC, DOMESTIC-WATER HEATERS**																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Product Data																
		Shop Drawings																
		Coordination Drawings																
		Product Certificates																
		Domestic-Water Heater Labeling																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
		Sample Warranty																
		Operation and Maintenance Data																
	224200	**COMMERCIAL PLUMBING FIXTURES**																
		Product Data																
		Shop Drawings																
		Coordination Drawings																
		Fixture Cut Sheets																
		Operation and Maintenance Data																
	224600	**SECURITY PLUMBING FIXTURES**																
		Product Data																
		Maintenance Data																
	224716	**PRESSURE WATER COOLERS**																
		Product Data																
		Shop Drawings																
		Fixture Cut Sheets																
		Maintenance Data																
		Extra Materials (Filter Cartridges)																
	230517	**SLEEVES AND SLEEVE SEALS FOR HVAC PIPING**																
		Product Data																
		Field Quality-Control Reports																
	230518	**ESCUTCHEONS FOR HVAC PIPING**																
		Product Data																
	230519	**METERS AND GAUGES FOR HVAC PIPING**																
		Product Data																
		Product Certificates																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Operation and Maintenance Data																
	230523.12	**BALL VALVES FOR HVAC PIPING**																
		Product Data																
	230523.13	**BUTTERFLY VALVES FOR HVAC PIPING**																
		Product Data																
	230523.15	**GATE VALVES FOR HVAC PIPING**																
		Product Data																
	230529	**HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT**																
		Product Data																
		Shop Drawings																
		Delegated-Design Submittal																
		Welding Certificates																
	230548.13	**VIBRATION CONTROLS FOR HVAC**																
		Product Data																
		Shop Drawings																
		Coordination Drawings																
		Qualification Data																
		Welding Certificates																
	230553	**IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT**																
		Product Data																
		Equipment Label Schedule																
		Valve Numbering Scheme																
		Valve Schedules																
	230593	**TESTING, ADJUSTING, AND BALANCING FOR HVAC**																
		Qualification Data																
		Contract Documents Examination Report																
		Strategies and Procedures Plan																
		System Readiness Checklists																
		Examination Report																
		Certified TAB Reports																
		Sample Report Forms																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Instrument Calibration Reports																
	230713	**DUCT INSULATION**																
		Product Data																
		Insulation Schedule																
		Qualification Data																
		Material Test Reports																
		Field Quality-Control Reports																
	230719	**HVAC PIPING INSULATION**																
		Product Data																
		Product																
		Qualification Statements																
		Material Test Reports																
		Field Quality-Control Reports																
	230800	**COMMISSIONING OF HVAC**																
		Qualification Data																
		Construction Checklists																
		Test Equipment and Instruments																
	230923	**DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC**																
		Product Data																
		Software Submittal																
		Shop Drawings																
		System Description																
		Coordination Drawings																
		Qualification Data																
		Product Certificates																
		Product Test Reports																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
		Sample Warranty																
		Operation and Maintenance Data																
		Extra Materials and Parts																
		Product Mfr's Recommended Parts Lists																
		Furnish Parts																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Furnish Quantity Indicated of Matching Products																
	230923.11	**CONTROL VALVES**																
		Product Data																
		Shop Drawings																
		Coordination Drawings																
		Operation and Maintenance Data																
	230923.12	**CONTROL DAMPERS**																
		Product Data																
		Shop Drawings																
		Coordination Drawings																
		Operation and Maintenance Data																
	230923.14	**FLOW INSTRUMENTS**																
		Product Data																
		Shop Drawings																
		Product Certificates																
		Product Test Reports																
		Operation and Maintenance Data																
		Extra Materials																
		Parts																
	230923.16	**GAS INSTRUMENTS**																
		Product Data																
		Shop Drawings																
		Coordination Drawings																
		Product Test Reports																
		Operation and Maintenance Data																
	230923.19	**MOISTURE INSTRUMENTS**																
		Product Data																
		Shop Drawings																
		Operation and Maintenance Data																
	230923.23	**PRESSURE INSTRUMENTS**																
		Product Data																
		Shop Drawings																
		Coordination Drawings																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Product Certificates																
		Product Test Reports																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
	230923.27	**TEMPERATURE INSTRUMENTS**																
		Product Data																
		Shop Drawings																
		Coordination Drawings																
		Product Certificates																
		Product Test Reports																
		Field Quality-Control Reports																
		Extra Materials																
		Two Matching Products in Project Inventory																
	230923.53	**VARIABLE-FREQUENCY MOTOR CONTROLLERS**																
		Product Data																
		Shop Drawings																
		Product Certificates																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
		Sample Warranty																
		Operation and Maintenance Data																
	231123	**NATURAL-GAS PIPING**																
		Product Data																
		Welding Certificates																
	232113	**HYDRONIC PIPING**																
		Product Data																
		Piping Schedule																
		Coordination Drawings																
		Qualification Data																
		Welding Certificates																
		Field Quality-Control Reports																
	232116	**HYDRONIC PIPING SPECIALTIES**																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Product Data																
		Operation and Maintenance Data																
		Differential Pressure Meter																
	232123	**HYDRONIC PUMPS**																
		Product Data																
		Shop Drawings																
		Equipment Cut Sheets																
		Warranty																
		Operation and Maintenance Data																
	233113	**METAL DUCTS**																
		Product Data																
		Coordination Drawings																
		Delegated-Design Submittal																
		Field Quality-Control Reports																
	233300	**AIR DUCT ACCESSORIES**																
		Product Data																
		Coordination Drawings																
		Source Quality-Control Reports																
		Operation and Maintenance Data																
	233346	**FLEXIBLE DUCTS**																
		Product Data																
	233600	**AIR TERMINAL UNITS**																
		Product Data																
		Shop Drawings																
		Coordination Drawings																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
	233713.13	**AIR DIFFUSERS**																
		Product Data																
		Coordination Drawings																
		Source Quality-Control Reports																
	233713.23	**REGISTERS AND GRILLES**																
		Product Data																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Coordination Drawings																
		Source Quality-Control Reports																
	235123	**GAS VENTS**																
		Product Data																
		Shop Drawings																
		Welding Certificates																
		Sample Warranty																
	235216	**CONDENSING BOILERS**																
		Product Data																
		Shop Drawings																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
		Sample Warranty																
		Other Informational Submittals																
		Operation and Maintenance Data																
	235700	**HEAT EXCHANGERS FOR HVAC**																
		Product Data																
		Shop Drawings																
		Sample Warranty																
		Operation and Maintenance Data																
	236423.13	**AIR-COOLED, SCROLL WATER CHILLERS**																
		Product Data																
		Sustainable Design Submittals																
		Shop Drawings																
		Coordination Drawings																
		Certificates																
		Installation Instructions																
		Source Quality-Control Reports																
		Startup Service Reports																
		Sample Warranty																
		Operation and Maintenance Data																
		Spare Parts List																
		Touchup Paint Description																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Instruction Videos																
	237343.16	**OUTDOOR, SEMI-CUSTOM AIR-HANDLING UNITS**																
		Shop Drawings																
		Source Quality-Control Reports																
		Startup Service Reports																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
		Extra Materials (filters, gaskets)																
	238126	**SPLIT-SYSTEM AIR-CONDITIONERS**																
		Product Data																
		Shop Drawings																
		Equipment Cut Sheets																
		Field Quality-Control Reports																
		Warranty																
		Operation and Maintenance Data																
		Extra Materials (Filters)																
	238219	**FAN COIL UNITS**																
		Product Data																
		Shop Drawings																
		Equipment Cut Sheets																
		Operation and Maintenance Data																
		Extra Materials (Fan Coil Unit Filters)																
	238229	**RADIATORS**																
		Product Data																
		Shop Drawings																
		Equipment Cut Sheets																
		Field Quality-Control Reports																
	238236	**FINNED-TUBE RADIATION HEATERS**																
		Product Data																
		Shop Drawings																
		Color Samples																
		Coordination Drawings																
		Field Quality-Control Reports																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	238239.13	**CABINET UNIT HEATERS**																
		Product Data																
		Shop Drawings																
		Equipment Cut Sheets																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
		Extra Materials (Cabinet Unit-Heater Filters)																
	238239.16	**PROPELLER UNIT HEATERS**																
		Product Data																
		Coordination Drawings																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
	260010	**SUPPLEMENTAL REQUIREMENTS FOR ELECTRICAL**																
		Coordination Drawings for Ceiling Areas																
		Coordination Drawings for Conduit and Cable Tray Routing																
		Coordination Drawings for Large Equipment Indoor Installations																
		Coordination Drawings for Large Equipment Outdoor Installations																
		Electrical Installation Schedule																
		Installation Schedule for Communications Systems																
		Installation Schedule for Security, Fire-Alarm and Other Life-Safety Systems																
		Operation and Maintenance Data																
		Software and Firmware Operational Documentation																
	260513	**MEDIUM-VOLTAGE CABLES**																
		Product Data																
		Samples																
		Coordination Darwings																
		Material Certificates																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Design Data																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
	260519	**LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES**																
		Product Data																
		Product Schedule																
		Field Quality-Control Reports																
	260523	**CONTROL-VOLTAGE ELECTRICAL POWER CABLES**																
		Product Data																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
	260526	**GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
	260529	**HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS**																
		Product Data																
	260533.13	**CONDUITS FOR ELECTRICAL SYSTEMS**																
		Product Data																
		Field Quality-Control Reports																
		Manufacturer's Published Instructions																
	260533.16	**BOXES AND COVERS FOR ELECTRICAL SYSTEMS**																
		Product Data																
		Manufacturer's Published Instructions																
	260533.23	**SURFACE RACEWAYS FOR ELECTRICAL SYSTEMS**																
		Product Data																
		Sustainable Design Submittals																
		Manufacturer's Published Instructions																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	260536	**CABLE TRAYS FOR ELECTRICAL SYSTEMS**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
		Manufacturer's Published Instructions																
		Field Reports																
	260543	**UNDERGROUND DUCTS AND RACEWAYS FOR ELECTRICAL SYSTEMS**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
		Manufacturer's Published Instructions																
		Field Reports																
	260544	**SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING**																
		Product Data																
		Sustainable Design Submittals																
	260553	**IDENTIFICATION FOR ELECTRICAL SYSTEMS**																
		Product Data																
		Identification Schedule																
	260573	**POWER SYSTEM STUDIES**																
		Product Data																
		Power System Study Reports																
		Data Files																
		Digital-Twin Models																
	260800	**COMMISSIONING OF ELECTRICAL SYSTEMS**																
		Construction Checklists by CxA																
		Construction Checklsits by Contractor																
	260923	**LIGHTING CONTROL DEVICES**																
		Product Data																
		Shop Drawings																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Field Quality-Control Reports																
		Manufacturer's Published Instructions																
		Field Reports																
		Warranty Documentation																
		Software and Firmware Service Agreement																
	260943.23	**RELAY-BASED LIGHTING CONTROLS**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
		Sample Warranties																
	261219	**PAD-MOUNTED, LIQUID-FILLED, MEDIUM-VOLTAGE TRANSFORMERS**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
		Product Certificates																
		Source Quality-Control Reports																
	262213	**LOW-VOLTAGE DISTRIBUTION TRANSFORMERS**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
		Manufacturer's Published Instructions																
		Source Quality-Control Reports																
	262413	**SWITCHBOARDS**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
		Manufacturer's Published Instructions																
		Sample Warranties																
		Warranty Documentation																
	262416	**PANELBOARDS**																
		Product Data																
		Shop Drawings																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Field Quality-Control Reports																
		Panelboard Schedules																
		Manufacturer's Published Instructions																
		Field Reports																
		Warranty Documentation																
	262713	**ELECTRICITY METERING**																
		Product Data																
		Shop Drawings																
		Manufacturer's Published Instructions																
		Sample Warranties																
		Maintenance Contracts																
		Warranty Documentation																
	262726	**WIRING DEVICES**																
		Product Data																
		Field Quality-Control Reports																
		Manufacturer's Instructions																
	262813	**FUSES**																
		Product Data																
		Operation and Maintenance Data																
	262816	**ENCLOSED SWITCHES**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
		Extra Materials (Fuses, Fuse Pullers)																
	263213.13	**DIESEL-ENGINE-DRIVEN GENERATOR SETS**																
		Product Data																
		Shop Drwings																
		Delegated Design Submittal																
		Qualification Data																
		Source Quality-Control Reports																
		Field Quality-Control Reports																
		Warranty																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Operation and Maintenance Data																
	263600	**TRANSFER SWITCHES**																
		Product Data																
		Shop Drawings																
		Qualification Data																
		Field Quality-Control Reports																
		Operation and Maintenance Data																
	264113	**LIGHTNING PROTECTION FOR STRUCTURES**																
		Product Data																
		Shop Drawings																
		Delegated Design Submittal																
		Coordination Drawings																
		Qualification Data																
		Product Certificates																
		Field Quality-Control Reports																
		Maintenance Data																
		Completion Certificate																
	264313	**SURGE PROTECTION FOR LOW-VOLTAGE ELECTRICAL POWER CIRCIUTS**																
		Product Data																
		Field Quality-Control Reports																
		Sample Warranty																
		Maintenance Data																
	265000	**LIGHTING**																
		Product Data																
		Shop Drawings																
		Sustainable Design Submittals																
		Field Quality-Control Reports																
		Manufacturer's Published Instructions																
		Field Reports																
		Warranty Documentation																
	271100	**COMMUNICATIONS EQUIPMENT ROOM**																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		FITTINGS																
		Product Data																
		Shop Drawings																
		Qualification Data																
	271323	**COMMUNICATIONS OPTICAL FIBER BACKBONE CABLING**																
		Product Data																
		Shop Drawings																
		Certificates																
		Field Quality-Control Submittals																
		Sustainable Design Submittals																
		Source Quality-Control Submittals																
		Maintenance Data																
		Maintenance Contracts																
	271513	**COMMUNICATIONS COPPER HORIZONTAL CABLING**																
		Product Data																
		Shop Drawings																
		Twisted Pair Cable Testing Plan																
		Sustainable Design Submittals																
		Field Quality-Control Submittals																
		Qualification Data																
		Product Certificates																
		Source Quality-Control Reports																
		Maintenance Data																
	275119	**SOUND MASKING SYSTEMS**																
		Product Data																
		Shop Drawings																
		Field Quality Control Reports																
		Manufacturer's Published Instructions																
		Field Reports																
		Warranty Documentation																
	281000	**ACCESS CONTROL**																
		Shop Drawings																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Field Quality-Control Submittals																
		Sample Warranties																
		Manufacturer's Published Instructions																
		Warranty Documentation																
	281400	**ACCESS CONTROL SYSTEM HARDWARE**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Submittals																
		Manufacturer's Published Instructions																
		Sample Warranties																
		Warranty Documentation																
	281500	**INTEGRATED ACCESS CONTROL HARDWARE DEVICES**																
		Product Data																
		Shop drawings																
		Manufacturer's Published Instructions																
		Sample Warranties																
		Maintenance Contracts																
		Warranty Documentation																
	282000	**VIDEAO SURVEILLANCE**																
		Product Data																
		Shop Drawings																
		Design data																
		Field Quality-Control Submittals																
		Product Warranty																
		Operation and Maintenance Data																
	283100	**INTRUSION DETECTION**																
		Product Data																
		Shop Drawings																
		Design Data																
		Samples for Initial Selection																
		Samples for Verification																
		Qualification Data																
		Field Quality-Control Submittals																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services
PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
		Product Warranty																
		Field Test Reports																
		Evaluation reports																
		Operation and Maintenance Data																
	284621.11	**ADDRESABLE FIRE ALARM SYSTEMS**																
		Approved Permit Submittals																
		Product Data																
		Shop Drawings																
		Delegated Design Submittal																
		Field Quality-Control Submittals																
		Qualification Statements																
		Samples Warranty																
		Operation and Maintennace Data																
		Software and Firmware Operational Documentation																
		Extra Stock Material																
	311000	**SITE CLEARING**																
		Existing Conditions																
		Record Drawings																
	312000	**EARTH MOVING**																
		Product Data																
		Material Test Reports																
		Qualification Data																
		Preexcavation Photographs or Videotape																
	312319	**DEWATERING**																
		Qualification Statements																
		Field Quality-Control Reports																
		Existing Conditions																
	321216	**ASPHALT PAVING**																
		Product Data																
		Hot-Mix Asphalt Designs																
		Qualification Data																
		Material Certificates																
		Field Quality-Control Reports																

MASTERWORKS SUBMITTAL LOG

PROJECT: 221 State Street, Building Renovations, Augusta, Maine
OWNER: Bureau of General Services

PROJECT NO:
CONTRACTOR:

DATE REC'D.	SPECIFICATION SECTION NO.	SUBMITTAL ITEM	CONTRACTOR SUBCONTRACTOR	NO. RECEIVED	OTHER REVIEWER					ACTION				DATE RETURNED	COPIES TO			
					DATE SENT	FIRM	NO. COPIES	DUE DATE	DATE REC'D.	APPROVED	APPROVED AS NOTED	REVISE & RESUBMIT	NOT APP' D.		CONTRACTOR	OWNER	FIELD	FILE
	321373	**CONCRETE PAVING JOINT SEALANTS**																
		Product Data																
	321723	**PAVEMENT MARKINGS**																
		Product Data																
	323113	**CHAIN LINK FENCES AND GATES**																
		Product Data																
		Shop Drawings																
		Product Certificates																
		Product Test Reports																
	329115	**SOIL PREPARATION (PERFORMANCE SPECIFICATION)**																
		Product Data																
		Sustainable Design Submittals																
		Samples																
		Qualification Data																
		Preconstruction Test Reports																
		Field Quality-Control Reports																
	329200	**TURF AND GRASSES**																
		Certification of Grass Seed																
		Product Certificates																
		Pesticides and Herbicides																
		Maintenance Data																
	333115	**SITE SANITARY SEWERAGE PIPING**																
		Product Data																
		Shop Drawings																
		Product Certificates																
		Field Quality-Control Reports																
	334200	**STORMWATER CONVEYANCE**																
		Product Data																
		Shop Drawings																
		Field Quality-Control Reports																

END

SECTION 013516 - ALTERATION PROJECT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes special procedures for alteration work.

1.2 DEFINITIONS

A. Alteration Work: This term includes remodeling, renovation, repair, and maintenance work performed within existing spaces or on existing surfaces as part of the Project.

B. Consolidate: To strengthen loose or deteriorated materials in place.

C. Design Reference Sample: A sample that represents the Architect's pre-bid selection of work to be matched; it may be existing work or work specially produced for the Project.

D. Dismantle: To remove by disassembling or detaching an item from a surface, using gentle methods and equipment to prevent damage to the item and surfaces; disposing of items unless indicated to be salvaged or reinstalled.

E. Match: To blend with adjacent construction and manifest no apparent difference in material type, species, cut, form, detail, color, grain, texture, or finish; as approved by Architect.

F. Refinish: To remove existing finishes to base material and apply new finish to match original, or as otherwise indicated.

G. Repair: To correct damage and defects, retaining existing materials, features, and finishes. This includes patching, piecing-in, splicing, consolidating, or otherwise reinforcing or upgrading materials.

H. Replace: To remove, duplicate, and reinstall entire item with new material. The original item is the pattern for creating duplicates unless otherwise indicated.

I. Replicate: To reproduce in exact detail, materials, and finish unless otherwise indicated.

J. Reproduce: To fabricate a new item, accurate in detail to the original, and from either the same or a similar material as the original, unless otherwise indicated.

K. Retain: To keep an element or detail secure and intact.

L. Strip: To remove existing finish down to base material unless otherwise indicated.

1.3 COORDINATION

A. Pedestrian and Vehicular Circulation: Coordinate alteration work with circulation patterns within Project building(s) and site. Some work is near circulation patterns. Circulation patterns cannot be closed off entirely and in places can be only temporarily redirected around small areas of work. Plan and execute the Work accordingly.

1.4 MATERIALS OWNERSHIP

A. Historic items, relics, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, antiques, and other items of interest or value to Owner that may be encountered or uncovered during the Work, regardless of whether they were previously documented, remain Owner's property.

1. Carefully dismantle and salvage each item or object in a manner to prevent damage and protect it from damage, then promptly deliver it to Owner where directed at Project site.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Preconstruction Documentation: Show preexisting conditions of adjoining construction and site improvements that are to remain, including finish surfaces, that might be misconstrued as damage caused by Contractor's alteration work operations.

C. Fire-Prevention Plan: Submit 30 days before work begins.

1.6 QUALITY ASSURANCE

A. Fire-Prevention Plan: Prepare a written plan for preventing fires during the Work, including placement of fire extinguishers, fire blankets, rag buckets, and other fire-control devices during each phase or process. Coordinate plan with Owner's fire-protection equipment and requirements. Include fire-watch personnel's training, duties, and authority to enforce fire safety.

B. Safety and Health Standard: Comply with ANSI/ASSP A10.6.

1.7 STORAGE AND HANDLING OF SALVAGED MATERIALS

A. Salvaged Materials:

1. Clean loose dirt and debris from salvaged items unless more extensive cleaning is indicated.
2. Pack or crate items after cleaning; cushion against damage during handling. Label contents of containers.
3. Store items in a secure area until delivery to Owner.

4. Transport items to Owner's storage area off-site designated by Owner.
5. Protect items from damage during transport and storage.

B. Salvaged Materials for Reinstallation:

1. Repair and clean items for reuse as indicated.
2. Pack or crate items after cleaning and repairing; cushion against damage during handling. Label contents of containers.
3. Protect items from damage during transport and storage.
4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment unless otherwise indicated. Provide connections, supports, and miscellaneous materials to make items functional for use indicated.

C. Existing Materials to Remain: Protect construction indicated to remain against damage and soiling from construction work. Where permitted by Architect, items may be dismantled and taken to a suitable, protected storage location during construction work and reinstalled in their original locations after alteration and other construction work in the vicinity is complete.

D. Storage: Catalog and store items within a weathertight enclosure where they are protected from moisture, weather, condensation, and freezing temperatures.

1. Identify each item for reinstallation with a nonpermanent mark to document its original location. Indicate original locations on plans, elevations, sections, or photographs by annotating the identifying marks.
2. Secure stored materials to protect from theft.
3. Control humidity so that it does not exceed 85 percent. Maintain temperatures 5 deg F or more above the dew point.

E. Storage Space:

1. Arrange for off-site locations for storage and protection of salvaged material that cannot be stored and protected on-site.

1.8 FIELD CONDITIONS

A. Survey of Existing Conditions: Record existing conditions that affect the Work by use of preconstruction photographs.

1. Comply with requirements specified in Section 013233 "Photographic Documentation."

B. Discrepancies: Notify Architect of discrepancies between existing conditions and Drawings before proceeding with removal and dismantling work.

PART 2 - PRODUCTS - (Not Used)

PART 3 - EXECUTION

3.1 PROTECTION

A. Protect persons, motor vehicles, surrounding surfaces of building, building site, plants, and surrounding buildings from harm resulting from alteration work.

1. Use only proven protection methods, appropriate to each area and surface being protected.
2. Provide temporary barricades, barriers, and directional signage to exclude the public from areas where alteration work is being performed.
3. Erect temporary barriers to form and maintain fire-egress routes.
4. Erect temporary protective covers over walkways and at points of pedestrian and vehicular entrance and exit that must remain in service during alteration work.
5. Contain dust and debris generated by alteration work, and prevent it from reaching the public or adjacent surfaces.
6. Provide shoring, bracing, and supports as necessary. Do not overload structural elements.
7. Protect floors and other surfaces along hauling routes from damage, wear, and staining.

B. Temporary Protection of Materials to Remain:

1. Protect existing materials with temporary protections and construction. Do not remove existing materials unless otherwise indicated.
2. Do not attach temporary protection to existing surfaces except as indicated as part of the alteration work program.

C. Comply with each product manufacturer's written instructions for protections and precautions. Protect against adverse effects of products and procedures on people and adjacent materials, components, and vegetation.

D. Utility and Communications Services:

1. Notify Owner, Architect, authorities having jurisdiction, and entities owning or controlling wires, conduits, pipes, and other services affected by alteration work before commencing operations.
2. Disconnect and cap pipes and services as required by authorities having jurisdiction, as required for alteration work.
3. Maintain existing services unless otherwise indicated; keep in service, and protect against damage during operations. Provide temporary services during interruptions to existing utilities.

E. Existing Drains: Prior to the start of work in an area, test drainage system to ensure that it is functioning properly. Notify Architect immediately of inadequate drainage or blockage. Do not begin work in an area until the drainage system is functioning properly.

1. Prevent solids such as adhesive or mortar residue or other debris from entering the drainage system. Clean out drains and drain lines that become sluggish or blocked by sand or other materials resulting from alteration work.
2. Protect drains from pollutants. Block drains or filter out sediments, allowing only clean water to pass.

3.2 PROTECTION FROM FIRE

A. General: Follow fire-prevention plan and the following:

1. Comply with NFPA 241 requirements unless otherwise indicated. Perform duties titled "Owner's Responsibility for Fire Protection."
2. Remove and keep area free of combustibles, including rubbish, paper, waste, and chemicals, unless necessary for the immediate work.

    a. If combustible material cannot be removed, provide fire blankets to cover such materials.

B. Heat-Generating Equipment and Combustible Materials: Comply with the following procedures while performing work with heat-generating equipment or combustible materials, including welding, torch-cutting, soldering, brazing, removing paint with heat, or other operations where open flames or implements using high heat or combustible solvents and chemicals are anticipated:

1. Obtain Owner's approval for operations involving use of open-flame or welding or other high-heat equipment. Notify Owner at least 72 hours before each occurrence, indicating location of such work.
2. As far as practicable, restrict heat-generating equipment to shop areas or outside the building.
3. Do not perform work with heat-generating equipment in or near rooms or in areas where flammable liquids or explosive vapors are present or thought to be present. Use a combustible gas indicator test to ensure that the area is safe.
4. Use fireproof baffles to prevent flames, sparks, hot gases, or other high-temperature material from reaching surrounding combustible material.
5. Prevent the spread of sparks and particles of hot metal through open windows, doors, holes, and cracks in floors, walls, ceilings, roofs, and other openings.
6. Fire Watch: Before working with heat-generating equipment or combustible materials, station personnel to serve as a fire watch at each location where such work is performed. Fire-watch personnel shall have the authority to enforce fire safety. Station fire watch according to NFPA 51B, NFPA 241, and as follows:

    a. Train each fire watch in the proper operation of fire-control equipment and alarms.
    b. Prohibit fire-watch personnel from other work that would be a distraction from fire-watch duties.
    c. Cease work with heat-generating equipment whenever fire-watch personnel are not present.
    d. Maintain fire-watch personnel at each area of Project site until 30 minutes after conclusion of daily heat-generating work.

C. Fire-Control Devices: Provide and maintain fire extinguishers, fire blankets, and rag buckets for disposal of rags with combustible liquids. Maintain each as suitable for the type of fire risk in each work area. Ensure that nearby personnel and the fire-watch personnel are trained in fire-extinguisher and blanket use.

3.3 PROTECTION DURING APPLICATION OF CHEMICALS

A. Protect motor vehicles, surrounding surfaces of building, building site, plants, and surrounding buildings from harm or spillage resulting from applications of chemicals and adhesives.

B. Cover adjacent surfaces with protective materials that are proven to resist chemicals selected for Project unless chemicals being used will not damage adjacent surfaces as indicated in alteration work program. Use covering materials and masking agents that are waterproof and UV resistant and that will not stain or leave residue on surfaces to which they are applied. Apply protective materials according to manufacturer's written instructions. Do not apply liquid masking agents or adhesives to painted or porous surfaces. When no longer needed, promptly remove protective materials.

C. Do not apply chemicals during winds of sufficient force to spread them to unprotected surfaces.

D. Neutralize alkaline and acid wastes and legally dispose of off Owner's property.

E. Collect and dispose of runoff from chemical operations by legal means and in a manner that prevents soil contamination, soil erosion, undermining of paving and foundations, damage to landscaping, or water penetration into building interior.

END OF SECTION

SECTION 014000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for quality assurance and quality control.

B. Testing and inspection services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.

1. Specific quality-assurance and quality-control requirements for individual work results are specified in their respective Specification Sections. Requirements in individual Sections may also cover production of standard products.
2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and quality-control procedures that facilitate compliance with the Contract Document requirements.
3. Requirements for Contractor to provide quality-assurance and quality-control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.

C. Related Requirements:

1. Section 00 72 13 “General Conditions.”

1.2 DEFINITIONS

A. Experienced: When used with an entity or individual, "experienced," unless otherwise further described, means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

B. Field Quality-Control Tests and Inspections: Tests and inspections that are performed on-site for installation of the Work and for completed Work.

C. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, subcontractor, or sub-subcontractor, to perform a particular construction operation, including installation, erection, application, assembly, and similar operations.

1. Use of trade-specific terminology in referring to a Work result does not require that certain construction activities specified apply exclusively to specific trade(s).

D. Mockups: Physical assemblies of portions of the Work constructed to establish the standard by which the Work will be judged. Mockups are not Samples.

1. Mockups are used for one or more of the following:

a. Verify selections made under Sample submittals.
b. Demonstrate aesthetic effects.
c. Demonstrate the qualities of products and workmanship.
d. Demonstrate successful installation of interfaces between components and systems.
e. Perform preconstruction testing to determine system performance.

2. Product Mockups: Mockups that may include multiple products, materials, or systems specified in a single Section.
3. In-Place Mockups: Mockups constructed on-site in their actual final location as part of permanent construction.

E. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria. Unless otherwise indicated, copies of reports of tests or inspections performed for other than the Project do not meet this definition.

F. Product Tests: Tests and inspections that are performed by a nationally recognized testing laboratory (NRTL) in accordance with 29 CFR 1910.7, by a testing agency accredited in accordance with NIST's National Voluntary Laboratory Accreditation Program (NVLAP), or by a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.

G. Source Quality-Control Tests and Inspections: Tests and inspections that are performed at the source (e.g., plant, mill, factory, or shop).

H. Testing Agency: An entity engaged to perform specific tests, inspections, or both. The term "testing laboratory" has the same meaning as the term "testing agency."

I. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work, to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.

J. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work, to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Contractor's quality-control services do not include contract administration activities performed by Architect.

1.3 DELEGATED DESIGN SERVICES

A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.

B. Delegated Design Services Statement: Submit a statement signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional, indicating that the products and systems are in compliance with performance and design criteria indicated. Include list of codes, loads, and other factors used in performing these services.

1.4 CONFLICTING REQUIREMENTS

A. Conflicting Standards and Other Requirements: If compliance with two or more standards or requirements is specified and the standards or requirements establish different or conflicting requirements for minimum quantities or quality levels, inform the Architect regarding the conflict and obtain clarification prior to proceeding with the Work. Refer conflicting requirements that are different, but apparently equal, to Architect for clarification before proceeding.

B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified is the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.

C. Qualification Data: For Contractor's quality-control personnel.

D. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility submitted to authorities having jurisdiction before starting work on the following systems:

1. Seismic-force-resisting system, designated seismic system, or component listed in the Statement of Special Inspections.
2. Primary wind-force-resisting system or a wind-resisting component listed in the Statement of Special Inspections.

E. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

F. Schedule of Tests and Inspections: Prepare in tabular form and include the following:

1. Specification Section number and title.
2. Entity responsible for performing tests and inspections.
3. Description of test and inspection.
4. Identification of applicable standards.
5. Identification of test and inspection methods.
6. Number of tests and inspections required.
7. Time schedule or time span for tests and inspections.
8. Requirements for obtaining samples.
9. Unique characteristics of each quality-control service.

G. Reports: Prepare and submit certified written reports and documents as specified.

H. Permits, Licenses, and Certificates: For Owner's record, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents established for compliance with standards and regulations bearing on performance of the Work.

1.6 CONTRACTOR'S QUALITY-CONTROL PLAN

A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice to Proceed, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities and to coordinate Owner's quality-assurance and quality-control activities. Coordinate with Contractor's Construction Schedule.

B. Quality-Control Personnel Qualifications: Engage qualified personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.

1. Project quality-control manager may also serve as Project superintendent.

C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.

D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:

1. Contractor-performed tests and inspections, including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections. Distinguish source quality-control tests and inspections from field quality-control tests and inspections.
2. Special inspections required by authorities having jurisdiction and indicated on the Statement of Special Inspections.

E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring the Work into compliance with standards of workmanship established by Contract requirements and approved mockups.

F. Monitoring and Documentation: Maintain testing and inspection reports, including log of approved and rejected results. Include Work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming Work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

1.7 REPORTS AND DOCUMENTS

A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:

1. Date of issue.
2. Project title and number.
3. Name, address, telephone number, and email address of testing agency.
4. Dates and locations of samples and tests or inspections.
5. Names of individuals making tests and inspections.
6. Description of the Work and test and inspection method.
7. Identification of product and Specification Section.
8. Complete test or inspection data.
9. Test and inspection results and an interpretation of test results.
10. Record of temperature and weather conditions at time of sample-taking and testing and inspection.
11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
12. Name and signature of laboratory inspector.
13. Recommendations on retesting and reinspecting.

B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:

1. Name, address, telephone number, and email address of technical representative making report.
2. Statement on condition of substrates and their acceptability for installation of product.
3. Statement that products at Project site comply with requirements.
4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
6. Statement of whether conditions, products, and installation will affect warranty.
7. Other required items indicated in individual Specification Sections.

C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:

1. Name, address, telephone number, and email address of factory-authorized service representative making report.
2. Statement that equipment complies with requirements.
3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
4. Statement of whether conditions, products, and installation will affect warranty.
5. Other required items indicated in individual Specification Sections.

1.8 QUALITY ASSURANCE

A. Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units. As applicable, procure products from manufacturers able to meet qualification requirements, warranty requirements, and technical or factory-authorized service representative requirements.

C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

D. Installer Qualifications: A firm or individual experienced in installing, erecting, applying, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that is similar in material, design, and extent to those indicated for this Project.

F. Specialists: Certain Specification Sections require that specific construction activities be performed by entities who are recognized experts in those operations. Specialists will satisfy qualification requirements indicated and engage in the activities indicated.

1. Requirements of authorities having jurisdiction supersede requirements for specialists.

G. Testing and Inspecting Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspection indicated, as documented in accordance with ASTM E329, and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.

H. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

I. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect, demonstrate, repair, and perform service on installations of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

J. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:

1. Build mockups of size indicated.

2. Build mockups in location indicated or, if not indicated, as directed by Architect.
3. Notify Architect seven days in advance of dates and times when mockups will be constructed.
4. Employ supervisory personnel who will oversee mockup construction. Employ workers who will be employed to perform same tasks during the construction at Project.
5. Demonstrate the proposed range of aesthetic effects and workmanship.
6. Obtain Architect's approval of mockups before starting corresponding Work, fabrication, or construction.

    a. Allow seven days for initial review and each re-review of each mockup.

7. Promptly correct unsatisfactory conditions noted by Architect's preliminary review, to the satisfaction of the Architect, before completion of final mockup.
8. Approval of mockups by the Architect does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
9. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
10. Demolish and remove mockups when directed unless otherwise indicated.

1.9 QUALITY CONTROL

A. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities, whether specified or not, to verify and document that the Work complies with requirements.

1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
2. Engage a qualified testing agency to perform quality-control services.

    a. Contractor will not employ same entity engaged by Owner, unless agreed to in writing by Owner.

3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspection will be performed.
4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
5. Testing and inspection requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.

B. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.

C. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.

1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
2. Determine the locations from which test samples will be taken and in which in-situ tests are conducted.
3. Conduct and interpret tests and inspections, and state in each report whether tested and inspected Work complies with or deviates from requirements.
4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
6. Do not perform duties of Contractor.

D. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."

E. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.

F. Contractor's Associated Requirements and Services: Cooperate with agencies and representatives performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:

1. Access to the Work.
2. Incidental labor and facilities necessary to facilitate tests and inspections.
3. Adequate quantities of representative samples of materials that require testing and inspection. Assist agency in obtaining samples.
4. Facilities for storage and field curing of test samples.
5. Delivery of samples to testing agencies.
6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
7. Security and protection for samples and for testing and inspection equipment at Project site.

G. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and quality-control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspection.

1. Schedule times for tests, inspections, obtaining samples, and similar activities.

H. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents as a component of Contractor's quality-control plan. Coordinate and submit concurrently with Contractor's Construction Schedule. Update and submit with each Application for Payment.

1. Schedule Contents: Include tests, inspections, and quality-control services, including Contractor- and Owner-retained services, commissioning activities, and other Project-required services paid for by other entities.
2. Distribution: Distribute schedule to Owner, Architect, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.

1.10 SPECIAL TESTS AND INSPECTIONS

A. Special Tests and Inspections: Owner will engage a qualified special inspector to conduct special tests and inspections required by authorities having jurisdiction as the responsibility of Owner, and as follows:

1. Notifying Architect and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
2. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect with copy to Contractor and to authorities having jurisdiction.
3. Retesting and reinspecting corrected Work.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:

1. Date test or inspection was conducted.
2. Description of the Work tested or inspected.
3. Date test or inspection results were transmitted to Architect.
4. Identification of testing agency or special inspector conducting test or inspection.

B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's and authorities' having jurisdiction reference during normal working hours.

1. Submit log at Project closeout as part of Project Record Documents.

3.2 REPAIR AND PROTECTION

A. General: On completion of testing, inspection, sample-taking, and similar services, repair damaged construction and restore substrates and finishes.

1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."

B. Protect construction exposed by or for quality-control service activities.

C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION

SECTION 014200 - REFERENCES

PART 1 - GENERAL

1.1 DEFINITIONS

A. General: Basic Contract definitions are included in the Conditions of the Contract.

B. "Reviewed": When used to convey Architect's action on Contractor's submittals, applications, and requests, "reviewed" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.

C. "Directed": A command or instruction by Architect. Other terms, including "requested," "authorized," "selected," "required," and "permitted," have the same meaning as "directed."

D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms, including "shown," "noted," "scheduled," and "specified," have the same meaning as "indicated."

E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.

F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.

G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.

H. "Provide": Furnish and install, complete and ready for the intended use.

I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.2 INDUSTRY STANDARDS

A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.

B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.

1. For standards referenced by applicable building codes, comply with dates of standards as listed in building codes.

C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.

1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.3 ABBREVIATIONS AND ACRONYMS

A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."

B. Industry Organizations, List: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the entities in the following list. Abbreviations and acronyms not included in this list are to mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States." The information in this list is subject to change and is believed to be accurate as of the date of the Contract Documents.

1. AABC - Associated Air Balance Council; www.aabc.com.
2. AAMA - American Architectural Manufacturers Association; (see FGIA).
3. AAPFCO - Association of American Plant Food Control Officials; www.aapfco.org.
4. AASHTO - American Association of State Highway and Transportation Officials; www.transportation.org.
5. AATCC - American Association of Textile Chemists and Colorists; www.aatcc.org.
6. ABMA - American Bearing Manufacturers Association; www.americanbearings.org.
7. ABMA - American Boiler Manufacturers Association; www.abma.com.
8. ACI - American Concrete Institute; www.concrete.org.
9. ACP - American Clean Power; (Formerly: American Wind Energy Association); www.cleanpower.org.
10. ACPA - American Concrete Pipe Association; www.concretepipe.org.
11. AEIC - Association of Edison Illuminating Companies, Inc. (The); www.aeic.org.
12. AF&PA - American Forest & Paper Association; www.afandpa.org.
13. AGA - American Gas Association; www.aga.org.
14. AHAM - Association of Home Appliance Manufacturers; www.aham.org.
15. AHRI - Air-Conditioning, Heating, and Refrigeration Institute (The); www.ahrinet.org.
16. AI - Asphalt Institute; www.asphaltinstitute.org.
17. AIA - American Institute of Architects (The); www.aia.org.
18. AISC - American Institute of Steel Construction; www.aisc.org.
19. AISI - American Iron and Steel Institute; www.steel.org.
20. AITC - American Institute of Timber Construction; (see PLIB).
21. AMCA - Air Movement and Control Association International, Inc.; www.amca.org.
22. AMPP - Association for Materials Protection and Performance; www.ampp.org.
23. ANSI - American National Standards Institute; www.ansi.org.
24. AOSA/SCST - Association of Official Seed Analysts (The)/Society of Commercial Seed Technologists (The); www.analyzeseeds.com.
25. APA - APA - The Engineered Wood Association; www.apawood.org.
26. APA - Architectural Precast Association; www.archprecast.org.

27. API - American Petroleum Institute; www.api.org.
28. ARMA - Asphalt Roofing Manufacturers Association; www.asphaltroofing.org.
29. ASA - Acoustical Society of America; www.acousticalsociety.org.
30. ASCE - American Society of Civil Engineers; www.asce.org.
31. ASCE/SEI - American Society of Civil Engineers/Structural Engineering Institute; (see ASCE).
32. ASHRAE - American Society of Heating, Refrigerating and Air-Conditioning Engineers; www.ashrae.org.
33. ASME - ASME International; American Society of Mechanical Engineers (The); www.asme.org.
34. ASSE - ASSE International; (American Society of Sanitary Engineering); www.asse-plumbing.org.
35. ASSP - American Society of Safety Professionals; www.assp.org.
36. ASTM - ASTM International; www.astm.org.
37. ATIS - Alliance for Telecommunications Industry Solutions; www.atis.org.
38. AVIXA - Audiovisual and Integrated Experience Association; www.avixa.org.
39. AWI - Architectural Woodwork Institute; www.awinet.org.
40. AWMAC - Architectural Woodwork Manufacturers Association of Canada; www.awmac.com.
41. AWPA - American Wood Protection Association; www.awpa.com.
42. AWS - American Welding Society; www.aws.org.
43. AWWA - American Water Works Association; www.awwa.org.
44. BHMA - Builders Hardware Manufacturers Association; www.buildershardware.com.
45. BIA - Brick Industry Association (The); www.gobrick.com.
46. BICSI - BICSI, Inc.; www.bicsi.org.
47. BIFMA - Business and Institutional Furniture Manufacturer's Association; www.bifma.org.
48. BISSC - Baking Industry Sanitation Standards Committee; www.bissc.org.
49. BSI - British Standards Institution; www.bsigroup.com.
50. BWF - Badminton World Federation; www.bwfbadminton.com.
51. CARB - California Air Resources Board; www.arb.ca.gov.
52. CDA - Copper Development Association Inc.; www.copper.org.
53. CE - Conformite Europeenne (European Commission); www.ec.europa.eu/growth/single-market/ce-marking.
54. CEA - Canadian Electricity Association; www.electricity.ca.
55. CFFA - Chemical Fabrics and Film Association, Inc.; www.chemicalfabricsandfilm.com.
56. CFSEI - Cold-Formed Steel Engineers Institute; www.cfsei.org.
57. CGA - Compressed Gas Association; www.cganet.com.
58. CIMA - Cellulose Insulation Manufacturers Association; www.cellulose.org.
59. CISCA - Ceilings & Interior Systems Construction Association; www.cisca.org.
60. CISPI - Cast Iron Soil Pipe Institute; www.cispi.org.
61. CLFMI - Chain Link Fence Manufacturers Institute; www.chainlinkinfo.org.
62. CMHA - Concrete Masonry & Hardscape Association; (Formerly: National Concrete Masonry Association); www.masonryandhardscapes.org.
63. CPA - Composite Panel Association; www.compositepanel.org.
64. CRI - Carpet and Rug Institute (The); www.carpet-rug.org.
65. CRRC - Cool Roof Rating Council; www.coolroofs.org.
66. CRSI - Concrete Reinforcing Steel Institute; www.crsi.org.
67. CSA - CSA Group; www.csagroup.org.
68. CSI - Cast Stone Institute; www.caststone.org.
69. CSI - Construction Specifications Institute (The); www.csiresources.org.

70. CSSB - Cedar Shake & Shingle Bureau; www.cedarbureau.org.
71. CTA - Consumer Technology Association; www.cta.tech.
72. CTI - Cooling Technology Institute; www.coolingtechnology.org.
73. DASMA - Door and Access Systems Manufacturers Association; www.dasma.com.
74. DHA - Decorative Hardwoods Association; www.decorativehardwoods.org.
75. DHI - Door and Hardware Institute; www.dhi.org.
76. ECIA - Electronic Components Industry Association; www.ecianow.org.
77. EIMA - EIFS Industry Members Association; www.eima.com.
78. EJMA - Expansion Joint Manufacturers Association, Inc.; www.ejma.org.
79. EOS/ESD - EOS/ESD Association, Inc.; Electrostatic Discharge Association; www.esda.org.
80. ESTA - Entertainment Services and Technology Association; www.esta.org.
81. EVO - Efficiency Valuation Organization; www.evo-world.org.
82. FCI - Fluid Controls Institute; www.fluidcontrolsinstitute.org.
83. FGIA - Fenestration and Glazing Industry Alliance; https://fgiaonline.org.
84. FIBA - Federation Internationale de Basketball; (The International Basketball Federation); www.fiba.com.
85. FIVB - Federation Internationale de Volleyball; (The International Volleyball Federation); www.fivb.org.
86. FM Approvals - FM Approvals LLC; www.fmapprovals.com.
87. FM Global - FM Global; www.fmglobal.com.
88. FRSA - Florida Roofing and Sheet Metal Contractors Association, Inc.; www.floridaroof.com.
89. FSA - Fluid Sealing Association; www.fluidsealing.com.
90. FSC - Forest Stewardship Council U.S.; www.fscus.org.
91. GA - Gypsum Association; www.gypsum.org.
92. GS - Green Seal; www.greenseal.org.
93. HI - Hydraulic Institute; www.pumps.org.
94. HMMA - Hollow Metal Manufacturers Association; (see NAAMM).
95. IAPSC - International Association of Professional Security Consultants; www.iapsc.org.
96. IAS - International Accreditation Service; www.iasonline.org.
97. ICC - International Code Council; www.iccsafe.org.
98. ICEA - Insulated Cable Engineers Association, Inc.; www.icea.net.
99. ICPA - International Cast Polymer Association (The); www.theicpa.com.
100. ICRI - International Concrete Repair Institute, Inc.; www.icri.org.
101. IEC - International Electrotechnical Commission; www.iec.ch.
102. IEEE SA - IEEE Standards Association; https://standards.ieee.org.
103. IES - Illuminating Engineering Society; www.ies.org.
104. IEST - Institute of Environmental Sciences and Technology; www.iest.org.
105. IGMA - Insulating Glass Manufacturers Alliance; (see FGIA).
106. IGSHPA - International Ground Source Heat Pump Association; www.igshpa.org.
107. ILI - Indiana Limestone Institute of America, Inc.; www.iliai.com.
108. Intertek - Intertek Group; www.intertek.com.
109. ISA - International Society of Automation (The); www.isa.org.
110. ISFA - International Surface Fabricators Association; www.isfanow.org.
111. ISO - International Organization for Standardization; www.iso.org.
112. ITU - International Telecommunication Union; www.itu.int.
113. KCMA - Kitchen Cabinet Manufacturers Association; www.kcma.org.
114. LPI - Lightning Protection Institute; www.lightning.org.
115. MBMA - Metal Building Manufacturers Association; www.mbma.com.
116. MCA - Metal Construction Association; www.metalconstruction.org.

117. MFMA - Maple Flooring Manufacturers Association, Inc.; www.maplefloor.org.
118. MFMA - Metal Framing Manufacturers Association, Inc.; www.metalframingmfg.org.
119. MHI - Material Handling Industry; www.mhi.org.
120. MMPA - Moulding & Millwork Producers Association; www.wmmpa.com.
121. MPI - Master Painters Institute; www.paintinfo.com.
122. MSS - Manufacturers Standardization Society of The Valve and Fittings Industry, Inc.; www.msshq.org.
123. NAAMM - National Association of Architectural Metal Manufacturers; www.naamm.org.
124. NACE - NACE International; (National Association of Corrosion Engineers International); (see AMPP).
125. NADCA - National Air Duct Cleaners Association; www.nadca.com.
126. NAIMA - North American Insulation Manufacturers Association; www.insulationinstitute.org.
127. NALP - National Association of Landscape Professionals; www.landscapeprofessionals.org.
128. NBGQA - National Building Granite Quarries Association, Inc.; www.nbgqa.com.
129. NBI - New Buildings Institute; www.newbuildings.org.
130. NCAA - National Collegiate Athletic Association (The); www.ncaa.org.
131. NCMA - National Concrete Masonry Association; (see CMHA).
132. NEBB - National Environmental Balancing Bureau; www.nebb.org.
133. NECA - National Electrical Contractors Association; www.necanet.org.
134. NeLMA - Northeastern Lumber Manufacturers Association; www.nelma.org.
135. NEMA - National Electrical Manufacturers Association; www.nema.org.
136. NETA - InterNational Electrical Testing Association; www.netaworld.org.
137. NFHS - National Federation of State High School Associations; www.nfhs.org.
138. NFPA - National Fire Protection Association; www.nfpa.org.
139. NFPA - NFPA International; (see NFPA).
140. NFRC - National Fenestration Rating Council; www.nfrc.org.
141. NGA - National Glass Association; www.glass.org.
142. NHLA - National Hardwood Lumber Association; www.nhla.com.
143. NLGA - National Lumber Grades Authority; www.nlga.org.
144. NOFMA - National Oak Flooring Manufacturers Association; (see NWFA).
145. NOMMA - National Ornamental & Miscellaneous Metals Association; www.nomma.org.
146. NRCA - National Roofing Contractors Association; www.nrca.net.
147. NRMCA - National Ready Mixed Concrete Association; www.nrmca.org.
148. NSF - NSF International; www.nsf.org.
149. NSI - Natural Stone Institute; www.naturalstoneinstitute.org.
150. NSPE - National Society of Professional Engineers; www.nspe.org.
151. NSSGA - National Stone, Sand & Gravel Association; www.nssga.org.
152. NTMA - National Terrazzo & Mosaic Association, Inc. (The); www.ntma.com.
153. NWFA - National Wood Flooring Association; www.nwfa.org.
154. NWRA - National Waste & Recycling Association; www.wasterecycling.org.
155. PCI - Precast/Prestressed Concrete Institute; www.pci.org.
156. PDI - Plumbing & Drainage Institute; www.pdionline.org.
157. PLASA - PLASA; www.plasa.org.
158. PLIB - Pacific Lumber Inspection Bureau; www.plib.org.
159. PVCPA - Uni-Bell PVC Pipe Association; www.uni-bell.org.
160. RCSC - Research Council on Structural Connections; www.boltcouncil.org.
161. RFCI - Resilient Floor Covering Institute; www.rfci.com.
162. RIS - Redwood Inspection Service; (see WWPA).

163. SAE - SAE International; www.sae.org.
164. SCTE - Society of Cable Telecommunications Engineers; www.scte.org.
165. SDI - Steel Deck Institute; www.sdi.org.
166. SDI - Steel Door Institute; www.steeldoor.org.
167. SEFA - Scientific Equipment and Furniture Association (The); www.sefalabs.com.
168. SEI/ASCE - Structural Engineering Institute/American Society of Civil Engineers; (see ASCE).
169. SIA - Security Industry Association; www.securityindustry.org.
170. SJI - Steel Joist Institute; www.steeljoist.org.
171. SMA - Screen Manufacturers Association; www.smainfo.org.
172. SMACNA - Sheet Metal and Air Conditioning Contractors' National Association; www.smacna.org.
173. SMPTE - Society of Motion Picture and Television Engineers; www.smpte.org.
174. SPFA - Spray Polyurethane Foam Alliance; www.sprayfoam.org.
175. SPIB - Southern Pine Inspection Bureau; www.spib.org.
176. SPRI - Single Ply Roofing Industry; www.spri.org.
177. SRCC - Solar Rating & Certification Corporation; www.solar-rating.org.
178. SSINA - Specialty Steel Industry of North America; www.ssina.com.
179. SSPC - SSPC: The Society for Protective Coatings; (see AMPP).
180. STI/SPFA - Steel Tank Institute/Steel Plate Fabricators Association; www.steeltank.com.
181. SWI - Steel Window Institute; www.steelwindows.com.
182. SWPA - Submersible Wastewater Pump Association; www.swpa.org.
183. TCA - Tilt-Up Concrete Association; www.tilt-up.org.
184. TCNA - Tile Council of North America, Inc.; www.tcnatile.com.
185. TEMA - Tubular Exchanger Manufacturers Association, Inc.; www.kbcdco.tema.org.
186. TIA - Telecommunications Industry Association; www.tiaonline.org.
187. TMS - The Masonry Society; www.masonrysociety.org.
188. TPI - Truss Plate Institute; www.tpinst.org.
189. TPI - Turfgrass Producers International; www.turfgrasssod.org.
190. TRI - Tile Roofing Industry Alliance; www.tileroofing.org.
191. ULSE - UL Standards & Engagement Inc.; www.ulse.org.
192. UL - UL Solutions Inc.; www.ul.com.
193. USAV - USA Volleyball; www.usavolleyball.org.
194. USGBC - U.S. Green Building Council; www.usgbc.org.
195. USITT - United States Institute for Theatre Technology, Inc.; www.usitt.org.
196. WA - Wallcoverings Association; www.wallcoverings.org.
197. WCLIB - West Coast Lumber Inspection Bureau; (see PLIB).
198. WCMA - Window Covering Manufacturers Association; www.wcmanet.org.
199. WDMA - Window & Door Manufacturers Association; www.wdma.com.
200. WI - Woodwork Institute; www.woodworkinstitute.com.
201. WSRCA - Western States Roofing Contractors Association; www.wsrca.com.
202. WWPA - Western Wood Products Association; www.wwpa.org.

C. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the entities in the following list. This information is believed to be accurate as of the date of the Contract Documents.

1. IAPMO - International Association of Plumbing and Mechanical Officials; www.iapmo.org.
2. ICC - International Code Council; www.iccsafe.org.
3. ICC-ES - ICC Evaluation Service, LLC; www.icc-es.org.

D. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the entities in the following list. Information is subject to change and is up to date as of the date of the Contract Documents.

1. CPSC - U.S. Consumer Product Safety Commission; www.cpsc.gov.
2. DOC - U.S. Department of Commerce; www.commerce.gov.
3. DOD - U.S. Department of Defense; www.defense.gov.
4. DOE - U.S. Department of Energy; www.energy.gov.
5. DOJ - U.S. Department of Justice; www.ojp.usdoj.gov
6. DOS - U.S. Department of State; www.state.gov.
7. EPA - United States Environmental Protection Agency; www.epa.gov.
8. FAA - Federal Aviation Administration; www.faa.gov.
9. GPO - U.S. Government Publishing Office; www.gpo.gov.
10. GSA - U.S. General Services Administration; www.gsa.gov.
11. HUD - U.S. Department of Housing and Urban Development; www.hud.gov.
12. LBNL - Lawrence Berkeley National Laboratory; Energy Technologies Area; www.lbl.gov/.
13. NIST - National Institute of Standards and Technology; www.nist.gov.
14. OSHA - Occupational Safety & Health Administration; www.osha.gov.
15. TRB - Transportation Research Board; National Cooperative Highway Research Program; The National Academies; www.trb.org.
16. USACE - U.S. Army Corps of Engineers; www.usace.army.mil.
17. USDA - U.S. Department of Agriculture; Agriculture Research Service; U.S. Salinity Laboratory; www.ars.usda.gov.
18. USDA - U.S. Department of Agriculture; Rural Utilities Service; www.usda.gov.
19. USP - U.S. Pharmacopeial Convention; www.usp.org.
20. USPS - United States Postal Service; www.usps.com.

E. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the standards and regulations in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.

1. CFR - Code of Federal Regulations; Available from U.S. Government Publishing Office; www.govinfo.gov.
2. DOD - U.S. Department of Defense; Military Specifications and Standards; Available from DLA Document Services; www.dsp.dla.mil/Specs-Standards/.
3. DSCC - Defense Supply Center Columbus; (see FS).
4. FED-STD - Federal Standard; (see FS).
5. FS - Federal Specification; Available from DLA Document Services; www.dsp.dla.mil/Specs-Standards/.

    a. Available from Defense Standardization Program; www.dsp.dla.mil.
    b. Available from U.S. General Services Administration; www.gsa.gov.
    c. Available from National Institute of Building Sciences/Whole Building Design Guide; www.wbdg.org.

6. MILSPEC - Military Specifications and Standards; (see DOD).
7. USAB - United States Access Board; www.access-board.gov.
8. USATBCB - U.S. Architectural & Transportation Barriers Compliance Board; (see USAB).

F. State Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the entities in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.

1. BEARHFTI; California Bureau of Electronic and Appliance Repair, Home Furnishings and Thermal Insulation; (see BHGS).
2. BHGS; State of California Bureau of Household Goods and Services; (Formerly: California Bureau of Electronic and Appliance Repair, Home Furnishings and Thermal Insulation); www.bhgs.dca.ca.gov.
3. CCR; California Code of Regulations; Office of Administrative Law; California Title 24 Energy Code; www.oal.ca.gov/publications/ccr/.
4. CDPH; California Department of Public Health; Indoor Air Quality Program; www.cdph.ca.gov/Programs/CCDPHP/DEODC/EHLB/IAQ/Pages/Main-Page.aspx.
5. CPUC; California Public Utilities Commission; www.cpuc.ca.gov.
6. SCAQMD; South Coast Air Quality Management District; www.aqmd.gov.
7. TFS; Texas A&M Forest Service; Sustainable Forestry and Economic Development; https://tfsweb.tamu.edu/.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 014339 - MOCKUPS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Integrated exterior mockups.

B. Related Requirements:

1. Section 014000 "Quality Requirements" for quality assurance requirements for aesthetic and workmanship mockups specified in other Sections.

1.2 DEFINITIONS

A. Integrated Exterior Mockups: Mockups of the exterior envelope constructed on-site as freestanding temporary built elements or part of permanent construction, consisting of multiple products, assemblies, and subassemblies.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Meet with Owner, Architect, testing and inspecting agency representative, and installers of major systems whose Work is included in integrated exterior mockups.
2. Review coordination of equipment and furnishings provided by the Owner for room mockups.
3. Review locations and extent of mockups.
4. Review testing procedures to be performed on mockups.
5. Review and finalize schedule for mockups, and verify availability of materials, personnel, equipment, and facilities needed to complete mockups and maintain schedule for the Work.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Shop Drawings: For integrated exterior mockups.

1. Include plans, elevations, sections, and mounting attachment and support details.
2. Indicate manufacturer and model number of individual components, subassemblies, and assemblies.
3. Include site location drawing indicating orientation of mockup.

4. Revise and resubmit Shop Drawings to reflect approved modifications in details and component interfaces resulting from changes made during testing procedures.

1.5 QUALITY ASSURANCE

A. Build mockups to do the following:

1. Verify selections made under Sample submittals.
2. Demonstrate aesthetic effects.
3. Demonstrate the qualities of products and workmanship.
4. Demonstrate acceptable coordination between components and systems.
5. Perform preconstruction testing, such as window air- and water-leakage testing.

B. Fabrication: Before fabricating or installing portions of the Work requiring mockups, build mockups for each form of construction and finish required. Use materials and installation methods as required for the Work.

1. Build mockups of size indicated.
2. Build mockups in location indicated or, if not indicated, as directed by Architect.
3. Employ supervisory personnel who will oversee mockup construction. Employ workers who will be employed to perform same tasks during the construction at Project.
4. Demonstrate the proposed range of aesthetic effects and workmanship.
5. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
6. Demolish and remove mockups when directed unless otherwise indicated.

C. Notifications:

1. Notify Architect seven days in advance of the dates and times when mockups will be constructed.
2. Notify Architect 14 days in advance of the dates and times when mockups will be tested.
3. Allow seven days for initial review and each re-review of each mockup.

D. Approval: Obtain Architect's approval of mockups before starting fabrication or construction of corresponding Work.

1. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.
2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.6 COORDINATION

A. Coordinate schedule for construction of mockups, so construction, testing, and review of mockups do not impact Project schedule.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Structural Performance:

1. Seismic Performance: Mockups and support structure to withstand the effects of earthquake motions determined in accordance with ASCE/SEI 7.
2. Wind Loads: As indicated on Drawings.

B. Mockup Testing Performance Requirements: Perform tests using design pressures and performance criteria indicated for assemblies and products that are specified in other Sections and incorporated into integrated exterior mockups.

2.2 INTEGRATED EXTERIOR MOCKUPS

A. Construct integrated exterior mockups according to approved mockup Shop Drawings. Construct mockups to demonstrate constructability, coordination of trades, and sequencing of Work; and to ensure materials, components, subassemblies, assemblies, and interfaces integrate into a system complying with indicated performance and aesthetic requirements.

B. Design and construct foundation and superstructure to support free-standing integrated exterior mockups.

C. Build integrated exterior mockups using installers and construction methods that will be used in completed construction.

D. Use specified products that have been approved by Architect. Coordinate installation of materials and products specified in individual Specification Sections that include Work included in integrated exterior mockups.

E. The Work of integrated exterior mockups includes, but is not limited to, the following:

1. Thermal insulation.
2. Through-wall flashing.
3. Flashing and sheet metal trim.
4. Joint sealants.
5. Glazed storefront.
6. Aluminum curtain wall.
7. Glazing.

F. Photographic Documentation: Document construction of integrated exterior mockups with photographs in accordance with Section 013233 "Photographic Documentation." Provide photographs showing details of interface of different materials and assemblies.

1. Document testing procedures, including water leakage and other deficiencies. Photograph modifications to component interfaces intended to correct deficiencies.

G. Provide and document modifications to construction details and interfaces between components and systems required to properly sequence the Work, or to pass performance testing requirements. Obtain Architect's approval for modifications.

H. Retain approved mockups constructed in place. Incorporate fully into the Work.

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 014535 - SPECIAL INSPECTIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 GENERAL REQUIREMENTS

A. Perform Special Inspections in accordance with the Schedule of Special Inspections and Chapter 17 of ICC IBC. The Schedule of Special Inspections are included as an attachment to this specification. Special Inspections are to be performed by an independent third party and are intended to ensure that the work of the Prime Contractor is in accordance with the Contract Documents and applicable building codes.

1.3 DEFINITIONS

A. Continuous Special Inspections: Continuous Special Inspections is the constant monitoring of specific tasks by a special inspector. These inspections must be carried out continuously over the duration of the particular tasks

B. Perform: Perform these Special Inspections tasks for each welded joint or member.

C. Observe: Observe these Special Inspections items on a periodic daily basis. Operations need not be delayed pending these inspections.

D. Special Inspector (SI): A qualified person approved by the Owner as having the competence necessary to inspect a particular type of construction requiring Special Inspections. The SI must be an independent third party hired directly by the Prime Contractor.

E. Associate Special Inspector (ASI): A qualified person who assists the SI in performing Special Inspections but must perform inspection under the direct supervision of the SI and cannot perform inspections without the SI on site.

F. Third Party: A Special inspector must not be an employee of the Contractor or of any Sub-Contractor performing the work to be inspected.

G. Special Inspector of Record (SIOR): A licensed engineer in responsible charge of supervision of all special inspectors for the project and approved by the Owner. The SIOR must be an independent third party entity hired directly by the Prime Contractor.

H. Contractor’s Quality Control (QC) Manager: An individual retained by the Prime Contractor and qualified in accordance with the Section 01 40 00 QUALITY REQUIREMENTS having the overall responsibility for the Contractor's QC organization.

I. Structural Engineer of Record (SER): A registered design professional contracted by the Owner as an A/E responsible for the overall design and review of submittal documents prepared by others. The SER is registered or licensed to practice their respective design profession as defined by the statutory requirements of the professional registration laws in the state in which the design professional works. The SER is also referred to as the Engineer of Record (EOR) in design code documents.

J. Schedule of Special Inspections (SSI): A schedule which lists each of the required Special Inspections, the extent to which each Special Inspection is to be performed, and the required frequency for each in accordance with ICC IBC Chapter 17. This schedule is included at the end of this specification.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Preconstruction Submittals:

1. SIOR Letter of Acceptance.
2. Special Inspections Project Manual.
3. Special Inspections Agency’s Written NDT Practices with method and evidence of regular equipment calibration where applicable.

C. Test Reports:

1. Special Inspections Daily Reports.
2. Special Inspections Biweekly Reports.

D. Certificates:

1. AISC Certified Steel Fabricator
2. Certificate of Compliance
3. Special Inspector Qualifications
4. Qualification Records for NDT technicians

1.5 SPECIAL INSPECTOR QUALIFICATIONS

A. Submit qualifications for each special inspector and the special inspector of record.

1. Steel Construction and High Strength Bolting

a. Special Inspector:

1) ICC Structural Steel and Bolting Special Inspector certificate with one year of related experience, or
2) Licensed Professional Engineer with three years of related experience.

b. Associate Special Inspector: Engineer-in-Training with one year of related experience.

2. Welding Structural Steel

    a. Special Inspector:

        1) ICC Structural Welding Special Inspector certificate with one year of related experience, or
        2) b. AWS Certified Welding Inspector

    b. Associate Special Inspector: AWS Certified Associate Welding Inspector

3. Nondestructive Testing of Welds:

    a. Special Inspector: NDT Level III Certificate.

    b. Associate Special Inspector: NDT Level II Certificate plus one year of related experience.

4. Cold Formed Steel Framing:

    a. Special Instructor:

        1) ICC Structural Steel and Bolting Special Inspector certificate with one year of related experience, or
        2) ICC Commercial Building Inspector with one year of experience, or
        3) Licensed Professional Engineer with three years related experience

    b. Associate Special Inspector: Engineer-In-Training with one year of related experience.

5. Concrete Construction:

    a. Special Inspector:

        1) ICC Reinforced Concrete Special Inspector Certificate with one year of related experience, or
        2) ACI Concrete Construction Special Inspector, or
        3) Licensed Professional Engineer with three years of related experience

    b. Associate Special Instructor:

        1) ACI Concrete Construction Special Inspector in Training, or
        2) Engineer-In-Training with one year of related experience

6. Masonry Construction:

    a. Special Inspector:

        1) ICC Structural Masonry Special Inspector Certificate with one year of related experience, or
        2) Licensed Professional Engineer with three years of related experience.

b. Associate Special Inspector: Engineer-in-Training with one year experience of related experience.

7. Wood:

a. Special Inspector:

1) ICC Commercial Building Inspector Certificate with one year of related experience, or
2) ICC Residential Building Inspector with on year of experience, or
3) Licensed Professional Engineer with three years of related experience.

b. Associate Special Inspector: Engineer-in-Training with one year experience of related experience.

8. Verification of Site Soil Condition, Fill Placement and Load-Bearing Requirements

a. Special Inspector:

1) ICC Soils Special Inspector Certificate with one year of related experience, or
2) NICET Soils Technician Level II Certificate in Construction Material Testing, or
3) Geologist-In-Training with three years of related experience, or
4) Licensed Professional Engineer with three years of related experience.

b. Associate Special Inspector:

1) NICET Soils Technician Level I Certificate in Construction Material Testing with one year of related experience, or
2) Engineer-In-Training with one year of related experience

9. Deep Foundations:

a. Special Inspector:

1) NICET Soils Technician Level II Certificate in Construction Material Testing, or
2) Geologist-In-Training with three years of related experience, or
3) Licensed Professional Engineer with three years of related experience.

b. Associate Special Inspector:

1) NICET Soils Technician Level I Certificate in Construction Material Testing with one year of related experience, or
2) NICET Geotechnical Engineering Technician Level I Construction or Generalist Certificate with one year of related experience, or
3) Engineer-In-Training with one year of related experience.

10. Exterior Insulation and Finish System (EIFS):

a. Special Inspector:

1) AWCI EIFS Inspector Certificate, or
2) Exterior Design Institute Certificate, or
3) Licensed Professional Engineer or Architect with related experience.

b. Associate Special Inspector: Engineer-In-Training with one year of related experience.

11. Special Inspector of Record (SIOR): Registered Professional Engineer with five years of related experience.

PART 2 - PRODUCTS

2.1 FABRICATOR SPECIAL INSPECTIONS

A. Special Inspections of fabricator's work performed in the fabricator's shop is required to be inspected in accordance with the Schedule of Special Inspections unless the fabricator is certified by the approved agency to perform such work without Special Inspections. Submit the following certification [certifications] to the Owner for information to allow work performed in the fabricator's shop to not be subjected to Special Inspections.

AISC Certified Steel Fabricator.
Truss Plate Institute (TPI) steel truss plant quality assurance program certification.
Truss Plate Institute (TPI) wood truss plant quality assurance program certification.
International Accreditation Service, AC472 Accreditation
Steel Joist Institute Membership
Precast Concrete Institute (PCI) Certified Plant, Group C

At the completion of fabrication, submit a certificate of compliance, to be included with the comprehensive final report of Special Inspections, stating that the materials supplied and work performed by the fabricator are in accordance with the construction documents.

PART 3 - EXECUTION

3.1 RESPONSIBILITIES

A. Special Inspector of Record:

1. Supervise all Special Inspectors required by the Contract Documents and the IBC.
2. Submit a SIOR Letter of Acceptance to the Owner attesting to acceptance of the duties of SIOR, signed and sealed by the SIOR.
3. Verify the qualifications of all of the Special Inspectors.
4. Verify the qualifications of fabricators.
5. Submit Special Inspections agency's written NDT practices for the monitoring and control of the agency's operations to include the following:

a. The agency's procedures for the selection and administration of inspection personnel, describing the training, experience and examination requirements for qualifications and certification of inspection personnel.

b. The agency's inspection procedures, including general inspection, material controls, and visual welding inspection.

6. Submit qualification records for nondestructive testing (NDT) technicians designated for the project.
7. Submit NDT procedures and equipment calibration records for NDT to be performed and equipment to be used for the project.

8. Prepare a Special Inspections Project Manual, which must cover the following:

   a. Roles and responsibilities of the following individuals during Special Inspections: SIOR, SI, ASI, General Contractor's QC Manager and SER.
   b. Organizational chart or communication plan, indicating lines of communication.
   c. Contractor's internal plan for scheduling inspections. Address items such as timeliness of inspection requests, who to contact for inspection requests, and availability of alternate inspectors.
   d. Propose forms or templates to be used by SI and SIOR to document inspections.
   e. Indicate procedures for tracking nonconforming work and verification that corrective work is complete.
   f. Indicate how the SIOR and SI will participate in weekly QC meetings.
   g. Indicate how Special Inspections of shop fabricated items will be handled when the fabricator's shop is not certified in accordance with paragraph FABRICATOR SPECIAL INSPECTIONS.
   h. Include a section in the manual that covers each specific item requiring Special Inspections that is indicated on the Schedule of Special Inspections. Provide names and qualifications of each special inspector who will be performing the Special Inspections for each specific item. Provide detail on how the Special Inspections are to be carried out for each item so that the expectations are clear for the General Contractor and the Subcontractor performing the work.

   Make a copy of the Special Inspections Project Manual available on the job site during construction. Submit a copy of the Special Inspections Project Manual for approval.

9. Attend coordination and mutual understanding meeting where the information in the Special Inspections Project Manual will be reviewed to verify that all parties have a clear understanding of the Special Inspections provisions and the individual duties and responsibilities of each party.
10. Maintain a 3-ring binder for the Special Inspector's daily and biweekly reports and the Special Inspections Project Manual. This file must be located in a conspicuous place in the project trailer/office to allow review by the Owner and the SER.
11. Submit a copy of the Special Inspector's daily reports to the QC Manager.
12. Discrepancies that are observed during Special Inspections must be reported to the QC Manager for correction. If discrepancies are not corrected before the special inspector leaves the site the observed discrepancies must be documented in the daily report.
13. Submit a biweekly Special Inspections report until all work requiring Special Inspections is complete. A report is required for each biweekly period in which Special Inspections activity occurs, and must include the following:

    a. A brief summary of the work performed during the reporting time frame.
    b. Changes and discrepancies with the drawings, specifications that were observed during the reporting period.
    c. Discrepancies which were resolved or corrected.

d. A list of nonconforming items requiring resolution.
e. All applicable test results including nondestructive testing reports.

B. Special Inspectors:

1. Inspect all elements of the project for which the special inspector is qualified to inspect and are identified in the Schedule of Special Inspections.
2. Attend preparatory phase meetings related to the Definable Feature of Work (DFOW) for which the special inspector is qualified to inspect.
3. Submit Special Inspections agency's written NDT practices for the monitoring and control of the agency's operations to include the following:

   a. The agency's procedures for the selection and administration of inspection personnel, describing the training, experience and examination requirements for qualifications and certification of inspection personnel.
   b. The agency's inspection procedures, including general inspection, material controls, and visual welding inspection.

4. Submit qualification records for nondestructive testing (NDT) technicians designated for the project.
5. Submit NDT procedures and equipment calibration records for NDT to be performed and equipment to be used for the project.
6. Submit a copy of the daily reports to the QC Manager.
7. Report discrepancies that are observed during Special Inspections to the QC Manager for correction. If discrepancies are not corrected before the special inspector leaves the site the observed discrepancies must be documented in the daily report.
8. Submit a biweekly Special Inspection Report until all inspections are complete. A report is required for each biweekly period in which Special Inspections activity occurs, and must include the following:

   a. A brief summary of the work performed during the reporting time frame.
   b. Changes and discrepancies with the drawings, specifications and mechanical or electrical component certification that were observed during the reporting period.
   c. Discrepancies which were resolved or corrected.
   d. A list of nonconforming items requiring resolution.
   e. All applicable test results including nondestructive testing reports.

3.2 DETECTIVE WORK

A. Check work as it progresses, but failure to detect any defective work or materials must in no way prevent later rejection if defective work or materials are discovered, nor obligate the Owner to accept such work.

END OF SECTION

SCHEDULE OF SPECIAL INSPECTIONS

Reference UFGS 01 45 35 for all requirements not noted as part of this schedule.

INSPECTION DEFINITIONS:

PERFORM: Perform these tasks for each weld, fastener or bolted connection, and noted verification.

OBSERVE: Observe these items randomly during the course of each work day to insure that applicable requirements are being met. Operations need not be delayed pending these inspections at contractor's risk.

DOCUMENT: Document, with a report, that the work has been performed in accordance with the contract documents. This is in addition to any other reports required in the Special Inspections guide specification.

CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

The Seismic Design Category for this project is: ☐ A, ☒ B, ☐ C, ☐ D, ☐ E, ☐ F (check appropriate box)

STRUCTURAL - STEEL – WELDING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

STEEL INSPECTION PRIOR TO WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.4-1		
TASK	INSPECTION TYPE[1]	DESCRIPTION
1. Verify that the welding procedures specification (WPS) is available	**PERFORM**	
2. Verify manufacturer certifications for welding consumables are available	**PERFORM**	
3. Verify material identification	**PERFORM**	Type and grade.
4. Welder Identification System	**PERFORM**	The fabricator or erector, as applicable, shall maintain a system by which a welder who has welded a joint or member can be identified. Stamps, if used, shall be the low-stress type.
5. Fit-up of groove welds (including joint geometry)	OBSERVE	✓ Joint preparation ✓ Dimensions (alignment, root opening, root face, bevel) ✓ Cleanliness (condition of steel surfaces) ✓ Tacking (tack weld quality and location) ✓ Backing type and fit (if applicable)
6. Configuration and finish of access holes	OBSERVE	
7. Fit-up of fillet welds	OBSERVE	✓ Dimensions (alignment, gaps at root) ✓ Cleanliness (condition of steel surfaces) ✓ Tacking (tack weld quality and location)
STEEL INSPECTION DURING WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.4-2		
TASK	INSPECTION TYPE	DESCRIPTION
8. Use of qualified welders	**PERFORM**	Welding by welders, welding operators, and tack welders who are qualified in conformance with requirements.
9. Control and handling of welding consumables	OBSERVE	✓ Packaging ✓ Electrode atmospheric exposure control
10. No welding over cracked tack welds	OBSERVE	
11. Environmental conditions	OBSERVE	✓ Wind speed within limits ✓ Precipitation and temperature
12. Welding Procedures Specification followed	OBSERVE	✓ Settings on welding equipment ✓ Travel speed ✓ Selected welding materials ✓ Shielding gas type/flow rate ✓ Preheat applied ✓ Interpass temperature maintained (min./max.) ✓ Proper position (F, V, H, OH) ✓ Intermix of filler metals avoided
13. Welding techniques	OBSERVE	✓ Interpass and final cleaning ✓ Each pass within profile limitations ✓ Each pass meets quality requirements

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

STRUCTURAL - STEEL – WELDING SECTION (CONTINUED)

STEEL INSPECTION AFTER WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.4-3		
TASK	INSPECTION TYPE [1]	DESCRIPTION
14. Welds cleaned	OBSERVE	
15. Size, length, and location of all welds	**PERFORM**	Size, length, and location of all welds conform to the requirements of the detail drawings.
16. Welds meet visual acceptance criteria	**PERFORM AND DOCUMENT**	✓ Crack prohibition ✓ Weld/base-metal fusion ✓ Crater cross section ✓ Weld profiles ✓ Weld size ✓ Undercut ✓ Porosity
17. Arc strikes	**PERFORM**	
18. k-area	**PERFORM**	When welding of doubler plates, continuity plates or stiffeners has been performed in the k-area, visually inspect the web k-area for cracks.
19. Backing removed, weld tabs removed and finished, and fillet welds added where required	**PERFORM**	
20. Repair activities	**PERFORM AND DOCUMENT**	
21. Document acceptance or rejection of welded joint or member	**PERFORM**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - STEEL – BOLTING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

STEEL INSPECTION TASKS PRIOR TO BOLTING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.6-1		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Manufacture's certifications available for fastener materials	**PERFORM**	
2. Fasteners marked in accordance with ASTM requirements	OBSERVE	
3. Proper fasteners selected for joint detail (grade, type, bolt length if threads are to be excluded from shear plane)	OBSERVE	
4. Proper bolting procedure selected for joint detail	OBSERVE	
5. Connecting elements, including appropriate faying surface condition and hole preparation, if specified, meet applicable requirements	OBSERVE	
6. Proper storage provided for bolts, nuts, washers, and other fastener components	OBSERVE	
STEEL INSPECTION TASKS DURING BOLTING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.6-2		
TASK	INSPECTION TYPE [1]	DESCRIPTION
7. Fastener assemblies of suitable condition, placed in all holes and washers (if required) are positioned as required	OBSERVE	
8. Joint brought to the snug-tight condition prior to pretensioning operation	OBSERVE	
9. Fastener component not turned by the wrench prevented from rotating	OBSERVE	
10. Bolts are pretensioned in accordance with RCSC Specification, progressing systematically from the most rigid point toward the free edges	OBSERVE	
STEEL INSPECTION TASKS AFTER BOLTING – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.2.1, AISC 360-10: Table C-N5.6-3		
TASK	INSPECTION TYPE [1]	DESCRIPTION
11. Document acceptance or rejection of all bolted connections	**DOCUMENT**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - STEEL - NON DESTRUCTIVE TESTING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

NONDESTRUCTIVE TESTING OF WELDED JOINTS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Section N5.5		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Use of qualified nondestructive testing personnel	**PERFORM**	Visual weld inspection and nondestructive testing (NDT) shall be conducted by personnel qualified in accordance with AWS D1.8 clause 7.2
2. Welded joints subject to fatigue	OBSERVE	Dye penetrant testing (DT) and Ultrasonic testing (UT) shall be performed on 100% of welded joints identified on contract drawings as being subject to fatigue.

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

STRUCTURAL - STEEL – AISC 341 REQUIREMENTS (SEISMIC PROVISIONS) SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

NONDESTRUCTIVE TESTING OF WELDED JOINTS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 341-16: Section J6.2		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. CJP groove welds	OBSERVE	Dye penetrant testing (DT) and ultrasonic testing (UT) shall be performed on 100% of CJP groove welds for materials greater than 5/16" thick (8mm).
2. Beam cope and access hole.	OBSERVE	At welded splices and connections, thermally cut surfaces of beam copes and access holes shall be tested using magnetic particle testing (MT) or dye penetrant testing (DT), when the flange thickness exceeds 1 1/2 in. for rolled shapes, or when the web thickness exceeds 1 1/2 in. for built-up shapes.
3. K-area NDT (AISC 341)	**PERFORM**	Where welding of doubler plates, continuity plates or stiffeners has been performed in the k-area, the web shall be tested for cracks using magnetic particle testing (MT). The MT inspection area shall include the k-area base metal within 3-inches of the weld. The MT shall be performed no sooner than 48 hours following completion of the welding.
4. Placement of reinforcing or contouring fillet welds	**DOCUMENT**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - STEEL - COMPOSITE CONSTRUCTION [1]

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

COMPOSITE CONSTRUCTION PRIOR TO PLACING CONCRETE – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table N6.1, AISC 341-16: Table J9.1		
TASK	INSPECTION TYPE [2]	DESCRIPTION
1. Placement and installation of steel headed stud anchors	**PERFORM**	
2. Material identification of reinforcing steel (Type/Grade)	OBSERVE	
3. Determination of carbon equivalent for reinforcing steel other than ASTM A706	OBSERVE	
4. Proper reinforcing steel size, spacing, clearances, support, and orientation	OBSERVE	
5. Reinforcing steel has not been re-bent in the field	OBSERVE	
6. Reinforcing clearances have been provided	OBSERVE	
7. Reinforcing steel has been tied and supported as required	OBSERVE	
8. Composite member has required size	OBSERVE	

END SECTION

STRUCTURAL - STEEL - OTHER INSPECTIONS

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

OTHER STEEL INSPECTIONS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 341-16: Tables J8.1 & J10.1		
TASK	INSPECTION TYPE [2]	DESCRIPTION
1. Anchor rods and other embedments supporting structural steel	**PERFORM**	Verify the diameter, grade, type, and length of the anchor rod or embedded item, and the extent or depth of embedment prior to placement of concrete.
2. Fabricated steel or erected steel frame	OBSERVE	Verify compliance with the details shown on the construction documents, such as braces, stiffeners, member locations and proper application of joint details at each connection.
3. Reduced beam sections (RBS) where/if occurs	**DOCUMENT**	✓ Contour and finish ✓ Dimensional tolerances
4. Protected zones	**DOCUMENT**	No holes or unapproved attachments made by fabricator or erector
5. H-piles where/if occurs	**DOCUMENT**	No holes or unapproved attachments made by the responsible contractor

END SECTION

---

[1] See Concrete Construction Section for all concrete related inspection of composite steel construction.

[2] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - COLD-FORMED METAL DECK - PLACEMENT SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

METAL DECK INSPECTION PRIOR TO DECK PLACEMENT – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.1		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Verify compliance of materials (deck and all deck accessories) with construction documents, including profiles, material properties, and base metal thickness	**PERFORM**	
2. Document acceptance or rejection of deck and deck accessories	**DOCUMENT**	
METAL DECK INSPECTION DURING DECK PLACEMENT – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.2		
TASK	INSPECTION TYPE [1]	DESCRIPTION
3. Verify compliance of deck and all deck accessories installation with construction documents	**PERFORM**	
4. Verify deck materials are represented by the mill certifications that comply with the construction documents	**PERFORM**	
5. Document acceptance or rejection of installation of deck and deck accessories	**DOCUMENT**	
METAL DECK INSPECTION AFTER DECK PLACEMENT – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.3		
TASK	INSPECTION TYPE [1]	DESCRIPTION
6. Welding procedure specification (WPS) available	**PERFORM**	
7. Manufactures certifications for welding consumables available	OBSERVE	
8. Material identification (type/grade)	OBSERVE	
9. Check welding equipment	OBSERVE	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - COLD-FORMED METAL DECK – WELDING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

METAL DECK INSPECTION DURING WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.4		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Use of qualified welders	OBSERVE	
2. Control and handling of welding consumables	OBSERVE	
3. Environmental conditions (wind speed, moisture, temperature)	OBSERVE	
4. WPS followed	OBSERVE	
METAL DECK INSPECTION AFTER WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.5		
TASK	INSPECTION TYPE [1]	DESCRIPTION
5. Verify size and location of welds, including support, sidelap, and perimeter welds.	**PERFORM**	
6. Welds meet visual acceptance criteria	**PERFORM**	
7. Verify repair activities	**PERFORM**	
8. Document acceptance or rejection of welds	**DOCUMENT**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - COLD-FORMED METAL DECK – FASTENING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

METAL DECK INSPECTION BEFORE MECHANICAL FASTENING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.6		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Manufacturer installation instructions available for mechanical fasteners	OBSERVE	
2. Proper tools available for fastener installation	OBSERVE	
METAL DECK INSPECTION DURING MECHANICAL FASTENING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.7		
TASK	INSPECTION TYPE [1]	DESCRIPTION
3. Fasteners are positioned as required	OBSERVE	
4. Fasteners are installed in accordance with manufacturer's instructions	OBSERVE	
METAL DECK INSPECTION AFTER MECHANICAL FASTENING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.8		
TASK	INSPECTION TYPE [1]	DESCRIPTION
5. Check spacing, type, and installation of support fasteners	**PERFORM**	
6. Check spacing, type, and installation of sidelap fasteners	**PERFORM**	
7. Check spacing, type, and installation of perimeter fasteners	**PERFORM**	
8. Verify repair activities	**PERFORM**	
9. Document acceptance or rejection of mechanical fasteners	**DOCUMENT**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - LIGHT GAUGE STEEL FRAMING AND/OR LIGHT GAUGE TRUSSES SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

LIGHT GAUGE STEEL CONSTRUCTION AND CONNECTIONS – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.2.2, 1705.11.2, 1705.11.3, UFC 4 023 03		
TASK	INSPECTION TYPE[1]	DESCRIPTION
1. Trusses spanning 60-feet or greater where/if applies	**PERFORM**	Verify that temporary and permanent truss restraint/bracing is installed in accordance with approved truss submittal package.
2. Welded connections (seismic and/or wind resisting system)	OBSERVE	Visually inspect all welds composing part of the main wind or seismic force resisting system, including shearwalls, braces, collectors (drag struts), and hold-downs.
3. Connections (seismic and/or wind resisting system)	OBSERVE	Visually inspect all screw attachment, bolting, anchoring and other fastening of components within the main wind or seismic force resisting system, including roof deck, roof framing, exterior wall covering, wall to roof/floor connections, braces, collectors (drag struts) and hold-downs.
4. Cold-formed steel (progressive collapse resisting system where/if applies)	OBSERVE	Verify proper welding operations, screw attachment, bolting, anchoring and other fastening of components within the progressive collapse resisting system, including horizontal tie force elements, vertical tie force elements and bridging elements (UFC 4 023 03).

END SECTION

STRUCTURAL - OPEN-WEB STEEL JOISTS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

OPEN-WEB STEEL JOISTS AND JOIST GIRDERS – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC TABLE 1705.2.3		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Installation of open-web steel joists and joist girders	OBSERVE	✓ End connections – welded or bolted ✓ Bridging – horizontal and diagonal

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

STRUCTURAL - CONCRETE CONSTRUCTION SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

CONCRETE CONSTRUCTION, INCLUDING COMPOSITE DECK – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC TABLE 1705.3 (ACI 318 REFERENCES NOTED IN IBC TABLE)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Inspect reinforcement, including prestressing tendons, and verify placement.	OBSERVE	Verify prior to placing concrete that reinforcing is of specified type, grade and size; that it is free of oil, dirt and unacceptable rust; that it is located and spaced properly; that hooks, bends, ties, stirrups and supplemental reinforcement are placed correctly; that lap lengths, stagger and offsets are provided; and that all mechanical connections are installed per the manufacturer's instructions and/or evaluation report.
2. Cast in place anchors and post installed drilled anchors (downward inclined)	OBSERVE	Verify prior to placing concrete that cast in place anchors and post installed drilled anchors have proper embedment, spacing and edge distance.
3. Post-installed adhesive anchors in horizontal or upward inclined orientations	**CONTINUOUS AND DOCUMENT**	✓ Inspect as required per approved ICC-ES report ✓ Verify that installer is certified for installation of horizontal and overhead installation applications ✓ Inspect proof loading as required by the contract documents
4. Verify use of required mix design	OBSERVE	Verify that all mixes used comply with the approved construction documents
5. Prior to concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete	**CONTINUOUS**	At the time fresh concrete is sampled to fabricate specimens for strength test verify these tests are performed by qualified technicians.
6. Inspect concrete and/or shotcrete placement for proper application techniques	**CONTINUOUS**	Verify proper application techniques are used during concrete conveyance and depositing avoids segregation or contamination. Verify that concrete is properly consolidated.
7. Verify maintenance of specified curing temperature and technique	OBSERVE	Inspect curing, cold weather protection, and hot weather protection procedures.
8. Inspect formwork for shape, location and dimensions of the concrete member being formed.	OBSERVE	

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.
CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

STRUCTURAL - MASONRY CONSTRUCTION SECTION (ALL RISK CATEGORIES)

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

MASONRY CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE AT START OF CONSTRUCTION IBC 1705.4 (ACI 530-13 TABLE 3.1.2 & 3.1.3)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Compliance with approved submittals prior to start	OBSERVE	
2. Proportions of site-mixed mortar.	OBSERVE	
3. Grade and type of reinforcement, anchor bolts, and prestressing tendons and anchorages	OBSERVE	
MASONRY CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE PRIOR TO GROUTING IBC 1705.4 (ACI 530-13 TABLE 3.1.2 & 3.1.3)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
4. Grout space	OBSERVE	
5. Proportions of site-prepared grout and prestressing grout for bonded tendons	OBSERVE	
6. Proportions of site-mixed grout and prestressing grout for bonded tendons	OBSERVE	
7. Placement of masonry units and mortar joints	OBSERVE	
MASONRY CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE DURING CONSTRUCTION IBC 1705.4 (ACI 530-13 TABLE 3.1.2 & 3.1.3)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
8. Size and location of structural elements is in compliance	OBSERVE	
9. Preparation, construction, and protection of masonry during cold weather (temperature below 40°F (4.4°c) or hot weather (temp above 90°F (32.2°C))	OBSERVE	
10. Placement of grout and prestressing grout for bonded tendons	**CONTINUOUS**	
11. Observe preparation of grout specimens, mortar specimens, and/or prisms	OBSERVE	
12. Type, size and placement of reinforcement, connectors, and anchorages, including details of anchorage of masonry to structural members, frames, or other construction	OBSERVE	

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

STRUCTURAL - WOOD CONSTRUCTION – SPECIALTY ITEMS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

WOOD CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.5		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. High-load diaphragms where applicable	OBSERVE	Verify thickness and grade of sheathing, size of framing members at panel edges, nail diameters and length, and the number of fastener lines and that fastener spacing is per approved contract documents.
2. Metal-plate connected wood trusses spanning 60 feet or greater	OBSERVE	Verify that the temporary installation restraint/bracing and the permanent individual truss member restraint/bracing are installed in accordance with the approved truss submittal package

END SECTION

STRUCTURAL - WOOD CONSTRUCTION - SEISMIC & WIND SECTION

THIS SECTION IS APPLICABLE IF BOX IS CHECKED: ☐

WOOD CONSTRUCTION SEISMIC AND WIND – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.11 & 1705.12.2		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Nailing, bolting, anchoring and other fastening of elements of the main wind/seismic force-resisting system	OBSERVE (CONTINUOUS FOR GLUING)	Includes connectors for: shearwall sheathing, roof/floor sheathing, drag struts/collectors (double top plates), braces, hold downs, roof connections to exterior walls.

END SECTION

STRUCTURAL – ISOLATION AND ENERGY DISSIPATION SYSTEMS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

ISOLATION AND ENERGY DISSIPATION SYSTEMS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC TABLE 1705.12.8		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Fabrication and installation	OBSERVE	Verify that fabrication and installation of isolator units and energy dissipation devices conform to manufacturer's recommendations and approved construction documents
2. Testing of seismic isolation Systems in seismically isolated structures		Seismic Isolation Systems in seismically isolated structures shall be tested accordance with ASCE 7, Section 17.8

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

GEOTECHNICAL - SOILS INSPECTION SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

SOILS INSPECTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.6		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Materials below shallow foundations are adequate to achieve the design bearing capacity.	OBSERVE	
2. Excavations are extended to proper depth and have reached proper material	OBSERVE	
3. Perform classification and testing of compacted fill materials	**OBSERVE**	
4. Verify use of proper materials, densities and lift thicknesses during placement and compaction of compacted fill	**CONTINUOUS**	
5. Prior to placement of compacted fill, inspect subgrade and verify that site has been prepared properly.	OBSERVE	During fill placement, the special inspector shall verify that proper materials and procedures are used in accordance with the provisions of the approved geotechnical report

END SECTION

GEOTECHNICAL - DRIVEN DEEP FOUNDATION ELEMENTS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

DEEP DRIVEN FOUNDATION CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.7		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Verify element materials, sizes and lengths comply with requirements	**CONTINUOUS**	
2. Inspect driving operations and maintain complete and accurate records for each element	**CONTINUOUS**	
3. Verify placement locations and plumbness, confirm type and size of hammer, record number of blows per foot of penetration, determine required penetrations to achiever design capacity, record tip and butt elevations and document any damage to foundation element	**CONTINUOUS**	
4. Determine capacities of test elements and conduct additional load tests if required.	**CONTINUOUS**	
5. For steel or concrete elements, perform additional special inspections in accordance with the Steel and Concrete sections in this schedule		

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

GEOTECHNICAL - MICRO PILE FOUNDATIONS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

MICRO PILE FOUNDATIONS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.9		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Record installation equipment used, pile dimensions, tip elevations, final depth, final installation torque and other pertinent installation data as required. The approved geotechnical report and the contract documents shall be used to determine compliance	**CONTINUOUS**	

END SECTION

GEOTECHNICAL - CAST IN PLACE DEEP FOUNDATION ELEMENTS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

CAST IN PLACE DEEP FOUNDATION ELEMENTS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.8		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Inspect drilling operations and maintain complete and accurate records for each element.	**CONTINUOUS**	
2. Verify placement locations and plumbness, confirm element diameters, bell diameters (if applicable), lengths, embedment into bedrock (if applicable) and adequate end-bearing strata capacity. Record concrete or grout volumes	**CONTINUOUS**	For concrete elements, perform additional special inspections in accordance with the Concrete section in this schedule

END SECTION

[1] **CONTINUOUS:** Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

FIRE PROTECTION - SPRAYED FIRE-RESISTANT MATERIALS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

SPRAYED FIRE RESISTANT MATERIALS (SFRM) – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.14		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Substrate condition	OBSERVE	Prior to application, confirm that surfaces have been prepared according to the approved fire-resistance design and manufacturer's instructions.
2. Material thickness	OBSERVE	Verify SFRM thickness according to 2018 IBC 1705.14.4
3. Material density	OBSERVE	Verify SFRM density according to 2018 IBC 1705.14.5
4. Bond strength	OBSERVE	Verify bond strength of cured SFRM according to IBC 1705.14.6

END SECTION

FIRE PROTECTION - MASTIC AND INTUMESCENT COATINGS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

MASTIC AND INTUMESCENT FIRE-RESISTANT COATINGS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.15		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Inspect according to AWCI 12-B and the contract documents	OBSERVE	Inspections shall be performed in accordance with AWCI 12-B, Standard Practice for the Testing and Inspection of Field Applied Thin Film Intumescent Fire-Resistive Materials.

END SECTION

FIRE PROTECTION – FIRE RESISTANT PENETRATIONS AND JOINTS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

FIRE RESISTANT PENETRATIONS AND JOINTS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.17		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Inspections of penetration firestop systems conducted in accordance with ASTM E 2174.	OBSERVE	
2. Inspections of fire-resistant joint systems conducted in accordance with ASTM E 2393	OBSERVE	

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

FIRE PROTECTION – SMOKE CONTROL SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

SMOKE CONTROL – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.18		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Verify device locations and perform leakage testing	OBSERVE	Perform during erection of ductwork and prior to concealment
2. Pressure difference testing, flow measurements and detection and control verification	OBSERVE	Perform prior to occupancy and after sufficient completion

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

ARCHITECTURAL - EXTERIOR INSULATION AND FINISH SYSTEMS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

EXTERIOR INSULATION AND FINISH SYSTEMS (EIFS) – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.16		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Water resistive barrier coating applied over a sheathing substrate.	OBSERVE	Verify that water resistive barrier coating complies with ASTM E 2570.

END SECTION

ARCHITECTURAL – ARCHITECTURAL COMPONENTS

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

ARCHITECTURAL COMPONENTS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.12.5, 1705.12.7		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Erection and fastening of exterior cladding and interior and exterior veneer.	OBSERVE	Verify appropriate materials, fasteners and attachment at commencement of work and at completion. **Inspector Note: Inspection not required if height is less than 30 feet or weight is less than 5psf**
2. Interior and exterior non-load bearing walls	OBSERVE	Verify appropriate materials, fasteners and attachment at commencement of work and at completion. **Inspector Note: Inspection not required if interior non-load bearing walls weigh less than 15psf**
3. Access floors	OBSERVE	Verify that anchorage complies with approved construction documents.
4. Storage racks	OBSERVE	Verify that anchorage complies with approved construction documents. Inspection of post-installed anchors shall comply with approved ICC-ES report. **Inspector Note: Not required for racks less than 8 feet in height**

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

PLUMBING/MECHANICAL/ELECTRICAL DESIGNATED SEISMIC SYSTEMS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

PLUMBING, MECHANICAL AND ELECTRICAL IBC 1705.12.6		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Anchorage of electrical equipment for emergency and standby power systems	OBSERVE	✓ Check for general conformance
2. Anchorage of all other electrical equipment in Seismic Design Categories E and F only (See first page of this schedule for Seismic Design Category)	OBSERVE	✓ Check for general conformance
3. Installation and anchorage of piping designed to carry hazardous materials and their associated mechanical units.	OBSERVE	✓ Check for general conformance
4. Installation and anchorage of vibration isolation systems where the construction documents require a nominal clearance of ¼" or less between support framing and restraint.	OBSERVE	✓ Check for general conformance
5. Verification of clearance between fire sprinkler piping and surrounding mechanical and electrical equipment, including ductwork, piping and their structural supports.	OBSERVE	✓ Check for minimum clearances noted in ASCE7 13.2.3 or a nominal clearance of not less than 3 inches

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

B. Related Requirements:

1. Section 011000 "Summary" for work restrictions and limitations on utility interruptions.

1.2 USE CHARGES

A. Installation, removal, and use charges for temporary facilities to be included in the Contract Sum unless otherwise indicated. Allow other entities engaged in the Project to use temporary services and facilities without cost, including, but not limited to, Architect, testing agencies, and authorities having jurisdiction.

B. Sewer Service: Pay sewer-service use charges for sewer usage by all entities for construction operations.

C. Water from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

D. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

1. Contractor’s Job Trailer: Provide temporary connection with meter. Contractor must pay for electrical charges for job trailer.

E. Snow Removal Charges: The Contractor must pay for all snow removal at work site parking areas A and B.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Site Utilization Plan: Show temporary facilities, temporary utility lines and connections, staging areas, construction site entrances, vehicle circulation, and parking areas for construction personnel.

C. Implementation and Termination Schedule: Within 15 days of date established for commencement of the Work, submit schedule indicating implementation and termination dates of each temporary utility.

D. Project Identification and Temporary Signs: Show fabrication and installation details, including plans, elevations, details, layouts, typestyles, graphic elements, and message content.

E. Erosion- and Sedimentation-Control Plan: Show compliance with requirements of EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.

F. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire-prevention program.

G. Moisture- and Mold-Protection Plan: Describe procedures and controls for protecting materials and construction from water absorption and damage and mold. Describe delivery, handling, storage, installation, and protection provisions for materials subject to water absorption or water damage.

1. Indicate procedures for discarding water-damaged materials, protocols for mitigating water intrusion into completed Work, and requirements for replacing water-damaged Work.
2. Indicate sequencing of work that requires water, such as sprayed fire-resistive materials, plastering, and terrazzo grinding, and describe plans for dealing with water from these operations. Show procedures for verifying that wet construction has dried sufficiently to permit installation of finish materials.
3. Indicate methods to be used to avoid trapping water in finished work.

H. Dust- and HVAC-Control Plan: Submit coordination drawing and narrative that indicates the dust- and HVAC-control measures proposed for use, proposed locations, and proposed time frame for their operation. Include the following:

1. Locations of dust-control partitions at each phase of work.
2. HVAC system isolation schematic drawing.
3. Location of proposed air-filtration system discharge.
4. Waste-handling procedures.
5. Other dust-control measures.

1.4 QUALITY ASSURANCE

A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.

B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

1.5 PROJECT CONDITIONS

A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Portable Chain-Link Fencing: Minimum 2-inch, 0.148-inch-thick, galvanized-steel, chain-link fabric fencing; minimum 6 feet high with galvanized-steel pipe posts; minimum 2-3/8-inch-OD line posts and 2-7/8-inch-OD corner and pull posts, with 1-5/8-inch-OD top and bottom rails. Provide galvanized-steel bases for supporting posts.

B. Fencing Windscreen Privacy Screen: Polyester fabric scrim with grommets for attachment to chain-link fence, sized to height of fence, in color selected by Architect from manufacturer's standard colors.

C. Polyethylene Sheet: Reinforced, fire-resistive sheet, 10-mil minimum thickness, with flame-spread rating of 15 or less in accordance with ASTM E84 and passing NFPA 701 Test Method 2.

D. Insulation: Unfaced mineral-fiber blanket, manufactured from glass, slag wool, or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively.

2.2 TEMPORARY FACILITIES

A. Field Offices:

1. Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.

B. Common-Use Field Office: Of sufficient size to accommodate needs of Owner, Architect, and construction personnel office activities and to accommodate Project meetings specified in other Division 01 Sections. Keep office clean and orderly. Furnish and equip offices as follows:

1. Furniture required for Project-site documents, including file cabinets, plan tables, plan racks, and bookcases.
2. Conference room of sufficient size to accommodate meetings of 10 individuals. Provide electrical power service and 120-V ac duplex receptacles, with no fewer than one receptacle on each wall. Furnish room with conference table, chairs, and 4-foot-square tack and marker boards.
3. Drinking water and private toilet.
4. Heating and cooling equipment necessary to maintain a uniform indoor temperature of 68 to 72 deg F.
5. Lighting fixtures capable of maintaining average illumination of 20 fc at desk height.

C. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.

1. Store combustible materials apart from building.

2.3 EQUIPMENT

A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

B. HVAC Equipment: Provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.

1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
2. Heating, Cooling, and Dehumidifying Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.

PART 3 - EXECUTION

3.1 TEMPORARY FACILITIES, GENERAL

A. Conservation: Coordinate construction and use of temporary facilities with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.

1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. See other Sections for disposition of salvaged materials that are designated as Owner's property.

3.2 INSTALLATION, GENERAL

A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.

1. Locate facilities to limit site disturbance as specified in Section 011000 "Summary."

B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.3 TEMPORARY UTILITY INSTALLATION

A. General: Install temporary service or connect to existing service.

1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.

B. Sewers and Drainage: Provide temporary utilities to remove effluent lawfully.

C. Water Service:

1. Connect to Owner's existing water service facilities. Clean and maintain water service facilities in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.

D. Sanitary Facilities: Provide temporary toilets, wash facilities, safety shower and eyewash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.

1. Use of Permanent Toilets: Use of Owner's existing or new toilet facilities is not permitted.

E. Temporary Heating and Cooling: Provide temporary heating and cooling to maintain work environment, and required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.

1. Provide temporary dehumidification systems when required to reduce ambient and substrate moisture levels to level required to allow installation or application of finishes and their proper curing or drying.

F. Electric Power Service:

1. Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.

G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.

1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

H. Telephone Service: Provide temporary telephone service in common-use facilities for use by all construction personnel. Install WiFi cell phone access equipment land-based telephone line(s) for each field office.

1. At each telephone, post a list of important telephone numbers.

a. Police and fire departments.
b. Ambulance service.
c. Contractor's home office.
d. Contractor's emergency after-hours telephone number.
e. Architect's office.
f. Engineers' offices.
g. Owner's office.
h. Principal subcontractors' field and home offices.

I. Electronic Communication Service: Provide secure WiFi wireless connection to internet with provisions for access by Architect and Owner.

J. Project Computer: Provide a desktop computer in the primary field office adequate for use by Architect and Owner to access Project electronic documents and maintain electronic communications. Equip computer with not less than the following:

1. Processor: Intel Core i5 or i7.

2. Memory: 16 gigabyte.
3. Disk Storage: 1 -terabyte hard-disk drive and combination DVD-RW/CD-RW drive.
4. Display: 24-inch LCD monitor with 256-Mb dedicated video RAM.
5. Full-size keyboard and mouse.
6. Network Connectivity: 10/100BaseT Ethernet.
7. Operating System: Microsoft Windows 10 Professional.
8. Productivity Software:

    a. Microsoft Office Professional, 2013 or higher, including Word, Excel, and Outlook.
    b. Adobe Reader DC.
    c. WinZip 10.0 or higher.

9. Printer: "All-in-one" unit equipped with printer server, combining color printing, photocopying, scanning, and faxing, or separate units for each of these three functions.
10. Internet Service: Broadband modem, router, and ISP, equipped with hardware firewall, providing minimum 10.0 -Mbps upload and 15 -Mbps download speeds at each computer.
11. Internet Security: Integrated software, providing software firewall, virus, spyware, phishing, and spam protection in a combined application.
12. Backup: External hard drive, minimum 2 terrabytes, with automated backup software providing daily backups.

3.4 SUPPORT FACILITIES INSTALLATION

A. Comply with the following:

1. Provide construction for temporary field offices, shops, and sheds located within construction area or within 30 feet of building lines that is noncombustible in accordance with ASTM E136. Comply with NFPA 241.
2. Maintain support facilities until Architect schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

B. Traffic Controls: Comply with requirements of authorities having jurisdiction.

1. Protect existing site improvements to remain, including curbs, pavement, and utilities.
2. Maintain access for fire-fighting equipment and access to fire hydrants.

C. Parking: Use designated areas of Owner's existing parking areas for construction personnel.

D. Storage and Staging: Use designated areas of Project site for storage and staging needs.

E. Dewatering Facilities and Drains: Comply with requirements of authorities having jurisdiction. Maintain Project site, excavations, and construction free of water.

1. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining properties or endanger permanent Work or temporary facilities.
2. Remove snow and ice as required to minimize accumulations.

F. Project Signs: Provide Project signs as indicated. Unauthorized signs are not permitted.

1. Identification Signs: Provide Project identification signs as indicated on Drawings.
2. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.

    a. Provide temporary, directional signs for construction personnel and visitors.

3. Maintain and touch up signs, so they are legible at all times.

G. Waste Disposal Facilities:

1. Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."
2. Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with progress cleaning requirements in Section 017300 "Execution."

H. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.

1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.

I. Temporary Elevator Use: Use of elevators is not permitted.

J. Existing Stair Usage: Use of Owner's existing stairs will be permitted, provided stairs are cleaned and maintained in a condition acceptable to Owner. At Substantial Completion, restore stairs to condition existing before initial use.

1. Provide protective coverings, barriers, devices, signs, or other procedures to protect stairs and to maintain means of egress. If stairs become damaged, restore damaged areas, so no evidence remains of correction work.

3.5 SECURITY AND PROTECTION FACILITIES INSTALLATION

A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.

1. Where access to adjacent properties is required in order to affect protection of existing facilities, obtain written permission from adjacent property owner to access property for that purpose.

B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.

1. Comply with work restrictions specified in Section 011000 "Summary."

C. Temporary Erosion and Sedimentation Control:

1. Provide measures to prevent soil erosion and discharge of soil-bearing water runoff and airborne dust to undisturbed areas and to adjacent properties and walkways, in accordance with erosion- and sedimentation-control Drawings.

    a. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross tree- or plant-protection zones.
    b. Inspect, repair, and maintain erosion- and sedimentation-control measures during construction until permanent vegetation has been established.
    c. Clean, repair, and restore adjoining properties and roads affected by erosion and sedimentation from Project site during the course of Project.
    d. Remove erosion and sedimentation controls, and restore and stabilize areas disturbed during removal.

D. Stormwater Control: Comply with requirements of authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of stormwater from heavy rains.

E. Tree and Plant Protection:

1. Install temporary fencing located as indicated or outside the drip line of trees to protect vegetation from damage from construction operations. Protect tree root systems from damage, flooding, and erosion.

F. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals, so Project will be free of pests and their residues at Substantial Completion. Perform control operations lawfully, using materials approved by authorities having jurisdiction.

G. Site Enclosure Fence: Before construction operations begin, furnish and install site enclosure fence in a manner that will prevent people from easily entering site except by entrance gates.

1. Extent of Fence: As required to enclose entire Project site or portion determined sufficient to accommodate construction operations.
2. Maintain security by limiting number of keys and restricting distribution to authorized personnel. Furnish one set of keys to Owner.

H. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each workday.

I. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including warning signs and lighting.

J. Temporary Egress: Provide temporary egress from existing occupied facilities as indicated and as required by authorities having jurisdiction. Provide signage directing occupants to temporary egress.

K. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.

1. Where heating or cooling is needed and permanent enclosure is incomplete, insulate temporary enclosures.

L. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire-prevention program.

1. Prohibit smoking in construction areas. Comply with additional limits on smoking specified in other Sections.
2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition in accordance with requirements of authorities having jurisdiction.
3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
4. Provide temporary standpipes and hoses for fire protection. Hang hoses with a warning sign, stating that hoses are for fire-protection purposes only and are not to be removed. Match hose size with outlet size and equip with suitable nozzles.

3.6 MOISTURE AND MOLD CONTROL

A. Moisture and Mold Protection: Protect stored materials and installed Work in accordance with Moisture and Mold Protection Plan.

B. Exposed Construction Period: Before installation of weather barriers, when materials are subject to wetting and exposure and to airborne mold spores, protect as follows:

1. Protect porous materials from water damage.
2. Protect stored and installed material from flowing or standing water.
3. Keep porous and organic materials from coming into prolonged contact with concrete.
4. Remove standing water from decks.
5. Keep deck openings covered or dammed.

C. Partially Enclosed Construction Period: After installation of weather barriers but before full enclosure and conditioning of building, when installed materials are still subject to infiltration of moisture and ambient mold spores, protect as follows:

1. Do not load or install drywall or other porous materials or components, or items with high organic content, into partially enclosed building.
2. Keep interior spaces reasonably clean and protected from water damage.
3. Periodically collect and remove waste containing cellulose or other organic matter.
4. Discard or replace water-damaged material.
5. Do not install material that is wet.
6. Discard and replace stored or installed material that begins to grow mold.
7. Perform work in a sequence that allows wet materials adequate time to dry before enclosing the material in gypsum board or other interior finishes.

D. Controlled Construction Period: After completing and sealing of the building enclosure but prior to the full operation of permanent HVAC systems, maintain as follows:

1. Control moisture and humidity inside building by maintaining effective dry-in conditions.
2. Use temporary or permanent HVAC system to control humidity within ranges specified for installed and stored materials.

3. Comply with manufacturer's written instructions for temperature, relative humidity, and exposure to water limits.

    a. Hygroscopic materials that may support mold growth, including wood and gypsum-based products, that become wet during the course of construction and remain wet for 24 hours are considered defective and require replacing.
    b. Measure moisture content of materials that have been exposed to moisture during construction operations or after installation. Record readings beginning at time of exposure and continuing daily for 48 hours. Identify materials containing moisture levels higher than allowed. Report findings in writing to Architect.
    c. Remove and replace materials that cannot be completely restored to their manufactured moisture level within 24 hours.

3.7 OPERATION, TERMINATION, AND REMOVAL

A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.

B. Maintenance: Maintain facilities in good operating condition until removal.

1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.

D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.

1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
2. Remove temporary roads and paved areas not intended for or acceptable for integration into permanent construction. Where area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at temporary entrances, as required by authorities having jurisdiction.
3. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 017700 "Closeout Procedures."

END OF SECTION

SECTION 015639 - TEMPORARY TREE AND PLANT PROTECTION

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of this Section Includes: General protection and pruning of existing trees and plants that are affected by execution of the Work, whether temporary or permanent construction.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for temporary controls, utilities, support facilities, temporary site fencing, and, if applicable, temporary erosion and sedimentation controls if not specified in Section 311000 "Site Clearing".
2. Section 311000 "Site Clearing" for removing existing trees and shrubs and for temporary erosion- and sedimentation-control measures if not specified in Section 015000 "Temporary Facilities and Controls".

1.2 DEFINITIONS

A. Caliper: Diameter of a trunk measured by a diameter tape at a height 6 inches above the ground for trees up to and including 4-inch size at this height and as measured at a height of 12 inches above the ground for trees larger than 4-inch size.

B. Caliper (DBH): Diameter breast height; diameter of a trunk as measured by a diameter tape at a height 54 inches above the ground line for trees with caliper of 8 inches or greater as measured at a height of 12 inches above the ground.

C. Plant-Protection Zone: Area surrounding individual trees, groups of trees, shrubs, or other vegetation to be protected during construction and indicated on Drawings.

D. Tree-Protection Zone: Area surrounding individual trees or groups of trees to be protected during construction and indicated on Drawings.

E. Vegetation: Trees, shrubs, groundcovers, grass, and other plants.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review methods and procedures related to temporary tree and plant protection including, but not limited to, the following:

a. Tree-service firm's personnel and equipment needed to make progress and avoid delays.
b. Arborist's responsibilities.
c. Quality-control program.

d. Coordination of Work and equipment movement with the locations of protection zones.
e. Trenching by hand or with air spade within protection zones.
f. Field quality control.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. General protection and pruning of existing trees and plants that are affected by execution of the Work, whether temporary or permanent construction

C. Tree-Pruning Schedule: Written schedule detailing scope and extent of pruning of trees to remain that interfere with or are affected by construction.

1. Species and size of tree.
2. Location on site plan. Include unique identifier for each.
3. Reason for pruning.
4. Description of pruning to be performed.
5. Description of maintenance following pruning.

D. Maintenance Recommendations: From arborist, for care and protection of trees affected by construction during and after completing the Work.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Statements: For arborist and tree service firm.

C. Certification: From arborist, certifying that trees indicated to remain have been protected during construction in accordance with recognized standards and that trees were promptly and properly treated and repaired when damaged.

D. Maintenance Recommendations: From arborist, for care and protection of trees affected by construction during and after completing the Work.

E. Existing Conditions: Documentation of existing trees and plantings indicated to remain, which establishes preconstruction conditions that might be misconstrued as damage caused by construction activities.

1. Use sufficiently detailed photographs or video recordings.
2. Include plans and notations to indicate specific wounds and damage conditions of each tree or other plants designated to remain.

F. Quality-control program.

1.6 QUALITY ASSURANCE

A. Arborist Qualifications: Certified Arborist as certified by ISA and Licensed arborist in jurisdiction where Project is located.

B. Tree-Service Firm Qualifications: An experienced tree-service firm that has successfully completed temporary tree- and plant-protection work similar to that required for this Project and that will assign an experienced, qualified arborist to Project site during execution of the Work.

C. Quality-Control Program: Prepare a written program to systematically demonstrate the ability of personnel to properly follow procedures and handle materials and equipment during the Work without damaging trees and plantings. Include dimensioned diagrams for placement of protection-zone fencing and signage, the arborist's and tree-service firm's responsibilities, instructions given to workers on the use and care of protection zones, and enforcement of requirements for protection zones.

1.7 FIELD CONDITIONS

A. The following practices are prohibited within protection zones:

1. Storage of construction materials, debris, or excavated material.
2. Moving or parking vehicles or equipment.
3. Foot traffic.
4. Erection of sheds or structures.
5. Impoundment of water.
6. Excavation or other digging unless otherwise indicated.
7. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated.

B. Do not direct vehicle or equipment exhaust toward protection zones.

C. Prohibit heat sources, flames, ignition sources, and smoking within or near protection zones and organic mulch.

D. Take precautions to protect plants from airborne contaminants, such as paint or fireproofing overspray.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Backfill Soil: Planting soil of suitable moisture content and granular texture for placing around tree; free of stones, roots, plants, sod, clods, clay lumps, pockets of coarse sand, concrete slurry, concrete layers or chunks, cement, plaster, building debris, and other extraneous materials harmful to plant growth.

B. Protection-Zone Fencing: Fencing fixed in position and meeting the following requirements: Previously used materials may be used when approved by Architect.

1. Plastic Protection-Zone Fencing: Plastic construction fencing constructed of high-density extruded and stretched polyethylene fabric with 2-inch maximum opening in pattern and weighing a minimum of 0.4 lb/ft.; remaining flexible from minus 60 to plus 200 deg F; inert to most chemicals and acids; minimum tensile yield strength of 2000 psi and ultimate tensile strength of 2680 psi; secured with plastic bands or galvanized-steel or stainless steel wire ties; and supported by tubular or T-shape galvanized-steel posts spaced not more than 96 inches apart.

    a. Height: 48 inches.
    b. Color: High-visibility orange, nonfading.

C. Protection-Zone Signage: Shop-fabricated, rigid plastic or metal sheet with attachment holes pre-punched and reinforced; legibly printed with nonfading lettering and as follows:

1. Size and Text: 12 inches x 18 inches, “Attention: Tree Protection Zone.”
2. Lettering: 3-inch-high minimum, white characters on red background.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Erosion and Sedimentation Control: Examine the site to verify that temporary erosion- and sedimentation-control measures are in place. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross protection zones.

B. Prepare written report, endorsed by arborist, listing conditions detrimental to tree and plant protection.

3.2 PREPARATION

A. Locate and clearly identify trees, shrubs, and other vegetation to remain. Flag each tree trunk at 54 inches above the ground.

B. Protect tree root systems from damage caused by runoff or spillage of noxious materials while mixing, placing, or storing construction materials. Protect root systems from ponding, eroding, or excessive wetting caused by dewatering operations.

3.3 TREE PROTECTION

A. Tree-Protection Zones: Mulch areas inside tree-protection zones and other areas indicated. Do not exceed indicated thickness of mulch.

1. Apply 3-inch uniform thickness of organic mulch unless otherwise indicated. Do not place mulch within 6 inches of tree trunks.
2. Install temporary root-protection matting over mulch to the extent indicated.

3.4 PROTECTION ZONES

A. Protection-Zone Fencing: Install protection-zone fencing along edges of protection zones before materials or equipment are brought on the site and construction operations begin in a manner that will prevent people from easily entering protected areas except by entrance gates. Construct fencing so as not to obstruct safe passage or visibility at vehicle intersections where fencing is located adjacent to pedestrian walkways or in close proximity to street intersections, drives, or other vehicular circulation.

1. Posts: Set or drive posts into ground at least 8 inches.
2. Plastic Fencing: Stretch fabric taut and secure to posts without bows or sags.

B. Protection-Zone Signage: Install protection-zone signage in visibly prominent locations in a manner approved by Architect. Install one sign spaced approximately every 20 ft. on protection-zone fencing, but no fewer than two signs with each facing a different direction.

C. Maintain protection zones free of weeds and trash.

D. Maintain hydration of plants to assure plant survival.

E. Maintain protection-zone fencing and signage in good condition as acceptable to Architect and remove when construction operations are complete and equipment has been removed from the site.

1. Do not remove protection-zone fencing, even temporarily, to allow deliveries or equipment access through the protection zone.
2. Temporary access is permitted subject to preapproval in writing by arborist if a root buffer effective against soil compaction is constructed as directed by arborist. Maintain root buffer so long as access is permitted.

3.5 EXCAVATION

A. General: Excavate at edge of protection zones and for trenches indicated within protection zones in accordance with requirements in Section 312000 "Earth Moving" unless otherwise indicated.

B. Trenching within Protection Zones: Where utility trenches are required within protection zones, excavate under or around tree roots by hand or with air spade, or tunnel under the roots by drilling, auger boring, or pipe jacking. Do not cut main lateral tree roots or taproots; cut only smaller roots that interfere with installation of utilities. Cut roots as required for root pruning. If excavating by hand, use narrow-tine spading forks to comb soil and expose roots.

3.6 ROOT PRUNING

A. Prune tree roots that are affected by temporary and permanent construction. Prune roots as follows:

1. Cut roots manually by digging a trench and cutting exposed roots with sharp pruning instruments; do not break, tear, chop, or slant the cuts. Do not use a backhoe or other equipment that rips, tears, or pulls roots.

2. Cut Ends: Do not paint cut root ends.
3. Temporarily support and protect roots from damage until they are permanently covered with soil.
4. Cover exposed roots with burlap and water regularly.
5. Backfill as soon as possible in accordance with requirements in Section 312000 "Earth Moving."

B. Root Pruning at Edge of Protection Zone: Prune tree roots flush with the edge of the protection zone by cleanly cutting all roots to the depth of the required excavation.

C. Root Pruning within Protection Zone: Clear and excavate by hand or with air spade to the depth of the required excavation to minimize damage to tree root systems. If excavating by hand, use narrow-tine spading forks to comb soil to expose roots. Cleanly cut roots as close to excavation as possible.

3.7 FIELD QUALITY CONTROL

A. Inspections: Engage a qualified arborist to direct plant-protection measures in the vicinity of trees, shrubs, and other vegetation indicated to remain and to prepare inspection reports.

3.8 REPAIR AND REPLACEMENT

A. General: Repair or replace trees, shrubs, and other vegetation indicated to remain or to be relocated that are damaged by construction operations, in a manner approved by Architect.

1. Submit details of proposed pruning and repairs.
2. Perform repairs of damaged trunks, branches, and roots within 24 hours in accordance with arborist's written instructions.
3. Replace trees and other plants that cannot be repaired and restored to full-growth status, as determined by Architect.

B. Trees: Remove and replace trees indicated to remain that are more than 50 percent dead or in an unhealthy condition before the end of the corrections period or are damaged during construction operations that Architect determines are incapable of restoring to normal growth pattern.

1. Small Trees: Provide new trees of same size and species as those being replaced for each tree that measures 6 inches or smaller in caliper size.
2. Large Trees: Provide one new tree of 6-inch caliper size for each tree being replaced that measures more than 6 inches in caliper size.

    a. Species: As selected by Architect.

END OF SECTION

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of This Section Includes: Administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

B. Related Requirements:

1. Section 012100 "Allowances" for products selected under an allowance.
2. Section 012300 "Alternates" for products selected under an alternate.
3. Section 012500 "Substitution Procedures" for requests for substitutions.
4. Section 014200 "References" for applicable industry standards for products specified.
5. Section 017700 "Closeout Procedures" for submitting warranties.

1.2 DEFINITIONS

A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.

1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
2. New Products: Items that have not previously been incorporated into another project or facility. Salvaged items or items reused from other projects are not considered new products. Items that are manufactured or fabricated to include recycled content materials are considered new products unless otherwise indicated.
3. Comparable Product: Product by named manufacturer that is demonstrated and approved through the comparable product submittal process described in "Comparable Products" Article, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.

B. Basis-of-Design Product Specification: A specification in which a single manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation. Published attributes and characteristics of basis-of-design product establish salient characteristics of products.

1. Evaluating Comparable Products: In addition to the basis-of-design product description, product attributes and characteristics may be listed to establish the significant qualities related to type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other special features and requirements for purposes of evaluating comparable products of additional manufacturers named in the specification. Manufacturer's published attributes and characteristics of basis-of-design

product also establish salient characteristics of products for purposes of evaluating comparable products.

C. Subject to Compliance with Requirements: Where the phrase "Subject to compliance with requirements" introduces a product selection procedure in an individual Specification Section, provide products qualified under the specified product procedure. In the event that a named product or product by a named manufacturer does not meet the other requirements of the specifications, select another named product or product from another named manufacturer that does meet the requirements of the specifications; submit a comparable product request or substitution request, if applicable.

D. Comparable Product Request Submittal: An action submittal requesting consideration of a comparable product, including the following information:

1. Identification of basis-of-design product or fabrication or installation method to be replaced, including Specification Section number and title and Drawing numbers and titles.
2. Data indicating compliance with the requirements specified in "Comparable Products" Article.

E. Basis-of-Design Product Specification Submittal: An action submittal complying with requirements in Section 013300 "Submittal Procedures."

F. Substitution: Refer to Section 012500 "Substitution Procedures" for definition and limitations on substitutions.

1.3 QUALITY ASSURANCE

A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.

B. Identification of Products: Except for required labels and operating data, do not attach or imprint manufacturer or product names or trademarks on exposed surfaces of products or equipment that will be exposed to view in occupied spaces or on the exterior.

1. Labels: Locate required product labels and stamps on a concealed surface, or, where required for observation following installation, on a visually accessible surface that is inconspicuous.
2. Equipment Nameplates: Provide a permanent nameplate on each item of service- or power-operated equipment. Locate on a visually accessible but inconspicuous surface. Include information essential for operation, including the following:

    a. Name of product and manufacturer.
    b. Model and serial number.
    c. Capacity.
    d. Speed.
    e. Ratings.

3. See individual identification Sections in Divisions 21, 22, 23, and 26 for additional equipment identification requirements.

1.4 COORDINATION

A. Modify or adjust affected work as necessary to integrate work of approved comparable products and approved substitutions.

1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products, using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
4. Inspect products on delivery to determine compliance with the Contract Documents and that products are undamaged and properly protected.

C. Storage:

1. Provide a secure location and enclosure at Project site for storage of materials and equipment.
2. Store products to allow for inspection and measurement of quantity or counting of units.
3. Store materials in a manner that will not endanger Project structure.
4. Store products that are subject to damage by the elements under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation and with adequate protection from wind.
5. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
6. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
7. Protect stored products from damage and liquids from freezing.
8. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.6 PRODUCT WARRANTIES

A. Warranties specified in other Sections are to be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

1. Manufacturer's Warranty: Written standard warranty form furnished by individual manufacturer for a particular product and issued in the name of Owner or endorsed by manufacturer to Owner.

2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner and issued in the name of Owner or endorsed by manufacturer to Owner.

B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.

1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
2. Specified Form: When specified forms are included in the Project Manual, prepare a written document, using indicated form properly executed.
3. See other Sections for specific content requirements and particular requirements for submitting special warranties.

C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.

1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
3. Owner reserves the right to limit selection to products with warranties meeting requirements of the Contract Documents.
4. Where products are accompanied by the term "as selected," Architect will make selection.
5. Descriptive, performance, and reference standard requirements in Specifications establish salient characteristics of products.
6. Or Equal: For products specified by name and accompanied by the term "or equal," "or approved equal," or "or approved," comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.

a. Submit additional documentation required by Architect in order to establish equivalency of proposed products. Unless otherwise indicated, evaluation of "or equal" product status is by Architect, whose determination is final.

B. Product Selection Procedures:

1. Sole Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

a. Sole product may be indicated by the phrase "Subject to compliance with requirements, provide the following."

2. Sole Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

    a. Sole manufacturer/source may be indicated by the phrase "Subject to compliance with requirements, provide products by the following."

3. Limited List of Products: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated.

    a. Limited list of products may be indicated by the phrase "Subject to compliance with requirements, provide one of the following."

4. Non-Limited List of Products: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed or an unnamed product that complies with requirements.

    a. Non-limited list of products is indicated by the phrase "Subject to compliance with requirements, available products that may be incorporated in the Work include, but are not limited to, the following."
    b. Provision of an unnamed product is not considered a substitution, if the product complies with requirements.

5. Limited List of Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated.

    a. Limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, provide products by one of the following."

6. Non-Limited List of Manufacturers: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed or a product by an unnamed manufacturer that complies with requirements.

    a. Non-limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following."
    b. Provision of products of an unnamed manufacturer is not considered a substitution, if the product complies with requirements.

7. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications may additionally indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.

a. For approval of products by unnamed manufacturers, comply with requirements in Section 012500 "Substitution Procedures" for substitutions for convenience.

C. Visual Matching Specification: Where Specifications require the phrase "match Architect's sample," provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.

1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 012500 "Substitution Procedures" for proposal of product.

D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or a similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

A. Conditions for Consideration of Comparable Products: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with the following requirements:

1. Evidence that proposed product does not require revisions to the Contract Documents, is consistent with the Contract Documents, will produce the indicated results, and is compatible with other portions of the Work.
2. Detailed comparison of significant qualities of proposed product with those of the named basis-of-design product. Significant product qualities include attributes such as type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other specific features and requirements.
3. Evidence that proposed product provides specified warranty.
4. List of similar installations for completed projects, with project names and addresses and names and addresses of architects and owners, if requested.
5. Samples, if requested.

B. Architect's Action on Comparable Products Submittal: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for a comparable product. Architect will notify Contractor of approval or rejection of proposed comparable product within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

1. Architect's Approval of Submittal: See Section 013300 "Submittal Procedures."
2. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.

C. Submittal Requirements, Two-Step Process: Approval by Architect of Contractor's request for use of comparable product is not intended to satisfy other submittal requirements. Comply with specified submittal requirements.

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes general administrative and procedural requirements governing execution of the Work, including, but not limited to, the following:

1. Construction layout.
2. Field engineering.
3. Installation.
4. Cutting and patching.
5. Progress cleaning.
6. Starting and adjusting.
7. Protection of installed construction.
8. Correction of the Work.

B. Related Requirements:

1. Section 013300 "Submittal Procedures" for submitting surveys.
2. Section 017700 "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, replacing defective work, and final cleaning.
3. Section 024119 "Selective Demolition" for demolition and removal of selected portions of the building.
4. Section 078413 "Penetration Firestopping" for patching penetrations in fire-rated construction.

1.2 DEFINITIONS

A. Cutting: Removal of in-place construction necessary to permit installation or performance of subsequent work.

B. Patching: Fitting and repair work required to restore construction to original conditions after installation of subsequent work.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Utilities and Mechanical and Electrical Systems: List services and systems that cutting and patching procedures will disturb or affect. List services and systems that will be relocated and those that will be temporarily out of service. Indicate length of time permanent services and systems will be disrupted.

1. Include description of provisions for temporary services and systems during interruption of permanent services and systems.

C. Landfill Receipts: Submit copy of receipts issued by a landfill facility, licensed to accept hazardous materials, for hazardous waste disposal.

1.4 QUALITY ASSURANCE

A. Land Surveyor Qualifications: A professional land surveyor who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing land-surveying services of the kind indicated.

B. Professional Engineer Qualifications: Refer to Section 014000 "Quality Requirements."

C. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.

1. Structural Elements: When cutting and patching structural elements, or when encountering the need for cutting and patching of elements whose structural function is not known, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection.
2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.
3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.
4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

D. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of specified products and equipment.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Comply with requirements specified in other Sections.

B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.

1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials. Use materials that are not considered hazardous.

C. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, mechanical and electrical systems, and other construction affecting the Work.

1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, gas service piping, and water-service piping; underground electrical services; and other utilities.
2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.

B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.

1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.

C. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Existing Utility Information: Furnish information to local utility and Owner that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.

B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.

D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Architect in accordance with requirements in Section 013100 "Project Management and Coordination."

3.3 CONSTRUCTION LAYOUT

A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks and existing conditions. If discrepancies are discovered, notify Architect promptly.

B. Engage a land surveyor and professional engineer experienced in laying out the Work, using the following accepted surveying practices:

1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
2. Establish limits on use of Project site.
3. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
4. Inform installers of lines and levels to which they must comply.
5. Check the location, level and plumb, of every major element as the Work progresses.
6. Notify Architect when deviations from required lines and levels exceed allowable tolerances.
7. Close site surveys with an error of closure equal to or less than the standard established by authorities having jurisdiction.

C. Site Improvements: Locate and lay out site improvements, including pavements, grading, fill and topsoil placement, utility slopes, and rim and invert elevations.

D. Building Lines and Levels: Locate and lay out control lines and levels for structures, building foundations, column grids, and floor levels, including those required for mechanical and electrical work. Transfer survey markings and elevations for use with control lines and levels. Level foundations and piers from two or more locations.

E. Record Log: Maintain a log of layout control work. Record deviations from required lines and levels. Include beginning and ending dates and times of surveys, weather conditions, name and duty of each survey party member, and types of instruments and tapes used. Make the log available for reference by Architect.

3.4 FIELD ENGINEERING

A. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.

1. Do not change or relocate existing benchmarks or control points without prior written approval of Architect. Report lost or destroyed permanent benchmarks or control points promptly. Report the need to relocate permanent benchmarks or control points to Architect before proceeding.

2. Replace lost or destroyed permanent benchmarks and control points promptly. Base replacements on the original survey control points.

B. Benchmarks: Establish and maintain a minimum of two permanent benchmarks on Project site, referenced to data established by survey control points. Comply with authorities having jurisdiction for type and size of benchmark.

1. Record benchmark locations, with horizontal and vertical data, on Project Record Documents.
2. Where the actual location or elevation of layout points cannot be marked, provide temporary reference points sufficient to locate the Work.
3. Remove temporary reference points when no longer needed. Restore marked construction to its original condition.

3.5 INSTALLATION

A. Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.

1. Make vertical work plumb, and make horizontal work level.
2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.
4. Maintain minimum headroom clearance of 96 inches in occupied spaces and 90 inches in unoccupied spaces, unless otherwise indicated on Drawings.

B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.

C. Install products at the time and under conditions that will ensure satisfactory results as judged by Architect. Maintain conditions required for product performance until Substantial Completion.

D. Conduct construction operations, so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy of type expected for Project.

E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on-site and placement in permanent locations.

F. Tools and Equipment: Select tools or equipment that minimize production of excessive noise levels.

G. Templates: Obtain and distribute to the parties involved templates for Work specified to be factory prepared and field installed. Check Shop Drawings of other portions of the Work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.

H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions with manufacturer.

1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
2. Allow for building movement, including thermal expansion and contraction.
3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

I. Joints: Make joints of uniform width. Where joint locations in exposed Work are not indicated, arrange joints for the best visual effect, as judged by Architect. Fit exposed connections together to form hairline joints.

3.6 CUTTING AND PATCHING

A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.

1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.

B. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.

C. Temporary Support: Provide temporary support of Work to be cut.

D. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.

E. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.

1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
4. Excavating and Backfilling: Comply with requirements in applicable Sections where required by cutting and patching operations.
5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
6. Proceed with patching after construction operations requiring cutting are complete.

F. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as practicable, as judged by Architect. Provide materials and comply with installation requirements specified in other Sections, where applicable.

1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.

a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
b. Restore damaged pipe covering to its original condition.

3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.

a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch, corner to corner of wall and edge to edge of ceiling. Provide additional coats until patch blends with adjacent surfaces.

4. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition and ensures thermal and moisture integrity of building enclosure.

G. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.7 PROGRESS CLEANING

A. Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.

1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F.
3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, in accordance with regulations.

a. Use containers intended for holding waste materials of type to be stored.

4. Coordinate progress cleaning for joint-use areas where Contractor and other contractors are working concurrently.

B. Site: Maintain Project site free of waste materials and debris.

C. Work Areas: Clean areas where Work is in progress to the level of cleanliness necessary for proper execution of the Work.

1. Remove liquid spills promptly.
2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.

D. Installed Work: Keep installed work clean. Clean installed surfaces in accordance with written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.

E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.

F. Exposed Surfaces: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.

G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Comply with waste disposal requirements in Section 017419 "Construction Waste Management and Disposal."

H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.

I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.

J. Limiting Exposures: Supervise construction operations to ensure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.8 STARTING AND ADJUSTING

A. Coordinate startup and adjusting of equipment and operating components with requirements in Section 019113 "General Commissioning Requirements."

B. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.

C. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.

D. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

E. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements."

3.9 PROTECTION OF INSTALLED CONSTRUCTION

A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.

B. Protection of Existing Items: Provide protection and ensure that existing items to remain undisturbed by construction are maintained in condition that existed at commencement of the Work.

C. Comply with manufacturer's written instructions for temperature and relative humidity.

3.10 CORRECTION OF THE WORK

A. Repair or remove and replace damaged, defective, or nonconforming Work. Restore damaged substrates and finishes.

1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.

B. Repair Work previously completed and subsequently damaged during construction period. Repair to like-new condition.

C. Restore permanent facilities used during construction to their specified condition.

D. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.

E. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.

F. Remove and replace chipped, scratched, and broken glass or reflective surfaces.

END OF SECTION

SECTION 017419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of this Section includes administrative and procedural requirements for the following:

1. Disposing of nonhazardous demolition and construction waste.

1.2 DEFINITIONS

A. CMU: Concrete masonry units.

B. Construction Waste: Building, structure, and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.

C. Demolition Waste: Building, structure, and site improvement materials resulting from demolition operations.

D. Disposal: Removal of demolition or construction waste and subsequent salvage, sale, recycling, or deposit in landfill, incinerator acceptable to authorities having jurisdiction, or designated spoil areas on Owner's property.

E. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.

F. Salvage: Recovery of demolition or construction waste and subsequent sale or reuse in another facility.

G. Salvage and Reuse: Recovery of demolition or construction waste and subsequent incorporation into the Work.

1.3 MATERIALS OWNERSHIP

A. Unless otherwise indicated, demolition and construction waste becomes property of Contractor.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Landfill and Incinerator Disposal Records: Indicate receipt and acceptance of waste by landfills and incinerator facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.

C. Qualification Statements: For waste management coordinator and refrigerant recovery technician.

D. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed in accordance with EPA regulations. Include name and address of technician and date refrigerant was recovered.

E. Refrigerant Recovery: Comply with requirements in Section 024119 "Selective Demolition" for refrigerant recovery submittals.

1.5 QUALITY ASSURANCE

A. Waste Management Coordinator Qualifications: Experienced firm, or individual employed and assigned by General Contractor, with a record of successful waste management coordination of projects with similar requirements. Superintendent may serve as Waste Management Coordinator.

B. Refrigerant Recovery Technician Qualifications:

1. Type I, certified by EPA-approved certification program.
2. Comply with requirements in Section 024119 "Selective Demolition."

C. Regulatory Requirements: Comply with transportation and disposal regulations of authorities having jurisdiction.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 DISPOSAL OF WASTE

A. Except for items or materials to be salvaged or recycled, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

1. Unless otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

B. Burning:

1. Do not burn waste materials.

END OF SECTION

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for Contract closeout, including, but not limited to, the following:

1. Substantial Completion procedures.
2. Final Completion procedures.
3. List of incomplete items.
4. Submittal of Project warranties.
5. Final cleaning.

B. Related Requirements:

1. Section 012900 "Payment Procedures" for requirements for Applications for Payment for Substantial Completion and Final Completion.
2. Section 013233 "Photographic Documentation" for submitting Final Completion construction photographic documentation.
3. Section 017823 "Operation and Maintenance Data" for additional operation and maintenance manual requirements.
4. Section 017839 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
5. Section 017900 "Demonstration and Training" for requirements to train Owner's maintenance personnel to adjust, operate, and maintain products, equipment, and systems.

1.2 DEFINITIONS

A. List of Incomplete Items: Contractor-prepared list of items to be completed or corrected, prepared for the Architect's use prior to Architect's inspection, to determine if the Work is substantially complete.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of cleaning agent.

C. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.

D. Certified List of Incomplete Items: Final submittal at Final Completion.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Certificates of Release: From authorities having jurisdiction.

C. Certificate of Insurance: For continuing coverage.

D. Field Report: For pest-control inspection.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Schedule of Maintenance Material Items: For maintenance material submittal items required by other Sections.

1.6 SUBSTANTIAL COMPLETION PROCEDURES

A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's "punch list"), indicating the value of each item on the list and reasons why the Work is incomplete.

B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.

1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction, permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
2. Submit closeout submittals specified in other Division 01 Sections, including Project Record Documents, operation and maintenance manuals, damage or settlement surveys, property surveys, and similar final record information.
3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number.

    a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Owner's signature for receipt of submittals.

5. Submit testing, adjusting, and balancing records.
6. Submit sustainable design submittals not previously submitted.
7. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.

C. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.

1. Advise Owner of pending insurance changeover requirements.
2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
3. Complete startup and testing of systems and equipment.
4. Perform preventive maintenance on equipment used prior to Substantial Completion.
5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training video recordings specified in Section 017900 "Demonstration and Training."
6. Advise Owner of changeover in utility services.
7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
9. Complete final cleaning requirements.
10. Touch up paint and otherwise repair and restore marred exposed finishes to eliminate visual defects.

D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for Final Completion.

1.7 FINAL COMPLETION PROCEDURES

A. Submittals Prior to Final Completion: Before requesting final inspection for determining Final Completion, complete the following:

1. Submit a final Application for Payment in accordance with Section 012900 "Payment Procedures."
2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list will state that each item has been completed or otherwise resolved for acceptance.
3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
4. Submit pest-control final inspection report.
5. Submit Final Completion photographic documentation.

B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On

receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.8 LIST OF INCOMPLETE ITEMS

A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.

1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor, listed by room or space number.
2. Organize items applying to each space by major element, including categories for ceilings, individual walls, floors, equipment, and building systems.
3. Include the following information at the top of each page:

    a. Project name.
    b. Date.
    c. Name of Architect.
    d. Name of Contractor.
    e. Page number.

4. Submit list of incomplete items in the following format:

    a. MS Excel Electronic File: Architect will return annotated file.
    b. PDF Electronic File: Architect will return annotated file.
    c. Web-Based Project Software Upload: Utilize software feature for creating and updating list of incomplete items (punch list).

1.9 SUBMITTAL OF PROJECT WARRANTIES

A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where warranties are indicated to commence on dates other than date of Substantial Completion, or when delay in submittal of warranties might limit Owner's rights under warranty.

B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.

C. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.

D. Warranty Electronic File: Provide warranties and bonds in PDF format. Assemble complete warranty and bond submittal package into a single electronic PDF file with bookmarks enabling navigation to each item. Provide bookmarked table of contents at beginning of document.

1. Submit on digital media acceptable to Architect.

E. Warranties in Paper Form:

1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.

F. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 FINAL CLEANING

A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.

B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.

1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:

a. Clean Project site of rubbish, waste material, litter, and other foreign substances.
b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
c. Rake grounds that are not planted, mulched, or paved to a smooth, even-textured surface.
d. Remove tools, construction equipment, machinery, and surplus material from Project site.
e. Remove snow and ice to provide safe access to building.

f. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
g. Remove debris and surface dust from limited-access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
h. Clean flooring, removing debris, dirt, and staining; clean in accordance with manufacturer's instructions.
i. Vacuum and mop concrete.
j. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean in accordance with manufacturer's instructions if visible soil or stains remain.
k. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
l. Remove labels that are not permanent.
m. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
n. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
o. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
p. Clean ducts, blowers, and coils if units were operated without filters during construction or that display contamination with particulate matter on inspection.

    1) Clean HVAC system in compliance with NADCA ACR. Provide written report on completion of cleaning.

q. Clean luminaires, lamps, globes, and reflectors to function with full efficiency.
r. Clean strainers.
s. Leave Project clean and ready for occupancy.

C. Pest Control: Comply with pest control requirements in Section 015000 "Temporary Facilities and Controls." Prepare written report.

D. Construction Waste Disposal: Comply with waste-disposal requirements inSection 017419 "Construction Waste Management and Disposal."

3.2 CORRECTION OF THE WORK

A. Complete repair and restoration operations required by "Correction of the Work" Article in Section 017300 "Execution" before requesting inspection for determination of Substantial Completion.

END OF SECTION

SECTION 017823 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Administrative and procedural requirements for preparing operation and maintenance manuals, including the following:

1. Operation and maintenance documentation directory manuals.
2. Emergency manuals.
3. Systems and equipment operation manuals.
4. Systems and equipment maintenance manuals.
5. Product maintenance manuals.

B. Related Requirements:

1. Section 013300 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.
2. Section 019113 "General Commissioning Requirements" for verification and compilation of data into operation and maintenance manuals.

1.2 DEFINITIONS

A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.

B. Subsystem: A portion of a system with characteristics similar to a system.

1.3 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Submit operation and maintenance manuals indicated. Provide content for each manual as specified in individual Specification Sections, and as reviewed and approved at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.

1. Architect and Commissioning Authority will comment on whether content of operation and maintenance submittals is acceptable.
2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.

C. Format: Submit operation and maintenance manuals in the following format:

1. Submit on digital media acceptable to Architect. Enable reviewer comments on draft submittals.
2. Submit three paper copies. Architect will return two copies.

D. Initial Manual Submittal: Submit draft copy of each manual at least 30 days before commencing demonstration and training. Architect and Commissioning Authority will comment on whether general scope and content of manual are acceptable.

E. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect and Commissioning Authority will return copy with comments.

1. Correct or revise each manual to comply with Architect's and Commissioning Authority's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's and Commissioning Authority's comments and prior to commencing demonstration and training.

F. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

1.4 FORMAT OF OPERATION AND MAINTENANCE MANUALS

A. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.

1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
2. File Names and Bookmarks: Bookmark individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.

B. Manuals, Paper Copy: Submit manuals in the form of hard-copy, bound and labeled volumes.

1. Binders: Heavy-duty, three-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.

a. If two or more binders are necessary to accommodate data of a system, organize data in each binder into groupings by subsystem and related components. Cross-reference other binders if necessary to provide essential information for proper operation or maintenance of equipment or system.
b. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name, and subject matter of contents, and indicate Specification Section number on bottom of spine. Indicate volume number for multiple-volume sets.

2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section of the manual. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software storage media for computerized electronic equipment. Enclose title pages and directories in clear plastic sleeves.
4. Supplementary Text: Prepared on 8-1/2-by-11-inch white bond paper.
5. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.

    a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
    b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

1.5 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

A. Organization of Manuals: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual to contain the following materials, in the order listed:

1. Title page.
2. Table of contents.
3. Manual contents.

B. Title Page: Include the following information:

1. Subject matter included in manual.
2. Name and address of Project.
3. Name and address of Owner.
4. Date of submittal.
5. Name and contact information for Contractor.
6. Name and contact information for Construction Manager.
7. Name and contact information for Architect.
8. Name and contact information for Commissioning Authority.
9. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
10. Cross-reference to related systems in other operation and maintenance manuals.

C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.

1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.

D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.

E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation in accordance with ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

1.6 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY MANUAL

A. Operation and Maintenance Documentation Directory: Prepare a separate manual that provides an organized reference to emergency, operation, and maintenance manuals. List items and their location to facilitate ready access to desired information. Include the following:

1. List of Systems and Subsystems: List systems alphabetically. Include references to operation and maintenance manuals that contain information about each system.
2. List of Equipment: List equipment for each system, organized alphabetically by system. For pieces of equipment not part of system, list alphabetically in separate list.
3. Tables of Contents: Include a table of contents for each emergency, operation, and maintenance manual.

1.7 EMERGENCY MANUALS

A. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.

B. Content: Organize manual into a separate section for each of the following:

1. Type of emergency.
2. Emergency instructions.
3. Emergency procedures.

C. Type of Emergency: Where applicable for each type of emergency indicated below, include instructions and procedures for each system, subsystem, piece of equipment, and component:

1. Fire.
2. Flood.
3. Gas leak.
4. Water leak.
5. Power failure.
6. Water outage.
7. System, subsystem, or equipment failure.
8. Chemical release or spill.

D. Emergency Instructions: Describe and explain warnings, trouble indications, error messages, and similar codes and signals. Include responsibilities of Owner's operating personnel for notification of Installer, supplier, and manufacturer to maintain warranties.

E. Emergency Procedures: Include the following, as applicable:

1. Instructions on stopping.
2. Shutdown instructions for each type of emergency.
3. Operating instructions for conditions outside normal operating limits.
4. Required sequences for electric or electronic systems.
5. Special operating instructions and procedures.

1.8 SYSTEMS AND EQUIPMENT OPERATION MANUALS

A. Systems and Equipment Operation Manual: Assemble a complete set of data indicating operation of each system, subsystem, and piece of equipment not part of a system. Include information required for daily operation and management, operating standards, and routine and special operating procedures.

1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.

B. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:

1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
2. Performance and design criteria if Contractor has delegated design responsibility.
3. Operating standards.
4. Operating procedures.
5. Operating logs.
6. Wiring diagrams.
7. Control diagrams.
8. Piped system diagrams.
9. Precautions against improper use.
10. License requirements including inspection and renewal dates.

C. Descriptions: Include the following:

1. Product name and model number. Use designations for products indicated on Contract Documents.
2. Manufacturer's name.
3. Equipment identification with serial number of each component.
4. Equipment function.
5. Operating characteristics.
6. Limiting conditions.
7. Performance curves.
8. Engineering data and tests.
9. Complete nomenclature and number of replacement parts.

D. Operating Procedures: Include the following, as applicable:

1. Startup procedures.

2. Equipment or system break-in procedures.
3. Routine and normal operating instructions.
4. Regulation and control procedures.
5. Instructions on stopping.
6. Normal shutdown instructions.
7. Seasonal and weekend operating instructions.
8. Required sequences for electric or electronic systems.
9. Special operating instructions and procedures.

E. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.

F. Piped Systems: Diagram piping as installed, and identify color coding where required for identification.

1.9 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

A. Systems and Equipment Maintenance Manuals: Assemble a complete set of data indicating maintenance of each system, subsystem, and piece of equipment not part of a system. Include manufacturers' maintenance documentation, preventive maintenance procedures and frequency, repair procedures, wiring and systems diagrams, lists of spare parts, and warranty information.

1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.

B. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranties and bonds as described below.

C. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

D. Manufacturers' Maintenance Documentation: Include the following information for each component part or piece of equipment:

1. Standard maintenance instructions and bulletins; include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.

a. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.

2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
3. Identification and nomenclature of parts and components.
4. List of items recommended to be stocked as spare parts.

E. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:

1. Test and inspection instructions.
2. Troubleshooting guide.
3. Precautions against improper maintenance.
4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
5. Aligning, adjusting, and checking instructions.
6. Demonstration and training video recording, if available.

F. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.

1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.

G. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.

H. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.

I. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

1. Include procedures to follow and required notifications for warranty claims.

J. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.

1. Do not use original project record documents as part of maintenance manuals.

1.10 PRODUCT MAINTENANCE MANUALS

A. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.

B. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.

C. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

D. Product Information: Include the following, as applicable:

1. Product name and model number.
2. Manufacturer's name.
3. Color, pattern, and texture.
4. Material and chemical composition.
5. Reordering information for specially manufactured products.

E. Maintenance Procedures: Include manufacturer's written recommendations and the following:

1. Inspection procedures.
2. Types of cleaning agents to be used and methods of cleaning.
3. List of cleaning agents and methods of cleaning detrimental to product.
4. Schedule for routine cleaning and maintenance.
5. Repair instructions.

F. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.

G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

1. Include procedures to follow and required notifications for warranty claims.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for Project Record Documents, including the following:

1. Record Drawings.
2. Record specifications.
3. Record Product Data.
4. Miscellaneous record submittals.

B. Related Requirements:

1. Section 00 72 13 “General Conditions.”
2. Section 017700 "Closeout Procedures" for general closeout procedures.
3. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

1.2 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Record Drawings: Comply with the following:

1. Number of Copies: Submit one set of marked-up record prints.
2. Number of Copies: Submit copies of Record Drawings as follows:

a. Initial Submittal:

1) Submit one paper-copy set of marked-up record prints.
2) Submit PDF electronic files of scanned record prints and one set of file prints.
3) Submit Record Digital Data Files and one set of plots.
4) Architect will indicate whether general scope of changes, additional information recorded, and quality of drafting are acceptable.

b. Final Submittal:

1) Submit PDF electronic files of scanned Record Prints and three set(s) of file prints.
2) Print each drawing, whether or not changes and additional information were recorded.

C. Record Specifications: Submit annotated PDF electronic files and one paper copy of Project's Specifications, including addenda and Contract modifications.

D. Record Product Data: Submit annotated PDF electronic files and directories and one paper copy of each submittal.

1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.

E. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit annotated PDF electronic files and directories and one paper copy of each submittal.

1.3 RECORD DRAWINGS

A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.

1. Preparation: Mark record prints to show the actual installation, where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.

a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
b. Accurately record information in an acceptable drawing technique.
c. Record data as soon as possible after obtaining it.
d. Record and check the markup before enclosing concealed installations.
e. Cross-reference record prints to corresponding photographic documentation.

2. Content: Types of items requiring marking include, but are not limited to, the following:

a. Dimensional changes to Drawings.
b. Revisions to details shown on Drawings.
c. Depths of foundations.
d. Locations and depths of underground utilities.
e. Revisions to routing of piping and conduits.
f. Revisions to electrical circuitry.
g. Actual equipment locations.
h. Duct size and routing.
i. Locations of concealed internal utilities.
j. Changes made by Change Order or Construction Change Directive.
k. Changes made following Architect's written orders.
l. Details not on the original Contract Drawings.
m. Field records for variable and concealed conditions.
n. Record information on the Work that is shown only schematically.

3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
4. Mark record prints with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
5. Mark important additional information that was either shown schematically or omitted from original Drawings.

6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Architect. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:

1. Format: Annotated PDF electronic file with comment function enabled.
2. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
3. Refer instances of uncertainty to Architect for resolution.
4. Architect will furnish Contractor with one set of digital data files of the Contract Drawings for use in recording information.

    a. See Section 013100 "Project Management and Coordination" for requirements related to use of Architect's digital data files.
    b. Architect will provide data file layer information. Record markups in separate layers.

C. Format: Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.

1. Record Prints: Organize record prints into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
2. Format: Annotated PDF electronic file with comment function enabled.
3. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.
4. Identification: As follows:

    a. Project name.
    b. Date.
    c. Designation "PROJECT RECORD DRAWINGS."
    d. Name of Architect.
    e. Name of Contractor.

1.4 RECORD SPECIFICATIONS

A. Preparation: Mark Specifications to indicate the actual product installation, where installation varies from that indicated in Specifications, addenda, and Contract modifications.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. For each principal product, indicate whether Record Product Data has been submitted in operation and maintenance manuals instead of submitted as Record Product Data.
3. Note related Change Orders, Record Product Data, and Record Drawings where applicable.

B. Format: Submit record specifications as annotated PDF electronic file.

1.5 RECORD PRODUCT DATA

A. Recording: Maintain one copy of each submittal during the construction period for Project Record Document purposes. Post changes and revisions to Project Record Documents as they occur; do not wait until end of Project.

B. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
3. Note related Change Orders, Record Specifications, and Record Drawings where applicable.

C. Format: Submit Record Product Data as annotated PDF electronic file.

1. Include Record Product Data directory organized by Specification Section number and title, electronically linked to each item of Record Product Data.

1.6 MISCELLANEOUS RECORD SUBMITTALS

A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.

B. Format: Submit miscellaneous record submittals as PDF electronic file.

1. Include miscellaneous record submittals directory organized by Specification Section number and title, electronically linked to each item of miscellaneous record submittals.

1.7 MAINTENANCE OF RECORD DOCUMENTS

A. Maintenance of Record Documents: Store Record Documents in the field office apart from the Contract Documents used for construction. Do not use Project Record Documents for construction purposes. Maintain Record Documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to Project Record Documents for Architect's reference during normal working hours.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 017900 - DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:

1. Instruction in operation and maintenance of systems, subsystems, and equipment.
2. Demonstration and training video recordings.

1.2 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.

1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.

C. Qualification Data: For facilitator, instructor, and videographer.

D. Attendance Record: For each training module, submit list of participants and length of instruction time.

E. Evaluations: For each participant and for each training module, submit results and documentation of performance-based test.

1.3 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Demonstration and Training Video Recordings: Submit two copies within seven days of end of each training module.

1. Identification: On each copy, provide an applied label with the following information:

a. Name of Project.
b. Name and address of videographer.
c. Name of Architect.

d. Name of Construction Manager.
e. Name of Contractor.
f. Date of video recording.

2. Transcript:

a. Prepared in PDF electronic format. Include a cover sheet with same label information as the corresponding video recording and a table of contents with links to corresponding training components. Include name of Project and date of video recording on each page.

3. At completion of training, submit complete training manual(s) for Owner's use prepared in same paper and PDF file format required for operation and maintenance manuals specified in Section 017823 "Operation and Maintenance Data."

1.4 QUALITY ASSURANCE

A. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.

B. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Section 014000 "Quality Requirements," experienced in operation and maintenance procedures and training.

C. Videographer Qualifications: A professional videographer who is experienced photographing demonstration and training events similar to those required.

D. Preinstruction Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to demonstration and training including, but not limited to, the following:

1. Inspect and discuss locations and other facilities required for instruction.
2. Review and finalize instruction schedule and verify availability of educational materials, instructors' personnel, audiovisual equipment, and facilities needed to avoid delays.
3. Review required content of instruction.
4. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.

1.5 COORDINATION

A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.

B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.

C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data have been reviewed and approved by Architect.

1.6 INSTRUCTION PROGRAM

A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.

B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:

1. Basis of System Design, Operational Requirements, and Criteria: Include the following:

a. System, subsystem, and equipment descriptions.
b. Performance and design criteria if Contractor is delegated design responsibility.
c. Operating standards.
d. Regulatory requirements.
e. Equipment function.
f. Operating characteristics.
g. Limiting conditions.
h. Performance curves.

2. Documentation: Review the following items in detail:

a. Emergency manuals.
b. Systems and equipment operation manuals.
c. Systems and equipment maintenance manuals.
d. Product maintenance manuals.
e. Project Record Documents.
f. Identification systems.
g. Warranties and bonds.
h. Maintenance service agreements and similar continuing commitments.

3. Emergencies: Include the following, as applicable:

a. Instructions on meaning of warnings, trouble indications, and error messages.
b. Instructions on stopping.
c. Shutdown instructions for each type of emergency.
d. Operating instructions for conditions outside of normal operating limits.
e. Sequences for electric or electronic systems.
f. Special operating instructions and procedures.

4. Operations: Include the following, as applicable:

a. Startup procedures.
b. Equipment or system break-in procedures.
c. Routine and normal operating instructions.
d. Regulation and control procedures.
e. Control sequences.
f. Safety procedures.
g. Instructions on stopping.
h. Normal shutdown instructions.

i. Operating procedures for emergencies.
j. Operating procedures for system, subsystem, or equipment failure.
k. Seasonal and weekend operating instructions.
l. Required sequences for electric or electronic systems.
m. Special operating instructions and procedures.

5. Adjustments: Include the following:

a. Alignments.
b. Checking adjustments.
c. Noise and vibration adjustments.
d. Economy and efficiency adjustments.

6. Troubleshooting: Include the following:

a. Diagnostic instructions.
b. Test and inspection procedures.

7. Maintenance: Include the following:

a. Inspection procedures.
b. Types of cleaning agents to be used and methods of cleaning.
c. List of cleaning agents and methods of cleaning detrimental to product.
d. Procedures for routine cleaning.
e. Procedures for preventive maintenance.
f. Procedures for routine maintenance.
g. Instruction on use of special tools.

8. Repairs: Include the following:

a. Diagnosis instructions.
b. Repair instructions.
c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
d. Instructions for identifying parts and components.
e. Review of spare parts needed for operation and maintenance.

1.7 PREPARATION

A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."

B. Set up instructional equipment at instruction location.

1.8 INSTRUCTION

A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.

B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.

C. Scheduling: Provide instruction at mutually agreed-on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.

1. Schedule training with Owner with at least 14 days' advance notice.

D. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.

E. Evaluation: At conclusion of each training module, assess and document each participant's mastery of module by use of a demonstration performance-based test.

F. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

1.9 DEMONSTRATION AND TRAINING VIDEO RECORDINGS

A. General: Engage a qualified commercial videographer to record demonstration and training video recordings. Record each training module separately. Include classroom instructions and demonstrations, board diagrams, and other visual aids, but not student practice.

1. At beginning of each training module, record each chart containing learning objective and lesson outline.

B. Digital Video Recordings: Provide high-resolution, digital video in MPEG format, produced by a digital camera with minimum sensor resolution of 12 megapixels and capable of recording in full HD mode.

1. Submit video recordings on CD-ROM or thumb drive.
2. File Hierarchy: Organize folder structure and file locations in accordance with Project Manual table of contents. Provide complete screen-based menu.
3. File Names: Utilize file names based on name of equipment generally described in video segment, as identified in Project specifications.
4. Contractor and Installer Contact File: Using appropriate software, create a file for inclusion on the equipment demonstration and training recording that describes the following for each Contractor involved on the Project, arranged in accordance with Project Manual table of contents:

a. Name of Contractor/Installer.
b. Business address.
c. Business phone number.
d. Point of contact.
e. Email address.

C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to adequately cover area of demonstration and training. Display continuous running time.

1. Film training session(s) in segments not to exceed 15 minutes.

    a. Produce segments to present a single significant piece of equipment per segment.
    b. Organize segments with multiple pieces of equipment to follow order of Project Manual table of contents.
    c. Where a training session on a particular piece of equipment exceeds 15 minutes, stop filming and pause training session. Begin training session again upon commencement of new filming segment.

D. Light Levels: Verify light levels are adequate to properly light equipment. Verify equipment markings are clearly visible prior to recording.

    1. Furnish additional portable lighting as required.

E. Preproduced Video Recordings: Provide video recordings used as a component of training modules in same format as recordings of live training.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 024119 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of this Section Includes:

1. Demolition and removal of selected portions of exterior or interior of building or structure and site elements.
2. Removal and salvage of existing items for delivery to Owner and removal of existing items for reinstallation.

B. Related Requirements:

1. Section 011000 "Summary" for restrictions on use of the premises, Owner-occupancy requirements, and phasing requirements.
2. Section 015639 "Temporary Tree and Plant Protection" for temporary protection of existing trees and plants that are affected by selective demolition.
3. Section 017300 "Execution" for cutting and patching procedures.
4. Section 013516 "Alteration Project Procedures" for general protection and work procedures for alteration projects.
5. Section 311000 "Site Clearing" for site clearing and removal of above- and below-grade improvements not part of selective demolition.

1.2 DEFINITIONS

A. Remove: Detach items from existing construction and legally dispose of off-site unless indicated to be removed and salvaged or removed and reinstalled.

B. Remove and Salvage: Detach items from existing construction, in a manner to prevent damage, and deliver to Owner as indicated.

C. Remove and Reinstall: Detach items from existing construction, in a manner to prevent damage; prepare for reuse; and reinstall where indicated.

D. Existing to Remain: Existing items of construction that are not to be removed.

1.3 MATERIALS OWNERSHIP

A. Unless otherwise indicated, demolition waste becomes property of Contractor.

B. Historic items, relics, antiques, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, and other items of interest or value to Owner that may be uncovered during demolition remain the property of Owner.

1. Carefully salvage in a manner to prevent damage and promptly return to Owner.

1.4 COORDINATION

A. Arrange selective demolition schedule so as not to interfere with Owner's operations.

1.5 PREINSTALLATION MEETINGS

A. Predemolition Conference: Conduct conference at Project site.

1. Inspect and discuss condition of construction to be selectively demolished.
2. Review structural load limitations of existing structure.
3. Review and finalize selective demolition schedule and verify availability of demolition personnel, equipment, and facilities needed to make progress and avoid delays.
4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
5. Review areas where existing construction is to remain and requires protection.
6. Review and finalize protection requirements.
7. Review procedures for noise control and dust control.
8. Review storage, protection, and accounting for items to be removed for salvage or reinstallation.

1.6 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Qualification Statements: For refrigerant recovery technician.

C. Survey of Existing Conditions: Submit survey.

D. Proposed Protection Measures: Submit report, including Drawings, that indicates the measures proposed for protecting individuals and property, for environmental protection, for dust control and for noise control. Indicate proposed locations and construction of barriers.

E. Schedule of Selective Demolition Activities: Indicate the following:

1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's on-site operations are uninterrupted.
2. Temporary interruption of utility services. Indicate how long utility services will be interrupted.
3. Coordination for shutoff, capping, and continuation of utility services.

F. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed in accordance with EPA regulations. Include name and address of technician and date refrigerant was recovered.

G. Warranties: Documentation indicating that existing warranties are still in effect after completion of selective demolition.

1.7 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Inventory: Submit a list of items that have been removed and salvaged.

1.8 QUALITY ASSURANCE

A. Refrigerant Recovery Technician Qualifications: **[Type I][Type II][Type III][Universal]** certified by an EPA-approved certification program.

1.9 FIELD CONDITIONS

A. Owner will not occupy portions of building immediately adjacent to selective demolition area.

B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.

C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.

D. Hazardous Materials:

1. Hazardous materials are present in buildings and structures to be selectively demolished. A report on the presence of hazardous materials is included in Specifications Appendix A “Existing Hazardous Material Information” for review and use. Examine report to become aware of locations where hazardous materials are present.

    a. Hazardous material remediation is specified in Sections 028200 "Asbestos Remediation," 028300 “Lead Remediation,” 028400 “PCB Remediation,” and 028416 “Handling of Lighting Ballasts and Lamps Containing PCB’s and Mercury.”

E. On-site sale of removed items or materials is not permitted.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

B. Standards: Comply with ANSI/ASSP A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify that utilities have been disconnected and capped before starting selective demolition operations.

B. Review Project Record Documents of existing construction or other existing condition and hazardous material information provided by Owner. Owner does not guarantee that existing conditions are same as those indicated in Project Record Documents.

C. Verify that hazardous materials have been remediated before proceeding with building demolition operations.

D. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs or video, measured drawings and templates. Comply with Section 013233 "Photographic Documentation."

1. Inventory and record the condition of items to be removed for salvage or reinstallation. Photograph or video conditions that might be misconstrued as damage caused by removal.
2. Photograph or video existing conditions of adjoining construction including finish surfaces, that might be misconstrued as damage caused by selective demolition operations or removal of items for salvage or reinstallation.

3.2 PREPARATION

A. Temporary Shoring: Design, provide, and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.

1. Strengthen or add new supports when required during progress of selective demolition.

B. Temporary Protection: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.

1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
4. Cover and protect furniture, furnishings, and equipment that have not been removed.
5. Comply with requirements for temporary enclosures, dust control, heating, and cooling specified in Section 015000 "Temporary Facilities and Controls."

C. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location and cleaned and reinstalled in their original locations after selective demolition operations are complete.

D. Refrigerant: Before starting demolition, remove refrigerant from mechanical equipment in accordance with 40 CFR 82 and regulations of authorities having jurisdiction.

3.3 UTILITY SERVICES AND BUILDING SYSTEMS

A. Existing Services/Systems to Remain: Maintain utilities and building systems and equipment to remain and protect against damage during selective demolition operations.

1. Maintain fire-protection facilities in service during selective demolition operations.

B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off utilities and building systems serving areas to be selectively demolished.

1. Arrange to shut off utilities with utility companies.
2. If disconnection of utilities and building systems will affect adjacent occupied parts of the building, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to those parts of the building.
3. Demolish and remove existing building systems, equipment, and components indicated on Drawings to be removed.

    a. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
    b. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.
    c. Equipment to Be Removed: Disconnect and cap services and remove equipment and components.

3.4 SALVAGE/REINSTALL

A. Removed and Salvaged Items:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers with label indicating elements, date of removal, quantity, and location where removed.
3. Store items in a secure area until delivery to Owner.
4. Transport items to Owner's storage area designated by Owner.
5. Protect items from damage during transport and storage.

B. Removed and Reinstalled Items:

1. Clean and repair items to functional condition adequate for intended reuse.
2. Pack or crate items after cleaning and repairing. Identify contents of containers.
3. Protect items from damage during transport and storage.

4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

3.5 SELECTIVE DEMOLITION, GENERAL

A. General: Demolish and remove existing construction only to extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:

1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping. Temporarily cover openings to remain.
3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
5. Maintain fire watch during and for at least four hours after flame-cutting operations.
6. Maintain adequate ventilation when using cutting torches.
7. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
8. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
9. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.

B. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

1. Do not close or obstruct streets, walks, walkways, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction. Provide alternate routes around closed or obstructed trafficways if required by authorities having jurisdiction.
2. Use water mist and other suitable methods to limit spread of dust and dirt. Comply with governing environmental-protection regulations. Do not use water when it may damage adjacent construction or create hazardous or objectionable conditions, such as ice, flooding, and pollution.

3.6 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

A. Concrete:

1. Demolish in small sections. Using power-driven saw, cut concrete to a depth of at least 3/4 inch at junctures with construction to remain. Dislodge concrete from reinforcement at perimeter of areas being demolished, cut reinforcement, and then remove remainder of concrete. Neatly trim openings to dimensions indicated.
2. Demolish in sections. Cut concrete full depth at junctures with construction to remain and at regular intervals using power-driven saw, and then remove concrete between saw cuts.

B. Masonry: Demolish in small sections. Cut masonry at junctures with construction to remain, using power-driven saw, and then remove masonry between saw cuts.

C. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, and then break up and remove.

D. Resilient Floor Coverings: Remove floor coverings and adhesive in accordance with recommendations in RFCI's "Recommended Work Practices for the Removal of Resilient Floor Coverings." Do not use methods requiring solvent-based adhesive strippers.

E. Roofing: Remove no more existing roofing than what can be covered in one day by new roofing and so that building interior remains watertight and weathertight.

1. Remove existing roof membrane, flashings, copings, and roof accessories.
2. Remove existing roofing system down to substrate.

3.7 DISPOSAL OF DEMOLISHED MATERIALS

A. Remove demolition waste materials from Project site and dispose of them in an EPA-approved construction and demolition waste landfill acceptable to authorities having jurisdiction and recycle or dispose of them in accordance with Section 017419 "Construction Waste Management and Disposal."

1. Do not allow demolished materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
4. Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."

B. Burning: Do not burn demolished materials.

3.8 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION

SECTION 028200 - ASBESTOS REMEDIATION

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP Z9.2	ASSP Z9.2(2018) Fundamentals Governing the Design and Operation of Local Exhaust Ventilation Systems

ASTM INTERNATIONAL (ASTM)

ASTM D4397	(2016) Standard Specification for Polyethylene Sheeting for Construction, Industrial, and Agricultural Applications
ASTM E1368	(2014) Visual Inspection of Asbestos Abatement Projects

COMPRESSED GAS ASSOCIATION (CGA)

CGA G-7	(2014) Compressed Air for Human Respiration; 6th Edition

INTERNATIONAL SAFETY EQUIPMENT ASSOCIATION (ISEA)

ANSI/ISEA Z87.1	(2020) Occupational and Educational Personal Eye and Face Protection Devices

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 701	(2023; ERTA 1 2023) Standard Methods of Fire Tests for Flame Propagation of Textiles and Films

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH)

NIOSH NMAM	(2016; 5th Ed) NIOSH Manual of Analytical Methods

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 340/1-90/018	(1990) Asbestos/NESHAP Regulated Asbestos Containing Materials Guidance

EPA 560/5-85-024	(1985) Guidance for Controlling Asbestos-Containing Materials in Buildings (Purple Book)

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.147	The Control of Hazardous Energy (Lock Out/Tag Out)
29 CFR 1926.51	Sanitation
29 CFR 1926.59	Hazard Communication
29 CFR 1926.103	Respiratory Protection
29 CFR 1926.200	Accident Prevention Signs and Tags
29 CFR 1926.1101	Asbestos
40 CFR 61-SUBPART A	General Provisions
40 CFR 61-SUBPART M	National Emission Standard for Asbestos
40 CFR 763	Asbestos
42 CFR 84	Approval of Respiratory Protective Devices
49 CFR 107	Hazardous Materials Program Procedures
49 CFR 171	General Information, Regulations, and Definitions
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements
49 CFR 173	Shippers - General Requirements for Shipments and Packagings

UNDERWRITERS LABORATORIES (UL)

UL 586	(2009; Reprint Sep 2022) UL Standard for Safety High-Efficiency Particulate, Air Filter Units

STATE OF MAINE, DEPARTMENT OF ENVIRONMENTAL PROTECTION

ME L&C PROGRAM	State of Maine Licensing and Certification Program http://www.mainelegisulature.org/legis/statutes/38/title 3
06 096 CMR	425 Asbestso Management Regulations http://www.maine.gov/sos/cec/rules/06/096/096c425.doc

1.2 DEFINITIONS

1.2.1 ACM

Asbestos Containing Materials.

1.2.2 Amended Water

Water containing a wetting agent or surfactant with a maximum surface tension of 0.00042 psi.

1.2.3 Area Sampling

Sampling of asbestos fiber concentrations which approximates the concentrations of asbestos in the theoretical breathing zone but is not actually collected in the breathing zone of an employee.

1.2.4 Asbestos

The term asbestos includes chrysotile, amosite, crocidolite, tremolite asbestos, anthophyllite asbestos, and actinolite asbestos and any of these minerals that has been chemically treated or altered. Materials are considered to contain asbestos if the asbestos content of the material is determined to be equal to or greater than one percent.

1.2.5 Asbestos Control Area

That area where asbestos removal operations are performed which is isolated by physical boundaries which assist in the prevention of the uncontrolled release of asbestos dust, fibers, or debris.

1.2.6 Asbestos Fibers

Those fibers having an aspect ratio of at least 3:1 and longer than 5 micrometers as determined by National Institute for Occupational Safety and Health (NIOSH) Method 7400.

1.2.7 Asbestos Permissible Exposure Limit

0.1 fibers per cubic centimeter of air as an 8-hour time weighted average measured in the breathing zone as defined by 29 CFR 1926.1101 or other Federal legislation having legal jurisdiction for the protection of workers health.

1.2.8 Authorized Person

Any person authorized by the Contractor and required by work duties to be present in the regulated areas.

1.2.9 Background

The ambient airborne asbestos concentration in an uncontaminated area as measured prior to any asbestos hazard abatement efforts. Background concentrations for other (contaminated) areas are measured in similar but asbestos free locations.

1.2.10 Competent Person (CP)

A person meeting the requirements for competent person as specified in 29 CFR 1926.1101 including a person capable of identifying existing asbestos hazards in the workplace and selecting the appropriate control strategy for asbestos exposure, who has the authority to take prompt corrective

measures to eliminate them, and is specifically trained in a training course which meet the criteria of EPA's Model Accreditation Plan (40 CFR 763) for project designer or supervisor, or its equivalent. The competent person must have a current State of Maine asbestos contractors or supervisors license.

1.2.11 Contractor

The Contractor is that individual, or entity under contract to perform the herein listed work.

1.2.12 Disposal Bag

A 6 mil thick, leak-tight plastic bag, pre-labeled in accordance with 29 CFR 1926.1101, used for transporting asbestos waste from containment to disposal site.

1.2.13 Disturbance

Activities that disrupt the matrix of ACM, crumble or pulverize ACM, or generate visible debris from ACM. Disturbance includes cutting away small amounts of ACM, no greater than the amount which can be contained in one standard sized glovebag or waste bag, not larger than 60 inches in length and width in order to access a building component.

1.2.14 Encapsulation

The abatement of an asbestos hazard through the appropriate use of chemical encapsulants.

1.2.15 Encapsulants

Specific materials in various forms used to chemically or physically entrap asbestos fibers in various configurations to prevent these fibers from becoming airborne. There are four types of encapsulants as follows which must comply with performance requirements as specified herein.

a. Removal Encapsulant (can be used as a wetting agent)

b. Bridging Encapsulant (used to provide a tough, durable surface coating to asbestos containing material)

c. Penetrating Encapsulant (used to penetrate the asbestos containing material encapsulating all asbestos fibers and preventing fiber release due to routine mechanical damage)

d. Lock-Down Encapsulant (used to seal off or "lock-down" minute asbestos fibers left on surfaces from which asbestos containing material has been removed).

1.2.16 Friable Asbestos Material

A term defined in 40 CFR 61-SUBPART M and EPA 340/1-90/018 meaning any material which contains equal to or greater than 1 percent asbestos, as determined using the method specified in 40 CFR 763, Polarized Light Microscopy (PLM), that when dry, can be crumbled, pulverized, or reduced to powder by hand pressure.

1.2.17 Glovebag Technique

Those asbestos removal and control techniques put forth in 29 CFR 1926.1101.

1.2.18 Government Consultant (GC)

That qualified person employed directly by the Government to monitor, sample, inspect the work or in some other way advise the Owner's Representative. The GC is normally a private consultant, but can be an employee of the Government.

1.2.19 HEPA Filter Equipment

High efficiency particulate air (HEPA) filtered vacuum and exhaust ventilation equipment with a filter system capable of collecting and retaining asbestos fibers. Filters must retain 99.97 percent of particles 0.3 microns or larger as indicated in UL 586.

1.2.20 Model Accreditation Plan (MAP)

USEPA training accreditation requirements for persons who work with asbestos as specified in 40 CFR 763.

1.2.21 Negative Pressure Enclosure (NPE)

That engineering control technique described as a negative pressure enclosure in 29 CFR 1926.1101.

1.2.22 NESHAP

National Emission Standards for Hazardous Air Pollutants. The USEPA NESHAP regulation for asbestos is at 40 CFR 61-SUBPART M.

1.2.23 Nonfriable Asbestos Material

Material that contains asbestos in which the fibers have been immobilized by a bonding agent, coating, binder, or other material so that the asbestos is well bound and will not normally release asbestos fibers during any appropriate use, handling, storage or transportation. It is understood that asbestos fibers may be released under other conditions such as demolition, removal, or mishap.

1.2.24 Permissible Exposure Limits (PELs)

1.2.24.1 PEL-Time Weighted Average(TWA)

Concentration of asbestos not in excess of 0.1 fibers per cubic centimeter of air (f/cc) as an 8-hour time weighted average (TWA).

1.2.24.2 PEL-Excursion Limit

An airborne concentration of asbestos not in excess of 1.0 f/cc of air as averaged over a sampling period of 30 minutes.

1.2.25 Personal Sampling

Air sampling which is performed to determine asbestos fiber concentrations within the breathing zone of a specific employee, as performed in accordance with 29 CFR 1926.1101.

1.2.26 Private Qualified Person (PQP)

That qualified person hired by the Contractor to perform the herein listed tasks.

1.2.27 Qualified Person (QP)

A Registered Architect, Professional Engineer, Certified Industrial Hygienist, consultant or other qualified person who has successfully completed training and is therefore accredited under a legitimate State Model Accreditation Plan as described in 40 CFR 763 as a Building Inspector, Contractor/Supervisor Abatement Worker, and Asbestos Project Designer; and has successfully completed the National Institute of Occupational Safety and Health (NIOSH) 582 course "Sampling and Evaluating Airborne Asbestos Dust" or equivalent. The QP must be qualified to perform visual inspections as indicated in ASTM E1368. The QP must be appropriately licensed in the State of Maine.

1.2.28 TEM

Refers to Transmission Electron Microscopy.

1.2.29 Time Weighted Average (TWA)

The TWA is an 8-hour time weighted average airborne concentration of asbestos fibers.

1.2.30 Transite

A generic name for asbestos cement wallboard and pipe.

1.2.31 Wetting Agent

A chemical added to water to reduce the water's surface tension thereby increasing the water's ability to soak into the material to which it is applied. An equivalent wetting agent must have a surface tension of at most0.00042 psi.

1.2.32 Worker

Individual (not designated as the Competent Person or a supervisor) who performs asbestos work and has completed asbestos worker training required by 29 CFR 1926.1101, to include EPA Model Accreditation Plan (MAP) "Worker" training; accreditation, if required by the OSHA Class of work to be performed or by the state where the work is to be performed. The worker must be appropriately licensed in the State of Maine.

1.3 REQUIREMENTS

1.3.1 Description of Work

The work covered by this section includes the handling and control of asbestos containing materials and describes some of the resultant procedures and equipment required to protect workers, the environment and occupants of the building or area, or both, from contact with airborne asbestos fibers. The work also includes the disposal of any asbestos containing materials generated by the work. More specific operational procedures must be outlined in the Asbestos Hazard Abatement Plan called for elsewhere in this specification. The asbestos work includes the demolition and removal of friable and non-friable materials located at Buildings 400 and 401 as indicated which is governed by MEDEP Chapter 425: Asbestos Management Regulations, 40 CFR 763, and other applicable Federal, State, and local requirements. Refer to the report at the end of this section. Under normal conditions non-friable or chemically bound materials containing asbestos would not be considered hazardous; however, this material may release airborne asbestos fibers during demolition and removal and therefore must be handled in accordance with the removal and disposal procedures as specified

herein. Provide negative pressure enclosure and glovebag techniques as outlined in this specification. The buildings will be evacuated during the asbestos abatement work. A competent person must supervise asbestos removal work as specified herein.

1.3.2 Unexpected Discovery of Asbestos

Notify the Owner's Representative if any previously untested building components suspected to contain asbestos are impacted by the work.

1.3.3 Medical Requirements

Provide medical requirements including but not limited to medical surveillance and medical record keeping as listed in 29 CFR 1926.1101.

1.3.3.1 Medical Examinations

Before exposure to airborne asbestos fibers, provide workers with a comprehensive medical examination as required by 29 CFR 1926.1101 or other pertinent State or local directives. This requirement must have been satisfied within the 12 months prior to the start of work on this contract. The same medical examination must be given on an annual basis to employees engaged in an occupation involving asbestos and within 30 calendar days before or after the termination of employment in such occupation. Specifically identify x-ray films of asbestos workers to the consulting radiologist and mark medical record jackets with the word "ASBESTOS."

1.3.3.2 Medical Records

Maintain complete and accurate records of employees' medical examinations, medical records, and exposure data for a period of indefinite time after termination of employment and make records of the required medical examinations and exposure data available for inspection and copying to: The Assistant Secretary of Labor for Occupational Safety and Health (OSHA), or authorized representatives of them, and an employee's physician upon the request of the employee or former employee.

1.3.4 Employee Training

Submit certificates, prior to the start of work but after the main abatement submittal, signed by each employee indicating that the employee has received training in the proper handling of materials and wastes that contain asbestos in accordance with 40 CFR 763; understands the health implications and risks involved, including the illnesses possible from exposure to airborne asbestos fibers; understands the use and limits of the respiratory equipment to be used; and understands the results of monitoring of airborne quantities of asbestos as related to health and respiratory equipment as indicated in 29 CFR 1926.1101 on an initial and annual basis. Organize certificates by individual worker, not grouped by type of certification. Post appropriate evidence of compliance with the training requirements of 40 CFR 763. Train personnel involved in the asbestos control work in accordance with United States Environmental Protection Agency (USEPA) Asbestos Hazard Emergency Response Act (AHERA) training criteria or State training criteria whichever is more stringent. Document the training by providing: dates of training, training entity, course outline, names of instructors, and qualifications of instructors upon request by the Owner's Representative. Furnish each employee with respirator training and fit testing administered by the PQP as required by 29 CFR 1926.1101 and 29 CFR 1926.103. Fully cover engineering and other hazard control techniques and procedures. Asbestos workers must have a current State of Maine asbestos worker's license in compliance with the ME L&C PROGRAM.

1.3.5 Permits, Licenses and Notifications

Prior to the start of work, obtain necessary permits and licenses in conjunction with asbestos removal, encapsulation, hauling, and disposition, and furnish notification of such actions required by Federal, State, regional, and local authorities. Notify the Maine Department of Environmental Protection and the Owner in writing 20 working days prior to commencement of work in accordance with MEDEP Chapter 425: Asbestos Management Regulations. Notify other appropriate Government agencies in writing 20 working days prior to the start of asbestos work as indicated in applicable laws, ordinances, criteria, rules, and regulations. Submit copies of all Notifications to the Owner's Representative.

1.3.6 Environment, Safety and Health Compliance

In addition to detailed requirements of this specification, comply with those applicable laws, ordinances, criteria, rules, and regulations of Federal, State, regional, and local authorities regarding handling, storing, transporting, and disposing of asbestos waste materials. Comply with the applicable requirements of the current issue of EM 385-1-1, 29 CFR 1926.1101, 40 CFR 61-SUBPART A, 40 CFR 61-SUBPART M, and 40 CFR 763. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting the work. Where the requirements of this specification, applicable laws, rules, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirement as defined by the Government apply. The following laws, ordinances, criteria, rules and regulations regarding removal, handling, storing, transporting and disposing of asbestos materials apply:

a. U.S. EPA, Title 40, CFR Part 61, National Standards for Hazardous Air Pollutants (NESHAP), Subparts A and M.

b. OSHA, 29 CFR, Part 1926.1101, Asbestos in Construction.

c. State of Maine, Department of Environmental Protection (ME DEP), 06 096 CMR Asbestos Management Regulations, Chapter 425, effective date 4-3-2011.

1.3.7 Respiratory Protection Program

Establish and implement a respirator program as required by 29 CFR 1926.1101, and 29 CFR 1926.103. Submit a written description of the program to the Owner's Representative. Submit a written program manual or operating procedure including methods of compliance with regulatory statutes.

1.3.7.1 Respirator Program Records

Submit records of the respirator program as required by 29 CFR 1926.103, and 29 CFR 1926.1101.

1.3.7.2 Respirator Fit Testing

The Contractor's PQP must conduct a qualitative or quantitative fit test conforming to 29 CFR 1926.103 for each worker required to wear a respirator, and any authorized visitors who enter a regulated area where respirators are required to be worn. A respirator fit test must be performed prior to initially wearing a respirator and every 12 months thereafter. If physical changes develop that will affect the fit, a new fit test must be performed. Functional fit checks must be performed each time a respirator is put on and in accordance with the manufacturer's recommendation.

1.3.7.3 Respirator Selection and Use Requirements

Provide respirators, and ensure that they are used as required by 29 CFR 1926.1101 and in accordance with CGA G-7 and the manufacturer's recommendations. Respirators must be approved by the National Institute for Occupational Safety and Health NIOSH, under the provisions of 42 CFR 84, for use in environments containing airborne asbestos fibers. For air-purifying respirators, the particulate filter must be high-efficiency particulate air (HEPA)/(N-,R-,P-100). The initial respirator selection and the decisions regarding the upgrading or downgrading of respirator type must be made by the Contractor's Designated IH based on the measured or anticipated airborne asbestos fiber concentrations to be encountered.

1.3.8 Asbestos Hazard Control Supervisor

The Contractor must be represented on site by a supervisor, trained using the model Contractor accreditation plan as indicated in the Federal statutes for all portions of the herein listed work.

1.3.9 Hazard Communication

Adhere to all parts of 29 CFR 1926.59 and provide the Owner's Representative with a copy of the Safety Data Sheets (SDS) for all materials brought to the site.

1.3.10 Asbestos Hazard Abatement Plan

Submit a detailed plan of the safety precautions such as lockout, tagout, tryout, fall protection, and confined space entry procedures and equipment and work procedures to be used in the removal and demolition of materials containing asbestos. The plan, not to be combined with other hazard abatement plans, must be prepared, signed, and sealed by the PQP. Provide a Table of Contents for each abatement submittal, which follows the sequence of requirements in the contract. The plan must include but not be limited to the precise personal protective equipment to be used including, but not limited to, respiratory protection, type of whole-body protection and if reusable coveralls are to be employed decontamination methods (operations and quality control plan), the location of asbestos control areas including clean and dirty areas, buffer zones, showers, storage areas, change rooms, removal method, interface of trades involved in the construction, sequencing of asbestos related work, disposal plan, type of wetting agent and asbestos sealer to be used, locations of local exhaust equipment, planned air monitoring strategies, and a detailed description of the method to be employed in order to control environmental pollution. The plan must also include (both fire and medical emergency) response plans and an Activity Hazard Analyses (AHAs) in accordance with EM 385-1-1. The Asbestos Hazard Abatement Plan must be approved in writing prior to starting any asbestos work. The Contractor, Asbestos Hazard Control Supervisor, CP and PQP must meet with the Owner's Representative prior to beginning work, to discuss in detail the Asbestos Hazard Abatement Plan, including work procedures and safety precautions. Once approved by the Owner's Representative, the plan will be enforced as if an addition to the specification. Any changes required in the specification as a result of the plan must be identified specifically in the plan to allow for free discussion and approval by the Owner's Representative prior to starting work.

1.3.11 Testing Laboratory

Submit the name, address, and telephone number of each testing laboratory selected for the sampling, analysis, and reporting of airborne concentrations of asbestos fibers along with evidence that each laboratory selected holds the appropriate State license and permits and certification that each laboratory is American Industrial Hygiene Association (AIHA) accredited and that persons counting the samples have been judged proficient by current inclusion on the AIHA Asbestos Analysis Registry

(AAR) and successful participation of the laboratory in the Proficiency Analytical Testing (PAT) Program. Where analysis to determine asbestos content in bulk materials or transmission electron microscopy is required, submit evidence that the laboratory is accredited by the National Institute of Science and Technology (NIST) under National Voluntary Laboratory Accreditation Program (NVLAP) for asbestos analysis. The testing laboratory firm must be independent of the asbestos contractor and must have no employee or employer relationship which could constitute a conflict of interest.

1.3.12 Landfill Approval

Submit written evidence that the landfill is approved for asbestos disposal by the U.S. Environmental Protection Agency, Region 1, Air Enforcement Section, and local regulatory agencies. Within three working days after delivery, submit detailed delivery tickets, prepared, signed, and dated by an agent of the landfill, certifying the amount of asbestos materials delivered to the landfill. Submit a copy of the waste shipment records within one day of the shipment leaving the project site.

1.3.13 Transporter Certification

Submit written evidence that the transporter is approved to transport asbestos waste in accordance with the DOT requirements of 49 CFR 171, 49 CFR 172 and 49 CFR 173 as well as registration requirements of 49 CFR 107 and all other State and local regulatory agency requirements.

1.3.14 Medical Certification

Provide a written certification for each worker and supervisor, signed by a licensed physician indicating that the worker and supervisor has met or exceeded all of the medical prerequisites listed herein and in 29 CFR 1926.1101 and 29 CFR 1926.103 as prescribed by law. Submit certificates prior to the start of work but after the main abatement submittal.

1.4 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES and the individual sections specifying the work:

SD-06 Test Reports

Air Sampling Results Pressure Differential Recordings for Local Exhaust

System

Clearance Sampling

Asbestos Disposal Quantity Report

SD-07 Certificates

Employee Training

Notifications

Respiratory Protection Program

Asbestos Hazard Abatement Plan

Testing Laboratory

Landfill Approval

Delivery Tickets

Waste Shipment Records

Transporter Certification

Medical Certification Private Qualified Person

Documentation

Competent Person

Worker's License

Contractor's License Equipment Used to Contain Airborne Asbestos

Fibers Water Filtration Equipment

Vacuums

Ventilation Systems

SD-11 Closeout Submittals

Permits and Licenses

Notifications

Respirator Program Records

Rental Equipment

1.5 QUALITY ASSURANCE

1.5.1 Private Qualified Person Documentation

Submit the name, address, and telephone number of the Private Qualified Person (PQP) selected to prepare the Asbestos Hazard Abatement Plan, direct monitoring and training, and documented evidence that the PQP has successfully completed training in and is accredited and where required is certified as, a Building Inspector, Contractor/Supervisor Abatement Worker, and Asbestos Project Designer as described by 40 CFR 763 and has successfully completed the National Institute of Occupational Safety and Health (NIOSH) 582 course "Sampling and Evaluating Airborne Asbestos Dust" or equivalent. The PQP must be appropriately licensed in the State of Maine as a Project Monitor. The PQP and the asbestos contractor must not have an employee/employer relationship or financial relationship which could constitute a conflict of interest. The PQP must be a first tier subcontractor.

1.5.2 Competent Person Documentation

The Competent Person must be experienced in the administration and supervision of asbestos abatement projects including exposure assessment and monitoring, work practices, abatement

methods, protective measures for personnel, setting up and inspecting asbestos abatement work areas, evaluating the integrity of containment barriers, placement and operation of local exhaust systems, ACM generated waste containment and disposal procedures, decontamination units installation and maintenance requirements, site safety and health requirements, and notification of other employees onsite. The Competent Person must be on-site at all times when asbestos abatement activities are underway. Submit training certification and a current State of Maine Asbestos Contractor's and Supervisor's License. Submit evidence that the Competent Person has a minimum of 2 years of on-the-job asbestos abatement experience relevant to OSHA competent person requirements.

1.5.3 Worker's License

Submit documentation that workers meet the requirements of 29 CFR 1926.1101, 40 CFR 61-SUBPART M and have a current State of Maine Asbestos Workers License.

1.5.4 Contractor's License

Submit a copy of the asbestos contractor's license issued by the State of Maine. Submit the following certification along with the license: "I certify that the personnel I am responsible for during the course of this project fully understand the contents of 29 CFR 1926.1101, 40 CFR 61-SUBPART M, EM 385-1-1, and the Federal, State and local requirements for those asbestos abatement activities that they will be involved in." This certification statement must be signed by the Company's President or Chief Executive.

1.5.5 Air Sampling Results

Complete fiber counting and provide results to the PQP and GC for review within 16 hours of the "time off" of the sample pump. Notify the Owner's Representative immediately of any airborne levels of asbestos fibers in excess of the acceptable limits. Submit sampling results to the Owner's Representative and the affected Contractor employees where required by law within three working days, signed by the testing laboratory employee performing air sampling, the employee that analyzed the sample, and the PQP and GC. Notify the Contractor and the Owner's Representative immediately of any variance in the pressure differential which could cause adjacent unsealed areas to have asbestos fiber concentrations in excess of 0.010 fibers per cubic centimeter or background whichever is higher. In no circumstance must levels exceed 0.10 fibers per cubic centimeter.

1.5.6 Pressure Differential Recordings for Local Exhaust System

Provide a local exhaust system that creates a negative pressure of at least 0.02 inches of water relative to the pressure external to the enclosure and operate it continuously, 24-hours a day, until the temporary enclosure of the asbestos control area is removed. Submit pressure differential recordings for each work day to the PQP and GC for review and to the Owner's Representative within 24-hours from the end of each work day.

1.5.7 Preconstruction Conference

Conduct a safety preconstruction conference to discuss the details of the Asbestos Hazard Abatement Plan, Accident Prevention Plan. The safety preconstruction conference must include the Contractor and their Designated Competent Person, Designated IH and Project Supervisor and the Owner's Representative. Deficiencies in the APP will be discussed. Onsite work must not begin until the APP has been accepted.

1.6 EQUIPMENT

1.6.1 Rental Equipment

Provide a copy of the written notification to the rental company concerning the intended use of the equipment and the possibility of asbestos contamination of the equipment.

PART 2 PRODUCTS

2.1 DUCT TAPE

Industrial grade duct tape of appropriate widths suitable for bonding sheet plastic and disposal container.

2.2 DISPOSAL CONTAINERS

Leak-tight (defined as solids, liquids, or dust that cannot escape or spill out) disposal containers must be provided for ACM wastes as required by 29 CFR 1926.1101. Disposal containers can be in the form of:

a. Disposal Bags

2.3 SHEET PLASTIC

Sheet plastic must be polyethylene of 6 mil minimum thickness and must be provided in the largest sheet size necessary to minimize seams. Film must be clear and conform to ASTM D4397, except as specified below

2.3.1 Flame Resistant

Where a potential for fire exists, flame-resistant sheets must be provided. Film must be frosted and must conform to the requirements of NFPA 701.

2.3.2 Reinforced

Reinforced sheets must be provided where high skin strength is required, such as where it constitutes the only barrier between the regulated area and the outdoor environment. The sheet stock must consist of translucent, nylon-reinforced or woven-polyethylene thread laminated between 2 layers of polyethylene film. Film must meet flame resistant standards of NFPA 701.

2.4 MASTIC REMOVING SOLVENT

Mastic removing solvent must be nonflammable and must not contain methylene chloride, glycol ether, or halogenated hydrocarbons. Solvents used onsite must have a flash point greater than 140 degrees F.

2.5 LEAK-TIGHT WRAPPING

At least two layers of 6 mil minimum thick polyethylene sheet stock must be used for the containment of removed asbestos-containing components or materials such as large tanks, boilers, insulated pipe segments and other materials. Upon placement of the ACM component or material, each layer must be individually leak-tight sealed with duct tape.

2.6 VIEWING INSPECTION WINDOW

Where feasible, a minimum of one clear, 1/8 inch thick, acrylic sheet, 18 by 24 inches, must be installed as a viewing inspection window at eye level on a wall in each containment enclosure. The windows must be sealed leak-tight with industrial grade duct tape.

2.7 WETTING AGENTS

Removal encapsulant (a penetrating encapsulant) must be provided when conducting removal abatement activities that require a longer removal time or are subject to rapid evaporation of amended water. The removal encapsulant must be capable of wetting the ACM and retarding fiber release during disturbance of the ACM greater than or equal to that provided by amended water.

PART 3 EXECUTION

3.1 EQUIPMENT

Provide the Owner's Representative with at least two complete sets of personal protective equipment as required for entry to and inspection of the asbestos control area. Provide equivalent training to the Owner's Representative as provided to Contractor employees in the use of the required personal protective equipment. Provide manufacturer's certificate of compliance for all equipment used to contain airborne asbestos fibers.

3.1.1 Air Monitoring Equipment

The Contractor's PQP must approve air monitoring equipment. The equipment must include, but must not be limited to:

a. High-volume sampling pumps that can be calibrated and operated at a constant airflow up to 16 liters per minute.

b. Low-volume, battery powered, body-attachable, portable personal pumps that can be calibrated to a constant airflow up to approximately 3.5 liters per minute, and a self-contained rechargeable power pack capable of sustaining the calibrated flow rate for a minimum of 10 hours. The pumps must also be equipped with an automatic flow control unit which must maintain a constant flow, even as filter resistance increases due to accumulation of fiber and debris on the filter surface.

c. Single use standard 25 mm diameter cassette, open face, 0.8 micron pore size, mixed cellulose ester membrane filters and cassettes with 50 mm electrically conductive extension cowl, and shrink bands for personal air sampling.

3.1.2 Respirators

Select respirators from those approved by the National Institute for Occupational Safety and Health (NIOSH), Department of Health and Human Services.

3.1.2.1 Respirators for Handling Asbestos

Provide personnel engaged in pre-cleaning, cleanup, handling, removal and demolition of asbestos materials with respiratory protection as indicated in 29 CFR 1926.1101 and 29 CFR 1926.103. Breathing air must comply with CGA G-7.

3.1.3 Exterior Whole Body Protection

3.1.3.1 Outer Protective Clothing

Provide personnel exposed to asbestos with disposable "non-breathable," or reusable "non-breathable" whole body outer protective clothing, head coverings, gloves, and foot coverings. Provide disposable plastic or rubber gloves to protect hands. Cloth gloves may be worn inside the plastic or rubber gloves for comfort, but must not be used alone. Make sleeves secure at the wrists, make foot coverings secure at the ankles, and make clothing secure at the neck by the use of tape.

3.1.3.2 Work Clothing

Provide cloth work clothes for wear under the outer protective clothing and foot coverings and either dispose of or properly decontaminate them as recommended by the PQP after each use.

3.1.3.3 Personal Decontamination Unit

Provide a temporary, negative pressure unit with a separate decontamination locker room and clean locker room with a shower that complies with 29 CFR 1926.51(f)(4)(ii) through (V) in between for personnel required to wear whole body protective clothing. Provide two separate lockers for each asbestos worker, one in each locker room. Keep street clothing and street shoes in the clean locker. HEPA vacuum and remove asbestos contaminated disposable protective clothing while still wearing respirators at the boundary of the asbestos work area and seal in impermeable bags or containers for disposal. HEPA vacuum and remove asbestos contaminated reusable protective clothing while still wearing respirators at the boundary of the asbestos work area, seal in two impermeable bags, label outer bag as asbestos contaminated waste, and transport for decontamination. Do not wear work clothing between home and work. Locate showers between the decontamination locker room and the clean locker room and require that all employees shower before changing into street clothes. Collect used shower water and filter with approved water filtration equipment to remove asbestos contamination. Wastewater filters must be installed in series with the first stage pore size 20 microns and the second stage pore size of 5 microns. Dispose of filters and residue as asbestos waste. Discharge clean water to the sanitary system. Dispose of asbestos contaminated work clothing as asbestos contaminated waste or properly decontaminate as specified in the Contractor's Asbestos Hazard Abatement Plan. Keep the floor of the decontamination unit's clean room dry and clean at all times. Proper housekeeping and hygiene requirements must be maintained. Provide soap and towels for showering, washing and drying. Cloth towels provided must be disposed of as ACM waste or must be laundered in accordance with 29 CFR 1926.1101. Physically attach the decontamination units to the asbestos control area. Construct both a personnel decontamination unit and an equipment decontamination unit onto and integral with each asbestos control area.

3.1.3.4 Eye Protection

Provide eye protection that complies with ANSI/ISEA Z87.1 when operations present a potential eye injury hazard. Provide goggles to personnel engaged in asbestos abatement operations when the use of a full face respirator is not required.

3.1.4 Regulated Areas

All Class I, II, and III asbestos work must be conducted within regulated areas. The regulated area must be demarcated to minimize the number of persons within the area and to protect persons outside the area from exposure to airborne asbestos. Control access to regulated areas, ensure that only

authorized personnel enter, and verify that Contractor required medical surveillance, training and respiratory protection program requirements are met prior to allowing entrance.

3.1.5 Load-out Unit

Provide a temporary load-out unit that is adjacent and connected to the regulated area and access tunnel. Attach the load-out unit in a leak-tight manner to each regulated area.

3.1.6 Warning Signs and Labels

Provide warning signs printed in English and at all approaches to asbestos control areas. Locate signs at such a distance that personnel may read the sign and take the necessary protective steps required before entering the area. Provide labels and affix to all asbestos materials, scrap, waste, debris, and other products contaminated with asbestos. Containers with preprinted warning labels conforming to the requirements are acceptable

3.1.6.1 Warning Sign

Provide vertical format conforming to 29 CFR 1926.200, and 29 CFR 1926.1101 minimum 20 by 14 inches displaying the following legend in the lower panel:

Legend	Notation
DANGER	one inch Sans Serif Gothic or Block
ASBESTOS	one inch Sans Serif Gothic or Block
MAY CAUSE CANCER	one inch Sans Serif Gothic or Block
CAUSES DAMAGE TO LUNGS	1/4 inch Sans Serif Gothic or Block
AUTHORIZED PERSONNEL ONLY	1/4 inch Sans Serif Gothic or Block
WEAR RESPIRATORY PROTECTION AND PROTECTIVE CLOTHING IN THIS AREA	1/4 inch Sans Serif Gothic or Block

Spacing between lines must be at least equal to the height of the upper of any two lines.

3.1.6.2 Warning Labels

Provide labels conforming to 29 CFR 1926.1101 of sufficient size to be clearly legible, displaying the following legend:

DANGER
CONTAINS ASBESTOS FIBERS
MAY CAUSE CANCER
CAUSES DAMAGE TO LUNGS
DO NOT BREATH DUST AVOID CREATING DUST

3.1.7 Local Exhaust System

Provide a local exhaust system in the asbestos control area in accordance with ASSP Z9.2 and 29 CFR 1926.1101 that will provide at least four air changes per hour inside of the negative pressure enclosure. Local exhaust equipment must be operated 24-hours per day, until the asbestos control area is removed and must be leak proof to the filter and equipped with HEPA filters. Maintain a minimum pressure differential in the control area of minus 0.02 inch of water column relative to adjacent, unsealed areas. Provide continuous 24-hour per day monitoring of the pressure differential with a pressure differential automatic recording instrument. The building ventilation system must not be used as the local exhaust system for the asbestos control area. Filters on exhaust equipment must conform to ASSP Z9.2 and UL 586. Terminate the local exhaust system out of doors and remote from any public access or ventilation system intakes.

3.1.8 Tools

Vacuums must be leak proof to the filter and equipped with HEPA filters. Filters on vacuums must conform to ASSP Z9.2 and UL 586. Do not use power tools to remove asbestos containing materials unless the tool is equipped with effective, integral HEPA filtered exhaust ventilation systems. Remove all residual asbestos from reusable tools prior to storage or reuse. Reusable tools must be thoroughly decontaminated prior to being removed from the regulated areas.

3.1.9 Rental Equipment

If rental equipment is to be used, furnish written notification to the rental agency concerning the intended use of the equipment and the possibility of asbestos contamination of the equipment.

3.1.10 Glovebags

Glovebag operations must be performed in accordance with the requirements of the State of Maine Department of Environmental Protection. Submit written manufacturers proof that glovebags will not break down under expected temperatures and conditions.

3.1.11 Decontamination Area Exit Procedures

Ensure that the following procedures are followed:

a. Before leaving the regulated area, remove all gross contamination and debris from work clothing using a HEPA vacuum.

b. Employees must remove their protective clothing in the equipment room and deposit the clothing in labeled impermeable bags or containers for disposal or laundering.

c. Employees must not remove their respirators until showering.

d. Employees must shower prior to entering the clean room. If a shower has not been located between the equipment room and the clean room or the work is performed outdoors, ensure that employees engaged in Class
I asbestos jobs: a) Remove asbestos contamination from their work suits in the equipment room or decontamination area using a HEPA vacuum before proceeding to a shower that is not adjacent to the work area; or b) Remove their contaminated work suits in the equipment room, without cleaning worksuits, and proceed to a shower that is not adjacent to the work area.

3.2 WORK PROCEDURE

Perform asbestos related work in accordance with MEDEP Chapter 425: Asbestos Management Regulations, 29 CFR 1926.1101, 40 CFR 61-SUBPART M, and as specified herein. Use wet removal procedures and negative pressure enclosure techniques. Wear and utilize protective clothing and equipment as specified herein. No eating, smoking, drinking, chewing gum, tobacco, or applying cosmetics is permitted in the asbestos work or control areas. Personnel of other trades not engaged in the removal and demolition of asbestos containing material must not be exposed at any time to airborne concentrations of asbestos unless all the personnel protection and training provisions of this specification are complied with by the trade personnel. Shut down the building heating, ventilating, and air conditioning system, cap the openings to the system, and provide temporary heating and ventilation, prior to the commencement of asbestos work. Power to the regulated area must be locked-out and tagged in accordance with 29 CFR 1910.147. Disconnect electrical service when wet removal is performed and provide temporary electrical service with verifiable ground fault circuit interrupter (GFCI) protection prior to the use of any water. All electrical work must be performed by a licensed electrician. Stop abatement work in the regulated area immediately when the airborne total fiber concentration: (1) equals or exceeds 0.010 f/cc, or the pre-abatement concentration, whichever is greater, outside the regulated area; or (2) equals or exceeds 1.0 f/cc inside the regulated area. Correct the condition to the satisfaction of the Owner's Representative, including visual inspection and air sampling. Work must resume only upon notification by the Owner's Representative. Corrective actions must be documented. If an asbestos fiber release or spill occurs, stop work immediately, correct the condition to the satisfaction of the Owner's Representative including clearance sampling, prior to resumption of work.

3.2.1 Building Ventilation System and Critical Barriers

Building ventilation system supply and return air ducts in a regulated area must be shut down and isolated by lockable switch or other positive means in accordance with 29 CFR 1910.147. The airtight seals must consist of air-tight rigid covers for building ventilation supply and exhaust grills where the ventilation system is required to remain in service during abatement. Edges to wall, ceiling and floor surfaces must be sealed with industrial grade duct tape.

a. A Competent Person must supervise the work.

b. For indoor work, critical barriers must be placed over all openings to the regulated area.

c. Impermeable dropcloths must be placed on surfaces beneath all removal activity.

3.2.2 Protection of Existing Work to Remain

Perform work without damage or contamination of adjacent work. Where such work is damaged or contaminated as verified by the Owner's Representative using visual inspection or sample analysis, it must be restored to its original condition or decontaminated by the Contractor at no expense to the Government as deemed appropriate by the Owner's Representative. This includes inadvertent spill of dirt, dust, or debris in which it is reasonable to conclude that asbestos may exist. When these spills occur, stop work immediately. Then clean up the spill. When satisfactory visual inspection and air sampling results are obtained from the PQP work may proceed at the discretion of the Owner's Representative.

3.2.3 Furnishings

Furniture and equipment will be removed from the area of work by the Government before asbestos work begins.

3.2.4 Precleaning

Wet wipe and HEPA vacuum all surfaces potentially contaminated with asbestos prior to establishment of an enclosure.

3.2.5 Asbestos Control Area Requirements

3.2.5.1 Negative Pressure Enclosure

Removal of asbestos contaminated acoustical ceiling tiles, thermal system insulation and gypsum or plaster wallboard/joint compound require the use of a negative pressure enclosure. Block and seal openings in areas where the release of airborne asbestos fibers can be expected. Establish an asbestos negative pressure enclosure with the use of curtains, portable partitions, or other enclosures in order to prevent the escape of asbestos fibers from the contaminated asbestos work area. Negative pressure enclosure development must include protective covering of uncontaminated walls, and ceilings with a continuous membrane of two layers of minimum 6-mil plastic sheet sealed with tape to prevent water or other damage. Provide two layers of 6-mil plastic sheet over floors and extend a minimum of 12 inches up walls. Seal all joints with tape. Provide local exhaust system in the asbestos control area. Openings will be allowed in enclosures of asbestos control areas for personnel and equipment entry and exit, the supply and exhaust of air for the local exhaust system and the removal of properly containerized asbestos containing materials. Replace local exhaust system filters as required to maintain the efficiency of the system.

3.2.5.2 Glovebag

If the construction of a negative pressure enclosure is infeasible for the removal of siding or roofing material. Use alternate techniques as indicated in MEDEP Chapter 425: Asbestos Management Regulations and 29 CFR 1926.1101. Establish designated limits for the asbestos regulated area with the use of rope or other continuous barriers, and maintain all other requirements for asbestos control areas. The PQP must conduct personal samples of each worker engaged in asbestos handling (removal, disposal, transport and other associated work) throughout the duration of the project. If the quantity of airborne asbestos fibers monitored at the breathing zone of the workers at any time exceeds background or 0.010 fibers per cubic centimeter whichever is greater, stop work, evacuate personnel in adjacent areas or provide personnel with approved protective equipment at the discretion of the Owner's Representative. This sampling may be duplicated by the Government at the discretion of the Owner's
Representative. If the air sampling results obtained by the Government differ from those obtained by the Contractor, the Government will determine which results predominate. If adjacent areas are contaminated as determined by the Owner's Representative, clean the contaminated areas, monitor, and visually inspect the area as specified herein.

3.2.6 Removal Procedures

Wet asbestos material with a fine spray of amended water during removal, cutting, or other handling so as to reduce the emission of airborne fibers. Remove material and immediately place in 6 mil plastic disposal bags. Remove asbestos containing material in a gradual manner, with continuous application of the amended water or wetting agent in such a manner that no asbestos material is

disturbed prior to being adequately wetted. Where unusual circumstances prohibit the use of 6 mil plastic bags, submit an alternate proposal for containment of asbestos fibers to the Owner's Representative for approval. For example, in the case where both piping and insulation are to be removed, the Contractor may elect to wet the insulation, wrap the pipes and insulation in plastic and remove the pipe by sections. Containerize asbestos containing material while wet. Do not allow asbestos material to accumulate or become dry. Lower and otherwise handle asbestos containing material as indicated in MEDEP Chapter 425: Asbestos Management Regulations and 40 CFR 61-SUBPART M.

3.2.6.1 Sealing Contaminated Items Designated for Disposal

Remove contaminated architectural, mechanical, and electrical appurtenances such as venetian blinds, full-height partitions, carpeting, duct work, pipes and fittings, radiators, light fixtures, conduit, panels, and other contaminated items designated for removal by completely coating the items with an asbestos lock-down encapsulant at the demolition site before removing the items from the asbestos control area. These items need not be vacuumed. The asbestos lock-down encapsulant must be tinted a contrasting color and spray-applied by airless method. Thoroughness of sealing operation must be visually gauged by the extent of colored coating on exposed surfaces. Lock-down encapsulants must comply with the performance requirements specified herein.

3.2.6.2 Exposed Pipe Insulation Edges

Contain edges of asbestos insulation to remain that are exposed by a removal operation. Wet and cut the rough ends true and square with sharp tools and then encapsulate the edges with a 1/4 inch thick layer of non-asbestos containing insulating cement troweled to a smooth hard finish. When cement is dry, lag the end with a layer of non-asbestos lagging cloth, overlapping the existing ends by at least 4 inches. When insulating cement and cloth is an impractical method of sealing a raw edge of asbestos, take appropriate steps to seal the raw edges as approved by the Owner's Representative.

3.2.7 Methods of Compliance

3.2.7.1 Mandated Practices

The specific abatement techniques and items identified must be detailed in the Contractor's AHAP. Use the following engineering controls and work practices in all operations, regardless of the levels of exposure:

a. Vacuum cleaners equipped with HEPA filters.

b. Wet methods or wetting agents except where it can be demonstrated that the use of wet methods is unfeasible due to the creation of electrical hazards, equipment malfunction, and in roofing.

c. Prompt clean-up and disposal.

d. Inspection and repair of polyethylene.

e. Cleaning of equipment and surfaces of containers prior to removing them from the equipment room or area.

3.2.7.2 Control Methods

Use the following control methods:

a. Local exhaust ventilation equipped with HEPA filter;

b. Enclosure or isolation of processes producing asbestos dust;

c. Where the feasible engineering and work practice controls are not sufficient to reduce employee exposure to or below the PELs, use them to reduce employee exposure to the lowest levels attainable and must supplement them by the use of respiratory protection.

3.2.7.3 Unacceptable Practices

The following work practices must not be used:

a. High-speed abrasive disc saws that are not equipped with point of cut ventilator or enclosures with HEPA filtered exhaust air.

b. Compressed air used to remove asbestos containing materials, unless the compressed air is used in conjunction with an enclosed ventilation system designed to capture the dust cloud created by the compressed air.

c. Dry sweeping, shoveling, or other dry clean up.

d. Employee rotation as a means of reducing employee exposure to asbestos.

3.2.8 Class I Work Procedures

In addition to requirements of paragraphs MANDATED PRACTICES and CONTROL METHODS, the following engineering controls and work practices must be used:

a. A Competent Person must supervise the installation and operation of the control methods.

b. Place critical barriers over all openings to the regulated area.

c. HVAC systems must be isolated in the regulated area by sealing with a double layer of plastic or air-tight rigid covers.

d. Impermeable dropcloths (6 mil or greater thickness) must be placed on surfaces beneath all removal activity.

e. Where a negative exposure assessment has not been provided or where exposure monitoring shows the PEL was exceeded, the regulated area must be ventilated with a HEPA unit and employees must use PPE.

3.2.9 Specific Control Methods for Class I Work

Use Class I work procedures, control methods and removal methods for the following ACM:

a. Spray Applied Fireproofing

b. Gypsum Wallboard and Joint Compound

c. Thermal System Insulation and Mudded Pipe Fittings

d. Plaster and Textured Ceilings and Walls

e. Vermiculite

3.2.9.1 Negative Pressure Enclosure (NPE) System

The system must provide at least four air changes per hour inside the containment. The local exhaust unit equipment must be operated 24-hours per day until the containment is removed. The NPE must be smoke tested for leaks at the beginning of each shift and be sufficient to maintain a minimum pressure differential of minus 0.02 inch of water column relative to adjacent, unsealed areas. Pressure differential must be monitored continuously, 24-hours per day, with an automatic manometric recording instrument and Records must be provided daily on the same day collected to the Owner's Representative. The Owner's Representative must be notified immediately if the pressure differential falls below the prescribed minimum. The building ventilation system must not be used as the local exhaust system for the regulated area. The NPE must terminate outdoors unless an alternate arrangement is allowed by the Owner's Representative. All filters used must be new at the beginning of the project and must be periodically changed as necessary and disposed of as ACM waste.

3.2.9.2 Glovebag Systems

Glovebags must be used without modification, smoke-tested for leaks, and completely cover the circumference of pipe or other structures where the work is to be done. Glovebags must be used only once and must not be moved. Glovebags must not be used on surfaces that have temperatures exceeding 150 degrees F. Prior to disposal, glovebags must be collapsed using a HEPA vacuum. Before beginning the operation, loose and friable material adjacent to the glovebag operation must be wrapped and sealed in 2 layers of plastic or otherwise rendered intact. At least two persons must perform glovebag removal. Asbestos regulated work areas must be established for glovebag abatement. Designated boundary limits for the asbestos work must be established with rope or other continuous barriers and all other requirements for asbestos control areas must be maintained, including area signage and boundary warning tape.

a. Attach HEPA vacuum systems to the bag to prevent collapse during removal of ACM.

b. The negative pressure glove boxes must be fitted with gloved apertures and a bagging outlet and constructed with rigid sides from metal or other material which can withstand the weight of the ACM and water used during removal. A negative pressure must be created in the system using a HEPA filtration system. The box must be smoke tested

for leaks prior to each use.

3.2.9.3 Mini-Enclosure

Single bulkhead containment, double bulkhead containment, or mini -containment (small walk-in enclosure) to accommodate no more than two persons, may be used if the disturbance or removal can be completely contained by the enclosure. The mini-enclosure must be inspected for leaks and smoke tested before each use. Air movement must be directed away from the employee's breathing zone within the mini-enclosure.

3.2.9.4 Wrap and Cut Operation

Prior to cutting pipe, the asbestos-containing insulation must be wrapped with polyethylene and securely sealed with duct tape to prevent asbestos becoming airborne as a result of the cutting process. The following steps must be taken: install glovebag, strip back sections to be cut 6 inches from point of cut, and cut pipe into manageable sections.

3.2.9.5 Class I Removal Method

Class I ACM must be removed using a control method described above. Prepare work area as previously specified. Establish designated limits for the asbestos regulated work area with the use of red barrier tape, critical barriers, signs, and maintain all other requirements for asbestos control area. Spread one layer of 6-mil seamless plastic sheeting on the floor below the work area. Cut manageable sections of gypsum wallboard and joint compound and immediately place into a 6-mil minimum thickness disposal bag or other approved container. Make every effort to keep the material from falling to the floor of the work area. Use a wire brush and wet clean to remove residual material from studs. Continue wet cleaning until the surface is clean of visible material and encapsulate stud walls. Remove ACM thermal system insulation and mudded pipe fittings using mechanical means and wet methods and immediately place into 6-mil thickness disposal bag. Continue wet cleaning until surfaces are free of visible debris. Remove ACM plaster ceilings or walls using mechanical means and adequately wet methods and immediately place into 6-mil thickness disposal bag. Make every effort to keep the material from falling to the floor of the work area. Continue wet cleaning until surfaces are free of visible debris. Remove ACM textured ceiling finish using a scraper and wet methods and immediately place into 6-mil thickness disposal bag. Floors are considered contaminated from fallen textured ceiling finish. Clean up debris on floor and dispose of carpet as asbestos contaminated material. After removal of the material use a wire brush to clean the exposed ceiling to remove residual material. Continue wet cleaning until surfaces are free of visible debris. Remove ACM vermiculite using mechanical means and adequately wet methods and immediately place into 6-mil thickness disposal bag. Make every effort to keep the material from falling to the floor of the work area. Continue wet cleaning until surfaces are free of visible debris. Bag all asbestos debris which has fallen to the floor as asbestos-containing debris. Place all debris in plastic disposal bags of 6-mil minimum thickness. Once the material is in the disposal bag, apply additional water as needed to achieve "adequately wet" conditions for NESHAP compliance. Place bagged asbestos waste under negative pressure with the use of a HEPA vacuum, goose neck and duct tape to seal the bag, wash to remove any visible contamination and place into a second 6-mil minimum thickness disposal bag. Containerize asbestos containing waste while wet. Lower and otherwise handle asbestos containing materials as indicated in MEDEP Chapter 425: Asbestos Management Regulations and 40 CFR 61-SUBPART M. Conduct area monitoring of airborne fibers during the work shift at the designated limits of the asbestos work area and conduct personal samples of each worker engaged in the work. If the quantity of airborne asbestos fibers monitored at the breathing zone of the workers or the designated limits at any time exceeds background or 0.010 fibers per cubic centimeter, whichever is greater, stop work, and immediately correct the situation.

3.2.10 Class II Work Procedures

In addition to the requirements of paragraphs MANDATED PRACTICES and CONTROL METHODS, the following engineering controls and work practices must be used:

a. A Competent Person must supervise the work.

b. For indoor work, critical barriers must be placed over all openings to the regulated area.

c. Impermeable dropcloths must be placed on surfaces beneath all removal activity.

3.2.11 Specific Control Methods for Class II Work

3.2.11.1 Suspect Fire Doors

Establish designated limits for the asbestos regulated work area with the use of red barrier tape, critical barriers, signs, and maintain all other requirements for asbestos control area except local exhaust. A detached decontamination system may be used. Spread 6-mil plastic sheeting on the ground beneath the work area and around the perimeter of the work area extending out in all directions. Remove door intact from hinges and wrap with 6-mil plastic sheeting. Inspect the interior areas of the door to determine if ACM is present. If ACM is not present the door may be disposed of as general construction debris. If ACM is present place whole door in enclosed container for disposal. Conduct area monitoring of airborne fibers during the work shift at the designated limits of the asbestos work area and conduct personal samples of each worker engaged in the work. If the airborne fiber concentration of the workers or designated limits at any time exceeds background or 0.010 fibers per cubic centimeter, whichever is greater, stop work immediately and correct the situation.

3.2.11.2 Roofing Materials

Establish designated limits for the asbestos regulated work area with the use of red barrier tape, critical barriers, signs, and maintain all other requirements for asbestos control area except local exhaust. When removing roofing materials which contain ACM as described in 29 CFR 1926.1101(g)(8)(ii), use the following practices. Roofing material must be removed in an intact state. Wet methods must be used to remove roofing materials that are not intact, or that will be rendered not intact during removal, unless such wet methods are not feasible or will create safety hazards. When removing built-up roofs, with asbestos-containing roofing felts and an aggregate surface, using a power roof cutter, all dust resulting from the cutting operations must be collected by a HEPA dust collector, or must be HEPA vacuumed by vacuuming along the cut line. Asbestos-containing roofing material must not be dropped or thrown to the ground, but must be lowered to the ground via covered, dust-tight chute, crane, hoist or other method approved by the Owner's Representative. Any ACM that is not intact must be lowered to the ground as soon as practicable, but not later than the end of the work shift. While the material remains on the roof it must be kept wet or placed in an impermeable waste bag or wrapped in plastic sheeting. Intact ACM must be lowered to the ground as soon as practicable, but not later than the end of the work shift. Unwrapped material must be transferred to a closed receptacle. Critical barriers must be placed over roof level heating and ventilation air intakes. Conduct area monitoring of airborne fibers during the work shift at the designated limits of the asbestos work area and conduct personal samples of each worker engaged in the work. If the airborne fiber concentration of the workers or designated limits at any time exceeds background or 0.010 fibers per cubic centimeter, whichever is greater, stop work immediately and correct the situation.

3.2.11.3 Cementitious Siding and Shingles or Transite Panels

Establish designated limits for the asbestos regulated work area with the use of red barrier tape, critical barriers, signs, and maintain all other requirements for asbestos control area except local exhaust. When removing cementitious asbestos-containing siding, shingles or Transite panels use the following work practices. Intentionally cutting, abrading or breaking is prohibited. Each panel or shingle must be sprayed with amended water prior to removal. Nails must be cut with flat, sharp instruments. Unwrapped or unbagged panels or shingles must be immediately lowered to the ground via covered dust-tight chute, crane or hoist, or placed in an impervious waste bag or wrapped in plastic sheeting and lowered to the ground no later than the end of the work shift. Place debris

into a 6-mil minimum thickness disposal bag or other approved container. Once the material is in the disposal bag, apply additional water as needed to achieve "adequately wet" conditions for NESHAP compliance. Place bagged asbestos waste under negative pressure with the use of a HEPA vacuum, goose neck and duct tape to seal the bag, wash to remove any visible contamination and place into a second 6-mil minimum thickness disposal bag. Containerize asbestos containing waste while wet. Conduct area monitoring of airborne fibers during the work shift at the designated limits of the asbestos work area and conduct personal samples of each worker engaged in the work. If the airborne fiber concentration of the workers or designated limits at any time exceeds background or 0.010 fibers per cubic centimeter, whichever is greater, stop work immediately and correct the situation.

3.2.11.4 Gaskets

Establish designated limits for the asbestos regulated work area with the use of red barrier tape, critical barriers, signs, and maintain all other requirements for asbestos control area except local exhaust. Gaskets must be thoroughly wetted with amended water prior to removal and immediately placed in a disposal container. If a gasket is visibly deteriorated and unlikely to be removed intact, removal must be undertaken within a glovebag. Any scraping to remove residue must be performed wet. Place debris into a 6-mil minimum thickness disposal bag or other approved container. Once the material is in the disposal bag, apply additional water as needed to achieve "adequately wet" conditions for NESHAP compliance. Place bagged asbestos waste under negative pressure with the use of a HEPA vacuum, goose neck and duct tape to seal the bag, wash to remove any visible contamination and place into a second 6-mil minimum thickness disposal bag. Containerize asbestos containing waste while wet. Conduct area monitoring of airborne fibers during the work shift at the designated limits of the asbestos work area and conduct personal samples of each worker engaged in the work. If the airborne fiber concentration of the workers or designated limits at any time exceeds background or 0.010 fibers per cubic centimeter, whichever is greater, stop work immediately and correct the situation.

3.2.12 Abatement of Asbestos Contaminated Soil

Establish designated limits for the asbestos regulated work area with the use of red barrier tape, critical barriers, signs, and maintain all other requirements for asbestos control area except local exhaust. Asbestos contaminated soil must be removed from areas to a minimum depth of 2 inches. Soil must be thoroughly dampened with amended water and then removed by manual shoveling into labeled containers. Place debris into a 6-mil minimum thickness disposal bag or other approved container. Once the material is in the disposal bag, apply additional water as needed to achieve "adequately wet" conditions for NESHAP compliance. Place bagged asbestos waste under negative pressure with the use of a HEPA vacuum, goose neck and duct tape to seal the bag, wash to remove any visible contamination and place into a second 6-mil minimum thickness disposal bag. Containerize asbestos containing waste while wet. Conduct area monitoring of airborne fibers during the work shift at the designated limits of the asbestos work area and conduct personal samples of each worker engaged in the work. If the airborne fiber concentration of the workers or designated limits at any time exceeds background or 0.010 fibers per cubic centimeter, whichever is greater, stop work immediately and correct the situation.

3.2.13 Air Sampling

Perform sampling of airborne concentrations of asbestos fibers in accordance with 29 CFR 1926.1101, the Contractor's air monitoring plan and as specified herein. Sampling performed in accordance with 29 CFR 1926.1101must be performed by the PQP. Sampling performed for

environmental and quality control reasons must be performed by the PQP. Unless otherwise specified, use NIOSH Method 7400 for sampling and analysis. Monitoring may be duplicated by the Government at the discretion of the Owner's Representative. If the air sampling results obtained by the Government differ from those results obtained by the Contractor, the Government will determine which results predominate. Results of breathing zone samples must be posted at the job site and made available to the Owner's Representative. Submit all documentation regarding initial exposure assessments, negative exposure assessments, and air-monitoring results.

3.2.13.1 Sampling Prior to Asbestos Work

Provide area air sampling and establish the baseline one day prior to the masking and sealing operations for each demolition or removal site. Establish the background by performing area sampling in similar but uncontaminated sites in the building.

3.2.13.2 Sampling During Asbestos Work

The PQP must provide personal and area sampling as indicated in 29 CFR 1926.1101 and governing environmental regulations. Breathing zone samples must be taken for at least 25 percent of the workers in each shift, or a minimum of two, whichever is greater. Air sample fiber counting must be completed and results provided within 24-hours (breathing zone samples), and 8 hours (environmental/clearance monitoring) after completion of a sampling period. In addition, provided the same type of work is being performed, provide area sampling at least once every work shift close to the work inside the enclosure, outside the clean room entrance to the enclosure, and at the exhaust opening of the local exhaust system. If sampling outside the enclosure shows airborne levels have exceeded background or 0.010 fibers per cubic centimeter, whichever is greater, stop all work, correct the condition(s) causing the increase, and notify the Owner's Representative immediately. Where alternate methods are used, perform personal and area air sampling at locations and frequencies that will accurately characterize the evolving airborne asbestos levels. The written results must be signed by testing laboratory analyst, testing laboratory principal and the Contractor's PQP. The air sampling results must be documented on a Contractor's daily air monitoring log.

The PQP must provide personal sampling as indicated in 29 CFR 1926.1101. Breathing zone samples must be taken for at least 25 percent of the workers in each shift, or a minimum of two, whichever is greater. Breathing zone samples must be taken for at least 25 percent of the workers in each shift, or a minimum of two, whichever is greater. Air sample fiber counting must be completed and results provided within 24-hours (breathing zone samples), and 8 hours (environmental/clearance monitoring) after completion of a sampling period. At the same time the GC will provide area sampling close to the work inside the enclosure, outside the clean room entrance to the enclosure, and at the exhaust opening of the local exhaust system. In addition, provided the same type of work is being performed, the GC will provide area sampling once every work shift close to the work inside the enclosure, outside the clean room entrance to the enclosure, and at the exhaust opening of the local exhaust system. If sampling outside the enclosure shows airborne levels have exceeded background or 0.010 fibers per cubic centimeter, whichever is greater, stop all work, correct the condition(s) causing the increase, and notify the Owner's Representative immediately. Where alternate methods are used, perform personal and area air sampling at locations and frequencies that will accurately characterize the evolving airborne asbestos levels. The written results must be signed by testing laboratory analyst, testing laboratory principal and the Contractor's PQP. The air sampling results must be documented on a Contractor's daily air monitoring log.

3.2.13.3 Final Clearance Requirements, NIOSH PCM Method

For PCM sampling and analysis using NIOSH NMAM Method 7400, the fiber concentration inside the abated regulated area, for each airborne sample, must be less than 0.010 f/cc. The abatement inside the regulated area is considered complete when every PCM final clearance sample is below the clearance limit. If any sample result is greater than 0.010 total f/cc, the asbestos fiber concentration (asbestos f/cc) must be confirmed from that same filter using NIOSH NMAM Method 7402 (TEM) at Contractor's expense. If any confirmation sample result is greater than 0.010 asbestos f/cc, abatement is incomplete and cleaning must be repeated at the Contractor's expense. Upon completion of any required recleaning, resampling with results to meet the above clearance criteria must be done at the Contractor's expense.

3.2.13.4 Final Clearance Requirements, EPA TEM Method

For EPA TEM sampling and analysis, using the EPA Method specified in 40 CFR 763, abatement inside the regulated area is considered complete when the arithmetic mean asbestos concentration of the five inside samples is less than or equal to 70 structures per square millimeter (70 S/mm). When the arithmetic mean is greater than 70 S/mm, the three blank samples must be analyzed. If the three blank samples are greater than 70 S/mm, resampling must be done. If less than 70 S/mm, the five outside samples must be analyzed and a Z-test analysis performed. When the Z-test results are less than 1.65, the decontamination must be considered complete. If the Z-test results are more than 1.65, the abatement is incomplete and cleaning must be repeated. Upon completion of any required recleaning, resampling with results to meet the above clearance criteria must be done at the Contractor's expense.

3.2.13.5 Sampling After Final Clean-Up (Clearance Sampling)

Provide area sampling of asbestos fibers using aggressive air sampling techniques as defined in the EPA 560/5-85-024 and establish an airborne asbestos concentration of less than 0.010 fibers per cubic centimeter after final clean-up but before removal of the enclosure or the asbestos work control area. After final cleanup and the asbestos control area is dry but prior to clearance sampling, the PQP and GC must perform a visual inspection in accordance with ASTM E1368 to ensure that the asbestos control and work area is free of any accumulations of dirt, dust, or debris. Prepare a written report signed and dated by the PQP documenting that the asbestos control area is free of dust, dirt, and debris and all waste has been removed. Collect the appropriate number of samples in accordance with Maine DEP regulations. Use transmission electron microscopy (TEM) to analyze clearance samples and report the results in accordance with current NIOSH criteria. The asbestos fiber counts from these samples must be less than 0.010 fibers per cubic centimeter or be not greater than the background, whichever is greater. Should any of the final samples indicate a higher value take appropriate actions to re-clean the area and repeat the sampling and TEM analysis at the Contractor's expense.

3.2.13.6 Air Clearance Failure

If clearance sampling results fail to meet the final clearance requirements, pay all costs associated with the required recleaning, resampling, and analysis, until final clearance requirements are met.

3.2.14 Lock-Down

Prior to removal of plastic barriers and after pre-clearance clean up of gross contamination, the PQP must conduct a visual inspection of all areas affected by the removal in accordance with ASTM E1368. Inspect for any visible fibers. Spray apply a post removal (lock-down) encapsulant to

ceiling, walls, floors and other areas exposed in the removal area. The exposed area includes but is not limited to plastic barriers, furnishings and articles to be discarded as well as dirty change room, air locks for bag removal and decontamination chambers.

3.2.15 Site Inspection

While performing asbestos engineering control work, the Contractor must be subject to on-site inspection by the Owner's Representative who may be assisted by or represented by safety or industrial hygiene personnel. If the work is found to be in violation of this specification, the Owner's Representative will issue a stop work order to be in effect immediately and until the violation is resolved. All related costs including standby time required to resolve the violation must be at the Contractor's expense.

3.3 CLEAN-UP AND DISPOSAL

3.3.1 Housekeeping

Essential parts of asbestos dust control are housekeeping and clean-up procedures. Maintain surfaces of the asbestos control area free of accumulations of asbestos fibers. Give meticulous attention to restricting the spread of dust and debris; keep waste from being distributed over the general area. Use HEPA filtered vacuum cleaners. DO NOT BLOW DOWN THE SPACE WITH COMPRESSED AIR. When asbestos removal is complete, all asbestos waste is removed from the work-site, and final clean-up is completed, the Owner's Representative will attest that the area is safe before the signs can be removed. After final clean-up and acceptable airborne concentrations are attained but before the HEPA unit is turned off and the enclosure removed, remove all pre-filters on the building HVAC system and provide new pre-filters. Dispose of filters as asbestos contaminated materials. Reestablish HVAC mechanical, and electrical systems in proper working order. The Owner's Representative will visually inspect all surfaces within the enclosure for residual material or accumulated dust or debris. The Contractor must re-clean all areas showing dust or residual materials. If re-cleaning is required, air sample and establish an acceptable asbestos airborne concentration after re-cleaning. The Owner's Representative must agree that the area is safe in writing before unrestricted entry will be permitted. The Government must have the option to perform monitoring to determine if the areas are safe before entry is permitted.

3.3.2 Title to Materials

All waste materials, except as specified otherwise, become the property of the Contractor and must be disposed of as specified in applicable local, State, and Federal regulations and herein.

3.3.3 Disposal of Asbestos

3.3.3.1 Procedure for Disposal

Coordinate all waste disposal manifests with the Owner's Representative. Collect asbestos waste, contaminated waste water filters, asbestos contaminated water, scrap, debris, bags, containers, equipment, and asbestos contaminated clothing which may produce airborne concentrations of asbestos fibers and place in sealed fiber-proof, waterproof, non-returnable containers (e.g. double plastic bags 6 mils thick, cartons, drums or cans). Wastes within the containers must be adequately wet in accordance with MEDEP Chapter 425: Asbestos Management Regulations and 40 CFR 61-SUBPART M. Affix a warning and Department of Transportation (DOT) label to each container including the bags or use at least 6 mils thick bags with the approved warnings and DOT labeling preprinted on the bag. Clearly indicate on the outside of each container the name of the waste

generator and the location at which the waste was generated. Prevent contamination of the transport vehicle (especially if the transport vehicle is a rented truck likely to be used in the future for non-asbestos purposes). These precautions include lining the vehicle

cargo area with plastic sheeting (similar to work area enclosure) and thorough cleaning of the cargo area after transport and unloading of asbestos debris is complete. Dispose of waste asbestos material at an Environmental Protection Agency (EPA) or State-approved asbestos landfill off Government property. For temporary storage, store sealed impermeable bags in asbestos waste drums or skids. An area for interim storage of asbestos waste-containing drums or skids will be assigned by the Owner's Representative. Comply with 40 CFR 61-SUBPART M, State, regional, and local standards for hauling and disposal. Sealed plastic bags may be dumped from drums into the burial site unless the bags have been broken or damaged. Damaged bags must remain in the drum and the entire contaminated drum must be buried. Uncontaminated drums may be recycled. Workers unloading the sealed drums must wear appropriate respirators and personal protective equipment when handling asbestos materials at the disposal site.

3.3.3.2 Asbestos Disposal Quantity Report

Direct the PQP to record and report, to the Owner's Representative, the amount of asbestos containing material removed and released for disposal. Deliver the report for the previous day at the beginning of each day shift with amounts of material removed during the previous day reported in linear feet or square feet as described initially in this specification and in cubic feet for the amount of asbestos containing material released for disposal.

Allow the GC to inspect, record and report the amount of asbestos containing material removed and released for disposal on a daily basis.

-- End of Section --

SECTION 028300 – LEAD, CHROMIUM, AND CADMIUM REMEDIATION

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced.The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP Z9.2	(2018) Fundamentals Governing the Design and Operation of Local Exhaust Ventilation Systems

ASTM INTERNATIONAL (ASTM)

ASTM E1613	(2012) Standard Test Method for Determination of Lead by Inductively Coupled Plasma Atomic Emission Spectrometry (ICP-AES), Flame Atomic Absorption Spectrometry (FAAS), or Graphite Furnace Atomic Absorption Spectrometry (GFAAS) Techniques
ASTM E1644	(2017) Standard Practice for Hot Plate Digestion of Dust Wipe Samples for the Determination of Lead
ASTM E1726	(2001; R 2009) Preparation of Soil Samples by Hotplate Digestion for Subsequent Lead Analysis
ASTM E1727	(2016) Standard Practice for Field Collection of Soil Samples for Subsequent Lead Determination

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 701	(2019) Standard Methods of Fire Tests for Flame Propagation of Textiles and Films

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (HUD)

HUD 6780	(1995; Errata Aug 1996;Rev Ch. 7 - 1997) Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926.103	Respiratory Protection
29 CFR 1926.1126	Chromium
29 CFR 1926.1127	Cadmium
29 CFR 1926.21	Safety Training and Education
29 CFR 1926.33	Access to Employee Exposure and Medical Records
29 CFR 1926.55	Gases, Vapors, Fumes, Dusts, and Mists
29 CFR 1926.59	Hazard Communication
29 CFR 1926.62	Lead
29 CFR 1926.65	Hazardous Waste Operations and Emergency Response
40 CFR 260	Hazardous Waste Management System: General
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
40 CFR 264	Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 265	Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 268	Land Disposal Restrictions
40 CFR 745	Lead-Based Paint Poisoning Prevention in Certain Residential Structures
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements
49 CFR 178	Specifications for Packagings

UNDERWRITERS LABORATORIES (UL)

UL 586	(2009; Reprint Dec 2017) UL Standard for Safety High-Efficiency Particulate, Air Filter Units

STATE OF MAINE REGULATIONS

MAINE REGS	The following State of Maine regulations are available at: http://www.maine.gov/sos/cec/rules/06/096/096c424.doc

1.2 DEFINITIONS

1.2.1 Abatement

Measures defined in 40 CFR 745, Section 223, designed to permanently eliminate lead-based paint hazards.

1.2.2 Action Level

Employee exposure, without regard to use of respirators, to an airborne concentration of lead of 30 micrograms per cubic meter of air averaged over an 8-hour period; to an airborne concentration of cadmium of 2.5 micrograms per cubic meter of air averaged over an 8-hour period; to an airborne concentration of chromium (VI) of 2.5 micrograms per cubic meter of air averaged over an 8-hour period.

1.2.3 Area Sampling

Sampling of lead, cadmium, chromium concentrations within the lead, cadmium, chromium control area and inside the physical boundaries which is representative of the airborne lead, cadmium, chromium concentrations but is not collected in the breathing zone of personnel (approximately 5 to 6 feet above the floor).

1.2.4 Cadmium Permissible Exposure Limit (PEL)

Five micrograms per cubic meter of air as an 8-hour time weighted average as determined by 29 CFR 1926.1127. If an employee is exposed for more than 8-hours in a work day, determine the PEL by the following formula:

PEL (micrograms/cubic meter of air) = 40/No. hrs worked per day

1.2.5 Certified Industrial Hygienist (CIH)

As used in this section refers to a person retained by the Contractor who is certified as an industrial hygienist and who is trained in the recognition and control of lead, cadmium and chromium hazards in accordance with current federal, State, and local regulations. CIH must be certified for comprehensive practice by the American Board of Industrial Hygiene. The Certified Industrial Hygienist must be independent of the Contractor and must have no employee or employer relationship which could constitute a conflict of interest.

1.2.6 Child-Occupied Facility

Real property which is a building or portion of a building constructed prior to 1978 visited regularly by the same child, six-years of age or under, on at least two different days within any week (Sunday through Saturday period), provided that each day's visit lasts at least 3-hours, and the combined annual visits last at least 60-hours. Child-occupied facilities include but are not limited to, day-care centers, preschools and kindergarten classrooms.

1.2.7 Chromium Permissible Exposure Limit (PEL)

Five micrograms per cubic meter of air as an 8-hour time weighted average as determined by 29 CFR 1926.1126. If an employee is exposed for more than 8-hours in a work day, determine the PEL by the following formula:

PEL (micrograms/cubic meter of air) = 40/No. hrs worked per day

1.2.8 Competent Person (CP)

As used in this section, refers to a person employed by the Contractor who is trained in the recognition and control of lead, cadmium and chromium hazards in accordance with current federal, State, and local regulations and has the authority to take prompt corrective actions to control the lead, cadmium and chromium hazard. The Contractor may provide more than one CP as required to supervise and monitor the work. The CP must be a Certified Industrial Hygienist (CIH) certified by the American Board of Industrial Hygiene or a Certified Safety Professional (CSP) certified by the Board of Certified Safety Professionals or a licensed lead-based paint abatement Supervisor/Project Designer in the State of Maine.

1.2.9 Contaminated Room

Refers to a room for removal of contaminated personal protective equipment (PPE).

1.2.10 Decontamination Shower Facility

That facility that encompasses a clean clothing storage room, and a contaminated clothing storage and disposal rooms, with a shower facility in between.

1.2.11 Deleading

Activities conducted by a person who offers to eliminate lead-based paint or lead-based paint hazards or paints containing cadmium/chromium or to plan such activities in commercial buildings, bridges or other structures.

1.2.12 Eight-Hour Time Weighted Average (TWA)

Airborne concentration of lead, cadmium, chromium to which an employee is exposed, averaged over an 8-hour workday as indicated in 29 CFR 1926.62,
29 CFR 1926.1126, 29 CFR 1926.1127.

1.2.13 High Efficiency Particulate Air (HEPA) Filter Equipment

HEPA filtered vacuuming equipment with a UL 586 filter system capable of collecting and retaining lead, cadmium, chromium-contaminated particulate. A high efficiency particulate filter demonstrates at least 99.97 percent efficiency against 0.3 micron or larger size particles.

1.2.14 Lead

Metallic lead, inorganic lead compounds, and organic lead soaps. Excludes other forms of organic lead compounds. The use of the term Lead in this section also refers to paints which contain detectable concentrations of Cadmium and Chromium. For the purposes of this section, lead-based paint (LBP) and paint with lead (PWL) also contains cadmium and chromium.

1.2.15 Lead-Based Paint (LBP)

Paint or other surface coating that contains lead in excess of 1.0 milligrams per centimeter squared or 0.5 percent by weight.

1.2.16 Lead-Based Paint Activities

In the case of target housing or child occupied facilities, lead-based paint activities include; a lead-based paint inspection, a risk assessment, or abatement of lead-based paint hazards.

1.2.17 Lead-Based Paint Hazards

Paint-lead hazard, dust-lead hazard or soil-lead hazard as identified in 40 CFR 745, Section 65. Any condition that causes exposure to lead from lead-contaminated dust, lead-contaminated soil, lead-based paint that is deteriorated or present in accessible surfaces, friction surfaces, or impact surfaces that would result in adverse human health effects.

1.2.18 Lead, Cadmium, Chromium Control Area

A system of control methods to prevent the spread of lead, cadmium, chromium dust, paint chips or debris to adjacent areas that may include temporary containment, floor or ground cover protection, physical boundaries, and warning signs to prevent unauthorized entry of personnel. HEPA filtered local exhaust equipment may be used as engineering controls to further reduce personnel exposures or building/outdoor environmental contamination.

1.2.19 Lead Permissible Exposure Limit (PEL)

Fifty micrograms per cubic meter of air as an 8-hour time weighted average as determined by 29 CFR 1926.62. If an employee is exposed for more than 8-hours in a work day, determine the PELby the following formula:

PEL (micrograms/cubic meter of air) = 400/No. hrs worked per day

1.2.20 Material Containing Lead/Paint with Lead (MCL/PWL)

Any material, including paint, which contains lead as determined by the testing laboratory using a valid test method. The requirements of this section do not apply if no detectable levels of lead are found using a quantitative method for analyzing paint or MCL using laboratory instruments with specified limits of detection (usually 0.01 percent). An X-Ray Fluorescence (XRF) instrument is not considered a valid test method.

1.2.21 Personal Sampling

Sampling of airborne lead, cadmium, chromium concentrations within the

breathing zone of an employee to determine the 8-hour time weighted average concentration in accordance with 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127. Samples must be representative of the employees' work tasks. Breathing zone must be considered an area within a

hemisphere, forward of the shoulders, with a radius of 6 to 9 inches and centered at the nose or mouth of an employee.

1.2.22 Physical Boundary

Area physically roped or partitioned off around lead, cadmium, chromium control area to limit unauthorized entry of personnel.

1.2.23 Target Housing

Residential real property which is housing constructed prior to 1978, except housing for the elderly or persons with disabilities (unless any one or more children age 6-years or under resides or is expected to reside in such housing for the elderly or persons with disabilities) or any zero bedroom dwelling.

1.3 DESCRIPTION

Construction activities impacting PWL or material containing lead, cadmium, chromium which are covered by this specification include the demolition or removal of material containing lead, cadmium, and chromium located in Buildings 400 and 401 and as indicated on the drawings. Refer to the report at the end of Section 02 82 00 ASBESTOS REMEDIATION. The work covered by this section includes work tasks and the precautions specified in this section for the protection of building occupants and the environment during and after the performance of the hazard abatement activities in accordance with MAINE REGS and as specified herein.

1.3.1 Protection of Existing Areas To Remain

Project work including, but not limited to, lead, cadmium, chromium hazard abatement work, storage, transportation, and disposal must be performed without damaging or contaminating adjacent work and areas. Where such work or areas are damaged or contaminated, restore work and areas to the original condition.

1.3.2 Coordination with Other Work

Coordinate with work being performed in adjacent areas to ensure there are no exposure issues. Explain coordination procedures in the Lead, Cadmium, Chromium Compliance Plan and describe how the Contractor will prevent lead, cadmium and chromium exposure to other contractors and Government personnel performing work unrelated to lead, cadmium and chromium activities.

1.3.3 Sampling and Analysis

Submit a log of the analytical results from sampling conducted during the abatement. Keep the log of results current with project activities and brief the results to the Owner's Representative as analytical results are reported.

1.3.3.1 Dust Wipe Materials, Sampling and Analysis

Sampling must conform to ASTM E1728 and ASTM E1792. Analysis must conform to ASTM E1613 and ASTM E1644.

1.3.3.2 Soil Sampling and Analysis

Sampling must conform to ASTM E1727. Analysis must conform to ASTM E1613 and ASTM E1726.

1.3.3.3 Clearance Monitoring

a. Collect dust wipe samples inside the lead, cadmium and chromium hazard control area after the final visual inspection.

b. Collect exterior bare soil samples inside the lead, cadmium and chromium hazard control area after the final visual inspection.

1.3.4 Clearance Requirements

Target clearance levels.

(1) Lead - 400 ug/sq ft.

1.4 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals Competent Person

Qualifications Training Certification

Occupational and Environmental Assessment Data Report Medical Examinations

Lead, Cadmium, Chromium Waste Management Plan Licenses,

Permits and Notifications

Occupant Protection Plan

Lead, Cadmium, Chromium Compliance Plan

Initial Sample Results

SD-03 Product Data

Respirators Vacuum

Filters

Negative Air Pressure System Materials and

Equipment Expendable Supplies

Local Exhaust Equipment

Pressure Differential Automatic Recording Instrument Pressure Differential Log

SD-06 Test Reports

Sampling and Analysis

Occupational and Environmental Assessment Data Report

Sampling Results; G

Pressure Differential Recordings For Local Exhaust System SD-07 Certificates

Testing Laboratory

Third Party Consultant Qualifications

Clearance Certification

SD-11 Closeout Submittals Hazardous Waste

Manifest

Turn-In Documents or Weight Tickets

1.5 QUALITY ASSURANCE

1.5.1 Qualifications

1.5.1.1 Competent Person (CP)

Submit name, address, and telephone number of the CP selected to perform responsibilities specified in paragraph COMPETENT PERSON (CP) RESPONSIBILITIES. Provide documented construction project-related experience with implementation of OSHA's Lead in Construction standard (29 CFR 1926.62), Chromium standard (29 CFR 1926.1126), Cadmium standard (29 CFR 1926.1127) which shows ability to assess occupational and environmental exposure to lead, cadmium, chromium; experience with the use of respirators, personal protective equipment and other exposure reduction methods to protect employee health. Demonstrate a minimum of 5 years experience implementing OSHA's Lead in Construction standard (29 CFR 1926.62), Chromium standard (29 CFR 1926.1126), and Cadmium standard (29 CFR 1926.1127). Submit proper documentation that the CP is trained and licensed and certified in accordance with federal, State and local laws. The competent person must be a licensed lead-based paint abatement Supervisor/Project Designer in the State of Maine.

1.5.1.2 Training Certification

Submit a certificate for each worker and supervisor, signed and dated by the accredited training provider, stating that the employee has received the required lead, cadmium and chromium training specified in 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 and is certified to perform or supervise deleading, lead removal or demolition activities in the State of Maine.

1.5.1.3 Testing Laboratory

Submit the name, address, and telephone number of the testing laboratory selected to perform the air and wipe analysis, testing, and reporting of airborne concentrations of lead, cadmium and chromium. Use a laboratory participating in the EPA National Lead Laboratory Accreditation Program (NLLAP) by being accredited by either the American Association for Laboratory Accreditation (A2LA) or the American Industrial Hygiene Association (AIHA) and that is successfully participating in the Environmental Lead Proficiency Analytical Testing (ELPAT) program to perform sample analysis. Laboratories selected to perform blood lead analysis must be OSHA approved.

1.5.1.4 Third Party Consultant Qualifications

Submit the name, address and telephone number of the third party consultant selected to perform the air and wipe sampling for determining concentrations of lead, cadmium and chromium in air and dust. Submit proper documentation that the consultant is trained and certified as an inspector technician or inspector/risk assessor by the USEPA authorized State (or local) certification and accreditation program.

1.5.2 Requirements

1.5.2.1 Competent Person (CP) Responsibilities

a. Verify training meets all federal, State, and local requirements.

b. Review and approve Lead, Cadmium, Chromium Compliance Plan for conformance to the applicable referenced standards.

c. Continuously inspect LBP/PWL or MCL work for conformance with the approved plan.

d. Perform (or oversee performance of) air sampling. Recommend upgrades or downgrades (whichever is appropriate based on exposure) on the use of PPE (respirators included) and engineering controls.

e. Ensure work is performed in strict accordance with specifications at all times.

f. Control work to prevent hazardous exposure to human beings and to the environment at all times.

g. Supervise final cleaning of the lead, cadmium, chromium control area, take clearance wipe samples if necessary; review clearance sample results and make recommendations for further cleaning.

h. Certify the conditions of the work as called for elsewhere in this specification.

1.5.2.2 Lead, Cadmium, Chromium Compliance Plan

Submit a detailed job-specific plan of the work procedures to be used in the disturbance of lead, cadmium and chromium, LBP/PWL or MCL. Include in the plan a sketch showing the location, size, and details of lead, cadmium, chromium control areas, critical barriers, physical boundaries, location and details of decontamination facilities, viewing ports, and mechanical ventilation system. Include a description of equipment and materials, work practices, controls and job responsibilities for each activity from which lead, cadmium, chromium is emitted. Include in the plan, eating, drinking, smoking, hygiene facilities and sanitary procedures, interface of trades, sequencing of

lead, cadmium, chromium related work, collected waste water and dust containing lead, cadmium, chromium and debris, air sampling, respirators, personal protective equipment, and a detailed description of the method of containment of the operation to ensure that lead, cadmium, chromium is not released outside of the lead, cadmium, chromium control area. Include site preparation, cleanup and clearance procedures. Include occupational and environmental sampling, training and strategy, sampling and analysis strategy and methodology, frequency of sampling, duration of sampling, and qualifications of sampling personnel in the air sampling portion of the plan. Include a description of arrangements made among contractors on multicontractor worksites to inform affected employees and to clarify responsibilities to control exposures.

The plan must be developed and signed by a certified Lead Project Designer in the State of Maine. The plan must include the name and certification number of the person signing the plan.

In occupied buildings, the plan must also include an occupant protection program that describes the measures that will be taken during the work to notify and protect the building occupants.

1.5.2.3 Occupational and Environmental Assessment Data Report

If initial monitoring is necessary, submit occupational and environmental sampling results to the Owner's Representative within three working days of collection, signed by the testing laboratory employee performing the analysis, the employee that performed the sampling, and the CP.

In order to reduce the full implementation of 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 the Contractor must provide documentation. Submit a report that supports the determination to reduce full implementation of the requirements of 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 and supporting the Lead, Cadmium, Chromium Compliance Plan.

a. The initial monitoring must represent each job classification, or if working conditions are similar to previous jobs by the same employer, provide previously collected exposure data that can be used to estimate worker exposures per 29 CFR 1926.62,29 CFR 1926.1126, 29 CFR 1926.1127. The data must represent the worker's regular daily exposure to lead, cadmium, chromium for stated work.

b. Submit worker exposure data gathered during the task based trigger operations of 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 with a complete process description. This includes manual demolition, manual scraping, manual sanding, heat gun, power tool cleaning, rivet busting, cleanup of dry expendable abrasives, abrasive blast enclosure removal, abrasive blasting, welding, cutting and torch burning where lead, cadmium and chromium containing coatings are present.

c. The initial assessment must determine the requirement for further monitoring and the need to fully implement the control and protective requirements including the lead, cadmium, chromium compliance plan per 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127.

1.5.2.4 Medical Examinations

Submit pre-work blood lead levels and post-work blood lead levels for all workers performing lead, cadmium, chromium activities during the execution of the work. Initial medical surveillance as required by 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 must be made available to all employees exposed to lead, cadmium, chromium at any time (one day) above the action level. Full medical surveillance must be made available to all employees on an annual basis who are or may be exposed to lead, cadmium and chromium in excess of the action level for more than 30 days a year or as required by 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127. Adequate records

must show that employees meet the medical surveillance requirements of 29 CFR 1926.33, 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 and 29 CFR 1926.103. Provide medical surveillance to all personnel exposed to lead, cadmium, chromium as indicated in 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127. Maintain complete and accurate medical records of employees for the duration of employment plus 30 years.

1.5.2.5 Training

Train each employee performing work that disturbs lead, cadmium, chromium, who performs LBP/MCL/PWL disposal, and air sampling operations prior to the time of initial job assignment and annually thereafter, in accordance with 29 CFR 1926.21, 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127, 40 CFR 745 and State and local regulations where appropriate.

1.5.2.6 Respiratory Protection Program

a. Provide each employee required to wear a respirator a respirator fit test at the time of initial fitting and at least annually thereafter as required by 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127.

b. Establish and implement a respiratory protection program as required by 29 CFR 1926.103, 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 and 29 CFR 1926.55.

1.5.2.7 Hazard Communication Program

Establish and implement a Hazard Communication Program as required by 29 CFR 1926.59.

1.5.2.8 Lead, Cadmium, Chromium Waste Management

The Lead, Cadmium, Chromium Waste Management Plan must comply with applicable requirements of federal, State, and local hazardous waste regulations and address:

a. Identification and classification of wastes associated with the work.

b. Estimated quantities of wastes to be generated and disposed of.

c. Names and qualifications of each contractor that will be transporting, storing, treating, and disposing of the wastes. Include the facility location and operator and a 24-hour point of contact. Furnish two copies of USEPA and State of Maine and hazardous waste permit applications, permits, manifests and USEPA Identification numbers.

d. Names and qualifications (experience and training) of personnel who will be working on-site with hazardous wastes.

e. List of waste handling equipment to be used in performing the work, to include cleaning, volume reduction, and transport equipment.

f. Spill prevention, containment, and cleanup contingency measures including a health and safety plan to be implemented in accordance with 29 CFR 1926.65.

g. Work plan and schedule for waste containment, removal and disposal. Proper containment of the waste includes using acceptable waste containers (e.g., 55-gallon drums) as well as proper marking/labeling of the containers. Clean up and containerize wastes daily.

h. Include any process that may alter or treat waste rendering a hazardous waste non hazardous.

i. Unit cost for hazardous waste disposal according to this plan.

1.5.2.9 Environmental, Safety and Health Compliance

In addition to the detailed requirements of this specification, comply with laws, ordinances, rules, and regulations of federal, State, and local authorities regarding lead, cadmium and chromium. Comply with the applicable requirements of the current issue of 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 Where specification requirements and the referenced documents vary, the most stringent requirements apply.

Licensing and certification in the State of Maine is required.

1.5.3 Pressure Differential Recordings for Local Exhaust System

Provide a local exhaust system that creates a negative pressure of at least 0.02 inches of water relative to the pressure external to the enclosure and operate it continuously, 24-hours a day, until the temporary enclosure of the lead, cadmium, chromium control area is removed. Submit pressure differential recordings for each work day to the PQP and GC for review and to the Owner's Representative within 24-hours from the end of each work day.

1.5.4 Licenses, Permits and Notifications

Certify and submit in writing to the state's environmental protection agency responsible for lead hazard abatement activities at least 10 days prior to the commencement of work that licenses, permits and notifications have been obtained. All associated fees or costs incurred in obtaining the licenses, permits and notifications are included in the contract price.

1.5.5 Occupant Protection Plan

The certified project designer must develop and implement an Occupant Protection Plan describing the measures and management procedures to be taken during lead, cadmium and chromium hazard abatement activities to protect the building occupants/building facilities and the outside environment from exposure to any lead, cadmium and chromium contamination while lead, cadmium and chromium hazard abatement activities are performed.

1.5.6 Pre-Construction Conference

Along with the CP, meet with the Owner's Representative to discuss in detail the Lead, Cadmium, Chromium Waste Management Plan and the Lead, Cadmium, Chromium Compliance Plan, including procedures and precautions for the work.

1.6 EQUIPMENT

1.6.1 Respirators

Furnish appropriate respirators approved by the National Institute for Occupational Safety and Health (NIOSH), Department of Health and Human Services, for use in atmospheres containing lead, cadmium and chromium dust, fume and mist. Respirators must comply with the requirements of 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127.

1.6.2 Special Protective Clothing

Personnel exposed to lead, cadmium, chromium contaminated dust must wear proper disposable protective whole body clothing, head covering, gloves, eye, and foot coverings as required by 29

CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127. Furnish proper disposable plastic or rubber gloves to protect hands. Reduce the level of protection only after obtaining approval from the CP.

1.6.3 Rental Equipment Notification

If rental equipment is to be used during PWL or MCL handling and disposal, notify the rental agency in writing concerning the intended use of the equipment.

1.6.4 Vacuum Filters

UL 586 labeled HEPA filters.

1.6.5 Equipment for Government Personnel

Furnish the Owner's Representative personal protective equipment (PPE), as required herein, for entry into and inspection of the lead, cadmium and chromium removal work within the lead, cadmium and chromium controlled area. Personal protective equipment must include disposable whole body covering, including appropriate foot, head, eye, and hand protection. PPE remains the property of the Contractor.

1.6.6 Abrasive Removal Equipment

The use of powered machine for vibrating, sanding, grinding, or abrasive blasting is prohibited unless equipped with local exhaust ventilation systems equipped with high efficiency particulate air (HEPA) filters.

1.6.7 Negative Air Pressure System

1.6.7.1 Minimum Requirements

Do not proceed with work in the area until containment is set up and HEPA filtration systems are in place. The negative air pressure system must meet the requirements of ASSP Z9.2 including approved HEPA filters in accordance with UL 586. Negative air pressure equipment must be equipped with new HEPA filters, and be sufficient to maintain a minimum pressure differential of minus 0.02 inch of water column relative to adjacent, unsealed areas. Negative air pressure system minimum requirements are listed as follows:

a. The unit must be capable of delivering its rated volume of air with a clean first stage filter, an intermediate filter and a primary HEPA filter in place.

b. The HEPA filter must be certified as being capable of trapping and retaining mono-disperse particles as small as 0.3 micrometers at a minimum efficiency of 99.97 percent.

c. The unit must be capable of continuing to deliver no less than 70 percent of rated capacity when the HEPA filter is 70 percent full or measures 2.5 inches of water static pressure differential on a magnehelic gauge.

d. Equip the unit with a manometer-type negative pressure differential monitor with minor scale division of 0.02 inch of water and accuracy within plus or minus 1.0 percent. The manometer must be calibrated daily as recommended by the manufacturer.

e. Equip the unit with a means for the operator to easily interpret the readings in terms of the volumetric flow rate of air per minute moving through the machine at any given moment.

f. Equip the unit with an electronic mechanism that automatically shuts the machine off in the event of a filter breach or absence of a filter.

g. Equip the unit with an audible horn that sounds an alarm when the machine has shut itself off.

h. Equip the unit with an automatic safety mechanism that prevents a worker from improperly inserting the main HEPA filter.

1.6.7.2 Auxiliary Generator

Provide an auxiliary generator with capacity to power a minimum of 50 percent of the negative air machines at any time during the work. When power fails, the generator controls must automatically start the generator and switch the negative air pressure system machines to generator power.
The generator must not present a carbon monoxide hazard to workers.

1.6.8 Vacuum Systems

Vacuum systems must be suitably sized for the project, and filters must be capable of trapping and retaining all mono-disperse particles as small as
0.3 micrometers (mean aerodynamic diameter) at a minimum efficiency of
99.97 percent. Properly dispose of used filters that are being replaced.

1.6.9 Heat Blower Guns

Heat blower guns must be flameless, electrical, paint-softener type with controls to limit temperature to 1,100 degrees F. Heat blower must be (grounded) 120 volts ac, and must be equipped with cone, fan, glass protector and spoon reflector nozzles.

1.7 PROJECT/SITE CONDITIONS

1.7.1 Protection of Existing Work to Remain

Perform work without damage or contamination of adjacent areas. Where existing work is damaged or contaminated, restore work to its original condition or better as determined by the Owner's Representative.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

Keep materials and equipment needed to complete the project available and on the site. Submit a description of the materials and equipment required; including Safety Data Sheets (SDSs) for material brought onsite to perform the work.

2.1.1 Expendable Supplies

Submit a description of the expendable supplies required.

2.1.1.1 Polyethylene Bags

Disposable bags must be polyethylene plastic and be a minimum of 6 mils thick (4 mils thick if double bags are used) or any other thick plastic material shown to demonstrate at least equivalent

performance; and capable of being made leak-tight. Leak-tight means that solids, liquids or dust cannot escape or spill out.

2.1.1.2 Polyethylene Leak-tight Wrapping

Wrapping used to wrap lead, cadmium, chromium contaminated debris must be polyethylene plastic that is a minimum of 6 mils thick or any other thick plastic material shown to demonstrate at least equivalent performance.

2.1.1.3 Polyethylene Sheeting

Sheeting must be polyethylene plastic with a minimum thickness of 6 mil, or any other thick plastic material shown to demonstrate at least equivalent performance; and be provided in the largest sheet size reasonably accommodated by the project to minimize the number of seams. Where the project location constitutes an out of the ordinary potential for fire, or where unusual fire hazards cannot be eliminated, provide flame-resistant polyethylene sheets which conform to the requirements of NFPA 701.

2.1.1.4 Tape and Adhesive Spray

Tape and adhesive must be capable of sealing joints between polyethylene sheets and for attachment of polyethylene sheets to adjacent surfaces.
After dry application, tape or adhesive must retain adhesion when exposed to wet conditions, including amended water. Tape must be minimum 2 inches wide, industrial strength.

2.1.1.5 Containers

When used, containers must be leak-tight and be labeled in accordance with EPA, DOT and OSHA standards.

2.1.1.6 Chemical Paint Strippers

Chemical paint strippers must not contain methylene chloride and be formulated to prevent stain, discoloration, or raising of the substrate materials.

2.1.1.7 Chemical Paint Stripper Neutralizer

Neutralizers for paint strippers must be compatible with the substrate and suitable for use with the chemical stripper that has been applied to the surface.

2.1.1.8 Detergents and Cleaners

Detergents or cleaning agents must not contain trisodium phosphate and have demonstrated effectiveness in lead, cadmium and chromium control work using cleaning techniques specified by HUD 6780 guidelines.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Protection

3.1.1.1 Notification

a. Notify the Owner's Representative 20 days prior to the start of any lead, cadmium and chromium work.

3.1.1.2 Lead, Cadmium, Chromium Control Area

a. Physical Boundary - Provide physical boundaries around the lead, cadmium, chromium control area by roping off the area designated in the work plan or providing curtains, portable partitions or other enclosures to ensure that lead, cadmium and chromium will not escape outside of the lead, cadmium and chromium control area. Prohibitthe general public from accessing the lead, cadmium, chromium control areas.

b. Warning Signs - Provide warning signs at approaches to lead, cadmium, chromium control areas. Locate signs at such a distance that personnel may read the sign and take the necessary precautions before entering the area. Signs must comply with the requirements of 29 CFR 1926.62.

3.1.1.3 Heating, Ventilating and Air Conditioning (HVAC) Systems

Shut down, lock out, and isolate HVAC systems that supply, exhaust, or pass through the lead, cadmium, chromium control areas. Seal intake and exhaust vents in the lead, cadmium, chromium control area with 6 mil plastic sheet and tape. Seal seams in HVAC components that pass through the lead, cadmium, chromium control area. Provide temporary HVAC system for areas in which HVAC has been shut down outside the lead, cadmium, chromium control area.

3.1.1.4 Local Exhaust System

Provide a local exhaust system in the lead, cadmium, chromium control area in accordance with ASSP Z9.2, 29 CFR 1926.62, 29 CFR 1926.1126 and 29 CFR 1926.1127 that will provide at least 4 air changes per hour inside of the negative pressure enclosure. Local exhaust equipment must be operated 24-hours per day, until the lead, cadmium, chromium control area is removed and must be leak proof to the filter and equipped with HEPA filters. Maintain a minimum pressure differential in the lead, cadmium, chromium control area of minus 0.02 inch of water column relative to adjacent, unsealed areas. Provide continuous 24-hour per day monitoring of the pressure differential with a pressure differential automatic recording instrument. The building ventilation system must not be used as the local exhaust system for the lead, cadmium, chromium control area. Filters on exhaust equipment must conform to ASSP Z9.2 and UL 586. Terminate the local exhaust system out of doors and remote from any public access or ventilation system intakes.

3.1.1.5 Negative Air Pressure System Containment

a. Operate the negative air pressure systems to provide at least 4 air changes per hour inside the containment. Operate the local exhaust unit equipment continuously until the containment is removed. Smoke test the negative air pressure system for leaks at the beginning of each shift. The certified supervisor is responsible to continuously monitor and keep a pressure differential log with an automatic manometric recording instrument. Notify the Owner's Representative immediately if the pressure differential falls below the prescribed minimum. Submit the continuously monitored pressure differential log, as specified. Do not use the building ventilation system as the local exhaust system.Terminate the local exhaust system out of doors. All filters must be new at the beginning of the project and be periodically changed as necessary to maintain specified pressure differential and disposed of as lead, cadmium and chromium contaminated waste.

b. Discontinuing Negative Air Pressure System: Operate the negative air pressure system continuously during abatement activities. At the completion of the project, units must be run until full cleanup has been completed and final clearance testing requirements have been met.Dismantling of the negative air pressure systems must be as presented in the Lead, Cadmium, Chromium Compliance Plan. Seal the HEPA filter machine intakes with polyethylene to prevent environmental contamination.

3.1.1.6 Decontamination Shower Facility

Provide clean and contaminated change rooms and shower facilities in accordance with this specification and 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127.

3.1.1.7 Eye Wash Station

Provide suitable facilities within the work area for quick drenching or flushing of the eyes where eyes may be exposed to injurious corrosive materials.

3.1.1.8 Mechanical Ventilation System

a. Use adequate ventilation to control personnel exposure to lead, cadmium and chromium in accordance with 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127. To the extent feasible, use local exhaust ventilation or other collection systems, approved by the CP. Evaluate and maintain local exhaust ventilation systems in accordance with 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127.

b. Vent local exhaust outside the building and away from building ventilation intakes or ensure system is connected to HEPA filters.

c. Use locally exhausted, power actuated tools or manual hand tools.

3.1.1.9 Personnel Protection

Personnel must wear and use protective clothing and equipment as specified herein. Eating, smoking, or drinking or application of cosmetics is not permitted in the lead, cadmium, chromium control area. No one will be permitted in the lead, cadmium, chromium control area unless they have been appropriately trained and provided with protective equipment.

3.2 ERECTION

3.2.1 Lead, Cadmium, Chromium Control Area Requirements

Establish a lead, cadmium, chromium control area by completely establishing barriers and physical boundaries around the area or structure where PWL or MCL removal operations will be performed.

Full containment - Contain removal operations by the use of critical barriers and HEPA filtered exhaust, a negative pressure enclosure system with decontamination facilities and with HEPA filtered exhaust if required by the CP. For containment areas larger than 1,000 square feet install a minimum of two 18 inch square viewing ports. Locate ports to provide a view of the required work from the exterior of the enclosed contaminated area. Glaze ports with laminated safety glass.

3.3 APPLICATION

3.3.1 Lead, Cadmium, Chromium Work

Perform lead, cadmium, chromium work in accordance with approved Lead, Cadmium, Chromium Compliance Plan. Use procedures and equipment required to limit occupational exposure and environmental contamination with lead, cadmium, chromium when the work is performed in accordance with 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 and as specified herein. Dispose of all PWL or MCL and associated waste in compliance with federal, State, and local requirements.

3.3.2 Paint with Lead, Cadmium, Chromium or Material Containing Lead, Cadmium, Chromium Removal

Manual or power sanding or grinding of lead, cadmium, chromium surfaces or materials is not permitted unless tools are equipped with HEPA attachments or wet methods. The dry sanding or grinding of surfaces that contain lead, cadmium, chromium is prohibited. Provide methodology for removing lead, cadmium, chromium in the Lead, Cadmium, Chromium Compliance Plan. Select lead, cadmium, chromium removal processes to minimize contamination of work areas outside the control area with lead, cadmium, chromium contaminated dust or other lead, cadmium, chromium contaminated debris or waste and to ensure that unprotected personnel are not exposed to hazardous concentrations of lead, cadmium, chromium. Describe this removal process in the Lead, Cadmium, Chromium Compliance Plan.

Provide methodology for lead, cadmium and chromium, LBP/PWL removal, abatement/control and processes to minimize contamination of work areas outside the control area with lead, cadmium, chromium contaminated dust or other lead, cadmium, chromium contaminated debris/waste and to ensure that unprotected personnel are not exposed to hazardous concentrations of lead, cadmium, chromium. Describe this lead,, cadmium and chromium, LBP/PWL removal/control process in the Lead, Cadmium, Chromium Compliance Plan.

3.3.2.1 Paint with Lead, Cadmium, Chromium or Material Containing Lead, Cadmium, Chromium - Indoor Removal

Perform manual or mechanical removal and thermal cutting in the lead, cadmium, chromium control areas using enclosures, barriers or containments and powered locally exhausted tools equipped with HEPA filters. Collect residue and debris for disposal in accordance with federal, State, and local requirements.

3.3.2.2 Paint with Lead, Cadmium, Chromium or Material Containing Lead, Cadmium, Chromium - Outdoor Removal

Perform outdoor removal as indicated in federal, State, and local regulations and in the Lead, Cadmium, Chromium Compliance Plan. The worksite preparation (barriers or containments) must be job dependent and presented in the Lead, Cadmium, Chromium Compliance Plan.

3.3.3 Personnel Exiting Procedures

Whenever personnel exit the lead, cadmium, chromium controlled area, they must perform the following procedures and must not leave the work place wearing any clothing or equipment worn in the control area:

a. Vacuum all clothing before entering the contaminated change room.

b. Remove protective clothing in the contaminated change room, and place them in an approved impermeable disposal bag.

c. Shower.

d. Change to clean clothes prior to leaving the clean clothes storage area.

3.4 FIELD QUALITY CONTROL

3.4.1 Tests

3.4.1.1 Air and Wipe Sampling

Conduct sampling for lead, cadmium, chromium in accordance with 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 and as specified herein. Air and wipe sampling must be directed or performed by the CP.

a. The CP must be on the job site directing the air and wipe sampling and inspecting the PWL or MCL removal work to ensure that the requirements of the contract have been satisfied during the entire PWL or MCL operation.

b. Collect personal air samples on employees who are anticipated to have the greatest risk of exposure as determined by the CP. In addition, collect air samples on at least twenty-five percent of the work crew or a minimum of two employees, whichever is greater, during each work shift.

c. Submit initial sample results of air samples, signed by the CP, within 72-hours after the air samples are taken.

d. Conduct area air sampling daily, on each shift in which lead, cadmium and chromium and lead-based paint removal operations are performed, in areas immediately adjacent to the lead, cadmium and chromium control area. Conduct sufficient area monitoring to ensure unprotected personnel are not exposed at or above 30 micrograms of lead per cubic meter of air or 2.5 micrograms of cadmium/chromium per cubic meter of air. If 30 micrograms of lead per cubic meter of air or 2.5 micrograms of cadmium/chromium per cubic meter of air is reached or exceeded, stop work, correct the conditions(s) causing the increased levels. Notify the Owner's Representative immediately. Determine if condition(s) require any further change in work methods. Resume removal work only after the CP and the Owner's Representative give approval.

e. Before any work begins, a third party consultant must collect and analyze baseline wipe and soil (if bare soil is present during exterior remediation operations) samples in accordance with methods defined by federal, State, and local standards inside and outside of the physical boundary to assess the degree of dust contamination in the facility prior to lead, cadmium and chromium disturbance or removal. Provide Initial Sample Results to the Owner's Representative before work begins.

f. Surface Wipe Samples - Collect surface wipe samples on floors at a location no greater than 10 feet outside the lead, cadmium, chromium control area at a frequency of once per day while lead, cadmium, chromium removal work is conducted in occupied buildings. Surface wipe samples or Micro Vacuum surface sample results must meet criteria in paragraph CLEARANCE CERTIFICATION.

3.4.1.2 Sampling After Removal

After the visual inspection, conduct soil sampling if bare soil is present during external removal

operations and collect wipe and soil samples according to the HUD protocol contained in HUD 6780 to determine the lead,

cadmium and chromium content of settled dust in micrograms per square foot of surface area and parts per million (ppm) for soil.

3.4.1.3 Testing of Material Containing Lead, Cadmium, Chromium Residue Test residue in

accordance with 40 CFR 261 for hazardous waste.

3.5 CLEANING AND DISPOSAL

3.5.1 Cleanup

Maintain surfaces of the lead, cadmium, chromium control area free of accumulations of dust and debris. Restrict the spread of dust and debris; keep waste from being distributed over the work area. Do not dry sweep or use pressurized air to clean up the area. At the end of each shift and when the lead, cadmium, chromium operation has been completed, clean the controlled area of all visible contamination by vacuuming with a HEPA filtered vacuum cleaner, wet mopping the area and wet wiping the area as indicated by the Lead, Cadmium, Chromium Compliance Plan. Reclean areas showing dust or debris. After visible dust and debris is removed, wet wipe and HEPA vacuum all surfaces in the controlled area. If adjacent areas become contaminated at any time during the work, clean, visually inspect, and then wipe sample all contaminated areas. The CP must then certify in writing that the area has been cleaned of lead, cadmium and chromium contamination before clearance testing.

3.5.1.1 Clearance Certification

The CP must certify in writing that air samples collected outside the lead, cadmium, chromium control area during paint removal operations are less than 30 micrograms of lead per cubic meter of air and less than 2.5 micrograms of cadmium/chromium per cubic meter of air; the respiratory protection used for the employees was adequate; the work procedures were performed in accordance with 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127; and that there were no visible accumulations of material and dust containing lead, cadmium, chromium left in the work site.Do not remove the lead, cadmium, chromium control area or roped off boundary and warning signs prior to the receipt of the CP certification.

The third party consultant must certify surface wipe sample results collected inside and outside the work area are less than 40 micrograms of lead per square foot on floors, less than 250 micrograms of lead per square foot on interior window sills and less than 400 micrograms of lead per square foot on window troughs not significantly greater than the initial surface loading determined prior to work.

The third party consultant must certify surface wipe sample or Micro Vacuum surface sample results collected inside and outside the work area are less than 200 micrograms of lead per square foot on floors or horizontal surfaces. Micro Vacuum technique should be used on rough or porous surfaces which are difficult to achieve clearance by the wipe sampling methodology.

Certify surface wipe samples are not significantly greater than the initial surface loading determined prior to work.

Clear the lead, cadmium, chromium control area in industrial facilities of all visible dust and debris.

For exterior work, soil samples taken at the exterior of the work site must be used to determine if soil lead, cadmium, chromium levels have increased at a statistically significant level (significant at the 95 percent confidence limit) from the soil lead, cadmium, chromium levels prior to the operation. If soil lead, cadmium, chromium levels either show a statistically significant increase above soil lead, cadmium, chromium levels prior to work or soil lead, cadmium, chromium levels above any applicable federal or state standard for lead, cadmium, chromium in soil, the soil must be remediated.

3.5.2 Disposal

a. Dispose of material, whether hazardous or non-hazardous in accordance with all laws and provisions and all federal, State or local regulations. Ensure all waste is properly characterized. The result of each waste characterization (TCLP for RCRA materials) will dictate disposal requirements.

b. Contractor is responsible for segregation of waste. Collect lead, cadmium, chromium contaminated waste, scrap, debris, bags, containers, equipment, and lead, cadmium, chromium-contaminated clothing that may produce airborne concentrations of lead, cadmium, chromium particles. Label the containers in accordance with 29 CFR 1926.62, 29 CFR 1926.1126, 29 CFR 1926.1127 and 40 CFR 261, 40 CFR 262 and corresponding state regulations.

c. Dispose of lead, cadmium, chromium-contaminated material classified as hazardous waste at an EPA or State approved hazardous waste treatment, storage, or disposal facility off Government property.

d. Accumulate waste materials in U.S. Department of Transportation (49 CFR 178) approved 55 gallon drums or appropriately sized container for smaller volumes. Properly label each drum to identify the type of hazardous material (49 CFR 172). For hazardous waste, the collection container requires marking/labeling in accordance with 40 CFR 262 and corresponding state regulations during the accumulation/collection timeframe. Coordinate authorized accumulation volumes and time limits with the host installation environmental function.

e. Handle, store, transport, and dispose lead, cadmium, chromium or lead, cadmium, chromium contaminated waste in accordance with 40 CFR 260, 40 CFR 261, 40 CFR 262, 40 CFR 263, 40 CFR 264, and 40 CFR 265. Comply with land disposal restriction notification requirements as required by 40 CFR 268.

f. All lead, cadmium, and chromium waste generation, management,and disposal will be coordinated with the Owner’s Representative.

3.5.2.1 Disposal Documentation

Submit written evidence of TSD approval to demonstrate the hazardous waste treatment, storage, or

disposal facility (TSD) is approved for lead, cadmium, chromium disposal by the EPA, State or local regulatory agencies. Submit one copy of the completed hazardous waste manifest, signed and dated by the initial transporter in accordance with 40 CFR 262. Provide a certificate that the waste was accepted by the disposal facility. Provide turn-in documents or weight tickets for non-hazardous waste disposal.

3.5.2.2 Payment for Hazardous Waste

Payment for disposal of hazardous and non-hazardous waste will not be made until a signed copy of the manifest from the treatment or disposal facility is received and approved by the Owner's Representative. The manifest must detail and certify the amount of lead, cadmium, chromium containing materials or non-hazardous waste delivered to the treatment or disposal facility.

END OF SECTION

SECTION 028400 – PCB REMEDIATION

PART 1 - GENERAL

1.1 SUMMARY

A. This section specifies requirements for the demolition and disposal of PCB Bulk Product Waste (BPW). The requirements of this section apply to demolition or renovation of the following:

1. Material (paint, caulk and sealants etc.) previously determined or assumed to contain greater than 50 parts per million (ppm) PCBs.
2. Substrate contaminated (>50 ppm) by PCB paints, caulks and/or sealants etc., if removed at the same time as PCB BPW.

B. Extent of PCB-containing materials is as follows:

1. Sealant at Door S3-1A Frame Exterior Perimeter: PCBs – 1,190 mg/Kg.

1.2 DEFINITIONS

A. The abbreviation “PCB” stands for Polychlorinated Biphenyl.

B. The term “PCB bulk product waste” refers to waste derived from manufactured products containing PCBs in a non-liquid state, where the concentration at time of disposal is greater than or equal to 50 parts per million (ppm). This includes caulks, applied dried paints, varnishes, waxes, or other similar coatings or sealants.

C. The term “Project Site” indicates the limits of the project site as indicated on drawings or by provisions of this specification.

D. The term “work area” indicates the area within the critical barrier.

E. The term "critical barrier" indicates the perimeter of the enclosure within which PCB disruption/removal work takes place. Critical barriers may include existing floor, wall, and ceiling structures, as well as constructed partitions, closures and seals.

1.3 RELATED SECTOIONS

A. Demolition and removal of items not containing PCB as a component is included in Division 02 Section "Selective Demolition."

PART 2 - PRODUCTS (NOT APPLICABLE)

PART 3 - EXECUTION

3.1 PCB BULK PRODUCT WASTE REMOVAL, GENERAL

A. Conduct PCB removal operations in a manner that fully protects Contractor's and subcontractor's employees, the general public, and building occupants from exposure to PCB's.

B. Protect adjacent areas, materials and surfaces from damage due to demolition operations, including but not necessarily limited to the following:

1. Water damage.
2. Dirt, dust, and debris.
3. Abrasion.
4. Cuts and scratches.
5. Holes from fasteners for temporary barriers.

C. All removal shall be conducted within a regulated area that complies with the following requirements:

1. Establish a regulated area with caution tape and signage to keep unauthorized personnel out of the area.
2. Allow only authorized, properly protected personnel to enter the regulated area. Immediately report unauthorized individuals entering the work area to Owner's Representative.

D. Provide respiratory protection to employees as required by current MiOSHA regulations including Part 451 Respiratory Protection and MiOSHA part 301 Air Contaminants.

1. Provide abatement workers with adequate respiratory protection during PCB BPW removal. At a minimum, half face respirators with HEPA cartridges must be used. If removal methods generate heat above 212^{O}F, combination HEPA/organic cartridges must be used.
2. Provide personal protective equipment for protection against dermal exposures including nitrile gloves and Tyvek^{R} or similar suits.

E. Maintain at each job site and post the following documents:

1. Employee respiratory protection program.
2. Material Safety Data Sheet locator.
3. Company standard operating procedure.
4. This specification Section.
5. Material Safety Data Sheets for products used on job.

F. Do not use any of the following equipment or work practices, regardless of measured exposure levels:

1. Dry sweeping or use of compressed air to clean work surfaces.

2. Removal of caulk using abrasive grinding wheels, wire wheels, sanding or other means that generate excessive dust.
3. Use of ordinary vacuums to clean up dust and debris. Vacuums with HEPA filtration must be used.

3.2 PCB BPW REMOVAL BY HAND METHODS

A. Preparation of the Work Area: Complete the following preparation work prior to beginning removal operations using hand methods (utility knife, hammer and chisel, putty knife etc.).

1. Seal intake and exhaust vents and duct seams within the regulated area with 1 layer of 6-mil polyethylene sheeting.
2. Protect all surfaces near removal activity. Remove moveable objects from the work area and cover fixed objects with impermeable drop cloths or plastic sheeting with edges securely sealed with tape.
3. All floor and wall areas adjacent to the work area shall have a layer of 6 mil fire retardant polyethylene sheeting, attached to the interior wall and on floor surfaces below the abatement work area, at least 5 feet wide.
4. Close all windows during interior and exterior removal projects.
5. Regardless of method of removal, if dust is noted during removal activities, stop removal and adjust work practices or engineering controls. If dust generation continues, a full enclosure is required. See Section 3.3 “PCB Removal by Mechanical Methods.”

B. PCB BPW Removal Operations: Comply with the following requirements for removal operations:

1. Remove PCB BPW using misting methods to assist in dust settling.
2. Material should be removed in intact sections if possible.
3. Adjust mechanical ventilation and or work practices accordingly to eliminate visible dust levels.
4. Place PCB BPW in labeled 6-mil polyethylene bags.
5. Place all bagged PCB BPW in drums or dumpsters.

C. Post-Removal Operation Requirements: After completion of PCB BPW removal and clean-up operations, comply with the following requirements:

1. HEPA vacuum and wet wipe/mop all areas until area is dust free.
2. The Contractor representative, in presence of Owner or Owner’s Representative shall inspect the entire work area for PCB BPW dust or material.
3. If any suspect material is found, repeat final cleaning operation, until the visual inspection is satisfactory to the Owner.

D. Employee Decontamination Requirements:

1. Employees shall immediately wash hands, face and other potentially exposed surfaces of the body with soap and water each time they leave the regulated area.
2. Change out of work clothes and shower if necessary to prevent bringing PCB contamination home.

3.3 PCB BPW REMOVAL BY MECHANICAL METHODS

A. Preparation of the Work Area: Complete the following preparation work prior to beginning removal operations using mechanical means (any method other than hand tools).

1. Mechanical cutting or grinding of PCB materials is not permitted, unless the equipment has a HEPA filtered exhaust.
2. Install critical barriers over each opening into the regulated area. The following requirements are in addition to, not in lieu of, other indicated surface and object protection requirements:

    a. Seal each opening between the work area and adjacent areas with 1 layer of 4-mil polyethylene sheeting. Openings include, but are not necessarily limited to, windows, skylights, doorways, elevator hoistway openings, corridor entrances, drains, ducts, grills, grates, and diffusers.
    b. Seal intake and exhaust vents and duct seams within the regulated area with 1 layer of 6-mil polyethylene sheeting.

3. Close all windows during interior and exterior removal projects.
4. Protection of Surfaces and Objects: The following requirements are in addition to, not in lieu of, indicated work area sealing requirements. Cover the following surfaces and objects as follows:

    a. Protect all surfaces near removal activity. Remove moveable objects from the work area and cover fixed objects with impermeable drop cloths or plastic sheeting with edges securely sealed with tape.
    b. Completely cover walls and floors within the regulated area with a layer of 6-mil polyethylene sheeting. Avoid seams where possible. If seams are necessary, overlap not less than 12 inches and tape joints. Immediately repair punctures and leaks and clean up seepage.
    c. Cleaning: Do not use cleaning methods that raise dust, such as sweeping or using vacuum cleaners not equipped with HEPA filters.
    d. Fully seal floor drains.

B. PCB BPW Removal Operations: Comply with the following requirements for removal operations:

1. Remove PCB BPW using misting methods to assist in dust settling.
2. Material should be removed in intact sections if possible.
3. Adjust mechanical ventilation and or work practices accordingly to minimize visible dust levels.
4. Place PCB BPW in labeled 6-mil polyethylene bags.
5. Place all bagged PCB BPW in drums or dumpsters.

C. Post-Removal Operation Requirements: After completion of PCB BPW removal and clean-up operations, comply with the following requirements:

1. HEPA vacuum and wet wipe/mop all areas until area is dust free.
2. The Contractor representative, in presence of Owner or Owner’s Representative shall inspect the entire work area for PCB BPW dust or material.
3. If any suspect material is found, repeat final cleaning operation, until the visual inspection is satisfactory to the Owner.

D. Employee Decontamination Requirements: Comply with the following requirements:

1. Access the work area only through an approved decontamination system. Lock or block other entrances. Seal emergency exits (for use during a fire or accident) with polyethylene sheeting and tape.
2. Entrance To The Regulated Area: Employees shall enter the decontamination area through the clean room, remove and store clothing, and put on protective clothing and respiratory protection before passing through to the equipment room.
3. Exit From The Regulated Area: Employees shall exit the regulated area by removing gross contamination and debris from their protective clothing. The clothing shall be removed and disposed of in the equipment room into labeled impermeable bags or containers.
4. Employees shall wash hands, face and other potentially exposed surfaces of the body with soap and water each time they leave the containment.
5. Employees shall change out of work clothes and shower if necessary to prevent bringing PCB contamination home.

3.4 DISPOSAL OF WASTE

A. PCB BPW shall be disposed of as PCB waste following the requirements listed below:

1. Bag and place PCB BPW in drums or dumpsters.
2. All PCB waste must be less than 3 foot x 3 foot prior to bagging or wrapping for disposal.
3. Store waste containers or articles in a secure area.
4. Do not stage containers on lawns, dirt piles, gravel drive areas with mud or basement areas with no elevator access.
5. Ensure that soil, ground water, and drains or sewers within the storage area are protected from possible contamination. Keep containers secure and tightly closed at all times, except when adding waste.
6. Keep abatement waste segregated from other waste and from other Projects. Do not co-mingle waste.
7. Place appropriate labels on all containers. Provide all information required on the label; mark labels using indelible ink.
8. Mark the side of each container with the name and phone number of Owner's Representative knowledgeable about the type of waste contained.

B. Disposal of PCB waste shall be done in coordination with 40 CFR 761.62.

1. Materials with PCB concentrations $\geq$50 mg/Kg are considered hazardous by Maine Solid Waste Regulations and must be sent for disposal out of state.

END OF SECTION

SECTION 028416 - HANDLING OF LIGHTING BALLASTS AND LAMPS CONTAINING PCBs AND MERCURY

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced.The publications are referred to within the text by the basic designation only.

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000	Air Contaminants
40 CFR 260	Hazardous Waste Management System: General
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
40 CFR 264	Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 265	Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 268	Land Disposal Restrictions
40 CFR 270	EPA Administered Permit Programs: The Hazardous Waste Permit Program
40 CFR 273	Standards For Universal Waste Management
40 CFR 761	Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions
49 CFR 178	Specifications for Packagings

1.2 REQUIREMENTS

Removal and disposal of PCB containing lighting ballasts and associated mercury-containing lamps. Contractor may encounter leaking PCB ballasts. Refer to the report at the end of Section 02 82 00 ASBESTOS REMEDIATION.

1.3 DEFINITIONS

1.3.1 Certified Industrial Hygienist (CIH)

A industrial hygienist hired by the contractor shall be certified by the American Board of Industrial Hygiene.

1.3.2 Leak

Leak or leaking means any instance in which a PCB article, PCB container, or PCB equipment has any PCBs on any portion of its external surface.

1.3.3 Lamps

Lamp, also referred to as "universal waste lamp", is defined as the bulb or tube portion of an electric lighting device. A lamp is specifically designed to produce radiant energy, most often in the ultraviolet, visible, and infra-red regions of the electromagnetic spectrum. Examples of common universal waste electric lamps include, but are not limited to, fluorescent, high intensity discharge, neon, mercury vapor, high pressure sodium, and metal halide lamps.

1.3.4 Polychlorinated Biphenyls (PCBs)

PCBs as used in this specification shall mean the same as PCBs, PCB containing lighting ballast, and PCB container, as defined in 40 CFR 761, Section 3, Definitions.

1.3.5 Spill

Spill means both intentional and unintentional spills, leaks, and other uncontrolled discharges when the release results in any quantity of PCBs running off or about to run off the external surface of the equipment or other PCB source, as well as the contamination resulting from those releases.

1.3.6 Universal Waste

Universal Waste means any of the following hazardous wastes that are managed under the universal waste requirements 40 CFR 273:

(1) Batteries as described in Sec. 273.2 of this chapter;
(2) Pesticides as described in Sec. 273.3 of this chapter;
(3) Thermostats as described in Sec. 273.4 of this chapter; and
(4) Lamps as described in Sec. 273.5 of this chapter.

1.4 QUALITY ASSURANCE

1.4.1 Regulatory Requirements

Perform PCB related work in accordance with 40 CFR 761. Perform mercury-containing lamps storage and transport in accordance with 40 CFR 261, 40 CFR 264, 40 CFR 265, and 40 CFR 273.

1.4.2 Training

Certified industrial hygienist (CIH) shall instruct and certify the training of all persons involved in

the removal of PCB containing lighting ballasts and mercury-containing lamps. The instruction shall include: The dangers of PCB and mercury exposure, decontamination, safe work practices, and applicable OSHA and EPA regulations. The CIH shall review and approve the PCB and Mercury-Containing Lamp Removal Work Plans.

1.4.3 Regulation Documents

Maintain at all times one copy each at the office and one copy each in view at the job site of 29 CFR 1910.1000, 40 CFR 260, 40 CFR 261,
40 CFR 262, 40 CFR 263, 40 CFR 265, 40 CFR 268, 40 CFR 270, and 40 CFR 273
and of the Contractor removal work plan and disposal plan for PCB and for associated mercury-containing lamps.

1.5 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-07 Certificates Qualifications of CIH

Training Certification

PCB and Lamp Removal Work Plan

PCB and Lamp Disposal Plan

SD-11 Closeout Submittals

Transporter certification of notification to EPA of their PCB waste activities and EPA ID numbers; G

Certification of Decontamination

Certificate of Disposal and/or recycling. Submit to the Government before application for payment within 30 days of the date that the disposal of the PCB and mercury-containing lamp waste identified on the manifest was completed.

1.6 ENVIRONMENTAL REQUIREMENTS

Use special clothing:

a. Disposable gloves (polyethylene)

b. Eye protection

c. PPE as required by CIH

1.7 SCHEDULING

Notify the Contracting Officer 20 days prior to the start of PCB and mercury-containing lamp removal work.

1.8 QUALITY ASSURANCE

1.8.1 Qualifications of CIH

Submit the name, address, and telephone number of the Industrial Hygienist selected to perform the duties in paragraph entitled "Certified Industrial Hygienist." Submit training certification that the Industrial Hygienist is certified, including certification number and date of certification or re certification.

1.8.2 PCB and Lamp Removal Work Plan

Submit a job-specific plan within 20 calendar days after award of contract of the work procedures to be used in the removal, packaging, and storage of PCB-containing lighting ballasts and associated mercury-containing lamps. Include in the plan: Requirements for Personal Protective Equipment (PPE), spill cleanup procedures and equipment, eating, smoking and restroom procedures. The plan shall be approved and signed by the Certified Industrial Hygienist. Obtain approval of the plan by the Contracting Officer prior to the start of PCB and/or lamp removal work.

1.8.3 PCB and Lamp Disposal Plan

Submit a PCB and lamp Disposal Plan with 45 calendar days after award of contract. The PCB and Lamp Disposal Plan shall comply with applicable requirements of federal, state, and local PCB and Universal waste regulations and address:

a. Estimated quantities of wastes to be generated, disposed of, and recycled.

b. Names and qualifications of each Contractor that will be transporting, storing, treating, and disposing of the wastes. Include the facility location. Furnish two copies of EPA and state PCB and
mercury-containing lamp waste permit applications and EPA identification numbers, as required.

c. Names and qualifications (experience and training) of personnel who will be working on-site with PCB and mercury-containing lamp wastes.

d. Spill prevention, containment, and cleanup contingency measures to be implemented.

e. Work plan and schedule for PCB and mercury-containing lamp waste removal, containment, storage, transportation, disposal and or recycling. Wastes shall be cleaned up and containerize daily.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 WORK PROCEDURE

Furnish labor, materials, services, and equipment necessary for the removal of PCB containing lighting ballasts, associated mercury-containing fluorescent lamps, and high intensity discharge (HID) lamps in accordance with local, state, or federal regulations. Do not expose PCBs to open flames or other high temperature sources since toxic decomposition

by-products may be produced. Do not break mercury containing fluorescent lamps or high intensity discharge lamps.

3.1.1 Work Operations

Ensure that work operations or processes involving PCB or PCB-contaminated materials are conducted in accordance with 40 CFR 761, 40 CFR 262
40 CFR 263, and the applicable requirements of this section, including but not limited to:

a. Obtaining suitable PCB and mercury-containing lamp storage sites.

b. Notifying Owner's Representative prior to commencing the operation.

c. Reporting leaks and spills to the Owner's Representative.

d. Cleaning up spills.

e. Inspecting PCB and PCB-contaminated items and waste containers for leaks and forwarding copies of inspection reports to the Contracting Officer.

f. Maintaining inspection, inventory and spill records.

3.2 PCB SPILL CLEANUP REQUIREMENTS

3.2.1 PCB Spills

Immediately report to the Owner's Representative any PCB spills.

3.2.2 PCB Spill Control Area

Rope off an area around the edges of a PCB leak or spill and post a "PCB Spill Authorized Personnel Only" caution sign. Immediately transfer leaking items to a drip pan or other container.

3.2.3 PCB Spill Cleanup

40 CFR 761, subpart G. Initiate cleanup of spills as soon as possible, but no later than 24 hours of its discovery. Mop up the liquid with rags or other conventional absorbent. The spent absorbent shall be properly contained and disposed of as solid PCB waste.

3.2.4 Records and Certification

Document the cleanup with records of decontamination in accordance with
40 CFR 761, Section 125, Requirements for PCB Spill Cleanup. Provide test results of cleanup and certification of decontamination.

3.3 REMOVAL

3.3.1 Ballasts

As ballast are removed from the lighting fixture, inspect label on ballast. Ballasts without a "No PCB" label shall be assumed to contain PCBs and containerized and disposed of as required under paragraphs STORAGE FOR DISPOSAL and DISPOSAL. If there are less than 1600 "No

PCB" labeled lighting ballasts dispose of them as normal demolition debris.

3.3.2 Lighting Lamps

Remove lighting tubes/lamps from the lighting fixture and carefully place (unbroken) into appropriate containers (original transport boxes or equivalent). In the event of a lighting tube/lamp breaking, sweep and place waste in double plastic taped bags and dispose of as universal waste as specified herein.

3.4 STORAGE FOR DISPOSAL

3.4.1 Storage Containers for PCBs

49 CFR 178. Store PCB in containers approved by DOT for PCB.

3.4.2 Storage Containers for lamps

Store mercury containing lamps in appropriate DOT containers. The boxes shall be stored and labeled for transport in accordance with 40 CFR 273.

3.4.3 Labeling of Waste Containers Label

with the following:

a. Date the item was placed in storage and the name of the cognizant activity/building.

b. "Caution Contains PCB," conforming to 40 CFR 761, CFR Subpart C. Affix labels to PCB waste containers.

c. Label mercury-containing lamp waste in accordance with 40 CFR 273. Affix labels to all lighting waste containers.

3.5 DISPOSAL

Dispose of off Government property in accordance with EPA, DOT, and local regulations at a permitted site.

3.5.1 Identification Number

Federal regulations 40 CFR 761, and 40 CFR 263 require that generators, transporters, commercial storers, and disposers of PCB waste posses U.S. EPA identification numbers. The contractor shall verify that the activity has a U.S. EPA generator identification number for use on the Uniform Hazardous Waste manifest. If not, the contractor shall advise the activity that it must file and obtain an I.D. number with EPA prior to commencement of removal work. For mercury containing lamp removal, Federal regulations 40 CFR 273 require that large quantity handlers of Universal waste (LQHUW) must provide notification of universal waste management to the appropriate EPA Region (or state director in authorized states), obtain an EPA identification number, and retain for three years records of off-site shipments of universal waste. The contractor shall verify that the activity has a U.S. EPA generator identification number for use on the Universal Waste manifest. If not, the contractor shall advise the activity that it must file and obtain an I.D. number with EPA prior to commencement of removal work.

3.5.2 Transporter Certification

Comply with disposal and transportation requirements outlined in 40 CFR 761 and 40 CFR 263. Before transporting the PCB waste, sign and date the manifest acknowledging acceptance of the PCB waste from the Government. Return a signed copy to the Government before leaving the job site. Ensure that the manifest accompanies the PCB waste at all times. Submit transporter certification of notification to EPA of their PCB waste activities (EPA Form 7710-53).

3.5.2.1 Certificate of Disposal and/or Recycling

40 CFR 761. Certificate for the PCBs and PCB items disposed shall include:

a. The identity of the disposal and or recycling facility, by name, address, and EPA identification number.

b. The identity of the PCB waste affected by the Certificate of Disposal including reference to the manifest number for the shipment.

c. A statement certifying the fact of disposal and or recycling of the identified PCB waste, including the date(s) of disposal, and identifying the disposal process used.

d. A certification as defined in 40 CFR 761.

END OF SECTION

SECTION 030130 - MAINTENANCE OF CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Bonding agents.
2. Patching mortar.
3. Epoxy crack-injection materials.
4. Repair underlayment.

1.2 ALLOWANCES

A. Allowances for maintenance of cast-in-place concrete are specified in Section 012100 "Allowances."

1.3 UNIT PRICES

A. Work of this Section is affected by unit prices specified in Section 012200 "Unit Prices."

1. Unit prices apply to authorized work covered by contingency allowances.
2. Unit prices apply to authorized additions to and deletions from the Work as authorized by Change Orders.

B. General: Unit prices include the cost of preparing existing construction to receive the Work indicated and costs of field quality control required for units of Work completed.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of product.

a. Include construction details, material descriptions, chemical composition, physical properties, test data, and mixing, preparation, project application types consisting of horizontal, vertical or overhead locations and application instructions.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For concrete-maintenance specialist and manufacturers.

C. Material Certificates: For each type of portland cement and aggregate supplied for mixing or adding to products at Project site.

D. Product Test Reports: For each manufactured bonding agent, cementitious patching mortar, joint filler, crack-injection adhesive, and polymer overlay, for tests performed by manufacturer and witnessed by a qualified testing agency.

1.6 QUALITY ASSURANCE

A. Concrete-Maintenance Specialist Qualifications: Engage an experienced concrete-maintenance firm that employs installers and supervisors who are trained and approved by manufacturer to apply packaged patching-mortar, crack-injection adhesive, corrosion-inhibiting treatments, and polymer overlays when performing the Work of this Section. Firm must have completed work similar in material, design, and extent to that indicated for this Project with a record of successful in-service performance. Experience in only installing or patching new concrete is insufficient experience for concrete-maintenance work.

1. Field Supervision: Concrete-maintenance specialist firm must maintain experienced full-time supervisors on Project site during times that concrete-maintenance work is in progress.

B. Quality-Control Program: Prepare a written plan for concrete maintenance to systematically demonstrate the ability of personnel to properly perform maintenance work, including each phase or process, protection of surrounding materials during operations, and control of debris and runoff during the Work. Describe in detail materials, methods, equipment, and sequence of operations to be used for each phase of the Work.

C. Ready-Mixed Concrete Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C94/C94M requirements for production facilities and equipment.

1.7 MOCKUPS

A. Build mockups to demonstrate aesthetic effects and to set quality standards for materials and execution.

1. Concrete Removal and Patching Mockup: Remove and repair approximately 2 SF area of deteriorated concrete wall.
2. Epoxy Crack Injection Mockup: Perform epoxy crack-injection material in two separate areas, each approximately 48 inches long.
3. Repair Underlayment Mockup: Apply an approximately 20 sq. ft. area of repair underlayment.
4. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
5. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Comply with manufacturer's written instructions for minimum and maximum temperature requirements and other conditions for storage.

B. Store cementitious materials off the ground, under cover, and in a dry location.

C. Store aggregates covered and in a dry location; maintain grading and other required characteristics and prevent contamination.

1.9 FIELD CONDITIONS

A. Environmental Limitations for Epoxies: Do not apply when air and substrate temperatures are outside limits permitted by manufacturer. During hot weather, cool epoxy components before mixing, store mixed products in shade, and cool unused mixed products to retard setting. Do not apply to wet substrates unless approved by manufacturer.

1. Use only Class A epoxies when substrate temperatures are below or are expected to go below 40 deg F within eight hours.
2. Use only Class A or B epoxies when substrate temperatures are below or are expected to go below 60 deg F within eight hours.
3. Use only Class C epoxies when substrate temperatures are above and are expected to stay above 60 deg F for eight hours.

B. Cold-Weather Requirements for Cementitious Materials:

1. Do not apply unless concrete surface and air temperatures are above 40 deg F and will remain so for at least 48 hours after completion of Work.
2. Comply with the following procedures:

    a. When air temperature is below 40 deg F, heat patching-material ingredients and existing concrete to produce temperatures between 40 and 90 deg F.
    b. When mean daily air temperature is between 25 and 40 deg F, cover completed Work with weather-resistant insulating blankets for 48 hours after repair or provide enclosure and heat to maintain temperatures above 32 deg F within the enclosure for 48 hours after repair.
    c. When mean daily air temperature is below 25 deg F, provide enclosure and heat to maintain temperatures above 32 deg F within the enclosure for 48 hours after repair.

C. Hot-Weather Requirements for Cementitious Materials: Protect repair work when temperature and humidity conditions produce excessive evaporation of water from patching materials. Provide artificial shade and wind breaks, and use cooled materials as required. Do not apply to substrates with temperatures of 90 deg F and above.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. For repair products, obtain each color, grade, finish, type, and variety of product from single source and from single manufacturer with resources to provide products of consistent quality in appearance and physical properties.

2.2 BONDING AGENTS

A. Epoxy-Modified, Cementitious Bonding and Anticorrosion Agent: Manufactured product that consists of water-insensitive epoxy adhesive, portland cement, and water-based solution of corrosion-inhibiting chemicals that forms a protective film on steel reinforcement.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ARDEX Americas
b. Dayton Superior Corporation
c. Euclid Chemical Company (The); a subsidiary of RPM International, Inc.
d. MAPEI Corporation
e. Sika Corporation

B. Mortar Scrub Coat: Mix consisting of 1 part portland cement and 1 part fine aggregate complying with ASTM C144, except 100 percent passing a No. 16 sieve.

2.3 PATCHING MORTAR

A. Patching Mortar Requirements:

1. Only use patching mortars that are recommended by manufacturer for each applicable horizontal, vertical, or overhead use orientation.

B. Job-Mixed Patching Mortar : 1 part portland cement and 2-1/2 parts fine aggregate complying with ASTM C144, except 100 percent passing a No. 16 sieve.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ChemMasters, Inc
b. MAPEI Corporation
c. Sika Corporation
d. Tnemec Company, Inc.

C. Cementitious Patching Mortar: Packaged, dry mix for repair of concrete.

1. Manufacturers: Subject to compliance with requirements, available manufacturers

offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ChemMasters, Inc
b. MAPEI Corporation
c. Sika Corporation

2. Compressive Strength: Not less than 4000 psi at 28 days when tested in accordance with ASTM C109/C109M.

D. Polymer-Modified, Cementitious Patching Mortar: Packaged, dry mix for repair of concrete and that contains a latex additive as either a dry powder or a separate liquid that is added during mixing.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ARDEX Americas
b. MAPEI Corporation
c. Sika Corporation

2. Compressive Strength: Not less than 4000 psi at 28 days when tested in accordance with ASTM C109/C109M.

2.4 EPOXY CRACK-INJECTION MATERIALS

A. Epoxy Crack-Injection Adhesive: ASTM C881/C881M, bonding system Type IV, free of VOCs.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ChemCo Systems, Inc.
b. MAPEI Corporation
c. Sika Corporation

2.5 REPAIR UNDERLAYMENT

A. Cement-based, polymer modified self-leveling repair material for floor and slab areas beneath floor coverings.

1. Basis-of-Design Product: Ardex Americas, Ardex V1200 self-leveling underlayment and Ardex P51 primer.

a. Maximum Installation Thickness: 2 inches.
b. Minimum Thickness: 1/8 inch.
c. Feather in edges with Ardex “Feather Finish.”

2.6 MISCELLANEOUS MATERIALS

A. Curing Materials: For ready-mixed concrete or packaged repair materials.

B. Formwork Materials: Form-facing materials must comply with ACI 301 requirements.

C. Water: Potable.

D. Cleaning Agent: Commercial muriatic acid solution.

2.7 MIXES

A. General: Mix products, in clean containers, in accordance with manufacturer's written instructions.

1. Do not add water, thinners, or additives unless recommended by manufacturer.
2. When practical, use manufacturer's premeasured packages to ensure that materials are mixed in proper proportions. When premeasured packages are not used, measure ingredients using graduated measuring containers; do not estimate quantities or use shovel or trowel as unit of measure.
3. Do not mix more materials than can be used within time limits recommended by manufacturer. Discard materials that have begun to set.

B. Mortar Scrub Coat: Mix dry ingredients with enough water to provide consistency of thick cream.

C. Dry-Pack Mortar: Mix required type(s) of patching-mortar dry ingredients with just enough liquid to form damp cohesive mixture that can be squeezed by hand into a ball but is not plastic.

D. Concrete Mixture Materials: Ready mixed.

1. ACI Publications: Comply with ACI 301 unless modified by requirements in the Contract Documents.
2. Portland Cement: ASTM C150/C150M, Type I, II, or III unless otherwise indicated.
3. Fly Ash: ASTM C618, Class C or F.
4. Slag Cement: ASTM C989/C989M, Grade 100 or 120.
5. Silica Fume: ASTM C1240 amorphous silica.
6. Aggregates: ASTM C330/C330M, nominal maximum aggregate size, gradation and types appropriate for the dimension of the repair area and project application.
7. Air-Entraining Admixture: ASTM C260/C260M.
8. Chemical Admixtures: Certified and as recommended by manufacturer for project applications to be compatible with other admixtures that do not contribute water-soluble chloride ions exceeding those permitted in hardened concrete. Do not use calcium chloride or admixtures containing calcium chloride.

E. Repair Underlayment:

1. Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/8 inch and that can be feathered at edges with feathering compound to match adjacent floor elevations.

2. Compressive Strength: Not less than 4100 psi at 28 days when tested in accordance with ASTM C109/C109M.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Notify Architect seven days in advance of dates when areas of deteriorated or delaminated concrete and deteriorated reinforcing bars will be located.

B. Locate areas of deteriorated or delaminated concrete using hammer or chain-drag sounding and mark boundaries. Mark areas for removal by simplifying and squaring off boundaries. At columns and walls, make boundaries level and plumb unless otherwise indicated.

C. Pachometer Testing: Locate at least three reinforcing bars using a pachometer, and drill test holes to determine depth of cover. Calibrate pachometer using depth of cover measurements, and verify depth of cover in removal areas using pachometer.

D. Perform surveys as the Work progresses to detect hazards resulting from concrete-maintenance work.

3.2 PREPARATION

A. Ensure that supervisory personnel are on-site and on duty when concrete-maintenance work begins and during its progress.

B. Protect persons, motor vehicles, surrounding surfaces of building being repaired, building site, plants, and surrounding buildings from harm resulting from concrete-maintenance work.

1. Comply with each product manufacturer's written instructions for protections and precautions. Protect against adverse effects of products and procedures on people and adjacent materials, components, and vegetation.
2. Use only proven protection methods appropriate to each area and surface being protected.
3. Provide temporary barricades, barriers, and directional signage to exclude public from areas where concrete-maintenance work is being performed.
4. Erect temporary protective covers over walkways and at points of pedestrian and vehicular entrance and exit that must remain in service during course of concrete-maintenance work.
5. Contain dust and debris generated by concrete-maintenance work and prevent it from reaching the public or adjacent surfaces.
6. Use water-mist sprinkling and other wet methods to control dust only with adequate, approved procedures and equipment that ensure that such water will not create a hazard or adversely affect other building areas or materials.
7. Protect floors and other surfaces along haul routes from damage, wear, and staining.
8. Protect adjacent surfaces and equipment by covering them with heavy polyethylene film and waterproof masking tape or a liquid-strippable masking agent. If practical, remove items, store, and reinstall after potentially damaging operations are complete.
9. Neutralize and collect alkaline and acid wastes for disposal off Owner's property.

10. Dispose of debris and runoff from operations by legal means and in a manner that prevents soil erosion, undermining of paving and foundations, damage to landscaping, and water penetration into building interiors.

C. Existing Drains: Prior to the start of concrete-maintenance work in an area, test drainage system to ensure that it is functioning properly. Notify Architect immediately of inadequate drainage or blockage. Do not begin concrete-maintenance work in an area until the drainage system is in working order.

1. Prevent solids, such as aggregate or mortar residue, from entering the drainage system. Clean out drains and drain lines that become sluggish or blocked by sand or other materials resulting from concrete-maintenance work.
2. Protect drains from pollutants. Block drains or filter out sediments, allowing only clean water to pass.

D. Preparation for Concrete Removal: Examine construction to be repaired to determine best methods to safely and effectively perform concrete-maintenance work. Examine adjacent work to determine what protective measures will be necessary. Make explorations, probes, and inquiries as necessary to determine condition of construction to be removed in the course of repair.

1. Verify that affected utilities have been disconnected and capped.
2. Inventory and record the condition of items to be removed for reinstallation or salvage.

E. Reinforcing-Bar Preparation: Remove loose and flaking rust from exposed reinforcing bars by needle scaling or wire brushing until only tightly adhered light rust remains.

1. Where section loss of reinforcing bar is more than 25 percent, or 20 percent in two or more adjacent bars, cut bars and remove and replace as indicated on Drawings.
2. Remove additional concrete as necessary to provide at least 3/4-inch clearance at existing and replacement bars.
3. Splice replacement bars to existing bars in accordance with ACI 318 by lapping, welding, or using mechanical couplings.

F. Surface Preparation for Overlays:

1. Remove delaminated material and deteriorated concrete surface material.
2. Roughen surface of concrete to produce a surface profile matching CSP 3 in accordance with ICRI 310.2.
3. Use sand blasting, shot blasting, scarifying, needle scaling, high-pressure water jetting, scabbling or milling.
4. Sweep and vacuum roughened surface to remove debris followed by low-pressure water cleaning.

3.3 REMOVAL OF CONCRETE

A. Do not overload structural elements with debris.

B. Saw-cut perimeter of areas indicated for removal to a depth of at least 3/4 inch. Make cuts perpendicular to concrete surfaces and no deeper than cover on reinforcement.

C. Remove deteriorated and delaminated concrete by breaking up and dislodging from reinforcement.

D. Remove additional concrete if necessary to provide a depth of removal of at least 3/4 inch over entire removal area.

E. Where half or more of the perimeter of reinforcing bar is exposed, bond between reinforcing bar and surrounding concrete is broken, or reinforcing bar is corroded, remove concrete from entire perimeter of bar and to provide at least 3/4-inch clearance around bar.

F. Test areas where concrete has been removed by tapping with hammer, and remove additional concrete until unsound and disbonded concrete is completely removed.

G. Provide surfaces with a fractured profile of at least 1/8 inch that are approximately perpendicular or parallel to original concrete surfaces. At columns and walls, make top and bottom surfaces level unless otherwise directed.

H. Thoroughly clean removal areas of loose concrete, dust, and debris.

3.4 APPLICATION OF BONDING AGENTS

A. Epoxy-Modified, Cementitious Bonding and Anticorrosion System: Apply to reinforcing bars and concrete by stiff brush or hopper spray in accordance with manufacturer's written instructions. Apply to reinforcing bars in two coats, allowing first coat to dry two to three hours before applying second coat. Allow to dry before placing patching mortar or concrete.

3.5 INSTALLATION OF PATCHING MORTAR

A. Place patching mortar as specified in this article unless otherwise recommended in writing by manufacturer or where dry-pack mortar is indicated.

1. Provide forms where necessary to confine patch to required shape.
2. Wet substrate and forms thoroughly and then remove standing water.

B. Pretreatment: Apply specified bonding agent.

C. General Placement: Place patching mortar by troweling toward edges of patch to force intimate contact with edge surfaces. For large patches, fill edges first and then work toward center, always troweling toward edges of patch. At fully exposed reinforcing bars, force patching mortar to fill space behind bars by compacting with trowel from sides of bars.

D. Vertical Patching: Place material in lifts of not more than 1 inch or less than 1/4 inch. Do not feather edge.

E. Overhead Patching: Place material in lifts of not more than 1 inch or less than 1/4 inch. Do not feather edge.

F. Consolidation: After each lift is placed, consolidate material and screed surface.

G. Multiple Lifts: Where multiple lifts are used, score surface of lifts to provide a rough surface for placing subsequent lifts. Allow each lift to reach final set before placing subsequent lifts.

H. Finishing: Allow surfaces of lifts that are to remain exposed to become firm and then finish to a surface matching adjacent concrete.

I. Curing: Wet-cure cementitious patching materials, including polymer-modified cementitious patching materials, for not less than seven days by water-fog spray or water-saturated absorptive cover.

3.6 INSTALLATION OF DRY-PACK MORTAR

A. Use dry-pack mortar for deep cavities and where indicated. Place as specified in this article unless otherwise recommended in writing by manufacturer.

1. Provide forms where necessary to confine patch to required shape.
2. Wet substrate and forms thoroughly and then remove standing water.

B. Pretreatment: Apply specified bonding agent.

C. Place dry-pack mortar into cavity by hand, and compact tightly into place. Do not place more material at a time than can be properly compacted. Continue placing and compacting until patch is approximately level with surrounding surface.

D. After cavity is filled and patch is compacted, trowel surface to match profile and finish of surrounding concrete. A thin coat of patching mortar may be troweled into the surface of patch to help obtain required finish.

E. Wet-cure patch for not less than seven days by water-fog spray or water-saturated absorptive cover.

3.7 CONCRETE PLACEMENT

A. Standard Placement: Place concrete by form-and-pump method unless otherwise indicated.

1. Use vibrators to consolidate concrete as it is placed.
2. At unformed surfaces, screed concrete to produce a surface that when finished with patching mortar will match required profile and surrounding concrete.

B. Wet-cure concrete for not less than seven days by leaving forms in place or keeping surfaces continuously wet by water-fog spray or water-saturated absorptive cover.

C. Fill placement cavities with dry-pack mortar and repair voids with patching mortar. Finish to match surrounding concrete.

3.8 APPLICATION OF EPOXY CRACK-INJECTION MATERIALS

A. Clean cracks with oil-free compressed air or low-pressure water to remove loose particles.

B. Clean areas to receive capping adhesive of oil, dirt, and other substances that would interfere with bond.

C. Place injection ports as recommended by epoxy manufacturer, spacing no farther apart than thickness of member being injected. Seal injection ports in place with capping adhesive.

D. Seal cracks at exposed surfaces with a ribbon of capping adhesive at least 1/4 inch thick by 1 inch wider than crack.

E. Inject cracks wider than 0.003 inch to a depth of 8 inches.

F. Inject epoxy adhesive, beginning at widest part of crack and working toward narrower parts. Inject adhesive into ports to refusal, capping adjacent ports when they extrude epoxy. Cap injected ports and inject through adjacent ports until crack is filled.

G. After epoxy adhesive has set, remove injection ports and grind surfaces smooth.

END OF SECTION

SECTION 031000 - CONCRETE FORMING AND ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Form-facing material for cast-in-place concrete.

1.3 DEFINITIONS

A. Form-Facing Material: Temporary structure or mold for the support of concrete while the concrete is setting and gaining sufficient strength to be self-supporting.

B. Formwork: The total system of support of freshly placed concrete, including the mold or sheathing that contacts the concrete, as well as supporting members, hardware, and necessary bracing.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each of the following:

1. Exposed surface form-facing material.
2. Concealed surface form-facing material.
3. Form ties.
4. Form-release agent.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For testing and inspection agency.

C. Field quality-control reports.

1.6 QUALITY ASSURANCE

A. Testing and Inspection Agency Qualifications: An independent agency, qualified in accordance with ASTM C1077 and ASTM E329 for testing indicated.

PART 2 - PRODUCTS

2.1 FORM-FACING MATERIALS

A. As-Cast Surface Form-Facing Material:

1. Provide continuous, true, and smooth concrete surfaces.
2. Furnish in largest practicable sizes to minimize number of joints.
3. Acceptable Materials: As required to comply with Surface Finish designations specified in Section 033000 "Cast-In-Place Concrete, and as follows:

a. Plywood, metal, or other approved panel materials.

B. Concealed Surface Form-Facing Material: Lumber, plywood, metal, plastic, or another approved material.

1. Provide lumber dressed on at least two edges and one side for tight fit.

2.2 RELATED MATERIALS

A. Chamfer Strips: Wood, metal, PVC, or rubber strips, 3/4 by 3/4 inch, minimum.

B. Form-Release Agent: Commercially formulated form-release agent that does not bond with, stain, or adversely affect concrete surfaces and does not impair subsequent treatments of concrete surfaces.

1. Formulate form-release agent with rust inhibitor for steel form-facing materials.
2. Form release agent for form liners shall be acceptable to form liner manufacturer.

C. Form Ties: Factory-fabricated, removable or snap-off, glass-fiber-reinforced plastic or metal form ties designed to resist lateral pressure of fresh concrete on forms and to prevent spalling of concrete on removal.

1. Furnish units that leave no corrodible metal closer than 1 inch to the plane of exposed concrete surface.
2. Furnish ties that, when removed, leave holes no larger than 1 inch in diameter in concrete surface.

PART 3 - EXECUTION

3.1 INSTALLATION OF FORMWORK

A. Comply with ACI 301.

B. Construct formwork, so concrete members are of size, shape, alignment, elevation, and position indicated, within tolerance limits of ACI 117 and to comply with the Surface Finish designations specified in Section 033000 "Cast-In-Place Concrete" for as-cast finishes.

C. Limit concrete surface irregularities as follows:

1. Surface Finish-2.0: ACI 117 Class B, 1/4 inch.

D. Construct forms tight enough to prevent loss of concrete mortar.

1. Minimize joints.
2. Exposed Concrete: Symmetrically align joints in forms.

E. Construct removable forms for easy removal without hammering or prying against concrete surfaces.

1. Provide crush or wrecking plates where stripping may damage cast-concrete surfaces.

F. Do not use rust-stained, steel, form-facing material.

G. Set edge forms, bulkheads, and intermediate screed strips for slabs to achieve required elevations and slopes in finished concrete surfaces.

1. Provide and secure units to support screed strips
2. Use strike-off templates or compacting-type screeds.

H. Chamfer exterior corners and edges as indicated.

I. At construction joints, overlap forms onto previously placed concrete not less than 12 inches.

J. Clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, and other debris just before placing concrete.

K. Retighten forms and bracing before placing concrete, as required, to prevent mortar leaks and maintain proper alignment.

L. Coat contact surfaces of forms with form-release agent, according to manufacturer's written instructions, before placing reinforcement.

3.2 INSTALLATION OF EMBEDDED ITEMS

A. Place and secure anchorage devices and other embedded items required for adjoining work that is attached to or supported by cast-in-place concrete.

1. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
2. Install anchor rods, accurately located, to elevations required and complying with tolerances in Section 7.5 of AISC 303.
3. Clean embedded items immediately prior to concrete placement.

3.3 REMOVING AND REUSING FORMS

A. Formwork may be removed after cumulatively curing at not less than 50 deg F for 24 hours after placing concrete. Concrete has to be hard enough to not be damaged by form-removal operations, and curing and protection operations need to be maintained.

B. Clean and repair surfaces of forms to be reused in the Work.

1. Split, frayed, delaminated, or otherwise damaged form-facing material are unacceptable for exposed surfaces.
2. Apply new form-release agent.

C. When forms are reused, clean surfaces, remove fins and laitance, and tighten to close joints.

1. Align and secure joints to avoid offsets.
2. Do not use patched forms for exposed concrete surfaces unless approved by Architect.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports.

B. Inspections:

1. Inspect formwork for shape, location, and dimensions of the concrete member being formed.

END OF SECTION

SECTION 032000 - CONCRETE REINFORCING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Steel reinforcement bars.
2. Welded-wire reinforcement.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For the following:

1. Each type of steel reinforcement.
2. Zinc repair material.
3. Bar supports.

C. Shop Drawings: Comply with ACI SP-066:

1. Include placing drawings that detail fabrication, bending, and placement.
2. Include bar sizes, lengths, materials, grades, bar schedules, stirrup spacing, bent bar diagrams, bar arrangement, location of splices, lengths of lap splices, and supports for concrete reinforcement.

D. Construction Joint Layout: Indicate proposed construction joints required to build the structure.

1. Locate construction joints as indicated.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Statements: For testing and inspection agency.

C. Field quality-control reports.

1.4 QUALITY ASSURANCE

A. Testing Agency Qualifications: An independent agency, qualified in accordance with ASTM C1077 and ASTM E329 for testing indicated.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Steel Reinforcement: Deliver, store, and handle steel reinforcement to prevent bending and damage and to avoid damaging coatings on steel reinforcement.

1. Store reinforcement to avoid contact with earth.

PART 2 - PRODUCTS

2.1 STEEL REINFORCEMENT

A. Reinforcing Bars: ASTM A615/A615M, Grade 60, deformed.

B. Galvanized Reinforcing Bars:

1. Steel Bars: ASTM A615/A615M, Grade 60, deformed bars.
2. Zinc Coating: ASTM A767/A767M, Class I zinc coated after fabrication and bending.

C. Plain-Steel Welded-Wire Reinforcement: ASTM A1064/A1064M, plain, fabricated from as drawn steel wire into flat sheets.

D. Galvanized-Steel Welded-Wire Reinforcement: ASTM A1064/A1064M, plain, fabricated from galvanized-steel wire into flat sheets.

2.2 REINFORCEMENT ACCESSORIES

A. Joint Dowel Bars: ASTM A615/A615M, Grade 60, plain-steel bars, cut true to length with ends square and free of burrs.

B. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars in place.

1. Manufacture bar supports from steel wire, plastic, or precast concrete in accordance with CRSI's "Manual of Standard Practice," of greater compressive strength than concrete and as follows:

a. For concrete surfaces exposed to view, where legs of wire bar supports contact forms, use CRSI Class 1 plastic-protected steel wire, all-plastic bar supports, or CRSI Class 2 stainless steel bar supports.
b. For zinc-coated reinforcement, use galvanized wire or dielectric-polymer-coated wire bar supports.

C. Steel Tie Wire: ASTM A1064/A1064M, annealed steel, not less than 0.0508 inch in diameter.

1. Finish: Plain.

D. Zinc Repair Material: ASTM A780/A780M.

2.3 FABRICATING REINFORCEMENT

A. Fabricate steel reinforcement according to CRSI's "Manual of Standard Practice."

PART 3 - EXECUTION

3.1 PREPARATION

A. Protection of In-Place Conditions:

1. Do not cut or puncture vapor retarder.
2. Repair damage and reseal vapor retarder before placing concrete.

B. Clean reinforcement of loose rust and mill scale, earth, ice, and other foreign materials that reduce bond to concrete.

3.2 INSTALLATION OF STEEL REINFORCEMENT

A. Comply with CRSI's "Manual of Standard Practice" for placing and supporting reinforcement.

B. Accurately position, support, and secure reinforcement against displacement.

1. Locate and support reinforcement with bar supports to maintain minimum concrete cover.
2. Do not tack weld crossing reinforcing bars.

C. Preserve clearance between bars of not less than 1 inch, not less than one bar diameter, or not less than 1-1/3 times size of large aggregate, whichever is greater.

D. Provide concrete coverage in accordance with ACI 318.

E. Set wire ties with ends directed into concrete, not toward exposed concrete surfaces.

F. Splices: Lap splices as indicated on Drawings.

1. Bars indicated to be continuous, and all vertical bars to be lapped not less than 36 bar diameters at splices, or 24 inches, whichever is greater.
2. Stagger splices in accordance with ACI 318.

G. Install welded-wire reinforcement in longest practicable lengths.

1. Support welded-wire reinforcement in accordance with CRSI “Manual of Standard Practice.”

    a. For reinforcement less than W4.0 or D4.0, continuous support spacing not to exceed 12 inches.

2. Lap edges and ends of adjoining sheets at least one wire spacing plus 2 inches for plain wire and 8 inches for deformed wire.
3. Offset laps of adjoining sheet to prevent continuous laps in either direction,
4. Lace overlaps with wire.

3.3 JOINTS

A. Construction Joints: Install so strength and appearance of concrete are not impaired, at locations indicated.

1. Place joints perpendicular to main reinforcement.
2. Continue reinforcement across construction joints unless otherwise indicated.
3. Do not continue reinforcement through sides of strip placements of slabs.

3.4 INSTALLATION TOLERANCES

A. Comply with ACI 117.

3.5 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports.

B. Inspections:

1. Steel-reinforcement placement.

END OF SECTION

SECTION 033000 - CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Concrete standards.
2. Concrete materials.
3. Admixtures.
4. Vapor retarders.
5. Liquid floor treatments.
6. Curing materials.
7. Accessories.
8. Repair materials.
9. Concrete mixture materials.
10. Concrete mixture class types.
11. Concrete mixing.

B. Related Requirements:

1. Section 031000 "Concrete Forming and Accessories" for form-facing materials.
2. Section 032000 "Concrete Reinforcing" for steel reinforcing bars and welded-wire reinforcement.

1.2 DEFINITIONS

A. Cementitious Materials: Portland cement alone or in combination with one or more of the following:

1. Fly ash, slag cement, and other pozzolans; materials subject to compliance with requirements.

B. Water/Cementitious Materials (w/cm) Ratio: The ratio by weight of mixing water to cementitious materials.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Portland cement.
2. Fly ash.

3. Slag cement.
4. Aggregates.
5. Admixtures:

    a. Include limitations of use. Admixtures that do not comply with reference ASTM International requirements must be submitted with test data for approval.

6. Vapor retarders.
7. Liquid floor treatments.
8. Curing materials.
9. Joint fillers.
10. Repair materials.
11. Flowable fill.

C. Design Mixtures: For each concrete mixture, include the following:

1. Mixture identification.
2. Compressive strength at 28 days or other age as specified.
3. Maximum w/cm ratio.
4. Slump.
5. Air content.
6. Nominal maximum aggregate size.
7. Intended placement method.
8. Submit adjustments to design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant changes.

D. Shop Drawings:

1. Construction Joint Layout: Indicate proposed construction joints required to construct the structure.

    a. Locate construction joints as indicated.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For the following:

1. Installer: Include copies of applicable ACI certificates.
2. Testing Agency: Include documentation indicating compliance with ASTM E329 or ASTM C1077 and copies of applicable ACI certificates for testing technicians or ACI Concrete Construction Special Inspector - MH, ASCC.

C. Material Certificates: For each of the following:

1. Cementitious materials.
2. Admixtures.

3. Curing compounds.
4. Bonding agents.
5. Adhesives.
6. Vapor retarders.
7. Joint-filler strips.
8. Repair materials.

D. Material Test Reports: For the following:

1. Portland cement.
2. Fly ash.
3. Slag cement.
4. Aggregates.
5. Admixtures.

E. Research Reports:

1. For concrete admixtures in accordance with ICC's Acceptance Criteria AC198.

F. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: A qualified Installer who employs Project personnel qualified as an ACI-certified Concrete Flatwork Associate and Concrete Flatwork Finisher and a supervisor who is a certified ACI Advanced Concrete Flatwork Finisher/Technician or an ACI Concrete Flatwork Finisher with experience installing and finishing concrete.

1. Post-Installed Concrete Anchors Installers: ACI-certified Adhesive Anchor Installer.

B. Ready-Mixed Concrete Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C94/C94M requirements for production facilities and equipment.

1. Manufacturer's production facilities and delivery vehicles certified in accordance with NRMCA's certification requirements or equivalent approval by a State DOT.

C. Laboratory Testing Agency Qualifications: A testing agency qualified in accordance with ASTM C1077 and ASTM E329 for testing that performs duties on behalf of the Architect/Engineer.

1. Personnel performing laboratory tests to be an ACI-certified Concrete Strength Testing Technician and Concrete Laboratory Testing Technician, Level 1. Testing agency laboratory supervisor tests to be an ACI-certified Concrete Laboratory Testing Technician, Level 2.

D. Field Quality-Control Testing Agency Qualifications: An independent agency, qualified in accordance with ASTM C1077 and ASTM E329 for testing indicated.

1. Personnel conducting field tests on plastic concrete properties are to be qualified as an ACI Concrete Field Testing Technician, Grade 1, in accordance with policies from ACI CPP 610.1 or an equivalent certification program.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Comply with ASTM C94/C94M and ACI 301.

1.7 FIELD CONDITIONS

A. Cold-Weather Placement: Comply with ACI 301 as follows:

1. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
2. When air temperature has fallen to, or is expected to fall below 40 deg F during the protection period, maintain delivered concrete mixture temperature within the temperature range required by ACI 301.
3. Do not use frozen materials or materials containing ice or snow.
4. Do not place concrete in contact with surfaces less than 35 deg F, other than reinforcing steel.

B. Hot-Weather Placement: Comply with ACI 301 and ACI 305.1, and as follows:

1. Maintain concrete temperature at time of discharge to not exceed 95 deg F.
2. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade uniformly moist without standing water, soft spots, or dry areas.

PART 2 - PRODUCTS

2.1 CONCRETE STANDARDS

A. ACI Publications: Comply with ACI 301 unless modified by requirements in the Contract Documents.

2.2 CONCRETE MATERIALS

A. Source Limitations:

1. Obtain all concrete mixtures from a single ready-mixed concrete manufacturer for entire Project.
2. Obtain each type of admixture from single source from single manufacturer.

B. Cementitious Materials:

1. Portland Cement: ASTM C150/C150M, Type I or Type II, gray.
2. Pozzolans: ASTM C618, Class C, F, or N.

3. Slag Cement: ASTM C989/C989M, Grade 100 or 120.

C. Normal-Weight Aggregates:

1. Coarse Aggregate: ASTM C33/C33M, Class 3S.
2. Maximum Coarse-Aggregate Size: 3/4 inch nominal.
3. Fine Aggregate: ASTM C33/C33M.

2.3 ADMIXTURES

A. Air-Entraining Admixture: ASTM C260/C260M.

B. Chemical Admixtures: Do not use calcium chloride or admixtures containing calcium chloride in steel-reinforced concrete.

1. Water-Reducing Admixture: ASTM C494/C494M, Type A.
2. Retarding Admixture: ASTM C494/C494M, Type B.
3. Water-Reducing and -Retarding Admixture: ASTM C494/C494M, Type D.
4. High-Range, Water-Reducing Admixture: ASTM C494/C494M, Type F.
5. High-Range, Water-Reducing and -Retarding Admixture: ASTM C494/C494M, Type G.
6. Admixtures with special properties, with documentation of claimed performance enhancement, ASTM C494/C494M, Type S.
7. Set-Accelerating Corrosion-Inhibiting Admixture: ASTM C1582/C1582M.

a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1) Euclid Chemical Company (The); a subsidiary of RPM International, Inc.
2) GCP Applied Technologies Inc.
3) MAPEI Corporation.
4) Master Builders Solutions, brand of MBCC Group, a Sika company.
5) Sika Corporation.

C. Mixing Water for Concrete Mixtures and Water Used to Make Ice: ASTM C1602/C1602M. Include documentation of compliance with limits for alkalis, sulfates, chlorides, or solids content of mixing water from Table 2 in ASTM C1602/C1602M.

2.4 VAPOR RETARDERS

A. Sheet Vapor Retarder, Class A: ASTM E1745, Class A. Include manufacturer's recommended thickness and adhesive or pressure-sensitive tape.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Barrier-Bac; Inteplast Group.

b. Foxfire Enterprises, Inc.
c. ISI Building Products.
d. Poly-America, L.P.
e. R&D Workshop.
f. Reef Industries, Inc.
g. Stego Industries, LLC.
h. Tex-Trude.
i. Viaflex.
j. W. R. Meadows, Inc.

2.5 LIQUID FLOOR TREATMENTS

A. Penetrating Liquid Floor Treatment: Clear, chemically reactive, waterborne solution of inorganic silicate or siliconate materials and proprietary components; odorless; that penetrates, hardens, and densifies concrete surfaces.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Bone Dry Products, Inc.
b. ChemMasters, Inc.
c. ChemTec International.
d. Concrete Sealers USA.
e. Curecrete Distribution Inc.
f. Dayton Superior Corporation.
g. Euclid Chemical Company (The); a subsidiary of RPM International, Inc.
h. HTS Chemical; Hi-Tech Systems.
i. Kaufman Products, Inc.
j. Laticrete International, Inc.
k. MAPEI Corporation.
l. Master Builders Solutions, brand of MBCC Group, a Sika company.
m. NewLook International, Inc.
n. Nox-Crete Products Group.
o. PROSOCO, Inc.
p. Penetron USA, Inc.
q. SINAK.
r. Solomon Colors Inc.
s. SpecChem, LLC.
t. Specialty Products Group.
u. US SPEC, Division of US MIX Company.
v. V-Seal Concrete Sealers & Specialty Coatings.
w. Vexcon Chemicals Inc.
x. W. R. Meadows, Inc.

2.6 CURING MATERIALS

A. Evaporation Retarder: Waterborne, monomolecular film forming, manufactured for application to fresh concrete.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Bon Tool Co.
b. Brickform; a division of Solomon Colors.
c. ChemMasters, Inc.
d. Dayton Superior Corporation.
e. Euclid Chemical Company (The); a subsidiary of RPM International, Inc.
f. Kaufman Products, Inc.
g. Lambert Corporation.
h. Laticrete International, Inc.
i. MAPEI Corporation.
j. Master Builders Solutions, brand of MBCC Group, a Sika company.
k. Metalcrete Industries.
l. Nox-Crete Products Group.
m. SINAK.
n. Sika Corporation.
o. SpecChem, LLC.
p. TK Products Construction Coatings, a Fenix Group SPC Company.
q. Vexcon Chemicals Inc.
r. W. R. Meadows, Inc.

B. Absorptive Cover: AASHTO M 182, Class 2, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. when dry.

C. Moisture-Retaining Cover: ASTM C171, polyethylene film burlap-polyethylene sheet.

D. Water: Potable water that does not cause staining of the surface.

E. Clear, Waterborne, Membrane-Forming, Dissipating Curing Compound: ASTM C309, Type 1, Class B.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Anti-Hydro International, Inc.
b. ChemMasters, Inc.
c. Dayton Superior Corporation.
d. Euclid Chemical Company (The); a subsidiary of RPM International, Inc.
e. Kaufman Products, Inc.
f. Lambert Corporation.
g. Laticrete International, Inc.
h. MAPEI Corporation.

i. Nox-Crete Products Group.
j. SpecChem, LLC.
k. TK Products Construction Coatings, a Fenix Group SPC Company.
l. Vexcon Chemicals Inc.
m. W. R. Meadows, Inc.

2.7 ACCESSORIES

A. Expansion- and Isolation-Joint-Filler Strips: ASTM D1751, asphalt-saturated cellulosic fiber or ASTM D1752, cork or self-expanding cork.

B. Bonding Agent: ASTM C1059/C1059M, Type II, nonredispersible, acrylic emulsion or styrene butadiene.

C. Epoxy Bonding Adhesive: ASTM C881/C881M, two-component epoxy resin, capable of humid curing and bonding to damp surfaces, of class suitable for application temperature and of grade and class to suit requirements, and as follows:

1. Types IV and V, load bearing, for bonding hardened or freshly mixed concrete to hardened concrete.

2.8 REPAIR MATERIALS

A. Repair Underlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/8 inch and that can be feathered at edges to match adjacent floor elevations.

1. Cement Binder: ASTM C150/C150M portland cement or hydraulic or blended hydraulic cement, as defined in ASTM C219.
2. Primer: Product of underlayment manufacturer recommended for substrate, conditions, and application.
3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch or coarse sand, as recommended by underlayment manufacturer.
4. Compressive Strength: Not less than 4100 psi at 28 days when tested in accordance with ASTM C109/C109M.

B. Repair Overlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/4 inch and that can be filled in over a scarified surface to match adjacent floor elevations.

1. Cement Binder: ASTM C150/C150M portland cement or hydraulic or blended hydraulic cement, as defined in ASTM C219.
2. Primer: Product of topping manufacturer recommended for substrate, conditions, and application.
3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch or coarse sand as recommended by topping manufacturer.
4. Compressive Strength: Not less than 5000 psi at 28 days when tested in accordance with ASTM C109/C109M.

2.9 CONCRETE MIXTURE MATERIALS

A. Prepare design mixtures for each type and strength of concrete, proportioned on the basis of laboratory trial mixture or field test data, or both, in accordance with ACI 301.

1. Use a qualified testing agency for preparing and reporting proposed mixture designs, based on laboratory trial mixtures.

B. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland or hydraulic cement in concrete assigned to Exposure Class F3 as follows:

1. Fly Ash or Other Pozzolans: 25 percent by mass.
2. Slag Cement: 25 percent by mass.
3. Total of Fly Ash and Slag Cement: 40 percent by mass, with fly ash not exceeding 25 percent by mass.

C. Admixtures: Use admixtures in accordance with manufacturer's written instructions.

1. Use corrosion-inhibiting admixture in concrete mixtures.

2.10 CONCRETE MIXTURE CLASS TYPES

A. Class B: Normal-weight concrete used for foundation walls/curbs exterior stoops and exterior concrete pads.

1. Exposure Class: ACI 318 Class F3.
2. Minimum Compressive Strength: 4000 psi at 28 days.
3. Maximum w/cm Ratio: 0.45.
4. Slump Limit: 4 inches, plus or minus 1 inch for concrete.
5. Air Content:

    a. Exposure Class F3: 6.0 percent, plus or minus 1.5 percent at point of delivery for concrete containing 3/4-inch nominal maximum aggregate size.

6. Limit water-soluble, chloride-ion content in hardened concrete to 0.15 percent by weight of cement.

B. Class C: Normal-weight concrete used for interior slabs-on-ground.

1. Exposure Class: ACI 318 Class F0.
2. Minimum Compressive Strength: 4000 psi at 28 days.
3. Maximum w/cm Ratio : 0.45.
4. Slump Limit: 4 inches, plus or minus 1 inch for concrete.
5. Air Content:

    a. Do not use an air-entraining admixture or allow total air content to exceed 3 percent for concrete used in trowel-finished floors.

6. Limit water-soluble, chloride-ion content in hardened concrete to 0.15 percent by weight of cement.

C. Class D: Leight-weight concrete used for interior suspended slabs.

1. Exposure Class: ACI 318 Class F0.
2. Minimum Compressive Strength: 4000 psi at 28 days.
3. Equilibrium Density: 115 lb/cu. ft., pus or minus 4 lb/cu. ft. in accordance with ASTM 567/C567M.
4. Slump Limit: 4 inches, plus or minus 1 inch for concrete.
5. Air Content:

a. Total air content must not exceed 3 percent for concrete used in trowel finished floors.

2.11 CONCRETE MIXING

A. Ready-Mixed Concrete: Measure, batch, mix, and deliver concrete in accordance with ASTM C94/C94M and furnish delivery ticket.

2.12 FLOWABLE FILL

A. Description: Low-strength-concrete, flowable-slurry mix.

1. Cement: ASTM C150, Type I, portland.
2. Density: 115-to 145-lb/cu. ft.
3. Aggregates:

a. ASTM C33, natural sand, fine.

4. Admixture: ASTM C618, fly-ash mineral.
5. Water: Comply with ASTM C94/C94M.
6. Strength: 100 to 200 psig at 28 days.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verification of Conditions:

1. Before placing concrete, verify that installation of concrete forms, accessories, reinforcement, and embedded items is complete and that required inspections have been performed.
2. Do not proceed until unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Provide reasonable auxiliary services to accommodate field testing and inspections, acceptable to testing agency, including the following:

1. Daily access to the Work.
2. Incidental labor and facilities necessary to facilitate tests and inspections.
3. Secure space for storage, initial curing, and field curing of test samples, including source of water and continuous electrical power at Project site during site curing period for test samples.
4. Security and protection for test samples and for testing and inspection equipment at Project site.

3.3 TOLERANCES

A. Comply with ACI 117.

3.4 INSTALLATION OF EMBEDDED ITEMS

A. Place and secure anchorage devices and other embedded items required for adjoining Work that is attached to or supported by cast-in-place concrete.

1. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.

3.5 INSTALLATION OF VAPOR RETARDERS

A. Sheet Vapor Retarders: Place, protect, and repair sheet vapor retarder in accordance with ASTM E1643 and manufacturer's written instructions.

1. Install vapor retarder with longest dimension parallel with direction of concrete pour.
2. Face laps away from exposed direction of concrete pour.
3. Lap joints 6 inches and seal with manufacturer's recommended tape.
4. Seal penetrations in accordance with vapor retarder manufacturer's instructions.
5. Protect vapor retarder during placement of reinforcement and concrete.

a. Repair damaged areas by patching with vapor retarder material, overlapping damages area by 6 inches on all sides and sealing to vapor retarder.

3.6 INSTALLATION OF CAST-IN-PLACE CONCRETE

A. Before placing concrete, verify that installation of formwork, reinforcement, embedded items, and vapor retarder is complete and that required inspections are completed.

1. Immediately prior to concrete placement, inspect vapor retarder for damage and deficient installation, and repair defective areas.

2. Provide continuous inspection of vapor retarder during concrete placement and make necessary repairs to damaged areas as Work progresses.

B. Notify Architect and testing and inspection agencies 24 hours prior to commencement of concrete placement.

C. Water addition in transit or at the Project site must be in accordance with ASTM C94/C94M and must not exceed the permitted amount indicated on the concrete delivery ticket.

D. Deposit concrete continuously in one layer or in horizontal layers of such thickness that no new concrete is placed on concrete that has hardened enough to cause seams or planes of weakness.

1. Deposit concrete to avoid segregation.
2. Deposit concrete in horizontal layers of depth not to exceed formwork design pressures and in a manner to avoid inclined construction joints.
3. Consolidate placed concrete with mechanical vibrating equipment in accordance with ACI 301.

a. Do not use vibrators to transport concrete inside forms.
b. Insert and withdraw vibrators vertically at uniformly spaced locations to rapidly penetrate placed layer and at least 6 inches into preceding layer.
c. Do not insert vibrators into lower layers of concrete that have begun to lose plasticity.
d. At each insertion, limit duration of vibration to time necessary to consolidate concrete, and complete embedment of reinforcement and other embedded items without causing mixture constituents to segregate.

E. Deposit and consolidate concrete for slabs in a continuous operation, within limits of construction joints, until placement of a panel or section is complete.

1. Do not place concrete slabs in a checkerboard sequence.
2. Consolidate concrete during placement operations, so concrete is thoroughly worked around reinforcement and other embedded items and into corners.
3. Maintain reinforcement in position on chairs during concrete placement.
4. Screed slab surfaces with a straightedge and strike off to correct elevations.
5. Level concrete, cut high areas, and fill low areas.
6. Slope surfaces uniformly to drains where required.
7. Begin initial floating using bull floats or darbies to form a uniform and open-textured surface plane, before excess bleedwater appears on the surface.
8. Do not further disturb slab surfaces before starting finishing operations.

3.7 INSTALLATION OF JOINTS

A. Construct joints true to line, with faces perpendicular to surface plane of concrete.

B. Construction Joints: Coordinate with floor slab pattern and concrete placement sequence.

1. Install so strength and appearance of concrete are not impaired, at locations indicated on Drawings.

2. Place joints perpendicular to main reinforcement.

    a. Continue reinforcement across construction joints unless otherwise indicated.

3. Use a bonding agent at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
4. Use epoxy-bonding adhesive at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.

C. Control Joints in Slabs-on-Ground: Form weakened-plane control joints, sectioning concrete into areas as indicated. Construct control joints for a depth equal to at least one-fourth of concrete thickness as follows:

1. Sawed Joints: Form control joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch wide joints into concrete when cutting action does not tear, abrade, or otherwise damage surface and before concrete develops random cracks.

D. Isolation Joints in Slabs-on-Ground: After removing formwork, install joint-filler strips at slab junctions with vertical surfaces, such as column pedestals, foundation walls, and other locations, as indicated.

1. Extend joint-filler strips full width and depth of joint, terminating flush with finished concrete surface unless otherwise indicated on Drawings.
2. Terminate full-width joint-filler strips not less than 1/2 inch or more than 1 inch below finished concrete surface, where joint sealants, specified in Section 079200 "Joint Sealants," are indicated.
3. Install joint-filler strips in lengths as long as practicable. Where more than one length is required, lace or clip sections together.

3.8 APPLICATION OF FINISHING FLOORS AND SLABS

A. Float Finish:

1. When bleedwater sheen has disappeared and concrete surface has stiffened sufficiently to permit operation of specific float apparatus, consolidate concrete surface with power-driven floats or by hand floating if area is small or inaccessible to power-driven floats.
2. Repeat float passes and restraightening until surface is left with a uniform, smooth, granular texture and complies with ACI 117 tolerances for conventional concrete.
3. Apply float finish to surfaces to receive trowel finish.

B. Trowel Finish:

1. After applying float finish, apply first troweling and consolidate concrete by hand or power-driven trowel.
2. Continue troweling passes and restraighten until surface is free of trowel marks and uniform in texture and appearance.
3. Grind smooth any surface defects that would telegraph through applied coatings or floor coverings.

4. Do not add water to concrete surface. Use of an approved finishing aid is acceptable.
5. Do not apply troweled finish to concrete, which has a total air content greater than 3 percent.
6. Apply a trowel finish to surfaces exposed to view.
7. Finish surfaces to the following tolerances, in accordance with ASTM E1155, for a randomly trafficked floor surface:

    a. Slabs on Ground:

        1) Specified overall values of flatness, F_F 25; and of levelness, F_L 20; with minimum local values of flatness, F_F 17; and of levelness, F_L 15.

C. Trowel and Fine-Broom Finish: First apply a trowel finish to exterior concrete pads surfaces. While concrete is still plastic, slightly scarify surface with a fine broom perpendicular to main traffic route.

1. Coordinate required final finish with Architect before application.
2. Comply with flatness and levelness tolerances for trowel-finished floor surfaces.

D. Broom Finish: Apply a broom finish to exterior concrete platforms, steps, ramps, and locations indicated on Drawings.

1. Immediately after float finishing, slightly roughen trafficked surface by brooming with a fiber-bristle broom perpendicular to main traffic route.
2. Coordinate required final finish with Architect before application.

3.9 APPLICATION OF FINISHING FORMED SURFACES

A. As-Cast Surface Finishes:

1. ACI 301 (ACI 301M) Surface Finish SF-1.0: As-cast concrete texture imparted by form-facing material.

    a. Patch voids larger than 1-1/2 inches wide or 1/2 inch deep.
    b. Remove projections larger than 1 inch.
    c. Tie holes do not require patching.
    d. Surface Tolerance: ACI 117, Class D.
    e. Apply to concrete surfaces for metal lap pan deck formed surfaces and those surfaces that are buried or covered with subsequent installed surfaces.

2. ACI 301 (ACI 301M) Surface Finish SF-2.0: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams.

    a. Patch voids larger than 3/4 inch wide or 1/2 inch deep.
    b. Remove projections larger than 1/4 inch.
    c. Patch tie holes.
    d. Surface Tolerance: ACI 117, Class B.
    e. Locations: Apply to concrete surfaces exposed to public view.

3. ACI 301 (ACI 301M) Surface Finish SF-3.0:

    a. Patch voids larger than 3/4 inch wide or 1/2 inch deep.
    b. Remove projections larger than 1/8 inch.
    c. Patch tie holes.
    d. Surface Tolerance: ACI 117 Class A.
    e. Locations: Apply to concrete surfaces exposed to public view.

3.10 APPLICATION OF CONCRETE CURING

A. Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.

1. Comply with ACI 301 for cold weather protection during curing.
2. Comply with ACI 301 and ACI 305.1 for hot-weather protection during curing.
3. Maintain moisture loss no more than 0.2 lb/sq. ft. x h, calculated in accordance with ACI 305R, before and during finishing operations.

B. Curing Formed Surfaces: Comply with ACI 308.1 as follows:

1. Cure formed concrete surfaces.
2. If forms remain during curing period, moist cure after loosening forms.
3. If removing forms before end of curing period, continue curing for remainder of curing period as follows:

    a. Continuous Fogging: Maintain standing water on concrete surface until final setting of concrete.
    b. Continuous Sprinkling: Maintain concrete surface continuously wet.
    c. Absorptive Cover: Pre-dampen absorptive material before application; apply additional water to absorptive material to maintain concrete surface continuously wet.
    d. Water-Retention Sheeting Materials: Cover exposed concrete surfaces with sheeting material, taping, or lapping seams.
    e. Membrane-Forming Curing Compound: Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's written instructions.

        1) Recoat areas subject to heavy rainfall within three hours after initial application.
        2) Maintain continuity of coating and repair damage during curing period.

C. Curing Unformed Surfaces: Comply with ACI 308.1 as follows:

1. Begin curing after finishing concrete.
2. Interior Concrete Floors:

    a. Floors to Receive Penetrating Liquid Floor Treatments: Contractor has option of the following:

1) Absorptive Cover: As soon as concrete has sufficient set to permit application without marring concrete surface, install prewetted absorptive cover over entire area of floor.

a) Lap edges and ends of absorptive cover not less than 12 inches.
b) Maintain absorptive cover water saturated, and in place, for duration of curing period, but not less than seven days.

2) Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches, and sealed by waterproof tape or adhesive.

a) Immediately repair any holes or tears during curing period, using cover material and waterproof tape.
b) Cure for not less than seven days.

3) Ponding or Continuous Sprinkling of Water: Maintain concrete surfaces continuously wet for not less than seven days, utilizing one, or a combination of, the following:

a) Water.
b) Continuous water-fog spray.

b. Floors To Receive Curing Compound:

1) Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's written instructions.
2) Recoat areas subjected to heavy rainfall within three hours after initial application.
3) Maintain continuity of coating, and repair damage during curing period.

3.11 APPLICATION OF LIQUID FLOOR TREATMENTS

A. Penetrating Liquid Floor Treatment: Prepare, apply, and finish penetrating liquid floor treatment in accordance with manufacturer's written instructions.

1. Remove curing compounds, sealers, oil, dirt, laitance, and other contaminants and complete surface repairs.
2. Do not apply to concrete that is less than 28 days' old.
3. Apply liquid until surface is saturated, scrubbing into surface until a gel forms; rewet; and repeat brooming or scrubbing.
4. Rinse with water; remove excess material until surface is dry.
5. Apply a second coat in a similar manner if surface has received a float finish or abrasive surface preparation.

B. Sealing Coat: Uniformly apply a continuous sealing coat of curing and sealing compound to hardened concrete by power spray or roller in accordance with manufacturer's written instructions.

3.12 INSTALLATION OF JOINT FILLING

A. Prepare, clean, and install joint filler in accordance with manufacturer's written instructions.

1. Defer joint filling until concrete has aged at least one month.

B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joints clean and dry.

C. Install semirigid joint filler full depth in saw-cut joints and at least 2 inches deep in formed joints.

D. Overfill joint, and trim joint filler flush with top of joint after hardening.

3.13 INSTALLATION OF CONCRETE SURFACE REPAIRS

A. Defective Concrete:

1. Repair and patch defective areas when approved by Architect.
2. Remove and replace concrete that cannot be repaired and patched to meet specification requirements.

B. Patching Mortar: Mix dry-pack patching mortar, consisting of 1 part portland cement to 2-1/2 parts fine aggregate passing a No. 16 sieve, using only enough water for handling and placing.

C. Repairing Formed Surfaces: Surface defects include color and texture irregularities, cracks in excess of 0.01 inch spalls, air bubbles exceeding surface finish limits, honeycombs, rock pockets, fins and other projections on the surface exceeding surface finish limits, and stains and other discolorations that cannot be removed by cleaning.

1. Immediately after form removal, cut out honeycombs, rock pockets, and voids more than 1/2 inch in any dimension to solid concrete.

a. Limit cut depth to 3/4 inch.
b. Make edges of cuts perpendicular to concrete surface.
c. Clean, dampen with water, and brush-coat holes and voids with bonding agent.
d. Fill and compact with patching mortar before bonding agent has dried.
e. Fill form-tie voids with patching mortar or cone plugs secured in place with bonding agent.

2. Repair defects on surfaces exposed to view by blending white portland cement and standard portland cement, so that, when dry, patching mortar matches surrounding color.

a. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching.
b. Compact mortar in place and match surrounding surface.

3. Repair defects on concealed formed surfaces that will affect concrete's durability and structural performance, as determined by Architect.

D. Repairing Unformed Surfaces:

1. Test unformed surfaces, such as floors and slabs, for finish, and verify surface tolerances specified for each surface.

    a. Correct low and high areas.
    b. Test surfaces sloped to drain for trueness of slope and smoothness; use a sloped template.

2. Repair finished surfaces containing surface defects, including spalls, popouts, honeycombs, rock pockets, crazing, and cracks in excess of 0.01 inch wide or that penetrate to reinforcement or completely through unreinforced sections regardless of width.
3. After concrete has cured at least 14 days, correct high areas by grinding.
4. Correct localized low areas during, or immediately after, completing surface-finishing operations by adding patching mortar.

    a. Finish repaired areas to blend into adjacent concrete.

5. Correct other low areas scheduled to receive floor coverings with a repair underlayment.

    a. Prepare, mix, and apply repair underlayment and primer in accordance with manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.
    b. Feather edges to match adjacent floor elevations.

6. Correct other low areas scheduled to remain exposed with repair topping.

    a. Cut out low areas to ensure a minimum repair topping depth of 1/4 inch to match adjacent floor elevations.
    b. Prepare, mix, and apply repair topping and primer in accordance with manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.

7. Repair defective areas, except random cracks and single holes 1 inch or less in diameter, by cutting out and replacing with fresh concrete.

    a. Remove defective areas with clean, square cuts, and expose steel reinforcement with at least a 3/4-inch clearance all around.
    b. Dampen concrete surfaces in contact with patching concrete and apply bonding agent.
    c. Mix patching concrete of same materials and mixture as original concrete, except without coarse aggregate.
    d. Place, compact, and finish to blend with adjacent finished concrete.
    e. Cure in same manner as adjacent concrete.

8. Repair random cracks and single holes 1 inch or less in diameter with patching mortar.

a. Groove top of cracks and cut out holes to sound concrete, and clean off dust, dirt, and loose particles.
b. Dampen cleaned concrete surfaces and apply bonding agent.
c. Place patching mortar before bonding agent has dried.
d. Compact patching mortar and finish to match adjacent concrete.
e. Keep patched area continuously moist for at least 72 hours.

E. Perform structural repairs of concrete, subject to Architect's approval, using epoxy adhesive and patching mortar.

F. Repair materials and installation not specified above may be used, subject to Architect's approval.

3.14 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports.

1. Testing agency to be responsible for providing curing facility for initial curing of strength test specimens on-site and verifying that test specimens are cured in accordance with standard curing requirements in ASTM C31/C31M.
2. Testing agency to immediately report to Architect, Contractor, and concrete manufacturer any failure of Work to comply with Contract Documents.
3. Testing agency to report results of tests and inspections, in writing, to Owner, Architect, Contractor, and concrete manufacturer within 48 hours of inspections and tests.

a. Test reports to include reporting requirements of ASTM C31/C31M, ASTM C39/C39M, and ACI 301, including the following as applicable to each test and inspection:

1) Project name.
2) Name of testing agency.
3) Names and certification numbers of field and laboratory technicians performing inspections and testing.
4) Name of concrete manufacturer.
5) Date and time of inspection, sampling, and field testing.
6) Date and time of concrete placement.
7) Location in Work of concrete represented by samples.
8) Date and time sample was obtained.
9) Truck and batch ticket numbers.
10) Design compressive strength at 28 days.
11) Concrete mixture designation, proportions, and materials.
12) Field test results of fresh concrete, including slump or slump flow, air content, temperature and density.
13) Information on storage and curing of samples at the Project site, including curing method and maximum and minimum temperatures during initial curing period.
14) Type of fracture and compressive break strengths at seven days and 28 days.

4. Provide a space and source of power or other resources for curing and access to test specimens by the testing agency.

B. Delivery Tickets: comply with ASTM C94/C94M.

C. Inspections:

1. Verification of use of required design mixture.
2. Concrete placement, including conveying and depositing.
3. Curing procedures and maintenance of curing temperature.
4. Batch Plant Inspections: On a random basis, as determined by Architect.

D. Concrete Tests: Testing of composite samples of fresh concrete obtained in accordance with ASTM C 172/C 172M to be performed in accordance with the following requirements:

1. Testing Frequency: Obtain one composite sample for each day's pour of each concrete mixture exceeding 5 cu. yd., but less than 25 cu. yd., plus one set for each additional 150 cu. yd. or fraction thereof.

    a. When frequency of testing provides fewer than five compressive-strength tests for each concrete mixture, testing is to be conducted from at least five randomly selected batches or from each batch if fewer than five are used.

2. Slump: ASTM C143/C143M:

    a. One test at point of delivery for each composite sample, but not less than one test for each day's pour of each concrete mixture.
    b. Perform additional tests as needed.

3. Air Content: ASTM C231/C231M pressure method, for normal-weight concrete.

    a. One test for each composite sample when strength test specimens are cast, but not less than one test for each day's pour of each concrete mixture.

4. Concrete Temperature: ASTM C1064/C1064M:

    a. One test hourly when air temperature is 40 deg F and below or 80 deg F and above, and one test for each composite sample when strength test specimens are cast.

5. Compression Test Specimens: ASTM C31/C31M:

    a. Cast and standard cure two sets of four 6 inches by 12-inches or 4-inch by 8-inch cylindrical specimens for each composite sample.

6. Compressive-Strength Tests: ASTM C39/C39M.

    a. Test one set of two standard cured specimens at seven days and one set of two specimens at 28 days.
    b. A compressive-strength test to be the average compressive strength from a set of two specimens obtained from same composite sample and tested at age indicated.

7. When strength of field-cured cylinders is less than 85 percent of companion laboratory-cured cylinders, Contractor to evaluate operations and provide corrective procedures for protecting and curing in-place concrete.
8. Strength of each concrete mixture will be satisfactory if every average of any three consecutive compressive-strength tests of standard cured cylinders equals or exceeds specified compressive strength, and no compressive-strength test value falls below specified compressive strength by more than 500 psi if specified compressive strength is 5000 psi, or no compressive strength test value is less than 10 percent of specified compressive strength if specified compressive strength is greater than 5000 psi.
9. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
10. Additional Tests:

    a. Testing and inspecting agency to make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect.
    b. Testing and inspecting agency may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C42/C42M or by other methods as directed by Architect.

        1) Acceptance criteria for concrete strength to be in accordance with ACI 301, Section 1.7.6.3.

11. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.
12. Correct deficiencies in the Work that test reports and inspections indicate do not comply with the Contract Documents.

E. Measure floor and slab flatness and levelness in accordance with ASTM E1155 within 24 hours of completion of floor finishing and promptly report test results to Architect.

3.15 PROTECTION

A. Protect concrete surfaces as follows:

1. Protect from petroleum stains.
2. Diaper hydraulic equipment used over concrete surfaces.
3. Prohibit vehicles from interior concrete slabs.
4. Prohibit use of pipe-cutting machinery over concrete surfaces.
5. Prohibit placement of steel items on concrete surfaces.
6. Prohibit use of acids or acidic detergents over concrete surfaces.
7. Protect liquid floor treatment from damage and wear during the remainder of construction period. Use protective methods and materials, including temporary covering, recommended in writing by liquid floor treatments installer.
8. Protect concrete surfaces scheduled to receive surface hardener using floor slab protective covering.

END OF SECTION

SECTION 040110 - MASONRY CLEANING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Cleaning of all exterior brick masonry.

1.2 DEFINITIONS

A. Very Low-Pressure Spray: Under 100 psi.

B. Low-Pressure Spray: 100 to 400 psi; 4 to 6 gpm.

C. Medium-Pressure Spray: 400 to 800 psi; 4 to 6 gpm.

D. High-Pressure Spray: 800 to 1200 psi; 4 to 6 gpm.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review methods and procedures related to cleaning masonry, including, but not limited to, the following:

    a. Scheduling a pre-mockup meeting.
    b. Mockup locations.
    c. Masonry types.
    d. Soiling types.
    e. Verify masonry-cleaning equipment and facilities needed to make progress and avoid delays.
    f. Materials, material application, and sequencing.
    g. Cleaning types and cleaning methods.
    h. Quality-control program.
    i. Review cleaning program.

1.4 SEQUENCING AND SCHEDULING

A. Work Sequence: Perform masonry-cleaning Work in the following sequence:

1. Remove plant growth and any other biological growth.
2. Inspect for open mortar joints. Where repairs are required, delay further cleaning Work until after repairs are completed, cured, and dried to prevent the intrusion of water and other cleaning materials into the wall.
3. Clean masonry surfaces.
4. Where water repellents are to be used on or near masonry, delay application of these chemicals until after cleaning.

B. As scaffolding is removed, patch anchor holes used to attach scaffolding. Patch holes in masonry units and joints in accordance with masonry repair Sections.

1.5 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include material descriptions and application instructions.
2. Include test data substantiating that products comply with requirements.

C. Material certificates signed by manufacturer and Contractor certifying that each material complies with requirements.

D. Each type of chemical cleaning material.

E. Qualification data for firms and specialists to demonstrate their capabilities and experience. Include list of five completed projects with project names and references.

F. Cleaning Program:

1. Describe cleaning protocol, materials, methods, and equipment to be used.
2. Indicate protection of surrounding materials on people, vehicles, buildings, and site items.
3. Describe control method of runoff during operations.
4. Create written report of final cleaning methods and process used.

1.6 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Preconstruction Test Reports: For cleaning materials and methods.

C. Cleaning program.

1.7 QUALITY ASSURANCE

A. Source of Materials: Obtain materials for masonry cleaning from a single source for each type of substrate required to ensure quality of cleaning.

B. Masonry-Cleaning Specialist Firms: A firm that provides masonry cleaning, including masonry cleaners that have been used for similar applications with successful results, and is manufacturer authorized for consultation and Project-site inspection, preconstruction product testing, and on-site assistance.

C. Chemical-Cleaner Manufacturer Qualifications: A firm regularly engaged in producing masonry cleaners that have been used for similar applications with successful results, who employs factory-authorized service representatives who are available for consultation and Project-site inspection, preconstruction product testing, and on-site assistance.

D. Quality-Control Program: Prepare a written quality-control program for this Project to systematically demonstrate the ability of personnel to properly follow methods and use materials and tools without damaging masonry. Include provisions for supervising performance and preventing damage.

E. Cleaning Program: Prepare a written cleaning program that describes cleaning process in detail, including materials, methods, and equipment to be used; protection of surrounding materials; and control of runoff during operations. Include provisions for supervising worker performance and preventing damage.

1. If materials and methods other than those indicated are proposed for any phase of cleaning Work, add a written description of such materials and methods, including evidence of successful use on comparable projects and demonstrations to show their effectiveness for this Project.

1.8 MOCKUPS

A. Prepare mockups of cleaning on existing surfaces to evaluate and establish cleaning materials and processes. Consult cleaning manufacturer for project applications.

1. Masonry Substrate: Clay masonry.
2. Cleaning: Clean an existing area approximately 25 sq. ft. for each type of masonry and surface condition.

a. Test cleaners and methods on samples of adjacent materials for possible adverse reactions. Do not test cleaners and methods known to have deleterious effect.
b. Consult with chemical cleaning product manufacturer to verify what products require pre-wetting of substrate before cleaner application.
c. Dilute chemical cleaners with water to produce solutions not exceeding concentration recommended in writing by chemical-cleaner manufacturer.
d. Allow a waiting period of not less than seven days after completion of sample cleaning to permit a study of sample panels for negative reactions.

3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.

1.9 DELIVERY, STORAGE, AND HANDLING

A. Deliver masonry materials to Project in undamaged condition.

B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

1.10 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit masonry-cleaning Work to be performed in accordance with product manufacturers' written instructions and specified requirements.

B. Clean masonry surfaces only when air temperature is 40 deg F and above and is predicted to remain so for at least seven days after completion of cleaning.

1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F and above and will remain so until masonry has thawed and dried out, but not less than seven days after completion of cleaning.
2. Hot-Weather Requirements: Protect unit masonry Work when temperature and humidity conditions produce excessive evaporation of water from masonry. Provide artificial shade and wind breaks and use cooled materials as required.

C. Refer to chemical cleaner manufacturer's recommendations for application techniques when hot-weather conditions exist.

PART 2 - PRODUCTS

2.1 CLEANING MATERIALS

A. Water: Potable.

B. Hot Water: Water heated to a temperature of 140 to 160 deg F.

C. Detergent Solution, Job Mixed: Solution prepared by mixing 2 cups of tetrasodium pyrophosphate (TSPP), 1/2 cup of laundry detergent, and 20 quarts of hot water for every 5 gal. of solution required.

D. Mold, Mildew, and Algae Remover, Job Mixed: Solution prepared by mixing 2 cups of tetrasodium pyrophosphate (TSPP), 5 quarts of 5 percent sodium hypochlorite (bleach), and 15 quarts of hot water for every 5 gal. of solution required.

2.2 ACCESSORY MATERIALS

A. Retain materials of use based on the approval of a mockup.

1. Provide materials with previous effectiveness in performing the Work involved.

a. Include materials with minimal possibility of damaging exposed surfaces.
b. Materials with consistency of each application.
c. Materials that provide uniformity of the resulting overall appearance.

B. Do not use products or tools that could do the following:

1. Remove, alter, or harm the present condition or future preservation of existing surfaces, including surrounding surfaces.

2. Leave residue on surfaces.

C. Equipment: Provide equipment for controlled spray application of water and chemical cleaners.

1. For chemical cleaner spray applications, provide a low-pressure tank or chemical pump suitable for the chemical cleaner indicated, equipped with spray tip for cleaning method applications.

D. Wood scrappers.

E. Trowels.

F. Provide additional accessories applicable to project conditions, including tapes, sheets, etc., to suit Project.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrate conditions with specialist present, for compliance with approved mockup requirements for cleaning type, methods, products, and other conditions affecting performance.

3.2 PREPARATION

A. General: Comply with each manufacturer's written instructions for protecting people, motor vehicles, surrounding buildings, masonry areas not to be cleaned, nonmasonry surfaces, landscaping, equipment, and other surfaces that could be injured or harmed by such Work.

1. Provide temporary protective covers over pedestrian walkway areas and at points of entrance and exit for people, motor vehicles, and equipment that must remain during duration of cleaning procedures.
2. Temporarily protect all open joints to prevent intrusion of washing waters into the wall structure or building interior.
3. Remove all extraneous items no longer in use on face of surface unless indicated to remain. Where not indicated, obtain approval with Architect.
4. Apply masking agents in accordance with manufacturer's written instructions. Do not apply liquid strippable masking agent to painted or porous surfaces. When no longer needed, promptly remove masking to prevent adhesive staining.
5. Neutralize alkaline and acid wastes before disposal where applicable.

B. Provide disposal of runoff from operations by legal means and in a manner that prevents soil erosion, undermining of paving and foundations, damage to landscaping, and water penetration into building interiors.

3.3 APPLICATION OF PRELIMINARY CLEANING MATERIALS

A. Preliminary Cleaning: Before beginning general cleaning, remove extraneous substances that are resistant to planned cleaning methods.

1. Carefully remove heavy accumulations of rigid materials from masonry surface with sharp chisel. Do not scratch or chip masonry surface.
2. Removing Biological Growth: Completely remove visible biological, moss, and shrub growth from masonry surfaces. Carefully remove biological growths, creepers, and vegetation by cutting at roots and allowing remaining growth to dry as long as possible before removal. Remove loose soil and biological debris from open joints to whatever depth they occur.
3. Mold, Mildew, and Algae Removal:

    a. Wet surface with water applied by low-pressure spray.
    b. Apply mold, mildew, and algae remover by brush or low-pressure spray.
    c. Scrub surface with medium-soft brushes until mold, mildew, and algae are thoroughly dislodged and can be removed by rinsing. Use small brushes for mortar joints and crevices. Dip brush in mold, mildew, and algae remover often to ensure that adequate fresh cleaner is used and that surface remains wet.
    d. Rinse with cold water applied by low-pressure spray to remove mold, mildew, and algae remover and soil.

B. Repeat cleaning procedure above where required to produce cleaning effect established by mockup.

3.4 GENERAL APPLICATION OF CLEANING METHODS

A. Chemical Cleaning: Do not apply during winds of enough force to spread them to unprotected surfaces.

B. Cleaning Appearance Standard: Cleaned surfaces are to have a uniform appearance as viewed from 20 ft. away by Architect.

C. Proceed with cleaning in an orderly manner; work from top to bottom of each scaffold width and from one end of each elevation to the other. Ensure that dirty residues and rinse water do not wash over dry, cleaned surfaces.

D. Use only those cleaning methods indicated for each masonry material and location.

1. Spray Equipment: Use spray equipment that provides controlled application at volume and pressure indicated, measured at nozzle. Adjust pressure and volume to ensure that cleaning methods do not damage surfaces, including joints.

    a. Equip units with pressure gages.
    b. For chemical-cleaner spray application, use low-pressure tank or chemical pump suitable for chemical cleaner indicated, equipped with nozzle having a cone-shaped spray.
    c. For water-spray application, use fan-shaped spray that disperses water at an angle of 25 to 50 degrees.
    d. For heated water-spray application, use equipment capable of maintaining temperature between 140 and 160 deg F at flow rates indicated.

E. Perform each cleaning method indicated in a manner that results in uniform coverage of all surfaces, including corners, moldings, and interstices, and that produces an even effect without streaking or damaging masonry surfaces. Keep wall wet below area being cleaned to prevent streaking from runoff.

F. Perform additional general cleaning, stain removal, and spot cleaning of small areas that are noticeably different when viewed in accordance with "Cleaning Appearance Standard" Paragraph, so that cleaned surfaces blend smoothly into surrounding areas.

G. Remove minor stains (cuprous, ferrous, etc.) if any.

H. Repeat cleaning procedure above where required to produce cleaning effect established by mockup.

3.5 CHEMICAL-CLEANING TYPE

A. Chemical-Cleaner Application Methods: Apply chemical cleaners to masonry surfaces in accordance with chemical-cleaner manufacturer's written instructions; use brush or spray application. Do not spray apply at pressures exceeding 50 psi. Do not allow chemicals to remain on surface for periods longer than those indicated or recommended in writing by manufacturer.

1. Consult with cleaning product manufacturer to verify what products require pre-wetting of substrate before cleaner application.

B. Dilute chemical cleaners with water when required to produce solutions not exceeding concentration recommended in writing by chemical-cleaner manufacturer.

C. Rinse off chemical residue and soil by working upward from bottom to top of each treated area at each stage or scaffold setting. Periodically during each rinse, test pH of rinse water running off of cleaned area to determine that chemical cleaner is completely removed.

1. Apply neutralizing agent and repeat rinse if necessary to produce tested pH of between 6.7 and 7.5.

D. After cleaning is complete, remove protection no longer required. Remove tape and adhesive marks.

E. Detergent Cleaning:

1. Wet surface with cold water applied by low-pressure spray.
2. Scrub surface with detergent solution using medium-soft brushes until soil is thoroughly dislodged and can be removed by rinsing. Use small brushes to remove soil from mortar joints and crevices. Dip brush in solution often to ensure that adequate fresh detergent is used and that surface remains wet.
3. Rinse with cold water applied by low-pressure spray to remove detergent solution and soil.
4. Repeat cleaning procedure above where required to produce cleaning effect established by mockup. D not repeat more than once.

3.6 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage chemical-cleaner manufacturer's factory-authorized service representatives for consultation and Project-site inspection, to perform preconstruction product testing, and provide on-site assistance when requested by Architect.

3.7 FINAL CLEANING

A. Clean adjacent nonmasonry surfaces of spillage and debris. Use detergent and soft brushes or cloths.

B. Remove debris from gutters and downspouts. Rinse off roof and flush gutters and downspouts.

C. Remove masking materials, leaving no residues that could trap dirt.

D. Clean landscaping areas of debris.

3.8 PROTECTION

A. Provide final protection and maintain conditions in a manner acceptable to Architect, which ensures cleaning Work without being soiled at time of substantial completion.

END OF SECTION

SECTION 040120.63 - BRICK MASONRY REPAIR

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Masonry materials.
2. Mortar materials.
3. Manufactured repair materials.

B. Related Requirements:

1. Section 013516 "Alteration Project Procedures" for general remodeling, renovation, repair, and maintenance requirements.
2. Section 040110 "Masonry Cleaning" for cleaning and paint removal existing masonry.
3. Section 040120.64 "Brick Masonry Repointing" for repointing existing brickwork.
4. Section 079200 "Joint Sealants" for joint sealants, joint fillers, and sealant-joint preparation for repaired masonry.

1.2 ALLOWANCES

A. Allowances for brick masonry repair are specified in Section 012100 "Allowances."

B. Abandoned anchor removal is part of Brick Repair Allowance No. 2.

C. Brick removal and replacement is part of brick removal and replacement allowance.

D. Removal and patching of removed brick anchors is part of Brick Repair Allowance No. 2

1.3 UNIT PRICES

A. Work of this Section is affected by unit prices specified in Section 012200 "Unit Prices."

1. Unit prices apply to authorized work covered by Contingency Allowance #2 Brick Repair.

1.4 DEFINITIONS

A. Existing to Remain: Existing items of construction that are not to be removed.

B. Low-Pressure Spray: 100 to 400 psi; 4 to 6 gpm.

C. Remove: Detach items from existing construction and legally dispose of off-site unless indicated to be removed and salvaged or removed and reinstalled.

D. Remove and Salvage: Detach items from existing construction, in a manner to prevent damage, and deliver to Owner or storage as indicated.

E. Remove and Reinstall: Detach items from existing construction, in a manner to prevent damage; prepare for reuse; and reinstall where indicated.

F. Rebuilding (Setting) Mortar: Mortar used to set and anchor masonry in a structure, distinct from pointing mortar installed after masonry is set in place.

G. Saturation Coefficient: Ratio of the weight of water absorbed during immersion in cold water to weight absorbed during immersion in boiling water; used as an indication of resistance of bricks to freezing and thawing.

1.5 SEQUENCING AND SCHEDULING

A. Work Sequence: Perform brick masonry repair work in the following sequence, which includes work specified in this and other Sections:

1. Remove plant growth.
2. Clean masonry.
3. Rake out mortar from joints surrounding masonry to be replaced and from joints adjacent to masonry repairs along joints.
4. Repair masonry, including replacing existing masonry with new masonry materials.
5. Rake out mortar from joints to be repointed.
6. Point mortar joints.
7. After repairs and repointing have been completed and cured, perform a final cleaning to remove residues from this work.

B. As scaffolding is removed, patch anchor holes used to attach scaffolding. Patch holes in bricks in accordance with "Brick Masonry Patching" Article. Patch holes in mortar joints according to Section 040120.64 "Brick Masonry Repointing."

1.6 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Samples for Initial Selection: For the following:

1. Mortar: Submit sets of mortar that will be left exposed in the form of sample mortar strips, 6 inches long by 1/2 inch wide, set in aluminum or plastic channels.

    a. Have each set contain a close color range of at least three Samples of different mixes of sands and cements that produce a mortar matching existing, cleaned mortar when cured and dry.
    b. Submit with precise measurements on ingredients, proportions, gradations, and source of sands from which each Sample was made.

2. Patching Compound: Submit sets of patching compound Samples in the form of plugs (patches in drilled holes) in sample units of masonry representative of the range of masonry colors on the building.

    a. Have each set contain a close color range of at least three Samples of different mixes of patching compound that matches the variations in existing masonry when cured and dry.

D. Samples for Verification: For the following:

1. Each type of brick unit to be used for replacing existing units. Include sets of Samples to show the full range of shape, color, and texture to be expected. For each brick type, provide straps or panels containing at least four bricks. Include multiple straps for brick with a wide range.
2. Accessories: Each type of accessory and miscellaneous support.

1.7 MOCKUPS

A. Prepare mockups of brick masonry repair to demonstrate aesthetic effects and to set quality standards for materials and execution, and for fabrication and installation.

1. Masonry Repair: Prepare sample areas for each type of masonry repair work performed. Construct sample areas in locations in existing walls where directed by Architect unless otherwise indicated. Demonstrate quality of materials, workmanship, and blending with existing work. Include the following as a minimum:

    a. Replacement: Eight brick units replaced.
    b. Patching: Three small holes at least 1 inch in diameter for each type of brick indicated to be patched.

2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Deliver bricks to Project site strapped together in suitable packs or pallets or in heavy-duty cartons and protected against impact and chipping.

B. Deliver packaged materials to Project site in manufacturer's original and unopened containers, labeled with manufacturer's name and type of products.

C. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

D. Store hydrated lime in manufacturer's original and unopened containers. Discard lime if containers have been damaged or have been opened for more than two days.

E. Store sand where grading and other required characteristics can be maintained and contamination avoided.

F. Handle bricks to prevent overstressing, chipping, defacement, and other damage.

1.9 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit brick masonry repair work to be performed in accordance with product manufacturers' written instructions and specified requirements.

B. Temperature Limits: Repair brick masonry only when air temperature is between 40 and 90 deg F and is predicted to remain so for at least seven days after completion of the Work unless otherwise indicated.

C. Cold-Weather Requirements: Comply with the following procedures for masonry repair unless otherwise indicated:

1. When air temperature is below 40 deg F, heat mortar ingredients, masonry repair materials, and existing masonry walls to produce temperatures between 40 and 120 deg F.
2. When mean daily air temperature is below 40 deg F, provide enclosure and heat to maintain temperatures above 32 deg F within the enclosure for seven days after repair.

D. Hot-Weather Requirements: Protect masonry repairs when temperature and humidity conditions produce excessive evaporation of water from mortar and repair materials. Provide artificial shade and wind breaks, and use cooled materials as required to minimize evaporation. Do not apply mortar to substrates with temperatures of 90 deg F and above unless otherwise indicated.

E. For manufactured repair materials, perform work within the environmental limits set by each manufacturer.

PART 2 - PRODUCTS

2.1 MASONRY MATERIALS

A. Masonry Materials: Face brick, required to complete brick masonry repair work.

1. Brick Matching Existing: Units with colors, color variation within units, surface texture, size, and shape that match existing brickwork and with physical properties.

a. For existing brickwork that exhibits a range of colors or color variation within units, provide brick that proportionally matches that range and variation rather than brick that matches an individual color within that range.

B. Building Brick: ASTM C62, of same vertical dimension as face brick, for masonry work concealed from view.

1. Grade SW where in contact with earth.

2.2 MORTAR MATERIALS

A. Portland Cement: ASTM C150/C150M, Type I or Type II, except Type III may be used for cold-weather construction; white or gray, or both where required for color matching of mortar.

B. Hydrated Lime: ASTM C207, Type S.

C. Masonry Cement: ASTM C91/C91M.

D. Mortar Cement: ASTM C1329/C1329M.

E. Mortar Sand: ASTM C144.

1. Exposed Mortar: Match size, texture, and gradation of existing mortar sand as closely as possible. Blend several sands if necessary to achieve suitable match.

F. Water: Potable.

2.3 MANUFACTURED REPAIR MATERIALS

A. Brick Patching Compound: Factory-mixed cementitious product that is custom manufactured for patching brick masonry.

1. Use formulation that is vapor and water permeable (equal to or more than the brick), exhibits low shrinkage, has lower modulus of elasticity than bricks being repaired, and develops high bond strength to all types of masonry.
2. Use formulation having working qualities and retardation control to permit forming and sculpturing where necessary.
3. Formulate patching compound in colors and textures to match each brick being patched. Provide no fewer than three colors to enable matching of the color, texture, and variation of each unit.

2.4 ACCESSORY MATERIALS

A. Setting Buttons and Shims: Resilient plastic, nonstaining to masonry, sized to suit joint thicknesses and bed depths of bricks, less the required depth of pointing materials unless removed before pointing.

B. Masking Tape: Nonstaining, nonabsorbent material; compatible with mortar, joint primers, sealants, and surfaces adjacent to joints; and that easily comes off entirely, including adhesive.

C. Other Products: Select materials and methods of use based on the following, subject to approval of a mockup:

1. Previous effectiveness in performing the work involved.
2. Minimal possibility of damaging exposed surfaces.
3. Consistency of each application.
4. Uniformity of the resulting overall appearance.
5. Do not use products or tools that could leave residue on surfaces.

2.5 MORTAR MIXES

A. Measurement and Mixing: Measure cementitious materials and sand in a dry condition by volume or equivalent weight. Do not measure by shovel; use known measure. Mix materials in a clean, mechanical batch mixer.

B. Do not use admixtures in mortar unless otherwise indicated.

C. Mixes: Mix mortar materials in the following proportions:

1. Rebuilding (Setting) Mortar by Property: ASTM C270, Property Specification, Type N unless otherwise indicated; with cementitious material limited to portland cement and lime, masonry cement, or mortar cement.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrate conditions for compliance with approved mockup requirements for brick units, repair methods, products, and other conditions affecting performance of the Work.

3.2 PREPARATION

A. General: Comply with each manufacturer's written instructions for protecting people, motor vehicles, surrounding buildings, masonry areas not to be cleaned, nonmasonry surfaces, landscaping, equipment, and other surfaces that could be injured or harmed by such Work.

1. Provide temporary protective covers over pedestrian walkway areas and at points of entrance and exit for people, motor vehicles, and equipment that must remain during duration of repairing procedures.
2. Cover adjacent surfaces with materials that are proven to resist paint removers and chemical cleaners used unless products being used will not damage adjacent surfaces. Use protective materials that are waterproof and UV resistant.
3. Temporarily protect all open joints to prevent intrusion of washing waters into the wall structure or building interior.
4. Remove all extraneous items no longer in use on face of surface unless indicated to remain. Where not indicated, obtain approval with Architect.

3.3 PROTECTION

A. Prevent mortar from staining face of surrounding masonry and other surfaces.

1. Cover sills, ledges, and other projecting items to protect them from mortar droppings.
2. Keep wall area wet below rebuilding and repair work to discourage mortar from adhering.
3. Immediately remove mortar splatters in contact with exposed masonry and other surfaces.

3.4 MASONRY REPAIR, GENERAL

A. Appearance Standard: Repaired surfaces are to have a uniform appearance as viewed from 20 ft. away by Architect.

3.5 ABANDONED ANCHOR REMOVAL

A. Remove abandoned anchors, brackets, wood nailers, and other extraneous items no longer in use unless indicated to remain.

1. Remove items carefully to avoid spalling or cracking masonry.
2. Notify Architect before proceeding if an item cannot be removed without damaging surrounding masonry. Do the following where directed:
3. Patch hole where each item was removed unless directed to remove and replace bricks.

3.6 BRICK REMOVAL AND REPLACEMENT

A. At locations indicated, remove bricks that are damaged, spalled, or deteriorated. Carefully remove entire units from joint to joint, without damaging surrounding masonry, in a manner that permits replacement with full-size units.

B. Support and protect remaining masonry that surrounds removal area.

C. Maintain flashing, reinforcement, lintels, and adjoining construction in an undamaged condition.

D. Notify Architect of unforeseen detrimental conditions, including voids, cracks, bulges, and loose units in existing masonry backup, rotted wood, rusted metal, and other deteriorated items.

E. Remove in an undamaged condition.

1. Remove mortar, loose particles, and soil from brick by cleaning with hand chisels, brushes, and water.
2. Remove sealants by cutting close to brick with utility knife and cleaning with solvents.

F. Clean masonry surrounding removal areas by removing mortar, dust, and loose particles in preparation for brick replacement.

G. Replace removed damaged brick with new brick matching existing brick.

H. Install replacement brick into bonding and coursing pattern of existing brick. If cutting is required, use a motor-driven saw designed to cut masonry with clean, sharp, unchipped edges.

1. Maintain joint width for replacement units to match existing joints.
2. Use setting buttons or shims to set units accurately spaced with uniform joints.

I. Lay replacement brick with rebuilding (setting) mortar and with completely filled bed, head, and collar joints. Butter ends with enough mortar to fill head joints and shove into place. Wet both replacement and surrounding bricks that have ASTM C67/C67M initial rates of absorption (suction) of more than 30 g/30 sq. in. per min. Use wetting methods that ensure that units are nearly saturated but surface is dry when laid.

1. Tool exposed mortar joints in repaired areas to match joints of surrounding existing brickwork.
2. When mortar is hard enough to support units, remove shims and other devices interfering with pointing of joints.

J. Curing: Cure mortar by maintaining in thoroughly damp condition for at least 72 consecutive hours, including weekends and holidays.

1. Hairline cracking within the mortar or mortar separation at edge of a joint is unacceptable. Completely remove such mortar and repoint.

3.7 BRICK MASONRY PATCHING

A. Patch the following bricks unless another type of repair or replacement is indicated:

1. Bricks with cracks or spalls.
2. Bricks with holes.
3. Bricks with chipped edges or corners.
4. Bricks with small areas of deep deterioration.

B. Remove and replace existing patches which do not match existing brick and mortar.

3.8 FINAL CLEANING

A. After mortar has fully hardened, thoroughly clean exposed masonry surfaces of excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water applied by low-pressure spray.

B. Clean adjacent nonmasonry surfaces. Use detergent and soft brushes or cloths.

C. Clean mortar and debris from roof and other surfaces below.

D. Remove masking materials, leaving no residues that could trap dirt.

3.9 MASONRY WASTE DISPOSAL

A. Masonry Waste: Remove masonry waste and legally dispose of off Owner's property.

END OF SECTION

SECTION 040120.64 - BRICK MASONRY REPOINTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Mortar materials.
2. Mortar mixes.

B. Related Requirements:

1. Section 012100 "Allowances" for brick repointing allowances.
2. Section 012200 "Unit Prices" for brick repointing unit prices.
3. Section 040110 "Masonry Cleaning" for cleaning from both clay masonry and stone.

1.2 DEFINITIONS

A. Low-Pressure Spray: 100 to 400 psi; 4 to 6 gpm.

1.3 SEQUENCING AND SCHEDULING

A. Work Sequence: Perform brick masonry repointing Work in the following sequence, which includes Work specified in this and other Sections:

1. Remove plant growth.
2. Inspect masonry for open mortar joints and permanently or temporarily point them before cleaning to prevent the intrusion of water and other cleaning materials into the wall.
3. Clean masonry.
4. Rake out mortar from joints surrounding masonry to be replaced and from joints adjacent to masonry repairs along joints.
5. Repair masonry, including replacing existing masonry with new masonry materials.
6. Rake out mortar from joints to be repointed.
7. Point mortar and sealant joints.
8. After repairs and repointing have been completed and cured, perform a final cleaning to remove residues from this work.

B. As scaffolding is removed, patch anchor holes used to attach scaffolding. Patch holes in bricks in accordance with Section 040120.63 "Brick Masonry Repair." Patch holes in mortar joints in accordance with "Repointing" Article.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Samples for Verification: For the following:

1. Each type, color, and texture of pointing mortar in the form of sample mortar strips, 6 inches long by1/2 inch wide, set in aluminum or plastic channels.

a. Include with each Sample a list of ingredients with proportions of each. Identify sources, both supplier and quarry, of each type of sand and brand names of cementitious materials and pigments if any.

2. Accessories: Each type of accessory and miscellaneous support.

1.5 QUALITY ASSURANCE

A. Brick Masonry Repointing Specialist Qualifications: Engage an experienced brick masonry repointing firm to perform work of this Section. Firm is to have completed work similar in material, design, and extent to that indicated for this Project with a record of successful in-service performance. Experience in only installing masonry is insufficient experience for masonry repointing work.

1.6 MOCKUPS

A. Prepare mockups of brick masonry repointing to demonstrate aesthetic effects and to set quality standards for materials and execution.

1. Repointing: Rake out joints at area approximately 36 inches high by 48 inches wide, and repoint the areas.
2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Owner specifically approves such deviations by Change Order.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver packaged materials to Project site in manufacturer's original and unopened containers, labeled with manufacturer's name and type of products.

B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

C. Store hydrated lime in manufacturer's original and unopened containers. Discard lime if containers have been damaged or have been opened for more than two days.

D. Store sand where grading and other required characteristics can be maintained and contamination avoided.

1.8 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit repointing work to be performed in accordance with product manufacturers' written instructions and specified requirements.

B. Temperature Limits: Repoint mortar joints only when air temperature is between 40 and 90 deg F and is predicted to remain so for at least seven days after completion of the Work unless otherwise indicated.

C. Cold-Weather Requirements: Comply with the following procedures for mortar-joint pointing unless otherwise indicated:

1. When air temperature is below 40 deg F, heat mortar ingredients and existing masonry walls to produce temperatures between 40 and 120 deg F.
2. When mean daily air temperature is below 40 deg F, provide enclosure and heat to maintain temperatures above 32 deg F within the enclosure for seven days after pointing.

D. Hot-Weather Requirements: Protect mortar-joint pointing when temperature and humidity conditions produce excessive evaporation of water from mortar materials. Provide artificial shade and wind breaks, and use cooled materials as required to minimize evaporation. Do not apply mortar to substrates with temperatures of 90 deg F and above unless otherwise indicated.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each type of material for repointing brick masonry (cement, sand, etc.) from single source with resources to provide materials of consistent quality in appearance and physical properties.

2.2 MORTAR MATERIALS

A. Portland Cement: ASTM C150/C150M, Type I or Type II, except Type III may be used for cold-weather construction; white or gray, or both where required for color matching of mortar.

B. Hydrated Lime: ASTM C207, Type S.

C. Masonry Cement: ASTM C91/C91M.

D. Mortar Cement: ASTM C1329/C1329M.

E. Mortar Sand: ASTM C144.

1. Match size, texture, and gradation of existing mortar sand as closely as possible. Blend several sands if necessary to achieve suitable match.
2. Color: Natural sand or ground marble, granite, or other sound stone of color necessary to produce required mortar color.

F. Water: Potable.

2.3 MORTAR MIXES

A. Measurement and Mixing: Measure cementitious materials and sand in a dry condition by volume or equivalent weight. Do not measure by shovel; use known measure. Mix materials in a clean, mechanical batch mixer.

1. Mixing Pointing Mortar: Thoroughly mix cementitious materials and sand together before adding any water. Then mix again, adding only enough water to produce a damp, unworkable mix that retains its form when pressed into a ball. Maintain mortar in this dampened condition for 15 to 30 minutes. Add remaining water in small portions until mortar reaches desired consistency. Use mortar within one hour of final mixing; do not retemper or use partially hardened material.

B. Do not use admixtures in mortar unless otherwise indicated.

C. Mixes: Mix mortar materials in the following proportions:

1. Pointing Mortar by Property: ASTM C270, Property Specification, Type N unless otherwise indicated; with cementitious material limited to portland cement and lime, masonry cement, or mortar cement.

2.4 ACCESSORY MATERIALS

A. Sealant Materials:

1. Sealant manufacturer's standard elastomeric sealant(s) of base polymer and characteristics in accordance with applicable requirements in Section 079200 "Joint Sealants."

B. Masking Tape: Nonstaining, nonabsorbent material; compatible with mortar, joint primers, sealants, and surfaces adjacent to joints; and that easily comes off entirely, including adhesive.

PART 3 - EXECUTION

3.1 PROTECTION

A. Prevent mortar from staining face of surrounding masonry and other surfaces.

1. Cover sills, ledges, and other projecting items to protect them from mortar droppings.
2. Keep wall area wet below pointing work to discourage mortar from adhering.
3. Immediately remove mortar splatters in contact with exposed masonry and other surfaces.

3.2 MASONRY REPOINTING, GENERAL

A. Appearance Standard: Repointed surfaces are to have a uniform appearance as viewed from 20 ft. away by Architect.

3.3 REPOINTING

A. Rake out and repoint joints to the following extent:

1. Joints at locations of the following defects:

a. Holes and missing mortar.
b. Cracks that can be penetrated by a knife blade 0.027 inch thick.
c. Hollow-sounding joints when tapped by metal object.
d. Eroded surfaces 1/8 inch deep or deeper.
e. Deterioration to point that mortar can be removed by hand, without tools.
f. Joints filled with substances other than mortar.

B. Do not rake out and repoint joints where not required.

C. Rake out joints as follows, in accordance with procedures demonstrated in approved mockup:

1. Remove mortar from joints to depth of 2-1/2 times joint width and not less than that required to expose sound, unweathered mortar. Do not remove unsound mortar more than 2 inches deep; consult Architect for direction.
2. Remove mortar from brick and other masonry surfaces within raked-out joints to provide reveals with square backs and to expose masonry for contact with pointing mortar. Brush, vacuum, or flush joints to remove dirt and loose debris.
3. Do not spall edges of brick or other masonry units or widen joints. Replace damaged brick or other masonry units as directed by Architect.

D. Notify Architect of unforeseen detrimental conditions including voids in mortar joints, cracks, loose masonry units, rotted wood, rusted metal, and other deteriorated items.

E. Pointing with Mortar:

1. Rinse joint surfaces with water to remove dust and mortar particles. Time rinsing application so, at time of pointing, joint surfaces are damp but free of standing water. If rinse water dries, dampen joint surfaces before pointing.
2. Apply pointing mortar first to areas where existing mortar was removed to depths greater than surrounding areas. Apply in layers not greater than 3/8 inch until a uniform depth is formed. Fully compact each layer, and allow it to become thumbprint hard before applying next layer.
3. After deep areas have been filled to same depth as remaining joints, point joints by placing mortar in layers not greater than 3/8 inch. Fully compact each layer and allow to become thumbprint hard before applying next layer. Take care not to spread mortar beyond joint edges onto exposed masonry surfaces or to featheredge the mortar.
4. When mortar is thumbprint hard, tool joints to match original appearance of joints as demonstrated in approved mockup. Remove excess mortar from edge of joint by brushing.
5. Cure mortar by maintaining in thoroughly damp condition for at least 72 consecutive hours, including weekends and holidays.
6. Hairline cracking within mortar or mortar separation at edge of a joint is unacceptable. Completely remove such mortar and repoint.

F. Pointing with Sealant: Comply with Section 079200 "Joint Sealants" and as follows:

1. After raking out, keep joints dry and free of mortar and debris.
2. Clean and prepare joint surfaces. Prime joint surfaces unless sealant manufacturer recommends against priming. Do not allow primer to spill or migrate onto adjoining surfaces.
3. Fill sealant joints with specified joint sealant.

    a. Install cylindrical sealant backing beneath the sealant. Where space is insufficient for cylindrical sealant backing, install bond-breaker tape.
    b. Install sealant using only proven installation techniques that ensure that sealant is deposited in a uniform, continuous ribbon, without gaps or air pockets, and with complete wetting of the joint bond surfaces equally on both sides. Fill joint flush with surrounding masonry and matching the contour of adjoining mortar joints.
    c. Install sealant as recommended in writing by sealant manufacturer but within the following general limitations, measured at the center (thin) section of the bead:

        1) Fill joints to a depth equal to joint width, but not more than 1/2 inch deep or less than 3/8 inch deep.

    d. Tool sealant to form smooth, uniform beads, slightly concave. Remove excess sealant from surfaces adjacent to joint.
    e. Do not allow sealant to overflow or spill onto adjoining surfaces, or to migrate into the voids of adjoining surfaces, particularly rough textures. Remove excess and spillage of sealant promptly as the work progresses. Clean adjoining surfaces by the means necessary to eliminate evidence of spillage, without damage to adjoining surfaces or finishes, as demonstrated in an approved mockup.

G. Where repointing work precedes cleaning of existing masonry, allow mortar to harden at least 30 days before beginning cleaning work.

3.4 FINAL CLEANING

A. After mortar has fully hardened, thoroughly clean exposed masonry surfaces of excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water applied by low-pressure spray.

B. Clean adjacent nonmasonry surfaces. Use detergent and soft brushes or cloths.

C. Clean mortar and debris from roof and surfaces below. Rinse off roof and adjacent surfaces.

D. Remove masking materials, leaving no residues that could trap dirt.

END OF SECTION

SECTION 040140.61 - STONE REPAIR

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Stone materials.
2. Mortar materials.
3. Manufactured repair materials.

B. Related Requirements:

1. Section 013516 "Alteration Project Procedures" for general remodeling, renovation, repair, and maintenance requirements.
2. Section 040110 "Masonry Cleaning" for cleaning and paint removal existing masonry.
3. Section 079200 "Joint Sealants" for joint sealants, joint fillers, and sealant-joint preparation for repaired masonry.

1.2 DEFINITIONS

A. Existing to Remain: Existing items of construction that are not to be removed.

B. Dutchman: A method of repair, removing deteriorated stone in part and replacing with salvage or new stone.

C. Low-Pressure Spray: 100 to 400 psi; 4 to 6 gpm.

D. Remove: Detach items from existing construction and legally dispose of off-site unless indicated to be removed and salvaged or removed and reinstalled.

E. Remove and Salvage: Detach items from existing construction, in a manner to prevent damage, and deliver to Owner or storage as indicated.

F. Remove and Reinstall: Detach items from existing construction, in a manner to prevent damage; prepare for reuse; and reinstall where indicated.

G. Rebuilding (Setting) Mortar: Mortar used to set and anchor masonry in a structure, distinct from pointing mortar installed after masonry is set in place.

H. Rift: The most pronounced direction of splitting or cleavage of a stone.

1.3 SEQUENCING AND SCHEDULING

A. Work Sequence: Perform stone repair work in the following sequence, which includes work specified in this and other Sections:

1. Remove plant growth.
2. Clean stone.
3. Repair stonework.
4. After repairs and repointing have been completed and cured, perform a final cleaning to remove residues from this work.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Samples for Verification: For the following:

1. Patching compound in form of briquettes, at least 3 inches long by 1-1/2 inches wide. Document each Sample with manufacturer and stock number or other information necessary to order additional material.

1.5 QUALITY ASSURANCE

A. Stone Repair Specialist Qualifications: Engage an experienced stone repair firm to perform Work of this Section. Firm is to have completed work similar in material, design, and extent to that indicated for this Project with a record of successful in-service performance. Experience in only installing standard unit masonry or new stone masonry is insufficient experience for stone repair work.

1.6 MOCKUPS

A. Prepare mockups of stone repair to demonstrate aesthetic effects and to set quality standards for materials and execution, and for fabrication and installation.

1. Stone Repair: Prepare sample area of stone indicated to have repair work performed. Construct sample areas in locations in existing walls where directed by Architect unless otherwise indicated. Demonstrate quality of materials, workmanship, and blending with existing work. Include the following as a minimum:

    a. Stone Plug Repair: Two stone plug repairs for each type of stone indicated to be plugged.
    b. Crack Injection: Apply crack injection at cracked stone.
    c. Patching: Patch cracked stone with patching mortar.

2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit stone repair work to be performed in accordance with product manufacturers' written instructions and specified requirements.

B. Temperature Limits, General: Repair stone units only when air temperature is between 40 and 90 deg F and is predicted to remain so for at least seven days after completion of the Work unless otherwise indicated.

C. Cold-Weather Requirements: Comply with the following procedures for stone repair unless otherwise indicated:

1. When air temperature is below 40 deg F, heat mortar ingredients, repair materials, and existing stone to produce temperatures between 40 and 120 deg F.
2. When mean daily air temperature is below 40 deg F, provide enclosure and heat to maintain temperatures above 32 deg F within the enclosure for seven days after repair.

D. Hot-Weather Requirements: Protect stone repairs when temperature and humidity conditions produce excessive evaporation of water from mortar and patching materials. Provide artificial shade and wind breaks, and use cooled materials as required to minimize evaporation. Do not apply mortar to substrates with temperatures of 90 deg F and above unless otherwise indicated.

E. For manufactured repair materials, perform work within the environmental limits set by each manufacturer.

PART 2 - PRODUCTS

2.1 MANUFACTURED REPAIR MATERIALS

A. Stone Patching Compound: Factory-mixed cementitious product that is custom manufactured for patching stone.

B. Cementitious Crack Filler: Ultrafine superplasticized grout that can be injected into cracks, is suitable for application to wet or dry cracks, exhibits low shrinkage, and develops high bond strength to all types of stone. Color to match existing stone.

2.2 ACCESSORY MATERIALS

A. Stone Repair Anchors and Pins: Mechanical fasteners and pins of Type 304 stainless steel; designed for stone stabilization and pinning stone pieces.

B. Masking Tape: Nonstaining, nonabsorbent material; compatible with mortar, joint primers, sealants, and surfaces adjacent to joints; and that easily comes off entirely, including adhesive.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrate conditions with specialist present, for compliance with approved mockup requirements for stone type, repair methods, products, and other conditions affecting performance of the Work.

3.2 PREPARATION

A. General: Comply with each manufacturer's written instructions for protecting people, motor vehicles, surrounding buildings, masonry areas not to be cleaned, nonmasonry surfaces, landscaping, equipment, and other surfaces that could be injured or harmed by such Work.

1. Provide temporary protective covers over pedestrian walkway areas and at points of entrance and exit for people, motor vehicles, and equipment that must remain during duration of repairing procedures.
2. Cover adjacent surfaces with materials that are proven to resist paint removers and chemical cleaners used unless products being used will not damage adjacent surfaces. Use protective materials that are waterproof and UV resistant.
3. Temporarily protect all open joints to prevent intrusion of washing waters into the wall structure or building interior.
4. Remove all extraneous items no longer in use on face of surface unless indicated to remain. Where not indicated, obtain approval with Architect.

3.3 PROTECTION

A. Prevent mortar from staining face of surrounding stone and other surfaces.

1. Cover sills, ledges, and other projecting items to protect them from mortar droppings.
2. Keep wall area wet below rebuilding and repair work to discourage mortar from adhering.
3. Immediately remove mortar splatters in contact with exposed stone and other surfaces.

3.4 STONE REPAIR, GENERAL

A. Appearance Standard: Repaired surfaces are to have a uniform appearance as viewed from 20 ft. away by Architect.

3.5 CRACK INJECTION

A. General: Comply with cementitious crack-filler manufacturer's written instructions.

B. Drill 1/4-inch-diameter injection holes as follows:

1. Transverse Cracks Less Than 3/8 inch Wide: Drill holes through center of crack at 12 to 18 inches o.c.

2. Transverse Cracks More Than 3/8 inch Wide: Drill holes through center of crack at 18 to 36 inches o.c.
3. Delaminations: Drill holes at approximately 18 inches o.c. both vertically and horizontally.
4. Drill holes 2 inches deep.

C. Clean out drill holes and cracks with compressed air and water. Remove dirt and organic matter, loose material, sealants, and failed crack repair materials.

D. Place plastic injection ports in drilled holes and seal face of cracks between injection ports with clay or other nonstaining, removable plugging material. Leave openings at upper ends of cracks for air release.

E. Inject cementitious crack filler through ports sequentially, beginning at one end of area and working to opposite end; where possible, begin at lower end of injection area and work upward. Inject filler until it extrudes from adjacent ports. After port has been injected, plug with clay or other suitable material and begin injecting filler at adjacent port, repeating process until all ports have been injected.

F. Clean cementitious crack filler from face of stone before it sets by scrubbing with water.

G. After cementitious crack filler has set, remove injection ports, plugging material, and excess filler. Patch injection holes and surface of cracks as specified in "Stone Patching" Article.

3.6 STONE PATCHING

A. Patch the following stone units unless another type of repair or replacement is indicated:

1. Units with visible cracks.
2. Units with holes.
3. Units with chipped edges or corners. Patch chipped edges or corners measuring more than 3/4 inch in least dimension.
4. Units with small areas of deep deterioration. Patch deep deteriorations measuring more than 1/8 inch in least dimension and more than 1/8 inch deep.

B. Remove deteriorated material and remove adjacent material that has begun to deteriorate. Carefully remove additional material so patch does not have feathered edges but has square or slightly undercut edges on area to be patched and is at least 1/4 inch thick, but not less than recommended in writing by patching compound manufacturer.

C. Mask adjacent mortar joint or rake out for repointing if patch extends to edge of stone unit.

D. Mix patching compound in individual batches to match each stone unit being patched. Combine one or more colors of patching compound, as needed, to produce exact match.

E. Brush-coat stone surfaces with slurry coat of patching compound in accordance with manufacturer's written instructions.

F. Place patching compound in layers as recommended in writing by patching compound manufacturer, but not less than 1/4 inch or more than 2 inches thick. Roughen surface of each layer to provide a key for next layer.

1. Simple Details: Trowel, scrape, or carve surface of patch to match texture and surrounding surface plane or contour of the stone. Shape and finish surface before or after curing, as determined by testing, to best match existing stone.

G. Keep each layer damp for 72 hours or until patching compound has set.

H. Remove and replace patches with hairline cracks or that show separation from stone at edges, and those that do not match adjoining stone in color or texture.

3.7 FINAL CLEANING

A. After mortar has fully hardened, thoroughly clean exposed stone surfaces of excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water, applied by low-pressure spray.

B. Clean adjacent nonstone surfaces. Use detergent and soft brushes or cloths.

C. Remove masking materials, leaving no residues that could trap dirt.

END OF SECTION

SECTION 042000 - UNIT MASONRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Concrete masonry units.
2. Lintels.
3. Brick.
4. Mortar and grout materials.
5. Reinforcement.
6. Ties and anchors.
7. Accessories.
8. Mortar and grout mixes.

B. Products Installed but not Furnished under This Section:

1. Cast-stone panels in unit masonry.
2. Steel lintels in unit masonry.

C. Related Requirements:

1. Section 040120.63 “Brick Masonry Repair” for repair of existing brick.
2. Section 040120.64 “Brick Masonry Repointing” for repointing existing brick.
3. Section 040140.61 “Stone Repair” for repair of stone sills and stone bands.
4. Section 047200 “Cast Stone Masonry” for cast stone wall panels.
5. Section 072119 "Foamed-in-Place Insulation" for wall insulation.
6. Section 076200 "Sheet Metal Flashing and Trim" for exposed sheet metal flashing and for furnishing manufactured reglets installed in masonry joints.

1.2 DEFINITIONS

A. CMU(s): Concrete masonry unit(s).

B. Reinforced Masonry: Masonry containing reinforcing steel in grouted cells.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Shop Drawings: For the following:

1. Masonry Units: Indicate sizes, profiles, coursing, and locations of special shapes.
2. Reinforcing Steel: Indicate bending, lap lengths, and placement of unit masonry reinforcing bars. Comply with ACI 315R.
3. Fabricated Flashing: Detail corner units, end-dam units, and other special applications.

D. Samples for Verification: For each type and color of the following:

1. Clay face brick, in the form of straps of five or more bricks.
2. Accessories embedded in masonry.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. List of Materials Used in Constructing Mockups: List generic product names together with manufacturers, manufacturers' product names, model numbers, lot numbers, batch numbers, source of supply, and other information as required to identify materials used. Include mix proportions for mortar and grout and source of aggregates.

1. Submittal is for information only. Receipt of list does not constitute approval of deviations from the Contract Documents unless such deviations are specifically brought to the attention of Architect and approved in writing.

C. Material Certificates: For each type of the following:

1. Masonry units.

a. Include data on material properties.
b. For brick, include size-variation data verifying that actual range of sizes falls within specified tolerances.
c. For exposed brick, include test report for efflorescence in accordance with ASTM C67/C67M.
d. For surface-coated brick, include test report for durability of surface appearance after 50 cycles of freezing and thawing in accordance with ASTM C67/C67M.

2. Cementitious materials. Include name of manufacturer, brand name, and type.
3. Mortar admixtures.
4. Preblended, dry mortar mixes. Include description of type and proportions of ingredients.
5. Grout mixes. Include description of type and proportions of ingredients.
6. Reinforcing bars.
7. Joint reinforcement.
8. Anchors, ties, and metal accessories.

D. Qualification Statements: For testing agency.

E. Mix Designs: For each type of mortar and grout. Include description of type and proportions of ingredients.

1. Include test reports for mortar mixes required to comply with property specification. Test in accordance with ASTM C109/C109M for compressive strength, ASTM C1506 for water retention, and ASTM C91/C91M for air content.
2. Include test reports, in accordance with ASTM C1019, for grout mixes required to comply with compressive strength requirement.

F. Statement of Compressive Strength of Masonry: For each combination of masonry unit type and mortar type, provide statement of average net-area compressive strength of masonry units, mortar type, and resulting net-area compressive strength of masonry determined in accordance with TMS 602.

G. Cold-Weather and Hot-Weather Procedures: Detailed description of methods, materials, and equipment to be used to comply with requirements.

1.5 QUALITY ASSURANCE

A. Qualifications:

1. Installers: All masonry flashing installers must complete the International Masonry Institute Flashing Upgrade training course.
2. Testing Agency Qualifications: Qualified in accordance with ASTM C1093 for testing indicated.

1.6 MOCKUPS

A. Sample Panel Mockups: Build sample panels to verify selections made under Sample submittals and to demonstrate aesthetic effects. Comply with requirements in Section 014000 "Quality Requirements" for mockups.

1. Build sample panels for typical exterior wall at parapet extension in sizes approximately 48 inches long by 36 inches high by full thickness.
2. Build sample panels facing south.
3. Where masonry is to match existing, build panels adjacent and parallel to existing surface.
4. Clean one-half of exposed faces of panels with masonry cleaner indicated.
5. Protect approved sample panels from the elements with weather-resistant membrane.
6. Approval of sample panels is for color, texture, and blending of masonry units; relationship of mortar and sealant colors to masonry unit colors; tooling of joints; aesthetic qualities of workmanship; and other material and construction qualities specifically approved by Architect in writing.

    a. Approval of sample panels does not constitute approval of deviations from the Contract Documents contained in sample panels unless Architect specifically approves such deviations in writing.

7. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Store masonry units on elevated platforms in a dry location. If units are not stored in an enclosed location, cover tops and sides of stacks with waterproof sheeting, securely tied. If units become wet, do not install until they are dry.

B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

C. Store aggregates where grading and other required characteristics can be maintained and contamination avoided.

D. Deliver preblended, dry mortar mix in moisture-resistant containers. Store preblended, dry mortar mix in delivery containers on elevated platforms in a dry location or in covered weatherproof dispensing silos.

E. Store masonry accessories, including metal items, to prevent corrosion and accumulation of dirt and oil.

1.8 FIELD CONDITIONS

A. Protection of Masonry: During construction, cover tops of walls, projections, and sills with waterproof sheeting at end of each day's work. Cover partially completed masonry when construction is not in progress.

1. Extend cover a minimum of 24 inches down both sides of walls, and hold cover securely in place.
2. Where one wythe of multiwythe masonry walls is completed in advance of other wythes, secure cover a minimum of 24 inches down face next to unconstructed wythe, and hold cover in place.

B. Do not apply uniform floor or roof loads for at least 12 hours and concentrated loads for at least three days after building masonry walls or columns.

C. Stain Prevention: Prevent grout, mortar, and soil from staining the face of masonry to be left exposed or painted. Immediately remove grout, mortar, and soil that come in contact with such masonry.

1. Protect base of walls from rain-splashed mud and from mortar splatter by spreading coverings on ground and over wall surface.
2. Protect sills, ledges, and projections from mortar droppings.
3. Protect surfaces of window and door frames, as well as similar products with painted and integral finishes, from mortar droppings.
4. Turn scaffold boards near the wall on edge at the end of each day to prevent rain from splashing mortar and dirt onto completed masonry.

D. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Remove and replace unit masonry damaged by frost or by freezing conditions. Comply with cold-weather construction requirements contained in TMS 602.

1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F and higher and will remain so until masonry has dried, but not less than seven days after completing cleaning.

E. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in TMS 602.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. For exposed masonry units and cementitious mortar components, obtain each color and grade from single source with resources to provide materials of consistent quality in appearance and physical properties.

2.2 PERFORMANCE REQUIREMENTS

A. Provide unit masonry that develops indicated net-area compressive strengths at 28 days.

1. Determine net-area compressive strength of masonry by testing masonry prisms in accordance with ASTM C1314.

2.3 UNIT MASONRY, GENERAL

A. Masonry Standard: Comply with TMS 602, except as modified by requirements in the Contract Documents.

B. Defective Units: Do not use masonry units that contain chips, cracks, or other defects.

C. Fire-Resistance Ratings: Comply with requirements for fire-resistance-rated assembly designs indicated.

2.4 CONCRETE MASONRY UNITS

A. Shapes: Provide shapes indicated and as follows, with exposed surfaces matching exposed faces of adjacent units unless otherwise indicated.

1. Provide square-edged units for outside corners unless otherwise indicated.

B. CMUs: ASTM C90, normal weight.

1. Size (Width): Manufactured to dimensions 3/8 inch less than nominal dimensions.

C. Concrete Building Brick: ASTM C55, normal weight.

1. Size (Actual Dimensions): 3-5/8 inches wide by 2-1/4 inches high by 7-5/8 inches long.

2.5 LINTELS

A. Masonry Lintels: Prefabricated or built-in-place masonry lintels made from bond beam CMUs matching adjacent CMUs in color, texture, and density classification, with reinforcing bars placed as indicated and filled with coarse grout. Cure precast lintels before handling and installing. Temporarily support built-in-place lintels until cured.

2.6 BRICK

A. General: Provide shapes indicated and as follows, with exposed surfaces matching finish and color of exposed faces of adjacent units:

1. For ends of sills and caps and for similar applications that would otherwise expose unfinished brick surfaces, provide units without cores or frogs and with exposed surfaces finished.

B. Clay Face Brick: Facing brick complying with ASTM C216, Grade SW or Type FBS.

1. Efflorescence: Provide brick that has been tested in accordance with ASTM C67/C67M and is rated "not effloresced."
2. Size: To match existing.
3. Application: Use where brick is exposed unless otherwise indicated.
4. Provide face brick matching color range, texture, and size of existing adjacent brickwork.

2.7 MORTAR AND GROUT MATERIALS

A. Portland Cement: ASTM C150/C150M, Type I or II, except Type III may be used for cold-weather construction. Provide natural color or white cement as required to produce mortar color indicated.

1. Alkali content will not be more than 0.1 percent when tested in accordance with ASTM C114.

B. Hydrated Lime: ASTM C207, Type S.

C. Portland Cement-Lime Mix: Packaged blend of portland cement and hydrated lime containing no other ingredients.

D. Masonry Cement: ASTM C91/C91M.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Argos USA LLC
b. Cemex S.A.B. de C.V.

E. Mortar Cement: ASTM C1329/C1329M.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Lafarge North America Inc.

F. Preblended Dry Mortar Mix: Packaged blend made from portland cement and hydrated lime, masonry cement, or mortar cement, sand, and admixtures and complying with ASTM C1714/C1714M.

1. Preblended Dry Portland Cement Mortar Mix:

a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1) Amerimix is a trademark of Bonsal American, an Oldcastle company
2) Quikrete; The QUIKRETE Companies, LLC
3) Sakrete; CRH Americas, Oldcastle APG
4) SPEC MIX, LLC

2. Preblended Dry Masonry Cement Mortar Mix:

a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1) Amerimix is a trademark of Bonsal American, an Oldcastle company
2) SPEC MIX, LLC

G. Aggregate for Mortar: ASTM C144.

1. For mortar that is exposed to view, use washed aggregate consisting of natural sand or crushed stone.
2. For joints less than 1/4 inch thick, use aggregate graded with 100 percent passing the No. 16 sieve.
3. White-Mortar Aggregates: Natural white sand or crushed white stone.
4. Colored-Mortar Aggregates: Natural sand or crushed stone of color necessary to produce required mortar color.

H. Aggregate for Grout: ASTM C404.

I. Water: Potable.

2.8 REINFORCEMENT

A. Uncoated-Steel Reinforcing Bars: ASTM A615/A615M or ASTM A996/A996M, Grade 60.

B. Reinforcing Bar Positioners: Wire units designed to fit into mortar bed joints spanning masonry unit cells and to hold reinforcing bars in center of cells. Units are formed from 0.148-inch steel wire, hot-dip galvanized after fabrication. Provide units designed for number of bars indicated.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. 3GEN Masonry Products, Inc.
b. Heckmann Building Products, Inc.
c. Hohmann & Barnard, Inc
d. Wire-Bond

C. Masonry-Joint Reinforcement, General: ASTM A951/A951M.

1. Interior Walls: Mill-galvanized carbon steel.
2. Exterior Walls: Hot-dip galvanized carbon steel.
3. Wire Size for Side Rods: 0.148-inch diameter.
4. Wire Size for Cross Rods: 0.148-inch diameter.
5. Wire Size for Veneer Ties: 0.187-inch diameter.
6. Spacing of Cross Rods, Tabs, and Cross Ties: Not more than 16 inches o.c.
7. Provide in lengths of not less than 10 ft.

D. Masonry-Joint Reinforcement for Single-Wythe Masonry: Ladder type with single pair of side rods.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. 3GEN Masonry Products, Inc.
b. Hohmann & Barnard, Inc
c. Wire-Bond

E. Masonry-Joint Reinforcement for Multiwythe Masonry:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. 3GEN Masonry Products, Inc.
b. Heckmann Building Products, Inc.
c. Hohmann & Barnard, Inc
d. Wire-Bond

2. Tab type, either ladder or truss design, with one side rod at each face shell of backing wythe and with rectangular tabs sized to extend at least halfway through facing wythe, but with at least 5/8-inch cover on outside face.
3. Adjustable (two-piece) type, either ladder or truss design, with one side rod at each face shell of backing wythe and with separate adjustable ties with pintle-and-eye connections having a maximum horizontal play of 1/16 inch and maximum vertical adjustment of 1-1/4 inches. Size ties to extend at least halfway through facing wythe but with at least 5/8-inch cover on outside face.

2.9 TIES AND ANCHORS

A. General: Ties and anchors extend at least 1-1/2 inches into veneer but with at least a 5/8-inch cover on outside face.

B. Materials: Provide ties and anchors specified in this article that are made from materials that comply with the following unless otherwise indicated:

1. Hot-Dip Galvanized, Carbon-Steel Wire: ASTM A1064/A1064M, with ASTM A153/A153M, Class B-2 coating.

C. Individual Wire Ties: Rectangular units with closed ends and not less than 4 inches wide.

1. Where wythes do not align, use adjustable ties with pintle-and-eye connections having a maximum adjustment of 1-1/4 inches.
2. Wire: Fabricate from 3/16-inch-diameter, hot-dip galvanized steel wire. Mill-galvanized wire ties may be used in interior walls unless otherwise indicated.

D. Adjustable Anchors for Connecting to Structural Steel Framing: Provide anchors that allow vertical or horizontal adjustment but resist tension and compression forces perpendicular to plane of wall.

1. Anchor Section for Welding to Steel Frame: Crimped 1/4-inch-diameter, hot-dip galvanized steel wire.
2. Tie Section: Triangular-shaped wire tie made from 0.187-inch-diameter, hot-dip galvanized steel wire. Mill-galvanized wire may be used at interior walls unless otherwise indicated.

E. Adjustable Anchors for Connecting to Concrete: Provide anchors that allow vertical or horizontal adjustment but resist tension and compression forces perpendicular to plane of wall.

F. Partition Top Anchors: 0.105-inch-thick metal plate with a 3/8-inch-diameter metal rod 6 inches long welded to plate and with closed-end plastic tube fitted over rod that allows rod to move in and out of tube. Fabricate from steel, hot-dip galvanized after fabrication.

G. Rigid Anchors: Fabricate from steel bars 1-1/2 inches wide by 1/4 inch thick by 24 inches long, with ends turned up 2 inches or with cross pins unless otherwise indicated.

1. Corrosion Protection: Hot-dip galvanized to comply with ASTM A153/A153M.

2.10 ACCESSORIES

A. Compressible Filler: Premolded filler strips complying with ASTM D1056, Grade 2A1; compressible up to 35 percent; of width and thickness indicated; formulated from neoprene or urethane.

B. Preformed Control-Joint Gaskets: Made from styrene-butadiene-rubber compound, complying with ASTM D2000, Designation M2AA-805 or PVC, complying with ASTM D2287, Type PVC-65406 and designed to fit standard sash block and to maintain lateral stability in masonry wall; size and configuration as indicated.

C. Bond-Breaker Strips: Asphalt-saturated felt complying with ASTM D226/D226M, Type I (No. 15 asphalt felt).

2.11 MORTAR AND GROUT MIXES

A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures unless otherwise indicated.

1. Do not use calcium chloride in mortar or grout.
2. Use portland cement-lime, masonry cement, or mortar cement mortar unless otherwise indicated.

B. Preblended, Dry Mortar Mix: Furnish dry mortar ingredients in form of a preblended mix. Measure quantities by weight to ensure accurate proportions, and thoroughly blend ingredients before delivering to Project site.

C. Mortar for Unit Masonry: Comply with ASTM C270, Proportion Specification. Provide the following types of mortar for applications stated unless another type is indicated or needed to provide required compressive strength of masonry.

1. For masonry below grade or in contact with earth, use Type M.
2. For mortar parge coats, use Type S or Type N.
3. For exterior, above-grade, load-bearing, nonload-bearing walls, and parapet walls; for interior load-bearing walls; for interior nonload-bearing partitions; and for other applications where another type is not indicated, use Type N.

D. Grout for Unit Masonry: Comply with ASTM C476.

1. Use grout of type indicated or, if not otherwise indicated, of type (fine or coarse) that will comply with TMS 602 for dimensions of grout spaces and pour height.
2. Proportion grout in accordance with ASTM C476, Table 1.
3. Provide grout with a slump of 8 to 11 inches as measured in accordance with ASTM C143/C143M.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

1. For the record, prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
2. Verify that foundations are within tolerances specified.
3. Verify that reinforcing dowels are properly placed.
4. Verify that substrates are free of substances that impair mortar bond.

B. Before installation, examine rough-in and built-in construction for piping systems to verify actual locations of piping connections.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Thickness: Build cavity and composite walls and other masonry construction to full thickness shown. Build single-wythe walls to actual widths of masonry units, using units of widths indicated.

B. Build chases and recesses to accommodate items specified in this and other Sections.

C. Leave openings for equipment to be installed before completing masonry. After installing equipment, complete masonry to match construction immediately adjacent to opening.

D. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed.

E. Matching Existing Brick Masonry: Match coursing, bonding, color, and texture of existing brick masonry.

F. Wetting of Brick: Wet brick before laying if initial rate of absorption exceeds 30 g/30 sq. in. per minute when tested in accordance with ASTM C67/C67M. Allow units to absorb water so they are damp but not wet at time of laying.

3.3 TOLERANCES

A. Dimensions and Locations of Elements:

1. For location of elements in elevation, do not vary from that indicated by more than plus or minus 1/4 inch in a story height or 1/2 inch total.

B. Lines and Levels:

1. For bed joints and top surfaces of bearing walls, do not vary from level by more than 1/4 inch in 10 ft., or 1/2-inch maximum.
2. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 ft., 1/4 inch in 20 ft., or 1/2-inch maximum.
3. For vertical lines and surfaces, do not vary from plumb by more than 1/4 inch in 10 ft., 3/8 inch in 20 ft., or 1/2-inch maximum.
4. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 ft., 1/4 inch in 20 ft., or 1/2-inch maximum.
5. For lines and surfaces, do not vary from straight by more than 1/4 inch in 10 ft., 3/8 inch in 20 ft., or 1/2-inch maximum.
6. For vertical alignment of exposed head joints, do not vary from plumb by more than 1/4 inch in 10 ft., or 1/2-inch maximum.
7. For faces of adjacent exposed masonry units, do not vary from flush alignment by more than 1/16 inch except due to warpage of masonry units within tolerances specified for warpage of units.

C. Joints:

1. For bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch, with a maximum thickness limited to 1/2 inch.
2. For exposed bed joints, do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch.
3. For head and collar joints, do not vary from thickness indicated by more than plus 3/8 inch or minus 1/4 inch.
4. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch.
5. For exposed bed joints and head joints of stacked bond, do not vary from a straight line by more than 1/16 inch from one masonry unit to the next.

3.4 LAYING MASONRY WALLS

A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.

B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in running bond; do not use units with less-than-nominal 4-inch horizontal face dimensions at corners or jambs.

C. Lay concealed masonry with all units in a wythe in running bond or bonded by lapping not less than 2 inches. Bond and interlock each course of each wythe at corners. Do not use units with less-than-nominal 4-inch horizontal face dimensions at corners or jambs.

D. Stopping and Resuming Work: Stop work by stepping back units in each course from those in course below; do not tooth. When resuming work, clean masonry surfaces that are to receive mortar, remove loose masonry units and mortar, and wet brick if required before laying fresh masonry.

E. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.

F. Fill space between steel frames and masonry solidly with mortar unless otherwise indicated.

G. Where built-in items are to be embedded in cores of hollow masonry units, place a layer of metal lath, wire mesh, or plastic mesh in the joint below, and rod mortar or grout into core.

H. Fill cores in hollow CMUs with grout 24 inches under bearing plates, beams, lintels, posts, and similar items unless otherwise indicated.

I. Build nonload-bearing interior partitions full height of story to underside of solid floor or roof structure above unless otherwise indicated.

1. Install compressible filler in joint between top of partition and underside of structure above.

2. Fasten partition top anchors to structure above and build into top of partition. Grout cells of CMUs solidly around plastic tubes of anchors, and push tubes down into grout to provide 1/2-inch clearance between end of anchor rod and end of tube. Space anchors 48 inches o.c. unless otherwise indicated.
3. At fire-rated partitions, treat joint between top of partition and underside of structure above to comply with Section 078443 "Joint Firestopping."

3.5 MORTAR BEDDING AND JOINTING

A. Lay CMUs and hollow brick as follows:

1. Bed face shells in mortar and make head joints of depth equal to bed joints.
2. Bed webs in mortar in all courses of piers, columns, and pilasters.
3. Bed webs in mortar in grouted masonry, including starting course on footings.
4. Fully bed entire units, including areas under cells, at starting course on footings where cells are not grouted.
5. Fully bed units and fill cells with mortar at anchors and ties as needed to fully embed anchors and ties in mortar.

B. Lay solid masonry units with completely filled bed and head joints; butter ends with sufficient mortar to fill head joints and shove into place. Do not deeply furrow bed joints or slush head joints.

C. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness unless otherwise indicated.

D. Cut joints flush for masonry walls to receive plaster or other direct-applied finishes (other than paint) unless otherwise indicated.

E. Cut joints flush where indicated to receive wall insulation unless otherwise indicated.

3.6 COMPOSITE MASONRY

A. Bond wythes of composite masonry together as follows:

1. Masonry-Joint Reinforcement: Installed in horizontal mortar joints.

a. Where bed joints of both wythes align, use ladder-type reinforcement extending across both wythes.
b. Where bed joints of wythes do not align, use adjustable-type (two-piece-type) reinforcement with continuous horizontal wire in facing wythe attached to ties.

B. Collar Joints: Solidly fill collar joints by parging face of first wythe that is laid and shoving units of other wythe into place.

C. Corners: Provide interlocking masonry unit bond in each wythe and course at corners unless otherwise indicated.

1. Provide continuity with masonry-joint reinforcement at corners by using prefabricated L-shaped units as well as masonry bonding.

D. Intersecting and Abutting Walls: Unless vertical expansion or control joints are indicated at juncture, bond walls together as follows:

1. Provide continuity with masonry-joint reinforcement by using prefabricated T-shaped units.

3.7 MASONRY-JOINT REINFORCEMENT

A. General: Install entire length of longitudinal side rods in mortar with a minimum cover of 5/8 inch on exterior side of walls, 1/2 inch elsewhere. Lap reinforcement a minimum of 6 inches.

1. Space reinforcement not more than 8 inches o.c. in foundation walls and parapet walls.
2. Provide reinforcement not more than 8 inches above and below wall openings and extending 12 inches beyond openings in addition to continuous reinforcement.

B. Interrupt joint reinforcement at control and expansion joints unless otherwise indicated.

C. Provide continuity at wall intersections by using prefabricated T-shaped units.

D. Provide continuity at corners by using prefabricated L-shaped units.

E. Cut and bend reinforcing units as directed by manufacturer for continuity at[**corners,**] returns, offsets, column fireproofing, pipe enclosures, and other special conditions.

3.8 ANCHORING MASONRY TO STRUCTURAL STEEL AND CONCRETE

A. Anchor masonry to structural steel and concrete, where masonry abuts or faces structural steel or concrete, to comply with the following:

1. Provide an open space not less than 1/2 inch wide between masonry and structural steel or concrete unless otherwise indicated. Keep open space free of mortar and other rigid materials.
2. Anchor masonry with anchors embedded in masonry joints and attached to structure.
3. Space anchors as indicated, but not more than 24 inches o.c. vertically and 36 inches o.c. horizontally.

3.9 CONTROL AND EXPANSION JOINTS

A. General: Install control- and expansion-joint materials in unit masonry as masonry progresses. Do not allow materials to span control and expansion joints without provision to allow for in-plane wall or partition movement.

B. Form control joints in concrete masonry using one of the following methods:

1. Fit bond-breaker strips into hollow contour in ends of CMUs on one side of control joint. Fill resultant core with grout, and rake out joints in exposed faces for application of sealant.
2. Install preformed control-joint gaskets designed to fit standard sash block.

3. Install interlocking units designed for control joints. Install bond-breaker strips at joint. Keep head joints free and clear of mortar, or rake out joint for application of sealant.
4. Install temporary foam-plastic filler in head joints, and remove filler when unit masonry is complete for application of sealant.

C. Form expansion joints in brick as follows:

1. Build flanges of metal expansion strips into masonry. Lap each joint 4 inches in direction of water flow. Seal joints below grade and at junctures with horizontal expansion joints if any.
2. Build flanges of factory-fabricated, expansion-joint units into masonry.
3. Build in compressible joint fillers where indicated.
4. Form open joint full depth of brick wythe and of width indicated, but not less than 3/8 inch for installation of sealant and backer rod specified in Section 079200 "Joint Sealants."

3.10 LINTELS

A. Install steel lintels where indicated.

B. Provide masonry lintels where indicated and where openings of more than 12 inches for brick-size units and 24 inches for block-size units are indicated without structural steel or other supporting lintels.

C. Provide minimum bearing of 8 inches at each jamb unless otherwise indicated.

3.11 REINFORCED UNIT MASONRY

A. Temporary Formwork and Shores: Construct formwork and shores as needed to support reinforced masonry elements during construction.

1. Construct formwork to provide shape, line, and dimensions of completed masonry as indicated. Make forms sufficiently tight to prevent leakage of mortar and grout. Brace, tie, and support forms to maintain position and shape during construction and curing of reinforced masonry.
2. Do not remove forms and shores until reinforced masonry members have hardened sufficiently to carry their own weight and that of other loads that may be placed on them during construction.

B. Placing Reinforcement: Comply with requirements in TMS 602.

C. Grouting: Do not place grout until entire height of masonry to be grouted has attained enough strength to resist grout pressure.

1. Comply with requirements in TMS 602 for cleanouts and for grout placement, including minimum grout space and maximum pour height.
2. Limit height of vertical grout pours to not more than 60 inches.

3.12 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections. Allow inspectors access to scaffolding and work areas as needed to perform tests and inspections. Retesting of materials that fail to comply with specified requirements will be at Contractor's expense.

B. Inspections: Special inspections in accordance with Level 2 in TMS 402.

1. Begin masonry construction only after inspectors have verified proportions of site-prepared mortar.
2. Place grout only after inspectors have verified compliance of grout spaces and of grades, sizes, and locations of reinforcement.
3. Place grout only after inspectors have verified proportions of site-prepared grout.

C. Testing Prior to Construction: One set of tests.

D. Testing Frequency: One set of tests for each 5000 sq. ft. of wall area or portion thereof.

E. Mortar Test (Property Specification): For each mix provided, in accordance with ASTM C780. Test mortar for compressive strength.

F. Grout Test (Compressive Strength): For each mix provided, in accordance with ASTM C1019.

3.13 REPAIRING, POINTING, AND CLEANING

A. Remove and replace masonry units that are loose, chipped, broken, stained, or otherwise damaged or that do not match adjoining units. Install new units to match adjoining units; install in fresh mortar, pointed to eliminate evidence of replacement.

B. Pointing: During the tooling of joints, enlarge voids and holes, except weep holes, and completely fill with mortar. Point up joints, including corners, openings, and adjacent construction, to provide a neat, uniform appearance. Prepare joints for sealant application, where indicated.

C. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.

D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:

1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
2. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes. Obtain Architect's approval of sample cleaning before proceeding with cleaning of masonry.
3. Protect adjacent stone and nonmasonry surfaces from contact with cleaner by covering them with liquid strippable masking agent or polyethylene film and waterproof masking tape.
4. Wet wall surfaces with water before applying cleaners; remove cleaners promptly by rinsing surfaces thoroughly with clear water.

5. Clean brick by bucket-and-brush hand-cleaning method described in BIA Technical Notes 20.
6. Clean concrete masonry by applicable cleaning methods indicated in NCMA TEK 8-4A.
7. Clean masonry with a proprietary acidic masonry cleaner applied according to manufacturer's written instructions.

3.14 MASONRY WASTE DISPOSAL

A. Excess masonry materials are Contractor's property. At completion of unit masonry work, remove from Project site.

END OF SECTION

SECTION 047200 - CAST STONE MASONRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Wall panels.
2. Accessories.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. For cast stone units, include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

C. Shop Drawings: Show fabrication and installation details for cast stone units. Include dimensions, details of reinforcement and anchorages if any, and indication of finished faces.

1. Include building elevations showing layout of units and locations of joints and anchors.

D. Samples for Verification:

1. For each color and texture of cast stone required, 4 inches square in size.
2. For colored mortar, make Samples using same sand and mortar ingredients to be used on Project. Label Samples to indicate types and amounts of pigments used.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For manufacturer.

1. Include copies of material test reports, indicating compliance of cast stone with ASTM C1364.

C. Material Test Reports: For each mix required to produce cast stone, based on testing according to ASTM C1364.

1. Provide test reports based on testing within previous six months.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Coordinate delivery of cast stone with unit masonry work to avoid delaying the Work and to minimize the need for on-site storage.

B. Pack, handle, and ship cast stone units in suitable packs or pallets.

1. Lift with wide-belt slings; do not use wire rope or ropes that might cause staining. Move cast stone units if required, using dollies with wood supports.
2. Store cast stone units on wood skids or pallets with nonstaining, waterproof covers, securely tied. Arrange to distribute weight evenly and to prevent damage to units. Ventilate under covers to prevent condensation.

C. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

D. Store mortar aggregates where grading and other required characteristics can be maintained and contamination can be avoided.

1.5 PROJECT CONDITIONS

A. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Comply with cold-weather construction requirements in TMS 602.

1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F and above and will remain so until cast stone has dried, but no fewer than seven days after completing cleaning.

B. Hot-Weather Requirements: Comply with hot-weather construction requirements in TMS 602.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Source Limitations for Cast Stone: Obtain cast stone units from single source from single manufacturer.

B. Source Limitations for Mortar Materials: Obtain mortar ingredients of a uniform quality, including color, from one manufacturer for each cementitious component and from one source or producer for each aggregate.

2.2 CAST STONE MATERIALS

A. General: Comply with ASTM C1364.

B. Portland Cement: ASTM C150/C150M, Type I or Type III, containing not more than 0.60 percent total alkali when tested according to ASTM C114. Provide natural color or white cement as required to produce cast stone color indicated.

C. Coarse Aggregates: Granite, quartz, or limestone complying with ASTM C33/C33M; gradation and colors as needed to produce required cast stone textures and colors.

D. Fine Aggregates: Natural sand or crushed stone complying with ASTM C33/C33M, gradation and colors as needed to produce required cast stone textures and colors.

E. Color Pigment: ASTM C979/C979M, synthetic mineral-oxide pigments or colored water-reducing admixtures; color stable, free of carbon black, nonfading, and resistant to lime and other alkalis.

F. Admixtures: Use only admixtures specified or approved in writing by Architect.

1. Do not use admixtures that contain more than 0.1 percent water-soluble chloride ions by mass of cementitious materials. Do not use admixtures containing calcium chloride.
2. Use only admixtures that are certified by manufacturer to be compatible with cement and other admixtures used.
3. Air-Entraining Admixture: ASTM C260/C260M. Add to mixes for units exposed to the exterior at manufacturer's prescribed rate to result in an air content of 4 to 6 percent, except do not add to zero-slump concrete mixes.
4. Water-Reducing Admixture: ASTM C494/C494M, Type A.
5. Water-Reducing, Retarding Admixture: ASTM C494/C494M, Type D.
6. Water-Reducing, Accelerating Admixture: ASTM C494/C494M, Type E.

G. Reinforcement:

1. Deformed steel bars complying with ASTM A615/A615M, Grade 40. Use galvanized or epoxy-coated reinforcement when covered with less than 1-1/2 inches of cast stone material.

    a. Epoxy Coating: ASTM A775/A775M.
    b. Galvanized Coating: ASTM A767/A767M.

2. Plain-Steel, Welded-Wire Reinforcement: ASTM A1064/A1064M, plain, fabricated from as-drawn steel wire into flat sheets.
3. Galvanized-Steel, Welded-Wire Reinforcement: ASTM A1064/A1064M, plain, fabricated from galvanized-steel wire into flat sheets.
4. Fiber Reinforcement: ASTM C1116/C1116M.

H. Embedded Anchors and Other Inserts: Fabricated from stainless steel complying with ASTM A240/A240M, ASTM A276/A276M, or ASTM A666, Type 304.

2.3 CAST STONE UNITS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Vestacast, 56-15 58th Street, Maspeth, NY 11378 (718-894-3424).

B. Cast Stone Units: Comply with ASTM C1364.

1. Units are manufactured using the manufacturer's selected method.

2. Wall Panels: Sizes as indicated on Drawings.

C. Fabrication Tolerances:

1. Variation in Cross Section: Do not vary from indicated dimensions by more than 1/8 inch.
2. Variation in Length: Do not vary from indicated dimensions by more than 1/360 of the length of unit or 1/8 inch, whichever is greater, but in no case by more than 1/4 inch.
3. Warp, Bow, and Twist: Not to exceed 1/360 of the length of unit or 1/8 inch, whichever is greater.
4. Location of Grooves, False Joints, Holes, Anchorages, and Similar Features: Do not vary from indicated position by more than 1/8 inch on formed surfaces of units and 3/8 inch on unformed surfaces.

D. Cure Units as Follows:

1. Cure units in enclosed, moist curing room at 95 percent relative humidity and temperature of 100 deg F for 12 hours or 70 deg F for 16 hours.
2. Keep units damp and continue curing to comply with one of the following:

a. No fewer than five days at mean daily temperature of 70 deg F or above.
b. No fewer than seven days at mean daily temperature of 50 deg F or above.

E. Acid etch units after curing to remove cement film from surfaces to be exposed to view.

F. Colors and Textures: As selected by Architect from manufacturer's full range.

2.4 MORTAR MATERIALS

A. Provide mortar materials that comply with Section 042000 "Unit Masonry."

2.5 ACCESSORIES

A. Anchors: Type and size indicated or necessary, fabricated from Type 304 stainless steel complying with ASTM A240/A240M, ASTM A276/A276M, or ASTM A666.

B. Dowels: 1/2-inch diameter round bars, fabricated from Type 304 stainless steel complying with ASTM A240/A240M, ASTM A276/A276M, or ASTM A666.

C. Proprietary Acidic Cleaner: Manufacturer's standard-strength cleaner designed for removing mortar/grout stains, efflorescence, and other new construction stains from new masonry without discoloring or damaging masonry surfaces. Use product expressly approved for intended use by cast stone manufacturer and expressly approved by cleaner manufacturer for use on cast stone and adjacent masonry materials.

2.6 MORTAR MIXES

A. Comply with requirements in Section 042000 "Unit Masonry" for mortar mixes.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 SETTING CAST STONE IN MORTAR

A. Set cast stone as indicated in TMS 604.

B. Set cast stone as indicated on Drawings. Set units accurately in locations indicated, with edges and faces aligned according to established relationships and indicated tolerances.

1. Install anchors, supports, fasteners, and other attachments indicated or necessary to secure units in place.
2. Coordinate installation of cast stone with installation of flashing specified in other Sections.

C. Wet joint surfaces thoroughly before applying mortar or setting in mortar.

D. Set units in full bed of mortar with full head joints unless otherwise indicated.

1. Set units with joints 1/4 to 3/8 inch wide unless otherwise indicated.
2. Build anchors and ties into mortar joints as units are set.
3. Fill dowel holes and anchor slots with mortar.
4. Fill collar joints solid as units are set.
5. Build concealed flashing into mortar joints as units are set.
6. Keep head joints in copings and between other units with exposed horizontal surfaces open to receive sealant.
7. Keep joints at shelf angles open to receive sealant.

E. Rake out joints for pointing with mortar to depths of not less than 3/4 inch. Rake joints to uniform depths with square bottoms and clean sides. Scrub faces of units to remove excess mortar as joints are raked.

F. Point mortar joints by placing and compacting mortar in layers not greater than 3/8 inch. Compact each layer thoroughly and allow it to become thumbprint hard before applying next layer.

G. Tool exposed joints slightly concave when thumbprint hard. Use a smooth plastic jointer larger than joint thickness.

H. Rake out joints for pointing with sealant to depths of not less than 3/4 inch. Scrub faces of units to remove excess mortar as joints are raked.

I. Point joints with sealant to comply with applicable requirements in Section 079200 "Joint Sealants."

1. Prime cast stone surfaces to receive sealant and install compressible backer rod in joints before applying sealant unless otherwise indicated.

J. Provide sealant joints at head joints of copings and other horizontal surfaces; at expansion, control, and pressure-relieving joints; and at locations indicated.

1. Keep joints free of mortar and other rigid materials.
2. Build in compressible foam-plastic joint fillers where indicated.
3. Form joint of width indicated, but not less than 3/8 inch.
4. Prime cast stone surfaces to receive sealant and install compressible backer rod in joints before applying sealant unless otherwise indicated.
5. Prepare and apply sealant of type and at locations indicated to comply with applicable requirements in Section 079200 "Joint Sealants."

3.3 INSTALLATION TOLERANCES

A. Variation from Plumb: Do not exceed1/8 inch in 10 ft.

B. Variation from Level: Do not exceed1/8 inch in 10 ft.

C. Variation in Joint Width: Do not vary joint thickness more than 1/8 inch in 36 inches or one-fourth of nominal joint width, whichever is less.

D. Variation in Plane between Adjacent Surfaces (Lipping): Do not vary from flush alignment with adjacent units or adjacent surfaces indicated to be flush with units by more than 1/16 inch, except where variation is due to warpage of units within tolerances specified.

3.4 ADJUSTING AND CLEANING

A. Remove and replace stained and otherwise damaged units and units not matching approved Samples. Cast stone may be repaired if methods and results are approved by Architect.

B. Replace units in a manner that results in cast stone matching approved Samples, complying with other requirements, and showing no evidence of replacement.

C. In-Progress Cleaning: Clean cast stone as work progresses.

1. Remove mortar fins and smears before tooling joints.
2. Remove excess sealant immediately, including spills, smears, and spatter.

D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed cast stone as follows:

1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
2. Test cleaning methods on sample; leave one sample uncleaned for comparison purposes. Obtain Architect's approval of sample cleaning before proceeding with cleaning of cast stone.
3. Protect adjacent surfaces from contact with cleaner by covering them with liquid strippable masking agent or polyethylene film and waterproof masking tape.

4. Wet surfaces with water before applying cleaners; remove cleaners promptly by rinsing thoroughly with clear water.
5. Clean cast stone with proprietary acidic cleaner applied according to manufacturer's written instructions.

END OF SECTION

SECTION 051200 - STRUCTURAL STEEL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Structural-steel materials.
2. Shrinkage-resistant grout.

B. Related Requirements:

1. Section 055000 "Metal Fabrications" for other steel items not defined as structural steel.
2. Section 099123 "Interior Painting" for painting requirements.

1.2 DEFINITIONS

A. Structural Steel: Elements of the structural frame indicated on Drawings and as described in ANSI/AISC 303.

1.3 COORDINATION

A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.

B. Coordinate installation of anchorage items to be embedded in or attached to other construction without delaying the Work. Provide setting diagrams, sheet metal templates, instructions, and directions for installation.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data:

1. Structural-steel materials.
2. High-strength, bolt-nut-washer assemblies.
3. Threaded rods.
4. Shop primer.

5. Shrinkage-resistant grout.

C. Shop Drawings: Show fabrication of structural-steel components.

1. Include details of cuts, connections, splices, camber, holes, and other pertinent data.
2. Include embedment Drawings.
3. Indicate welds by standard AWS symbols, distinguishing between shop and field welds, and show size, length, and type of each weld. Show backing bars that are to be removed and supplemental fillet welds where backing bars are to remain.
4. Indicate type, size, and length of bolts, distinguishing between shop and field bolts. Identify high-strength bolted connections.
5. Identify members not to be shop primed.

D. Welding Procedure Specifications (WPSs) and Procedure Qualification Records (PQRs): Provide in accordance with AWS D1.1/D1.1M for each welded joint whether prequalified or qualified by testing:

1. Power source (constant current or constant voltage).
2. Electrode manufacturer and trade name, for demand-critical welds.

1.6 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Welding certificates.

C. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.

D. Mill test reports for structural-steel materials, including chemical and physical properties.

E. Product Test Reports: For the following:

1. Bolts, nuts, and washers, including mechanical properties and chemical analysis.
2. Direct-tension indicators.
3. Tension-control, high-strength, bolt-nut-washer assemblies.

F. Survey of existing conditions.

G. Source quality-control reports.

H. Field quality-control reports.

1.7 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel in accordance with AWS D1.1/D1.1M.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Store materials to permit easy access for inspection and identification. Keep steel members off ground and spaced by using pallets, dunnage, or other supports and spacers. Protect steel members and packaged materials from corrosion and deterioration.

1. Do not store materials on structure in a manner that might cause distortion, damage, or overload to members or supporting structures. Repair or replace damaged materials or structures as directed.

B. Store fasteners in a protected place in sealed containers with manufacturer's labels intact.

1. Fasteners may be repackaged provided Owner's testing and inspecting agency observes repackaging and seals containers.
2. Clean and relubricate bolts and nuts that become dry or rusty before use.
3. Comply with manufacturers' written recommendations for cleaning and lubricating ASTM F3125/F3125M, Grade F1852 bolt assemblies and for retesting bolt assemblies after lubrication.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Comply with applicable provisions of the following specifications and documents:

1. ANSI/AISC 303.
2. RCSC's "Specification for Structural Joints Using High-Strength Bolts."

B. Connection Design Information:

1. Option 1: Connection designs have been completed and connections indicated on the Drawings.

C. Construction: Existing plan concrete masonry shear walls.

2.2 STRUCTURAL-STEEL MATERIALS

A. W-Shapes: ASTM A992/A992M.

B. Channels and Angles: ASTM A36/A36M.

C. Plate: ASTM A36/A36M.

D. Cold-Formed Hollow Structural Sections: ASTM A500/A500M, Grade C structural tubing.

E. Welding Electrodes: Comply with AWS requirements.

2.3 BOLTS AND CONNECTORS

A. Tension-Control, High-Strength Bolt-Nut-Washer Assemblies: ASTM F3125/F3125M, Grade F1852, Type 1, heavy-hex round head assemblies, consisting of steel structural bolts with splined ends; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers.

1. Finish: Plain.

2.4 PRIMER

A. Steel Primer:

1. Fabricator's standard lead- and chromate-free, nonasphaltic, rust-inhibiting primer complying with MPI#79 and compatible with topcoat.
2. Color: Gray.

2.5 SHRINKAGE-RESISTANT GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C1107/C1107M, factory-packaged, nonmetallic aggregate grout, noncorrosive and nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

2.6 FABRICATION

A. Structural Steel: Fabricate and assemble in shop to greatest extent possible. Fabricate in accordance with ANSI/AISC 303 and to ANSI/AISC 360.

1. Identify high-strength structural steel in accordance with ASTM A6/A6M and maintain markings until structural-steel framing has been erected.
2. Mark and match-mark materials for field assembly.
3. Complete structural-steel assemblies, including welding of units, before starting shop-priming operations.

B. Thermal Cutting: Perform thermal cutting by machine to greatest extent possible.

1. Plane thermally cut edges to be welded to comply with requirements in AWS D1.1/D1.1M.

C. Bolt Holes: Cut, drill,or punch standard bolt holes perpendicular to metal surfaces.

D. Finishing: Accurately finish ends of columns and other members transmitting bearing loads.

E. Cleaning: Clean and prepare steel surfaces that are to remain unpainted in accordance with SSPC-SP 2. or SSPC-SP 3.

F. Holes: Provide holes required for securing other work to structural steel and for other work to pass through steel members.

1. Cut, drill, or punch holes perpendicular to steel surfaces. Do not thermally cut bolt holes or enlarge holes by burning.
2. Baseplate Holes: Cut, drill, mechanically thermal cut, or punch holes perpendicular to steel surfaces.
3. Weld threaded nuts to framing and other specialty items indicated to receive other work.

2.7 SHOP CONNECTIONS

A. High-Strength Bolts: Shop install high-strength bolts in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for type of bolt and type of joint specified.

1. Joint Type: Pretensioned.

B. Weld Connections: Comply with AWS D1.1/D1.1M for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.

2.8 SHOP PRIMING

A. Shop prime steel surfaces, except the following:

1. Surfaces to be field welded.

B. Surface Preparation of Steel: Clean surfaces to be painted. Remove loose rust and mill scale and spatter, slag, or flux deposits. Prepare surfaces in accordance with the following specifications and standards:

1. SSPC-SP 2.
2. SSPC-SP 3.

C. Priming: Immediately after surface preparation, apply primer in accordance with manufacturer's written instructions and at rate recommended by SSPC to provide a minimum dry film thickness of 1.5 mils. Use priming methods that result in full coverage of joints, corners, edges, and exposed surfaces.

1. Stripe paint corners, crevices, bolts, welds, and sharp edges.
2. Apply two coats of shop paint to surfaces that are inaccessible after assembly or erection. Change color of second coat to distinguish it from first.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify, with certified steel erector present, elevations of concrete-bearing surfaces and locations of anchor rods, bearing plates, and other embedments for compliance with requirements.

1. Prepare a certified survey of existing conditions. Include bearing surfaces, anchor rods, bearing plates, and other embedments showing dimensions, locations, angles, and elevations.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Provide temporary shores, guys, braces, and other supports during erection to keep structural steel secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural steel, connections, and bracing are in place unless otherwise indicated on Drawings.

1. Do not remove temporary shoring supporting composite deck construction and structural-steel framing until cast-in-place concrete has attained its design compressive strength.

3.3 ERECTION

A. Set structural steel accurately in locations and to elevations indicated and in accordance with ANSI/AISC 303 and ANSI/AISC 360.

B. Bearing Plates: Clean masonry surfaces of bond-reducing materials, and roughen surfaces prior to setting plates. Clean bottom surface of plates.

1. Set plates for structural members on wedges, shims, or setting nuts as required.
2. Promptly pack shrinkage-resistant grout solidly between bearing surfaces and plates, so no voids remain. Neatly finish exposed surfaces; protect grout and allow to cure. Comply with manufacturer's written installation instructions for grouting.

C. Maintain erection tolerances of structural steel within ANSI/AISC 303.

D. Align and adjust various members that form part of complete frame or structure before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that are in permanent contact with members. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.

1. Level and plumb individual members of structure. Slope roof framing members to slopes indicated on Drawings.
2. Make allowances for difference between temperature at time of erection and mean temperature when structure is completed and in service.

E. Do not use thermal cutting during erection unless approved by Architect/Owner. Finish thermally cut sections within smoothness limits in AWS D1.1/D1.1M.

F. Do not enlarge unfair holes in members by burning or using drift pins. Ream holes that must be enlarged to admit bolts.

3.4 FIELD CONNECTIONS

A. High-Strength Bolts: Install high-strength bolts in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for bolt and joint type specified.

1. Joint Type: Pretensioned.

B. Weld Connections: Comply with AWS D1.1/D1.1M for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.

1. Comply with ANSI/AISC 303 and ANSI/AISC 360 for bearing, alignment, adequacy of temporary connections, and removal of paint on surfaces adjacent to field welds.

3.5 REPAIR

A. Touchup Painting:

1. Immediately after erection, clean exposed areas where primer is damaged or missing, and paint with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.

a. Clean and prepare surfaces by SSPC-SP 2 hand-tool cleaning or SSPC-SP 3 power-tool cleaning.

2. Cleaning and touchup painting are specified in Section 099123 "Interior Painting."

3.6 FIELD QUALITY CONTROL

A. Special Inspections: Owner will engage a special inspector to perform the following special inspections:

1. Verify structural-steel materials and inspect steel frame joint details.
2. Verify weld materials and inspect welds.
3. Verify connection materials and inspect high-strength bolted connections.

B. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

1. Bolted Connections: Inspect bolted connections in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts."
2. Welded Connections: Visually inspect field welds in accordance with AWS D1.1/D1.1M.

END OF SECTION

SECTION 053100 - STEEL DECKING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Roof deck.
2. Composite floor deck.

B. Related Requirements:

1. Section 033000 “Cast-in-Place Concrete” for light-weight structural concrete fill over steel deck.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data:

1. Roof deck.
2. Composite floor deck.

C. Shop Drawings:

1. Include layout and types of deck panels, anchorage details, special jointing, accessories, and attachments to other construction.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Welding certificates.

C. Product Certificates: For each type of steel deck.

D. Test and Evaluation Reports:

1. Product Test Reports: For tests performed by a qualified testing agency, indicating that each of the following complies with requirements:

a. Power-actuated mechanical fasteners.

2. Research Reports: For steel deck, from ICC-ES showing compliance with the building code.

E. Field Quality-Control Submittals:

1. Field quality-control reports.

F. Qualification Statements: For welding personnel and testing agency.

1.4 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel in accordance with SDI QA/QC and the following welding codes:

1. AWS D1.1/D1.1M.
2. AWS D1.3/D1.3M.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Protect steel deck from corrosion, deformation, and other damage during delivery, storage, and handling.

B. Store products in accordance with SDI MOC3. Stack steel deck on platforms or pallets and slope to provide drainage. Protect with a waterproof covering and ventilate to avoid condensation.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. AISI Specifications: Comply with calculated structural characteristics of steel deck in accordance with AISI S100.

2.2 ROOF DECK

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ASC Steel Deck; ASC Profiles, LLC.
2. Canam Buildings US Inc.; Canam Group Inc.
3. Cordeck.
4. DACS, Inc.
5. Epic Metals Corporation.
6. Marlyn Steel Decks, Inc.
7. Miami Metal Deck.
8. New Millennium Building Systems, LLC.
9. OEG Building Materials Inc.

10. Roof Deck, Inc.
11. Tristate Decking, Inc.
12. Valley Joist.
13. Vulcraft/Verco Group; a division of Nucor Corp.

B. Fabrication of Roof Deck: Fabricate panels, without top-flange stiffening grooves, to comply with SDI RD and with the following:

1. Galvanized-Steel Sheet: ASTM A653/A653M, Structural Steel (SS), Grade 80, zinc coating.
2. Deck Profile: Type WR, wide rib.
3. Profile Depth: 9/16 inches.
4. Design Uncoated-Steel Thickness: 0.0296 inches (22 gauge).
5. Side Laps: Overlapped.

2.3 FLOOR DECK

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ASC Steel Deck; ASC Profiles, LLC.
2. Canam Buildings US Inc.; Canam Group Inc.
3. Cordeck.
4. DACS, Inc.
5. Epic Metals Corporation.
6. Marlyn Steel Decks, Inc.
7. Miami Metal Deck.
8. New Millennium Building Systems, LLC.
9. OEG Building Materials Inc.
10. Roof Deck, Inc.
11. Tristate Decking, Inc.
12. Verco Decking, Inc.; a Nucor company.
13. Vulcraft Group; Division of Nucor Corp.
14. Vulcraft/Verco Group; a division of Nucor Corp.

B. Fabrication of Floor Deck: Fabricate panels, with integrally embossed or raised pattern ribs and interlocking side laps, to comply with SDI C, with the minimum section properties indicated, and with the following:

1. Galvanized-Steel Sheet: ASTM A653/A653M, Structural Steel (SS), Grade 80, G90 zinc coating.
2. Profile Depth: 9/16 inches.
3. Design Uncoated-Steel Thickness: 0.0296 inches (22 gauge).

2.4 ACCESSORIES

A. Provide manufacturer's standard accessory materials for deck that comply with requirements indicated.

B. Mechanical Fasteners: Corrosion-resistant, low-velocity, power-actuated or pneumatically driven carbon-steel fasteners; or self-drilling, self-threading screws.

C. Side-Lap Fasteners: Corrosion-resistant, hexagonal washer head; self-drilling, carbon-steel screws, No. 10 minimum diameter.

D. Flexible Closure Strips: Vulcanized, closed-cell, synthetic rubber.

E. Miscellaneous Sheet Metal Deck Accessories: Steel sheet, minimum yield strength of 33,000 psi, not less than 0.0359-inch design uncoated thickness, of same material and finish as deck; of profile indicated or required for application.

F. Pour Stops and Girder Fillers: Steel sheet, minimum yield strength of 33,000 psi, of same material and finish as deck, and of thickness and profile recommended by SDI standards for overhang and slab depth.

G. Column Closures, End Closures, Z-Closures, and Cover Plates: Steel sheet, of same material, finish, and thickness as deck unless otherwise indicated.

H. Galvanizing Repair Paint: ASTM A780/A780M.

I. Repair Paint: Manufacturer's standard rust-inhibitive primer of same color as primer.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine supporting frame and field conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Install deck panels and accessories in accordance with SDI C, SDI NC, and SDI RD, as applicable; manufacturer's written instructions; and requirements in this Section.

B. Locate deck bundles to prevent overloading of supporting members.

C. Place deck panels on supporting frame and adjust to final position with ends accurately aligned and bearing on supporting frame before being permanently fastened. Do not stretch or contract side-lap interlocks.

D. Place deck panels flat and square and fasten to supporting frame without warp or deflection.

E. Cut and neatly fit deck panels and accessories around openings and other work projecting through or adjacent to deck.

F. Provide additional reinforcement and closure pieces at openings as required for strength, continuity of deck, and support of other work.

G. Comply with AWS requirements and procedures for manual shielded metal arc welding, appearance and quality of welds, and methods used for correcting welding work.

3.3 INSTALLATION OF ROOF DECK

A. Fasten roof-deck panels to steel supporting members by arc spot (puddle) welds of the surface diameter indicated or arc seam welds with an equal perimeter that is not less than 1-1/2 inches long, and as follows:

1. Weld Diameter: 5/8 inch, nominal.
2. Weld Spacing: Weld edge and interior ribs of deck units with a minimum of two welds per deck unit at each support. Space welds 12 inches as indicated.

B. Side-Lap and Perimeter Edge Fastening: Fasten side laps and perimeter edges of panels between supports, at intervals indicated:

1. Mechanically fasten with self-drilling, No. 10 diameter or larger, carbon-steel screws.
2. Fasten with a minimum of 1-1/2-inch-long welds.

C. End Bearing: Install deck ends over supporting frame with a minimum end bearing of 1-1/2 inches, with end joints as follows:

1. End Joints: Lapped 2 inches minimum.

D. Flexible Closure Strips: Install flexible closure strips over partitions, walls, and where indicated. Install with adhesive in accordance with manufacturer's written instructions to ensure complete closure.

3.4 INSTALLATION OF FLOOR DECK

A. Fasten floor-deck panels to steel supporting members by arc spot (puddle) welds of the surface diameter indicated and as follows:

1. Weld Diameter: 3/4 inch, nominal.
2. Weld Spacing:

    a. Weld edge ribs of panels at each support. Space additional welds an average of 16 inches apart, but not more than 18 inches apart.
    b. Space and locate welds as indicated.

B. Side-Lap and Perimeter Edge Fastening: Fasten side laps and perimeter edges of panels between supports, at intervals not exceeding the lesser of one-half of the span or 36 inches, and as follows:

1. Mechanically fasten with self-drilling, No. 10 diameter or larger, carbon-steel screws.
2. Fasten with a minimum of 1-1/2-inch-long welds.

C. End Bearing: Install deck ends over supporting frame with a minimum end bearing of 1-1/2 inches, with end joints as follows:

1. End Joints: Lapped.

D. Pour Stops and Girder Fillers: Weld steel sheet pour stops and girder fillers to supporting structure in accordance with SDI recommendations unless otherwise indicated.

E. Floor-Deck Closures: Weld steel sheet column closures, cell closures, and Z-closures to deck, in accordance with SDI recommendations, to provide tight-fitting closures at open ends of ribs and sides of deck.

3.5 REPAIR

A. Galvanizing Repairs: Prepare and repair damaged galvanized coatings on both surfaces of deck with galvanized repair paint in accordance with ASTM A780/A780M and manufacturer's written instructions.

3.6 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.

B. Tests and Inspections:

1. Special inspections and qualification of welding special inspectors for cold-formed steel floor and roof deck in accordance with quality-assurance inspection requirements of SDI QA/QC.

a. Field welds will be subject to inspection.

2. Steel decking will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

END OF SECTION

SECTION 055000 - METAL FABRICATIONS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Miscellaneous framing and supports.
2. Metal bollards.
3. Exterior steel ladders.
4. Prefabricated cable fall arrest system.

B. Related Requirements:

1. Section 051200 "Structural Steel Framing" for steel framing, supports, door frames, and other steel items attached to the structural-steel framing.

1.2 COORDINATION

A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written instructions to ensure that shop primers and topcoats are compatible with one another.

B. Coordinate installation of metal fabrications that are anchored to or that receive other work. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 “Administrative Provisions” and the individual sections specifying the work.

B. Product Data: For the following:

1. Fasteners.
2. Shop primers.
3. Shrinkage-resisting grout.
4. Slotted channel framing.
5. Metal bollards.

C. Shop Drawings: Show fabrication and installation details. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items. Provide Shop Drawings for the following:

1. Miscellaneous framing and supports for applications where framing and supports are not specified in other Sections.
2. Metal bollards.
3. Exterior steel ladders.
4. Prefabricated cable fall arrest system.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 “Administrative Provisions” and the individual sections specifying the work.

B. Certificates:

1. Welding certificates.
2. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.

C. Research Reports: For post-installed anchors.

1.5 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel in accordance with the following welding codes:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 METALS

A. Metal Surfaces, General: Provide materials with smooth, flat surfaces unless otherwise indicated. For metal fabrications exposed to view in the completed Work, provide materials without seam marks, roller marks, rolled trade names, or blemishes.

B. Steel Plates, Shapes, and Bars: ASTM A36/A36M.

C. Steel Tubing: ASTM A500/A500M, cold-formed steel tubing.

D. Steel Pipe: ASTM A53/A53M, Standard Weight (Schedule 40) unless otherwise indicated.

E. Slotted Channel Framing: Cold-formed metal box channels (struts) complying with MFMA-4.

1. Size of Channels: 1-5/8 by 1-5/8 inches.
2. Galvanized Steel: ASTM A653/A653M, structural steel, Grade 33, with G90 coating; 0.108-inch nominal thickness.
3. Cold-Rolled Steel: ASTM A1008/A1008M, structural steel, Grade 33; 0.0966-inch minimum thickness; hot-dip galvanized after fabrication.

2.3 FASTENERS

A. Steel Bolts and Nuts: Regular hexagon-head bolts, ASTM A307, Grade A; with hex nuts, ASTM A563; and, where indicated, flat washers.

B. Anchors, General: Capable of sustaining, without failure, a load equal to six times the load imposed when installed in unit masonry and four times the load imposed when installed in concrete, as determined by testing in accordance with ASTM E488/E488M, conducted by a qualified independent testing agency.

C. Cast-in-Place Anchors in Concrete: Either threaded or wedge type unless otherwise indicated; galvanized ferrous castings, either ASTM A47/A47M malleable iron or ASTM A27/A27M cast steel. Provide bolts, washers, and shims as needed, all hot-dip galvanized per ASTM F2329/F2329M.

D. Post-Installed Anchors: Torque-controlled expansion anchors or chemical anchors.

1. Material for Interior Locations: Carbon-steel components zinc plated to comply with ASTM B633 or ASTM F1941/F1941M, Class Fe/Zn 5, unless otherwise indicated.

2.4 MISCELLANEOUS MATERIALS

A. Universal Shop Primer: Fast-curing, lead- and chromate-free, universal modified-alkyd primer complying with MPI#79 and compatible with topcoat.

1. Use primer containing pigments that make it easily distinguishable from zinc-rich primer.

B. Water-Based Primer: Emulsion type, anticorrosive primer for mildly corrosive environments that is resistant to flash rusting when applied to cleaned steel, complying with MPI#107 and compatible with topcoat.

C. Epoxy Zinc-Rich Primer: Complying with MPI#20 and compatible with topcoat.

D. Shop Primer for Galvanized Steel: Primer formulated for exterior use over zinc-coated metal and compatible with finish paint systems indicated.

E. Galvanizing Repair Paint: High-zinc-dust-content paint complying with SSPC-Paint 20 and compatible with paints specified to be used over it.

F. Shrinkage-Resistant Grout: Factory-packaged, nonmetallic, nonstaining, noncorrosive, nongaseous grout complying with ASTM C1107/C1107M. Provide grout specifically recommended by manufacturer for interior and exterior applications.

G. Concrete: Comply with requirements in Section 033000 "Cast-in-Place Concrete" for normal-weight, air-entrained concrete with a minimum 28-day compressive strength of 5000 psi.

2.5 FABRICATION, GENERAL

A. Shop Assembly: Preassemble items in the shop to greatest extent possible. Disassemble units only as necessary for shipping and handling limitations. Use connections that maintain structural value of joined pieces. Clearly mark units for reassembly and coordinated installation.

B. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges to a radius of approximately 1/32 inch unless otherwise indicated. Remove sharp or rough areas on exposed surfaces.

C. Form bent-metal corners to smallest radius possible without causing grain separation or otherwise impairing work.

D. Form exposed work with accurate angles and surfaces and straight edges.

E. Weld corners and seams continuously to comply with the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.

F. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners or welds where possible. Where exposed fasteners are required, use Phillips flat-head (countersunk) fasteners unless otherwise indicated. Locate joints where least conspicuous.

G. Fabricate seams and other connections that are exposed to weather in a manner to exclude water. Provide weep holes where water may accumulate.

H. Cut, reinforce, drill, and tap metal fabrications as indicated to receive finish hardware, screws, and similar items.

I. Provide for anchorage of type indicated; coordinate with supporting structure. Space anchoring devices to secure metal fabrications rigidly in place and to support indicated loads.

2.6 MISCELLANEOUS FRAMING AND SUPPORTS

A. General: Provide steel framing and supports not specified in other Sections as needed to complete the Work.

B. Fabricate units from steel shapes, plates, and bars of welded construction unless otherwise indicated. Fabricate to sizes, shapes, and profiles indicated and as necessary to receive adjacent construction.

1. Fabricate units from slotted channel framing where indicated.
2. Furnish inserts for units installed after concrete is placed.

C. Galvanize miscellaneous framing and supports where indicated.

D. Prime miscellaneous framing and supports with zinc-rich primer where indicated.

2.7 METAL BOLLARDS

A. Fabricate metal bollards from steel shapes, as indicated.

B. Galvanize steel bollards.

2.8 EXTERIOR GALVANIZED STEEL LADDERS

A. Fabricate ladders from steel shapes as indicated.

B. Hot-dipped galvanized finish after fabrication.

C. Heavy duty one-piece welded assembly.

D. Load Capacity 300 lbs.

E. Side member Dimensions: 3/4" x 3" steel plate.

F. Climbing Rungs: 3/4" x 3" flat steel plate.

G. Stand-off Bracket length: 7 inches.

H. OSHA 1910.27 and 1926.150 compliant.

2.9 PREFABRICATED CABLE LADDER FALL ARREST SYSTEM

A. Basis of Design Product: 3M DBI SALA Lad-Saf Cable Vertical Safety System.

B. Galvanized Steel.

C. 3/8" galvanized cable.

D. Detachable Cable Sleeve.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installing metal fabrications. Set metal fabrications accurately in location, alignment, and elevation; with edges and surfaces level, plumb, true, and free of rack; and measured from established lines and levels.

B. Fit exposed connections accurately together to form hairline joints. Weld connections that are not to be left as exposed joints but cannot be shop welded because of shipping size limitations. Do not weld, cut, or abrade surfaces of exterior units that have been hot-dip galvanized after fabrication and are for bolted or screwed field connections.

C. Field Welding: Comply with the following requirements:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.

D. Fastening to In-Place Construction: Provide anchorage devices and fasteners where metal fabrications are required to be fastened to in-place construction. Provide threaded fasteners for use with concrete and masonry inserts, toggle bolts, through bolts, lag screws, wood screws, and other connectors.

E. Provide temporary bracing or anchors in formwork for items that are to be built into concrete or similar construction.

3.2 INSTALLATION OF MISCELLANEOUS FRAMING AND SUPPORTS

A. General: Install framing and supports to comply with requirements of items being supported, including manufacturers' written instructions and requirements indicated on Shop Drawings.

B. Anchor supports for overhead doors securely to, and rigidly brace from, building structure.

3.3 INSTALLATION OF METAL BOLLARDS

A. Anchor bollards in concrete as indicated.

B. Fill bollards solidly with concrete, mounding top surface to shed water.

3.4 INSTALLATION OF METAL BOLLARDS (SURFACE-MOUNTED)

A. Anchor bollards to concrete construction to comply with manufacturer’s written instruction.

3.5 INSTALLATION OF EXTERIOR STEEL LADDERS

A. Anchor ladders to brick masonry construction.

3.6 INSTALLATION OF PREMANUFACTURED CABLE LADDER FALL ARREST SYSTEM

A. Fasten to steel ladder using manufacturer's standard hardware.

3.7 REPAIRS

A. Touchup Painting:

1. Immediately after erection, clean field welds, bolted connections, and abraded areas. Paint uncoated and abraded areas with same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.

a. Apply by brush or spray to provide a minimum 2.0-mil dry film thickness.

B. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas and repair galvanizing to comply with ASTM A780/A780M.

END OF SECTION

SECTION 055213 - PIPE AND TUBE RAILINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Steel railings and handrails.
2. Infill panel system for existing stair guardrails.
3. Add-on handrail for existing stair guardrails.
4. Wall mounted handrails.
5. Roof edge protection guardrail system.
6. Ladder safety roof corral guardrails and gates.
7. Exterior guardrails.

1.2 COORDINATION

A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.

B. Coordinate installation of anchorages for railings. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data:

1. Fasteners.
2. Post-installed anchors.
3. Handrail brackets.
4. Shop primer.
5. Intermediate coats and topcoats.
6. Bituminous paint.
7. Nonshrink, nonmetallic grout.
8. Anchoring cement.
9. Metal finishes.
10. Paint products.
11. Escutcheon plate.

C. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.

D. Samples for Initial Selection: For products involving selection of color, texture, or design, including mechanical finishes.

E. Samples for Verification: For each type of exposed finish required.

1. Sections of each distinctly different linear railing member, including handrails, top rails, posts, and balusters, infill panels, including finish.
2. Fittings and brackets.
3. Assembled Sample of railing system, made from full-size components, including top rail, post, handrail, and infill. Sample need not be full height.

a. Show method of connecting and finishing members at intersections.

F. Delegated Design Submittal: For railings, including analysis data signed and sealed by the qualified engineer in the State or Maine responsible for their preparation.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Qualification Data: For testing agency.

C. Welding certificates.

D. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.

E. Product Test Reports: For tests on railings performed by a qualified testing agency, in accordance with ASTM E894 and ASTM E935.

F. Research Reports: For post-installed anchors, from ICC-ES or other qualified testing agency acceptable to authorities having jurisdiction.

1.5 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel in accordance with the following:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."

1.6 DELIVERY, STORAGE, AND HANDLING

A. Protect mechanical finishes on exposed surfaces of railings from damage by applying a strippable, temporary protective covering before shipping.

1.7 FIELD CONDITIONS

A. Field Measurements: Verify actual locations of walls and other construction contiguous with railings by field measurements before fabrication.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in 014000 "Quality Requirements," to design railings, including attachment to building construction.

B. Structural Performance: Railings, including attachment to building construction, withstand the effects of the gravity loads and the following loads and stresses within limits and under conditions indicated:

1. Handrails and Top Rails of Guards:

a. Uniform load of 50 lbf/ft applied in any direction.
b. Concentrated load of 200 lbf applied in any direction.
c. Uniform and concentrated loads need not be assumed to act concurrently.

2. Infill of Guards:

a. Concentrated load of 50 lbf applied horizontally on an area of 1 sq. ft.
b. Infill load and other loads need not be assumed to act concurrently.

3. Design Railings indicated as removable and associated connections.

C. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes:

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 METALS, GENERAL

A. Metal Surfaces, General: Provide materials with smooth surfaces, without seam marks, roller marks, rolled trade names, stains, discolorations, or blemishes.

B. Brackets, Flanges, and Anchors: Cast or formed metal of same type of material and finish as supported rails unless otherwise indicated.

1. Provide type of bracket with predrilled hole for exposed bolt anchorage and that provides 2-1/4-inch clearance from inside face of handrail to finished wall surface, unless indicated otherwise.

2.3 STEEL RAILINGS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Hollaender Mfg. Co.
2. Trex Commercial Products, Inc.
3. Tuttle, a Dant Clayton Division.
4. VIVA Railings, LLC.
5. Wagner Companies (The); R&B Wagner, Inc.

B. Source Limitations: Obtain each type of railing from single source from single manufacturer.

C. Tubing: ASTM A500/A500M (cold formed).

D. Pipe: ASTM A53/A53M, Type F or Type S, Grade A, Standard Weight (Schedule 40), unless another grade and weight are required by structural loads, or as indicated.

1. Provide galvanized finish for all exterior installations and where indicated.

E. Plates, Shapes, and Bars: ASTM A36/A36M.

F. Cast Iron Fittings: Either gray iron, ASTM A48/A48M, or malleable iron, ASTM A47/A47M, unless otherwise indicated.

2.4 FIXED ROOF EDGE PROTECTION GUARDRAILS

A. Provide galvanized railings, including pipe railings, sleeves, and baseplates.

1. System shall have top and mid rail in accordance with OSHA Standards – 29 CFR 1910.23(a)(2).
2. Structural Load: 200 lb, minimum, in any direction to all components, in accordance with OSHA Regulation 29 CFR 1926.502.
3. Height: 42 inches, minimum from roof surface.
4. Railings 1-5/8 inch O.D. hot rolled pickled electric weld tubing, free of sharp edges and snag points with hot-dipped galvanized finish.
5. Sleeves and baseplates as indicated on drawings.

2.5 LADDER SAFETY ROOF GUARDRAILS AND GATES

A. Provide complete non-penetrating standing pedestrian egress barrier system on roof, including pipe railings, bases, and fittings. Basis of Design is Ladder Defense as manufactured by Blue Water Manufacturing.

1. System shall have top and mid rail in accordance with OSHA Standards - 29 CFR 1910.23(a)(2).
2. Structural Load: 200 lb, minimum, in any direction to all components, in accordance with OSHA Regulation 29 CFR 1926.502.
3. Height: 42 inches, minimum.
4. Railings 1-5/8 inch O.D. hot rolled pickled electric weld tubing, free of sharp edges and snag points with hot-dipped galvanized finish.
5. Mounting Bases: Plates: Manufacturers non-penetrating steel plates with hot-dipped galvanized finish. Provide rubber pads on bottom of plates.

6. Receiver Posts: Shall have a positive locking system into slots that allow rails to be mounted in any direction. Friction locking systems are not allowed. Receiver posts shall have drain holes. Single posts shall be provided at each base (architectural assembly) with fittings to top and midrails. Double posts are not acceptable.
7. Hardware: Manufacturer's standard installation hardware.
8. Gates: Gates to be provided by manufacturer of ladder safety roof guardrail system.

2.6 INFILL FOR RAILINGS

A. Panel:

1. Welded wire steel mesh infill panels constructed from 0.120-inch diameter steel wire, and every second wire is welded within the steel hem frame.
2. Pattern: 2-inch by 2-inch square.
3. Panels to be attached to railing using panel manufacturer's recommended clips and hardware.

B. Manufacturers:

1. Basis-of-Design Railing Product: Subject to compliance with requirements, provide Steel Wire Mesh Infill Panels as manufactured and assembled by Hollaender® Manufacturing or an approved equivalent. Single source manufacturer is required.

C. Metals, General:

1. Brackets, Flanges, and Anchors: Cast or formed metal of same type of material and finish as infill panels, unless otherwise indicated.

D. Panel Finish:

1. Steel Wire Mesh Infill Panels:

a. Finish: Powder coat. Entire panel shall be powder coated with Silver powder coat, or equivalent powder coat color of Architect's choice: As selected from manufacturer's full line. Powder to be TGIC Polyester, minimum AAMA 2604.

2.7 HANDRAIL FOR ADA RAMPS OR STAIRWAYS

A. Ramps that have a drop off of 30 inches or more on the side require guardrail, per above spec. Ramps with a rise greater than 6 inches shall have handrails on both sides.

B. Stairways shall have handrails on both sides.

C. Handrail will be attached to the guardrail sections using infill panel manufacturer's adjustable brackets.

D. Handrail will be installed at a height of 34-38 inches above ramp surface or stair tread nosings.

E. Handrail will be steel Schedule 40, 1-1/2 inches IPS nominal (1.90 inch OD), unless indicated otherwise, and shall have a continuous surface. Where necessary, lengths of the handrail will be spliced using internal locking splices.

F. Handrails shall return to a wall, guard or walking surface. If returning to the guard, post return swivel shall be used to connect the end of the handrail to the guardrail post.

2.8 FASTENERS

A. Fastener Materials:

1. Ungalvanized-Steel Railing Components: Plated steel fasteners complying with ASTM F1941/F1941M, Class Fe/Zn 5 for zinc coating.
2. Hot-Dip Galvanized Railing Components: Type 304 stainless steel or hot-dip zinc-coated steel fasteners complying with ASTM A153/A153M or ASTM F2329/F2329M for zinc coating.
3. Finish exposed fasteners to match appearance, including color and texture, of railings.

B. Fasteners for Anchoring Railings to Other Construction: Select fasteners of type, grade, and class required to produce connections suitable for anchoring railings to other types of construction and capable of withstanding design loads.

C. Fasteners for Interconnecting Railing Components:

1. Provide concealed fasteners for interconnecting railing components and for attaching them to other work, unless exposed fasteners are unavoidable or are the standard fastening method for railings indicated.

D. Post-Installed Anchors: Fastener systems with working capacity greater than or equal to the design load, according to an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC193.

1. Material for Interior Locations: Carbon-steel components zinc-plated to comply with ASTM B633 or ASTM F1941/F1941M, Class Fe/Zn 5, unless otherwise indicated.

E. Fasten infill panels to rails and posts with manufacturer’s standard installation hardware.

2.9 MISCELLANEOUS MATERIALS

A. Handrail Brackets: Cast iron or galvanized steel center of handrail 2-1/2 inches from wall, unless indicated otherwise.

B. Welding Rods and Bare Electrodes: Select in accordance with AWS specifications for metal alloy welded.

1. For railings, provide type and alloy as recommended by producer of metal to be welded and as required for color match, strength, and compatibility in fabricated items.

C. Etching Cleaner for Galvanized Metal: Complying with MPI#25.

D. Galvanizing Repair Paint: High-zinc-dust-content paint, complying with SSPC-Paint 20 and compatible with paints specified to be used over it.

E. Shop Primers: Provide primers that comply with Section 099123 "Interior Painting."

F. Universal Shop Primer: Fast-curing, lead- and chromate-free, universal modified-alkyd primer complying with MPI#79 and compatible with topcoat.

1. Use primer containing pigments that make it easily distinguishable from zinc-rich primer.

G. Epoxy Zinc-Rich Primer: Complying with MPI#20 and compatible with topcoat.

H. Shop Primer for Galvanized Steel: Primer formulated for exterior use over zinc-coated metal and compatible with finish paint systems indicated.

I. Intermediate Coats and Topcoats: Provide products that comply with Section 099123 "Interior Painting."

J. Nonshrink, Nonmetallic Grout: Factory-packaged, nonstaining, noncorrosive, nongaseous grout, complying with ASTM C1107/C1107M. Provide grout specifically recommended by manufacturer for interior and exterior applications.

K. Anchoring Cement: Factory-packaged, nonshrink, nonstaining, hydraulic-controlled expansion cement formulation for mixing with water at Project site to create pourable anchoring, patching, and grouting compound.

1. Water-Resistant Product: At exterior locations provide formulation that is resistant to erosion from water exposure without needing protection by a sealer or waterproof coating and that is recommended by manufacturer for exterior use.

2.10 FABRICATION

A. General: Fabricate railings to comply with requirements indicated for design, dimensions, member sizes and spacing, details, finish, and anchorage, but not less than that required to support structural loads.

B. Shop assemble railings to greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations.

1. Clearly mark units for reassembly and coordinated installation.
2. Use connections that maintain structural value of joined pieces.

C. Cut, drill, and punch metals cleanly and accurately.

1. Remove burrs and ease edges to a radius of approximately 1/32 inch unless otherwise indicated.
2. Remove sharp or rough areas on exposed surfaces.

D. Form work true to line and level with accurate angles and surfaces.

E. Fabricate connections that are exposed to weather in a manner that excludes water.

1. Provide weep holes where water may accumulate.
2. Locate weep holes in inconspicuous locations.

F. Cut, reinforce, drill, and tap as indicated to receive finish hardware, screws, and similar items.

G. Connections: Fabricate railings with welded connections unless otherwise indicated.

H. Welded Connections: Cope components at connections to provide close fit, or use fittings designed for this purpose. Weld all around at connections, including at fittings.

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove flux immediately.
4. At exposed connections, finish exposed welds to comply with NOMMA's "Voluntary Joint Finish Standards" for Finish #2 welds; good appearance, completely sanded joint, some undercutting and pinholes okay.

I. Nonwelded Connections: Connect members with concealed mechanical fasteners and fittings. Fabricate members and fittings to produce flush, smooth, rigid, hairline joints.

1. Fabricate splice joints for field connection, using an epoxy structural adhesive, if this is manufacturer's standard splicing method.

J. Form changes in direction as follows:

1. As detailed.
2. By radius bends of radius indicated or by inserting prefabricated elbow fittings of radius indicated.
3. By bending to smallest radius that will not result in distortion of railing member.

K. Bend members in jigs to produce uniform curvature for each configuration required. Maintain cross section of member throughout entire bend without buckling, twisting, cracking, or otherwise deforming exposed surfaces of components.

L. Close exposed ends of hollow railing members with prefabricated cap and end fittings of same metal and finish as railings.

M. Provide wall returns at ends of wall-mounted handrails unless otherwise indicated. Close ends of returns unless clearance between end of rail and wall is 1/4 inch or less.

N. Brackets, Flanges, Fittings, and Anchors: Provide wall brackets, flanges, miscellaneous fittings, and anchors to interconnect railing members to other work unless otherwise indicated.

1. At brackets and fittings fastened to plaster or gypsum board partitions, provide crush-resistant fillers or other means to transfer loads through wall finishes to structural supports and prevent bracket or fitting rotation and crushing of substrate.

O. Provide inserts and other anchorage devices for connecting railings to concrete work.

1. Fabricate anchorage devices capable of withstanding loads imposed by railings.
2. Coordinate anchorage devices with supporting structure.

P. For railing posts set in concrete, provide stainless steel sleeves not less than 6 inches long with inside dimensions not less than 1/2 inch greater than outside dimensions of post, with metal plate forming bottom closure, unless indicated otherwise.

Q. For removable railing posts, fabricate slip-fit sockets from stainless steel tube or pipe whose ID is sized for a close fit with posts; limit movement of post without lateral load, measured at top, to not more than one-fortieth of post height.

1. Provide socket covers designed and fabricated to resist being dislodged.
2. Provide chain with eye, snap hook, and staple across gaps formed by removable railing sections at locations indicated. Fabricate from same metal as railings.

R. Toe Boards: Where indicated, provide toe boards at railings around openings and at edge of open-sided floors and platforms. Fabricate to dimensions and details indicated.

2.11 STEEL AND IRON FINISHES

A. At exterior locations, provide hot-dipped galvanized-steel railings, provide hot-dipped galvanized ferrous-metal fittings, brackets, fasteners, and sleeves; hot-dip galvanize anchors to be embedded in exterior concrete or masonry.

B. At interior locations, provide factory prime finish for field painting.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine plaster and gypsum board assemblies, where reinforced to receive anchors, to verify that locations of concealed reinforcements are clearly marked for Installer. Locate reinforcements and mark locations if not already done.

3.2 INSTALLATION, GENERAL

A. Perform cutting, drilling, and fitting required for installing railings.

1. Fit exposed connections together to form tight, hairline joints.
2. Install railings level, plumb, square, true to line; without distortion, warp, or rack.
3. Set railings accurately in location, alignment, and elevation; measured from established lines and levels.
4. Do not weld, cut, or abrade surfaces of railing components that are coated or finished after fabrication and that are intended for field connection by mechanical or other means without further cutting or fitting.
5. Set posts plumb within a tolerance of 1/16 inch in 3 feet.
6. Align rails so variations from level for horizontal members and variations from parallel with rake of steps and ramps for sloping members do not exceed 1/4 inch in 12 feet.

B. Control of Corrosion: Prevent galvanic action and other forms of corrosion by insulating metals and other materials from direct contact with incompatible materials.

C. Adjust railings before anchoring to ensure matching alignment at abutting joints.

D. Fastening to In-Place Construction: Use anchorage devices and fasteners where necessary for securing railings and for properly transferring loads to in-place construction.

3.3 RAILING CONNECTIONS

A. Nonwelded Connections: Use mechanical or adhesive joints for permanently connecting railing components. Use wood blocks and padding to prevent damage to railing members and fittings. Seal recessed holes of exposed locking screws, using plastic cement filler colored to match finish of railings.

B. Welded Connections: Use fully welded joints for permanently connecting railing components. Comply with requirements for welded connections in "Fabrication" Article, whether welding is performed in the shop or in the field.

3.4 ANCHORING POSTS

A. Form or core-drill holes not less than 5 inches deep and 3/4 inch larger than OD of post for installing posts in concrete. Clean holes of loose material, insert posts, and fill annular space between post and concrete with nonshrink, nonmetallic grout, mixed and placed to comply with anchoring material manufacturer's written instructions.

B. Cover anchorage joint with flange of same metal as post, welded to post after placing anchoring material.

C. Anchor posts to metal surfaces with flanges, angle type, or floor type, as required by conditions, connected to posts and to metal supporting members as follows:

1. For steel railings, weld flanges to post and bolt to metal supporting surfaces.

D. Install removable railing sections, where indicated, in slip-fit stainless steel sockets cast in concrete.

3.5 ATTACHING RAILINGS

A. Anchor railing ends to concrete with flanges connected to railing ends and anchored to wall construction with anchors and bolts.

B. Attach handrails to walls with wall brackets, except where end flanges are used. Provide brackets with 1-1/2-inch clearance from inside face of handrail and finished wall surface, unless otherwise indicated.

1. Use type of bracket with predrilled hole for exposed bolt anchorage.
2. Locate brackets as indicated or, if not indicated, at spacing required to support structural loads.

C. Secure wall brackets and railing end flanges to building construction as follows:

1. For concrete anchorage, use drilled-in expansion shields and hanger or lag bolts.
2. For steel-framed partitions, use hanger or lag bolts set into fire-retardant-treated wood backing between studs. Coordinate with stud installation to locate backing members.
3. For steel-framed partitions, fasten brackets directly to steel framing or concealed steel reinforcements, using self-tapping screws of size and type required to support structural loads.
4. For steel-framed partitions, use toggle bolts installed through flanges of steel framing or through concealed steel reinforcements.

D. Install railing gates level, plumb, and secure for full opening without interference.

1. Attach hardware using tamper-resistant or concealed means.
2. Adjust hardware for smooth operation.

3.6 REPAIR

A. Touchup Painting:

1. Immediately after erection, clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.

a. Apply by brush or spray to provide a minimum 2.0-mil dry film thickness.

2. Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint are specified in Section 099123 "Interior Painting."

3.7 CLEANING

A. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas, and repair galvanizing to comply with ASTM A780/A780M.

3.8 PROTECTION

A. Protect finishes of railings from damage during construction period with temporary protective coverings approved by railing manufacturer. Remove protective coverings at time of Substantial Completion.

B. Restore finishes damaged during installation and construction period, so no evidence remains of correction work. Return items that cannot be refinished in the field to the shop; make required alterations and refinish entire unit, or provide new units.

END OF SECTION

SECTION 061000 - ROUGH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Wood products.
2. Wood-preservative-treated lumber.
3. Fire-retardant-treated lumber.
4. Dimension lumber framing.
5. Miscellaneous lumber.
6. Plywood backing panels.

B. Related Requirements:

1. Section 061600 "Sheathing" for sheathing, subflooring, and underlayment.

1.2 DEFINITIONS

A. Boards or Strips: Lumber of less than 2 inches nominal size in least dimension.

B. Dimension Lumber: Lumber of 2 inches nominal size or greater but less than 5 inches nominal size in least dimension.

C. Exposed Framing: Framing not concealed by other construction.

D. Lumber grading agencies, and abbreviations used to reference them, include the following:

1. NeLMA: Northeastern Lumber Manufacturers' Association.
2. NLGA: National Lumber Grades Authority.
3. SPIB: The Southern Pine Inspection Bureau.
4. WCLIB: West Coast Lumber Inspection Bureau.
5. WWPA: Western Wood Products Association.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used and net amount of preservative retained.

2. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Include physical properties of treated materials based on testing by a qualified independent testing agency.
3. For fire-retardant treatments, include physical properties of treated lumber both before and after exposure to elevated temperatures, based on testing by a qualified independent testing agency in accordance with ASTM D5664.
4. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Material Certificates:

1. For dimension lumber specified to comply with minimum allowable unit stresses. Indicate species and grade selected for each use and design values approved by the ALSC Board of Review.
2. For preservative-treated wood products. Indicate type of preservative used and net amount of preservative retained.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Stack wood products flat with spacers beneath and between each bundle to provide air circulation. Protect wood products from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS

A. Lumber: Comply with DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, comply with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Grade lumber by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.

1. Factory mark each piece of lumber with grade stamp of grading agency.
2. For exposed lumber indicated to receive a stained or natural finish, mark grade stamp on end or back of each piece.
3. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry wood products.
4. Dress lumber, S4S, unless otherwise indicated.

B. Maximum Moisture Content:

1. Boards: 15 percent.
2. Dimension Lumber: 15 percent for 2-inch nominal thickness or less; 19 percent for more than 2-inch nominal thickness unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED LUMBER

A. Preservative Treatment by Pressure Process: AWPA U1, Use categories as follows:

1. UC2: Interior construction not in contact with ground but may be subject to moisture. Include the following items:

    a. Wood sills, sleepers, blocking, furring, stripping, and similar concealed members in contact with masonry or concrete.
    b. Wood framing and furring attached directly to the interior of below-grade exterior masonry or concrete walls.
    c. Wood floor plates that are installed over concrete slabs-on-grade.
    d. Wood millwork.

2. UC3A (All Other Commodity Specifications): Coated products excluding sawn products in exterior construction not in contact with ground, exposed to all weather cycles but protected from liquid water. Include the following items:

    a. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
    b. Wood floor plates that are installed over concrete slabs-on-grade.
    c. Wood siding and trim.

3. UC3B (Commodity Specification A): Uncoated sawn products in exterior construction not in contact with ground, exposed to all weather cycles including intermittent wetting but with sufficient air circulation for wood to dry. Excludes sawn products not in contact with ground but with ground contact-type hazards. Include the following items:

    a. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
    b. Wood decking, railings, and joists and beams for rooftop stairs.

4. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.
5. After treatment, redry dimension lumber to 19 percent maximum moisture content.

B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or that does not comply with requirements for untreated material.

C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.

D. Application: Treat items indicated on Drawings, and the following:

1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
2. Wood sills, sleepers, blocking, and similar concealed members in contact with masonry or concrete.
3. Wood framing and furring attached directly to the interior of below-grade exterior masonry or concrete walls.
4. Wood floor plates that are installed over concrete slabs-on-grade.

2.3 FIRE-RETARDANT-TREATED LUMBER

A. General: Where fire-retardant-treated materials are indicated, materials are to comply with requirements in this article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.

B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Products with a flame-spread index of 25 or less when tested in accordance with ASTM E84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet beyond the centerline of the burners at any time during the test.

1. Treatment is not to promote corrosion of metal fasteners.
2. Interior Type A: Treated materials are to have a moisture content of 28 percent or less when tested in accordance with ASTM D3201/D3201M at 92 percent relative humidity. Use where exterior type is not indicated.
3. Design Value Adjustment Factors: Treated lumber is to be tested according to ASTM D5664 and design value adjustment factors are to be calculated according to ASTM D6841.

C. Kiln-dry lumber after treatment to maximum moisture content of 19 percent. Kiln-dry plywood after treatment to maximum moisture content of 15 percent.

D. Identify fire-retardant-treated wood with appropriate classification marking of qualified testing agency and other information required by authorities having jurisdiction.

E. Application: Treat items indicated on Drawings, and the following:

1. Concealed blocking.
2. Plywood backing panels.

2.4 MISCELLANEOUS LUMBER

A. Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:

1. Blocking.
2. Nailers.
3. Rooftop equipment bases and support curbs.
4. Cants.
5. Furring.

6. Grounds.
7. Utility shelving.

B. Dimension Lumber Items: Standard, Stud, or No. 3 grade lumber of any of the following species:

1. Hem-fir (north); NLGA.
2. Spruce-pine-fir; NLGA.
3. Northern species; NLGA.
4. Eastern softwoods; NeLMA.

C. Utility Shelving: Lumber with 15 percent maximum moisture content of any of the following species and grades:

1. Eastern white pine, Idaho white, lodgepole, ponderosa, or sugar pine; Premium or No. 2 Common (Sterling) grade; NeLMA, NLGA, WCLIB, or WWPA.
2. Mixed southern pine or southern pine; No. 1 grade; SPIB.
3. Hem-fir or hem-fir (north); Select Merchantable or No. 1 Common grade; NLGA, WCLIB, or WWPA.

D. Concealed Boards: 15 percent maximum moisture content and any of the following species and grades:

1. Hem-fir or hem-fir (north); Construction or No. 2 Common grade; NLGA, WCLIB, or WWPA.
2. Eastern softwoods; No. 2 Common grade; NeLMA.
3. Northern species; No. 2 Common grade; NLGA.

E. For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to eliminate defects that will interfere with its attachment and purpose.

F. For furring strips for installing plywood or hardboard paneling, select boards with no knots capable of producing bent-over nails and damage to paneling.

2.5 PLYWOOD BACKING PANELS

A. Equipment Backing Panels: Plywood, DOC PS 1, Exterior, A-C, fire-retardant treated, in thickness indicated or, if not indicated, not less than 3/4-inch nominal thickness.

2.6 FASTENERS

A. General: Fasteners are to be of size and type indicated and comply with requirements specified in this article for material and manufacture. Provide nails or screws, in sufficient length, to penetrate not less than 1-1/2 inches into wood substrate.

1. Where rough carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A153/A153M or ASTM F2329.

B. Nails, Brads, and Staples: ASTM F1667.

C. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.

2.7 METAL FRAMING ANCHORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. MiTek Industries, Inc.
2. Simpson Strong-Tie Co., Inc.
3. Tamlyn

B. Materials: Unless otherwise indicated, fabricate from the following materials:

1. Galvanized-Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A653/A653M, G60 coating designation.

a. Use for interior locations unless otherwise indicated.

2. Heavy-Galvanized-Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A653/A653M; structural steel (SS), high-strength low-alloy steel Type A (HSLAS Type A), or high-strength low-alloy steel Type B (HSLAS Type B); G185 coating designation; and not less than 0.036 inch thick.

a. Use for wood-preservative-treated lumber and where indicated.

2.8 MISCELLANEOUS MATERIALS

A. Sill-Sealer Gaskets:

1. Glass-fiber-resilient insulation, fabricated in strip form, for use as a sill sealer; 1-inch nominal thickness, compressible to 1/32 inch; selected from manufacturer's standard widths to suit width of sill members indicated.
2. Closed-cell neoprene foam, 1/4 inch thick, selected from manufacturer's standard widths to suit width of sill members indicated.

B. Flexible Flashing: Composite, self-adhesive, flashing product consisting of a pliable, butyl rubber or rubberized-asphalt compound, bonded to a high-density polyethylene film, aluminum foil, or spunbonded polyolefin to produce an overall thickness of not less than 0.025 inch.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Framing Standard: Comply with AF&PA's WCD 1, "Details for Conventional Wood Frame Construction," unless otherwise indicated.

B. Set work to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry accurately to other construction. Locate furring, nailers, blocking, grounds, and similar supports to comply with requirements for attaching other construction.

C. Install plywood backing panels by fastening to studs; coordinate locations with utilities requiring backing panels. Install fire-retardant-treated plywood backing panels with classification marking of testing agency exposed to view.

D. Install metal framing anchors to comply with manufacturer's written instructions. Install fasteners through each fastener hole.

E. Install sill sealer gasket to form continuous seal between sill plates and foundation walls.

F. Install sill sealer gasket/termite barrier in accordance with manufacturer's written instructions at the underside of wall bottom track or rim track and at the top of foundation wall or slab at stud or joist locations.

G. Do not splice structural members between supports unless otherwise indicated.

H. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.

1. Provide metal clips for fastening gypsum board or lath at corners and intersections where framing or blocking does not provide a surface for fastening edges of panels. Space clips not more than 16 inches o.c.

I. Provide fire blocking in furred spaces, stud spaces, and other concealed cavities as indicated and as follows:

1. Fire block furred spaces of walls, at each floor level, at ceiling, and at not more than 96 inches o.c. with solid wood blocking or noncombustible materials accurately fitted to close furred spaces.

J. Sort and select lumber so that natural characteristics do not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.

K. Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.

1. Use inorganic boron for items that are continuously protected from liquid water.
2. Use copper naphthenate for items not continuously protected from liquid water.

L. Where wood-preservative-treated lumber is installed adjacent to metal decking, install continuous flexible flashing separator between wood and metal decking.

M. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:

1. Table 2304.10.1, "Fastening Schedule," in ICC's International Building Code (IBC).
2. ICC-ES evaluation report for fastener.

N. Securely attach roofing nailers to substrates by anchoring and fastening to withstand bending, shear, or other stresses imparted by Project wind loads and fastener-resistance loads as designed in accordance with ASCE/SEI 7.

O. Use steel common nails at untreated wood unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

3.2 INSTALLATION OF WOOD BLOCKING AND NAILERS

A. Install where indicated and where required for screeding or attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.

B. Attach wood blocking to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwise indicated.

C. Attach wood roofing nailers securely to substrate to resist the designed outward and upward wind loads indicated on Drawings and in accordance with ANSI/SPRI ED-1, Tables A6 and A7.

3.3 INSTALLATION OF WOOD FURRING

A. Install level and plumb with closure strips at edges and openings. Shim with wood as required for tolerance of finish work.

B. Furring to Receive Gypsum Board or Plaster Lath: Install 1-by-3-inch nominal-size furring vertically at 16 inches o.c.

3.4 PROTECTION

A. Protect miscellaneous rough carpentry from weather. If, despite protection, miscellaneous rough carpentry becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION

SECTION 061600 - SHEATHING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Wall sheathing.
2. Roof sheathing.
3. Parapet sheathing.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for plywood backing panels.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Wall sheathing.
2. Roof sheathing.
3. Parapet sheathing.

C. Product Data Submittals: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated plywood complies with requirements. Indicate type of preservative used and net amount of preservative retained.
2. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated plywood complies with requirements. Include physical properties of treated materials.
3. For fire-retardant treatments, include physical properties of treated plywood both before and after exposure to elevated temperatures, based on testing by a qualified independent testing agency in accordance with ASTM D5516.
4. For products receiving waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.
5. For air-barrier and water-resistant glass-mat gypsum sheathing, include manufacturer's technical data and tested physical and performance properties of products.

D. Shop Drawings: For air-barrier and water-resistant glass-mat gypsum sheathing assemblies.

1. Show locations and extent of sheathing, accessories, and assemblies specific to Project conditions.

2. Include details for sheathing joints and cracks, counterflashing strips, penetrations, inside and outside corners, terminations, and tie-ins with adjoining construction.
3. Include details of interfaces with other materials that form part of air barrier.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer, including list of ABAA-certified installers and supervisors employed by Installer, who work on Project.

C. Product Certificates: From air-barrier and water-resistant glass-mat gypsum sheathing manufacturer, certifying compatibility of sheathing accessory materials with Project materials that connect to or that come in contact with the sheathing.

D. Product Test Reports: For each air-barrier and water-resistant glass-mat gypsum sheathing assembly, indicating compliance with specified requirements, for tests performed by a qualified testing agency.

E. Evaluation Reports: For the following, from ICC-ES:

1. Wood-preservative-treated plywood.
2. Fire-retardant-treated plywood.
3. Foam-plastic sheathing.
4. Air-barrier and water-resistant glass-mat gypsum sheathing.

F. Field quality-control reports.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer of air-barrier and water-resistant glass-mat gypsum sheathing.

1. Installer is to be licensed by ABAA in accordance with ABAA's Quality Assurance Program and is to employ ABAA-certified installers and supervisors on Project.

B. Testing Agency Qualifications:

1. For testing agency providing classification marking for fire-retardant-treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.
2. For testing and inspecting agency providing tests and inspections related to air-barrier and water-resistant glass-mat gypsum sheathing: an independent agency, qualified in accordance with ASTM E329 for testing indicated, and certified by Air Barrier Association of America, Inc.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Stack panels flat with spacers beneath and between each bundle to provide air circulation. Protect sheathing from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Resistance Ratings: As tested in accordance with ASTM E119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Fire-Resistance Ratings: Indicated by design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.

B. Air-Barrier and Water-Resistant Glass-Mat Gypsum Sheathing Performance: Air-barrier and water-resistant glass-mat gypsum sheathing assembly, and seals with adjacent construction, are to be capable of performing as a continuous air barrier and as a liquid-water drainage plane flashed to discharge to the exterior incidental condensation or water penetration. Air-barrier assemblies are to be capable of accommodating substrate movement and of sealing substrate expansion and control joints, construction material changes, penetrations, and transitions at perimeter conditions without deterioration and air leakage exceeding specified limits.

2.2 PRESERVATIVE-TREATED PLYWOOD

A. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC2 for interior construction not in contact with ground, Use Category UC3b for exterior construction not in contact with ground, and Use Category UC4a for items in contact with ground.

1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.

B. Mark plywood with appropriate classification marking of an inspection agency acceptable to authorities having jurisdiction.

C. Application: Treat items indicated on Drawings and plywood in contact with masonry or concrete or used with roofing, flashing, vapor barriers, and waterproofing.

2.3 FIRE-RETARDANT-TREATED PLYWOOD

A. General: Where fire-retardant-treated materials are indicated, use materials complying with requirements in this article that are acceptable to authorities having jurisdiction and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.

B. Fire-Retardant-Treated Plywood by Pressure Process: Products with a flame-spread index of 25 or less when tested in accordance with ASTM E84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet beyond the centerline of the burners at any time during the test.

1. Use treatment that does not promote corrosion of metal fasteners.
2. Exterior Type: Treated materials are to comply with requirements specified above for fire-retardant-treated plywood by pressure process after being subjected to accelerated weathering in accordance with ASTM D2898. Use for exterior locations and where indicated.
3. Interior Type A: Treated materials are to have a moisture content of 28 percent or less when tested in accordance with ASTM D3201/D3201M at 92 percent relative humidity. Use where exterior type is not indicated.
4. Design Value Adjustment Factors: Treated lumber plywood is to be tested in accordance with ASTM D5516 and design value adjustment factors are to be calculated in accordance with ASTM D6305. Span ratings after treatment are to be not less than span ratings specified. For roof sheathing and where high-temperature fire-retardant treatment is indicated, span ratings for temperatures up to 170 deg F are to be not less than span ratings specified.

C. Kiln-dry material after treatment to a maximum moisture content of 15 percent. Do not use material that is warped or does not comply with requirements for untreated material.

D. Identify fire-retardant-treated plywood with appropriate classification marking of qualified testing agency.

E. Application: Treat plywood indicated on Drawings.

2.4 WALL SHEATHING

A. Plywood Sheathing, Walls: ,Exposure 1, Structural I sheathing.

1. Span Rating: Not less than 32/16.
2. Nominal Thickness: Not less than 1/2 inch.

B. Glass-Mat Gypsum Sheathing, Walls: ASTM C1177/C1177M.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. CertainTeed; SAINT-GOBAIN
   b. Continental Building Products Inc.
   c. Georgia-Pacific Gypsum LLC
   d. Gold Bond Building Products, LLC provided by National Gypsum Company
   e. USG Corporation

2. Type and Thickness: Type X, 5/8 inch thick.
3. Size: 48 by 96 inches for vertical installation.

C. Cementitious Backer Units, Walls: ASTM C1325, Type A.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. C-Cure
b. Custom Building Products
c. FinPan, Inc.
d. USG Corporation

2. Thickness: 5/8 inch.

2.5 PARAPET SHEATHING

A. Plywood Sheathing, Parapets: , Exterior, Structural I sheathing.

1. Span Rating: Not less than 32/16.
2. Nominal Thickness: Not less than 3/4 inch.

2.6 FASTENERS

A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.

1. For roof, parapet, and wall sheathing, provide fasteners with organic-polymer or other corrosion-protective coating having a salt-spray resistance of more than 800 hours in accordance with ASTM B117.

B. Nails, Brads, and Staples: ASTM F1667.

C. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.

D. Screws for Fastening Sheathing to Wood Framing: ASTM C1002.

E. Screws for Fastening Wood Structural Panels to Cold-Formed Metal Framing: ASTM C954, except with wafer heads and reamer wings, length as recommended by screw manufacturer for material being fastened.

F. Screws for Fastening Gypsum Sheathing to Cold-Formed Metal Framing: Steel drill screws, in length recommended by sheathing manufacturer for thickness of sheathing to be attached.

1. For steel framing less than 0.0329 inch thick, use screws that comply with ASTM C1002.
2. For steel framing from 0.033 to 0.112 inch thick, use screws that comply with ASTM C954.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Do not use materials with defects that impair quality of sheathing or pieces that are too small to use with minimum number of joints or optimum joint arrangement. Arrange joints so that pieces do not span between fewer than three support members.

B. Cut panels at penetrations, edges, and other obstructions of work; fit tightly against abutting construction unless otherwise indicated.

C. Securely attach to substrate by fastening as indicated, complying with the following:

1. Table 2304.10.1, "Fastening Schedule," in the ICC's International Building Code.
2. ICC-ES evaluation report for fastener.

D. Use common wire nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections. Install fasteners without splitting wood.

E. Coordinate sheathing installation with flashing and joint-sealant installation so these materials are installed in sequence and manner that prevent exterior moisture from passing through completed assembly.

F. Do not bridge building expansion joints; cut and space edges of panels to match spacing of structural support elements.

G. Coordinate sheathing installation with installation of materials installed over sheathing so sheathing is not exposed to precipitation or left exposed at end of the workday when rain is forecast.

3.2 INSTALLATION OF WOOD STRUCTURAL PANEL

A. General: Comply with applicable recommendations in APA Form No. E30, "Engineered Wood Construction Guide," for types of structural-use panels and applications indicated.

B. Fastening Methods: Fasten panels as indicated below:

1. Wall and Roof Sheathing:

a. Nail to wood framing.
b. Screw to cold-formed metal framing.
c. Space panels 1/8 inch apart at edges and ends.

3.3 INSTALLATION OF CEMENTITIOUS BACKER UNITS

A. Install panels and treat joints in accordance with ANSI A108.11 and manufacturer's written instructions for type of application indicated.

END OF SECTION

SECTION 064116 - PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Plastic-laminate-clad architectural cabinets.
2. Cabinet hardware and accessories.
3. Miscellaneous materials.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for wood furring, blocking, shims, and hanging strips required for installing cabinets that are concealed within other construction before cabinet installation.
2. Section 123623.13 "Plastic-Laminate-Clad Countertops."

1.2 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to support loads imposed by installed and fully loaded cabinets.

1.3 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data:

1. Plastic-laminate-clad architectural cabinets.
2. Cabinet hardware and accessories.
3. Miscellaneous materials.

C. Shop Drawings:

1. Include plans, elevations, sections, and attachment details.
2. Show large-scale details.
3. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.
4. Show locations and sizes of cutouts and holes for items installed in plastic-laminate architectural cabinets.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Qualification Data: For manufacturer.

1.5 QUALITY ASSURANCE

A. Manufacturer's Qualifications: Employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver cabinets until painting and similar finish operations that might damage architectural cabinets have been completed in installation areas. Store cabinets in installation areas or in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.7 FIELD CONDITIONS

A. Environmental Limitations without Humidity Control: Do not deliver or install cabinets until building is enclosed, wet-work is complete, and HVAC system is operating and maintaining temperature and relative humidity at levels planned for building occupants during the remainder of the construction period.

B. Field Measurements: Where cabinets are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1. Locate concealed framing, blocking, and reinforcements that support cabinets by field measurements before being enclosed/concealed by construction, and indicate measurements on Shop Drawings.

PART 2 - PRODUCTS

2.1 PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS

A. Quality Standard: Unless otherwise indicated, comply with the Architectural Woodwork Standards for grades of cabinets indicated for construction, finishes, installation, and other requirements.

B. Architectural Woodwork Standards Grade: Custom.

C. Type of Construction: Frameless.

D. Door and Drawer-Front Style: Flush overlay.

E. High-Pressure Decorative Laminate: ISO 4586-3, grades as indicated or if not indicated, as required by quality standard.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. ABET Inc.
b. Formica Corporation.
c. Laminart LLC.
d. Pionite; a Panolam Industries International, Inc. brand.
e. Wilsonart LLC.

F. Exposed Surfaces:

1. Plastic-Laminate Grade: HGS.
2. Edges: Grade HGS.
3. Pattern Direction: Vertically for drawer fronts, doors, and fixed panels.

G. Semiexposed Surfaces:

1. Surfaces Other Than Drawer Bodies: Thermally fused laminate panels.

a. Edges of Thermally Fused Laminate Panel Shelves: PVC or polyester edge banding.
b. For semiexposed backs of panels with exposed plastic-laminate surfaces, provide surface of high-pressure decorative laminate, ISO 4586-3, grade to match exposed surface.

2. Drawer Sides and Backs: Thermally fused laminate panels with PVC or polyester edge banding.
3. Drawer Bottoms: Thermally fused laminate panels.

H. Drawer Construction: Fabricate with exposed fronts fastened to subfront with mounting screws from interior of body.

1. Join subfronts, backs, and sides with glued rabbeted joints supplemented by mechanical fasteners.

I. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:

1. As indicated by laminate manufacturer's designations.

2.2 WOOD MATERIALS

A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of architectural cabinet and quality grade specified unless otherwise indicated.

B. Composite Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of architectural cabinet and quality grade specified unless otherwise indicated.

1. Particleboard (Medium Density): ANSI A208.1, Grade M-2.

2.3 CABINET HARDWARE AND ACCESSORIES

A. Cabinet Hardware: Provide cabinet hardware and accessory materials associated with architectural cabinets except for items specified in Section 087100 "Door Hardware."

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Accuride International Inc.
b. CompX International, Inc.
c. Doug Mockett.
d. Grass America.
e. Hardware Resources.
f. Hettich America L.P.
g. Julius Blum & Co., Inc.
h. Knape & Vogt Manufacturing Company.

B. Frameless Concealed Hinges (European Type): ANSI/BHMA A156.9, B01602, 100 degrees of opening.

C. Back-Mounted Pulls:

1. Basis-of Design Product: Doug Mockett's DP305A in graphite.

D. Shelf Rests: ANSI/BHMA A156.9, B04013; metal.

E. Drawer Slides: ANSI/BHMA A156.9.

1. Standard Duty (Grade 1 and Grade 2): Side mount.

F. Door and Drawer Silencers: ANSI/BHMA A156.16, L03011.

G. For concealed hardware, provide manufacturer's standard finish that complies with product class requirements in ANSI/BHMA A156.9.

2.4 MISCELLANEOUS MATERIALS

A. Furring, Blocking, Shims, and Hanging Strips: Softwood or hardwood lumber, kiln-dried to less than 15 percent moisture content.

B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls and at floors.

C. Adhesive for Bonding Plastic Laminate: Type II water-resistant type as selected by fabricator to comply with requirements.

1. Adhesive for Bonding Edges: Hot-melt adhesive or adhesive specified above for faces.

2.5 FABRICATION

A. Fabricate architectural cabinets to dimensions, profiles, and details indicated.

B. Complete fabrication, including assembly and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

C. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installation, condition cabinets to humidity conditions in installation areas for not less than 72 hours.

3.2 INSTALLATION

A. Architectural Woodwork Standards Grade: Install cabinets to comply with quality standard grade of item to be installed.

B. Assemble cabinets and complete fabrication at Project site to extent that it was not completed in the shop.

C. Anchor cabinets to anchors or blocking built in or directly attached to substrates. Secure with wafer-head cabinet installation screws.

D. Install cabinets level, plumb, and true in line to a tolerance of 1/8 inch in 96 inches using concealed shims.

1. Scribe and cut cabinets to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.
2. Install cabinets without distortion so doors and drawers fit openings and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.

3. Fasten wall cabinets through back, near top and bottom, and at ends not more than 16 inches o.c. with No. 10 wafer-head screws sized for not less than 1-1/2-inch penetration into wood framing, blocking, or hanging strips.

3.3 ADJUSTING AND CLEANING

A. Repair damaged and defective cabinets, where possible, to eliminate functional and visual defects. Where not possible to repair, replace architectural cabinets. Adjust joinery for uniform appearance.

B. Clean, lubricate, and adjust hardware.

C. Clean cabinets on exposed and semiexposed surfaces.

END OF SECTION

SECTION 066400 - PLASTIC PANELING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Plastic sheet paneling.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include material descriptions and tested physical and performance properties of paneling.
2. Include manufacturer's written instructions for evaluating, preparing, and treating substrate.

1.3 QUALITY ASSURANCE

A. Testing Agency: Acceptable to authorities having jurisdiction.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver paneling until painting and similar operations that might damage paneling have been completed in installation areas. Store paneling in installation areas or in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.5 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install plastic paneling until spaces are enclosed and weathertight and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.6 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace defective panels and components that fail in materials or workmanship under normal conditions of use within specified warranty period.

1. Warranty Period - Plastic Sheet Paneling: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain plastic paneling and trim accessories from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: As determined by testing identical plastic paneling applied with identical adhesives to substrates in accordance with test method indicated below by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

a. Flame-Spread Index: 25 or less.
b. Smoke-Developed Index: 450 or less.

2.3 PLASTIC SHEET PANELING

A. Glass-Fiber-Reinforced Plastic Paneling: Gelcoat-finished, glass-fiber-reinforced plastic panels complying with ASTM D5319.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Marlite, Inc.
b. Nudo; a Verzatec Group Company
c. Parkland Plastics Inc.; a Patrick Industries Inc. Company
d. Stabilit America Inc.
e. Valto Engineered Materials

2. Nominal Thickness: Not less than 0.075 inch.
3. Surface Finish: Smooth.
4. Color: As selected by Architect from manufacturer's full range.

2.4 ACCESSORIES

A. Trim Accessories: Manufacturer's standard one-piece vinyl extrusions designed to retain and cover edges of panels. Provide division bars.

1. Color: Match panels.

B. Adhesive: As recommended by plastic paneling manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove materials that might interfere with adhesive bond.

B. Prepare substrate by sanding high spots and filling low spots as needed to provide flat, even surface for panel installation.

C. Clean substrates of substances that could impair adhesive bond, including oil, grease, dirt, and dust.

D. Condition panels by unpacking and placing in installation space before installation in accordance with manufacturer's written instructions.

E. Lay out paneling before installing. Locate panel joints to provide equal panels at ends of walls not less than half the width of full panels.

1. Mark plumb lines on substrate at panel joint locations for accurate installation.
2. Locate panel joints to allow clearance at panel edges in accordance with manufacturer's written instructions.

3.3 INSTALLATION OF PLASTIC PANELING

A. Install in accordance with manufacturer's written instructions.

B. Install panels in a full spread of adhesive.

C. Maintain uniform space between panels and wall fixtures. Fill space with sealant.

END OF SECTION

SECTION 070150.19 - PREPARATION FOR REROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of This Section Includes:

1. Full roof tear-off.
2. Temporary roofing.
3. Base flashing removal.
4. Disposal.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for temporary construction and environmental-protection measures for reroofing preparation.

1.2 DEFINITIONS

A. EPS: Molded (expanded) polystyrene.

B. Full Roof Tear-off: Removal of existing roofing system down to existing roof deck.

C. Roofing Terminology: Definitions in ASTM D1079 and glossary of NRCA's "The NRCA Roofing Manual: Membrane Roof Systems" apply to work of this Section.

1.3 FIELD CONDITIONS

A. Existing Roofing System: EPDM roofing.

B. Owner will not occupy portions of building immediately below reroofing area.

C. Protect building to be reroofed, adjacent buildings, walkways, site improvements, exterior plantings, and landscaping from damage or soiling from reroofing operations.

D. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities.

E. Conditions existing at time of inspection for bidding will be maintained by Owner as far as practical.

1. Construction Drawings for existing roofing system are provided for Contractor's convenience and information, but they are not a warranty of existing conditions. They are intended to supplement rather than serve in lieu of Contractor's own investigations. Contractor is responsible for conclusions derived from existing documents.

F. Hazardous Materials:

1. A report on the presence of hazardous materials is on file for review and use. Examine report to become aware of locations where hazardous materials are present.

    a. Hazardous material remediation is specified elsewhere in the Contract Documents.
    b. Do not disturb hazardous materials or items suspected of containing hazardous materials except according to procedures specified elsewhere in the Contract Documents.
    c. Coordinate reroofing preparation with hazardous material remediation to prevent water from entering existing roofing system or building.

PART 2 - PRODUCTS

2.1 TEMPORARY ROOFING MATERIALS

A. Design and selection of materials for temporary roofing are Contractor's responsibilities.

PART 3 - EXECUTION

3.1 PREPARATION

A. Protection of In-Place Conditions:

1. Protect existing roofing system that is not to be reroofed.
2. Loosely lay 1-inch-minimum thick, EPS insulation over existing roofing in areas not to be reroofed.

    a. Loosely lay 15/32-inch plywood or OSB panels over EPS. Extend EPS past edges of plywood or OSB panels a minimum of 1 inch.

B. During removal operations, have sufficient and suitable materials on-site to facilitate rapid installation of temporary protection in the event of unexpected rain.

C. Maintain roof drains in functioning condition to ensure roof drainage at end of each workday.

1. Prevent debris from entering or blocking roof drains and conductors.

    a. Use roof-drain plugs specifically designed for this purpose.
    b. Remove roof-drain plugs at end of each workday, when no work is taking place, or when rain is forecast.

2. If roof drains are temporarily blocked or unserviceable due to roofing system removal or partial installation of new roofing system, provide alternative drainage method to remove water and eliminate ponding.

3.2 ROOF TEAR-OFF

A. Lower removed roofing materials to ground and onto lower roof levels, using dust-tight chutes or other acceptable means of removing materials from roof areas.

B. Full Roof Tear-off: Remove existing roofing and other roofing system components down to the existing roof deck.

1. Remove roof insulation and cover board.
2. Remove perimeter edge flashing and gravel stops.
3. Remove copings.
4. Remove flashings at pipes, curbs, mechanical equipment, and other penetrations.
5. Remove roof drains indicated on Drawings to be removed.
6. Remove wood blocking, curbs, and nailers.

3.3 TEMPORARY ROOFING

A. Install approved temporary roofing over area to be reroofed.

B. Remove temporary roofing before installing new roofing.

3.4 BASE FLASHING REMOVAL

A. Remove existing base flashings where indicated.

1. Clean substrates of contaminants, such as asphalt, sheet materials, dirt, and debris.

B. Do not damage metal counterflashings that are to remain.

C. Remove existing parapet sheathing and replace with new parapet sheathing to comply with Section 061600 "Sheathing."

3.5 DISPOSAL

A. Collect demolished materials and place in containers.

1. Promptly dispose of demolished materials.
2. Do not allow demolished materials to accumulate on-site.
3. Storage or sale of demolished items or materials on-site is not permitted.

B. Transport and legally dispose of demolished materials off Owner's property.

END OF SECTION

SECTION 071326 - SELF-ADHERING SHEET WATERPROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Modified bituminous sheet waterproofing.
2. Accessory waterproofing system materials.

B. Related Requirements:

1. Section 072100 "Thermal Insulation."
2. Section 079200 "Joint Sealants" for joint sealants, joint fillers, and joint preparation.

1.2 DEFINITIONS

A. Compatible: Material that will not adversely affect adjacent materials, is chemically compatible with adjacent materials, and where required for bond, achieves adhesive compatibility with adjacent materials.

B. Chemical Compatibility: Material that will not break down, deteriorate, degrade, or prematurely fail when in contact with another material. Material that will not cause chemical breakdown, deterioration, degradation, staining, or premature failure of another material.

C. Adhesive Compatibility: Material that will develop bond strength or provide a suitable surface for another material to develop bond strength complying with requirements when in contact with another material.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, material descriptions, and tested physical and performance properties of waterproofing.
2. Include manufacturer's written installation instructions for evaluating, preparing, and treating substrate.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Field quality-control reports.

C. Qualification Statements: For Installer.

D. Sample warranties.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by waterproofing manufacturer.

1.6 FIELD CONDITIONS

A. Environmental Limitations: Apply waterproofing within the range of ambient and substrate temperatures recommended in writing by waterproofing manufacturer. Do not apply waterproofing to frozen, damp, or wet substrates.

1. Do not apply waterproofing when snow, rain, fog, or mist is present.

B. Maintain adequate ventilation during preparation and application of waterproofing materials.

1.7 WARRANTY

A. Manufacturer's Warranty:

1. Waterproofing Warranty: Manufacturer agrees to furnish replacement waterproofing material for waterproofing that does not comply with requirements or that fails to remain watertight within specified warranty period.

a. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Waterproofing System: Obtain waterproofing materials from same manufacturer as waterproofing membrane.

2.2 MODIFIED BITUMINOUS SHEET WATERPROOFING

A. Modified Bituminous Sheet Waterproofing: Minimum 60-mil nominal thickness, self-adhering sheet consisting of 56 mils of rubberized asphalt laminated on one side to a 4-mil-thick, polyethylene-film reinforcement, and with release liner on adhesive side.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. American Hydrotech, Inc.
b. Carlisle Coatings & Waterproofing Inc
c. CETCO is a subsidiary of Minerals Technologies Inc.
d. GCP Applied Technologies Inc.
e. Henry, a Carlisle Company (formerly Henry Company and Carlisle Coatings & Waterproofing Inc. brands)
f. MAPEI Corporation
g. Mar-flex Waterproofing & Building Products
h. Polyglass U.S.A., Inc.
i. Polyguard Products, Inc.
j. Protecto Wrap Company
k. Soprema, Inc.
l. Tamko Building Products LLC
m. Tremco Commercial Sealants and Waterproofing, part of Tremco CPG
n. W. R. Meadows, Inc

2. Physical Properties:

a. Tensile Strength, Membrane: 250 psi minimum; ASTM D412, Die C, modified.
b. Ultimate Elongation: 300 percent minimum; ASTM D412, Die C, modified.
c. Low-Temperature Flexibility: Pass at minus 20 deg F; ASTM D1970/D1970M.
d. Puncture Resistance: 40 lbf minimum; ASTM E154/E154M.
e. Water Absorption: 0.2 percent weight-gain maximum after 48-hour immersion at 70 deg F; ASTM D570.
f. Water Vapor Permeance: 0.05 perm maximum; ASTM E96/E96M, Water Method.
g. Hydrostatic-Head Resistance: 200 ft. minimum; ASTM D5385/D5385M.

3. Sheet Strips: Self-adhering, rubberized-asphalt strips of same material and thickness as sheet waterproofing.

2.3 ACCESSORY WATERPROOFING SYSTEM MATERIALS

A. General: Accessory materials as recommended in writing by waterproofing manufacturer for intended use and compatibility with one another and with sheet waterproofing.

B. Primer: Liquid primer as recommended in writing for substrate by sheet waterproofing material manufacturer.

C. Surface Conditioner: Liquid, waterborne surface conditioner as recommended in writing for substrate by sheet waterproofing material manufacturer.

D. Liquid Membrane: Elastomeric, two-component liquid, cold fluid applied, of trowel grade or low viscosity.

E. Substrate Patching Membrane: Low-viscosity, two-component, modified asphalt coating.

F. Metal Termination Bars: Aluminum or stainless steel bars, approximately 1 by 1/8 inch, predrilled at 9-inch centers.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of waterproofing.

1. Verify that concrete has cured and aged for minimum time recommended in writing by waterproofing manufacturer.
2. Verify that substrate is visibly dry and within the moisture limits recommended in writing by manufacturer. Test for capillary moisture by plastic sheet method in accordance with ASTM D4263.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean, prepare, and treat substrates in accordance with manufacturer's written installation instructions. Provide clean, dust-free, and dry substrates for waterproofing application.

B. Mask off adjoining surfaces not receiving waterproofing to prevent spillage and overspray affecting other construction.

C. Remove grease, oil, bitumen, form-release agents, paints, curing compounds, and other penetrating contaminants or film-forming coatings from concrete.

D. Remove fins, ridges, mortar, and other projections.

E. Fill form tie holes, honeycomb, aggregate pockets, holes, and other voids.

F. Prepare, fill, prime, and treat joints and cracks in substrates. Remove dust and dirt from joints and cracks in accordance with ASTM D4258.

1. Install sheet strips of width in accordance with manufacturer's written installation instructions and center over treated construction and contraction joints and cracks exceeding a width of 1/16 inch.

G. Bridge and cover isolation joints, expansion joints, and discontinuous deck-to-wall and deck-to-deck joints with overlapping sheet strips of widths in accordance with manufacturer's written installation instructions.

1. Invert and loosely lay first sheet strip over center of joint. Firmly adhere second sheet strip to first and overlap to substrate.

H. Corners: Prepare, prime, and treat inside and outside corners in accordance with manufacturer's written installation instructions.

1. Install membrane strips centered over vertical inside corners.

3.3 INSTALLATION OF MODIFIED BITUMINOUS SHEET WATERPROOFING

A. Install modified bituminous sheets in accordance with waterproofing manufacturer's written installation instructions.

B. Apply primer to substrates at required rate and allow it to dry. Limit priming to areas that will be covered by sheet waterproofing in same day. Reprime areas exposed for more than 24 hours.

C. Apply and firmly adhere sheets over area to receive waterproofing. Accurately align sheets and maintain uniform 2-1/2-inch-minimum lap widths and end laps. Overlap and seal seams, and stagger end laps to ensure watertight installation.

1. When ambient and substrate temperatures range between 25 and 40 deg F, install self-adhering, modified bituminous sheets produced for low-temperature application. Do not apply sheets if ambient or substrate temperature is lower than 40 deg F.

D. Horizontal Application: Apply sheets from low to high points of decks to ensure that laps shed water.

E. Apply continuous sheets over already-installed sheet strips, bridging substrate cracks, construction, and contraction joints.

F. Seal edges of sheet waterproofing terminations with mastic.

G. Install sheet waterproofing and accessory materials to tie into adjacent waterproofing.

H. Roll waterproofing membrane to firmly adhere to substrate. Roll seams and terminations.

I. Repair tears, voids, and lapped seams in waterproofing not complying with requirements. Slit and flatten fishmouths and blisters. Patch with sheet waterproofing extending 6 inches beyond repaired areas in all directions.

J. Immediately install protection course with butted joints over waterproofing membrane.

3.4 PROTECTION, REPAIR, AND CLEANING

A. Do not permit foot or vehicular traffic on unprotected membrane.

B. Protect waterproofing from damage and wear during remainder of construction period.

C. Correct deficiencies in or remove waterproofing that does not comply with requirements; repair substrates, reapply waterproofing, and repair sheet flashings.

D. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended in writing by manufacturer of affected construction.

END OF SECTION

SECTION 072100 - THERMAL INSULATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Mineral-wool blanket insulation.
2. Poly vapor barrier and vapor barrier tape.
3. Extruded polystyrene foam-plastic board insulation (below concrete slab-on-grade).
4. Polyisocyanurate foam-plastic board insulation (at stair walls).

B. Related Requirements.

1. Section 033000 "Cast-In-Place Concrete" for below slab vapor barrier.
2. Section 072119 " Foamed-In-Place Insulation" for insulation installed at exterior walls.
3. Section 075419 "Polyvinyl-Chloride (PVC) roofing for " for insulation specified as part of roofing construction.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Installer's Certification: Listing type, manufacturer, and R-value of insulation installed in each element of the building thermal envelope.

1. For blown-in or sprayed fiberglass and cellulosic-fiber loose-fill insulation, indicate initial installed thickness, settled thickness, settled R-value, installed density, coverage area, and number of bags installed.
2. Sign, date, and post the certification in a conspicuous location on Project site.

C. Product Test Reports: For each product, for tests performed by a qualified testing agency.

D. Research Reports: For foam-plastic insulation, from ICC-ES.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Protect insulation materials from physical damage and from deterioration due to moisture, soiling, and other sources. Store inside and in a dry location. Comply with manufacturer's written instructions for handling, storing, and protecting during installation.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Maximum flame-spread and smoke-developed indexes less than Class A, 25 and 450 when tested in accordance with ASTM E84.

B. Thermal-Resistance Value (R-Value): R-value as indicated on Drawings in accordance with ASTM C518.

2.2 MINERAL-WOOL BLANKET INSULATION

A. Mineral-Wool Blanket Insulation, Unfaced: ASTM C665, Type I (blankets without membrane facing); consisting of fibers; complying with ASTM E136 for combustion characteristics.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Johns Manville; a Berkshire Hathaway company.
b. Owens Corning.
c. ROCKWOOL.

2.3 EXTRUDED POLYSTYRENE FOAM-PLASTIC BOARD INSULATION (XPS)

A. Extruded Polystyrene Board Insulation, Type VI : ASTM C578, Type VI, 40 psi minimum compressive strength.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. DiversiFoam Products.
b. DuPont de Nemours, Inc.
c. Kingspan Insulation LLC.
d. Owens Corning.
e. The Dow Chemical Company.

2.4 POLYETHYLENE VAPOR BARRIER

A. 10 mil clear vapor barrier.

B. Vapor Barrier Tape: 9 mil – 4 inches wide, waterproof.

2.5 POLYISOCYANURATE FOAM-PLASTIC BOARD INSULATION

A. Polyisocyanurate Board Insulation, Foil Faced : ASTM C1289, foil faced, Type I, Class 1 or 2.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Atlas Molded Products, a division of Atlas Roofing Corporation
b. Atlas Polyiso Roof and Wall Insulation
c. Carlisle Coatings & Waterproofing Inc
d. DuPont de Nemours, Inc.
e. Elevate; Holcim Building Envelope
f. Hunter Panels; a Carlisle company
g. Johns Manville; a Berkshire Hathaway company
h. Rmax, A Business Unit of Sika Corporation
i. The Dow Chemical Company

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean substrates of substances that are harmful to insulation, including removing projections capable of puncturing insulation or vapor retarders, or those that interfere with insulation attachment.

3.2 INSTALLATION, GENERAL

A. Comply with insulation manufacturer's written instructions applicable to products, applications and applicable codes.

B. Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.

C. Install insulation with manufacturer's R-value label exposed after insulation is installed.

D. Extend insulation to envelop entire area to be insulated. Fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.

E. Provide sizes to fit applications and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units unless multiple layers are otherwise shown or required to make up total thickness or to achieve R-value.

3.3 INSTALLATION OF INSULATION IN FRAMED CONSTRUCTION

A. Blanket Insulation: Install in cavities formed by framing members in accordance with the following requirements:

1. Use insulation widths and lengths that fill the cavities formed by framing members. If more than one length is required to fill the cavities, provide lengths that will produce a snug fit between ends.
2. Place insulation in cavities formed by framing members to produce a friction fit between edges of insulation and adjoining framing members.
3. Maintain 3-inch clearance of insulation around recessed lighting fixtures not rated for or protected from contact with insulation.

B. Miscellaneous Voids: Install insulation in miscellaneous voids and cavity spaces where required to prevent gaps in insulation using the following materials:

1. Mineral Wool Fiber Insulation: Compact to approximately 40 percent of normal maximum volume equaling a density of approximately 2.5 lb/cu. ft.

3.4 PROTECTION

A. Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes.

B. Provide temporary coverings or enclosures where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

3.5 INSTALLATION OF VAPOR BARRIER

A. Install with all edges fastened and sealed to abutting construction. Seal all seams, mechanical equipment and duct penetrations, mechanical and sprinkler piping penetrations, and electrical conduit, wiring, and device penetrations with vapor barrier tape.

END OF SECTION

SECTION 072119 - FOAMED-IN-PLACE INSULATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Closed-cell spray polyurethane foam insulation.
2. Accessories.

B. Related Requirements:

1. Section 072100 "Thermal Insulation" for foam-plastic board insulation.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Closed-cell spray polyurethane foam insulation.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Test Reports: For each product, for tests performed by qualified testing agency.

C. Qualification Statements: For Installer.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.

PART 2 - PRODUCTS

2.1 CLOSED-CELL SPRAY POLYURETHANE FOAM INSULATION

A. Closed-Cell Spray Polyurethane Foam: ASTM C1029, Type II, minimum density of 1.5 lb/cu. ft. and minimum aged R-value at 1-inch thickness of 6.2 deg F x h x sq. ft./Btu at 75 deg F.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. AMBIT Polyurethane
    b. Carlisle Spray Foam Insulation
    c. ENVERGE
    d. Gaco; Holcim Building Envelope
    e. Henry, a Carlisle Company (formerly Henry Company and Carlisle Coatings & Waterproofing Inc. brands)
    f. Huntsman Building Solutions
    g. Johns Manville; a Berkshire Hathaway company
    h. Master Builders Solutions, brand of MBCC Group, a Sika company
    i. NCFI Polyurethanes; a division of Barnhardt Manufacturing Company
    j. Quadrant Performance Materials
    k. SWD Urethane Company
    l. Thermoseal USA
    m. Volatile Free, Inc.

2. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

    a. Flame-Spread Index: 25 or less.
    b. Smoke-Developed Index: 450 or less.

3. Fire Propagation Characteristics: Passes NFPA 285 testing as part of an approved assembly.

2.2 ACCESSORIES

A. Primer: Material recommended by insulation manufacturer where required for adhesion of insulation to substrates.

PART 3 - EXECUTION

3.1 PREPARATION

A. Verify that substrates are clean, dry, and free of substances that are harmful to insulation.

B. Priming: Prime substrates where recommended by insulation manufacturer. Apply primer to comply with insulation manufacturer's written instructions. Confine primers to areas to be insulated; do not allow spillage or migration onto adjoining surfaces.

3.2 INSTALLATION

A. Comply with insulation manufacturer's written instructions applicable to products and applications.

B. Spray insulation to envelop entire area to be insulated and fill voids.

C. Apply in multiple passes to not exceed maximum thicknesses recommended by manufacturer. Do not spray into rising foam.

D. Framed Construction: Install into cavities formed by framing members to achieve thickness indicated on Drawings.

E. Miscellaneous Voids: Apply according to manufacturer's written instructions.

3.3 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect spray foam insulation installation, including accessories. Report results in writing.

3.4 PROTECTION

A. Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes.

END OF SECTION

SECTION 072600 - VAPOR RETARDERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Polyethylene vapor retarders.

B. Related Requirements:

1. Section 033000 "Cast-in-Place Concrete" for under-slab vapor retarders.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Polyethylene vapor retarders.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Test Reports: For each product, for tests performed by a qualified testing agency.

PART 2 - PRODUCTS

2.1 POLYETHYLENE VAPOR RETARDERS

A. Polyethylene Vapor Retarders: ASTM D4397, 6-mil- thick sheet, with maximum permeance rating of 0.1 perm.

2.2 ACCESSORIES

A. Vapor-Retarder Tape: Pressure-sensitive tape of type recommended by vapor-retarder manufacturer for sealing joints and penetrations in vapor retarder.

B. Adhesive for Vapor Retarders: Product recommended by vapor-retarder manufacturer and has demonstrated capability to bond vapor retarders securely to substrates indicated.

C. Vapor-Retarder Fasteners: Pancake-head, self-tapping steel drill screws; with fender washers.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean substrates of substances that are harmful to vapor retarders, including removing projections capable of puncturing vapor retarders.

3.2 INSTALLATION OF VAPOR RETARDERS

A. Place vapor retarders on side of construction indicated on Drawings.

B. Extend vapor retarders to extremities of areas to protect from vapor transmission. Secure vapor retarders in place with adhesives, vapor retarder fasteners, or other anchorage system as recommended by manufacturer. Extend vapor retarders to cover miscellaneous voids in insulated substrates, including those filled with loose-fiber insulation.

C. Seal vertical joints in vapor retarders over framing by lapping no fewer than two studs and sealing with vapor-retarder tape according to vapor-retarder manufacturer's written instructions. Locate all joints over framing members or other solid substrates.

D. Seal joints caused by pipes, conduits, electrical boxes, and similar items penetrating vapor retarders with vapor-retarder tape to create an airtight seal between penetrating objects and vapor retarders.

E. Repair tears or punctures in vapor retarders immediately before concealment by other work. Cover with vapor-retarder tape or another layer of vapor retarders.

F. Seal around penetrations such as utilities and columns in order to create a monolithic, airtight membrane at grade surface, perimeter, and all vertical penetrations.

3.3 PROTECTION

A. Protect vapor retarders from damage until concealed by permanent construction.

END OF SECTION

SECTION 074293 - SOFFIT PANELS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Metal soffit panels.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Metal soffit panels.

C. Product Data Submittals:

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of panel and accessory.

D. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below:

1. Metal Panels: 12 inches long by actual panel width. Include fasteners, closures, and other metal panel accessories.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

C. Product Test Reports: For each product, tests performed by a qualified testing agency.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For metal panels to include in maintenance manuals.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver components, metal panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.

B. Unload, store, and erect metal panels in a manner to prevent bending, warping, twisting, and surface damage.

C. Stack metal panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness, with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.

D. Retain strippable protective covering on metal panels during installation.

E. Copper Panels: Wear gloves when handling to prevent fingerprints and soiling of surface.

1.7 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit assembly of metal panels to be performed according to manufacturers' written instructions and warranty requirements.

1.8 COORDINATION

A. Coordinate metal panel installation with rain drainage work, flashing, trim, construction of walls, and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

1.9 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal panel systems that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

    a. Structural failures including rupturing, cracking, or puncturing.
    b. Deterioration of metals and other materials beyond normal weathering.

2. Warranty Period: Two years from date of Substantial Completion.

B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.

1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:

a. Color fading more than 5 Delta E units when tested according to ASTM D2244.
b. Chalking in excess of a No. 8 rating when tested according to ASTM D4214.
c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.

2. Finish Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.

1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

2.2 METAL SOFFIT PANELS

A. Provide metal soffit panels designed to be installed by lapping and interconnecting side edges of adjacent panels and mechanically attaching through panel to supports using concealed fasteners in side laps. Include accessories required for weathertight installation.

B. Flush-Profile Metal Soffit Panels : Solid panels formed with vertical panel edges and a flat pan between panel edges; with flush joint between panels.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. AEP Span a brand of ASC Profiles LLC, a part of BlueScope
b. ATAS International, Inc.
c. Berridge Manufacturing Company
d. CENTRIA, a Nucor Brand
e. Dimensional Metals, Inc.
f. Drexel Metals Corp.
g. Elevate; Holcim Building Envelope
h. Englert, Inc.
i. Fabral; a brand of Flack Global Metals
j. Innovative Metals Company, Inc
k. Knotwood US LLC
l. MBCI; Cornerstone Building Brands
m. McElroy Metal, Inc

n. Merchant & Evans Inc.
o. Metal Sales Manufacturing Corporation
p. PAC-CLAD; Petersen; a Carlisle company
q. Sentrigard; NB Handy Company
r. Ultra Seam Incorporated

2. Aluminum Sheet: Coil-coated sheet, ASTM B209, alloy as standard with manufacturer, with temper as required to suit forming operations and structural performance required.

a. Thickness: 0.040 inch.
b. Surface: Smooth, flat finish.
c. Exterior Finish: Two-coat fluoropolymer.
d. Color: As selected by Architect from manufacturer's full range.

2.3 MISCELLANEOUS MATERIALS

A. Miscellaneous Metal Subframing and Furring: ASTM C645, cold-formed, metallic-coated steel sheet, ASTM A653/A653M, G90 hot-dip galvanized coating designation or ASTM A792/A792M, Class AZ50 aluminum-zinc-alloy coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.

B. Panel Accessories: Provide components required for a complete, weathertight panel system including trim, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal panels unless otherwise indicated.

1. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch-thick, flexible closure strips; cut or premolded to match metal panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.

C. Flashing and Trim: Provide flashing and trim formed from same material as metal panels as required to seal against weather and to provide finished appearance. Finish flashing and trim with same finish system as adjacent metal panels.

D. Panel Fasteners: Self-tapping screws designed to withstand design loads. Provide exposed fasteners with heads matching color of metal panels by means of plastic caps or factory-applied coating. Provide EPDM or PVC sealing washers for exposed fasteners.

E. Panel Sealants: Provide sealant types recommended by manufacturer that are compatible with panel materials, are nonstaining, and do not damage panel finish.

1. Sealant Tape: Pressure-sensitive, 100 percent solids, gray polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch wide and 1/8 inch thick.
2. Joint Sealant: ASTM C920; elastomeric polyurethane or silicone sealant; of type, grade, class, and use classifications required to seal joints in metal panels and remain weathertight; and as recommended in writing by metal panel manufacturer.
3. Butyl-Rubber-Based, Solvent-Release Sealant: ASTM C1311.

2.4 FABRICATION

A. Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.

B. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel.

C. Fabricate metal panel joints with factory-installed captive gaskets or separator strips that provide a weathertight seal and prevent metal-to-metal contact, and that minimize noise from movements.

D. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.

1. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.
2. Seams for Aluminum: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints for additional strength.
3. Sealed Joints: Form nonexpansion, but movable, joints in metal to accommodate sealant and to comply with SMACNA standards.
4. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of accessories exposed to view.
5. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal recommended in writing by metal panel manufacturer.

    a. Size: As recommended by SMACNA's "Architectural Sheet Metal Manual" or metal soffit panel manufacturer for application but not less than thickness of metal being secured.

2.5 FINISHES

A. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

B. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

C. Aluminum Panels and Accessories:

1. Two-Coat Fluoropolymer: AAMA 2605. Fluoropolymer finish containing not less than 70 percent polyvinylidene fluoride (PVDF) resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal panel supports, and other conditions affecting performance of the Work.

1. Examine framing to verify that girts, angles, channels, studs, and other structural panel support members and anchorage have been installed within alignment tolerances required by metal panel manufacturer.
2. Examine sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by metal panel manufacturer.

B. Examine roughing-in for components and systems penetrating metal panels to verify actual locations of penetrations relative to seam locations of metal panels before installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C754 and metal panel manufacturer's written recommendations.

1. Soffit Framing: Wire tie or clip furring channels to supports.

3.3 INSTALLATION OF METAL SOFFIT PANELS

A. Install metal panels according to manufacturer's written instructions in orientation, sizes, and locations indicated. Install panels perpendicular to supports unless otherwise indicated. Anchor metal panels and other components of the Work securely in place, with provisions for thermal and structural movement.

1. Shim or otherwise plumb substrates receiving metal panels.
2. Flash and seal metal panels at perimeter of all openings. Fasten with self-tapping screws. Do not begin installation until air- or water-resistive barriers and flashings that will be concealed by metal panels are installed.
3. Install screw fasteners in predrilled holes.
4. Locate and space fastenings in uniform vertical and horizontal alignment.
5. Install flashing and trim as metal panel work proceeds.
6. Locate panel splices over, but not attached to, structural supports. Stagger panel splices and end laps to avoid a four-panel lap splice condition.
7. Provide weathertight escutcheons for pipe- and conduit-penetrating panels.

B. Fasteners:

1. Aluminum Panels: Use aluminum or stainless steel fasteners for surfaces exposed to the exterior; use aluminum or galvanized-steel fasteners for surfaces exposed to the interior.

C. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action as recommended in writing by metal panel manufacturer.

D. Lap-Seam Metal Panels: Fasten metal panels to supports with fasteners at each lapped joint at location and spacing recommended by manufacturer.

1. Apply panels and associated items true to line for neat and weathertight enclosure.
2. Provide metal-backed washers under heads of exposed fasteners bearing on weather side of metal panels.
3. Locate and space exposed fasteners in uniform vertical and horizontal alignment. Use proper tools to obtain controlled uniform compression for positive seal without rupture of washer.
4. Install screw fasteners with power tools having controlled torque adjusted to compress washer tightly without damage to washer, screw threads, or panels. Install screws in predrilled holes.

E. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.

1. Install components required for a complete metal panel system including trim, corners, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items. Provide types indicated by metal panel manufacturer; or, if not indicated, provide types recommended by metal panel manufacturer.

F. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.

1. Install exposed flashing and trim that is without buckling, and tool marks, and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and to achieve waterproof performance.
2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet with no joints allowed within 24 inches of corner or intersection. Where lapped expansion provisions cannot be used or would not be waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with mastic sealant (concealed within joints).

3.4 CLEANING AND PROTECTION

A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.

B. After metal panel installation, clear weep holes and drainage channels of obstructions, dirt, and sealant.

C. Replace metal panels that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION

SECTION 075419 - POLYVINYL-CHLORIDE (PVC) ROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Polyvinyl chloride (PVC) roofing system.
2. Accessory roofing system materials.
3. Substrate board.
4. Vapor retarder.
5. Roof insulation and accessories.
6. Cover board.
7. Walkways.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for wood nailers, curbs, and blocking; and for wood-based, structural-use roof deck panels.
2. Section 061600 "Sheathing" for wood-based, structural-use roof panels.
3. Section 076200 "Sheet Metal Flashing and Trim" for metal roof flashings and counterflashings.
4. Section 077100 "Roof Specialties" for premanufactured copings and roof edge fasciae.
5. Section 077200 "Roof Accessories" for manufactured roof curbs, equipment supports, roof hatches, vents, and other manufactured roof accessory units.
6. Section 079200 "Joint Sealants" for joint sealants, joint fillers, and joint preparation.

1.2 DEFINITIONS

A. Roofing Terminology: Definitions in ASTM D1079 and glossary in NRCA's "Roofing Manual: Membrane Roof Systems" apply to Work of this Section.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Roofing Conference: Conduct conference at Project site.

1. Meet with Owner, Architect, Owner's insurer if applicable, testing and inspecting agency representative, Roofing System Installer, roofing system manufacturer's representative, deck Installer, air barrier Installer, and installers whose work interfaces with or affects roofing, including installers of roof accessories and roof-mounted equipment.
2. Review methods and procedures related to roofing installation, including manufacturer's written instructions.
3. Review and finalize construction schedule, and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
4. Examine deck substrate conditions and finishes for compliance with requirements, including flatness and fastening.

5. Review structural loading limitations of roof deck during and after roofing.
6. Review base flashings, special roofing details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that affects roofing system.
7. Review governing regulations and requirements for insurance and certificates if applicable.
8. Review temporary protection requirements for roofing system during and after installation.
9. Review roof observation and repair procedures after roofing installation.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of product.

C. Shop Drawings: Include roof plans, sections, details, and attachments to other work, including the following:

1. Layout and thickness of insulation.
2. Base and sheet flashings and membrane termination details.
3. Flashing details at penetrations.
4. Tapered insulation layout, thickness, and slopes.
5. Roof plan showing orientation of roof deck and orientation of roofing membrane, fastening spacings, and patterns for corner, perimeter, and field-of-roof locations.
6. Insulation fastening patterns for corner, perimeter, and field-of-roof locations.
7. Crickets, saddles, and tapered edge strips, including slopes.
8. Tie-in with adjoining wall system air barrier.

D. Samples for Verification: For the following products:

1. Roofing membrane and flashings, of color required.
2. Walkways, of color required.

E. Wind-Uplift-Resistance Submittal: For roofing system, indicating compliance with wind-uplift performance requirements.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturer Certificates:

1. Performance Requirement Certificate: Signed by roofing membrane manufacturer, certifying that roofing system complies with requirements specified in "Performance Requirements" Article.

a. Submit evidence of compliance with specified performance requirements.

2. Special Warranty Certificate: Signed by roofing membrane manufacturer, certifying that all materials supplied under this Section are acceptable for special warranty.

C. Product Test Reports: For roofing membrane and insulation, tests performed by an independent qualified testing agency indicating compliance with specified requirements.

D. Field quality-control reports.

E. Qualification Data: For roofing system Installer and manufacturer.

F. Sample warranties.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For roofing system.

1.7 QUALITY ASSURANCE

A. Manufacturer Qualifications: A qualified manufacturer that is UL listed for roofing system identical to that used for this Project.

B. Installer Qualifications: A qualified firm that is approved, authorized, certified, or licensed by roofing system manufacturer to install manufacturer's product and that is eligible to receive manufacturer's special warranty.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Deliver roofing system materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, approval or listing agency markings, and directions for storing and mixing with other components.

B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer.

1. Protect stored liquid material from direct sunlight.
2. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.

C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources.

1. Store in a dry location.
2. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.

D. Handle and store roofing system materials, and place equipment in a manner to avoid permanent deflection of deck.

1.9 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed in accordance with manufacturer's written installation instructions and warranty requirements.

1.10 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of roofing system that fail in materials or workmanship within specified warranty period.

1. Special warranty to include all components of roofing system, such as substrate board, vapor retarder, roof insulation, fasteners, adhesives, cover board, roofing membrane, base flashing sheet, walkways, and other components of roofing system.
2. Warranty Period: 30 years from date of Substantial Completion.
3. Warranty must cover peak 3-second windspeed to 72 mph.

B. Roofing System Installer's Warranty: Submit Roofing System Installer's warranty, on warranty form at end of this Section, signed by Roofing System Installer, covering the Work of this Section, including all components of roofing system, such as substrate board, vapor retarder, roof insulation, fasteners, adhesives, cover board, roofing membrane, base flashing sheet, walkways and other components of roofing system.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain components for roofing system from roofing membrane manufacturer or manufacturer approved by roofing membrane manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. General Performance: Installed roofing system and flashings to withstand specified uplift pressures, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Roofing system and flashings to remain watertight.

1. Accelerated Weathering: Roofing membrane to withstand 2000 hours of exposure when tested in accordance with ASTM G152, ASTM G154, or ASTM G155.
2. Impact Resistance: Roofing membrane to resist impact damage when tested in accordance with ASTM D3746/D3746M, ASTM D4272/D4272M, or the Resistance to Foot Traffic Test in FM Approvals 4470.

B. Material Compatibility: Roofing system materials to be compatible with one another and adjacent materials under conditions of service and application required, as demonstrated by roofing membrane manufacturer based on testing and field experience.

C. Wind-Uplift Resistance: Design roofing system to resist the wind-uplift pressures as indicated below when tested in accordance with FM Approvals 4474, UL 580, or UL 1897:

1. Zone 1 (Roof Area Field): 55 lbs./sq. ft.
2. Zone 2 (Roof Area Perimeter): 85 lbs./sq. ft.
3. Zone 3 (Roof Area Corners): 115 lbs./sq. ft.
4. Zone 4 (Perimeter Roof Edge Fascia-outward from building face): 45 lbs./sq. ft.
5. Zone 5 (Coner Roof Edge Fascia-outward from building face): 65 lbs./sq. ft.

D. FM Approvals' RoofNav Listing: Roofing membrane, base flashings, and component materials to comply with requirements in FM Approvals 4450 or FM Approvals 4470 as part of a roofing system and are listed in FM Approvals' RoofNav for Class 1 or noncombustible construction, as applicable. Identify materials with FM Approvals Certification markings.

1. Fire/Windstorm Classification: Class 1A-105.
2. Hail-Resistance Rating: FM Global Property Loss Prevention Data Sheet 1-34 SH.

E. Exterior Fire-Test Exposure: Class A; for application and roof slopes indicated; when tested by a qualified testing agency in accordance with ASTM E108 or UL 790.

2.3 POLYVINYL CHLORIDE (PVC) ROOFING SYSTEM

A. PVC-Ketone Ethylene Ester (KEE)-Alloy Roofing Membrane Sheet: ASTM D4434/D4434M, fabric reinforced.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Carlisle Syntec Systems
b. GAF
c. Johns Manville; a Berkshire Hathaway company

2. Classification: Type III, with fabric backing.
3. Nominal Thickness: 80 mil.
4. Exposed Face Color: White.

2.4 ACCESSORY ROOFING SYSTEM MATERIALS

A. General: Accessory materials as recommended in writing by roofing membrane manufacturer for intended use and compatible with other roofing system components.

B. Base and Sheet Flashings: Manufacturer's standard sheet flashing of same material, type, reinforcement, thickness, and color as roofing membrane.

C. Prefabricated Pipe Flashings: As recommended in writing by roofing membrane manufacturer.

D. Roof Vents: As recommended in writing by roofing membrane manufacturer.

1. Size: Not less than 4-inch diameter.

E. Bonding Adhesive: Roofing membrane manufacturer's standard, water based.

F. Low-Rise, Urethane, Fabric-Backed Membrane Adhesive: Roofing membrane manufacturer's standard spray-applied, low-rise, two-component urethane adhesive formulated for compatibility and use with fabric-backed roofing membrane.

G. Metal Termination Bars: Manufacturer's standard, predrilled stainless steel or aluminum bars, approximately 1 by 1/8 inch thick; with anchors.

H. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening roofing system components to substrate, tested for required pullout strength, and acceptable to roofing membrane manufacturer.

I. Miscellaneous Accessories: As recommended in writing by roofing membrane manufacturer.

2.5 SUBSTRATE BOARD

A. Glass-Mat Gypsum Roof Substrate Board: ASTM C1177/C1177M, water-resistant gypsum board.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. CertainTeed; SAINT-GOBAIN
b. Georgia-Pacific Gypsum LLC
c. Gold Bond Building Products, LLC provided by National Gypsum Company
d. USG Corporation

B. High-Density Polyisocyanurate Cover Board: ASTM C1289, Type II, Class 4, Grade 1, 1/2 inch thick, having a minimum compressive strength of 80 psi.

C. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening substrate board to roof deck.

D. Bonding Adhesive: Manufacturer's standard, designed for adhering substrate board to roof deck.

2.6 VAPOR RETARDER

A. Rubberized-Asphalt-Sheet Vapor Retarder, Self-Adhering: ASTM D1970/D1970M, polyethylene film laminated to layer of rubberized asphalt adhesive, minimum 40-mil total thickness; maximum permeance rating of 0.1 perm; cold applied, with slip-resisting surface and release paper backing. Provide primer when recommended by vapor retarder manufacturer.

2.7 ROOF INSULATION AND ACCESSORIES

A. General: Preformed roof insulation boards manufactured or approved by roofing membrane manufacturer approved for use in FM Approvals' RoofNav listed roof assemblies.

B. Polyisocyanurate Board Insulation: ASTM C1289, Type II, Class 1, Grade 2, felt or glass-fiber mat facer on both major surfaces.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Atlas Polyiso Roof and Wall Insulation
b. Carlisle Syntec Systems
c. CertainTeed; SAINT-GOBAIN
d. Elevate; Holcim Building Envelope
e. GAF
f. Hunter Panels; a Carlisle company
g. IKO Industries Inc.
h. Insulfoam; a Carlisle Company
i. Johns Manville; a Berkshire Hathaway company
j. Kingspan Insulation LLC
k. Polyglass U.S.A., Inc.
l. Rmax, A Business Unit of Sika Corporation

2. Compressive Strength: Grade 3, 25 psi.
3. Size: 48 by 48 inches.
4. Thickness:

a. Base Layer: 4-1/2 inches.
b. Upper Layer: 4-1/2 inches.

C. Tapered Insulation: Provide factory-tapered insulation boards.

1. Material: Match roof insulation.
2. Minimum Thickness: 1/4 inch.
3. Slope:

a. Roof Field: 1/4 inch per foot unless otherwise indicated on Drawings.
b. Saddles and Crickets: 1/2 inch per foot unless otherwise indicated on Drawings.

D. General: Roof insulation accessories as recommended in writing by insulation manufacturer for intended use and compatibility with other roofing system components.

1. Insulation Adhesive: Insulation manufacturer's standard adhesive formulated to attach roof insulation to substrate and to another insulation layer as follows:

a. Bead-applied, low-rise, one-component or multicomponent urethane adhesive.

2. Insulation Fasteners: Insulation manufacturer's standard factory-coated steel fasteners with metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening roof insulation and cover board to substrate, and acceptable to roofing system manufacturer.

2.8 COVER BOARD

A. General: Cover board as recommended in writing by roofing membrane manufacturer for intended use and compatible with other roofing system components.

B. High-Density Polyisocyanurate Cover Board: ASTM C1289, Type II, Class 4, Grade 1, 1/2 inch thick, having a minimum compressive strength of 80 psi.

2.9 WALKWAYS

A. Flexible Walkways: Factory-formed, nonporous, heavy-duty, slip-resisting, surface-textured walkway pads or rolls, approximately 3/16 inch thick and acceptable to roofing system manufacturer.

1. Size: Approximately 36 by 60 inches.
2. Color: Contrasting with roofing membrane.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Roofing System Installer present, for compliance with requirements and other conditions affecting performance of the Work.

1. Verify that roof openings and penetrations are in place, curbs are set and braced, and roof-drain bodies are securely clamped in place.
2. Verify that wood blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
3. Verify that concrete substrate is visibly dry and free of moisture, and that minimum concrete internal relative humidity is not more than 75 percent, or as recommended by roofing system manufacturer, when tested in accordance with ASTM F2170.

a. Test Frequency: One test probe per each 1000 sq. ft., or portion thereof, of roof deck, with no fewer than three test probes.
b. Submit test reports within 24 hours of performing tests.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing system installation in accordance with roofing system manufacturer's written instructions. Remove sharp projections.

B. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.

C. Prime surface of concrete deck with primer in accordance with roofing system manufacturer's written installation instructions and allow primer to dry.

3.3 INSTALLATION OF POLYVINYL-CHLORIDE (PVC) ROOFING SYSTEM, GENERAL

A. Install roofing system materials and components in accordance with roofing system manufacturer's written installation instructions, FM Approvals' Roof, Nav listed roof assembly requirements, and FM Global Property Loss Prevention Data Sheet 1-29.

B. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at end of workday or when rain is forecast. Remove and discard temporary seals before beginning Work on adjoining roofing.

C. Substrate-Joint Penetrations: Prevent adhesives from penetrating substrate joints, entering building, or damaging roofing system components or adjacent building construction.

3.4 INSTALLATION OF SUBSTRATE BOARD

A. Install substrate board with long joints in continuous straight lines, with end joints staggered not less than 24 inches in adjacent rows.

1. Install substrate board at right angle to flutes of steel roof deck. Locate end joints over crests of steel roof deck.
2. Tightly butt substrate boards together.
3. Cut substrate board to fit tight around penetrations and projections, and to fit tight to intersecting sloping roof decks.
4. Fasten substrate board to top flanges of steel deck to resist uplift pressure at corners, perimeter, and field of roof in accordance with roofing system manufacturers' written installation instructions.

3.5 INSTALLATION OF VAPOR RETARDER

A. Install vapor retarder in a single layer over roof area in accordance with manufacturer's written installation instructions, side and end lapping each sheet a minimum of 2 and 6 inches, respectively.

1. Extend vertically up parapet walls and projections to a minimum height equal to height of insulation and cover board.
2. Continuously seal side and end laps with tape.

B. Completely seal vapor retarder at terminations, obstructions, and penetrations to prevent air movement into roofing system.

3.6 INSTALLATION OF ROOF INSULATION AND ACCESSORIES

A. Coordinate installation of roofing system components so insulation is not exposed to precipitation or left exposed at end of workday.

B. Comply with roofing system and insulation manufacturer's written installation instructions. Install minimum of two layers of insulation under area of roofing to achieve required thickness.

C. Install each layer of insulation with joints staggered not less than 24 inches in adjacent rows and end joints staggered not less than 12 inches in adjacent rows and offset not less than 12 inches from previous layer.

1. Trim insulation neatly to fit around penetrations and projections, and to fit tightly to intersecting sloping roof decks.
2. Make joints between adjacent insulation boards not more than 1/4 inch in width.
3. At internal roof drains, slope insulation to create a square drain sump, with each side equal to the diameter of the drain bowl plus 24 inches.
4. Trim insulation, so that water flow is unrestricted.
5. Fill gaps exceeding 1/4 inch with insulation.
6. Cut and fit insulation within 1/4 inch of nailers, projections, and penetrations.
7. Secure insulation in accordance with FM Approvals' RoofNav for specified Windstorm Resistance Classification.
8. Secure insulation to resist specified uplift pressure at corners, perimeter, and field of roof.

3.7 INSTALLATION OF COVER BOARD

A. Install cover board over insulation with long joints in continuous straight lines with end joints staggered between rows. Offset joints of insulation below a minimum of 6 inches in each direction.

1. Trim cover board neatly to fit around penetrations and projections, and to fit tight to intersecting sloping roof decks.
2. At internal roof drains, conform to slope of drain sump.

    a. Trim cover board so that water flow is unrestricted.

3. Cut and fit cover board tight to nailers, projections, and penetrations.
4. Adhere cover board to substrate in accordance with FM Approvals' RoofNav listed roof assembly requirements for specified Windstorm Resistance Classification and FM Global Property Loss Prevention Data Sheet 1-29.

3.8 INSTALLATION OF PVC ROOFING MEMBRANE

A. Install roofing membrane over roof area for adhered application method in accordance with roofing system manufacturer's written installation instructions.

B. Unroll roofing membrane and allow it to relax before installing.

C. Start installation in presence of roofing system manufacturer's technical personnel.

D. Accurately align roofing membrane and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps. Apply roofing membrane with side laps shingled with slope of roof deck where possible.

E. Adhered Application: Apply bonding adhesive to substrate and underside of roofing membrane at rate required by manufacturer and allow to partially dry before installing roofing membrane. Do not apply to splice area of roofing membrane.

1. In addition to adhering, mechanically fasten roofing membrane securely at terminations, penetrations, and perimeter of roofing.

F. Seams and End Laps: Clean seam areas, overlap membrane, and hot-air-weld side seams and end laps of roofing membrane and sheet flashing to ensure a watertight installation.

1. Test lap edges with probe to verify seam weld continuity. Apply lap sealant to seal cut edges of roofing membrane and sheet flashings.
2. Verify field strength of seams a minimum of twice daily, and repair seam sample areas.
3. Repair tears, voids, and lapped seams in roofing membrane that do not comply with requirements.

G. Spread sealant bed over deck-drain flange at roof drains, and securely seal roof membrane in place with clamping ring.

3.9 INSTALLATION OF BASE AND SHEET FLASHINGS

A. General: Install and adhere base and sheet flashings and preformed flashing accessories to substrates in accordance with roofing system manufacturer's written installation instructions.

B. Apply bonding adhesive to substrate and underside of flashings at required rate and allow to partially dry. Do not apply to seam area of flashing.

C. Flash penetrations and field-formed inside and outside corners.

D. Clean seam areas, overlap, and firmly roll flashings into the adhesive. Hot-air-weld side seams and end laps to ensure a watertight installation.

E. Terminate and seal top of flashings and mechanically anchor to substrate through termination bars.

3.10 INSTALLATION OF WALKWAYS

A. Flexible Walkways: Install walkway products in accordance with manufacturer's written instructions.

1. Install flexible walkways at the following locations:

a. Perimeter of each rooftop unit.
b. Between each rooftop unit location, creating a continuous path connecting rooftop unit locations.
c. Between each roof hatch and each rooftop unit location or path connecting rooftop unit locations.
d. Top and bottom of each roof access ladder.
e. Between each roof access ladder and each rooftop unit location or path connecting rooftop unit locations.

f. Locations indicated on Drawings.
g. As required by roofing membrane manufacturer's warranty requirements.

2. Provide 6-inch clearance between adjoining pads.
3. Heat weld to substrate or adhere walkway products to substrate with compatible adhesive in accordance with roofing system manufacturer's written instructions.

3.11 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspect substrate conditions, surface preparation, and application of roofing membrane, flashings, protection, and drainage components, and to furnish reports to Architect.

B. Perform the following tests:

1. ELD Testing: Testing agency surveys entire roof area and flashings to locate discontinuities in the roofing membrane using ELD in accordance with ASTM D7877 and ASTM D8231.

a. After testing, repair areas of discontinuities, repeat tests, and make further repairs until roofing and flashing installations are contiguous.

1) Cost of retesting is Contractor's responsibility.

b. Testing agency to prepare survey report indicating locations of initial discontinuities, if any.

C. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion, in presence of Architect, and to prepare inspection report.

1. Notify Architect 48 hours in advance of date and time of inspection.

D. Repair or remove and replace components of roofing system where inspections indicate that they do not comply with specified requirements.

E. Additional testing and inspecting, at Contractor's expense, will be performed to determine if replaced or additional work complies with specified requirements.

3.12 PROTECTING AND CLEANING

A. Protect roofing system from damage and wear during remainder of construction period. When remaining construction does not affect or endanger roofing, inspect roofing system for deterioration and damage, describing its nature and extent in a written report, with copies to Architect and Owner.

B. Correct deficiencies in or remove roofing system that does not comply with requirements, repair substrates, and repair or reinstall roofing system to a condition free of damage and deterioration at time of Substantial Completion and in accordance with warranty requirements.

C. Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

3.13 ROOFING SYSTEM INSTALLER'S WARRANTY

A. WHEREAS _____ of _____, herein called the "Roofing System Installer," has performed roofing and associated Work on the following Project:

1. Owner: <**Insert name of Owner**>.
2. Owner Address: <**Insert address**>.
3. Building Name/Type: <**Insert information**>.
4. Building Address: <**Insert address**>.
5. Area of Work: <**Insert information**>.
6. Acceptance Date: _____.
7. Warranty Period: Five years from date of Substantial Completion.
8. Date of Substantial Completion: _____.

B. AND WHEREAS Roofing System Installer has contracted (either directly with Owner or indirectly as a subcontractor) to warrant said Work against leaks and faulty or defective materials and workmanship for designated Warranty Period,

C. NOW THEREFORE Roofing System Installer hereby warrants, subject to terms and conditions herein set forth, that during Warranty Period Roofing Installer will, at Roofing System Installer's own cost and expense, make or cause to be made such repairs to or replacements of said Work as are necessary to correct faulty and defective work and as are necessary to maintain said Work in a watertight condition.

D. This Warranty is made subject to the following terms and conditions:

1. Specifically excluded from this Warranty are damages to Work and other parts of the building, and to building contents, caused by:

    a. lightning;
    b. peak gust wind speed exceeding 72 mph;
    c. fire;
    d. failure of roofing system substrate, including cracking, settlement, excessive deflection, deterioration, and decomposition;
    e. faulty construction of parapet walls, copings, chimneys, skylights, vents, equipment supports, and other edge conditions and penetrations of the Work;
    f. vapor condensation on bottom of roofing; and
    g. activity on roofing by others, including construction contractors, maintenance personnel, other persons, and animals, whether authorized or unauthorized by Owner.

2. When Work has been damaged by any of foregoing causes, Warranty will be null and void until such damage has been repaired by Roofing System Installer and until cost and expense thereof have been paid by Owner or by another responsible party so designated.
3. Roofing System Installer is responsible for damage to Work covered by this Warranty but is not liable for consequential damages to building or building contents resulting from leaks or faults or defects of Work.

4. During Warranty Period, if Owner allows alteration of Work by anyone other than Roofing System Installer, including cutting, patching, and maintenance in connection with penetrations, attachment of other work, and positioning of anything on roof, this Warranty will become null and void on date of said alterations, but only to the extent said alterations affect Work covered by this Warranty. If Owner engages Roofing System Installer to perform said alterations, Warranty will not become null and void unless Roofing System Installer, before starting said Work, will have notified Owner in writing, showing reasonable cause for claim, that said alterations would likely damage or deteriorate Work, thereby reasonably justifying a limitation or termination of this Warranty.
5. During Warranty Period, if original use of roof is changed and it becomes used for, but was not originally specified for, a promenade, work deck, spray-cooled surface, flooded basin, or other use or service more severe than originally specified, this Warranty will become null and void on date of said change, but only to the extent said change affects Work covered by this Warranty.
6. Owner will promptly notify Roofing System Installer of observed, known, or suspected leaks, defects, or deterioration and afford reasonable opportunity for Roofing System Installer to inspect Work and to examine evidence of such leaks, defects, or deterioration.
7. This Warranty is recognized to be the only warranty of Roofing System Installer on said Work and will not operate to restrict or cut off Owner from other remedies and resources lawfully available to Owner in cases of roofing failure. Specifically, this Warranty will not operate to relieve Roofing System Installer of responsibility for performance of original Work in accordance with requirements of the Contract Documents, regardless of whether Contract was a contract directly with Owner or a subcontract with Owner's General Contractor.

E. IN WITNESS THEREOF, this instrument has been duly executed this _____ day of _____, _____.

1. Authorized Signature: _____.
2. Name: _____.
3. Title: _____.

END OF SECTION

SECTION 076200 - SHEET METAL FLASHING AND TRIM

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Custom flashing and trim fabrications, made from the following:

1. Sheet metal materials.
2. Underlayment.
3. Miscellaneous materials.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for wood nailers, curbs, and blocking.
2. Section 077100 "Roof Specialties" for manufactured copings, roof-edge specialties, roof-edge drainage systems, reglets, and counterflashings.
3. Section 077200 "Roof Accessories" for set-on-type curbs, equipment supports, roof hatches, vents, and other manufactured roof accessory units.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Shop Drawings: For sheet metal flashing and trim.

1. Plans, elevations, sections, and attachment details.
2. Fabrication and installation layouts, expansion-joint locations, and keyed details. Distinguish between shop- and field-assembled Work.
3. Identification of material, thickness, weight, and finish for each item and location in Project.
4. Details for forming, including profiles, shapes, seams, and dimensions.
5. Details for joining, supporting, and securing, including layout and spacing of fasteners, cleats, clips, and other attachments. Include pattern of seams.
6. Details of termination points and assemblies.
7. Details of roof-penetration flashing.
8. Details of edge conditions, including flashings and counterflashings.
9. Details of special conditions.
10. Details of connections to adjoining work.
11. Formed flashing and trim at scale of not less than 1-1/2 inches per 12 inches.

D. Samples for Verification: Actual sample of finished products for each type of exposed finish for sheet metal and other metal accessories.

1. Sheet Metal Flashing and Trim: 12 inches long by actual width of unit. Include finished

seam with required profile. Include fasteners, cleats, clips, closures, and other attachments.

2. Anodized Aluminum Samples: Samples to show full range to be expected for each color required.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Statements: For fabricator.

C. Sample warranties.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For sheet metal flashing and trim, and its accessories.

1.5 QUALITY ASSURANCE

A. Fabricator Qualifications: Entity that employs skilled workers who custom fabricate sheet metal flashing and trim similar to that required for this Project and whose products have a record of successful in-service performance.

B. For roof edge flashings and copings that are ANSI/SPRI/FM 4435/ES-1 tested and FM Approvals approved, shop is to be listed as able to fabricate required details as tested and approved.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Do not store sheet metal flashing and trim materials in contact with other materials that might cause staining, denting, or other surface damage.

1. Store sheet metal flashing and trim materials away from uncured concrete and masonry.
2. Protect stored sheet metal flashing and trim from contact with water.

B. Protect strippable protective covering on sheet metal flashing and trim from exposure to sunlight and high humidity, except to extent necessary for period of sheet metal flashing and trim installation.

1.7 COORDINATION

A. Coordinate sheet metal flashing and trim layout and seams with sizes and locations of penetrations to be flashed, and joints and seams in adjacent materials.

B. Coordinate sheet metal flashing and trim installation with adjoining roofing and wall materials, joints, and seams to provide leakproof, secure, and noncorrosive installation.

1.8 WARRANTY

A. Special Warranty on Finishes: Manufacturer agrees to repair finish or replace sheet metal flashing and trim that shows evidence of deterioration of factory-applied finishes within specified warranty period.

1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:

a. Color fading more than 5 Delta E units when tested in accordance with ASTM D2244.
b. Chalking in excess of a No. 8 rating when tested in accordance with ASTM D4214.
c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.

2. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Sheet metal flashing and trim assemblies, including cleats, anchors, and fasteners, are to withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Completed sheet metal flashing and trim are not to rattle, leak, or loosen, and are to remain watertight.

B. Sheet Metal Standard for Flashing and Trim: Comply with NRCA's "The NRCA Roofing Manual: Architectural Metal Flashing, Condensation and Air Leakage Control, and Reroofing" and SMACNA's "Architectural Sheet Metal Manual" requirements for dimensions and profiles shown unless more stringent requirements are indicated.

C. Sheet Metal Standard for Copper: Comply with CDA's "Copper in Architecture Design Handbook." Conform to dimensions and profiles shown unless more stringent requirements are indicated.

D. SPRI Wind Design Standard: Manufacture and install roof edge flashings and copings tested in accordance with ANSI/SPRI/FM 4435/ES-1 and capable of resisting the following design pressure:

1. Design Pressure: As indicated on Drawings.

E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 SHEET METAL MATERIALS

A. Protect mechanical and other finishes on exposed surfaces from damage by applying strippable, temporary protective film before shipping.

B. Aluminum Sheet: Coil-coated sheet, ASTM B209/B209M, alloy as standard with manufacturer, with temper as required to suit forming operations and structural performance required.

1. Thickness: 0.040 inch.
2. Surface: Smooth, flat.
3. Exposed Coil-Coated Finish:

    a. Two-Coat Fluoropolymer: AAMA 2605. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

4. Color: As selected by Architect from manufacturer's full range.
5. Concealed Finish: Pretreat with manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with minimum total dry film thickness of 0.5 mil.

C. Stainless Steel Sheet: ASTM A240/A240M, Type 304, dead soft, fully annealed.

1. Nominal Thickness: 0.0188 inch.
2. Surface: Smooth, flat.
3. Exterior Finish: ASTM A480/A480M, No. 2D (dull, cold rolled).

    a. Surface Preparation: Remove tool and die marks and stretch lines, or blend into finish.

D. Copper Sheet: ASTM B370, cold-rolled copper sheet, H00 or H01 temper.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Hussey Copper Ltd.
    b. Revere Copper Products, Inc

2. Nonpatinated, Exposed Finish: Mill.

2.3 UNDERLAYMENT

A. Self-Adhering, High-Temperature Sheet Underlayment: Provide self-adhering, cold-applied, sheet underlayment, a minimum of 30 mils thick, specifically designed to withstand high metal temperatures beneath metal roofing. Provide primer when recommended by underlayment manufacturer.

1. Thermal Stability: Stable after testing at 240 deg F; ASTM D1970/D1970M.
2. Low-Temperature Flexibility: Passes after testing at minus 20 deg F or lower; ASTM

D1970/D1970M.

3. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Carlisle WIP Products; a brand of Carlisle Construction Materials
    b. GCP Applied Technologies Inc.
    c. Henry, a Carlisle Company (formerly Henry Company and Carlisle Coatings & Waterproofing Inc. brands)
    d. Owens Corning

B. Felt: ASTM D226/D226M, Type II (No. 30), asphalt-saturated organic felt; nonperforated.

C. Slip Sheet: Rosin-sized building paper, 3 lb/100 sq. ft. minimum, of type required for application.

2.4 MISCELLANEOUS MATERIALS

A. Provide materials and types of fasteners, solder, protective coatings, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and as recommended by manufacturer of primary sheet metal or manufactured item unless otherwise indicated.

B. Fasteners: Wood screws, annular threaded nails, self-tapping screws, self-locking rivets and bolts, and other suitable fasteners designed to withstand design loads and recommended by manufacturer of primary sheet metal or manufactured item.

1. General: Blind fasteners or self-drilling screws, gasketed, with hex-washer head.

    a. Exposed Fasteners: Heads matching color of sheet metal using plastic caps or factory-applied coating. Provide metal-backed EPDM or PVC sealing washers under heads of exposed fasteners bearing on weather side of metal.
    b. Blind Fasteners: High-strength aluminum or stainless steel rivets suitable for metal being fastened.
    c. Spikes and Ferrules: Same material as gutter; with spike with ferrule matching internal gutter width.

2. Fasteners for Aluminum Sheet: Aluminum or Series 300 stainless steel.
3. Fasteners for Stainless Steel Sheet: Series 300 stainless steel.
4. Fasteners for Copper, Zinc-Tin Alloy-Coated Copper, or Copper-Clad Stainless Steel Sheet: Copper, hardware bronze or passivated Series 300 stainless steel.

C. Solder:

1. For Stainless Steel: ASTM B32, Grade Sn60, with acid flux of type recommended by stainless steel sheet manufacturer.
2. For Copper or Copper-Clad Stainless Steel: ASTM B32, Grade Sn50, 50 percent tin and 50 percent lead.

D. Sealant Tape: Pressure-sensitive, 100 percent solids, polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape

1/2 inch wide and 1/8 inch thick.

E. Elastomeric Sealant: ASTM C920, elastomeric silicone polymer sealant; of type, grade, class, and use classifications required to seal joints in sheet metal flashing and trim and remain watertight.

F. Butyl Sealant: ASTM C1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.

G. Epoxy Seam Sealer: Two-part, noncorrosive, aluminum seam-cementing compound, recommended by aluminum manufacturer for exterior nonmoving joints, including riveted joints.

H. Bituminous Coating: Cold-applied asphalt emulsion in accordance with ASTM D1187/D1187M.

I. Asphalt Roofing Cement: ASTM D4586/D4586M, asbestos free, of consistency required for application.

J. Reglets: Units of type, material, and profile required, formed to provide secure interlocking of separate reglet and counterflashing pieces, and compatible with flashing indicatedwith interlocking counterflashing on exterior face, of same metal as reglet.

1. Material: Copper, 16 oz./sq. ft..
2. Masonry Type: Provide with offset top flange for embedment in masonry mortar joint.
3. Accessories:

    a. Flexible-Flashing Retainer: Provide resilient plastic or rubber accessory to secure flexible flashing in reglet where clearance does not permit use of standard metal counterflashing or where Drawings show reglet without metal counterflashing.
    b. Counterflashing Wind-Restraint Clips: Provide clips to be installed before counterflashing to prevent wind uplift of counterflashing's lower edge.

4. Finish: Mill.

2.5 FABRICATION, GENERAL

A. Custom fabricate sheet metal flashing and trim to comply with details indicated and recommendations in cited sheet metal standard that apply to design, dimensions, geometry, metal thickness, and other characteristics of item required.

1. Fabricate sheet metal flashing and trim in shop to greatest extent possible.
2. Fabricate sheet metal flashing and trim in thickness or weight needed to comply with performance requirements, but not less than that specified for each application and metal.
3. Verify shapes and dimensions of surfaces to be covered and obtain field measurements for accurate fit before shop fabrication.
4. Form sheet metal flashing and trim to fit substrates without excessive oil-canning, buckling, and tool marks; true to line, levels, and slopes; and with exposed edges folded back to form hems.
5. Conceal fasteners and expansion provisions where possible. Do not use exposed fasteners

on faces exposed to view.

B. Fabrication Tolerances:

1. Fabricate sheet metal flashing and trim that is capable of installation to a tolerance of 1/4 inch in 20 ft. on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.
2. Fabricate sheet metal flashing and trim that is capable of installation to tolerances specified.

C. Expansion Provisions: Form metal for thermal expansion of exposed flashing and trim.

1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with butyl sealant concealed within joints.
2. Use lapped expansion joints only where indicated on Drawings.

D. Sealant Joints: Where movable, nonexpansion-type joints are required, form metal in accordance with cited sheet metal standard to provide for proper installation of elastomeric sealant.

E. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.

F. Seams:

1. Fabricate copper nonmoving seams with flat-lock seams. Tin edges to be seamed, form seams, and solder.
2. Fabricate aluminum nonmoving seams with flat-lock seams. Form seams and seal with elastomeric sealant unless otherwise recommended by sealant manufacturer for intended use.

2.6 ROOF-DRAINAGE SHEET METAL FABRICATIONS

A. Parapet Scuppers: Fabricate scuppers to dimensions required, with closure flange trim to exterior, 4-inch-wide wall flanges to interior, and base extending 4 inches beyond cant or tapered strip into field of roof. Fabricate from the following materials:

1. Aluminum: 0.040 inch thick.

2.7 LOW-SLOPE ROOF SHEET METAL FABRICATIONS

A. Base Flashing: Fabricate from the following materials:

1. Copper: 20 oz./sq. ft..

B. Counterflashing: Fabricate from the following materials:

1. Copper: 16 oz./sq. ft..

C. Flashing Receivers: Fabricate from the following materials:

1. Copper: 16 oz./sq. ft..

D. Roof-Penetration Flashing: Fabricate from the following materials:

1. Stainless Steel: 0.0188 inch thick.

E. Roof-Drain Flashing: Fabricate from the following materials:

1. Stainless Steel: 0.0156 inch thick.

2.8 WALL SHEET METAL FABRICATIONS

A. Through-Wall Flashing: Fabricate continuous flashings in minimum 96-inch-long, but not exceeding 12 ft. long, sections, under copings, and at shelf angles. Fabricate discontinuous lintel, sill, and similar flashings to extend 6 inches beyond each side of wall openings; and form with 2-inch-high, end dams. Fabricate from the following materials:

1. Copper: 16 oz./sq. ft..

2.9 MISCELLANEOUS SHEET METAL FABRICATIONS

A. Equipment Support Flashing: Fabricate from the following materials:

1. Stainless Steel: 0.0188 inch thick.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, substrates, and other conditions affecting performance of the Work.

1. Verify compliance with requirements for installation tolerances of substrates.
2. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
3. Verify that air- or water-resistant barriers have been installed over substrate to prevent air infiltration or water penetration.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF UNDERLAYMENT

A. Self-Adhering, High-Temperature Sheet Underlayment:

1. Install self-adhering, high-temperature sheet underlayment; wrinkle free.
2. Prime substrate if recommended by underlayment manufacturer.

3. Comply with temperature restrictions of underlayment manufacturer for installation; use primer for installing underlayment at low temperatures.
4. Apply in shingle fashion to shed water, with end laps of not less than 6 inches staggered 24 inches between courses.
5. Overlap side edges not less than 3-1/2 inches. Roll laps and edges with roller.
6. Roll laps and edges with roller.
7. Cover underlayment within 14 days.

B. Install slip sheet, wrinkle free, over underlayment before installing sheet metal flashing and trim.

1. Install in shingle fashion to shed water.
2. Lapp joints not less than 4 inches.

3.3 INSTALLATION OF SHEET METAL FLASHING AND TRIM, GENERAL

A. Install sheet metal flashing and trim to comply with details indicated and recommendations of cited sheet metal standard that apply to installation characteristics required unless otherwise indicated on Drawings.

1. Install fasteners, solder, protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.
2. Install sheet metal flashing and trim true to line, levels, and slopes. Provide uniform, neat seams with minimum exposure of sealant.
3. Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement.
4. Install sheet metal flashing and trim to fit substrates and to result in watertight performance.
5. Install continuous cleats with fasteners spaced not more than 12 inches o.c.
6. Install exposed sheet metal flashing and trim with limited oil-canning, and free of buckling and tool marks.
7. Do not field cut sheet metal flashing and trim by torch.

B. Metal Protection: Where dissimilar metals contact each other, or where metal contacts pressure-treated wood or other corrosive substrates, protect against galvanic action or corrosion by painting contact surfaces with bituminous coating or by other permanent separation as recommended by sheet metal manufacturer or cited sheet metal standard.

1. Underlayment: Where installing sheet metal flashing and trim directly on cementitious or wood substrates, install underlayment and cover with slip sheet.

C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim.

1. Space movement joints at maximum of 10 ft. with no joints within 24 inches of corner or intersection.
2. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with sealant concealed within joints.
3. Use lapped expansion joints only where indicated on Drawings.

D. Fasteners: Use fastener sizes that penetrate wood blocking or sheathing not less than 1-1/4 inches for nails and not less than 3/4 inch for wood screws.

E. Conceal fasteners and expansion provisions where possible in exposed work and locate to minimize possibility of leakage. Cover and seal fasteners and anchors as required for a tight installation.

F. Seal joints as required for watertight construction.

1. Use sealant-filled joints unless otherwise indicated.

a. Embed hooked flanges of joint members not less than 1 inch into sealant.
b. Form joints to completely conceal sealant.
c. When ambient temperature at time of installation is between 40 and 70 deg F, set joint members for 50 percent movement each way.
d. Adjust setting proportionately for installation at higher ambient temperatures.

1) Do not install sealant-type joints at temperatures below 40 deg F.

2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."

G. Soldered Joints: Clean surfaces to be soldered, removing oils and foreign matter.

1. Pretin edges of sheets with solder to width of 1-1/2 inches; however, reduce pretinning where pretinned surface would show in completed Work.
2. Do not solder aluminum sheet.
3. Do not use torches for soldering.
4. Heat surfaces to receive solder, and flow solder into joint.

a. Fill joint completely.
b. Completely remove flux and spatter from exposed surfaces.

5. Stainless Steel Soldering:

a. Tin edges of uncoated sheets, using solder for stainless steel and acid flux.
b. Promptly remove acid-flux residue from metal after tinning and soldering.
c. Comply with solder manufacturer's recommended methods for cleaning and neutralization.

6. Copper Soldering: Tin edges of uncoated sheets, using solder for copper.

H. Rivets: Rivet joints in uncoated aluminum where necessary for strength.

3.4 INSTALLATION OF ROOF-DRAINAGE SHEET METAL FABRICATIONS

A. Install sheet metal roof-drainage items to produce complete roof-drainage system in accordance with cited sheet metal standard unless otherwise indicated. Coordinate installation of roof perimeter flashing with installation of roof-drainage system.

B. Parapet Scuppers:

1. Continuously support scupper, set to correct elevation, and seal flanges to interior wall face, over cants or tapered edge strips, and under roofing membrane.

3.5 INSTALLATION OF SLOPED ROOF SHEET METAL FABRICATIONS

A. Install sheet metal flashing and trim to comply with performance requirements, sheet metal manufacturer's written installation instructions, and cited sheet metal standard.

1. Provide concealed fasteners where possible, and set units true to line, levels, and slopes.
2. Install work with laps, joints, and seams that are permanently watertight and weather resistant.

B. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with elastomeric sealant and clamp flashing to pipes that penetrate roof.

3.6 INSTALLATION OF WALL SHEET METAL FABRICATIONS

A. Install sheet metal wall flashing to intercept and exclude penetrating moisture in accordance with cited sheet metal standard unless otherwise indicated. Coordinate installation of wall flashing with installation of wall-opening components such as windows, doors, and louvers.

3.7 INSTALLATION OF MISCELLANEOUS SHEET METAL FABRICATIONS

A. Equipment Support Flashing:

1. Coordinate installation of equipment support flashing with installation of roofing and equipment.
2. Weld or seal flashing with elastomeric sealant to equipment support member.

3.8 INSTALLATION TOLERANCES

A. Shim and align sheet metal flashing and trim within installed tolerance of 1/4 inch in 20 ft. on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

3.9 CLEANING

A. Clean and neutralize flux materials. Clean off excess solder.

B. Clean off excess sealants.

3.10 PROTECTION

A. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions.

B. On completion of sheet metal flashing and trim installation, remove unused materials and clean finished surfaces as recommended in writing by sheet metal flashing and trim manufacturer.

C. Maintain sheet metal flashing and trim in clean condition during construction.

D. Replace sheet metal flashing and trim that have been damaged or that have deteriorated beyond successful repair by finish touchup or similar minor repair procedures, as determined by Architect.

END OF SECTION

SECTION 077100 - ROOF SPECIALTIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Manufactured units for the following applications:

1. Roof-edge specialties.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for wood nailers, curbs, and blocking.
2. Section 076200 "Sheet Metal Flashing and Trim" for custom- and site-fabricated, sheet metal flashing and trim.
3. Section 077200 "Roof Accessories" for manufactured roof curbs, equipment supports, roof hatches, vents, and other manufactured roof accessory units.
4. Section 079200 "Joint Sealants" for field-applied sealants between roof specialties and adjacent materials.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of roof specialty.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

C. Shop Drawings: For roof specialties.

1. Plans, keyed details, and attachments to other work. Distinguish between factory pre manufactured- and field-assembled installation.

D. Samples for Verification:

1. Include Samples of each type of roof specialty to verify finish and color selection, in manufacturer's standard sizes.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Certificates: For each type of roof specialty roof-edge flashings that is ANSI/SPRI/FM 4435/ES-1 tested and FM Approvals approved.

C. Product Test Reports: For roof-edge flashings, for tests performed by a qualified testing agency.

D. Qualification Statements: For manufacturer.

E. Sample warranties.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For roof specialties.

1.5 QUALITY ASSURANCE

A. Manufacturer Qualifications: A qualified manufacturer offering products that are FM Approvals listed for specified class and ANSI/SPRI/FM 4435/ES-1 tested to specified design pressure.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Do not store roof specialties in contact with other materials that might cause staining, denting, or other surface damage. Store roof specialties away from uncured concrete and masonry.

B. Protect strippable protective covering on roof specialties from exposure to sunlight and high humidity, except to extent necessary for the period of roof-specialty installation.

1.7 FIELD CONDITIONS

A. Field Measurements: Verify profiles and tolerances of roof-specialty substrates by field measurements before fabrication, and indicate measurements on Shop Drawings.

1.8 COORDINATION

A. Coordinate roof specialties with roofing system, exterior wall system, air barrier, flashing, trim, and construction of parapets, roof deck, roof and wall panels, and other adjoining work to provide a leakproof, weathertight, secure, and noncorrosive installation.

1.9 WARRANTY

A. Roofing-System Warranty: Roof specialties are included in warranty provisions in Section 075419 "Polyvinyl-Chloride (PVC) Roofing."

B. Special Warranty on Painted Finishes: Manufacturer agrees to repair finishes or replace roof specialties that show evidence of deterioration of factory-applied finishes within specified warranty period.

1. Fluoropolymer Finish: Deterioration includes, but is not limited to, the following:

a. Color fading more than 5 Delta E units when tested in accordance with ASTM

D2244.

b. Chalking in excess of a No. 8 rating when tested in accordance with ASTM D4214.

c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.

2. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain roof specialties from single manufacturer providing roofing-system warranty specified in Section 075419 "Polyvinyl-Chloride (PVC) Roofing."

2.2 PERFORMANCE REQUIREMENTS

A. General Performance: Roof specialties to withstand exposure to weather and resist thermally induced movement without failure, rattling, leaking, or fastener disengagement due to defective manufacture, fabrication, installation, or other defects in construction.

B. FM Approvals' Listing: Manufacture and install roof-edge specialties that are listed in FM Approvals' "Approval Guide" and approved for windstorm classification, Class 1-105. Identify materials with FM Approvals' markings.

C. SPRI Wind Design Standard: Manufacture and install roof-edge specialties tested in accordance with ANSI/SPRI/FM 4435/ES-1 and capable of resisting the following design pressures:

1. Design Pressure: As indicated on Drawings.

D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes to prevent buckling, opening of joints, hole elongation, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Provide clips that resist rotation and avoid shear stress as a result of thermal movements. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.3 ROOF-EDGE SPECIALTIES

A. Roof-Edge Fascia: Manufactured, two-piece, roof-edge fascia consisting of snap-on metal fascia cover in section lengths not exceeding 12 ft. and a continuous metal receiver with integral drip-edge cleat to engage fascia cover and secure single-ply roof membrane. Provide matching corner units.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ATAS International, Inc.
b. Berridge Manufacturing Company
c. Drexel Metals Corp.
d. Englert, Inc.
e. EXCEPTIONAL Metals
f. Fabral; a brand of Flack Global Metals
g. FlashCo Manufacturing Inc.
h. Hickman; an MTL Company
i. Metal-Era, Inc.
j. OMG Roofing Products; a Division of OMG, Inc.

2. Formed Aluminum Fascia Covers: Aluminum sheet, 0.063 inch thick.

a. Surface: Smooth, flat finish.
b. Finish: Two-coat fluoropolymer.
c. Color: As selected by Architect from manufacturer's full range.

3. Corners: Factory mitered and continuously welded.
4. Splice Plates: Concealed, of same material, finish, and shape as fascia cover.
5. Receiver: Manufacturer's standard material and thickness.
6. Fascia Accessories: Fascia extenders with continuous hold-down cleats.

2.4 MISCELLANEOUS MATERIALS

A. Provide materials and types of fasteners, protective coatings, sealants, and other miscellaneous items required by manufacturer for a complete installation.

B. Fasteners: Roof specialty manufacturer's recommended fasteners, designed to meet performance requirements, suitable for application and metals being fastened. Match finish of exposed fasteners with finish of material being fastened. Provide nonremovable fastener heads to exterior exposed fasteners. Furnish the following unless otherwise indicated:

1. Fasteners for Aluminum Sheet: Aluminum or Series 300 stainless steel.

C. Gaskets: Manufacturer's standard tubular or fingered design of neoprene, PVC, or silicone or a flat design of foam rubber, sponge neoprene, or cork.

D. Elastomeric Sealant: ASTM C920, elastomeric silicone polymer sealant of type, grade, class, and use classifications required by roofing-specialty manufacturer for each application.

E. Butyl Sealant: ASTM C1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type joints with limited movement.

2.5 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM/NOMMA AMP 500, "Metal Finishes Manual for Architectural and Metal Products," for recommendations for applying and designating finishes.

B. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, to verify actual locations, dimensions, and other conditions affecting performance of the Work.

B. Examine walls, roof edges, and parapets for suitable conditions for roof specialties.

C. Verify that substrate is sound, dry, smooth, clean, sloped for drainage where applicable, and securely anchored.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Install roof specialties in accordance with manufacturer's written instructions. Anchor roof specialties securely in place, with provisions for thermal and structural movement. Use fasteners, solder, protective coatings, separators, underlayments, sealants, and other miscellaneous items as required to complete roof-specialty systems.

1. Install roof specialties level, plumb, true to line and elevation; with limited oil-canning and without warping, jogs in alignment, buckling, or tool marks.
2. Provide uniform, neat seams with minimum exposure of solder and sealant.
3. Install roof specialties to fit substrates and to result in weathertight performance. Verify shapes and dimensions of surfaces to be covered before manufacture.
4. Torch cutting of roof specialties is not permitted.
5. Do not use graphite pencils to mark metal surfaces.

B. Metal Protection: Protect metals against galvanic action by separating dissimilar metals from contact with each other or with corrosive substrates by painting contact surfaces with bituminous coating or by other permanent separation as recommended by manufacturer's written installation instructions.

C. Expansion Provisions: Allow for thermal expansion of exposed roof specialties.

1. Space movement joints at a maximum of 12 ft. with no joints within 18 inches of corners or intersections unless otherwise indicated on Drawings.
2. When ambient temperature at time of installation is between 40 and 70 deg F, set joint members for 50 percent movement each way. Adjust setting proportionately for installation at higher ambient temperatures.

D. Fastener Sizes: Use fasteners of sizes that penetrate substrate not less than recommended in writing by fastener manufacturer to achieve maximum pull-out resistance.

E. Seal concealed joints with butyl sealant as required by roof specialty manufacturer.

F. Seal joints as required for weathertight construction. Place sealant to be completely concealed in joint. Do not install sealants at temperatures below 40 deg F.

3.3 INSTALLATION OF ROOF-EDGE SPECIALTIES

A. Install cleats, cants, and other anchoring and attachment accessories and devices with concealed fasteners.

B. Anchor roof edgings with manufacturer's required devices, fasteners, and fastener spacing to meet performance requirements.

3.4 CLEANING AND PROTECTION

A. Clean off excess sealants.

B. Remove temporary protective coverings and strippable films as roof specialties are installed. On completion of installation, clean finished surfaces, including removing unused fasteners, metal filings, pop rivet stems, and pieces of flashing. Maintain roof specialties in a clean condition during construction.

C. Replace roof specialties that have been damaged or that cannot be successfully repaired by finish touchup or similar minor repair procedures, as determined by Architect.

END OF SECTION

SECTION 077200 - ROOF ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Manufactured units for the following applications:

1. Roof curbs.
2. Equipment supports.
3. Pipe and duct supports.
4. Pipe portals.
5. Preformed flashing sleeves.
6. Chimney cap.
7. Miscellaneous materials.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for roof cants, nailers, blocking, and other pressure-preservative-treated wood.
2. Section 077100 "Roof Specialties" for roof-edge specialties.
3. Section 079200 "Joint Sealants" for field-applied sealants between roof accessories and adjacent materials.
4. Section 108213 “Roof Screens” for roof equipment screens.
5. Section 230548 “Vibration and Seismic Controls for HVAC” for special curbs designed to accommodate seismic and vibration controls.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of roof accessory.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

C. Shop Drawings: For roof accessories.

1. Include plans, elevations, keyed details, and attachments to other work. Indicate dimensions, loadings, and special conditions. Distinguish between plant- and field-assembled work.

D. Delegated Design Submittals: For roof curbs equipment supports indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Detail mounting, securing, and flashing of roof-mounted items to roof structure. Indicate coordinating requirements with roof membrane system.

2. Wind-Restraint Details: Detail fabrication and attachment of wind restraints. Show anchorage details and indicate quantity, diameter, and depth of penetration of anchors.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Roof plans, drawn to scale, and coordinating penetrations and roof-mounted items. Show the following:

1. Size and location of roof accessories specified in this Section.
2. Method of attaching roof accessories to roof or building structure.
3. Other roof-mounted items, including mechanical and electrical equipment, ductwork, piping, and conduit.
4. Required clearances.

C. Qualification Statements: For manufacturer.

D. Delegated Design Engineer Qualifications: For roof accessories.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For roof accessories.

1.5 QUALITY ASSURANCE

A. Delegated Design Engineer Qualifications: A professional engineer who is legally qualified to practice in Maine where Project is located and who is experienced in providing engineering services of the type indicated.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Do not store roof accessories in contact with other materials that might cause staining, denting, or other surface damage. Store roof accessories in accordance with manufacturer's instructions.

B. Store materials off ground in dry location and in accordance with manufacturer's instructions in well-ventilated area.

C. Store and protect roof accessories from nicks, scratches, and blemishes.

1.7 FIELD CONDITIONS

A. Field Measurements: Verify profiles and tolerances of roof-accessory substrates by field measurements before fabrication, and indicate measurements on Shop Drawings.

1.8 COORDINATION

A. Coordinate layout and installation of roof accessories with roofing membrane and base flashing and interfacing and adjoining construction to provide a leakproof, weathertight, secure, and noncorrosive installation.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. General Performance: Roof accessories to withstand exposure to weather and resist thermally induced movement without failure, rattling, leaking, or fastener disengagement due to defective manufacture, fabrication, installation, or other defects in construction.

B. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design roof curbs and equipment supports to comply with wind performance requirements, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

C. Wind-Restraint Performance: As indicated on Drawings.

2.2 ROOF CURBS

A. Internally reinforced roof-curb units capable of supporting superimposed live and dead loads, including equipment loads and other construction indicated on Drawings, bearing continuously on roof structure, and capable of meeting performance requirements; with welded or mechanically fastened and sealed corner joints, straight sides, and integrally formed deck-mounting flange at perimeter bottom.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. AES Industries, Inc
2. AES Sunoptics; Acuity Brands International, Inc.
3. Air Balance; MESTEK, Inc.
4. ATAS International, Inc.
5. Conn-Fab Sales, Inc
6. Curbs Plus, Inc
7. Custom Solution Roof and Metal Products, a division of Colony Heating
8. Greenheck Fan Corporation
9. KCC Manufacturing
10. Lloyd Industries, Inc.
11. LMCurbs
12. Louvers & Dampers, Inc.; Mestek, Inc.
13. Metallic Products Corporation
14. Pate Company (The)
15. Plenums of Florida Incorporated
16. RCS Fabrications Inc.
17. Roof Products and Systems (RPS); Duravent Group

18. Roof Products, Inc.
19. Thybar Corporation
20. Vent Products Co., Inc

C. Size: Coordinate dimensions with roughing-in information or Shop Drawings of equipment to be supported.

D. Steel: Zinc-coated (galvanized) Aluminum-zinc alloy-coated steel sheet, 0.064 inch thick.

1. Finish: Powder coat.
2. Color: As selected by Architect from manufacturer's full range.

E. Construction:

1. Curb Profile: Manufacturer's standard compatible with roofing system.
2. On ribbed or fluted metal roofs, form deck-mounting flange at perimeter bottom to conform to roof profile.
3. Fabricate curbs to minimum height of 12 inches above roofing surface unless otherwise indicated.
4. Top Surface: Level top of curb, with roof slope accommodated by sloping deck-mounting flange or by use of leveler frame.
5. Sloping Roofs: Where roof slope exceeds 1/4 inch per 12 inches, fabricate curb with perimeter curb height tapered to accommodate roof slope so that top surface of perimeter curb is level. Equip unit with water diverter or cricket on side that obstructs water flow.
6. Insulation: Factory insulated with 1-1/2-inch- thick glass-fiber board insulation.
7. Liner: Same material as curb, of manufacturer's standard thickness and finish.
8. Nailer: Factory-installed wood nailer under top flange on side of curb, continuous around curb perimeter.
9. Wind-Restraint Straps and Base Flange Attachment: Provide wind-restraint straps, welded strap connectors, and base flange attachment to roof structure at perimeter of curb, of size and spacing required to comply with wind-uplift requirements.
10. Platform Cap: Where portion of roof curb is not covered by equipment, provide weathertight platform cap formed from 3/4-inch-thick plywood covered with metal sheet of same type, thickness, and finish as required for curb.
11. Metal Counterflashing: Manufacturer's standard, removable, fabricated of same metal and finish as curb.

2.3 PIPE AND DUCT SUPPORTS

A. Fixed-Height Cradle-Type Pipe Supports: Polycarbonate pipe stand accommodating up to 1-1/2-inch- diameter pipe or conduit; with provision for pipe retainer and with manufacturer's support pad or deck plate as recommended for penetration-free installation over roof membrane type; as required for quantity of pipe runs and sizes.

B. Fixed-Height Roller-Bearing Pipe Supports: Polycarbonate pipe stand withstainless steel roller carrying assembly accommodating up to 7-inch- diameter pipe or conduit; with provision for pipe retainer and with manufacturer's support pad or deck plate as recommended for penetration-free installation over roof membrane type; as required for quantity of pipe runs and sizes.

C. Adjustable-Height Roller-Bearing Pipe Supports: Polycarbonate pipe stand base, pipe support, and roller housing, with stainless steel threaded rod designed for adjusting support height, accommodating up to 18-inch diameter pipe or conduit; with provision for pipe retainer and with manufacturer's support pad or deck plate as recommended for penetration-free installation over roof membrane type; as required for quantity of pipe runs and sizes.

D. Adjustable-Height Structure-Mounted Pipe Supports: Extruded-aluminum tube, filled with urethane insulation; 2 inches in diameter; accommodating up to 7-inch- diameter pipe or conduit, with provision for pipe retainer; with aluminum baseplate, EPDM base seal, manufacturer's recommended hardware for mounting to structure or structural roof deck as indicated, stainless steel roller and retainer, and extruded-aluminum carrier assemblies; as required for quantity of pipe runs and sizes.

E. Curb-Mounted Pipe Supports: Galvanized-steel support with welded or mechanically fastened and sealed corner joints, straight sides, and integrally formed deck-mounting flange at perimeter bottom; with adjustable-height roller-bearing pipe support accommodating up to 20-inch-diameter pipe or conduit and with provision for pipe retainer; as required for quantity of pipe runs and sizes.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. MIRO Industries Inc.
b. Pate Company (The)
c. PHP Systems/Design
d. Portals Plus; Duravent Group
e. Roof Products and Systems (RPS); Duravent Group
f. Thaler Metal Industries Ltd.

F. Duct Supports: Extruded-aluminum, urethane-insulated supports, 2 inches in diameter; with manufacturer's recommended hardware for mounting to structure or structural roof deck.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Roof Products and Systems (RPS); Duravent Group
b. Thaler Metal Industries Ltd.

2.4 PIPE PORTALS

A. Curb-Mounted Pipe Portal: Insulated roof-curb units with welded or mechanically fastened and sealed corner joints, straight sides, and integrally formed deck-mounting flange at perimeter bottom; with weathertight curb cover with single or multiple collared openings and pressure-sealed conically shaped EPDM protective rubber caps sized for piping indicated, with stainless steel snaplock swivel clamps.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Portals Plus; Duravent Group
b. Roof Products and Systems (RPS); Duravent Group

B. Flashing Pipe Portal: Formed aluminum membrane-mounting flashing flange and sleeve with collared opening and pressure-sealed conically shaped PVC protective rubber cap sized for piping indicated, with stainless steel snaplock swivel clamps.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Portals Plus; Duravent Group

2.5 PREFORMED FLASHING SLEEVES

A. Exhaust Vent Flashing: Double-walled metal flashing sleeve or boot, insulation filled, with integral deck flange, 12 inches high, with removable metal hood and slotted metal collar.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Custom Solution Roof and Metal Products, a division of Colony Heating
b. Menzies Metal Products
c. Thaler Metal Industries Ltd.

B. Vent Stack Flashing: Metal flashing sleeve, uninsulated, with integral deck flange.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Custom Solution Roof and Metal Products, a division of Colony Heating
b. Menzies Metal Products
c. Milcor by Duravent; Duravent Group.
d. Thaler Metal Industries Ltd.

2. Metal: Aluminum sheet, 0.063 inch thick.
3. Height: 19 inches.
4. Diameter: As indicated on Drawings.
5. Finish: Manufacturer's standard.

2.6 CHIMNEY CAP

A. 16 gauge stainless steel pyramid style with screen.

B. Size: Custom.

1. Length: 44 inches.
2. Width: 44 inches.
3. Height: 24 inches.

C. Finish: Brushed stainless steel.

D. Basis-of-Design: Master Custom Stainless Chimney Cap-Pyramid Style with Screen MS-P03.

2.7 NISCELLANEOUS MATERIALS

A. Provide materials and types of fasteners, protective coatings, sealants, and other miscellaneous items required by manufacturer for a complete installation.

B. Wood Nailers: Softwood lumber, pressure treated with waterborne preservatives for aboveground use, acceptable to authorities having jurisdiction, and complying with AWPA C2; not less than 1-1/2 inches thick.

2.8 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM/NOMMA AMP 500, "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

B. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, to verify actual locations, dimensions, and other conditions affecting performance of the Work.

B. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.

C. Verify dimensions of roof openings for roof accessories.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Install roof accessories in accordance with manufacturer's written instructions.

1. Install roof accessories level; plumb; true to line and elevation; and without warping, jogs in alignment, buckling, or tool marks.
2. Anchor roof accessories securely in place so they are capable of resisting indicated loads.
3. Use fasteners, separators, sealants, and other miscellaneous items as required to complete installation of roof accessories and fit them to substrates.

4. Install roof accessories to resist exposure to weather without failing, rattling, leaking, or loosening of fasteners and seals.

B. Metal Protection: Protect metals against galvanic action by separating dissimilar metals from contact with each other or with corrosive substrates by painting contact surfaces with bituminous coating or by other permanent separation as recommended in writing by manufacturer's written installation instructions.

3.3 INSTALLATION OF ROOF ACCESSORIES

A. Roof Curb: Install each roof curb so top surface is level.

B. Equipment Support: Install equipment supports so top surfaces are level with each other.

C. Pipe and Duct Support: Comply with MSS SP-58. Install supports and attachments as required to properly support piping. Arrange for grouping of parallel runs of horizontal piping, and support together.

1. Pipes of Various Sizes: Space supports for smallest pipe size or install intermediate supports for smaller-diameter pipes as specified for individual pipe hangers.

D. Preformed Flashing-Sleeve and Flashing-Pipe Portal: Secure flashing sleeve to roof membrane in accordance with flashing-sleeve manufacturer's written instructions; flash sleeve flange to surrounding roof membrane in accordance with roof membrane manufacturer's instructions.

3.4 CLEANING AND PROTECTION

A. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas and repair galvanizing in accordance with ASTM A780/A780M.

B. On completion of installation, clean exposed surfaces in according with manufacturer's written instructions. Clean off excess sealants.

C. Remove temporary protective coverings and strippable films as roof accessories are installed. On completion of installation, clean finished surfaces, including removing unused fasteners, metal filings, pop rivet stems, and pieces of flashing. Maintain roof accessories in a clean condition during construction.

D. Replace roof accessories that have been damaged or that cannot be successfully repaired by finish touchup or similar minor repair procedures, as determined by Architect.

END OF SECTION

SECTION 078413 - PENETRATION FIRESTOPPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Penetration firestopping systems.

1. Penetration firestopping systems in fire-resistance-rated walls.
2. Penetration firestopping systems in horizontal assemblies.
3. Penetration firestopping systems in smoke barriers.
4. Exposed penetration firestopping systems.

B. Related Requirements:

1. Section 078443 "Joint Firestopping" for joints in or between fire-resistance-rated construction, at exterior curtain-wall/floor intersections, and in smoke barriers.
2. Section 079200 "Joint Sealants" for non-fire-resistance-rated joint sealants.
3. Section 079219 "Acoustical Joint Sealants" for sealing joints in sound-rated construction.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Product Schedule: For each penetration firestopping system. Include location, illustration of firestopping system, and design designation of qualified testing and inspecting agency.

1. Engineering Judgments: Where Project conditions require modification to a qualified testing and inspecting agency's illustration for a particular penetration firestopping system, submit illustration, with modifications marked, approved by penetration firestopping system manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly developed in accordance with current International Firestop Council (IFC) recommended guidelines. Obtain approval of authorities having jurisdiction prior to submittal.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

C. Listed System Designs: For each penetration firestopping system, for tests performed by a qualified testing agency.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Installer Certificates: From Installer indicating that penetration firestopping systems have been installed in compliance with requirements and manufacturer's written instructions.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: Entity that has been approved by FM Approvals in accordance with FM Approvals 4991 or been evaluated by UL Solutions and found to comply with "UL Solutions Qualified Firestop Contractor Program."

B. Manufacturer Qualifications: Entity that has received UL Solutions' "Firestop Movement Certification," which demonstrates that manufacturer's firestopping products designated with M-Ratings are based on exposure to cyclic movement and UL 1479 fire test evaluation when tested in accordance with ASTM E3037.

1.7 FIELD CONDITIONS

A. Environmental Limitations: Do not install penetration firestopping systems when ambient or substrate temperatures are outside limits permitted by penetration firestopping system manufacturers or when substrates are wet because of rain, frost, condensation, or other causes.

B. Install and cure penetration firestopping system materials in accordance with manufacturer's written instructions using natural means of ventilations or, where this is inadequate, forced-air circulation.

1.8 COORDINATION

A. Coordinate construction of openings and penetrating items to ensure that penetration firestopping systems can be accessed and installed in accordance with specified firestopping system design.

B. Coordinate sizing of sleeves, openings, core-drilled holes, or cut openings to accommodate penetration firestopping systems.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain penetration firestopping systems for each type of opening indicated from single manufacturer.

2.2 PENETRATION FIRESTOPPING SYSTEMS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. 3M Building and Construction
2. Balco; a CSW Industrials Company
3. Everkem Diversified Products, Inc.
4. FireShield; Fire Rated Solutions LLC
5. Grabber Construction Products, Inc.
6. Hilti, Inc.
7. Holdrite; a division of Reliance Worldwide Corporation
8. International Fireproof Technology Inc
9. NUCO Inc
10. Passive Fire Protection Partners
11. Roxtec Inc.
12. Specified Technologies Inc.
13. STC Sound Control
14. Tremco Incorporated
15. Unique Fire Stop Products

B. Penetration firestopping systems must be compatible with one another, with the substrates forming openings, and with penetrating items if any.

1. Penetration firestopping systems must be installed with products bearing the classification marking of a qualified testing agency.

    a. UL Solutions in its online directory "Product iQ."
    b. Intertek Group in its "Directory of Building Products."
    c. FM Approvals in its "Approval Guide."

2. Provide components for each penetration firestopping system that, upon curing, do not re-emulsify, dissolve, leach, break down, or otherwise deteriorate over time from exposure to atmospheric moisture, sweating pipes, ponding water, or other forms of moisture characteristic during and after construction.
3. Provide components for each penetration firestopping system that do not contain ethylene glycol.
4. Provide components for each penetration firestopping system that are sufficiently flexible to accommodate movement, such as pipe vibration, water hammer, thermal expansion, and other normal building movement without damage.
5. Provide components for each penetration firestopping system that are appropriately tested for the thickness and type of insulation utilized.

C. Provide penetration firestopping systems that resist spread of fire, resist passage of smoke and other gases, and maintain original fire-resistance rating of construction penetrated.

D. Penetration Firestopping Systems in Fire-Resistance-Rated Walls: Systems with ratings determined in accordance with ASTM E814 or UL 1479.

1. F-Rating: Not less than the fire-resistance rating of the wall assembly penetrated.
2. Membrane Penetrations: Install recessed fixtures such that the required fire resistance will not be reduced.

E. Penetration Firestopping Systems in Horizontal Assemblies: Systems with ratings determined in accordance with ASTM E814 or UL 1479.

1. F-Rating: At least one hour, but not less than the fire-resistance rating of the floor/ceiling assembly penetrated.
2. T-Rating: At least one hour, but not less than the fire-resistance rating of the floor/ceiling assembly. The following horizontal penetrations do not require a T-rating:

    a. Those within the cavity of a wall.
    b. Floor, tub, or shower drains within a concealed space.
    c. 4-inch or smaller metal conduit penetrating directly into metal-enclosed electrical switchgear.

3. W-Rating: Provide penetration firestopping systems with a Class 1 W-rating in accordance with UL 1479.

F. Penetration Firestopping Systems in Smoke Barriers: Systems with ratings determined in accordance with UL 1479.

1. L-Rating: Not exceeding 5.0 cfm/sq. ft. of penetration opening and no more than 50-cfm cumulative total for any 100 sq. ft. at both ambient and elevated temperatures.

G. Exposed Penetration Firestopping Systems: Flame-spread and smoke-developed indexes of less than 25 and 450, respectively, when tested in accordance with ASTM E84 or UL 723.

2.3 ACCESSORIES

A. Provide components for each penetration firestopping system that are needed to install fill materials and to maintain ratings required. Use only those components specified by penetration firestopping system manufacturer and approved by qualified testing and inspecting agency for conditions indicated, including but not limited to:

1. Permanent forming/damming/backing materials.
2. Substrate primers.
3. Collars.
4. Steel sleeves.

2.4 FILL MATERIALS

A. Cast-in-Place Firestopping Devices: Factory-assembled devices for use in cast-in-place concrete

floors and consisting of an outer sleeve lined with an intumescent strip, a flange attached to one end of the sleeve for fastening to concrete formwork, and a neoprene gasket.

B. Firestopping Devices: Factory-assembled collars formed from galvanized steel and lined with intumescent material sized to fit specific diameter of penetrant.

C. Intumescent Putties: Nonhardening, water-resistant, intumescent putties containing no solvents or inorganic fibers.

D. Intumescent Wrap Strips: Single-component intumescent elastomeric strips for use around combustible penetrants.

E. Mortars: Prepackaged dry mixes consisting of a blend of inorganic binders, hydraulic cement, fillers and lightweight aggregate formulated for mixing with water at Project site to form a nonshrinking, homogeneous mortar.

F. Pillows/Bags: Compressible, removable, and reusable intumescent pillows encased in fire-retardant polyester or glass-fiber cloth. Where exposed, and when required by a listed system, cover openings with steel-reinforcing wire mesh to protect pillows/bags from being easily removed or dislodged.

G. Thermal and Endothermic Wraps: Flexible, insulating, and fire-resistant protective wraps tested and listed for up to 2-hour fire ratings in accordance with ASTM E814 or UL 1479; for protecting membrane penetrations of utility boxes, critical electrical circuits, communications lines, and fuel lines, and for thermal barrier and circuit integrity protection in accordance with ASTM E1725 or UL 1724.

H. Fire-Rated Cable Sleeve Kits: Complete kits designed for new or existing cable penetrations through walls which accept standard accessories.

I. Fire-Rated Cable Pathways: Single or gangable device modules composed of a steel raceway with integral intumescent material and requiring no additional action in the form of plugs, twisting closure, putty, pillows, sealant, or otherwise to achieve fire and air-leakage ratings.

1. Fire-rated cable pathway devices are the preferred product for data, video, and communications cable penetrations. Install these devices in locations where frequent cable moves, add-ons, and changes will occur. Such devices must be:

    a. Capable of retrofit around existing cables.
    b. Designed so that two or more devices can be ganged together.
    c. Maintenance-free so no action is required to activate the smoke- and fire-sealing mechanism.

2. Where fire-rated cable pathway devices are not practical, openings within walls and floors designed to accommodate data, video, and communications cabling must be provided with re-enterable products specifically designed for retrofit, such as retrofit devices for cable bundles, firestopping putty, plugs, or pillows.

J. Wall-Opening Protective Materials: Intumescent, non-curing putty pads or self-adhesive inserts for protection of electrical switch and receptacle boxes.

K. Fire-Rated HVAC Retaining Angles: Steel angle system with integral intumescent firestopping

gasket for use around rectangular steel HVAC ducts without fire dampers.

L. Firestopping Plugs: Flexible, re-enterable, intumescent, foam-rubber plug for use in blank round openings and cable sleeves.

M. Fire-Rated Cable Grommet: Molded two-piece grommet made of plenum-grade polymer and foam inner core for sealing small cable penetrations in gypsum walls up to 1/2 inch in diameter.

N. Closet Flange Gasket: Molded, single-component, flexible, intumescent gasket for use beneath a water closet (toilet) flange in floor applications.

2.5 MIXING

A. Penetration Firestopping Materials: For those products requiring mixing before application, comply with penetration firestopping system manufacturer's written instructions for accurate proportioning of materials, water (if required), type of mixing equipment, selection of mixer speeds, mixing containers, mixing time, and other items or procedures needed to produce products of uniform quality with optimum performance characteristics for application indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning: Before installing penetration firestopping systems, clean out openings in accordance with manufacturer's written instructions and with the following requirements:

1. Remove foreign materials from substrate surfaces that could interfere with adhesion of penetration firestopping materials.
2. Clean opening substrates and penetrating items to produce clean, sound surfaces capable of developing optimum bond with penetration firestopping materials. Remove loose particles remaining from cleaning operation.
3. Remove laitance and form-release agents from concrete.

B. Prime substrates in accordance with penetration firestopping system manufacturer's written installation instructions, using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

3.3 INSTALLATION OF PENETRATION FIRESTOPPING SYSTEMS

A. General: Install penetration firestopping systems in accordance with manufacturer's written installation instructions and published drawings for products and applications.

B. Install forming materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.

1. After installing fill materials and allowing them to fully cure, remove combustible forming materials and other accessories not forming permanent components of firestopping.

C. Install fill materials by proven techniques to produce the following results:

1. Fill voids and cavities formed by openings, forming materials, accessories, and penetrating items to achieve required fire-resistance ratings.
2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.
3. For fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.4 IDENTIFICATION

A. Wall Identification: Permanently label walls containing penetration firestopping systems with the words "FIRE AND/OR SMOKE BARRIER - PROTECT ALL OPENINGS," using lettering not less than 3 inches high and with minimum 0.375-inch strokes.

1. Locate in accessible concealed floor, floor-ceiling, or attic space at 15 ft. from end of wall and at intervals not exceeding 30 ft..

B. Penetration Identification: Identify each penetration firestopping system with legible metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches of penetration firestopping system edge so labels are visible to anyone seeking to remove penetrating items or firestopping systems. Use mechanical fasteners or self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:

1. The words "Warning - Penetration Firestopping - Do Not Disturb. Notify Building Management of Any Damage."
2. Contractor's name, address, and phone number.
3. Designation of applicable testing and inspecting agency.
4. Date of installation.
5. Manufacturer's name.
6. Installer's name.

3.5 FIELD QUALITY CONTROL

A. Contractor must engage a qualified testing agency to perform tests and inspections according to ASTM E 2174 and prepare report(s) of findings.

1. Test and inspect as required by 2015 International Building Code. Subsection 1705.17, “Fire-Resistant Penetrations and Joints.”

B. Testing shall include destructive testing to assure proper installation/application.

C. Proceed with enclosing penetration firestopping systems with other construction only after inspection reports are issued and installations comply with requirements.

3.6 CLEANING AND PROTECTION

A. Clean off excess fill materials adjacent to openings as the Work progresses by methods and with cleaning materials that are approved in writing by penetration firestopping system manufacturers and that do not damage materials in which openings occur.

B. Provide final protection and maintain conditions during and after installation that ensure that penetration firestopping systems are without damage or deterioration at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, immediately cut out and remove damaged or deteriorated penetration firestopping material and install new materials to produce systems complying with specified requirements.

END OF SECTION

SECTION 078443 - JOINT FIRESTOPPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Joints in or between fire-resistance-rated construction.
2. Joints in smoke barriers.

B. Related Requirements:

1. Section 078413 "Penetration Firestopping" for penetrations in fire-resistance-rated walls, horizontal assemblies, and smoke barriers and for wall identification.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of product.

C. Product Schedule: For each joint firestopping system. Include location, illustration of firestopping system, and design designation of qualified testing agency.

1. Engineering Judgments: Where Project conditions require modification to a qualified testing agency's illustration for a particular joint firestopping system condition, submit illustration, with modifications marked, approved by joint firestopping system manufacturer's fire-protection engineer as an EJ or equivalent fire-resistance-rated assembly developed in accordance with current IFC guidelines.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

C. Listed System Designs: For each joint firestopping system, for tests performed by a qualified testing agency.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and

the individual sections specifying the work.

B. Installer Certificates: From Installer indicating that joint firestopping systems have been installed in compliance with requirements and manufacturer's written installation instructions.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: A firm that has been approved by FM Approvals in accordance with FM Approvals 4991 or been evaluated by UL and found to comply with UL's "UL Solutions Qualified Firestop Contractor Program."

1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not install joint firestopping systems when ambient or substrate temperatures are outside limits permitted by joint firestopping system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.

B. Install and cure joint firestopping systems in accordance with manufacturer's written installation instructions using natural means of ventilation or, where this is inadequate, forced-air circulation.

1.7 COORDINATION

A. Coordinate construction of joints to ensure that joint firestopping systems can be installed in accordance with specified firestopping system design.

B. Coordinate sizing of joints to accommodate joint firestopping systems.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain joint firestop systems for each type of joint opening indicated from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics:

1. A qualified testing agency, acceptable to authorities having jurisdiction, will perform joint firestopping system tests.
2. Test in accordance with testing standards referenced in "Joint Firestopping Systems" Article. Provide rated systems complying with the following requirements:

    a. Joint firestop systems installed with products bearing the classification marking of a qualified product certification agency in accordance with listed system designs published by a qualified testing agency.

1) UL in its online directory "Product iQ."
2) Intertek Group in its "Directory of Building Products."

2.3 JOINT FIRESTOPPING SYSTEM TYPES

A. General: Systems that resist spread of fire, passage of smoke and other gases, and maintain original fire-resistance rating of assemblies in or between which joint firestopping systems are installed. Joint firestopping systems must accommodate building movements without impairing their ability to resist the passage of fire and hot gases.

1. Joint firestopping systems that are compatible with one another, with the substrates forming openings, and with penetrating items, if any.
2. Provide products that, upon curing, do not re-emulsify, dissolve, leach, break down, or otherwise deteriorate over time from exposure to atmospheric moisture, sweating pipes, ponding water or other forms of moisture.
3. Provide firestop products that do not contain ethylene glycol.

B. Joints in or between Fire-Resistance-Rated Construction: Provide joint firestopping systems with ratings determined in accordance with ASTM E1966 or UL 2079, with published L-Ratings for ambient and elevated temperatures as evidence of the ability of the fire-resistive joint system to restrict the movement of smoke.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. 3M Building and Construction
b. Balco; a CSW Industrials Company
c. CEMCO; California Expanded Metal Products Co.
d. ClarkDietrich
e. Everkem Diversified Products, Inc.
f. Grabber Construction Products, Inc.
g. Hilti, Inc.
h. International Fireproof Technology Inc
i. Marino\WARE
j. Nelson; Emerson Electric Co., Automation Solutions
k. NUCO Inc
l. Owens Corning
m. Passive Fire Protection Partners
n. RectorSeal Firestop; a CSW Industrials Company
o. ROCKWOOL
p. Specified Technologies Inc.
q. Tremco Incorporated
r. Willseal LLC, part of Tremco CPG

2. Fire-Resistance Rating: Equal to or exceeding the fire-resistance rating of the wall, floor, or roof in or between which it is installed.

C. Joints in Smoke Barriers: Provide joint firestopping systems with ratings determined in accordance with UL 2079 based on testing at a positive pressure differential of 0.30 inch wg.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. 3M Building and Construction
    b. Balco; a CSW Industrials Company
    c. CEMCO; California Expanded Metal Products Co.
    d. Everkem Diversified Products, Inc.
    e. Grabber Construction Products, Inc.
    f. Hilti, Inc.
    g. International Fireproof Technology Inc
    h. Marino\WARE
    i. Nelson; Emerson Electric Co., Automation Solutions
    j. NUCO Inc
    k. Owens Corning
    l. Passive Fire Protection Partners
    m. Polyset
    n. RectorSeal Firestop; a CSW Industrials Company
    o. Specified Technologies Inc.
    p. Tremco Incorporated
    q. Willseal LLC, part of Tremco CPG

2. L-Rating: Not exceeding 5.0 cfm/ft. of joint at both ambient and elevated temperatures.

D. Exposed Joint Firestopping Systems: Flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined in accordance with ASTM E84.

2.4 ACCESSORIES

A. Provide components of joint firestopping systems, including primers and forming materials, that are needed to install elastomeric fill materials and to maintain ratings required. Use only components specified by joint firestopping system manufacturer and approved by the qualified testing agency for conditions indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for joint configurations, substrates, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning: Before installing joint firestopping systems, clean joints in accordance with fire-resistive joint system manufacturer's written installation instructions and the following requirements:

1. Remove foreign materials from substrate surfaces that could interfere with adhesion of elastomeric fill materials or compromise fire-resistive rating.
2. Clean joint substrates to produce clean, sound surfaces capable of developing optimum bond with elastomeric fill materials. Remove loose particles remaining from cleaning operation.
3. Remove laitance and form-release agents from concrete.

B. Prime substrates in accordance with joint firestopping system manufacturer's written installation instructions, using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

C. Apply a suitable bond breaker to prevent three-sided adhesion in applications where condition occurs.

3.3 INSTALLATION

A. General: Install joint firestopping systems in accordance with manufacturer's written installation instructions and published drawings for products and applications indicated.

B. Install forming materials and other accessories of types required to support elastomeric fill materials during their application and in position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.

1. After installing elastomeric fill materials and allowing them to fully cure, remove combustible forming materials and other accessories not indicated as permanent components of fire-resistive joint system.

C. Install elastomeric fill materials for joint firestopping systems by proven techniques to produce the following results:

1. Apply elastomeric fill in voids and cavities formed by joints and forming materials as required to achieve fire-resistance ratings indicated.
2. Apply elastomeric fill materials so they contact and adhere to substrates formed by joints.
3. For elastomeric fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.4 IDENTIFICATION

A. Wall Identification: Permanently label walls containing firestopping systems with the words "FIRE AND/OR SMOKE BARRIER - PROTECT ALL OPENINGS," using lettering not less than 3 inches high and with minimum 0.375-inch strokes.

1. Locate in accessible concealed floor, floor-ceiling, or attic space at 15 ft. from end of wall and at intervals not exceeding 30 ft..

B. Joint Identification: Identify joint firestopping systems with legible metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches of joint edge, so labels are visible to anyone seeking to remove joint firestopping system. Use mechanical fasteners or self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:

1. The words "Warning - Joint Firestopping - Do Not Disturb. Notify Building Management of Any Damage."
2. Contractor's name, address, and phone number.
3. Designation of applicable testing agency.
4. Date of installation.
5. Manufacturer's name.
6. Installer's name.

3.5 FIELD QUALITY CONTROL

A. Inspecting Agency: Contractor must engage a qualified testing agency to perform tests and inspections according to ASTM E 2393 and prepare report(s) of findings.

1. Test and inspect as required by the 2015 International Building Code (IBC), Subsection 1705.17, “Fire-resistant penetrations and joints.”

B. Proceed with enclosing joint firestopping systems with other construction only after inspection reports are issued and installations comply with requirements.

3.6 CLEANING AND PROTECTION

A. Clean off excess elastomeric fill materials adjacent to joints as the Work progresses by methods and with cleaning materials that are approved in writing by joint firestopping system manufacturers and that do not damage materials in which joints occur.

B. Provide final protection and maintain conditions during and after installation that ensure joint firestopping systems are without damage or deterioration at time of Substantial Completion. If damage or deterioration occurs despite such protection, cut out and remove damaged or deteriorated joint firestopping systems immediately and install new materials to produce joint firestopping systems complying with specified requirements.

END OF SECTION

SECTION 079100 - PREFORMED JOINT SEALS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Extruded-silicone joint seals.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for liquid sealants applied over preformed seals in dual-seal systems.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Extruded-silicone joint seals.

C. Samples for Verification: Actual samples of each type and color of exposed preformed joint seal.

1. Size: 1/2-inch-wide joints formed between two 6-inch-long strips of material matching the appearance of exposed surfaces adjacent to joint seals.

D. Preformed Joint Seal Schedule: Include the following information:

1. Joint seal location and designation.
2. Joint width and movement capability.
3. Joint seal manufacturer and product name.
4. Joint seal color.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Test and Evaluation Reports:

1. Product Test Reports: For each preformed joint seal, for tests performed by manufacturer and witnessed by a qualified testing agency.

C. Sample warranties.

1.4 WARRANTY

A. Special Installer's Warranty: Installer agrees to repair or replace preformed joint seals that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish preformed joint seals to repair or replace those that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. For preformed joint seals, obtain each color, type, and variety of joint seal from single source with resources to provide products of consistent quality in appearance and physical properties.

2.2 EXTRUDED-SILICONE JOINT SEALS

A. Extruded-Silicone Joint Seals : Manufacturer's standard seal consisting of precured low-modulus silicone extrusion, with a neutral-curing silicone sealant for bonding extrusions to substrates.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. GE Construction Sealants; Momentive Performance Materials Inc.
b. Nystrom, Inc.
c. Pecora Corporation
d. Sika Corporation
e. The Dow Chemical Company
f. Tremco Incorporated

2. Joint Seal Width: Joint size indicated on Drawings plus 1 inch.
3. Joint Seal Color: As selected by Architect from full range of industry colors.

2.3 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by preformed joint seal manufacturer for joint substrates indicated.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to preformed joint seal manufacturer, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces, and formulated to promote best adhesion to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with preformed joint seals and surfaces adjacent to joints.

D. Sealant for Adhering Extruded-Silicone Joint Seals: Silicone adhesive sealant recommended by extruded-silicone joint seal manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive preformed joint seals, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting preformed joint seal performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing preformed joint seals to comply with preformed joint seal manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of preformed joint seal, including dust, paints (except for permanent protective coatings tested and approved for seal adhesion and compatibility by seal manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimal bond with preformed joint seals. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

    a. Concrete.
    b. Masonry.
    c. Exterior insulation.

3. Remove laitance and form-release agents from concrete.
4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint seals. Nonporous joint substrates include the following:

    a. Metal.
    b. Glass.

B. Joint Priming: Prime joint substrates where recommended by preformed joint seal manufacturer or as indicated by tests or prior experience. Apply primer to comply with joint seal manufacturer's written instructions. Confine primers to areas of joint seal bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of adhesive or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF EXTRUDED-SILICONE JOINT SEALS

A. General: Comply with preformed joint seal manufacturer's written installation instructions for products and applications indicated unless more stringent requirements apply.

1. Apply masking tape to each side of joint, outside of area to be covered by seal system.
2. Apply silicone sealant to each side of joint to produce a bead of size complying with preformed silicone seal system manufacturer's written instructions and covering a bonding area of not less than 3/8 inch. Hold edge of sealant bead 1/4 inch inside masking tape.
3. Press silicone extrusion into sealant to wet extrusion and substrate. Use a roller to apply consistent pressure and ensure uniform contact with substrate.
4. Complete installation of seal system in horizontal joints before installing in vertical joints. Lap vertical joints over horizontal joints. At ends of joints, cut silicone extrusion with a razor knife.

3.4 PROTECTION

A. Protect preformed joint seals from damage resulting from construction operations or other causes so seals are without deterioration or damage at time of Substantial Completion.

B. Cut out, remove, and repair damaged or deteriorated seals so repaired areas are indistinguishable from original work.

END OF SECTION

SECTION 079200 - JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Nonstaining silicone joint sealants.
2. Mildew-resistant joint sealants.
3. Latex joint sealants.

B. Related Requirements:

1. Section 079100 "Preformed Joint Seals" for preformed compressible foam and precured joint seals.
2. Section 079219 "Acoustical Joint Sealants" for sealing joints in sound-rated construction.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Nonstaining silicone joint sealants.
2. Mildew-resistant joint sealants.
3. Latex joint sealants.

C. Samples for Verification: For each type and color of joint sealant required, provide Samples with joint sealants in 1/2-inch-wide joints formed between two 6-inch-long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

D. Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Field Quality-Control Reports: For field-adhesion-test reports, for each sealant application tested.

C. Sample warranties.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturers' special warranties.

C. Installer's special warranties.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Authorized representative who is trained and approved by manufacturer.

1.6 MOCKUPS

A. Install sealant in mockups of assemblies specified in other Sections that are indicated to receive joint sealants specified in this Section. Use materials and installation methods specified in this Section.

1.7 FIELD CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.8 WARRANTY

A. Special Installer's Warranty: Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:

1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
2. Disintegration of joint substrates from causes exceeding design specifications.
3. Mechanical damage caused by individuals, tools, or other outside agents.
4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain joint sealants from single manufacturer for each sealant type.

2.2 JOINT SEALANTS, GENERAL

A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.

B. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.3 NONSTAINING SILICONE JOINT SEALANTS

A. Nonstaining Joint Sealants: No staining of substrates when tested in accordance with ASTM C1248.

B. Silicone, Nonstaining, S, NS, 50, NT: Nonstaining, single-component, nonsag, plus 50 percent and minus 50 percent movement capability, nontraffic-use, neutral-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 50, Use NT.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Adfast
b. GE Construction Sealants; Momentive Performance Materials Inc.
c. Pecora Corporation
d. Sika Corporation - Building Components
e. Soudal Accumetric
f. The Dow Chemical Company
g. Tremco Incorporated

2.4 MILDEW-RESISTANT JOINT SEALANTS

A. Mildew-Resistant Joint Sealants: Formulated for prolonged exposure to humidity with fungicide to prevent mold and mildew growth.

B. Silicone, Mildew Resistant, Acid Curing, S, NS, 25, NT: Mildew-resistant, single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, acid-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 25, Use NT.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Adfast
    b. GE Construction Sealants; Momentive Performance Materials Inc.
    c. Pecora Corporation
    d. PPG Paints; PPG Industries, Inc.
    e. Sika Corporation - Building Components
    f. Soudal Accumetric
    g. The Dow Chemical Company
    h. Tremco Incorporated

2.5 LATEX JOINT SEALANTS

A. Acrylic Latex: Acrylic latex or siliconized acrylic latex, ASTM C834, Type OP, Grade NF.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Adfast
    b. Everkem Diversified Products, Inc.
    c. Franklin International
    d. Pecora Corporation
    e. PPG Paints; PPG Industries, Inc.
    f. Sherwin-Williams Company (The)
    g. Tremco Incorporated

2.6 JOINT-SEALANT BACKING

A. Sealant Backing Material: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.

B. Cylindrical Sealant Backings: ASTM C1330, Type C (closed-cell material with a surface skin), Type B (bicellular material with a surface skin), or any of the preceding types, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.

C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant

manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.7 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

    a. Concrete.
    b. Masonry.

3. Remove laitance and form-release agents from concrete.
4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint

sealants. Nonporous joint substrates include the following:

a. Metal.
b. Glass.
c. Porcelain enamel.
d. Glazed surfaces of ceramic tile.

B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.

B. Sealant Installation Standard: Comply with recommendations in ASTM C1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.

C. Install sealant backings of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of sealant backings.
2. Do not stretch, twist, puncture, or tear sealant backings.
3. Remove absorbent sealant backings that have become wet before sealant application, and replace them with dry materials.

D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.

E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:

1. Place sealants so they directly contact and fully wet joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants in accordance with requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.

2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint profile in accordance with Figure 8A in ASTM C1193 unless otherwise indicated.

    a. Use masking tape to protect surfaces adjacent to recessed tooled joints.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Tests and Inspections:

1. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:

    a. Extent of Testing: Test completed and cured sealant joints as follows:

        1) Perform 10 tests for the first 1000 ft. of joint length for each kind of sealant and joint substrate.
        2) Perform one test for each 1000 ft. of joint length thereafter or one test per each floor per elevation.

    b. Test Method: Test joint sealants in accordance with Method A, Tail Procedure, in ASTM C1521.

        1) For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

    c. Inspect tested joints and report on the following:

        1) Whether sealants filled joint cavities and are free of voids.
        2) Whether sealant dimensions and configurations comply with specified requirements.
        3) Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.

    d. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.
    e. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.

2. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to

comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

C. Prepare test and inspection reports.

3.5 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.6 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION

SECTION 079219 - ACOUSTICAL JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Acoustical joint sealants.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for joint sealants for nonacoustical applications.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Test and Evaluation Reports:

1. Product Test Reports: For each type of acoustical joint sealant, for tests performed by manufacturer and witnessed by a qualified testing agency.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained between 40 and 95 deg F.

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.5 FIELD CONDITIONS

A. Apply coatings only when temperature of surfaces to be coated and ambient air temperatures are between 60 and 90 deg F.

PART 2 - PRODUCTS

2.1 ACOUSTICAL JOINT SEALANTS

A. Acoustical joint-sealant products that effectively reduce airborne sound transmission through perimeter joints and openings in building construction, as demonstrated by testing representative assemblies in accordance with ASTM E90.

B. Acoustical Sealant for Exposed and Concealed Joints: Manufacturer's standard nonsag, paintable, nonstaining latex acoustical sealant complying with ASTM C834.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. DAP Products Inc.
b. Everkem Diversified Products, Inc.
c. Franklin International
d. Grabber Construction Products, Inc.
e. Hilti, Inc.
f. OSI Sealants; Henkel Corporation
g. Pecora Corporation
h. Specified Technologies Inc.

2. Colors of Exposed Acoustical Joint Sealants: As selected by Architect from manufacturer's full range of colors.

2.2 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by acoustical joint-sealant manufacturer where required for adhesion of sealant to joint substrates.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive acoustical joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing acoustical joint sealants to comply with joint-sealant manufacturer's written instructions.

B. Joint Priming: Prime joint substrates where recommended by acoustical joint-sealant manufacturer. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF ACOUSTICAL JOINT SEALANTS

A. Comply with acoustical joint-sealant manufacturer's written installation instructions unless more stringent requirements apply.

B. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical joint sealant. Install acoustical joint sealants at both faces of partitions, at perimeters, and through penetrations. Comply with ASTM C919, ASTM C1193, and manufacturer's written instructions for closing off sound-flanking paths around or through assemblies, including sealing partitions to underside of floor slabs above acoustical ceilings.

C. Acoustical Ceiling Areas: Apply acoustical joint sealant at perimeter edge moldings of acoustical ceiling areas in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.

3.4 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of acoustical joint sealants and of products in which joints occur.

3.5 PROTECTION

A. Protect acoustical joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated acoustical joint sealants immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION

SECTION 081113 - HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior standard steel doors and frames.
2. Exterior standard steel doors and frames.
3. Borrowed lites.

B. Related Requirements:

1. Section 087111 "Door Hardware (Descriptive Specification)" for door hardware for hollow-metal doors.

1.2 DEFINITIONS

A. Minimum Thickness: Minimum thickness of base metal without coatings in accordance with NAAMM-HMMA 803 or ANSI/SDI A250.8.

1.3 COORDINATION

A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

B. Coordinate requirements for installation of door hardware, electrified door hardware, and access control and security systems.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Interior standard steel doors and frames.
2. Exterior standard steel doors and frames.
3. Borrowed lites.

C. Product Data Submittals: For each product.

1. Include construction details, material descriptions, core descriptions, fire-resistance ratings, and finishes.

D. Shop Drawings: Include the following:

1. Elevations of each door type.
2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.
3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
4. Locations of reinforcement and preparations for hardware.
5. Details of each different wall opening condition.
6. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.
7. Details of anchorages, joints, field splices, and connections.
8. Details of accessories.
9. Details of moldings, removable stops, and glazing.

E. Product Schedule: For hollow-metal doors and frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final door hardware schedule.

1.6 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For door inspector.

1. Fire-Rated Door Inspector: Submit documentation of compliance with NFPA 80, Section 5.2.3.1.
2. Egress Door Inspector: Submit documentation of compliance with NFPA 101, Section 7.2.1.15.4.
3. Submit copy of DHI Fire and Egress Door Assembly Inspector (FDAI) certificate.

C. Product Test Reports: For each type of fire-rated hollow-metal door and frame assembly for tests performed by a qualified testing agency indicating compliance with performance requirements.

D. Oversize Construction Certification: For assemblies required to be fire-rated and exceeding limitations of labeled assemblies.

E. Field quality-control reports.

1.7 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Record Documents: For fire-rated doors, list of door numbers and applicable room name and number to which door accesses.

1.8 QUALITY ASSURANCE

A. Fire-Rated Door Inspector Qualifications: Inspector for field quality-control inspections of fire-rated door assemblies is to meet the qualifications set forth in NFPA 80, Section 5.2.3.1 and the following:

1. Door and Hardware Institute Fire and Egress Door Assembly Inspector (FDAI) certification.

B. Egress Door Inspector Qualifications: Inspector for field quality-control inspections of egress door assemblies is to meet the qualifications set forth in NFPA 101, Section 7.2.1.15.4 and the following:

1.9 DELIVERY, STORAGE, AND HANDLING

A. Deliver hollow-metal doors and frames palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.

1. Provide additional protection to prevent damage to factory-finished units.

B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.

C. Store hollow-metal doors and frames vertically under cover at Project site with head up. Place on minimum 4-inch-high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.

PART 2 - PRODUCTS

2.1 HOLLOW METAL DOORS AND FRAMES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Curries, AADG, Inc.; ASSA ABLOY Group
2. Fleming Door Products Ltd.; ASSA ABLOY Group
3. Republic Doors and Frames; a Allegion brand
4. Steelcraft; Allegion plc

2.2 PERFORMANCE REQUIREMENTS

A. Fire-Rated Door Assemblies: Assemblies complying with NFPA 80 that are listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction for fire-protection ratings indicated on Drawings, based on testing at positive pressure in accordance with NFPA 252 or UL 10C.

1. Smoke- and Draft-Control Door Assemblies: Listed and labeled for smoke and draft control by a qualified testing agency acceptable to authorities having jurisdiction, based on testing in accordance with UL 1784 and installed in compliance with NFPA 105.
2. Oversize Fire-Rated Door Assemblies: For units exceeding sizes of tested assemblies, provide certification by a qualified testing agency that doors comply with standard construction requirements for tested and labeled fire-rated door assemblies except for size.

B. Fire-Rated, Borrowed-Lite Assemblies: Assemblies complying with NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction, for fire-protection ratings indicated, based on testing in accordance with NFPA 257 or UL 9.

C. Thermally Rated Door Assemblies: Provide door assemblies with U-factor of not more than 0.40 deg Btu/F x h x sq. ft. when tested in accordance with ASTM C1363 or ASTM E1423.

2.3 INTERIOR STANDARD STEEL DOORS AND FRAMES

A. Construct hollow-metal doors and frames to comply with standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.

B. Extra-Heavy-Duty Doors and Frames: ANSI/SDI A250.8, Level 3; ANSI/SDI A250.4, Level A.

1. Doors:

   a. Type: As indicated in the Door and Frame Schedule on Drawings.
   b. Thickness: 1-3/4 inches.
   c. Face: Uncoated steel sheet, minimum thickness of 0.053 inch.
   d. Edge Construction: Model 1, Full Flush.
   e. Edge Bevel: Provide manufacturer's standard beveled or square edges.
   f. Core: Manufacturer's standard.
   g. Fire-Rated Core: Manufacturer's standard core for fire-rated doors.

2. Frames:

   a. Materials: Uncoated steel sheet, minimum thickness of 0.053 inch.
   b. Sidelite and Transom Frames: Fabricated from same thickness material as adjacent door frame.
   c. Construction: Face welded.

3. Exposed Finish: Prime.

2.4 EXTERIOR STANDARD STEEL DOORS AND FRAMES

A. Construct hollow-metal doors and frames to comply with standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.

B. Extra-Heavy-Duty Doors and Frames: ANSI/SDI A250.8, Level 3; ANSI/SDI A250.4, Level A.

1. Doors:

    a. Type: As indicated in the Door and Frame Schedule on Drawings.
    b. Thickness: 1-3/4 inches.
    c. Face: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum A60 coating.
    d. Edge Construction: Model 1, Full Flush.
    e. Edge Bevel: Provide manufacturer's standard beveled or square edges.
    f. Top Edge Closures: Close top edges of doors with flush closures of same material as face sheets. Seal joints against water penetration.
    g. Bottom Edges: Close bottom edges of doors with end closures or channels of same material as face sheets. Provide weep-hole openings in bottoms of exterior doors to permit moisture to escape.
    h. Core: Polystyrene, polyurethane, or polyisocyanurate.
    i. Fire-Rated Core: Manufacturer's standard core for fire-rated doors.

2. Frames:

    a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum A60 coating.
    b. Construction: Full profile welded.

3. Exposed Finish: Prime.

2.5 BORROWED LITES

A. Fabricate of uncoated steel sheet, minimum thickness of 0.053 inch.

B. Construction: Face welded.

C. Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of metal of same or greater thickness as metal as frames.

D. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.

2.6 HOLLOW-METAL PANELS

A. Provide hollow-metal panels of same materials, construction, and finish as adjacent door assemblies.

2.7 FRAME ANCHORS

A. Jamb Anchors:

1. Type: Anchors of minimum size and type required by applicable door and frame standard, and suitable for performance level indicated.

2. Quantity: Minimum of three anchors per jamb, with one additional anchor for frames with no floor anchor. Provide one additional anchor for each 24 inches of frame height above 7 feet.
3. Postinstalled Expansion Anchor: Minimum 3/8-inch-diameter bolts with expansion shields or inserts, with manufacturer's standard pipe spacer.

B. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor.

C. Floor Anchors for Concrete Slabs with Underlayment: Adjustable-type anchors with extension clips, allowing not less than 2-inch height adjustment. Terminate bottom of frames at top of underlayment.

D. Material: ASTM A879/A879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.

1. For anchors built into exterior walls, steel sheet complying with ASTM A1008/A1008M or ASTM A1011/A1011M; hot-dip galvanized in accordance with ASTM A153/A153M, Class B.

2.8 MATERIALS

A. Cold-Rolled Steel Sheet: ASTM A1008/A1008M, Commercial Steel (CS), Type B; suitable for exposed applications.

B. Hot-Rolled Steel Sheet: ASTM A1011/A1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.

C. Metallic-Coated Steel Sheet: ASTM A653/A653M, Commercial Steel (CS), Type B.

D. Inserts, Bolts, and Fasteners: Hot-dip galvanized in accordance with ASTM A153/A153M.

E. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.

F. Mineral-Fiber Insulation: ASTM C665, Type I (blankets without membrane facing); consisting of fibers manufactured from slag or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively; passing ASTM E136 for combustion characteristics.

G. Glazing: Comply with requirements in Section 088000 "Glazing" and Section 088813 “Fire Rated Glazing.”

2.9 FABRICATION

A. Door Astragals: Provide overlapping astragal on one leaf of pairs of doors where required by NFPA 80 for fire-performance rating or where indicated. Extend minimum 3/4 inch beyond edge of door on which astragal is mounted or as required to comply with published listing of qualified testing agency.

B. Hollow-Metal Frames: Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections, provide alignment plates or angles at each joint, fabricated of metal of same or greater thickness as frames.

1. Sidelite and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by welding, or by rigid mechanical anchors.
2. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
3. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.

    a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
    b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.

C. Hardware Preparation: Factory prepare hollow-metal doors and frames to receive templated mortised hardware, and electrical wiring; include cutouts, reinforcement, mortising, drilling, and tapping in accordance with ANSI/SDI A250.6, the Door Hardware Schedule on Drawings, and templates.

1. Reinforce doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.
2. Comply with BHMA A156.115 for preparing hollow-metal doors and frames for hardware.

D. Glazed Lites: Provide stops and moldings around glazed lites where indicated. Form corners of stops and moldings with mitered hairline joints.

1. Provide stops and moldings flush with face of door, and with square stops unless otherwise indicated.
2. Multiple Glazed Lites: Provide fixed and removable stops and moldings so that each glazed lite is capable of being removed independently.
3. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames. Provide loose stops and moldings on inside of hollow-metal doors and frames.
4. Coordinate rabbet width between fixed and removable stops with glazing and installation types indicated.
5. Provide stops for installation with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches o.c. and not more than 2 inches o.c. from each corner.

2.10 STEEL FINISHES

A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.

1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with ANSI/SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

2.11 LOUVERS

A. Provide louvers for interior doors, where indicated, which comply with SDI 111, with blades or baffles formed of 0.020-inch-thick, cold-rolled steel sheet set into 0.032-inch-thick steel frame.

1. Sightproof Louver: Stationary louvers constructed with inverted-V or inverted-Y blades.
2. Lightproof Louver: Stationary louvers constructed with baffles to prevent light from passing from one side to the other.
3. Fire-Rated Automatic Louvers: Louvers constructed with movable blades closed by actuating fusible link, and listed and labeled for use in fire-rated door assemblies of type and fire-resistance rating indicated by same qualified testing and inspecting agency that established fire-resistance rating of door assembly.

B. Form corners of moldings with hairline joints. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames.

PART 3 - EXECUTION

3.1 PREPARATION

A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces. Touch up factory-applied finishes where spreaders are removed.

B. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

3.2 INSTALLATION

A. Install hollow-metal doors and frames plumb, rigid, properly aligned, and securely fastened in place. Comply with approved Shop Drawings and with manufacturer's written instructions.

B. Hollow-Metal Frames: Comply with ANSI/SDI A250.11.

1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces without damage to completed Work.

    a. Where frames are fabricated in sections, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces. Touch-up finishes.
    b. Install frames with removable stops located on secure side of opening.

2. Fire-Rated Openings: Install frames in accordance with NFPA 80.
3. Floor Anchors: Secure with postinstalled expansion anchors.
4. Solidly pack mineral-fiber insulation inside frames.
5. Masonry Walls: Coordinate installation of frames to allow for solidly filling space between frames and masonry with grout or mortar.
6. In-Place Concrete or Masonry Construction: Secure frames in place with postinstalled

expansion anchors. Countersink anchors, and fill and make smooth, flush, and invisible on exposed faces.

7. Installation Tolerances: Adjust hollow-metal frames to the following tolerances:

    a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
    b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
    c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
    d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.

C. Hollow-Metal Doors: Fit and adjust hollow-metal doors accurately in frames, within clearances specified below.

1. Non-Fire-Rated Steel Doors: Comply with ANSI/SDI A250.8.
2. Fire-Rated Doors: Install doors with clearances in accordance with NFPA 80.
3. Smoke-Control Doors: Install doors in accordance with NFPA 105.

D. Glazing: Comply with installation requirements in Section 088000 "Glazing," Section 088813 “Fire Rated Glazing,” and with hollow-metal manufacturer's written instructions.

3.3 FIELD QUALITY CONTROL

A. Inspection Agency: Engage a qualified inspector to perform inspections and to furnish reports to Architect.

B. Inspections:

1. Fire-Rated Door Inspections: Inspect each fire-rated door in accordance with NFPA 80, Section 5.2.
2. Egress Door Inspections: Inspect each door equipped with panic hardware, each door equipped with fire exit hardware, each door located in an exit enclosure, each electrically controlled egress door, and each door equipped with special locking arrangements in accordance with NFPA 101, Section 7.2.1.15.

C. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.

D. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

E. Prepare and submit separate inspection report for each fire-rated door assembly indicating compliance with each item listed in NFPA 80 and NFPA 101.

3.4 REPAIR

A. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

B. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint in accordance with manufacturer's written instructions.

C. Touchup Painting: Cleaning and touchup painting of abraded areas of paint are specified in painting Sections.

END OF SECTION

SECTION 081116.13 - INTERIOR ALUMINUM DOORS AND WINDOWS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior aluminum doors and frames.
2. Interior aluminum window frames with glazing.
3. Transaction windows at Police Reception 102.
4. Reception Windows at Reception 214.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of product.

a. Include construction details, material descriptions, dimensions of individual components and profiles, fire rating, and finishes.

C. Shop Drawings:

1. Elevations, sections, and installation details for each wall-opening condition.
2. Details of construction of each component, including dimensioned profiles and metal thicknesses.
3. Locations of reinforcements and preparations for hardware.
4. Details of anchorages, joints, splices, connections, and accessories.
5. Details of trim, removable stops, and glazing.

D. Samples for Initial Selection: Manufacturer's standard color sheets, showing full range of available colors for each type of exposed finish.

E. Samples for Verification: Actual sample of finished products for each type of the following products:

1. Framing Member and Finish: 12 inches long. Include trim.
2. Window Corner Fabrication and Finish: 12-by-12-inch-long, full-size corner, including full-size sections of extrusions with removable stops.
3. Door Finish: Manufacturer's standard-size unit, but not less than 3 inches square.

F. Product Schedule: Use same designations indicated on Drawings. Coordinate with door hardware schedule and glazing.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Oversize Fire-Rated Construction Certification: For assemblies required to be fire rated and exceeding limitations of labeled assemblies.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For interior aluminum doors and frames.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Rated Door Assemblies: Complying with requirements in NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction for fire-protection ratings indicated in schedules, based on testing at positive pressure in accordance with NFPA 252 or UL 10C.

B. Smoke- and Draft-Control Door Assemblies: Listed and labeled for smoke and draft control based on testing in accordance with UL 1784 by a qualified testing agency acceptable to authorities having jurisdiction.

2.2 INTERIOR ALUMINUM DOORS AND WINDOWS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Alpha Aluminum Architectural Products
2. Avalon International Aluminum LLC
3. DIRTT Environmental Solutions
4. Frameworks
5. Modulex Products, Inc
6. RACO Interiors
7. Special-Lite
8. Speed View USA
9. Tubelite Inc.
10. Western Integrated Materials, Inc.
11. Wilson Partitions; a division of Arcadia Inc.

B. Source Limitations: Obtain interior aluminum doors and frames from single source from single manufacturer.

C. Interior Transaction Window sat Police Reception 102 (BL5): Basis of Design Product-Covenant Security Equipment Ready Access 503 Window.

1. Size: 36" (W) x 36" (H).
2. Frame: Aluminum 6036-T6, gauge .096, 4" depth, clear anodized finish.
3. Glass: 1/4" tempered clear.
4. Stainless Steel Shelf with Built-In Deal Tray: 12.25" x 2.25" x 36".
5. Stainless Steel Speak Thru: 4" Dia.

D. Interior Reception Windows at Reception 214 (BL6):

1. Size: 48" (W) x 48" (H).
2. Frame: Aluminum U channel with glazing gasket, clear anodized finish.
3. Glass: 1/4" Tempered.
4. Stainless Steel Deal Tray: Inset into solid surface counter as shown on drawings.
5. Stainless Steel Speak Thru: 4" Dia.

E. Aluminum Framing: ASTM B221, with alloy and temper required to suit structural and finish requirements, and not less than 0.062 inch thick.

1. Frame Dimensions: 2 inches wide by 4 inches deep.

F. Door Frames: Extruded aluminum, reinforced for hinges, strikes, and closers.

G. Window Glazing Frames: Extruded aluminum, for glass thickness indicated on Drawings.

H. Trim: Extruded aluminum, not less than 0.062 inch thick; removable, snap-in casing trim, glazing stops, and door stops, without exposed fasteners.

I. Aluminum-Framed Glass Doors: Manufacturer's standard, factory-assembled, 1-3/4-inch-thick doors.

1. Stile Width: 3-3/4 inches.
2. Top-Rail Height: 3-3/4 inches.
3. Bottom-Rail Height: Provides smooth surface within 10 inches of finished floor measured vertically.

2.3 ACCESSORIES

A. Fasteners: Aluminum, nonmagnetic, stainless steel, zinc-plated steel or other noncorrosive metal fasteners compatible with frames, stops, panels, reinforcement plates, hardware, anchors, and other items being fastened.

B. Corner Reinforcements and Alignment Clips: Manufacturer's standard concealed units to provide accurately fitted hairline joints at butted and mitered connections.

C. Door Silencers: Manufacturer's standard continuous mohair, wool pile, or vinyl seals, in manufacturer's standard color.

D. Glazing Gaskets: Manufacturer's standard extruded or molded rubber or plastic, to accommodate glazing thickness indicated; in manufacturer's standard color.

E. Glazing Stops: Removable to allow glazing replacement without framing disassembly.

F. Glass: As specified in Section 088000 "Glazing" and Section 088813 "Fire-Rated Glazing."

G. Door Hardware: As specified in Section 087111 "Door Hardware (Descriptive Specification)."

2.4 FABRICATION

A. Hardware Preparation: Factory-prepare components to receive templated mortised hardware; include cutouts, reinforcements, mortising, drilling, and tapping.

1. Reinforce doors and frames to receive non-templated mortised and surface-mounted hardware.

B. Glazing Stops: Locate removable stops on inside of spaces accessed by locking doors.

C. Fabricate components to allow secure installation without exposed fasteners and to provide accurately fitted hairline joints at butted and mitered connections.

2.5 ALUMINUM FINISHES

A. Comply with NAAMM/NOMMA AMP 500 for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

D. Clear Anodic Finish: AAMA 611, AA-M12C22A31, Class II, 0.010 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF ALUMINUM DOORS AND FRAMES

A. Install aluminum frames plumb, rigid, properly aligned, and securely fastened in place in accordance with manufacturer's written instructions.

1. Fire-Rated Door Assemblies: Install in accordance with NFPA 80.
2. Smoke- and Draft-Control Door Assemblies: Install in accordance with NFPA 105.

3. Use concealed installation clips to produce tightly fitted and aligned splices and connections.
4. Secure clips to extruded main-frame components and not to snap-in or trim members.
5. Do not leave screws or other fasteners exposed to view when installation is complete.

B. Glass: Install glass in accordance with Section 088000 "Glazing" and Section 088813 "Fire-Rated Glazing" and aluminum-frame manufacturer's written instructions.

C. Doors: Install doors aligned with frames and fitted with required hardware.

3.3 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Egress Door Assembly Acceptance Testing: Test and inspect egress doors in accordance with NFPA 101.

C. Repair or remove and replace installations where testing and inspections indicate that they do not comply with specified requirements.

D. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

E. Prepare test and inspection reports.

3.4 ADJUSTING AND CLEANING

A. Inspect installation, correct misalignments, and tighten loose connections.

B. Doors: Adjust doors to operate smoothly and easily, without binding or warping. Adjust hardware to function smoothly in accordance with manufacturer's written instructions.

C. Clean exposed frame surfaces promptly after installation, using cleaning methods recommended in writing by frame manufacturer and in accordance with AAMA 609 & 610.

D. Touch Up: Immediately after installation, repair damaged areas of aluminum finishes and touchup in accordance with manufacturer's written instructions.

END OF SECTION

SECTION 081416 - FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid-core five-ply flush wood veneer-faced doors and transom panels for transparent finish.
2. Light frames and louvers.

B. Related Requirements:

1. Section 088000 "Glazing" for glass view panels in flush wood doors.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Solid-core five-ply flush wood veneer-faced doors and transom panels for transparent finish.
2. Light frames and louvers.

C. Product Data Submittals: For each product, including the following:

1. Door core materials and construction.
2. Door edge construction
3. Door face type and characteristics.
4. Door louvers.
5. Door trim for openings.
6. Door frame construction.
7. Factory-machining criteria.
8. Factory-finishing specifications.

D. Shop Drawings: Indicate location, size, and hand of each door; elevation of each type of door; construction details not covered in Product Data; and the following:

1. Door schedule indicating door and frame location, type, size, fire protection rating, and swing.
2. Door elevations, dimension and locations of hardware, lite and louver cutouts, and glazing thicknesses.
3. Details of frame for each frame type, including dimensions and profile.
4. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.

5. Dimensions and locations of blocking for hardware attachment.
6. Dimensions and locations of mortises and holes for hardware.
7. Clearances and undercuts.
8. Requirements for veneer matching.
9. Doors to be factory finished and application requirements.

E. Samples for Initial Selection: For factory-finished doors.

F. Samples for Verification:

1. Factory finishes applied to actual door face materials, approximately 8 by 10 inches, for each material and finish. For each wood species and transparent finish, provide set of three Samples showing typical range of color and grain to be expected in finished Work.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Sample Warranty: For special warranty.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Comply with requirements of referenced standard and manufacturer's written instructions.

B. Package doors individually in plastic bags or cardboard cartons.

C. Mark each door on top and bottom rail with opening number used on Shop Drawings.

1.5 FIELD CONDITIONS

A. Environmental Limitations:

1. Do not deliver or install doors until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and HVAC system is operating and maintaining temperature and relative humidity at levels designed for building occupants for the remainder of construction period.

1.6 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Delamination of veneer.
b. Warping (bow, cup, or twist) more than 1/4 inch in a 42-by-84-inch section.
c. Telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch span.

2. Warranty also includes installation and finishing that may be required due to repair or replacement of defective doors.
3. Warranty Period for Solid-Core Interior Doors: Life of installation.

PART 2 - PRODUCTS

2.1 FLUSH WOOD DOORS, GENERAL

A. Quality Standard: In addition to requirements specified, comply with AWI/AWMAC/WI's "Architectural Woodwork Standards."

1. Provide labels from AWI certification program indicating that doors comply with requirements of grades specified.
2. The Contract Documents contain requirements that are more stringent than the referenced quality standard. Comply with the Contract Documents in addition to those of the referenced quality standard.

B. Adhesives: Do not use adhesives that contain urea formaldehyde.

2.2 SOLID-CORE FIVE-PLY FLUSH WOOD VENEER-FACED DOORS AND TRANSOM PANELS FOR TRANSPARENT FINISH

A. Interior Doors, Solid-Core Five-Ply Veneer-Faced :

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Lambton Doors
    b. Lynden Door, Inc.
    c. Masonite Architectural
    d. Oregon Door
    e. Oshkosh Door Company
    f. VT Industries, Inc.
    g. Wilsonart LLC

2. Performance Grade: ANSI/WDMA I.S. 1A Extra Heavy Duty.
3. ANSI/WDMA I.S. 1A Quality Grade: Premium.
4. Faces: Single-ply wood veneer not less than 1/50 inch thick.

    a. Species: Select white birch.
    b. Cut: Rotary cut.
    c. Match between Veneer Leaves: Book match.
    d. Assembly of Veneer Leaves on Door Faces: Center-balance match.
    e. Pair and Set Match: Provide for doors hung in same opening or separated only by mullions.

5. Exposed Vertical and Top Edges: Same species as faces - Architectural Woodwork Standards edge Type A.

6. Core for Non-Fire-Rated Doors:

    a. ANSI A208.1, Grade LD-1 particleboard.

        1) Provide doors with glued-wood-stave or WDMA I.S. 10 structural-composite-lumber cores instead of particleboard cores for doors scheduled to receive exit devices in Section 087111 "Door Hardware (Descriptive Specification."

    b. Glued wood stave.
    c. WDMA I.S. 10 structural composite lumber.

        1) Screw Withdrawal, Door Face: 550 lbf.
        2) Screw Withdrawal, Vertical Door Edge: 550 lbf.

    d. Either glued wood stave or WDMA I.S. 10 structural composite lumber.

7. Construction: Five plies, hot-pressed bonded (vertical and horizontal edging is bonded to core), with entire unit abrasive planed before veneering.

2.3 LIGHT FRAMES AND LOUVERS

A. Wood Beads for Light Openings in Wood Doors: Provide manufacturer's standard wood beads unless otherwise indicated.

1. Wood Species: Same species as door faces.
2. Profile: Manufacturer's standard shape.
3. At wood-core doors with 20-minute fire-protection ratings, provide wood beads and metal glazing clips approved for such use.

B. Wood Louvers: Door manufacturer's standard solid-wood louvers unless otherwise indicated.

1. Wood Species: Same species as door faces.
2. Profile: Flat.

C. Metal Louvers:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Allegion plc
    b. Anemostat Air Distribution; Anemostat, Inc.; Mestek, Inc.
    c. ASSA ABLOY
    d. JL Industries; Activar Construction Products Group, Inc.
    e. L & L Louvers, Inc.
    f. McGill Architectural Products

2. Blade Type: Vision-proof, inverted V.
3. Metal and Finish:

a. Hot-dip galvanized steel, 0.040 inch thick, with baked-enamel- or powder-coated finish.

2.4 FABRICATION

A. Factory fit doors to suit frame-opening sizes indicated.

1. Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.
2. Comply with NFPA 80 requirements for fire-rated doors.

B. Factory machine doors for hardware that is not surface applied.

1. Locate hardware to comply with DHI-WDHS-3.
2. Comply with final hardware schedules, door frame Shop Drawings, ANSI/BHMA-156.115-W, and hardware templates.
3. Coordinate with hardware mortises in metal frames, to verify dimensions and alignment before factory machining.
4. For doors scheduled to receive electrified locksets, provide factory-installed raceway and wiring to accommodate specified hardware.

C. Openings: Factory cut and trim openings through doors.

1. Light Openings: Trim openings with moldings of material and profile indicated.
2. Glazing: Factory install glazing in doors indicated to be factory finished. Comply with applicable requirements in Section 088000 "Glazing."
3. Louvers: Factory install louvers in prepared openings.

2.5 FACTORY FINISHING

A. Comply with referenced quality standard for factory finishing.

1. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.
2. Finish faces, all four edges, edges of cutouts, and mortises.
3. Stains and fillers may be omitted on bottom edges, edges of cutouts, and mortises.

B. Factory finish doors.

C. Transparent Finish:

1. ANSI/WDMA I.S. 1A Grade: Premium.

a. TR-8 UV Cured Acrylated Polyester/Urethane.

2. Staining: As selected by Architect from manufacturer's full range.
3. Sheen: Satin.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine doors and installed door frames, with Installer present, before hanging doors.

1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
2. Reject doors with defects.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Hardware: For installation, seeSection 087111 "Door Hardware (Descriptive Specification)."

B. Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.

1. Install fire-rated doors and frames in accordance with NFPA 80.
2. Install smoke- and draft-control doors in accordance with NFPA 105.

C. Factory-Fitted Doors: Align in frames for uniform clearance at each edge.

D. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

3.3 ADJUSTING

A. Operation: Rehang or replace doors that do not swing or operate freely.

B. Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION

SECTION 083113 - ACCESS DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Flush access doors with exposed flanges.
2. Fire-rated access doors with exposed flanges.

B. Related Requirements:

1. Section 077200 "Roof Accessories" for roof hatches.
2. Section 233300 "Air Duct Accessories" for heating and air-conditioning duct access doors.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, fire ratings, material descriptions, dimensions of individual components and profiles, and finishes.

C. Samples: For each type of access door and frame and for each finish specified, complete assembly minimum 6 by 6 inches in size.

D. Product Schedule: For access doors and frames. Use same designations indicated on Drawings.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Qualification Statements: For testing and inspecting agency.

1. Fire-Rated Door Inspector: Submit documentation of compliance with NFPA 80, Section 5.2.3.1.
2. Submit copy of DHI Fire and Egress Door Assembly Inspector (FDAI) certificate.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Record Documents: For fire-rated doors, list of applicable room name and number in which access door is located.

1.5 QUALITY ASSURANCE

A. Fire-Rated Door Inspector Qualifications: Inspector for field quality-control inspections of fire-rated door assemblies complies with the qualifications set forth in NFPA 80, Section 5.2.3.1 and the following:

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Rated Access Doors and Frames: Assemblies complying with NFPA 80 that are listed and labeled by a qualified testing agency, for fire-protection ratings indicated, in accordance with NFPA 252 or UL 10B.

2.2 ACCESS DOORS AND FRAMES

A. Flush Access Doors with Exposed Flanges :

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. ACUDOR Products, Inc
    b. Babcock-Davis
    c. Cendrex Inc.
    d. Elmdor; Morris Group International, Inc.
    e. JL Industries; Activar Construction Products Group, Inc.
    f. Karp Associates, Inc
    g. Lane-Aire Manufacturing Corp.
    h. Larsen's Manufacturing Company
    i. Maxam Metal Products Limited
    j. Metropolitan Door Industries Corp.
    k. MIFAB, Inc
    l. Milcor by Duravent; Duravent Group.
    m. Nystrom, Inc.
    n. Williams Brothers Corporation of America

2. Description: Face of door flush with frame, with exposed flange and concealed hinge.
3. Locations: Wall and ceiling.
4. Door Size: As indicated on drawings.
5. Uncoated Steel Sheet for Door: Nominal 0.060 inch, 16 gage, factory inished.
6. Frame Material: Same material, thickness, and finish as door.
7. Latch and Lock: Cam latch, screwdriver operated.

2.3 FIRE-RATED ACCESS DOORS AND FRAMES

A. Fire-Rated Access Doors with Exposed Flanges :

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. ACUDOR Products, Inc
    b. Babcock-Davis
    c. Cendrex Inc.
    d. Elmdor; Morris Group International, Inc.
    e. JL Industries; Activar Construction Products Group, Inc.
    f. Karp Associates, Inc
    g. Lane-Aire Manufacturing Corp.
    h. Larsen's Manufacturing Company
    i. Maxam Metal Products Limited
    j. Metropolitan Door Industries Corp.
    k. MIFAB, Inc
    l. Milcor by Duravent; Duravent Group.
    m. Nystrom, Inc.
    n. Williams Brothers Corporation of America

2. Description: Door flush with frame, with a core of mineral-fiber insulation enclosed in sheet metal uninsulated; with exposed flange, self-closing door, and concealed hinge.
3. Door Type:

    a. Flush.

4. Locations: Wall.
5. Door Size: As indicated on drawings.
6. Fire-Resistance Rating: Not less than that of adjacent construction.
7. Uncoated Steel Sheet for Door: Nominal 0.036 inch, 20gage, factory finished.
8. Frame Material: Same material, thickness, and finish as door.
9. Latch and Lock: Self-latching door hardware, operated by key.

2.4 MATERIALS

A. Steel Plates, Shapes, and Bars: ASTM A36/A36M.

B. Steel Sheet: Uncoated or electrolytic zinc coated, ASTM A879/A879M, with cold-rolled steel sheet substrate complying with ASTM A1008/A1008M, Commercial Steel (CS), exposed.

C. Frame Anchors: Same material as door face.

D. Inserts, Bolts, and Anchor Fasteners: Hot-dip galvanized steel in accordance with ASTM A153/A153M or ASTM F2329/F2329M.

2.5 FABRICATION

A. General: Provide access door and frame assemblies manufactured as integral units ready for installation.

B. Metal Surfaces: For metal surfaces exposed to view in the completed Work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names, or roughness.

C. Doors and Frames: Grind exposed welds smooth and flush with adjacent surfaces. Furnish mounting holes, attachment devices and fasteners of type required to secure access doors to types of supports indicated.

D. Latch and Lock Hardware:

1. Quantity: Furnish number of latches and locks required to hold doors tightly closed.
2. Keys: Furnish two keys per lock and key all locks alike.

2.6 FINISHES

A. Comply with NAAMM/NOMMA AMP 500 for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

D. Painted Finishes: Comply with coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.

1. Factory Finished: Apply manufacturer's standard baked-enamel or powder-coat finish immediately after cleaning and pretreating, with minimum dry-film thickness of **1 mil** for topcoat.

a. Color: As selected by Architect from full range of industry colors.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF ACCESS DOORS AND FRAMES

A. Comply with manufacturer's written instructions for installing access doors and frames.

3.3 FIELD QUALITY CONTROL

A. Inspection Agency: Engage a qualified inspector to perform inspections and to furnish reports to Architect.

B. Inspections:

1. Fire-Rated Door Inspections: Inspect each fire-rated access door in accordance with NFPA 80, Section 5.2.

C. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.

D. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

E. Prepare and submit separate inspection report for each fire-rated access door indicating compliance with each item listed in NFPA 80 and NFPA 101.

3.4 ADJUSTING

A. Adjust doors and hardware, after installation, for proper operation.

END OF SECTION

SECTION 083323 - OVERHEAD COILING DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Insulated service doors.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type and size of overhead coiling door and accessory.

C. Shop Drawings: For each installation and for special components not dimensioned or detailed in manufacturer's product data.

1. Include points of attachment and their corresponding static and dynamic loads imposed on structure.
2. Show locations of controls, locking devices, and other accessories.
3. Include diagrams for power, signal, and control wiring.

D. Samples: For each exposed product and for each color and texture specified.

1.3 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance data.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer for both installation and maintenance of units required for this Project.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Structural Performance, Exterior Doors: Capable of withstanding the design wind loads.

1. Design Wind Load: Design for wind velocity, exposure and importance factor indicated in accordance with ASCE 7 for component and cladding wind pressures.

2.2 DOOR ASSEMBLY

A. Insulated Service Door: Overhead coiling door formed with curtain of interlocking metal slats.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ACME Rolling Doors.
b. Alpine Overhead Doors, Inc.
c. C.H.I. Overhead Doors.
d. City-Gates.
e. Cookson Company.
f. Cornell Iron Works, Inc.
g. Overhead Door Corporation.

B. Operation Cycles: Door components and operators capable of operating for not less than 20,000.

C. Curtain R-Value: 8 deg F x h x sq. ft./Btu.

D. Door Curtain Material: Galvanized steel.

E. Door Curtain Slats: Flat profile slats of 1-7/8-inch center-to-center height.

1. Insulated-Slat Interior Facing: Metal.

F. Bottom Bar: Two angles, each not less than 1-1/2 by 1-1/2 by 1/8 inch thick; fabricated from stainless steel or aluminum extrusions and finished to match door.

G. Curtain Jamb Guides: Galvanized steel with exposed finish matching curtain slats.

H. Hood: Match curtain material and finish.

1. Mounting: Face of wall.

I. Locking Devices: Equip door with locking device assembly and chain lock keeper.

1. Locking Device Assembly: Single-jamb side locking bars, operable from inside with thumb turn.

J. Electric Door Operator:

1. Usage Classification: Heavy duty, 25 or more cycles per hour and over 90 cycles per day.
2. Safety: Listed according to UL 325 by a qualified testing agency for commercial or industrial use.
3. Motor Exposure: Interior.

4. Emergency Manual Operation: Chain type.
5. Obstruction-Detection Device: Automatic photoelectric sensor ; self-monitoring type.
6. Control Station(s): Interior mounted.
7. Horsepower: 1/2 hp.

K. Curtain Accessories: Equip door with weatherseals.

L. Door Finish:

1. Baked-Enamel or Powder-Coated Finish: Color as selected by Architect from manufacturer's full range.
2. Interior Curtain-Slat Facing: Match finish of exterior curtain-slat face.

2.3 MATERIALS, GENERAL

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.4 DOOR CURTAIN MATERIALS AND CONSTRUCTION

A. Door Curtains: Fabricate overhead coiling-door curtain of interlocking metal slats, designed to withstand wind loading indicated, in a continuous length for width of door without splices. Unless otherwise indicated, provide slats of thickness and mechanical properties recommended by door manufacturer for performance, size, and type of door indicated, and as follows:

1. Insulation: Fill slats for insulated doors with manufacturer's standard thermal insulation complying with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, according to ASTM E 84 or UL 723. Enclose insulation completely within slat faces.
2. Metal Interior Curtain-Slat Facing: Match metal of exterior curtain-slat face, with minimum steel thickness of 0.010 inch.

B. Curtain Jamb Guides: Manufacturer's standard angles or channels and angles of same material and finish as curtain slats unless otherwise indicated, with sufficient depth and strength to retain curtain, to allow curtain to operate smoothly, and to withstand loading. Slot bolt holes for guide adjustment. Provide removable stops on guides to prevent overtravel of curtain.

2.5 HOODS

A. General: Form sheet metal hood to entirely enclose coiled curtain and operating mechanism at opening head. Contour to fit end brackets to which hood is attached. Roll and reinforce top and bottom edges for stiffness. Form closed ends for surface-mounted hoods and fascia for any portion of between-jamb mounting that projects beyond wall face. Equip hood with intermediate support brackets as required to prevent sagging.

2.6 LOCKING DEVICES

A. Slide Bolt: Fabricate with side-locking bolts to engage through slots in tracks for locking by padlock, located on both left and right jamb sides, operable from coil side.

B. Locking Device Assembly: Fabricate with cylinder lock, spring-loaded dead bolt, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.

1. Lock Cylinders: Cylinders standard with manufacturer and keyed to building keying system.
2. Keys: Three for each cylinder.

C. Chain Lock Keeper: Suitable for padlock.

D. Safety Interlock Switch: Equip power-operated doors with safety interlock switch to disengage power supply when door is locked.

2.7 CURTAIN ACCESSORIES

A. Smoke Seals: Equip each fire-rated door with replaceable smoke-seal perimeter gaskets or brushes for smoke and draft control as required for door listing and labeling by a qualified testing agency.

B. Weatherseals for Exterior Doors: Equip each exterior door with weather-stripping gaskets fitted to entire exterior perimeter of door for a weather-resistant installation unless otherwise indicated.

C. Astragal for Interior Doors: Equip each door bottom bar with a replaceable, adjustable, continuous, compressible gasket of flexible vinyl, rubber, or neoprene as a cushion bumper.

D. Push/Pull Handles: Equip each push-up-operated or emergency-operated door with lifting handles on each side of door, finished to match door.

E. Pull-Down Strap: Provide pull-down straps for doors more than 84 inches high.

F. Poll Hooks: Provide pole hooks and poles for doors more than 84 inches high.

2.8 COUNTERBALANCING MECHANISM

A. General: Counterbalance doors by means of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed bearings or self-lubricating graphite bearings for rotating members.

B. Brackets: Manufacturer's standard mounting brackets of either cast iron or cold-rolled steel plate.

2.9 ELECTRIC DOOR OPERATORS

A. General: Electric door operator assembly of size and capacity recommended and provided by door manufacturer for door and operation-cycles requirement specified, with electric motor and factory-prewired motor controls, starter, gear-reduction unit, solenoid-operated brake, clutch, control stations, control devices, integral gearing for locking door, and accessories required for proper operation.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Chamberlain Group, Inc. (The).

2. Comply with NFPA 70.
3. Control equipment complying with NEMA ICS 1, NEMA ICS 2, and NEMA ICS 6, with NFPA 70 Class 2 control circuit, maximum 24-V ac or dc.

B. Usage Classification: Electric operator and components capable of operating for not less than number of cycles per hour indicated for each door.

C. Motors: Reversible-type motor with controller (disconnect switch) for motor exposure indicated.

1. Electrical Characteristics:

a. Phase: Single phase.
b. Volts: 115 V.
c. Hertz: 60.

2. Motor Size: Minimum size as indicated. If not indicated, large enough to start, accelerate, and operate door in either direction from any position, at a speed not less than 8 in./sec. and not more than 12 in./sec., without exceeding nameplate ratings or service factor.
3. Operating Controls, Controllers, Disconnect Switches, Wiring Devices, and Wiring: Manufacturer's standard unless otherwise indicated.

D. Obstruction Detection Devices: External entrapment protection consisting of indicated automatic safety sensor capable of protecting full width of door opening. For non-fire-rated doors, activation of device immediately stops and reverses downward door travel.

1. Photoelectric Sensor: Manufacturer's standard system designed to detect an obstruction in door opening without contact between door and obstruction.

a. Self-Monitoring Type: Designed to interface with door operator control circuit to detect damage to or disconnection of sensing device. When self-monitoring feature is activated, door closes only with sustained or constant pressure on close button.

E. Control Station: Three-button control station in fixed location with momentary-contact push-button controls labeled "Open" and "Stop" and sustained- or constant-pressure push-button control labeled "Close."

1. Interior-Mounted Units: Full-guarded, surface-mounted, heavy-duty type, with general-purpose NEMA ICS 6, Type 1 enclosure.

F. Emergency Manual Operation: Equip each electrically powered door with capability for emergency manual operation. Design manual mechanism so required force for door operation does not exceed 25 lbf.

G. Emergency Operation Disconnect Device: Equip operator with hand-operated disconnect mechanism for automatically engaging manual operator and releasing brake for emergency manual operation while disconnecting motor without affecting timing of limit switch. Mount mechanism so it is accessible from floor level. Include interlock device to automatically prevent motor from operating when emergency operator is engaged.

H. Motor Removal: Design operator so motor may be removed without disturbing limit-switch adjustment and without affecting emergency manual operation.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install overhead coiling doors and operating equipment complete with necessary hardware, anchors, inserts, hangers, and equipment supports; according to manufacturer's written instructions and as specified.

B. Fire-Rated Doors: Install according to NFPA 80.

C. Smoke-Control Doors: Install according to NFPA 80 and NFPA 105.

D. Power-Operated Doors: Install according to UL 325.

E. Adjust hardware and moving parts to function smoothly so that doors operate easily, free of warp, twist, or distortion. Lubricate bearings and sliding parts as recommended by manufacturer. Adjust seals to provide tight fit around entire perimeter.

3.2 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain overhead coiling doors.

END OF SECTION

SECTION 084113 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Aluminum-framed entrance and storefront systems.

B. Related Requirements:

1. Section 081116.13 "Interior Aluminum Doors and Frames" for interior aluminum framing.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Operating characteristics, electrical characteristics, and furnished accessories.

C. Shop Drawings:

1. Plans, elevations, sections, full-size details, and attachments to other work.
2. Details of provisions for assembly expansion and contraction and for draining moisture occurring within the assembly to the exterior.
3. Full-size isometric details of each type of vertical-to-horizontal intersection of aluminum-framed entrance and storefront systems, showing the following:

    a. Joinery, including concealed welds.
    b. Anchorage.
    c. Expansion provisions.
    d. Glazing.
    e. Flashing and drainage.

4. Connection to and continuity with adjacent thermal, weather, air, and vapor barriers.
5. Point-to-point wiring diagrams showing the following:

    a. Power requirements for each electrically operated door hardware.
    b. Location and types of switches, signal device, conduit sizes, and number and size of wires.

6. Signed and sealed by the qualified professional engineer responsible for their preparation.

D. Samples for Initial Selection: Manufacturer's standard color sheets, showing full range of available colors for each type of exposed finish.

E. Samples for Verification: Actual sample of finished products for each type of exposed finish.

1. Size: Manufacturers' standard size.

F. Entrance Door Hardware Schedule: Prepared by or under supervision of supplier, detailing fabrication and assembly of entrance door hardware, as well as procedures and diagrams. Coordinate final entrance door hardware schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of entrance door hardware.

G. Delegated Design Submittals: For aluminum-framed entrances and storefront systems, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Energy Performance Certificates: For aluminum-framed entrance and storefront systems, accessories, and components, from manufacturer.

1. Basis for Certification: NFRC-certified energy performance values for each aluminum-framed entrance and storefront system.

C. Product Test Reports: For aluminum-framed entrance and storefront systems, for tests performed by manufacturer and witnessed by a qualified testing agency.

D. Field Quality-Control Reports: For aluminum-framed entrance and storefront systems.

E. Quality-Control Program: Developed specifically for Project, including fabrication and installation, in accordance with recommendations in ASTM C1401. Include periodic quality-control reports.

F. Qualification Statements:

1. For Installer and egress door inspector.

G. Delegated Design Engineer Qualifications: For aluminum-framed entrance and storefront systems.

H. Sample Warranties: For aluminum-framed entrance and storefront systems.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For aluminum-framed entrance and storefront systems.

C. Maintenance Data for Structural Sealant: For structural-sealant-glazed storefront. Include ASTM C1401 recommendations for post-installation-phase quality-control program.

1.5 QUALITY ASSURANCE

A. Installer Qualifications:

1. Entity that employs installers and supervisors who are trained and approved by manufacturer.

B. Delegated Design Engineer Qualifications: A professional engineer who is legally qualified to practice in state where Project is located and who is experienced in providing engineering services of the type indicated.

C. Testing Agency Qualifications: Qualified in accordance with ASTM E699 for testing indicated and accredited by IAS or ILAC Mutual Recognition Arrangement as complying with ISO/IEC 17025 and acceptable to Owner and Architect.

D. Egress Door Inspector Qualifications:

1. Inspector for field quality-control inspections of egress door assemblies to comply with qualifications set forth in NFPA 101, Ch. 7 "Means of Egress," Section "Means of Egress Components," Article "Inspection of Door Openings."
2. Inspector for field quality-control inspections of egress door assemblies to be certified under DHI's certification program as a Fire and Egress Door Assembly Inspector (FDAI) or a Certified Fire and Egress Door Assembly Inspector (CFDAI).

E. Product Options: Information on Drawings and in Specifications establishes requirements for aesthetic effects and performance characteristics of assemblies. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction.

1. Do not change intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If changes are proposed, submit comprehensive explanatory data to Architect for review.

1.6 WARRANTY

A. Special Warranty: Manufacturer and Installer agree to repair or replace components of aluminum-framed entrance and storefront systems that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures, including but not limited to, excessive deflection.
b. Faulty operation of operating components and hardware.
c. Deterioration of metals, metal finishes, and other materials beyond normal weathering.

2. Warranty Period: Ten years from date of Substantial Completion.

B. Special Finish Warranty, Factory-Applied Finishes: Standard form in which manufacturer agrees to repair finishes or replace aluminum that shows evidence of deterioration of organic finishes within specified warranty period.

1. Deterioration includes, but is not limited to, the following:

a. Color fading more than 5 Delta E units when tested in accordance with ASTM D 2244.
b. Chalking in excess of a No. 8 rating when tested in accordance with ASTM D 4214.
c. Cracking, peeling, or chipping.

2. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain all components of aluminum-framed entrance and storefront system, including framing spandrel panels and accessories, from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design aluminum-framed entrance and storefront systems.

B. General Performance: Comply with performance requirements specified, as determined by testing of aluminum-framed entrance and storefront systems representing those indicated for this Project without failure due to defective manufacture, fabrication, installation, or other defects in construction.

1. Aluminum-framed entrance and storefront systems to withstand movements of supporting structure, including, but not limited to, twist, column shortening, long-term creep, and deflection from uniformly distributed and concentrated live loads.
2. Failure also includes the following:

a. Thermal stresses transferring to building structure.
b. Glass breakage.
c. Noise or vibration created by wind and thermal and structural movements.
d. Loosening or weakening of fasteners, attachments, and other components.
e. Failure of operating units.

C. Structural Loads:

1. Wind Loads: As indicated on Drawings.

D. Deflection of Framing Members Supporting Glass: At design wind load, as follows:

1. Deflection Normal to Wall Plane: Limited to 1/175 of length of span of the framing member for lengths of up to 13 feet 6 inches and to 1/240 of length of span of the framing member plus 1/4 inch for lengths greater than 13 feet 6 inches.
2. Deflection Parallel to Glazing Plane: Limited to amount not exceeding that which reduces glazing bite to less than 75 percent of design dimension and that which reduces edge clearance between framing members and glazing or other fixed components to less than 1/8 inch.

E. Structural: Test in accordance with ASTM E330/E330M as follows:

1. When tested at positive and negative wind-load design pressures, storefront assemblies, including entrance doors, do not evidence deflection exceeding specified limits.
2. When tested at 150 percent of positive and negative wind-load design pressures, storefront assemblies, including entrance doors and anchorage, do not evidence material failures, structural distress, or permanent deformation of main framing members exceeding 0.2 percent of span.
3. Test Durations: As required by design wind velocity, but not less than 10 seconds.

F. Water Penetration under Static Pressure: Test in accordance with ASTM E331 as follows:

1. No evidence of water penetration through fixed glazing and framing areas, including entrance doors, when tested in accordance with a minimum static-air-pressure differential of 20 percent of positive wind-load design pressure, but not less than10 lbf/sq. ft.
2. Maximum Water Leakage: No uncontrolled water penetrating assemblies or water appearing on assemblies' normally exposed interior surfaces from sources other than condensation. Water leakage does not include water controlled by flashing and gutters, or water that is drained to exterior.

G. Seismic Performance: Aluminum-framed entrance and storefront systems to withstand the effects of earthquake motions determined in accordance with ASCE/SEI 7.

1. Seismic Drift Causing Glass Fallout: Complying with criteria for passing based on building occupancy type when tested in accordance with AAMA 501.6 at design displacement and 1.5 times the design displacement.

H. Energy Performance: Certified and labeled by manufacturer for energy performance as follows:

1. Thermal Transmittance (U-factor):

   a. Fixed Glazing and Framing Areas: U-factor for the system of not more than 0.34 Btu/sq. ft. x h x deg F as determined in accordance with NFRC 100.
   b. Entrance Doors: U-factor of not more than 0.43 Btu/sq. ft. x h x deg F as determined in accordance with NFRC 100.

2. Air Leakage:

   a. Fixed Glazing and Framing Areas: Air leakage for the system of not more than 0.06 cfm/sq. ft. at a static-air-pressure differential of 6.24 lbf/sq. ft. when tested in accordance with ASTM E283.
   b. Entrance Doors: Air leakage of not more than 1.0 cfm/sq. ft. at a static-air-pressure differential of 1.57 lbf/sq. ft.

3. Condensation Resistance Factor (CRF):

    a. Fixed Glazing and Framing Areas: CRF for the system of not less than 55 as determined in accordance with AAMA 1503.
    b. Entrance Doors: CRF of not less than 57 as determined in accordance with AAMA 1503.

I. Thermal Movements: Allow for thermal movements resulting from ambient and surface temperature changes.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.
2. Thermal Cycling: No buckling; stress on glass; sealant failure; excess stress on framing, anchors, and fasteners; or reduction of performance when tested in accordance with AAMA 501.5.

    a. High Exterior Ambient-Air Temperature: That which produces an exterior metal-surface temperature of 180 deg F.
    b. Low Exterior Ambient-Air Temperature: 0 deg F.
    c. Interior Ambient-Air Temperature: 75 deg F.

2.3 ALUMINUM-FRAMED ENTRANCE AND STOREFRONT SYSTEMS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Kawneer Company, Inc.; Arconic Corporation
2. Old Castle Building Envelope (OBE)
3. Tubelite Inc.
4. YKK AP America Inc.

B. Framing Members: Manufacturer's extruded- or formed-aluminum framing members of thickness required and reinforced as required to support imposed loads.

1. Exterior Framing Construction: Thermally broken.
2. Interior Vestibule Framing Construction: Nonthermal.
3. Glazing System: Retained mechanically with gaskets on four sides.
4. Glazing Plane: Front.
5. Finish: High-performance organic finish.
6. Fabrication Method: Field-fabricated stick system.
7. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.
8. Steel Reinforcement: As required by manufacturer.

C. Backer Plates: Manufacturer's standard, continuous backer plates for framing members, if not integral, where framing abuts adjacent construction.

D. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.

E. Insulated Spandrel Panels:

1. Laminated, metal-faced flat panels with no deviations in plane exceeding 0.8 percent of panel dimension in width or length.

a. Overall Panel Thickness: 1 inch.
b. Exterior Skin: Aluminum.

1) Thickness: Manufacturer's standard for finish and texture indicated.
2) Finish: Match framing system.
3) Texture: Smooth.
4) Backing Sheet: 1/8-inch-thick tempered hardboard.

c. Interior Skin: Aluminum.

1) Thickness: Manufacturer's standard for finish and texture indicated.
2) Finish: Matching storefront framing.
3) Texture: Smooth.
4) Backing Sheet: 1/8-inch-thick tempered hardboard.

d. Thermal Insulation Core: Manufacturer's standard extruded-polystyrene board.
e. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1) Flame-Spread Index: 25 or less.
2) Smoke-Developed Index: 450 or less.

F. Entrance Doors: Manufacturer's standard glazed entrance doors for manual-swing or automatic operation.

1. Door Construction: 2- to 2-1/4-inch overall thickness, with minimum 0.125-inch- thick, extruded-aluminum tubular rail and stile members. Mechanically fasten corners with reinforcing brackets that are deeply penetrated and fillet welded or that incorporate concealed tie rods.

a. Thermal Construction: High-performance plastic connectors separate aluminum members exposed to the exterior from members exposed to the interior.

2. Door Design: As indicated.
3. Glazing Stops and Gaskets: Square, snap-on, extruded-aluminum stops and preformed gaskets.

a. Provide nonremovable glazing stops on outside of door.

4. Finish: Match adjacent storefront framing finish.

2.4 ENTRANCE DOOR HARDWARE

A. Entrance Door Hardware: Hardware not specified in this Section is specified in Section 087111 "Door Hardware (Descriptive Specification)."

B. General: Provide entrance door hardware and entrance door hardware sets indicated in "Entrance Door Hardware Sets" Article for each entrance door, to comply with requirements in this Section.

1. Entrance Door Hardware Sets: Provide quantity, item, size, finish or color indicated, and products complying with BHMA standard referenced.
2. Sequence of Operation: Provide electrified door hardware function, sequence of operation, and interface with other building control systems indicated.
3. Opening-Force Requirements:

a. Egress Doors: Not more than 15 lbf to release the latch and not more than 30 lbf to set the door in motion and not more than 15 lbf to open the door to its minimum required width.
b. Accessible Interior Doors: Not more than 5 lbf to fully open door.

C. Designations: Requirements for design, grade, function, finish, quantity, size, and other distinctive qualities of each type of entrance door hardware are indicated in "Entrance Door Hardware Sets" Article. Products are identified by using entrance door hardware designations as follows:

1. References to BHMA Standards: Provide products complying with these standards and requirements for description, quality, and function.

D. Continuous-Gear Hinges: BHMA A156.26.

E. Mortise Auxiliary Locks: BHMA A156.5, Grade 1.

F. Panic Exit Devices: BHMA A156.3, Grade 1, listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for panic protection, based on testing in accordance with UL 305.

G. Cylinders:

1. As specified in Section 087111 "Door Hardware (Descriptive Specification)."

H. Strikes: Provide strike with black-plastic dust box for each latch or lock bolt; fabricated for aluminum framing.

I. Operating Trim: BHMA A156.6.

J. Removable Mullions: BHMA A156.3 extruded aluminum.

1. When used with panic exit devices, provide keyed removable mullions listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for panic protection, based on testing in accordance with UL 305. Use only mullions that have been tested with exit devices to be used.

K. Closers: BHMA A156.4, Grade 1, with accessories required for a complete installation, sized as required by door size, exposure to weather, and anticipated frequency of use; adjustable to comply with field conditions and requirements for opening force.

L. Concealed Overhead Holders and Stops: BHMA A156.8, Grade 1.

M. Door Stops: BHMA A156.16, Grade 1, floor or wall mounted, as appropriate for door location indicated, with integral rubber bumper.

N. Weather Stripping: Manufacturer's standard replaceable components.

1. Compression Type: Made of ASTM D2000 molded neoprene or ASTM D2287 molded PVC.
2. Sliding Type: AAMA 701/702, made of wool, polypropylene, or nylon woven pile with nylon-fabric or aluminum-strip backing.

O. Weather Sweeps: Manufacturer's standard exterior-door bottom sweep with concealed fasteners on mounting strip.

P. Thresholds: BHMA A156.21 raised thresholds beveled with a slope of not more than 1:2, with maximum height of 1/2 inch.

2.5 GLAZING

A. Glazing: Comply with Section 088000 "Glazing."

B. Glazing Gaskets: Manufacturer's standard sealed-corner pressure-glazing system of black, resilient elastomeric glazing gaskets, setting blocks, and shims or spacers.

C. Glazing Sealants: As recommended by manufacturer.

2.6 MATERIALS

A. Sheet and Plate: ASTM B209.

B. Extruded Bars, Rods, Profiles, and Tubes: ASTM B221.

C. Structural Profiles: ASTM B308/B308M.

D. Steel Reinforcement:

1. Structural Shapes, Plates, and Bars: ASTM A36/A36M.
2. Cold-Rolled Sheet and Strip: ASTM A1008/A1008M.
3. Hot-Rolled Sheet and Strip: ASTM A1011/A1011M.

E. Steel Reinforcement Primer: Manufacturer's standard zinc-rich, corrosion-resistant primer complying with SSPC-PS Guide No. 12.00; applied immediately after surface preparation and pretreatment. Select surface preparation methods in accordance with recommendations in SSPC-SP COM, and prepare surfaces in accordance with applicable SSPC standard.

2.7 ACCESSORIES

A. Automatic Door Operators: Section 087113 "Power Door Operators."

B. Fasteners and Accessories: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.

1. Use self-locking devices where fasteners are subject to loosening or turning out from thermal and structural movements, wind loads, or vibration.
2. Reinforce members as required to receive fastener threads.
3. Use exposed fasteners with countersunk Phillips screw heads, finished to match framing system, fabricated from 300 series stainless steel.

C. Anchors: Three-way adjustable anchors with minimum adjustment of 1 inch that accommodate fabrication and installation tolerances in material and finish compatible with adjoining materials and recommended by manufacturer.

1. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts complying with ASTM A123/A123M or ASTM A153/A153M requirements.

D. Concealed Flashing: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding flashing compatible with adjacent materials.

E. Bituminous Paint: Cold-applied asphalt-mastic paint containing no asbestos, formulated for 30-mil thickness per coat.

F. Rigid PVC filler.

2.8 FABRICATION

A. Form or extrude aluminum shapes before finishing.

B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.

C. Fabricate components that, when assembled, have the following characteristics:

1. Profiles that are sharp, straight, and free of defects or deformations.
2. Accurately fitted joints with ends coped or mitered.
3. Physical and thermal isolation of glazing from framing members.
4. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
5. Provisions for field replacement of glazing from interior.
6. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.

D. Mechanically Glazed Framing Members: Fabricate for flush glazing without projecting stops.

E. Storefront Framing: Fabricate components for assembly using screw-spline system.

F. Entrance Door Frames: Reinforce as required to support loads imposed by door operation and for installing entrance door hardware.

1. At interior and exterior doors, provide compression weather stripping at fixed stops.

G. Entrance Doors: Reinforce doors as required for installing entrance door hardware.

1. At pairs of exterior doors, provide sliding-type weather stripping retained in adjustable strip and mortised into door edge.
2. At exterior doors, provide weather sweeps applied to door bottoms.

H. Entrance Door Hardware Installation: Factory install entrance door hardware to the greatest extent possible. Cut, drill, and tap for factory-installed entrance door hardware before applying finishes.

I. After fabrication, clearly mark components to identify their locations in Project in accordance with Shop Drawings.

2.9 ALUMINUM FINISHES

A. High-Performance Organic Finish, Two-Coat PVDF: Fluoropolymer finish complying with AAMA 2604 and containing not less than 70 percent PVDF resin by weight in color coat.

1. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
2. Color and Gloss: As selected by Architect from manufacturer's full range.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF ALUMINUM-FRAMED ENTRANCE AND STOREFRONT SYSTEMS

A. Comply with manufacturer's written instructions.

B. Do not install damaged components.

C. Fit joints to produce hairline joints free of burrs and distortion.

D. Rigidly secure nonmovement joints.

E. Install anchors with separators and isolators to prevent metal corrosion and electrolytic deterioration and to prevent impeding movement of moving joints.

F. Seal perimeter and other joints watertight unless otherwise indicated.

G. Metal Protection:

1. Where aluminum is in contact with dissimilar metals, protect against galvanic action by painting contact surfaces with materials recommended by manufacturer for this purpose or by installing nonconductive spacers.
2. Where aluminum is in contact with concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.

H. Set continuous sill members and flashing in full sealant bed, as specified in Section 079200 "Joint Sealants," to produce weathertight installation.

I. Install joint filler behind sealant as recommended by sealant manufacturer.

J. Install components plumb and true in alignment with established lines and grades.

K. Install entrance doors to produce smooth operation and tight fit at contact points.

1. Exterior Doors: Install to produce weathertight enclosure and tight fit at weather stripping.

L. Install glazing as specified in Section 088000 "Glazing."

3.3 ERECTION TOLERANCES

A. Install aluminum-framed entrance and storefront systems to comply with the following maximum tolerances:

1. Plumb: 1/8 inch in 10 feet; 1/4 inch in 40 feet.
2. Level: 1/8 inch in 20 feet; 1/4 inch in 40 feet.
3. Alignment:

a. Where surfaces abut in line or are separated by reveal or protruding element up to 1/2 inch wide, limit offset from true alignment to 1/16 inch.
b. Where surfaces are separated by reveal or protruding element from 1/2 to 1 inch wide, limit offset from true alignment to 1/8 inch.
c. Where surfaces are separated by reveal or protruding element of 1 inch wide or more, limit offset from true alignment to 1/4 inch.

4. Location: Limit variation from plane to 1/8 inch in 12 feet; 1/2 inch over total length.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests.

B. Tests: Perform the following tests on representative areas of aluminum-framed entrance and storefront systems.

1. Water-Spray Test: Before installation of interior finishes has begun, areas designated by Architect to be tested in accordance with AAMA 501.2 and to not evidence water penetration.

    a. Perform a minimum of two tests in areas as directed by Architect.

2. Air Leakage: ASTM E783 at 1.5 times the rate specified for laboratory testing in "Performance Requirements" Article but not more than 0.09 cfm/sq. ft. at a static-air-pressure differential of 1.57 lbf/sq. ft.

    a. Perform a minimum of two tests in areas as directed by Architect.

3. Water Penetration: ASTM E1105 at a minimum uniform and cyclic static-air-pressure differential of 0.67 times the static-air-pressure differential specified for laboratory testing in "Performance Requirements" Article, but not less than 6.24 lbf/sq. ft., and to not evidence water penetration.

C. Inspection Agency: Engage a qualified inspector to perform inspections.

D. Inspections:

1. Egress Door Inspections: Inspect each aluminum-framed entrance door equipped with panic hardware, located in an exit enclosure, electrically controlled, and equipped with special locking arrangements, in accordance with NFPA 101, Ch. 7 "Means of Egress," Section "Means of Egress Components," Article "Inspection of Door Openings."

E. Aluminum-framed entrance and storefront systems will be considered defective if they do not pass tests and inspections.

F. Prepare test and inspection reports.

3.5 MAINTENANCE SERVICE

A. Entrance Door Hardware Maintenance:

1. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance, and removal and replacement of entrance door hardware.
2. Initial Maintenance Service: Beginning at Substantial Completion, provide six months' full maintenance by skilled employees of entrance door hardware Installer. Include quarterly preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper entrance door hardware operation at rated speed and capacity. Use parts and supplies that are the same as those used in the manufacture and installation of original equipment.

3.6 ENTRANCE DOOR HARDWARE SETS

A. See Specification Section 087100 “Door Hardware.”

END OF SECTION

SECTION 084413 - GLAZED ALUMINUM CURTAIN WALLS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Glazed aluminum curtain wall systems:

1. Conventionally glazed.
2. Decorative sealant applied horizontal aluminum mullions.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for installation of joint sealants installed with glazed aluminum curtain walls and for sealants to the extent not specified in this Section.
2. Section 088000 "Glazing" for curtain wall glazing.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of product.

a. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

C. Shop Drawings: For glazed aluminum curtain walls. Include plans, elevations, sections, full-size details, and attachments to other work.

1. Include details of provisions for assembly expansion and contraction and for draining moisture occurring within the assembly to the exterior.
2. Include full-size isometric details of each type of vertical-to-horizontal intersection of glazed aluminum curtain walls, showing the following:

a. Joinery, including concealed welds.
b. Anchorage.
c. Expansion provisions.
d. Glazing.
e. Flashing and drainage.

3. Show connection to and continuity with adjacent thermal, weather, air, and vapor barriers.

D. Samples for Initial Selection: For units with factory-applied color finishes.

E. Samples for Verification: For each type of exposed finish required, in manufacturer's standard sizes.

F. Fabrication Sample: Of each vertical-to-horizontal intersection of assemblies, made from 12-inch lengths of full-size components and showing details of the following:

1. Joinery, including concealed welds.
2. Anchorage.
3. Expansion provisions.
4. Glazing.
5. Flashing and drainage.

G. Delegated Design Submittal: For glazed aluminum curtain walls, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data:

1. For Installer and field testing agency.
2. For professional engineer's experience with providing delegated design engineering services of the kind indicated, including documentation that engineer is licensed in the state in which Project is located.

C. Energy Performance Certificates: For glazed aluminum curtain walls, accessories, and components from manufacturer.

1. Basis for Certification: NFRC-certified energy performance values for each glazed aluminum curtain wall.

D. Product Test Reports: For glazed aluminum curtain walls, for tests performed by manufacturer and witnessed by a qualified testing agency.

E. Field quality-control reports.

F. Sample Warranties: For special warranties.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For glazed aluminum curtain walls to include in maintenance manuals.

C. Maintenance Data for Structural Sealant: For structural-sealant-glazed curtain walls to include in maintenance manuals. Include ASTM C1401 recommendations for post-installation-phase quality-control program.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer and that employs a qualified glazing contractor for this Project who is certified under the North American Contractor Certification Program (NACC) for Architectural Glass & Metal (AGM) contractors and that employs glazing technicians certified under the Architectural Glass and Metal Technician (AGMT) certification program.

B. Testing Agency Qualifications: Qualified in accordance with ASTM E699 for testing indicated and accredited by IAS or ILAC Mutual Recognition Arrangement as complying with ISO/IEC 17025 and acceptable to Owner and Architect.

C. Product Options: Information on Drawings and in Specifications establishes requirements for aesthetic effects and performance characteristics of assemblies. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction.

1. Do not change intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If changes are proposed, submit comprehensive explanatory data to Architect for review.

D. Structural-Sealant Glazing: Comply with ASTM C1401 for design and installation of structural-sealant-glazed curtain wall assemblies.

1.7 WARRANTY

A. Special Assembly Warranty: Manufacturer and Installer agrees to repair or replace components of glazed aluminum curtain wall that do not comply with requirements or that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures including, but not limited to, excessive deflection.
b. Noise or vibration created by wind and thermal and structural movements.
c. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
d. Water penetration through fixed glazing and framing areas.
e. Failure of operating components.

2. Warranty Period: Ten years from date of Substantial Completion.

B. Special Finish Warranty, Factory-Applied Finishes: Standard form in which manufacturer agrees to repair finishes or replace aluminum that shows evidence of deterioration of organic finishes within specified warranty period.

1. Deterioration includes, but is not limited to, the following:

    a. Color fading more than 5 Delta E units when tested in accordance with ASTM D2244.
    b. Chalking in excess of a No. 8 rating when tested in accordance with ASTM D4214.
    c. Cracking, peeling, or chipping.

2. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design glazed aluminum curtain walls.

B. General Performance: Comply with performance requirements specified, as determined by testing of glazed aluminum curtain walls representing those indicated for this Project without failure due to defective manufacture, fabrication, installation, or other defects in construction.

1. Glazed aluminum curtain walls shall withstand movements of supporting structure, including, but not limited to, story drift, twist, column shortening, long-term creep, and deflection from uniformly distributed and concentrated live loads.
2. Failure also includes the following:

    a. Thermal stresses transferring to building structure.
    b. Glass breakage.
    c. Noise or vibration created by wind and thermal and structural movements.
    d. Loosening or weakening of fasteners, attachments, and other components.
    e. Failure of operating units.

C. Structural Loads:

1. Wind Loads: As indicated on Drawings.

D. Deflection of Framing Members Supporting Glass: At design wind load, as follows:

1. Deflection Normal to Wall Plane: Limited to 1/175 of length of span of the framing member for lengths of up to 13 feet 6 inches and to 1/240 of length of span of the framing member plus 1/4 inch for lengths of greater than 13 feet 6 inches.
2. Deflection Parallel to Glazing Plane: Limited to amount not exceeding that which reduces glazing bite to less than 75 percent of design dimension and that which reduces edge clearance between framing members and glazing or other fixed components to less than 1/8 inch.
3. Cantilever Deflection: Limited to 2/175 of the unsupported length.

E. Structural: Test in accordance with ASTM E330/E330M as follows:

1. When tested at positive and negative wind-load design pressures, assemblies do not evidence deflection exceeding specified limits.
2. When tested at 150 percent of positive and negative wind-load design pressures, assemblies, including anchorage, do not evidence material failures, structural distress, or permanent deformation of main framing members exceeding 0.2 percent of span.
3. Test Durations: As required by design wind velocity, but not less than 10 seconds.

F. Water Penetration under Static Pressure: Test in accordance with ASTM E331 as follows:

1. No evidence of water penetration through fixed glazing and framing areas when tested in accordance with a minimum static-air-pressure differential of 20 percent of positive wind-load design pressure, but not less than 15 lbf/sq. ft.

G. Water Penetration under Dynamic Pressure: Test in accordance with AAMA 501.1 as follows:

1. No evidence of water penetration through fixed glazing and framing areas when tested at dynamic pressure equal to 20 percent of positive wind-load design pressure, but not less than 15 lbf/sq. ft.

H. Seismic Performance: Glazed aluminum curtain walls shall withstand the effects of earthquake motions determined in accordance with ASCE/SEI 7.

1. Seismic Drift Causing Glass Fallout: Complying with criteria for passing based on building occupancy type when tested in accordance with AAMA 501.6 at design displacement and 1.5 times the design displacement.
2. Vertical Interstory Movement: Complying with criteria for passing based on building occupancy type when tested in accordance with AAMA 501.7 at design displacement and 1.5 times the design displacement.

I. Energy Performance: Certified and labelled by manufacturer for energy performance as follows:

1. Thermal Transmittance (U-factor):

a. Fixed Glazing and Framing Areas: U-factor for the system of not more than 0.34 Btu/sq. ft. x h x deg F as determined in accordance with NFRC 100.

2. Solar Heat Gain Coefficient (SHGC):

a. Fixed Glazing and Framing Areas: SHGC for the system of not more than 0.29 as determined in accordance with NFRC 200.

3. Air Leakage:

a. Fixed Glazing and Framing Areas: Air leakage for the system of not more than 0.06 cfm/sq. ft. at a static-air-pressure differential of 6.24 lbf/sq. ft. when tested in accordance with ASTM E283.

4. Condensation Resistance Factor (CRF):

a. Fixed Glazing and Framing Areas: CRF for the system of not less than 55 as determined in accordance with AAMA 1503.

J. Thermal Movements: Allow for thermal movements resulting from ambient and surface temperature changes:

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.
2. Thermal Cycling: No buckling; stress on glass; sealant failure; excess stress on framing, anchors, and fasteners; or reduction of performance when tested in accordance with AAMA 501.5.

a. High Exterior Ambient-Air Temperature: That which produces an exterior metal-surface temperature of 180 deg F.
b. Low Exterior Ambient-Air Temperature: 0 deg F.

2.2 SOURCE LIMITATIONS

A. Obtain all components of curtain-wall system, including framing and accessories, from single manufacturer.

2.3 GLAZED ALUMINUM CURTAIN WALL SYSTEMS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Kawneer Company, Inc., 1600UT System 2, or comparable product by one of the following:

1. Graham Architectural Products Corporation
2. Old Castle Building Envelope (OBE)
3. Tubelite Inc.

B. Framing Members: Manufacturer's extruded- or formed-aluminum framing members of thickness required and reinforced as required to support imposed loads.

1. Construction: Thermally broken.
2. Glazing System: Retained mechanically with gaskets on four sides.
3. Glazing Plane: Front.
4. Finish: High-performance organic finish.
5. System: Either stick or unitized system.
6. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.
7. Steel Reinforcement: As required by manufacturer.

C. Pressure Caps: Manufacturer's standard aluminum components that mechanically retain glazing.

1. Include snap-on aluminum trim that conceals fasteners.

D. Decorative Horizontal Mullions: Manufacturers aluminum components with profiles as shown on drawings applied with structural adhesive tape, finish to match curtainwall framing members.

E. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.

F. Entrance Door Systems: Comply with Section 084113 "Aluminum-Framed Entrances and Storefronts".

2.4 GLAZING

A. Glazing: Comply with Section 088000 "Glazing."

B. Glazing Gaskets: ASTM C509 or ASTM C864. Manufacturer's standard.

C. Glazing Sealants: As recommended by manufacturer.

2.5 MATERIALS

A. Sheet and Plate: ASTM B209.

B. Extruded Bars, Rods, Profiles, and Tubes: ASTM B221.

C. Structural Profiles: ASTM B308/B308M.

D. Steel Reinforcement:

1. Structural Shapes, Plates, and Bars: ASTM A36/A36M.
2. Cold-Rolled Sheet and Strip: ASTM A1008/A1008M.
3. Hot-Rolled Sheet and Strip: ASTM A1011/A1011M.

E. Steel Reinforcement Primer: Manufacturer's standard zinc-rich, corrosion-resistant primer complying with SSPC-PS Guide No. 12.00; applied immediately after surface preparation and pretreatment. Select surface preparation methods in accordance with recommendations in SSPC-SP COM, and prepare surfaces in accordance with applicable SSPC standard.

2.6 ACCESSORIES

A. Fasteners and Accessories: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.

1. Use self-locking devices where fasteners are subject to loosening or turning out from thermal and structural movements, wind loads, or vibration.
2. Reinforce members as required to receive fastener threads.
3. Use exposed fasteners with countersunk Phillips screw heads, fabricated from 300 series stainless steel.

B. Anchors: Three-way adjustable anchors with minimum adjustment of 1 inch that accommodate fabrication and installation tolerances in material and finish compatible with adjoining materials and recommended by manufacturer.

1. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts complying with ASTM A123/A123M or ASTM A153/A153M requirements.

C. Concealed Flashing: Dead-soft, 0.018-inch-thick stainless steel, ASTM A240/A240M of type recommended by manufacturer.

D. Decorative Horizontal Mullion Structural Glazing Tape:

1. 3M VHB Structural Glazing Tape G23F. `

2.7 FABRICATION

A. Form or extrude aluminum shapes before finishing.

B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.

C. Fabricate components that, when assembled, have the following characteristics:

1. Profiles that are sharp, straight, and free of defects or deformations.
2. Accurately fitted joints with ends coped or mitered.
3. Physical and thermal isolation of glazing from framing members.
4. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
5. Provisions for field replacement of glazing from exterior.
6. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.

D. Fabricate components to resist water penetration as follows:

1. Internal guttering system or other means to drain water passing joints, condensation occurring within framing members, and moisture migrating within glazed aluminum curtain wall to exterior.

E. Curtain-Wall Framing: Fabricate components for assembly using manufacturer's standard assembly method.

1. Prepare surfaces that are in contact with structural sealant in accordance with sealant manufacturer's written instructions, to ensure compatibility and adhesion. Preparation includes, but is not limited to, cleaning and priming surfaces.
2. Seal joints watertight unless otherwise indicated.
3. Install glazing to comply with requirements in Section 088000 "Glazing."
4. Install decorative horizontal mullions to inside and outside of glass with structural adhesive window tape in accordance with manufacturer’s instructions.

F. After fabrication, clearly mark components to identify their locations in Project in accordance with Shop Drawings.

2.8 ALUMINUM FINISHES

A. High-Performance Organic Finish, Two-Coat PVDF: Fluoropolymer finish complying with AAMA 2604 and containing not less than 70 percent PVDF resin by weight in color coat.

1. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
2. Color and Gloss: As selected by Architect from manufacturer's full range.

2.9 SOURCE QUALITY CONTROL

A. Structural Sealant: Perform quality-control procedures complying with ASTM C1401 recommendations, including, but not limited to, assembly material qualification procedures, sealant testing, and assembly fabrication reviews and checks.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Comply with manufacturer's written instructions.

B. Do not install damaged components.

C. Fit joints to produce hairline joints free of burrs and distortion.

D. Rigidly secure nonmovement joints.

E. Install anchors with separators and isolators to prevent metal corrosion and electrolytic deterioration and to prevent impeding movement of moving joints.

F. Where welding is required, weld components in concealed locations to minimize distortion or discoloration of finish. Protect glazing surfaces from welding.

G. Seal joints watertight unless otherwise indicated.

H. Metal Protection:

1. Where aluminum is in contact with dissimilar metals, protect against galvanic action by painting contact surfaces with primer, applying sealant or tape, or installing nonconductive spacers as recommended by manufacturer for this purpose.
2. Where aluminum is in contact with concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.

I. Install components to drain water passing joints, condensation occurring within framing members, and moisture migrating within glazed aluminum curtain wall to exterior.

J. Install components plumb and true in alignment with established lines and grades.

3.3 INSTALLATION OF GLAZING

A. Install glazing as specified in Section 088000 "Glazing."

3.4 ERECTION TOLERANCES

A. Install glazed aluminum curtain walls to comply with the following maximum tolerances:

1. Plumb: 1/8 inch in 10 feet; 1/4 inch in 40 feet.
2. Level: 1/8 inch in 20 feet; 1/4 inch in 40 feet.
3. Alignment:

    a. Where surfaces abut in line or are separated by reveal or protruding element up to 1/2 inch wide, limit offset from true alignment to 1/16 inch.
    b. Where surfaces are separated by reveal or protruding element from 1/2 to 1 inch wide, limit offset from true alignment to 1/8 inch.
    c. Where surfaces are separated by reveal or protruding element of 1 inch wide or more, limit offset from true alignment to 1/4 inch.

4. Location: Limit variation from plane to 1/8 inch in 12 feet; 1/2 inch over total length.

3.5 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Test Area: Perform tests on representative areas of glazed aluminum curtain walls.

C. Field Quality-Control Testing: Perform the following test on representative areas of glazed aluminum curtain walls.

1. Water-Spray Test: Before installation of interior finishes has begun, areas designated by Architect shall be tested in accordance with AAMA 501.2 and shall not evidence water penetration.

    a. Perform a minimum of two tests in areas as directed by Architect.

2. Air Leakage: ASTM E783 at 1.5 times the rate specified for laboratory testing in "Performance Requirements" Article but not more than 0.09 cfm/sq. ft. at a static-air-pressure differential of 1.57 lbf/sq. ft.

    a. Perform a minimum of two tests in areas as directed by Architect.

3. Water Penetration: ASTM E1105 at a minimum uniform and cyclic static-air-pressure differential of 0.67 times the static-air-pressure differential specified for laboratory testing in "Performance Requirements" Article, but not less than 6.24 lbf/sq. ft., and shall not evidence water penetration.

D. Glazed aluminum curtain walls will be considered defective if they do not pass tests and inspections.

E. Prepare test and inspection reports.

END OF SECTION

SECTION 087100 - DOOR HARDWARE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Mechanical door hardware for the following:

   a. Swinging doors.
   b. Sliding doors.

2. Cylinders for door hardware specified in all other Sections.
3. Electrified door hardware.

B. Related Requirements:

1. Section 081113 "Hollow Metal Doors and Frames" for astragals provided as part of labeled fire-rated assemblies and for door silencers provided as part of hollow-metal frames.
2. Section 083323 “Overhead Coiling Doors” for overhead coiling door hardware.
3. Section 087113 “Power Door Operators” for power door operators for swinging doors.
4. Section 233300 “Air Duct Accessories” for heating and air-conditioning duct access doors.

1.2 COORDINATION

A. Installation Templates: Distribute for doors, frames, and other work specified to be factory prepared. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing door hardware to comply with indicated requirements.

B. Security: Coordinate installation of door hardware, keying, and access control with Owner's security consultant.

C. Electrical System Roughing-In: Coordinate layout and installation of electrified door hardware with connections to power supplies and building safety and security systems.

D. Existing Openings: Where hardware components are scheduled for application to existing construction or where modifications to existing door hardware are required, field verify existing conditions and coordinate installation of door hardware to suit opening conditions and to provide proper door operation.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Conference participants shall include Installer's Architectural Hardware Consultant, Owner's security consultant and Owner Lock Shop Manager.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

C. Shop Drawings: For electrified door hardware.

1. Include diagrams for power, signal, and control wiring.

a. Utilize SOM Building Control Wiring Appendix Set for reference.

2. Include details of interface of electrified door hardware and building safety and security systems.

D. Samples: For each exposed product in each finish specified, in manufacturer's standard size.

1. Tag Samples with full product description to coordinate Samples with door hardware schedule.

E. Door Hardware Schedule: Prepared by or under the supervision of Installer's Architectural Hardware Consultant. Coordinate door hardware schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.

1. Submittal Sequence: Submit door hardware schedule concurrent with submissions of Product Data, Samples, and Shop Drawings. Coordinate submission of door hardware schedule with scheduling requirements of other work to facilitate the fabrication of other work that is critical in Project construction schedule.
2. Format: Use same scheduling sequence and format and use same door numbers as in door hardware schedule in the Contract Documents.
3. Content: Include the following information:

a. Identification number, location, hand, fire rating, size, and material of each door and frame.
b. Locations of each door hardware set, cross-referenced to Drawings on floor plans and to door and frame schedule.
c. Complete designations, including name and manufacturer, type, style, function, size, quantity, function, and finish of each door hardware product.
d. Description of electrified door hardware sequences of operation and interfaces with other building control systems.
e. Fastenings and other installation information.
f. Explanation of abbreviations, symbols, and designations contained in door hardware schedule.
g. Mounting locations for door hardware.
h. List of related door devices specified in other Sections for each door and frame.

F. Keying Schedules: Keying shall be performed by Owner.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Certificates: For each type of electrified door hardware.

1. Certify that door hardware for use on each type and size of labeled fire-rated doors complies with listed fire-rated door assemblies.

C. Product Test Reports: For compliance with accessibility requirements, for tests performed by manufacturer and witnessed by a qualified testing agency, for door hardware on doors located in accessible routes.

D. Sample Warranty: For special warranty.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For each type of door hardware to include in maintenance manuals.

C. Schedules: Final door hardware schedule.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: Supplier of products and an employer of workers trained and approved by product manufacturers and of an Architectural Hardware Consultant who is available during the course of the Work to consult Contractor, Architect, and Owner about door hardware and keying.

1. Warehousing Facilities: In Project's vicinity.
2. Scheduling Responsibility: Preparation of door hardware and keying schedule.
3. Engineering Responsibility: Preparation of data for electrified door hardware, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Inventory door hardware on receipt and provide secure lock-up for door hardware delivered to Project site.

B. Tag each item or package separately with identification coordinated with the final door hardware schedule, and include installation instructions, templates, and necessary fasteners with each item or package.

C. Deliver keys and permanent cores to Owner by registered mail or overnight package service.

1. State of Maine, BGS
Lock Shop Attn: Gary
Tibbetts
15 Columbia St.
Augusta, ME 04330

1.9 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures including excessive deflection, cracking, or breakage.
b. Faulty operation of doors and door hardware.
c. Deterioration of metals, metal finishes, and other materials beyond normal weathering and use.

2. Warranty Period: Three years from date of Substantial Completion unless otherwise indicated below:

a. Exit Devices: Two years from date of Substantial Completion.
b. Manual Closers: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

A. Acceptable Manufacturers: Only hardware manufactured by one of the companies indicated below shall be accepted for use in the Project, and acceptance is limited only to the category of hardware for which the manufacturer is specified or listed as an acceptable equal.

1. Hinges: McKinney, Stanley
2. Electrified Hinges, Power Transfers: Marray, SDC (Security Door Controls), Sargent, Von Duprin, Keedex, Securitron)
3. Mortise Locksets: Sargent, Schlage
4. Exit Devices: Sargent, Von Duprin
5. Flush Bolts: Rockwood, Sargent
6. Door Closers: LCN, Sargent
7. Power Door Operators: Horton, no substitutes
8. Door Stops: Glynn Johnson, Ives, Rockwood
9. Push/Pulls: Rockwood, Burns, Ives
10. Protective Plates: Rockwood, Burns, Ives
11. Thresholds, Weather-stripping, Rain Drips: NGP, Pemko, Reese
12. Silencers: Rockwood
13. Power Supplies: Altronix unless otherwise specified.
14. Magnetic Locks: Securitron, Schlage

15. Keys and Cores: KABA 7-Pin SFIC, no substitutions
16. Specialty Key Switches: Medeco M3, no substitutions
17. Key Cabinet: Telkee
18. Fire Department Lock Box: Knox Co.

2.2 PERFORMANCE REQUIREMENTS

A. Fire-Rated Door Assemblies: Where fire-rated doors are indicated, provide door hardware complying with NFPA 80 that is listed and labeled by a qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure in accordance with NFPA 252 or UL 10C.

B. Electrified Door Hardware: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application. Electrically Operated and/or Controlled Hardware:

1. All Power Supplies shall be centrally located with the associated Access Control Panel and not individually at each opening.
2. All Power Supplies are to be mains powered from generator circuits when available.

C. Means of Egress Doors: Latches do not require more than 15 lbf (67 N) to release the latch. Locks do not require use of a key, tool, or special knowledge for operation.

D. Accessibility Requirements: For door hardware on doors in an accessible route, comply with the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.

1. Provide operating devices that do not require tight grasping, pinching, or twisting of the wrist and that operate with a force of not more than 5 lbf (22.2 N).
2. Comply with the following maximum opening-force requirements:

    a. Interior, Non-Fire-Rated Hinged Doors: 5 lbf (22.2 N) applied perpendicular to door.
    b. Sliding or Folding Doors: 5 lbf (22.2 N) applied parallel to door at latch.
    c. Fire Doors: Minimum opening force allowable by authorities having jurisdiction.

3. Bevel raised thresholds with a slope of not more than 1:2. Provide thresholds not more than 1/2 inch (13 mm) high.
4. Adjust door closer sweep periods so that, from an open position of 90 degrees, the door will take at least 5 seconds to move to a position of 12 degrees from the latch.
5. Adjust spring hinges so that, from an open position of 70 degrees, the door will take at least 1.5 seconds to move to the closed position.

2.3 KEYS AND CORES

A. All Key Blanks and Cores shall be drop shipped:

1. State of Maine, BGS Lock Shop Attn: Gary Tibbetts
   15 Columbia St.
   Augusta, ME 04330
2. Products:

a. Primary Lock Cores

1) Shall be 7-Pin Small Format Interchangeable Core (SFIC)
2) Cores: KABA 3850-25-1007 PK1
3) Keys: KABA 3800-00-0003-PK1-C95W21

b. Specialty Switch Locks

1) Medeco M3 “1 switch, Maintained 2 Key pull” sub-assembled.
- 652150T 012 (S)
- CP-270511 Lead Wires - Required Accessory

2.4 FIRE DEPARTMENT LOCK BOX

A. Fire Department Lock Box: Salvage and reuse existing Knox box, provide flush mount kit, with Tamper switches wired to the Access Control System.

B. Secondary Lock shall be keyed to Knox system ID KX-48-007-08-01.

2.5 HINGES

A. Hinges: BHMA A156.1. Provide template-produced hinges for hinges installed on hollow-metal doors and hollow-metal frames.

1. All exterior and interior with Access Control System shall be NRP (Non-Removable Pin) design.

B. Antifriction-Bearing Hinges:

1. Mounting: Full mortise (butts).
2. Bearing Material: Manufacturer's standard antifriction bearing.
3. Grade 1 (heavy weight).
4. Base and Pin Metal:

a. Exterior Hinges: Stainless steel with stainless steel pin.
b. Interior Hinges: Steel with steel pin.
c. Hinges for Fire-Rated Assemblies: Steel with steel pin.

5. Pins: Nonrising loose unless otherwise indicated.

a. Outswinging Exterior Doors: Nonremovable.
b. Outswinging Corridor Doors with Locks: Nonremovable.

6. Tips: Flat button.
7. Corners: Square.

2.6 ELECTRIFIED HINGES, POWER TRANSFER

A. Products:

1. Von Duprin EPT2
2. Securitron EPT, CEPT
3. Marray TEF2+4
4. SDC PTH2-4
5. Keedex K-DL-38A

B. Electrified Antifriction-Bearing Hinges: Full-mortise mounting.

1. Bearing Material: Manufacturer's standard antifriction bearing.
2. Grade 1 (heavy weight).
3. Base and Pin Metal:

    a. Exterior Hinges: Stainless steel with stainless steel pin.
    b. Interior Hinges: Steel with steel pin.
    c. Hinges for Fire-Rated Assemblies: Steel with steel pin.

4. Pins: Nonrising loose unless otherwise indicated.

    a. Outswinging Exterior Doors: Nonremovable.
    b. Outswinging Corridor Doors with Locks: Nonremovable.

5. Tips: Flat button.
6. Corners: Square.
7. Electric Feature: Concealed electric through wires.

2.7 DOOR CLOSERS

A. Approved Products:

1.	Exterior:	LCN 4040XP-CUSH	Sargent 281-CPS
2.	Interior:	LCN 4040XP 1461	Sargent 281-0
		LCN 1461	Sargent 281-P9

2.8 POWER DOOR OPERATOR (LOW ENERGY)

A. General: See Specification Section 087113 “Power Door Operators” for additional information.

1. Shall be integrated with Access Control System on access controlled (Card Reader) openings
2. All actuator buttons shall be hardwired, no wireless accepted.

B. Approved Product:

1. Exterior Horton 4100 series
2. Interior Horton 7100 series

2.9 EXIT DEVICES

A. Approved Products: Sargent

1. Functions:

    a. 70-56-8806-ETL
    b. 70-56-8506-ETL
    c. 70-12-56-8806-ETL
    d. 70-8806-ETL
    e. 70-12-8806-ETL
    f. 8815-ETL
    g. 12-8815-ETL

B. Panic Exit Devices: Listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for panic protection, based on testing in accordance with UL 305.

C. Fire Exit Devices: Devices complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire and panic protection, based on testing in accordance with UL 305 and NFPA 252.

D. Rim Exit Devices: Grade 1.

1. Type 1, rim.
2. Actuating Bar: Narrow-stile push pad.
3. Material: Stainless steel.
4. Electrified Features:

    a. Electric locking and unlocking.
    b. Fail-secure electric latch retraction (dogging) that engages latch when fire-alarm system is activated.

E. Mortise Exit Devices: Grade 1.

1. Type 3.
2. Actuating Bar: Narrow-stile push pad.
3. Material: Stainless steel.
4. Electrified Features:

    a. Electric locking and unlocking.
    b. Fail-secure electric latch retraction (dogging) that engages latch when fire-alarm system is activated.

F. Surface Vertical-Rod Exit Devices: Grade 1.

1. Type 2.
2. Actuating Bar: Cross bar.
3. Material: Stainless steel.
4. Configuration: Top and bottom rods.
5. Electrified Features:

    a. Electric locking and unlocking.

G. Extruded-Aluminum Removable Mullions: With malleable-iron top and bottom retainers, and prepared for strikes as follows:

1. Strikes: Two standard recessed strikes.

H. Tube-Steel Removable Mullions: With malleable-iron top and bottom retainers, and prepared for strikes as follows:

1. Strikes: Two standard recessed strikes.

I. Fire-Exit Removable Mullions: Provide removable mullions for use with fire-exit devices complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire and panic protection, based on testing in accordance with UL 305 and NFPA 252. Use mullions only with exit devices for which they have been tested.

J. Exit Device Outside Trim: Lever; material and finish to match locksets unless otherwise indicated.

1. Match design for lock trim unless otherwise indicated.

K. Through-Bolt Fasteners: For exit devices and trim on non-fire-rated wood doors or fire-rated wood doors.

2.10 MORTISE LEVER SETS

A. Products: Sargent 8200 Series

1. Functions:

a. Stockroom – 70-8204-LNL ANSI F07
b. Entry / Office – 70- 8205-LNL ANSI F04
c. Break or Conference – 70-8257-LNL
d. Privacy – 70-V20- 8267-LNL ANSI F26
e. Elec Fail-Secure – 70-8271-LNL
f. Elec. Fail-Safe – 70-8270-LNL
g. Elec. Asylum Fail-Safe – 70-8272-LNL

B. Implementation:

1. The Shelter-In-Place “SIP Protocol” adopted by Owner requires that all rooms be lockable from the inside where possible. To this end Owner provides lock hardware on nearly any door that can be fitted with one without causing day to day inconvenience to employees.

a. Individual Offices shall be fitted with Functions b.
b. Rooms utilized by more than two people or common areas; Conference, Break, Copier rooms shall be fitted with Function c.
c. Restrooms, Showers, Locker, Nursing type rooms shall be fitted with Function d.

2.11 MANUAL FLUSH BOLTS

A. Manual Flush Bolts: BHMA A156.16; minimum 3/4-inch throw; designed for mortising into door edge.

1. Utilize “Combination Flush Bolts” such as Rockwood 2845 and 2945.

2.12 ELECTROMECHANICAL LOCKS

A. NOT ALLOWED

2.13 ELECTRIC STRIKES

A. Products:

1. For Rim Exit Devices: 9400, 9500, 9600 by HES
2. For Mortised / Cylindrical Devices: 1006, 1600 by HES

2.14 OPERATING TRIM

A. Operating Trim: ANSI/BHMA A156.6; aluminum unless otherwise indicated.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Allegion plc
b. Hager Companies
c. Hiawatha, Inc; a division of the Activar Construction Products Group
d. INOX; Unison Hardware, Inc
e. Rockwood Manufacturing Company; ASSA ABLOY Accessories and Door Controls Group, Inc.; ASSA ABLOY

B. Flat Push Plates: With square corners and beveled edges; secured with exposed screws.

1. Thickness: 0.050 inch.
2. Size: 4 inches wide by 16 inches high.

C. Push-Pull Plates: With square corners, beveled edges, and raised integral lip; secured with exposed screws.

1. Thickness: 1/8 inch.
2. Size: 3-1/2 inches wide by 15-3/4 inches high.

D. Straight Door Pulls:

1. Type: 3/4-inch constant-diameter pull.
2. Mounting: Surface applied with concealed fasteners.
3. Minimum Clearance: 1-1/2 inches from face of door.
4. Overall Length: 9 inches.

E. Straight Pull-Plate Door Pulls: Pull fixed to 0.050-inch-thick plate, 4 inches wide by 16 inches high with square corners and beveled edges.

1. Type: 3/4-inch constant-diameter pull.
2. Mounting: Surface applied with concealed fasteners.

3. Minimum Pull Clearance: 1-1/2 inches from face of door.
4. Overall Pull Length: 9 inches.

2.15 ACCESSORIES FOR PAIRS OF DOORS

A. Coordinators: BHMA A156.3; consisting of active-leaf, hold-open lever and inactive-leaf release trigger; fabricated from steel with nylon-coated strike plates; with built-in, adjustable safety release; and with internal override.

B. Carry-Open Bars: BHMA A156.3; prevent the inactive leaf from opening before the active leaf; provide polished brass or bronze carry-open bars with strike plate for inactive leaves of pairs of doors unless automatic or self-latching bolts are used.

C. Astragals: BHMA A156.22.

2.16 WEATHER STRIPPING

A. Sweeps shall be of a brush design.

2.17 MECHANICAL STOPS AND HOLDERS

A. Wall- and Floor-Mounted Stops: BHMA A156.16.

2.18 DOOR GASKETING

A. Door Gasketing: BHMA A156.22; with resilient or flexible seal strips that are easily replaceable and readily available from stocks maintained by manufacturer.

B. Maximum Air Leakage: When tested in accordance with ASTM E283/E283M with tested pressure differential of 0.3 inch wg, as follows:

1. Smoke-Rated Gasketing: 0.3 cfm/sq. ft. of door opening.
2. Gasketing on Single Doors: 0.3 cfm/sq. ft. of door opening.
3. Gasketing on Double Doors: 0.50 cfm per ft. of door opening.

C. Adhesive-backed, spring-metal, and rigid and adjustable housed perimeter gasketing is available for smoke-labeled, fire-labeled, and sound-rated doors.

D. Rigid, Housed, Perimeter Gasketing: Sponge neoprene gasket material held in place by housing; fastened to frame stop with screws.

1. Housing Material: Stainless steel.

E. Meeting Astragals for Meeting Stiles: Neoprene bulb gasket material held in place by housing; mounted with screws.

1. Housing Material: Aluminum.
2. Mounting: Surface mounted on face of each door.

F. Door Sweeps: Neoprene gasket material held in place by flat housing or flange; surface mounted to face of door with screws.

1. Housing or Flange Material: Aluminum.

2.19 THRESHOLDS

A. Thresholds: BHMA A156.21; fabricated to full width of opening indicated.

B. Compressing-Top Thresholds: Metal member with compressible vinyl seal on top of threshold that seals against bottom of door; and base metal of aluminum.

C. Saddle Thresholds:

1. Type: Thermal break and fluted top.
2. Base Metal: Aluminum.

D. Half-Saddle Thresholds: Fluted-top metal member; and base metal of aluminum.

E. Plate Thresholds: Solid metal plate.

1. Top Surface: Fluted.
2. Base Metal: Aluminum.

2.20 METAL PROTECTIVE TRIM UNITS

A. Metal Protective Trim Units: ANSI/BHMA A156.6; fabricated from 0.050-inch-thick stainless steel; with manufacturer's standard machine or self-tapping screw fasteners.

B. Armor Plates: 36 inches high by door width with allowance for frame stops.

C. Kick Plates: 10 inches high by door width with allowance for frame stops.

2.21 ANTI-LIGATURE DOOR HARDWARE

A. Anti-Ligature Door Hardware: ANSI/BHMA A156.34.

2.22 AUXILIARY DOOR HARDWARE

A. Auxiliary Door Hardware: ANSI/BHMA A156.16.

B. Silencers for Metal Door Frames: Grade 1; neoprene or rubber; minimum diameter 1/2 inch; fabricated for drilled-in application to frame.

2.23 AUXILIARY ELECTRIFIED DOOR HARDWARE

A. Auxiliary Electrified Door Hardware: ANSI/BHMA A156.35.

B. Electrified Power Transfer Hinges: ANSI/BHMA A156.1.

C. Electromagnetic Locks: ANSI/BHMA A156.23.

D. Boxed Power Supplies: Modular unit in NEMA ICS 6, Type 4 enclosure; filtered and regulated; voltage rating and type matching requirements of door hardware served; listed and labeled for use with fire-alarm systems.

E. Monitor Strikes: Dustbox monitor for installation under standard strike.

F. Door Position Switches: Magnetically operated reed switch designed for concealed mounting.

G. Door and Frame Transfer Devices: Steel housing for mortise in hinge stile of door, with flexible tube for wiring bundle; accommodating doors that swing open to 120 degrees.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire-rated door assembly construction, wall and floor construction, and other conditions affecting performance of the work.

B. Examine roughing-in for electrical power systems to verify actual locations of wiring connections before electrified door hardware installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Steel Doors and Frames: For surface-applied door hardware, drill and tap doors and frames in accordance with ANSI/SDI A250.6.

B. Wood Doors: Comply with door and hardware manufacturers' written instructions.

3.3 INSTALLATION

A. Mounting Heights: Mount door hardware units at heights to comply with the following unless otherwise indicated or required to comply with governing regulations.

1. Standard Steel Doors and Frames: ANSI/SDI A250.8.
2. Wood Doors: DHI's "Recommended Locations for Architectural Hardware for Wood Flush Doors."

B. Install each door hardware item to comply with manufacturer's written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage, and reinstallation of surface protective trim units with finishing work. Do not install surface-mounted items until finishes have been completed on substrates involved.

1. Set units level, plumb, and true to line and location. Adjust and reinforce attachment substrates as necessary for proper installation and operation.
2. Drill and countersink units that are not factory prepared for anchorage fasteners. Space fasteners and anchors according to industry standards.

C. Hinges: Install types and in quantities indicated in door hardware schedule, but not fewer than the number recommended by manufacturer for application indicated or one hinge for every 30 inches of door height, whichever is more stringent, unless other equivalent means of support for door, such as spring hinges or pivots, are provided.

D. Lock Cylinders: Install construction cores to secure building and areas during construction period.

1. Furnish permanent cores to Owner for installation.

E. Stops: Provide wall stops for doors unless floor or other type stops are indicated in door hardware schedule. Do not mount floor stops where they will impede traffic.

F. Perimeter Gasketing: Apply to head and jamb, forming seal between door and frame.

1. Do not notch perimeter gasketing to install other surface-applied hardware.

G. Meeting Stile Gasketing: Fasten to meeting stiles, forming seal when doors are closed.

H. Door Bottoms: Apply to bottom of door, forming seal with threshold when door is closed.

3.4 ADJUSTING

A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.

1. Door Closers: Adjust sweep period to comply with accessibility requirements and requirements of authorities having jurisdiction.
2. Spring Hinges: Adjust to achieve positive latching when door is allowed to close freely from an open position of 70 degrees and so that closing time complies with accessibility requirements of authorities having jurisdiction.
3. Electric Strikes: Adjust horizontal and vertical alignment of keeper to properly engage lock bolt.

3.5 CLEANING AND PROTECTION

A. Clean adjacent surfaces soiled by door hardware installation.

B. Clean operating items as necessary to restore proper function and finish.

C. Provide final protection and maintain conditions that ensure that door hardware is without damage or deterioration at time of Substantial Completion.

3.6 MAINTENANCE SERVICE

A. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions for Owner's continued adjustment, maintenance, and removal and replacement of door hardware.

3.7 DOOR HARDWARE SCHEDULE

Door Hardware Set No. EH-1 (200A)

2	Continuous Hinges	
1	Exit Device	Rim: Electric Latch Retraction, Function A Entry
1	Exit Device	Rim: Function A Entry
1	Electric Power Transfer Hinge	
2	Lever Exit Trim	
2	Closers	
2	Cylinders	
1	Power Door Operator	See Specification Section 087113
1	Removeable Hardware Mullion	
2	Door Position Switches	
2	Sets Weatherstripping	Jamb/Head
2	Door Bottom Sweep	
1	Threshold	
2	Door Stops	

Door Hardware Set No. EH-2 (200)

2	Continuous Hinges	
2	Door Pulls	
2	Push Plates	
2	Closers	
1	Power Door Operator	See Specification Section 087113
2	Sets Weatherstripping	Jamb/Head
2	Door Bottom Sweeps	
1	Threshold	
2	Door Stops	

Door Hardware Set No. EH-3 (100A, 109A)

1	Continuous Hinge	
1	Exit Device	Rim: Function A Entry
1	Electric Strike	Card reader operated
1	Lever Exit Trim	
1	Cylinder	
1	Power Door Operator (Door 100A only)	See Specification Section 087113.
1	Door Position Sensor	
1	Set Weatherstripping	Jamb/Head
1	Door Bottom Sweep	
1	Threshold	
1	Door Stop	

Door Hardware Set No. EH-4 (144A, 135)

1	Continuous Hinge	
1	Exit Device	Rim Function D
1	Lever Exit Trim	
1	Electric Strike	Card reader operated
1	Closer	
1	Cylinder	
1	Set Weatherstripping	Jamb/Head
1	Door Bottom Sweep	
1	Threshold	
1	Door Stop	

Door Hardware Set No. EH-5 (107, S3-1A, S2-1)

3	Hinges	
1	Exit Device	Rim Function D
1	Lever Exit Trim	
1	Electric Strike	Card reader operated
1	Cylinder	
1	Closer	
1	Door Position Switch	
1	Set Weatherstripping	Jamb/Head
1	Door Bottom Sweep	
1	Threshold	
1	Door Stop	

Door Hardware Set No. EH-6 (109)

1	Continuous Hinge	
1	Exit Device	Rim
1	Electric Strike	Card reader operated
1	Power Door Operator	See Specification Section 087113
1	Lever Exit Trim	
1	Cylinder	
1	Closer	
1	Door Position Switch	
1	Set Weatherstripping	Jamb/Head
1	Door Bottom Sweep	
1	Threshold	
1	Door Stop	

Door Hardware Set No. EH-7 (339A)

3	Hinges	
1	Mortise Lockset	Electrified Latch Retraction
1	Electric Power Transfer Hinge	
1	Door Position Switch	
1	Closer	
1	Cylinder	
1	Set Weatherstripping	Jamb/Head
1	Door Bottom Sweep	
1	Threshold	

Door Hardware Set No. HW-1 (Typical Office)

3	Hinges	
1	Mortise Lockset	Function B
1	Cylinder	
1	Door Stop	

Door Hardware Set No. HW-2 (Typical Conference, Focus, Huddle)

3	Hinges	
1	Mortise Lockset	Institutional Privacy
1	Cylinder	
1	Door Stop	

Door Hardware Set No. HW-3 (Typical Storage, Utility)

3	Hinges	
1	Mortise Lockset	Storeroom
1	Closer	
1	Cylinder	
1	Door Stop	

Door Hardware Set No. HW-4 (Typical Toilet)

3	Hinges	
1	Lockset	Privacy
1	Closer	
1	Cylinder	
1	Door Stop	

Door Hardware Set No. HW-5 (Interior Stair) S3-0, 144

3	Hinges	
1	Fire Exit Device	Rim Function G Passage
1	Lever Exit Trim	
1	Closer	
1	Door Stop	

Door Hardware Set No. HW-6 (Interior Stair w/ Card Reader) S1-1, S1-3, S1-4, S2-2, S2-3, S3-3

3	Hinges	
1	Fire Exit Device	Rim
1	Lever Exit Trim	
1	Closer	
1	Electric Strike	Card reader operated
1	Cylinder	
1	Door Position Switch	
1	Door Stop	

Door Hardware Set No. HW-6A (Interior Stair) S3-1, S3-2

3	Hinges	
1	Fire Exit Device	Rim Function G Passage
1	Lever Exit Trim	
1	Closer	
1	Electromagnetic Lock	Fire alarm interconnected
1	Door Position Switch	
1	Door Stop	

Door Hardware Set No. HW-6B (Interior Stair-Not an Exit) S1-2

3	Hinges	
1	Mortise Lockset	Electrified Latch Function F
1	Electric Power Transfer Hinge	
1	Closer	
1	Door Position Switch	
1	Door Stop	

Door Hardware Set No. HW-7 (Interior Corridor w/ Card Reader) 100B, 136, 108A, 201, 201B, 209, 209A, 209B, 209C, 338, 346,

3	Hinges	
1	Exit Device	Rim
1	Lever Exit Trim	
1	Closer	
1	Electric Strike	Card reader operated
1	Power Door Operator (Door 100B)	See Specification Section 087113
1	Cylinder	
1	Door Position Switch	
1	Door Stop	

Door Hardware Set No. HW-8 (Interior Corridor w/ Card Reader) 339

6	Hinges	
2	Exit Devices	Rim
1	Lever Exit Trim	Active leaf with electric strike
2	Closer	
1	Electric Strike	Card reader operated
1	Removeable Hardware Mullion	Electrical Disconnect
1	Cylinder	
2	Door Position Switches	
2	Door Stops	

Door Hardware Set No. HW-9 (Interior Room w/ Card Reader) 100, 101, 101B, 106, 112, 113, 113A, 120, 134, 120A, 124, 140, 141, 142, 143, 205, 206, 220, 300, 318 332,

3	Hinges	
1	Mortise Lockset	Office
1	Closer	
1	Electric Strike	Card reader operated
1	Cylinder	
1	Door Position Switch	
1	Door Stop	

Door Hardware Set No. HW-10 (001, 146)

6	Hinges	
1	Mortise Lockset	Storage
1	Set Automatic Flush Bolts	Inactive Leaf
2	Closers	
2	Cylinders	
2	Door Position Switches	
2	Door Stops	

Door Hardware Set No. HW-11 Special Corrections (110, 112A)

1	Continuous Hinge	Anti-Ligature, Electric Power Transfer
1	Mortise Lockset	Electrified Latch Function H, Fail Secure Asylum, Anti-Ligature
1	Concealed Closer	Anti-Ligature
2	Cylinders	
1	Door Position Switch	
1	Door Stop	Correctional
1	Weather Seals	
1	Door Sweep	

Door Hardware Set No. HW-11A Restroom (110A)

1	Continuous Hinge	Anti-Ligature
1	Mortise Lockset	Passage, Anti-Ligature

Door Hardware Set No. HW-12 (135A)

3	Hinges	
1	Mortise Lockset	
1	Electric Strike	Card reader operated
1	Closer	
1	Cylinder	
1	Door Position Switch	
1	Door Stop	

Door Hardware Set No. HW-13 (106)

3	Hinges	
1	Fire Exit Device	
1	Electric Strike	Card reader operated
1	Closer	
1	Cylinder	
1	Door Position Switch	
1	Door Stop	

Door Hardware Set No. HW-14 (106A)

3	Hinges	
1	Mortise Lockset	
1	Closer	
1	Cylinder	
1	Door Position Switch	
1	Door Stop	

END OF SECTION

SECTION 087113 - POWER DOOR OPERATORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Power door operators for swinging doors.

B. Related Requirements:

1. Section 281500 “Access Control Hardware Devices” for integration and servicing of equipment provided as part of security system.

1.2 DEFINITIONS

A. AAADM: American Association of Automatic Door Manufacturers.

B. Activation Device: A control that, when actuated, sends an electrical signal to the door operator to open the door.

C. Double-Egress (Doors): A pair of doors that simultaneously swing, with the two doors moving in opposite directions with no mullion between them.

D. Double-Swing (Doors): A pair of doors that swing, with the two doors moving in opposite directions with a mullion between them; each door functioning as a single-swing door.

E. Safety Device: A control that, to avoid injury, prevents a door from opening or closing.

F. For automatic door terminology, see BHMA A156.10 for definitions of terms.

1.3 COORDINATION

A. Coordinate sizes and locations of recesses in concrete floors for recessed control mats that control power door operators. Concrete, reinforcement, and formwork requirements are specified elsewhere.

B. Templates: Distribute for doors, frames, and other work specified to be factory prepared and reinforced for installing power door operators.

C. Coordinate hardware for doors with operators to ensure proper size, thickness, hand, function, and finish.

D. Electrical System Roughing-in: Coordinate layout and installation of power door operators with connections to the following:

1. Power supplies.
2. Access-control system.
3. Remote activation devices.
4. Remote monitoring systems.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for power door operators.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

C. Shop Drawings: For power door operators.

1. Include plans, elevations, sections, hardware mounting heights, and attachment details.
2. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Indicate locations of activation and safety devices.
4. Include diagrams for power, signal, and control wiring.
5. Include plans, elevations, sections, and attachment details for guide rails.

D. Samples: For each exposed product and for each color and texture specified, manufacturer's standard size.

1.6 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

C. Field quality-control reports.

D. Sample Warranties: For manufacturer's special warranties.

1.7 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For power door operators, safety devices, and control systems, to include in maintenance manuals.

1.8 QUALITY ASSURANCE

A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer for installation and maintenance of units required for this Project and who employs a Certified Inspector.

1. Maintenance Proximity: Not more than two hours' normal travel time from Installer's place of business to Project site.

B. Certified Inspector Qualifications: Certified by AAADM.

1.9 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of power door operators that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Faulty or sporadic operation of power door operator, including controls.
b. Deterioration of metals, metal finishes, and other materials beyond normal weathering or use.

2. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 POWER DOOR OPERATORS, GENERAL

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. ASSA ABLOY Entrance Systems; ASSA ABLOY
2. Ditec; Entrematic; ASSA ABLOY
3. Door Motion Technologies, Inc.
4. dormakaba USA Inc.
5. Horton Automatics; Overhead Door Corporation
6. LCN; Allegion plc
7. SARGENT Manufacturing Company; ASS ABLOY
8. STANLEY Access Technologies LLC; STANLEY Security Solutions, Inc.

B. Source Limitations: Obtain power door operators, including activation and safety devices, from single source from single manufacturer.

C. General: Provide operators of size recommended by manufacturer for door size, weight, and movement; for condition of exposure; and for long-term, maintenance-free operation under

normal traffic load for occupancy type indicated; and in accordance with UL 325. Coordinate operator mechanisms with door operation, hinges, and activation and safety devices.

1. Wind Load: Provide door operators on exterior doors that will open and close doors and maintain them in fully closed position when subjected to wind load indicated on Drawings.

D. Electromechanical Operating System: Self-contained unit powered by permanent-magnet dc motor; with closing speed controlled mechanically by gear train and dynamically by braking action of electric motor, connections for power and activation- and safety-device wiring, and manual operation, including spring closing when power is off.

E. Cover for Surface-Mounted Operators: Fabricated from 0.125-inch-thick, extruded or formed aluminum; manufacturer's standard width; with enclosed end caps, provision for maintenance access, and fasteners concealed when door is in closed position.

F. Brackets and Reinforcements: Fabricated from aluminum with nonstaining, nonferrous shims for aligning system components.

G. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 POWER DOOR OPERATORS FOR SWINGING DOORS

A. Standard: BHMA A156.10.

B. Performance Requirements:

1. Opening Force:

a. Power-Operated Doors: Not more than 50 lbf required to manually set door in motion if power fails; not more than 15 lbf required to open door to minimum required width.
b. Power-Operated Swinging Doors: Not more than 30 lbf required to manually open door if power fails.

2. Entrapment-Prevention Force: Not more than 40 lbf required to prevent stopped door in the last 10 degrees of opening from moving in the direction of opening; not more than 30 lbf required to prevent stopped door from moving in direction of closing.

C. Configuration: Operator to control single swinging door.

1. Traffic Pattern: Two way.
2. Operator Mounting: Surface.

D. Operation: Power opening and spring closing. Provide time delay for door to remain open before initiating closing cycle as required by BHMA A156.10.

E. Operating System: Electromechanical.

F. Microprocessor Control Unit: Solid-state controller.

G. Features:

1. Adjustable opening and closing speed.
2. Adjustable opening and closing force.
3. Adjustable backcheck.
4. Adjustable hold-open time from zero to 30 seconds.
5. Adjustable time delay.
6. Adjustable acceleration.
7. Adjustable limit switch.
8. Obstruction recycle.
9. Power door re-open if stopped while closing.
10. On-off/hold-open switch to control electric power to operator; key operated.

H. Controls: Activation and safety devices in accordance with BHMA standards.

1. Activation Device, Switch: Push-plate switch on each side of door to activate door operator.
2. Safety Device, Presence Sensor: Mounted on door header to detect pedestrians in presence zone and to prevent door from closing.

I. Exposed Finish: Class I, clear anodic finish.

2.3 MATERIALS

A. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.

1. Extrusions: ASTM B221.
2. Sheet: ASTM B209.

B. Fasteners and Accessories: Corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.

2.4 CONTROLS

A. General: Provide controls, including activation and safety devices, in accordance with BHMA standards; for condition of exposure; and for long-term, maintenance-free operation under normal traffic load for occupancy type indicated. Coordinate activation and safety devices with door operation and door operator mechanisms.

B. Presence Sensors: Self-contained, active-infrared scanner units; adjustable to provide detection field sizes and functions required by BHMA A156.10. Sensors shall remain active at all times.

C. Push-Plate Switch: Momentary-contact door control switch with flat push-plate actuator with contrasting-colored, engraved message.

1. Configuration:

a. Rectangular Push Plate: 2-by-4-inch junction box.

1) Mounting: Surface mounted on wall.

2. Push-Plate Material: Stainless steel as selected by Architect from manufacturer's full range.
3. Message: International symbol of accessibility and "Push to Open."

D. Electrical Interlocks: Unless units are equipped with self-protecting devices or circuits, provide electrical interlocks to prevent activation of operator when door is locked, latched, or bolted.

2.5 FABRICATION

A. Factory fabricate power door operators to comply with indicated standards.

B. Form aluminum shapes before finishing.

C. Fabricate exterior components to drain condensation and water-passing joints within operator enclosure to the exterior.

D. Use concealed fasteners to greatest extent possible. Where exposed fasteners are required, use countersunk Phillips flat-head machine screws, finished to match operator.

2.6 GENERAL FINISH REQUIREMENTS

A. Protect mechanical finishes on exposed surfaces from damage by applying strippable, temporary, protective covering before shipping.

B. Apply organic and anodic finishes to formed metal after fabrication unless otherwise indicated.

C. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within range of approved Samples and are assembled or installed to minimize contrast.

2.7 ALUMINUM FINISHES

A. Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances, door and frame preparation and reinforcements, and other conditions affecting performance of power door operators.

B. Examine roughing-in for electrical systems to verify actual locations of power connections before power door operator installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Install power door operators in accordance with manufacturer's written instructions and cited BHMA standard for type of door operation and direction of pedestrian travel, including signage, controls, wiring, remote power units if any, and connection to building's power supply.

1. Do not install damaged components. Fit joints to produce hairline joints free of burrs and distortion.
2. Install operators true in alignment with established lines and door geometry without warp or rack. Anchor securely in place.

B. Controls: Install activation and safety devices in accordance with manufacturer's written instructions and cited BHMA standard for operator type and direction of pedestrian travel. Connect control wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

C. Access-Control System: Connect operators to access-control system as specified in Section 281500 "Access Control Hardware Devices."

D. Signage: Apply on both sides of each door as required by cited BHMA standard for type of door operator and direction of pedestrian travel.

3.3 FIELD QUALITY CONTROL

A. Certified Inspector: Engage a Certified Inspector to test and inspect components, assemblies, and installations, including connections.

B. Perform the following tests and inspections with the assistance of a factory-authorized service representative:

1. Test and inspect each power door operator installation, using AAADM inspection forms, to determine compliance of installed systems with applicable BHMA standards.

C. Power door operators will be considered defective if they do not pass tests and inspections.

D. Prepare test and inspection reports.

3.4 ADJUSTING

A. Adjust power door operators to function smoothly, and lubricate as recommended by manufacturer; comply with requirements of applicable BHMA standards.

1. Adjust operators on exterior doors for tight closure.

B. After completing installation of power door operators, inspect exposed finishes on doors and operators. Repair damaged finish to match original finish.

C. Readjust power door operators and controls after repeated operation of completed installation equivalent to three days' use by normal traffic (100 to 300 cycles).

D. Occupancy Adjustment: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.5 MAINTENANCE SERVICE

A. Initial Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by skilled employees of power door operator Installer. Include quarterly preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper door operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.

1. Engage a Certified Inspector to perform safety inspection after each adjustment or repair and at end of maintenance period. Furnish completed inspection reports to Owner.
2. Perform maintenance, including emergency callback service, during normal working hours.
3. Include 24-hour-per-day, seven-day-per-week, emergency callback service.

3.6 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain power door operators.

END OF SECTION

SECTION 088000 - GLAZING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Glass products.
2. Insulating glass.
3. Insulating spandrel glass.
4. Glazing sealants.
5. Glazing tapes.
6. Miscellaneous glazing materials.
7. Adhesive glazing films.

B. Related Requirements:

1. Section 088300 "Mirrors."
2. Section 088813 "Fire-Rated Glazing."

1.2 DEFINITIONS

A. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.

B. Glass Thicknesses: Indicated by thickness designations in millimeters in accordance with ASTM C1036.

C. IBC: International Building Code.

D. Interspace: Space between lites of an insulating-glass unit.

1.3 COORDINATION

A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances to achieve proper safety margins for glazing retention under each design load case, load case combination, and service condition.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Glass Samples: For each type of glass product other than clear monolithic vision glass; 12 inches square.

D. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

E. Delegated Design Submittal: For glass indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by qualified professional engineer responsible for their preparation.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Qualification Data: For Installer manufacturers of fabricated glass units.

C. Product Certificates: For glass.

D. Product Test Reports: For fabricated glass and glazing sealants, for tests performed by a qualified testing agency.

1. For glazing sealants, provide test reports based on testing current sealant formulations within previous 36-month period.

E. Preconstruction adhesion and compatibility test report.

F. Sample Warranties: For special warranties.

1.6 QUALITY ASSURANCE

A. Fabricated-Glass Manufacturer Qualifications: A qualified manufacturer of fabricated glass units who is approved and certified by primary glass manufacturer.

B. Installer Qualifications: A qualified glazing contractor for this Project who is certified under the North American Contractor Certification Program (NACC) for Architectural Glass & Metal (AG&M) contractors.

C. Glass Testing Agency Qualifications: A qualified independent testing agency accredited according to the NFRC CAP 1 Certification Agency Program.

D. Sealant Testing Agency Qualifications: An independent testing agency qualified according to ASTM C1021 to conduct the testing indicated.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Protect glazing materials in accordance with manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

B. Comply with insulating-glass manufacturer's written instructions for venting and sealing units to avoid hermetic seal ruptures due to altitude change.

1.8 FIELD CONDITIONS

A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.

1. Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or are below 40 deg F.

1.9 WARRANTY

A. Manufacturer's Special Warranty for Insulating Glass: Manufacturer agrees to replace insulating-glass units that deteriorate within specified warranty period. Deterioration of insulating glass is defined as failure of hermetic seal under normal use that is not attributed to glass breakage or to maintaining and cleaning insulating glass contrary to manufacturer's written instructions. Evidence of failure is obstruction of vision by dust, moisture, or film on interior surfaces of glass.

1. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. General: Installed glazing systems shall withstand normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to defective manufacture, fabrication, or installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.

B. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design glazing.

C. Structural Performance: Glazing shall withstand the following design loads within limits and under conditions indicated determined in accordance with the IBC and ASTM E1300:

1. Design Wind Pressures: Determine design wind pressures applicable to Project in accordance with ASCE/SEI 7, based on heights above grade indicated on Drawings.

a. Wind Design Data: As indicated on Drawings.

D. Safety Glazing: Where safety glazing is indicated, provide glazing that complies with 16 CFR 1201, Category II.

E. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:

1. For monolithic-glass lites, properties are based on units with lites 6 mm thick.
2. For insulating-glass units, properties are based on units of thickness indicated for overall unit and for each lite.

3. U-Factors: Center-of-glazing values, in accordance with NFRC 100 and based on most current non-beta version of LBL's WINDOW computer program, expressed as Btu/sq. ft. x h x deg F.
4. SHGC and Visible Transmittance: Center-of-glazing values, in accordance with NFRC 200 and based on most current non-beta version of LBL's WINDOW computer program.
5. Visible Reflectance: Center-of-glazing values, in accordance with NFRC 300.

2.2 GLASS PRODUCTS, GENERAL

A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below unless more stringent requirements are indicated. See these publications for glazing terms not otherwise defined in this Section or in referenced standards.

1. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."

B. Safety Glazing Labeling: Where safety glazing is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction or manufacturer. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.

C. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of the IGCC.

D. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass that complies with performance requirements and is not less than thickness indicated.

1. Minimum Glass Thickness for Exterior Lites: 6 mm.

E. Strength: Where annealed float glass is indicated, provide annealed float glass, heat-strengthened float glass, or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where heat-strengthened float glass is indicated, provide heat-strengthened float glass or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where fully tempered float glass is indicated, provide fully tempered float glass.

2.3 GLASS PRODUCTS

A. Clear Annealed Float Glass: ASTM C1036, Type I, Class 1 (clear), Quality-Q3.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. AGC Glass Company North America, Inc.
b. Cardinal Glass Industries, Inc.
c. Guardian Glass LLC
d. Pilkington North America; NSG Group
e. Saint-Gobain Glass Corp
f. Vitro Architectural Glass

B. Fully Tempered Float Glass: ASTM C1048, Kind FT (fully tempered), Condition A (uncoated) unless otherwise indicated, Type I, Class 1 (clear) or Class 2 (tinted) as indicated, Quality-Q3.

1. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of glass as installed unless otherwise indicated.

C. Reflective- and Low-E-Coated Vision Glass: ASTM C1376.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Cardinal Glass Industries, Inc.
b. Guardian Glass LLC
c. Pilkington North America; NSG Group
d. Saint-Gobain Glass Corp
e. Vitro Architectural Glass

D. Silicone-Coated Spandrel Glass: ASTM C1048, Type 1, Condition C, Quality-Q3.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Guardian Glass LLC
b. ICD High Performance Coatings
c. Old Castle Building Envelope (OBE)

2.4 INSULATING GLASS

A. Insulating-Glass Units: Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified in accordance with ASTM E2190.

1. Sealing System: Dual seal, with manufacturer's standard primary and secondary sealants.
2. Perimeter Spacer: Thermally broken aluminum.
3. Desiccant: Molecular sieve or silica gel, or a blend of both.

2.5 GLAZING SEALANTS

A. General:

1. Compatibility: Compatible with one another and with other materials they contact, including glass products, seals of insulating-glass units, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
3. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range of industry colors.

B. Neutral-Curing Silicone Glazing Sealant, Class 50: Complying with ASTM C920, Type S, Grade NS, Use NT.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Adfast
b. GE Construction Sealants; Momentive Performance Materials Inc.
c. Pecora Corporation
d. Polymeric Systems, Inc
e. Sika Corporation
f. The Dow Chemical Company
g. Tremco Incorporated

2.6 GLAZING TAPES

A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C1281 and AAMA 800 for products indicated below:

1. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
2. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.

B. Expanded Cellular Glazing Tapes: Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:

1. AAMA 810.1, Type 1, for glazing applications in which tape acts as primary sealant.
2. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

2.7 ADHESIVE GLAZING FILMS

A. Translucent Glazing Film:

1. Interior application.
2. Basis-of-Design: 3M Frosted Crystal.

B. One-Way Mirror Glazing Film:

1. Exterior application.
2. Basis-of-Design: 3M One-Way Mirror Window Film.

2.8 sMISCELLANEOUS GLAZING MATERIALS

A. General: Provide products of material, size, and shape complying with referenced glazing standard, recommended in writing by manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.

B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

C. Setting Blocks:

1. EPDM Silicone with Shore A durometer hardness of 85, plus or minus 5.
2. Type recommended in writing by sealant or glass manufacturer.

D. Spacers:

1. Neoprene blocks or continuous extrusions of hardness required by glass manufacturer to maintain glass lites in place for installation indicated.
2. Type recommended in writing by sealant or glass manufacturer.

E. Edge Blocks:

1. EPDM Silicone with Shore A durometer hardness per manufacturer's written instructions.
2. Type recommended in writing by sealant or glass manufacturer.

F. Cylindrical Glazing Sealant Backing: ASTM C1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

2.9 FABRICATION OF GLAZING UNITS

A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.

1. Allow for thermal movements from ambient and surface temperature changes acting on glass framing members and glazing components.

a. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

B. Clean-cut or flat-grind vertical edges of butt-glazed monolithic lites to produce square edges with slight chamfers at junctions of edges and faces.

C. Grind smooth and polish exposed glass edges and corners.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine framing, glazing channels, and stops, with Installer present, for compliance with the following:

1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
2. Presence and functioning of weep systems.
3. Minimum required face and edge clearances.
4. Effective sealing between joints of glass-framing members.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.

B. Examine glazing units to locate exterior and interior surfaces. Label or mark units as needed so that exterior and interior surfaces are readily identifiable. Do not use materials that leave visible marks in the completed Work.

3.3 GLAZING, GENERAL

A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.

B. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass includes glass with edge damage or other imperfections that, when installed, could weaken glass, impair performance, or impair appearance.

C. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.

D. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

E. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.

F. Provide spacers for glass lites where length plus width is larger than 50 inches.

1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances, unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.

2. Provide 1/8-inch-minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.

G. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and in accordance with requirements in referenced glazing publications.

H. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.

I. Set glass lites with proper orientation so that coatings face exterior or interior as specified.

3.4 TAPE GLAZING

A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.

B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.

C. Cover vertical framing joints by applying tapes to heads and sills first, then to jambs. Cover horizontal framing joints by applying tapes to jambs, then to heads and sills.

D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.

E. Do not remove release paper from tape until right before each glazing unit is installed.

F. Apply heel bead of elastomeric sealant.

G. Center glass lites in openings on setting blocks, and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.

H. Apply cap bead of elastomeric sealant over exposed edge of tape.

3.5 GASKET GLAZING (DRY)

A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.

B. Insert soft compression gasket between glass and frame or fixed stop so it is securely in place with joints miter cut and bonded together at corners.

C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.

D. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.

E. Install gaskets so they protrude past face of glazing stops.

3.6 SEALANT GLAZING (WET)

A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances and to prevent sealant from extruding into glass channel and blocking weep systems until sealants cure. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.

B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.

C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

3.7 CLEANING AND PROTECTION

A. Immediately after installation, remove nonpermanent labels and clean surfaces.

B. Protect glass from contact with contaminating substances resulting from construction operations. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains.

1. If, despite such protection, contaminating substances do contact with glass, remove substances immediately as recommended in writing by glass manufacturer. Remove and replace glass that cannot be cleaned without damage to coatings.

C. Remove and replace glass that is damaged during construction period.

D. Wash glass on both exposed surfaces not more than four days before date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended in writing by glass manufacturer.

3.8 MONOLITHIC GLASS SCHEDULE

A. Clear Glass Type : Fully tempered float glass.

1. Minimum Thickness: 6 mm.
2. Safety glazing required.

3.9 INSULATING GLASS SCHEDULE

A. Low-E-Coated, Clear Insulating Glass Type:

1. Overall Unit Thickness: 1 inch.
2. Minimum Thickness of Each Glass Lite: 6 mm.
3. Outdoor Lite: Fully tempered float glass.
4. Interspace Content: Argon.
5. Indoor Lite: Fully tempered float glass.
6. Low-E Coating: Pyrolytic or sputtered on second surface.
7. Winter Nighttime U-Factor: 0.25 maximum.
8. Summer Daytime U-Factor: 0.27 maximum.
9. Visible Light Transmittance: 70 percent minimum.
10. SGHC: 0.37 maximum.
11. Safety glazing required.

END OF SECTION

SECTION 088813 - FIRE-RATED GLAZING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Fire-protection-rated glazing.

1.2 DEFINITIONS

A. Fire-Protection-Rated Glazing: Glazing that prevents spread of fire and smoke and complies with requirements for rated openings; incapable of blocking radiant heat

B. Fire-Resistance-Rated Glazing: Glazing that prevents spread of fire and smoke and radiant heat and complies with requirements for rated walls and rated openings; capable of blocking radiant heat

C. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.

D. Glass Thicknesses: Indicated by thickness designations in millimeters in accordance with ASTM C1036.

1.3 COORDINATION

A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Glass Samples: For each type of glass product; 12 inches square.

D. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

C. Product Certificates: For each type of glass and glazing product.

D. Sample Warranties: For special warranties.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: A qualified installer who employs glass installers for this Project who are certified under the NGA's Certified Glass Installer Program.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Protect glazing materials in accordance with manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

1.8 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install fire-resistant glazing until spaces are enclosed and weathertight and temporary HVAC system is operating and maintaining ambient temperature conditions at occupancy levels during remainder of construction period.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Glass: For each glass type, obtain from single source from single manufacturer.

B. Glazing Accessories: For each product and installation method, obtain from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. General: Installed glazing systems shall withstand normal thermal movement and impact loads (where applicable) without failure, including loss or glass breakage attributable to defective manufacture, fabrication, or installation; deterioration of glazing materials; or other defects in construction.

2.3 GLASS PRODUCTS, GENERAL

A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organization below unless more stringent requirements are indicated. See these publications for glazing terms not otherwise defined in this Section or in referenced standards.

B. Safety Glazing Labeling: Where safety glazing is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction or manufacturer. Label shall indicate manufacturer's name, type of glass, glass thickness, and safety glazing standard with which glass complies.

2.4 GLASS PRODUCTS

A. Tempered Float Glass: ASTM C1048, Kind FT (fully tempered), Condition A (uncoated) unless otherwise indicated, Type I, Class I (clear) unless otherwise indicated, Quality-Q3.

1. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of glass as installed unless otherwise indicated.

2.5 FIRE-PROTECTION-RATED GLAZING

A. General: Listed and labeled by a testing agency acceptable to authorities having jurisdiction, for fire-protection ratings indicated, based on positive-pressure testing in accordance with NFPA 257 or UL 9, including hose-stream test, and shall comply with NFPA 80.

1. Fire-protection-rated glazing required to have a fire-protection rating of 20 minutes shall be exempt from hose-stream test.

B. Fire-Protection-Rated Glazing Labeling: Permanently mark fire-protection-rated glazing with certification label of a testing agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name; test standard; whether glazing is permitted to be used in doors or openings; if permitted in openings, whether glazing has passed hose-stream test; whether glazing meets 450 deg F temperature-rise limitation; and fire-resistance rating in minutes.

C. Fire-Protection-Rated Monolithic Glass for Doors and Protected Openings: 19-mm thickness; low-iron fire-protection-rated glass; complying with 16 CFR 1201, Category II. UL listed and tested in accordance with NFPA 252 for fire-rated doors and NFPA 257 for protected openings with hose-stream testing.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. McGrory Glass, Inc
b. SAFTI FIRST Fire Rated Glazing Solutions
c. Schott North America, Inc.

2.6 GLAZING ACCESSORIES

A. Provide glazing gaskets, glazing sealants, glazing tapes, setting blocks, spacers, edge blocks, and other glazing accessories that are compatible with glazing products and each other and are approved by testing agencies that listed and labeled fire-resistant glazing products with which products are used for applications and fire-protection ratings indicated.

2.7 MISCELLANEOUS GLAZING MATERIALS

A. General: Provide products of material, size, and shape complying with referenced glazing standard, recommended in writing by manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.

B. Cylindrical Glazing Sealant Backing: ASTM C1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

C. Perimeter Insulation for Fire-Resistance-Rated Glazing: Product that is approved by testing agency that listed and labeled fire-resistant glazing product with which it is used for application and fire-protection rating indicated.

2.8 FABRICATION OF GLAZING UNITS

A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine framing, glazing channels, and stops, with Installer present, for compliance with manufacturing and installation tolerances, including those for size, squareness, and offsets at corners, and for compliance with minimum required face and edge clearances.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.

B. Examine glazing units to locate fire side and protected side. Label or mark units as needed so that fire side and protected side are readily identifiable. Do not use materials that leave visible marks in the completed Work.

3.3 GLAZING, GENERAL

A. Use methods approved by testing agencies that listed and labeled fire-resistant glazing products.

B. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials unless more stringent requirements are indicated, including those in referenced glazing publications.

C. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass is glass with edge damage or other imperfections that, when installed, could weaken glass and impair performance and appearance.

D. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.

E. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.

G. Provide spacers for glass lites where length plus width is larger than 50 inches.

1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
2. Provide 1/8-inch-minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.

H. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and in accordance with requirements in referenced glazing publications.

I. Set glass lites with proper orientation so that coatings face fire side or protected side as specified.

3.4 TAPE GLAZING

A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.

B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.

C. Cover vertical framing joints by applying tapes to heads and sills first and then to jambs. Cover horizontal framing joints by applying tapes to jambs and then to heads and sills.

D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.

E. Do not remove release paper from tape until right before each glazing unit is installed.

F. Center glass lites in openings on setting blocks and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.

G. Apply cap bead of elastomeric sealant over exposed edge of tape.

3.5 GASKET GLAZING (DRY)

A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.

B. Insert soft compression gasket between glass and frame or fixed stop, so it is securely in place with joints miter cut and bonded together at corners.

C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.

D. Install gaskets so they protrude past face of glazing stops.

3.6 SEALANT GLAZING (WET)

A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.

B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.

C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

3.7 CLEANING AND PROTECTION

A. Immediately after installation, remove nonpermanent labels and clean surfaces.

B. Protect glass from contact with contaminating substances resulting from construction operations. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains.

1. If, despite such protection, contaminating substances do contact with glass, remove substances immediately as recommended in writing by glass manufacturer.

C. Remove and replace glass that is damaged during construction period.

D. Wash glass on both exposed surfaces not more than four days before date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended in writing by glass manufacturer.

END OF SECTION

SECTION 089119 - FIXED LOUVERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Fixed extruded-aluminum louvers.
2. Blank-off panels for louvers

B. Related Requirements:

1. Section 081113 "Hollow Metal Doors and Frames" for louvers in hollow-metal doors.

1.2 DEFINITIONS

A. Louver Terminology: Definitions of terms for metal louvers contained in AMCA 501 apply to this Section unless otherwise defined in this Section or in referenced standards.

B. Horizontal Louver: Louver with horizontal blades (i.e., the axis of the blades are horizontal).

C. Vertical Louver: Louver with vertical blades (i.e., the axis of the blades are vertical).

D. Drainable-Blade Louver: Louver with blades having gutters that collect water and drain it to channels in jambs and mullions, which carry it to bottom of unit and away from opening.

E. Wind-Driven-Rain-Resistant Louver: Louver that provides specified wind-driven-rain performance, as determined by testing in accordance with AMCA 500-L.

F. Windborne-Debris-Impact-Resistant Louver: Louver that provides specified windborne-debris-impact resistance, as determined by testing in accordance with AMCA 540.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. For louvers specified to bear AMCA seal, include printed catalog pages showing specified models with appropriate AMCA Certified Ratings Seals.

C. Shop Drawings: For louvers and accessories. Include plans, elevations, sections, details, and attachments to other work. Show frame profiles and blade profiles, angles, and spacing.

1. Show weep paths, gaskets, flashings, sealants, and other means of preventing water intrusion.
2. Show mullion profiles and locations.

D. Samples: For each type of metal finish required.

E. Delegated Design Submittal: For louvers indicated to comply with structural and seismic performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Test Reports: Based on evaluation of comprehensive tests performed in accordance with AMCA 500-L by a qualified testing agency or by manufacturer and witnessed by a qualified testing agency, for each type of louver and showing compliance with performance requirements specified.

C. Sample Warranties: For manufacturer’s special warranties.

1.5 FIELD CONDITIONS

A. Field Measurements: Verify actual dimensions of openings by field measurements before fabrication.

1.6 WARRANTY

A. Special Finish Warranty, Factory-Applied Finishes: Standard form in which manufacturer agrees to repair finishes or replace aluminum that shows evidence of deterioration of baked enamel, powder coat, or organic finishes within specified warranty period.

1. Deterioration includes, but is not limited to, the following:

    a. Color fading more than 5 Delta E units when tested in accordance with ASTM D2244.
    b. Chalking in excess of a No. 8 rating when tested in accordance with ASTM D4214.
    c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.

2. Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain fixed louvers from single source from a single manufacturer where indicated to be of same type, design, or factory-applied color finish.

2.2 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design louvers, including comprehensive engineering analysis by a qualified professional engineer, using structural and seismic performance requirements and design criteria indicated.

B. Structural Performance: Louvers withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated without permanent deformation of louver components, noise or metal fatigue caused by louver-blade rattle or flutter, or permanent damage to fasteners and anchors. Wind pressures are considered to act normal to the face of the building.

1. Wind Loads:

a. Determine loads based on pressures as indicated on Drawings.

C. Seismic Performance:

1. As indicated on Drawings.

a. Component Importance Factor: 1.0.

D. Louver Performance Ratings: Provide louvers complying with requirements specified, as demonstrated by testing manufacturer's stock units identical to those provided, except for length and width in accordance with AMCA 500-L.

E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.

1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

F. SMACNA Standard: Comply with recommendations in SMACNA's "Architectural Sheet Metal Manual" for fabrication, construction details, and installation procedures.

2.3 FIXED EXTRUDED-ALUMINUM LOUVERS

A. Horizontal Nondrainable-Blade Louver, Extruded Aluminum :

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Airolite Company, LLC (The)
b. Architectural Louvers Co.; Harray, LLC
c. Construction Specialties, Inc.
d. Greenheck Fan Corporation

2. Louver Depth: 6 inches.
3. Blade Profile: Plain blade without center baffle.
4. Frame and Blade Nominal Thickness: Not less than 0.080 inch for frames.
5. Mullion Type: Exposed.
6. Louver Performance Ratings:

a. Free Area: Not less than 7.5 sq. ft. for 48-inch-wide by 48-inch-high louver.
b. Point of Beginning Water Penetration: Not less than 950 fpm.
c. Air Performance: Not more than 0.10-inch wg static pressure drop at750-fpm free-area intake velocity.

7. AMCA Seal: Mark units with AMCA Certified Ratings Seal.

2.4 LOUVER SCREENS

A. General: Provide screen at each exterior louver.

1. Screen Location for Fixed Louvers: Interior face.
2. Screening Type: Insect screening.

B. Secure screen frames to louver frames with stainless steel machine screws, spaced a maximum of 6 inches from each corner and at 12 inches o.c.

C. Louver Screen Frames: Fabricate with mitered corners to louver sizes indicated.

1. Metal: Same type and form of metal as indicated for louver to which screens are attached.
2. Finish: Same finish as louver frames to which louver screens are attached.
3. Type: Rewirable frames with a driven spline or insert.

D. Louver Screening for Aluminum Louvers:

1. Insect Screening, Aluminum: 18-by-16 mesh, 0.012-inch wire.

2.5 BLANK-OFF PANELS

A. Insulated Blank-Off Panels: Laminated panels consisting of an insulating core surfaced on back and front with metal sheets and attached to back of louver.

1. Thickness: 1 inch.
2. Metal Facing Sheets, Aluminum: Not less than 0.032-inch nominal thickness.
3. Insulating Core: Extruded-polystyrene foam.
4. Edge Treatment: Trim perimeter edges of blank-off panels with louver manufacturer's standard extruded-aluminum-channel frames, not less than 0.080-inch nominal thickness, with corners mitered and with same finish as panels.

5. Seal perimeter joints between panel faces and louver frames with gaskets or sealant.
6. Panel Finish: Same type of finish applied to louvers, but black color.
7. Attach blank-off panels with sheet metal screws.

2.6 MATERIALS

A. Aluminum Extrusions: ASTM B221, Alloy 6063-T5, T-52, or T6.

B. Aluminum Sheet: ASTM B209, Alloy 3003 or 5005, with temper as required for forming, or as otherwise recommended by metal producer for required finish.

C. Fasteners: Use types and sizes to suit unit installation conditions.

1. Use Phillips flat-head screws for exposed fasteners unless otherwise indicated.
2. For fastening aluminum, use aluminum or 300 series stainless steel fasteners.
3. For color-finished louvers, use fasteners with heads that match color of louvers.

D. Postinstalled Fasteners for Concrete and Masonry: Torque-controlled expansion anchors, fabricated from stainless steel components, with allowable load or strength design capacities calculated in accordance with ICC-ES AC193 and ACI 318 greater than or equal to the design load, as determined by testing in accordance with ASTM E488/E488M conducted by a qualified testing agency.

2.7 FABRICATION

A. Factory assemble louvers to minimize field splicing and assembly. Disassemble units as necessary for shipping and handling limitations. Clearly mark units for reassembly and coordinated installation.

B. Vertical Assemblies: Where height of louver units exceeds fabrication and handling limitations, fabricate units to permit field-bolted assembly with close-fitting joints in jambs and mullions, reinforced with splice plates.

1. Continuous Vertical Assemblies: Fabricate units without interrupting blade-spacing pattern unless horizontal mullions are indicated.

C. Maintain equal louver blade spacing to produce uniform appearance.

D. Fabricate frames, including integral sills, to fit in openings of sizes indicated, with allowances made for fabrication and installation tolerances, adjoining material tolerances, and perimeter sealant joints.

1. Frame Type: Channel unless otherwise indicated.

E. Include supports, anchorages, and accessories required for complete assembly.

F. Provide vertical mullions of type and at spacings indicated, but not more than is recommended by manufacturer, or 72 inches o.c., whichever is less.

1. Semirecessed Mullions: Where indicated, provide mullions partly recessed behind louver

blades, so louver blades appear continuous. Where length of louver exceeds fabrication and handling limitations, fabricate with interlocking split mullions and close-fitting blade splices designed to permit expansion and contraction.

2. Exterior Corners: Prefabricated corner units with mitered blades with concealed close-fitting splices and with semirecessed mullions at corners.

G. Provide subsills made of same material as louvers for recessed louvers.

H. Join frame members to each other and to fixed louver blades with fillet welds, threaded fasteners, or both, as standard with louver manufacturer unless otherwise indicated or size of louver assembly makes bolted connections between frame members necessary.

2.8 ALUMINUM FINISHES

A. Finish louvers after assembly.

B. High-Performance Organic Finish, Two-Coat PVDF: Fluoropolymer finish complying with AAMA 2605 and containing not less than 70 percent PVDF resin by weight in color coat.

1. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
2. Color and Gloss: As selected by Architect from manufacturer's full range.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and openings, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Coordinate setting drawings, diagrams, templates, instructions, and directions for installation of anchorages that are to be embedded in concrete or masonry construction. Coordinate delivery of such items to Project site.

3.3 INSTALLATION

A. Locate and place louvers level, plumb, and at indicated alignment with adjacent work.

B. Use concealed anchorages where possible. Provide brass or lead washers fitted to screws where required to protect metal surfaces and to make a weathertight connection.

C. Form closely fitted joints with exposed connections accurately located and secured.

D. Provide perimeter reveals and openings of uniform width for sealants and joint fillers, as indicated.

E. Protect unpainted galvanized- and nonferrous-metal surfaces that are in contact with concrete, masonry, or dissimilar metals from corrosion and galvanic action by applying a heavy coating of bituminous paint or by separating surfaces with waterproof gaskets or nonmetallic flashing.

F. Install concealed gaskets, flashings, joint fillers, and insulation as louver installation progresses, where weathertight louver joints are required. Comply with Section 079200 "Joint Sealants" for sealants applied during louver installation.

3.4 ADJUSTING AND CLEANING

A. Clean exposed louver surfaces that are not protected by temporary covering, to remove fingerprints and soil during construction period. Do not let soil accumulate during construction period.

B. Before final inspection, clean exposed surfaces with water and a mild soap or detergent not harmful to finishes. Thoroughly rinse surfaces and dry.

C. Restore louvers damaged during installation and construction, so no evidence remains of corrective work. If results of restoration are unsuccessful, as determined by Architect, remove damaged units and replace with new units.

1. Touch up minor abrasions in finishes with air-dried coating that matches color and gloss of, and is compatible with, factory-applied finish coating.

END OF SECTION

SECTION 092216 - NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Non-load-bearing steel framing systems for interior partitions.
2. Suspension systems for interior ceilings and soffits.
3. Grid suspension systems for gypsum board ceilings.

B. Related Requirements:

1. Section 054000 "Cold-Formed Metal Framing" for exterior and interior load-bearing and exterior non-load-bearing wall studs; floor joists; roof rafters and ceiling joists; and roof trusses.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Certificates: For each type of code-compliance certification for studs and tracks.

C. Evaluation Reports: For embossed steel studs and tracks, firestop tracks, post-installed anchors and power-actuated fasteners, from ICC-ES or other qualified testing agency acceptable to authorities having jurisdiction.

1.5 QUALITY ASSURANCE

A. Code-Compliance Certification of Studs and Tracks: Provide documentation that framing members are certified according to the product-certification program of the Steel Framing Industry Association or the Steel Stud Manufacturers Association.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: For fire-resistance-rated assemblies that incorporate non-load-bearing steel framing, provide materials and construction identical to those tested in assembly indicated, according to ASTM E 119 by an independent testing agency.

B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings, according to ASTM E 90 and classified according to ASTM E 413 by an independent testing agency.

C. Horizontal Deflection: For wall assemblies, limited to 1/240 of the wall height based on horizontal loading of 5 lbf/sq. ft.

2.2 FRAMING SYSTEMS

A. Framing Members, General: Comply with ASTM C 754 for conditions indicated.

1. Steel Sheet Components: Comply with ASTM C 645 requirements for metal unless otherwise indicated.
2. Protective Coating: ASTM A 653/A 653M, G40, hot-dip galvanized unless otherwise indicated.

B. Studs and Tracks: ASTM C 645. Use either steel studs and tracks or embossed steel studs and tracks.

1. Steel Studs and Tracks:

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) CEMCO; California Expanded Metal Products Co.
2) Custom Stud.
3) MarinoWARE.
4) MBA Building Supplies.
5) MRI Steel Framing, LLC.
6) Phillips Manufacturing Co.
7) SCAFCO Steel Stud Company.
8) Steel Network, Inc. (The).
9) Telling Industries.

b. Minimum Base-Metal Thickness: As required by performance requirements for horizontal deflection.
c. Depth: As indicated on Drawings.

2. Embossed Steel Studs and Tracks: Roll-formed and embossed with surface deformations to stiffen the framing members so that they are structurally equivalent to conventional ASTM C 645 steel studs and tracks.

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) CEMCO; California Expanded Metal Products Co.
2) ClarkDietrich Building Systems.
3) MarinoWARE.
4) MBA Building Supplies.
5) Phillips Manufacturing Co.
6) SCAFCO Steel Stud Company.
7) Steel Network, Inc. (The).
8) Telling Industries.

b. Minimum Base-Metal Thickness: As required by horizontal deflection performance requirements.
c. Depth: As indicated on Drawings.

C. Slip-Type Head Joints: Where indicated, provide one of the following:

1. Single Long-Leg Track System: ASTM C 645 top track with 2-inch- deep flanges in thickness not less than indicated for studs, installed with studs friction fit into top track and with continuous bridging located within 12 inches of the top of studs to provide lateral bracing.
2. Double-Track System: ASTM C 645 top outer tracks, inside track with 2-inch- deep flanges in thickness not less than indicated for studs and fastened to studs, and outer track sized to friction-fit over inner track.
3. Deflection Track: Steel sheet top track manufactured to prevent cracking of finishes applied to interior partition framing resulting from deflection of structure above; in thickness not less than indicated for studs and in width to accommodate depth of studs.

a. Products: Subject to compliance with requirements, provide one of the following:

1) Blazeframe Industries; Bare Slotted Track (BST/BST 2).
2) CEMCO; California Expanded Metal Products Co.; SLP-TRK Slotted Deflection Track.
3) ClarkDietrich Building Systems; MaxTrak Slotted Deflection Track.
4) MBA Building Supplies; Slotted Deflecto Track.
5) Metal-Lite; The System.
6) Perfect Wall, Inc.; The System Slotted Deflection Track.
7) SCAFCO Steel Stud Company; SCAFCO Slotted Leg Track System.
8) Steel Network, Inc. (The); VertiTrack VTD.
9) Telling Industries; Vertical Slip Track II.

D. Firestop Tracks: Top track manufactured to allow partition heads to expand and contract with movement of structure while maintaining continuity of fire-resistance-rated assembly indicated; in thickness not less than indicated for studs and in width to accommodate depth of studs.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Blazeframe Industries; Intumescent Framing, Fire Stop System.
b. CEMCO; California Expanded Metal Products Co.; FAS Track.
c. ClarkDietrich Building Systems; BlazeFrame.
d. Fire Trak Corp; Fire Trak System attached to studs with Fire Trak Posi Klip.

e. Metal-Lite; The System.

E. Flat Strap and Backing Plate: Steel sheet for blocking and bracing in length and width indicated.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ClarkDietrich Building Systems.
b. MarinoWARE.
c. MRI Steel Framing, LLC.
d. SCAFCO Steel Stud Company.

2. Minimum Base-Metal Thickness: 0.0296 inch.

F. Cold-Rolled Channel Bridging: Steel, 0.0538-inch minimum base-metal thickness, with minimum 1/2-inch- wide flanges.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ClarkDietrich Building Systems.
b. MarinoWARE.
c. MRI Steel Framing, LLC.
d. SCAFCO Steel Stud Company.

2. Depth: As indicated on Drawings.
3. Clip Angle: Not less than 1-1/2 by 1-1/2 inches, 0.068-inch- thick, galvanized steel.

G. Hat-Shaped, Rigid Furring Channels: ASTM C 645.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ClarkDietrich Building Systems.
b. MarinoWARE.
c. MRI Steel Framing, LLC.
d. SCAFCO Steel Stud Company.

2. Minimum Base-Metal Thickness: 0.0179 inch.
3. Depth: As indicated on Drawings.

H. Resilient Furring Channels: 1/2-inch-deep, steel sheet members designed to reduce sound transmission.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ClarkDietrich Building Systems.

b. MarinoWARE.
c. MRI Steel Framing, LLC.
d. SCAFCO Steel Stud Company.

2. Configuration: Hat shaped.

I. Cold-Rolled Furring Channels: 0.053-inch uncoated-steel thickness, with minimum 1/2-inch-wide flanges.

1. Depth: As indicated on Drawings.
2. Furring Brackets: Adjustable, corrugated-edge-type steel sheet with minimum uncoated-steel thickness of 0.0329 inch.
3. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- diameter wire, or double strand of 0.048-inch- diameter wire.

J. Z-Shaped Furring: With slotted or nonslotted web, face flange of 1-1/4 inches, wall attachment flange of 7/8 inch, minimum uncoated-metal thickness of 0.0179 inch, and depth required to fit insulation thickness indicated.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ClarkDietrich Building Systems.
b. MarinoWARE.
c. MRI Steel Framing, LLC.
d. SCAFCO Steel Stud Company.

2.3 SUSPENSION SYSTEMS

A. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch-diameter wire, or double strand of 0.048-inch- diameter wire.

B. Hanger Attachments to Concrete:

1. Post-Installed Anchors: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC193 as appropriate for the substrate.

a. Uses: Securing hangers to structure.
b. Type: Torque-controlled, adhesive anchor.
c. Material for Interior Locations: Carbon-steel components zinc-plated to comply with ASTM B 633 or ASTM F 1941, Class Fe/Zn 5, unless otherwise indicated.
d. Material for Exterior or Interior Locations and Where Stainless Steel Is Indicated: Alloy Group 1 stainless-steel bolts, ASTM F 593, and nuts, ASTM F 594.

2. Power-Actuated Anchors: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.

C. Wire Hangers: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.16 inch in diameter.

D. Carrying Channels (Main Runners): Cold-rolled, commercial-steel sheet with a base-metal thickness of 0.0538 inch and minimum 1/2-inch-wide flanges.

1. Depth: As indicated on Drawings.

E. Furring Channels (Furring Members):

1. Cold-Rolled Channels: 0.0538-inch uncoated-steel thickness, with minimum 1/2-inch-wide flanges, 3/4 inch deep.
2. Steel Studs and Tracks: ASTM C 645.

a. Minimum Base-Metal Thickness: 0.0179 inch.
b. Depth: As indicated on Drawings.

3. Embossed Steel Studs and Tracks: ASTM C 645.

a. Minimum Base-Metal Thickness: 0.0147 inch.
b. Depth: As indicated on Drawings.

4. Hat-Shaped, Rigid Furring Channels: ASTM C 645, 7/8 inch deep.

a. Minimum Base-Metal Thickness: 0.0179 inch.

5. Resilient Furring Channels: 1/2-inch-deep members designed to reduce sound transmission.

a. Configuration: Hat shaped.

6. Resilient Sound Isolation Clip: ASTM D 2000.

a. Minimum Base-Metal Thickness: 0.040 inch.
b. Depth: As indicated on Drawings. Projects 1-5/8 inches from supporting structure, when 7/8-inch drywall furring channels are use.

F. Grid Suspension System for Gypsum Board Ceilings: ASTM C 645, direct-hung system composed of main beams and cross-furring members that interlock.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Armstrong World Industries, Inc; Drywall Grid Systems.
b. Chicago Metallic Corporation; 640/660 Drywall Ceiling Suspension or 650/670 Fire Rated Drywall Ceiling Suspension.
c. USG Corporation; Drywall Suspension System.

2.4 AUXILIARY MATERIALS

A. General: Provide auxiliary materials that comply with referenced installation standards.

1. Fasteners for Steel Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.

B. Isolation Strip at Exterior Walls: Provide the following:

1. Asphalt-Saturated Organic Felt: ASTM D 226/D 226M, Type I (No. 15 asphalt felt), nonperforated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Suspended Assemblies: Coordinate installation of suspension systems with installation of overhead structure to ensure that inserts and other provisions for anchorages to building structure have been installed to receive hangers at spacing required to support the Work and that hangers will develop their full strength.

1. Furnish concrete inserts and other devices indicated to other trades for installation in advance of time needed for coordination and construction.

3.3 INSTALLATION, GENERAL

A. Installation Standard: ASTM C 754.

1. Gypsum Board Assemblies: Also comply with requirements in ASTM C 840 that apply to framing installation.

B. Install framing and accessories plumb, square, and true to line, with connections securely fastened.

C. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.

D. Install bracing at terminations in assemblies.

E. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

3.4 INSTALLING FRAMED ASSEMBLIES

A. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.

1. Single-Layer Application: 16 inches o.c. unless otherwise indicated.
2. Multilayer Application: 16 inches o.c. unless otherwise indicated.

3. Tile Backing Panels: 16 inches o.c. unless otherwise indicated.

B. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.

C. Install studs so flanges within framing system point in same direction.

D. Install tracks at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts that penetrate partitions above ceiling.

1. Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
2. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install track section (for cripple studs) at head and secure to jamb studs.

    a. Install two studs at each jamb unless otherwise indicated.
    b. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.

3. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
4. Fire-Resistance-Rated Partitions: Install framing to comply with fire-resistance-rated assembly indicated and support closures and to make partitions continuous from floor to underside of solid structure.

    a. Firestop Track: Where indicated, install to maintain continuity of fire-resistance-rated assembly indicated.

5. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.

E. Direct Furring:

1. Attach to concrete or masonry with stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches o.c.

F. Z-Shaped Furring Members:

1. Erect insulation, specified in Section 072100 "Thermal Insulation," vertically and hold in place with Z-shaped furring members spaced 24 inches o.c.
2. Except at exterior corners, securely attach narrow flanges of furring members to wall with concrete stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches o.c.
3. At exterior corners, attach wide flange of furring members to wall with short flange extending beyond corner; on adjacent wall surface, screw-attach short flange of furring channel to web of attached channel. At interior corners, space second member no more than 12 inches from corner and cut insulation to fit.

G. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch from the plane formed by faces of adjacent framing.

3.5 INSTALLING CEILING SUSPENSION SYSTEMS

A. Install suspension system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.

1. Hangers: 48 inches o.c.
2. Carrying Channels (Main Runners): 48 inches o.c.
3. Furring Channels (Furring Members): 16 inches o.c.

B. Isolate suspension systems from building structure where they abut or are penetrated by building structure to prevent transfer of loading imposed by structural movement.

C. Suspend hangers from building structure as follows:

1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or suspension system.

    a. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.

2. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with locations of hangers required to support standard suspension system members, install supplemental suspension members and hangers in the form of trapezes or equivalent devices.

    a. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced installation standards.

3. Wire Hangers: Secure by looping and wire tying, either directly to structures or to inserts, eye screws, or other devices and fasteners that are secure and appropriate for substrate, and in a manner that will not cause hangers to deteriorate or otherwise fail.
4. Do not attach hangers to steel roof deck.
5. Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
6. Do not attach hangers to rolled-in hanger tabs of composite steel floor deck.
7. Do not connect or suspend steel framing from ducts, pipes, or conduit.

D. Fire-Resistance-Rated Assemblies: Wire tie furring channels to supports.

E. Seismic Bracing: Sway-brace suspension systems with hangers used for support.

F. Grid Suspension Systems: Attach perimeter wall track or angle where grid suspension systems meet vertical surfaces. Mechanically join main beam and cross-furring members to each other and butt-cut to fit into wall track.

G. Installation Tolerances: Install suspension systems that are level to within 1/8 inch in 12 feet measured lengthwise on each member that will receive finishes and transversely between parallel members that will receive finishes.

END OF SECTION

SECTION 092900 - GYPSUM BOARD

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior gypsum board.
2. Tile backing panels.
3. Trim accessories.
4. Partition cap closure and mullion mate.

B. Related Requirements:

1. Section 079219 "Acoustical Joint Sealants" for acoustical joint sealants installed in gypsum board assemblies.
2. Section 092216 "Non-Structural Metal Framing" for nonstructural steel framing and suspension systems that support gypsum board panels.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Samples for Verification: Actual sample of finished products for the following:

1. Trim Accessories: Actual sample of finished products for each profile of trim required.

a. Size: Full size profile, 12 inches long,

1.3 DELIVERY, STORAGE, AND HANDLING

A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

1.4 FIELD CONDITIONS

A. Environmental Limitations: Comply with ASTM C840 requirements or manufacturer's written instructions, whichever are more stringent.

B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.

C. Do not install panels that are wet, moisture damaged, or mold damaged.

1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each type of gypsum panel and joint finishing material from single source with resources to provide products of consistent quality in appearance and physical properties.

2.2 PERFORMANCE REQUIREMENTS

A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings in accordance with ASTM E119; tested by a qualified testing agency.

B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings in accordance with ASTM E90 and classified in accordance with ASTM E413; tested by a qualified testing agency.

2.3 GYPSUM BOARD, GENERAL

A. Size: Provide panel products in maximum lengths and widths available that will minimize joints in each area and that correspond with support system specified or indicated on Drawings.

2.4 INTERIOR GYPSUM BOARD

A. Gypsum Board, Type X: ASTM C1396/C1396M.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. American Gypsum
    b. CertainTeed; SAINT-GOBAIN
    c. Georgia-Pacific Gypsum LLC
    d. Gold Bond Building Products, LLC provided by National Gypsum Company
    e. PABCO Gypsum
    f. Panel Rey
    g. USG Corporation

2. Thickness: 5/8 inch.
3. Long Edges: Tapered and featured (rounded or beveled) for prefilling.

B. Mold-Resistant Gypsum Board: ASTM C1396/C1396M; manufactured with moisture- and mold-resistant core and paper surfaces.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. American Gypsum
b. CertainTeed; SAINT-GOBAIN
c. Georgia-Pacific Gypsum LLC
d. Gold Bond Building Products, LLC provided by National Gypsum Company
e. PABCO Gypsum
f. Panel Rey
g. USG Corporation

C. Gypsum Ceiling Board: ASTM C1396/C1396M.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. CertainTeed; SAINT-GOBAIN
b. Georgia-Pacific Gypsum LLC
c. Gold Bond Building Products, LLC provided by National Gypsum Company
d. USG Corporation

2. Thickness: 1/2-inch.
3. Long Edges: Tapered.

2.5 SHAFTWALL SYSTEM

A. Basis-of-Design Product: Subject to compliance with requirements, provide Clark Dietrich Shaftwall Systems, or comparable product by one of the following:

1. Gold Bond Building Products, LLC provided by National Gypsum Company
2. National Gypsum Co.
3. USG Corporation

2.6 TILE BACKING PANELS

A. Glass-Mat, Water-Resistant Backing Board: ASTM C1178/C1178M, with manufacturer's standard edges.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. CertainTeed; SAINT-GOBAIN
b. Georgia-Pacific Gypsum LLC
c. Gold Bond Building Products, LLC provided by National Gypsum Company
d. USG Corporation

2. Core: 5/8 inch, Type X.
3. Mold Resistance: ASTM D3273, score of 10 as rated in accordance with ASTM D3274.

2.7 TRIM ACCESSORIES

A. Interior Trim: ASTM C1047.

1. Material: Galvanized-steel sheet or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized-steel sheet.
2. Shapes:

a. Cornerbead.
b. Bullnose bead.
c. LC-Bead: J-shaped; exposed long flange receives joint compound.
d. L-Bead: L-shaped; exposed long flange receives joint compound.
e. Expansion (control) joint.
f. Curved-Edge Cornerbead: With notched or flexible flanges.

B. Aluminum Trim: Extruded accessories of profiles and dimensions indicated on Drawings.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Brand X Metals, Inc
b. Flannery, Inc.
c. Fry Reglet Corporation
d. Gordon Inc.
e. Pittcon Industries

2. Aluminum: Alloy and temper with not less than the strength and durability properties of ASTM B221, Alloy 6063-T5.
3. Finish: Corrosion-resistant primer compatible with joint compound and finish materials specified.

2.8 PARTITION CAP CLOSURE AND MULLION MATE

A. Extruded Aluminum partition end cap and mullion mate.

B. Powder coat paint finish.

C. Basis of Design Product:

1. Abutting curtain wall mullion-Gordon Mullion Mate Pro FR.
2. Abutting glass-Gordon Mullion Mate Plus.

2.9 JOINT TREATMENT MATERIALS

A. General: Comply with ASTM C475/C475M requirements.

1. Mold-Resistant Joint Compound: Use mold-resistant formulations with mold-resistant panel products.

B. Joint Tape:

1. Interior Gypsum Board: Paper.
2. Tile Backing Panels: As recommended in writing by panel manufacturer.

C. Joint Compound for Interior Gypsum Board: For each coat, use formulation that is compatible with other compounds applied on previous or for successive coats.

1. Prefilling: At open joints, rounded or beveled panel edges, and damaged surface areas, use setting-type taping compound.
2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use drying-type, all-purpose compound.

a. Use setting-type compound for installing paper-faced metal trim accessories.

3. Fill Coat: For second coat, use drying-type, all-purpose compound.
4. Finish Coat: For third coat, use drying-type, all-purpose compound.
5. Skim Coat: For final coat of Level 5 finish, use drying-type, all-purpose compound, high-build interior coating product designed for application by airless sprayer and to be used instead of skim coat to produce Level 5 finish.

D. Joint Compound for Tile Backing Panels:

1. Glass-Mat, Water-Resistant Backing Panel: As recommended in writing by backing panel manufacturer.

2.10 AUXILIARY MATERIALS

A. Provide auxiliary materials that comply with referenced installation standards and manufacturer's written instructions.

B. Steel Drill Screws: ASTM C1002 unless otherwise specified or indicated on Drawings.

1. Use screws complying with ASTM C954 for fastening panels to steel members from 0.033 to 0.112 inch thick.

C. Sound-Attenuation Blankets: ASTM C665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers as follows:

1. Non-Fire-Resistance-Rated Assemblies: Glass or slag or rock wool.
2. Fire-Resistance-Rated Assemblies: Comply with mineral-fiber requirements of assembly.

D. Acoustical Sealant: As specified in Section 079219 "Acoustical Joint Sealants."

E. Thermal Insulation: As specified in Section 072100 "Thermal Insulation."

F. Vapor Retarder: As specified in Section 072600 "Vapor Retarders."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and substrates including welded hollow-metal frames and support framing, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.

B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION AND FINISHING OF PANELS, GENERAL

A. Comply with ASTM C840 requirements.

B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.

C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch of open space between panels. Do not force into place.

D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Do not make joints other than control joints at corners of framed openings.

E. Form control and expansion joints with space between edges of adjoining gypsum panels.

F. Cover both faces of support framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases braced internally.

1. Unless concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than 8 sq. ft. in area.
2. Fit gypsum panels around ducts, pipes, and conduits.
3. Where partitions intersect structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by structural members; allow 1/4- to 3/8-inch-wide joints to install sealant.

G. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments. Provide 1/4- to 1/2-inch-wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.

H. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.

I. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical sealant. Install acoustical sealant at both faces of partitions at perimeters and through penetrations. Comply with ASTM C919 requirements and with manufacturer's written instructions for locating edge trim and closing off sound-flanking paths around or through assemblies, including sealing partitions above acoustical ceilings.

J. Install sound-attenuation blankets before installing gypsum panels unless blankets are readily installed after panels have been installed on one side.

3.3 INSTALLATION OF INTERIOR GYPSUM BOARD

A. Install interior gypsum board in the following locations:

1. Gypsum Board, Type X: Vertical and horizontal surfaces, unless otherwise indicated.
2. Mold-Resistant Gypsum Board: As indicated on Drawings.

B. Single-Layer Application:

1. On ceilings, apply gypsum panels before wall/partition board application to greatest extent possible and at right angles to framing unless otherwise indicated on Drawings.
2. On partitions/walls, apply gypsum panels vertically (parallel to framing) unless otherwise specified or indicated on Drawings or required by fire-resistance-rated assembly, and minimize end joints.

    a. Stagger abutting end joints not less than one framing member in alternate courses of panels.
    b. At stairwells and other high walls, install panels horizontally unless otherwise indicated on Drawings or required by fire-resistance-rated assembly.

3. On Z-shaped furring members, apply gypsum panels vertically (parallel to framing) with no end joints. Locate edge joints over furring members.
4. Fastening Methods: Apply gypsum panels to supports with steel drill screws.

C. Multilayer Application:

1. On partitions/walls, apply gypsum board indicated for base layers and face layers vertically (parallel to framing) with joints of base layers located over studs or furring members and face-layer joints offset at least one stud or furring member with base-layer joints unless otherwise indicated on Drawings or required by fire-resistance-rated assembly. Stagger joints on opposite sides of partitions.
2. On Z-shaped furring members, apply base layer vertically (parallel to framing) and face layer either vertically (parallel to framing) or horizontally (perpendicular to framing) with vertical joints offset at least one furring member. Locate edge joints of base layer over furring members.
3. Fastening Methods: Fasten base layers and face layers separately to supports with screws.

3.4 INSTALLATION OF TILE BACKING PANELS

A. Glass-Mat, Water-Resistant Backing Panels: Comply with manufacturer's written installation instructions and install at locations indicated to receive tile. Install with 1/4-inch gap where panels abut other construction or penetrations.

B. Where tile backing panels abut other types of panels in same plane, shim surfaces to produce a uniform plane across panel surfaces.

3.5 INSTALLATION OF TRIM ACCESSORIES

A. General: For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim in accordance with manufacturer's written instructions.

B. Control Joints: Install control joints in accordance with ASTM C840 and in specific locations approved by Architect for visual effect.

C. Interior Trim: Install in the following locations:

1. Cornerbead: Install at outside corners.
2. Bullnose Bead: Install where indicated on Drawings.
3. LC-Bead: Install at exposed panel edges.
4. L-Bead: Install where indicated on Drawings.

D. Aluminum Trim: Install in locations indicated on Drawings.

3.6 APPLICATION OF JOINT TREATMENT MATERIALS

A. Finishing Panel Products: Treat joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare panel surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.

B. Prefill open joints, rounded or beveled edges, and damaged surface areas.

C. Apply joint tape over panel joints, except for trim products specifically indicated as not intended to receive tape.

D. Interior Gypsum Board: Finish panels to levels indicated below and in accordance with ASTM C840:

1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
2. Level 2: Panels that are substrate for tile.
3. Level 4: At panel surfaces that will be exposed to view unless otherwise indicated.

    a. Primer and its application to surfaces are specified in Section 099123 "Interior Painting."

3.7 PROTECTION

A. Protect adjacent surfaces from joint compound and promptly remove from floors and other non-gypsum board surfaces. Repair surfaces stained, marred, or otherwise damaged during gypsum board installation and finishing.

B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.

C. Remove and replace panels that are wet, moisture damaged, and mold damaged.

1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION

SECTION 093013 - CERAMIC TILING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Porcelain tile.
2. Glazed wall tile.
3. Crack isolation membranes.
4. Setting material.
5. Grout materials.

B. Related Requirements:

1. Section 092900 "Gypsum Board" for tile backing panels.

1.2 DEFINITIONS

A. General: Definitions in ANSI A108 series of tile installation standards and in ANSI A137.1 apply to Work of this Section unless otherwise specified.

B. Face Size: Actual tile size, excluding spacer lugs.

C. Large Format Tile: Tile with at least one edge 15 inches or longer.

D. Module Size: Actual tile size plus joint width indicated.

1.3 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Qualification Data: For Installer.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are competent in techniques required by manufacturer for flooring installation indicated.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store packaged materials in original containers with seals unbroken and labels intact until time of use. Comply with requirements in ANSI A137.1 for labeling tile packages.

B. Store tile and cementitious materials on elevated platforms, under cover, and in a dry location.

C. Store aggregates where grading and other required characteristics can be maintained and contamination can be avoided.

D. Store liquid materials in unopened containers and protected from freezing.

1.7 FIELD CONDITIONS

A. Environmental Limitations: Do not install tile until construction in spaces is complete and ambient temperature and humidity conditions are maintained at the levels indicated in referenced standards and manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Tile: Obtain tile of each type from single source or producer.

1. Obtain tile of each type and color or finish from same production run and of consistent quality in appearance and physical properties for each contiguous area.

2.2 PRODUCTS, GENERAL

A. ANSI Ceramic Tile Standard: Provide tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.

1. Provide tile complying with Standard Grade requirements.

B. ANSI Standards for Tile Installation Materials: Provide materials complying with ANSI A108.02, ANSI standards referenced in other Part 2 articles, ANSI standards referenced by TCNA installation methods specified in tile installation schedules, and other requirements specified.

C. Factory Blending: For tile exhibiting color variations within ranges, blend tile in factory and package so tile units taken from one package show same range in colors as those taken from other packages and match approved Samples.

2.3 PORCELAIN TILE

A. Porcelain Tile Type (PFT): Unglazed.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Daltile's Calgary, or comparable product by one of the following:

    a. American Olean; a brand of Dal-Tile Corporation.
    b. Crossville, Inc.
    c. Interceramic.
    d. Iris Ceramics U.S., a division of Stonepeak Ceramics, Inc.
    e. Marazzi USA; a brand of Dal-Tile Corporation.

2. Face Size: As indicated.
3. Face Size Variation: Rectified.
4. Thickness: 5/16 inch.
5. Physical Properties: Chemical resistant when tested with indicated chemicals in accordance with ASTM C650.
6. Tile Color: As indicated.
7. Grout Color: As selected by Architect from manufacturer's full range.
8. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable.

2.4 GLAZED WALL TILE

A. Glazed Wall Tile Type (CWT):

1. Basis-of-Design Product: Subject to compliance with requirements, provide Daltile's Color Wheel Collection, or comparable product by one of the following:

    a. American Olean; a brand of Dal-Tile Corporation.
    b. Crossville, Inc.
    c. Interceramic.
    d. Marazzi USA; a brand of Dal-Tile Corporation.

2. Module Size: As indicated.
3. Face Size Variation: Rectified.
4. Thickness: 5/16 inch.
5. Tile Color: As indicated.
6. Grout Color: As selected by Architect from manufacturer's full range.
7. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable and matching characteristics of adjoining flat tile. Provide shapes as follows, selected from manufacturer's standard shapes:

    a. Base for Thinset Mortar Installations: Straight, module size matching wall tile.
    b. Wainscot Cap for Thinset Mortar Installations: Surface bullnose, module size matching wall tile.
    c. External Corners for Thinset Mortar Installations: Surface bullnose; same size as adjoining flat tile.
    d. Internal Corners: Field-butted square corners. For coved base and cap, use angle pieces designed to fit with stretcher shapes.

2.5 TILE BACKING PANELS

A. Water-Resistant Gypsum Backing Board: ASTM C1396/C1396M, with manufacturer's standard edges.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. American Gypsum.
   b. CertainTeed; SAINT-GOBAIN.
   c. Georgia-Pacific Gypsum LLC.
   d. Gold Bond Building Products, LLC provided by National Gypsum Company.
   e. PABCO Gypsum.
   f. Panel Rey.
   g. USG Corporation.

2. Core: 5/8 inch, Type X.

2.6 CRACK ISOLATION MEMBRANES

A. General: Manufacturer's standard product that complies with ANSI A118.12 for standard performance and is recommended by manufacturer for application indicated. Include reinforcement and accessories recommended by manufacturer.

B. Crack Isolation Membrane, Polyethylene Sheet: Polyethylene faced on both sides with polyester fabric.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Custom Building Products.
   b. Laticrete International, Inc.
   c. MAPEI Corporation.
   d. Noble Company (The).
   e. Schluter Systems L.P.

2.7 SETTING MATERIALS

A. Improved Modified Dry-Set Mortar (Thinset): ANSI A118.15.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. ARDEX Americas.
   b. Custom Building Products.
   c. H.B. Fuller Construction Products Inc. / TEC.
   d. Laticrete International, Inc.
   e. MAPEI Corporation.
   f. Parex, a Sika brand.
   g. Siena Tile & Stone Installation Products; Omega Products International.

2. For wall applications, provide mortar that complies with requirements for nonsagging mortar in addition to other requirements in ANSI A118.15.

2.8 GROUT MATERIALS

A. High-Performance Tile Grout: ANSI A118.7.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. ARDEX Americas.
b. Bostik; Arkema.
c. Custom Building Products.
d. H.B. Fuller Construction Products Inc. / TEC.
e. Laticrete International, Inc.
f. MAPEI Corporation.
g. Parex, a Sika brand.
h. Southern Grouts & Mortars, Inc.
i. Summitville Tiles, Inc.

2.9 MISCELLANEOUS MATERIALS

A. Trowelable Underlayments and Patching Compounds: Latex-modified, portland cement-based formulation provided or approved by manufacturer of tile-setting and adhesive materials for installations indicated.

B. Metal Flooring Transitions: Profile designed specifically for flooring applications; height to match tile and setting-bed thickness.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Blanke Corporation.
b. Dural USA, Inc.
c. Profilitec Corp.
d. Progress Profiles America Inc.
e. Schluter Systems L.P.

2. Description: L-shaped.
3. Material and Finish: As indicated.

C. Metal Edge Trim: Profile designed for wall terminations and edge protection.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Blanke Corporation.
b. Dural USA, Inc.
c. Profilitec Corp.
d. Progress Profiles America Inc.

e. Schluter Systems L.P.

2. Description: L-shaped.
3. Material and Finish: As indicated.

D. Tile Cleaner: A neutral cleaner capable of removing soil and residue without harming tile and grout surfaces, specifically approved for materials and installations indicated by tile and grout manufacturers.

E. Grout Sealer: Grout manufacturer's standard product for sealing grout joints that does not change color or appearance of grout.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

1. Verify that substrates for setting tile are firm; dry; clean; free of coatings that are incompatible with tile-setting materials, including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.
2. Verify that concrete substrates for tile floors installed with thinset mortar comply with surface finish requirements in ANSI A108.01 for installations indicated.

    a. Verify that surfaces that received a steel trowel finish have been mechanically scarified.
    b. Verify that protrusions, bumps, and ridges have been removed by sanding or grinding.

3. Verify that installation of grounds, anchors, recessed frames, electrical and mechanical units of work, and similar items located in or behind tile has been completed.
4. Verify that joints and cracks in tile substrates are coordinated with tile joint locations; if not coordinated, adjust joint locations in consultation with Architect.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove coatings, including curing compounds or other coatings, that are incompatible with tile-setting materials.

B. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with thinset mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer.

C. Blending: For tile exhibiting color variations, verify that tile has been factory blended and packaged so tile units taken from one package show same range of colors as those taken from other packages and match approved Samples. If not factory blended, either return to manufacturer or blend tiles at Project site before installing.

D. Substrate Flatness:

1. For tile shorter than 15 inches, confirm that structure or substrate is limited to variation of 1/4 inch in 10 ft. from the required plane, and no more than 1/16 inch in 12 inches when measured from tile surface high points.
2. For large format tile, tile with at least one edge 15 inches or longer, confirm that structure or substrate is limited to 1/8 inch in 10 ft. from the required plane, and no more than 1/16 inch in 24 inches when measured from tile surface high points.

3.3 INSTALLATION OF CERAMIC TILE SYSTEM

A. Install tile backing panels and treat joints in accordance with ANSI A108.11 and manufacturer's written instructions for type of application indicated.

B. Install crack isolation membrane to comply with ANSI A108.17 and manufacturer's written instructions to produce membrane of uniform thickness that is bonded securely to substrate.

C. Mix mortars and grouts to comply with referenced standards and mortar and grout manufacturers' written instructions.

1. Add materials, water, and additives in accurate proportions.
2. Obtain and use type of mixing equipment, mixer speeds, mixing containers, mixing time, and other procedures to produce mortars and grouts of uniform quality with optimum performance characteristics for installations indicated.

D. Install tile in accordance with TCNA's "Handbook for Ceramic, Glass, and Stone Tile Installation" for TCNA installation methods specified in tile installation schedules. Comply with parts of ANSI A108 series that are referenced in TCNA installation methods and specified in tile installation schedules, and apply to types of setting and grouting materials used.

1. For the following installations, follow procedures in ANSI A108 series of tile installation standards for providing 95 percent mortar coverage:

   a. Tile floors consisting of tiles 8 by 8 inches or larger.

2. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.
3. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.
4. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.

5. Jointing Pattern: Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.
6. Lay out tile wainscots to dimensions indicated or to next full tile beyond dimensions indicated.

E. Movement Joints: Provide movement joints and other sealant-filled joints, including control, contraction, and isolation joints, where indicated on Drawings. Form joints during installation of setting materials, mortar beds, and tile. Keep joints free of dirt, debris, and setting materials prior to filling with sealants. Do not saw-cut joints after installing tiles.

1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.

F. Metal Flooring Transitions: Install where exposed edge of tile flooring meets carpet or other flooring.

G. Metal Wall Trim: Install at outside corners.

H. Grout Sealer: Apply grout sealer to grout joints in tile floors in accordance with manufacturer's written instructions. As soon as sealer has penetrated grout joints, remove excess sealer and sealer from tile faces by wiping with soft cloth.

3.4 ADJUSTING AND CLEANING

A. Remove and replace tile that is damaged or that does not match adjoining tile. Provide new matching units, installed as specified and in a manner to eliminate evidence of replacement.

B. Cleaning: On completion of placement and grouting, clean all ceramic tile surfaces so they are free of foreign matter.

1. Remove grout residue from tile as soon as possible.
2. Clean grout smears and haze from tile in accordance with tile and grout manufacturer's written instructions. Use only cleaners recommended by tile and grout manufacturers and only after determining that cleaners are safe to use by testing on samples of tile and other surfaces to be cleaned. Protect metal surfaces and plumbing fixtures from effects of cleaning. Flush surfaces with clean water before and after cleaning.

3.5 PROTECTION

A. Protect installed tile work with kraft paper or other heavy covering during construction period to prevent staining, damage, and wear. If recommended by tile manufacturer, apply coat of neutral protective cleaner to completed tile walls and floors.

B. Prohibit foot and wheel traffic from tiled floors for at least seven days after grouting is completed.

C. Before final inspection, remove protective coverings and rinse neutral protective cleaner from tile surfaces.

3.6 INTERIOR CERAMIC TILE INSTALLATION SCHEDULE

A. Interior Floor Installations, Concrete Subfloor:

1. TCNA F125-Full: Thinset mortar on crack isolation membrane.

a. Ceramic Tile Type: 12-inch by 24-inch porcelain tile.
b. Thinset Mortar: Dry set mortar for large and heavy tile (LHT mortar).
c. Grout: High-performance sanded cement grout.
d. Crack Isolation Membrane: As recommended by setting material manufacturer.
e. Joint Width: 1/8 inch.
f. Movement Joints: Types located on Drawings.

B. Interior Wall Installations, Wood or Metal Studs or Furring:

1. TCNA W245: Thinset mortar on gwater-resistant gypsum backer board.

a. Ceramic Tile Type: Glazed wall tile.
b. Thinset Mortar: Improved modified dry-set mortar.
c. Grout: High-performance sanded cement grout.
d. Joint Width: 1/8 inch.
e. Movement Joints: Types located on Drawings.

END OF SECTION

SECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Acoustical panels.
2. Metal suspension system.
3. Metal edge moldings and trim.

B. Products furnished, but not installed under this Section, include anchors, clips, and other ceiling attachment devices to be cast in concrete.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data:

1. For each type of product.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Ceiling suspension-system members.
2. Structural members to which suspension systems will be attached.
3. Method of attaching hangers to building structure.
4. Items penetrating finished ceiling and ceiling-mounted items including the following:

    a. Lighting fixtures.
    b. Diffusers.
    c. Grilles.
    d. Sprinklers.

5. Minimum Drawing Scale: 1/8 inch = 1 foot.

1.4 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Maintenance Data: For finishes to include in maintenance manuals.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver acoustical panels, suspension-system components, and accessories to Project site and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.

B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.

1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Source Limitations for Ceiling System: Obtain each type of acoustical ceiling panel and its supporting suspension system from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: Class A in accordance with ASTM E1264.
2. Smoke-Developed Index: 50 or less.

2.3 ACOUSTICAL PANELS (ACT)

A. Acoustical Panels:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Armstrong’s Cirrus High NRC, or comparable product by one of the following:

a. American Gypsum
b. CertainTeed; SAINT-GOBAIN
c. Rockfon; ROCKWOOL International
d. USG Corporation

2. Acoustical Panel Standard: Provide manufacturer's standard panels in accordance with ASTM E1264 and designated by type, form, pattern, acoustical rating, and light reflectance unless otherwise indicated.
3. Classification: Provide panels as follows:

a. Type and Form, Type III: Mineral base with painted finish; Form 1, nodular.
b. Pattern: E (lightly textured).

4. Color: White.
5. Light Reflectance (LR): Not less than 0.84.
6. Ceiling Attenuation Class (CAC): Not less than 35.
7. Noise Reduction Coefficient (NRC): Not less than 0.75.
8. Articulation Class (AC): Not less than 170.
9. Edge/Joint Detail: Angled tegular.
10. Thickness: 7/8 inch.
11. Modular Size: 24 by 24 inches.
12. Antimicrobial Treatment: Manufacturer's standard broad spectrum, antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested in accordance with ASTM D3273, ASTM D3274, or ASTM G21 and evaluated in accordance with ASTM D3274 or ASTM G21.

2.4 METAL SUSPENSION SYSTEM

A. Exposed Metal Suspension System :

1. Basis-of-Design Product: Subject to compliance with requirements, provide Armstrong’s 15/16-inch Prelude, or comparable product by one of the following:

a. CertainTeed; SAINT-GOBAIN
b. Rockfon; ROCKWOOL International
c. USG Corporation

2. Metal Suspension-System Standard: Provide manufacturer's standard, direct-hung, metal suspension system and accessories in accordance with ASTM C635/C635M and designated by type, structural classification, and finish indicated.
3. Wide-Face, Aluminum-Capped, Double-Web, Hot-Dip Galvanized, G60 (Z180), Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet; hot-dip galvanized, G60 coating designation; with prefinished, 15/16-inch-wide aluminum caps on flanges.

a. Structural Classification: Intermediate-duty system.
b. Face Design: Flat, flush.
c. Cap Finish: Painted white.

2.5 ACCESSORIES

A. Attachment Devices: Size for five times the design load indicated in ASTM C635/C635M, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.

1. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hangers of type indicated and with capability to sustain, without failure, a load equal to 10 times that imposed by ceiling construction, as determined by testing in accordance with ASTM E1190, conducted by a qualified testing and inspecting agency.

B. Wire Hangers, Braces, and Ties: Provide wires as follows:

1. Zinc-Coated, Carbon-Steel Wire: ASTM A641/A641M, Class 1 zinc coating, soft temper.
2. Size: Wire diameter sufficient for its stress at three times hanger design load (ASTM C635/C635M, Table 1, "Direct Hung") will be less than yield stress of wire, but not less than 0.106-inch-diameter wire.

2.6 METAL EDGE TRIM (FOR CEILING CLOUDS)

A. Metal Edge Moldings and Trim :

1. Basis-of-Design Product: Subject to compliance with requirements, provide Armstrong’s Axiom Classic Straight Perimeter 4-inch trim, or comparable product by one of the following:

a. Armstrong Ceiling & Wall Solutions
b. CertainTeed; SAINT-GOBAIN
c. Cipriani USA
d. Rockfon; ROCKWOOL International
e. USG Corporation

2. Extruded-Aluminum Edge Trim: Where indicated, provide manufacturer's extruded-aluminum edge trim of profile indicated or referenced by manufacturer's designations, including splice plates, corner pieces, and attachment and other clips, complying with seismic design requirements.

a. Baked-Enamel or Powder-Coat Finish: Minimum dry film thickness of 1.5 mils. Comply with ASTM C635/C635M and coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.

2.7 ACOUSTICAL SEALANT

A. Acoustical Sealant: As specified in Section 079219 "Acoustical Joint Sealants."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.

B. Examine acoustical panels before installation. Reject acoustical panels that are wet, moisture damaged, or mold damaged.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders unless otherwise indicated, and comply with layout shown on reflected ceiling plans.

B. Layout openings for penetrations centered on the penetrating items.

3.3 INSTALLATION OF ACOUSTICAL PANEL CEILINGS

A. Install acoustical panel ceilings in accordance with ASTM C636/C636M and manufacturer's written instructions.

B. Suspend ceiling hangers from building's structural members and as follows:

1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension-system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
4. Secure wire hangers to ceiling-suspension members and to supports above with a minimum of three tight turns. Connect hangers directly to structure or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
5. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, post-installed mechanical or adhesive anchors, or power-actuated fasteners that extend through forms into concrete.
6. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
7. Do not attach hangers to steel deck tabs.
8. Do not attach hangers to steel roof deck. Attach hangers to structural members.

9. Space hangers not more than 48 inches o.c. along each member supported directly from hangers unless otherwise indicated; provide hangers not more than 8 inches from ends of each member.
10. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards.

C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or post-installed anchors.

D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.

1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
2. Screw attach moldings to substrate at intervals not more than 16 inches o.c. and not more than 3 inches from ends. Miter corners accurately and connect securely.
3. Do not use exposed fasteners, including pop rivets, on moldings and trim.

E. Install suspension-system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.

F. Install acoustical panels with undamaged edges and fit accurately into suspension-system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide precise fit.

1. For reveal-edged panels on suspension-system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.
2. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.
3. Protect lighting fixtures and air ducts in accordance with requirements indicated for fire-resistance-rated assembly.

3.4 CLEANING

A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension-system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage.

B. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION

SECTION 096513 - RESILIENT BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Thermoset-rubber base.

2. Rubber stair treads.
3. Vinyl molding accessory.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F.

1.5 FIELD CONDITIONS

A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive resilient products during the following periods:

1. 48 hours before installation.
2. During installation.
3. 48 hours after installation.

B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 90 deg F.

C. Install resilient products after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 THERMOSET-RUBBER BASE - RWB

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Burke Mercer Flooring Products; a division of Burke Industries Inc.
2. Flexco.
3. Johnsonite; a Tarkett company.
4. Roppe Corporation.
5. Mannington.

B. Product Standard: ASTM F1861, Type TS (rubber, vulcanized thermoset), Group I (solid, homogeneous).

1. Style:

a. Style A, Straight: Provide in areas with carpet.

b. Style B, Cove: Provide in areas with resilient flooring.

C. Thickness: 0.125 inch.

D. Height: 4 inches.

E. Lengths: Coils in manufacturer's standard length.

F. Outside Corners: Job formed or preformed.

G. Inside Corners: Job formed or preformed.

H. Colors: To be selected.

2.2 RESILIENT STAIR ACCESSORIES

A. Rubber Stair Treads :

1. Basis-of-Design Product: Subject to compliance with requirements, provide Johnsonite’s Color Splash Treads or comparable product by one of the following:

a. Flexco Corporation
b. Mannington Mills, Inc
c. Mohawk Group
d. VPI Corporation

2. Classification: ASTM F2169, Type TS (rubber, vulcanized thermoset).

a. Class: 2 (pattern; embossed).

3. Nosing Style: Square, adjustable to cover angles between 60 and 90 degrees.
4. Nosing Height: Verify in field.
5. Thickness: 1/4 inch and tapered to back edge.
6. Size: Lengths and depths to fit each stair tread in one piece.

2.3 VINYL MOLDING ACCESSORY

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Armstrong World Industries, Inc.
2. Flexco Corporation.
3. Johnsonite; a Tarkett company.
4. Roppe Corporation; Roppe Holding Company.
5. The R.C. Musson Rubber Co.

B. Description: Vinyl transition strips.

C. Profile and Dimensions: As indicated.

D. Locations: Provide vinyl molding accessories where carpet tile meets concrete floors.

E. Colors and Patterns: As indicated by manufacturer's designations.

2.4 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.

C. Stair-Tread Nose Filler: Two-part epoxy compound recommended by resilient stair-tread manufacturer to fill nosing substrates that do not conform to tread contours.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

1. Installation of resilient products indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.

B. Concrete Substrates for Resilient Stair Accessories: Prepare horizontal surfaces in accordance with ASTM F710.

1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.
3. Alkalinity and Adhesion Testing: Perform tests recommended by manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.

4. Moisture Testing: Perform tests so that each test area does not exceed 1000 sq. ft. , and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.

    a. Anhydrous Calcium Chloride Test: ASTM F1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 7 lb of water/1000 sq. ft. in 24 hours.
    b. Relative Humidity Test: Using in-situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 90 percent relative humidity level measurement.

C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

D. Do not install resilient products until materials are the same temperature as space where they are to be installed.

1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.

E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.3 RESILIENT BASE INSTALLATION

A. Comply with manufacturer's written instructions for installing resilient base.

B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.

C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.

D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.

E. Do not stretch resilient base during installation.

F. Job-Formed Corners:

1. Outside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 9 inches in length.

    a. Form without producing discoloration (whitening) at bends.

2. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 9 inches in length.

    a. Miter or cope corners to minimize open joints.

3.4 RESILIENT ACCESSORY INSTALLATION

A. Comply with manufacturer's written instructions for installing resilient accessories.

3.5 INSTALLATION OF RESILIENT STAIR ACCESSORIES

A. Comply with manufacturer's written instructions for installing resilient accessories.

B. Resilient Stair Accessories:

1. Use stair-tread-nose filler to fill nosing substrates that do not conform to tread contours.
2. Tightly adhere to substrates throughout length of each piece.

C. Resilient Molding Accessories: Butt to adjacent materials and tightly adhere to substrates throughout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.

3.6 CLEANING AND PROTECTION

A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.

B. Perform the following operations immediately after completing resilient-product installation:

1. Remove adhesive and other blemishes from surfaces.
2. Sweep and vacuum horizontal surfaces thoroughly.
3. Damp-mop horizontal surfaces to remove marks and soil.

C. Resilient Molding Accessories: Butt to adjacent materials and tightly adhere to substrates throughout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.

D. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

E. Floor Polish: Remove soil, adhesive, and blemishes from resilient stair treads before applying liquid floor polish if recommended by manufacturer.

F. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION

SECTION 096519 - RESILIENT TILE FLOORING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Solid vinyl floor tile.

2. Rubber floor tile.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Sustainable Design Submittals:

1. Free of ortho phthalates, PFAS, and all six classes of harmful chemicals.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Qualification Data: For Installer.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Maintenance Data: For each type of floor tile to include in maintenance manuals.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are competent in techniques required by manufacturer for floor tile installation and seaming method indicated.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Store floor tile and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F. Store floor tiles on flat surfaces.

1.8 FIELD CONDITIONS

A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 85 deg F, in spaces to receive floor tile during the following periods:

1. 48 hours before installation.
2. During installation.
3. 48 hours after installation.

B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.

C. Close spaces to traffic during floor tile installation.

D. Close spaces to traffic for 48 hours after floor tile installation.

E. Install floor tile after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 SOLID VINYL FLOOR TILE (VFT)

A. Products: Subject to compliance with requirements, provide Tarkett’s IQ Eminent, or comparable product by one of the following:

1. Altro.
2. Gerflor USA.
3. Mannington Mills, Inc.

B. Tile Standard: ASTM F1700.

1. Class: Class I, Monolithic Vinyl Tile.
2. Type: A, Smooth Surface.

C. Thickness: 0.080 inch.

D. Size: 24 by 24 inches and 12 by 24 inches..

E. Colors and Patterns: As indicated.

2.2 RUBBER FLOOR TILE

A. Basis-of-Design Product: Subject to compliance with requirements, provide Tarkett's Color splash tile or comparable product by one of the following:

1. American Biltrite
2. Flexco Corporation
3. Mannington Mills, Inc
4. Nora by Interface
5. Roppe Corporation; Roppe Holding Company

B. Tile Standard: ASTM F1344, Class I-B, Homogeneous Rubber Tile, through mottled.

C. Hardness: Grade 1, minimum hardness of 85, measured using Shore, Type A durometer according to ASTM D2240.

D. Wearing Surface: Textured.

1. Molded-Pattern Figure: Hammered.

E. Thickness: 0.125 inch.

F. Size: 24 by 24 inches.

G. Colors and Patterns: As indicated on drawings.

2.3 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by floor tile manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended by floor tile and adhesive manufacturers to suit floor tile and substrate conditions indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of floor tile.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Prepare substrates according to floor tile manufacturer's written instructions to ensure adhesion of resilient products.

B. Concrete Substrates: Prepare according to ASTM F710.

1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by floor tile manufacturer. Do not use solvents.
3. Alkalinity and Adhesion Testing: Perform tests recommended by floor tile manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
4. Moisture Testing: Perform tests so that each test area does not exceed 1,000 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.

    a. Anhydrous Calcium Chloride Test: ASTM F1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 7 lb of water/1000 sq. ft. in 24 hours.
    b. Relative Humidity Test: Using in-situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 85 percent relative humidity level measurement.

C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

D. Do not install floor tiles until materials are the same temperature as space where they are to be installed.

1. At least 48 hours in advance of installation, move resilient floor tile and installation materials into spaces where they will be installed.

E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient floor tile.

3.3 FLOOR TILE INSTALLATION

A. Comply with manufacturer's written instructions for installing floor tile.

B. Lay out floor tiles from center marks established with principal walls, discounting minor offsets, so tiles at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half tile at perimeter.

1. Lay tiles square with room axis.

C. Match floor tiles for color and pattern by selecting tiles from cartons in the same sequence as manufactured and packaged, if so numbered. Discard broken, cracked, chipped, or deformed tiles.

D. Scribe, cut, and fit floor tiles to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.

E. Extend floor tiles into toe spaces, door reveals, closets, and similar openings. Extend floor tiles to center of door openings.

F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on floor tiles as marked on substrates. Use chalk or other nonpermanent marking device.

G. Install floor tiles on covers for telephone and electrical ducts, building expansion-joint covers, and similar items in installation areas. Maintain overall continuity of color and pattern between pieces of tile installed on covers and adjoining tiles. Tightly adhere tile edges to substrates that abut covers and to cover perimeters.

H. Adhere floor tiles to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.

3.4 CLEANING AND PROTECTION

A. Comply with manufacturer's written instructions for cleaning and protecting floor tile.

B. Perform the following operations immediately after completing floor tile installation:

1. Remove adhesive and other blemishes from surfaces.
2. Sweep and vacuum surfaces thoroughly.
3. Damp-mop surfaces to remove marks and soil.

C. Protect floor tile from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

D. Cover floor tile until Substantial Completion.

END OF SECTION

SECTION 096723 - RESINOUS FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Resinous flooring (Flat metal, power, or hand troweled).
2. Integral cove base accessories.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review manufacturer's written instructions for substrate preparation and environmental conditions affecting resinous flooring installation.
2. Review details of integral cove bases.
3. Review manufacturer's written instructions for installing resinous flooring systems.
4. Review protection measures for adjacent construction and installed flooring, floor drainage requirements, curbs, base details, and so forth.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include manufacturer's technical data, installation instructions, and recommendations for each resinous flooring component required.

C. Samples: For each resinous floor system required and for each color and texture specified, 3 inches square in size, applied to a rigid backing by Installer for this Project.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and

the individual sections specifying the work.

B. Maintenance Data: For resinous flooring to include in maintenance manuals.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.

1. Engage an installer who is certified in writing by resinous flooring manufacturer as qualified to apply resinous flooring systems indicated.

B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.

1. Apply full-thickness mockups on 48-inch-square floor area selected by Architect.

a. Include 48-inch length of integral cove base.

2. Simulate finished lighting conditions for Architect's review of mockups.
3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials in original packages and containers, with seals unbroken, bearing manufacturer's labels indicating brand name and directions for storage and mixing with other components.

1.8 FIELD CONDITIONS

A. Environmental Limitations: Comply with resinous flooring manufacturer's written instructions for substrate temperature, ambient temperature, moisture, ventilation, and other conditions affecting resinous flooring installation.

B. Lighting: Provide permanent lighting or, if permanent lighting is not in place, simulate permanent lighting conditions during resinous flooring installation.

C. Close spaces to traffic during resinous flooring installation and for 24 hours after installation unless manufacturer recommends a longer period.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Flammability: Self-extinguishing in accordance with ASTM D635.

2.2 RESINOUS FLOORING

A. Resinous Flooring System: Abrasion-, impact-, and chemical-resistant, aggregate-filled, resin-based monolithic floor surfacing designed to produce a seamless floor and integral cove base.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Stonhard's Stoneclad UR/Stonkote HT4 or comparable product by one of the following:

a. Dur-A-Flex; a Sherwin Williams Company
b. Key Resin Company
c. Laticrete International, Inc.
d. Sherwin-Williams High Performance Flooring
e. Sika Corporation; Flooring
f. Tnemec Company, Inc.

B. Source Limitations: Obtain primary resinous flooring materials, including primers, resins, hardening agents, grouting coats, and topcoats, from single source from single manufacturer. Obtain secondary materials, including patching and fill material, joint sealant, and repair materials, of type and from manufacturer recommended in writing by manufacturer of primary materials.

C. System Characteristics:

1. Color and Pattern: As selected by Architect from manufacturer's full range.
2. Wearing Surface: Smooth.
3. Overall System Thickness: 1/4 inch.

D. System Physical Properties: Provide resinous flooring system with the following minimum physical property requirements when tested in accordance with test methods indicated:

1. Compressive Strength: 5,000 PSI minimum in accordance with ASTM C579.
2. Tensile Strength: 1,000 PSI minimum in accordance with ASTM C307.
3. Flexural Modulus of Elasticity: 2,000 PSI minimum in accordance with ASTM C580.
4. Water Absorption: <1 percent percent maximum in accordance with ASTM C413.
5. Impact Resistance: No chipping, cracking, or delamination and not more than 1/16-inch permanent indentation in accordance with MIL-D-3134J.
6. Resistance to Elevated Temperature: No slip or flow of more than 1/16 inch in accordance with MIL-D-3134J.
7. Abrasion Resistance: 7160 in. lbs. maximum weight loss in accordance with ASTM D4226.
8. Hardness: 80 to 84, Shore D in accordance with ASTM D2240.
9. Critical Radiant Flux: 0.45 W/sq. cm or greater in accordance with NFPA 253.

E. Primer: Type recommended in writing by resinous flooring manufacturer for substrate and

resinous flooring system indicated.

1. Products:

    a. Stonhard Urethane Primer.

2. Formulation Description: 100 percent solids.

F. Patching and Fill Material: Resinous product of or approved by resinous flooring manufacturer and recommended in writing by manufacturer for installation indicated.

G. Body Coats:

1. Products:

    a. Stonclad UR.

2. Resin: Urethane.
3. Formulation Description: High solids.
4. Type: Pigmented.
5. Installation Method: Troweled or screeded.
6. Number of Coats: One.
7. Thickness of Coats: 1/4 inch.
8. Aggregates: Pigmented blended aggregate.

H. Topcoats: Sealing or finish coats.

1. Products:

    a. Stonkote HT4.

2. Resin: Bisphenol F Epoxy.
3. Formulation Description: 100 percent solids.
4. Type: Pigmented.
5. Number of Coats: One.
6. Thickness of Coats: 6 mils.
7. Finish: Gloss.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resinous flooring systems.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Prepare and clean substrates in accordance with resinous flooring manufacturer's written instructions for substrate indicated to ensure adhesion.

B. Concrete Substrates: Provide sound concrete surfaces free of laitance, glaze, efflorescence, curing compounds, form-release agents, dust, dirt, grease, oil, and other contaminants incompatible with resinous flooring.

1. Roughen concrete substrates as follows:

a. Shot-blast surfaces with an apparatus that abrades the concrete surface, contains the dispensed shot within the apparatus, and recirculates the shot by vacuum pickup.

2. Repair damaged and deteriorated concrete in accordance with resinous flooring manufacturer's written instructions.
3. Moisture Testing: Perform tests so that each test area does not exceed 1000 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.

a. Anhydrous Calcium Chloride Test: ASTM F1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 5 lb of water/1000 sq. ft. in 24 hours.
b. Relative Humidity Test: Using in-situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 85 percent relative humidity level measurement.

4. Alkalinity and Adhesion Testing: Perform tests recommended in writing by resinous flooring manufacturer. Proceed with installation only after substrate alkalinity is not less than 6 or more than 8 pH unless otherwise recommended in writing by flooring manufacturer,

C. Patching and Filling: Use patching and fill material to fill holes and depressions in substrates in accordance with manufacturer's written instructions.

1. Control Joint Treatment: Treat control joints and other nonmoving substrate cracks to prevent cracks from reflecting through resinous flooring in accordance with manufacturer's written instructions.

D. Resinous Materials: Mix components and prepare materials in accordance with resinous flooring manufacturer's written instructions.

3.3 INSTALLATION

A. Apply components of resinous flooring system in accordance with manufacturer's written instructions to produce a uniform, monolithic wearing surface of thickness specified.

1. Coordinate installation of components to provide optimum adhesion of resinous flooring system to substrate, and optimum intercoat adhesion.
2. Cure resinous flooring components in accordance with manufacturer's written

instructions. Prevent contamination during installation and curing processes.

B. Primer: Apply primer over prepared substrate at spreading rate recommended in writing by manufacturer.

C. Field-Formed Integral Cove Base: Apply cove base mix to wall surfaces before applying flooring coats. Apply in accordance with manufacturer's written instructions and details, including those for taping, mixing, priming, troweling, sanding, and topcoating of cove base. Round internal and external corners.

1. Integral Cove Base: 4 inches high.

D. Troweled or Screeded Body Coats: Apply troweled or screeded body coats in thickness specified for flooring system. Hand or power trowel and grout to fill voids. When body coats are cured, remove trowel marks and roughness using method recommended in writing by manufacturer.

E. Topcoats: Apply topcoats in number indicated for flooring system specified, at spreading rates recommended in writing by manufacturer, and to produce wearing surface specified.

3.4 PROTECTION

A. Protect resinous flooring from damage and wear during the remainder of construction period. Use protective methods and materials, including temporary covering, recommended in writing by resinous flooring manufacturer.

END OF SECTION

SECTION 096813 - TILE CARPETING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Carpet tile.

B. Related Requirements:

1. Section 096513 "Resilient Base and Accessories" and Section 096519 "Resilient Tile Flooring" for resilient wall base and accessories installed with carpet tile.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include manufacturer's written data on physical characteristics, durability, and fade resistance.
2. Include manufacturer's written installation recommendations for each type of substrate.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Statements: For Installer.

C. Sample Warranties: For carpet tile.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For carpet tiles. Include the following:

1. Methods for maintaining carpet tile, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
2. Precautions for cleaning materials and methods that could be detrimental to carpet tile.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are competent in techniques required by manufacturer for carpet tile installation.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Comply with CRI 104.

1.7 FIELD CONDITIONS

A. Comply with CRI 104 for temperature, humidity, and ventilation limitations.

B. Environmental Limitations: Do not deliver or install carpet tiles until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at levels planned for building occupants during the remainder of the construction period.

C. Do not install carpet tiles over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended in writing by carpet tile manufacturer.

D. Where demountable partitions or other items are indicated for installation on top of carpet tiles, install carpet tiles before installing these items.

1.8 WARRANTY

A. Special Warranty for Carpet Tiles: Manufacturer agrees to repair or replace components of carpet tile installation that fail in materials or workmanship within specified warranty period.

1. Warranty does not include deterioration or failure of carpet tile due to unusual traffic, failure of substrate, vandalism, or abuse.
2. Failures include, but are not limited to, the following:

    a. More than 10 percent loss of face fiber, edge raveling, snags, and runs.
    b. Loss of tuft-bind strength.
    c. Excess static discharge.
    d. Delamination.
    e. Dimensional instability.

3. Warranty Period: 15 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 CARPET TILE (CPTT 1, CPTT 5)

A. Basis-of-Design Product: Subject to compliance with requirements, provide Interface's Open Air 403, or comparable product by one of the following:

1. Bentley Mills, Inc.
2. Mannington Commercial; a business unit of Mannington Mills, Inc.
3. Milliken & Company.

B. Color: As indicated on Drawings.

C. Fiber Content: 100 percent recycled content nylon.

D. Fiber Type: Aquafil.

E. Pile Characteristic: Tufted textured loop pile.

F. Density: 8,241 oz./cu. yd.

G. Pile Thickness: 0.08 inches for finished carpet tile.

H. Stitches: 8.5 stitches per inch.

I. Gage: 1/12 ends per inch.

J. Surface Pile Weight: 19 oz./sq. yd.

K. Installation Method: Non-directional.

L. Primary Backing/Backcoating: Manufacturer's standard PVC backing containing post-industrial recycled content.

M. Backing System: Glasbac.

N. Size: 19.79 by 19.79 inches.

O. Applied Treatments:

1. Soil-Resistance Treatment: Protekt.
2. Antimicrobial Treatment: Intersept.

P. Sustainable Design Requirements:

1. Sustainable Product Certification: Gold level certification in accordance with NSF/ANSI 140.

Q. Performance Characteristics:

1. Texture Appearance Retention Rating (TARR): Severe traffic, 3.5 minimum in accordance with ASTM D7330.
2. Critical Radiant Flux Classification: Not less than 0.45 W/sq. cm in accordance with NFPA 253.
3. Dry Breaking Strength: Not less than 100 lbf in accordance with ASTM D2646.
4. Tuft Bind: Not less than 10 lbf in accordance with ASTM D1335.
5. Dimensional Tolerance: Within 1/32 inch of specified size dimensions, as determined by physical measurement.
6. Colorfastness to Crocking: Not less than 4, wet and dry, in accordance with AATCC 165.
7. Colorfastness to Light: Not less than 4 after 60 AFU (AATCC fading units) in accordance with AATCC 16.3 Option 3.
8. Electrostatic Propensity: Less than 3.5 kV in accordance with AATCC 134.

2.2 CARPET TILE (CPTT 2)

A. Basis-of-Design Product: Subject to compliance with requirements, provide Interface's Keys View, or comparable product by one of the following:

1. Bentley Mills, Inc.
2. Mannington Commercial; a business unit of Mannington Mills, Inc.
3. Milliken & Company.

B. Color: As indicated on Drawings.

C. Fiber Content: 100 percent recycled content nylon.

D. Fiber Type: Aquafil.

E. Pile Characteristic: Tufted textured loop pile.

F. Density: 6,612 oz./cu. yd.

G. Stitches: 8.3 stitches per inch.

H. Gage: 1/12 ends per inch.

I. Surface Pile Weight: 18 oz./sq. yd.

J. Installation Method: Ashlar

K. Primary Backing/Backcoating: Manufacturer's standard PVC backing containing post-industrial recycled content.

L. Backing System: Glasbac.

M. Size: 19.79 by 19.79 inches.

N. Applied Treatments:

1. Soil-Resistance Treatment: Protekt.
2. Antimicrobial Treatment: Intersept.

O. Sustainable Design Requirements:

1. Sustainable Product Certification: Gold level certification in accordance with NSF/ANSI 140.

P. Performance Characteristics:

1. Texture Appearance Retention Rating (TARR): Severe traffic, 3.5 minimum in accordance with ASTM D7330.
2. Critical Radiant Flux Classification: Not less than 0.45 W/sq. cm in accordance with NFPA 253.
3. Dry Breaking Strength: Not less than 100 lbf in accordance with ASTM D2646.
4. Tuft Bind: Not less than 10 lbf in accordance with ASTM D1335.
5. Dimensional Tolerance: Within 1/32 inch of specified size dimensions, as determined by physical measurement.
6. Colorfastness to Crocking: Not less than 4, wet and dry, in accordance with AATCC 165.
7. Colorfastness to Light: Not less than 4 after 60 AFU (AATCC fading units) in accordance with AATCC 16.3 Option 3.
8. Electrostatic Propensity: Less than 3.5 kV in accordance with AATCC 134.

2.3 CARPET TILE (CPTT 3, CPTT 6)

A. Basis-of-Design Product: Subject to compliance with requirements, provide Interface's Diddley Dot, or comparable product by one of the following:

1. Bentley Mills, Inc.
2. Mannington Commercial; a business unit of Mannington Mills, Inc.
3. Milliken & Company.

B. Color: As indicated on Drawings.

C. Fiber Content: 100 percent recycled content nylon.

D. Fiber Type: Aquafil.

E. Pile Characteristic: Tufted textured loop pile.

F. Density:7,200 oz./cu. yd.

G. Pile Thickness: 0.10 inches for finished carpet tile.

H. Stitches: 9.0 stitches per inch.

I. Gage: 1/12 ends per inch.

J. Surface Pile Weight: 20 oz./sq. yd.

K. Installation Method: Ashlar.

L. Primary Backing/Backcoating: Manufacturer's standard PVC backing containing post-industrial recycled content.

M. Backing System: Glasbac.

N. Size: 9.85 by 39.38 inches.

O. Applied Treatments:

1. Soil-Resistance Treatment: Protekt.
2. Antimicrobial Treatment: Intersept.

P. Sustainable Design Requirements:

1. Sustainable Product Certification: Gold level certification in accordance with NSF/ANSI 140.

Q. Performance Characteristics:

1. Texture Appearance Retention Rating (TARR): Severe traffic, 3.5 minimum in accordance with ASTM D7330.
2. Critical Radiant Flux Classification: Not less than 0.45 W/sq. cm in accordance with NFPA 253.
3. Dry Breaking Strength: Not less than 100 lbf in accordance with ASTM D2646.
4. Tuft Bind: Not less than 10 lbf in accordance with ASTM D1335.
5. Dimensional Tolerance: Within 1/32 inch of specified size dimensions, as determined by physical measurement.
6. Colorfastness to Crocking: Not less than 4, wet and dry, in accordance with AATCC 165.
7. Colorfastness to Light: Not less than 4 after 60 AFU (AATCC fading units) in accordance with AATCC 16.3 Option 3.
8. Electrostatic Propensity: Less than 3.5 kV in accordance with AATCC 134.

2.4 CARPET TILE (CPTT 4)

A. Basis-of-Design Product: Subject to compliance with requirements, provide Interface's Open Air 407, or comparable product by one of the following:

1. Bentley Mills, Inc.
2. Mannington Commercial; a business unit of Mannington Mills, Inc.
3. Milliken & Company.

B. Color: As indicated on Drawings.

C. Fiber Content: 100 percent recycled content nylon.

D. Fiber Type: Aquafil.

E. Pile Characteristic: Tufted textured loop pile.

F. Density: 6,968 oz./cu. yd.

G. Pile Thickness: 0.09 inches for finished carpet tile.

H. Stitches: 8.3 stitches per inch.

I. Gage: 1/12 ends per inch.

J. Surface Pile Weight: 18 oz./sq. yd.

K. Installation Method: Ashlar.

L. Primary Backing/Backcoating: Manufacturer's standard PVC backing containing post-industrial recycled content.

M. Backing System: Glasbac.

N. Size: 9.85 by 39.38 inches.

O. Applied Treatments:

1. Soil-Resistance Treatment: Protekt.
2. Antimicrobial Treatment: Intersept.

P. Sustainable Design Requirements:

1. Sustainable Product Certification: Gold level certification in accordance with NSF/ANSI 140.

Q. Performance Characteristics:

1. Texture Appearance Retention Rating (TARR): Heavy traffic, 3.0 minimum in accordance with ASTM D7330.
2. Critical Radiant Flux Classification: Not less than 0.45 W/sq. cm in accordance with NFPA 253.
3. Dry Breaking Strength: Not less than 100 lbf in accordance with ASTM D2646.
4. Tuft Bind: Not less than 10 lbf in accordance with ASTM D1335.
5. Dimensional Tolerance: Within 1/32 inch of specified size dimensions, as determined by physical measurement.
6. Colorfastness to Crocking: Not less than 4, wet and dry, in accordance with AATCC 165.
7. Colorfastness to Light: Not less than 4 after 60 AFU (AATCC fading units) in accordance with AATCC 16.3 Option 3.
8. Electrostatic Propensity: Less than 3.5 kV in accordance with AATCC 134.

2.5 CARPET TILE (CPTT 7)

A. Basis-of-Design Product: Subject to compliance with requirements, provide Mohawk's "Step in Style II", or comparable product by one of the following:

1. Bentley Mills, Inc.
2. Mannington Commercial; a business unit of Mannington Mills, Inc.
3. Milliken & Company.

B. Color: As indicated on Drawings.

C. Fiber Content: 100 percent nylon 6.

D. Fiber Type: Duracolor.

E. Pile Characteristic: Texture performance cut and loop pile.

F. Density: 7,448 oz./cu. yd.

G. Pile Thickness: 0.145 inches for finished carpet tile.

H. Stitches: 10 stitches per inch.

I. Gage: 5/32 ends per inch.

J. Surface Pile Weight: 30 oz./sq. yd.

K. Installation Method: Ashlar.

L. Primary Backing/Backcoating: Non-woven primary backing.

M. Secondary Backing: Polyolefin backing with a minimum of 35 percent pre-consumer recycled content.

N. Backing System: EcoFlex NXT.

O. Size: 24 by 24 inches.

P. Applied Treatments:

1. Soil-Resistance Treatment: Protekt.
2. Antimicrobial Treatment: Intersept.

Q. Sustainable Design Requirements:

1. Sustainable Product Certification: Gold level certification in accordance with NSF/ANSI 140.
2. Indoor Air Quality: Green Label Plus.

R. Performance Characteristics:

1. Texture Appearance Retention Rating (TARR): Severe traffic, 3.5 minimum in accordance with ASTM D7330.
2. Critical Radiant Flux Classification: Not less than 0.45 W/sq. cm in accordance with NFPA 253.
3. Dry Breaking Strength: Not less than 100 lbf in accordance with ASTM D2646.
4. Tuft Bind: Not less than 10 lbf in accordance with ASTM D1335.
5. Dimensional Tolerance: Within 1/32 inch of specified size dimensions, as determined by physical measurement.
6. Colorfastness to Crocking: Not less than 4, wet and dry, in accordance with AATCC 165.
7. Colorfastness to Light: Not less than 4 after 60 AFU (AATCC fading units) in accordance with AATCC 16.3 Option 3.
8. Electrostatic Propensity: Less than 3.5 kV in accordance with AATCC 134.

2.6 INSTALLATION ACCESSORIES

A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided or recommended in writing by carpet tile manufacturer.

B. Adhesives: Water-resistant, mildew-resistant, nonstaining, pressure-sensitive types to suit products and subfloor conditions indicated, that comply with flammability requirements for installed carpet tile, and that are recommended in writing by carpet tile manufacturer for releasable installation.

C. Metal Edge/Transition Strips: As indicated on Drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet tile performance.

B. Examine carpet tile for type, color, pattern, and potential defects.

C. Concrete Slabs: Verify that finishes comply with requirements specified in Section 033000 "Cast-in-Place Concrete" and that surfaces are free of cracks, ridges, depressions, scale, and foreign deposits.

1. Moisture Testing: Perform tests so that each test area does not exceed 1000 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.

    a. Relative Humidity Test: Using in situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 80 percent relative humidity level measurement, or up to 95 percent with the use of manufacturer recommended primer.
    b. Perform additional moisture tests recommended in writing by adhesive and carpet tile manufacturers. Proceed with installation only after substrates pass testing.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. General: Comply with CRI 104 and with carpet tile manufacturer's written installation instructions for preparing substrates.

B. Use trowelable leveling and patching compounds, in accordance with manufacturer's written instructions, to fill cracks, holes, depressions, and protrusions in substrates. Fill or level cracks, holes and depressions 1/8 inch wide or wider, and protrusions more than 1/32 inch unless more stringent requirements are required by manufacturer's written instructions.

C. Concrete Substrates: Remove coatings, including curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, without using solvents. Use mechanical methods recommended in writing by adhesive and carpet tile manufacturers.

D. Broom and vacuum clean substrates to be covered immediately before installing carpet tile.

3.3 INSTALLATION

A. General: Comply with CRI 104, Section 10, "Carpet Tile," and with carpet tile manufacturer's written installation instructions.

B. Installation Method: Glue down; install every tile with full-spread, releasable, pressure-sensitive adhesive.

C. Maintain dye-lot integrity. Do not mix dye lots in same area.

D. Cut and fit carpet tile to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended in writing by carpet tile manufacturer.

E. Extend carpet tile into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.

F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on carpet tile as marked on subfloor. Use nonpermanent, nonstaining marking device.

G. Install pattern parallel to walls and borders.

3.4 CLEANING AND PROTECTION

A. Perform the following operations immediately after installing carpet tile:

1. Remove excess adhesive and other surface blemishes using cleaner recommended in writing by carpet tile manufacturer.
2. Remove yarns that protrude from carpet tile surface.
3. Vacuum carpet tile using commercial machine with face-beater element.

B. Protect installed carpet tile to comply with CRI 104, Section 13.7.

C. Protect carpet tile against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet tile manufacturer.

END OF SECTION

SECTION 099123 - INTERIOR PAINTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Primers.
2. Water-based finish coatings.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product. Include preparation requirements and application instructions.

C. Product Schedule: Use same designations indicated on Drawings and in the Interior Painting Schedule to cross-reference paint systems specified in this Section. Include color designations.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.5 FIELD CONDITIONS

A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F.

B. Do not apply paints when relative humidity exceeds 85 percent; at temperatures of less than 5 deg F above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Benjamin Moore & Co.
2. California Paints.
3. Kelly-Moore Paint Company Inc.
4. PPG Paints.
5. Sherwin-Williams Company (The).
6. Valspar Corporation (The).

B. Source Limitations: Obtain each paint product from single source from single manufacturer.

2.2 PAINT PRODUCTS, GENERAL

A. Material Compatibility:

1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.

B. Colors: As indicated on Drawings.

2.3 PRIMERS

A. Interior Latex Primer Sealer: Pigmented, water-based latex sealer; formulated to reduce porosity of substrate for finish coats; for use on new interior plaster, concrete, and gypsum board substrates. Not intended for use on wood or previously painted surfaces.

B. Interior, Latex Primer for Wood: Waterborne-emulsion primer formulated for resistance to extractive bleeding, mold, and microbials; for hiding stains; and for use on interior wood substrates.

2.4 WATER-BASED FINISH COATS

A. Interior, High-Performance Architectural Latex: Water-based, pigmented, low-VOC, emulsion coating formulated to provide a significantly higher level of performance than conventional latex paints in the areas of scrub resistance, burnish resistance, and ease of stain removal.

1. Gloss and Sheen Level: Manufacturer's standard eggshell finish for gypsum board and semigloss for woods and metals.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:

1. Concrete: 12 percent.
2. Gypsum Board: 12 percent.

C. Gypsum Board Substrates: Verify that finishing compound is sanded smooth.

D. Verify suitability of substrates, including surface conditions and compatibility, with existing finishes and primers.

E. Proceed with coating application only after unsatisfactory conditions have been corrected.

1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations applicable to substrates and paint systems indicated.

B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.

C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.

D. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.

E. Steel Substrates: Remove rust, loose mill scale, and shop primer, if any. Clean using methods recommended in writing by paint manufacturer.

F. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and areas where shop paint is abraded. Paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.

G. Aluminum Substrates: Remove loose surface oxidation.

H. Cotton or Canvas Insulation Covering Substrates: Remove dust, dirt, and other foreign material that might impair bond of paints to substrates.

3.3 INSTALLATION

A. Apply paints according to manufacturer's written instructions.

1. Use applicators and techniques suited for paint and substrate indicated.
2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
5. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.

B. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.

C. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

D. Painting Fire-Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:

1. Paint the following work where exposed in occupied spaces:

a. Equipment, including panelboards.
b. Uninsulated metal piping.
c. Uninsulated plastic piping.
d. Pipe hangers and supports.
e. Metal conduit.
f. Plastic conduit.
g. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.

3.4 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

1. Do not clean equipment with free-draining water and prevent solvents, thinners, cleaners, and other contaminants from entering into waterways, sanitary and storm drain systems, and ground.

2. Dispose of contaminants in accordance with requirements of authorities having jurisdiction.
3. Allow empty paint cans to dry before disposal.

B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.

D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

3.5 INTERIOR PAINTING SCHEDULE

A. Concrete Substrates, Nontraffic Surfaces:

1. High-Performance Architectural Latex System :

a. Prime Coat: Alkali-resistant, water-based primer.
b. Intermediate Coat: Matching topcoat.
c. Topcoat: Interior, high-performance architectural latex, satin.

B. Steel Substrates:

1. High-Performance Architectural Latex System:

a. Prime Coat: Shop primer specified in Section where substrate is specified.
b. Intermediate Coat: Matching topcoat.
c. Topcoat: Topcoat: Interior, high-performance architectural latex, semigloss.

C. Aluminum (Not Anodized or Otherwise Coated) Substrates:

1. Institutional Low-Odor/VOC Latex System:

a. Prime Coat: Quick-dry primer for aluminum.
b. Intermediate Coat: Matching topcoat.
c. Topcoat: Interior, latex, institutional low-odor/VOC, semigloss.

D. Gypsum Board Substrates:

1. Institutional Low-Odor/VOC Latex System:

a. Prime Coat: Interior latex primer sealer.
b. Intermediate Coat: Matching topcoat.
c. Topcoat: Interior, high-performance architectural latex, eggshell.

E. Cotton or Canvas and ASJ Insulation-Covering Substrates: Including pipe and duct coverings.

1. Latex System:

a. Prime Coat: Interior latex primer sealer.
b. Intermediate Coat: Matching topcoat.
c. Topcoat: Interior, latex, institutional low-odor/VOC, eggshell.

F. Finish Carpentry Substrates: Wood trim.

1. High-Performance Architectural Latex System :

a. Prime Coat: Interior latex primer for wood.
b. Intermediate Coat: Matching topcoat.
c. Topcoat: Interior, high-performance architectural latex, semigloss.

END OF SECTION

SECTION 099600 - HIGH-PERFORMANCE COATINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes surface preparation and the application of high-performance coating systems on the following substrates:

1. Exterior Substrates:

a. Steel.
b. Galvanized metal.

1.3 DEFINITIONS

A. MPI Gloss Level 5: 35 to 70 units at 60 degrees, according to ASTM D523.

B. MPI Gloss Level 6: 70 to 85 units at 60 degrees, according to ASTM D523.

C. MPI Gloss Level 7: More than 85 units at 60 degrees, according to ASTM D523.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. Include preparation requirements and application instructions.

1. Include printout of current "MPI Approved Products List" for each product category specified, with the proposed product highlighted.
2. Indicate VOC content.

C. Samples for Initial Selection: For each type of topcoat product indicated.

D. Samples for Verification: For each type of coating system and each color and gloss of topcoat indicated.

1. Submit Samples on rigid backing, 8 inches square.
2. Apply coats on Samples in steps to show each coat required for system.
3. Label each coat of each Sample.

4. Label each Sample for location and application area.

E. Product List: Cross-reference to coating system and locations of application areas. Use same designations indicated on Drawings and in schedules. Include color designations.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Coatings: 5 percent, but not less than 1 gal. of each material and color applied.

1.6 QUALITY ASSURANCE

A. Mockups: Apply mockups of each coating system indicated to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Architect will select one surface to represent surfaces and conditions for application of each coating system.

a. Other Items: Architect will designate items or areas required.

2. Final approval of color selections will be based on mockups.

a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.

3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

B. For interior walls, the Manufacturer shall have a minimum of 10 years’ experience in the production, sales, and technical support of urethane industrial flooring and wall coatings and related materials.

C. The Applicator shall have experience in installation of the wall system as confirmed by the manufacturer in all phases of surface preparation and application of the product specified.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.8 FIELD CONDITIONS

A. Apply coatings only when temperature of surfaces to be coated and ambient air temperatures are between 50 and 95 deg F.

B. For interior applications, apply coatings only when temperature of surfaces to be coated and ambient air temperatures are between 60 and 90 deg F.

C. Do not apply coatings when relative humidity exceeds 80 percent; at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.

D. Do not apply exterior coatings in snow, rain, fog, or mist.

E. Provide adequate lighting equal to the final lighting level during the preparation and installation of the system.

F. Safety Requirements For Interior Epoxy Wall Finish:

1. All open flames and spark-producing equipment shall be removed from the work area prior to commencement of application.
2. "No Smoking" signs shall be posted at the entrances to the work area.
3. The Owner shall be responsible for the removal of foodstuffs from the work area.
4. Non-related personnel in the work area shall be kept to a minimum.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Behr Paint Company (Behr Process LLC).
2. Benjamin Moore & Co.
3. Carboline Company; a subsidiary of RPM International.
4. Coronado Paint; Benjamin Moore & Co.
5. Corotech Coatings; Benjamin Moore & Co.
6. Diamond Vogel Paint Company.
7. Dur-A-Flex.
8. H&C Decorative Concrete Products; a brand of Sherwin-Williams Co.
9. Hempel (USA), Inc.
10. International Protective Coatings; AkzoNobel.
11. PPG Paints; PPG Industries, Inc.
12. Rust-Oleum Corporation; a subsidiary of RPM International, Inc.
13. Sherwin-Williams Company (The).
14. Tnemec Company, Inc.

B. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to products listed in the Exterior High-Performance Coating Schedule or Interior High-Performance Coating Schedule for the coating category indicated.

2.2 HIGH-PERFORMANCE COATINGS, GENERAL

A. MPI Standards: Products shall comply with MPI standards indicated and shall be listed in its "MPI Approved Products Lists."

B. Material Compatibility:

1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.
3. Products shall be of same manufacturer for each coat in a coating system.

C. Colors: As selected by Architect from manufacturer's full range.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:

1. Wood: 15 percent.

C. Verify suitability of substrates, including surface conditions and compatibility, with existing finishes and primers.

D. Proceed with coating application only after unsatisfactory conditions have been corrected.

1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual" applicable to substrates and coating systems indicated.

B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.

C. Clean substrates of substances that could impair bond of coatings, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce coating systems indicated.

D. Steel Substrates: Remove rust, loose mill scale, and shop primer if any. Clean using methods recommended in writing by paint manufacturer.

E. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and areas where shop paint is abraded. Paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.

F. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied coatings.

G. Wood Substrates:

1. Scrape and clean knots. Before applying primer, apply coat of knot sealer that is recommended in writing by topcoat manufacturer for coating system indicated.
2. Sand surfaces that will be exposed to view and dust off.
3. Prime edges, ends, faces, undersides, and backsides of wood.
4. After priming, fill holes and imperfections in the finish surfaces with filler that is recommended in writing by topcoat manufacturer for coating system indicated. Sand smooth when dried.

H. Drywall shall be completely clean and free of any oils, soap residue, and gypsum dust and prepared to a #4 to #5 finish.

A. Drywall shall be completely clean and free of any oils, soap residue, gypsum, etc. and primed with Dur-A-Flex, Dur-A-Wall HP Gripper Primer.

3.3 APPLICATION

A. Apply high-performance coatings according to manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual."

1. Use applicators and techniques suited for coating and substrate indicated.
2. Coat surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, coat surfaces behind permanently fixed equipment or furniture with prime coat only.
3. Coat backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
4. Do not apply coatings over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.

B. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of the same material are to be applied. Tint undercoats to match color of finish coat, but provide sufficient difference in shade of undercoats to distinguish each separate coat.

C. If undercoats or other conditions show through final coat, apply additional coats until cured film has a uniform coating finish, color, and appearance.

D. Apply coatings to produce surface films without cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections. Produce sharp glass lines and color breaks.

E. The handling, mixing and addition of components shall be performed in a safe manner to achieve the desired results in accordance with the Manufacturer's recommendations.

3.4 FIELD QUALITY CONTROL

A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test coatings for dry film thickness.

1. Contractor shall touch up and restore coated surfaces damaged by testing.
2. If test results show that dry film thickness of applied coating does not comply with coating manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with coating manufacturer's written recommendations.

3.5 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

B. After completing coating application, clean spattered surfaces. Remove spattered coatings by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

C. Protect work of other trades against damage from coating operation. Correct damage to work of other trades by cleaning, repairing, replacing, and recoating, as approved by Architect, and leave in an undamaged condition.

D. At completion of construction activities of other trades, touch up and restore damaged or defaced coated surfaces.

E. Cure material in compliance with manufacturer’s directions, taking care to prevent their contamination during stages of application and prior to completion of the curing process.

3.6 EXTERIOR HIGH-PERFORMANCE COATING SCHEDULE

A. Steel Substrates:

1. Epoxy System MPI EXT 5.1F:

a. Prime Coat: Primer, epoxy, anti-corrosive, for metal, MPI #101.
b. Intermediate Coat: Epoxy, high build, low gloss, MPI #108.
c. Topcoat: Epoxy, gloss, MPI #77.

2. Epoxy over Self-Priming Epoxy System MPI EXT 5.1S:

a. Prime Coat: Epoxy, high build, self-priming , MPI #120.
b. Intermediate Coat: Epoxy, matching topcoat.
c. Topcoat: Epoxy, gloss, MPI #77.

B. Galvanized-Metal Substrates:

1. Epoxy System MPI EXT 5.3C:

a. Prime Coat: Primer, epoxy, anti-corrosive, for metal, MPI #101.
b. Intermediate Coat: Epoxy, matching topcoat.
c. Topcoat: Epoxy, gloss, MPI #77.

2. Pigmented Polyurethane over Epoxy Primer System MPI EXT 5.3L:

a. Prime Coat: Primer, epoxy, anti-corrosive, for metal, MPI #101.
b. Intermediate Coat: Polyurethane, two component, pigmented, gloss matching topcoat.
c. Topcoat: Polyurethane, two component, pigmented, gloss (MPI Gloss Level 6), MPI #72.

END OF SECTION

SECTION 099726 - CEMENTITIOUS COATINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes surface preparation and application of cementitious coating systems on the following substrates:

1. Exterior concrete.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Samples for Verification: In each color and gloss of topcoat.

1. Submit Samples on rigid backing, not less than 8 inches square, with mortar joint in center.
2. Apply coats on Samples in steps to show each coat required for system.
3. Label each coat of each Sample.
4. Label each Sample for location and application area.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Material Certificates: For each cementitious coating, from manufacturer.

C. Product Test Reports: Based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified testing agency or performed by a qualified testing agency, for each product formulation.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials that are from same production run (batch mix) as materials applied and that are packaged with protective covering for storage and identified with labels describing contents.

1. Quantity: Furnish an additional 5 percent of each color applied.

1.5 QUALITY ASSURANCE

A. Mockups: Apply mockups of coating system indicated and each color and finish selected to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Architect will select one actual substrate of each type to represent surfaces and conditions for application of coating.

a. Wall Surfaces: Prepare Samples of at least 15 sq. ft.

2. Apply mockups after permanent lighting and other environmental services have been activated.
3. Final approval of color selections will be based on mockups.

a. If preliminary color selections are not approved, apply additional mockups of colors selected by Architect at no added cost to Owner.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials to Project site in manufacturer's original, new, unopened packages and containers bearing manufacturer's name and label, and the following information:

1. Product name or title of material.
2. Manufacturer's stock number and date of manufacture.
3. Contents by volume, for pigment and vehicle constituents.
4. Application instructions.
5. Color name and number.
6. Handling instructions and precautions.

B. Store materials not in use in tightly covered containers in a well-ventilated area at a minimum ambient temperature of 45 deg F. Maintain containers used in storage of coatings in a clean condition, free of foreign materials and residue.

1. Protect cementitious coating materials from freezing. Keep materials dry and storage area neat and orderly. Remove waste daily. Take necessary measures to ensure that workers and work areas are protected from health hazards resulting from handling, mixing, and applying the coating.

1.7 FIELD CONDITIONS

A. Apply coatings only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F.

B. Do not apply coatings when relative humidity exceeds 85 percent; at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 CEMENTITIOUS COATINGS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Expo 43, as manufactured by Edison Coatings, Inc., or comparable product by one of the following:

1. Euclid Chemical Company (The); a subsidiary of RPM International, Inc.
2. Fox Industries, Inc.
3. Gemite Products Inc., a W.R. Meadows company
4. MAPEI Corporation
5. Master Builders Solutions, brand of MBCC Group, a Sika company
6. Sakrete; CRH Americas, Oldcastle APG
7. Silpro Corporation

B. Source Limitations: Obtain cementitious coating materials from single source and from single manufacturer.

C. Polymer-Modified Cementitious Coating: Containing portland cement, polymer, and hydrated lime or aggregates.

1. Compressive Strength: Not less than 3500 psi at 28 days according to ASTM C109/C109M.
2. Tensile Strength: Not less than 350 psi at 28 days according to ASTM C109/C109M.

D. Prime Coat: As recommended in writing by cementitious coating manufacturer.

E. Colors: As selected by Architect from manufacturer's full range.

F. Other Materials: Provide crack fillers, block fillers, and related materials that are compatible with cementitious finish-coat materials and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements and other conditions affecting performance of the Work.

B. Verify suitability of substrates, including surface conditions and compatibility.

C. Begin coating application only after unsatisfactory conditions have been corrected and surfaces are dry.

1. Beginning coating application constitutes Contractor's acceptance of substrates and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions for mixing and preparing materials and as applicable to substrates indicated.

B. Remove plates, machined surfaces, and similar items already in place that are not to be coated. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and coating.

1. After completing coating operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.

C. Clean substrates of substances that could impair bond of coatings, including dirt, oil, grease, incompatible coatings, and loose substrate materials.

D. Cementitious and Masonry Surfaces: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.

E. Crack Repair: Fill cracks according to manufacturer's written instructions before coating surfaces.

1. Cracks Larger Than 1/32 Inch: Cut out static cracks, voids, or honeycombing larger than 1/32 inch and patch with materials recommended in writing by coating manufacturer. Identify dynamic cracks and treat according to manufacturer's written instructions before beginning application.

3.3 APPLICATION

A. Apply coatings according to manufacturer's written instructions. Use applicators and techniques suited for coating and substrate indicated.

1. Dampen substrate of surfaces to receive cementitious coatings one hour before beginning application to prevent surface drag. Immediately before applying coatings, redampen substrate. Substrates shall be saturated and surface dry at time of application.
2. Brushes: Use Tampico or masonry brushes best suited for material being applied.

B. Apply coating to achieve material thickness as recommended in writing by manufacturer, but not less than the following:

1. First Coat: Apply polymer-modified cementitious coating material at the rate of 2 lb/sq. yd. to achieve a total cured thickness of 25 mils.
2. Second Coat: Apply polymer-modified cementitious coating material at the rate of 1 lb/sq. yd. to achieve a total cured thickness of 15 mils.
3. Apply additional coats when undercoats or other conditions show through final coat until cured film is of uniform coating finish, color, and appearance.

C. Brush Application: Brush out and work brush coats into surfaces in an even film, filling all pores and voids at rate recommended in writing by manufacturer to achieve cured material thickness indicated. Finish coat with smooth, horizontal strokes.

3.4 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

B. After completing coating application, clean spattered surfaces. Remove spattered coatings by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

C. Protect work of other trades against damage from coating application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.

D. At completion of construction activities of other trades, touch up and restore damaged or defaced coated surfaces.

3.5 CEMENTITIOUS COATING SCHEDULE

A. Above-Grade Concrete Foundation Walls and Exposed Concrete Building Surfaces:

1. Polymer-Modified Cementitious Coating:

a. Prime Coat: As recommended in writing by topcoat manufacturer.
b. Intermediate Coat: As recommended in writing by topcoat manufacturer.
c. Topcoat: Polymer-modified cementitious coating.

END OF SECTION

SECTION 101423.16 - ROOM-IDENTIFICATION PANEL SIGNAGE

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes room-identification signs that are directly attached to the building.

1.2 DEFINITIONS

A. Accessible: In accordance with the accessibility standard.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Shop Drawings: For room-identification signs.

1. Include fabrication and installation details and attachments to other work.
2. Show sign mounting heights, locations of supplementary supports to be provided by other installers, and accessories.
3. Show message list, typestyles, graphic elements, including raised characters and Braille, and layout for each sign at least half size.

D. Product Schedule: For room-identification signs. Use same designations indicated on Drawings or specified.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

C. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

1.7 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of signs that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Deterioration of finishes beyond normal wear.
b. Separation or delamination of sheet materials and components.

2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Accessibility Standard: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design".

2.2 ROOM-IDENTIFICATION SIGNS

A. Room-Identification Sign : Sign with smooth, uniform surfaces; with message and characters having uniform faces, sharp corners, and precisely formed lines and profiles; and as follows:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ACE Sign Systems, Inc.
b. Advance Corporation
c. Allen Industries
d. APCO Graphics, Inc
e. ASE, Inc
f. ASI Sign Systems, Inc
g. Best Sign Systems, Inc.
h. Clarke Systems
i. Cosco
j. Diskey Sign Company
k. Foresight Supersign
l. inpro Corporation
m. Mohawk Sign Systems
n. Nelson-Harkins Industries
o. Poblocki Sign Company, LLC

p. Seton Identification Products; a Brady Corporation company
q. Signature Signs, Inc.
r. Signs & Decal Corp
s. Vista System, LLC
t. Vomar Products, Inc

2. Laminated-Sheet Sign: Photopolymer face sheet with raised graphics laminated over subsurface graphics to acrylic backing sheet to produce composite sheet.

a. Composite-Sheet Thickness: Manufacturer's standard for size of sign.
b. Color(s): As selected by Architect from manufacturer's full range.

3. Sign-Panel Perimeter: Finish edges smooth.

a. Edge Condition at Vertical Edges at Horizontal Edges: Square cut.
b. Corner Condition in Elevation: Square.

4. Mounting: Manufacturer's standard method for substrates indicated. Provide standoffs for directories.
5. Text and Typeface: Accessible raised characters and Braille where indicated and typeface as indicated. Finish raised characters to contrast with background color, and finish Braille to match background color.

2.3 SIGN MATERIALS

A. Aluminum Extrusions: ASTM B221, alloy and temper recommended by aluminum producer and finisher for type of use and finish indicated.

B. Acrylic Sheet: ASTM D4802, category as standard with manufacturer for each sign, Type UVF (UV filtering).

C. Paints and Coatings for Sheet Materials: Inks, dyes, and paints that are recommended by manufacturer for optimum adherence to surface and are UV and water resistant for colors and exposure indicated.

2.4 ACCESSORIES

A. Standoffs: 5/8 by 3/4 inch modular standoff support in clear satin anodized finish. Include stud cap, standoff spacer/barrel, and coupling anchor.

2.5 FABRICATION

A. General: Provide manufacturer's standard sign assemblies according to requirements indicated.

B. Subsurface-Applied Graphics: Apply graphics to back face of clear face-sheet material to produce precisely formed image. Image shall be free of rough edges.

C. Signs with Changeable Message Capability: Fabricate signs to allow insertion of changeable messages as follows:

1. For slide-in changeable inserts, fabricate slot without burrs or constrictions that inhibit function. Furnish initial changeable insert. Subsequent changeable inserts are by Owner.

2.6 GENERAL FINISH REQUIREMENTS

A. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 INSTALLATION

A. General: Install signs using mounting methods indicated and according to manufacturer's written instructions.

1. Install signs level, plumb, true to line, and at locations and heights indicated, with sign surfaces free of distortion and other defects in appearance.
2. Install signs so they do not protrude or obstruct according to the accessibility standard.
3. Before installation, verify that sign surfaces are clean and free of materials or debris that would impair installation.

B. Accessibility: Install signs in locations on walls as indicated on Drawings and according to the accessibility standard.

C. Mounting Methods:

1. Standoffs: Using a template, drill holes in substrate aligning with studs on back of sign. Remove loose debris from hole and substrate surface.
2. Two-Face Tape: Clean bond-breaking materials from substrate surface and remove loose debris. Apply tape strips symmetrically to back of sign and of suitable quantity to support weight of sign without slippage. Keep strips away from edges to prevent visibility at sign edges. Place sign in position, and push to engage tape adhesive.

3.2 ADJUSTING AND CLEANING

A. Remove and replace damaged or deformed signs and signs that do not comply with specified requirements. Replace signs with damaged or deteriorated finishes or components that cannot be successfully repaired by finish touchup or similar minor repair procedures.

B. Remove temporary protective coverings and strippable films as signs are installed.

C. On completion of installation, clean exposed surfaces of signs according to manufacturer's written instructions, and touch up minor nicks and abrasions in finish. Maintain signs in a clean condition during construction and protect from damage until acceptance by Owner.

END OF SECTION

SECTION 102113.13 - METAL TOILET COMPARTMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Metal toilet compartments.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for blocking.
2. Section 102800 "Toilet, Bath, and Laundry Accessories" for accessories mounted on toilet compartments.

1.2 COORDINATION

A. Coordinate requirements for blocking, reinforcing, and other supports concealed within wall to ensure that toilet compartments can be supported and installed as indicated.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Metal toilet compartments.

a. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for toilet compartments.

C. Shop Drawings:

1. Include plans, elevations, sections, and attachment details.
2. Show locations of cutouts for compartment-mounted toilet accessories.
3. Show locations of reinforcements for compartment-mounted grab bars and locations of blocking for surface-mounted toilet accessories.
4. Show locations of centerlines of toilet fixtures.
5. Show locations of floor drains.

D. Samples for Initial Selection: Manufacturer's standard color sheets, showing full range of available colors for each type of toilet compartment.

1. Include Samples of hardware and accessories involving material and color selection.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For toilet compartments.

1.5 FIELD CONDITIONS

A. Field Measurements: Verify actual locations of toilet fixtures, walls, columns, ceilings, and other construction contiguous with toilet compartments by field measurements, and coordinate before fabrication.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain metal toilet compartments from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: 75 or less.
2. Smoke-Developed Index: 450 or less.

B. Structural Performance: Where grab bars are mounted on toilet compartments, design panels to comply with the following requirements:

1. Panels are able to withstand a concentrated load on grab bar of at least 250 lbf applied at any direction and at any point, without deformation of panel.

C. Regulatory Requirements: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" for toilet compartments designated as accessible.

2.3 METAL TOILET COMPARTMENTS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. American Sanitary Partition Corporation
2. ASI Accurate Partitions
3. ASI Global Partitions
4. Bradley Corporation
5. General Partitions Mfg. Corp
6. Hadrian Inc.; Zurn Industries, LLC

7. Metpar Corp

B. Toilet-Enclosure Style: Overhead braced.

C. Urinal-Screen Style: Wall hung with integral flanges.

D. Door, Panel, and Pilaster Construction: Seamless, metal facing sheets pressure laminated to core material; with continuous, interlocking molding strip or lapped-and-formed edge closures; corners secured by welding or clips and exposed welds ground smooth. Provide with no-sightline system consisting of a full-height continuous stop on latch side of door and full-height continuous filler strip on hinge side of door (unless continuous hinge is used). Exposed surfaces shall be free of pitting, seam marks, roller marks, stains, discolorations, telegraphing of core material, or other imperfections.

1. Core Material: Manufacturer's standard sound-deadening honeycomb of resin-impregnated kraft paper in thickness required to provide finished thickness of 1 inch for doors and panels and 1-1/4 inches for pilasters.
2. Grab-Bar Reinforcement: Provide concealed internal reinforcement for grab bars mounted on units of size and material adequate for panel to withstand specified structural performance requirements.
3. Tapping Reinforcement: Provide concealed reinforcement for tapping (threading) at locations where machine screws are used for attaching items to units.

E. Urinal-Screen Construction:

1. Integral-Flange, Wall-Hung Urinal Screen: Similar to panel construction, with integral full-height flanges for wall attachment, and maximum 1-1/4 inches thick.

F. Facing Sheets and Closures: Electrolytically coated steel or hot-dip galvanized-steel sheet with nominal base-metal (uncoated) thicknesses as follows:

1. Pilasters, Braced at Both Ends: Manufacturer's standard thickness, but not less than 0.036 inch.
2. Panels: Manufacturer's standard thickness, but not less than 0.030 inch.
3. Doors: Manufacturer's standard thickness, but not less than 0.030 inch.
4. Integral-Flange, Wall-Hung Urinal Screens: Manufacturer's standard thickness, but not less than 0.030 inch.

G. Pilaster Shoes: Formed from stainless steel sheet, not less than 0.031-inch nominal thickness and 3 inches high, finished to match hardware.

H. Brackets (Fittings):

1. Stirrup Type: Ear or U-brackets; stainless steel.

I. Steel Sheet Finish: Immediately after cleaning and pretreating, apply manufacturer's standard baked-on finish, including thermosetting, electrostatically applied, and powder coatings. Apply one color in each room.

1. Color: As selected by Architect from manufacturer's full range.

2.4 HARDWARE AND ACCESSORIES

A. Door Hardware and Accessories: Manufacturer's operating hardware and accessories.

1. Hinges:

a. Manufacturer's continuous, cam type that swings to a closed or partially open position, allowing emergency access by lifting door.

1) Material, Continuous, Cam-Type Hinge: Stainless steel.

2. Latch and Keeper: Manufacturer's surface-mounted latch unit designed for emergency access and with combination rubber-faced door strike and keeper. Provide units that comply with regulatory requirements for accessibility at toilet enclosures designated as accessible.

a. Material: Manufacturer's standard.

3. Coat Hook: Manufacturer's combination hook and rubber-tipped bumper, sized to prevent inswinging door from hitting compartment-mounted accessories.

a. Material: Manufacturer's standard.

4. Door Bumper: Manufacturer's rubber-tipped bumper at outswinging doors.

a. Material: Manufacturer's standard.

5. Door Pull: Manufacturer's unit at outswinging doors that complies with regulatory requirements for accessibility. Provide units on both sides of doors at toilet enclosures designated as accessible.

a. Material: Manufacturer's standard.

B. Overhead Bracing: Manufacturer's standard continuous, extruded-aluminum head rail with antigrip profile and in manufacturer's standard finish.

C. Anchorages and Fasteners: Manufacturer's standard exposed fasteners of stainless steel, finished to match items they are securing, with theft-resistant-type heads. Provide sex-type bolts for through-bolt applications. For concealed anchors, use stainless steel, hot-dip galvanized steel, or other rust-resistant, protective-coated steel compatible with related materials.

2.5 MATERIALS

A. Aluminum Castings: ASTM B26/B26M.

B. Aluminum Extrusions: ASTM B221.

C. Steel Sheet: Commercial steel sheet for exposed applications; mill phosphatized and selected for smoothness.

1. Electrolytically Zinc Coated: ASTM A879/A879M, 01Z.

2. Hot-Dip Galvanized: ASTM A653/A653M, either hot-dip galvanized or galvannealed.

D. Stainless Steel Castings: ASTM A743/A743M.

E. Zamac: ASTM B86, commercial zinc-alloy die castings, chrome plated.

2.6 FABRICATION

A. Fabricate toilet compartment components to sizes indicated. Coordinate requirements and provide cutouts for through-partition toilet accessories, and solid blocking within panel where required for attachment of toilet accessories.

B. Overhead-Braced Units: Manufacturer's standard corrosion-resistant supports, leveling mechanism, and anchors at pilasters and walls to suit floor and wall conditions. Provide shoes at pilasters to conceal supports and leveling mechanism.

C. Door Size and Swings: Unless otherwise indicated, provide 24-inch-wide, inswinging doors for standard toilet enclosures and 36-inch-wide, outswinging doors with a minimum 32-inch-wide, clear opening for toilet enclosures designated as accessible.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas and conditions, with Installer present, for compliance with requirements for fastening, support, alignment, operating clearances, and other conditions affecting performance of the Work.

1. Confirm location and adequacy of blocking and supports required for installation.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General: Comply with manufacturer's written installation instructions. Install units rigid, straight, level, and plumb. Secure units in position indicated with manufacturer's recommended anchoring devices.

1. Maximum Clearances:

a. Pilasters and Panels or Screens: 1/2 inch.
b. Panels or Screens and Walls: 1 inch.

2. Stirrup Brackets: Secure panels or screens to walls and to pilasters with no fewer than three brackets attached at midpoint and near top and bottom of panel.

a. Locate wall brackets so holes for wall anchors occur in masonry or tile joints.
b. Align brackets at pilasters with brackets at walls.

3. Full-Height (Continuous) Brackets: Secure doors to pilasters with full-height brackets.

a. Align brackets at pilasters with brackets at walls.

B. Overhead-Braced Units: Secure pilasters to floor and level, plumb, and tighten. Set pilasters with anchors penetrating not less than 1-3/4 inches into structural floor unless otherwise indicated in manufacturer's written instructions. Secure continuous head rail to each pilaster with no fewer than two fasteners. Hang doors to align tops of doors with tops of panels, and adjust so tops of doors are parallel with overhead brace when doors are in closed position.

C. Urinal Screens: Attach with anchoring devices to suit supporting structure. Set units level and plumb, rigid, and secured to resist lateral impact.

3.3 ADJUSTING

A. Hardware Adjustment: Adjust and lubricate hardware in accordance with hardware manufacturer's written instructions for proper operation. Set hinges on inswinging doors to hold doors open approximately 30 degrees from closed position when unlatched. Set hinges on outswinging doors to return doors to fully closed position.

END OF SECTION

SECTION 102239 - FOLDING PANEL PARTITIONS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Operable acoustical panel partitions.

B. Related Requirements:

1. Section 055000 "Metal Fabrications" for supports that attach supporting tracks to overhead structural system.

1.2 DEFINITIONS

A. NIC: Noise Isolation Class.

B. NRC: Noise Reduction Coefficient.

C. STC: Sound Transmission Class.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Operable acoustical panel partitions.

C. Shop Drawings: For operable panel partitions.

1. Include plans, elevations, sections, attachment details, and numbered panel installation sequence.
2. Indicate stacking and operating clearances. Indicate location and installation requirements for hardware and track, blocking, and direction of travel.

D. Samples for Verification: For each type of exposed material, finish, covering, or facing, prepared on Samples of size indicated below:

1. Textile Facing Material: Full width by not less than 36-inch-long section of carpet from dye lot to be used for the Work, with specified treatments applied. Show complete pattern repeat.
2. Panel Facing Material: Manufacturer's standard-size unit, not less than 3 inches square.
3. Panel Edge Material: Not less than 3 inches long.
4. Chair Rail: Manufacturer's standard-size unit, 6 inches long.

5. Hardware: One of each exposed door-operating device.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Partition track, track supports and bracing, switches, turning space, and storage layout.
2. Suspended ceiling components.
3. Structural members to which suspension systems will be attached.
4. Size and location of initial access modules for acoustical tile.
5. Items penetrating finished ceiling including the following:

    a. Lighting fixtures.
    b. HVAC ductwork, outlets, and inlets.
    c. Speakers.
    d. Sprinklers.
    e. Smoke detectors.
    f. Access panels.

6. Plenum acoustical barriers.

C. Setting Drawings: For embedded items and cutouts required in other work, including support-beam, mounting-hole template.

D. Qualification Data: For Installer.

E. Seismic Qualification Certificates: For operable panel partitions, tracks, accessories, and components, from manufacturer. Include seismic capacity of partition assemblies to remain in vertical position during a seismic event and the following:

1. Basis for Certification: Indicate whether certification is based on analysis, testing, or experience data, in accordance with ASCE/SEI 7.
2. Detailed description of partition anchorage devices on which the certification is based and their installation requirements.

F. Product Test Reports: For each operable panel partition, for tests performed by a qualified testing agency.

G. Field quality-control reports.

H. Sample Warranty: For manufacturer's special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For operable panel partitions to include in maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. Panel finish facings and finishes for exposed trim and accessories. Include precautions for cleaning materials and methods that could be detrimental to finishes and performance.
b. Seals, hardware, track, track switches, carriers, and other operating components.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Protectively package and sequence panels in order for installation. Clearly mark packages and panels with numbering system used on Shop Drawings. Do not use permanent markings on panels.

1.8 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of operable panel partitions that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Faulty operation of operable panel partitions.
b. Deterioration of metals, metal finishes, and other materials beyond normal use.

2. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Seismic Performance: Operable panel partitions are to withstand the effects of earthquake motions determined in accordance with ASCE/SEI 7.

1. The term "withstand" means "the partition panels will remain in place without separation of any parts when subjected to the seismic forces specified."

B. Acoustical Performance: Provide operable panel partitions tested by a qualified testing agency for the following acoustical properties in accordance with test methods indicated:

1. Sound-Transmission Requirements: Operable panel partition assembly tested for laboratory sound-transmission loss performance in accordance with ASTM E90, determined by ASTM E413, and rated for not less than the STC indicated.
2. Noise-Reduction Requirements: Operable panel partition assembly, identical to partition tested for STC, tested for sound-absorption performance in accordance with ASTM C423, and rated for not less than the NRC indicated.
3. Noise-Isolation Requirements: Installed operable panel partition assembly, identical to partition tested for STC, tested for NIC in accordance with ASTM E336, determined by ASTM E413, and rated for 10 dB less than STC value indicated.

C. Fire-Test-Response Characteristics: Provide panels with finishes complying with one of the following as determined by testing identical products by a testing and inspecting agency acceptable to authorities having jurisdiction:

1. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

a. Flame-Spread Index: 25 or less.
b. Smoke-Developed Index: 450 or less.

2.2 OPERABLE ACOUSTICAL PANEL PARTITIONS

A. Operable Acoustical Panel Partitions : Partition system, including panels, seals, finish facing, suspension system, operators, and accessories.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Advanced Equipment Corporation
b. KWIK-WALL Company
c. Moderco Inc
d. Modernfold, Inc.

B. Panel Operation: Manually operated, paired panels.

C. Panel Construction: As required to support panel from suspension components and with reinforcement for hardware attachment. Fabricate panels with tight hairline joints and concealed fasteners. Fabricate panels so finished in-place partition is rigid; level; plumb; aligned, with tight joints and uniform appearance; and free of bow, warp, twist, deformation, and surface and finish irregularities.

D. Dimensions: Fabricate operable acoustical panel partitions to form an assembled system of dimensions indicated and verified by field measurements.

1. Panel Width: Standard widths.

E. STC: Not less than 50.

F. NRC: Not less than 0.50.

G. Panel Weight: 8 lb/sq. ft. maximum.

H. Panel Thickness: Nominal dimension of 3 inches.

I. Panel Materials:

1. Steel Frame: Steel sheet, manufacturer's standard nominal minimum thickness for uncoated steel.
2. Steel Face/Liner Sheets: Tension-leveled steel sheet, manufacturer's standard minimum nominal thickness for uncoated steel.
3. Gypsum Board: ASTM C1396/C1396M.

J. Panel Closure: Manufacturer's standard unless otherwise indicated.

1. Initial Closure: Resilient, bulb-shaped acoustical seal.
2. Final Closure: Constant-force, lever-operated mechanical closure expanding from panel edge to create a constant-pressure acoustical seal.

K. Hardware: Manufacturer's standard as required to operate operable panel partition and accessories; with decorative, protective finish.

1. Hinges: Manufacturer's standard.

L. Finish Facing: Fabric wall covering.

2.3 SEALS

A. Description: Seals that produce operable panel partitions complying with performance requirements and the following:

1. Manufacturer's standard seals unless otherwise indicated.
2. Seals made from materials and in profiles that minimize sound leakage.
3. Seals fitting tight at contact surfaces and sealing continuously between adjacent panels and between operable panel partition perimeter and adjacent surfaces, when operable panel partition is extended and closed.

B. Horizontal Top Seals: Continuous-contact, resilient seal exerting uniform constant pressure on track.

C. Horizontal Bottom Seals:

1. Resilient, mechanical, retractable, constant-force-contact seal exerting uniform constant pressure on floor when extended, ensuring horizontal and vertical sealing and resisting panel movement.

a. Automatically Operated for Acoustical Panels: Extension and retraction of bottom seal automatically operated by movement of partition, with operating range not less than 2 inches between retracted seal and floor finish.

2.4 PANEL FINISH FACINGS

A. Description: Finish facings for panels that comply with indicated fire-test-response characteristics and that are factory applied to operable panel partitions with appropriate backing, using mildew-resistant nonstaining adhesive as recommended by facing manufacturer's written instructions.

1. Apply one-piece, seamless facings free of air bubbles, wrinkles, blisters, and other defects, with edges tightly butted, and with no gaps or overlaps. Horizontal seams are not permitted. Tightly secure and conceal raw and selvage edges of facing for finished appearance.

B. Fabric Wall Covering: Manufacturer's standard fabric, from same dye lot, treated to resist stains.

1. Color/Pattern: As selected by Architect from manufacturer's full range.

C. Trimless Edges: Fabricate exposed panel edges so finish facing wraps uninterrupted around panel, covering edge and resulting in an installed partition with facing visible on vertical panel edges, without trim, for minimal sightlines at panel-to-panel joints.

2.5 SUSPENSION SYSTEMS

A. Tracks: Steel or aluminum with adjustable steel hanger rods for overhead support, designed for operation, size, and weight of operable panel partition indicated. Size track to support partition operation and storage without damage to suspension system, operable panel partitions, or adjacent construction. Limit track deflection to no more than 0.10 inch between bracket supports. Provide a continuous system of track sections and accessories to accommodate configuration and layout indicated for partition operation and storage.

B. Carriers: Trolley system as required for configuration type, size, and weight of partition and for easy operation; with ball-bearing wheels.

C. Track Intersections, Switches, and Accessories: As required for operation, storage, track configuration, and layout indicated for operable panel partitions, and compatible with partition assembly specified. Fabricate track intersections and switches from steel or aluminum.

D. Steel Finish: Manufacturer's standard, factory-applied, corrosion-resistant, protective coating unless otherwise indicated.

2.6 ACCESSORIES

A. Pass Doors: Swinging door built into and matching panel materials, construction, acoustical qualities, finish and thickness, complete with frames and operating hardware. Hinges finished to match other exposed hardware.

1. Accessibility Standard: Fabricate doors to comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.
2. Single Pass Door: 36 by 80 inches.
3. Pass-Door Hardware: Equip pass door with the following:

a. Door Seals: Mechanically operated floor seal on panels containing pass doors.
b. Panic hardware.
c. Concealed door closer.
d. Door Viewer: Installed with view in direction of swing.
e. Exit Sign: Recessed, self-illuminated.
f. Latchset: Passage set.

B. Storage Pocket Door: Full height at end of partition runs to conceal stacked partition; of same materials, finish, construction, thickness, and acoustical qualities as panels; complete with operating hardware and acoustical seals at soffit, floor, and jambs. Hinges in finish to match other exposed hardware.

1. Manufacturer's standard method to secure storage pocket door in closed position.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine flooring, floor levelness, structural support, and opening, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of operable panel partitions.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF OPERABLE PANEL PARTITIONS

A. Install operable panel partitions and accessories after other finishing operations, including painting, have been completed in area of partition installation.

B. Install panels in numbered sequence indicated on Shop Drawings.

C. Broken, cracked, chipped, deformed, or unmatched panels are not acceptable.

D. Broken, cracked, deformed, or unmatched gasketing or gasketing with gaps at butted ends is not acceptable.

3.3 ADJUSTING

A. Adjust operable panel partitions, hardware, and other moving parts to function smoothly, and lubricate as recommended by manufacturer.

B. Adjust pass doors and storage pocket doors to operate smoothly and easily, without binding or warping.

C. Verify that safety devices are properly functioning.

3.4 MAINTENANCE SERVICE

A. Maintenance Service: Beginning at Substantial Completion, maintenance service is to include six months' full maintenance by manufacturer's authorized service representative. Include quarterly preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper operable-partition operation. Parts and supplies are to be manufacturer's authorized replacement parts and supplies.

3.5 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain operable panel partitions.

END OF SECTION

SECTION 102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Public-use washroom accessories.
2. Childcare accessories.
3. Underlavatory guards.

1.2 COORDINATION

A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.

B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Include anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.

C. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.

1. Identify locations using room designations indicated.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Sample Warranty: For manufacturer's special warranties.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For accessories to include in maintenance manuals.

1.6 WARRANTY

A. Manufacturer's Special Warranty for Mirrors: Manufacturer agrees to repair or replace mirrors that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, visible silver spoilage defects.
2. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Structural Performance: Design accessories and fasteners to comply with the following requirements:

1. Grab Bars: Installed units are able to resist 250 lbf concentrated load applied in any direction and at any point.

2.2 PUBLIC-USE WASHROOM ACCESSORIES

A. Source Limitations: Obtain each type of public-use washroom accessory from single source from single manufacturer.

B. Toilet Tissue (Roll) Dispenser:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Impact’s #2519, or a comparable product by one of the following:

a. AJW Architectural Products.
b. American Specialties, Inc. (ASI).
c. Bradley Corporation.
d. Brey-Krause Manufacturing Co.
e. GAMCO Specialty Accessories; a division of Bobrick.
f. Seachrome Corporation.
g. Tubular Specialties Manufacturing, Inc.

2. Description: Double-roll dispenser.
3. Mounting: Surface mounted.
4. Operation: Noncontrol delivery with theft-resistant spindle.
5. Capacity: Designed for 5-inch- diameter tissue rolls.
6. Material and Finish: Heavy-gauge metal back with see through plastic front.

C. Paper Towel (Folded) Dispenser:

1. Basis-of-Design Product: Subject to compliance with requirements, provide San Jamar's Ultrafold #T1700BK, or a comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc. (ASI).
    c. Bradley Corporation.
    d. GAMCO Specialty Accessories; a division of Bobrick.

2. Mounting: Surface mounted.
3. Minimum Capacity: Holds 240 C-fold or 400 multi-fold.
4. Material and Finish: ABS plastic, gray.

D. Soap Dispenser:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Spartan's Black Foaming ManualDispenser, #975700, or a comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc. (ASI).
    c. Bradley Corporation.
    d. Brey-Krause Manufacturing Co.
    e. GAMCO Specialty Accessories; a division of Bobrick.

2. Description: Designed for manual operation and dispensing soap in lather form.
3. Mounting: Surface mounted.
4. Capacity: 34 oz.
5. Materials: ABS plastic.

E. Grab Bar:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc. (ASI).
    c. Bobrick Washroom Equipment, Inc.
    d. Bradley Corporation.
    e. Brey-Krause Manufacturing Co.
    f. GAMCO Specialty Accessories; a division of Bobrick.
    g. Oatey.
    h. Seachrome Corporation.
    i. Tubular Specialties Manufacturing, Inc.

2. Mounting: Flanges with concealed fasteners.
3. Material: Stainless steel, 0.05 inch thick.

    a. Finish: Smooth, ASTM A480/A480M No. 4 finish (satin).

4. Outside Diameter: 1-1/4 inches.

5. Configuration and Length: As indicated on Drawings.

F. Sanitary-Napkin Disposal Unit:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Rubbermaid's #6140, or a comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc. (ASI).
    c. Bobrick Washroom Equipment, Inc.
    d. Bradley Corporation.
    e. Brey-Krause Manufacturing Co.
    f. GAMCO Specialty Accessories; a division of Bobrick.
    g. Seachrome Corporation.
    h. Tubular Specialties Manufacturing, Inc.

2. Mounting: Surface mounted.
3. Door or Cover: Self-closing, disposal-opening cover and hinged face panel.
4. Receptacle: Removable.
5. Material and Finish: Plastic.

G. Mirror Unit:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc. (ASI).
    c. Bobrick Washroom Equipment, Inc.
    d. Bradley Corporation.
    e. Brey-Krause Manufacturing Co.
    f. GAMCO Specialty Accessories; a division of Bobrick.
    g. Seachrome Corporation.
    h. Tubular Specialties Manufacturing, Inc.

2. Frame: Stainless steel angle, 0.05 inch thick.

    a. Corners: Welded and ground smooth.

3. Size: As indicated on Drawings.
4. Hangers: Manufacturer's standard rigid, tamper and theft resistant.

H. Hook:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc. (ASI).
    c. Bobrick Washroom Equipment, Inc.
    d. Bradley Corporation.
    e. Brey-Krause Manufacturing Co.

f. GAMCO Specialty Accessories; a division of Bobrick.
g. Seachrome Corporation.
h. Tubular Specialties Manufacturing, Inc.

2. Description: Single-prong unit.
3. Mounting: Concealed.
4. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

I. Sanitary-Napkin and Tampon Vendor:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Hospeco's #D1-25C, or comparable product by one of the following:

a. ASI-American Specialties, Inc.
b. Bobrick Washroom Equipment, Inc
c. Bradley Corporation
d. Gamco Commercial Restroom Accessories; Bobrick Washroom Equipment, Inc.
e. Tubular Specialties Manufacturing, Inc.

2. Mounting: Surface mounted.
3. Capacity: 15 #4 box sanitary napkins; 25 tampons.
4. Operation: Single coin (25 cents).
5. Exposed Material and Finish: Painted metal.
6. Lockset: Tumbler type with separate lock and key for coin box.

J. Seat-Cover Dispenser:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Kimberly Clark's #09506, or comparable product by one of the following:

a. ASI-American Specialties, Inc.
b. Bobrick Washroom Equipment, Inc
c. Bradley Corporation
d. Brey-Krause Manufacturing Co.
e. Gamco Commercial Restroom Accessories; Bobrick Washroom Equipment, Inc.
f. Seachrome Corporation
g. Tubular Specialties Manufacturing, Inc.

2. Mounting: Surface mounted.
3. Minimum Capacity: 125 seat covers.
4. Exposed Material and Finish: ABS plastic.
5. Lockset: Tumbler type.

2.3 CHILDCARE ACCESSORIES

A. Diaper-Changing Station:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. American Specialties, Inc. (ASI).

b. Bradley Corporation.
c. Diaper Deck & Company, Inc.
d. Foundations Worldwide, Inc.
e. GAMCO Specialty Accessories; a division of Bobrick.
f. Koala Kare Products; a Division of Bobrick.
g. SafeStrap Company, Inc. (SSC, Inc.).
h. Tubular Specialties Manufacturing, Inc.

2. Description: Horizontal unit that opens by folding down from stored position and with child-protection strap.

a. Engineered to support minimum of 250-lb static load when opened.

3. Mounting: Surface mounted, with unit projecting not more than 4 inches from wall when closed.
4. Operation: By pneumatic shock-absorbing mechanism.
5. Material and Finish: HDPE with plastic-laminate insert in color selected by Architect.
6. Liner Dispenser: Provide built-in dispenser for disposable sanitary liners.

2.4 UNDERLAVATORY GUARDS

A. Underlavatory Guard:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Buckaroos, Inc.
b. Plumberex Specialty Products, Inc.
c. Truebro by IPS Corporation.

2. Description: Insulating pipe covering for supply and drain piping assemblies that prevents direct contact with and burns from piping; allow service access without removing coverings.
3. Material and Finish: Antimicrobial, molded plastic, white.

2.5 MATERIALS

A. Stainless Steel: ASTM A240/A240M or ASTM A666, Type 304, 0.031-inch-minimum nominal thickness unless otherwise indicated.

B. Steel Sheet: ASTM A1008/A1008M, Designation CS (cold rolled, commercial steel), 0.036-inch-minimum nominal thickness.

C. Galvanized-Steel Sheet: ASTM A653/A653M, with G60 hot-dip zinc coating.

D. Galvanized-Steel Mounting Devices: ASTM A153/A153M, hot-dip galvanized after fabrication.

E. Fasteners: Screws, bolts, and other devices of same material as accessory unit, unless otherwise recommended by manufacturer or specified in this Section, and tamper and theft resistant where exposed, and of stainless or galvanized steel where concealed.

F. Chrome Plating: ASTM B456, Service Condition Number SC 2 (moderate service).

G. Mirrors: ASTM C1503, Mirror Glazing Quality, clear-glass mirrors, nominal 6.0 mm thick.

2.6 FABRICATION

A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.

B. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.

1. Remove temporary labels and protective coatings.

B. Grab Bars: Install to comply with specified structural-performance requirements.

3.2 ADJUSTING AND CLEANING

A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.

B. Clean and polish exposed surfaces according to manufacturer's written instructions.

END OF SECTION

SECTION 104413 - FIRE PROTECTION CABINETS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Fire-protection cabinets for the following:

a. Portable fire extinguisher-non-rated cabinet.
b. Portable fire extinguisher-fire-rated cabinet (match fire rating of installed wall).

B. Related Requirements:

1. Section 104416 "Fire Extinguishers" for portable, hand-carried fire extinguishers accommodated by fire-protection cabinets.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Show door hardware, cabinet type, trim style, and panel style. Include roughing-in dimensions and details showing recessed-, semirecessed-, or surface-mounting method and relationships of box and trim to surrounding construction.

C. Shop Drawings: For fire-protection cabinets.

1. Include plans, elevations, sections, details, and attachments to other work.

D. Samples: For each type of exposed finish required.

E. Product Schedule: For fire-protection cabinets. Indicate whether recessed, semirecessed, or surface mounted. Coordinate final fire-protection cabinet schedule with fire-extinguisher schedule to ensure proper fit and function.

1.3 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For fire-protection cabinets to include in maintenance manuals.

1.4 COORDINATION

A. Coordinate size of fire-protection cabinets to ensure that type and capacity of fire extinguishers indicated are accommodated.

B. Coordinate sizes and locations of fire-protection cabinets with wall depths.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Rated Fire-Protection Cabinets: Listed and labeled to comply with requirements in ASTM E814 for fire-resistance rating of walls where they are installed.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 FIRE-PROTECTION CABINET

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Babcock-Davis
2. Croker; a Division of Morris Group International
3. Guardian Fire Equipment, Inc
4. JL Industries; Activar Construction Products Group, Inc.
5. Larsen's Manufacturing Company
6. Modern Metal Products
7. MOON American, Inc.
8. Nystrom, Inc.
9. Potter Roemer LLC; a Division of Morris Group International
10. Strike First Corporation of America

B. Fire-Protection Cabinet Type: Suitable for fire extinguisher.

C. Cabinet Construction: Nonrated, One-hour fire rated, two-hour fire rated.

1. Fire-Rated Cabinets: Construct fire-rated cabinets with double walls fabricated from 0.043-inch-thick cold-rolled steel sheet lined with minimum 5/8-inch-thick fire-barrier material. Provide factory-drilled mounting holes.

D. Cabinet Material: Cold-rolled steel sheet.

E. Recessed Cabinet:

1. Exposed Flat Trim: One-piece combination trim and perimeter door frame overlapping surrounding wall surface, with exposed trim face and wall return at outer edge (backbend).

F. Semirecessed Cabinet at Fire Rated Walls: One-piece combination trim and perimeter door frame overlapping surrounding wall surface, with exposed trim face and wall return at outer edge (backbend).

1. Square-Edge Trim: 1-1/4- to 1-1/2-inch backbend depth.

G. Cabinet Trim Material: Steel sheet.

H. Door Material: Steel sheet.

I. Door Style: Vertical duo panel with frame.

J. Door Glazing: Tempered float glass (clear).

K. Door Hardware: Manufacturer's standard door-operating hardware of proper type for cabinet type, trim style, and door material and style indicated.

1. Provide manufacturer's standard.
2. Provide manufacturer's standard hinge, permitting door to open 180 degrees.

L. Accessories:

1. Mounting Bracket: Manufacturer's standard steel, designed to secure fire extinguisher to fire-protection cabinet, of sizes required for types and capacities of fire extinguishers indicated, with plated or baked-enamel finish.
2. Door Lock: Cam lock that allows door to be opened during emergency by pulling sharply on door handle.
3. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as directed by Architect.

a. Identify fire extinguisher in fire-protection cabinet with the words "FIRE EXTINGUISHER."

1) Location: Applied to cabinet door.
2) Application Process: Pressure-sensitive vinyl letters.
3) Lettering Color: White.
4) Orientation: Vertical.

M. Materials:

1. Cold-Rolled Steel: ASTM A1008/A1008M, Commercial Steel (CS), Type B.

a. Finish: Baked enamel, TGIC polyester powder coat, HAA polyester powder coat, epoxy powder coat, or polyester/epoxy hybrid powder coat, complying with AAMA 2603.
b. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
c. Color: As selected by Architect from manufacturer's full range.

2. Tempered Float Glass: ASTM C1048, Kind FT, Condition A, Type I, Quality q3, 3 mm thick, Class 1 (clear).

2.3 FABRICATION

A. Fire-Protection Cabinets: Provide manufacturer's standard box (tub) with trim, frame, door, and hardware to suit cabinet type, trim style, and door style indicated.

1. Weld joints and grind smooth.
2. Miter corners and grind smooth.
3. Provide factory-drilled mounting holes.
4. Prepare doors and frames to receive locks.

B. Cabinet Doors: Fabricate doors according to manufacturer's standards, from materials indicated and coordinated with cabinet types and trim styles.

1. Fabricate door frames with tubular stiles and rails and hollow-metal design, minimum 1/2 inch thick.
2. Fabricate door frames of one-piece construction with edges flanged.
3. Miter and weld perimeter door frames and grind smooth.

C. Cabinet Trim: Fabricate cabinet trim in one piece with corners mitered, welded, and ground smooth.

2.4 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM's AMP 500, "Metal Finishes Manual for Architectural and Metal Products," for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces of fire-protection cabinets from damage by applying a strippable, temporary protective covering before shipping.

C. Finish fire-protection cabinets after assembly.

D. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in for hose valves and cabinets to verify actual locations of piping connections before cabinet installation.

B. Examine walls and partitions for suitable framing depth and blocking where recessed and semirecessed cabinets will be installed.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Prepare recesses for recessed and semirecessed fire-protection cabinets as required by type and size of cabinet and trim style.

3.3 INSTALLATION OF FIRE-PROTECTION CABINETS

A. General: Install fire-protection cabinets in locations and at mounting heights indicated or, if not indicated, at heights acceptable to authorities having jurisdiction.

1. Fire-Protection Cabinet Mounting Height: 42 inches above finished floor to top of fire extinguisher.

B. Fire-Protection Cabinets: Fasten cabinets to structure, square and plumb.

1. Unless otherwise indicated, provide recessed fire-protection cabinets. If wall thickness is inadequate for recessed cabinets, provide semirecessed fire-protection cabinets.
2. Fasten mounting brackets to inside surface of fire-protection cabinets, square and plumb.

C. Identification:

1. Apply vinyl lettering at locations indicated.

3.4 ADJUSTING AND CLEANING

A. Remove temporary protective coverings and strippable films, if any, as fire-protection cabinets are installed unless otherwise indicated in manufacturer's written installation instructions.

B. Adjust fire-protection cabinet doors to operate easily without binding. Verify that integral locking devices operate properly.

C. On completion of fire-protection cabinets installation, clean interior and exterior surfaces as recommended by manufacturer.

D. Touch up marred finishes, or replace fire-protection cabinets that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by fire-protection cabinet and mounting bracket manufacturers.

E. Replace fire-protection cabinets that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION

SECTION 104416 - FIRE EXTINGUISHERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes portable, hand-carried fire extinguishers and mounting brackets for fire extinguishers.

B. Related Requirements:

1. Section 104413 "Fire Protection Cabinets."

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. Include rating and classification, material descriptions, dimensions of individual components and profiles, and finishes for fire extinguisher and mounting brackets.

C. Product Schedule: For fire extinguishers. Coordinate final fire-extinguisher schedule with fire-protection cabinet schedule to ensure proper fit and function.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Warranty: Sample of special warranty.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For fire extinguishers to include in maintenance manuals.

1.5 COORDINATION

A. Coordinate type and capacity of fire extinguishers with fire-protection cabinets to ensure fit and function.

1.6 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace fire extinguishers that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Failure of hydrostatic test according to NFPA 10 when testing interval required by NFPA 10 is within the warranty period.
b. Faulty operation of valves or release levers.

2. Warranty Period: Six years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. NFPA Compliance: Fabricate and label fire extinguishers to comply with NFPA 10, "Portable Fire Extinguishers."

B. Fire Extinguishers: Listed and labeled for type, rating, and classification by an independent testing agency acceptable to authorities having jurisdiction.

1. Provide fire extinguishers approved, listed, and labeled by FM Global.

2.2 PORTABLE, HAND-CARRIED FIRE EXTINGUISHERS

A. Fire Extinguishers: Type, size, and capacity for each fire-protection cabinet and mounting bracket indicated.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Amerex Corporation
b. Ansul; brand of Johnson Controls International plc, Building Solutions North America
c. Babcock-Davis
d. Badger Fire Protection; a Carrier company
e. Buckeye Fire Equipment Company
f. Croker; a Division of Morris Group International
g. Guardian Fire Equipment, Inc
h. JL Industries; Activar Construction Products Group, Inc.
i. Kidde; Carrier Global Corporation
j. Larsen's Manufacturing Company
k. MOON American, Inc.
l. Nystrom, Inc.
m. Potter Roemer LLC; a Division of Morris Group International

n. Pyro-Chem; brand of Johnson Controls International plc, Building Solutions North America
o. Strike First Corporation of America

2. Valves: Manufacturer's standard.
3. Handles and Levers: Manufacturer's standard.
4. Instruction Labels: Include pictorial marking system complying with NFPA 10, Appendix B, and bar coding for documenting fire-extinguisher location, inspections, maintenance, and recharging.

B. Multipurpose Dry-Chemical Type in Steel Container : UL-rated 4-A:60-B:C, 10-lb nominal capacity, with monoammonium phosphate-based dry chemical in enameled-steel container.

C. Carbon Dioxide Type in Steel Container: U.S. DOT (Department of Transportation) approved carbon dioxide (CO2) type fire extinguisher bearing a UL (Underwriters Laboratories) rating mounted in a semi-recessed fire rated cabinet outside of the Telecom MDF and IDF Rooms 142, 220, 318, immediately adjacent to the handle side of the entrance door.

2.3 MOUNTING BRACKETS

A. Mounting Brackets: Manufacturer's standard galvanized steel, designed to secure fire extinguisher to wall or structure, of sizes required for types and capacities of fire extinguishers indicated, with plated or red baked-enamel finish.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Amerex Corporation
b. Ansul; brand of Johnson Controls International plc, Building Solutions North America
c. Babcock-Davis
d. Badger Fire Protection; a Carrier company
e. Buckeye Fire Equipment Company
f. Croker; a Division of Morris Group International
g. Guardian Fire Equipment, Inc
h. JL Industries; Activar Construction Products Group, Inc.
i. Kidde; Carrier Global Corporation
j. Larsen's Manufacturing Company
k. Nystrom, Inc.
l. Potter Roemer LLC; a Division of Morris Group International
m. Pyro-Chem; brand of Johnson Controls International plc, Building Solutions North America
n. Strike First Corporation of America

2. Source Limitations: Obtain mounting brackets and fire extinguishers from single source from single manufacturer.

B. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated by Architect.

1. Identify bracket-mounted fire extinguishers with the words "FIRE EXTINGUISHER" in red letter decals applied to mounting surface.

    a. Orientation: Vertical.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine fire extinguishers for proper charging and tagging.

1. Remove and replace damaged, defective, or undercharged fire extinguishers.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General: Install fire extinguishers and mounting brackets in locations indicated and in compliance with requirements of authorities having jurisdiction.

B. Mounting Brackets: Fasten mounting brackets to surfaces, square and plumb, at locations indicated.

1. Mounting Height: Top of fire extinguisher to be at 42 inches above finished floor.

END OF SECTION

SECTION 105113 - METAL LOCKERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Welded lockers with bottom drawer.
2. Locker benches.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of metal locker.

C. Shop Drawings: For metal lockers.

1. Include plans, elevations, sections, and attachment details.
2. Show locker trim and accessories.
3. Include locker identification system and numbering sequence.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

C. Sample Warranty: For special warranty.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For adjusting, repairing, and replacing locker doors and latching mechanisms to include in maintenance manuals.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver metal lockers until spaces to receive them are clean, dry, and ready for their installation.

1.6 FIELD CONDITIONS

A. Field Measurements: Verify actual dimensions of recessed openings by field measurements before fabrication.

1.7 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of work specified in other Sections to ensure that metal lockers can be supported and installed as indicated.

1.8 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of metal lockers that fail in materials or workmanship, excluding finish, within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures.
b. Faulty operation of latches and other door hardware.

2. Damage from deliberate destruction and vandalism is excluded.
3. Warranty Period for Welded Metal Lockers: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Accessibility Standard: For lockers indicated to be accessible, comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design".

2.2 WELDED LOCKERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Art Metal Products
2. ASI Storage Solutions
3. DEBOURGH ALL-AMERICAN LOCKERS
4. GSS Lockers
5. List Industries Inc.
6. LockersMFG
7. Lyon LLC
8. Olympus Lockers & Storage Products, Inc.
9. Republic Storage Systems, LLC
10. Top Tier Storage Products

11. WEC Manufacturing LLC

B. Doors: Shall be formed from two (2) pieces of minimum 20-gauge cold rolled steel box formed and riveted together. Door with inner and outer door panels shall have a combined steel thickness of no less than 0.075inches.

1. Door Style: Double door with vented panel as follows:

a. Louvered Vents: No fewer than two louver openings at top and bottom per door lockers.

C. Body: Assembled by welding body components together. Fabricate from unperforated steel sheet with thicknesses as follows:

1. Tops, Bottoms, and Sides: 16 gauge nominal thickness.
2. Backs: 18 gauge nominal thickness.
3. Shelves: 16 gauge nominal thickness, with double bend at front and single bend at sides and back.

D. Frames: Channel formed; fabricated from 16 gauge nominal-thickness steel sheet; lapped and factory welded at corners; with top and bottom main frames factory welded into vertical main frames. Form continuous, integral, full-height door strikes on vertical main frames.

E. Hinges: Welded to door and attached to door frame with no fewer than two factory-installed rivets per hinge that are completely concealed and tamper resistant when door is closed; fabricated to swing 180 degrees.

1. Continuous Hinges: Manufacturer's standard, steel, full height.

F. Recessed Door Handle and Latch: Stainless steel cup with integral door pull, recessed so locking device does not protrude beyond door face; pry and vandal resistant.

1. Multipoint Latching: Finger-lift latch control designed for use with built-in combination locks or padlocks; positive automatic latching and prelocking.

a. Latch Hooks: Equip doors 48 inches and higher with three latch hooks and doors less than 48 inches high with two latch hooks; fabricated from 0.120-inch nominal-thickness steel sheet; welded to full-height door strikes; with resilient silencer on each latch hook.
b. Latching Mechanism: Manufacturer's standard, rattle-free latching mechanism and moving components isolated to prevent metal-to-metal contact, and incorporating a prelocking device that allows locker door to be locked while door is open and then closed without unlocking or damaging lock or latching mechanism.

G. Door Handle and Latch for Box Lockers: Stainless steel strike plate with integral pull; with steel padlock loop that projects through metal locker door.

H. Identification Plates: Manufacturer's standard, etched, embossed, or stamped aluminum plates, with numbers and letters at least 3/8 inch high.

I. Hooks: Manufacturer's standard ball-pointed, aluminum or steel; zinc plated.

J. Coat Rods: 1-inch-diameter steel, chrome finished.

K. Locker Drawer Base: 18” high external access drawer. Drawer face to have integral finger grab and punched to accept built-in spring bolt locker lock, key lock.

L. Continuous Sloping Tops: Fabricated from 16 gauge nominal-thickness steel sheet, with a pitch of approximately 20 degrees.

1. Closures: Vertical-end type.

M. Filler Panels: Fabricated from 0.048-inch nominal-thickness steel sheet.

N. Finished End Panels: Fabricated from 16 gauge nominal-thickness steel sheet to cover unused penetrations and fasteners, except for perimeter fasteners, at exposed ends of nonrecessed metal lockers; finished to match lockers.

O. Materials:

1. Cold-Rolled Steel Sheet: ASTM A1008/A1008M, Commercial Steel (CS), Type B, suitable for exposed applications.

P. Finish: Baked enamel or powder coat.

1. Color: As selected by Architect from manufacturer's full range.

2.3 LOCKS

A. Combination Padlock: Provided by Owner.

2.4 FABRICATION

A. Fabricate metal lockers square, rigid, without warp, and with metal faces flat and free of dents or distortion. Make exposed metal edges safe to touch and free of sharp edges and burrs.

1. Form body panels, doors, shelves, and accessories from one-piece steel sheet unless otherwise indicated.
2. Provide fasteners, filler plates, supports, clips, and closures as required for complete installation.

B. Fabricate each metal locker with an individual door(s) and frame; individual top, bottom, and back; and common intermediate uprights separating compartments.

C. Equipment: Provide each locker with an identification plate and the following equipment:

1. Single-Tier Units: Full width shelf, two single-prong wall hooks, interior drawer, half width shelf, integral drawer base.

D. Welded Construction: Factory preassemble metal lockers by welding all joints, seams, and connections; with no bolts, nuts, screws, or rivets used in assembly of main locker groups. Factory weld main locker groups into one-piece structures. Grind exposed welds smooth and flush.

E. Accessible Lockers: Fabricate as follows:

1. Locate bottom shelf no lower than 15 inches above the floor.
2. Where hooks, coat rods, or additional shelves are provided, locate no higher than 48 inches above the floor.

F. Continuous Sloping Tops: Fabricated in lengths as long as practical, without visible fasteners at splice locations; finished to match lockers.

G. Filler Panels: Fabricated in an unequal leg angle shape; finished to match lockers. Provide slip-joint filler angle formed to receive filler panel.

H. Finished End Panels: Fabricated to conceal unused penetrations and fasteners, except for perimeter fasteners, at exposed ends of nonrecessed metal lockers; finished to match lockers.

1. Provide one-piece panels for double-row (back-to-back) locker ends.

2.5 ACCESSORIES

A. Fasteners: Zinc- or nickel-plated steel, slotless-type, exposed bolt heads; with self-locking nuts or lock washers for nuts on moving parts.

B. Anchors: Material, type, and size required for secure anchorage to each substrate.

1. Provide toothed-steel or lead expansion sleeves for drilled-in-place anchors.

2.6 LOCKER BENCHES

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Art Metal Products
2. ASI Storage Solutions
3. Hadrian Inc.; Zurn Industries, LLC
4. List Industries Inc.
5. Lyon LLC
6. Penco Products, Inc.
7. Top Tier Storage Products

B. Provide bench units with overall assembly height of 17-1/2 inches for non ADA bench and 18 inches for ADA bench.

C. Bench Tops: Maple hardwood top, with rounded corners and edges.

1. Size: Minimum 9-1/2 inches wide by 1-1/4 inches thick except provide 20- to 24-inch-wide tops where accessible benches are indicated.
2. Laminated clear hardwood with one coat of clear sealer on all surfaces and one coat of clear lacquer on top and sides.

D. Fixed-Bench Pedestals: Manufacturer's standard supports, with predrilled fastener holes for attaching bench top and anchoring to floor, complete with fasteners and anchors, and as follows:

1. Tubular Steel:

a. 1-1/2-inch- diameter steel tubing threaded on both ends, with standard pipe flange at top and bell-shaped cast-iron base; with baked-enamel or powder-coat finish; anchored with exposed fasteners.

b. Color: As selected by Architect from manufacturer's full range.

E. Materials:

1. Stainless Steel Plate, Sheet, and Strip: ASTM A240/A240M or ASTM A666, Type 304.
2. Steel Tube: ASTM A500/A500M, cold rolled.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine walls and floors or support bases, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install lockers level, plumb, and true; shim as required, using concealed shims.

1. Anchor locker runs at ends and at intervals recommended by manufacturer, but not more than 36 inches o.c. Using concealed fasteners, install anchors through backup reinforcing plates, channels, or blocking as required to prevent metal distortion.
2. Anchor single rows of metal lockers to walls near top.
3. Anchor back-to-back metal lockers to floor.

B. Welded Lockers: Connect groups together with manufacturer's standard fasteners, with no exposed fasteners on face frames.

C. Equipment:

1. Attach hooks with at least two fasteners.
2. Attach door locks on doors using security-type fasteners.
3. Identification Plates:

a. Attach plates to each locker door, near top, centered, with at least two aluminum rivets.

D. Trim: Fit exposed connections of trim, fillers, and closures accurately together to form tight, hairline joints, with concealed fasteners and splice plates.

1. Attach filler panels with concealed fasteners. Locate filler panels where indicated on Drawings.
2. Attach sloping-top units to metal lockers, with closures at exposed ends.
3. Attach finished end panels using fasteners only at perimeter to conceal exposed ends of nonrecessed metal lockers.

E. Fixed Benches: Provide no fewer than two pedestals for each bench, uniformly spaced not more than 72 inches apart. Securely fasten tops of pedestals to undersides of bench tops, and anchor bases to floor.

3.3 ADJUSTING

A. Clean, lubricate, and adjust hardware. Adjust doors and latches to operate easily without binding.

3.4 PROTECTION

A. Protect metal lockers from damage, abuse, dust, dirt, stain, or paint. Do not permit use during construction.

B. Touch up marred finishes, or replace metal lockers that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by locker manufacturer.

END OF SECTION

SECTION 108213 – ROOF SCREENS

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. Stand-alone roof equipment screens and supporting hardware. Screens shall be designed to attach to the roof mechanical equipment platform structure and not the equipment being screened.

B. Roof screen accessories.

1.2 COORDINATION

A. Coordinate Work with other operations and installation of roofing materials to avoid damage to installed insulation and membrane materials.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: Manufacturer's data sheets on each product to be used, including:

1. Preparation instructions and recommendations.
2. Storage and handling requirements and recommendations.
3. Installation methods.

C. Shop Drawings: Layout and erection drawings showing typical cross sections and dimensioned locations of all frames and base supports. Include erection drawings, elevations, and details where applicable. Indicate welded connections using standard AWS A2.4 welding symbols. Indicate net weld lengths.

D. Selection Samples: For each finish product specified, two complete sets of color chips representing manufacturer's full range of available colors and patterns.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Design Calculations: 3 copies of structural design calculations for structural components and components resisting wind loads with seal and signature of professional engineer licensed in the State of Maine.

C. Manufacturer's Certificates: Certify products meet or exceed specified requirements.

D. Welders Certificates: Certify welders employed on the Work, verifying AWS qualification within previous 12 months.

E. Warranties: 3 signed copies.

1.5 QUALITY ASSURANCE

A. Manufacturer Qualifications: Manufacturer with a minimum five years documented experience in producing pre-manufactured metal-framed equipment screens.

B. Design Qualifications: Provide structural design calculations stamped by a professional engineer licensed in the state in which this project is located.

C. Welders: AWS certified within previous 12 months.

D. Pre-Installation Meeting:

1. Convene at job site, at least seven calendar days prior to scheduled beginning of construction activities of this section, to review requirements of this section.
2. Require attendance by representatives of the installing subcontractor (who will represent the system manufacturer), the structural subcontractors and other entities affected by construction activities of this section.
3. Notify Architect four calendar days in advance of scheduled meeting date.

E. Mock-Up: Provide a mock-up for evaluation of surface preparation techniques and application workmanship.

1. Locate in area designated by Architect.
2. Construct mock-up, one full screen section wide, including two roof supports.
3. Do not proceed with remaining work until workmanship, color, and location is approved by Architect.
4. Remove mock-up if required by Architect.
5. Accepted mock-up may remain in place.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials to the project site clearly marked for proper identification.

B. Receive, handle and store materials in conformance with the manufacturers printed instructions.

C. Store products under cover, in manufacturer's unopened packaging until ready for installation.

D. Protect materials from exposure to moisture.

E. Store materials in a dry, warm, ventilated weathertight location.

F. Protect metal fabrications from damage by exposure to weather.

G. Handling: Use a crane to move material. Do not lift the bundles by the metal bands.

1. Crane: Position the canvas sling straps so that the space between the straps is at

least 1/3 the length of the bundle. Use sling straps with looped ends running one end of the strap through the loop at the other end to cinch the bundle when lifted. When setting the load on the roof, put wood blocks under it to protect the roof and allow space to remove the sling straps.

2. Roof Placement: Spread the bundles and crates out to avoid overloading the roof structure. Place the material directly over major supports such as beams or trusses.

1.7 PROJECT CONDITIONS

A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

B. Field Measurements: Verify roof screen dimensions and conditions of the installation by field measurements before fabrication and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating equipment enclosure without field measurements. Coordinate construction to ensure that actual dimensions correspond to established dimensions.

1.8 WARRANTY

A. Framing System: Provide manufacturer's standard written limited warranty stating that the complete framing system shall be warranted against structural failure due to cracking, buckling, bending, tearing or corrosion arising under normal use and environmental conditions for the coverage period applicable.

1. Products installed on projects shall be warranted for twenty (20) years

B. Panel Finish:

1. Provide written warranty stating that the paint finish applied on all equipment enclosure panels will be warranted against chipping, peeling, cracking, fading, or blistering for the coverage period of up to twenty (20) years, see panel manufacturer warranty for coverage details.
2. Provide warranty signed by the panel manufacturer and paint finish applicator (if separate from manufacturer).

C. The above warranties are in addition to, and not a limitation of, other rights the Owner may have under the Contract Documents.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Design Loads: Comply with Building Code for site location and building height.

1. Design to resist ASCE 7 - Minimum Design Loads for Buildings and Other

Structures, using the latest published ASCE version.

2. Design all materials, assembly and attachments to resist snow, wind, suction and uplift loading at any point without damage or permanent set.

B. Structural Design: Prepare structural design calculations for screen framing and attachment to structure including reactions at base supports for verification of roof structure by Architect.

C. All welds to be performed by an AWS certified welder. Valid certification to be provided.

2.2 MANUFACTURERS

A. Basis-of-Design Product: RoofScreen Mfg., 347 Coral St.; Santa Cruz, CA 95060; Toll Free Tel: 866-766-3727; Tel: 831-421-9230; Fax: 866-253-0738; Email: request info (info@roofscreen.com); Web: www.roofscreen.com.

B. Requests for substitutions will be considered in accordance with provisions of Section 012500, Substitutions Procedures.

2.3 MATERIALS

A. Framing: Galvanized steel structural tubing in manufacturer's standard sizes, conforming to ASTM A 500 and/or ASTM A787 with manufacturer's standard galvanized coating conforming to ASTM A 1057. Provide with wall thickness as determined by structural calculations.

B. Connector Fittings: Fabricated from AISI Type 304 stainless steel with mill finish.

C. Steel Girts: Steel tube conforming to ASTM A 500 and/or A 787, with a G90 hot-dip galvanized coating.

D. Steel Hat Channel: Steel sheet conforming to ASTM A 653, Class SS, with a G90 hot-dip galvanized coating per ASTM A 1057.

E. Hardware: Bolts, nuts and washers: 18-8 stainless steel.

F. Self-Drilling Screws: Carbon steel with factory applied protective coating conforming to ASTM B 117 salt spray testing.

G. Welding Materials: AWS D1.1; type required for materials being welded.

H. Panel:

1. Profile:

a. 3 inch Deep Rib Panel.

2. Base Metal:

a. Minimum 24 gauge Galvalume steel sheet, AZ50, conforming to ASTM A 792 for painted and unpainted panels.

3. Finish:

   a. PVDF fluoropolymer, 1 mil, 2 coat, 70 percent.
   b. Color as selected by Architect from manufacturer's standard color range, 20 colors minimum.
   c. Coat reverse side with same finish as front side.

4. Panel Fasteners: No. 12 self-tapping sheet metal screw. Color coat heads to match panel color.
5. Panel Trim: Same material and finish as panel. Configuration as per manufacturer's standard details.

2.4 FABRICATION

A. Fit and shop assemble items in largest practical sections, for delivery to site.

B. Fabricate items with joints tightly fitted and secured.

C. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.

D. Supply components required for anchorage of fabrications. Fabricate anchors and related components of same material and finish as fabrication, except where specifically noted otherwise.

E. Fabricate system components so that portions of screen can be dismantled for repairs to equipment being screened and for future roof replacement.

F. Trim and Closures: Fabricated from 24 gauge metal and finished with the manufacturer's standard coating system.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine area where work will be installed to verify the installation can be performed in accordance with the Drawings and structural calculation requirements without interference from other equipment or trades.

B. If preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

C. Do not begin installation until conditions have been properly prepared.

3.2 PREPARATION

A. Clean surfaces thoroughly prior to installation.

B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

3.3 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Install components plumb and level, accurately fitted, free from distortion or defects.

C. Provide for erection loads, and for sufficient temporary bracing to maintain indicated alignment until completion of erection and installation of permanent attachments.

D. Anchor fabrications to structure at raised mechanical equipment platform.

E. Separate dissimilar metals and use gasketed fasteners, isolation shim, or isolation tape to eliminate possibility of corrosive or electrolytic action between metals.

F. Exercise care when installing components so as not to damage finish surfaces. Touch up as required to repair damaged finishes.

G. Remove all protective masking from material immediately after installation.

3.4 CLEANING AND PROTECTION

A. Remove all protective masking from framing and trim material immediately after installation. Remove temporary protective coverings and strippable films, if any, as metal wall panels are installed, unless otherwise indicated in manufacturer’s written installation instructions. Maintain in a clean condition during construction.

B. Protect installed products until completion of project.

1. Ensure that finishes and structure of installed systems are not damaged by subsequent construction activities.
2. If minor damage to finishes occurs, repair damage in accordance with manufacturer’s recommendations; provide replacement components if repaired finishes are unacceptable to Architect.

C. Prior to Substantial Completion: Remove dust or other foreign matter from component surfaces; clean finishes in accordance with manufacturer’s instructions.

D. Replace metal wall panels and framing members that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION

SECTION 111313 - LOADING DOCK BUMPERS

1.1 SUMMARY

A. Section includes loading dock bumpers.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of loading dock bumper.

C. Shop Drawings: For dock bumpers. Include plans, elevations, sections, and attachment details.

PART 2 - PRODUCTS

2.1 LOADING DOCK BUMPERS

A. Dock Bumpers: Surface-mounted bumpers; of type, size, and construction indicated; designed to absorb kinetic energy and minimize damage to loading dock structure.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. American Floor Products Company, Inc
    b. Beacon Industries, Inc
    c. Chalfant Sewing Fabricators, Inc
    d. Durable Corporation
    e. Kelley; Entrematic; ASSA ABLOY
    f. Rite-Hite Holding Corporation

2. Source Limitations: Obtain from single source from single manufacturer.

B. Laminated-Tread Loading Dock Bumper : Fabricated from multiple, uniformly thick plies cut from fabric-reinforced rubber tires. Laminate plies under pressure on not less than two 3/4-inch-diameter, steel supporting rods that are welded at one end to 1/4-inch-thick, structural-steel end angle and secured with a nut and angle at the other end. Fabricate angles with predrilled anchor holes and sized to provide not less than 1 inch of tread plies extending beyond the face of closure angles.

1. Thickness: 6 inches.
2. Horizontal Style: 10 inches high by 26 inches.

C. Anchorage Devices: Galvanized-steel anchor bolts, nuts, washers, bolts, sleeves, cast-in-place plates, and other anchorage devices as required to fasten bumpers securely in place and to suit installation type indicated. Hot-dip galvanized according to ASTM A153/A153M or ASTM F2329/F2329M.

D. Materials: ASTM A36/A36M for steel plates, shapes, and bars. Hot-dip galvanize according to ASTM A123/A123M.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Loading Dock Bumpers: Attach loading dock bumpers to face of loading dock in a manner that complies with requirements indicated for arrangement and position relative to top of platform and anchorage.

1. Welded Attachment: Plug-weld anchor holes in contact with steel inserts and fillet weld at other locations.
2. Bolted Attachment: Attach dock bumpers to preset anchor bolts embedded in concrete or to cast-in-place inserts or threaded studs welded to embedded-steel plates or angles. If preset anchor bolts, cast-in-place inserts, or threaded studs welded to embedded-steel plates or angles are not provided, attach dock bumpers by drilling and anchoring with expansion anchors and bolts.

3.3 ADJUSTING

A. After completing installation of exposed, factory-finished dock bumpers, inspect exposed finishes and repair damaged finishes.

END OF SECTION

SECTION 113013 - RESIDENTIAL APPLIANCES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Cooking appliances.
2. Refrigeration appliances.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include installation details, material descriptions, dimensions of individual components, and finishes for each appliance.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished accessories.

C. Sustainable Design Submittals:

1. ENERGY STAR: Product data for indicated products, showing compliance with requirements for ENERGY STAR product labeling.

1.3 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For each residential appliance to include in operation and maintenance manuals.

1.4 WARRANTY

A. Special Warranties: Manufacturer agrees to repair or replace residential appliances or components that fail in materials or workmanship within specified warranty period.

B. Microwave Oven: Full warranty, including parts and labor.

1. Warranty Period: Two years from date of Substantial Completion.

C. Refrigerator/Freezer, Sealed System: Full warranty, including parts and labor, for on-site service on the product.

1. Warranty Period for Sealed Refrigeration System: Two years from date of Substantial Completion.
2. Warranty Period for Other Components: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain residential appliances from single source.

2.2 PERFORMANCE REQUIREMENTS

A. Electrical Appliances: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Accessibility: Where residential appliances are indicated to comply with accessibility requirements, comply with applicable provisions in the DOJ's 2010 ADA Standards for Accessible Design.

2.3 COOKING APPLIANCES

A. Microwave Oven :

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Amana; Whirlpool Corporation
    b. Bosch US; BSH Home Appliances Corporation
    c. Dacor, Inc.
    d. DCS Appliances; Fisher and Paykel Appliances Ltd
    e. Fisher & Paykel Appliances Ltd
    f. Frigidaire
    g. Gaggenau; BSH Home Appliances Corporation
    h. GE Appliances; Haier Group
    i. Jennair; Whirlpool Corporation
    j. Kenmore; Transformco SR Brands LLC
    k. KitchenAid; Whirlpool Corporation
    l. LG Electronics USA, Inc.; LG Electronics Inc.
    m. Maytag; Whirlpool Corporation
    n. Miele
    o. Samsung Electronics America, Inc. (SEA); Samsung Electronics Co., Ltd. (SEC)
    p. Sharp Electronics Corp.
    q. Thermador; BSH Home Appliances Corporation
    r. Viking Range, LLC; Middleby Corporation
    s. Whirlpool Corporation
    t. Wolf; Sub-Zero Group, Inc.

2. Mounting: Countertop.
3. Type: Conventional.
4. Dimensions:

    a. Width: 24 inches.
    b. Depth: 19-1/2 inches.
    c. Height: 14 inches.

5. Capacity: 2.0 cu. ft.
6. Oven Door: Door with observation window.
7. Microwave Power Rating: 1200 W.
8. Electric Power Supply: 120 V, 60 Hz, 1 phase, 15 A.
9. Controls: Digital panel controls and timer display.
10. Other Features: Turntable and lock-out feature.
11. Material: Stainless steel.

2.4 REFRIGERATION APPLIANCES

A. Refrigerator/Freezer: Two-door refrigerator/freezer with freezer on top and complying with AHAM HRF-1.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Amana; Whirlpool Corporation
    b. Bosch US; BSH Home Appliances Corporation
    c. Dacor, Inc.
    d. DCS Appliances; Fisher and Paykel Appliances Ltd
    e. Fisher & Paykel Appliances Ltd
    f. Frigidaire
    g. Gaggenau; BSH Home Appliances Corporation
    h. GE Appliances; Haier Group
    i. Jennair; Whirlpool Corporation
    j. Kenmore; Transformco SR Brands LLC
    k. KitchenAid; Whirlpool Corporation
    l. LG Electronics USA, Inc.; LG Electronics Inc.
    m. Maytag; Whirlpool Corporation
    n. Miele
    o. Samsung Electronics America, Inc. (SEA); Samsung Electronics Co., Ltd. (SEC)
    p. Thermador; BSH Home Appliances Corporation
    q. Viking Range, LLC; Middleby Corporation
    r. Whirlpool Corporation
    s. Wolf; Sub-Zero Group, Inc.

2. Type: Freestanding.
3. Dimensions:

    a. Width: 33 inches.
    b. Depth: 33 inches.
    c. Height: 86 inches.

4. Storage Capacity:

    a. Refrigeration Compartment Volume: 15.6 cu. ft.
    b. Freezer Volume: 6.5 cu. ft.
    c. Shelf Area: Three adjustable glass shelves.

5. General Features:

    a. Door Configuration: Overlay.

6. Refrigerator Features:

    a. Interior light in refrigeration compartment.
    b. Door Storage: Modular compartments 1 gal. milk-container storage.
    c. Temperature-controlled meat/deli bin.

7. Freezer Features: One freezer compartment(s) with door(s).

    a. Automatic defrost.
    b. Interior light in freezer compartment.

8. Energy Star: Provide appliances that qualify for the EPA/DOE Energy Star product-labeling program.
9. Front Panel(s): Manufacturer's standard.
10. Appliance Color/Finish: Stainless steel.

2.5 GENERAL FINISH REQUIREMENTS

A. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, power connections, and other conditions affecting installation and performance of residential appliances.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF RESIDENTIAL APPLIANCES

A. Install appliances according to manufacturer's written instructions.

B. Freestanding Equipment: Place units in final locations after finishes have been completed in each area. Verify that clearances are adequate to properly operate equipment.

END OF SECTION

SECTION 122413 - ROLLER WINDOW SHADES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Manually operated roller shades with single rollers.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" or 061053 "Miscellaneous Rough Carpentry" for wood blocking and grounds for mounting roller shades and accessories.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, features, finishes, and operating instructions for roller shades.

C. Shop Drawings: Show fabrication and installation details for roller shades, including shadeband materials, their orientation to rollers, and their seam and batten locations.

D. Product Schedule: For roller shades.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For roller shades to include in maintenance manuals.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: Fabricator of products.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver roller shades in factory packages, marked with manufacturer, product name, and location of installation using same designations indicated on Drawings.

1.8 FIELD CONDITIONS

A. Environmental Limitations: Do not install roller shades until construction and finish work in spaces, including painting, is complete and dry and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

B. Field Measurements: Where roller shades are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Allow clearances for operating hardware of operable glazed units through entire operating range. Notify Architect of installation conditions that vary from Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain roller shades from single source from single manufacturer.

2.2 MANUALLY OPERATED SHADES WITH SINGLE ROLLERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Draper Inc.; Clutch Operated FlexShade, or a comparable product by one of the following:

1. BTX Window Automation Inc.
2. CACO, Inc., Window Fashions.
3. DFB Sales Inc.
4. Hunter Douglas Contract.
5. Insolroll Window Shading Systems.

6. Lutron Electronics Co., Inc.
7. MechoShade Systems, Inc.
8. OEM Shades Inc.
9. Qmotion Shades.
10. Silent Gliss Inc.
11. SM Automatic, Inc.
12. Springs Window Fashions; SWFcontract.

B. Chain-and-Clutch Operating Mechanisms: With continuous-loop bead chain and clutch that stops shade movement when bead chain is released; permanently adjusted and lubricated.

1. Bead Chains: Stainless steel.

a. Loop Length: Full length of roller shade.
b. Limit Stops: Provide upper and lower ball stops.
c. Chain-Retainer Type: Chain tensioner, jamb mounted.

2. Spring Lift-Assist Mechanisms: Manufacturer's standard for balancing roller shade weight and for lifting heavy roller shades.

a. Provide for shadebands that weigh more than 10 lb or for shades as recommended by manufacturer, whichever criterion is more stringent.

C. Rollers: Corrosion-resistant steel or extruded-aluminum tubes of diameters and wall thicknesses required to accommodate operating mechanisms and weights and widths of shadebands indicated without deflection. Provide with permanently lubricated drive-end assemblies and idle-end assemblies designed to facilitate removal of shadebands for service.

1. Roller Drive-End Location: Right side of interior face of shade.
2. Direction of Shadeband Roll: Regular, from back (exterior face) of roller.
3. Shadeband-to-Roller Attachment: Removable spline fitting into integral channel in tube.

D. Mounting Hardware: Brackets or endcaps, corrosion resistant and compatible with roller assembly, operating mechanism, installation accessories, and mounting location and conditions indicated.

E. Roller-Coupling Assemblies: Coordinated with operating mechanism and designed to join up to three inline rollers into a multiband shade that is operated by one roller drive-end assembly.

F. Shadebands:

1. Shadeband Material: Light-filtering fabric.
2. Shadeband Bottom (Hem) Bar: Steel or extruded aluminum.

a. Type: Enclosed in sealed pocket of shadeband material.
b. Color and Finish: As selected by Architect from manufacturer's full range.

G. Installation Accessories:

1. Front Fascia: Aluminum extrusion that conceals front and underside of roller and operating mechanism and attaches to roller endcaps without exposed fasteners.

    a. Shape: L-shaped.
    b. Height: Manufacturer's standard height required to conceal roller and shadeband assembly when shade is fully open, but not less than 3 inches.

2. Endcap Covers: To cover exposed endcaps.
3. Installation Accessories Color and Finish: As selected from manufacturer's full range.

2.3 SHADEBAND MATERIALS

A. Shadeband Material Flame-Resistance Rating: Comply with NFPA 701. Testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

B. Light-Filtering Fabric: Woven fabric, stain and fade resistant.

1. Source: Roller shade manufacturer.
2. Type: 100 percent non-PVC warp knit polyester.
3. Weave: Diamond knit.
4. Thickness: .029.
5. Weight: 8.85 oz/sq. yd.
6. Roll Width: 118 inches.
7. Orientation on Shadeband: Up the bolt.
8. Openness Factor: 3 percent.
9. Color: As selected by Architect from manufacturer's full range.

2.4 ROLLER SHADE FABRICATION

A. Product Safety Standard: Fabricate roller shades to comply with WCMA A 100.1, including requirements for flexible, chain-loop devices; lead content of components; and warning labels.

B. Unit Sizes: Fabricate units in sizes to fill window and other openings as follows, measured at 74 deg F:

1. Between (Inside) Jamb Installation: Width equal to jamb-to-jamb dimension of opening in which shade is installed less 1/4 inch per side or 1/2-inch total, plus or minus 1/8 inch. Length equal to head-to-sill or -floor dimension of opening in which shade is installed less 1/4 inch, plus or minus 1/8 inch.

C. Shadeband Fabrication: Fabricate shadebands without battens or seams.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, operational clearances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 ROLLER SHADE INSTALLATION

A. Install roller shades level, plumb, and aligned with adjacent units according to manufacturer's written instructions.

B. Roller Shade Locations: At windows indicated on Drawings.

3.3 ADJUSTING

A. Adjust and balance roller shades to operate smoothly, easily, safely, and free from binding or malfunction throughout entire operational range.

3.4 CLEANING AND PROTECTION

A. Clean roller shade surfaces, after installation, according to manufacturer's written instructions.

B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that roller shades are without damage or deterioration at time of Substantial Completion.

C. Replace damaged roller shades that cannot be repaired, in a manner approved by Architect, before time of Substantial Completion.

END OF SECTION

SECTION 123661.16 - SOLID SURFACING COUNTERTOPS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid surface material countertops.
2. Solid surface material backsplashes.
3. Solid surface material end splashes.

B. Related Requirements:

1. Section 224200 "Commercial Plumbing Fixtures" for non-integral sinks and plumbing fittings.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For countertop materials and sinks.

C. Shop Drawings: For countertops. Show materials, finishes, edge and backsplash profiles, methods of joining, and cutouts for plumbing fixtures.

1. Show locations and details of joints.
2. Show direction of directional pattern, if any.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Qualification Data: For fabricator.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Maintenance Data: For solid surface material countertops to include in maintenance manuals. Include Product Data for care products used or recommended by Installer and names, addresses, and telephone numbers of local sources for products.

1.5 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate countertops similar to that required for this Project, and whose products have a record of successful in-service performance.

B. Installer Qualifications: Fabricator of countertops.

1.6 FIELD CONDITIONS

A. Field Measurements: Verify dimensions of countertops by field measurements after base cabinets are installed but before countertop fabrication is complete.

1.7 COORDINATION

A. Coordinate locations of utilities that will penetrate countertops or backsplashes.

PART 2 - PRODUCTS

2.1 SOLID SURFACE COUNTERTOP MATERIALS

A. Solid Surface Material: Homogeneous-filled plastic resin complying with ISFA 2-01.

1. Basis-of-Design Product: Formica’s Blanco Terrazzo or comparable product by one of the following:

a. E.I. du Pont de Nemours and Company.
b. Formica Corporation.
c. LG Chemical, Ltd.
d. Wilsonart LLC.

2. Type: Provide Standard type unless Special Purpose type is indicated.
3. Colors and Patterns: As indicated by manufacturer's designations.

2.2 FABRICATION

A. Fabricate countertops according to solid surface material manufacturer's written instructions and to the AWI/AWMAC/WI's "Architectural Woodwork Standards."

1. Grade: Custom.

B. Configuration:

1. Front: Straight, slightly eased at top.
2. Backsplash: Straight, slightly eased at corner.
3. End Splash: Matching backsplash.

C. Countertops:

1. 1/2-inch- thick, solid surface material. Provide front edge built up with same material for counters.

D. Backsplashes: 1/2-inch- thick, solid surface material.

E. Fabricate tops with shop-applied edges and backsplashes unless otherwise indicated. Comply with solid surface material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.

F. Joints:

1. Fabricate countertops without joints.

G. Cutouts and Holes:

1. Undercounter Plumbing Fixtures: Make cutouts for fixtures using template or pattern furnished by fixture manufacturer. Form cutouts to smooth, even curves.

a. Provide vertical edges, slightly eased at juncture of cutout edges with top and bottom surfaces of countertop and projecting 3/16 inch into fixture opening.

2. Fittings: Drill countertops in shop for plumbing fittings, undercounter soap dispensers, and similar items.

2.3 INSTALLATION MATERIALS

A. Adhesive: Product recommended by solid surface material manufacturer.

B. Sealant for Countertops: Comply with applicable requirements in Section 079200 "Joint Sealants."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates to receive solid surface material countertops and conditions under which countertops will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of countertops.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install countertops level to a tolerance of 1/8 inch in 8 feet, 1/4 inch maximum. Do not exceed 1/64-inch difference between planes of adjacent units.

B. Anchor securely by screwing through corner blocks of base cabinets or other supports into underside of countertop.

C. Complete cutouts not finished in shop. Mask areas of countertops adjacent to cutouts to prevent damage while cutting. Make cutouts to accurately fit items to be installed, and at right angles to finished surfaces unless beveling is required for clearance. Ease edges slightly to prevent snipping.

1. Seal edges of cutouts in particleboard subtops by saturating with varnish.

D. Apply sealant to gaps at walls; comply with Section 079200 "Joint Sealants."

END OF SECTION

SECTION 142410 – HYDRAULIC ELEVATOR – MODERNIZATION

PART 1 - GENERAL

1.1 DESCRIPTION

A. This section specifies the engineering, furnishing and installation of the complete hydraulic elevator system as described herein and as indicated on the contract drawings.

B. Items listed in the singular apply to each elevator in this specification except where noted.

C. Passenger Elevator must be oil hydraulic, microprocessor control system and power-operated car and hoistway doors. Elevator must be Class "A" loading rated as a minimum.

ELEVATOR SCHEDULE	
Overall Platform Size	
Clear Inside Platform	
Rated Load – lb	2500
Contract Speed - fpm	
Total Travel – ft	
Floors Served	4
Number of Openings	4
Entrance Type & Size	
Plunger Size	

1.2 RELATED WORK

A. Section 012100 "Allowances" for allowances for elevator hydraulic cylinder and plunger assembly hole drilling and hydraulic plunger assembly.

B. Section 078400, FIRESTOPPING: Sealing around penetrations to maintain the integrity of fire-rated construction.

C. Section 260010, SUPPLEMENTARY REQUIREMENTS FOR ELECTRICAL.

D. Section 260519, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES.

E. Section 260526, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS.

F. Section 260533.13, CONDUITS FOR ELECTRICAL SYSTEMS.

G. Section 260573, POWER SYSTEM STUDIES.

H. Section 262213, LOW-VOLTAGE DISTRIBUTION TRANSFORMERS.

I. Section 262416, PANELBOARDS.

J. Section 264313, SURGE PROTECTIVE DEVICES FOR LOW-VOLTAGE ELECTRICAL POWER CIRCUITS.

K. Section 265000, LIGHTING.

1.3 QUALIFICATIONS

A. Approval by the Architect is required for products and services of proposed manufacturers, suppliers, installers and must be contingent upon submission of certificates by the Contractor stating the following:

1. Elevator contractor is currently and regularly engaged in the installation of elevator equipment as one of his principal products.
2. Elevator contractor must have five (5) years of successful experience, trained supervisory personnel and facilities to install elevator equipment specified herein.
3. Elevator Mechanic (Installer) must have passed a Mechanic Examination approved by the U.S. Department of Labor and have technical qualifications of at least five years of experience in the elevator industry or 10,000 hours of field experience working in the elevator industry with technical update training. Apprentices must be actively pursuing Certified Elevator Mechanic status. Certification must be submitted for all workers employed in this capacity.

B. Welding at the project site must be performed by certified welders who have previously qualified by test as prescribed in American Welding Society Publications AWS Dl.1 to perform the type of work required. Certificates must be submitted for all workers employed in this capacity. A welding or hot work permit is required for each day and must be obtained from the VAMC safety department. Request permit one day in advance.

C. Electrical work must be performed by a Licensed Master Electrician and Licensed Journeymen Electricians as requirements by NEC. Certificates must be submitted for all workers employed in this capacity.

D. Approval will not be given to elevator contractors and manufacturers who have established on prior projects, either government, municipal, or commercial, a record of unsatisfactory elevator installations, have failed to complete awarded contracts within the contract period and do not have the requisite record of satisfactorily performing elevator installations of similar type and magnitude.

E. Approval of Elevator Contractor’s equipment will be contingent upon their providing factory training, engineering and technical support, including all manuals, wiring diagrams and tools necessary for adjusting, maintenance, repair and testing of equipment to the Owner for use by the Owner’s designated Elevator Maintenance Service Provider.

F. Identifying an elevator maintenance service provider that must render services within two hours of receipt of notification, together with certification that the quantity and quality of replacement parts stock is enough to warranty continued operation of the elevator installation.

G. Equipment within a group of hydraulic elevators must be the product of the same manufacturer.

H. The Contractor must provide and install safety devices that have been subjected to tests witnessed and certified by an independent professional testing laboratory that is not a subsidiary of the firm that manufactures supplies or installs the equipment.

1.4 APPLICABLE PUBLICATIONS

A. The publications listed below form a part of this specification. Elevator installation must meet the requirements of the latest editions published and adopted by the State of Maine on the date this contract is signed.

B. Federal Specifications (Fed. Spec.):

J-C-30B - Cable and Wire, Electrical (Power, Fixed Installation)
J-C-580 – Cord, Flexible and Wire, Fixture
W-S-610 – Splice Connectors
W-C-596F - Connector, Plug, Electrical; Connector, Receptacle, Electrical
W-F-406E - Fittings for Cable, Power, Electrical and Conduit, Metal, Flexible
HH-I-558C - Insulation, Blankets, Thermal (Mineral Fiber, Industrial Type)
W-F-408E - Fittings for Conduit, Metal, Rigid (Thick- Wall and Thin-wall (EMT) Type)
RR-W-410 - Wire Rope and Strand
TT-E-489J - Enamel, Alkyd, Gloss, Low VOC Content
QQ-S-766 - Steel, Stainless and Heat Resisting, Alloys, Plate, Sheet and Strip

C. American Society of Mechanical Engineers (ASME):

A17.1 - Safety Code for Elevators and Escalators
A17.2 - Inspectors Manual for Electric Elevators and Escalators

D. National Fire Protection Association:

NFPA 13 - Standard for the Installation of Sprinkler Systems
NFPA 70 - National Electrical Code (NEC)
NFPA 72 - National Fire Alarm and Signaling Code
NFPA 101 - Life Safety Code
NFPA 252 - Fire Test of Door Assemblies

E. International Building Code (IBC)

F. American Society for Testing and Materials (ASTM):

A1008/A1008M-09 - Steel, Sheet, Cold Rolled, Carbon, Structural, High-Strength Low-Alloy and High Strength Low-Alloy with Improved Formability
E1042-02 - Acoustically Absorptive Materials Applied by Trowel or Spray

G. Manufacturer's Standardization Society of the Valve and Fittings Industry (MSS):

SP-58 - Pipe Hangers and Supports

H. Society of Automotive Engineers, Inc. (SAE)

J517-91 - Hydraulic Hose, Standard

I. Gages:

For Sheet and Plate: U.S. Standard (USS)
For Wires: American Wire Gauge (AWG)

J. American Welding Society (AWS):

D1.1 - Structured Welding Code – Steel

K. National Electrical Manufacturers Association (NEMA):

LD-3 - High-Pressure Decorative Laminates

L. Underwriter's Laboratories (UL):

486A - Safety Wire Connectors for Copper Conductors
797 - Safety Electrical Metallic Tubing

M. Institute of Electrical and Electronic Engineers (IEEE)

N. Regulatory Standards:

Uniform Federal Accessibility Standards
Americans with Disabilities Act

O. National Elevator Industry, Inc.

NEII-1 Building Transportation Standards and Guidelines

1.5 SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Before execution of work, furnish information to evidence full compliance with contract requirements for proposed items. Such information must include, as required: Manufacturer's Name, Trade Names, Model or Catalog Number, Nameplate Data (size, capacity and rating) and corresponding specification reference (Federal or project specification number and paragraph). All submitted drawings and related elevator material must be forwarded to the Owner’s Representative.

C. Shop Drawings:

1. Complete scaled and dimensioned layout in plan and section view showing the arrangement of equipment and all details of each elevator unit specified including:

   a. Complete layout showing location of storage tank/pump assembly, controller, piping layout, outside diameter of cylinder/plunger assembly, size of car platform, car frame members and support assembly.
   b. Car, guide rails, brackets, buffers and other components located in hoistway.
   c. Rail bracket spacing and maximum vertical forces on guide rails in accordance with H-18-8 for Seismic Design Category B or greater.
   d. Reaction at points of support and buffer impact loads.
   e. Weight of principal parts.
   f. Top and bottom clearances and over travel of the car.
   g. Location of main line switch/shunt trip circuit breaker, switchboard panel, light switch and feeder extension points in the machine room.

2. Drawings of hoistway entrances and doors showing details of construction and method of fastening to the structural members of the building.

    a. Submit details of interface fastenings between entrance frames and cmu shaft walls.
    b. Sill details including sill support.

D. Samples:

1. One each of stainless steel, 3 inches x 5 inches.
2. One each of baked enamel, 3 inches x 5 inches.
3. One each of color floor covering.
4. One each of protection pads, 3 inches x 5 inches if used.
5. One each car and hoistway Braille plate sample.
6. One each car and hall button sample.
7. One each car and hall lantern/position indicator sample.
8. One each wall and ceiling material finish sample.
9. One each car lighting sample.

E. Name of manufacturer, type or style designation and applicable data of the following equipment must be shown on the elevator layouts:

1. Storage tank/pump assembly.
2. Pump and motor, HP and RPM rating, Voltage, Starting and Full Load Ampere, Number of phases and Gallons per minute.
3. Controller.
4. Starters and Overload Current Protection Devices.
5. Car Safety Device; Rupture Valve and Manual Shut Off Valves.
6. Electric Door Operator; HP, RPM, Voltage and Ampere rating of motor.
7. Hoistway Door Interlocks.
8. Car Buffers; maximum and minimum rated load, maximum rated striking speed and stroke.
9. Cab Ventilation Unit; HP rating and CFM rating.

F. Complete construction drawings of elevator car enclosure, showing dimensioned details of construction, fastenings to platform, car lighting, ventilation, ceiling framing, top exits and location of car equipment.

G. Complete dimensioned detail of vibration isolating foundations for storage tank/pump assembly.

H. Dimensioned drawings showing details of:

1. All signal and operating fixtures.
2. Car slide guides/roller guides.
3. Hoistway door tracks, hangers and sills.
4. Door operator, infrared curtain units.

I. Cut sheets or drawings showing details of controllers and supervisory panels.

J. Furnish certificates as required under: Paragraph "QUALIFICATIONS".

1.6 WIRING DIAGRAMS

A. Provide one electronic set of field wiring and straight-line wiring diagrams showing all electrical circuits in the hoistway, machine room and fixtures. Install one set coated with an approved plastic sealer and mounted in the elevator machine room as directed by the Owner's Representative.

B. In the event field modifications are necessary during installation, diagrams must be revised to include all corrections made prior to and during the final inspection. Corrected diagrams must be delivered to the Owner's Representative within 30 days of final acceptance.

C. Provide the following information relating to the specific type of microprocessor controls installed:

1. Owner's information manual, containing job specific data on major components, maintenance and adjustment.
2. System logic description.
3. Complete wiring diagrams needed for field troubleshooting, adjustment, repair and replacement of components. Diagrams must be base diagrams, containing all changes and additions made to the equipment during the design and construction period.
4. Changes made during the warranty period must be noted on the drawings in adequate time to have the finalized drawings reproduced for mounting in the machine room no later than six months prior to the expiration of the warranty period.

1.7 PERFORMANCE STANDARDS

A. The elevators must meet the highest standards of the industry and specifically the following:

1. Contract speed is high speed in either direction of travel with rated capacity load in the elevator. Speed variation under all load conditions, regardless of direction of travel, must not vary more than five (5) percent.
2. The controlled rate of change of acceleration and retardation of the car must not exceed 0.1G per ft/s/s and the maximum acceleration and retardation must not exceed 0.2G per ft/s/s.
3. Starting, stopping and leveling must be smooth and comfortable without appreciable steps of acceleration and deceleration.

B. The door operator must open the car door and hoistway door simultaneously at 2.5-feet per second and close at 1-foot per second.

C. Pressure: Fluid system components must be designed and factory tested for 500 psi operating pressure.

D. Floor level stopping accuracy must be within 0.125 inches above or below the floor, regardless of load condition.

E. Noise and Vibration Isolation: All elevator equipment including their supports and fastenings to the building, must be mechanically and electrically isolated from the building structure to minimize objectionable noise and vibration transmission to car, building structure, or adjacent occupied areas of building.

F. Sound Isolation: Noise level relating to elevator equipment operation in machine room must not exceed 80 decibels. All db readings must be taken three (3) feet off the floor and three (3) feet from equipment.

G. Airborne Noise: Measured noise level of elevator equipment during operation must not exceed 50 decibels in elevator lobbies and 60 decibels inside car under any condition including door operation and car ventilation exhaust blower on its highest speed.

1.8 WARRANTY

A. Submit all labor and materials furnished regarding elevator system and installation to terms of "Warranty of Construction" articles of FAR clause 52.246-21. The One-Year Warranty and Guarantee Period of Service must commence and run concurrent after final inspection, completion of performance test and upon acceptance of each elevator.

B. During warranty period if a device is not functioning properly in accordance with specification requirements, more maintenance than the contract requires keeping device operational, device must be removed and a new device meeting all requirements must be installed as part of work until satisfactory operation of installation is obtained. Period of warranty must start anew for such parts from date of completion of each new installation performed, in accordance with foregoing requirements.

1.9 POWER SUPPLY

A. For power supply in each machine room, see Electrical specifications and Electrical drawings.

B. Main Line Fused Disconnect Switch/Shunt Trip Circuit Breaker for each controller must be located inside the machine room at the strike side of the machine room door and lockable in the “Off” position.

C. Provide Surge Suppressors to protect the elevator equipment.

1.10 EMERGENCY POWER SUPPLY

A. Emergency power supply, its starting means, transfer switch for transfer of elevator supply from normal to emergency power, two pair of conductors in a conduit from an auxiliary contact on the transfer switch (open or close contacts as required by Elevator Controller Manufacturer) to terminals in the group elevator controller and other related work must be provided by the Electrical Contractor.

B. Upon loss of normal power supply there must be a delay before transferring to emergency power of 10 seconds minimum to 45 seconds maximum, the delay must be accomplished through an adjustable timing device.

C. Prior to the return of normal power an adjustable timed circuit must be activated that will cause all cars to remain at a floor if already there or stop and remain at the next floor if in flight. Actual transfer of power from emergency power to normal building power must take place after all cars are stopped at a floor with their doors open.

D. Car lighting circuits must be connected to the emergency power panel.

1.11 ELEVATOR MACHINE ROOM

A. Reuse existing machine room and meet the requirements of ASME A17.1, NFPA 70, NFPA 101 and IBC. The elevator drive machine and elevator controller must be in the same code approved machine room.

B. Locate the shunt trip breakers and machine room light switch to the lock side of the door inside the room.

C. Locate sprinkler pipes to provide seven (7) foot head clearance. Do not locate sprinkler heads, heat detectors and smoke detectors directly over elevator equipment.

1.12 HOISTWAY LIGHTING

A. Provide lighting with 3-way switches at the top and bottom of the hoistway accessible from elevator hoistway entrance prior to entering the pit or stepping onto the car top.

B. Lighting must illuminate top of elevator cab when it is at the top floor and the pit when at the bottom floor.

1.13 TOOL CABINET

A. Provide a metal parts/tool cabinet, having two shelves and hinged doors. Cabinet must be 48 inches high, 30 inches wide and 18 inches deep.

1.14 WORK SCHEDULE

A. Before starting work submit a detailed work schedule for approval and arrange with Owner's Representative sequence of procedure, means of access to premises, space for storage, use of approaches, corridors, stairways, elevators, location of temporary partitions, disposal of trash and recyclable materials. The Owner's Representative must be notified twenty (20) calendar days, in writing, in advance of starting work on elevators. No work may begin on any elevator until all materials for that elevator have been delivered to the site and verified by the Owner's Representative. The phasing of work on the elevators must be coordinated with the Owner's Representative.

1.15 SAFETY PRECAUTIONS

A. Provide fire extinguishers that are readily available always.

B. It must be the obligation of the contractor to maintain a free and clear passageway in each elevator lobby. Parts and tools must be kept within the confines of entrance partitions. Trash and debris must be removed daily.

C. Provide fire rated partition during the modernization of elevators. Barrier must extend to the full height of the elevator entrance and must be dust and vapor proof with dust absorbing mats at access points.

1.16 REMOVAL OF MATERIALS AND EQUIPMENT

A. Material and equipment that are not specified to be reused or retained under contract must be removed daily from the site at the expense of the contractor. The contractor must receive title to

all material and equipment not specified to be reused as of date of withdrawal from service. The Owner does not warranty condition of the material to which contractor must obtain title, nor must the Owner be liable for damage before or after title passes to contractor.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Where stainless steel is specified, it must be corrosion resisting steel complying with Fed. Spec. QQ-S-766, Class 302 or 304, Condition A with Number 4 finish on exposed surfaces. Stainless steel must have the grain of belting in the direction of the longest dimension and surfaces must be smooth and without waves. During installation stainless steel surfaces must be protected with a suitable material.

B. Where cold rolled steel is specified, it must be low-carbon steel rolled to stretcher level standard flatness, complying with ASTM A109.

2.2 MANUFACTURED PRODUCTS

A. Materials, devices and equipment furnished must be of current production by manufacturers regularly engaged in the manufacture of such items. The elevator equipment, including controllers, door operators and supervisory system must be the product of manufacturers of established reputation, provided such items are capably engineered and produced under coordinated specifications to ensure compatibility with the total operating system.

B. Manufacturers of equipment assemblies which include components made by others must assume complete responsibility for the final assembled unit. Components must be compatible with each other and with the total assembly for the intended service.

C. Mixing of manufactures related to a single system or group of components must be identified in the submittals.

D. Key operated switches must be provided for this elevator modernization, provide four (4) keys for each individual switch or lock. Provide different key tumblers for different switch and lock functions. Each key must have a tag bearing a stamped or etched legend identifying its purpose.

2.3 CONDUIT AND WIREWAY

A. Remove existing and provide new conduit and wireway. Install electrical conductors, except traveling cable connected to the elevator, in rigid zinc-coated steel or aluminum conduit, electrical metallic tubing or metal wireways. Rigid conduit smaller than .75 inch or electrical metallic tubing smaller than .50-inch electrical trade size must not be used. All raceways completely embedded in concrete slabs, walls, or floor fill must be rigid steel conduit. Wireway (duct) must be installed in the hoistway and to the controller and between similar apparatus in the elevator machine room. Fully protect self-supporting connections, where approved, from abrasion or other mechanical injury. Flexible metal conduit not less than .375-inch electrical trade size may be used, not exceeding 18 inches in length unsupported, for short connections between risers and limit switches, interlocks and for other applications permitted by NEC.

B. All conduits terminating in steel cabinets, junction boxes, wireways, switch boxes, outlet boxes and similar locations must have approved insulation bushings. Install a steel lock nut under the

bushings if they are constructed completely of insulating materials. Protect the conductors at ends of conduits not terminating in steel cabinets or boxes by terminal fittings having an insulated opening for the conductors.

C. Rigid conduit and EMT fittings using set screws or indentations as a means of attachment must not be used.

D. Connect motors or other items subject to movement, vibration or removal to the conduit or EMT systems with flexible, steel conduits.

2.4 CONDUCTORS

A. Remove existing and provide new. Conductors must be stranded or solid coated annealed copper in accordance with Federal Specification J-C-30B for Type RHW or THW. Where 16 and 18 AWG are permitted by NEC, single conductors or multiple conductor cables in accordance with Federal Specification J-C-580 for Type TF may be used provided the insulation of single conductor cable and outer jacket of multiple conductor cable is flame retardant and moisture resistant. Multiple conductor cable must have color or number coding for each conductor. Conductors for control boards must be in accordance with NEC. Joints or splices are not permitted in wiring except at outlets. Tap connectors may be used in wireways provided they meet all UL requirements.

B. Provide all conduit and wiring between machine room, hoistway and fixtures.

C. All wiring must test free from short circuits or ground faults. Insulation resistance between individual external conductors and between conductors and ground must be a minimum of one megohm.

D. Where size of conductors is not given, voltage and amperes must not exceed limits set by NEC.

E. Provide equipment grounding. Ground the conduits, supports, controller enclosure, motor, platform and car frame and all other non-current conducting metal enclosures for electrical equipment in accordance with NEC. The ground wires must be copper, green insulated and sized as required by NEC. Bond the grounding wires to all junction boxes, cabinets and wire raceways.

F. Terminal connections for all conductors used for external wiring between various items of elevator equipment must be solderless pressure wire connectors in accordance with Federal Specification W-S-610. The Elevator Contractor may, at his option, make these terminal connections on #10 gauge or smaller conductors with approved terminal eyelets set on the conductor with a special setting tool, or with an approved pressure type terminal block. Terminal blocks using pierce-through serrated washers are not acceptable.

2.5 TRAVELING CABLES

A. Remove existing and provide new flexible traveling cables conforming to the requirements of NEC. Traveling cables must run from the junction box on the car directly to the controller. Junction boxes on the car must be equipped with terminal blocks. Terminal blocks having pressure wire connectors of the clamp type that meet UL 486A requirements for stranded wire may be used in lieu of terminal eyelet connections. Terminal blocks must have permanent indelible identifying numbers for each connection. Cables must be securely anchored to avoid strain on individual terminal connections. Flame and moisture resistant outer covering must

remain intact between junction boxes. Abrupt bending, twisting and distortion of the cables must not be permitted.

B. Provide spare conductors equal to 10 percent of the total number of conductors furnished, but not less than 5 spare conductors in each traveling cable.

C. Provide Cat 6 communications cable, Cat 6 camera cable, composite access control cable, shielded wires for the auto dial telephone system within the traveling cable, five (5) pair shielded wires for card reader, one (1) RG-6 Ethernet cable for Wi-FI, two (2) pair 14-gauge wires for 110 Volt power supply and wire for video display monitor.

D. If traveling cables contact the hoistway or elevator due to sway or change in position, provide shields or pads to the elevator and hoistway to prevent damage to the traveling cables.

E. Hardware cloth may be installed from the hoistway suspension point to the elevator pit to prevent traveling cables from rubbing or chafing and securely fastened and tensioned to prevent buckling. Hardware cloth is not required when traveling cable is hung against a flat wall.

2.6 CONTROLLER AND SUPERVISORY PANEL

A. Remove existing and provide new UL/CSA Labeled Controller. Mount all assemblies, power supplies, chassis switches and relays on a steel frame in a NEMA Type 1 General Purpose Enclosure. Cabinet must be securely attached to the building structure.

B. Properly identify each device on all panels by name, letter, or standard symbol which must be neatly stencil painted or decaled in an indelible and legible manner. Identification markings must be coordinated with identical markings used on wiring diagrams. The ampere rating must be marked adjacent to all fuse holders. All spare conductors to controller and supervisory panel must be neatly formed, laced and identified.

C. Controller must be provided with wiring and components for additional future travel if required.

2.7 MICROPROCESSOR CONTROL SYSTEM

A. Provide a microprocessor control system with absolute position/speed feedback to control dispatching, signal functions, door operation and pump motor control. Complete details of the components and printed circuit boards, together with a complete operational description, must be submitted for approval. Provide closed transition SCR soft start.

B. Controller manufacturer must provide factory training, engineering and technical support, including all manuals, wiring diagrams and tools necessary for adjusting, maintenance, repair and testing of equipment to the Owner for use by the Owner’s designated Elevator Maintenance Service Provider.

C. Microprocessor dispatching system must evaluate building traffic demand including number of elevators in service, hall calls, car calls, elevator position, direction of travel, load in elevator, door status and select an elevator to answer hall calls for least possible passenger wait times.

D. Provide a low oil control feature that must shut off the motor and pump and return the elevator to the lowest landing. Upon reaching the lowest landing, doors will open automatically allowing passengers to leave the elevator and then doors must close. All control buttons, except the door open button, alarm bell button and the call for help button must be made ineffective.

2.8 MACHINE ROOM MONITOR

A. Provide a monitor in the machine room. Provide a separate keyboard for each monitor.

B. The monitor must contain indicators to provide the following information:

1. The floor where each elevator is currently located.
2. The direction that each elevator is currently traveling or is scheduled to travel.
3. The location and direction of currently registered hall calls.
4. Elevators that are currently out of service.
5. Elevators that are currently bypassing hall calls.
6. Elevators that are currently engaged in passenger transfers.
7. Operations program under which entire group is currently operating.
8. Zone divisions of the entire group.
9. Door positions.
10. Status indication for elevators on independent service, car top inspection, fire service, earthquake protection and activated stop switch and alarm bell.

C. The maintenance terminal must be suitable for all troubleshooting procedures related to the specific type of microprocessor installed on this project.

2.9 EMERGENCY POWER OPERATION

A. The control system for Elevator(s) must provide for the operation of the elevator on emergency power upon failure of the normal power supply.

B. Auxiliary equipment on elevator controller and wiring between elevator controller and remote selector panel as required to permit the elevator to operate as detailed, must be provided by the Elevator Contractor.

C. Upon loss of normal power supply there must be a delay before transferring to emergency power of 10 seconds minimum to 45 seconds maximum, the delay must be accomplished through an adjustable timing device. After adjusting delay, the associated elevators must function the same as on normal power or as follows:

D. Prior to the return of normal power an adjustable timer circuit must activate that will cause all cars to remain at a floor if already there or stop and remain at the next floor if in flight. Actual transfer of power from auxiliary power to normal building power must take place after all cars are stopped at a floor with their doors open.

2.10 FIREFIGHTER'S SERVICE

A. Provide Firefighter's Service. All key switches must be barrel-key FEOK1.

1. Main Floor:
2. Alternate Floor:
3. Verify main and alternate floors with RE/CO or authorized representative.

2.11 INDEPENDENT SERVICE

A. Provide an INDEPENDENT SERVICE key switch on the face of the main car operating panel or a toggle switch in the service operating panel that must have its positions marked "ON" and "OFF". When the switch is in the "ON" position, the car must respond only to calls registered on its car dispatch buttons and must bypass all calls registered on landing push buttons. The car must start when a car call is registered, car call button or door close button is pressed, car and hoistway doors are closed and interlock circuits are made. When switch is returned to "OFF" position, normal service must be resumed.

2.12 SEISMIC REQUIREMENTS

A. Meet the requirements of the Maine Elevator and Escalator Code.

2.13 PUMP, MOTOR AND VALVE ASSEMBLY

A. Provide new pump assembly for the control of the elevator self-contained in a unit fabricated of structural steel. The unit must consist of a hydraulic fluid pump, AC motor, oil control valves with down speed regulator, muffler, piping and fittings.

B. Control valves must be electronically controlled. Hydraulic fluid flow must be controlled to insure speed variation of not more than five (5) percent under all load conditions in either direction of travel. Locate the manual lowering valve, easily accessible, properly identified and not concealed within the storage tank. Mark the operating handle in red.

C. Pump must be designed for hydraulic elevator service, having a steady discharge without pulsation to give smooth and quiet operation. Pump output must be capable of lifting elevator car with rated capacity, with a speed variation of no more than five (5) percent between no load and full load. Hydraulic fluid by-pass must discharge directly into storage tank.

D. Provide motor specifically designed for elevator service, synchronous speed of 1800 RPM, not to exceed nameplate full load current by more than 10% and rated 120 starts per hour without exceeding a rise of 40 degrees C.

E. Provide isolation pads to prevent transmission of pump and motor vibration to the building.

F. Install blowout-proof, non-hammering, oil-hydraulic muffler in the hydraulic fluid supply pressure line near power unit in machine room. Design muffler to reduce to a minimum any pulsation or noises that may be transmitted through the hydraulic fluid into the hoistway.

2.14 HYDRAULIC SYSTEM

A. Construct the storage tank of sheet steel, welded construction and a steel cover with means for filling, a minimum one-inch protected vent opening and a valve drain connection. Tank must be sized to pass through machine room door as shown on drawings. Provide marked gauge to monitor hydraulic fluid level. Tank must be sized to hold volume of hydraulic fluid required to lift elevator to stop ring, plus a reserve of not less than ten gallons. Provide a baffle in the bottom of the tank to prevent entry of any sediment or foreign particles into hydraulic system. Baffle must also minimize aeration of hydraulic fluid. Permissible minimum hydraulic fluid level must be clearly indicated. Hydraulic fluid must be of good grade to assure free flow when cool and have minimum flash point of 380-400 degrees F. Provide initial supply of hydraulic fluid for operation of elevator.

1. Provide a means to maintain the fluid viscosity in the reservoir, pump and control valve at the manufacturer's recommended operating temperature.
2. Provide a data plate on the tank frame indicating the characteristics of the hydraulic fluid used.

B. Provide and install connections between the storage tank, pump, muffler, operating valves and cylinder complete with necessary valves, pipe supports and fittings. Pipe must be minimum schedule 40 steel with threaded, flanged, or welded mechanical couplings. Size of pipe and couplings between cylinder and pumping unit must be such that fluid pressure loss is limited to 10 percent.

C. Hydraulic system working pressure must not exceed 500 psi under any load condition. Do not subject valves, piping and fittings to working pressure greater than those recommended by the manufacturer.

D. Support all horizontal piping. Place hangers or supports within 12 inches on each side of every change of direction of pipeline and space supports not over 10 feet apart. Secure vertical runs properly with iron clamps at sufficiently close intervals to carry weight of pipe and contents. Provide supports under pipe to floor.

1. Provide all piping from machine room to hoistway, including necessary supports or hangers. If remote piping is underground or in damp inaccessible areas, install hydraulic piping thru PVC sleeve.

E. Install pipe sleeves where pipes pass through walls or floors. After installation of piping, equip the sleeves with snug fitting inner liner of fire rated insulation.

F. Provide an automatic shut-off valve in the oil supply line at the cylinder inlet. Activate the automatic shut-off valve when there is more than a ten percent increase in high speed in the down direction. When activated, this device must immediately stop the descent of the elevator and hold the elevator. The exposed adjustments of the automatic shut-off valve must have their means of adjustment sealed after being set to their correct position.

G. Provide external tank shut-off valve to isolate hydraulic fluid during maintenance operations.

H. Provide shut-off valves in the pit near the cylinder and in the machine room capable of withstanding 150 percent of design operating pressure. Each manual valve must have an attached handle.

I. Provide oil-tight drip pan for assembled pumping unit, including storage tank. Pan must be not less than 16-gauge sheet steel, with one-inch sides.

J. Components of the hydraulic system must be factory certified to withstand pressure equal to twice the calculated working pressure.

2.15 HYDRAULIC PLUNGER ASSEMBLY (ALLOWANCE #7)

A. If existing hydraulic plunger assembly is in need of replacement, provide new cylinder and plunger sized to lift gross load the height specified. Factory test the plunger assembly at a pressure equal to twice the calculated working pressure, for strength and to insure freedom from leakage. Provide bottom of cylinder head with internal guide bearing and top of cylinder head with removable packing gland. Victaulic type packing gland head must not be permitted.

1. Provide a bleeder valve located below the cylinder flange to release air or other gases from the system.
2. Equip cylinder with drip ring below the packing gland to collect leakage of hydraulic fluid.
3. Bolt the cylinder mounting brackets to footing channels that support the buffers.

B. Install a flexible tubing scavenger line with an electrically operated pump between the piston drip ring and oil storage tank. Scavenger line, pump and strainers must operate independently of hydraulic fluid pressure. Equip scavenger pump with a water float designed to prevent operation of the pump should the pit flood and designed to be manually reset. Secure pump and reservoir to the pit channels.

C. Plunger must be heavy seamless steel tubing, turned smooth and true to within plus or minus 0.015 inch tolerance and no diameter change greater than 0.003 inches per-inch of length. Where plunger is multi-piece construction, machine the joints to assure perfectly matching surfaces.

1. Secure plunger to underside of platform supporting beams with fastenings capable of supporting four times the weight of the plunger. The platen plate must incorporate piston to car vibration isolation.
2. Provide a stop ring welded or screwed to the bottom of plunger that must prevent the plunger from leaving its cylinder.
3. Isolate plunger head from the platen plate to prevent corrosion or electrolysis.
4. Protect plunger, repair or replace if gouged, nicked or scored.

2.16 HYDRAULIC CYLINDER CASING AND PVC LINER (ALLOWANCE #6)

A. If existing casing and PVC liner is missing or in need of replacement, provide new drilled hole, cylinder casing and PVC casing liner.

B. Clean casing and remove waste oil, sand and other waste materials from site.

C. Provide PVC casing liner to fit inside steel casing or fabricate liner with watertight bottom and a top flange gasket to seal plunger flange and form a complete, watertight, electrically non-conductive encasement of the entire unit.

2.17 CAR BUFFERS

A. Provide two new spring buffers for the elevator. Securely fasten buffers and supports to the pit channels and in the alignment with striker plates on elevator. Buffers must have a permanently attached metal plate indicating its stroke and load rating. Buffer anchorage must not puncture pit waterproofing.

B. Provide pipe stanchions and struts as required to properly support the buffer.

2.18 GUIDE RAILS, SUPPORTS AND FASTENINGS

A. Reuse existing. Clean, replace missing bolts and tighten as needed.

2.19 NORMAL AND FINAL TERMINAL STOPPING DEVICES

A. Mount new terminal slowdown switches and direction limit switches on the elevator or in hoistway to reduce speed and bring car to an automatic stop at the terminal landings.

1. Switches must function with any load up to and including 100 percent of rated elevator capacity at any speed obtained in normal operation.
2. Switches, when opened, must permit operation of elevator in reverse direction of travel.

B. Mount final terminal stopping switches in the hoistway.

1. Switches must be positively opened should the car travel beyond the terminal direction limit switches.
2. Switches must be independent of other stopping devices.
3. Switches, when opened, must remove power from pump motor and control valves preventing operation of car in either direction.

2.20 CROSSHEAD DATA PLATE AND CODE DATA PLATE

A. Permanently attach a non-corrosive metal Data Plate to car crosshead.

B. Permanently attach a Code Data Plate, in plain view, to the controller.

2.21 WORKMAN'S LIGHTS AND OUTLETS

A. Provide duplex GFCI protected type receptacles and lamp, with guards on top of elevator car and beneath platform.

B. The receptacles must be in accordance with Fed. Spec. W-C-596 for Type D7, 2-pole, 3-wire grounded type rated for 15 amperes and 125 volts.

2.22 CARTOP OPERATING DEVICE

A. Provide a new cartop operating device.

B. The device must be activated by a toggle switch mounted in the device. The switch must be clearly marked "INSPECTION" and "NORMAL" on the faceplate, with 0.25 inch letters.

C. Movement of the elevator must be accomplished by the continuous pressure on a direction button and a safety button.

D. Provide an emergency stop switch, push to stop/pull to run.

E. Provide permanent identification for the operation of all components in the device.

F. The device must be permanently attached to the elevator crosshead on the side of the elevator nearest to the hoistway doors used for accessing the top of the car.

2.23 LEVELING DEVICE

A. Car must be equipped with a new two-way leveling device to automatically bring the car to within 0.125 inches of exact level with the landing for which a stop is initiated regardless of load in car or direction of travel.

B. If the car stops short or travels beyond the floor, the leveling device, within its zone must automatically correct this condition and maintain the car within 0.125 inches of level with the floor landing regardless of the load carried.

2.24 EMERGENCY STOP SWITCHES

A. Provide an emergency stop switch, push to stop/pull to run, for the top-of-car device, pit, machine spaces, service panel and firefighter's control panel inside the elevator. Mount stop switches in the pit adjacent to pit access door, at top of the pit ladder 48 inches above the bottom landing sill and 48 inches above the pit floor adjacent to the pit ladder.

B. Each stop switch must be red in color and must have "STOP" and "RUN" positions legibly and indelibly identified.

2.25 MAIN CAR OPERATING PANEL

A. Provide new main car operating panel in the car enclosure on the front return panel for passenger/service elevators. The top floor car call push button must not be more than 48 inches above the finished floor. "Vandal Resistant" car push buttons and indicator lights must be LED illuminated, round with a minimum diameter of 1 inch. Each button must contain an integral registration LED white light which must illuminate upon registration of a call and must extinguish when that call is answered.

B. One-piece hinged front faceplate with edges beveled 15 degrees must have the firefighter's service panel recessed into the upper section and the service operation panel recessed into the lower section fitted with hinged doors. Doors must have concealed hinges, be in the same front plane as the faceplate and fitted with cylinder type key operated locks. Secure the faceplate with stainless steel tamperproof screws.

C. All terminology and tactile symbols on the faceplate must be on square or rectangular plates recessed into the faceplate with its surface flush with the surface of the faceplate. Use 0.25 inch letters to identify all devices in the faceplate. The handicapped markings with contrasting background must be 0.50 inches high raised 0.030 inches on the plate. Surface mounted plates are not acceptable.

D. The upper section must contain the following items in order listed from top to bottom:

1. Elevator number, 0.50 inches high with black paint for contrast.
2. Capacity plate information with black paint for contrast with freight loading class and number of passengers allowed.
3. LED illuminated digital car position indicator with direction arrows.
4. Emergency car lighting system consisting of a rechargeable battery, charger, controls and LED illuminated light fixture. The system must automatically provide emergency light in the car upon failure or interruption of the normal car lighting service and function irrespective of the position of the light control switch in the car. The system must maintain a minimum

illumination of 1.0 foot-candle when measured 48 inches above the car floor and approximately 12 inches in front of the car operating panel, for not less than four (4) hours.

5. Firefighter's Emergency Operation Panel must be 66 inches minimum to 72 inches maximum to the top of the panel above finished floor.
6. Firefighter's Emergency Indicator Light must be round with a minimum diameter of 1 inch.
7. Key operated Independent Service Switch on the face of panel.
8. Provide a Door Hold Button on the faceplate above the call buttons. It must have "DOOR HOLD" indelibly marked on the button. Button must light when activated. When activated, the door must stay open for a maximum of one minute. To override hold timer, push a car call button or door close button.
9. Provide round "Vandal Resistant" car push buttons and indicator lights, minimum diameter of 1 inch and LED illuminated, corresponding to the floors served. Car call buttons must be legibly and indelibly identified by a floor number, letter or symbol not less than 0.50 inches high in the face of the button or indicator.
10. Door Open and Door Close buttons must be located below the car call buttons. They must have "OPEN" and "CLOSE" legibly and indelibly identified by letters in the face of the respective button. The Door Open button must be located closest to the door jamb.
11. Red Emergency Alarm button that must be located below the car operating buttons. Mount the emergency alarm button not lower than 35 inches above the finished floor. It must be connected to audible signaling devices. Provide audible signaling devices including the necessary wiring.
12. Emergency Help push button must activate two-way communications by Auto Dial telephone system that is compatible with the VAMC's telephone system. Help button must be LED white light illuminated and flash when call is acknowledged. Legibly and indelibly label the button "HELP" in the face of the button with 0.50 inch high letters.

E. The service operation panel, in the lower section must contain the following items:

1. Light switch labeled "LIGHTS" for controlling interior car lighting with its two positions marked "ON" and "OFF".
2. Inspection switch that will disconnect normal operation and activate hoistway access switches at terminal landings. Switch must be labeled "ACCESS ENABLE" with its two positions marked "ON" and "OFF".
3. Three position switch labeled "FAN" with its positions marked "HIGH", "LOW" and "OFF" for controlling car ventilating blower.
4. Two position, spring return, toggle switch or push button to test the emergency light and alarm device. It must be labeled "TEST EMERGENCY LIGHT AND ALARM".
5. Independent service switch labeled "ON" AND "OFF". (Delete if key switch on face of panel).
6. Two-position emergency stop switch, when operated, must interrupt power supply and stop the elevator independently of regular operating devices. Emergency stop switch must be marked "PUSH TO STOP" and "PULL TO RUN".

2.26 AUXILIARY CAR OPERATING PANEL

A. Provide an auxiliary car operating panel in the front return panel opposite the main car operating panel. The auxiliary car operating panel must contain only those controls essential to passenger (public) operation. The auxiliary car operating panel faceplate must match the main car operating panel faceplate in material and general design. Secure the faceplate with stainless steel tamperproof screws.

1. Provide round “Vandal Resistant” car push buttons and indicator lights, minimum diameter 1 inch and LED illuminated corresponding to the floors served. Car buttons and indicator lights must be legibly and indelibly identified by a floor number, letter, or symbol not less than 0.50 inches high in the face of the button or indicator light corresponding to the main car operating panel buttons or indicator light.
2. Door "OPEN" and door "CLOSE" buttons closest to the door jamb and mount the alarm button no lower than 35 inches above the finished floor. The Door Open button must be located closest to the door.
3. Cross-connect all buttons in the auxiliary car operating panels to their corresponding buttons in the main car operating panel. Registration of a car call must cause the corresponding button to illuminate in the main and auxiliary car operating panel.
4. Emergency Help push button must activate two-way communications by auto dial telephone that is compatible with the VAMC’s telephone system. Help button must be LED white light illuminated and flash when call is acknowledged. Legibly and indelibly label the button “HELP” in the face of the button with 0.50 inch high letters.

B. All terminology and tactile symbols on the faceplate must be on square or rectangular plates recessed into the faceplate with its surface flush with the surface of the faceplate. Use 0.25 inch letters to identify all devices in the faceplate. The tactile symbols with contrasting background must be 0.50 inches high raised 0.030 inches on the plate. Surface mounted plates are not acceptable.

2.27 CAR POSITION INDICATOR

A. Provide an alpha-numeric digital car position indicator in the main car operating panel, consisting of numerals and arrows 2.5 inches high, to indicate position of car and direction of car travel. Locate position indicator at the top of the main car operating panel, illuminated by light emitting diodes.

2.28 AUDIO VOICE SYSTEM

A. Provide digitized audio voice system activated by stopping at a floor. Audio voice must announce floor designations, direction of travel and special announcements. The voice announcement system must be a natural sounding human voice that receives messages and must comply with ADA requirements for audible car position indicators. The voice announcer must have two separate volume controls, one for the floor designations and direction of travel and another for special announcements. The voice announcer must have a full range loudspeaker, located on top of the cab. The audio voice unit must contain the number of ports necessary to accommodate the number of floors, direction messages and special announcements. Install voice announcer per manufacturer’s recommendations and instructions. The voice system must be the product of a manufacturer of established reputation. Provide manufacturer literature and list of voice messages.

1. Fire Service Message.
2. “Please do not block doors”.
3. Provide special messages as directed by COR.

2.29 AUTO DIAL TELEPHONE SYSTEM

A. Provide a complete, ADA compliant, auto dial communication system that is compatible with the VAMC’s telephone system.

B. Two-way communication device shall be in full compliance with ASME A17.1 Rule 2.27.1.1 (2019) or later editions.

2.30 CORRIDOR OPERATING DEVICES

A. Provide new corridor operating device faceplates from not less than 0.125 inch thick flat stainless steel with all edges beveled 15 degrees.

B. Corridor push button faceplates must be sized to cover existing openings in the walls. The centerline of the landing push buttons must be 42 inches above the corridor floor.

C. Elevator Corridor Call Station Pictograph must be engraved in the faceplate.

D. Fasten all car and corridor operating device and signal device faceplates with stainless steel tamperproof screws.

E. All terminology and tactile symbols on the faceplate must be raised .030 inch with contrasting background, on square or rectangular plates recessed into the faceplate with its surface flush with the surface of the faceplate. The handicapped markings with contrasting background must be 0.50 inches high raised 0.030 inches on the plate, square or rectangular. Use 0.25 inch letters to identify all other devices in the faceplate. Surface mounted plates are not acceptable.

F. Provide one riser of landing call buttons for each elevator or group of elevators as shown on contract drawings.

G. “Vandal Resistant” hall buttons and indicator lights must be LED illuminated upon registration of a call and shall extinguish when that call is answered.

H. The direction of each button must be legibly and indelibly identified by arrows not less than 0.50 inches high in the face of each button. Provide a corresponding Braille plate on the left side of each button.

I. Hall call buttons must not re-open the doors while the car and hoistway doors are closing at that floor. Calls registered must be canceled if closing doors are re-opened by means of "DOOR OPEN" button or infrared curtain unit.

J. Provide emergency power indicator light, fire service recall key switch and indicator light, fire recall instruction, communication failure light, audible enunciator and reset key switch in the fixture at the designated main floor.

K. Remove old fixtures, repair and refinish walls.

L. Submit design of hall pushbutton fixtures for approval.

2.31 CORRIDOR ARRIVAL LANTERN/POSITION INDICATOR

A. Provide combination fixtures at main and alternate fire recall floors. Provide each terminal landing with "UP" or "DOWN", minimum 2.5 inches high digital arrow lanterns and each intermediate landing with "UP" and "DOWN" digital arrow lanterns. Each lens must be LED illuminated of proper intensity, so shielded to illuminate individual lens only. The lenses in each lantern must be illuminated green to indicate "UP" travel and red to indicate "DOWN" travel. Lanterns must signal in advance of car arrival at the landing indicating the direction of travel.

Corridor lanterns must not be illuminated when a car passes a floor without stopping. Each lantern must be equipped with an audible electronic chime which must sound once for "UPWARD" bound car and twice for "DOWNWARD" bound car. Audible signal must not sound when a car passes the floor without stopping. Provide adjustable sound level on audible signal. Car riding lanterns are not acceptable.

B. Install alpha-numeric digital position indicator between the arrival lanterns. Indicator faceplate must be stainless steel. Numerals must be not less than 2.5 inches high with direction arrows. Cover plates must be readily removable for re-lamping. The appropriate direction arrow must be illuminated during entire travel of car in corresponding direction.

C. Remove old fixtures, repair and refinish walls.

2.32 HOISTWAY ACCESS

A. Provide new n hoistway access switches for elevator at top terminal landing to permit access to top of car and at bottom terminal landing to permit access to pit. Elevators with side slide doors, mount the access key switch 6 feet above the corridor floor in the wall next to the strike jamb.

B. Exposed portion of each access switch or its faceplate must have legible, indelible legends to indicate "UP", "DOWN" and "OFF" positions.

C. Each access switch must be a constant pressure cylinder type lock having not less than five pins or five stainless steel disc combination with key removable only when switch is in the "OFF" position.

D. Lock must not be operable by any other key which will operate any other lock or device used for any other purpose.

E. Arrange the hoistway switch to initiate and maintain movement of the car. When the elevator is operated in the down direction from the top terminal landing, limit the zone of travel to a distance not greater than the top of the car crosshead level with the top floor. Submit design and location of access switches for approval.

F. Provide emergency access for all hoistway entrances, keyways for passenger and service elevators.

2.33 HOISTWAY ENTRANCES: PASSENGER/SERVICE ELEVATORS

A. Provide new stainless-steel entrance frames.

B. Clean and reuse existing hoistway sills, hanger supports, strut angles, fascia plates and toe guards.

C. Replace all damaged or missing dust covers.

D. Provide new stainless steel hoistway doors. Door panels must be flush hollow metal construction, not less than 1.25 inches thick, consisting of one continuous piece 16-gauge stainless steel on corridor side wrapped around the leading edge. Separate two plates by a sound-deadening material and reinforce by steel shapes welded to the plates at frequent intervals. Reinforce panels as required for installation of hangers, power-operating and door-opening devices. Top and bottom of door panels must have continuous stiffener channels welded in place. Reinforcement of the door panels must be a minimum of 0.04 inches in thickness and of the hat section type.

E. Hang doors on two-point suspension hangers having sealed ball-bearing sheaves not less than 3 inches in diameter, with non-metallic sound-reducing tires. Equip hangers with adjustable ball-bearing rollers to take upward thrust of panels. Provide two removable non-metallic door gibs of approved material and a separate fire gib at the bottom of each door panel. Gibs must be replaceable without removing of door panel. One door panel for each entrance must bear an Underwriters' label, or other labels may be furnished provided they are based on fire test reports and factory inspection procedures acceptable to the State Elevator Inspector. Fasten stainless steel sight guard of 14-gauge metal, extending full height of panel, to leading edge of fast speed panel of two-speed doors.

F. Provide new hardware, tracks, gibs, separate fire gibs, door rollers, door locks, drive roller assemblies and sill mounted closers or spirators.

G. Provide new Braille plates on both sides of door frame entrances located 60 inches to center above finished floor.

H. Provide unique car number on every elevator entrance at designated main fire service floor level, minimum 3 inches in height.

I. Equip each hoistway entrance with new electrical/mechanical interlock, functioning as hoistway unit system, to prevent operation of elevator until all hoistway doors are locked in the closed position unless car is operating in the leveling zone or hoistway access switch is used.

J. Wiring installed from the hoistway riser to each door interlock must be NEC type SF-2 or equivalent.

2.34 CAR GUIDES

A. Provide new adjustable roller guides, each assembled on a substantial metal base, to permit individual alignment to the guide rails.

B. Each guide must consisting of not less than three (3) wheels, each with a durable, resilient oil-resistant material tire rotating on ball bearings having sealed-in lubrication. Assemble rollers on a substantial metal base and mount to provide continuous spring pressure contact of all wheels with the corresponding rail surfaces under all conditions of loading and operation. Secure the roller guides at top and bottom on each side of car frame and counterweight frame. All mounting bolts must be fitted with nuts, flat washers, split lock washers and if required, beveled washers.

C. Provide sheet metal guards to protect rollers on top of car and counterweight.

D. Minimum diameter of car rollers must be 6 inches. The entire elevator car must be properly balanced to equalize pressure on all guide rollers. Cars must be balanced in post-wise and front-to-back directions. Test for this balanced condition must be witnessed at time of final inspection.

E. Equip car with an auxiliary guiding device for each guide that must prevent the car from leaving the rails if the normal guides fail. These auxiliary guides must not, during normal operation, touch the guiding surfaces of the rails. Fabricate the auxiliary guides from hot rolled steel plate and mount between the normal guide shoes and the car frames. The auxiliary guides may be an extension of the normal guide shoe mounting plate if that plate is fabricated from hot rolled steel. The portion of the auxiliary guide which must contacts the rail guiding surfaces in the event of loss of the normal guides must be lined with an approved bearing material to minimize damage to the rail guiding surfaces.

2.35 CAR FRAME: PASSENGER ELEVATORS

A. Car frame must be constructed of channel stiles, crosshead, gussets and braces, securely bolted and/or welded. The entire assembly must be constructed to withstand unequal loading of platform. Car frame members must be constructed to relieve the car enclosure of all strains.

2.36 CAR PLATFORM: PASSENGERELEVATORS

A. The platform must be designed to withstand the forces developed under the loading class specified. Provide car entrance with new stainless-steel sill with machined or extruded guide grooves and recessed- for platform guard. Cover underside and all exposed edges of wood filled platform with sheet metal of not less than 27-gauge, with all exposed joints and edges folded under. Fire resistant paint is not acceptable. Platform must have flexible composition flooring not less than 0.125 inches thick. Adhesive material must be type recommended by manufacturer of flooring. Lay flooring flush with threshold plate and base.

B. Provide a platform guard (toe guard) of not less than 12-gauge sheet-steel on the entrance side, extend 3 inches beyond each side of entrance jamb. Securely brace platform guard to car platform and bevel bottom edge at a 60-75-degree angle from horizontal. Install platform in the hoistway, so that the clearance between front edge and landing threshold must not exceed 1.25 inches.

C. Provide new isolation pads between the platform and platform frame. Use approved rubber pads or other approved material.

D. Provide adjustable diagonal brace rods to hold platform firmly within car suspension frame.

E. Balance car front to back and side to side. Provide balancing frame and weights, properly located, to achieve the required true balance.

F. Provide a bonding wire between frame and platform.

2.37 CAR ENCLOSURE: PASSENGER ELEVATORS

A. Car enclosure must have a dome height inside the cab of 8 feet.

B. Securely fasten car enclosure to platform by through bolts located at intervals of not more than 18 inches running through an angle at the base of panels to underside of platform.

C. Front return wall panel, entrance columns, entrance head-jamb and transom must be 14-gauge stainless steel. Transom must be full width of cab. Side and rear walls must be constructed of 14-gauge cold rolled steel. Coat exterior of walls with mastic sound insulation material approximately 0.10 inches thick followed by a prime coat of paint.

D. Side and rear walls of passenger elevators may have raised panels covered in fire rated materials approved for use in elevator interior.

E. Construct canopy of not less than 12-gauge steel.

F. Provide car top railings.

G. Provide a hinged top emergency exit cover. Exit must be unobstructed when open and must have mechanical stops on the cover. Provide an exit switch to prevent operation of the elevator when the emergency exit is open.

H. Provide duplex, GFCI protected receptacle in car. Locate flush-mounted receptacle on the centerline of the main car operating panel, 6 inches above the car floor.

I. Lighting for passenger/service elevators:

1. Provide stainless steel hanging ceiling frame. Construct frame of 0.125 inches thick x 1.50 inches wide x 1.50 inches high “T” and “L” sections, divide ceiling into six panels.
2. Provide LED illuminated car light fixtures above the ceiling panels. Maintain a minimum light level of 50-foot candles at 36 inches above the finished floor.

J. Provide a blower unit arranged to exhaust through an opening in the canopy. Provide a stainless or chrome plated fan grill on the interior side of the opening. Provide screening over intake and exhaust end of blower. Provide 2-speed fan, with rated air displacement of 250 cfm and 400 cfm at respective speeds. Mount fan on top of car with rubber isolation to prevent transmission of vibration to car structure. Provide a 3-position switch to control the unit in the service panel.

K. Provide car enclosure with two sets of handrails with centerlines 30 inches and 42 inches above the car floor.

1. Locate handrails 1.50 inches from cab wall. Install handrails on side and rear walls. Conceal all handrail fastenings. Handrails must be removable from inside the car enclosure.

L. Provide passenger car with single speed center opening horizontal sliding doors constructed the same as hoistway doors.

M. Provide one set of protective pads of sufficient length to completely cover two sides, rear walls and front return of cab interior. Pads must consist of a minimum of 0.25 inches thick glass fiber insulation securely sewn between flame resistant vinyl coated coverings. Color of the covering must be approved by the Owner. Provide stainless steel pad buttons or hooks, spaced at intervals of not more than 18 inches to adequately support pads.

2.37 POWER DOOR OPERATORS: PASSENGER ELEVATORS

A. Provide a new high-speed heavy-duty door operator to automatically open the car and hoistway doors simultaneously when the car is level with the floor and automatically close the doors simultaneously at the expiration of the door-open time. Provide solid-state door control with closed loop circuitry to constantly monitor and automatically adjust door operation based upon velocity, position and motor current. Motor must be of the high-internal resistance type, capable of withstanding high currents resulting from stall without damage to the motor. The door operator must open the car door and hoistway door simultaneously, at a speed of 2.5 feet per second. The closing speed of the doors must be 1 foot per second. A reversal of direction of the doors from the closing to opening operation, whether initiated by obstruction of the infrared curtain or the door "OPEN" button, must be accomplished within 1.5 inches maximum of door movement. Emphasis is placed on obtaining quiet interlock and door operation; smooth, fast, dynamic braking for door reversals, stopping of the door reversal and stopping of the doors at extremes of travel. Construct all levers and drive arms operating the doors, of heavy steel members and all pivot points must have ball or roller bearings.

B. Car and hoistway doors must be manually operable (open only) in an emergency without disconnecting the power door operating equipment unless the car is outside the unlocking zone.

1. It must not be possible for the doors to open by power unless the elevator is within the leveling zone.
2. Provide infrared curtain unit. The device must cause the car and hoistway doors to reverse automatically to the fully open position should the unit be actuated while the doors are closing. Unit must function when the doors are not closed, irrespective of all other operating features except firefighter's service.

C. Should the doors be prevented from closing for more than a predetermined adjustable interval of 20 to 60 seconds by operation of the curtain unit, the doors must stay open, the audio voice message and a buzzer located on the car must sound only on automatic operation. Do not provide door nudging.

1. If an obstruction of the doors should not activate the photo-electric door control device and prevent the doors from closing for more than a predetermined adjustable interval of 15 to 30 seconds, the doors must reverse to the fully open position and remain open until the "Door Close" button re-establishes the closing cycle.

D. Provide door "OPEN" and "CLOSE" buttons. When the door "OPEN" button is pressed and held, the doors, if in the open position, must remain open and if the doors are closing, they must stop, reverse and re-open. Momentary pressure of the door "CLOSE" button must initiate the closing of the doors prior to the expiration of the normal door open time.

PART 3 - EXECUTION

3.1 PREPARATION

A. Examine work of other trades on which the work of this section depends. Report defects to the Owner in writing which may affect the work of the elevator contractor.

B. Examine elevator hoistway openings for plumb, level, in line and that elevator pit is proper size, waterproofed and drained with necessary access door and ladder.

C. Examine machine room for proper illumination, heating, ventilation, electrical equipment and beams are correctly located complete with access stairs and door.

D. Before fabrication, take necessary job site measurements and verify where work is governed by other trades. Check measurement of space for equipment and means of access for installation and operation. Obtain dimensions from site for preparation of shop drawings.

E. Work required prior to the completion of the elevator installation:

1. Supply of electric feeder wires to the terminals of the elevator control panel, including circuit breaker.
2. Provide light and GFCI outlets in the elevator pit and machine room.
3. Furnish electric power for testing and adjusting elevator equipment.
4. Furnish circuit breaker panel in machine room for car and hoistway lights and receptacles.
5. Supply power for cab lighting and ventilation from an emergency power panel specified in Division 26, ELECTRICAL.

6. Machine room enclosed and protected from moisture, with self-closing, self-locking door and access stairs.
7. Provide fire extinguisher in machine room.

3.2 ARRANGEMENT OF EQUIPMENT

A. Arrange equipment in machine room so that major equipment components can be removed for repair or replacement without dismantling or removing other equipment in the same machine room. Locate controller near and visible to its respective hoisting machine.

3.3 WORKMANSHIP AND PROTECTION

A. Installations must be performed by Certified Elevator Mechanics and Apprentices to best possible industry standards. Details of the installation must be mechanically and electrically correct. Materials and equipment must be new and without imperfections.

B. Recesses, cutouts, slots, holes, patching, grouting, refinishing to accommodate installation of equipment must be included in the Contractor's work. All new holes in concrete must be core drilled.

C. Structural members must not be cut or altered. Work in place that is damaged or defaced must be restored equal to original new condition.

D. Finished work must be straight, plumb, level and square with smooth surfaces and lines. All machinery and equipment must be protected against dirt, water, or mechanical injury. At completion, all work must be thoroughly cleaned and delivered in perfect unblemished condition.

E. Sleeves for conduit and other small holes must project 2 inches above concrete slabs.

F. Exposed gears, sprockets and sheaves must be guarded from accidental contact.

3.4 CLEANING

A. After completion of installation and prior to final inspection, all equipment must be thoroughly cleaned of grease, oil, cement, plaster, dust and other debris.

B. Clean machine room and equipment.

C. Perform hoistway clean down.

D. Prior to final acceptance remove protective coverings from finished or ornamental surfaces. Clean and polish as required for type of material.

3.5 PAINTING AND FINISHING

A. All equipment, except specified as architectural finish, must be painted one coat of approved color, conforming to manufacturer's standard.

B. Pump Unit Assembly must be factory painted with manufacturer's standard finish and color.

C. Controller, sheave, car frame and platform, counterweight, beams, rails and buffers except their machined surfaces, cams, brackets and all other uncoated ferrous metal items must be painted one factory primer coat or approved equal.

D. Stencil or apply decal floor designations not less than 4 inches high on hoistway doors, fascia or walls within door restrictor areas. The color of paint used must contrast with the color of the surfaces to which it is applied.

E. Elevator pump/motor machine, controller, main line switch/shunt trip circuit breaker, bolster channel and cross head of car must be identified by 4-inch high numerals and letters located as directed. Numerals must contrast with surrounding color and must be stenciled or decaled.

F. Hoistway Entrances of Passenger Elevators:

1. Door panels must be given rust resistant treatment and a factory finish of one coat of baked-on primer and one factory finish coat of baked-on enamel.
2. Fascia plates, top and bottom shear guards, dust covers, hanger covers and other metalwork, including built-in or hidden work and structural metal, (except stainless steel entrance frames and surfaces to receive baked enamel finish) must be given one approved prime coat in the shop and one field coat of paint of approved color.

G. Elevator Cabs for Passenger Elevators:

1. Interior and exterior steel surfaces must be given rust resistant treatment before finish is applied.
2. Interior steel surfaces must be factory finished with one coat of paint of approved color.
3. Give exterior faces of car doors one finish coat of paint of approved color.

3.6 PRE-TESTS AND TESTS

A. Pre-test the elevators and related equipment in the presence of the Owner or his authorized representative for proper operation before requesting final inspection. Conduct final inspection at other than normal working hours, if required by the State Elevator Inspector.

1. The Contractor must obtain the services of an Independent Qualified Elevator Inspector, ANSI/ASME QEI-1 Certified, that must witness all tests. The QEI must utilize an Elevator Acceptance Inspection Form to record the results of inspection and all testing and to identify safety code and contract deficiencies. Specific values must be provided for all tests required by ASME A17.1, ASME A17.2 and contract documents. After completion of inspection and testing, the QEI must sign a copy of the completed form and provide it to the Architect. Within 14 days of the inspection, the QEI must also prepare a formal inspection report, including all test results and deficiencies. After successful completion of inspection and testing, the QEI will complete, sign and provide a certificate of compliance.
2. Owner must furnish electric power including necessary current for starting, testing and operating machinery of each elevator.
3. Contractor must furnish the following test instruments and materials on-site and at the designated time of inspection: properly marked certified test weights, voltmeter, amp probe, thermometers, direct reading tachometer, megohm meter, vibration meter, sound meter, light meter, stopwatch and a means of two-way communication.

B. Inspection of workmanship, equipment furnished and installation for compliance with specification.

C. Full-Load Run Test: Elevators must be tested for a period of one-hour continuous run with full contract load in the car. The test run must consist of the elevator stopping at all floors, in either direction of travel, for not less than five or more than ten seconds per floor.

D. Speed Test: The actual speed of the elevator must be determined in both directions of travel with full contract load and no load in the elevator. Speed must be determined by certified tachometer. The actual measured speed of the elevator with all loads in either direction must be within five (5) percent of specified rated speed. Full speed runs must be quiet and free from vibration and sway.

E. Temperature Rise Test: The temperature rise of the pump motor must be determined during the full load test run. Temperatures must be measured using thermometers. Under these conditions, the temperature rise of the equipment must not exceed 50 degrees Centigrade above ambient temperature. Test must start when all machine room equipment is within 5 degrees Centigrade of the ambient temperature. Other tests for heat runs on motors must be performed as prescribed by the Institute of Electrical and Electronic Engineers.

F. Car Leveling Test: Elevator car leveling devices must be tested for accuracy of leveling at all floors with no load in car and with contract load in car in both directions of travel. Accuracy of floor level must be within plus or minus 0.125 of level with any landing floor for which the stop has been initiated regardless of load in car or direction of travel. The car leveling device must automatically correct over travel as well as under travel and must maintain the car floor within plus or minus 0.125 inches of level with the landing floor regardless of change in load.

G. Insulation Resistance Test: The elevator's complete wiring system must be free from short circuits and ground faults and the insulation resistance of the system must be determined by use of megohm meter, at the discretion of the Elevator Inspector conducting the test.

H. Overload Devices: Test all overload current protection devices in the system at final inspection.

I. Limit Stops:

1. The position of the car when stopped by each of the normal limit stops with no load and with contract load in the car must be accurately measured.
2. Final position of the elevator relative to the terminal landings must be determined when the elevator has been stopped by the final limits. The lower limit stop must be made with contract load in the elevator. Elevator must be operated at inspection speed for both tests. Normal limit stopping devices must be inoperative for the tests.

J. Working Pressure: Verify working pressure of the hydraulic system by pressure gauge placed in the system line. Take readings with no load and full load in car.

K. Test automatic shut-off valve for proper operation.

L. Operating and Signal System: The elevator must be operated by the operating devices provided and the operation signals and automatic floor leveling must function in accordance with requirements specified. Starting, stopping and leveling must be smooth and comfortable without appreciable steps of acceleration or deceleration.

M. Performance of the Elevator supervisory system must be witnessed and approved by the Elevator Inspector.

N. Evidence of malfunction in any tested system or parts of equipment that occurs during the testing must be corrected, repaired, or replaced at no additional cost to the Owner and the test repeated.

O. If equipment fails test requirements and a re-inspection is required, the Contractor must be responsible for the cost of re-inspection; salaries, transportation expenses and per-diem expenses incurred by the representative of the Owner.

3.7 INSTRUCTION TO OWNER PERSONNEL

A. Provide competent instruction to Owner personnel regarding the operation of equipment and accessories installed under this contract, for a period equal to one eight-hour workday. Instruction must commence after completion of all work and at the time and place directed by the Owner or authorized representative.

B. Written instructions in triplicate relative to care, adjustments and operation of all equipment and accessories must be furnished and delivered to the Owner or authorized representative in independently bound folders. DVD recordings will also be acceptable. Written instructions must include correct and legible wiring diagrams, nomenclature sheet of all electrical apparatus including location of each device, complete and comprehensive sequence of operation, complete replacement parts list with descriptive literature and identification and diagrammatic cuts of equipment and parts. Information must also include electrical operation characteristics of all circuits, relays, timers and electronic devices, as well as rpm values and related characteristics for all rotating equipment.

C. Provide supplementary instruction for any new equipment that may become necessary because of changes, modifications or replacement of equipment or operation under requirements of paragraph entitled "Warranty of Construction".

3.8 ELEVATOR GUARANTEE PERIOD OF SERVICE: MAINTENANCE SERVICE AND INSPECTIONS

A. Provide complete maintenance service and inspections during the modernization period for all elevators and on each elevator for one (1) year after completion and acceptance of elevator in this specification by the Owner. This maintenance service must run concurrently with the warranty. Maintenance work must be performed by Certified Elevator Mechanics and Apprentices.

B. This contract will cover full maintenance including emergency call back service, inspections and servicing the elevators listed in the schedule of elevator. The Elevator Contractor must be required to perform the following:

1. Monthly systematic examination of equipment.
2. During each maintenance visit the Elevator Contractor must clean, lubricate, adjust, repair and replace all parts as necessary to keep the equipment in first class condition and proper working order.
3. Furnishing all lubricant, cleaning materials, parts and tools necessary to perform the work required. Lubricants must be only those products recommended by the manufacturer of the equipment.
4. As required, motors, controllers, selectors, leveling devices, operating devices, switches on cars and in hoistways, hoistway doors and car doors or gate operating device, interlock contacts, guide shoes, guide rails, car door sills, hangers for doors, car doors or gates and signal system must be cleaned, lubricated and adjusted.
5. Guide rails and bottom of platforms must be cleaned every three months. Car tops and machine room floors must be cleaned monthly. Accumulated rubbish must be removed from

the pits monthly. A general cleaning of the entire installation including all machine room equipment and hoistway equipment must be accomplished quarterly. Cleaning supplies and vacuum cleaner must be furnished by the Contractor.

6. Maintain the performance standards set forth in this specification.
7. The operational system must be maintained to the standards specified hereinafter.
8. Maintain smooth starting and stopping and accurate leveling always.

C. Maintenance service must not include the performance of work required because of improper use, accidents and negligence for which the Elevator Contractor is not directly responsible.

D. Provide 24-hour emergency call-back service that must consist of promptly responding to calls within two hours for emergency service should a shutdown or emergency develop between regular examinations. Overtime emergency call-back service must be limited to minor adjustments and repairs required to protect the immediate safety of the equipment and persons in and about the elevator.

E. Service and emergency personnel must report to the Owner or his authorized representative upon arrival at the building and again upon completion of the required work. A copy of the work ticket containing a complete description of the work performed must be given to the Owner.

F. The Elevator Contractor must maintain a logbook in the machine room. The log must list the date and time of all bi-weekly examinations and all trouble calls. Each trouble call must be fully described including the nature of the call, necessary correction performed, or parts replaced.

G. Written “Maintenance Control Program” must be in place to maintain the equipment in compliance with ASME A17.1.

END OF SECTION

SECTION 210517 – SLEEVES AND SLEEVE SEALS FOR FIRE-SUPPRESSION PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Sleeves without waterstop.
2. Sleeve-seal systems.
3. Grout.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Field quality-control reports.

PART 2 - PRODUCTS

2.1 SLEEVES WITHOUT WATERSTOP

A. Cast-Iron Pipe Sleeves: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends.

B. Steel Pipe Sleeves: ASTM A53/A53M, Type E, Grade B, Schedule 40, hot-dip galvanized, with plain ends.

C. Steel Sheet Sleeves: ASTM A653/A653M, 0.0239-inch minimum thickness; hot-dip galvanized, round tube closed with welded longitudinal joint.

2.2 SLEEVE-SEAL SYSTEMS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Advance Products & Systems, LLC.
2. CALPICO, Inc.
3. GPT; an EnPro Industries company.
4. Metraflex Company (The).
5. Proco Products, Inc.

B. Description: Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.

1. Designed to form a hydrostatic seal of 20 psig minimum.
2. Sealing Elements: EPDM-rubber or Nitrile (Buna N) interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size.
3. Pressure Plates: Carbon steel or Stainless steel.
4. Connecting Bolts and Nuts: Carbon steel, with ASTM B633 coating or Stainless steel of length required to secure pressure plates to sealing elements.

2.3 GROUT

A. Description: Nonshrink, for interior and exterior sealing openings in non-fire-rated walls or floors.

B. Standard: ASTM C1107/C1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.

C. Design Mix: 5000 psi, 28-day compressive strength.

D. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 INSTALLATION OF SLEEVES - GENERAL

A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.

B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.

1. Sleeves are not required for core-drilled holes.

C. Install sleeves in concrete floors, as new floors are constructed. Install sleeves in existing concrete and masonry walls.

1. Cut sleeves to length for mounting flush with both surfaces.

a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.

2. Using grout, seal space outside of sleeves in slabs and walls without sleeve-seal system.

D. Install sleeves for pipes passing through interior partitions.

1. Cut sleeves to length for mounting flush with both surfaces.
2. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
3. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint.

E. Fire-Resistance-Rated Penetrations, Horizontal Assembly Penetrations, and Smoke Barrier Penetrations: Maintain indicated fire or smoke rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with fire- and smoke-stop materials. Comply with requirements for firestopping and fill materials specified in Section 078413 "Penetration Firestopping."

3.2 INSTALLATION OF SLEEVE-SEAL SYSTEMS

A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building, and passing through exterior walls.

B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

3.3 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Leak Test: After allowing for a full cure, test sleeves and sleeve seals for leaks. Repair leaks and retest until no leaks exist.
2. Sleeves and sleeve seals will be considered defective if they do not pass tests and inspections.

B. Prepare test and inspection reports.

3.4 SLEEVE SCHEDULE

A. Use sleeves and sleeve seals for the following piping-penetration applications:

1. Existing Exterior Concrete and Masonry Walls above and below Grade:

a. Sleeves without waterstops.

1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.

2. Concrete Slabs above Grade:

a. Sleeves without waterstops.

3. Interior Walls and Partitions:

a. Sleeves without waterstops.

END OF SECTION

SECTION 210518 – ESCUTCHEONS FOR FIRE-SUPPRESSION PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Escutcheons.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is to be described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. BrassCraft Manufacturing Co.; a Masco company.
2. Dearborn Brass.
3. Jones Stephens Corp.
4. Keeney Manufacturing Company (The).
5. Mid-America Fittings, LLC; A Midland Industries Company.
6. ProFlo; a Ferguson Enterprises, Inc. brand.

2.2 ESCUTCHEONS

A. One-Piece, Cast-Brass Type: With polished, chrome-plated finish and setscrew fastener.

B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with polished, chrome-plated finish and spring-clip fasteners.

C. One-Piece, Stamped-Steel Type: With polished, chrome-plated finish and spring-clip fasteners.

D. Split-Plate, Stamped-Steel Type: With polished, chrome-plated finish; concealed and exposed-rivet hinge; and spring-clip fasteners.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.

B. Install escutcheons with ID to closely fit around pipe, tube, and insulation of piping and with OD that completely covers opening.

1. Escutcheons for New Piping:

a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep pattern.
b. Chrome-Plated Piping: One-piece cast brass with polished, chrome-plated finish.
c. Insulated Piping: One-piece stamped steel or split-plate, stamped steel with concealed hinge with polished, chrome-plated finish.
d. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece stamped steel or split-plate, stamped steel with concealed hinge with polished, chrome-plated finish.
e. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece cast brass with polished, chrome-plated finish.
f. Bare Piping in Unfinished Service Spaces: One-piece stamped steel or split-plate, stamped steel with exposed-rivet hinge with polished, chrome-plated finish.

3.2 FIELD QUALITY CONTROL

A. Using new materials, replace broken and damaged escutcheons.

END OF SECTION

SECTION 210523 – GENERAL-DUTY VALVES FOR WATER-BASED FIRE-SUPPRESSION PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Two-piece ball valves with indicators.
2. Bronze butterfly valves with indicators.
3. Iron butterfly valves with indicators.
4. Check valves.
5. Bronze OS&Y gate valves.
6. Iron OS&Y gate valves.
7. Trim and drain valves.

1.2 DEFINITIONS

A. NRS: Nonrising stem.

B. OS&Y: Outside screw and yoke.

C. SBR: Styrene-butadiene rubber.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of valve. On data submittal sheets where more than one product is to be described, clearly annotate which product(s) is to be supplied.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:

1. Protect internal parts against rust and corrosion.
2. Protect threads, flange faces, and weld ends.
3. Set valves open to minimize exposure of functional surfaces.

B. Use the following precautions during storage:

1. Maintain valve end protection.
2. Store valves indoors and maintain at higher-than-ambient dew point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use operating handles or stems as lifting or rigging points.

D. Protect flanges and specialties from moisture and dirt.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each type of valve from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. UL Listed: Valves shall be listed in UL's "Online Certifications Directory" and shall bear UL mark:

B. FM Global Approved: Valves shall be listed in its "Approval Guide."

C. Source Limitations for Valves: Obtain valves for each valve type from single manufacturer.

D. ASME Compliance:

1. ASME B1.20.1 for threads for threaded-end valves.
2. ASME B16.1 for flanges on iron valves.
3. ASME B31.9 for building services piping valves.

E. AWWA Compliance: Comply with AWWA C606 for grooved-end connections.

F. NFPA Compliance for valves:

1. Comply with NFPA 13 and NFPA 24.

G. Valve Pressure Ratings: Not less than the minimum pressure rating indicated or higher, as required by system pressures.

H. Valve Sizes: Same as upstream piping unless otherwise indicated.

I. Valve Actuator Types:

1. Worm-gear actuator with handwheel for quarter-turn valves, except for trim and drain valves.
2. Handwheel: For other than quarter-turn trim and drain valves.
3. Handlever: For quarter-turn trim and drain valves NPS 2 and smaller.

2.3 TWO-PIECE BALL VALVES WITH INDICATORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Ames Fire & Waterworks; A Watts Water Technologies Company.
2. NIBCO INC.
3. Victaulic Company.

B. Description:

1. UL 1091, except with ball instead of disc and FM Global approved for indicating valves (butterfly or ball type), Class Number 1112.
2. Minimum Pressure Rating: 175 psig.
3. Body Design: Two piece.
4. Body Material: Forged brass or bronze.
5. Port Size: Full or standard.
6. Seats: PTFE.
7. Stem: Bronze or stainless steel.
8. Ball: Chrome-plated brass.
9. Actuator: Worm gear
10. Supervisory Switch: Internal or external.
11. End Connections for Valves NPS 1 through NPS 2: Threaded ends.
12. End Connections for Valves NPS 2-1/2: Grooved ends.

2.4 BRONZE BUTTERFLY VALVES WITH INDICATORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ALEUM USA.
2. Globe Fire Sprinkler Corporation.
3. Milwaukee Valve Company.

B. Description:

1. Standard: UL 1091 and FM Global standard for indicating valves, (butterfly or ball type), Class Number 1112.
2. Minimum: Pressure rating: 175 psig.
3. Body Material: Bronze.
4. Seat Material: EPDM.
5. Stem Material: Bronze or stainless steel.
6. Disc: Bronze or stainless steel.
7. Actuator: Worm gear.
8. Supervisory Switch: Internal or external.
9. Ends Connections for Valves NPS 1 through NPS 2: Threaded ends.
10. Ends Connections for Valves NPS 2-1/2: Grooved ends.

2.5 IRON BUTTERFLY VALVES WITH INDICATORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ALEUM USA.
2. Anvil International/Smith-Cooper International; Tailwind Capital, LLC.

3. Globe Fire Sprinkler Corporation.
4. Kennedy Valve Company; a division of McWane, Inc.
5. NIBCO INC.
6. Tyco Fire Products; brand of Johnson Controls International plc, Building Solutions North America.
7. Victaulic Company.
8. Zurn Industries, LLC.

B. Description:

1. Standard: UL 1091 and FM Global standard for indicating valves, (butterfly or ball type), Class Number 112.
2. Minimum Pressure Rating: 175 psig.
3. Body Material: Cast or ductile iron.
4. Seat Material: EPDM.
5. Stem: Stainless steel.
6. Disc: Ductile iron, nickel plated and EPDM or SBR coated.
7. Actuator: Worm gear.
8. Supervisory Switch: Internal or external.
9. Body Design: Grooved-end connections.

2.6 CHECK VALVES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Ames Fire & Waterworks; A Watts Water Technologies Company.
2. Anvil International/Smith-Cooper International; Tailwind Capital, LLC.
3. FEBCO; A WATTS Brand.
4. Globe Fire Sprinkler Corporation.
5. Kennedy Valve Company; a division of McWane Inc.
6. Mueller Co. LLC; Mueller Water Products, Inc.
7. NIBCO INC.
8. Reliable Automatic Sprinkler Co., Inc. (The).
9. Tyco Fire Products; brand of Johnson Controls International plc, Building Solutions North America.
10. United Brass Works, Inc.
11. Victaulic Company.
12. Viking Group Inc.
13. WATTS; A Watts Water Technologies Company.
14. Zurn Industries, LLC.

B. Description:

1. Standard: UL 312 and FM Global standard for swing check valves, Class Number 1210.
2. Minimum Pressure Rating: 175 psig.
3. Type: Single swing check.
4. Body Material: Cast iron, ductile iron, or bronze.
5. Clapper: Bronze, ductile iron, or stainless steel with elastomeric seal.
6. Clapper Seat: Brass, bronze, or stainless steel.
7. Hinge Shaft: Bronze or stainless steel.

8. Hinge Spring: Stainless steel.
9. End Connections: Flanged, grooved, or threaded.

2.7 BRONZE OS&Y GATE VALVES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Milwaukee Valve Company.
2. NIBCO INC.
3. United Brass Works, Inc.
4. Zurn Industries, LLC.

B. Description:

1. Standard: UL 262 and FM Global standard for fire-service water control valves (OS&Y- and NRS-type gate valves).
2. Minimum Pressure Rating: 175 psig.
3. Body and Bonnet Material: Bronze or brass.
4. Wedge: One-piece bronze or brass.
5. Wedge Seat: Bronze.
6. Stem: Bronze or brass.
7. Packing: Non-asbestos PTFE.
8. Supervisory Switch: External.
9. End Connections: Threaded.

2.8 IRON OS&Y GATE VALVES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. American Cast Iron Pipe Company.
2. Clow Valve Company; a subsidiary of McWane, Inc.
3. Hammond Valve.
4. Mueller Co. LLC; Mueller Water Products, Inc.
5. NIBCO INC.
6. Victaulic Company.
7. WATTS; A Watts Water Technologies Company.
8. Zurn Industries, LLC.

B. Description:

1. Standard: UL 262 and FM Global standard for fire-service water control valves (OS&Y- and NRS-type gate valves).
2. Minimum Pressure Rating: 175 psig.
3. Body and Bonnet Material: Cast or ductile iron.
4. Wedge: Cast or ductile iron, or bronze with elastomeric coating.
5. Wedge Seat: Cast or ductile iron, or bronze with elastomeric coating.
6. Stem: Brass or bronze.
7. Packing: Non-asbestos PTFE.

8. Supervisory Switch: External.
9. End Connections: Flanged or grooved.

2.9 TRIM AND DRAIN VALVES

A. Ball Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
    b. Fire Protection Products Inc (FPPI); a brand of Anvil International and Smith-Cooper International.
    c. Jomar Valve.
    d. Legend Valve & Fitting, Inc.
    e. Milwaukee Valve Company.
    f. NIBCO INC.
    g. Potter Roemer LLC; a Division of Morris Group International.
    h. Red-White Valve Corp.
    i. Tyco Fire Products; brand of Johnson Controls International plc, Building Solutions North America.
    j. Victaulic Company.
    k. WATTS; A Watts Water Technologies Company.
    l. Zurn Industries, LLC.

2. Description:

    a. Pressure Rating: 175 psig.
    b. Body Design: Two piece.
    c. Body Material: Forged brass or bronze.
    d. Port size: Full or standard.
    e. Seats: PTFE.
    f. Stem: Bronze or stainless steel.
    g. Ball: Chrome-plated brass.
    h. Actuator: Handlever.
    i. End Connections for Valves NPS 1 through NPS 2-1/2: Threaded ends.
    j. End Connections for Valves NPS 1-1/4 and NPS 2-1/2: Grooved ends.

B. Globe Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. NIBCO INC.
    b. United Brass Works, Inc.

2. Description:

    a. Pressure Rating: 175 psig.

b. Body Material: Bronze with integral seat and screw-in bonnet.
c. Ends: Threaded.
d. Stem: Bronze.
e. Disc Holder and Nut: Bronze.
f. Disc Seat: Nitrile.
g. Packing: Asbestos free.
h. Handwheel: Malleable iron, bronze, or aluminum.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.

C. Examine threads on valve and mating pipe for form and cleanliness.

D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.

E. Do not attempt to repair defective valves; replace with new valves.

3.2 INSTALLATION, GENERAL

A. Comply with requirements in the following Sections for specific valve-installation requirements and applications:

1. Section 211313 "Wet-Pipe Sprinkler Systems" for application of valves in wet-pipe, fire-suppression sprinkler systems.

B. Install listed fire-protection shutoff valves supervised-open, located to control sources of water supply, except from fire-department connections. Install permanent identification signs, indicating portion of system controlled by each valve.

C. Retain existing backflow preventer assembly in existing fire-protection water-supply connection.

D. Install valves having threaded connections with unions at each piece of equipment arranged to allow easy access, service, maintenance, and equipment removal without system shutdown. Provide separate support where necessary.

E. Install valves in horizontal piping with stem at or above the pipe center.

F. Install valves in position to allow full stem movement.

G. Install valve tags. Comply with requirements in Section 210553 "Identification for Fire-Suppression Piping and Equipment" for valve tags and schedules and signs on surfaces concealing valves; and the NFPA standard applying to the piping system in which valves are installed. Install permanent identification signs indicating the portion of system controlled by each valve.

END OF SECTION

SECTION 210529 - HANGERS AND SUPPORTS FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Metal pipe hangers and supports.
2. Metal framing systems.
3. Fastener systems.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Welding certificates.

1.5 QUALITY ASSURANCE

A. Structural-Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.

B. Pipe Welding Qualifications: Qualify procedures and operators according to 2015 ASME Boiler and Pressure Vessel Code, Section IX.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Structural Performance: Hangers and supports for fire-suppression piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.

B. NFPA Compliance: Comply with NFPA 13.

C. UL Compliance: Comply with UL 203.

2.2 METAL PIPE HANGERS AND SUPPORTS

A. Carbon-Steel Pipe Hangers and Supports:

1. Description: Factory-fabricated components, NFPA approved, UL listed, or FM approved for fire-suppression piping support.
2. Galvanized Metallic Coatings: Pregalvanized or hot-dip galvanized.
3. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

2.3 METAL FRAMING SYSTEMS

A. MFMA Manufacturer Metal Framing Systems:

1. Description: Shop- or field-fabricated pipe-support assembly, made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
2. Standard: Comply with MFMA-4, factory-fabricated components for field assembly.
3. Channels: Continuous slotted carbon-steel channel with inturned lips.
4. Channel Width: Selected for applicable load criteria.
5. Channel Nuts: Formed or stamped nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
7. Metallic Coating: Electroplated zinc or hot-dip galvanized.

2.4 FASTENER SYSTEMS

A. Powder-Actuated Fasteners: NFPA-approved, UL-listed, or FM-approved threaded-steel stud, for use in hardened portland cement concrete, with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

B. Mechanical-Expansion Anchors: NFPA-approved, UL-listed, or FM-approved, insert-wedge-type anchors, for use in hardened portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

1. Indoor Applications: Zinc-coated or Stainless steel.

2.5 MATERIALS

A. Aluminum: ASTM B221.

B. Carbon Steel: ASTM A1011/A1011M.

C. Structural Steel: ASTM A36/A36M, carbon-steel plates, shapes, and bars; black and galvanized.

D. Stainless Steel: ASTM A240/A240M.

PART 3 - EXECUTION

3.1 APPLICATION

A. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping materials and installation, for penetrations through fire-rated walls, ceilings, and assemblies.

B. Strength of Support Assemblies: Where not indicated, select sizes of components, so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

3.2 INSTALLATION OF HANGERS AND SUPPORTS

A. Metal Pipe-Hanger Installation: Comply with installation requirements of approvals and listings. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.

B. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal strut systems.

C. Fastener System Installation:

1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete, after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual. Install in accordance with approvals and listings.
2. Install mechanical-expansion anchors in concrete, after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions. Install in accordance with approvals and listings.

D. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.

E. Install hangers and supports to allow controlled thermal movement of piping systems.

F. Install lateral bracing with pipe hangers and supports to prevent swaying.

G. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms, and install reinforcing bars through openings at top of inserts.

H. Load Distribution: Install hangers and supports, so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.

I. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.

3.3 ADJUSTING

A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.

B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.4 PAINTING

A. Touchup:

1. Cleaning and touchup painting of field welds, bolted connections, and abraded, shop-painted areas on miscellaneous metal are specified in Section 099123 "Interior Painting."

B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas, and apply galvanizing-repair paint to comply with ASTM A780/A780M.

3.5 HANGER AND SUPPORT SCHEDULE

A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.

B. Comply with NFPA requirements for pipe-hanger selections and applications that are not specified in piping system Sections.

C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finishes.

D. Use carbon-steel pipe hangers and supports and metal framing systems and attachments for general service applications.

E. Horizontal-Piping Hangers and Supports: Comply with NFPA requirements. Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
2. Steel Pipe Clamps (MSS Type 4): For suspension of NPS 1/2 to NPS 24 if little or no insulation is required.

3. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
4. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
5. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
6. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
7. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
8. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
9. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.

F. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.

G. Hanger-Rod Attachments: Comply with NFPA requirements.

H. Building Attachments: Comply with NFPA requirements. Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel or Malleable-Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
2. C-Clamps (MSS Type 23): For structural shapes.
3. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.

I. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.

J. Use powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where required in concrete construction.

END OF SECTION

SECTION 210553 – IDENTIFICATION FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Warning signs and labels.
2. Pipe labels.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 WARNING SIGNS AND LABELS

A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, with predrilled holes for attachment hardware.

B. Letter and Background Color: As indicated for specific application under Part 3.

C. Maximum Temperature: Able to withstand temperatures of up to 160 deg F.

D. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.

E. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances of up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.

F. Fasteners: Stainless steel rivets or self-tapping screws.

G. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

H. Label Content: Include caution and warning information, plus emergency notification instructions.

2.2 PIPE LABELS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Actioncraft Products, Inc.; a division of Industrial Test Equipment Co., Inc.
2. Brady Corporation.
3. Carlton Industries, LP.
4. Champion America.
5. Craftmark Pipe Markers.
6. Kolbi Pipe Marker Co.
7. LEM Products Inc.
8. Marking Services Inc.
9. Pipemarker.com; Brimar Industries, Inc.
10. Seton Identification Products; a Brady Corporation company.
11. emedco.

B. General Requirements for Manufactured Pipe Labels: Preprinted, color coded, with lettering indicating service and showing flow direction in accordance with ASME A13.1.

C. Letter and Background Color: As indicated for specific application under Part 3.

D. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.

E. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.

F. Pipe-Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings. Also include the following:

1. Pipe size.
2. Flow-Direction Arrows: Include flow-direction arrows on distribution piping. Arrows may be either integral with label or applied separately.
3. Lettering Size: At least 1/2 inch for viewing distances of up to 72 inches and proportionately larger lettering for greater viewing distances.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean piping and equipment surfaces of incompatible primers, paints, and encapsulants, as well as dirt, oil, grease, release agents, and other substances that could impair bond of identification devices.

3.2 INSTALLATION GENERAL REQUIREMENTS

A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be installed.

B. Coordinate installation of identifying devices with locations of access panels and doors.

C. Install identifying devices before installing acoustical ceilings and similar concealment.

D. Locate identifying devices so that they are readily visible from the point of normal approach.

3.3 INSTALLATION OF WARNING SIGNS AND LABELS

A. Sign and Label Colors:

1. White letters on an ANSI Z535.1 safety-red background.

3.4 INSTALLATION OF PIPE LABELS

A. Piping Color Coding: Painting of piping is specified in Section 099123 "Interior Painting."

B. Install pipe labels showing service and flow direction with permanent adhesive on pipes.

C. Pipe-Label Locations: Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:

1. Within 3 ft. of each valve and control device.
2. At access doors, manholes, and similar access points that permit a view of concealed piping.
3. Within 3 ft. of equipment items and other points of origination and termination.
4. Spaced at maximum intervals of 25 ft. along each run. Reduce intervals to 10 ft. in areas of congested piping and equipment.

D. Flow- Direction Arrows: Provide arrows to indicate direction of flow in pipes, including pipes where flow is allowed in both directions.

E. Fire-Suppression Pipe Label Color Schedule:

1. Fire-Suppression Pipe Labels: White letters on an ANSI Z535.1 safety-red background.

END OF SECTION

SECTION 211000 - WATER-BASED FIRE-SUPPRESSION SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Fire-suppression piping, fittings, and appurtenances.
2. System control valves.
3. Fire-suppression piping specialties.
4. Sprinklers.
5. Alarm devices.
6. Manual control stations.
7. Pressure gauges.

1.2 DEFINITIONS

A. Standard-Pressure Fire-Suppression System Piping: Piping designed to operate at working pressure of 175 psig maximum.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

    a. Include construction details, material descriptions, dimensions of individual components and profiles.
    b. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

C. Shop Drawings:

1. Prepare in accordance with NFPA 13 section "Working Plans."

    a. Include plans, elevations, and sections of the system piping and details.
    b. Include detailed riser diagram and schematic diagram showing system supply, supply connection, devices, valves, pipe and fittings, as well as the delineation of the standard-pressure and high-pressure portions of the fire-suppression system.
    c. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.

2. Prepare computer-generated hydraulic calculations in accordance with the following:

    a. Minimum operating pressure at hydraulically most remote fire hose valve is to be 100 psig.
    b. Name of hydraulic program used.
    c. Water supply information, including fire hydrant flow test data report.

3. Submit documents and calculations signed and sealed by qualified professional engineer responsible for their preparation
4. Include diagrams for power, signal, and control wiring.

D. Delegated Design Submittals: For fire-suppression systems indicated to comply with performance requirements and design criteria, including analysis data, signed and sealed by the qualified professional engineer responsible for their preparation.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Fire-suppression system plans and sections, or Building Information Model (BIM), drawn to scale, showing the items described in this Section and coordinated with all building trades. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

C. Qualification Data: For qualified Installer, professional engineer, and NICET-certified technician.

D. Design Data: Approved fire-suppression piping working plans, prepared in accordance with NFPA 13, including documented approval by AHJs, and including hydraulic calculations if applicable.

E. Welding certificates.

F. Field Test Reports:

1. Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13. Include "Contractor's Material and Test Certificate for Aboveground Piping."
2. Fire-hydrant flow test report.

G. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For fire-suppression systems and specialties to include in emergency, operation, and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Sprinkler Cabinets: Finished, wall-mounted, steel cabinet with hinged cover, and with space for minimum of six spare sprinklers plus sprinkler wrench. Include number of sprinklers required by NFPA 13 and sprinkler wrench. Include separate cabinet with sprinklers and wrench for each type of sprinkler used on Project.

1.7 QUALITY ASSURANCE

A. Installer Qualifications:

1. Installer's responsibilities include designing, fabricating, and installing fire-suppression systems and providing professional engineering services needed to assume engineering responsibility. Base calculations on results of fire-hydrant flow test.

a. Engineering Responsibility: Preparation of working plans, calculations, and field test reports by qualified professional engineer.

B. Welding Qualifications: Qualify procedures and operators in accordance with ASME Boiler and Pressure Vessel Code.

1.8 FIELD CONDITIONS

A. Interruption of Existing Fire-Suppression Service: Do not interrupt fire-suppression service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary fire-suppression service in accordance with requirements indicated:

1. Notify Owner no fewer than seven days in advance of proposed interruption of fire-suppression service.
2. Do not proceed with interruption of fire-suppression service without Owner's written permission.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Automatic wet-pipe sprinkler system.

2.2 PERFORMANCE REQUIREMENTS

A. Seismic Performance: Fire-suppression system piping to withstand the effects of earthquake motions determined in accordance with NFPA 13.

B. Fire-Suppression System Components, Devices, and Accessories: Listed in UL's "Fire Protection Equipment Directory" and FM Approvals' "Approval Guide."

C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

D. Fire-suppression system equipment, specialties, accessories, installation, and testing to comply with NFPA 13.

E. Standard-Pressure Piping System Component: Listed for 175 psig minimum working pressure.

F. Delegated Design: Engage a qualified professional engineer to design fire-suppression systems.

1. Fire-Hydrant Flow Test:

a. Perform fire-hydrant flow test and record the following conditions:

1) Date:
2) Time:
3) Performed by:
4) Location of Residual Fire Hydrant R:
5) Location of Flow Fire Hydrant F:
6) Static Pressure at Residual Fire Hydrant R:
7) Measured Flow at Flow Fire Hydrant F:
8) Residual Pressure at Residual Fire Hydrant R:

b. Fire-hydrant flow test must be performed within previous 12 months prior to completion of design documents and hydraulic calculations.

2. Margin of Safety for Available Water Flow and Pressure: 10 percent, including losses through water-service piping, valves, and backflow preventers.
3. Maximum protection area per sprinkler in accordance with UL listing.

G. Obtain documented approval of fire-suppression system design from AHJs.

2.3 FIRE-SUPPRESSION PIPING, FITTINGS, AND APPURTENANCES

A. Steel Pipe, Fittings, and Appurtenances:

1. Schedule 40 Steel Pipe: Black-steel pipe, ASTM A53/A53M, ASTM A135/A135M, or ASTM A795/A795M.

a. Standards:

1) UL 852.
2) FM 1630.

b. Factory-applied exterior coating.
c. Factory-applied bacterial-resistant internal coating to reduce microbiologically influenced corrosion.
d. Pipe ends may be factory or field formed to match joining method.

2. Schedule 10 Steel Pipe: Black-steel pipe, ASTM A53/A53M, ASTM A135/A135M, or ASTM A795/A795M.

a. Standards:

1) UL 852.
2) FM 1630.

b. Factory-applied exterior coating.
c. Factory-applied bacterial resistant internal coating to reduce microbiologically influenced corrosion.
d. Pipe ends may be factory or field formed to match joining method.

3. Steel Pipe Nipples: Black steel, ASTM A733, made of ASTM A53/A53M, standard-weight, seamless steel pipe with threaded ends.
4. Steel Couplings: Uncoated steel, ASTM A865/A865M, threaded.
5. Gray-Iron Threaded Fittings: Uncoated gray-iron threaded fittings, ASME B16.4, Class 125, standard pattern.
6. Malleable- or Ductile-Iron Unions: ASME B16.3.
7. Cast-Iron Flanges: ASME B16.1, Class 125.
8. Steel Flanges and Flanged Fittings: ASME B16.5, Class 150.

a. Pipe-Flange Gasket Materials: ASME B16.21, nonmetallic and asbestos free or EPDM rubber gasket.

1) Class 125 and Class 250, Cast-Iron, Flat-Face Flanges: Full-face gaskets.
2) Class 150 and Class 300, Ductile-Iron or -Steel, Raised-Face Flanges: Ring-type gaskets.

b. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1 carbon steel unless otherwise indicated.

9. Steel Welding Fittings: ASTM A234/A234M and ASME B16.9.

a. Welding Filler Metals: Comply with AWS D10.12M/D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

10. Plain-End-Pipe Fittings:

a. Pressure Rating: 175 psig minimum.
b. Plain-End Fittings for Steel Piping: Uncoated plain-end fittings, ASTM A53/A53M, carbon steel or ASTM A106/A106M, forged steel with dimensions matching steel pipe.
c. Plain-End-Pipe Couplings for Steel Piping: Rigid pattern for steel-pipe dimensions, ductile-iron or malleable-iron housing. Include EPDM-rubber gasket, and bolts and nuts.

11. Grooved-Joint, Steel-Pipe Appurtenances:

    a. Pressure Rating: 175 psig minimum.
    b. Grooved-End Fittings for Steel Piping: Uncoated grooved-end fittings, ASTM A47/A47M, malleable-iron casting or ASTM A536, ductile-iron casting, with dimensions matching steel pipe.
    c. Grooved-End-Pipe Couplings for Steel Piping: AWWA C606 and UL 213 rigid pattern, unless otherwise indicated, for steel-pipe dimensions. Include ferrous housing sections, EPDM-rubber gasket, and bolts and nuts.

2.4 SYSTEM CONTROL VALVES

A. Listed in UL's "Fire Protection Equipment Directory" or FM Approvals' "Approval Guide."

B. Pressure Rating:

1. Standard-Pressure Piping Valves: 175 psig minimum.

C. Body Material: Cast or ductile iron.

D. Size: Same as connected piping.

E. End Connections: Flanged or grooved.

F. System Control Valve, Alarm Valve:

1. Standard: UL 193.
2. Design: For horizontal or vertical installation.
3. Include trim sets for bypass, drain, electrical sprinkler alarm switch, pressure gauges, retarding chamber, and fill-line attachment with strainer.
4. Drip cup assembly pipe drain with check valve to main drain piping.

2.5 FIRE-SUPPRESSION PIPING SPECIALTIES

A. Branch Outlet Fittings:

1. Standard: UL 213.
2. Pressure Rating: 175 psig minimum.
3. Body Material: Ductile-iron housing with EPDM seals and bolts and nuts.
4. Type: Mechanical-tee and -cross fittings.
5. Configurations: Snap-on and strapless, ductile-iron housing with branch outlets.
6. Size: Of dimension to fit onto sprinkler main and with outlet connections as required to match connected branch piping.
7. Branch Outlets: Grooved, plain-end pipe, or threaded.

B. Flow Detection and Test Assemblies:

1. Standard: UL's "Fire Protection Equipment Directory" or FM Approvals' "Approval Guide."
2. Pressure Rating: 175 psig minimum.

3. Body Material: Cast- or ductile-iron housing with orifice, sight glass, and integral test valve.
4. Size: Same as connected piping.
5. Inlet and Outlet: Threaded or grooved.

C. Branch Line Testers:

1. Standard: UL 199.
2. Pressure Rating: 175 psig.
3. Body Material: Brass.
4. Size: Same as connected piping.
5. Inlet: Threaded.
6. Drain Outlet: Threaded and capped.
7. Branch Outlet: Threaded, for sprinkler.

D. Sprinkler Inspector's Test Fittings:

1. Standard: UL's "Fire Protection Equipment Directory" or FM Approvals' "Approval Guide."
2. Pressure Rating: 175 psig minimum.
3. Body Material: Cast- or ductile-iron housing with sight glass.
4. Size: Same as connected piping.
5. Inlet and Outlet: Threaded.

E. Adjustable Drop Nipples:

1. Standard: UL 1474.
2. Pressure Rating: 250 psig minimum.
3. Body Material: Steel pipe with EPDM-rubber O-ring seals.
4. Size: Same as connected piping.
5. Length: Adjustable.
6. Inlet and Outlet: Threaded.

F. Flexible Sprinkler Hose Fittings:

1. Standards:

   a. UL 2443.
   b. FM 1637.

2. Description: Flexible hose for connection to sprinkler, and with bracket for connection to ceiling grid.
3. Pressure Rating: 175 psig minimum.
4. Size: Same as connected piping, for sprinkler.

G. Automatic (Ball-Drip) Drain Valves:

1. Pressure Rating: 175 psig minimum.
2. Type: Automatic draining, ball check.
3. Size: NPS 3/4.
4. End Connections: Threaded.

H. Manual Air Vent/Valve:

1. Description: Ball valve that requires human intervention to vent air.
2. Body: Forged brass.
3. Ends: Threaded.
4. Minimize Size: 1/2 inch.
5. Minimum Water Working Pressure Rating: 300 psig.

I. Automatic Air Vent Assembly:

1. Description: Automatic air vent assembly that automatically vents trapped air without human intervention, including Y-strainer and ball valve in a pre-piped assembly. Approved for use in wet-pipe fire-suppression system.
2. Vents oxygen continuously from system.
3. Float valve to prevent water discharge.
4. Minimum Water Working Pressure Rating: 175 psig.

2.6 SPRINKLERS

A. Standards:

1. UL 199.
2. UL 1767.
3. UL 1626.
4. FM 2000.
5. FM 2008.
6. FM 2030.

B. Listed in UL's "Fire Protection Equipment Directory" or FM Approvals' "Approval Guide."

C. Pressure Rating for Sprinklers:

1. Standard Automatic Sprinklers: 175 psig minimum.

D. Sprinklers, Automatic Wet with Heat-Responsive Element:

1. Characteristics: Nominal 1/2-inch orifice with Discharge Coefficient K of 5.6, and for "Ordinary" temperature classification rating unless otherwise indicated or required by application.
2. Standard Spray, Standard Response:

    a. Upright.
    b. Pendent.
    c. Recessed pendent.
    d. Flat, concealed pendent.
    e. Horizontal sidewall.

3. Standard Spray, Quick Response:

    a. Upright.
    b. Pendent.

c. Recessed pendent.
d. Flat, concealed pendent.
e. Horizontal sidewall.

4. Extended Coverage:

a. Upright.
b. Pendent.
c. Flat, concealed pendent.
d. Horizontal sidewall.

E. Sprinkler Escutcheons: Materials, types, and finishes for the following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.

1. Ceiling Mounting: White-painted steel, one piece, flat.
2. Sidewall Mounting: White-painted steel, one piece, flat.

F. Sprinkler Guards and Water Shields:

1. Standard: UL 199.
2. Description: Wire cage with fastening device for attaching to sprinkler.

2.7 ALARM DEVICES

A. Match alarm-device material and connection types to piping and equipment materials and connection types.

B. Electrically Operated Notification Appliances:

1. Electric Bell:

a. Standard: UL 464.
b. Type: Vibrating, metal alarm bell.
c. Size: 8-inch minimum- diameter.
d. Voltage: 120 V ac, 60 Hz, single phase or 24 V dc.
e. Finish: Red-enamel or polyester powder-coat factory finish, suitable for outdoor use with approved and listed weatherproof backbox.

C. Water-Flow Indicators:

1. Standard: UL 346.
2. Water-Flow Detector: Electrically supervised.
3. Components: Two single-pole, double-throw circuit switches for isolated alarm and auxiliary contacts, 7 A, 125 V ac and 0.25 A, 24 V dc; complete with factory-set, field-adjustable retard element to prevent false signals and tamperproof cover that sends signal if removed.
4. Type: Paddle operated.
5. Pressure Rating: 250 psig.
6. Design Installation: Horizontal or vertical.

D. Pressure Switches - Water-Flow Alarm Detection:

1. Description: Electrically supervised, pressure-activated water-flow switch with retard feature.
2. Components: Two single-pole, double-throw switches with normally closed contacts.
3. Design Operation: Rising pressure to 6 psi, plus or minus 2 psi signals water flow.
4. Adjustability: Each switch is to be independently adjustable.
5. Wire Separation: Pressure switch to provide for separation of wiring to each switch connection to allow for low- and high-voltage connections to comply with NFPA 70, Article 760 requirements.

E. Valve Supervisory Switches:

1. Standard: UL 346.
2. Type: Electrically supervised.
3. Design: Signals that controlled valve is in other than fully open position.
4. Wire Terminal Designations: Indicates normal switch position when switch is properly installed on valve and valve is fully open.
5. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
6. OS&Y Valve Supervisory Switches:

    a. One or two single-pole, double-throw switches.
    b. NEMA Rating: NEMA 4 and NEMA 6P enclosures suitable for mounting in any position indoors or outdoors.
    c. Visual Switch Indication: Indicates device is properly installed and OS&Y valve is fully open.
    d. Mounting Hardware: Mounting bracket to grip valve yoke and prevent movement of switch assembly on OS&Y valve.
    e. Trip Rod Length: Adjustable

7. Butterfly Valve Supervisory Switches:

    a. Two single-pole, double-throw switches.
    b. NEMA Rating: NEMA 4 and NEMA 6P enclosures suitable for mounting in any position indoors or outdoors.
    c. Mounting Hardware: Removable nipple.
    d. Trip Rod Length: Adjustable

8. Ball Valve Supervisory Switches:

    a. One single-pole, double-throw switch.
    b. NEMA Rating: NEMA 4 enclosure suitable for mounting in any position indoors or outdoors.
    c. Mounting Hardware: Suitable for mounting directly to pipe, ball valves, or backflow preventers sized from up to NPS 2.

2.8 PRESSURE GAUGES

A. Standard: UL 393.

B. Dial Size: 3-1/2- to 4-1/2-inch diameter.

C. Pressure Gauge Range: 0 to 250 psig minimum.

D. Water System Piping Gauge: Include "WATER" or "AIR/WATER" label on dial face.

PART 3 - EXECUTION

3.1 PREPARATION

A. Perform fire-hydrant flow test. Use results for system design calculations required in "Quality Assurance" Article.

1. Flow test is to be performed to meet the criteria established by NFPA 13.
2. Flow test is to be conducted in accordance with NFPA 291.
3. Test is to be performed during a period of ordinary demand for the water system.

    a. To obtain satisfactory test results of expected flow or rated capacities, sufficient discharge should be achieved to cause drop of at least 10 percent.

4. Pitot readings are to be taken at the 2-1/2-inch orifice connection.
5. The pitot reading is to range from 10 to 35 psig.
6. Open additional hydrant outlets as needed to control pitot readings.
7. The pitot pressure and corresponding residual pressure readings are to be taken consecutively as pressure fluctuates between a high number and low number.

B. Flow Test Data Written Report:

1. Flow data report is to be written in accordance with NFPA 291.
2. Flow data report is to include a copy of all flow data recorded during the test, including a site plan showing the tested fire hydrants with respect to the fire water service to the building. Site plan is to indicate which hydrant was flowed and which hydrant was used for pressure reading. Provide date of test, name of testing agency, and name of individual performing test.

C. Water Supply Curve: Provide water supply curve based on the lowest supply for a given set of test data. For a given residual pressure reading, the supply is to be graphed utilizing the corresponding pitot pressure/flow reading and static pressure reading.

D. Documentation is to include calibration certifications for gauges used in the flow tests. The certifications are to be from within the previous six (6) months from a reputable agency recognized for certifying pressure gauges.

E. Report flow test results promptly and in writing. A copy of the flow test data report is to be submitted with the hydraulic calculations.

3.2 INSTALLATION OF FIRE-SUPPRESSION PIPING

A. Locations and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of piping. Install piping as indicated on approved working plans.

1. Deviations from approved working plans for piping require written approval from AHJs. File written approval with Architect before deviating from approved working plans.
2. Coordinate layout and installation of sprinklers with other construction that penetrates ceilings, including light fixtures, HVAC equipment, and partition assemblies.

B. Piping Standard: Comply with NFPA 13 requirements for installation of fire-suppression piping.

C. Install seismic restraints on piping. Comply with NFPA standards requirements for seismic-restraint device materials and installation.

D. Install listed fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.

E. Install unions adjacent to each valve in pipes NPS 2 and smaller.

F. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.

G. Install inspector's test connections in sprinkler system piping, complete with shutoff valve, and sized and located in accordance with NFPA 13.

H. Install fire-suppression system piping with drains for complete system drainage. Extend drain piping to exterior of building where possible.

I. Install sprinkler control valves, test assemblies, and drain risers adjacent to standpipes when sprinkler piping is connected to standpipes.

J. Install automatic (ball drip) drain valve at each check valve for fire department connection, to drain piping between fire department connection and check valve. Install drain piping to and spill over floor drain or to exterior of building.

K. Install alarm devices in piping systems.

L. Install hangers and supports for fire-suppression piping in accordance with NFPA standards. Comply with requirements for hanger materials in NFPA standards.

M. Install pressure gauges on riser or feed main, at each sprinkler test connection, and at top of each standpipe/sprinkler supply. Include pressure gauges with connection not less than NPS 1/4 and with soft-metal seated globe valve, arranged for draining pipe between gauge and valve. Install gauges to permit removal, and install where they are not subject to freezing.

N. Fill wet-type fire-suppression system piping with water.

O. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 210517 "Sleeves and Sleeve Seals for Fire-Suppression Piping."

P. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 210517 "Sleeves and Sleeve Seals for Fire-Suppression Piping."

Q. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 210518 "Escutcheons for Fire-Suppression Piping."

3.3 INSTALLATION OF PIPING JOINTS

A. Install couplings, flanges, flanged fittings, unions, nipples, and transition and special fittings that have finish and pressure ratings same as or higher than system's pressure rating for aboveground applications unless otherwise indicated.

B. Install unions adjacent to each valve in pipes NPS 2 and smaller.

C. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.

D. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.

E. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.

F. Flanged Joints: Select appropriate gasket material in size, type, and thickness suitable for water service. Join flanges with gasket and bolts in accordance with ASME B31.9.

G. Threaded Joints: Thread pipe with tapered pipe threads in accordance with ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:

1. Apply appropriate tape or thread compound to external pipe threads.
2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.

H. Welded Joints: Construct joints in accordance with AWS D10.12M/D10.12, using qualified processes and welding operators in accordance with "Quality Assurance" Article.

1. Shop weld pipe joints where welded piping is indicated. Do not use welded joints for galvanized-steel pipe.

I. Steel-Piping, Cut-Grooved Joints: Cut square-edge groove in end of pipe in accordance with AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings in accordance with AWWA C606 for steel-pipe joints.

J. Steel-Piping, Roll-Grooved Joints: Roll rounded-edge groove in end of pipe in accordance with AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings in accordance with AWWA C606 for steel-pipe grooved joints.

K. Dissimilar-Material Piping Joints: Make joints using adapters compatible with materials of both piping systems.

3.4 INSTALLATION OF FIRE DEPARTMENT CONNECTIONS

A. Install wall-type fire department connections.

B. Install automatic (ball-drip) drain valve at each check valve for fire department connection.

3.5 INSTALLATION OF VALVES AND SPECIALTIES

A. Install listed fire-suppression system control valves, trim and drain valves, specialty valves and trim, controls, and specialties in accordance with manufacturer's installation instructions, NFPA standards, and AHJ.

B. Install listed fire-suppression system shutoff valves in supervised open position, located to control sources of water supply except from fire department connections. Install permanent identification signs indicating portion of system controlled by each valve.

C. System Control Valves:

1. Install alarm valves with bypass check valve and retarding chamber drain-line connection.

D. Air Vent:

1. Provide at least one air vent at high point in each wet-pipe fire-suppression system in accordance with NFPA standards. Connect vent into top of fire-suppression piping.
2. Provide dielectric union for dissimilar metals, ball valve, and strainer upstream of automatic air vent.
3. Pipe from outlet of air vent to drain.

3.6 INSTALLATION OF SPRINKLERS

A. Install sprinklers in suspended ceilings symmetrically in center of acoustical ceiling panels within tolerance of 1/2 inch. Coordinate entire pattern of sprinkler locations with approved reflected ceiling plan.

B. Install dry-type sprinklers with water supply from heated space. Do not install pendent or sidewall, wet-type sprinklers in areas subject to freezing.

C. Install sprinklers into flexible, sprinkler hose fittings, and install hose into bracket on ceiling grid.

3.7 IDENTIFICATION

A. Install labeling and pipe markers on piping in accordance with requirements for identification specified in Section 210553 "Identification for Fire-Suppression Piping and Equipment."

B. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

3.8 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Perform the following tests and inspections:

1. Leak Test: After installation, charge systems and test for leaks. Repair leaks and retest until no leaks exist.
2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
3. Flush, test, and inspect fire-suppression systems in accordance with NFPA standards.
4. Energize circuits to electrical equipment and devices.
5. Start and run air compressors.
6. Coordinate with fire-alarm tests. Operate as required.
7. Coordinate with fire-pump tests. Operate as required.
8. Verify that equipment hose threads are same as local fire department equipment.
9. Verify that sprinklers original factory finish has not been contaminated with dirt, debris, or paint. Sprinklers containing other-than-original factory finish are to be considered defective and replaced with new products. Repair and/or cleaning is not acceptable.

C. Fire-suppression piping system will be considered defective if it does not pass tests and inspections.

D. Fire-suppression piping system components considered defective during testing will be replaced with new components. Repair of defective components is not acceptable.

E. Prepare test and inspection reports.

3.9 CLEANING

A. Clean dirt and debris from fire-suppression system piping, system control valves, sprinklers, and associated components.

B. Only sprinklers with their original factory finish are acceptable. Remove and replace any sprinklers that are painted or have any other finish than their original factory finish.

3.10 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain system control valves.

3.11 PIPING SCHEDULE

A. Standard-Pressure, Wet-Pipe Sprinkler System, NPS 2 (DN 50) and Smaller, to Be One of the Following:

1. Schedule 40, black-steel pipe with threaded ends; uncoated, gray-iron threaded fittings; and threaded joints.
2. Schedule 40, black-steel pipe with cut- or roll-grooved ends; uncoated, grooved-end fittings for steel piping; grooved-end-pipe couplings for steel piping; and grooved joints.

3. Schedule 40, black-steel pipe with plain ends; steel welding fittings; and welded joints.

B. Standard-Pressure, Wet-Pipe Sprinkler System, NPS 2-1/2 and Larger, to Be One of the Following:

1. Schedule 40, black-steel pipe with threaded ends; uncoated, gray-iron threaded fittings; and threaded joints.
2. Schedule 40, black-steel pipe with cut- or roll-grooved ends; uncoated, grooved-end fittings for steel piping; grooved-end-pipe couplings for steel piping; and grooved joints.
3. Schedule 40, black-steel pipe with plain ends; steel welding fittings; and welded joints.
4. Schedule 10 steel pipe with roll-grooved ends; uncoated, grooved-end fittings for steel piping; grooved-end-pipe couplings for steel piping; and grooved joints.
5. Schedule 10 steel pipe with plain ends; welding fittings; and welded joints.

3.12 SPRINKLER SCHEDULE

A. Provide sprinkler types in subparagraphs below with finishes indicated.

1. Upright, Pendent, and Sidewall Sprinklers: White-painted in finished spaces exposed to view; rough bronze in unfinished spaces and locations not generally exposed to view; and wax coated where exposed to acids, chemicals, or other corrosive fumes.
2. Recessed Sprinklers: White-painted, with factory-painted white escutcheon.
3. Flat Concealed Sprinklers: Rough brass, with factory-painted white cover plate.

END OF SECTION

SECTION 211119 – FIRE DEPARTMENT CONNECTIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Exposed-type fire-department connections.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each fire-department connection.

PART 2 - PRODUCTS

2.1 EXPOSED-TYPE FIRE-DEPARTMENT CONNECTION

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Elkhart Brass Mfg. Co., Inc.
2. Fire Protection Products Inc (FPPI); a brand of Anvil International and Smith-Cooper International.
3. Guardian Fire Equipment, Inc.
4. Wilson & Cousins Inc.

B. Standard: UL 405.

C. Type: Exposed, projecting, for wall mounting.

D. Pressure Rating: 175 psig minimum.

E. Body Material: Corrosion-resistant metal.

F. Inlets: Brass with threads according to NFPA 1963 and matching local fire-department sizes and threads. Include extension pipe nipples, brass lugged swivel connections, and check devices or clappers.

G. Caps: Brass, lugged type, with gasket and chain.

H. Escutcheon Plate: Round, brass, wall type.

I. Outlet: Back, with pipe threads.

J. Number of Inlets: Two.

K. Escutcheon Plate Marking: Similar to "AUTO SPKR."

L. Finish: Polished chrome plated.

M. Outlet Size: NPS 4.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of fire-department connections.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install wall-type fire-department connections.

B. Install automatic (ball-drip) drain valve at each check valve for fire-department connection.

END OF SECTION

SECTION 220513 - COMMON MOTOR REQUIREMENTS FOR PLUMBING EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes general requirements for single-phase and polyphase, general-purpose, horizontal, small and medium, squirrel-cage induction motors for use on ac power systems up to 600 V and installed at equipment manufacturer's factory or shipped separately by equipment manufacturer for field installation.

1.3 COORDINATION

A. Coordinate features of motors, installed units, and accessory devices to be compatible with the following:

1. Motor controllers.
2. Torque, speed, and horsepower requirements of the load.
3. Ratings and characteristics of supply circuit and required control sequence.
4. Ambient and environmental conditions of installation location.

PART 2 - PRODUCTS

2.1 GENERAL MOTOR REQUIREMENTS

A. Comply with NEMA MG 1 unless otherwise indicated.

B. Comply with IEEE 841 for severe-duty motors.

2.2 MOTOR CHARACTERISTICS

A. Duty: Continuous duty at ambient temperature of 40 deg C and at altitude of 3300 feet above sea level.

B. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.

2.3 POLYPHASE MOTORS

A. Description: NEMA MG 1, Design B, medium induction motor.

B. Efficiency: Premium efficiency.

C. Service Factor: 1.15.

D. Rotor: Random-wound, squirrel cage.

E. Bearings: Regreasable, shielded, antifriction ball bearings suitable for radial and thrust loading.

F. Temperature Rise: Match insulation rating.

G. Insulation: Class F.

H. Code Letter Designation:

1. Motors 15 HP and Larger: NEMA starting Code F or Code G.
2. Motors Smaller than 15 HP: Manufacturer's standard starting characteristic.

2.4 ADDITIONAL REQUIREMENTS FOR POLYPHASE MOTORS

A. Motors Used with Variable-Frequency Controllers: Ratings, characteristics, and features coordinated with and approved by controller manufacturer.

1. Windings: Copper magnet wire with moisture-resistant insulation varnish, designed and tested to resist transient spikes, high frequencies, and short time rise pulses produced by pulse-width-modulated inverters.
2. Inverter-Duty Motors: Class F temperature rise; Class H insulation.

2.5 SINGLE-PHASE MOTORS

A. Motors larger than 1/20 hp shall be one of the following, to suit starting torque and requirements of specific motor application:

1. Permanent-split capacitor.
2. Split phase.
3. Capacitor start, inductor run.
4. Capacitor start, capacitor run.

B. Multispeed Motors: Variable-torque, permanent-split-capacitor type.

C. Bearings: Prelubricated, antifriction ball bearings or sleeve bearings suitable for radial and thrust loading.

D. Motors 1/20 HP and Smaller: Shaded-pole type.

E. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor

insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range.

PART 3 - EXECUTION (Not Applicable)

END OF SECTION

SECTION 220517 - SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Sleeves.
2. Sleeve-seal systems.
3. Grout.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product indicated. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 SLEEVES

A. Cast-Iron Pipe Sleeve: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.

B. Black-Steel-Pipe Sleeves: ASTM A 53/A53M, Type E, Grade B, Schedule 40, with plain ends.

C. Galvanized-Steel-Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, with plain ends.

D. Galvanized-Steel-Sheet Sleeves: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.

2.2 SLEEVE-SEAL SYSTEMS

A. Description: Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.

1. Sealing Elements: EPDM-rubber or NBR interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
2. Pressure Plates: Carbon steel or stainless steel.
3. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements.

2.3 GROUT

A. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.

B. Characteristics: Nonshrink; recommended for interior and exterior applications.

C. Design Mix: 5000-psi, 28-day compressive strength.

D. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 SLEEVE INSTALLATION

A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.

B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.

1. Sleeves are not required for core-drilled holes through walls.

C. Install sleeves in concrete floors and concrete walls as new slabs and walls are constructed.

1. Cut sleeves to length for mounting flush with both surfaces.

a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.

2. Using grout, seal the space outside of sleeves in slabs and walls.
3. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint. Comply with requirements for sealants specified in Section 079200 "Joint Sealants."

D. Install sleeves for pipes passing through interior partitions.

1. Extend sleeves installed in concealed interior partitions a minimum of 1-inch beyond finished wall surface.
2. Cut sleeves to length in exposed locations for mounting flush with both surfaces where escutcheons are required.
3. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation. Patch and/or seal wall penetration to seal around exterior of sleeve.

4. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint. Comply with requirements for sealants specified in Section 079200 "Joint Sealants."

E. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements for firestopping specified in Section 078413 "Penetration Firestopping."

3.2 SLEEVE-SEAL-SYSTEM INSTALLATION

A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building.

B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

3.3 SLEEVE AND SLEEVE-SEAL SCHEDULE

A. Use sleeves and sleeve seals for the following piping-penetration applications:

1. Exterior Concrete Walls above Grade:

   a. Galvanized-steel-pipe sleeves with sleeve-seal system.

      1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.

2. Exterior Concrete Walls below Grade:

   a. Cast-iron wall sleeves with sleeve-seal system or Galvanized-steel-pipe sleeves with sleeve-seal system.

      1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.

3. Concrete Slabs-on-Grade:

   a. Galvanized-steel-pipe sleeves with sleeve-seal system.

      1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.

4. Concrete Slabs above Grade:

   a. Black-steel-pipe sleeves.

5. Interior Partitions:

a. Piping Smaller than NPS 6: Black-steel-pipe sleeves.
b. Piping NPS 6 and Larger: Galvanized-steel-sheet sleeves.

END OF SECTION

SECTION 220518 - ESCUTCHEONS FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Escutcheons.
2. Floor plates.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product indicated. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 ESCUTCHEONS

A. One-Piece, Cast-Brass Type: With polished, chrome-plated or rough-brass finish and setscrew fastener.

B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with chrome-plated finish and spring-clip fasteners.

C. Split-Plate, Stamped-Steel Type: With polished, chrome-plated finish; concealed hinge, and spring-clip fasteners.

2.2 FLOOR PLATES

A. One-Piece Floor Plates: Cast-iron flange with holes for fasteners.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.

B. Install escutcheons with ID to closely fit around pipe, tube, and insulation of insulated piping and with OD that completely covers opening.

1. Escutcheons for New Piping:

a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type.
b. Chrome-Plated Piping: One-piece, cast-brass type with polished, chrome-plated finish.
c. Insulated Piping: Split-plate, stamped-steel with concealed hinge with polished, chrome-plated finish.
d. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece, cast-brass type with polished, chrome-plated finish.
e. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece, cast-brass type with polished, chrome-plated finish.
f. Bare Piping in Unfinished Service Spaces: One-piece, cast-brass type with rough-brass finish.
g. Bare Piping in Equipment Rooms: One-piece, cast-brass type with rough-brass finish.

C. Install floor plates for piping penetrations of equipment-room floors.

D. Install floor plates with ID to closely fit around pipe, tube, and insulation of piping and with OD that completely covers opening.

1. New Piping: One-piece, floor-plate type.

3.2 FIELD QUALITY CONTROL

A. Replace broken and damaged escutcheons and floor plates using new materials.

END OF SECTION

SECTION 220519 - METERS AND GAGES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Liquid-in-glass thermometers.
2. Thermowells.
3. Dial-type pressure gages.
4. Gage attachments.

B. Related Requirements:

1. Section 221119 "Domestic Water Piping Specialties" for water meters by the municipal water supplier.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Certificates: For each type of meter and gage.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Operation and Maintenance Data: For meters and gages to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 LIQUID-IN-GLASS THERMOMETERS

A. Metal-Case, Industrial-Style, Liquid-in-Glass Thermometers:

1. Manufacturers: subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. Flo Fab Inc.
   b. Palmer Wahl Instrumentation Group.
   c. Trerice, H. O. Co.
   d. Weiss Instruments, Inc.
   e. Weksler Glass Thermometer Corp.

2. Standard: ASME B40.200.
3. Case: Cast aluminum; 7-inch nominal size unless otherwise indicated.
4. Case Form: Adjustable angle unless otherwise indicated.
5. Tube: Glass with magnifying lens and blue or red organic liquid.
6. Tube Background: Nonreflective aluminum with permanently etched scale markings graduated in deg F.
7. Window: Glass.
8. Stem: Aluminum and of length to suit installation.

   a. Design for Thermowell Installation: Bare stem.

9. Connector: 1-1/4 inches, with ASME B1.1 screw threads.
10. Accuracy: Plus or minus 1 percent of scale range or one scale division, to a maximum of 1.5 percent of scale range.

2.2 THERMOWELLS

A. Thermowells:

1. Standard: ASME B40.200.
2. Description: Pressure-tight, socket-type fitting made for insertion into piping tee fitting.
3. Type: Stepped shank unless straight or tapered shank is indicated.
4. External Threads: NPS 1/2, NPS 3/4, or NPS 1, ASME B1.20.1 pipe threads.
5. Internal Threads: 1/2, 3/4, and 1 inch, with ASME B1.1 screw threads.
6. Bore: Diameter required to match thermometer bulb or stem.
7. Insertion Length: Length required to match thermometer bulb or stem.
8. Lagging Extension: Include on thermowells for insulated piping and tubing.
9. Bushings: For converting size of thermowell's internal screw thread to size of thermometer connection.

B. Heat-Transfer Medium: Mixture of graphite and glycerin.

2.3 PRESSURE GAGES

A. Direct-Mounted, Metal-Case, Dial-Type Pressure Gages:

1. Manufacturers: subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Ashcroft Inc.
    b. Flo Fab Inc.
    c. Palmer Wahl Instrumentation Group.
    d. Trerice, H. O. Co.
    e. Watts; a Watts Water Technologies company.
    f. Weiss Instruments, Inc.
    g. Weksler Glass Thermometer Corp.

2. Standard: ASME B40.100.
3. Case: Liquid-filled, sealed type(s); cast aluminum or drawn steel; 4-1/2-inch nominal diameter.
4. Pressure-Element Assembly: Bourdon tube unless otherwise indicated.
5. Pressure Connection: Brass, with ASME B1.20.1 pipe threads and bottom-outlet type unless back-outlet type is indicated.
6. Movement: Mechanical, with link to pressure element and connection to pointer.
7. Dial: Nonreflective aluminum with permanently etched scale markings graduated in psi.
8. Pointer: Dark-colored metal.
9. Window: Glass.
10. Ring: Metal.
11. Accuracy: Grade A, plus or minus 1 percent of middle half of scale range.

2.4 GAGE ATTACHMENTS

A. Snubbers: ASME B40.100, brass; with ASME B1.20.1 pipe threads and piston or porous-metal-type surge-dampening device. Include extension for use on insulated piping.

B. Valves: Brass or stainless-steel needle, with ASME B1.20.1 pipe threads.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install thermowells with socket extending one-third of pipe diameter and in vertical position in piping tees.

B. Install thermowells of sizes required to match thermometer connectors. Include bushings if required to match sizes.

C. Install thermowells with extension on insulated piping.

D. Fill thermowells with heat-transfer medium.

E. Install direct-mounted thermometers in thermowells and adjust vertical and tilted positions.

F. Install direct-mounted pressure gages in piping tees with pressure gage located on pipe at the most readable position.

G. Install valve and snubber in piping for each pressure gage.

H. Install thermometers in the following locations:

1. Inlet and outlet of each water heater.

I. Install pressure gages in the following locations:

1. Building water service entrance into building.
2. Suction and discharge of each domestic water pump.

3.2 CONNECTIONS

A. Install meters and gages adjacent to machines and equipment to allow service and maintenance of meters, gages, machines, and equipment.

3.3 ADJUSTING

A. Adjust faces of meters and gages to proper angle for best visibility.

3.4 THERMOMETER SCHEDULE

A. Thermometers at inlet and outlet of each domestic water heater shall be the following:

1. Metal case, industrial-style, liquid-in-glass type.

B. Thermometer stems shall be of length to match thermowell insertion length.

3.5 THERMOMETER SCALE-RANGE SCHEDULE

A. Scale Range for Domestic Hot-Water Piping: 30 to 240 deg F.

3.6 PRESSURE-GAGE SCHEDULE

A. Pressure gages at water service into building, and suction and discharge at domestic pump shall be the following:

1. Liquid-filled, sealed, direct-mounted, metal case.

3.7 PRESSURE-GAGE SCALE-RANGE SCHEDULE

A. Scale Range for Water Service Piping: 0 to 160 psi.

END OF SECTION

SECTION 220523.12 - BALL VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Bronze ball valves.

1.3 DEFINITIONS

A. CWP: Cold working pressure.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of valve. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1. Certification that products comply with NSF 61 Annex G and NSF 372.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:

1. Protect internal parts against corrosion.
2. Protect threads and flange faces.
3. Set ball valves open to minimize exposure of functional surfaces.

B. Use the following precautions during storage:

1. Maintain valve end protection.
2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR VALVES

A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.

B. ASME Compliance:

1. ASME B1.20.1 for threads for threaded end valves.
2. ASME B16.18 for solder-joint connections.

C. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.

D. NSF Compliance: NSF 61 Annex G and NSF 372 for valve materials for potable-water service.

E. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.

F. Valve Sizes: Same as upstream piping unless otherwise indicated.

G. Valve Actuator Types:

1. Handlever: For quarter-turn valves smaller than NPS 4.

H. Valves in Insulated Piping:

1. Include 2-inch stem extensions.
2. Extended operating handles of nonthermal-conductive material and protective sleeves that allow operation of valves without breaking vapor seals or disturbing insulation.
3. Memory stops that are fully adjustable after insulation is applied.

2.2 BRONZE BALL VALVES

A. Bronze Ball Valves, Two-Piece with Full Port and Stainless-Steel Trim:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Apollo Valves; Conbraco Industries, Inc.
b. Crane; Crane Energy Flow Solutions.
c. Hammond Valve.
d. Milwaukee Valve Company.
e. NIBCO INC.
f. Watts; a Watts Water Technologies company.

2. Description:

a. Standard: MSS SP-110.
b. CWP Rating: 600 psig.
c. Body Design: Two piece.
d. Body Material: Bronze.
e. Ends: Threaded, soldered, or flanged.
f. Seats: PTFE.
g. Stem: Stainless-steel.
h. Ball: Stainless-steel.
i. Port: Full.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.

C. Examine threads on valve and mating pipe for form and cleanliness.

D. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE INSTALLATION

A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.

B. Locate valves for easy access and provide separate support where necessary.

C. Install valves in horizontal piping with stem at or above center of pipe.

D. Install valves in position to allow full stem movement.

E. Install valve tags. Comply with requirements in Section 220553 "Identification for Plumbing Piping and Equipment" for valve tags and schedules.

3.3 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

A. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.

B. Select valves with the following end connections:

1. For Copper Tubing, NPS 2 and Smaller: Threaded ends except where soldered-joint valve-end option is indicated in schedules below.
2. For Copper Tubing, NPS 2-1/2 to NPS 3: Flanged ends except where threaded valve-end option is indicated in valve schedules below.

3.4 DOMESTIC HOT- AND COLD-WATER VALVE SCHEDULE

A. Pipe NPS 2 and Smaller:

1. Bronze Valves: May be provided with solder-joint ends instead of threaded ends.
2. Bronze ball valves, two-piece with full port, stainless-steel trim, and threaded ends.

B. Pipe NPS 2-1/2 to NPS 3:

1. Bronze ball valves, two-piece with full port, stainless-steel trim, and threaded or flanged ends.

END OF SECTION

SECTION 220523.14 - CHECK VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Bronze swing check valves.

1.3 DEFINITIONS

A. CWP: Cold working pressure.

B. EPDM: Ethylene propylene-diene terpolymer rubber.

C. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Construction Contract Clauses, Section 007213 "General Conditions" and the individual sections specifying the work.

B. Product Data: For each type of valve. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:

1. Protect internal parts against rust and corrosion.
2. Protect threads.
3. Set check valves in either closed or open position.

B. Use the following precautions during storage:

1. Maintain valve end protection.
2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR VALVES

A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.

B. ASME Compliance:

1. ASME B1.20.1 for threads for threaded end valves.
2. ASME B16.18 for solder joint.
3. ASME B31.9 for building services piping valves.

C. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.

D. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.

E. Valve Sizes: Same as upstream piping unless otherwise indicated.

2.2 BRONZE SWING CHECK VALVES

A. Bronze Swing Check Valves with Nonmetallic Disc, Class 125:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Crane; Crane Energy Flow Solutions.
b. Hammond Valve.
c. Milwaukee Valve Company.
d. NIBCO INC.
e. Watts; a Watts Water Technologies company.

2. Description:

a. Standard: MSS SP-80, Type 4.
b. CWP Rating: 200 psig.
c. Body Design: Horizontal flow.
d. Body Material: ASTM B 62, bronze.
e. Ends: Threaded or soldered. See valve schedule articles.
f. Disc: PTFE.

B. Bronze Swing Check Valves with Bronze Disc, Class 150:

1. Manufacturers: subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Apollo Valves; Conbraco Industries, Inc.
b. Crane; Crane Energy Flow Solutions.
c. Milwaukee Valve Company.
d. NIBCO INC.

2. Description:

a. Standard: MSS SP-80, Type 3.
b. CWP Rating: 300 psig.
c. Body Design: Horizontal flow.
d. Body Material: ASTM B 62, bronze.
e. Ends: Threaded or soldered. See valve schedule articles.
f. Disc: Bronze.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.

C. Examine threads on valve and mating pipe for form and cleanliness.

D. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE INSTALLATION

A. Locate valves for easy access and provide separate support where necessary.

B. Install check valves for proper direction of flow and as follows:

1. Swing Check Valves: In horizontal position with hinge pin level.

3.3 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

A. If valve applications are not indicated, use the following:

1. Pump-Discharge Check Valves:

a. NPS 2 and Smaller: Bronze swing check valves with nonmetallic disc.

B. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.

C. End Connections:

1. For Copper Tubing, NPS 2 and Smaller: Threaded or soldered.
2. For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged or threaded.
3. For Steel Piping, NPS 2 and Smaller: Threaded.

3.4 DOMESTIC HOT- AND COLD-WATER VALVE SCHEDULE

A. Pipe NPS 2 and Smaller: Bronze swing check valves with nonmetallic disc, Class 125, with soldered or threaded end connections.

3.5 SANITARY WASTE AND STORM DRAINAGE VALVE SCHEDULE

A. Pipe NPS 2 and Smaller: Bronze swing check valves, Class 125, nonmetallic disc with threaded end connections.

END OF SECTION

SECTION 220529 - HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Metal pipe hangers and supports.
2. Trapeze pipe hangers.
3. Metal framing systems.
4. Thermal-hanger shield inserts.
5. Fastener systems.
6. Pipe stands.
7. Pipe positioning systems.
8. Equipment supports.

B. Related Sections:

1. Section 055000 "Metal Fabrications" for structural-steel shapes and plates for trapeze hangers for pipe and equipment supports.
2. Section 220548.13 "Vibration Controls for Plumbing Piping and Equipment" for vibration isolation devices.

1.3 DEFINITIONS

A. MSS: Manufacturers Standardization Society of The Valve and Fittings Industry Inc.

1.4 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design trapeze pipe hangers and equipment supports, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Structural Performance: Hangers and supports for plumbing piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.

1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.

2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

1.5 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product indicated. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Shop Drawings: Show fabrication and installation details and include calculations for the following; include Product Data for components:

1. Trapeze pipe hangers.
2. Metal framing systems.
3. Pipe stands.

1.6 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Welding certificates.

1.7 QUALITY ASSURANCE

A. Structural Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.

PART 2 - PRODUCTS

2.1 METAL PIPE HANGERS AND SUPPORTS

A. Carbon-Steel Pipe Hangers and Supports:

1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
2. Galvanized Metallic Coatings: Pregalvanized or hot dipped.
3. Nonmetallic Coatings: Plastic coating, jacket, or liner.
4. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

B. Copper Pipe Hangers:

1. Description: MSS SP-58, Types 1 through 58, copper-coated-steel, factory-fabricated components.
2. Hanger Rods: Continuous-thread rod, nuts, and washer made of copper-coated steel.

2.2 TRAPEZE PIPE HANGERS

A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

2.3 METAL FRAMING SYSTEMS

A. Metal Framing Systems:

1. Description: Shop- or field-fabricated pipe-support assembly for supporting multiple parallel pipes.
2. Standard: MFMA-4.
3. Channels: Continuous slotted steel channel with inturned lips.
4. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
6. Metallic Coating: Galvanized.

2.4 THERMAL-HANGER SHIELD INSERTS

A. Insulation-Insert Material for Piping: ASTM C 552, Type II cellular glass with 100-psig or ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength and vapor barrier.

B. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.

C. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.

D. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.5 FASTENER SYSTEMS

A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

B. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel anchors, for use in hardened portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

2.6 PIPE STANDS

A. General Requirements for Pipe Stands: Shop- or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.

B. Compact Pipe Stand: One-piece plastic unit with integral-rod roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.

C. High-Type, Single-Pipe Stand:

1. Description: Assembly of base, vertical and horizontal members, and pipe support, for roof installation without membrane penetration.
2. Base: Plastic or stainless steel.
3. Vertical Members: Two or more cadmium-plated-steel or stainless-steel, continuous-thread rods.
4. Horizontal Member: Cadmium-plated-steel or stainless-steel rod with plastic or stainless-steel, roller-type pipe support.

D. High-Type, Multiple-Pipe Stand:

1. Description: Assembly of bases, vertical and horizontal members, and pipe supports, for roof installation without membrane penetration.
2. Bases: One or more; plastic.
3. Vertical Members: Two or more protective-coated-steel channels.
4. Horizontal Member: Protective-coated-steel channel.
5. Pipe Supports: Galvanized-steel, clevis-type pipe hangers.

E. Curb-Mounting-Type Pipe Stands: Shop- or field-fabricated pipe supports made from structural-steel shapes, continuous-thread rods, and rollers, for mounting on permanent stationary roof curb.

2.7 PIPE POSITIONING SYSTEMS

A. Description: IAPMO PS 42, positioning system of metal brackets, clips, and straps for positioning piping in pipe spaces; for plumbing fixtures in commercial applications.

2.8 EQUIPMENT SUPPORTS

A. Description: Welded, shop- or field-fabricated equipment support made from structural carbon-steel shapes.

2.9 MISCELLANEOUS MATERIALS

A. Structural Steel: ASTM A 36/A 36M, carbon-steel plates, shapes, and bars; black and galvanized.

B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.

1. Properties: Nonstaining, noncorrosive, and nongaseous.
2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT INSTALLATION

A. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.

B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.

1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.
2. Field fabricate from ASTM A 36/A 36M, carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.

C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.

D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.

E. Fastener System Installation:

1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual.
2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.

F. Pipe Stand Installation:

1. Pipe Stand Types except Curb-Mounted Type: Assemble components and mount on smooth roof surface. Do not penetrate roof membrane.
2. Curb-Mounted-Type Pipe Stands: Assemble components or fabricate pipe stand and mount on permanent, stationary roof curb. See Section 077200 "Roof Accessories" for curbs.

G. Pipe Positioning-System Installation: Install support devices to make rigid supply and waste piping connections to each plumbing fixture.

H. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.

I. Equipment Support Installation: Fabricate from welded-structural-steel shapes.

J. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.

K. Install lateral bracing with pipe hangers and supports to prevent swaying.

L. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.

M. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.

N. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.

O. Insulated Piping:

1. Attach clamps and spacers to piping.

    a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
    b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
    c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.

2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.

    a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.

    a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

4. Shield Dimensions for Pipe: Not less than the following:

    a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
    b. NPS 4: 12 inches long and 0.06 inch thick.
    c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
    d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.

5. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.2 EQUIPMENT SUPPORTS

A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.

B. Grouting: Place grout under supports for equipment and make bearing surface smooth.

C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.3 METAL FABRICATIONS

A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.

B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.

C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

3.4 ADJUSTING

A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.

B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.5 PAINTING

A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.

1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.

B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

3.6 HANGER AND SUPPORT SCHEDULE

A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.

B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.

C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.

D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.

E. Use carbon-steel pipe hangers and supports, metal trapeze pipe hangers, and metal framing systems and attachments for general service applications.

F. Use copper-plated pipe hangers and copper attachments for copper piping and tubing.

G. Use thermal-hanger shield inserts for insulated piping and tubing.

H. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of stationary pipes NPS 1/2 to NPS 30.
2. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
3. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
4. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
5. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.
6. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction might occur.
7. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.

I. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.

J. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
3. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.

K. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
6. C-Clamps (MSS Type 23): For structural shapes.
7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
10. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
11. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:

    a. Light (MSS Type 31): 750 lb.
    b. Medium (MSS Type 32): 1500 lb.
    c. Heavy (MSS Type 33): 3000 lb.

L. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.

M. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.

N. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.

O. Use powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where required in concrete construction.

P. Use pipe positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

END OF SECTION

SECTION 220553 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Equipment labels.
2. Pipe labels.
3. Valve tags.
4. Warning tags.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.

D. Valve numbering scheme.

E. Valve Schedules: For each piping system to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

A. Plastic Labels for Equipment:

1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
2. Letter Color: White.
3. Background Color: Black.

4. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
6. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
7. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

B. Label Content: Include equipment's Drawing designation or unique equipment number.

2.2 PIPE LABELS

A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.

B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.

C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.

D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings; also include pipe size and an arrow indicating flow direction.

1. Flow-Direction Arrows: Integral with piping-system service lettering to accommodate both directions or as separate unit on each pipe label to indicate flow direction.
2. Lettering Size: Size letters according to ASME A13.1 for piping.

2.3 VALVE TAGS

A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.

1. Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
2. Fasteners: Brass wire-link chain or S-hook.

B. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.

1. Valve-tag schedule shall be included in operation and maintenance data.

2.4 WARNING TAGS

A. Description: Preprinted or partially preprinted accident-prevention tags of plasticized card stock with matte finish suitable for writing.

1. Size: 3 by 5-1/4 inches minimum.
2. Fasteners: Brass grommet and wire.
3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
4. Color: Safety yellow background with black lettering.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 GENERAL INSTALLATION REQUIREMENTS

A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.

B. Coordinate installation of identifying devices with locations of access panels and doors.

C. Install identifying devices before installing acoustical ceilings and similar concealment.

3.3 EQUIPMENT LABEL INSTALLATION

A. Install or permanently fasten labels on each major item of mechanical equipment.

B. Locate equipment labels where accessible and visible.

3.4 PIPE LABEL INSTALLATION

A. Pipe Label Locations: Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:

1. Near each valve and control device.

2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
4. At access doors, manholes, and similar access points that permit view of concealed piping.
5. Near major equipment items and other points of origination and termination.
6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.

B. Directional Flow Arrows: Arrows shall be used to indicate direction of flow in pipes, including pipes where flow is allowed in both directions.

C. Pipe Label Color Schedule:

1. Domestic Water Piping

a. Background: Safety green.
b. Letter Colors: White.

2. Sanitary Waste and Vent, and Storm Drainage Piping:

a. Background Color: Safety gray.
b. Letter Color: Black.

3.5 VALVE-TAG INSTALLATION

A. Install tags on valves and control devices in piping systems, except check valves, valves within factory-fabricated equipment units, shutoff valves, faucets, convenience and lawn-watering hose connections, and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.

B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:

1. Valve-Tags:

a. Valve-Tag Size and Shape: 2 inches, round.
b. Valve-Tag Color: Natural.
c. Letter Colors: Black.

3.6 WARNING-TAG INSTALLATION

A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION

SECTION 220593 – TESTING, ADJUSTING, AND BALANCING FOR PLUMBING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. TAB of domestic water system.
2. TAB of plumbing equipment:

    a. Domestic hot-water in-line circulation pumps.

B. Related Requirements:

1. Section 230593 “Testing, Adjusting, and Balancing for HVAC.”

1.3 DEFINITIONS

A. AABC: Associated Air Balance Council.

B. NEBB: National Environmental Balancing Bureau.

C. TAB: Testing, adjusting, and balancing.

D. TABB: Testing, Adjusting, and Balancing Bureau.

E. TAB Specialist: An independent entity meeting qualifications to perform TAB work.

F. TDH: Total dynamic head.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of the Construction Contract Clauses, Division 01 Section "Submittal Procedures" and the individual sections specifying the work.

B. Qualification Data: Within 60 days of Contractor's Notice to Proceed, submit documentation that the TAB specialist and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article.

C. Contract Documents Examination Report: Within 90 days of Contractor's Notice to Proceed, submit the Contract Documents review report, as specified in Part 3.

D. Strategies and Procedures Plan: Within 90 days of Contractor's Notice to Proceed, submit TAB strategies and step-by-step procedures, as specified in "Preparation" Article.

E. System Readiness Checklists: Within 90 days of Contractor's Notice to Proceed, submit system readiness checklists, as specified in "Preparation" Article.

F. Examination Report: Submit a summary report of the examination review required in "Examination" Article.

G. Certified TAB reports.

H. Sample report forms.

I. Instrument calibration reports, to include the following:

1. Instrument type and make.
2. Serial number.
3. Application.
4. Dates of use.
5. Dates of calibration.

1.5 QUALITY ASSURANCE

A. TAB Specialists Qualifications, Certified by AABC:

1. TAB Field Supervisor: Employee of the TAB specialist and certified by AABC.
2. TAB Technician: Employee of the TAB specialist and certified by AABC.

B. TAB Specialists Qualifications, Certified by NEBB or TABB:

1. TAB Field Supervisor: Employee of the TAB specialist and certified by NEBB or TABB.
2. TAB Technician: Employee of the TAB specialist and certified by NEBB or TABB.

C. Instrumentation Type, Quantity, Accuracy, and Calibration: Comply with requirements in ASHRAE 111, Section 4, "Instrumentation."

D. ASHRAE 111 Compliance: Requirements in ASHRAE 111 applicable to analogous domestic water system and plumbing equipment balancing.

E. ASHRAE 188 Compliance: Comply with balancing and report requirements, Section 8.3 "Balancing."

F. Code and Authorities Having Jurisdiction Compliance: TAB is required to comply with governing codes and requirements of authorities having jurisdiction.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems designs that may preclude proper TAB of systems and equipment.

B. Examine installed systems for balancing devices, such as test ports, gauge cocks, thermometer wells, flow-control devices, and balancing valves and fittings. Verify that locations of these balancing devices are applicable for intended purpose and are accessible.

C. Examine approved submittals for plumbing systems and equipment.

D. Examine equipment performance data, including pump curves.

1. Relate performance data to Project conditions and requirements, including pump system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
2. Calculate pump system-effect factors to reduce performance ratings of plumbing equipment when installed under conditions different from the conditions used to rate equipment performance. Compare results with the design data and installed conditions.

E. Examine system and equipment installations, and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.

F. Examine test reports specified in individual system and equipment Sections.

G. Examine plumbing equipment and verify that bearings are greased, belts are aligned and tight, filters are clean, and equipment with functioning controls is ready for operation.

H. Examine temporary and permanent strainers. Verify that temporary strainer screens used during system cleaning and flushing have been removed and permanent strainers are installed and clean.

I. Examine system pumps to ensure absence of entrained air in the suction piping.

J. Examine operating safety interlocks and controls on plumbing equipment.

K. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.2 PREPARATION

A. Prepare a TAB plan that includes the following:

1. Equipment and systems to be tested.

2. Strategies and step-by-step procedures for balancing the systems.
3. Instrumentation to be used.
4. Sample forms with specific identification for all equipment.

B. Perform system-readiness checks of plumbing systems and equipment to verify system readiness for TAB work. Include, at a minimum, the following:

1. Domestic Water System:

a. Verify leakage and pressure tests on water distribution systems have been satisfactorily completed in accordance with applicable code and authority having jurisdiction.
b. Water heaters are installed and functioning.
c. Piping is complete and all points of outlet are installed.
d. Water treatment is complete.
e. Systems are flushed, filled, and air purged.
f. Strainers are clean.
g. Shutoff and balance valves are 100 percent open.
h. Hot-water circulating pumps are operational and proper rotation is verified.
i. Pump gauge connections are installed directly at pump inlet and outlet flanges or in discharge and suction pipe prior to valves or strainers.
j. Suitable access to balancing devices and equipment is provided.

3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

A. Perform testing and balancing procedures on each system in accordance with the procedures contained in AABC's "National Standards for Total System Balance," ASHRAE 111, or NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems" and in this Section.

B. Mark equipment and balancing devices, including valve position indicators and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.

C. Take and report testing and balancing measurements in inch-pound (IP) units.

3.4 GENERAL PROCEDURES FOR PLUMBING EQUIPMENT

A. Test, adjust, and balance plumbing equipment indicated on Drawings, including, but not limited to, the following:

1. Motors.
2. Domestic water in-line pumps.

3.5 PROCEDURES FOR DOMESTIC WATER SYSTEMS

A. Prepare test reports for pumps and other equipment. Obtain approved submittals and manufacturer-recommended testing procedures. Crosscheck the summation of required equipment flow rates with system design flow rates.

B. Prepare schematic diagrams of systems' Record drawings piping layouts.

C. In addition to requirements in "Preparation" Article, prepare domestic water systems for testing and balancing as follows:

1. Check expansion tank for proper setting.
2. Check water heater for proper discharge temperature setting.
3. Check remotest point of outlet for adequate pressure.
4. Check flow-control valves for proper position.
5. Locate start-stop and disconnect switches, electrical interlocks, and motor controllers.
6. Verify that motor controllers are equipped with properly sized thermal protection.
7. Check that air has been purged from the system.

D. Measure and record upstream and downstream pressure of each piece of equipment.

E. Check settings and operation of automatic temperature-control valves, self-contained control valves, and pressure-reducing valves. Record final settings.

F. Check settings and operation of each safety valve. Record settings.

3.6 PROCEDURES FOR DOMESTIC HOT-WATER CIRCULATING INLINE PUMP

A. Balance system with manual or automatic balancing valves by setting at design flow.

1. Measure flow in main and branch pipes.
2. Adjust main and branch balance valves for design flow.
3. Re-measure each main and branch after all have been adjusted.

B. Adjust pump to deliver total design flow.

1. Measure pump TDH as follows:

a. Measure discharge pressure directly at the pump outlet flange or in discharge pipe prior to any valves.
b. Measure inlet pressure directly at the pump inlet flange or in suction pipe prior to any valves or strainers.
c. Convert pressure to head and correct for differences in gauge heights.
d. Verify pump impeller size by measuring the TDH with the discharge valve closed. Note the point on manufacturer's pump curve at zero flow, and verify that the pump has the intended impeller size.

2. Monitor motor performance during procedures, and do not operate motor in an overloaded condition.
3. Mark final settings and verify that all memory stops have been set.
4. Verify final system conditions as follows:

a. Re-measure and confirm that total flow is within design.
b. Re-measure final pumps' operating data, TDH, volts, amps, speed, and static profile.
c. Mark final settings.

3.7 TOLERANCES

A. Set plumbing system's flow rates within the following tolerances:

1. Domestic Water Flow Rate: Plus or minus 10 percent. If design value is less than 10 gpm, within 10 percent.

3.8 FINAL REPORT

A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.

1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
2. Include a list of instruments used for procedures, along with proof of calibration.
3. Certify validity and accuracy of field data.

B. Final Report Contents: In addition to certified field-report data, include the following:

1. Pump curves.
2. Manufacturers' test data.
3. Field test reports prepared by system and equipment installers.
4. Other information relative to equipment performance; do not include Shop Drawings and Product Data.

C. General Report Data: In addition to form titles and entries, include the following data:

1. Title page.
2. Name and address of the TAB specialist.
3. Project name.
4. Project location.
5. Architect's name and address.
6. Engineer's name and address.
7. Contractor's name and address.
8. Report date.
9. Signature of TAB supervisor who certifies the report.
10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
11. Summary of contents, including the following:

    a. Indicated versus final performance.
    b. Notable characteristics of systems.
    c. Description of system operation sequence if it varies from the Contract Documents.

12. Nomenclature sheets for each item of equipment.
13. Notes to explain why certain final data in the body of reports vary from indicated values.
14. Test conditions for pump performance forms, including the following:

    a. Settings for pressure controller(s).
    b. Other system operating conditions that affect performance.

D. System Diagrams: Include schematic layouts of distribution systems. Present each system with single-line diagram and include the following:

1. Flow rates.
2. Pipe and valve sizes and locations.
3. Balancing stations.
4. Position of balancing devices.

E. Pump Test Reports: Calculate impeller size by plotting the shutoff head on pump curves, and include the following:

1. Unit Data:

a. Unit identification.
b. Location.
c. Service.
d. Make and size.
e. Model number and serial number.
f. Water flow rate in gpm.
g. Water-pressure differential in feet of head or psig.
h. Required net positive suction head in feet of head or psig.
i. Pump speed.
j. Impeller diameter in inches.
k. Motor make and frame size.
l. Motor horsepower and rpm.
m. Voltage at each connection.
n. Amperage for each phase.
o. Full-load amperage and service factor.
p. Seal type.

2. Test Data (Indicated and Actual Values):

a. Static head in feet of head or psig.
b. Pump shutoff pressure in feet of head or psig.
c. Actual impeller size in inches.
d. Full-open flow rate in gpm.
e. Full-open pressure in feet of head or psig.
f. Final discharge pressure in feet of head or psig.
g. Final suction pressure in feet of head or psig.
h. Final total pressure in feet of head or psig.
i. Final water flow rate in gpm.
j. Voltage at each connection.
k. Amperage for each phase.

F. Instrument Calibration Reports:

1. Report Data:

a. Instrument type and make.
b. Serial number.
c. Application.

d. Dates of use.
e. Dates of calibration.

END OF SECTION

SECTION 220719 - PLUMBING PIPING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes insulating the following plumbing piping services:

1. Domestic cold-water piping.
2. Domestic hot-water piping.
3. Roof drains and rainwater leaders.

B. Related Sections:

1. Section 224200 "Commercial Plumbing Fixtures" for protective shielding coverage for supplies and drains for handicapped-accessible fixtures.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory- and field-applied, if any). For adhesives, mastics, and sealants, indicating VOC content. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Insulation Schedule: Identify type of material, thickness, vapor barrier provision and where required, field-applied jacket to be provided for each system application.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For qualified Installer.

C. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.

B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84 by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.

1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."

B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.8 SCHEDULING

A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.

B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

A. Comply with requirements in "Piping Insulation Schedule, General" and "Indoor Piping Insulation Schedule" articles for where insulating materials shall be applied.

B. Products shall not contain asbestos, lead, mercury, or mercury compounds.

C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.

D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.

E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.

F. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials.

1. Manufacturers: subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Aeroflex USA, Inc.
b. Armacell LLC.
c. K-Flex USA.

G. Mineral-Fiber, Preformed Pipe Insulation:

1. Manufacturers: subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Johns Manville; a Berkshire Hathaway company.
b. Knauf Insulation.
c. Manson Insulation Inc.
d. Owens Corning.

2. Type I, 850 Deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A, with factory-applied ASJ-SSL. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

2.2 INSULATING CEMENTS

A. Mineral-Fiber Insulating Cement: Comply with ASTM C 195.

B. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449.

2.3 ADHESIVES

A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated, unless otherwise indicated.

B. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.

1. Adhesive: As recommended by flexible elastomeric manufacturer and with a VOC content of 80 g/L or less.

C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.

1. Adhesive: As recommended by mineral fiber manufacturer and with a VOC content of 80 g/L or less.

D. ASJ Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.

1. Adhesives shall have a VOC content of 80 g/L or less.

E. PVC Jacket Adhesive: Compatible with PVC jacket.

1. Adhesive: As recommended by Adhesive - PVC Jacket manufacturer and with a VOC content of 50 g/L or less.

2.4 MASTICS

A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.

1. Adhesive: As recommended by insulation manufacturer and with a VOC content of 50 g/L or less.

B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below-ambient services.

1. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm at 43-mil dry film thickness.
2. Service Temperature Range: Minus 20 to plus 180 deg F.
3. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
4. Color: White.

C. Breather Mastic: Water based; suitable for indoor and outdoor use on above-ambient services.

1. Water-Vapor Permeance: ASTM F 1249, 1.8 perms at 0.0625-inch dry film thickness.
2. Service Temperature Range: Minus 20 to plus 180 deg F.
3. Solids Content: 60 percent by volume and 66 percent by weight.
4. Color: White.

2.5 LAGGING ADHESIVES

A. Description: Comply with MIL-A-3316C, Class I, Grade A, and shall be compatible with insulation materials, jackets, and substrates.

1. For indoor applications, use lagging adhesives that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
2. Fire-resistant, water-based lagging adhesive and coating for use indoors to adhere fire-resistant lagging cloths over pipe insulation.

3. Service Temperature Range: 0 to plus 180 deg F.
4. Color: White.

2.6 SEALANTS

A. ASJ Flashing Sealants and PVC Jacket Flashing Sealants:

1. Materials shall be compatible with insulation materials, jackets, and substrates.
2. Fire- and water-resistant, flexible, elastomeric sealant.
3. Service Temperature Range: Minus 40 to plus 250 deg F.
4. Color: White.
5. Sealant shall have a VOC content of 420 g/L or less.

2.7 FACTORY-APPLIED JACKETS

A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:

1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.
2. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.

2.8 FIELD-APPLIED JACKETS

A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.

B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.

C. Manufacturers: subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Johns Manville; a Berkshire Hathaway company.
b. P.I.C. Plastics, Inc.
c. Proto Corporation.
d. Speedline Corporation.

2. Adhesive: As recommended by jacket material manufacturer.
3. Color: White.
4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.

a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

2.9 TAPES

A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.

1. Width: 3 inches.
2. Thickness: 11.5 mils.
3. Adhesion: 90 ounces force/inch in width.
4. Elongation: 2 percent.
5. Tensile Strength: 40 lbf/inch in width.
6. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.

B. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.

1. Width: 2 inches.
2. Thickness: 6 mils.
3. Adhesion: 64 ounces force/inch in width.
4. Elongation: 500 percent.
5. Tensile Strength: 18 lbf/inch in width.

2.10 SECUREMENTS

A. Bands:

1. Stainless Steel: ASTM A 167 or ASTM A 240/A 240M, Type 304 or Type 316; 0.015 inch thick, 1/2 inch wide with wing seal or closed seal.

B. Staples: Outward-clinching insulation staples, nominal 3/4-inch-wide, stainless steel or Monel.

C. Wire: 0.062-inch soft-annealed, stainless steel.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.

1. Verify that systems to be insulated have been tested and are free of defects.
2. Verify that surfaces to be insulated are clean and dry.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

B. Coordinate insulation installation with the trade installing heat tracing. Comply with requirements for heat tracing that apply to insulation.

C. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless-steel surfaces, use demineralized water.

3.3 GENERAL INSTALLATION REQUIREMENTS

A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.

B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of pipe system as specified in insulation system schedules.

C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.

D. Install insulation with longitudinal seams at top and bottom of horizontal runs.

E. Install multiple layers of insulation with longitudinal and end seams staggered.

F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.

G. Keep insulation materials dry during application and finishing.

H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.

I. Install insulation with least number of joints practical.

J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.

1. Install insulation continuously through hangers and around anchor attachments.
2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.

K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.

L. Install insulation with factory-applied jackets as follows:

1. Draw jacket tight and smooth.

2. Cover circumferential joints with 3-inch-wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.

    a. For below-ambient services, apply vapor-barrier mastic over staples.

4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.

M. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.

N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

P. For above-ambient services, do not install insulation to the following:

1. Vibration-control devices.
2. Testing agency labels and stamps.
3. Nameplates and data plates.
4. Cleanouts.

3.4 PENETRATIONS

A. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.

B. Insulation Installation at Aboveground Exterior Wall Penetrations:

1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant.
3. Seal jacket to wall flashing with flashing sealant.

C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.

D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.

1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.

E. Insulation Installation at Floor Penetrations:

1. Pipe: Install insulation continuously through floor penetrations.
2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

3.5 GENERAL PIPE INSULATION INSTALLATION

A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.

B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:

1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.
7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
8. For services not specified to receive a field-applied jacket except for flexible elastomeric, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
9. Label the outside insulation jacket of each union with the word "union." Match size and color of pipe labels.

C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.

3.6 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

B. Insulation Installation on Pipe Flanges:

1. Install pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install mitered sections of pipe insulation.
2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed valve covers manufactured of same material as pipe insulation when available.
2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
3. Install insulation to flanges as specified for flange insulation application.
4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.7 INSTALLATION OF MINERAL-FIBER INSULATION

A. Insulation Installation on Straight Pipes and Tubes:

1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward clinched staples at 6 inches o.c.

4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
4. Install insulation to flanges as specified for flange insulation application.

3.8 FIELD-APPLIED JACKET INSTALLATION

A. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints. Seal with manufacturer's recommended adhesive.

1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

3.9 FINISHES

A. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.

3.10 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Tests and Inspections:

1. Inspect pipe, fittings, strainers, and valves, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to three locations of straight pipe, three locations of threaded fittings, two locations of threaded strainers, three locations of threaded valves, and three locations of flanged valves for each pipe service defined in the "Piping Insulation Schedule, General" Article.

C. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

3.11 PIPING INSULATION SCHEDULE, GENERAL

A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.

B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:

1. Underground Piping.
2. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

3.12 INDOOR PIPING INSULATION SCHEDULE

A. Domestic Cold Water:

1. NPS 1 and Smaller: Insulation shall be the following:

a. Flexible Elastomeric: 1/2 inch thick.

2. NPS 1-1/4 and Larger: Insulation shall be the following:

a. Flexible Elastomeric: 1 inch thick.

3. Vapor Barrier: Required.

B. Domestic Hot Water:

1. NPS 1 and Smaller: Insulation shall be the following:

a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1/2 inch thick.

2. NPS 1-1/4 and Larger: Insulation shall be the following:

a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1-1/2 inches thick.

3. Vapor Barrier: Not Required.

C. Stormwater and Overflow:

1. All Pipe Sizes: Insulation shall be the following:

    a. Flexible Elastomeric: 1 inch thick.
    b. Vapor Barrier: Required.

D. Roof Drain and Overflow Drain Bodies:

1. All Pipe Sizes: Insulation shall be the following:

    a. Flexible Elastomeric: 1 inch thick.
    b. Vapor Barrier: Required.

3.13 INDOOR, FIELD-APPLIED JACKET SCHEDULE

A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.

B. If more than one material is listed, selection from materials listed is Contractor's option.

C. Piping, Concealed:

1. None.

D. Exposed, vertical roof leader or domestic water piping risers to 8 feet above finished floor:

1. PVC: 20 mils thick.

END OF SECTION

SECTION 220800 – COMMISSIONING OF PLUMBING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes Cx process requirements for the following plumbing systems, assemblies, and equipment:

1. Domestic hot- and cold-water piping.
2. Sanitary waste and vent piping.
3. Storm drainage piping.
4. Plumbing pumps.
5. Plumbing equipment.

B. Related Requirements:

1. Section 01 91 13 "General Commissioning Requirements" for general Cx process requirements and CxA responsibilities.
2. Section 23 08 00 “Commissioning of HVAC.”

1.2 DEFINITIONS

A. Cx: Commissioning, as defined in Section 01 91 13 "General Commissioning Requirements."

B. CxA: Commissioning Authority, as defined in Section 01 91 13 "General Commissioning Requirements."

C. IAPMO: International Association of Plumbing and Mechanical Officials.

D. IgCC: International Green Construction Code.

E. "Systems," "Assemblies," "Subsystems," "Equipment," and "Components": Where these terms are used together or separately, they shall mean "as-built" systems, assemblies, subsystems, equipment, and components.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For plumbing testing technician.

C. Construction Checklists:

1. Draft Cx plan, including draft construction checklists to be prepared by CxA under Section 01 91 13 "General Commissioning Requirements." Contractor is to review Construction Checklist in accordance with requirements in Section 01 91 13 "General

Commissioning Requirements" and ASHRAE 202 and to resolve any issues with the CxA.

D. Test Equipment and Instruments: For all test equipment and instruments to be used in conducting Cx tests by Contractor, provide the following:

1. Equipment/instrument identification number.
2. Planned Cx application or use.
3. Manufacturer, make, model, and serial number.
4. Calibration history, including certificates from agencies that calibrate the equipment and instrumentation.
5. Equipment manufacturers' proprietary instrumentation and tools. For each instrument or tool, identify the following:

    a. Instrument or tool identification number.
    b. Equipment schedule designation of equipment for which the instrument or tool is required.
    c. Manufacturer, make, model, and serial number.
    d. Calibration history, including certificates from agencies that calibrate the instrument or tool, where appropriate.

1.4 QUALITY ASSURANCE

A. Plumbing Testing Technician Qualifications: Technicians to perform plumbing Construction Checklist verification tests. Construction Checklist verification test demonstrations, Cx tests, and Cx test demonstrations shall have the following minimum qualifications:

1. Journey level or equivalent skill level with knowledge of plumbing system, electrical concepts, and building operations.

B. Testing Equipment and Instrumentation Quality and Calibration:

1. Capable of testing and measuring performance within the specified acceptance criteria.
2. Be calibrated at manufacturer's recommended intervals with current calibration tags permanently affixed to the instrument being used.
3. Be maintained in good repair and operating condition throughout duration of use on Project.
4. Be recalibrated/repaired if dropped or damaged in any way since last calibrated.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 Cx PROCESS

A. Perform Cx process for plumbing systems in accordance with:

1. IgCC, which requires compliance with ASHRAE 202.

3.2 CONSTRUCTION CHECKLISTS

A. Preliminary detailed construction checklists are to be prepared under Section 01 91 13 "General Commissioning Requirements" for each plumbing system, assembly, subsystem, equipment, and component required to be commissioned, as detailed in IgCC. Contractor performs the following:

1. Review plumbing preliminary construction checklists and provide written comments on Construction Checklist items where appropriate.
2. Return preliminary Construction Checklist with review comments within 10 days of receipt.
3. When review comments have been resolved, the CxA will provide final construction checklists marked "Approved for Use, (date)."
4. Use only construction checklists marked "Approved for Use, (date)." Mark construction checklists in the appropriate place, as indicated Project events are completed, and provide pertinent details and other information.

B. Systems Required to Be Commissioned:

1. Domestic hot-water systems and controls.
2. Domestic water piping, including the following:

    a. Domestic cold- and hot-water piping, fittings, and specialties inside the building.
    b. Pumps, motors, accessories, and controls.
    c. Sleeves and sleeve seals.
    d. Meters and gauges.
    e. General-duty and specialty valves.
    f. Hangers and supports.
    g. Vibration isolation.

3. Sanitary waste and vent piping, including the following:

    a. Gravity sewerage piping, fittings, and specialties.
    b. Drains.
    c. Sleeves and sleeve seals.
    d. Hangers and supports.

4. Storm-water piping, including the following:

    a. Drainage piping, fittings, and specialties.
    b. Drains.
    c. Sleeves and sleeve seals.
    d. Hangers and supports.

5. Plumbing fixtures, including the following:

    a. Water closets, supports and connections, supplies, and flush valves.
    b. Urinals, supports and connections, supplies, and flush valves.
    c. Lavatories, supports, supplies, drain connections, and faucets.
    d. Sinks, supports, supplies, drain connections, and faucets.
    e. Electric water coolers, supplies, and drainage connections.

3.3 Cx TESTING PREPARATION

A. Certify that plumbing systems, subsystems, and equipment have been installed, calibrated, and started and that they are operating in accordance with the Contract Documents and approved submittals.

B. Certify that plumbing system instrumentation and control systems have been completed and calibrated, point-to-point checkout has been successfully completed, and systems are operating in accordance with their design sequence of operation, Contract Documents, and approved submittals. Certify that all sensors are operating within specified accuracy and that all systems are set to and maintaining set points as required by the design documents.

C. Set systems, subsystems, and equipment into operating mode to be tested in accordance with approved test procedures (for example, normal shutdown, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).

3.4 Cx TEST CONDITIONS

A. Perform tests using design conditions, whenever possible.

1. Simulated conditions may, with approval of Architect, be imposed using an artificial load when it is impractical to test under design conditions. Before simulating conditions, calibrate testing instruments. Provide equipment to simulate loads. Set simulated conditions as directed by CxA, and document simulated conditions and methods of simulation. After tests, return configurations and settings to normal operating conditions.
2. Cx test procedures may direct that set points be altered when simulating conditions is impractical.
3. Cx test procedures may direct that sensor values be altered with a signal generator when design or simulating conditions and altering set points are impractical.

B. If tests cannot be completed because of a deficiency outside the scope of the plumbing system, document the deficiency and report it to Architect. After deficiencies are resolved, reschedule tests.

3.5 Cx TESTS COMMON TO PLUMBING SYSTEMS

A. Measure capacities and effectiveness of systems, assemblies, subsystems, equipment, and components, including operational and control functions, to verify compliance with acceptance criteria.

B. Test systems, assemblies, subsystems, equipment, and components for operating modes, interlocks, control responses, responses to abnormal or emergency conditions, and response compared to acceptance criteria.

C. Coordinate schedule with, and perform Cx activities at the direction of, CxA.

D. Comply with Construction Checklist requirements, including material verification, installation checks, startup, and performance test requirements specified in Division 22 Sections specifying plumbing systems and equipment.

E. Provide technicians, instrumentation, tools, and equipment to perform and document the following:

1. Cx Construction Checklist verification tests.
2. Cx Construction Checklist verification test demonstrations.

END OF SECTION

SECTION 221116 - DOMESTIC WATER PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Under-building slab and aboveground domestic water pipes, tubes, and fittings inside buildings.

    a. Copper tube and fittings.
    b. PEX tube and fittings.
    c. Piping joining materials.
    d. Dielectric fittings.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1. Domestic water pipes, tubes and fittings.
2. Dielectric fittings.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Provide piping layouts, including pipe size and insulation requirements, to General Contractor for inclusion in project coordination drawings. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

C. System purging and disinfecting activities report.

D. Field quality-control reports.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

B. Potable-water piping and components shall comply with NSF 14 and NSF 61 Annex G. Plastic piping components shall be marked with "NSF-pw."

C. Comply with NSF Standard 372 for low lead.

2.2 COPPER TUBE AND FITTINGS

A. Hard Copper Tube: ASTM B 88, Type L water tube, drawn temper.

B. Soft Copper Tube: ASTM B 88, Type M water tube, annealed temper.

C. Wrought-Copper, Solder-Joint Fittings: ASME B16.22, wrought-copper pressure fittings.

D. Bronze Flanges: ASME B16.24, Class 150, with solder-joint ends.

E. Copper Unions:

1. MSS SP-123.
2. Cast-copper-alloy, hexagonal-stock body.
3. Ball-and-socket, metal-to-metal seating surfaces.
4. Solder-joint or threaded ends.

F. Pressure-Seal-Joint Fittings, Copper or Bronze - Domestic Water:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Apollo Valves; a part of Aalberts Integrated Piping Systems
    b. Copper Press Brand; Merit Brass Company
    c. Elkhart Brass Mfg. Co., Inc
    d. Mueller Streamline Co.; a company of Mueller Industries
    e. NIBCO INC.
    f. Viega LLC

2. Source Limitations: Obtain pressure-seal-joint fittings, copper or bronze, from single manufacturer.
3. Housing: Copper.
4. O-Rings and Pipe Stops: EPDM.
5. Tools: Manufacturer's special tools.
6. Minimum 200 psig working-pressure rating at 250 deg F.

2.3 PEX TUBE AND FITTINGS

A. PEX Distribution System Tube Material: PEX plastic according to ASTM F 877, SDR 9 tubing.

B. Fittings for PEX Tube: ASTM F 1807, metal insert type with copper or stainless-steel crimp rings and matching PEX tube dimensions.

2.4 PIPING JOINING MATERIALS

A. Pipe-Flange Gasket Materials:

1. AWWA C110/A21.10, rubber, flat face, 1/8 inch thick or ASME B16.21, nonmetallic and asbestos free unless otherwise indicated.
2. Full-face or ring type unless otherwise indicated.

B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.

C. Solder Filler Metals: ASTM B 32, lead-free alloys.

D. Flux: ASTM B 813, water flushable.

2.5 DIELECTRIC FITTINGS

A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.

B. Dielectric Unions:

1. Standard: ASSE 1079.
2. Pressure Rating: 125 psig minimum at 180 deg F.
3. End Connections: Solder-joint copper alloy and threaded ferrous.

C. Dielectric Flanges:

1. Standard: ASSE 1079.
2. Factory-fabricated, bolted, companion-flange assembly.
3. Pressure Rating: 125 psig minimum at 180 deg F.
4. End Connections: Solder-joint copper alloy and threaded ferrous; threaded solder-joint copper alloy and threaded ferrous.

D. Dielectric-Flange Insulating Kits:

1. Nonconducting materials for field assembly of companion flanges.
2. Pressure Rating: 150 psig.
3. Gasket: Neoprene or phenolic.
4. Bolt Sleeves: Phenolic or polyethylene.
5. Washers: Phenolic with steel backing washers.

E. Dielectric Nipples:

1. Standard: IAPMO PS 66.
2. Electroplated steel nipple complying with ASTM F 1545.
3. Pressure Rating and Temperature: 300 psig at 225 deg F.
4. End Connections: Male threaded or grooved.
5. Lining: Inert and noncorrosive, propylene.

PART 3 - EXECUTION

3.1 PIPING INSTALLATION

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.

B. Install copper tubing under building slab according to CDA's "Copper Tube Handbook."

C. Install shutoff valve, hose-end drain valve, strainer, pressure gage, and test tee with valve inside the building at domestic water-service entrance. Comply with requirements for pressure gages in Section 220519 "Meters and Gages for Plumbing Piping" and with requirements for drain valves and strainers in Section 221119 "Domestic Water Piping Specialties."

D. Install shutoff valve immediately upstream of each dielectric fitting.

E. Install domestic water piping level and plumb.

F. Rough-in domestic water piping for water-meter installation according to utility company's requirements.

G. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.

H. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

I. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.

J. Install piping to permit valve servicing.

K. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than the system pressure rating used in applications below unless otherwise indicated.

L. Install piping free of sags and bends.

M. Install fittings for changes in direction and branch connections.

N. Install PEX tubing with loop at each change of direction of more than 90 degrees.

O. Install unions in copper tubing at final connection to each piece of equipment, machine, and specialty.

P. Install pressure gages on suction and discharge piping for each pump. Comply with requirements for pressure gages in Section 220519 "Meters and Gages for Plumbing Piping."

Q. Install thermometers on inlet and outlet piping from each water heater. Comply with requirements for thermometers in Section 220519 "Meters and Gages for Plumbing Piping."

R. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

S. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

T. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

3.2 JOINT CONSTRUCTION

A. Ream ends of pipes and tubes and remove burrs.

B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.

C. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Joint pipe fittings and valves as follows:

1. Apply appropriate tape or thread compound to external pipe threads.
2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.

D. Soldered Joints for Copper Tubing: Apply ASTM B 813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B 828 or CDA's "Copper Tube Handbook."

E. Flanged Joints: Select appropriate asbestos-free, nonmetallic gasket material in size, type, and thickness suitable for domestic water service. Join flanges with gasket and bolts according to ASME B31.9.

F. Pressure-Sealed Joints for Copper Tubing: Join copper tube and pressure-seal fittings with tools and procedure recommended by pressure-seal fitting manufacturer. Leave insertion marks in pipe after assembly.

G. Joints for PEX Tubing: Join according to ASTM F 1807 for metal insert and copper crimp ring fittings.

H. Joints for Dissimilar-Material Piping: Make joints using adapters compatible with materials of both piping systems.

3.3 DIELECTRIC FITTING INSTALLATION

A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.

3.4 HANGER AND SUPPORT INSTALLATION

A. Comply with requirements for pipe hanger, support products, and installation in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."

1. Vertical Piping: MSS Type 8 or 42, clamps.
2. Individual, Straight, Horizontal Piping Runs:

    a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.

3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
4. Base of Vertical Piping: MSS Type 52, spring hangers.

B. Support vertical piping and tubing at base and at each floor.

C. Rod diameter may be reduced one size for double-rod hangers, to a minimum of 3/8 inch.

D. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 3/4 and Smaller: 60 inches with 3/8-inch rod.
2. NPS 1 and NPS 1-1/4: 72 inches with 3/8-inch rod.
3. NPS 1-1/2 and NPS 2: 96 inches with 3/8-inch rod.
4. NPS 2-1/2: 108 inches with 1/2-inch rod.
5. NPS 3 to NPS 5: 10 feet with 1/2-inch rod.

E. Install supports for vertical copper tubing every 10 feet.

F. Support piping and tubing not listed in this article according to MSS SP-58 and manufacturer's written instructions.

3.5 CONNECTIONS

A. Drawings indicate general arrangement of piping, fittings, and specialties.

B. When installing piping adjacent to equipment and machines, allow space for service and maintenance.

C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.

D. Connect domestic water piping to water-service piping with shutoff valve; extend and connect to the following:

1. Water Heaters: Cold-water inlet and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.
2. Plumbing Fixtures: Cold- and hot-water-supply piping in sizes indicated, but not smaller than that required by plumbing code.
3. Equipment: Cold- and hot-water-supply piping as indicated, but not smaller than equipment connections. Provide shutoff valve and union for each connection. Use flanges instead of unions for NPS 2-1/2 and larger.

3.6 IDENTIFICATION

A. Identify system components. Comply with requirements for identification materials and installation in Section 220553 "Identification for Plumbing Piping and Equipment."

3.7 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Piping Inspections:

   a. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.
   b. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:

      1) Roughing-in Inspection: Arrange for inspection of piping before concealing or closing in after roughing in and before setting fixtures.
      2) Final Inspection: Arrange for authorities having jurisdiction to observe tests specified in "Piping Tests" Subparagraph below and to ensure compliance with requirements.

   c. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.
   d. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

2. Piping Tests:

   a. Fill domestic water piping. Check components to determine that they are not air bound and that piping is full of water.
   b. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit a separate report for each test, complete with diagram of portion of piping tested.
   c. Leave new, altered, extended, or replaced domestic water piping uncovered and unconcealed until it has been tested and approved. Expose work that was covered or concealed before it was tested.
   d. Cap and subject piping to static water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials. Isolate test source and allow it to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.

e. Repair leaks and defects with new materials, and retest piping or portion thereof until satisfactory results are obtained.
f. Prepare reports for tests and for corrective action required.

B. Domestic water piping will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.8 ADJUSTING

A. Perform the following adjustments before operation:

1. Close drain valves, hydrants, and hose bibbs.
2. Open shutoff valves to fully open position.
3. Open throttling valves to proper setting.
4. Remove plugs used during testing of piping and for temporary sealing of piping during installation.
5. Remove and clean strainer screens. Close drain valves and replace drain plugs.
6. Check plumbing specialties and verify proper settings, adjustments, and operation.

3.9 CLEANING

A. Clean and disinfect potable domestic water piping as follows:

1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction; if methods are not prescribed, use procedures described in either AWWA C651 or AWWA C652 or follow procedures described below:

a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
b. Fill and isolate system according to either of the following:

1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.
2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for three hours.

c. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
d. Repeat procedures if biological examination shows contamination.
e. Submit water samples in sterile bottles to authorities having jurisdiction.

B. Prepare and submit reports of purging and disinfecting activities. Include copies of water-sample approvals from authorities having jurisdiction.

C. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.

3.10 PIPING SCHEDULE

A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.

B. Flanges and unions may be used for aboveground piping joints unless otherwise indicated.

C. Under-building-slab, trap primer piping, shall be the following:

1. PEX tube with crimped joints.

D. Aboveground trap primer piping shall be the following:

1. Soft copper tube, ASTM B 88, Type M; cast- or wrought-copper, solder-joint fittings; and soldered joints.

E. Aboveground domestic water piping, shall be the following:

1. Hard copper tube, ASTM B 88, Type L; cast- or wrought-copper, solder-joint fittings; and soldered joints.
2. Hard copper tube, ASTM B 88, Type L; copper pressure-seal-joint fitting and pressure-sealed joints.

3.11 VALVE SCHEDULE

A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:

1. Shutoff Duty: Use ball or butterfly valves.
2. Throttling Duty: Use ball valves.
3. Drain Duty: Hose-end drain valves.

B. Use check valves to maintain correct direction of domestic water flow to and from equipment.

END OF SECTION

SECTION 221119 - DOMESTIC WATER PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Vacuum breakers.
2. Backflow preventers.
3. Balancing valves.
4. Temperature-actuated, water mixing valves.
5. Strainers.
6. Hose bibbs.
7. Wall hydrants.
8. Drain valves.
9. Water-hammer arresters.
10. Air vents.
11. Trap-seal primer systems.
12. Flexible connectors.
13. Water meters.

B. Related Requirements:

1. Section 220519 "Meters and Gages for Plumbing Piping" for thermometers, and pressure gages in domestic water piping.
2. Section 224716 "Pressure Water Coolers" for water filters for water coolers.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Shop Drawings: For domestic water piping specialties.

1. Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Operation and Maintenance Data: For domestic water piping specialties to include in emergency, operation, and maintenance manuals.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR PIPING SPECIALTIES

A. Potable-water piping and components shall comply with NSF 61 Annex G, NSF 14, and NSF 372. Mark "NSF-pw" on plastic piping components.

2.2 PERFORMANCE REQUIREMENTS

A. Minimum Working Pressure for Domestic Water Piping Specialties: 125 psig unless otherwise indicated.

2.3 VACUUM BREAKERS

A. Pipe-Applied, Atmospheric-Type Vacuum Breakers:

1. Standard: ASSE 1001.
2. Size: NPS 1/4 to NPS 3, as required to match connected piping.
3. Body: Bronze.
4. Inlet and Outlet Connections: Threaded.
5. Finish: Rough bronze or chrome plated.

B. Hose-Connection Vacuum Breakers:

1. Standard: ASSE 1011.
2. Body: Bronze, nonremovable, with manual drain.
3. Outlet Connection: Garden-hose threaded complying with ASME B1.20.7.
4. Finish: Chrome or nickel plated.

2.4 BACKFLOW PREVENTERS

A. Reduced-Pressure-Principle Backflow Preventers (BFP):

1. Basis-of-Design Product: Subject to compliance with requirements, provide Watts product scheduled on Drawings or a comparable product by one of the following:

    a. Ames Co.
    b. Conbraco Industries, Inc.
    c. Watts; a Watts Water Technologies company.
    d. Zurn Industries, LLC.

2. Standard: ASSE 1013.
3. Operation: Continuous-pressure applications.
4. Pressure Loss at Design Flow Rate: As indicated on drawings
5. Body: Bronze for NPS 2 and smaller; cast iron or steel with interior lining that complies with AWWA C550 or that is FDA approved for NPS 2-1/2 and larger.
6. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
7. Configuration: Designed for horizontal, straight-through flow.
8. Accessories:

    a. Valves NPS 2 and Smaller: Ball type with threaded ends on inlet and outlet.
    b. Valves NPS 2-1/2 and Larger: Outside-screw and yoke-gate type with flanged ends on inlet and outlet.
    c. Air-Gap Fitting: ASME A112.1.2, matching backflow-preventer connection.
    d. High Volume Flow Sensor: Integral by manufacturer; for connection to building DDC System.

9. Capacity and Characteristics: As scheduled on Drawings.

2.5 BALANCING VALVES

A. Copper-Alloy Calibrated Balancing Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Bell & Gossett; a Xylem brand
    b. IMI Hydronic Engineering Inc
    c. Nexus Valve, Inc.; Aalberts Hydronic Flow Control
    d. NIBCO INC.
    e. WATTS; A Watts Water Technologies Company

2. Type: Ball valve with two readout ports and memory-setting indicator.
3. Body: Bronze.
4. Size: Same as connected piping, but not larger than NPS 2.
5. Accessories: Meter hoses, fittings, valves, differential pressure meter, and carrying case.

B. Automatic Flow Control Balancing Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Caleffi North America
    b. IMI Hydronic Engineering Inc
    c. ThermOmegaTech

2. Flow Regulation: Plus or minus 5 percent over 95 percent of the working range.
3. Pressure Rating: 200 psig.
4. Size: NPS 2 or smaller.
5. Body: Stainless steel or brass.
6. Flow Cartridge: Stainless steel or antiscale polymer.
7. End Connections: Threaded or solder joint.

2.6 TEMPERATURE-ACTUATED, WATER MIXING VALVES

A. Water-Temperature Limiting Devices:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Acorn Controls; a Division of Morris Group International
    b. Acorn Engineering Company; a Division of Morris Group International
    c. Apollo Valves; a part of Aalberts Integrated Piping Systems
    d. Cash Acme Plumbing Products; an RWC brand
    e. POWERS; A Watts Water Technologies Company
    f. Symmons Industries, Inc
    g. Taco Comfort Solutions
    h. WATTS; A Watts Water Technologies Company
    i. Zurn Industries, LLC

2. Standard: ASSE 1070.
3. Pressure Rating: 125 psig.
4. Type: Thermostatically controlled, water mixing valve.
5. Material: Bronze body with corrosion-resistant interior components.
6. Connections: Threaded or union inlets and outlet.
7. Accessories: Check stops on hot- and cold-water supplies, and adjustable, temperature-control handle.
8. Tempered-Water Setting: 105 deg F.
9. Valve Finish: Chrome plated.

B. Manifold, Thermostatic, Water Mixing Valve Assemblies:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Acorn Engineering Company; a Division of Morris Group International
    b. Leonard Water Temperature Controls
    c. POWERS; A Watts Water Technologies Company
    d. Symmons Industries, Inc
    e. WATTS; A Watts Water Technologies Company

2. Description: Factory-fabricated, exposed-mounted, thermostatically controlled, water mixing valve assembly in two-valve parallel arrangement.
3. Large-Flow Parallel: Thermostatic, water mixing valve and downstream-pressure regulator with pressure gauges on inlet and outlet.
4. Small-Flow Parallel: Thermostatic, water mixing valve.
5. Thermostatic Mixing Valves: Comply with ASSE 1017. Include check stops on hot- and cold-water inlets and shutoff valve on outlet.
6. Water Regulator(s): Comply with ASSE 1003. Include pressure gauge on inlet and outlet.
7. Pressure Rating: 125 psig minimum unless otherwise indicated.
8. Thermostatic Mixing Valve and Water Regulator Finish: Rough bronze.
9. Piping Finish: Copper.
10. Capacity and Characteristics: As scheduled on Drawings.

2.7 STRAINERS FOR DOMESTIC WATER PIPING

A. Y-Pattern Strainers:

1. Pressure Rating: 125 psig minimum unless otherwise indicated.
2. Body: Bronze for NPS 2 and smaller; cast iron with interior lining that complies with AWWA C550 or that is FDA approved, epoxy coated for NPS 2-1/2 and larger.
3. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
4. Screen: Stainless steel with round perforations unless otherwise indicated.
5. Perforation Size:

    a. Strainers NPS 2 and Smaller: 0.033 inch.
    b. Strainers NPS 2-1/2 to NPS 4: 0.062 inch.

6. Drain: Factory-installed, hose-end drain valve.

2.8 HOSE BIBBS

A. Hose Bibbs (HB):

1. Standard: ASME A112.18.1 for sediment faucets.
2. Body Material: Bronze.
3. Seat: Bronze, replaceable.
4. Supply Connections: NPS 1/2 or NPS 3/4 threaded or solder-joint inlet.
5. Outlet Connection: Garden-hose thread complying with ASME B1.20.7.
6. Pressure Rating: 125 psig.

7. Vacuum Breaker: Integral nonremovable, drainable, hose-connection vacuum breaker complying with ASSE 1011.
8. Finish for Equipment Rooms and Service Areas: Rough bronze, or chrome or nickel plated.
9. Finish for Finished Rooms: Chrome or nickel plated.
10. Operation for Equipment Rooms and Service Areas: Wheel handle or operating key.
11. Operation for Finished Rooms: Operating key.
12. Include operating key with each operating-key hose bibb.
13. Include integral wall flange with each chrome- or nickel-plated hose bibb.

2.9 WALL HYDRANTS

A. Nonfreeze Wall Hydrants, Concealed (NFWH):

1. Standard: ASME A112.21.3M for concealed-outlet, self-draining wall hydrants.
2. Pressure Rating: 125 psig.
3. Operation: Loose key.
4. Casing and Operating Rod: Of length required to match wall thickness. Include wall clamp.
5. Inlet: NPS 3/4.
6. Outlet: Concealed, with integral vacuum breaker and garden-hose thread complying with ASME B1.20.7.
7. Box: Deep, flush mounted with cover.
8. Box and Cover Finish: Polished nickel bronze.
9. Nozzle and Wall-Plate Finish: Polished nickel bronze.
10. Operating Keys(s): Two with each wall hydrant.

B. Moderate-Climate Wall Hydrants, Narrow Wall Installation (WH):

1. Standard: ASME A112.21.3M for exposed-outlet, self-draining wall hydrants for narrow wall installation.
2. Pressure Rating: 125 psig.
3. Operation: Loose key.
4. Inlet: NPS 3/4.
5. Outlet: Exposed, with integral vacuum breaker or nonremovable hose-connection vacuum breaker comply with ASSE 1011; and garden-hose thread complying with ASME B1.20.7.
6. Nozzle and Wall-Plate Finish: Polished nickel.
7. Operating Keys(s): One with each wall hydrant.

2.10 DRAIN VALVES

A. Ball-Valve-Type, Hose-End Drain Valves:

1. Standard: MSS SP-110 for standard-port, two-piece ball valves.
2. Pressure Rating: 400-psig minimum CWP.
3. Size: NPS 3/4.
4. Body: Copper alloy.
5. Ball: Chrome-plated brass.
6. Seats and Seals: Replaceable.

7. Handle: Vinyl-covered steel.
8. Inlet: Threaded or solder joint.
9. Outlet: Threaded, short nipple with garden-hose thread complying with ASME B1.20.7 and cap with brass chain.

B. Stop-and-Waste Drain Valves:

1. Standard: MSS SP-110 for ball valves or MSS SP-80 for gate valves.
2. Pressure Rating: 200-psig minimum CWP or Class 125.
3. Size: NPS 3/4.
4. Body: Copper alloy or ASTM B 62 bronze.
5. Drain: NPS 1/8 side outlet with cap.

2.11 WATER-HAMMER ARRESTERS

A. Water-Hammer Arresters (WHA):

1. Standard: ASSE 1010 or PDI-WH 201.
2. Type: Copper tube with piston.
3. Size: ASSE 1010, Sizes AA and A through F, or PDI-WH 201, Sizes A through F.

2.12 AIR VENTS

A. Welded-Construction Automatic Air Vents:

1. Body: Stainless steel.
2. Pressure Rating: 150-psig minimum pressure rating.
3. Float: Replaceable, corrosion-resistant metal.
4. Mechanism and Seat: Stainless steel.
5. Size: NPS 3/8 minimum inlet.
6. Inlet and Vent Outlet End Connections: Threaded.

2.13 TRAP-SEAL PRIMER SYSTEMS

A. Trap-Seal Primer Systems (TPA):

1. Basis-of-Design Product: Subject to compliance with requirements, provide Precision Plumbing Products Inc. product scheduled on drawings or a comparable product.
2. Standard: ASSE 1044.
3. Piping: NPS 3/4, ASTM B 88, Type L; copper, water tubing.
4. Cabinet: Recessed- or surface-mounted, as scheduled; steel box with manufacturer's stainless-steel cover.
5. Electric Controls: 24-hour timer, solenoid valve, and manual switch for 120-V ac power.

    a. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

6. Vacuum Breaker: ASSE 1001.

7. Number Outlets: As scheduled on drawings.
8. Size Outlets: NPS 1/2.

2.14 FLEXIBLE CONNECTORS

A. Flexible connectors shall have materials suitable for system fluid. Include 175-psig minimum working-pressure rating and ends according to the following:

1. NPS 2 and Smaller: Threaded.
2. NPS 2-1/2 and Larger: Flanged.

2.15 WATER METERS

A. Water meter shall be furnished and installed by local water utility company: Greater Augusta Utility District.

B. Contractor shall provide pipe flanges and spool section at water service entrance as directed by utility company, and shall contact utility company to schedule meter installation.

C. Water meter shall be provided with pulse output for connection to building DDC system under Section 23092 "Instrumentation and Control for HVAC."

D. Remote Registration System: Direct-reading type complying with AWWA C706; modified with signal-transmitting assembly, low-voltage connecting wiring, and remote register assembly as required by utility company.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install backflow preventers in each water supply to mechanical equipment and systems and to other equipment and water systems that may be sources of contamination. Comply with authorities having jurisdiction.

1. Locate backflow preventers in same room as connected equipment or system.
2. Install drain for backflow preventers with atmospheric-vent drain connection with air-gap fitting, fixed air-gap fitting, or equivalent positive pipe separation of at least two pipe diameters in drain piping and pipe-to-floor drain. Locate air-gap device attached to or under backflow preventer. Simple air breaks are unacceptable for this application.
3. Do not install bypass piping around backflow preventers.

B. Balancing Valves: Install in locations where they can be easily adjusted. Set at indicated design flow rates.

C. Install temperature-actuated, water mixing valves with check stops or shutoff valves on inlets and with shutoff valve on outlet.

1. Install cabinet-type units recessed in or surface mounted on wall as specified.

D. Install Y-pattern strainers for water on supply side of each water pressure-reducing valve and pump.

E. Install water-hammer arresters in water piping according to PDI-WH 201.

F. Install air vents at high points of water piping.

G. Install trap-seal primer systems with outlet piping pitched down toward drain trap a minimum of 1 percent, and connect to floor-drain body, trap, or inlet fitting. Adjust system for proper flow.

H. Install water meters in accordance with requirements of municipal water department and manufacturer's written instructions. Install meter on incoming water main.

3.2 CONNECTIONS

A. Comply with requirements for ground equipment in Section 260526 "Grounding and Bonding for Electrical Systems."

B. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for electrical connections.

C. Install piping and specialties adjacent to equipment to allow service and maintenance.

3.3 LABELING AND IDENTIFYING

A. Equipment Labels and Signs: Install engraved plastic-laminate equipment label or sign on or near each of the following:

1. Reduced-pressure-principal backflow prevents.
2. Thermostatic, water mixing-valve assemblies.
3. Trap-seal primer systems.

B. Distinguish among multiple units in addition to identifying unit. Nameplates and signs are specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.4 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Test each pressure vacuum breaker and reduced-pressure-principle backflow preventer, assembly according to authorities having jurisdiction and the device's reference standard.

B. Domestic water piping specialties will be considered defective if they do not pass tests and inspections.

3.5 ADJUSTING

A. Set field-adjustable temperature set points of temperature-actuated, water mixing valves.

END OF SECTION

SECTION 221123.21 – INLINE, DOMESTIC-WATER PUMPS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. In-line, sealless centrifugal pumps.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of product. Include construction materials, rated capacities, certified performance curves with operating points plotted on curves, operating characteristics, electrical characteristics, and furnished specialties and accessories. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Provide equipment cut sheets to General Contractor for inclusion in project coordination drawings. Include all equipment dimensions, noting manufacturer's clearance requirements, as well as location and sizes of all equipment connections. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Operation and Maintenance Data: For inline, domestic-water pumps to include in operation and maintenance manuals.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Retain shipping flange protective covers and protective coatings during storage.

B. Protect bearings and couplings against damage.

C. Comply with pump manufacturer's written instructions for handling.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. UL Compliance: UL 778 for motor-operated water pumps.

C. Drinking Water System Components - Health Effects and Drinking Water System Components - Lead Content Compliance: NSF 61 and NSF 372.

2.2 IN-LINE, SEALLESS CENTRIFUGAL PUMPS

A. Description: Factory-assembled and -tested, in-line, close-coupled, canned-motor, sealless, overhung-impeller centrifugal pumps.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Flo Fab Inc.
2. Grundfos Pumps Corporation.
3. Taco Comfort Solutions.
4. WILO USA LLC - WILO Canada Inc.

C. Capacities and Characteristics: As scheduled on Drawings.

D. Pump Construction:

1. Pump and Motor Assembly: Hermetically sealed, replaceable-cartridge type with motor and impeller on common shaft and designed for installation with pump and motor shaft horizontal.
2. Minimum Working Pressure: 125 psig.
3. Maximum Continuous Operating Temperature: 220 deg F.
4. Casing: Stainless steel, with threaded or companion-flange connections.
5. Impeller: Plastic composite or stainless steel.
6. Motor: ECM.

2.3 MOTORS

A. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 22 05 13 "Common Motor Requirements for Plumbing Equipment."

1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.

2.4 CONTROLS

A. Provide controls as specified in Section 23 09 23 “Direct Digital Control (DDC) System for HVAC.”

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in for domestic-water-piping system to verify actual locations of piping connections before pump installation.

3.2 PUMP INSTALLATION

A. Comply with HI 1.4.

B. Mount pumps in orientation complying with manufacturer's written instructions.

C. Install continuous-thread hanger rods of size required to support pump weight.

1. Comply with requirements for hangers and supports specified in Section 22 05 29 "Hangers and Supports for Plumbing Piping and Equipment."

3.3 PIPING CONNECTIONS

A. Comply with requirements for piping specified in Section 22 11 16 "Domestic Water Piping." Drawings indicate general arrangement of piping, fittings, and specialties.

B. Where installing piping adjacent to inline, domestic-water pumps, allow space for service and maintenance.

C. Connect domestic-water piping to pumps. Install suction and discharge piping equal to or greater than size of pump nozzles.

D. Install shutoff valve and strainer on suction side of each pump, and check, shutoff, and throttling valves on discharge side of each pump. Install valves same size as connected piping. Comply with requirements for strainers specified in Section 22 11 19 "Domestic Water Piping Specialties." Comply with requirements for valves specified in the following:

1. Section 22 05 23.12 "Ball Valves for Plumbing Piping."
2. Section 22 05 23.14 "Check Valves for Plumbing Piping."
3. Install pressure gauge and snubber at suction of each pump and pressure gauge and snubber at discharge of each pump. Install at integral pressure-gauge tappings where provided or install pressure-gauge connectors in suction and discharge piping around pumps. Comply with requirements for pressure gauges and snubbers specified in Section 22 05 19 "Meters and Gages for Plumbing Piping."

3.4 IDENTIFICATION

A. Identify system components. Comply with requirements for identification specified in Section 22 05 53 "Identification for Plumbing Piping and Equipment" for identification of pumps.

3.5 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Tests and Inspections:

1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
2. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

C. Inline, domestic-water pump will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

3.6 STARTUP SERVICE

A. Perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.
2. Check piping connections for tightness.
3. Clean strainers on suction piping.
4. Perform the following startup checks for each pump before starting:

    a. Verify bearing lubrication.
    b. Verify that pump is free to rotate by hand and that pump for handling hot liquid is free to rotate with pump hot and cold. If pump is bound or drags, do not operate until cause of trouble is determined and corrected.
    c. Verify that pump is rotating in the correct direction.

5. Prime pump by opening suction valves and closing drains, and prepare pump for operation.

6. Start motor.
7. Open discharge valve slowly.
8. Adjust temperature settings on thermostats.

3.7 ADJUSTING

A. Adjust inline, domestic-water pumps to function smoothly, and lubricate as recommended by manufacturer.

B. Adjust initial temperature set points.

END OF SECTION

SECTION 221316 - SANITARY WASTE AND VENT AND RADON PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Hubless, cast-iron soil pipe and fittings.
2. Galvanized-steel pipe and fittings.
3. Copper tube and fittings.
4. PVC pipe and fittings.
5. Specialty pipe fittings.

B. Related Requirements:

1. Section 221429 "Sump Pumps" for submersible sump pumps.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. For adhesives, indicating VOC content. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Piping Schedule: Identify type of material, fittings and joining method to be used for each piping application and size range.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Provide piping layouts, including pipe size and insulation requirements to General Contractor for inclusion in project coordination drawings. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

C. Field quality-control reports.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Components and installation shall be capable of withstanding the following minimum working pressure unless otherwise indicated:

1. Soil, Waste, and Vent Piping: 10-foot head of water.
2. Waste, Force-Main Piping: 50 psig.

2.2 PIPING MATERIALS

A. Piping materials shall bear label, stamp, or other markings of specified testing agency.

B. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

2.3 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS

A. Pipe and Fittings: ASTM A 888 or CISPI 301.

B. Heavy-Duty, Hubless-Piping Couplings:

1. Standards: ASTM C 1277 and ASTM C 1540.
2. Description: Stainless-steel shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.

2.4 GALVANIZED-STEEL PIPE AND FITTINGS

A. Galvanized-Steel Pipe: ASTM A 53/A 53M, Type E, Standard Weight class. Include square-cut-grooved or threaded ends matching jointing method.

B. Steel Pipe Pressure Fittings:

1. Galvanized-Steel Pipe Nipples: ASTM A 733, made of ASTM A 53/A 53M or ASTM A 106/A 106M, Schedule 40, seamless steel pipe. Include ends matching joining method.
2. Malleable-Iron Unions: ASME B16.39; Class 150; hexagonal-stock body with ball-and-socket, metal-to-metal, bronze seating surface; and female threaded ends.
3. Galvanized-Gray-Iron, Threaded Fittings: ASTM B16.4, Class 125, standard pattern.

2.5 COPPER TUBE AND FITTINGS

A. Copper Type DWV Tube: ASTM B 306, drainage tube, drawn temper.

B. Copper Drainage Fittings: ASME B16.23, cast copper or ASME B16.29, wrought copper, solder-joint fittings.

C. Solder: ASTM B 32, lead free with ASTM B 813, water-flushable flux.

2.6 PVC PIPE AND FITTINGS

A. Comply with NSF 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping and "NSF-sewer" for plastic sewer piping.

B. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.

C. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.

D. Adhesive Primer: ASTM F 656.

1. Adhesive primer shall have a VOC content of 550 g/L or less.

E. Solvent Cement: ASTM D 2564.

1. Solvent cement shall have a VOC content of 510 g/L or less.

2.7 SPECIALTY PIPE FITTINGS

A. Transition Couplings:

1. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.
2. Unshielded, Nonpressure Transition Couplings:

a. Standard: ASTM C 1173.
b. Description: Elastomeric, sleeve-type, reducing or transition pattern. Include shear ring and corrosion-resistant-metal tension band and tightening mechanism on each end.
c. End Connections: Same size as and compatible with pipes to be joined.
d. Sleeve Materials:

1) For Cast-Iron Soil Pipes: ASTM C 564, rubber.
2) For Plastic Pipes: ASTM F 477, elastomeric seal or ASTM D 5926, PVC.
3) For Dissimilar Pipes: ASTM D 5926, PVC or other material compatible with pipe materials being joined.

PART 3 - EXECUTION

3.1 PIPING INSTALLATION

A. Drawing plans, schematics, and diagrams and diagrammatic in nature and indicate general location and arrangement of piping systems.

1. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations.
2. Install piping as indicated unless deviations to layout are approved on coordination drawings.

B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

E. Install piping to permit valve servicing.

F. Install piping at indicated slopes.

G. Install piping free of sags and bends.

H. Install fittings for changes in direction and branch connections.

I. Install piping to allow application of insulation.

J. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends.

1. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical.
2. Use long-turn, double Y-branch and 1/8-bend fittings if two fixtures are installed back to back or side by side with common drain pipe.

    a. Straight tees, elbows, and crosses may be used on vent lines.

3. Do not change direction of flow more than 90 degrees.
4. Use proper size of standard increasers and reducers if pipes of different sizes are connected.

    a. Reducing size of waste piping in direction of flow is prohibited.

K. Lay buried building waste piping beginning at low point of each system.

1. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream.
2. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements.
3. Maintain swab in piping and pull past each joint as completed.

L. Install soil and waste and vent piping at the following minimum slopes unless otherwise indicated:

1. Building Sanitary Waste: 2 percent downward in direction of flow for piping NPS 3 and smaller; 1 percent downward in direction of flow for piping NPS 4 and larger.
2. Horizontal Sanitary Waste Piping: 2 percent downward in direction of flow.
3. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.

M. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."

N. Install steel piping according to applicable plumbing code.

O. Install aboveground copper tubing according to CDA's "Copper Tube Handbook."

P. Install aboveground PVC piping according to ASTM D 2665.

Q. Install underground PVC piping according to ASTM D 2321.

R. Plumbing Specialties:

1. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers in sanitary waste gravity-flow piping.

    a. Install cleanout fitting with closure plug inside the building in sanitary drainage force-main piping.
    b. Comply with requirements for cleanouts specified in Section 221319 "Sanitary Waste Piping Specialties."

2. Install drains in sanitary waste gravity-flow piping.

    a. Comply with requirements for drains specified in Section 221319 "Sanitary Waste Piping Specialties."

S. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.

T. Install sleeves for piping penetrations of walls, ceilings, and floors.

1. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

U. Install sleeve seals for piping penetrations of concrete walls and slabs.

1. Comply with requirements for sleeve seals specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

V. Install escutcheons for piping penetrations of walls, ceilings, and floors.

1. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

3.2 JOINT CONSTRUCTION

A. Join hubless, cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-piping coupling joints.

B. Ream ends of pipes and tubes and remove burrs.

C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

D. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1.

1. Cut threads full and clean using sharp dies.
2. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:

    a. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
    b. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
    c. Do not use pipe sections that have cracked or open welds.

E. Join copper tube and fittings with soldered joints according to ASTM B 828. Use ASTM B 813, water-flushable, lead-free flux and ASTM B 32, lead-free-alloy solder.

F. Plastic, Nonpressure-Piping, Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
2. PVC Piping: Join according to ASTM D 2855 and ASTM D 2665 appendixes.

G. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.

3.3 SPECIALTY PIPE FITTING INSTALLATION

A. Transition Couplings:

1. Install transition couplings at joints of piping with small differences in ODs.

3.4 VALVE INSTALLATION

A. Comply with requirements in Section 220523.12 "Ball Valves for Plumbing Piping" and Section 220523.14 "Check Valves for Plumbing Piping," for general-duty valve installation requirements.

B. Shutoff Valves:

1. Install shutoff valve on each sump pump discharge.
2. Install full-port ball valve for piping NPS 2 and smaller.

C. Check Valves: Install swing check valve, between pump and shutoff valve, on each sewage or sump pump discharge.

3.5 HANGER AND SUPPORT INSTALLATION

A. Comply with requirements for pipe hanger and support devices and installation specified in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."

B. Support horizontal piping and tubing within 12 inches of each fitting, valve, and coupling.

C. Support vertical piping and tubing at base and at each floor.

D. Rod diameter may be reduced one size for double-rod hangers, with 3/8-inch minimum rods.

E. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
2. NPS 3: 60 inches with 1/2-inch rod.
3. NPS 4 and NPS 5: 60 inches with 5/8-inch rod.
4. NPS 6 and NPS 8: 60 inches with 3/4-inch rod.
5. Spacing for 10-foot lengths may be increased to 10 feet. Spacing for fittings is limited to 60 inches.

F. Install supports for vertical cast-iron soil piping every 15 feet.

G. Install hangers for steel piping with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 1-1/4: 84 inches with 3/8-inch rod.
2. NPS 1-1/2: 108 inches with 3/8-inch rod.
3. NPS 2: 10 feet with 3/8-inch rod.

H. Install supports for vertical steel piping every 10 feet.

I. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 1-1/4: 72 inches with 3/8-inch rod.
2. NPS 1-1/2 and NPS 2: 96 inches with 3/8-inch rod.
3. NPS 2-1/2: 108 inches with 1/2-inch rod.

J. Install supports for vertical copper tubing every 10 feet.

K. Install hangers for PVC piping with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 1-1/2 and NPS 2: 48 inches with 3/8-inch rod.

2. NPS 3: 48 inches with 1/2-inch rod.
3. NPS 4 and NPS 5: 48 inches with 5/8-inch rod.
4. NPS 6 and NPS 8: 48 inches with 3/4-inch rod.

L. Install supports for vertical PVC piping every 48 inches.

M. Support piping and tubing not listed above according to MSS SP-58 and manufacturer's written instructions.

3.6 CONNECTIONS

A. Drawings indicate general arrangement of piping, fittings, and specialties.

B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.

C. Connect waste and vent piping to the following:

1. Plumbing Fixtures: Connect waste piping in sizes indicated, but not smaller than required by plumbing code.
2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
3. Plumbing Specialties: Connect waste and vent piping in sizes indicated, but not smaller than required by plumbing code.
4. Install test tees (wall cleanouts) in conductors near floor and floor cleanouts with cover flush with floor.
5. Comply with requirements for cleanouts and drains specified in Section 221319 "Sanitary Waste Piping Specialties" and in Section 221319.13 "Sanitary Drains."
6. Equipment: Connect waste piping as indicated.

    a. Provide shutoff valve if indicated and union for each connection.
    b. Use flanges instead of unions for connections NPS 2-1/2 and larger.

D. Connect force-main piping to the following:

1. Sewage Sump Pumps: To sewage pump discharge.

E. Where installing piping adjacent to equipment, allow space for service and maintenance of equipment.

3.7 IDENTIFICATION

A. Identify exposed sanitary waste and vent piping.

B. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.8 FIELD QUALITY CONTROL

A. During installation, notify authorities having jurisdiction at least 72 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.

1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.

B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.

C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

D. Test sanitary waste and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:

1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired.

    a. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.

2. Leave uncovered and unconcealed new, altered, extended, or replaced waste and vent piping until it has been tested and approved.

    a. Expose work that was covered or concealed before it was tested.

3. Roughing-in Plumbing Test Procedure: Test waste and vent piping except outside leaders on completion of roughing-in.

    a. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water.
    b. From 15 minutes before inspection starts to completion of inspection, water level must not drop.
    c. Inspect joints for leaks.

4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight.

    a. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg.
    b. Use U-tube or manometer inserted in trap of water closet to measure this pressure.
    c. Air pressure must remain constant without introducing additional air throughout period of inspection.
    d. Inspect plumbing fixture connections for gas and water leaks.

5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
6. Prepare reports for tests and required corrective action.

E. Test force-main piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:

1. Leave uncovered and unconcealed new, altered, extended, or replaced force-main piping until it has been tested and approved.

    a. Expose work that was covered or concealed before it was tested.

2. Cap and subject piping to static-water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials.

    a. Isolate test source and allow to stand for four hours.
    b. Leaks and loss in test pressure constitute defects that must be repaired.

3. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
4. Prepare reports for tests and required corrective action.

3.9 CLEANING AND PROTECTION

A. Clean interior of piping. Remove dirt and debris as work progresses.

B. Protect sanitary waste and vent piping during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.

C. Place plugs in ends of uncompleted piping at end of day and when work stops.

D. Exposed PVC Piping: Protect plumbing vents exposed to sunlight with two coats of water-based latex paint.

E. Repair damage to adjacent materials caused by waste and vent piping installation.

3.10 PIPING SCHEDULE

A. Flanges and unions may be used on aboveground pressure piping unless otherwise indicated.

B. Aboveground, soil and waste piping shall be the following:

1. Hubless, cast-iron soil pipe and fittings; heavy-duty hubless-piping couplings; and coupled joints.

C. Aboveground, vent piping shall be the following:

1. Hubless, cast-iron soil pipe and fittings; heavy-duty hubless-piping couplings; and coupled joints.

D. Underground, soil, waste, and vent piping shall be the following:

1. Hubless, cast-iron soil pipe and fittings; heavy-duty hubless-piping couplings; and coupled joints.

2. Solid-Wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
3. Dissimilar Pipe-Material Couplings: , nonpressure transition couplings.

E. Aboveground sanitary-sewage force mains shall be the following:

1. Galvanized-steel pipe, pressure fittings, and threaded joints.

F. Aboveground indirect waste piping NPS 2 and smaller, shall be the following:

1. Copper type DWV tube, copper drainage fittings, and soldered joints.

G. Radon vent piping, aboveground and underground, shall be the following:

1. Solid-wall PVC pipe, PVC socket fittings, and solvent cemented joints.

END OF SECTION

SECTION 221319 - SANITARY WASTE PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Cleanouts.
2. Miscellaneous sanitary drainage piping specialties.

B. Related Requirements:

1. Section 221423 "Storm Drainage Piping Specialties" for roof drains.
2. Section 221319.13 “Sanitary Drains” for floor drains, shower drains, and floor sinks.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. Include rated capacities, operating characteristics, and accessories. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTIONS

A. Sanitary waste piping specialties shall bear label, stamp, or other markings of specified testing agency.

B. Comply with NSF 14 for plastic sanitary waste piping specialty components.

2.2 CLEANOUTS

A. Cast-Iron Exposed Cleanouts (CO):

1. Standard: ASME A112.36.2M.
2. Size: Same as connected drainage piping

3. Body Material: Hubless, cast-iron soil pipe test tee as required to match connected piping.
4. Closure: Countersunk, brass plug.
5. Closure Plug Size: Same as or not more than one size smaller than cleanout size.

B. Cast-Iron Exposed Floor Cleanouts (FCO):

1. Standard: ASME A112.36.2M.
2. Size: Same as connected branch.
3. Type: Threaded, adjustable housing.
4. Body or Ferrule: Cast iron.
5. Closure: Brass plug with tapered threads.
6. Adjustable Housing Material: Cast iron with threads.
7. Frame and Cover Material and Finish: Polished bronze.
8. Frame and Cover Shape: Round.
9. Top Loading Classification: Light Duty.
10. Riser: ASTM A 74, Service class, cast-iron drainage pipe fitting and riser to cleanout.

C. Cast-Iron Wall Cleanouts (WCO):

1. Standard: ASME A112.36.2M. Include wall access.
2. Size: Same as connected drainage piping.
3. Body: As required to match connected piping.
4. Closure Plug:

   a. Brass.
   b. Countersunk head.
   c. Drilled and threaded for cover attachment screw.
   d. Size: Same as or not more than one size smaller than cleanout size.

5. Wall Access: Round, flat, chrome-plated brass or stainless steel cover plate with screw.

2.3 MISCELLANEOUS SANITARY DRAINAGE PIPING SPECIALTIES

A. Open Hub Drains:

1. Description: Shop or field fabricate from ASTM A74, Service Class, hubless, cast-iron soil-pipe fittings. Include P-trap, hubless riser section; and where required, increase fitting joined with CISPI hubless-piping coupling.
2. Size: Same as connected waste-piping with increaser fitting of size indicated on plans.

B. Deep-Seal Traps:

1. Description: Cast-iron or bronze casting, with inlet and outlet matching connected piping and cleanout trap-seal primer valve connection.
2. Size: Same as connected waste piping.

   a. NPS 2: 4-inch-minimum water seal.
   b. NPS 2-1/2 and Larger: 5-inch-minimum water seal.

C. Floor-Drain, Trap-Seal Primer Fittings:

1. Description: Cast iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
2. Size: Same as floor drain outlet with NPS 1/2 side inlet.

D. Air-Gap Fittings:

1. Standard: ASTM A112.1.2, for fitting designed to ensure fixed, positive air gap between installed inlet and outlet piping.
2. Body: Bronze or cast iron.
3. Inlet: Opening in top of body.
4. Outlet: Larger than inlet.
5. Size: Same as connected waste piping and with inlet large enough for associated indirect waste piping.

E. Drainage Outlet Boxes (DOB):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. LSP Products Group
   b. Oatey Co.
   c. Sioux Chief Manufacturing Company, Inc.
   d. IPS Corporation

2. Mounting: Recessed.
3. Material and Finish: Plastic box and faceplate.
4. Drain Size: 2-inch.
5. Accessories: Indirect waste adapter to provide air gap for indirect waste or condensate drains.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install cleanouts in aboveground piping and building drain piping according to the following, unless otherwise indicated:

1. Size same as drainage piping up to NPS 4. Use NPS 4 for larger drainage piping unless larger cleanout is indicated.
2. Locate at each change in direction of piping greater than 45 degrees.
3. Locate at minimum intervals of 50 feet for piping NPS 4 and smaller and 100 feet for larger piping.
4. Locate at base of each vertical soil and waste stack.

B. For floor cleanouts for piping below floors, install cleanout deck plates with top flush with finished floor.

C. For cleanouts located in concealed piping, install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall.

D. Install roof flashing assemblies on sanitary stack vents and vent stacks that extend through roof. Comply with requirements in Section 076200 "Sheet Metal Flashing and Trim."

E. Assemble open drain fittings and install with top of hub 1 inch above floor or as indicated on plans.

F. Install deep-seal traps on floor drains and other waste outlets, if indicated.

G. Install floor-drain, trap-seal primer fittings on inlet to floor drains that require trap-seal primer connection.

1. Exception: Fitting may be omitted if trap has trap-seal primer connection.
2. Size: Same as floor drain inlet.

H. Install air-gap fittings on draining-type backflow preventers and on indirect-waste piping discharge into sanitary drainage system.

I. Outlet Boxes: Install boxes recessed in wall or surface mounted on wall. Install 1-1/2-by-3-1/2-inch fire-retardant-treated-wood blocking, wall reinforcement between studs. Comply with requirements for fire-retardant-treated-wood blocking in Section 061000 "Rough Carpentry."

J. Install sleeve and sleeve seals with each riser and stack passing through floors with waterproof membrane.

K. Install traps on plumbing specialty drain outlets. Omit traps on indirect wastes unless trap is indicated.

3.2 CONNECTIONS

A. Comply with requirements in Section 221316 "Sanitary Waste and Vent and Radon Piping" for piping installation requirements. Drawings indicate general arrangement of piping, fittings, and specialties.

B. Install piping adjacent to equipment to allow service and maintenance.

3.3 FLASHING INSTALLATION

A. Flashing shall be provided by Section 076200 "Sheet Metal Flashing and Trim."

3.4 PROTECTION

A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.

B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION

SECTION 221319.13 - SANITARY DRAINS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Floor drains.
2. Shower drains.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 DRAIN ASSEMBLIES

A. Sanitary drains shall bear label, stamp, or other markings of specified testing agency.

2.2 FLOOR DRAINS

A. Cast-Iron Floor Drains (FD):

1. Basis-of-Design Product: Subject to compliance with requirements, provide Zurn Industries, LLC's product scheduled on Drawings or a comparable product by one of the following:

a. Josam Company.
b. MIFAB, Inc.
c. Smith, Jay R. Mfg. Co.
d. Tyler Pipe; a subsidiary of McWane Inc.
e. Watts; a Watts Water Technologies company.

2. Standard: ASME A112.6.3.

3. Pattern: Floor drain.
4. Body Material: Gray iron.
5. Anchor Flange: Required.
6. Clamping Device: Not required.
7. Outlet: Bottom.
8. Sediment Bucket: Provide where scheduled on Drawings.
9. Top or Strainer Material: Nickel bronze.
10. Top Shape: As scheduled on Drawings.
11. Dimensions of Top or Strainer: As scheduled on Drawings.
12. Top Loading Classification: Light Duty.
13. Funnel: As scheduled on Drawings.
14. Trap Pattern: Standard P-trap unless otherwise noted on Drawings.
15. Trap Features: Trap-seal primer valve drain connection.

2.3 SHOWER DRAINS

A. Cast-Iron Shower Drains (SH):

1. Basis-of-Design Product: Subject to compliance with requirements, provide Zurn Industries, LLC's product scheduled on Drawings or comparable product by one of the following:

    a. Josam Company.
    b. MIFAB, Inc.
    c. Smith, Jay R. Mfg. Co.
    d. Tyler Pipe; a subsidiary of McWane Inc.
    e. Watts; a Watts Water Technologies company.

2. Standard: ASME A112.6.3.
3. Pattern: Floor drain.
4. Body Material: Gray iron.
5. Anchor Flange: Required.
6. Clamping Device: Not required.
7. Outlet: Bottom.
8. Sediment Bucket: Not required.
9. Top or Strainer Material: Stainless steel.
10. Top Shape: Round.
11. Dimensions of Top or Strainer: As scheduled on Drawings.
12. Top Loading Classification: Light Duty.
13. Trap Features: Trap-seal primer valve drain connection.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install floor drains and shower drains at low points of surface areas to be drained. Set grates of drains flush with finished floor, unless otherwise indicated.

1. Position drains for easy access and maintenance.

2. Set floor drains below elevation of surrounding finished floor to allow floor drainage.
3. Set with grates depressed according to the following drainage area radii:

    a. Radius, 30 Inches or Less: Equivalent to 1 percent slope, but not less than 1/4-inch total depression.
    b. Radius, 30 to 60 Inches: Equivalent to 1 percent slope.
    c. Radius, 60 Inches or Larger: Equivalent to 1 percent slope, but not greater than 1-inch total depression.

4. Install individual traps for floor drains connected to sanitary building drain, unless otherwise indicated.

3.2 CONNECTIONS

A. Comply with requirements in Section 221316 "Sanitary Waste and Vent and Radon Piping" for piping installation requirements. Drawings indicate general arrangement of piping, fittings, and specialties.

B. Comply with requirements in Section 221319 "Sanitary Waste Piping Specialties" for cleanouts and miscellaneous sanitary drainage piping specialties.

C. Install piping adjacent to equipment to allow service and maintenance.

3.3 PROTECTION

A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.

B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION

SECTION 221329 - SANITARY SEWERAGE PUMPS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Oil-sensing sump pump and controller.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Shop Drawings:

1. Include plans, elevations, sections, and attachment details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.

1.3 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For pumps and controls, to include in operation and maintenance manuals.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Retain shipping flange protective covers and protective coatings during storage.

B. Protect bearings and couplings against damage.

C. Comply with manufacturer's written instructions for handling.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. UL Compliance: Comply with UL 778 for motor-operated water pumps.

2.2 SUBMERSIBLE EFFLUENT PUMPS

A. Submersible, Fixed-Position, Single-Seal, Oil Minder Oil Effluent Pumps (SP-1):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. GRUNDFOS CBS Inc.
    b. Liberty Pumps
    c. Stancor, Inc
    d. Zoeller Company

2. Description: Factory-assembled and -tested effluent-pump unit that allows water to be automatically pumped from elevator pit, with controls to shut-down pump and alarm if it senses oil is in the pit.
3. Pump Type: Submersible, end-suction, single-stage, close-coupled, overhung-impeller, centrifugal effluent pump as defined in HI 1.1-1.2 and HI 1.3.
4. Pump Casing: Cast iron, with open inlet, legs that elevate pump to permit flow into impeller, and vertical discharge for piping connection.
5. Pump and Motor Shaft: Stainless steel, with factory-sealed, grease-lubricated ball bearings.
6. Seal: Mechanical.
7. Motor: Hermetically sealed, capacitor-start type; with built-in overload protection; lifting eye or lug; and three-conductor, waterproof power cable of length required and with grounding plug and cable-sealing assembly for connection at pump.
8. Controls:

    a. Industrial-grade switch(es) with internal 20A relay and type 304 stainless steel sensor probes.
    b. Liquid/oil sensor that differentiates and indicates the presence of oil and/or water under high water conditions.
    c. Alarm Panel:

        1) High-oil-level alarm.
        2) High-water-level alarm.
        3) Audible and visual alarms for each alarm condition.
        4) Dry contacts for remote monitoring of oil, water, and high liquid condition.

    d. Control Panel:

1) Simplex.
2) Enclosure: NEMA 250, Type 4X.
3) Green pump run light; power on light.

9. Control-Interface Features:

a. Building Automation System Interface: Auxiliary contacts in pump controls for interface to building automation system and capable of providing the following:

1) On-off status of pump.
2) Alarm status.

2.3 MOTORS

A. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 220500 "Common Work Results for Plumbing."

1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.

B. Motors for submersible pumps shall be hermetically sealed.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in for plumbing piping to verify actual locations of existing drainage piping connections before sewage pump installation.

3.2 INSTALLATION

A. Pump Installation Standards:

1. Comply with HI 1.4 for installation of centrifugal pumps.

B. Wiring Method: Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

3.3 CONNECTIONS

A. Comply with requirements for piping specified in Section 221316 "Sanitary Waste and Vent Piping." Drawings indicate general arrangement of piping, fittings, and specialties.

B. Where installing piping adjacent to equipment, allow space for service and maintenance.

3.4 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Perform each visual and mechanical inspection.
2. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
3. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

B. Pumps and controls will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports.

3.5 STARTUP SERVICE

A. Perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.

3.6 ADJUSTING

A. Adjust pumps to function smoothly, and lubricate as recommended by manufacturer.

B. Adjust control set points.

3.7 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain controls and pumps.

END OF SECTION

SECTION 221413 - STORM DRAINAGE PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Hubless, cast-iron soil pipe and fittings
2. PVC pipe and fittings.
3. Specialty pipe fittings.

1.3 PERFORMANCE REQUIREMENTS

A. Components and installation shall be capable of withstanding the following minimum working pressure unless otherwise indicated:

1. Storm Drainage Piping: 10-foot head of water.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. For adhesives, indicating VOC content. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Piping Schedule: Identify type of material, fittings and joining method to be used for each piping application and size range.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Provide piping layouts, including pipe size and insulation requirements to General Contractor for inclusion in project coordination drawings. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

C. Field quality-control reports.

1.6 QUALITY ASSURANCE

A. Piping materials shall bear label, stamp, or other markings of specified testing agency.

B. Comply with NSF/ANSI 14, "Plastics Piping System Components and Related Materials," for plastic piping components. Include marking with "NSF-drain" for plastic drain piping and "NSF-sewer" for plastic sewer piping.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

2.2 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS

A. Pipe and Fittings: ASTM A 888 or CISPI 301. Marked with CISPI collective trademark and NSF certification mark.

B. CISPI, Hubless-Piping Couplings:

1. Standards: ASTM C 1277 and CISPI 310.
2. Description: Stainless-steel corrugated shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.
3. Couplings shall bear CISPI collective trademark.

2.3 PVC PIPE AND FITTINGS

A. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.

B. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.

C. Adhesive Primer: ASTM F 656.

1. Adhesive primer shall have a VOC content of 550 g/L or less.

D. Solvent Cement: ASTM D 2564.

1. Solvent cement shall have a VOC content of 510 g/L or less.

2.4 SPECIALTY PIPE FITTINGS

A. Transition Couplings:

1. General Requirements: Fitting or device for joining piping with small differences in ODs or of different materials. Include end connections same size as and compatible with pipes to be joined.
2. Fitting-Type Transition Couplings: Manufactured piping coupling or specified-piping-system fitting.
3. Unshielded, Nonpressure Transition Couplings:

    a. Standard: ASTM C 1173.
    b. Description: Elastomeric, sleeve-type, reducing or transition pattern. Include shear ring and corrosion-resistant-metal tension band and tightening mechanism on each end.
    c. Sleeve Materials:

        1) For Cast-Iron Soil Pipes: ASTM C 564, rubber.
        2) For Plastic Pipes: ASTM F 477, elastomeric seal or ASTM D 5926, PVC.
        3) For Dissimilar Pipes: ASTM D 5926, PVC or other material compatible with pipe materials being joined.

PART 3 - EXECUTION

3.1 PIPING INSTALLATION

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations from layout are approved on coordination drawings.

B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

E. Install piping to permit valve servicing.

F. Install piping at indicated slopes.

G. Install piping free of sags and bends.

H. Install fittings for changes in direction and branch connections.

I. Install piping to allow application of insulation.

J. Make changes in direction for storm drainage piping using appropriate branches, bends, and long-sweep bends. Do not change direction of flow more than 90 degrees. Use proper size of standard increasers and reducers if pipes of different sizes are connected. Reducing size of drainage piping in direction of flow is prohibited.

K. Lay buried building storm drainage piping beginning at low point of each system. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements. Maintain swab in piping and pull past each joint as completed.

L. Install storm drainage piping at the following minimum slopes unless otherwise indicated:

1. Building Storm Drain: 2 percent downward in direction of flow for piping NPS 3 and smaller; 1 percent downward in direction of flow for piping NPS 4 and larger.
2. Horizontal Branch Storm Drain: 2 percent downward in direction of flow unless otherwise indicated on plans.

M. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."

N. Install underground PVC piping according to ASTM D 2321.

O. Plumbing Specialties:

1. Install cleanouts at floor or grade and extend to where building storm drains connect to building storm sewers in storm drainage gravity-flow piping. Comply with requirements for cleanouts specified in Section 221423 "Storm Drainage Piping Specialties."
2. Install drains in storm drainage gravity-flow piping. Comply with requirements for drains specified in Section 221423 "Storm Drainage Piping Specialties."

P. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.

Q. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

R. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

S. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

3.2 JOINT CONSTRUCTION

A. Hubless, Cast-Iron Soil Piping Coupled Joints: Join according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-piping coupling joints.

B. Plastic, Nonpressure-Piping, Solvent-Cemented Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
2. PVC Piping: Join according to ASTM D 2855 and ASTM D 2665 Appendices.

3.3 SPECIALTY PIPE FITTING INSTALLATION

A. Transition Couplings:

1. Install transition couplings at joints of piping with small differences in ODs.
2. In Drainage Piping: Unshielded, nonpressure transition couplings.

3.4 HANGER AND SUPPORT INSTALLATION

A. Comply with requirements for pipe hanger and support devices and installation specified in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."

1. Install carbon-steel pipe hangers for horizontal piping in noncorrosive environments.
2. Install carbon-steel pipe support clamps for vertical piping in noncorrosive environments.
3. Vertical Piping: MSS Type 8 or Type 42, clamps.
4. Individual, Straight, Horizontal Piping Runs:

    a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.

5. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
6. Base of Vertical Piping: MSS Type 52, spring hangers.

B. Support horizontal piping and tubing within 12 inches of each fitting and coupling.

C. Support vertical piping and tubing at base and at each floor.

D. Rod diameter may be reduced one size for double-rod hangers, with 3/8-inch minimum rods.

E. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
2. NPS 3: 60 inches with 1/2-inch rod.
3. NPS 4 and NPS 5: 60 inches with 5/8-inch rod.
4. NPS 6 and NPS 8: 60 inches with 3/4-inch rod.
5. Spacing for 10-foot pipe lengths may be increased to 10 feet. Spacing for fittings is limited to 60 inches.

F. Install supports for vertical cast-iron soil piping every 15 feet.

G. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.

3.5 CONNECTIONS

A. Drawings indicate general arrangement of piping, fittings, and specialties.

B. Connect interior storm drainage piping to exterior storm drainage piping. Use transition fitting to join dissimilar piping materials.

C. Connect storm drainage piping to roof drains and storm drainage specialties.

1. Install test tees (wall cleanouts) in conductors near floor, and floor cleanouts with cover flush with floor.
2. Comply with requirements specified in Section 221423 "Storm Drainage Piping Specialties."

D. Where installing piping adjacent to equipment, allow space for service and maintenance of equipment.

3.6 IDENTIFICATION

A. Identify exposed storm drainage piping. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.7 FIELD QUALITY CONTROL

A. During installation, notify authorities having jurisdiction at least 72 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.

1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in.
2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.

B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.

C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

D. Test storm drainage piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:

1. Test for leaks and defects in new piping. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
2. Leave uncovered and unconcealed new storm drainage piping until it has been tested and approved. Expose work that was covered or concealed before it was tested.
3. Test Procedure: Test storm drainage piping on completion of roughing-in. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water. From 15 minutes before inspection starts until completion of inspection, water level must not drop. Inspect joints for leaks.
4. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
5. Prepare reports for tests and required corrective action.

3.8 CLEANING AND PROTECTION

A. Clean interior of piping. Remove dirt and debris as work progresses.

B. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.

C. Place plugs in ends of uncompleted piping at end of day and when work stops.

3.9 PIPING SCHEDULE

A. Aboveground storm drainage piping shall be the following:

1. Hubless, cast-iron soil pipe and fittings; CISPI, hubless-piping couplings; and coupled joints.

B. Underground storm drainage piping shall be the following:

1. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.

END OF SECTION

SECTION 221423 - STORM DRAINAGE PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. General-purpose roof drains.
2. Miscellaneous storm drainage piping specialties.
3. Cleanouts.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Provide drain cut sheets, including dimensions, to General Contractor for inclusion in project coordination drawings. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

1.5 QUALITY ASSURANCE

A. Drainage piping specialties shall bear label, stamp, or other markings of specified testing agency.

PART 2 - PRODUCTS

2.1 GENERAL-PURPOSE ROOF DRAINS

A. Cast-Iron, Medium-Sump, Roof Drains and Overflow Roof Drains (RD-1):

1. Basis-of-Design Product: Subject to compliance with requirements, provide Zurn Plumbing Products Group product scheduled on drawings or comparable product by available manufacturers offering products that may be incorporated into the Work which include, but are not limited to, the following:

    a. Josam Company.
    b. MIFAB, Inc.
    c. Smith, Jay R. Mfg. Co.
    d. Tyler Pipe.
    e. Watts; a Watts Water Technologies company.

2. Standard: ASME A112.6.4, for general-purpose roof drains.
3. Body Material: Cast iron.
4. Dimension of Body: 12-inch diameter.
5. Combination Flashing Ring and Gravel Stop: Required.
6. Outlet: Bottom. Or side.
7. Extension Collars: Adjustable required to suit roof insulation thickness.
8. Underdeck Clamp: Required.
9. Dome Material: Aluminum or cast iron, 4 inches high minimum.
10. Deck Plate: To accommodate roof drain and overflow drain on common plate.

2.2 MISCELLANEOUS STORM DRAINAGE PIPING SPECIALTIES

A. Metal Overflow Downspout Nozzles: (ODN).

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Jay R. Smith Mfg Co; a division of Morris Group International.
    b. Josam Company.
    c. WATTS; A Watts Water Technologies Company.
    d. Wade; a subsidiary of McWane Inc.
    e. Zurn Industries, LLC.

2. Description: Nozzle with wall flange and mounting holes to cover rough opening and serve as anchor.
3. Size: Same as connected storm drainage piping.
4. Material: Cast bronze or nickel bronze nozzle and flange.
5. Piping Connection Type: No-hub or slip on.
6. Finish: Nickel Bronze.
7. Opening Protection: Birdscreen.

2.3 CLEANOUTS

A. Cast-Iron Exposed Floor Cleanouts (FCO):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Jay R. Smith Mfg. Co.
b. Josam Company.
c. Tyler Pipe; a subsidiary of McWane Inc.
d. Watts; a Watts Water Technologies company.
e. Zurn Industries, LLC.

2. Standard: ASME A112.36.2M, for threaded, adjustable housing cleanouts.
3. Size: Same as connected branch.
4. Type: Threaded, adjustable housing.
5. Body or Ferrule Material: Cast iron.
6. Clamping Device: Not required.
7. Closure: Bronze or brass plug.
8. Adjustable Housing Material: Cast iron with threads.
9. Frame and Cover Material and Finish: Nickel-bronze, copper alloy.
10. Frame and Cover Shape: Round.
11. Top-Loading Classification: Light Duty.
12. Riser: ASTM A 74, Service class, cast-iron drainage pipe fitting and riser to cleanout.

B. Exposed Cleanouts (CO):

1. Standard: ASME A112.36.2M and ASTM A 74, ASTM A 888, or CISPI 301, for cleanout test tees.
2. Size: Same as connected drainage piping.
3. Body Material: No-hub cast-iron soil-pipe test tee; as required to match connected piping.
4. Closure Plug: Raised head, brass or plastic plug.
5. Closure Plug Size: Same as or not more than one size smaller than cleanout size.

C. Cast-Iron Wall Cleanouts (WCO):

1. Standard: ASME A112.36.2M, for cleanouts. Include wall access.
2. Size: Same as connected drainage piping.
3. Body Material: No-hub cast-iron soil-pipe test tee; or PVC as required to match connected piping.
4. Closure: Countersunk or raised-head, drilled-and-threaded brass or plastic plug for cover attachment screw.
5. Closure Plug Size: Same as or not more than one size smaller than cleanout size.
6. Wall Access: Round, flat, chrome-plated brass or stainless-steel cover plate with screw.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install roof drains at low points of roof areas according to roof membrane manufacturer's written installation instructions.

1. Install flashing collar or flange of roof drain to prevent leakage between drain and adjoining roofing. Maintain integrity of waterproof membranes where penetrated.
2. Position roof drains for easy access and maintenance.

B. Install downspout nozzles at exposed bottom of conductors where they spill onto grade.

C. Install cleanouts in aboveground piping and building drain piping according to the following instructions unless otherwise indicated:

1. Use cleanouts the same size as drainage piping up to NPS 4. Use NPS 4 for larger drainage piping unless larger cleanout is indicated.
2. Locate cleanouts at each change in direction of piping greater than 45 degrees.
3. Locate cleanouts at minimum intervals of 50 feet for piping NPS 4 and smaller and 100 feet for larger piping.
4. Locate cleanouts at base of each vertical storm drainage stack.

D. For floor cleanouts for piping below floors, install cleanout deck plates with top flush with finished floor.

E. For cleanouts located in concealed piping, install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall.

F. Install exposed cleanouts in vertical conductors and near floor.

G. Install wall cleanouts in vertical conductors. Install access door in wall if indicated.

3.2 CONNECTIONS

A. Comply with requirements for piping specified in Section 221413 "Storm Drainage Piping." Drawings indicate general arrangement of piping, fittings, and specialties.

3.3 PROTECTION

A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.

B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION

SECTION 223300 - ELECTRIC, DOMESTIC-WATER HEATERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Commercial, heat pump, storage, electric, domestic-water heaters.
2. Domestic-water heater accessories.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is to be described, clearly annotate which product(s) is to be supplied.

1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

C. Shop Drawings:

1. Include diagrams for power, signal, and control wiring.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Equipment room drawing or BIM model, drawn to scale, on which the items described in this Section are shown and coordinated with all building trades. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

C. Product Certificates: For each type of commercial, electric, domestic-water heater.

D. Domestic-Water Heater Labeling: Certified and labeled by testing agency acceptable to authorities having jurisdiction.

E. Source quality-control reports.

F. Field quality-control reports.

G. Sample Warranty: For special warranty.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For electric, domestic-water heaters to include emergency, operation, and maintenance manuals.

1.5 COORDINATION

A. Coordinate sizes and locations of concrete bases with actual equipment provided.

1.6 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of electric, domestic-water heaters that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures including storage tank and supports.
b. Faulty operation of controls.
c. Deterioration of metals, metal finishes, and other materials beyond normal use.

2. Warranty Periods: From date of Substantial Completion.

a. Commercial, Heat Pump, Storage, Electric, Domestic-Water Heaters:

1) Storage Tank: Three years.
2) Controls and Other Components: One year.

b. Expansion Tanks: Five years.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and use.

B. ASHRAE/IES Compliance: Applicable requirements in ASHRAE/IES 90.1.

C. ASME Compliance: Where ASME-code construction is indicated, fabricate and label commercial, domestic-water heater storage tanks to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.

D. NSF Compliance: Fabricate and label equipment components that will be in contact with potable water to comply with NSF 61 and NSF 372.

2.2 COMMERCIAL, ELECTRIC HEAT PUMP, DOMESTIC-WATER HEATERS

A. Commercial, Electric Heat Pump, Storage, Domestic-Water Heaters (EWH-1):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. A.O. Smith Corporation.
   b. Lochinvar, LLC.
   c. State Industries.

2. Source Limitations: Obtain domestic-water heaters from single source from single manufacturer.
3. Standard: UL 174.
4. Commercial storage water heater shall use an air-to-water heat pump as the primary heat source.
5. Storage-Tank Construction: Steel vertical arrangement.

   a. Tappings: Factory fabricated of materials compatible with tank and piping connections. Attach tappings to tank before testing.

      1) NPS 2 (DN 50) and Smaller: Threaded ends in accordance with ASME B1.20.1.
      2) NPS 2-1/2 (DN 65) and Larger: Flanged ends in accordance with ASME B16.5 for steel and stainless steel flanges, and in accordance with ASME B16.24 for copper and copper-alloy flanges.

   b. Pressure Rating: 150 psig.
   c. Interior Finish: Comply with NSF 61 and NSF 372 barrier materials for potable-water tank linings, including extending lining material into tappings.

6. Heat pump water heater shall be capable of operating in efficiency, hybrid, or electric only modes.
7. Factory-Installed, Storage-Tank Appurtenances:

   a. Anode Rod: Replaceable magnesium.
   b. Dip Tube: Required unless cold-water inlet is near bottom of tank.
   c. Drain Valve: Corrosion-resistant metal with hose-end connection.
   d. Insulation: Comply with ASHRAE/IES 90.1.
   e. Jacket: Steel with enameled finish or high-impact composite material.
   f. Heating Elements: Electric, screw-in or bolt-on immersion type.
   g. Temperature Control: Adjustable thermostat.
   h. Safety Controls: High-temperature-limit and low-water cutoff devices or systems.
   i. Relief Valves: ASME rated and stamped for combination temperature-and-pressure relief valves. Include one or more relief valves with total relieving capacity at least as great as heat input, and include pressure setting less than working-pressure rating of domestic-water heater. Select one relief valve with sensing element that extends into storage tank.

2.3 DOMESTIC-WATER HEATER ACCESSORIES

A. Domestic-Water Expansion Tanks:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. A. O. Smith Corporation.
    b. AMTROL, Inc.
    c. State Industries.
    d. Taco Comfort Solutions.

2. Source Limitations: Obtain domestic-water expansion tanks from single source from single manufacturer.
3. Description: Steel pressure-rated tank constructed with welded joints and factory-installed, butyl-rubber diaphragm. Include air precharge to minimum system-operating pressure at tank.
4. Construction:

    a. Tappings: Factory-fabricated steel, welded to tank before testing and labeling. Include ASME B1.20.1 pipe thread.
    b. Interior Finish: Comply with NSF 61 and NSF 372 barrier materials for potable-water tank linings, including extending finish into and through tank fittings and outlets.
    c. Air-Charging Valve: Factory installed.

B. Piping-Type Heat Traps: Field-fabricated piping arrangement in accordance with ASHRAE/IES 90.1.

C. Heat-Trap Fittings: ASHRAE/IES 90.1.

D. Combination Temperature-and-Pressure Relief Valves: ASME rated and stamped. Include relieving capacity at least as great as heat input, and include pressure setting less than working-pressure rating of domestic-water heater. Select relief valves with sensing element that extends into storage tank.

E. Vacuum Relief Valves: ANSI Z21.22/CSA 4.4.

2.4 SOURCE QUALITY CONTROL

A. Hydrostatically test domestic-water heaters to minimum of one and one-half times pressure rating before shipment.

B. Electric, domestic-water heaters will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 DOMESTIC-WATER HEATER INSTALLATION

A. Electric, Domestic-Water Heater Mounting: Install electric, domestic-water heaters on concrete base. Comply with requirements for concrete bases specified in Section 033000 "Cast-in-Place Concrete."

1. Exception: Omit concrete bases for commercial, electric, domestic-water heaters if installation on stand, bracket, suspended platform, or directly on floor is indicated.
2. Maintain manufacturer's recommended clearances.
3. Arrange units so controls and devices that require servicing are accessible.

B. Install electric, domestic-water heaters level and plumb, in accordance with layout drawings, original design, and referenced standards. Maintain manufacturer's recommended clearances. Arrange units so controls and devices needing service are accessible.

1. Install shutoff valves on domestic-water-supply piping to domestic-water heaters and on domestic-hot-water outlet piping. Comply with requirements for shutoff valves specified in Section 220523.12 "Ball Valves for Plumbing Piping."

C. Install combination temperature-and-pressure relief valves in top portion of storage tanks. Use relief valves with sensing elements that extend into tanks. Extend domestic-water heater relief-valve outlet, with drain piping same as domestic-water piping in continuous downward pitch, and discharge by positive air gap onto closest floor drain.

D. Install water-heater drain piping as indirect waste to spill by positive air gap into open drains or over floor drains. Install hose-end drain valves at low points in water piping for electric, domestic-water heaters that do not have tank drains. Comply with requirements for hose-end drain valves specified in Section 221119 "Domestic Water Piping Specialties."

E. Install thermometers on inlet and outlet piping of electric, domestic-water heaters. Comply with requirements for thermometers specified in Section 220519 "Meters and Gages for Plumbing Piping."

F. Install piping-type heat traps on inlet and outlet piping of electric, domestic-water heater storage tanks without integral or fitting-type heat traps.

G. Fill electric, domestic-water heaters with water.

H. Charge domestic-water expansion tanks with air to required system pressure.

I. Install dielectric fittings in all locations where piping of dissimilar metals is to be joined. The wetted surface of the dielectric fitting contacted by potable water to contain less than 0.25 percent of lead by weight.

3.2 PIPING CONNECTIONS

A. Comply with requirements for piping specified in Section 221116 "Domestic Water Piping." Drawings indicate general arrangement of piping, fittings, and specialties.

B. Where installing piping adjacent to electric, domestic-water heaters, allow space for service and maintenance of water heaters. Arrange piping for easy removal of domestic-water heaters.

3.3 IDENTIFICATION

A. Identify system components. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.4 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Tests and Inspections:

1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
2. Operational Test: After electrical circuitry has been energized, start units to confirm proper operation.
3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

C. Electric, domestic-water heaters will be considered defective if they do not pass tests and inspections.

D. Prepare test and inspection reports.

3.5 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain commercial, electric, domestic-water heaters. Training to be a minimum of two hour(s).

END OF SECTION

SECTION 224200 - COMMERCIAL PLUMBING FIXTURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Commercial lavatories.
2. Commercial showers.
3. Commercial sinks.
4. Commercial urinals.
5. Commercial water closets.
6. Flushometer valves.
7. Toilet seats.
8. Fixture carriers.

1.2 DEFINITIONS

A. FRP: Fiberglass-reinforced plastic.

B. High-Efficiency Flush Volume: 1.28 gal. or less per flush.

C. Standard-Efficiency Flush Volume: 1.6 gal. per flush.

D. WaterSense Fixture: Water closet and/or flushometer valve/tank certified by the EPA to meet the WaterSense performance criteria.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include construction details, material descriptions and thicknesses, dimensions of individual components and profiles, and finishes for plumbing fixtures.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

C. Shop Drawings:

1. Plans, elevations, sections, and mounting or attachment details.
2. Details of equipment assemblies, including accessories. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, location and size of each field connection, location and size of each cutout, and anchorage provisions and attachment methods. Indicate coordination requirements for adjacent and interfacing Work.

3. Diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Counter cutout templates for mounting of counter-mounted lavatories and/or counter-mounted sinks.

C. Provide fixture cut sheets to General Contractor for inclusion in project coordination drawings. Include all fixture dimensions, noting manufacturer’s clearance requirements, as well as location and sizes of all fixture connections and supports. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data:

1. For lavatories and faucets.

a. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

1) Servicing and adjustments of automatic faucets.

2. For shower valves to include in maintenance manuals.
3. For sinks and faucets to include in operation and maintenance manuals.
4. For flushometer valves to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Lavatory faucets, sink faucets, and shower valves intended to convey or dispense water for human consumption are to comply with the U.S. Safe Drinking Water Act (SDWA), with requirements of the Authority Having Jurisdiction (AHJ), and with NSF 61 and NSF 372, or be certified in compliance with NSF 61 and NSF 372 by an ANSI-accredited third-party certification body, in that the weighted average lead content at wetted surfaces is less than or equal to 0.25 percent.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 COMMERCIAL LAVATORIES

A. Lavatories, Counter Mounted:

1. Lavatories, Counter Mounted – Accessible, Solid-Surface Integral with Countertop (L-1):

a. Solid-surface countertop and lavatories are specified in Section 123661, "Simulated Stone Countertops".
b. Fixture:

1) Faucet-Hole Punching: One hole, centered.
2) Faucet-Hole Location: Top.

c. Faucet: L-1/2.
d. Protective Shielding Guards: Not required, architectural skirt board provided with countertop.

B. Lavatories, Wall Mounted:

1. Lavatories, Wall Mounted - Vitreous China, Rectangular with Ledge Back (L-2):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Sloan SS-3003 or comparable product by one of the following:

1) American Standard
2) Kohler Co
3) Zurn Industries, LLC

b. Fixture:

1) Standard: ASME A112.19.2/CSA B45.1.
2) Type: For wall hanging.
3) Nominal Size: Rectangular, 20 by 18 inches.
4) Faucet-Hole Punching: One hole.
5) Faucet-Hole Location: Top.
6) Color: White.
7) Mounting Material: Chair carrier.

c. Faucet: L-1/2.
d. Support: Lavatory carrier, floor affixed with steel uprights, concealed arm.
e. Lavatory Mounting Height: Accessible in accordance with ICC A117.1.
f. Protective Shielding Guards: Required.

C. Lavatory Faucets, Automatically Operated, Hard Wired (L-1/2):

1. Basis-of-Design Product: Subject to compliance with requirements, provide Sloan SF-2100-4-PLG-BDM-CP-0.5 GPM or comparable product by one of the following:

a. American Standard
b. Bradley Corporation
c. Chicago Faucets; Geberit Group
d. Delta Faucet Company

e. Elkay
f. Kohler Co
g. Moen Incorporated
h. Speakman Company
i. T&S Brass and Bronze Works, Inc.
j. TOTO USA, INC
k. Zurn Industries, LLC

2. Standards: ASME A112.18.1/CSA B125.1 and UL 1951.
3. Operation Type: Hardwired electronic sensor operated, mixing. Provide ASSE 1070 protection either integral with faucet by manufacturer, or with ASSE1070 temperature limiting device on hot water connection to faucet. For separate temperature limiting device, refer to Section 221119 " Domestic Water Piping Specialties."
4. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
5. General: Include hot- and cold-water indicators; coordinate faucet inlets with supplies and fixture hole punchings; coordinate outlet with spout and fixture receptor.
6. Body Type: Single hole.
7. Body Material: Commercial, solid-brass, or die-cast housing with brazed copper and brass waterway.
8. Finish: Polished chrome plate.
9. Maximum Flow Rate: 0.5 gpm.
10. Mounting Type: Deck, concealed.
11. Spout: Rigid type.
12. Spout Outlet: Laminar flow.

D. Lavatory Supply Fittings:

1. NSF Standards: Comply with NSF 61 and NSF 372 for supply-fitting materials that will be in contact with potable water.
2. Standard: ASME A112.18.1/CSA B125.1.
3. Supply Piping: Chrome-plated-brass pipe or chrome-plated copper tube matching water-supply piping size. Include chrome-plated-brass or stainless steel wall flange.
4. Supply Stops: Chrome-plated-brass, one-quarter-turn, ball-type or compression valve with inlet connection matching supply piping.
5. Operation: Loose key.

a. Risers Size: NPS 3/8.
b. Risers Material: ASME A112.18.6/CSA B125.6, braided or corrugated stainless steel, flexible hose.

E. Lavatory Waste Fittings:

1. Standard: ASME A112.18.2/CSA B125.2.
2. Drain: Grid type with NPS 1-1/4 offset and straight tailpiece.
3. Trap:

a. Size: NPS 1-1/2 by NPS 1-1/4.
b. Material:

1) Chrome-plated, two-piece, cast-brass trap and swivel elbow with 0.032-inch-thick brass tube to wall; and chrome-plated, brass or steel wall flange.

2.3 COMMERCIAL SHOWERS

A. Showers, Individual:

1. Showers, Individual - FRP, One Piece without Top; Accessible for Side Transfer (SH-1), Standard (SH-2):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Oasis Model SHFW-WX-3837 or comparable product by one of the following:

1) Clarion Bathware
2) Florestone Products Co., Inc.
3) Lasco Bathware
4) Sterling
5) Swan Corporation

b. Source Limitations: Obtain FRP showers without top from single source from single manufacturer.
c. Description: FRP shower enclosure with valve and receptor; and appurtenances for SH-1.
d. Standard: CSA B45.5/IAPMO Z124.
e. Style: Standard (SH-2) Accessible in accordance with ICC A117 (SH-1).
f. Shower Head and Shower Valve: SH-1/2.
g. Shower Nominal Size and Shape: 36 by 36 inches square clear inside
h. Color: White.
i. Outlet: Drain with NPS 2 outlet.
j. Bathing Surface: Slip resistant according to ASTM F 462.
k. Shower Rod: Required.
l. Integral Grab Bar: Required for SH-1.
m. Integral Fold-Down Seat: Required for SH-1.

B. Shower Valve Assemblies:

1. Shower Valve Assemblies - Single-Handle, Pressure-Balanced Mixing Valve with Head (SH-1/2):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Zurn Industries Temp-Guard III Model Z7300-SS-HW-MT or comparable product by one of the following:

1) Kohler Co
2) Leonard Valve Company
3) Moen Incorporated
4) POWERS; A Watts Water Technologies Company
5) Symmons Industries, Inc

b. Source Limitations: Obtain shower heads and shower valves from single source from single manufacturer.
c. Description: Single-handle, accessible, pressure-balance mixing valve with hot- and cold-water indicators; check stops; and hose with handheld shower head on sliding rod shower head.
d. Shower Valve:

1) Standards:

a) ASME A112.18.1/CSA B125.1.
b) ASSE 1016/ASME A112.1016/CSA B125.16.

2) Body Material: Solid brass.
3) Finish: Polished chrome plate.
4) Mounting: Concealed.
5) Operation: Single-handle, twist or rotate control.
6) Antiscald Device: Integral with mixing valve.
7) Check Stops: Check-valve type, integral with or attached to body; on hot- and cold-water supply connections.

e. Supply Connections: NPS 1/2.
f. Shower Head:

1) Standard: ASME A112.18.1/CSA B125.1.
2) Type: Fixed flow, hand held, slide bar mounting.
3) Shower Head Maximum Flow Rate: 1.5 gpm.
4) Shower Head Material: Metallic with chrome-plated finish.
5) Spray Pattern: Fixed.
6) Integral Volume Control: 1.5 gpm flow restrictor.
7) Hose: 59-inch length.
8) Slide Bar: 25-inch, vertical, metal.
9) Vacuum Breaker: Required.

2.4 COMMERCIAL SINKS

A. Mop Receptors, Floor Mounted:

1. Service Sinks, Floor Mounted - Molded Stone (MR-1):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Fiat MSB2424 or comparable product by one of the following:

1) Florestone Products Co., Inc.

b. Source Limitations: Obtain sinks from single source from single manufacturer.
c. Fixture:

1) Standard: ASME A112.18.2/CSA B125.2.
2) Shape: Square.
3) Nominal Size: 24 by 24 inches.
4) Height: 10 inches.
5) Rim Guard: On front top surfaces.
6) Color: White.
7) Drain: Stainless steel grid with NPS 3 outlet.

d. Mounting: On floor and flush to wall.
e. Faucet: MR-1.

B. Kitchen/Utility Sinks:

1. Kitchen/Utility Sinks, Counter Under Mounted - Stainless Steel (S-1):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Elkay Model ELUHAD 191650 or comparable product by one of the following:

1) Advance Tabco
2) Dayton Products Inc.
3) Just Manufacturing

b. Source Limitations: Obtain sinks from single source from single manufacturer.
c. Fixture:

1) Standard: ASME A112.19.3/CSA B45.4.
2) Type: Stainless steel, single bowl, under mount, sound-deadened unit.
3) Number of Compartments: One.
4) Overall Dimensions: 21-1/2 inches long by 18-1/2 inches wide.
5) Material: 18 gauge, Type 304 stainless steel.
6) Compartment:

a) Dimensions: 19 inches long by 16 inches wide by 5 inches deep.
b) Drain: Grid with NPS 1-1/2 tailpiece.
c) Drain Location: Centered, near back of compartment.
d) Depth: Accessible in accordance with ICC A117.1.

d. Faucet(s): S-1.

1) Number Required: One.
2) Mounting: On countertop.

e. Supply Fittings:

1) Standard: ASME A112.18.1/CSA B125.1.
2) Supplies: Chrome-plated brass compression stop with inlet connection matching water-supply piping type and size.

a) Operation: Loose key.
b) Risers: NPS 1/2, ASME A112.18.6/CSA B125.6, braided or corrugated stainless steel flexible hose.

f. Waste Fittings:

1) Standard: ASME A112.18.2/CSA B125.2.
2) Trap(s) Size: NPS 2.
3) Trap(s) Material:

a) Chrome-plated, two-piece, cast-brass trap and ground-joint swivel elbow with 17-gauge brass tube to wall; and chrome-plated brass or steel wall flange.

g. Mounting: Under counter with sealant.

h. Protective Shielding Guards: Not required, architectural skirt board provided with countertops.

2. Kitchen/Utility Sinks, Freestanding - Stainless Steel (S-2L and S-2R):

a. Basis-of-Design Product: Subject to compliance with requirements, provide ULINE H-8967 or comparable product by one of the following:

1) Advance Tabco
2) Eagle Group
3) Elkay
4) Just Manufacturing

b. Source Limitations: Obtain sinks from single source from single manufacturer.
c. Fixture:

1) Standards:

a) ASME A112.19.3/CSA B45.4.

2) Type: Stainless steel, freestanding, sound-deadened unit with backsplash.
3) Number of Compartments: One with integral stainless steel side board.
4) Overall Dimensions: 72 inches long by 30 inches deep.
5) Material: 16 gauge, Type 304 stainless steel.
6) Compartment:

a) Dimensions: 18 inches long by 16 inches wide by 12 inches deep.
b) Drain: Grid with NPS 2 tailpiece and twist drain.
c) Drain Location: Centered in compartment.

7) Integral Drainboard(s): Left for S-1L, right for S-1R side(s).

d. Legs and Feet: Stainless steel tubing legs with adjustable bullet feet.
e. Faucet(s): Integral by manufacturer.

1) Number Required: One.
2) Mounting: On countertop.

f. Supply Fittings:

1) Standard: ASME A112.18.1/CSA B125.1.
2) Supplies: Chrome-plated brass compression stop with inlet connection matching water-supply piping type and size.

a) Operation: Loose key.
b) Risers: NPS 1/2, ASME A112.18.6/CSA B125.6, braided or corrugated stainless steel flexible hose.

g. Waste Fittings:

1) Standard: ASME A112.18.2/CSA B125.2.
2) Trap(s) Size: NPS 2.

3) Trap(s) Material:

a) Chrome-plated, two-piece, cast-brass trap and ground-joint swivel elbow with 17-gauge brass tube to wall; and chrome-plated brass or steel wall flange.

C. Sink Faucets, Manually Operated (S-1):

1. Sink Faucets, Manually Operated: Single control, mixing.

a. Basis-of-Design Product: Subject to compliance with requirements, provide Zurn Z82300-XL or comparable product by one of the following:

1) American Standard
2) Chicago Faucets; Geberit Group
3) Elkay
4) Kohler Co
5) T&S Brass and Bronze Works, Inc.

b. Source Limitations: Obtain sink faucets from single source from single manufacturer.
c. Standards:

1) ASME A112.18.1/CSA B125.1.
2) NSF 61.
3) NSF 372.

d. Description: Kitchen faucet less side spray for one-hole fixture. Include hot- and cold-water indicators; coordinate faucet inlets with supplies and fixture hole punchings; coordinate outlet with spout and sink receptor.
e. Body Type: Single hole.
f. Body Material: Commercial, solid-brass, or die-cast housing with brazed copper and brass waterway.
g. Finish: Chrome plated.
h. Maximum Flow Rate: 1.5 gpm.
i. Mounting Type: Deck, concealed.
j. Valve Handle(s): Lever.
k. Spout Type: Swing.
l. Spout Outlet: Laminar flow.
m. Operation: Non-compression, manual.

2. Sink Faucets, Manually Operated - Service Sink (MR-1):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Zurn Z842MI or comparable product by one of the following:

1) Chicago Faucets; Geberit Group
2) Fiat Products
3) Just Manufacturing
4) Kohler Co
5) T&S Brass and Bronze Works, Inc.

b. Source Limitations: Obtain sink faucets from single source from single manufacturer.
c. Description: Wall/back mounted, brass body, with integral service stops, checks, spout with bucket/pail hook wall brace, 3/4-inch hose thread end, integral vacuum breaker, inlets 8 inches o.c., and two-handle mixing.
d. Faucet:

1) Standards:

a) ASME A112.18.1/CSA B125.1.
b) NSF 61 and NSF 372.
c) ICC A117.1.
d) ASSE 1001 (VB).

2) Finish: Polished chrome plated.
3) Handles: Lever.
4) Brace: Adjustable top brace.

e. Vacuum Breaker: Required for hose outlet.
f. Spout Outlet: Hose thread in accordance with ASME B1.20.7.

D. Grout:

1. Standard: ASTM C1107/C1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
2. Characteristics: Nonshrink; recommended for interior and exterior applications.
3. Design Mix: 5000 psi, 28-day compressive strength.
4. Packaging: Premixed and factory packaged.

2.5 COMMERCIAL URINALS

A. Urinals, Wall Hung:

1. Urinals, Wall Hung - Back Outlet, Washout (U-1):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Sloan SU-1009 or comparable product by one of the following:

1) American Standard
2) Kohler Co
3) TOTO USA, INC
4) Zurn Industries, LLC

b. Fixture:

1) Standards:

a) ASME A112.19.2/CSA B45.1.
b) ASME A112.19.5/CSA B45.15.

2) Material: Vitreous china.

3) Type: Washout with extended shields.
4) Strainer or Trapway: Manufacturer's standard strainer with integral trap.
5) Water Consumption: 0.5 gpf.
6) Spud Size and Location: NPS 3/4, back.
7) Outlet Size and Location: NPS 2, back.
8) Color: White.

c. Flushometer Valve: UR.
d. Waste Fitting:

1) Standard: ASME A112.18.2/CSA B125.2 for coupling.
2) Size: NPS 2.

e. Support: Urinal carrier, floor affixed with steel uprights with fixture support plates and coupling with seal and fixture bolts and hardware matching fixture.
f. Urinal Mounting Height: Accessible in accordance with ICC A117.1.

2.6 COMMERCIAL WATER CLOSETS

A. Water Closets, Floor Mounted:

1. Water Closets, Floor Mounted - Bottom Outlet, Top Spud (WC-3):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Sloan ST-2029 or comparable product by one of the following:

1) American Standard
2) Kohler Co
3) TOTO USA, INC
4) Zurn Industries, LLC

b. Source Limitations: Obtain water closets from single source from single manufacturer.
c. Standard: ASME A112.19.2/CSA B45.1.
d. Bowl:

1) Material: Vitreous china.
2) Type: Siphon jet.
3) Style: Flushometer valve.
4) Height: Accessible in accordance with ICC A117.1.
5) Rim Contour: Elongated.
6) Water Consumption: 1.28 gal. per flush.
7) Spud Size and Location: NPS 1-1/2; top.
8) Color: White.

e. Flushometer Valve: WC.
f. Toilet Seat: WC.

B. Water Closets, Wall Mounted:

1. Water Closets, Wall Mounted - Top Spud (WC-1 and WC-2):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Sloan ST-2459 or comparable product by one of the following:

1) American Standard
2) Kohler Co
3) TOTO USA, INC
4) Zurn Industries, LLC

b. Source Limitations: Obtain water closets from single source from single manufacturer.
c. Standard: ASME A112.19.2/CSA B45.1.
d. Bowl:

1) Material: Vitreous china.
2) Type: Siphon jet.
3) Style: Flushometer valve.
4) Mounting Height: Standard for WC-2, Accessible in accordance with ICC A117.1 for WC-1.
5) Rim Contour: Elongated.
6) Water Consumption: 1.28 gal. per flush.
7) Spud Size and Location: NPS 1-1/2; top.
8) Color: White.

e. Flushometer Valve: WC.
f. Toilet Seat: WC.
g. Support: Water-closet carrier, floor affixed.

2.7 FLUSHOMETER VALVES

A. Flushometer Valves, Manually Operated:

1. Flushometer Valves, Manually Operated - Diaphragm, Lever Handle (WC and UR):

a. Basis-of-Design Product: Subject to compliance with requirements, provide Sloan Royal 186 for UR and Sloan Royal 111-1.28 for WC or comparable product by one of the following:

1) American Standard
2) Zurn Industries, LLC

b. Source Limitations: Obtain flushometer valve from single source from single manufacturer.
c. Standard: ASSE 1037/ASME 112.1037/CSA B125.37.
d. Minimum Pressure Rating: 125 psig.
e. Features: Include integral check stop and backflow-prevention device.
f. Material: Brass body with corrosion-resistant components.
g. Style: Exposed.
h. Flushometer-Valve Finish: Chrome-plated.
i. Handle Finish: Chrome plated.
j. Consumption: 0.5 gal for UR, 1.28 gal for WC per flush.
k. Minimum Inlet: NPS 3/4 for UR, NPS 1 for WC.

2.8 TOILET SEATS

A. Toilet Seats - Commercial (WC):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. American Standard
    b. Bemis Manufacturing Company
    c. Church Seats; Bemis Manufacturing Company
    d. Kohler Co
    e. TOTO USA, INC
    f. Zurn Industries, LLC

2. Source Limitations: Obtain toilet seat from single source from single manufacturer.
3. Standard: IAPMO/ANSI Z124.5.
4. Material: Plastic.
5. Type: Commercial (heavy duty).
6. Shape: Elongated rim, open front.
7. Hinge: Self-sustaining, check.
8. Hinge Material: Noncorroding metal.
9. Seat Cover: Not required.
10. Color: White.
11. Surface Treatment: Not required.

2.9 FIXTURE CARRIERS

A. Fixture Carriers - Lavatory:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Jay R. Smith Mfg Co; a division of Morris Group International
    b. Josam Company
    c. MIFAB, Inc
    d. Wade; a subsidiary of McWane Inc.
    e. WATTS; A Watts Water Technologies Company
    f. Zurn Industries, LLC

2. Source Limitations: Obtain lavatory carriers from single source from single manufacturer.
3. Standards:

    a. ASME A112.6.1M.
    b. ASME A112.6.2.

B. Fixture Carriers - Urinal:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Jay R. Smith Mfg Co; a division of Morris Group International
    b. Josam Company
    c. MIFAB, Inc
    d. Wade; a subsidiary of McWane Inc.
    e. WATTS; A Watts Water Technologies Company
    f. Zurn Industries, LLC

2. Source Limitations: Obtain urinal carriers from single source from single manufacturer.
3. Standard: ASME A112.6.1M.
4. Description: Waste-fitting assembly, as required to match drainage piping material and arrangement with faceplates, couplings, gaskets, and feet; bolts and hardware matching fixture. Include additional extension coupling, faceplate, and feet for installation in wide pipe space.

C. Fixture Carriers - Water Closet:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Jay R. Smith Mfg Co; a division of Morris Group International
    b. MIFAB, Inc
    c. Wade; a subsidiary of McWane Inc.
    d. WATTS; A Watts Water Technologies Company
    e. Zurn Industries, LLC

2. Source Limitations: Obtain water closet carriers from single source from single manufacturer.
3. Standard: ASME A112.6.1M.
4. Description: Waste-fitting assembly, as required to match drainage piping material and arrangement with faceplates, couplings, gaskets, and feet; bolts and hardware matching fixture. Include additional extension coupling, faceplate, and feet for installation in wide pipe space.

2.10 PROTECTIVE SHIELDING GUARDS

A. Protective Shielding Pipe and Trap Protectors (L-2):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. McGuire Manufacturing Co., Inc.
    b. Plumberex Specialty Products, Inc.
    c. TCI Products.
    d. TRUEBRO, Inc.

2. Description: Manufactured plastic wraps for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with Americans with Disabilities Act (ADA) requirements.

B. Protective Shielding for Pipe and Trap, L-1 and S-1.

1. Architectural skirt board trim. Refer to casework and countertop details on drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in of water-supply piping and sanitary drainage and vent piping systems to verify actual locations of piping connections before plumbing fixture installation.

B. Examine walls and floors for suitable conditions where plumbing fixtures will be installed.

C. Examine counters for suitable conditions where lavatories and sinks will be installed.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF COMMERCIAL PLUMBING FIXTURES

A. Lavatory Installation:

1. Install lavatories level and plumb in accordance with roughing-in drawings.
2. Install supports, affixed to building substrate, for wall-mounted lavatories.
3. Install accessible, wall-mounted lavatories at mounting height in accordance with ICC A117.1.
4. Install water-supply piping with stop on each supply to each lavatory faucet. Install stops in locations that are accessible for ease of operation.
5. Install trap and waste piping on each drain outlet of each lavatory to be connected to sanitary drainage system.
6. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220500 "Common Work Results for Plumbing."
7. Seal joints between lavatories, counters, and walls using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."
8. Install protective shielding pipe covers and enclosures on exposed supplies and waste piping of accessible lavatories.

B. Shower Installation:

1. Assemble shower components in accordance with manufacturers' written instructions.
2. Install showers level and plumb in accordance with roughing-in drawings.

3. Install ball valves in water-supply piping to the shower if supply stops are specified with the shower valve. Comply with ball valve requirements specified in Section 220523 "General Duty Valves for Plumbing Piping." Install valves in locations that are accessible for ease of operation.
4. Install shower flow-control fittings with specified maximum flow rates in shower arms.
5. Set shower receptors in leveling bed of cement grout.
6. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220500 "Common Work Results for Plumbing."
7. Showers: Seal joints between showers, floors, and walls using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

C. Sink Installation:

1. Install sinks level and plumb in accordance with roughing-in drawings.
2. Install supports, affixed to building substrate, for wall-mounted sinks.
3. Set floor-mounted sinks in leveling bed of cement grout.
4. Install water-supply piping with stop on each supply to each sink faucet.

    a. Exception: Use ball valves if supply stops are not specified with sink. Comply with valve requirements specified in Section 220523 "General Duty Valves for Plumbing Piping."
    b. Install stops/valves in locations that are accessible for ease of operation.

5. Install trap and waste piping on each drain outlet of each sink to be connected to sanitary drainage system.
6. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220500 "Common Work Results for Plumbing."
7. Seal joints between sinks, counters, floors, and walls using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

D. Urinal Installation:

1. Install urinals level and plumb in accordance with roughing-in drawings.
2. Install wall-hung, back-outlet urinals onto waste-fitting seals and attached to supports.
3. Install accessible, wall-mounted urinals at mounting height in accordance with ICC A117.1.
4. Install supports, affixed to building substrate, for wall-hung urinals.
5. Use chair-type carrier supports with rectangular steel uprights for accessible urinals.
6. Measure support height installation from finished floor, not structural floor.
7. Install flushometer-valve, water-supply fitting on each supply to each urinal.
8. Attach supply piping to supports or substrate within pipe spaces behind fixtures.
9. Install lever-handle flushometer valves for accessible urinals with handle mounted on open side of compartment.
10. Install actuators in locations easily reachable for people with disabilities.

11. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Install deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220500 "Common Work Results for Plumbing."
12. Seal joints between urinals, walls, and floors using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to urinal color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

E. Water Closet Installation:

1. Install water closets level and plumb in accordance with roughing-in drawings.
2. Install floor-mounted water closets on bowl-to-drain connecting fitting attachments to piping or building substrate.
3. Install accessible, wall-mounted water closets at mounting height in accordance with ICC A117.1.
4. Install supports, affixed to building substrate, for floor-mounted, back-outlet water closets.
5. Use carrier supports with waste-fitting assembly and seal.
6. Measure support height installation from finished floor, not structural floor.
7. Install flushometer-valve, water-supply fitting on each supply to each water closet.
8. Attach supply piping to supports or substrate within pipe spaces behind fixtures.
9. Install lever-handle flushometer valves for accessible water closets with handle mounted on open side of water closet.
10. Install actuators in locations easily reachable for people with disabilities.
11. Install toilet seats on water closets.
12. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Install deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220500 "Common Work Results for Plumbing."
13. Seal joints between water closets, walls, and floors using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to water-closet color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

3.3 INSTALLATION OF PIPING CONNECTIONS

A. Connect plumbing fixtures with water supplies and soil, waste, and vent piping. Use size fittings required to match plumbing fixtures.

B. Comply with water piping requirements specified in Section 221116 "Domestic Water Piping."

C. Comply with soil, waste, and vent piping requirements specified in Section 221316 "Sanitary Waste and Vent Piping."

D. Install protective-shielding pipe covers and enclosures on exposed supplies and waste piping of accessible plumbing fixtures.

E. Where installing piping adjacent to water closets and urinals, allow space for service and maintenance.

3.4 INSTALLATION OF ELECTRICAL CONNECTIONS

A. Connect wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. Ground equipment in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

C. Install electrical devices furnished by manufacturer, but not factory mounted in accordance with NFPA 70 and NECA 1.

3.5 INSTALLATION OF CONTROL CONNECTIONS

A. Install control and electrical power wiring to field-mounted control devices.

B. Connect control wiring in accordance with Section 260523 "Control-Voltage Electrical Power Cables."

3.6 ADJUSTING

A. Operate and adjust plumbing fixtures and controls. Replace damaged and malfunctioning plumbing fixtures, fittings, and controls.

B. Adjust water pressure at faucets to produce proper flow.

C. Adjust water pressure at shower valves to produce proper flow.

D. Adjust water pressure at flushometer valves to produce proper flow.

3.7 CLEANING AND PROTECTION

A. After completing installation of plumbing fixtures, inspect and repair damage to finishes. Replace any fixtures unable to be repaired to the satisfaction of the Owner.

B. Clean plumbing fixtures and associated faucets, valves, flushometer valves, and fittings with manufacturers' recommended cleaning methods and materials.

C. Provide protective covering for installed plumbing fixtures and associated faucets, valves, flushometer valves, and fittings.

D. Do not allow use of plumbing fixtures for temporary facilities unless approved in writing by Owner.

END OF SECTION

SECTION 224600 - SECURITY PLUMBING FIXTURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Security combination water closet/lavatory fixtures.
2. Flushometer valves.
3. Toilet seats.

B. Related Requirements:

1. Section 224200 "Commercial Plumbing Fixtures."
2. Section 224300 "Healthcare Plumbing Fixtures."
3. Section 224500 "Emergency Plumbing Fixtures."
4. Section 224700 "Drinking Fountains and Water Coolers."

1.2 DEFINITIONS

A. Accessible Service Space: Service area in secure space behind wall-mounted fixtures.

B. Front-Access Fixture: Security plumbing fixture designed to mount on wall with installation and removal from fixture side of wall, and with piping and other components accessible only from access panel in fixture.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for security plumbing fixtures.
2. Include rated capacities, operating characteristics, and furnished specialties and accessories.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For security plumbing fixtures and components.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Faucets and bubblers intended to convey or dispense water for human consumption are to comply with the U.S. Safe Drinking Water Act, with requirements of authorities having jurisdiction, and with NSF 61 and NSF 372, or be certified in compliance with NSF 61 and NSF 372 by an ANSI-accredited third-party certification body, in that the weighted average lead content at wetted surfaces is less than or equal to 0.25 percent.

2.2 SECURITY COMBINATION WATER CLOSET/LAVATORY FIXTURES

A. Security Combination Water Closet/Lavatory Fixture - Stainless Steel, Front Access, On Floor, Cabinet :

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Acorn Engineering Company; a Division of Morris Group International
    b. I-Con Systems, Inc.
    c. Metcraft Industries, Inc.
    d. Willoughby Industries, Inc.

2. Source Limitations:

    a. Obtain security combination water closet/lavatory fixtures from single manufacturer.

3. Standards:

    a. ASME A112.19.3/CSA B45.4.
    b. ICC A117.1.

4. Material: 14-gauge, Type 304 stainless steel, seamless welded construction, with fire-resistant sound-deadening material in cabinet interior. Toilet to be able to withstand a 5000 lb load without deflection and/or damage.
5. Finish: Satin polished finish on exposed surfaces.
6. Cabinet: Rectangular apron, with backsplash and access panel.

    a. Water-Closet Bowl Location: Left of center on front of apron.

7. Features: ADA compliant and ligature resistant.
8. Mounting: Bolts through wall sleeve into accessible service space.
9. Water Closet:

    a. Bowl:

        1) Type: Elongated, with back inlet, integral trap, and blowout design with back outlet and integral contoured seat.

2) Seat Surface: Satin polished finish.
3) Punching: Two holes for installation of separate toilet seat.
4) Outlet Connection: NPS 4, horizontal with cleanout and slip joint.

10. Flushometer Valve: FV-1.
11. Lavatory:

a. Location: In top of cabinet.
b. Receptor: Oval or rectangular bowl with integral soap depression.
c. Hot- and Cold-Water and Bubbler Supply Valves: Pneumatic, push-button, hot and cold, metering type with individual check stops. Non-hold-open valve.
d. Filler Spout: Backsplash or deck mounted.
e. Drain: Integral punched grid with NPS 1-1/4 minimum waste and trap.

2.3 FLUSHOMETER VALVES

A. Flushometer Valve - Diaphragm:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Master-Trol
b. Sloan Valve Company
c. Zurn Industries, LLC

2. Source Limitations:

a. Obtain flushometer valves from single manufacturer.

3. Standards:

a. ASSE 1037/ASME A112.1037/CSA B125.37
b. ASME A112.19.5/CSA B45.15.

4. Minimum Pressure Rating: 125 psig.
5. Features: Integral check stops and backflow-prevention device.
6. Material: Brass body with corrosion-resistant components.
7. Actuator: Hydraulic, push button.
8. Style: Concealed.
9. Finish: Panel and exposed surfaces, chrome plated or stainless steel.
10. Consumption: 1.28 gal. per flush.
11. Minimum Inlet: NPS 1.
12. Minimum Outlet: NPS 1-1/4.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in for water supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before fixture installation.

B. Examine walls and floors for suitable conditions where fixtures will be installed.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF SECURITY PLUMBING FIXTURES

A. Install security plumbing fixtures level and plumb.

B. Install front-access, stainless steel fixtures as follows:

1. Install fixture support or mounting bracket.
2. Install fixture on support; mount components inside of or attached to fixture.
3. Extend supply piping from pipe space to fixture.
4. Install trap below fixture and extend soil and waste piping into pipe space.

C. Install fixture outlets with gasket seals.

D. Install fixtures designated "accessible" in accordance with ICC A117.1 for heights, dimensions, and clearances.

E. Seal joints between fixtures, floors, and walls using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

F. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220500 "Common Work Results for Plumbing."

3.3 PIPING CONNECTIONS

A. Connect fixtures with water supplies, stops, and risers and with traps, soil, waste, and vent piping. Use size fittings required to match fixtures.

B. Comply with requirements for water piping specified in Section 221116 "Domestic Water Piping."

C. Comply with requirements for soil and waste drainage piping specified in Section 221316 "Sanitary Waste and Vent Piping."

3.4 ADJUSTING

A. Operate and adjust flushometer valves and flow-control valves on fixtures. Replace damaged and malfunctioning fixtures, fittings, and controls.

B. Adjust water pressure at fixtures to produce proper flow.

3.5 CLEANING AND PROTECTION

A. After installing fixtures, inspect and replace damaged finishes.

B. Clean fixtures, faucets, and other fittings with manufacturers' recommended cleaning methods and materials.

C. Provide protective covering for installed fixtures and fittings.

D. Do not allow use of fixtures for temporary facilities unless approved in writing by Owner.

END OF SECTION

SECTION 224716 - PRESSURE WATER COOLERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes pressure water coolers, bottle fillers, and related components.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of pressure water cooler. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

C. Shop Drawings: Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Provide fixture cut sheets to General Contractor for inclusion in project coordination drawings. Include all fixture dimensions, noting manufacturer’s clearance requirements, as well as location and sizes of all fixture connections and supports. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For pressure water coolers to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Filter Cartridges: Equal to 10 percent of quantity installed for each type and size indicated, but no fewer than two of each.

1.7 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Regulatory Requirements: Comply with requirements in ICC A117.1, "Accessible and Usable Buildings and Facilities"; Public Law 90-480, "Architectural Barriers Act"; and Public Law 101-336, "Americans with Disabilities Act"; for fixtures for people with disabilities.

C. NSF Standard: Comply with NSF 61, "Drinking Water System Components--Health Effects," for fixture materials that will be in contact with potable water.

D. ARI Standard: Comply with ARI 1010, "Self-Contained, Mechanically Refrigerated Drinking-Water Coolers," for water coolers and with ARI's "Directory of Certified Drinking Water Coolers" for type and style classifications.

E. ASHRAE Standard: Comply with ASHRAE 34, "Designation and Safety Classification of Refrigerants," for water coolers. Provide HFC 134a (tetrafluoroethane) refrigerant, unless otherwise indicated.

PART 2 - PRODUCTS

2.1 PRESSURE WATER COOLERS

A. Pressure Water Coolers with Bottle Filler (EWC-1): Wall mounted, dual height, wheelchair accessible with integral bottle filler.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Elkay Manufacturing Co. LZSTL8WSSP, or a comparable product by available manufacturers offering products that may be incorporated into the Work which include, but are not limited to, the following:

a. Halsey Taylor.

2. Standards:

a. Comply with NSF 61 Annex G.

b. Comply with ASHRAE 34, "Designation and Safety Classification of Refrigerants," for water coolers. Provide HFC 134a (tetrafluoroethane) refrigerant unless otherwise indicated.

3. Cabinet: Bi-level with two attached cabinets, vinyl-covered steel with stainless-steel top.
4. Bubbler: Adjustable stream regulator, one located on each deck.
5. Control: Push bar on front and sides.
6. Drain: Grid with NPS 1-1/4 tailpiece.
7. Supply: NPS 3/8 with shutoff valve.
8. Waste Fitting: ASME A112.18.2/CSA B125.2, NPS 1-1/4 brass P-trap.
9. Filter: One or more water filters complying with NSF 42 and NSF 53 for cyst and lead reduction to below EPA standards, with capacity sized for unit peak flow rate.
10. Cooling System: Electric, with hermetically sealed compressor, cooling coil, air-cooled condensing unit, corrosion-resistant tubing, refrigerant, corrosion-resistant-metal storage tank, and adjustable thermostat.

    a. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

11. Bottle Filler: Mounted on water cooler section:

    a. Cabinet: Stainless steel and plastic.
    b. Water Dispenser: Anti-microbial plastic with 1.1 gpm fill rate and laminar flow.
    c. Control: Touchless operation with 30-second shut-off timer.
    d. Drain: To water cooler deck.
    e. Visual User Interface Display: Shall include a filter monitoring indicator for filter replacement and a “Green Ticker” indicating the quantity of bottles kept from landfills by use of the bottle filler.

12. Capacities and Characteristics:

    a. Cooled Water: 8 gph.
    b. Ambient-Air Temperature: 90 deg F.
    c. Inlet-Water Temperature: 80 deg F.
    d. Cooled-Water Temperature: 50 deg F.
    e. Electrical Characteristics:

        1) Volts: 120-V ac.
        2) Phase: Single.
        3) Hertz: 60.
        4) Full-Load Amperes: 4.0.

13. Support: ASME A112.6.1M, Type I water-cooler carrier.

2.2 SUPPORTS

A. Type I Water Cooler Carrier: Floor mounted plate type carrier with rectangular steel uprights with integral welded feet.

1. Standard: ASME A112.6.1M.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in for water-supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before fixture installation.

B. Examine walls and floors for suitable conditions where fixtures will be installed.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install fixtures level and plumb according to roughing-in drawings. For fixtures indicated for children, install at height required by authorities having jurisdiction.

B. Install off-the-floor carrier supports, affixed to building substrate, for wall-mounted fixtures.

C. Install water-supply piping with shutoff valve on supply to each fixture to be connected to domestic-water distribution piping. Use ball valve. Install valves in locations where they can be easily reached for operation. Valves are specified in Section 220523.12 "Ball Valves for Plumbing Piping."

D. Install trap and waste piping on drain outlet of each fixture to be connected to sanitary drainage system.

E. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons where required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220518 "Escutcheons for Plumbing Piping."

F. Seal joints between fixtures and walls using sanitary-type, one-part, mildew-resistant, silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

3.3 CONNECTIONS

A. Connect fixtures with water supplies, stops, and risers, and with traps, soil, waste, and vent piping. Use size fittings required to match fixtures.

B. Comply with water piping requirements specified in Section 221116 "Domestic Water Piping."

C. Install ball shutoff valve on water supply to each fixture. Install valve upstream from filter for water cooler. Comply with valve requirements specified in Section 220523.12 "Ball Valves for Plumbing Piping."

D. Comply with soil and waste piping requirements specified in Section 221316 "Sanitary Waste and Vent and Radon Piping."

3.4 ADJUSTING

A. Adjust fixture flow regulators for proper flow and stream height.

B. Adjust pressure water-cooler temperature settings.

3.5 CLEANING

A. After installing fixture, inspect unit. Remove paint splatters and other spots, dirt, and debris. Repair damaged finish to match original finish.

B. Clean fixtures, on completion of installation, according to manufacturer's written instructions.

C. Provide protective covering for installed fixtures.

D. Do not allow use of fixtures for temporary facilities unless approved in writing by Owner.

END OF SECTION

SECTION 230513 - COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes general requirements for single-phase and polyphase, general-purpose, horizontal, small and medium, squirrel-cage induction motors for use on alternating-current power systems up to 600 V and installed at equipment manufacturer's factory or shipped separately by equipment manufacturer for field installation.

1.3 COORDINATION

A. Coordinate features of motors, installed units, and accessory devices to be compatible with the following:

1. Motor controllers.
2. Torque, speed, and horsepower requirements of the load.
3. Ratings and characteristics of supply circuit and required control sequence.
4. Ambient and environmental conditions of installation location.

PART 2 - PRODUCTS

2.1 GENERAL MOTOR REQUIREMENTS

A. Comply with NEMA MG 1 unless otherwise indicated.

B. Comply with IEEE 841 for severe-duty motors.

2.2 MOTOR CHARACTERISTICS

A. Duty: Continuous duty at ambient temperature of 40 deg C and at altitude of 3300 feet above sea level.

B. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.

2.3 POLYPHASE MOTORS

A. Description: NEMA MG 1, Design B, medium induction motor.

B. Efficiency: Premium efficient, as defined in NEMA MG 1.

C. Service Factor: 1.15.

D. Multispeed Motors: Variable torque.

1. For motors with 2:1 speed ratio, consequent pole, single winding.
2. For motors with other than 2:1 speed ratio, separate winding for each speed.

E. Rotor: Random-wound, squirrel cage.

F. Bearings: Regreasable, shielded, antifriction ball bearings suitable for radial and thrust loading.

G. Temperature Rise: Match insulation rating.

H. Insulation: Class F.

I. Code Letter Designation:

1. Motors 15 HP and Larger: NEMA starting Code F or Code G.
2. Motors Smaller Than 15 HP: Manufacturer's standard starting characteristic.

J. Enclosure Material: Cast iron for motor frame sizes 324T and larger; rolled steel for motor frame sizes smaller than 324T.

2.4 ADDITIONAL REQUIREMENTS FOR POLYPHASE MOTORS

A. Motors Used with Reduced-Voltage and Multispeed Controllers: Match wiring connection requirements for controller with required motor leads. Provide terminals in motor terminal box, suited to control method.

B. Motors Used with Variable-Frequency Controllers: Ratings, characteristics, and features coordinated with and approved by controller manufacturer.

1. Windings: Copper magnet wire with moisture-resistant insulation varnish, designed and tested to resist transient spikes, high frequencies, and short time rise pulses produced by pulse-width-modulated inverters.
2. Premium-Efficient Motors: Class B temperature rise; Class F insulation.
3. Inverter-Duty Motors: Class F temperature rise; Class H insulation.
4. Thermal Protection: Comply with NEMA MG 1 requirements for thermally protected motors.

C. Severe-Duty Motors: Comply with IEEE 841, with 1.15 minimum service factor.

2.5 SINGLE-PHASE MOTORS

A. Motors larger than 1/20 hp shall be one of the following, to suit starting torque and requirements of specific motor application:

1. Permanent-split capacitor.
2. Split phase.
3. Capacitor start, inductor run.
4. Capacitor start, capacitor run.

B. Multispeed Motors: Variable-torque, permanent-split-capacitor type.

C. Bearings: Prelubricated, antifriction ball bearings or sleeve bearings suitable for radial and thrust loading.

D. Motors 1/20 HP and Smaller: Shaded-pole type.

E. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range.

PART 3 - EXECUTION (Not Applicable)

END OF SECTION

SECTION 230517 - SLEEVES AND SLEEVE SEALS FOR HVAC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Sleeves.
2. Sleeve-seal systems.
3. Grout.

B. Related Requirements:

1. Section 078413 "Penetration Firestopping" for penetration firestopping installed in fire-resistance-rated walls, horizontal assemblies, and smoke barriers, with and without penetrating items.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Field quality-control reports.

PART 2 - PRODUCTS

2.1 SLEEVES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Advance Products & Systems, Inc.
2. CALPICO, Inc.
3. GPT; an EnPro Industries company.

B. Cast-Iron Pipe Sleeves: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop collar unless otherwise indicated.

C. Galvanized Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, with plain ends.

2.2 SLEEVE-SEAL SYSTEMS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Advance Products & Systems, Inc.
2. CALPICO, Inc.
3. GPT; an EnPro Industries company.
4. Metraflex Company (The).
5. Proco Products, Inc.

B. Description:

1. Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.
2. Designed to form a hydrostatic seal of 20-psig.
3. Sealing Elements: EPDM-rubber or Nitrile (Buna N) interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size.
4. Pressure Plates: Carbon steel or stainless steel.
5. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating, ASTM B 633 or stainless steel of length required to secure pressure plates to sealing elements.

2.3 GROUT

A. Description: Nonshrink, recommended for interior and exterior sealing openings in nonfire-rated walls or floors.

B. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.

C. Design Mix: 5000-psi, 28-day compressive strength.

D. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 SLEEVE INSTALLATION

A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.

B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.

C. Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed.

1. Cut sleeves to length for mounting flush with both surfaces.

    a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.

2. Using grout, seal space outside of sleeves in slabs and walls without sleeve-seal system.
3. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth and location of joint. Comply with requirements for sealants specified in Section 079200 "Joint Sealants."

D. Install sleeves for pipes passing through interior partitions.

1. Extend sleeves installed in concealed interior partitions a minimum of 1-inch beyond finished wall surface.
2. Cut sleeves to length in exposed locations to mount flush with finished surface where escutcheons required.
3. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
4. Seal annular space between sleeve and piping or piping insulation; use sealants appropriate for size, depth, and location of joint. Comply with requirements for sealants specified in Section 079200 "Joint Sealants."

E. Fire-Resistance-Rated Penetrations, Horizontal Assembly Penetrations, and Smoke-Barrier Penetrations: Maintain indicated fire or smoke rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with fire- and smoke-stop materials. Comply with requirements for firestopping and fill materials specified in Section 078413 "Penetration Firestopping."

3.2 SLEEVE-SEAL-SYSTEM INSTALLATION

A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building.

B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal-system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

3.3 SLEEVE AND SLEEVE-SEAL SCHEDULE

A. Use sleeves and sleeve seals for the following piping-penetration applications:

1. Exterior Concrete Walls Above Grade:

a. Piping Smaller Than NPS 6: Cast-iron sleeves with sleeve-seal system.

1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.

2. Exterior Concrete Walls Below Grade:

a. Piping Smaller Than NPS 6: Cast-iron pipe sleeves with sleeve-seal system.

1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.

3. Concrete Slabs-on-Grade:

a. Piping Smaller Than NPS 6: Cast-iron pipe sleeves with sleeve-seal system.

1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.

4. Concrete Slabs Above Grade:

a. Piping Smaller Than NPS 6: Galvanized steel pipe sleeves.

5. Interior Partitions:

a. Piping Smaller Than NPS 6: Galvanized steel pipe sleeves.

END OF SECTION

SECTION 230518 - ESCUTCHEONS FOR HVAC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Escutcheons.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. BrassCraft Manufacturing Co.; a Masco company.
2. Dearborn Brass.
3. Jones Stephens Corp.
4. Keeney Manufacturing Company (The).
5. Mid-America Fittings, Inc.
6. ProFlo; a Ferguson Enterprises, Inc. brand.

2.2 ESCUTCHEONS

A. One-Piece, Cast-Brass Type: With polished, chrome-plated finish and setscrew fastener.

B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with polished, chrome-plated finish and spring-clip fasteners.

C. One-Piece, Stamped-Steel Type: With polished, chrome-plated finish and spring-clip fasteners.

D. Split-Casting Brass Type: With polished, chrome-plated finish and with concealed hinge and setscrew.

E. Split-Plate, Stamped-Steel Type: With polished, chrome-plated finish; concealed and exposed-rivet hinge; and spring-clip fasteners.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.

B. Install escutcheons with ID to closely fit around pipe, tube, and insulation of piping and with OD that completely covers opening.

1. Escutcheons for New Piping:

a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep pattern.
b. Chrome-Plated Piping: One-piece cast brass with polished, chrome-plated finish.
c. Insulated Piping: One-piece stamped steel or split-plate, stamped steel with concealed hinge with polished, chrome-plated finish.
d. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece stamped steel or split-plate, stamped steel with concealed hinge with polished, chrome-plated finish.
e. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece cast brass or split-casting brass type with polished, chrome-plated finish.
f. Bare Piping in Unfinished Service Spaces: One-piece stamped steel or split-plate, stamped steel with exposed-rivet hinge with polished, chrome-plated finish.

3.2 FIELD QUALITY CONTROL

A. Using new materials, replace broken and damaged escutcheons.

END OF SECTION

SECTION 230519 – METERS AND GAUGES FOR HVAC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Liquid-in-glass thermometers.
2. Thermowells.
3. Dial-type pressure gages.
4. Gage attachments.
5. Test plugs.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Certificates: For each type of meter and gage.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For meters and gages to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 LIQUID-IN-GLASS THERMOMETERS

A. Metal-Case, Industrial-Style, Liquid-in-Glass Thermometers:

1. Standard: ASME B40.200.
2. Case: Cast aluminum; 9-inch nominal size unless otherwise indicated.
3. Case Form: Adjustable angle unless otherwise indicated.
4. Tube: Glass with magnifying lens and blue or red organic liquid.
5. Tube Background: Nonreflective aluminum with permanently etched scale markings graduated in deg F.
6. Window: Glass.
7. Stem: Aluminum and of length to suit installation.

    a. Design for Thermowell Installation: Bare stem.

8. Connector: 1-1/4 inches, with ASME B1.1 screw threads.
9. Accuracy: Plus or minus 1 percent of scale range or one scale division, to a maximum of 1.5 percent of scale range.

2.2 THERMOWELLS

A. Thermowells:

1. Standard: ASME B40.200.
2. Description: Pressure-tight, socket-type fitting made for insertion in piping tee fitting.
3. Material for Use with Copper Tubing: CNR or CUNI.
4. Material for Use with Steel Piping: CRES or CSA.
5. Type: Stepped shank unless straight or tapered shank is indicated.
6. External Threads: NPS 1/2, NPS 3/4, or NPS 1, ASME B1.20.1 pipe threads.
7. Internal Threads: 1/2, 3/4, and 1 inch, with ASME B1.1 screw threads.
8. Bore: Diameter required to match thermometer bulb or stem.
9. Insertion Length: Length required to match thermometer bulb or stem.
10. Lagging Extension: Include on thermowells for insulated piping and tubing.
11. Bushings: For converting size of thermowell's internal screw thread to size of thermometer connection.

B. Heat-Transfer Medium: Mixture of graphite and glycerin.

2.3 DIAL-TYPE PRESSURE GAGES

A. Direct-Mounted, Metal-Case, Dial-Type Pressure Gages:

1. Standard: ASME B40.100.
2. Case: Liquid-filled type; cast aluminum or drawn steel; 4-1/2-inch nominal diameter.
3. Pressure-Element Assembly: Bourdon tube unless otherwise indicated.
4. Pressure Connection: Brass, with NPS 1/4 or NPS 1/2, ASME B1.20.1 pipe threads and bottom-outlet type unless back-outlet type is indicated.
5. Movement: Mechanical, with link to pressure element and connection to pointer.

6. Dial: Nonreflective aluminum with permanently etched scale markings graduated in psi.
7. Pointer: Dark-colored metal.
8. Window: Glass.
9. Ring: Metal.
10. Accuracy: Grade B, plus or minus 2 percent of middle half of scale range.

2.4 GAGE ATTACHMENTS

A. Snubbers: ASME B40.100, brass; with NPS 1/4 or NPS 1/2, ASME B1.20.1 pipe threads and porous-metal-type surge-dampening device. Include extension for use on insulated piping.

B. Valves: Brass or stainless-steel needle, with NPS 1/4 or NPS 1/2, ASME B1.20.1 pipe threads.

2.5 TEST PLUGS

A. Description: Test-station fitting made for insertion in piping tee fitting.

B. Body: Brass or stainless steel with core inserts and gasketed and threaded cap. Include extended stem on units to be installed in insulated piping.

C. Thread Size: NPS 1/4 or NPS 1/2, ASME B1.20.1 pipe thread.

D. Minimum Pressure and Temperature Rating: 500 psig at 200 deg F.

E. Core Inserts: Chlorosulfonated polyethylene synthetic and EPDM self-sealing rubber.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install thermowells with socket extending to center of pipe and in vertical position in piping tees.

B. Install thermowells of sizes required to match thermometer connectors. Include bushings if required to match sizes.

C. Install thermowells with extension on insulated piping.

D. Fill thermowells with heat-transfer medium.

E. Install direct-mounted thermometers in thermowells and adjust vertical and tilted positions.

F. Install direct-mounted pressure gages in piping tees with pressure gage located on pipe at the most readable position.

G. Install valve and snubber in piping for each pressure gage for fluids (except steam).

H. Install test plugs in piping tees.

I. Install thermometers in the following locations:

1. Inlet and outlet of each heat exchanger.
2. Inlet and outlet of each hydronic boiler.
3. Inlet and outlet of each reversing chiller.
4. Inlet and outlet of each hydronic coil in air-handling units.

J. Install pressure gages in the following locations:

1. Discharge of each pressure-reducing valve.
2. Inlet and outlet of each reversing chiller water connection.
3. Suction and discharge of each pump.

3.2 CONNECTIONS

A. Install meters and gages adjacent to machines and equipment to allow space for service and maintenance of meters, gages, machines, and equipment.

3.3 ADJUSTING

A. After installation, calibrate meters according to manufacturer's written instructions.

B. Adjust faces of meters and gages to proper angle for best visibility.

END OF SECTION

SECTION 230523.12 – BALL VALVES FOR HVAC PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Bronze ball valves.
2. Steel ball valves.
3. Iron ball valves.

1.2 DEFINITIONS

A. CWP: Cold working pressure.

B. RPTFE: Reinforced polytetrafluoroethylene.

C. SWP: Steam working pressure.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of valve. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:

1. Protect internal parts against rust and corrosion.
2. Protect threads, flange faces, and weld ends.
3. Set ball valves open to minimize exposure of functional surfaces.

B. Use the following precautions during storage:

1. Maintain valve end protection.
2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use operating handles or stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each type of valve from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. ASME Compliance:

1. ASME B1.20.1 for threads for threaded-end valves.
2. ASME B16.1 for flanges on iron valves.
3. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
4. ASME B16.18 for cast copper solder-joint connections.
5. ASME B16.22 for wrought copper and copper alloy solder-joint connections.
6. ASME B16.34 for flanged and threaded end connections.
7. ASME B31.9 for building services piping valves.

B. Provide bronze valves made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.

C. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.

D. Valve Sizes: Same as upstream piping unless otherwise indicated.

E. Valve Actuator Types:

1. Hand Lever: For quarter-turn valves smaller than NPS 4.

F. Valves in Insulated Piping:

1. Provide 2-inch extended neck stems.
2. Extended operating handles with nonthermal-conductive covering material, and protective sleeves that allow operation of valves without breaking vapor seals or disturbing insulation.
3. Memory stops that are fully adjustable after insulation is applied.

2.3 BRONZE BALL VALVES

A. Bronze Ball Valves, Two Piece with Full Port and Bronze or Brass Trim, Threaded or Soldered Ends:

1. Standard: MSS SP-110.
2. SWP Rating: 150 psig.
3. CWP Rating: 600 psig.
4. Body Design: Two piece.
5. Body Material: Bronze.
6. Ends: Threaded or soldered.
7. Seats: PTFE.

8. Stem: Bronze.
9. Ball: Chrome-plated brass.
10. Port: Full.

B. Bronze Ball Valves, Two Piece with Full Port and Stainless Steel Trim, Threaded or Soldered Ends:

1. Standard: MSS SP-110.
2. SWP Rating: 150 psig.
3. CWP Rating: 600 psig.
4. Body Design: Two piece.
5. Body Material: Bronze.
6. Ends: Threaded or soldered.
7. Seats: PTFE.
8. Stem: Stainless steel.
9. Ball: Stainless steel, vented.
10. Port: Full.

2.4 STEEL BALL VALVES

A. Steel Ball Valves with Full Port and Stainless Steel Trim, Class 150:

1. Standard: MSS SP-72.
2. CWP Rating: 285 psig.
3. Body Design: Split body.
4. Body Material: Carbon steel, ASTM A216/A216M, Type WCB.
5. Ends: Flanged.
6. Seats: PTFE.
7. Stem: Stainless steel.
8. Ball: Stainless steel, vented.
9. Port: Full.

2.5 IRON BALL VALVES

A. Iron Ball Valves, Class 125:

1. Standard: MSS SP-72.
2. CWP Rating: 200 psig.
3. Body Design: Split body.
4. Body Material: ASTM A126, gray iron.
5. Ends: Flanged.
6. Seats: PTFE.
7. Stem: Stainless steel.
8. Ball: Stainless steel.
9. Port: Full.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.

C. Examine threads on valve and mating pipe for form and cleanliness.

D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.

E. Do not attempt to repair defective valves; replace with new valves. Remove defective valves from site.

3.2 INSTALLATION OF VALVES

A. Install valves with unions or flanges at each piece of equipment arranged to allow space for service, maintenance, and equipment removal without system shutdown.

B. Provide support of piping adjacent to valves such that no force is imposed upon valves.

C. Locate valves for easy access.

D. Install valves in horizontal piping with stem at or above center of pipe.

E. Install valves in position to allow full valve actuation movement.

F. Valve Tags: Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for valve tags and schedules.

G. Adhere to manufacturer's written installation instructions. When soldering or brazing valves, do not heat valves above maximum permitted temperature. Do not use solder with melting point temperature above valve manufacturer's recommended maximum.

3.3 ADJUSTING

A. Adjust or replace valve packing after piping systems have been tested and put into service, but before final adjusting and balancing. Replace valves exhibiting leakage.

3.4 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

A. If valves with specified SWP classes or CWP ratings are unavailable, provide the same types of valves with higher SWP classes or CWP ratings.

B. Select valves with the following end connections:

1. For Copper Tubing, NPS 2 and Smaller: Threaded ends except where solder-joint valve-end option or press-end option is indicated in valve schedules below.
2. For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
3. For Steel Piping, NPS 2 and Smaller: Threaded ends.
4. For Steel Piping, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.

3.5 CHILLED-WATER VALVE SCHEDULE

A. Pipe NPS 2 and Smaller: Bronze ball valves.

1. Valves may be provided with solder-joint ends instead of threaded ends.

B. Pipe NPS 2-1/2 and Larger:

1. Iron ball valves, Class 125.

a. Iron Valves, NPS 2-1/2 to NPS 4: May be provided with threaded ends instead of flanged ends.

2. Steel ball valves, Class 150.

3.6 HEATING-WATER VALVE SCHEDULE

A. Pipe NPS 2 and Smaller: Bronze ball valves.

B. Pipe NPS 2-1/2 and Larger:

1. Iron ball valves, Class 125.

a. Iron Valves, NPS 2-1/2 to NPS 4: May be provided with threaded ends instead of flanged ends.

2. Steel ball valves, Class 150.

END OF SECTION

SECTION 230523.13 - BUTTERFLY VALVES FOR HVAC PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Iron, single-flange (lug-type) butterfly valves.
2. Chainwheels.

1.2 DEFINITIONS

A. CWP: Cold working pressure.

B. EPDM: Ethylene propylene copolymer rubber.

C. NBR: ABS, Buna-N, or nitrile butadiene rubber.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Product Data: For each type of valve. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:

1. Protect internal parts against rust and corrosion.
2. Protect threads, flange faces, grooves, and weld ends.
3. Set butterfly valves closed or slightly open.

B. Use the following precautions during storage:

1. Maintain valve end protection.
2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each type of valve from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. ASME Compliance:

1. ASME B16.1 for flanges on iron valves.
2. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
3. ASME B31.9 for building services valves.

B. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.

C. Valve Sizes: Same as upstream piping unless otherwise indicated.

D. Valve Actuator Types:

1. Gear Actuator: For valves NPS 8 and larger.
2. Hand Lever: For valves NPS 6 and smaller.
3. Chainwheel: Device for attachment to gear, stem, or other actuator of size and with chain for mounting height, according to "Installation of Valves" Article.

E. Valves in Insulated Piping: Provide with 2-inch extended neck stems.

2.3 IRON, SINGLE-FLANGE (LUG-TYPE) BUTTERFLY VALVES

A. Iron, Single-Flange (Lug-Type) Butterfly Valves with Aluminum-Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Apollo Valves; a part of Aalberts Integrated Piping Systems
b. Center Line; a Crane Co. brand
c. DeZURIK
d. Hammond Valve
e. Jomar Valve
f. Kennedy Valve Company; a division of McWane, Inc.
g. Milwaukee Valve Company
h. Stockham; a Crane Co. brand
i. Viega LLC
j. WATTS

2. Standard: MSS SP-67, Type I.
3. CWP Rating: 150 psig.

4. Body Design: Single flange (lug type), suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
5. Body Material: ASTM A126, cast iron or ASTM A536, ductile iron.
6. Seat: EPDM or NBR.
7. Stem: One- or two-piece stainless steel.
8. Disc: Aluminum bronze.

2.4 CHAINWHEELS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Babbitt Steam Specialty Co.
2. Roto Hammer Industries; Rotork
3. Trumbull Industries

B. Description: Valve actuation assembly with sprocket rim, chain guides, chain, and attachment brackets for mounting chainwheels directly to hand wheels.

1. Sprocket Rim with Chain Guides: Ductile or cast iron, of type and size required for valve.
2. Chain: Hot-dip, galvanized steel, of size required to fit sprocket rim.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.

C. Examine mating flange faces for damage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.

D. Do not attempt to repair defective valves; replace with new valves. Remove defective valves from site.

3.2 INSTALLATION OF VALVES

A. Install valves with unions or flanges at each piece of equipment arranged to allow space for service, maintenance, and equipment removal without system shutdown.

B. Provide support of piping adjacent to valves such that no force is imposed upon valves.

C. Locate valves for easy access.

D. Install valves in horizontal piping with stem at or above center of pipe.

E. Install valves in position to allow full valve actuation movement.

F. Install chainwheels on manual actuators for butterfly valves NPS 4 and larger and more than 96 inches above floor. Extend chains to 60 inches above finished floor.

G. Valve Tags: Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for valve tags and schedules.

3.3 ADJUSTING

A. Adjust or replace valve packing after piping systems have been tested and put into service, but before final adjusting and balancing. If leakage cannot be repaired, replace valve.

3.4 HYDRONIC SYSTEMS VALVE SCHEDULE

A. Pipe NPS 2-1/2 and Larger:

1. Iron, Single-Flange Butterfly Valves, NPS 2-1/2 to NPS 12: Aluminum-bronze disc, 200 CWP, and EPDM or NBR seat.

END OF SECTION

SECTION 230523.15 – GATE VALVES FOR HVAC PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Iron gate valves.

1.2 DEFINITIONS

A. CWP: Cold working pressure.

B. NRS: Nonrising stem.

C. OS&Y: Outside screw and yoke.

D. RS: Rising stem.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of valve. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:

1. Protect internal parts against rust and corrosion.
2. Protect threads, flange faces, and weld ends.
3. Set gate valves closed to prevent rattling.

B. Use the following precautions during storage:

1. Maintain valve end protection.
2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels, stems, or other components as lifting or rigging points unless specifically indicated for this purpose in manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each type of valve from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. ASME Compliance:

1. ASME B1.20.1 for threads for threaded-end valves.
2. ASME B16.1 for flanges on iron valves.
3. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
4. ASME B16.34 for flanged, threaded, and welding ends.
5. ASME B31.9 for building services piping valves.

B. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.

C. Valve Sizes: Same as upstream piping unless otherwise indicated.

D. RS Valves in Insulated Piping: With 2-inch stem extensions.

2.3 IRON GATE VALVES

A. Iron Gate Valves, NRS, Class 125:

1. Description:

a. Standard: MSS SP-70, Type I.
b. NPS 2-1/2 to NPS 12, CWP Rating: 200 psig.
c. NPS 14 to NPS 24, CWP Rating: 150 psig.
d. Body Material: ASTM A126, gray iron with bolted bonnet.
e. Ends: Flanged.
f. Trim: Bronze.
g. Disc: Solid wedge.
h. Packing and Gasket: Asbestos free.

B. Iron Gate Valves, OS&Y, Class 125:

1. Description:

a. Standard: MSS SP-70, Type I.
b. NPS 2-1/2 to NPS 12, CWP Rating: 200 psig.
c. NPS 14 to NPS 24, CWP Rating: 150 psig.
d. Body Material: ASTM A126, gray iron with bolted bonnet.
e. Ends: Flanged.
f. Trim: Bronze.
g. Disc: Solid wedge.
h. Packing and Gasket: Asbestos free.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.

C. Examine threads on valve and mating pipe for form and cleanliness.

D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.

E. Do not attempt to repair defective valves; replace with new valves.

3.2 INSTALLATION OF VALVES

A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.

B. Provide support of piping adjacent to valves such that no force is imposed upon valves.

C. Locate valves for easy access and where not blocked by equipment, other piping, or building components.

D. Install valves so that stems are horizontal or slope upward from centerline of pipe.

E. Install valves in position that does not project into aisles or block access to other equipment.

F. Install valves in position to allow full stem and manual operator movement.

G. Verify that joints of each valve have been properly installed and sealed to ensure that there is no leakage or damage.

H. Install valve tags. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for valve tags and schedules.

I. Adhere to manufacturer's written installation instructions.

3.3 ADJUSTING

A. Adjust or replace valve packing after piping systems have been tested and put into service, but before final adjusting and balancing. Replace valves if persistent leaking occurs.

3.4 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

A. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.

END OF SECTION

SECTION 230529 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Metal pipe hangers and supports.
2. Trapeze pipe hangers.
3. Metal framing systems.
4. Thermal-hanger shield inserts.
5. Fastener systems.
6. Equipment supports.

B. Related Sections:

1. Section 055000 "Metal Fabrications" for structural-steel shapes and plates for trapeze hangers for pipe and equipment supports.
2. Section 230548.13 "Vibration Controls for HVAC" for vibration isolation devices.
3. Section 233113 "Metal Ducts" for duct hangers and supports.

1.3 DEFINITIONS

A. MSS: Manufacturers Standardization Society of The Valve and Fittings Industry Inc.

1.4 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design trapeze pipe hangers and equipment supports, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Structural Performance: Hangers and supports for HVAC piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.

1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

1.5 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Shop Drawings: Signed and sealed by a qualified professional engineer. Show fabrication and installation details and include calculations for the following; include Product Data for components:

1. Trapeze pipe hangers.
2. Metal framing systems.
3. Equipment supports.

D. Delegated-Design Submittal: For trapeze hangers indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Detail fabrication and assembly of trapeze hangers.
2. Design Calculations: Calculate requirements for designing trapeze hangers.

1.6 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Welding certificates.

1.7 QUALITY ASSURANCE

A. Structural Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.

PART 2 - PRODUCTS

2.1 METAL PIPE HANGERS AND SUPPORTS

A. Carbon-Steel Pipe Hangers and Supports:

1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
2. Galvanized Metallic Coatings: Pregalvanized or hot dipped.
3. Nonmetallic Coatings: Plastic coating, jacket, or liner.

4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

B. Copper Pipe Hangers:

1. Description: MSS SP-58, Types 1 through 58, copper-coated-steel, factory-fabricated components.
2. Hanger Rods: Continuous-thread rod, nuts, and washer made of copper-coated steel.

2.2 TRAPEZE PIPE HANGERS

A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

2.3 METAL FRAMING SYSTEMS

A. MFMA Manufacturer Metal Framing Systems:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

   a. Allied Tube & Conduit.
   b. B-line, an Eaton business.
   c. Flex-Strut Inc.
   d. GS Metals Corp.
   e. Thomas & Betts Corporation; A Member of the ABB Group.
   f. Unistrut; Part of Atkore International.
   g. Wesanco, Inc.

2. Description: Shop- or field-fabricated pipe-support assembly for supporting multiple parallel pipes.
3. Standard: MFMA-4.
4. Channels: Continuous slotted steel channel with inturned lips.
5. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
7. Metallic Coating: Hot-dipped galvanized.

2.4 THERMAL-HANGER SHIELD INSERTS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Carpenter & Paterson, Inc.
2. Clement Support Services.
3. ERICO International Corporation.

4. National Pipe Hanger Corporation.
5. PHS Industries, Inc.
6. Pipe Shields Inc.
7. Piping Technology & Products, Inc.
8. Rilco Manufacturing Co., Inc.
9. Value Engineered Products, Inc.

B. Insulation-Insert Material for Cold Piping: ASTM C 552, Type II cellular glass with 100-psig or ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength and vapor barrier.

C. Insulation-Insert Material for Hot Piping: ASTM C 552, Type II cellular glass with 100-psig or ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength.

D. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.

E. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.

F. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.5 FASTENER SYSTEMS

A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

B. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel anchors, for use in hardened portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

2.6 EQUIPMENT SUPPORTS

A. Description: Welded, shop- or field-fabricated equipment support made from structural carbon-steel shapes.

2.7 MISCELLANEOUS MATERIALS

A. Structural Steel: ASTM A 36/A 36M, carbon-steel plates, shapes, and bars; black and galvanized.

B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.

1. Properties: Nonstaining, noncorrosive, and nongaseous.
2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT INSTALLATION

A. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.

B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.

1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.
2. Field fabricate from ASTM A 36/A 36M, carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.

C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.

D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.

E. Fastener System Installation:

1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual.
2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.

F. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.

G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.

H. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.

I. Install lateral bracing with pipe hangers and supports to prevent swaying.

J. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.

K. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.

L. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.

M. Insulated Piping:

1. Attach clamps and spacers to piping.

   a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
   b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
   c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.

2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.

   a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.

   a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

4. Shield Dimensions for Pipe: Not less than the following:

   a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
   b. NPS 4: 12 inches long and 0.06 inch thick.
   c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.

5. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.2 EQUIPMENT SUPPORTS

A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.

B. Grouting: Place grout under supports for equipment and make bearing surface smooth.

C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.3 METAL FABRICATIONS

A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.

B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.

C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

3.4 ADJUSTING

A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.

B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.5 PAINTING

A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports as specified in Division 09 painting sections.

B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

3.6 HANGER AND SUPPORT SCHEDULE

A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.

B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.

C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.

D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.

E. Use carbon-steel pipe hangers and supports, metal trapeze pipe hangers, and metal framing systems and attachments for general service applications.

F. Use copper-plated pipe hangers and copper attachments for copper piping and tubing.

G. Use padded hangers for piping that is subject to scratching.

H. Use thermal-hanger shield inserts for insulated piping and tubing.

I. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
2. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
3. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.

J. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.

K. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.

L. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
5. C-Clamps (MSS Type 23): For structural shapes.
6. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
7. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
8. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
9. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
10. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:

    a. Light (MSS Type 31): 750 lb.
    b. Medium (MSS Type 32): 1500 lb.
    c. Heavy (MSS Type 33): 3000 lb.

11. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
12. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.

M. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.

N. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.

O. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.

P. Use powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where required in concrete construction.

END OF SECTION

SECTION 230548.13 - VIBRATION CONTROLS FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Elastomeric isolation pads.
2. Elastomeric isolation mounts.
3. Open spring isolators.
4. Housed-restrained-spring isolators.
5. Pipe-riser resilient supports.
6. Resilient pipe guides.
7. Spring hangers.
8. Vibration isolation equipment bases.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
2. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of vibration isolation device type required.

C. Shop Drawings:

1. Detail fabrication and assembly of equipment bases. Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.
2. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Show coordination of vibration isolation device installation for HVAC piping and equipment with other systems and equipment in the vicinity, including other supports and restraints, if any.

C. Qualification Data: For testing agency.

D. Welding certificates.

1.5 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

PART 2 - PRODUCTS

2.1 ELASTOMERIC ISOLATION PADS

A. Elastomeric Isolation Pads:

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Ace Mountings co., Inc.
b. California Dynamics Corporation.
c. Isolation Technology, Inc.
d. Kinetics Noise Control, Inc.
e. Mason Industries, Inc.
f. Vibration Elininator Co., Inc.
g. Vibration Isolation.
h. Vibration Mountings & Controls, Inc.

2. Fabrication: Single or multiple layers of sufficient durometer stiffness for uniform loading over pad area.
3. Size: Factory or field cut to match requirements of supported equipment.
4. Pad Material: Oil and water resistant with elastomeric properties.
5. Surface Pattern: Smooth pattern.
6. Infused nonwoven cotton or synthetic fibers.
7. Load-bearing metal plates adhered to pads.

2.2 ELASTOMERIC ISOLATION MOUNTS

A. Double-Deflection, Elastomeric Isolation Mounts:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Ace Mountings Co., Inc.
    b. California Dynamics Corporation.
    c. Isolation Technology, Inc.
    d. Kinetics Noise Control, Inc.
    e. Mason Industries, Inc.
    f. Vibration Eliminator Co., Inc.
    g. Vibration Isolation.
    h. Vibration Mountings & Controls, Inc.

2. Mounting Plates:

    a. Top Plate: Encapsulated steel load transfer top plates, factory drilled and threaded.
    b. Baseplate: Encapsulated steel bottom plates with holes provided for anchoring to support structure.

3. Elastomeric Material: Molded, oil-resistant rubber, neoprene, or other elastomeric material.

2.3 OPEN-SPRING ISOLATORS

A. Freestanding, Laterally Stable, Open-Spring Isolators:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Ace Mountings Co., Inc.
    b. California Dynamics Corporation.
    c. Isolation Technology, Inc.
    d. Kinetics Noise Control, Inc.
    e. Mason Industries, Inc.
    f. Vibration Eliminator Co., Inc.
    g. Vibration Isolation.
    h. Vibration Mountings & Controls, Inc.

2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
6. Baseplates: Factory-drilled steel plate for bolting to structure with an elastomeric isolator pad attached to the underside. Baseplates shall limit floor load to 500 psig.

7. Top Plate and Adjustment Bolt: Threaded top plate with adjustment bolt and cap screw to fasten and level equipment.

2.4 HOUSED-RESTRAINED-SPRING ISOLATORS

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Ace Mountings Co., Inc.
    b. California Dynamics Corporation.
    c. Isolation Technology, Inc.
    d. Kinetics Noise Control, Inc.
    e. Mason Industries, Inc.
    f. Vibration Eliminator Co., Inc.
    g. Vibration Isolation.
    h. Vibration Mountings & Controls, Inc.

B. Freestanding, Steel, Open-Spring Isolators with Vertical-Limit Stop Restraint in Two-Part Telescoping Housing:

1. Two-Part Telescoping Housing: A steel top and bottom frame separated by an elastomeric material and enclosing the spring isolators. Housings are equipped with adjustable snubbers to limit vertical movement.

    a. Drilled base housing for bolting to structure with an elastomeric isolator pad attached to the underside. Bases shall limit floor load to 500 psig.
    b. Threaded top housing with adjustment bolt and cap screw to fasten and level equipment.

2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.

2.5 PIPE-RISER RESILIENT SUPPORT

A. Description: All-directional, acoustical pipe anchor consisting of two steel tubes separated by a minimum 1/2-inch-thick neoprene.

1. Vertical-Limit Stops: Steel and neoprene vertical-limit stops arranged to prevent vertical travel in both directions.
2. Maximum Load Per Support: 500 psig on isolation material providing equal isolation in all directions.

2.6 RESILIENT PIPE GUIDES

A. Description: Telescopic arrangement of two steel tubes or post and sleeve arrangement separated by a minimum 1/2-inch-thick neoprene.

1. Factory-Set Height Guide with Shear Pin: Shear pin shall be removable and reinsertable to allow for selection of pipe movement. Guides shall be capable of motion to meet location requirements.

2.7 SPRING HANGERS

A. Combination Coil-Spring and Elastomeric-Insert Hanger with Spring and Insert in Compression:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

   a. Ace Mountings Co., Inc.
   b. California Dynamics Corporation.
   c. Isolation Technology, Inc.
   d. Kinetics Noise Control, Inc.
   e. Mason Industries, Inc.
   f. Vibration Eliminator Co., Inc.
   g. Vibration Isolation.
   h. Vibration Mountings & Controls, Inc.

2. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
3. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
4. Minimum Additional Travel: 50 percent of the required deflection at rated load.
5. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
6. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
7. Elastomeric Element: Molded, oil-resistant rubber or neoprene. Steel-washer-reinforced cup to support spring and bushing projecting through bottom of frame.
8. Adjustable Vertical Stop: Steel washer with neoprene washer "up-stop" on lower threaded rod.
9. Self-centering hanger rod cap to ensure concentricity between hanger rod and support spring coil.

2.8 VIBRATION ISOLATION EQUIPMENT BASES

A. Concrete Inertia Base: Factory-fabricated, welded, structural-steel bases and rails ready for placement of cast-in-place concrete.

1. Design Requirements: Lowest possible mounting height with not less than 1-inch clearance above the floor. Include equipment anchor bolts and auxiliary motor slide bases or rails.

   a. Include supports for suction diffusers for pumps.

2. Structural Steel: Steel shapes, plates, and bars complying with ASTM A 36/A 36M. Bases shall have shape to accommodate supported equipment.
3. Support Brackets: Factory-welded steel brackets on frame for outrigger isolation mountings and to provide for anchor bolts and equipment support.
4. Fabrication: Fabricate steel templates to hold equipment anchor-bolt sleeves and anchors in place during placement of concrete. Obtain anchor-bolt templates from supported equipment manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and equipment to receive vibration isolation control devices for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 VIBRATION CONTROL DEVICE INSTALLATION

A. Coordinate the location of embedded connection hardware with supported equipment attachment and mounting points and with requirements for concrete reinforcement and formwork specified in Section 033000 "Cast-in-Place Concrete."

B. Installation of vibration isolators must not cause any change of position of equipment, piping, or ductwork resulting in stresses or misalignment.

3.3 VIBRATION ISOLATION EQUIPMENT BASES INSTALLATION

A. Coordinate the location of embedded connection hardware with supported equipment attachment and mounting points and with requirements for concrete reinforcement and formwork specified in Section 033000 "Cast-in-Place Concrete."

END OF SECTION

SECTION 230553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Equipment labels.
2. Warning signs and labels.
3. Pipe labels.
4. Valve tags.
5. Warning tags.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.

D. Valve numbering scheme.

E. Valve Schedules: For each piping system to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

A. Plastic Labels for Equipment:

1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
2. Letter Color: White.
3. Background Color: Black.
4. Maximum Temperature: Able to withstand temperatures up to 160 deg F.

5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
6. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
7. Fasteners: Stainless-steel rivets or self-tapping screws.
8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

B. Label Content: Include equipment's Drawing designation or unique equipment number.

C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number, and identify Drawing numbers where equipment is indicated (plans, details, and schedules) and the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

2.2 WARNING SIGNS AND LABELS

A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.

B. Letter Color: White.

C. Background Color: Red.

D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.

E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.

F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.

G. Fasteners: Stainless-steel rivets or self-tapping screws.

H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

I. Label Content: Include caution and warning information plus emergency notification instructions.

2.3 PIPE LABELS

A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction according to ASME A13.1.

B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.

C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.

D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings; also include pipe size and an arrow indicating flow direction.

1. Flow-Direction Arrows: Integral with piping system service lettering to accommodate both directions or as separate unit on each pipe label to indicate flow direction.
2. Lettering Size: Size letters according to ASME A13.1 for piping.

2.4 VALVE TAGS

A. Description: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.

1. Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
2. Fasteners: Brass wire-link chain or beaded chain or S-hook.

B. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.

1. Valve-tag schedule shall be included in operation and maintenance data.

2.5 WARNING TAGS

A. Description: Preprinted or partially preprinted accident-prevention tags of plasticized card stock with matte finish suitable for writing.

1. Size: Approximately 4 by 7 inches.
2. Fasteners: Brass grommet and wire.
3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
4. Color: Safety-yellow background with black lettering.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 GENERAL INSTALLATION REQUIREMENTS

A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.

B. Coordinate installation of identifying devices with locations of access panels and doors.

C. Install identifying devices before installing acoustical ceilings and similar concealment.

3.3 EQUIPMENT LABEL INSTALLATION

A. Install or permanently fasten labels on each major item of mechanical equipment.

B. Locate equipment labels where accessible and visible.

3.4 PIPE LABEL INSTALLATION

A. Pipe Label Locations: Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:

1. Near each valve and control device.
2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
3. Near penetrations and on both sides of through walls, floors, ceilings, and inaccessible enclosures.
4. At access doors, manholes, and similar access points that permit view of concealed piping.
5. Near major equipment items and other points of origination and termination.
6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.

B. Directional Flow Arrows: Arrows shall be used to indicate direction of flow in pipes, including pipes where flow is allowed in both directions.

C. Pipe Label Color Schedule:

1. Refrigerant Piping: White letters on a safety-blue background.
2. Hydronic Water Piping, Including Glycol Systems: White letters on a safety-green background.
3. Natural Gas Piping: Black letters on a safety-yellow background.
4. Condensate Drain Piping: White letters on a safety-green background.

3.5 VALVE-TAG INSTALLATION

A. Install tags on valves and control devices in piping systems, except check valves, valves within factory-fabricated equipment units, shutoff valves, faucets, convenience and lawn-watering hose

connections, and HVAC terminal devices and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.

B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:

1. Valve-Tag Size and Shape: 1-1/2 inches, round.

2. Valve-Tag Colors:

a. Toxic and Corrosive Fluids: Black letters on a safety-orange background.
b. Flammable Fluids: Black letters on a safety-yellow background.
c. Combustible Fluids: White letters on a safety-brown background.
d. Potable and Other Water: White letters on a safety-green background.
e. Defined by User: White letters on a safety-purple background, black letters on a safety-white background, white letters on a safety-gray background, and white letters on a safety-black background

3.6 WARNING-TAG INSTALLATION

A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION

SECTION 230593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Balancing Air Systems:

    a. Constant-volume air systems.
    b. Variable-air-volume systems.

2. Testing, Adjusting, and Balancing Equipment:

    a. Motors.
    b. Condensing units.
    c. Heat-transfer coils.

3. Testing, adjusting, and balancing existing systems and equipment.
4. Control system verification.

1.3 DEFINITIONS

A. AABC: Associated Air Balance Council.

B. BAS: Building automation systems.

C. NEBB: National Environmental Balancing Bureau.

D. TAB: Testing, adjusting, and balancing.

E. TABB: Testing, Adjusting, and Balancing Bureau.

F. TAB Specialist: An independent entity meeting qualifications to perform TAB work.

G. TDH: Total dynamic head.

1.4 PREINSTALLATION MEETINGS

A. TAB Conference: If requested by the Owner, conduct a TAB conference at Project site after approval of the TAB strategies and procedures plan to develop a mutual understanding of the details. Provide a minimum of 14 days' advance notice of scheduled meeting time and location.

1. Minimum Agenda Items:

a. The Contract Documents examination report.
b. The TAB plan.
c. Needs for coordination and cooperation of trades and subcontractors.
d. Proposed procedures for documentation and communication flow.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: Within 60 days of Contractor's Notice to Proceed, submit documentation that the TAB specialist and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article.

C. Contract Documents Examination Report: Within 90 days of Contractor's Notice to Proceed, submit the Contract Documents review report as specified in Part 3.

D. Strategies and Procedures Plan: Within 90 days of Contractor's Notice to Proceed, submit TAB strategies and step-by-step procedures as specified in "Preparation" Article.

E. System Readiness Checklists: Within 90 days of Contractor's Notice to Proceed, submit system readiness checklists as specified in "Preparation" Article.

F. Examination Report: Submit a summary report of the examination review required in "Examination" Article.

G. Certified TAB reports.

H. Sample report forms.

I. Instrument calibration reports, to include the following:

1. Instrument type and make.
2. Serial number.
3. Application.
4. Dates of use.
5. Dates of calibration.

1.6 QUALITY ASSURANCE

A. TAB Specialists Qualifications: Engage a TAB firm certified within the past 10 years by either AABC, NEBB, or TABB or a firm that has 10 years' experience with testing and balancing of mechanical systems.

B. Instrumentation Type, Quantity, Accuracy, and Calibration: Comply with requirements in ASHRAE 111, Section 4, "Instrumentation."

C. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6.7.2.3 - "System Balancing."

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems designs that may preclude proper TAB of systems and equipment.

B. Examine installed systems for balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are applicable for intended purpose and are accessible.

C. Examine the approved submittals for HVAC systems and equipment.

D. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems output, and statements of philosophies and assumptions about HVAC system and equipment controls.

E. Examine equipment performance data including fan and pump curves.

1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems - Duct Design." Compare results with the design data and installed conditions.

F. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.

G. Examine test reports specified in individual system and equipment Sections.

H. Examine HVAC equipment and verify that bearings are greased, belts are aligned and tight, filters are clean, and equipment with functioning controls is ready for operation.

I. Examine terminal units and verify that they are accessible and their controls are connected and functioning.

J. Examine heat-transfer coils for correct piping connections and for clean and straight fins.

K. Examine operating safety interlocks and controls on HVAC equipment.

L. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.2 PREPARATION

A. Prepare a TAB plan that includes the following:

1. Equipment and systems to be tested.
2. Strategies and step-by-step procedures for balancing the systems.
3. Instrumentation to be used.
4. Sample forms with specific identification for all equipment.

B. Perform system-readiness checks of HVAC systems and equipment to verify system readiness for TAB work. Include, at a minimum, the following:

1. Airside:

a. Duct systems are complete with terminals installed.
b. Volume and fire dampers are open and functional.
c. Clean filters are installed.
d. Fans are operating, free of vibration, and rotating in correct direction.
e. Variable-frequency controllers' startup is complete and safeties are verified.
f. Automatic temperature-control systems are operational.
g. Ceilings are installed.
h. Windows and doors are installed.
i. Suitable access to balancing devices and equipment is provided.

3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

A. Perform testing and balancing procedures on each system according to the procedures contained in AABC's "National Standards for Total System Balance", ASHRAE 111, NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems", or SMACNA's "HVAC Systems - Testing, Adjusting, and Balancing" and in this Section.

B. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary for TAB procedures.

1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
2. After testing and balancing, install test ports and duct access doors that comply with requirements in Section 233300 "Air Duct Accessories."

3. Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish according to Section 230713 "Duct Insulation," Section 230716 "HVAC Equipment Insulation," and Section 230719 "HVAC Piping Insulation."

C. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.

D. Take and report testing and balancing measurements in inch-pound (IP) units.

3.4 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Cross-check the summation of required outlet volumes with required fan volumes.

B. Prepare schematic diagrams of systems' "as-built" duct layouts.

C. For variable-air-volume systems, develop a plan to simulate diversity.

D. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.

E. Check airflow patterns from the outdoor-air louvers and dampers and the return- and exhaust-air dampers through the supply-fan discharge and mixing dampers.

F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.

G. Verify that motor starters are equipped with properly sized thermal protection.

H. Check dampers for proper position to achieve desired airflow path.

I. Check for airflow blockages.

J. Check condensate drains for proper connections and functioning.

K. Check for proper sealing of air-handling-unit components.

L. Verify that air duct system is sealed as specified in Section 233113 "Metal Ducts."

3.5 PROCEDURES FOR CONSTANT-VOLUME AIR SYSTEMS

A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.

1. Measure total airflow.

a. Set outside-air, return-air, and relief-air dampers for proper position that simulates minimum outdoor-air conditions.

b. Where duct conditions allow, measure airflow by Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses to obtain total airflow.
c. Where duct conditions are not suitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
d. If a reliable Pitot-tube traverse or coil traverse is not possible, measure airflow at terminals and calculate the total airflow.

2. Measure fan static pressures as follows:

a. Measure static pressure directly at the fan outlet or through the flexible connection.
b. Measure static pressure directly at the fan inlet or through the flexible connection.
c. Measure static pressure across each component that makes up the air-handling system.
d. Report artificial loading of filters at the time static pressures are measured.

3. Review Record Documents to determine variations in design static pressures versus actual static pressures. Calculate actual system-effect factors. Recommend adjustments to accommodate actual conditions.
4. Obtain approval from Owner for adjustment of fan speed higher or lower than indicated speed. Comply with requirements in HVAC Sections for air-handling units for adjustment of fans, belts, and pulley sizes to achieve indicated air-handling-unit performance.
5. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload occurs. Measure amperage in full-cooling, full-heating, economizer, and any other operating mode to determine the maximum required brake horsepower.

B. Adjust volume dampers for main duct, submain ducts, and major branch ducts to indicated airflows.

1. Measure airflow of submain and branch ducts.
2. Adjust submain and branch duct volume dampers for specified airflow.
3. Re-measure each submain and branch duct after all have been adjusted.

C. Adjust air inlets and outlets for each space to indicated airflows.

1. Set airflow patterns of adjustable outlets for proper distribution without drafts.
2. Measure inlets and outlets airflow.
3. Adjust each inlet and outlet for specified airflow.
4. Re-measure each inlet and outlet after they have been adjusted.

D. Verify final system conditions.

1. Re-measure and confirm that minimum outdoor, return, and relief airflows are within design. Readjust to design if necessary.
2. Re-measure and confirm that total airflow is within design.
3. Re-measure all final fan operating data, rpms, volts, amps, and static profile.
4. Mark all final settings.
5. Test system in economizer mode. Verify proper operation and adjust if necessary.
6. Measure and record all operating data.
7. Record final fan-performance data.

3.6 PROCEDURES FOR VARIABLE-AIR-VOLUME SYSTEMS

A. Adjust the variable-air-volume systems as follows:

1. Verify that the system static pressure sensor is located two-thirds of the distance down the duct from the fan discharge.
2. Verify that the system is under static pressure control.
3. Select the terminal unit that is most critical to the supply-fan airflow. Measure inlet static pressure, and adjust system static pressure control set point so the entering static pressure for the critical terminal unit is not less than the sum of the terminal-unit manufacturer's recommended minimum inlet static pressure plus the static pressure needed to overcome terminal-unit discharge system losses.
4. Calibrate and balance each terminal unit for maximum and minimum design airflow as follows:

    a. Adjust controls so that terminal is calling for maximum airflow. Some controllers require starting with minimum airflow. Verify calibration procedure for specific project.
    b. Measure airflow and adjust calibration factor as required for design maximum airflow. Record calibration factor.
    c. When maximum airflow is correct, balance the air outlets downstream from terminal units.
    d. Adjust controls so that terminal is calling for minimum airflow.
    e. Measure airflow and adjust calibration factor as required for design minimum airflow. Record calibration factor. If no minimum calibration is available, note any deviation from design airflow.
    f. On constant volume terminals, in critical areas where room pressure is to be maintained, verify that the airflow remains constant over the full range of full cooling to full heating. Note any deviation from design airflow or room pressure.

5. After terminals have been calibrated and balanced, test and adjust system for total airflow. Adjust fans to deliver total design airflows within the maximum allowable fan speed listed by fan manufacturer.

    a. Set outside-air, return-air, and relief-air dampers for proper position that simulates minimum outdoor-air conditions.
    b. Set terminals for maximum airflow. If system design includes diversity, adjust terminals for maximum and minimum airflow so that connected total matches fan selection and simulates actual load in the building.
    c. Where duct conditions allow, measure airflow by Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses to obtain total airflow.
    d. Where duct conditions are not suitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
    e. If a reliable Pitot-tube traverse or coil traverse is not possible, measure airflow at terminals and calculate the total airflow.

6. Measure fan static pressures as follows:

    a. Measure static pressure directly at the fan outlet or through the flexible connection.
    b. Measure static pressure directly at the fan inlet or through the flexible connection.
    c. Measure static pressure across each component that makes up the air-handling system.

d. Report any artificial loading of filters at the time static pressures are measured.

7. Set final return and outside airflow to the fan while operating at maximum return airflow and minimum outdoor airflow.

   a. Balance the return-air ducts and inlets the same as described for constant-volume air systems.
   b. Verify that terminal units are meeting design airflow under system maximum flow.

8. Re-measure the inlet static pressure at the most critical terminal unit and adjust the system static pressure set point to the most energy-efficient set point to maintain the optimum system static pressure. Record set point and give to controls contractor.
9. Verify final system conditions as follows:

   a. Re-measure and confirm that minimum outdoor, return, and relief airflows are within design. Readjust to match design if necessary.
   b. Re-measure and confirm that total airflow is within design.
   c. Re-measure final fan operating data, rpms, volts, amps, and static profile.
   d. Mark final settings.
   e. Test system in economizer mode. Verify proper operation and adjust if necessary. Measure and record all operating data.
   f. Verify tracking between supply and return fans.

3.7 PROCEDURES FOR MOTORS

A. Motors 1/2 HP and Larger: Test at final balanced conditions and record the following data:

   1. Manufacturer's name, model number, and serial number.
   2. Motor horsepower rating.
   3. Motor rpm.
   4. Phase and hertz.
   5. Nameplate and measured voltage, each phase.
   6. Nameplate and measured amperage, each phase.
   7. Starter size and thermal-protection-element rating.
   8. Service factor and frame size.

B. Motors Driven by Variable-Frequency Controllers: Test manual bypass of controller to prove proper operation.

3.8 PROCEDURES FOR AIR-COOLED CONDENSING UNITS

A. Verify proper rotation of fans.

B. Measure entering- and leaving-air temperatures.

C. Record fan and motor operating data.

3.9 PROCEDURES FOR HEAT-TRANSFER COILS

A. Measure, adjust, and record the following data for each electric heating coil:

1. Nameplate data
2. Airflow.
3. Entering- and leaving-air temperature at full load.
4. Air pressure drop.
5. Voltage and amperage input of each phase at full load.
6. Calculated kilowatt at full load.
7. Fuse or circuit-breaker rating for overload protection.

B. Measure, adjust, and record the following data for each refrigerant coil:

1. Dry-bulb temperature of entering and leaving air.
2. Wet-bulb temperature of entering and leaving air.
3. Airflow.

3.10 PROCEDURES FOR TEMPERATURE MEASUREMENTS

A. During TAB, report the need for adjustment in temperature regulation within the automatic temperature-control system.

B. Measure indoor wet- and dry-bulb temperatures every other hour for a period of two successive eight-hour days, in each separately controlled zone, to prove correctness of final temperature settings. Measure when the building or zone is in occupied mode.

C. Measure outside-air, wet- and dry-bulb temperatures.

3.11 CONTROLS VERIFICATION

A. In conjunction with system balancing, perform the following:

1. Verify temperature control system is operating within the design limitations.
2. Confirm that the sequences of operation are in compliance with Contract Documents.
3. Verify that controllers are calibrated and function as intended.
4. Verify that controller set points are as indicated.
5. Verify the operation of lockout or interlock systems.
6. Verify the operation of valve and damper actuators.
7. Verify that controlled devices are properly installed and connected to correct controller.
8. Verify that controlled devices travel freely and are in position indicated by controller: open, closed, or modulating.
9. Verify location and installation of sensors to ensure that they sense only intended temperature, humidity, or pressure.

B. Reporting: Include a summary of verifications performed, remaining deficiencies, and variations from indicated conditions.

3.12 TOLERANCES

A. Set HVAC system's airflow rates and water flow rates within the following tolerances:

1. Supply, Return, and Exhaust Fans and Equipment with Fans: Plus or minus 10 percent.
2. Air Outlets and Inlets: Plus or minus 10 percent.
3. Heating-Water Flow Rate: Plus or minus 10 percent.
4. Cooling-Water Flow Rate: Plus or minus 10 percent.

B. Maintaining pressure relationships as designed shall have priority over the tolerances specified above.

3.13 PROGRESS REPORTING

A. Initial Construction-Phase Report: Based on examination of the Contract Documents as specified in "Examination" Article, prepare a report on the adequacy of design for systems balancing devices. Recommend changes and additions to systems balancing devices to facilitate proper performance measuring and balancing. Recommend changes and additions to HVAC systems and general construction to allow access for performance measuring and balancing devices.

B. Status Reports: Prepare biweekly progress reports to describe completed procedures, procedures in progress, and scheduled procedures. Include a list of deficiencies and problems found in systems being tested and balanced. Prepare a separate report for each system and each building floor for systems serving multiple floors.

3.14 FINAL REPORT

A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.

1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
2. Include a list of instruments used for procedures, along with proof of calibration.
3. Certify validity and accuracy of field data.

B. Final Report Contents: In addition to certified field-report data, include the following:

1. Pump curves.
2. Fan curves.
3. Manufacturers' test data.
4. Field test reports prepared by system and equipment installers.
5. Other information relative to equipment performance; do not include Shop Drawings and Product Data.

C. General Report Data: In addition to form titles and entries, include the following data:

1. Title page.
2. Name and address of the TAB specialist.
3. Project name.

4. Project location.
5. Architect's name and address.
6. Engineer's name and address.
7. Contractor's name and address.
8. Report date.
9. Signature of TAB supervisor who certifies the report.
10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
11. Summary of contents including the following:

    a. Indicated versus final performance.
    b. Notable characteristics of systems.
    c. Description of system operation sequence if it varies from the Contract Documents.

12. Nomenclature sheets for each item of equipment.
13. Data for terminal units, including manufacturer's name, type, size, and fittings.
14. Notes to explain why certain final data in the body of reports vary from indicated values.
15. Test conditions for fans and pump performance forms including the following:

    a. Settings for outdoor-, return-, and exhaust-air dampers.
    b. Conditions of filters.
    c. Cooling coil, wet- and dry-bulb conditions.
    d. Fan drive settings including settings and percentage of maximum pitch diameter.
    e. Settings for supply-air, static-pressure controller.
    f. Other system operating conditions that affect performance.

D. System Diagrams: Include schematic layouts of air and hydronic distribution systems. Present each system with single-line diagram and include the following:

1. Quantities of outdoor, supply, return, and exhaust airflows.
2. Water flow rates.
3. Duct, outlet, and inlet sizes.
4. Pipe and valve sizes and locations.
5. Terminal units.
6. Position of balancing devices.

E. Air-Handling-Unit Test Reports: For air-handling units with coils, include the following:

1. Unit Data:

    a. Unit identification.
    b. Location.
    c. Make and type.
    d. Model number and unit size.
    e. Manufacturer's serial number.
    f. Unit arrangement and class.
    g. Discharge arrangement.
    h. Sheave make, size in inches, and bore.
    i. Center-to-center dimensions of sheave and amount of adjustments in inches.
    j. Number, make, and size of belts.
    k. Number, type, and size of filters.

2. Motor Data:

    a. Motor make, and frame type and size.
    b. Horsepower and rpm.
    c. Volts, phase, and hertz.
    d. Full-load amperage and service factor.
    e. Sheave make, size in inches, and bore.
    f. Center-to-center dimensions of sheave and amount of adjustments in inches.

3. Test Data (Indicated and Actual Values):

    a. Total airflow rate in cfm.
    b. Total system static pressure in inches wg.
    c. Fan rpm.
    d. Discharge static pressure in inches wg.
    e. Filter static-pressure differential in inches wg.
    f. Preheat-coil static-pressure differential in inches wg.
    g. Cooling-coil static-pressure differential in inches wg.
    h. Heating-coil static-pressure differential in inches wg.
    i. Outdoor airflow in cfm.
    j. Return airflow in cfm.
    k. Outdoor-air damper position.
    l. Return-air damper position.

F. Apparatus-Coil Test Reports:

1. Coil Data:

    a. System identification.
    b. Location.
    c. Coil type.
    d. Number of rows.
    e. Fin spacing in fins per inch o.c.
    f. Make and model number.
    g. Face area in sq. ft.
    h. Circuiting arrangement.

2. Test Data (Indicated and Actual Values):

    a. Airflow rate in cfm.
    b. Average face velocity in fpm.
    c. Air pressure drop in inches wg.
    d. Outdoor-air, wet- and dry-bulb temperatures in deg F.
    e. Return-air, wet- and dry-bulb temperatures in deg F.
    f. Entering-air, wet- and dry-bulb temperatures in deg F.
    g. Leaving-air, wet- and dry-bulb temperatures in deg F.
    h. Refrigerant expansion valve and refrigerant types.
    i. Refrigerant suction pressure in psig.
    j. Refrigerant suction temperature in deg F.

G. Electric Coil Test Reports: In addition to manufacturer's factory startup equipment reports, include the following:

1. Unit Data:

    a. System identification.
    b. Location.
    c. Coil identification.
    d. Capacity in Btu/h.
    e. Number of stages.
    f. Connected volts, phase, and hertz.
    g. Rated amperage.
    h. Airflow rate in cfm.
    i. Face area in square feet.
    j. Minimum face velocity in fpm.

2. Test Data (Indicated and Actual Values):

    a. Total airflow rate in cfm.
    b. Entering-air temperature in deg F.
    c. Leaving-air temperature in deg F.
    d. Heat input in Btu/h.
    e. Air velocity in fpm.
    f. Motor voltage at each connection.
    g. Motor amperage for each phase.

H. Fan Test Reports: For supply, return, transfer, and exhaust fans, include the following:

1. Fan Data:

    a. System identification.
    b. Location.
    c. Make and type.
    d. Model number and size.
    e. Manufacturer's serial number.
    f. Arrangement and class.
    g. Sheave make, size in inches, and bore.
    h. Center-to-center dimensions of sheave and amount of adjustments in inches.

2. Motor Data:

    a. Motor make, and frame type and size.
    b. Horsepower and rpm.
    c. Volts, phase, and hertz.
    d. Full-load amperage and service factor.
    e. Sheave make, size in inches, and bore.
    f. Center-to-center dimensions of sheave, and amount of adjustments in inches.
    g. Number, make, and size of belts.

3. Test Data (Indicated and Actual Values):

    a. Total airflow rate in cfm.
    b. Total system static pressure in inches wg.
    c. Fan rpm.
    d. Discharge static pressure in inches wg.

e. Suction static pressure in inches wg.

I. Round and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:

1. Report Data:

a. System and air-handling-unit number.
b. Location and zone.
c. Traverse air temperature in deg F.
d. Duct static pressure in inches wg.
e. Duct size in inches.
f. Duct area in sq. ft.
g. Indicated airflow rate in cfm.
h. Indicated velocity in fpm.
i. Actual airflow rate in cfm.
j. Actual average velocity in fpm.
k. Barometric pressure in psig.

J. Air-Terminal-Device Reports:

1. Unit Data:

a. System and air-handling unit identification.
b. Location and zone.
c. Apparatus used for test.
d. Area served.
e. Make.
f. Number from system diagram.
g. Type and model number.
h. Size.

2. Test Data (Indicated and Actual Values):

a. Airflow rate in cfm.
b. Preliminary airflow rate as needed in cfm.
c. Final airflow rate in cfm.
d. Space temperature in deg F.

K. Air-to-Air Energy-Recovery Unit Reports:

1. Unit Data:

a. Unit identification.
b. Location.
c. Service.
d. Make and type.
e. Model and serial numbers.

2. Motor Data (For Each Motor):

a. Make and frame type and size.

b. Horsepower and rpm.
c. Volts, phase, and hertz.
d. Full load amperage and service factor.

3. If fans are an integral part of the unit, include the following for each fan:

a. Make and type.
b. Arrangement and size.
c. Sheave make, size in inches, and bore.
d. Sheave dimensions, center-to-center, and amount of adjustments in inches.

4. Test Data (Indicated and Actual Values):

a. Total exhaust airflow rate in cfm.
b. Total outside airflow rate in cfm.
c. Total exhaust fan static pressure in inches wg.
d. Total outside-air fan static pressure in inches wg.
e. Pressure drop on each side of recovery wheel in inches wg.
f. Exhaust air temperature entering in deg F.
g. Exhaust air temperature leaving in deg F.
h. Outside-air temperature entering in deg F.
i. Outside-air temperature leaving in deg F.

L. System-Coil Reports: Electric unit heaters and cabinet unit heaters.

1. Unit Data:

a. System unit identification.
b. Location and zone.
c. Room or riser served.
d. Coil make and size.
e. Connected volts, phase, and hertz.
f. Rated amperage.

2. Test Data (Indicated and Actual Values):

a. Airflow rate in cfm.
b. Heat input in Btu/h.
c. Entering-air temperature in deg F.
d. Leaving-air temperature in deg F.
e. Motor voltage.
f. Motor amperage.

M. Instrument Calibration Reports:

1. Report Data:

a. Instrument type and make.
b. Serial number.
c. Application.
d. Dates of use.
e. Dates of calibration.

3.15 VERIFICATION OF TAB REPORT

A. The TAB specialist's test and balance engineer shall conduct the inspection in the presence of Owner.

B. Owner shall randomly select measurements, documented in the final report, to be rechecked. Rechecking shall be limited to either 10 percent of the total measurements recorded or the extent of measurements that can be accomplished in a normal 8-hour business day.

C. If rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."

D. If the number of "FAILED" measurements is greater than 10 percent of the total measurements checked during the final inspection, the testing and balancing shall be considered incomplete and shall be rejected.

E. If TAB work fails, proceed as follows:

1. TAB specialists shall recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes; resubmit the final report and request a second final inspection.
2. If the second final inspection also fails, Owner may contract the services of another TAB specialist to complete TAB work according to the Contract Documents and deduct the cost of the services from the original TAB specialist's final payment.
3. If the second verification also fails, Owner may contact AABC Headquarters regarding the AABC National Performance Guaranty.

F. Prepare test and inspection reports.

END OF SECTION

SECTION 230713 - DUCT INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes insulating the following duct services:

1. Indoor concealed supply and outdoor air.
2. Indoor concealed return located in unconditioned space.

B. Related Sections:

1. Section 230719 "HVAC Piping Insulation."

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory- and field-applied if any). On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Insulation Schedule: Identify type of material, thickness, vapor barrier provision, and where required, field-applied jacket to be provided for each system application.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For qualified Installer.

C. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.

D. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.

B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.

1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 230529 "Hangers and Supports for HVAC Piping and Equipment."

B. Coordinate clearance requirements with duct Installer for duct insulation application. Before preparing ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.8 SCHEDULING

A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.

B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

A. Comply with requirements in "Duct Insulation Schedule, General," "Indoor Duct and Plenum Insulation Schedule" articles for where insulating materials shall be applied.

B. Products shall not contain asbestos, lead, mercury, or mercury compounds.

C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.

D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.

E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.

F. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type III with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:

a. CertainTeed Corporation; SoftTouch Duct Wrap.
b. Johns Manville; a Berkshire Hathaway company; Microlite.
c. Knauf Insulation; Friendly Feel Duct Wrap with ECOSE Technology.
d. Manson Insulation Inc.; Allen Wrap.
e. Owens Corning; SOFTR All-Service Duct Wrap.

G. Mineral-Fiber Board Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 612, Type IA or Type IB. For duct and plenum applications, provide insulation with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:

a. CertainTeed Corporation; Commercial Board.
b. Johns Manville; a Berkshire Hathaway company; 800 Series Spin-Glas.
c. Knauf Insulation; Insulation Board with ECOSE Technology.
d. Manson Insulation Inc.; AK Board.
e. Owens Corning; Fiberglas 700 Series.

2.2 ADHESIVES

A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.

B. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.

1. Fiberglass adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

D. FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.

1. Adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.3 MASTICS

A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.

1. VOC Content: 300 g/L or less.

B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below ambient services.

1. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm at 43-mil dry film thickness.
2. Service Temperature Range: Minus 20 to plus 180 deg F.
3. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
4. Color: White.

C. Breather Mastic: Water based; suitable for indoor and outdoor use on above ambient services.

1. Water-Vapor Permeance: ASTM F 1249, 1.8 perms at 0.0625-inch dry film thickness.
2. Service Temperature Range: Minus 20 to plus 180 deg F.
3. Solids Content: 60 percent by volume and 66 percent by weight.
4. Color: White.

2.4 LAGGING ADHESIVES

A. Description: Comply with MIL-A-3316C, Class I, Grade A and shall be compatible with insulation materials, jackets, and substrates.

1. Adhesives shall have a VOC content of 50 g/L or less.
2. Fire-resistant, water-based lagging adhesive and coating for use indoors to adhere fire-resistant lagging cloths over duct insulation.
3. Service Temperature Range: 0 to plus 180 deg F.
4. Color: White.

2.5 SEALANTS

A. FSK Sealants:

1. Materials shall be compatible with insulation materials, jackets, and substrates.
2. Fire- and water-resistant, flexible, elastomeric sealant.
3. Service Temperature Range: Minus 40 to plus 250 deg F.
4. Color: Aluminum.
5. Sealant shall have a VOC content of 420 g/L or less.

B. PVC Jacket Flashing Sealants

1. Materials are compatible with insulation materials, jackets, and substrates.

2. Fire- and water-resistant, flexible, elastomeric sealant.
3. Service Temperature Range: Minus 40 to plus 250 deg F.
4. Color: White.

2.6 FACTORY-APPLIED JACKETS

A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:

1. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.

2.7 FIELD-APPLIED JACKETS

A. Field-applied jackets comply with ASTM C921, Type I, unless otherwise indicated.

B. Metal Jacket:

1. Aluminum Jacket: Comply with ASTM B209, Alloy 3003, 3005, 3105, or 5005, Temper H-14.

a. Sheet and roll stock ready for shop or field sizing.
b. Finish and thickness are indicated in field-applied jacket schedules.
c. Moisture Barrier for Outdoor Applications: 3-mil-thick, heat-bonded polyethylene and kraft paper.

C. Self-Adhesive Outdoor Jacket (Asphaltic): 60-mil-thick, laminated vapor barrier and waterproofing membrane for installation over insulation located aboveground outdoors; consisting of a rubberized bituminous resin on a crosslaminated polyethylene film covered with stucco-embossed aluminum-foil facing.

2.8 TAPES

A. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.

1. Width: 3 inches.
2. Thickness: 6.5 mils.
3. Adhesion: 90 ounces force/inch in width.
4. Elongation: 2 percent.
5. Tensile Strength: 40 lbf/inch in width.
6. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.

2.9 SECUREMENTS

A. Bands:

1. Stainless Steel: ASTM A 167 or ASTM A 240/A 240M, Type 304 or Type 316; 0.015 inch thick, 1/2 inch wide with wing seal or closed seal.

2. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 1/2 inch wide with wing seal or closed seal.
3. Springs: Twin spring set constructed of stainless steel with ends flat and slotted to accept metal bands. Spring size determined by manufacturer for application.

B. Insulation Pins and Hangers:

1. Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated.

2. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.

3. Self-Sticking Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:

   a. Baseplate: Galanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
   b. Spindle: Copper- or zinc-coated, low-carbon steel, fully annealed, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
   c. Adhesive-backed base with a peel-off protective cover.

4. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch- thick, galvanized-steel sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.

   a. Protect ends with capped self-locking washers incorporating a spring steel insert to ensure permanent retention of cap in exposed locations.

C. Staples: Outward-clinching insulation staples, nominal 3/4-inch- wide, stainless steel or Monel.

D. Wire: 0.062-inch soft-annealed, stainless steel.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.

1. Verify that systems to be insulated have been tested and are free of defects.
2. Verify that surfaces to be insulated are clean and dry.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

3.3 GENERAL INSTALLATION REQUIREMENTS

A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of ducts and fittings.

B. Install insulation materials, vapor barriers or retarders, jackets, and thicknesses required for each item of duct system as specified in insulation system schedules.

C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.

D. Install insulation with longitudinal seams at top and bottom of horizontal runs.

E. Install multiple layers of insulation with longitudinal and end seams staggered.

F. Keep insulation materials dry during application and finishing. Replace insulation materials that get wet during storage or in the installation process before being properly covered and sealed in accordance with Contract Documents.

G. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.

H. Install insulation with least number of joints practical.

I. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.

1. Install insulation continuously through hangers and around anchor attachments.
2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.

J. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.

K. Install insulation with factory-applied jackets as follows:

1. Draw jacket tight and smooth.
2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.

3. Overlap jacket longitudinal seams at least 1-1/2 inches. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.

    a. For below ambient services, apply vapor-barrier mastic over staples.

4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct flanges and fittings.

L. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.

M. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

N. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

3.4 PENETRATIONS

A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.

1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
4. Seal jacket to roof flashing with flashing sealant.

B. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.

1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
4. Seal jacket to wall flashing with flashing sealant.

C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.

D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.

1. Comply with requirements in Section 078413 "Penetration Firestopping."

E. Insulation Installation at Floor Penetrations:

1. Duct: For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

3.5 INSTALLATION OF MINERAL-FIBER INSULATION

A. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.

1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
3. Install cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:

    a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    d. Do not overcompress insulation during installation.
    e. Impale insulation over pins and attach speed washers.
    f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.

4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.

    a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
    b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.

5. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.

6. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch- wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

B. Board Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.

1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:

    a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    b. On duct sides with dimensions larger than 18 inches, space pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    d. Do not overcompress insulation during installation.
    e. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.

4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.

    a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
    b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.

5. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Groove and score insulation to fit as closely as possible to outside and inside radius of elbows. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
6. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch- wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

3.6 FIELD-APPLIED JACKET INSTALLATION

A. Where FSK jackets are indicated, install as follows:

1. Draw jacket material smooth and tight.
2. Install lap or joint strips with same material as jacket.
3. Secure jacket to insulation with manufacturer's recommended adhesive.
4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch-wide joint strips at end joints.
5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.

B. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless steel bands 12 inches o.c. and at end joints.

3.7 FINISHES

A. Insulation with ASJ, Glass-Cloth, or other Paintable Jacket Material: Paint jacket with paint system identified below and as specified in Division 09 painting Sections.

1. Flat Acrylic Finish: Two finish coats over a primer that is compatible jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.

a. Finish Coat Material: Interior, flat, latex-emulsion size.

B. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.

C. Do not field paint aluminum or stainless-steel jackets.

3.8 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Tests and Inspections:

1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location for each duct system defined in the "Duct Insulation Schedule, General" Article.

C. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

3.9 DUCT INSULATION SCHEDULE, GENERAL

A. Plenums and Ducts Requiring Insulation:

1. Indoor, supply and outdoor air.

2. Indoor, return located in unconditioned space.
3. Outdoor supply air.
4. Outdoor return/exhaust air.

B. Items Not Insulated:

1. Factory-insulated flexible ducts.
2. Factory-insulated plenums and casings.
3. Flexible connectors.
4. Vibration-control devices.
5. Factory-insulated access panels and doors.

3.10 INDOOR DUCT AND PLENUM INSULATION SCHEDULE

A. Concealed, round and flat-oval, supply-air duct insulation shall be the following:

1. Mineral-Fiber Blanket: 1-1/2 inches thick and 0.75-lb/cu. ft. nominal density.

B. Round and flat-oval, return-air duct insulation shall be the following:

1. Mineral-Fiber Blanket: 1-1/2 inches thick and 0.75-lb/cu. ft. nominal density.

C. Round and flat-oval, outdoor-air duct insulation shall be the following:

1. Mineral-Fiber Blanket: 1-1/2 inches thick and 0.75-lb/cu. ft. nominal density.

D. Rectangular, supply-air duct insulation shall be one of the following:

1. Mineral-Fiber Blanket: 2 inches thick and 0.75-lb/cu. ft. nominal density.

2. Mineral-Fiber Board: 1-1/2 inches thick and 2-lb/cu. ft. nominal density.

E. Rectangular, return-air duct insulation shall be the following:

1. Mineral-Fiber Board: 1-1/2 inches thick and 2-lb/cu. ft. nominal density.

F. Rectangular, outdoor-air duct insulation shall be the following:

1. Mineral-Fiber Board: 2 inches thick and 2-lb/cu. ft. nominal density.

3.11 ABOVEGROUND, OUTDOOR DUCT AND PLENUM INSULATION SCHEDULE

A. Insulation materials and thicknesses are identified below. If more than one material is listed for a duct system, selection from materials listed is Contractor’s option.

B. Exposed rectangular, supply and exhaust-air duct insulation shall pitch to prevent ice/snow build up. Insulation shall be one of the following:

1. Mineral-Fiber Board: 2 inches thick and 2-lb/cu. ft. nominal density.
2. Polyisocyanurate Foam Board: 2 inches thick (R-14) with foil facing both sides.

3.12 OUTDOOR, FIELD-APPLIED JACKET SCHEDULE

A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.

B. If more than one material is listed, selection from materials listed is Contractor's option.

C. Ducts and Plenums, Exposed, up to 48 Inches in Diameter or with Flat Surfaces up to 72 Inches:

1. Aluminum, Stucco Embossed: 0.020 inch thick.
2. Self-adhesive outdoor jacket.

END OF SECTION

SECTION 230719 – HVAC PIPING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes insulating the following HVAC piping systems:

1. Condensate drain piping, indoors.
2. Heating hot-water piping, indoors.
3. Glycol heating water piping, indoors and outdoors.
4. Chilled-water piping, indoors.
5. Glycol cooling water piping, indoors and outdoors.
6. Refrigerant suction and hot-gas piping indoors and outdoors.

B. Related Sections:

1. Section 230713 "Duct Insulation."
2. Section 230716 "HVAC Equipment Insulation."

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory and field applied if any). On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Insulation Schedule: Identify type of material, thickness, vapor barrier provision, and where required, field-applied jacket to be provided for each system application.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For qualified Installer.

C. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.

D. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.

B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.

1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 230529 "Hangers and Supports for HVAC Piping and Equipment."

B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.8 SCHEDULING

A. Schedule insulation application after pressure testing systems. Insulation application may begin on segments that have satisfactory test results.

B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

A. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule" and "Outdoor, Aboveground Piping Insulation Schedule" Articles for where insulating materials shall be applied.

B. Products shall not contain asbestos, lead, mercury, or mercury compounds.

C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.

D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.

E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.

F. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials.

G. Mineral-Fiber, Preformed Pipe Insulation:

1. Type I, Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A, with factory-applied ASJ-SSL. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

2.2 INSULATING CEMENTS

A. Mineral-Fiber Insulating Cement: Comply with ASTM C 195.

B. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449.

2.3 ADHESIVES

A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.

B. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.

1. Adhesives shall have a VOC content of 50 g/L or less.

C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.

1. Fiberglass adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

D. ASJ Adhesive Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.

1. Adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

E. PVC Jacket Adhesive: Compatible with PVC jacket.

1. Adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.4 MASTICS

A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.

1. VOC Content: 300 g/L or less.

B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below-ambient services.

1. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, at manufacturer's recommended dry film thickness.
2. Service Temperature Range: 0 to plus 180 deg F.
3. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
4. Color: White.

C. Breather Mastic: Water based; suitable for indoor and outdoor use on above-ambient services.

1. Water-Vapor Permeance: ASTM F 1249, at manufacturer's recommended dry film thickness.
2. Service Temperature Range: 0 to plus 180 deg F.
3. Solids Content: 60 percent by volume and 66 percent by weight.
4. Color: White.

2.5 LAGGING ADHESIVES

A. Description: Comply with MIL-A-3316C, Class I, Grade A and shall be compatible with insulation materials, jackets, and substrates.

1. Adhesives shall have a VOC content of 50 g/L or less.
2. Fire-resistant, water-based lagging adhesive and coating for use indoors to adhere fire-resistant lagging cloths over pipe insulation.
3. Service Temperature Range: 0 to plus 180 deg F.
4. Color: White.

2.6 SEALANTS

A. ASJ Flashing Sealants and PVC Jacket Flashing Sealants:

1. Materials shall be compatible with insulation materials, jackets, and substrates.
2. Fire- and water-resistant, flexible, elastomeric sealant.
3. Service Temperature Range: 0 to plus 180 deg F.
4. Color: White.
5. Sealant shall have a VOC content of 420 g/L or less.

2.7 FACTORY-APPLIED JACKETS

A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:

1. ASJ: White, Kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.
2. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.

2.8 FIELD-APPLIED JACKETS

A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.

B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.

1. Adhesive: As recommended by jacket material manufacturer.
2. Color: White.
3. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.

    a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

C. Metal Jacket:

1. Aluminum Jacket: Comply with ASTM B209, Alloy 3003, 3005, 3105, or 5005, Temper H-14.

    a. Factory cut and rolled to size.
    b. Finish and thickness are indicated in field-applied jacket schedules.
    c. Moisture Barrier for Indoor Applications: 1-mil thick, heat-bonded polyethylene and Kraft paper.
    d. Moisture Barrier for Outdoor Applications: 3-mil thick, heat-bonded polyethylene and Kraft paper.
    e. Factory-Fabricated Fitting Covers:

        1) Same material, finish, and thickness as jacket.
        2) Preformed 2-piece or gore, 45- and 90-degree, short- and long-radius elbows.
        3) Tee covers.
        4) Flange and union covers.

5) End caps.
6) Beveled collars.
7) Valve covers.
8) Field fabricate fitting covers only if factory-fabricated fitting covers are not available.

D. Self-Adhesive Outdoor Jacket (Asphaltic): 60-mil thick, laminated vapor barrier and waterproofing membrane for installation over insulation located aboveground outdoors; consisting of a rubberized bituminous resin on a cross-laminated polyethylene film covered with stucco-embossed aluminum-foil facing.

1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:

a. MFM Building Products Corp.
b. Polyguard Products, Inc.; Alumaguard 60.

2.9 TAPES

A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.

1. Width: 3-inches.
2. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.

B. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.

1. Width: 2-inches.

2.10 SECUREMENTS

A. Bands:

1. Stainless Steel: ASTM A 167 or ASTM A 240/A 240M, Type 304 or Type 316; 0.015-inch thick, ½-inch wide with wing seal or closed seal.
2. Springs: Twin spring set constructed of stainless steel with ends flat and slotted to accept metal bands. Spring size determined by manufacturer for application.

B. Staples: Outward-clinching insulation staples, nominal 3/4 inch wide, stainless steel or Monel.

C. Wire: 0.080-inch nickel-copper alloy or 0.062-inch soft-annealed, galvanized steel.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.

1. Verify that systems to be insulated have been tested and are free of defects.
2. Verify that surfaces to be insulated are clean and dry.
3. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

B. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless-steel surfaces, use demineralized water.

3.3 GENERAL INSTALLATION REQUIREMENTS

A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.

B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of pipe system as specified in insulation system schedules.

C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.

D. Install insulation with longitudinal seams at top and bottom of horizontal runs.

E. Install multiple layers of insulation with longitudinal and end seams staggered.

F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.

G. Keep insulation materials dry during application and finishing.

H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.

I. Install insulation with least number of joints practical.

J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.

1. Install insulation continuously through hangers and around anchor attachments.

2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.

K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.

L. Install insulation with factory-applied jackets as follows:

1. Draw jacket tight and smooth.
2. Cover circumferential joints with 3-inch wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 2 inches o.c.
3. Overlap jacket longitudinal seams at least 1-1/2-inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.

    a. For below-ambient services, apply vapor-barrier mastic over staples.

4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.

M. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.

N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

P. For above-ambient services, do not install insulation to the following:

1. Vibration-control devices.
2. Testing agency labels and stamps.
3. Nameplates and data plates.
4. Manholes.
5. Handholes.
6. Cleanouts.

3.4 PENETRATIONS

A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.

1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
3. Extend jacket of outdoor insulation outside roof flashing at least below top of roof flashing.
4. Seal jacket to roof flashing with flashing sealant.

B. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.

1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
4. Seal jacket to wall flashing with flashing sealant.

C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.

D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.

1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.

E. Insulation Installation at Floor Penetrations:

1. Pipe: Install insulation continuously through floor penetrations.
2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

3.5 GENERAL PIPE INSULATION INSTALLATION

A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.

B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:

1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.

2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.
7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
8. For services not specified to receive a field-applied jacket except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
9. Stencil or label the outside insulation jacket of each union with the word "union." Match size and color of pipe labels.

C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.

D. Install removable insulation covers at locations indicated. Installation shall conform to the following:

1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe

insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.

3. Construct removable valve insulation covers in same manner as for flanges, except divide the two-part section on the vertical center line of valve body.
4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

3.6 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

B. Insulation Installation on Pipe Flanges:

1. Install pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install mitered sections of pipe insulation.
2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed valve covers manufactured of same material as pipe insulation when available.
2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
3. Install insulation to flanges as specified for flange insulation application.
4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.7 INSTALLATION OF MINERAL-FIBER INSULATION

A. Insulation Installation on Straight Pipes and Tubes:

1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward-clinched staples at 6 inches o.c.
4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
4. Install insulation to flanges as specified for flange insulation application.

3.8 FIELD-APPLIED JACKET INSTALLATION

A. Where PVC jackets are indicated, install with 1 inch overlap at longitudinal seams and end joints; for horizontal applications. Seal with manufacturer's recommended adhesive.

1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

B. Where metal jackets are indicated, install with 2 inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal and joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless steel bands 12 inches o.c. and at end joints.

3.9 FINISHES

A. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.

3.10 FIELD QUALITY CONTROL

A. Mechanical Contractor shall perform tests and inspections.

B. Tests and Inspections:

1. Inspect pipe, fittings, strainers, and valves, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to three locations of straight pipe, three locations of threaded fittings, three locations of welded fittings, two locations of threaded strainers, two locations of welded strainers, three locations of threaded valves, and three locations of flanged valves for each pipe service defined in the "Piping Insulation Schedule, General" Article.

C. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

D. All materials removed during inspections shall be replaced with new materials.

3.11 PIPING INSULATION SCHEDULE, GENERAL

A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.

B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:

1. Underground piping.
2. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

3.12 INDOOR PIPING INSULATION SCHEDULE

A. Condensate and Equipment Drain Water below 60 deg F:

1. All Pipe Sizes: Insulation shall be the following:

a. Flexible Elastomeric: 3/4 inch thick.
b. Vapor Barrier: Required.

B. Heating-Hot-, and Gycol-Heating Water Supply and Return, and Below:

1. NPS 1-1/4 and Smaller: Insulation shall be the following:

a. Mineral-Fiber, Preformed Pipe, Type I: 1-inch thick.

2. NPS 1-1/2 and Larger: Insulation shall be the following:

a. Mineral-Fiber, Preformed Pipe, Type I: 1-1/2 inches thick.

3. Vapor Barrier: Not required.

C. Refrigerant Suction and Hot-Gas Piping:

1. All Pipe Sizes: Insulation shall be the following:

a. Flexible Elastomeric: 1-inch thick.

2. Vapor Barrier: Required.

D. Glycol-Cooling and Chilled Water Piping; above 40 deg F:

1. Pipe Sizes Less Than 1-inch:

a. Flexible Elastomeric: 1/2 thick.

2. Pipe Sizes 1-inch and Greater:

a. Flexible Elastomeric: 1-inch thick.

3.13 OUTDOOR, ABOVEGROUND PIPING INSULATION SCHEDULE

A. Refrigerant Suction and Hot-Gas Piping:

1. All Pipe Sizes: Insulation shall be the following:

a. Flexible Elastomeric: 2-inches thick.

B. Glycol-Heating Water Supply and Return:

1. NPS 1-1/2 and larger: Insulation shall be the following:

a. Mineral-Fiber, Preformed Pipe, Type I: 2-inches thick.

C. Glycol-Cooling Water Supply and Return:

1. NPS 1-1/2 and larger: Insulation shall be the following:

a. Flexible Elastomeric: 2-inches thick.

3.14 INDOOR, FIELD-APPLIED JACKET SCHEDULE

A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.

B. Piping, Concealed:

1. None.

C. Piping, Exposed Piping in Finished Areas:

1. PVC: 20-mil thick.

3.15 OUTDOOR, FIELD-APPLIED JACKET SCHEDULE

A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.

B. Piping, Exposed:

1. For line set covers required for exposed refrigerant piping, both indoor and outdoor refer to Section 238126 “Split-system air-conditioners”.
2. Aluminum, Stucco Embossed: 0.020 inch thick.
3. Self-Adhesive Outdoor Jacket.

END OF SECTION

SECTION 230800 - COMMISSIONING OF HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes Cx process requirements for the following HVAC systems, assemblies, and equipment:

1. Energy supply systems.
2. Heat generation systems.
3. Cooling generation systems.
4. Central-station air-handling systems.
5. Air and hydronic distribution systems.
6. Heating and cooling terminal and unitary equipment.
7. HVAC controls.
8. TAB verification.

B. Related Requirements:

1. Section 019113 "General Commissioning Requirements" for general Cx process requirements and CxA responsibilities.
2. For construction checklists, comply with requirements in various Division 23 Sections specifying HVAC systems, system components, equipment, and products.

1.3 DEFINITIONS

A. BAS: Building automation system.

B. Cx: Commissioning, as defined in Section 019113 "General Commissioning Requirements."

C. CxA: Commissioning Authority, as defined in Section 019113 "General Commissioning Requirements."

D. IgCC: International Green Construction Code.

E. "Systems," "Assemblies," "Subsystems," "Equipment," and "Components": Where these terms are used together or separately, they mean "as-built" systems, assemblies, subsystems, equipment, and components.

F. TAB: Testing, adjusting, and balancing.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For BAS and HVAC testing technicians.

C. Construction Checklists:

1. Draft Cx plan, including draft construction checklists to be prepared by CxA under Section 019113 "General Commissioning Requirements." Div. 23 Subcontractor is to review Construction Checklist in accordance with requirements in Section 019113 "General Commissioning Requirements" and ASHRAE 202 and to resolve any issues with the CxA.
2. Cx plan, including material, installation, and performance construction checklists for systems, assemblies, subsystems, equipment, and components relating to BAS and HVAC to be part of the Cx process and in accordance with requirements in Section 019113 "General Commissioning Requirements and ASHRAE 202."

D. Test Equipment and Instruments: For all test equipment and instruments to be used in conducting Cx tests by Div. 23 Subcontractor, provide the following:

1. Equipment/instrument identification number.
2. Planned Cx application or use.
3. Manufacturer, make, model, and serial number.
4. Calibration history, including certificates from agencies that calibrate the equipment and instrumentation.
5. Equipment manufacturers' proprietary instrumentation and tools. For each instrument or tool, identify the following:

    a. Instrument or tool identification number.
    b. Equipment schedule designation of equipment for which the instrument or tool is required.
    c. Manufacturer, make, model, and serial number.
    d. Calibration history, including certificates from agencies that calibrate the instrument or tool, where appropriate.

1.5 QUALITY ASSURANCE

A. HVAC Testing Technician Qualifications: Technicians to perform HVAC Construction Checklist verification tests, Construction Checklist verification test demonstrations, Cx tests, and Cx test demonstrations shall have the following minimum qualifications:

1. Journey level or equivalent skill level; vocational school four-year-program graduate or an Associate's degree in mechanical systems, air conditioning, or similar field. Degree may be offset by three years' experience in servicing mechanical systems in the HVAC industry. Generally, required knowledge includes HVAC systems, electrical concepts, building operations, and application and use of tools and instrumentation to measure performance of HVAC equipment, assemblies, and systems.

B. Testing Equipment and Instrumentation Quality and Calibration:

1. Capable of testing and measuring performance within the specified acceptance criteria.
2. Be calibrated at manufacturer's recommended intervals with current calibration tags permanently affixed to the instrument being used.
3. Be maintained in good repair and operating condition throughout duration of use on Project.
4. Be recalibrated/repaired if dropped or damaged in any way since last calibrated.

C. Proprietary Test Instrumentation and Tools:

1. Equipment Manufacturer's Proprietary Instrumentation and Tools: For installed equipment included in the Cx process, test instrumentation and tools manufactured or prescribed by equipment manufacturer to service, calibrate, adjust, repair, or otherwise work on its equipment or required as a condition of equipment warranty, shall comply with the following:

   a. Be calibrated by manufacturer with current calibration tags permanently affixed.
   b. Include a separate list of proprietary test instrumentation and tools in operation and maintenance manuals.

2. HVAC proprietary test instrumentation and tools become property of University at the time of Substantial Completion.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 Cx PROCESS:

A. Perform Cx process in accordance with Section 019113 "General Commissioning Requirements" for BAS and HVAC and in accordance with the following:

1. ASHRAE 202.
2. Commissioning standards acceptable to the authority having jurisdiction.

3.2 CONSTRUCTION CHECKLISTS

A. Preliminary detailed construction checklists are to be prepared under Section 019113 "General Commissioning Requirements" for each BAS and HVAC system, assembly, subsystem, equipment, and component required to be commissioned, as detailed in ASHRAE 202. Contractor performs the following:

1. Review BAS and HVAC preliminary construction checklists and provide written comments on checklist items where appropriate.
2. Return preliminary Construction Checklist with review comments within 10 days of receipt.
3. When review comments have been resolved, the CxA will provide final construction checklists marked "Approved for Use, (date)."

4. Use only construction checklists marked "Approved for Use, (date)" When performing tests. Mark construction checklists in the appropriate place as indicated Project events are completed, and provide pertinent details and other information.

B. Systems required to be commissioned under IgCC:

1. Heating, ventilating, air-conditioning, and refrigeration systems (mechanical and/or passive) and associated controls.
2. Water-pumping and -mixing systems.

C. Additional systems required to be commissioned:

1. Cooling generation systems, including the following:

   a. Direct-expansion refrigeration systems.

2. Air-handling systems, including the following:

   a. Supply, return, and exhaust air fans, motors, and drives.
   b. Automatic and gravity dampers.
   c. Heating and cooling devices.
   d. Air filters.
   e. Hangers and supports.

3. Air duct systems, including the following:

   a. Duct systems.
   b. Air-duct accessories, including volume dampers, turning vanes, sound attenuators, and flexible connectors.
   c. Duct-mounted access doors and panels.
   d. Hangers and supports.

4. Refrigerant piping, including the following:

   a. Refrigerant piping, fittings, and specialties.
   b. Refrigerant charge.
   c. Sleeves and sleeve seals.
   d. Meters and gauges.
   e. General-duty and specialty valves.
   f. Hangers and supports.

5. TAB Verification:

   a. Airflow.
   b. Water flow.
   c. Space pressurization.

6. Documentation:

   a. Mechanical systems manuals.
   b. Documentation of required commissioning.

7. Mechanical insulation, including the following:

    a. Duct and plenum insulation.
    b. HVAC piping insulation.

3.3 Cx TESTING PREPARATION

A. Certify that HVAC systems, subsystems, and equipment have been installed, calibrated, and started and that they are operating in accordance with the Contract Documents and approved submittals.

B. Certify that HVAC instrumentation and control systems have been completed and calibrated, point-to-point checkout has been successfully completed, and systems are operating in accordance with their design sequence of operation, Contract Documents, and approved submittals. Certify that all sensors are operating within specified accuracy and all systems are set to and maintaining set points as required by the design documents.

C. Certify that TAB procedures have been completed and that TAB reports have been submitted, discrepancies corrected, and corrective work approved.

D. Set systems, subsystems, and equipment into operating mode to be tested in accordance with approved test procedures (e.g., normal shutdown, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).

3.4 Cx TEST CONDITIONS

A. Perform tests using design conditions, whenever possible.

1. Simulated conditions may, with approval of Architect, be imposed using an artificial load when it is impractical to test under design conditions. Before simulating conditions, calibrate testing instruments. Provide equipment to simulate loads. Set simulated conditions as directed by CxA, and document simulated conditions and methods of simulation. After tests, return configurations and settings to normal operating conditions.
2. Cx test procedures may direct that set points be altered when simulating conditions is impractical.
3. Cx test procedures may direct that sensor values be altered with a signal generator when design or simulating conditions and altering set points are impractical.

B. If tests cannot be completed because of a deficiency outside the scope of the HVAC system, document the deficiency and report it to Architect. After deficiencies are resolved, reschedule tests.

C. If seasonal testing is specified, complete appropriate initial performance tests and documentation, and schedule seasonal tests.

3.5 Cx TESTS COMMON TO HVAC SYSTEMS

A. Measure capacities and effectiveness of systems, assemblies, subsystems, equipment, and components, including operational and control functions, to verify compliance with acceptance criteria.

B. Test systems, assemblies, subsystems, equipment, and components for operating modes, interlocks, control responses, responses to abnormal or emergency conditions, and response in accordance with acceptance criteria.

C. Coordinate schedule with, and perform Cx activities at the direction of, CxA.

D. Comply with Construction Checklist requirements, including material verification, installation checks, startup, and performance test requirements specified in Division 23 Sections specifying HVAC systems and equipment.

E. Provide technicians, instrumentation, tools, and equipment to perform and document the following:

1. Cx Construction Checklist verification tests.
2. Cx Construction Checklist verification test demonstrations.

3.6 TAB VERIFICATION

A. Prerequisites: Completion of "Examination" Article requirements and correction of deficiencies, as specified in Section 230593 "Testing, Adjusting, and Balancing for HVAC."

B. Completion of "Preparation" Article requirements for preparation of a TAB plan that includes strategies and step-by-step procedures, and system-readiness checks and reports, as specified in Section 230593 "Testing, Adjusting, and Balancing for HVAC."

C. Scope: HVAC air systems and hydronic piping systems.

D. Conditions of the Test:

1. Cx Test Demonstration Sampling Rate: As specified in "Inspections" Article in Section 230593 "Testing, Adjusting, and Balancing for HVAC."
2. Systems operating in full heating mode.
3. Systems operating in full cooling mode.

E. Acceptance Criteria:

1. Under all conditions, rechecked measurements comply with "Inspections" Article in Section 230593 "Testing, Adjusting, and Balancing for HVAC."
2. Additionally, no rechecked measurement shall differ from measurements documented in the final report by more than the tolerances allowed.
3. Under all conditions, where the Contract Documents indicate a differential in airflow between supply and exhaust and/or return in a space, the differential relationship shall be maintained.

3.7 AIR-HANDLING SYSTEM Cx TESTS

A. Supply Fan(s) Variable-Volume Control:

1. Prerequisites: Installation verification of the following:

a. Volume-Control Input Device: Static-pressure transmitter sensing supply-duct static pressure referenced to conditioned-space static pressure.
b. Volume-Control Output Device: DDC system analog output to modulate fan speed.

2. Scope: VAV supply fan units and associated controls.

END OF SECTION

SECTION 230923 - DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. DDC system for monitoring and controlling of HVAC systems.
2. Delivery of selected control devices to equipment and systems manufacturers for factory installation and to HVAC systems installers for field installation.

B. Related Requirements:

1. Communications Cabling:

   a. Section 260523 "Control-Voltage Electrical Power Cables" for balanced twisted pair communications cable.
   b. Section 271513 "Communications Copper Horizontal Cabling" for balanced twisted pair communications cable.

2. Section 260553 "Identification for Electrical Systems" for identification requirements for electrical components.

C. General Description:

1. The control system shall consist of a high-speed, peer-to-peer network of DDC controllers, a control system server, and a web-based operator interface. DDC system is for monitoring and controlling various HVAC systems. The control system shall be seamlessly integrated with the State of Maine Building Control Center (BCC) which provides 24 hours a day, 7 days a week, 365 days a year monitoring of state facilities. The HVAC controls shall be an extension of the existing Honeywell Enterprise Building Integrator (EBI) with host server hardware located in Augusta Maine. The Building Automation System (BAS) shall enable monitoring and control of mechanical systems installed under the scope of this project through to the BCC. Integration of HVAC system, panels, associated devices, front-end programming, and graphics is proprietary to Honeywell International Inc. Contact: Bob Masland, Senior Account Executive, Honeywell Building Technologies; Robert.masland2@Honeywell.com.
2. DDC system shall interface with an existing BCC building control center enterprise system to adhere to Owner standards already in-place and to achieve integration. Integration is limited to 3 State of Maine network connections.
3. Engage Owner's control system integrator Honeywell EBI to provide the following services:

a. Enterprise system expansion and development of graphics, logs, reports, trends, and other operational capabilities of enterprise system for I/O being added to DDC control system for use by enterprise system operators.
b. Assistance during commissioning to extent of DDC system integration with existing enterprise system.
c. Prepare on-site demonstration mockup of integration of DDC system to be installed with existing system before installing DDC system.

4. Graphic Interface:

a. The graphics interface shall be designed and installed by Honeywell EBI for the BCC system.
b. Graphic Interface shall have a similar look, feel, and operation as other controls in existing State of Maine Buildings.
c. Modifications to the DDC system graphics is done through the system integrator – Honeywell EBI.
d. The graphics interface shall be designed and installed by Honeywell EBI for the BCC system.
e. Graphic Interface for the Department of Inland Fisheries and Wildlife building shall have a similar look, feel, and operation as other controls in existing State of Maine Buildings
f. Modifications to the DDC system graphics is done through the system integrator – Honeywell EBI.

5. Reporting: Reports and logs shall be provided via the existing Honeywell EBI system and shall include the following, in addition to alarms indicated on the controls drawings:

a. All I/O: With current status and values.
b. Alarm: All current alarms, except those in alarm lockout.
c. Disabled I/O: All I/O points that are disabled.
d. Alarm Lockout I/O: All I/O points in alarm lockout, whether manual or automatic.
e. Alarm Lockout I/O in Alarm: All I/O in alarm lockout that are currently in alarm.
f. Logs:

1) Alarm history.
2) System messages.
3) System events.
4) Trends.
5) Communications

6. One of the following communication types which are supported by the Honeywell Building Manager (EBI) must be used. Note controls package will be limited to 5 HVAC network IP addressable devices, any request to add additional network devices would need approval.

a. Modbus
b. LON Works
c. BACnet
d. XL Direct
e. XL Net
f. BNPS
g. C-Bus

h. OPC

7. The State of Maine has a requirement for no local space temperature sensor control by occupants. Space sensor control will follow state standard of 68 degrees for heating and 75 degrees for cooling.
8. When programming, the following point name structure will be followed.

   a. Short Descriptor Building Code, Device type – Device – parameter

      1) Example – BRH_HEX_3_1/3_VlvCtrl

   b. Long Descriptor City, Street Address, Device Location, Device type – Device – parameter

      1) Augusta, 90 Blossom Lane, Basement, Heat Exchanger 1/3 Valve, Open

9. The State of Maine uses FORGE, an intuitive program that uses analytics to report abnormalities within the HVAC systems. New, retrofits and upgrades will require asset integration into FORGE.
10. The State of Maine uses Command & Control, an intelligent solution, that provides a more effectively monitoring, optimization, and automate essential functions, for energy management and HVAC assets will require modifications to the current facility Command and Control Suite model.
11. Licensing - Provide required additional Honeywell EBI HVAC licensing points.
12. Point to point - Documentation & Verification of HVAC equipment, location, valve operations, sensor readings, Night setbacks, damper controls etc.

1.3 DEFINITIONS

A. Algorithm: A logical procedure for solving a recurrent mathematical problem. A prescribed set of well-defined rules or processes for solving a problem in a finite number of steps.

B. Analog: A continuously varying signal value, such as current, flow, pressure, or temperature.

C. BACnet Specific Definitions:

1. BACnet: Building Automation Control Network Protocol, ASHRAE 135. A communications protocol allowing devices to communicate data over and services over a network.
2. BACnet Interoperability Building Blocks (BIBBs): BIBB defines a small portion of BACnet functionality that is needed to perform a particular task. BIBBs are combined to build the BACnet functional requirements for a device.
3. BACnet/IP: Defines and allows using a reserved UDP socket to transmit BACnet messages over IP networks. A BACnet/IP network is a collection of one or more IP subnetworks that share the same BACnet network number.
4. BACnet Testing Laboratories (BTL): Organization responsible for testing products for compliance with ASHRAE 135, operated under direction of BACnet International.
5. PICS (Protocol Implementation Conformance Statement): Written document that identifies the particular options specified by BACnet that are implemented in a device.

D. Binary: Two-state signal where a high signal level represents ON" or "OPEN" condition and a low signal level represents "OFF" or "CLOSED" condition. "Digital" is sometimes used interchangeably with "Binary" to indicate a two-state signal.

E. Controller: Generic term for any standalone, microprocessor-based, digital controller residing on a network, used for local or global control. Three types of controllers are indicated: Network Controller, Programmable Application Controller, and Application-Specific Controller.

F. Control System Integrator: An entity that assists in expansion of existing enterprise system and support of additional operator interfaces to I/O being added to existing enterprise system.

G. COV: Changes of value.

H. DDC System Provider: Authorized representative of, and trained by, DDC system manufacturer and responsible for execution of DDC system Work indicated.

I. Distributed Control: Processing of system data is decentralized and control decisions are made at subsystem level. System operational programs and information are provided to remote subsystems and status is reported back. On loss of communication, subsystems shall be capable of operating in a standalone mode using the last best available data.

J. Gateway: Bidirectional protocol translator that connects control systems that use different communication protocols.

K. HLC: Heavy load conditions.

L. I/O: System through which information is received and transmitted. I/O refers to analog input (AI), binary input (BI), analog output (AO) and binary output (BO). Analog signals are continuous and represent control influences such as flow, level, moisture, pressure, and temperature. Binary signals convert electronic signals to digital pulses (values) and generally represent two-position operating and alarm status. "Digital," (DI and (DO), is sometimes used interchangeably with "Binary," (BI) and (BO), respectively.

M. LAN: Local area network.

N. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control, signaling power-limited circuits.

O. Mobile Device: A data-enabled phone or tablet computer capable of connecting to a cellular data network and running a native control application or accessing a web interface.

P. MS/TP: Master-slave/token-passing, IEE 8802-3. Datalink protocol LAN option that uses twisted-pair wire for low-speed communication.

Q. MTBF: Mean time between failures.

R. Network Controller: Digital controller, which supports a family of programmable application controllers and application-specific controllers, that communicates on peer-to-peer network for transmission of global data.

S. Network Repeater: Device that receives data packet from one network and rebroadcasts it to another network. No routing information is added to protocol.

T. Peer to Peer: Networking architecture that treats all network stations as equal partners.

U. POT: Portable operator's terminal.

V. PUE: Performance usage effectiveness.

W. RAM: Random access memory.

X. RF: Radio frequency.

Y. Router: Device connecting two or more networks at network layer.

Z. Server: Computer used to maintain system configuration, historical and programming database.

AA. TCP/IP: Transport control protocol/Internet protocol.

BB. UPS: Uninterruptible power supply.

CC. USB: Universal Serial Bus.

DD. User Datagram Protocol (UDP): This protocol assumes that the IP is used as the underlying protocol.

EE. VAV: Variable air volume.

FF. WLED: White light emitting diode.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Multiple Submissions:

1. If multiple submissions are required to execute work within schedule, first submit a coordinated schedule clearly defining intent of multiple submissions. Include a proposed date of each submission with a detailed description of submittal content to be included in each submission.
2. Clearly identify each submittal requirement indicated and in which submission the information will be provided.
3. Include an updated schedule in each subsequent submission with changes highlighted to easily track the changes made to previous submitted schedule.

C. Product Data: On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied. For each type of product include the following:

1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
3. Product description with complete technical data, performance curves, and product specification sheets.
4. Installation, operation and maintenance instructions including factors effecting performance.
5. Bill of materials of indicating quantity, manufacturer, and extended model number for each unique product.
6. When manufacturer's product datasheets apply to a product series rather than a specific product model, clearly indicate and highlight only applicable information.
7. Each submitted piece of product literature shall clearly cross reference specification and drawings that submittal is to cover.

D. Software Submittal. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Cross-referenced listing of software to be loaded on each operator workstation, server, gateway, and DDC controller.
2. Description and technical data of all software provided, and cross-referenced to products in which software will be installed.
3. Operating system software, operator interface and programming software, color graphic software, DDC controller software, maintenance management software, and third-party software.
4. Description of operator interface to alphanumeric and graphic programming.
5. Description of each network communication protocol.
6. Description of system database, including all data included in database, database capacity and limitations to expand database.
7. Controlled Systems: Instrumentation list with element name, type of device, manufacturer, model number, and product data. Include written description of sequence of operation including schematic diagram.

E. Shop Drawings:

1. General Requirements:

    a. Include cover drawing with Project name, location, Owner, Architect, Contractor and issue date with each Shop Drawings submission.
    b. Include a drawing index sheet listing each drawing number and title that matches information in each title block.

2. Include plans, elevations, sections, and mounting details where applicable.
3. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
4. Plan Drawings indicating the following:

a. Screened backgrounds of walls, structural grid lines, HVAC equipment, ductwork and piping.
b. Room names and numbers with coordinated placement to avoid interference with control products indicated.
c. Each desktop workstation, server, gateway, router, DDC controller, control panel instrument connecting to DDC controller, and damper and valve connecting to DDC controller, included in Project.
d. Exact placement of products in rooms, ducts, and piping to reflect proposed installed condition.
e. Network communication cable and raceway routing.
f. Proposed routing of wiring, cabling, conduit, and tubing, coordinated with building services for review before installation.

5. Schematic drawings for each controlled HVAC system indicating the following:

a. I/O points labeled with point names shown. Indicate instrument range, normal operating set points, and alarm set points. Indicate fail position of each damper and valve, if included in Project.
b. I/O listed in table format showing point name, type of device, manufacturer, model number, and cross-reference to product data sheet number.
c. A graphic showing location of control I/O in proper relationship to HVAC system.
d. Wiring diagram with each I/O point having a unique identification and indicating labels for all wiring terminals.
e. Unique identification of each I/O that shall be consistently used between different drawings showing same point.
f. Elementary wiring diagrams of controls for HVAC equipment motor circuits including interlocks, switches, relays and interface to DDC controllers.
g. Narrative sequence of operation.

6. Control panel drawings indicating the following:

a. Panel dimensions, materials, size, and location of field cable, raceways, and wiring connections.
b. Interior subpanel layout, drawn to scale and showing all internal components, cabling and wiring raceways, nameplates and allocated spare space.
c. Front, rear, and side elevations and nameplate legend.
d. Unique drawing for each panel.

7. DDC system network riser diagram indicating the following:

a. Each device connected to network with unique identification for each.
b. Interconnection of each different network in DDC system.
c. For each network, indicate communication protocol, speed and physical means of interconnecting network devices, such as copper cable type, or optical fiber cable type. Indicate raceway type and size for each.
d. Each network port for connection of an operator workstation or other type of operator interface with unique identification for each.

8. DDC system electrical power riser diagram indicating the following:

a. Each point of connection to field power with requirements (volts/phase//hertz/amperes/connection type) listed for each.

b. Each control power supply including, as applicable, transformers, power-line conditioners, transient voltage suppression and high filter noise units, DC power supplies, and UPS units with unique identification for each.
c. Each product requiring power with requirements (volts/phase//hertz/amperes/connection type) listed for each.
d. Power wiring type and size, race type, and size for each.

9. Monitoring and control signal diagrams indicating the following:

a. Control signal cable and wiring between controllers and I/O.
b. Point-to-point schematic wiring diagrams for each product.

10. Color graphics indicating the following:

a. Itemized list of color graphic displays to be provided.
b. For each display screen to be provided, a true color copy showing layout of pictures, graphics and data displayed.
c. Intended operator access between related hierarchical display screens.

F. System Description:

1. Full description of DDC system architecture, network configuration, operator interfaces and peripherals, servers, controller types and applications, gateways, routers and other network devices, and power supplies.
2. Complete listing and description of each report, log and trend for format and timing and events which initiate generation.
3. System and product operation under each potential failure condition including, but not limited to, the following:

a. Loss of power.
b. Loss of network communication signal.
c. Loss of controller signals to inputs and outpoints.
d. Operator workstation failure.
e. Server failure.
f. Gateway failure.
g. Network failure
h. Controller failure.
i. Instrument failure.
j. Control damper and valve actuator failure.

4. Complete bibliography of documentation and media to be delivered to Owner.
5. Description of testing plans and procedures.
6. Description of Owner training.

1.6 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings:

1. Plan drawings and corresponding product installation details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

    a. Product installation location shown in relationship to room, duct, pipe and equipment.
    b. Structural members to which products will be attached.
    c. Wall-mounted instruments located in finished space showing relationship to light switches, fire-alarm devices and other installed devices.
    d. Size and location of wall access panels for products installed behind walls and requiring access.

2. Reflected ceiling plans and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

    a. Ceiling components.
    b. Size and location of access panels for products installed above inaccessible ceiling assemblies and requiring access.
    c. Items penetrating finished ceiling including the following:

        1) Lighting fixtures.
        2) Air outlets and inlets.
        3) Speakers.
        4) Sprinklers.
        5) Access panels.
        6) Motion sensors.
        7) Pressure sensors.
        8) Temperature sensors and other DDC control system instruments.

C. Qualification Data:

1. Systems Provider Qualification Data:

    a. Resume of project manager assigned to Project.
    b. Resumes of application engineering staff assigned to Project.
    c. Resumes of installation and programming technicians assigned to Project.
    d. Resumes of service technicians assigned to Project.
    e. Brief description of past project including physical address, floor area, number of floors, building system cooling and heating capacity and building's primary function.
    f. Description of past project DDC system, noting similarities to Project scope and complexity indicated.
    g. Names of staff assigned to past project that will also be assigned to execute work of this Project.
    h. Owner contact information for past project including name, phone number, and e-mail address.
    i. Contractor contact information for past project including name, phone number, and e-mail address.
    j. Architect and Engineer contact information for past project including name, phone number, and e-mail address.

2. Manufacturer's qualification data.

3. Testing agency's qualifications data.

D. Product Certificates:

1. Data Communications Protocol Certificates: Certifying that each proposed DDC system component complies with ASHRAE 135.

E. Product Test Reports: For each product that requires testing to be performed by manufacturer.

F. Source quality-control reports.

G. Field quality-control reports.

H. Sample Warranty: For manufacturer's warranty.

1.7 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For DDC system to include in emergency, operation and maintenance manuals. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. Project Record Drawings of as-built versions of submittal Shop Drawings provided in electronic PDF format.
b. Testing and commissioning reports and checklists of completed final versions of reports, checklists, and trend logs.
c. As-built versions of submittal Product Data.
d. Names, addresses, e-mail addresses and 24-hour telephone numbers of Installer and service representatives for DDC system and products.
e. Operator's manual with procedures for operating control systems including logging on and off, handling alarms, producing point reports, trending data, overriding computer control and changing set points and variables.
f. Programming manuals with description of programming language and syntax, of statements for algorithms and calculations used, of point database creation and modification, of program creation and modification, and of editor use.
g. Documentation of all programs created using custom programming language including set points, tuning parameters, and object database.
h. Backup copy of graphic files, programs, and database on electronic media such as DVDs or CDs.
i. List of recommended spare parts with part numbers and suppliers.
j. Complete original-issue documentation, installation, and maintenance information for furnished third-party hardware including computer equipment and sensors.
k. Complete original-issue copies of furnished software, including operating systems, custom programming language, operator workstation software, and graphics software.
l. Licenses, guarantees, and warranty documents.

m. Recommended preventive maintenance procedures for system components, including schedule of tasks such as inspection, cleaning, and calibration; time between tasks; and task descriptions.
n. Owner training materials.

1.8 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials and parts that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

C. Include product manufacturers' recommended parts lists for proper product operation over four-year period following warranty period. Parts list shall be indicated for each year.

D. Furnish parts, as indicated by manufacturer's recommended parts list, for product operation during two-year period following warranty period.

E. Furnish quantity indicated of matching product(s) in Project inventory for each unique size and type of following:

1. Network Controller: One.
2. Programmable Application Controller: One.
3. Application-Specific Controller: One.
4. Room and Outdoor Carbon Dioxide Sensor and Transmitter: One of each.
5. Transformer: One of each size and type.
6. DC Power Supply: One of each size and type.

1.9 QUALITY ASSURANCE

A. DDC System Manufacturer Qualifications:

1. Nationally recognized manufacturer of DDC systems and products.
2. DDC systems with similar requirements to those indicated for a continuous period of 10 years within time of bid.
3. DDC systems and products that have been successfully tested and in use on at least five past projects.
4. Having complete published catalog literature, installation, operation and maintenance manuals for all products intended for use.
5. Having full-time in-house employees for the following:

a. Product research and development.
b. Product and application engineering.
c. Product manufacturing, testing and quality control.
d. Technical support for DDC system installation training, commissioning and troubleshooting of installations.
e. Owner operator training.

B. DDC System Provider Qualifications:

1. Authorized representative of, and trained by, DDC system manufacturer.
2. In-place facility located within 50 miles of Project.
3. Demonstrated past experience with installation of DDC system products being installed for period within five consecutive years before time of bid.
4. Demonstrated past experience on five projects of similar complexity, scope and value.
5. Product parts inventory to support on-going DDC system operation for a period of not less than 5 years after Substantial Completion.
6. DDC system manufacturer's backing to take over execution of Work if necessary to comply with requirements indicated. Include Project-specific written letter, signed by manufacturer's corporate officer, if requested.

1.10 WARRANTY

A. Manufacturer's Warranty: Manufacturer and Installer agree to repair or replace products that fail in materials or workmanship within specified warranty period.

1. Failures shall be adjusted, repaired, or replaced at no additional cost or reduction in service to Owner.
2. Include updates or upgrades to software and firmware if necessary to resolve deficiencies.

    a. Install updates only after receiving Owner's written authorization.

3. Warranty service shall occur during normal business hours and commence within 16 hours of Owner's warranty service request.
4. Warranty Period: Three years from date of Substantial Completion.

    a. For Gateway: Three-year parts and labor warranty for each.

PART 2 - PRODUCTS

2.1 DDC SYSTEM MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Johnson Controls, Inc.
2. Siemens Building Technologies, Inc.
3. Trane.

2.2 DDC SYSTEM DESCRIPTION

A. Microprocessor-based monitoring and control including analog/digital conversion and program logic. A control loop or subsystem in which digital and analog information is received and processed by a microprocessor, and digital control signals are generated based on control algorithms and transmitted to field devices to achieve a set of predefined conditions.

1. DDC system shall consist of a high-speed, peer-to-peer network of distributed DDC controllers, other network devices, operator interfaces, and software.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.3 WEB ACCESS

A. DDC system shall be Web based.

1. Web-Based Access to DDC System:

a. DDC system software shall be based on server thin-client architecture, designed around open standards of Web technology. DDC system server shall be accessed using a Web browser over DDC system network, using Owner's LAN, and remotely over Internet through Owner's LAN.
b. Intent of thin-client architecture is to provide operators complete access to DDC system via a Web browser. No special software other than a Web browser shall be required to access graphics, point displays, and trends; to configure trends, points, and controllers; and to edit programming.
c. Web access shall be password protected.

2.4 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Products installed in ducts, equipment, and return-air paths shall comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: 25 or less.
2. Smoke-Developed Index: 50 or less.

B. DDC System Speed:

1. Response Time of Connected I/O:

a. AI point values connected to DDC system shall be updated at least every five seconds for use by DDC controllers. Points used globally shall also comply with this requirement.
b. BI point values connected to DDC system shall be updated at least every five seconds for use by DDC controllers. Points used globally shall also comply with this requirement.
c. AO points connected to DDC system shall begin to respond to controller output commands within two seconds. Global commands shall also comply with this requirement.
d. BO point values connected to DDC system shall respond to controller output commands within two seconds. Global commands shall also comply with this requirement.

2. Display of Connected I/O:

a. Analog point COV connected to DDC system shall be updated and displayed at least every 10 seconds for use by operator.
b. Binary point COV connected to DDC system shall be updated and displayed at least every 10 seconds for use by operator.
c. Alarms of analog and digital points connected to DDC system shall be displayed within 45 seconds of activation or change of state.
d. Graphic display refresh shall update within eight seconds.
e. Point change of values and alarms displayed from workstation to workstation when multiple operators are viewing from multiple workstations shall not exceed graphic refresh rate indicated.

C. Network Bandwidth: Design each network of DDC system to include at least 30 percent available spare bandwidth with DDC system operating under normal and heavy load conditions indicated. Calculate bandwidth usage, and apply a safety factor to ensure that requirement is satisfied when subjected to testing under worst case conditions.

D. DDC System Data Storage:

1. Include capability to archive not less than 24 consecutive months of historical data for all I/O points connected to system, including alarms, event histories, transaction logs, trends and other information indicated.
2. Local Storage:

a. Provide workstation with data storage indicated. Server(s) shall use IT industry standard database platforms and be capable of functions described in "DDC Data Access" Paragraph.

E. DDC Data Access:

1. When logged into the system, operator shall be able to also interact with any DDC controller connected to DDC system as required for functional operation of DDC system.
2. System(s) shall be used for application configuration; for archiving, reporting and trending of data; for operator transaction archiving and reporting; for network information management; for alarm annunciation; and for operator interface tasks and controls application management.

F. Future Expandability:

1. DDC system size shall be expandable to an ultimate capacity of at least two times total I/O points indicated.
2. Additional DDC controllers, I/O and associated wiring shall be all that is needed to achieve ultimate capacity. Initial network infrastructure shall be designed and installed to support ultimate capacity.
3. Operator interfaces installed initially shall not require hardware and software additions and revisions for ultimate capacity.

G. Input Point Displayed Accuracy: Input point displayed values shall meet following end-to-end overall system accuracy, including errors associated with meter, sensor, transmitter, lead wire or cable, and analog to digital conversion.

1. Energy:

a. Thermal: Within 5 percent of reading.
b. Electric Power: Within 1 percent of reading.
c. Requirements indicated on Drawings for meters not supplied by utility.

2. Flow:

a. Air: Within 5 percent of design flow rate.
b. Air (Terminal Units): Within 5 percent of design flow rate.

3. Gas:

a. Carbon Dioxide: Within 50 ppm.
b. Carbon Monoxide: Within 5 percent of reading.
c. Refrigerant: Within 50 ppm.

4. Moisture (Relative Humidity):

a. Air: Within 3 percent RH.
b. Space: Within 3 percent RH.
c. Outdoor: Within 3 percent RH.

5. Level: Within 5 percent of reading.
6. Pressure:

a. Air, Ducts and Equipment: 0.5 percent of instrument range.
b. Space: Within 0.25 percent of instrument range.

7. Speed: Within percent of reading.
8. Temperature, Dry Bulb:

a. Air: Within 1 deg F.
b. Space: Within 1 deg F.
c. Outdoor: Within 1 deg F.
d. Other Temperatures Not Indicated: Within 1 deg F.

H. Precision of I/O Reported Values: Values reported in database and displayed shall have following precision:

1. Current:

a. Milliamperes: Nearest 1/100th of a milliampere.
b. Amperes: Nearest 1/10th of an ampere up to 100 A; nearest ampere for 100 A and more.

2. Energy:

a. Electric Power:

1) Rate (Watts): Nearest 1/10th of a watt through 1000 W.
2) Rate (Kilowatts): Nearest 1/10th of a kilowatt through 1000 kW; nearest kilowatt above 1000 kW.

3) Usage (Kilowatt-Hours): Nearest kilowatt through 10,000 kW; nearest 10 kW between 10,000 and 100,000 kW; nearest 100 kW for above 100,000 kW.

b. Thermal, Rate:

1) Heating: For Btu/h, nearest Btu/h up to 1000 Btu/h; nearest 10 Btu/h between 1000 and 10,000 Btu/h; nearest 100 Btu/h for above 10,000 Btu/h. For Mbh, round to nearest Mbh up to 1000 Mbh; nearest 10 Mbh between 1000 and 10,000 Mbh; nearest 100 Mbh above 10,000 Mbh.
2) Cooling: For tons, nearest ton up to 1000 tons; nearest 10 tons between 1000 and 10,000 tons; nearest 100 tons above 10,000 tons.

c. Thermal, Usage:

1) Heating: For Btu, nearest Btu up to 1000 Btu; nearest 10 Btu between 1000 and 10,000 Btu; nearest 100 Btu for above 10,000 Btu. For Mbtu, round to nearest Mbtu up to 1000 Mbtu; nearest 10 Mbtu between 1000 and 10,000 Mbtu; nearest 100 Mbtu above 10,000 Mbtu.
2) Cooling: For ton-hours, nearest ton-hours up to 1000 ton-hours; nearest 10 ton-hours between 1000 and 10,000 ton-hours; nearest 100 tons above 10,000 tons.

3. Flow:

a. Air: Nearest 1/10th of a cfm through 100 cfm; nearest cfm between 100 and 1000 cfm; nearest 10 cfm between 1000 and 10,000 cfm; nearest 100 cfm above 10,000 cfm.

4. Gas:

a. Carbon Dioxide (ppm): Nearest ppm.
b. Carbon Monoxide (ppm): Nearest ppm.
c. Refrigerant (ppm): Nearest ppm.

5. Moisture (Relative Humidity):

a. Relative Humidity (Percentage): Nearest 1 percent.

6. Pressure:

a. Air, Ducts and Equipment: Nearest 1/10th in. w.c..
b. Space: Nearest 1/100th in. w.c..

7. Temperature:

a. Air, Ducts and Equipment: Nearest 1/10th of a degree.
b. Outdoor: Nearest degree.
c. Space: Nearest 1/10th of a degree.
d. Heating Hot Water: Nearest degree.

8. Voltage: Nearest 1/10 volt up to 100 V; nearest volt above 100 V.

I. Control Stability: Control variables indicated within the following limits:

1. Flow:

a. Air, Ducts and Equipment, except Terminal Units: Within 5 percent of design flow rate.
b. Air, Terminal Units: Within 5 percent of design flow rate.

2. Gas:

a. Carbon Dioxide: Within 50 ppm.
b. Carbon Monoxide: Within 5 percent of reading.

3. Moisture (Relative Humidity):

a. Air: Within 5 percent RH.
b. Space: Within 5 percent RH.
c. Outdoor: Within 5 percent RH.

4. Pressure:

a. Air, Ducts and Equipment: 0.5 percent of instrument range.
b. Space: Within 0.25 percent of instrument range.

5. Temperature, Dry Bulb:

a. Air: Within 0.5 deg F.
b. Space: Within 0.5 deg F.

J. Environmental Conditions for Controllers, Gateways, and Routers:

1. Products shall operate without performance degradation under ambient environmental temperature, pressure and humidity conditions encountered for installed location.

a. If product alone cannot comply with requirement, install product in a protective enclosure that is isolated and protected from conditions impacting performance. Enclosure shall be internally insulated, electrically heated, cooled and ventilated as required by product and application.

2. Products shall be protected with enclosures satisfying the following minimum requirements unless more stringent requirements are indicated. Products not available with integral enclosures complying with requirements indicated shall be housed in protective secondary enclosures. Installed location shall dictate the following NEMA 250 enclosure requirements:

a. Outdoors, Protected: Type 3.
b. Outdoors, Unprotected: Type 4.
c. Indoors, Heated with Filtered Ventilation: Type 1 or Type 2.
d. Indoors, Heated with Non-Filtered Ventilation: Type 2.
e. Indoors, Heated and Air Conditioned: Type 1.
f. Mechanical Equipment Rooms:

1) Air-Moving Equipment Rooms: Type 1.

g. Localized Areas Exposed to Washdown: Type 4.
h. Within Duct Systems and Air-Moving Equipment Not Exposed to Possible Condensation: Type 2.
i. Within Duct Systems and Air-Moving Equipment Exposed to Possible Condensation: Type 4.

K. Environmental Conditions for Instruments and Actuators:

1. Instruments and actuators shall operate without performance degradation under the ambient environmental temperature, pressure, humidity, and vibration conditions specified and encountered for installed location.

a. If instruments and actuators alone cannot comply with requirement, install instruments and actuators in protective enclosures that are isolated and protected from conditions impacting performance. Enclosure shall be internally insulated, electrically heated and ventilated as required by instrument and application.

L. DDC System Reliability:

1. Design, install and configure DDC controllers, devices and to yield a MTBF of at least 40,000 hours, based on a confidence level of at least 90 percent. MTBF value shall include any failure for any reason to any part of products indicated.
2. If required to comply with MTBF indicated, include DDC system and product redundancy to maintain DCC system, and associated systems and equipment that are being controlled, operational and under automatic control.
3. Critical systems and equipment that require a higher degree of DDC system redundancy than MTBF indicated shall be indicated on Drawings.

M. Electric Power Quality:

1. Power-Line Surges:

a. Protect DDC system products connected to ac power circuits from power-line surges.
b. Do not use fuses for surge protection.

2. Power Conditioning:

a. Protect susceptible DDC system products connected to ac power circuits from irregularities and noise rejection. Characteristics of power-line conditioner shall be as follows:

1) At 85 percent load, output voltage shall not deviate by more than plus or minus 1 percent of nominal when input voltage fluctuates between minus 20 percent to plus 10 percent of nominal.
2) During load changes from zero to full load, output voltage shall not deviate by more than plus or minus 3 percent of nominal.
3) Accomplish full correction of load switching disturbances within five cycles, and 95 percent correction within two cycles of onset of disturbance.
4) Total harmonic distortion shall not exceed 3-1/2 percent at full load.

3. Ground Fault: Protect products from ground fault by providing suitable grounding. Products shall not fail due to ground fault condition.

N. Backup Power Source:

1. HVAC systems and equipment served by a backup power source shall have associated DDC system products that control such systems and equipment also served from a backup power source.

O. UPS:

1. DDC system products powered by UPS units shall include the following:

a. Desktop workstations.
b. Printers.
c. Servers.

P. Continuity of Operation after Electric Power Interruption:

1. Equipment and associated factory-installed controls, field-installed controls, electrical equipment, and power supply connected to building normal and backup power systems shall automatically return equipment and associated controls to operating state occurring immediately before loss of normal power, without need for manual intervention by operator when power is restored either through backup power source or through normal power if restored before backup power is brought online.

2.5 SYSTEM ARCHITECTURE

A. System architecture shall consist of no more than two levels of LANs.

1. Level one LAN shall connect network controllers and operator workstations.
2. Level one or Level two LAN shall connect programmable application controllers to other programmable application controllers, and to network controllers.
3. Level two LAN shall connect application-specific controllers to programmable application controllers and network controllers.
4. Level two LAN shall connect application-specific controllers to application-specific controllers.

B. DDC system shall consist of dedicated and separated LANs that are not shared with other building systems and tenant data and communication networks.

C. System architecture shall be modular and have inherent ability to expand to not less than two times system size indicated with no impact to performance indicated.

D. System architecture shall perform modifications without having to remove and replace existing network equipment.

E. Number of LANs and associated communication shall be transparent to operator. All I/O points residing on any LAN shall be capable of global sharing between all system LANs.

F. System design shall eliminate dependence on any single device for system alarm reporting and control execution. Each controller shall operate independently by performing its' own control, alarm management and historical data collection.

G. Special Network Architecture Requirements:

1. Air-Handling Systems: For control applications of an air-handling system that consists of air-handling unit(s) and VAV or CAV terminal units, include a dedicated LAN of application-specific controllers serving VAV or CAV terminal units connected directly to controller that is controlling air-handling system air-handling unit(s). Create a DDC system LAN that aligns with air-handling system being controlled.

2.6 DDC SYSTEM OPERATOR INTERFACES

A. Operator Means of System Access: Operator shall be able to access entire DDC system through any of multiple means, including, but not limited to, the following:

1. Desktop and portable workstation with hardwired connection through LAN port.
2. Portable operator terminal with hardwired connection through LAN port.
3. Portable operator workstation with wireless connection through LAN router.
4. Mobile device and application with secured wireless connection through LAN router or cellular data service.
5. Remote connection through web access.

B. Access to system, regardless of operator means used, shall be transparent to operator.

C. Network Ports: For hardwired connection of desktop or portable workstation. Network port shall be easily accessible, properly protected, clearly labeled, and installed at the following locations:

1. Each mechanical equipment room.
2. Each different roof level with roof-mounted air-handling units or rooftop units.

D. Mobile Device:

1. Connect to system through a wireless router connected to LAN and cellular data service.
2. Able to communicate with any DDC controller connected to DDC system using a dedicated application and secure web access.

E. Critical Alarm Reporting:

1. Operator-selected critical alarms shall be sent by DDC system to notify operator of critical alarms that require immediate attention.
2. DDC system shall send alarm notification to multiple recipients that are assigned for each alarm.
3. DDC system shall notify recipients by any or all means, including e-mail, text message and prerecorded phone message to mobile and landline phone numbers.

F. Simultaneous Operator Use: Capable of accommodating up to five simultaneous operators that are accessing DDC system through any one of operator interfaces indicated.

2.7 NETWORK COMMUNICATION PROTOCOL

A. Network communication protocol(s) used throughout entire DDC system shall be open to Owner and available to other companies for use in making future modifications to DDC system.

B. ASHRAE 135 Protocol:

1. ASHRAE 135 communication protocol shall be sole and native protocol used throughout entire DDC system.
2. DDC system shall not require use of gateways except to integrate HVAC equipment and other building systems and equipment, not required to use ASHRAE 135 communication protocol.
3. If used, gateways shall connect to DDC system using ASHRAE 135 communication protocol and Project object properties and read/write services indicated by interoperability schedule.
4. Operator workstations, controllers and other network devices shall be tested and listed by BACnet Testing Laboratories.

C. Industry Standard Protocols:

1. DDC system shall use any one or a combination of the following industry standard protocols for network communication while complying with other DDC system requirements indicated:

    a. ASHRAE 135.

2. Operator workstations and network controllers shall communicate through ASHRAE 135 protocol.
3. Portions of DDC system networks using ASHRAE 135 communication protocol shall be an open implementation of network devices complying with ASHRAE 135. Network devices shall be tested and listed by BACnet Testing Laboratories.

2.8 DESKTOP WORKSTATIONS

A. Description: A tower or all-in-one computer designed for normal use at a single, semipermanent location.

B. Performance Requirements:

1. Performance requirements may dictate equipment exceeding minimum requirements indicated.
2. Energy Star compliant.

C. Personal Computer:

1. Minimum Processor Speed: 5.4 GHz.
2. RAM:

    a. Capacity: 16 GB.

3. Hard Drive:

a. Media: Rotating disc, nominal rotational speed of 7200 rpm.
b. Number of Hard Drives: One.
c. Capacity: 1 TB.

4. Network Interface Card: Include card with connection, as applicable.

a. 10-100-1000 base TX Ethernet with RJ45 connector port.

D. Keyboard:

1. 101 enhanced keyboard.
2. Full upper- and lowercase ASCII keyset, numeric keypad, dedicated cursor control keypad, and 12 programmable function keys.

E. Pointing Device:

1. Either a two- or three-button mouse.

2.9 PORTABLE WORKSTATIONS

A. Description: A self-contained computer designed to allow for normal use in different locations and conditions.

B. Performance Requirements:

1. Performance requirements may dictate equipment exceeding minimum requirements indicated.
2. Energy Star compliant.
3. Hardware and software shall support local down-loading to DDC controllers.
4. Data transfer rate to DDC controller shall be at network speed.

C. Processor:

1. Minimum Processor Speed: 4.7 GHz.
2. RAM:

a. Capacity: 16 GB.

3. Hard Drive:

a. Number of Hard Drives: One.
b. Capacity: 500 GB.

D. Input and Output Ports:

1. Four USB 3.0 ports.
2. HDMI port.

E. Battery:

1. Battery life of at least three years.

2. Battery charge time of less than three hours.

F. Keyboard:

1. 85-key backlit keyboard.
2. Full upper- and lowercase ASCII keyset.

G. Integral Pointing Device: Touchpad with two buttons. Gesture enabled.

H. Display:

1. Antiglare screen.
2. 1920 by 1080 pixel resolution.

I. Network Interfaces:

1. Network Interface Card: Include card with connection, as application.

a. 10-100-1000 base TX Ethernet with RJ45 connector port.

J. Accessories:

1. Nylon carrying case.
2. Wireless optical mouse.
3. HDMI cable. Minimum cable length shall be 6 feet.

2.10 PRINTERS

A. Color Inkjet Printer:

1. Inkjet technology with true four-color printing (black, cyan, magenta, and yellow).
2. Print quality of 1200 by 600 dots per inch with black on inkjet paper and 4800 by 1200 dots per inch color printing on premium photo paper.

2.11 SYSTEM SOFTWARE

A. System Software Minimum Requirements:

1. Real-time multitasking and multiuser 64-bit operating system that allows concurrent multiple operator workstations operating and concurrent execution of multiple real-time programs and custom program development.
2. Operating system shall be capable of operating DOS and Microsoft Windows applications.
3. Network communications software shall manage and control multiple network communications to provide exchange of global information and execution of global programs.
4. Operator interface software shall include day-to-day operator transaction processing, alarm and report handling, operator privilege level and data segregation control, custom programming, and online data modification capability.

5. Scheduling software shall schedule centrally based time and event, temporary, and exception day programs.

B. Operator Interface Software:

1. Minimize operator training through use of English language prorating and English language point identification.
2. Minimize use of a typewriter-style keyboard through use of a pointing device similar to a mouse.
3. Operator sign-off shall be a manual operation or, if no keyboard or mouse activity takes place, an automatic sign-off.
4. Automatic sign-off period shall be programmable from one to 60 minutes in one-minute increments on a per operator basis.
5. Security Access:

    a. Operator access to DDC system shall be under password control.
    b. An alphanumeric password shall be field assignable to each operator.
    c. Operators shall be able to access DDC system by entry of proper password.
    d. Operator password shall be same regardless of which computer or other interface means is used.
    e. Additions or changes made to passwords shall be updated automatically.
    f. Each operator shall be assigned an access level to restrict access to data and functions the operator is cable of performing.
    g. Software shall have at least five access levels.
    h. Each menu item shall be assigned an access level so that a one-for-one correspondence between operator assigned access level(s) and menu item access level(s) is required to gain access to menu item.
    i. Display menu items to operator with those capable of access highlighted. Menu and operator access level assignments shall be online programmable and under password control.

6. Operators shall be able to perform commands including, but not limited to, the following:

    a. Start or stop selected equipment.
    b. Adjust set points.
    c. Add, modify, and delete time programming.
    d. Enable and disable process execution.
    e. Lock and unlock alarm reporting for each point.
    f. Enable and disable totalization for each point.
    g. Enable and disable trending for each point.
    h. Override control loop set points.
    i. Enter temporary override schedules.
    j. Define holiday and event schedules.
    k. Change time and date.
    l. Enter and modify analog alarm limits.
    m. Enter and modify analog warning limits.
    n. View limits.
    o. Enable and disable demand limiting.

7. Reporting:

    a. Generated automatically and manually.

b. Sent to displays, printers and disk files.
c. Types of Reporting:

1) General listing of points.
2) List points currently in alarm.
3) List of off-line points.
4) List points currently in override status.
5) List of disabled points.
6) List points currently locked out.
7) List weekly schedules.
8) List holiday programming.

8. Summaries: For specific points, for a logical point group, for an operator selected group(s), or for entire system without restriction due to hardware configuration.

C. Graphic Interface Software:

1. Include a full interactive graphical selection means of accessing and displaying system data to operator. Include at least five levels with the penetration path operator assignable (for example, site, building, floor, air-handling unit, and supply temperature loop). Native language descriptors assigned to menu items are to be operator defined and modifiable under password control.
2. Include a hierarchical-linked dynamic graphic operator interface for accessing and displaying system data and commanding and modifying equipment operation. Interface shall use a pointing device with pull-down or penetrating menus, color and animation to facilitate operator understanding of system.
3. Include at least 10 levels of graphic penetration with the hierarchy operator assignable.
4. Descriptors for graphics, points, alarms and such shall be modified through operator's workstation under password control.
5. Graphic displays shall be online user definable and modifiable using the hardware and software provided.
6. Data to be displayed within a graphic shall be assignable regardless of physical hardware address, communication or point type.
7. Graphics are to be online programmable and under password control.
8. Points may be assignable to multiple graphics where necessary to facilitate operator understanding of system operation.
9. Graphics shall also contain software points.
10. Penetration within a graphic hierarchy shall display each graphic name as graphics are selected to facilitate operator understanding.
11. Display operator accessed data on the monitor.
12. Operator shall select further penetration using pointing device to click on a site, building, floor, area, equipment, and so on. Defined and linked graphic below that selection shall then be displayed.
13. Dynamic data shall be assignable to graphics.
14. Use color, rotation, or other highly visible means, to denote status and alarm states. Color shall be variable for each class of points, as chosen by operator.
15. Points shall be dynamic update rates on a per point basis.
16. For operators with appropriate privilege, points shall be commanded directly from display using pointing device.

D. Project-Specific Graphics: Graphics documentation including, but not limited to, the following:

1. Site plan showing each building, and additional site elements, which are being controlled or monitored by DDC system.
2. Plan for each building floor and the roof, showing the following:

    a. Room layouts with room identification and name.
    b. Locations and identification of all monitored and controlled HVAC equipment and other equipment being monitored and controlled by DDC system.
    c. Location and identification of each hardware point being controlled or monitored by DDC system.

3. Control schematic for each of following, including a graphic system schematic representation, similar to that indicated on Drawings, with point identification, set point and dynamic value indication, sequence of operation and controller wiring diagram.
4. Graphic display for each piece of equipment connected to DDC system through a data communications link. Include dynamic indication of all points associated with equipment.
5. DDC system network riser diagram that shows schematic layout for entire system including all networks and all controllers, operator workstations and other network devices.

E. Customizing Software:

1. Software to modify and tailor DDC system to specific and unique requirements of equipment installed, to programs implemented and to staffing and operational practices planned.
2. Online modification of DDC system configuration, program parameters, and database using menu selection and keyboard entry of data into preformatted display templates.
3. As a minimum, include the following modification capability:

    a. Operator assignment shall include designation of operator passwords, access levels, point segregation and auto sign-off.
    b. System text addition and change capability shall include English or native language descriptors for points and access levels and action messages for alarms, run time and trouble condition.
    c. Time and schedule change capability shall include time and date set, time and occupancy schedules, exception and holiday schedules and daylight savings time schedules.
    d. Point related change capability shall include the following:

        1) System and point enable and disable.
        2) Assignment of alarm and warning limits.

    e. Application program change capability shall include the following:

        1) Programming changes.

4. Software shall allow operator to add points, or groups of points, to DDC system and to link them to energy optimization and management programs. Additions and modifications shall be online programmable using operator workstation, downloaded to other network devices and entered into their databases. After verification of point additions and associated program operation, database shall be uploaded and recorded on hard drive and disk for archived record.

F. Alarm Handling Software:

1. Include alarm handling software to report all alarm conditions monitored and transmitted through DDC controllers and other network devices.
2. Include first in, first out handling of alarms according to alarm priority ranking, with most critical alarms first, and with buffer storage in case of simultaneous and multiple alarms.
3. Alarm handling shall be active at all times to ensure that alarms are processed even if an operator is not currently signed on to DDC system.
4. Alarms display shall include the following:

    a. Indication of alarm condition such as "Abnormal Off," "Hi Alarm," and "Low Alarm."
    b. "Analog Value" or "Status" group and point identification with native language point descriptor such as "Space Temperature, Building 110, 2nd Floor, Room 212."
    c. Discrete per point alarm action message, such as "Call Maintenance Dept. Ext-5561."
    d. Include extended message capability to allow assignment and printing of extended action messages. Capability shall be operator programmable and assignable on a per point basis.

5. Alarms shall be directed to appropriate operator workstations, printers, and individual operators by privilege level and assignments.
6. Include an unacknowledged alarm indicator on display to alert operator that there are unacknowledged alarms in system. Operator shall be able to acknowledge alarms on an individual basis or through a multiple alarm acknowledge key, depending on alarm class.

G. Reports and Logs:

1. Include reporting software package that allows operator to select, modify, or create reports using DDC system I/O point data available.
2. Each report shall be definable as to data content, format, interval and date.
3. Report data shall be sampled and stored on DDC controller, within storage limits of DDC controller, and then uploaded to archive on workstation for historical reporting.
4. Operator shall be able to obtain real-time logs of all I/O points by type or status, such as alarm, point lockout, or normal.
5. Reports and logs shall be stored on workstation hard drives in a format that is readily accessible by other standard software applications, including spreadsheets and word processing.
6. Reports and logs shall be readily printed and set to be printed either on operator command or at a specific time each day.

H. Standard Reports: Standard DDC system reports shall be provided and operator shall be able to customize reports later.

1. All I/O: With current status and values.
2. Alarm: All current alarms, except those in alarm lockout.
3. Disabled I/O: All I/O points that are disabled.
4. Alarm Lockout I/O: All I/O points in alarm lockout, whether manual or automatic.
5. Alarm Lockout I/O in Alarm: All I/O in alarm lockout that are currently in alarm.
6. Logs:

a. Alarm history.
b. System messages.
c. System events.
d. Trends.

I. Standard Trends:

1. Trend all I/O point present values, set points, and other parameters indicated for trending.
2. Trends shall be associated into groups, and a trend report shall be set up for each group.
3. Trends shall be stored within DDC controller and uploaded to hard drives automatically on reaching 75 percent of DDC controller buffer limit, or by operator request, or by archiving time schedule.
4. Preset trend intervals for each I/O point after review with Owner.
5. Trend intervals shall be operator selectable from 10 seconds up to 60 minutes. Minimum number of consecutive trend values stored at one time shall be 100 per variable.
6. When drive storage memory is full, most recent data shall overwrite oldest data.
7. Archived and real-time trend data shall be available for viewing numerically and graphically by operators.

J. Programming Software:

1. Include programming software to execute sequences of operation indicated.
2. Include programming routines in simple and easy to follow logic with detailed text comments describing what the logic does and how it corresponds to sequence of operation.
3. Include means for detecting programming errors and testing software control strategies with a simulation tool before implementing in actual control. Simulation tool may be inherent with programming software or as a separate product.

2.12 ASHRAE 135 GATEWAYS

A. Include BACnet communication ports, whenever available as an equipment OEM standard option, for integration via a single communication cable. BACnet-controlled plant equipment includes, but is not limited to, boilers, and variable-speed drives.

2.13 DDC CONTROLLERS

A. DDC system shall consist of a combination of network controllers, programmable application controllers and application-specific controllers to satisfy performance requirements indicated.

B. DDC controllers shall perform monitoring, control, energy optimization and other requirements indicated.

C. DDC controllers shall use a multitasking, multiuser, real-time digital control microprocessor with a distributed network database and intelligence.

D. Each DDC controller shall be capable of full and complete operation as a completely independent unit and as a part of a DDC system wide distributed network.

E. Environment Requirements:

1. Controller hardware shall be suitable for the anticipated ambient conditions.

F. Power and Noise Immunity:

1. Controller shall operate at 90 to 110 percent of nominal voltage rating and shall perform an orderly shutdown below 80 percent of nominal voltage.
2. Operation shall be protected against electrical noise of 5 to 120 Hz and from keyed radios with up to 5 W of power located within36 inches of enclosure.

G. DDC Controller Spare Processing Capacity:

1. Include spare processing memory for each controller. RAM, PROM, or EEPROM will implement requirements indicated with the following spare memory:

a. Network Controllers: 50 percent.
b. Programmable Application Controllers: Not less than 60 percent.
c. Application-Specific Controllers: Not less than 70 percent.

H. DDC Controller Spare I/O Point Capacity: Include spare I/O point capacity for each controller as follows:

1. Network Controllers:

a. 10 percent of each AI, AO, BI, and BO point connected to controller.
b. Minimum Spare I/O Points per Controller:

1) AIs: Two.
2) AOs: Two.
3) BIs: Three.
4) BOs: Three.

2. Programmable Application Controllers:

a. 10 percent of each AI, AO, BI, and BO point connected to controller.
b. Minimum Spare I/O Points per Controller:

1) AIs: Three.
2) AOs: Three.
3) BIs: Three.
4) BOs: Three.

3. Application-Specific Controllers:

a. 10 percent of each AI, AO, BI, and BO point connected to controller.
b. Minimum Spare I/O Points per Controller:

1) AIs: One.
2) AOs: One.
3) BIs: One.
4) BOs: One.

I. Maintenance and Support: Include the following features to facilitate maintenance and support:

1. Mount microprocessor components on circuit cards for ease of removal and replacement.
2. Means to quickly and easily disconnect controller from network.
3. Means to quickly and easily access connect to field test equipment.
4. Visual indication that controller electric power is on, of communication fault or trouble, and that controller is receiving and sending signals to network.

J. Input and Output Point Interface:

1. Hardwired input and output points shall connect to network, programmable application and application-specific controllers.
2. Input and output points shall be protected so shorting of point to itself, to another point, or to ground will not damage controller.
3. Input and output points shall be protected from voltage up to 24 V of any duration so that contact will not damage controller.
4. AIs:

    a. AIs shall include monitoring of low-voltage (zero- to 10-V dc), current (4 to 20 mA) and resistance signals from thermistor and RTD sensors.
    b. AIs shall be compatible with, and field configurable to, sensor and transmitters installed.
    c. Controller AIs shall perform analog-to-digital (A-to-D) conversion with a minimum resolution of 12 bits or better to comply with accuracy requirements indicated.
    d. Signal conditioning including transient rejection shall be provided for each AI.
    e. Capable of being individually calibrated for zero and span.
    f. Incorporate common-mode noise rejection of at least 50 dB from zero to 100 Hz for differential inputs, and normal-mode noise rejection of at least 20 dB at 60 Hz from a source impedance of 10000 ohms.

5. AOs:

    a. Controller AOs shall perform analog-to-digital (A-to-D) conversion with a minimum resolution of 12 bits or better to comply with accuracy requirements indicated.
    b. Output signals shall have a range of 4 to 20 mA dc or zero- to 10-V dc as required to include proper control of output device.
    c. Capable of being individually calibrated for zero and span.
    d. AOs shall not exhibit a drift of greater than 0.4 percent of range per year.
    e. Network and programmable application controller AOs shall be equipped with individual H-O-A switches and output adjustment potentiometers for use in the hand position.

6. BIs:

    a. Controller BIs shall accept contact closures and shall ignore transients of less than 5-ms duration.
    b. Isolation and protection against an applied steady-state voltage of up to 180-V ac peak.
    c. BIs shall include a wetting current of at least 12 mA to be compatible with commonly available control devices and shall be protected against effects of contact bounce and noise.

d. BIs shall sense "dry contact" closure without external power (other than that provided by the controller) being applied.
e. Pulse accumulation input points shall comply with all requirements of BIs and accept up to 10 pulses per second for pulse accumulation. Buffer shall be provided to totalize pulses. Pulse accumulator shall accept rates of at least 20 pulses per second. The totalized value shall be reset to zero on operator's command.

7. BOs:

a. Controller BOs shall include relay contact closures or triac outputs for momentary and maintained operation of output devices.

1) Relay contact closures shall have a minimum duration of 0.1 second. Relays shall include at least 180 V of isolation. Electromagnetic interference suppression shall be provided on all output lines to limit transients to non-damaging levels. Minimum contact rating shall be 1 A at 24-V ac.
2) Triac outputs shall include at least 180 V of isolation. Minimum contact rating shall be 1 A at 24-V ac.

b. BOs shall include for two-state operation or a pulsed low-voltage signal for pulse-width modulation control.
c. BOs shall be selectable for either normally open or normally closed operation.
d. Include tristate outputs (two coordinated BOs) for control of three-point floating-type electronic actuators without feedback.
e. Limit use of three-point floating devices to VAV terminal unit control applications. Control algorithms shall operate actuator to one end of its stroke once every 24 hours for verification of operator tracking.

2.14 NETWORK CONTROLLERS

A. General Network Controller Requirements:

1. Include adequate number of controllers to achieve performance indicated.
2. System shall consist of one or more independent, standalone, microprocessor-based network controllers to manage global strategies indicated.
3. Controller shall have enough memory to support its operating system, database, and programming requirements.
4. Data shall be shared between networked controllers and other network devices.
5. Operating system of controller shall manage input and output communication signals to allow distributed controllers to share real and virtual object information and allow for central monitoring and alarms.
6. Controller shall continually check status of its processor and memory circuits. If an abnormal operation is detected, controller shall assume a predetermined failure mode and generate an alarm notification.
7. Controllers shall be fully programmable.

B. Communication:

1. Network controllers shall communicate with other devices on DDC system Level one network.

2. Network controller also shall perform routing if connected to a network of programmable application and application-specific controllers.

C. Operator Interface:

1. Controller shall be equipped with a service communications port for connection to a portable operator's workstation or mobile device.

D. Serviceability:

1. Controller shall be equipped with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
2. Wiring and cable connections shall be made to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
3. Controller shall maintain BIOS and programming information in event of a power loss for at least 96 hours.

2.15 PROGRAMMABLE APPLICATION CONTROLLERS

A. General Programmable Application Controller Requirements:

1. Include adequate number of controllers to achieve performance indicated.
2. Controller shall have enough memory to support its operating system, database, and programming requirements.
3. Data shall be shared between networked controllers and other network devices.
4. Operating system of controller shall manage input and output communication signals to allow distributed controllers to share real and virtual object information and allow for central monitoring and alarms.
5. Controller shall continually check status of its processor and memory circuits. If an abnormal operation is detected, controller shall assume a predetermined failure mode and generate an alarm notification.
6. Controllers shall be fully programmable.

B. Communication:

1. Programmable application controllers shall communicate with other devices on network.

C. Operator Interface:

1. Controller shall be equipped with a service communications port for connection to a portable operator's workstation or mobile device.

D. Serviceability:

1. Controller shall be equipped with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
2. Wiring and cable connections shall be made to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
3. Controller shall maintain BIOS and programming information in event of a power loss for at least 72 hours.

2.16 APPLICATION-SPECIFIC CONTROLLERS

A. Description: Microprocessor-based controllers, which through hardware or firmware design are dedicated to control a specific piece of equipment. Controllers are not fully user-programmable but are configurable and customizable for operation of equipment they are designed to control.

1. Capable of standalone operation and shall continue to include control functions without being connected to network.
2. Data shall be shared between networked controllers and other network devices.

B. Communication: Application-specific controllers shall communicate with other application-specific controller and devices on network, and to programmable application and network controllers.

C. Operator Interface: Controller shall be equipped with a service communications port for connection to a portable operator's workstation. Connection shall extend to port on space temperature sensor that is connected to controller.

D. Serviceability:

1. Controller shall be equipped with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
2. Wiring and cable connections shall be made to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
3. Controller shall use nonvolatile memory and maintain all BIOS and programming information in event of power loss.

2.17 CONTROLLER SOFTWARE

A. General Controller Software Requirements:

1. Software applications shall reside and operate in controllers. Editing of applications shall occur at operator workstations.
2. I/O points shall be identified by up to 30-character point name and up to 16-character point descriptor. Same names shall be used at operator workstations.
3. Control functions shall be executed within controllers using DDC algorithms.
4. Controllers shall be configured to use stored default values to ensure fail-safe operation. Default values shall be used when there is a failure of a connected input instrument or loss of communication of a global point value.

B. Security:

1. Operator access shall be secured using individual security passwords and user names.
2. Passwords shall restrict operator to points, applications, and system functions as assigned by system manager.
3. Operator log-on and log-off attempts shall be recorded.
4. System shall protect itself from unauthorized use by automatically logging off after last keystroke. The delay time shall be operator-definable.

C. Scheduling: Include capability to schedule each point or group of points in system.

D. System Coordination:

1. Include standard application for proper coordination of equipment.
2. Application shall include operator with a method of grouping together equipment based on function and location.
3. Group may then be used for scheduling and other applications.

E. Binary Alarms:

1. Each binary point shall be set to alarm based on operator-specified state.
2. Include capability to automatically and manually disable alarming.

F. Analog Alarms:

1. Each analog object shall have both high and low alarm limits.
2. Alarming shall be able to be automatically and manually disabled.

G. Alarm Reporting:

1. Operator shall be able to determine action to be taken in event of an alarm.
2. Alarms shall be routed to appropriate operator workstations based on time and other conditions.
3. Alarm shall be able to start programs, print, be logged in event log, generate custom messages, and display graphics.

H. Remote Communication:

1. System shall have ability to dial out in the event of an alarm.

I. Maintenance Management: System shall monitor equipment status and generate maintenance messages based on operator-designated run-time, starts, and calendar date limits.

J. Sequencing: Include application software based on sequences of operation indicated to properly sequence chillers, boilers, and other applicable HVAC equipment.

K. Control Loops:

1. Support any of the following control loops, as applicable to control required:

a. Two-position (on/off, open/close, slow/fast) control.
b. Proportional control.
c. Proportional plus integral (PI) control.
d. Proportional plus integral plus derivative (PID) control.

1) Include PID algorithms with direct or reverse action and anti-windup.
2) Algorithm shall calculate a time-varying analog value used to position an output or stage a series of outputs.
3) Controlled variable, set point, and PID gains shall be operator-selectable.

e. Adaptive (automatic tuning).

L. Staggered Start: Application shall prevent all controlled equipment from simultaneously restarting after a power outage. Order which equipment (or groups of equipment) is started, along with the time delay between starts, shall be operator-selectable.

M. Anti-Short Cycling:

1. BO points shall be protected from short cycling.
2. Feature shall allow minimum on-time and off-time to be selected.

N. On and Off Control with Differential:

1. Include an algorithm that allows a BO to be cycled based on a controlled variable and set point.
2. Algorithm shall be direct- or reverse-acting and incorporate an adjustable differential.

O. Run-Time Totalization:

1. Include software to totalize run-times for all BI and BO points.
2. A high run-time alarm shall be assigned, if required, by operator.

2.18 ENCLOSURES

A. General Enclosure Requirements:

1. House each controller and associated control accessories in an enclosure. Enclosure shall serve as central tie-in point for control devices such as switches, transmitters, transducers, power supplies and transformers.
2. Do not house more than one controller in a single enclosure.
3. Include enclosure door with key locking mechanism. Key locks alike for all enclosures and include one pair of keys per enclosure.
4. Include wall-mounted enclosures with brackets suitable for mounting enclosures to wall or freestanding support stand as required.
5. Supply each enclosure with a complete set of as-built schematics and wiring diagrams and product literature located in a pocket on inside of door.

B. Environmental Requirements:

1. Evaluate temperature and humidity requirements of each product to be installed within each enclosure.
2. Where required by application, include temperature-controlled electrical heat to maintain inside of enclosure above minimum operating temperature of product with most stringent requirement.

2.19 RELAYS

A. General-Purpose Relays:

1. Relays shall be heavy duty and rated for at least 10 A at 250-V ac and 60 Hz.
2. Relays shall be either double pole double throw (DPDT) or three-pole double throw, depending on the control application.

3. Relays shall have LED indication.

B. Current Sensing Relay:

1. Monitors ac current.
2. Independent adjustable controls for pickup and dropout current.
3. Energized when supply voltage is present and current is above pickup setting.
4. De-energizes when monitored current is below dropout current.
5. Dropout current is adjustable from 50 to 95 percent of pickup current.

2.20 ELECTRICAL POWER DEVICES

A. Transformers:

1. Transformer shall be sized for the total connected load, plus an additional 25 percent of connected load.
2. Transformer shall be at least 40 VA.
3. Transformer shall have both primary and secondary fuses.

B. Power-Line Conditioner:

1. General Power-Line Conditioner Requirements:

a. Design to ensure maximum reliability, serviceability and performance.
b. Overall function of the power-line conditioner is to receive raw, polluted electrical power and purify it for use by electronic equipment. The power-line conditioner shall provide isolated, regulated, transient and noise-free sinusoidal power to loads served.

2. Standards: NRTL listed per UL 1012.

2.21 UNINTERRUPTABLE POWER SUPPLY (UPS) UNITS FOR WORKSTATIONS

A. 250 through 1000 VA:

1. UPS units shall provide continuous, regulated output power without using their batteries during brown-out, surge, and spike conditions.
2. Load served shall not exceed 75 percent of UPS rated capacity, including power factor of connected loads.

a. Larger-capacity units shall be provided for systems with larger connected loads.
b. UPS shall provide five minutes of battery power.

3. Performance:

a. Input Voltage: Single phase, 120- or 230-V ac, compatible with field power source.
b. Load Power Factor Range (Crest Factor): 0.65 to 1.0.
c. Output Voltage: 101- to 132-V ac, while input voltage varies between 89 and 152-V ac.

d. On Battery Output Voltage: Sine wave.
e. Inverter overload capacity shall be minimum 150 percent for 30 seconds.
f. Recharge time shall be a maximum of six hours to 90 percent capacity after full discharge to cutoff.
g. Transfer Time: 6 ms.
h. Surge Voltage Withstand Capacity: IEEE C62.41, Categories A and B; 6 kV/200 and 500 A; 100-kHz ringwave.

4. UPS shall be automatic during fault or overload conditions.
5. Unit with integral line-interactive, power condition topology to eliminate all power contaminants.
6. Include front panel with power switch and visual indication of power, battery, fault and temperature.
7. Unit shall include an audible alarm of faults and front panel silence feature.
8. Unit with four NEMA WD 1, NEMA WD 6 Configuration 5-15R receptacles.
9. Batteries shall be sealed lead-acid type and be maintenance free. Battery replacement shall be front accessible by user without dropping load.
10. Include tower models installed in ventilated cabinets to the particular installation location.

B. 1000 through 3000 VA:

1. UPS units shall provide continuous, regulated output power without using their batteries during brown-out, surge, and spike conditions.
2. Load served shall not exceed 75 percent of UPS rated capacity, including power factor of connected loads.

a. Larger-capacity units, or multiple units, shall be provided for systems with larger connected loads.
b. UPS shall provide five minutes of battery power.

3. Performance:

a. Input Voltage: Single phase, 120-V ac, plus 20 to minus 30 percent.
b. Power Factor: Minimum 0.97 at full load.
c. Output Voltage: Single phase, 120-V ac, within 3 percent, steady state with rated output current of 10.0 A, 30.0-A peak.
d. Inverter overload capacity shall be minimum 150 percent for 30 seconds.
e. Recharge time shall be a maximum of eight hours to 90 percent capacity.

4. UPS bypass shall be automatic during fault or overload conditions.
5. UPS shall include dry contacts (digital output points) for low battery condition and battery-on (primary utility power failure).
6. Batteries shall be sealed lead-acid type and be maintenance free.
7. Include tower models installed in ventilated cabinets or rack models installed on matching racks, as applicable to the particular installation location and space availability/configuration.

2.22 CONTROL WIRE AND CABLE

A. LAN and Communication Cable: Comply with DDC system manufacturer requirements for network being installed.

1. Cable shall be balanced twisted pair.
2. Comply with the following requirements and for balanced twisted pair cable described in Section 260523 "Control-Voltage Electrical Power Cables" and Section 271513 "Communications Copper Horizontal Cabling."

a. Cable shall be plenum rated.
b. Cable shall have a unique color that is different from other cables used on Project.

2.23 RACEWAYS

A. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems" for electrical power raceways and boxes.

B. Comply with requirements in Section 270528 "Pathways for Communications Systems" for raceways for balanced twisted pair cables and optical fiber cables.

C. Provide junction boxes for wall-mounted thermostats and wall-mounted temperature sensors, and provide conduit from junction box to an accessible location above a ceiling.

2.24 ACCESSORIES

A. Damper Blade Limit Switches:

1. Sense positive open and/or closed position of the damper blades.
2. NEMA 250, Type 13, oil-tight construction.
3. Arrange for the mounting application.
4. Additional waterproof enclosure when required by its environment.
5. Arrange to prevent "over-center" operation.

2.25 IDENTIFICATION

A. Control Equipment, Instruments, and Control Devices:

1. Self-adhesive label bearing unique identification.

a. Include instruments with unique identification identified by equipment being controlled or monitored, followed by point identification.

2. Letter size shall be as follows:

a. Operator Workstations: Minimum of 0.5 inch high.
b. Printers: Minimum of 0.5 inch high.
c. DDC Controllers: Minimum of 0.5 inch high.
d. Repeaters: Minimum of 0.5 inch high.

e. Enclosures: Minimum of 0.5 inch high.
f. Electrical Power Devices: Minimum of 0.25 inch high.
g. UPS units: Minimum of 0.5 inch high.
h. Accessories: Minimum of 0.25 inch high.
i. Instruments: Minimum of 0.25 inch high.
j. Control Damper and Valve Actuators: Minimum of 0.25 inch high.

3. Legend shall consist of white lettering on black background.
4. Instruments, control devices and actuators with Project-specific identification tags having unique identification numbers following requirements indicated and provided by original manufacturer do not require additional identification.

B. Raceway and Boxes:

1. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
2. Paint cover plates on junction boxes and conduit same color as the tape banding for conduits. After painting, label cover plate "HVAC Controls," using an engraved phenolic tag.

C. Equipment Warning Labels:

1. Self-adhesive label with pressure-sensitive adhesive back and peel-off protective jacket.
2. Lettering size shall be at least 14-point type with white lettering on red background.
3. Warning label shall read "CAUTION-Equipment operated under remote automatic control and may start or stop at any time without warning. Switch electric power disconnecting means to OFF position before servicing."
4. Lettering shall be enclosed in a white line border. Edge of label shall extend at least 0.25 inch beyond white border.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

1. Verify compatibility with and suitability of substrates.

B. Examine roughing-in for products to verify actual locations of connections before installation.

1. Examine roughing-in for instruments installed in piping to verify actual locations of connections before installation.
2. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.

C. Examine walls, floors, roofs, and ceilings for suitable conditions where product will be installed.

D. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 DDC SYSTEM INTERFACE WITH OTHER SYSTEMS AND EQUIPMENT

A. Communication Interface to Equipment with Integral Controls:

1. DDC system shall have communication interface with equipment having integral controls and having a communication interface for remote monitoring or control.

3.3 CONTROL DEVICES FOR INSTALLATION BY INSTALLERS

A. Deliver selected control devices, specified in indicated HVAC instrumentation and control device Sections, to identified equipment and systems manufacturers for factory installation and to identified installers for field installation.

B. Deliver the following to duct fabricator and Installer for installation in ductwork. Include installation instructions to Installer and supervise installation for compliance with requirements.

1. DDC control dampers, which are specified in Section 230923.12 "DDC Control Dampers."
2. Airflow sensors and switches, which are specified in Section 230923.14 "Flow Instruments."
3. Pressure sensors, which are specified in Section 230923.23 "Pressure Instruments."

3.4 GENERAL INSTALLATION REQUIREMENTS

A. Install products to satisfy more stringent of all requirements indicated.

B. Install products level, plumb, parallel, and perpendicular with building construction.

C. Support products, piping wiring, and raceways. Brace products to prevent lateral movement and sway or a break in attachment when subjected to a force.

D. If codes and referenced standards are more stringent than requirements indicated, comply with requirements in codes and referenced standards.

E. Fabricate openings and install sleeves in ceilings, floors, roof, and walls required by installation of products. Before proceeding with drilling, punching, and cutting, check for concealed work to avoid damage. Patch, flash, grout, seal, and refinish openings to match adjacent condition.

F. Firestop Penetrations Made in Fire-Rated Assemblies: Comply with requirements in Section 078413 "Penetration Firestopping."

G. Seal penetrations made in acoustically rated assemblies. Comply with requirements in Section 079219 "Acoustical Joint Sealants."

H. Fastening Hardware:

1. Stillson wrenches, pliers, and other tools that damage surfaces of rods, nuts, and other parts are prohibited for work of assembling and tightening fasteners.
2. Tighten bolts and nuts firmly and uniformly. Do not overstress threads by excessive force or by oversized wrenches.
3. Lubricate threads of bolts, nuts and screws with graphite and oil before assembly.

I. If product locations are not indicated, install products in locations that are accessible and that will permit service and maintenance from floor, equipment platforms, or catwalks without removal of permanently installed furniture and equipment.

3.5 WORKSTATION INSTALLATION

A. Desktop Workstations Installation:

1. Install workstation(s) at location(s) directed by Owner.
2. Install multiple-receptacle power strip with cord for use in connecting multiple workstation components to a single duplex electrical power receptacle.
3. Install software on workstation(s) and verify software functions properly.
4. Develop Project-specific graphics, trends, reports, logs and historical database.
5. Power each workstation through a dedicated UPS unit. Locate UPS adjacent to workstation.

B. Portable Workstations Installation:

1. Turn over portable workstations to Owner at Substantial Completion.
2. Install software on workstation(s) and verify software functions properly.

C. Color Graphics Application:

1. Use system schematics indicated as starting point to create graphics.
2. Develop Project-specific library of symbols for representing system equipment and products.
3. Incorporate digital images of Project-completed installation into graphics where beneficial to enhance effect.
4. Submit sketch of graphic layout with description of all text for each graphic for Owner's and Architect's review before creating graphic using graphics software.
5. Seek Owner input in graphics development once using graphics software.
6. Final editing shall be done on-site with Owner's and Architect's review and feedback.
7. Refine graphics as necessary for Owner acceptance.
8. On receiving Owner acceptance, print a hard copy for inclusion in operation and maintenance manual. Prepare a scanned copy PDF file of each graphic and include with softcopy of DDC system operation and maintenance manual.

3.6 PRINTER INSTALLATION

A. Provide the following printer(s) at location(s) directed by Owner:

1. Color Inkjet: Quantity, one.

B. Install printer software on workstations and verify that software functions properly.

3.7 ROUTER INSTALLATION

A. Install routers if required for DDC system communication interface requirements indicated.

1. Install router(s) required to suit indicated requirements.

B. Test router to verify that communication interface functions properly.

3.8 CONTROLLER INSTALLATION

A. Install controllers in enclosures to comply with indicated requirements.

B. Connect controllers to field power supply.

C. Install controller with latest version of applicable software and configure to execute requirements indicated.

D. Test and adjust controllers to verify operation of connected I/O to achieve performance indicated requirements while executing sequences of operation.

E. Installation of Network Controllers:

1. Quantity and location of network controllers shall be determined by DDC system manufacturer to satisfy requirements indicated.
2. Install controllers in a protected location that is easily accessible by operators.
3. Top of controller shall be within 84 inches of finished floor.

F. Installation of Programmable Application Controllers:

1. Quantity and location of programmable application controllers shall be determined by DDC system manufacturer to satisfy requirements indicated.
2. Install controllers in a protected location that is easily accessible by operators.
3. Top of controller shall be within 84 inches of finished floor.

G. Application-Specific Controllers:

1. Quantity and location of application-specific controllers shall be determined by DDC system manufacturer to satisfy requirements indicated.
2. For controllers not mounted directly on equipment being controlled, install controllers in a protected location that is easily accessible by operators.

3.9 INSTALLATION OF WIRELESS ROUTERS FOR OPERATOR INTERFACE

A. Install wireless routers to achieve optimum performance and best possible coverage.

B. Mount wireless routers in a protected location that is within 60 inches of floor and easily accessible by operators.

3.10 ELECTRIC POWER CONNECTIONS

A. Connect electrical power to DDC system products requiring electrical power connections.

B. Design of electrical power to products not indicated with electric power is delegated to DDC system provider and installing trade. Work shall comply with NFPA 70 and other requirements indicated.

C. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers" for electrical power circuit breakers.

D. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for electrical power conductors and cables.

E. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems" for electrical power raceways and boxes.

3.11 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Comply with requirements in Section 260553 "Identification for Electrical Systems" for identification products and installation.

B. Install unique instrument identification on face of each instrument connected to a DDC controller.

C. Install unique identification on face of each control damper and valve actuator connected to a DDC controller.

D. Warning Labels and Signs:

1. Shall be permanently attached to equipment that can be automatically started by DDC control system.
2. Shall be located in highly visible location near power service entry points.

3.12 NETWORK INSTALLATION

A. Install cable in continuous raceway.

1. Where indicated on Drawings, cable trays may be used for copper cable in lieu of conduit.

3.13 NETWORK NAMING AND NUMBERING

A. Coordinate with Owner and provide unique naming and addressing for networks and devices.

B. ASHRAE 135 Networks:

1. MAC Address:

a. Every network device shall have an assigned and documented MAC address unique to its network.
b. Ethernet Networks: Document MAC address assigned at its creation.
c. ARCNET or MS/TP networks: Assign from 00 to 64.

2. Network Numbering:

a. Assign unique numbers to each new network.
b. Provide ability for changing network number through device switches or operator interface.
c. DDC system, with all possible connected LANs, can contain up to 65,534 unique networks.

3.14 CONTROL WIRE, CABLE AND RACEWAYS INSTALLATION

A. Comply with NECA 1.

B. Wire and Cable Installation:

1. Comply with installation requirements in Section 260523 "Control-Voltage Electrical Power Cables."

C. Conduit Installation:

1. Comply with Section "260533 "Raceways and Boxes for Electrical Systems" for control-voltage conductors.

3.15 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and installations, including connections.

B. Perform the following tests and inspections with the assistance of a factory-authorized service representative:

1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

3.16 DDC SYSTEM I/O CHECKOUT PROCEDURES

A. Check installed products before continuity tests, leak tests and calibration.

B. Check instruments for proper location and accessibility.

C. Check instruments for proper installation on direction of flow, elevation, orientation, insertion depth, or other applicable considerations that will impact performance.

D. Control Damper Checkout:

1. Verify that control dampers are installed correctly for flow direction.
2. Verify that proper blade alignment, either parallel or opposed, has been provided.
3. Verify that damper frame attachment is properly secured and sealed.
4. Verify that damper actuator and linkage attachment is secure.
5. Verify that actuator wiring is complete, enclosed and connected to correct power source.
6. Verify that damper blade travel is unobstructed.

E. Instrument Checkout:

1. Verify that instrument is correctly installed for location, orientation, direction and operating clearances.
2. Verify that attachment is properly secured and sealed.
3. Verify that conduit connections are properly secured and sealed.
4. Verify that wiring is properly labeled with unique identification, correct type and size and is securely attached to proper terminals.
5. Inspect instrument tag against approved submittal.
6. For instruments with tubing connections, verify that tubing attachment is secure and isolation valves have been provided.
7. For flow instruments, verify that recommended upstream and downstream distances have been maintained.
8. For temperature instruments:

   a. Verify sensing element type and proper material.
   b. Verify length and insertion.

3.17 DDC SYSTEM I/O ADJUSTMENT, CALIBRATION AND TESTING:

A. Calibrate each instrument installed that is not factory calibrated and provided with calibration documentation.

B. Provide a written description of proposed field procedures and equipment for calibrating each type of instrument. Submit procedures before calibration and adjustment.

C. For each analog instrument, make a three-point test of calibration for both linearity and accuracy.

D. Equipment and procedures used for calibration shall comply with instrument manufacturer's written instructions.

E. Provide diagnostic and test equipment for calibration and adjustment.

F. Field instruments and equipment used to test and calibrate installed instruments shall have accuracy at least twice the instrument accuracy being calibrated. An installed instrument with an accuracy of 1 percent shall be checked by an instrument with an accuracy of 0.5 percent.

G. Calibrate each instrument according to instrument instruction manual supplied by manufacturer.

H. If after calibration indicated performance cannot be achieved, replace out-of-tolerance instruments.

I. Comply with field testing requirements and procedures indicated by ASHRAE's Guideline 11, "Field Testing of HVAC Control Components," in the absence of specific requirements, and to supplement requirements indicated.

J. Analog Signals:

1. Check analog voltage signals using a precision voltage meter at zero, 50, and 100 percent.
2. Check analog current signals using a precision current meter at zero, 50, and 100 percent.
3. Check resistance signals for temperature sensors at zero, 50, and 100 percent of operating span using a precision-resistant source.

K. Digital Signals:

1. Check digital signals using a jumper wire.
2. Check digital signals using an ohmmeter to test for contact making or breaking.

L. Control Dampers:

1. Stroke and adjust control dampers following manufacturer's recommended procedure, from 100 percent open to 100 percent closed and back to 100 percent open.
2. Check and document open and close cycle times for applications with a cycle time less than 30 seconds.
3. For control dampers equipped with positive position indication, check feedback signal at multiple positions to confirm proper position indication.

M. Meters: Check sensors at zero, 50, and 100 percent of Project design values.

N. Sensors: Check sensors at zero, 50, and 100 percent of Project design values.

O. Switches: Calibrate switches to make or break contact at set points indicated.

P. Transmitters:

1. Check and calibrate transmitters at zero, 50, and 100 percent of Project design values.
2. Calibrate resistance temperature transmitters at zero, 50, and 100 percent of span using a precision-resistant source.

3.18 DDC SYSTEM CONTROLLER CHECKOUT

A. Verify power supply.

1. Verify voltage, phase and hertz.
2. Verify that protection from power surges is installed and functioning.
3. Verify that ground fault protection is installed.
4. If applicable, verify if connected to UPS unit.
5. If applicable, verify if connected to a backup power source.
6. If applicable, verify that power conditioning units, transient voltage suppression and high-frequency noise filter units are installed.

B. Verify that wire and cabling is properly secured to terminals and labeled with unique identification.

C. Verify that spare I/O capacity is provided.

3.19 DDC CONTROLLER I/O CONTROL LOOP TESTS

A. Testing:

1. Test every I/O point connected to DDC controller to verify that safety and operating control set points are as indicated and as required to operate controlled system safely and at optimum performance.
2. Test every I/O point throughout its full operating range.
3. Test every control loop to verify operation is stable and accurate.
4. Adjust control loop proportional, integral and derivative settings to achieve optimum performance while complying with performance requirements indicated. Document testing of each control loop's precision and stability via trend logs.
5. Test and adjust every control loop for proper operation according to sequence of operation.
6. Test software and hardware interlocks for proper operation. Correct deficiencies.
7. Operate each analog point at the following:

    a. Upper quarter of range.
    b. Lower quarter of range.
    c. At midpoint of range.

8. Exercise each binary point.
9. For every I/O point in DDC system, read and record each value at operator workstation, at DDC controller and at field instrument simultaneously. Value displayed at operator workstation, at DDC controller and at field instrument shall match.
10. Prepare and submit a report documenting results for each I/O point in DDC system and include in each I/O point a description of corrective measures and adjustments made to achieve desire results.

3.20 DDC SYSTEM VALIDATION TESTS

A. Perform validation tests before requesting final review of system. Before beginning testing, first submit Pretest Checklist and Test Plan.

B. After approval of Test Plan, execute all tests and procedures indicated in plan.

C. After testing is complete, submit completed test checklist.

D. Pretest Checklist: Submit the following list with items checked off once verified:

1. Detailed explanation for any items that are not completed or verified.
2. Required mechanical installation work is successfully completed and HVAC equipment is working correctly.
3. HVAC equipment motors operate below full-load amperage ratings.
4. Required DDC system components, wiring, and accessories are installed.

5. Installed DDC system architecture matches approved Drawings.
6. Control electric power circuits operate at proper voltage and are free from faults.
7. Required surge protection is installed.
8. DDC system network communications function properly, including uploading and downloading programming changes.
9. Each controller's programming is backed up.
10. Equipment, products, tubing, wiring cable and conduits are properly labeled.
11. All I/O points are programmed into controllers.
12. Testing, adjusting and balancing work affecting controls is complete.
13. Dampers and actuators zero and span adjustments are set properly.
14. Each control damper and actuator goes to failed position on loss of power.
15. Meter, sensor and transmitter readings are accurate and calibrated.
16. Control loops are tuned for smooth and stable operation.
17. View trend data where applicable.
18. Each controller works properly in standalone mode.
19. Safety controls and devices function properly.
20. Interfaces with fire-alarm system function properly.
21. Electrical interlocks function properly.
22. Operator workstations and other interfaces are delivered, all system and database software is installed, and graphic are created.
23. Record Drawings are completed.

E. Test Plan:

1. Prepare and submit a validation test plan including test procedures for performance validation tests.
2. Test plan shall address all specified functions of DDC system and sequences of operation.
3. Explain detailed actions and expected results to demonstrate compliance with requirements indicated.
4. Explain method for simulating necessary conditions of operation used to demonstrate performance.
5. Include a test checklist to be used to check and initial that each test has been successfully completed.
6. Submit test plan documentation 20 business days before start of tests.

F. Validation Test:

1. Verify operating performance of each I/O point in DDC system.

    a. Verify analog I/O points at operating value.
    b. Make adjustments to out-of-tolerance I/O points.

        1) Identify I/O points for future reference.
        2) Simulate abnormal conditions to demonstrate proper function of safety devices.
        3) Replace instruments and controllers that cannot maintain performance indicated after adjustments.

2. Simulate conditions to demonstrate proper sequence of control.
3. Readjust settings to design values and observe ability of DDC system to establish desired conditions.
4. After 24 Hours following Initial Validation Test:

a. Re-check I/O points that required corrections during initial test.
b. Identify I/O points that still require additional correction and make corrections necessary to achieve desired results.

5. After 24 Hours of Second Validation Test:

a. Re-check I/O points that required corrections during second test.
b. Continue validation testing until I/O point is normal on two consecutive tests.

6. Completely check out, calibrate, and test all connected hardware and software to ensure that DDC system performs according to requirements indicated.
7. After validation testing is complete, prepare and submit a report indicating all I/O points that required correction and how many validation re-tests it took to pass. Identify adjustments made for each test and indicate instruments that were replaced.

3.21 FINAL REVIEW

A. Submit written request to Architect and Owner when DDC system is ready for final review. Written request shall state the following:

1. DDC system has been thoroughly inspected for compliance with contract documents and found to be in full compliance.
2. DDC system has been calibrated, adjusted and tested and found to comply with requirements of operational stability, accuracy, speed and other performance requirements indicated.
3. DDC system monitoring and control of HVAC systems results in operation according to sequences of operation indicated.
4. DDC system is complete and ready for final review.

B. Review by Architect and Owner shall be made after receipt of written request. A field report shall be issued to document observations and deficiencies.

C. Take prompt action to remedy deficiencies indicated in field report and submit a second written request when all deficiencies have been corrected. Repeat process until no deficiencies are reported.

D. Should more than two reviews be required, DDC system manufacturer and Installer shall compensate entity performing review for total costs, labor and expenses, associated with third and subsequent reviews. Estimated cost of each review shall be submitted and approved by DDC system manufacturer and Installer before making the review.

E. Prepare and submit closeout submittals and begin procedures indicated in "Extended Operation Test" Article when no deficiencies are reported.

F. A part of DDC system final review shall include a demonstration to parties participating in final review.

1. Provide staff familiar with DDC system installed to demonstrate operation of DDC system during final review.
2. Provide testing equipment to demonstrate accuracy and other performance requirements of DDC system that is requested by reviewers during final review.

3.22 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.23 MAINTENANCE SERVICE

A. Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by DDC system manufacturer's authorized service representative. Include monthly preventive maintenance, repair or replacement of worn or defective components, cleaning, calibration and adjusting as required for proper operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.

3.24 SOFTWARE SERVICE AGREEMENT

A. Technical Support: Beginning at Substantial Completion, service agreement shall include software support for two years.

B. Upgrade Service: At Substantial Completion, update software to latest version. Install and program software upgrades that become available within two years from date of Substantial Completion. Upgrading software shall include operating system and new or revised licenses for using software.

1. Upgrade Notice: At least 30 days to allow Owner to schedule and access system and to upgrade computer equipment if necessary.

3.25 DEMONSTRATION

A. Engage a factory-authorized service representative with complete knowledge of Project-specific system installed to train Owner's maintenance personnel to adjust, operate, and maintain DDC system.

B. Extent of Training:

1. Base extent of training on scope and complexity of DDC system indicated and training requirements indicated. Provide extent of training required to satisfy requirements indicated even if more than minimum training requirements are indicated.
2. Inform Owner of anticipated training requirements if more than minimum training requirements are indicated.
3. Minimum Training Requirements:

    a. Provide not less than five days of training total.
    b. Stagger training over multiple training classes to accommodate Owner's requirements. All training shall occur before end of warranty period.

C. Training Schedule:

1. Schedule training with Owner 20 business days before expected Substantial Completion.

2. Schedule training to provide Owner with at least 15 business days of notice in advance of training.
3. Training shall occur within normal business hours at a mutually agreed on time. Unless otherwise agreed to, training shall occur Monday through Friday, except on U.S. Federal holidays, with two morning sessions and two afternoon sessions. Each morning session and afternoon session shall be split in half with 15-minute break between sessions. Morning and afternoon sessions shall be separated by 30-minute lunch period. Training, including breaks and excluding lunch period, shall not exceed eight hours per day.
4. Provide staggered training schedule as requested by Owner.

D. Training Attendee List and Sign-in Sheet:

1. Request from Owner in advance of training a proposed attendee list with name, phone number and e-mail address.
2. Provide a preprinted sign-in sheet for each training session with proposed attendees listed and no fewer than six blank spaces to add additional attendees.

E. Training Attendee Headcount:

1. Plan in advance of training for five attendees.
2. Make allowance for Owner to add up to two attendees at time of training.
3. Headcount may vary depending on training content covered in session. Attendee access may be restricted to some training content for purposes of maintaining system security.

F. Attendee Training Manuals:

1. Provide each attendee with a color hard copy of all training materials and visual presentations.

G. Instructor Requirements:

1. One or multiple qualified instructors, as required, to provide training.
2. Instructors shall have not less than five years of providing instructional training on not less than five past projects with similar DDC system scope and complexity to DDC system installed.

H. Training Content for Daily Operators:

1. Basic operation of system.
2. Understanding DDC system architecture and configuration.
3. Understanding each unique product type installed including performance and service requirements for each.
4. Understanding operation of each system and equipment controlled by DDC system including sequences of operation, each unique control algorithm and each unique optimization routine.
5. Operating operator workstations, printers and other peripherals.
6. Logging on and off system.
7. Accessing graphics, reports and alarms.
8. Adjusting and changing set points and time schedules.
9. Recognizing DDC system malfunctions.
10. Understanding content of operation and maintenance manuals including control drawings.

11. Understanding physical location and placement of DDC controllers and I/O hardware.
12. Accessing data from DDC controllers.
13. Operating portable operator workstations.
14. Running each specified report and log.
15. Displaying and demonstrating each data entry to show Project-specific customizing capability. Demonstrating parameter changes.
16. Stepping through graphics penetration tree, displaying all graphics, demonstrating dynamic updating, and direct access to graphics.
17. Executing digital and analog commands in graphic mode.
18. Demonstrating control loop precision and stability via trend logs of I/O for not less than 10 percent of I/O installed.
19. Demonstrating DDC system performance through trend logs and command tracing.
20. Demonstrating on-line user guide, and help function and mail facility.

END OF SECTION

SECTION 230923.11 - CONTROL VALVES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Ball-style control valves.
2. Globe-style control valves.
3. Electric and electronic control valve actuators.

B. Related Requirements:

1. Section 230923 "Direct Digital Control (DDC) System for HVAC" control equipment and software, relays, electrical power devices, uninterruptible power supply units, wire, and cable.

1.2 DEFINITIONS

A. Cv: Valve coefficient.

B. DDC: Direct digital control.

C. EPT: Ethylene-propylene terpolymer rubber.

D. HNBR: Hydrogenated nitrile butadiene rubber.

E. NBR: Nitrile butadiene rubber.

F. PEEK: Polyether Ether Ketone rubber.

G. PTFE: Polytetrafluoroethylene.

H. RMS: Root-mean-square value of alternating voltage, which is the square root of the mean value of the square of the voltage values during a complete cycle.

I. RTFE: Glass-fiber-reinforced PTFE.

J. TFM: A chemically modified PTFE.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Ball-style control valves.
2. Globe-style control valves.
3. Solenoid valves.
4. Electric and electronic control valve actuators.

C. Product Data Submittals: For each product.

1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
3. Product description with complete technical data, performance curves, and product specification sheets.
4. Installation, operation, and maintenance instructions, including factors affecting performance.

D. Shop Drawings:

1. Include plans, elevations, sections, and details.
2. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.
4. Include diagrams for pneumatic signal and main air tubing.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Plan drawings and corresponding product installation details, drawn to scale, on which the following items are indicated and coordinated with each other, using input from installers of the items involved:

1. Control valve installation location indicated in relationship to room, duct, pipe, and equipment.
2. Size and location of wall access panels for control valves installed behind walls.
3. Size and location of ceiling access panels for control valves installed above inaccessible ceilings.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For control valves.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

C. ASME Compliance: Fabricate and label products to comply with ASME Boiler and Pressure Vessel Code where required by authorities having jurisdiction.

D. Code Compliance: Comply with governing energy code.

E. Ground Fault: Properly ground products to prevent failing due to ground fault conditions.

F. Backup Power Source: Serve control valve actuators from a backup power source where associated with systems and equipment served by a backup power source.

G. Environmental Conditions: For actuators not available with integral enclosures complying with requirements indicated, house in protective secondary enclosures complying with requirements.

H. Selection Criteria:

1. Suitable for operation throughout full range of system operating conditions encountered.
2. Control Valve Leakage: FCI 70-2, Class IV or less leakage, unless otherwise indicated.
3. Control Valve Pattern: Straight-through or three-way, as indicated on Drawings.
4. Control Valve Flow Characteristics, Unless Otherwise Indicated:

    a. Modulating, Two-Way Pattern: Equal percentage.
    b. Modulating Three-Way Pattern: Linear flow. Total flow through the valve to be constant regardless of the valve's position.

5. Fail-Safe Positions, Unless Otherwise Indicated:

    a. Chilled Water: Close.
    b. Heating Hot Water: Open.
    c. Valves on FCUs: Last position.

6. Stable Operation: Select control valves and actuators for stable operation throughout full range of operation, from design Cv at design flow to minimum Cv.
7. Control Valve Styles:

    a. Hydronic Systems:

        1) Pipe Sizes NPS 2 (DN 50) and Smaller: Ball- or globe-style control valves.
        2) Pipe Sizes Larger than NPS 2 (DN 50): Globe-style control valves.

I. Sizing Criteria: Unless otherwise indicated, select control valve size using the following:

1. ISA Standards:

    a. Control Valve Sizes and Flow Coefficients: ISA 75.01.01.
    b. Control Valve Characteristics and Rangeability: ISA 75.11.01.

2. Correction Factors: Consider viscosity, flashing, and cavitation corrections when selecting control valves.
3. Ball-Style Control Valves: Select valve size with design Cv at design flow between 65 and 75 degrees of valve full open position and minimum Cv between 15 and 25 percent of open position.
4. Globe-Style Control Valves: Select valve size to pass the design Cv at design flow with not more than 95 percent of stem travel.
5. Modulating Control Valves in Hydronic Systems:

    a. Select modulating control valve sizes at terminal equipment for a design Cv based on a pressure drop of 5 psig at design flow.

6. Two-Position Valves: Select two-position control valves for full pipeline size.

2.2 BALL-STYLE CONTROL VALVES

A. Ball Valves with Characterized Disk and Threaded Ends, Two Way:

1. Source Limitations: Obtain two-way ball valves, with characterized disk and threaded ends, from single manufacturer.
2. Performance:

    a. Stem Action: Rotary, 0 to 90 degrees.
    b. Controllable Flow Range: 75 percent open.
    c. Flow Characteristic: Equal percentage.
    d. Hydronic Pressure:

        1) Rating for Sizes NPS 1-1/4 (DN 32) and Smaller: Nominal 600 psig.
        2) Rating for Sizes NPS 1-1/2 through NPS 2 (DN 38 through DN 50): Nominal 400 psig.
        3) Close-off Pressure: 200 psig.
        4) Pressure Differential (Maximum): 50 psig.

    e. Hydronic Process Temperature Range: 0 to 250 deg F.

3. Construction:

    a. Size Range: NPS 1/2 to NPS 2.
    b. Body: Cast bronze or forged brass.
    c. End Connections: Female threaded (NPT) ends.
    d. Ball: Chrome-plated brass or bronze or 300 series stainless steel.
    e. Ball Seats: Reinforced PTFE.
    f. Characterizing Disk: Tefzel or stainless steel.
    g. Stem and Stem Extension:

        1) Material to match ball.

2) Blowout-proof design.
3) For valves installed in insulated piping systems, provide stem extension extending beyond OD of insulation.
4) Provide sleeve or other approved means to allow valve to be opened and closed without damaging the insulation and the insulation vapor barrier seal.

h. Stem Seal: Reinforced PTFE packing ring with a threaded packing ring follower to retain the packing ring under design pressure with the linkage removed. Alternative means, such as EPDM O-rings, are acceptable if an equivalent cycle endurance can be demonstrated by testing.

B. Ball Valves with Characterized Disk and Threaded Ends, Three Way:

1. Source Limitations: Obtain three-way ball valves, with characterized disk and threaded ends, from single manufacturer.
2. Performance:

a. Stem Action: Rotary, 0 to 90 degrees.
b. Controllable Flow Range: 75 percent open.
c. Flow Characteristics:

1) A-Port: Equal percentage.
2) B-Port: Modified for constant common port flow.

d. Hydronic Pressure:

1) Rating for Sizes NPS 1 (DN 25) and Smaller: Nominal 600 psig.
2) Rating for Sizes NPS 1-1/4 through NPS 2 (DN 32 through DN 50): Nominal 400 psig.
3) Close-off Pressure: 200 psig.
4) Pressure Differential (Maximum): 50 psig.

3. Construction:

a. Size Range: NPS 1/2 to NPS 2.
b. Body: Cast bronze or forged brass.
c. End Connections: Female threaded (NPT) ends.
d. Ball: Chrome-plated brass or bronze or 300 series stainless steel.
e. Ball Seats: Reinforced PTFE.
f. Characterizing Disk: Tefzel or stainless steel.
g. Stem and Stem Extension:

1) Material to match ball.
2) Blowout-proof design.
3) For valves installed in insulated piping systems, provide stem extension extending beyond OD of insulation.
4) Provide sleeve or other approved means to allow valve to be opened and closed without damaging the insulation and the insulation vapor barrier seal.

h. Stem Seal: Reinforced PTFE packing ring with a threaded packing ring follower to retain the packing ring under design pressure with the linkage removed.

Alternative means, such as EPDM O-rings, are acceptable if an equivalent cycle endurance can be demonstrated by testing.

2.3 GLOBE-STYLE CONTROL VALVES

A. General Requirements:

1. Body Dimensions: Comply with ISA 75.08.01.
2. Field Service: Construct the valves to be serviceable from the top with replaceable seats and plugs.
3. Field-Interchangeable Trim:

    a. Cage Guided Valves: Available with field-interchangeable trim for different valve flow characteristics, such as equal percentage, linear, and quick opening.
    b. Industrial Valves NPS 1 and Larger: Available with reduced trim one nominal size smaller.

4. Nameplate: Corrosion-resistant, indicating the following:

    a. Manufacturer's name, model number, and serial number.
    b. Body and trim size.
    c. Arrow indicating direction of flow.

B. Globe Valves NPS 2 (DN 50) and Smaller, Two Way:

1. Source Limitations: Obtain two-way globe valves, NPS 2 and smaller, from single manufacturer.
2. Performance:

    a. Stem Action: Linear stem travel.
    b. Flow Characteristic: Equal percentage.
    c. Hydronic Pressure:

        1) Rating: In accordance with ASME B16.15, Class 250.
        2) Close-off Pressure: Equal to pressure rating at maximum temperature.
        3) Pressure Differential (Maximum): 35 psig.

    d. Ambient Operating Temperature: 35 to 150 deg F.
    e. Process Temperature Range:

        1) Hydronic: 35 to 248 deg F.
        2) Steam: Temperature at saturated steam pressure.

3. Construction:

    a. Size Range: NPS 1/2 to NPS 2.
    b. Body: Cast bronze or forged brass; ASME B16.15, Class 250.
    c. End Connections: Female NPT threaded ends,.
    d. Bonnet: Bronze or brass, threaded.
    e. Plug: Top guided.
    f. Brass Trim:

1) Packing: Self-adjusting Ethylene Propylene Rubber (EPR) rings or PTFE V-ring.
2) Plug: Brass.
3) Seat: Bronze or molded elastomeric disk.
4) Stem: Stainless steel.

g. Stainless Steel Trim:

1) Packing: PTFE V-ring.
2) Plug: Stainless steel.
3) Seat: Stainless steel.
4) Stem: Stainless steel.

C. Globe Valves NPS 2 (DN 50) and Smaller, Three Way:

1. Source Limitations: Obtain three-way globe valves, NPS 2 and smaller, from single manufacturer.
2. Performance:

a. Stem Action: Linear stem travel.
b. Flow Characteristic: Linear.
c. Hydronic Pressure:

1) Rating: In accordance with ASME B16.15, Class 250.
2) Close-off Pressure: Equal to pressure rating at maximum temperature.
3) Pressure Differential (Maximum): 35 psig.

d. Ambient Operating Temperature: 35 to 150 deg F.
e. Hydronic Process Temperature Range: 35 to 248 deg F.

3. Construction:

a. Size Range: NPS 1/2 to NPS 2.
b. Body: Cast bronze or forged brass; ASME B16.15, Class 250.
c. End Connections: Female NPT threaded ends,.
d. Bonnet: Bronze or brass, threaded.
e. Plug: Top guided.
f. Brass Trim:

1) Packing: Self-adjusting Ethylene Propylene Rubber (EPR) rings or PTFE V-ring.
2) Plug: Brass
3) Seat: Bronze or molded elastomeric disk.
4) Stem: Stainless steel.

D. Globe Valves NPS 2-1/2 to NPS 6 (DN 65 to DN 150), Two Way:

1. Source Limitations: Obtain two-way globe valves, NPS 2-1/2 to NPS 6, from single manufacturer.
2. Performance:

a. Stem Action: Linear stem travel.

b. Flow Characteristic: Equal percentage or linear.
c. Hydronic Pressure:

1) Rating: In accordance with ASME B16.1, Class 125 or 250 as required by application.
2) Close-off Pressure: Equal to pressure rating.

d. Hydronic Process Temperature: 35 to 280 deg F.

3. Construction:

a. Size Range: NPS 2-1/2 to NPS 6.
b. Body: Cast iron; ASME B16.1.
c. End Connections: Flanged; suitable for mating to ASME B16.5 flanges.
d. Bonnet: Cast iron; bolted.
e. Plug: Top or bottom guided.
f. Brass or Bronze Trim:

1) Packing: EPT rings or PTFE V-ring.
2) Plug: Brass or bronze.
3) Seat: Brass or bronze.
4) Stem: Stainless steel.

g. Stainless Steel Trim:

1) Packing: PTFE V-ring.
2) Plug: Stainless steel.
3) Seat: Stainless steel.
4) Stem: Stainless steel.

E. Globe Valves NPS 2-1/2 to NPS 6 (DN 65 to DN 150), Three Way:

1. Source Limitations: Obtain three-way globe valves, NPS 2-1/2 to NPS 6, from single manufacturer.
2. Performance:

a. Stem Action: Linear stem travel.
b. Flow Characteristic: Linear.
c. Hydronic Pressure:

1) Rating: In accordance with ASME B16.1, Class 125 or 250 as required by application.
2) Close-off Pressure: Equal to pressure rating.

3. Construction:

a. Size Range: NPS 2-1/2 to NPS 6.
b. Body: Cast iron; ASME B16.1.
c. End Connections: Flanged; suitable for mating to ASME B16.5 flanges.
d. Bonnet: Cast iron; bolted.
e. Plug: Top or bottom guided.
f. Brass or Bronze Trim:

1) Packing: EPT rings or PTFE V-ring.
2) Plug: Brass or bronze.
3) Seat: Brass or bronze.
4) Stem: Stainless steel.

g. Stainless Steel Trim:

1) Packing: PTFE V-ring.
2) Plug: Stainless steel.
3) Seat: Stainless steel.
4) Stem: Stainless steel.

2.4 ELECTRIC AND ELECTRONIC CONTROL VALVE ACTUATORS

A. Furnish control valves with factory-installed actuators from control valve manufacturer. Actuators manufactured by listed control valve manufacturers are acceptable subject to compliance with requirements.

B. Actuators for Control Valves in Hydronic Systems: Select actuators to close off against system pump shutoff head.

C. Type: Motor operated, with or without gears, electric and electronic.

D. Voltage:

1. Actuator to deliver torque required for continuous uniform movement of controlled device from limit to limit when operated at rated voltage.
2. Actuator to function properly within a range of 85 to 120 percent of nameplate voltage.

E. Construction:

1. Less Than 100 W: Fiber or reinforced nylon gears with steel shaft, copper alloy or nylon bearings, and pressed steel enclosures.
2. 100 up to 400 W: Ground steel gears, oil immersed; shaft-hardened steel running in bronze, copper alloy, or ball bearings. Operator and gear trains are to be totally enclosed in dustproof cast-iron, cast-steel, or cast-aluminum housing.
3. Greater Than 400 W: Totally enclosed reversible induction motors with auxiliary hand crank and permanently lubricated bearings.

F. Local Field Adjustment: Make spring-return actuators easily switchable from fail-safe open to fail-safe closed in the field without replacement.

G. Local Manual Override: Provide gear-type actuators with an external manual adjustment mechanism to allow manual positioning of the damper when the actuator is not powered.

H. Two-Position Actuators: Single direction, spring-return or reversing type.

I. Modulating Actuators:

1. Capable of stopping at all points across full range, and starting in either direction from any point in range.

2. Control Input Signal:

    a. Three Point, Tristate, or Floating Point: Clockwise and counter-clockwise inputs. One input drives actuator to open position, and other input drives actuator to close position. No signal of either input remains in last position.
    b. Proportional: Actuator drives proportionally to input signal, modulates throughout its angle of rotation, and is suitable for zero to 10 or 2 to 10 V dc and 4 to 20 mA signals.
    c. Pulse Width Modulation (PWM): Actuator drives to a specified position according to a pulse duration (length) of signal from a dry-contact closure, triac sink, or source controller.
    d. Programmable Multifunction:

        1) Control input, position feedback, and running time are to be factory or field programmable.
        2) Diagnostic feedback of hunting or oscillation, mechanical overload, mechanical travel, and mechanical load limit.
        3) Service data, including at a minimum, number of hours powered and number of hours in motion.

J. Fail-Safe:

1. Where indicated, provide actuator to fail to an end position.
2. Internal spring-return mechanism to drive controlled device to an end position (open or close) on loss of power.
3. Batteries, capacitors, and other nonmechanical forms of fail-safe operation are acceptable only where uniquely indicated.

K. Integral Overload Protection:

1. Provide against overload throughout the entire operating range in both directions.
2. Electronic overload, digital rotation sensing circuitry, mechanical end switches, or magnetic clutches are acceptable methods of protection.

L. Valve Attachment:

1. Unless otherwise required for valve interface, provide an actuator designed to be directly coupled to valve stem without the need for connecting linkages.
2. Attach actuator to valve drive shaft in a way that ensures maximum transfer of power and torque without slippage.
3. Bolt and set screw method of attachment is acceptable only if provided with at least two points of attachment.

M. Temperature and Humidity:

1. Temperature: Suitable for operating temperature range encountered by application with minimum operating temperature range of minus 20 to plus 120 deg F.
2. Humidity: Suitable for humidity range encountered by application; minimum operating range is to be from 5 to 95 percent relative humidity, noncondensing.

N. Enclosure:

1. Suitable for ambient conditions encountered by application.
2. Provide actuator enclosure with a heater and controller where required by application.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for valves installed in piping to verify actual locations of piping connections before installation.

C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 CONTROL VALVE APPLICATIONS

A. Control Valves:

1. Select from valves specified in "Control Valves" Article to achieve performance requirements and characteristics indicated while subjected to full range of system operation encountered.

3.3 INSTALLATION, GENERAL

A. Furnish and install products required to satisfy most stringent requirements indicated.

B. Install products level, plumb, parallel, and perpendicular with building construction.

C. Properly support control valves and actuators, wiring, and conduits to comply with requirements indicated. Brace all products to prevent lateral movement and sway or a break in attachment when subjected to a seismic event, wind, or other forces common to the application.

D. Provide ceiling, floor, roof, and wall openings and sleeves required by installation. Before proceeding with drilling, punching, or cutting, check location first for concealed products that could potentially be damaged. Patch, flash, grout, seal, and refinish openings to match adjacent condition.

E. Seal penetrations made in fire-rated and acoustically rated assemblies.

F. Fastening Hardware:

1. Wrenches, pliers, and other tools that will cause injury to or mar surfaces of rods, nuts, and other parts are prohibited for assembling and tightening nuts.
2. Tighten bolts and nuts firmly and uniformly. Do not overstress threads by excessive force or by oversized wrenches.

3. Lubricate threads of bolts, nuts, and screws with graphite and oil before assembly.

G. Install products in locations that are accessible and that will permit calibration and maintenance from floor, equipment platforms, or catwalks. Where ladders are required for Owner's access, confirm unrestricted ladder placement is possible under occupied condition.

3.4 CONTROL VALVES

A. Install pipe reducers for control valves smaller than line size. Position reducers as close to control valve as possible but at distance to avoid interference and impact to performance. Install with manufacturer-recommended clearance.

B. Install flanges or unions to allow drop-in and -out valve installation.

C. Valve Orientation:

1. Where possible, install ball and globe valves that are installed in horizontal piping, with stems upright and not more than 15 degrees off of vertical, not inverted.
2. Install valves in a position to allow full stem movement.

D. Clearance:

1. Locate valves for easy access, and provide separate support of valves that cannot be handled by service personnel without hoisting mechanism.
2. Install valves with at least 12 inches of clear space around valve and between valves and adjacent surfaces.

E. Threaded Valves:

1. Note internal length of threads in valve ends, and proximity of valve internal seat or wall, to determine how far pipe should be threaded into valve.
2. Align threads at point of assembly.
3. Apply thread compound to external pipe threads, except where dry seal threading is specified.
4. Assemble joint, wrench tight. Apply wrench on valve end as pipe is being threaded.

F. Flanged Valves:

1. Align flange surfaces parallel.
2. Assemble joints by sequencing bolt-tightening to make initial contact of flanges and gaskets as flat and parallel as possible. Use suitable lubricants on bolt threads. Tighten bolts gradually and uniformly with a torque wrench.

3.5 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Use same designation at each end for each piece of wire, cable, and tubing for operators to determine continuity at points of connection. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

3.6 ELECTRICAL CONNECTIONS

A. Install electrical power to field-mounted control devices requiring electrical power.

B. Connect wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables" and Section 260523 "Control-Voltage Electrical Power Cables."

C. Ground equipment in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

D. Furnish and install raceways. Comply with requirements in Section 260533.13 "Conduits for Electrical Systems."

E. Furnish and install circuit breakers. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers."

F. Install electrical devices furnished by manufacturer, but not factory mounted, in accordance with NFPA 70 and NECA 1.

G. Install nameplate for each electrical connection, indicating electrical equipment designation and circuit number feeding connection.

1. Nameplate to be laminated acrylic or melamine plastic signs, as specified in Section 260553 "Identification for Electrical Systems."
2. Nameplate to be laminated acrylic or melamine plastic signs with a black background and engraved white letters at least 1/2 inch high.

3.7 CONTROL CONNECTIONS

A. Install control signal wiring to field-mounted control devices.

B. Connect control signal wiring in accordance with Section 260523 "Control-Voltage Electrical Power Cables."

C. Furnish and install raceways. Comply with requirements in Section 260533.13 "Conduits for Electrical Systems."

3.8 CLEANING

A. Remove grease, mastic, adhesives, dust, dirt, stains, fingerprints, labels, and other foreign materials from exposed surfaces.

3.9 STARTUP

A. Control Valve Checkout:

1. Check installed products before continuity tests, leak tests, and calibration.
2. Check valves for proper location and accessibility.

3. Check valves for proper installation for direction of flow, elevation, orientation, insertion depth, or other applicable considerations that will impact performance.
4. For pneumatic products, verify air supply for each product is properly installed.
5. Verify that control valves are installed correctly for flow direction.
6. Verify that valve body attachment is properly secured and sealed.
7. Verify that valve actuator and linkage attachment are secure.
8. Verify that actuator wiring is complete, enclosed, and connected to correct power source.
9. Verify that valve ball, disc, and plug travel are unobstructed.
10. After piping systems have been tested and put into service, but before insulating and balancing, inspect each valve for leaks. Adjust or replace packing to stop leaks. Replace the valve if leaks persist.

3.10 ADJUSTMENT, CALIBRATION, AND TESTING

A. Stroke and adjust control valves following manufacturer's recommended procedure, from 100 percent open to 100 percent closed back to 100 percent open.

END OF SECTION

SECTION 230923.12 - CONTROL DAMPERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes the following types of control dampers and actuators for DDC systems:

1. Rectangular control dampers.
2. Round control dampers.
3. General control-damper actuator requirements.
4. Electric and electronic actuators.

B. Related Requirements:

1. Section 230923 "Direct-Digital Control System for HVAC" for control equipment and software, relays, electrical power devices, uninterruptible power supply units, wire, and cable.

1.3 DEFINITIONS

A. DDC: Direct-digital control.

B. RMS: Root-mean-square value of alternating voltage, which is the square root of the mean value of the square of the voltage values during a complete cycle.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Product Data: For each type of product, including the following:

1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical

power requirements, and limitations of ambient operating environment, including temperature and humidity.
3. Product description with complete technical data, performance curves, and product specification sheets.
4. Installation instructions, including factors affecting performance.

D. Shop Drawings:

1. Include plans, elevations, sections, and mounting details.
2. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Coordination Drawings: Plan drawings and corresponding product installation details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Product installation location shown in relationship to room, duct, and equipment.
2. Size and location of wall access panels for control dampers and actuators installed behind walls.
3. Size and location of ceiling access panels for control dampers and actuators installed above inaccessible ceilings.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Operation and Maintenance Data: For control dampers to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. ASME Compliance: Fabricate and label products to comply with ASME Boiler and Pressure Vessel Code where required by authorities having jurisdiction.

C. Ground Fault: Products shall not fail due to ground fault condition when suitably grounded.

D. Backup Power Source: Systems and equipment served by a backup power source shall have associated control damper actuators served from a backup power source.

E. Selection Criteria:

1. Dampers shall have stable operation throughout full range of operation, from design to minimum airflow over varying pressures and temperatures encountered.
2. Select modulating dampers for a pressure drop of 2 percent of fan total static pressure unless otherwise indicated.
3. Two-position dampers shall be full size of duct or equipment connection unless otherwise indicated.

2.2 RECTANGULAR CONTROL DAMPERS

A. General Requirements:

1. Unless otherwise indicated, use parallel blade configuration for two-position control, equipment isolation service, and when mixing two airstreams. For other applications, use opposed blade configuration.
2. Factory assemble multiple damper sections to provide a single damper assembly of size required by the application.
3. Damper actuator shall be factory installed by damper manufacturer as integral part of damper assembly. Coordinate actuator location and mounting requirements with damper manufacturer.

B. Rectangular Dampers with Steel Airfoil Blades:

1. Performance:

a. Leakage: AMCA 511, Class 1A. Leakage shall not exceed 3 cfm/sq. ft. against 1-in. wg differential static pressure.
b. Pressure Drop: 0.06-in. wg at 1500 fpm across a 24-by-24-inch damper when tested according to AMCA 500-D, figure 5.3.
c. Velocity: Up to 6000 fpm.
d. Temperature: Minus 40 to plus 185 deg F.
e. Pressure Rating: Damper close-off pressure equal to fan shutoff pressure with a maximum blade deflection of 1/200 of blade length.
f. Damper shall have AMCA seal for both air leakage and air performance.

2. Construction:

a. Frame:

1) Material: ASTM A 653/A 653M galvanized-steel profiles, 0.06 inch thick.
2) Hat-shaped channel with integral flanges. Mating face shall be a minimum of 1 inch.
3) Width not less than 5 inches.

b. Blades:

1) Hollow, airfoil, galvanized steel.

2) Parallel or opposed blade configuration as required by application.
3) Material: ASTM A 653/A 653M galvanized steel, 0.05 inch thick.
4) Width not to exceed 6 inches.
5) Length as required by close-off pressure, not to exceed 48 inches.

c. Seals:

1) Blades: Replaceable, mechanically attached extruded silicone, vinyl, or plastic composite.
2) Jambs: Stainless steel, compression type.

d. Axles: 0.5-inch-diameter plated or stainless steel, mechanically attached to blades.
e. Bearings:

1) Stainless steel mounted in frame.
2) Where blade axles are installed in vertical position, provide thrust bearings.

f. Linkage:

1) Concealed in frame.
2) Constructed of aluminum and plated or stainless steel.
3) Hardware: Stainless steel.

g. Transition:

1) For round and flat oval duct applications, provide damper assembly with integral transitions to mate to adjoining field connection.
2) Factory mount damper in a sleeve with a close transition to mate to field connection.
3) Damper size and sleeve shall be connection size plus 2 inches.
4) Sleeve length shall be not less than 12 inches for dampers without jackshafts and shall be not less than 16 inches for dampers with jackshafts.
5) Sleeve material shall match adjacent duct.

h. Additional Corrosion Protection for Corrosive Environments:

1) Provide epoxy finish for surfaces in contact with airstream.
2) Axles, damper linkage, and hardware shall be constructed of Type 316L stainless steel.

C. Insulated Rectangular Dampers:

1. Performance:

a. Leakage: AMCA 511, Class 1A. Leakage shall not exceed 3 cfm/sq. ft. against 1-in. wg differential static pressure and shall not exceed 4.9 cfm/sq. ft. against 4-in. wg differential static pressure at minus 40 deg F.
b. Pressure Drop: 0.1-in. wg at 1500 fpm across a 24-by-24-inch damper when tested according to AMCA 500-D, figure 5.3.
c. Velocity: Up to 4000 fpm.
d. Temperature: Minus 100 to plus 185 deg F.

e. Pressure Rating: Damper close-off pressure equal to fan shutoff pressure with a maximum blade deflection of 1/200 of blade length.
f. Damper shall have AMCA seal for both air leakage and air performance.

2. Construction:

a. Frame:

1) Material: ASTM B 211, Alloy 6063 T5 extruded-aluminum profiles, 0.08 inch thick.
2) C-shaped channel with integral flange(s). Mating face shall be a minimum of 1 inch.
3) Width not less than 4 inches.
4) Entire frame shall be thermally broken by means of polyurethane resin pockets, complete with thermal cuts.
5) Damper frame shall be insulated with polystyrofoam on four sides.

b. Blades:

1) Hollow shaped, extruded aluminum.
2) Blades shall be internally insulated with expanded polyurethane foam and shall be thermally broken. Complete blade shall have an insulating factor of R-2.29 and a temperature index of 55.
3) Parallel or opposed blade configuration as required by application.
4) Material: ASTM B 211, Alloy 6063 T5 aluminum, 0.08 inch thick.
5) Width not to exceed 6 inches.
6) Length as required by close-off pressure, not to exceed 48 inches.

c. Seals: Blade and frame seals shall be of flexible silicone and secured in an integral slot within the aluminum extrusions.
d. Axles: 0.44-inch-diameter plated or stainless steel, mechanically attached to blades.
e. Bearings:

1) Bearings shall be composed of a Celcon inner bearing fixed to axle, rotating within a polycarbonate outer bearing inserted in the frame, resulting in no metal-to-metal or metal-to-plastic contact.
2) Where blade axles are installed in vertical position, provide thrust bearings.

f. Linkage:

1) Concealed in frame.
2) Constructed of aluminum and plated or stainless steel.
3) Hardware: Stainless steel.

g. Transition:

1) For round and flat oval duct applications, provide damper assembly with integral transitions to mate to adjoining field connection.
2) Factory mount damper in a sleeve with a close transition to mate to field connection.
3) Damper size and sleeve shall be connection size plus 2 inches.

4) Sleeve length shall be not less than 12 inches for dampers without jackshafts and shall be not less than 16 inches for dampers with jackshafts.
5) Sleeve material shall match adjacent duct.

h. Additional Corrosion Protection for Corrosive Environments:

1) Provide anodized finish for aluminum surfaces in contact with airstream. Anodized finish shall be a minimum of 0.0007 inch thick.
2) Axles, damper linkage, and hardware shall be constructed of Type 316L stainless steel.

2.3 ROUND CONTROL DAMPERS

A. Round Dampers, Sleeve Type:

1. Performance:

a. Leakage: Leakage shall not exceed 0.15 cfm/in. of perimeter blade at 4-in. wg differential static pressure.
b. Pressure Drop: 0.02-in. wg at 1500 fpm across a 12-inch damper when tested according to AMCA 500-D, figure 5.3.
c. Velocity: Up to 4000 fpm.
d. Temperature: Minus 25 to plus 200 deg F.
e. Pressure Rating: 8-in. wg for sizes through 12 inches, 6-in. wg for larger sizes.

2. Construction:

a. Frame:

1) Material: Galvanized steel, 0.04 in thick.
2) Outward rolled stiffener beads positioned approximately 1 inch inboard of each end.
3) Sleeve-type connection for mating to adjacent ductwork.
4) Size Range: 4 to 24 inches.
5) Length not less than 7 inches.
6) Provide 2-inch sheet metal stand-off for mounting actuator.

b. Blade: Double-thickness circular flat blades sandwiched together and constructed of galvanized steel.
c. Blade Seal: Polyethylene foam seal sandwiched between two sides of blades and fully encompassing blade edge.
d. Axle: 0.5-inch-diameter plated or stainless steel, mechanically attached to blade.
e. Bearings: Stainless-steel sleeve pressed into frame.

2.4 GENERAL CONTROL-DAMPER ACTUATORS REQUIREMENTS

A. Actuators shall operate related damper(s) with sufficient reserve power to provide smooth modulating action or two-position action and proper speed of response at velocity and pressure conditions to which the damper is subjected.

B. Actuators shall produce sufficient power and torque to close off against the maximum system pressures encountered. Actuators shall be sized to close off against one and a half (1.5) times the fan shutoff pressure as a minimum requirement.

C. The total damper area operated by an actuator shall not exceed 80 percent of manufacturer's maximum area rating.

D. Provide one actuator for each damper assembly where possible. Multiple actuators required to drive a single damper assembly shall operate in unison.

E. Avoid the use of excessively oversized actuators which could overdrive and cause linkage failure when the damper blade has reached either its full open or closed position.

F. Use jackshafts and shaft couplings in lieu of blade-to-blade linkages when driving axially aligned damper sections.

G. Provide mounting hardware and linkages for connecting actuator to damper.

H. Select actuators to fail in desired position in the event of a power failure.

I. Actuator Fail Positions: As indicated below:

1. Exhaust Air: Close.
2. Outdoor Air: Close.
3. Supply Air: Open.
4. Return Air: Open.

2.5 ELECTRIC AND ELECTRONIC ACTUATORS

A. Type: Motor operated, with or without gears, electric and electronic.

B. Voltage:

1. Voltage selection is delegated to professional designing control system.
2. Actuator shall deliver torque required for continuous uniform movement of controlled device from limit to limit when operated at rated voltage.
3. Actuator shall function properly within a range of 85 to 120 percent of nameplate voltage.

C. Field Adjustment:

1. Spring return actuators shall be easily switchable from fail open to fail closed in the field without replacement.
2. Provide gear-type actuators with an external manual adjustment mechanism to allow manual positioning of the damper when the actuator is not powered.

D. Two-Position Actuators: Single direction, spring return or reversing type.

E. Modulating Actuators:

1. Capable of stopping at all points across full range, and starting in either direction from any point in range.
2. Control Input Signal:

    a. Three Point, Tristate, or Floating Point: Clockwise and counter-clockwise inputs. One input drives actuator to open position, and other input drives actuator to close position. No signal of either input remains in last position.
    b. Proportional: Actuator drives proportional to input signal and modulates throughout its angle of rotation. Suitable for zero- to 10- or 2- to 10-V dc and 4- to 20-mA signals.

F. Fail-Safe:

1. Where indicated, provide actuator to fail to an end position.
2. Internal spring return mechanism to drive controlled device to an end position (open or close) on loss of power.
3. Batteries, capacitors, and other non-mechanical forms of fail-safe operation are acceptable only where uniquely indicated.

G. Integral Overload Protection:

1. Provide against overload throughout the entire operating range in both directions.
2. Electronic overload, digital rotation sensing circuitry, mechanical end switches, or magnetic clutches are acceptable methods of protection.

H. Damper Attachment:

1. Unless otherwise required for damper interface, provide actuator designed to be directly coupled to damper shaft without need for connecting linkages.
2. Attach actuator to damper drive shaft in a way that ensures maximum transfer of power and torque without slippage.
3. Bolt and set screw method of attachment is acceptable only if provided with at least two points of attachment.

I. Temperature and Humidity:

1. Temperature: Suitable for operating temperature range encountered by application with minimum operating temperature range of minus 20 to plus 120 deg F.
2. Humidity: Suitable for humidity range encountered by application; minimum operating range shall be from 5 to 95 percent relative humidity, non-condensing.

J. Enclosure:

1. Suitable for ambient conditions encountered by application.
2. NEMA 250, Type 2 for indoor and protected applications.
3. NEMA 250, Type 4 or Type 4X for outdoor and unprotected applications.
4. Provide actuator enclosure with a heater and controller where required by application.

K. Stroke Time:

1. Operate damper from fully closed to fully open within seconds.
2. Operate damper from fully open to fully closed within seconds.

3. Move damper to failed position within 10 seconds.
4. Select operating speed to be compatible with equipment and system operation.
5. Actuators operating in smoke control systems comply with governing code and NFPA requirements.

L. Sound:

1. Spring Return: 62 dBA.
2. Non-Spring Return: 45 dBA.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for dampers and instruments installed in duct systems to verify actual locations of connections before installation.

C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Furnish and install products required to satisfy most stringent requirements indicated.

B. Properly support dampers and actuators, wiring, and conduit to comply with requirements indicated. Brace all products to prevent lateral movement and sway or a break in attachment when subjected to a force.

C. Provide ceiling, floor, roof, and wall openings and sleeves required by installation. Before proceeding with drilling, punching, or cutting, check location first for concealed products that could potentially be damaged. Patch, flash, grout, seal, and refinish openings to match adjacent condition.

D. Seal penetrations made in fire-rated and acoustically rated assemblies.

E. Fastening Hardware:

1. Stillson wrenches, pliers, or other tools that will cause injury to or mar surfaces of rods, nuts, and other parts are prohibited for assembling and tightening nuts.
2. Tighten bolts and nuts firmly and uniformly. Do not overstress threads by excessive force or by oversized wrenches.
3. Lubricate threads of bolts, nuts, and screws with graphite and oil before assembly.

F. Install products in locations that are accessible and that will permit calibration and maintenance from floor, equipment platforms, or catwalks. Where ladders are required for Owner's access, confirm unrestricted ladder placement is possible under occupied condition.

3.3 ELECTRIC POWER

A. Furnish and install electrical power to products requiring electrical connections.

B. Furnish and install circuit breakers. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers."

C. Furnish and install power wiring. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

D. Furnish and install raceways. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems."

3.4 CONTROL DAMPERS

A. Install smooth transitions, not exceeding 30 degrees, to dampers smaller than adjacent duct. Install transitions as close to damper as possible but at distance to avoid interference and impact to performance. Consult manufacturer for recommended clearance.

B. Clearance:

1. Locate dampers for easy access and provide separate support of dampers that cannot be handled by service personnel without hoisting mechanism.
2. Install dampers with at least 24 inches of clear space on sides of dampers requiring service access.

C. Service Access:

1. Dampers and actuators shall be accessible for visual inspection and service.
2. Install access door(s) in duct or equipment located upstream of damper to allow service personnel to hand clean any portion of damper, linkage, and actuator. Comply with requirements in Section 233300 "Air Duct Accessories."

D. Install dampers straight and true, level in all planes, and square in all dimensions. Install supplementary structural steel reinforcement for large multiple-section dampers if factory support alone cannot handle loading.

E. Attach actuator(s) to damper drive shaft.

F. For duct-mounted and equipment-mounted dampers installed outside of equipment, install a visible and accessible indication of damper position from outside.

3.5 CONNECTIONS

A. Connect electrical devices and components to electrical grounding system. Comply with requirements in Section 260526 "Grounding and Bonding for Electrical Systems."

3.6 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Each piece of wire and cable shall have the same designation at each end for operators to determine continuity at points of connection. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."Section 16075 "Electrical Identification."

B. Install engraved nameplate with damper identification on damper and on face of ceiling where damper is concealed above ceiling.

3.7 CHECKOUT PROCEDURES

A. Control-Damper Checkout:

1. Check installed products before continuity tests, leak tests, and calibration.
2. Check dampers for proper location and accessibility.
3. Verify that control dampers are installed correctly for flow direction.
4. Verify that proper blade alignment, either parallel or opposed, has been provided.
5. Verify that damper frame attachment is properly secured and sealed.
6. Verify that damper actuator and linkage attachment are secure.
7. Verify that actuator wiring is complete, enclosed, and connected to correct power source.
8. Verify that damper blade travel is unobstructed.

3.8 ADJUSTMENT, CALIBRATION, AND TESTING:

A. Stroke and adjust control dampers following manufacturer's recommended procedure, from 100 percent open to 100 percent closed back to 100 percent open.

B. Stroke control dampers with pilot positioners. Adjust damper and positioner following manufacturer's recommended procedure, so damper is 100 percent closed, 50 percent closed, and 100 percent open at proper air pressure.

C. Check and document open and close cycle times for applications with a cycle time of less than 30 seconds.

D. For control dampers equipped with positive position indication, check feedback signal at multiple positions to confirm proper position indication.

END OF SECTION

SECTION 230923.14 - FLOW INSTRUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Airflow sensors.
2. Airflow transmitters.
3. Liquid flow switches.

B. Related Requirements:

1. Section 230923 "Direct-Digital Control System for HVAC" for control equipment and software, relays, electrical power devices, uninterruptible power supply units, wire, and cable.

1.3 DEFINITIONS

A. Ethernet: Local area network based on IEEE 802.3 standards.

B. HART: Highway addressable remote transducer protocol is the global standard for sending and receiving digital information across analog wires between smart devices and control or monitoring systems through bi-directional communication that provides data access between intelligent field instruments and host systems. A host can be any software application from technician's hand-held device or laptop to a plant's process control, asset management, safety, or other system using any control platform.

C. PEEK: polyetheretherketone.

D. PTFE: Polytetrafluoroethylene.

E. PPS: Polyphenylene sulfide.

F. RS-485: A TIA standard for multipoint communications using two twisted pairs.

G. RTD: Resistance temperature detector.

H. TCP/IP: Transport control protocol/Internet protocol incorporated into Microsoft Windows.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product, including the following. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Operating characteristics; electrical characteristics; and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
3. Product description with complete technical data, performance curves, and product specification sheets.
4. Installation instructions, including factors affecting performance.

C. Shop Drawings:

1. Include plans, elevations, sections, and mounting details.
2. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.
4. Include diagrams for air and process signal tubing.
5. Number-coded identification system for unique identification of wiring, cable, and tubing ends.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Certificates: For each product requiring a certificate.

C. Product Test Reports: For each product, for tests performed by manufacturer and witnessed by a qualified testing agency.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For instruments to include in operation and maintenance manuals.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials and parts that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

C. Provide parts, as indicated by manufacturer's recommended parts list, for product operation during two-year period following warranty period.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 GENERAL REQUIREMENTS FOR FLOW INSTRUMENTS

A. Air sensors and transmitters shall have an extended range of 20 percent above Project design flow and 20 percent below minimum Project flow to signal abnormal flow conditions and to provide flexibility for changes in operation.

B. Liquid sensors, meters, and transmitters shall have an extended range of 20 percent above Project design flow and 10 percent below Project minimum flow to signal abnormal flow conditions and to provide flexibility for changes in operation.

2.3 AIRFLOW SENSORS:

A. Performance Requirements:

1. Adjustable for changes in system operational parameters.
2. Airflow Sensor and Transmitter Range: Extended range of 20 percent above Project design flow and 20 percent below minimum Project flow to signal abnormal flow conditions.
3. Manufacturer shall certify that each flow instrument indicated complies with specified performance requirements and characteristics.

    a. Product certificates are required.

B. Pitot-Tube Airflow Sensor Station:

1. Description: Multiple total- and static-pressure sensors positioned at the center of equal area of the station cross section and interconnected by respective averaging manifolds.

    a. Stations 4 sq. ft. and Smaller: One total-pressure sensor and one static-pressure sensor for every 16 sq. in. of station area.

b. Stations Larger than 4 sq. ft.: One total-pressure sensor and one static-pressure sensor for every 36 sq. in. of station area.

2. Casing: Galvanized sheet steel at least 0.079 inch thick with coating complying with ASTM A 653/A 653M, G90. Casings shall be stainless steel, 0.0781 inch thick, when connected to stainless duct and aluminum, 0.063 inch thick, when connected to aluminum duct.

   a. Joints and Seams: Continuously weld. Clean galvanized areas damaged by welding and coat with aluminum paint.
   b. Casing Depth: At least 8 inches.
   c. Casing Flanges: Outward flange, minimum flange face 1.5 inches.
   d. Casing Configuration and Size: Match shape (rectangular, round, flat oval) and same size as adjacent duct unless otherwise indicated.

3. Include an open parallel cell air straightener or air equalizer honeycomb mechanically fastened to casing.

   a. Construct straightener or equalizer from Type 3003 aluminum or Type 316 stainless steel, depending on casing material. Use stainless steel for units with stainless-steel casings.

4. Construct pressure sensor array from drawn copper or stainless-steel tubing. Use stainless steel for units with stainless-steel casings. Copper tubing shall comply with ASTM B 75 and ASTM B 280. Minimum tube wall thickness shall be 0.030 inch. Include internal piping and external pressure transmitter ports.
5. Station Labeling: Identification label on each station casing indicating model number, size, area, and application-specific airflow range.
6. Performance:

   a. Pressure Loss: 0.015-inch wg at 1000 fpm, or 0.085-inch wg at 2000 fpm.
   b. Accuracy: Within 2 percent of actual airflow.
   c. Self-Generated Sound: NC 40 and sound level within the duct shall not be amplified.
   d. Performance rated and tested according to AMCA 610. Each station shall bear the AMCA seal.

C. Pitot-Tube Fan Inlet Airflow Traverse Sensor:

1. Traverse manifold designed for mounting in fan inlets.
2. Contain multiple total- and static-pressure sensors placed at concentric area centers along the exterior surface of cylindrical manifold and internally connected to their respective averaging manifolds. Sensors shall not protrude beyond the surface of the manifold nor be adversely affected by particle contamination present in airstream.
3. Manifold (two per inlet) shall have dual end support swivel brackets suitable for mounting in the fan inlet bell and symmetrical averaging signal takeoffs and fittings.
4. Sensors shall be capable of producing steady, non-pulsating signals of standard total- and static-pressure without need for flow corrections or factors, with an accuracy of 3 percent of actual flow over a turndown range of 6 to 1.
5. Manifold Materials: Copper or anodized aluminum or Type 316 stainless steel.
6. Unless otherwise required by application and without affecting the fan and sensor performance, nominal diameter copper and aluminum manifolds shall be the following:

a. For Fan Inlets Smaller than 20 Inches: 0.375 inch.
b. For Fan Inlets 20 Inches and Larger: 0.75 inch.

7. Unless otherwise required by application and without affecting the fan and sensor performance, nominal diameter stainless-steel manifolds shall be the following:

a. For Fan Inlets Smaller than 20 Inches: 0.375 inch.
b. For Fan Inlets 20 through 48 Inches: 0.75 inch.
c. For Fan Inlets Larger than 48 Inches: 1.0 inch.

D. Piezometer Ring Fan Inlet Airflow Sensor:

1. In lieu of externally mounted fan inlet airflow sensors, option to provide fans with airflow measurement integral to fan inlet cones for continuous measurement of air volume flow rate.
2. Multiple pressure sensor points strategically placed along the circumference of the inlet cone and internally connected to an averaging ring manifold located behind the inlet cone.
3. Sensor points shall not protrude beyond the surface of the inlet cone nor be adversely affected by particle contamination present in the airstream.
4. Sensor shall produce steady, non-pulsating signals to achieve accuracy within 5 percent of actual airflow.
5. Sensor shall be non-intrusive and not impact fan performance.
6. Product shall be a standard offering of the fan manufacturer and include published literature with supporting test data to validate sensor performance.

E. Thermal Airflow Station:

1. Source Limitations: Obtain airflow and temperature measuring sensors and transmitters from single manufacturer.
2. Description: Airflow station shall consist of one or more sensor probes mounted in a casing, and a remotely mounted microprocessor-based transmitter.
3. Performance:

a. Capable of independently processing up to 16 independently wired sensor assemblies.
b. Airflow rate of each sensor assembly shall be equally weighted and averaged by transmitter prior to output.
c. Temperature of each sensor assembly shall be velocity weighted and averaged by transmitter prior to output.
d. Listed and labeled by an NRTL as successfully tested as an assembly according to UL 873, "Temperature-Indicating and Regulating Equipment."
e. Components shall be interconnected by exposed NRTL-listed plenum-rated cable or non-listed cable placed in conduit.
f. Each flow station shall be factory calibrated at a minimum of 16 airflow rates and three temperatures to standards that are traceable to NIST.
g. Airflow Accuracy: Within 3 percent of reading over the entire operating airflow range.

1) Devices whose accuracy is combined accuracy of transmitter and sensor probes must demonstrate that total accuracy meets the performance requirements throughout the measurement range.

h. Temperature Accuracy: Within 0.2 deg F over entire operating range of minus 20 to plus 140 deg F.
i. Sensor Ambient Operating Temperature Range: Minus 20 to plus 160 deg F.
j. Transmitter Ambient Operating Temperature Range: Minus 20 to plus 120 deg F.
k. Sensor and Transmitter Ambient Operating Humidity Range: Zero to 99 percent, non-condensing.
l. Instrument shall compensate for changes in air temperature and density throughout calibrated velocity range for seasonal extremes at Project location.
m. Pressure Drop: 0.05-inch wg at 2000 fpm across a 24-by-24-inch area.
n. Instruments mounted in throat or face of fan inlet cone shall not negatively influence fan performance by reducing flow more than 1 percent of Project design flow or negatively impact fan-generated sound. Losses in performance shall be documented with submittal data, and adjustments to compensate for performance impact shall be made to fan in order to deliver Project design airflow indicated.

4. Sensor Assemblies:

a. Each sensor probe shall contain two individually wired, hermetically sealed bead-in-glass thermistors.
b. Mount thermistors in sensor using a marine-grade, waterproof epoxy.
c. Thermistor leads shall be protected and not exposed to the environment.
d. Each sensor assembly shall independently determine airflow rate and temperature at each measurement point.
e. Each sensor probe shall have an integral cable for connection to remotely mounted transmitter.
f. Sensor Probe Material: Gold anodized, extruded 6063 aluminum tube or Type 304 stainless steel.
g. Probe Assembly Mounting Brackets Material: Type 304 stainless steel.

5. Casing:

a. Factory mount sensor probes in an airflow station casing to create a single assembly for field mounting.
b. Material: Galvanized sheet steel at least 0.079 inch thick with coating complying with ASTM A 653/A 653M, G90. Casings shall be stainless steel, 0.0781 inch thick, when connected to stainless duct and aluminum, 0.063 inch thick, when connected to aluminum duct.
c. Joints and Seams: Continuously weld. Clean galvanized areas damaged by welding and coat with zinc-rich paint.
d. Casing Depth: At least 8 inches.
e. Include casing inlet and discharge connections with a minimum1.5-inch face flange.

6. Transmitter:

a. Integral digital display capable of simultaneously displaying total airflow and average temperature, individual airflow, and temperature readings of each independent sensor assembly.
b. Capable of field configuration and diagnostics using an onboard push-button interface and digital display.

1) Include an integral power switch to operate on 24-V ac (isolation not required) and include the following:

a) Integral protection from transients and power surges.
b) Circuitry to ensure reset after power disruption, transients, and brownouts.
c) Integral transformer to convert field power source to operating voltage required by instrument.

c. Remote Signal Interface:

1) Linear Analog Signals for Airflow and Temperature: Fuse protected and isolated, field selectable, zero- to 10-V dc or 4 to 20 mA.
2) RS-485: BACnet-ARCNET, BACnet-MS/TP, and Modbus-RTU.
3) 10 Base-T Ethernet: BACnet Ethernet, BACnet-IP, Modbus-TCP, and TCP/IP.
4) LonWorks free topology.

2.4 AIRFLOW TRANSMITTERS

A. Airflow Transmitter with 0.10 Percent Accuracy and Auto-Zero Feature:

1. Transmitter shall receive total- and static-pressure signals from a primary element, amplify signals, extract the square root, and scale the signals to produce 4- to 20-mA dc output signals linear to airflow.
2. NEMA 250, Type 1 enclosure.
3. Construct assembly so that shock, vibration, and pressures surges of up to 1 psig will neither harm transmitter, nor affect its accuracy.
4. Transmitter with automatic zeroing circuit capable of automatically readjusting transmitter zero at predetermined time intervals. The automatic zeroing circuit shall re-zero transmitter to within 0.1 percent of true zero.
5. Performance:

a. Range: As required by application and at least 10 percent below minimum airflow and 10 percent greater than design airflow.
b. Calibrated Span: Field adjustable, minus 40 percent of the range.
c. Accuracy: Within 0.10 percent of natural span.
d. Repeatability: Within 0.15 percent of calibrated span.
e. Linearity: Within 0.2 percent of calibrated span.
f. Hysteresis and Deadband (Combined): Less than 0.2 percent of calibrated span.

6. Integral digital LED or digital display for continuous indication of airflow.

B. Airflow Transmitters with 0.25 Percent Accuracy and Auto-Zero Feature:

1. Transmitter shall receive total- and static-pressure signals from a flow element, amplify signals, extract the square foot, and scale the signals to produce 4- to 20-mA dc output signals linear to airflow.
2. NEMA 250, Type 1 enclosure.
3. Construct assembly so shock, vibration, and pressures surges of up to 1 psig will neither harm transmitter, nor affect its accuracy.

4. Transmitter with automatic zeroing circuit capable of automatically readjusting transmitter zero at predetermined time intervals. The automatic zeroing circuit shall re-zero the transmitter to within 0.1 percent of true zero.
5. Performance:

    a. Range: As required by application and at least 10 percent below minimum airflow and 10 percent greater than design airflow.
    b. Calibrated Span: Field adjustable, minus 40 percent of the range.
    c. Accuracy: Within 0.25 percent of natural span.
    d. Repeatability: Within 0.15 percent of calibrated span.
    e. Linearity: Within 0.2 percent of calibrated span.
    f. Hysteresis and Deadband (Combined): Less than 0.2 percent of calibrated span.

6. Integral digital display for continuous indication of airflow.

C. Pressure Differential Transmitters for Airflow Measurement:

1. Performance:

    a. Range: As required by application and at least 10 percent below minimum airflow and 10 percent greater than design airflow.
    b. Accuracy: Within 1 percent of the full-scale range.
    c. Hysteresis: Within 0.10 percent of full scale.
    d. Repeatability: Within 0.05 percent of full scale.
    e. Stability: Within one percent of span per year.
    f. Overpressure: 10 psig.
    g. Temperature Limits: Zero to 150 deg F.
    h. Compensate Temperature Limits: 40 to 150 deg F.
    i. Thermal Effects: 0.033 percent of full scale per degree F.
    j. Shock and vibration shall not harm the transmitter.

2. Output Signals:

    a. Analog Current Signal:

        1) Two-wire, 4- to 20-mA dc current source.
        2) Signal capable of operating into 800-ohm load.

    b. Analog Voltage Signal:

        1) Three wire, zero to 10 V.
        2) Minimum Load Resistance: 1000 ohms.

3. Display: Four-digit digital with minimum 0.4-inch-high numeric characters.
4. Operator Interface:

    a. Zero and span adjustments located behind cover.

5. Construction:

    a. Plastic casing with removable plastic cover.

b. Fittings: Swivel fittings for connection to copper tubing or barbed fittings for connection to polyethylene tubing. Fittings on bottom of instrument case.
c. Screw terminal block for wire connections.
d. Vertical plane mounting.
e. NEMA 250, Type 4.
f. Mounting Bracket: Appropriate for installation.

D. Pressure Differential Indicating Transmitter, Switch, and Controller for Airflow Measurement:

1. Description:

a. Three-in-one instrument, including digital display, control relay switches, and a transmitter with a current output.
b. Field configurable for pressure, velocity, and volumetric flow applications through user interface.
c. Select instrument range based on application.

2. Performance:

a. Accuracy including hysteresis and repeatability:

1) Ranges Less than 5-Inch wg: Within 1 percent.
2) Other Ranges: Within 0.5 percent at 77 deg F.

b. Stability: Within 1 percent per year.
c. Response Time: 250 ms.
d. Overpressure:

1) Ranges Less than 50-Inch wg: 5 psi
2) Range of 100-Inch wg: 9 psi.

e. Temperature Limits: 32 to 140 deg F.
f. Thermal Effects: 0.020 percent per deg F.
g. Warm-up Period: One hour.

3. Controller: Programming through menu keys to access five menus.

a. Security level.
b. Pressure, velocity, or flow application.
c. Engineering units.
d. K-factor for use with flow application.
e. Set-point control only; set-point and alarm operation; alarm operation as high, low, or high/low with manual; or automatic reset and delay.
f. View high and low readings.
g. Digital dampening for smoothing erratic applications.
h. Scaling of analog output to fit range and field calibration.

4. Display:

a. Four-digit digital, with minimum 0.4-inch-high alphanumeric characters.
b. Four LED indicators; two LEDs for set point and two LEDs for alarm status.

5. Operator Interface:

    a. Set-point adjustment through keypad on face of instrument.
    b. Zero and span adjustments accessible through menu.
    c. Programming through keypad.

6. Output Analog Signal: Two-wire, 4- to 20-mA dc current source; capable of operating into a 900-ohm load.
7. Output Digital Signal: Two, SPDT relays; each rated for 1 A at 30-V ac or 30-V dc.
8. Construction:

    a. Die-cast aluminum casing and bezel.
    b. Connections on side and back.
    c. Vertical plane mounting.
    d. NEMA 250, Type 1 rating.
    e. Nominal 4-inch-diameter face.
    f. Mounting Bracket: Appropriate for installation.

2.5 LIQUID FLOW SWITCHES

A. Liquid Flow Switch (Magnetic Type):

1. Description:

    a. Field-adjustable five-vane combinations.
    b. Suitable for pipe sizes NPS 1-1/2 through NPS 20.
    c. Mounting Suitable for Application: Switch vertically mounted in horizontal pipe, or switch horizontally mounted in vertical pipe with flow up.
    d. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for hazardous-environment Class I, Groups C and D; Class II, Groups E, F, and G.

2. Performance:

    a. Flow Rate Actuation and De-actuation: Varies with vane combination.
    b. Pressure Limit: 1000 psig for brass body, 2000 psig for Type 316 stainless-steel body.
    c. Temperature Range: Minus 4 to plus 275 deg F.
    d. Electrical Rating: 10 A at 125/250-V ac.

3. Wetted Parts Construction:

    a. Vanes: Type 316 stainless steel.
    b. Body: Brass.
    c. Magnetic Keeper: Type 316 or 430 stainless steel.
    d. Process Connection: NPS 1-1/2.

4. Enclosure:

    a. Die-cast aluminum alloy.
    b. Threaded cover.

c. NEMA 250, Type 4.
d. Electrical Connection: Terminal block.
e. Conduit Connection:trade size.

B. Liquid Flow Switch (Magnetic Type) for Small-Diameter Pipe:

1. Description:

a. Suitable for pipe sizes NPS 1/2 through NPS 2.
b. Mounting Suitable for Application: Switch vertically mounted in horizontal pipe, or switch horizontally mounted in vertical pipe with flow up.
c. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for hazardous-environment Class I, Groups A, B, C, and D; Class II, Groups E, F, and G.

2. Performance:

a. Flow Rate Actuation and De-actuation: Not adjustable.
b. Pressure Limit of Body: 1000 psig for brass, 2000 psig for Type 303 stainless-steel body.
c. Pressure Limit of Tee: 250 psig for brass, 1000 psig for malleable iron, and 2000 psig for forged carbon steel and stainless steel.
d. Temperature Range: Minus 4 to plus 220 deg F.
e. Electrical Rating: 5 A at 125/250-V ac.

3. Wetted Parts Construction (Lower Body):

a. Vanes: Type 301 stainless steel.
b. Body: Brass.
c. Magnet: Ceramic.
d. Process Connection: NPS 1/2.

4. Enclosure (Upper Body):

a. Brass.
b. NEMA 250, Type 4.
c. Electrical Connection: Terminal block.
d. Conduit Connection: 3/4-inchtrade size.

5. Integral Mounting Tee Furnished with Switch:

a. Brass.
b. Size: Match adjacent pipe.
c. Connection: Threaded pipe.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for instruments installed in piping to verify actual locations of connections before installation.

C. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTRUMENT APPLICATIONS

A. Select from instrument types to achieve performance requirements and characteristics indicated while subjected to full range of system operation encountered.

B. Duct-Mounted Airflow Sensors:

1. Measured Velocities 500 fpm and Less: Thermal airflow station.
2. Measured Velocities Greater than 500 fpm: Pitot-tube airflow sensor station or thermal airflow station.

3.3 INSTALLATION, GENERAL

A. Furnish and install products required to satisfy more stringent of all requirements indicated.

B. Install products level, plumb, parallel, and perpendicular with building construction.

C. Properly support instruments, tubing, piping, wiring, and conduit to comply with requirements indicated. Brace all products to prevent lateral movement and sway or a break in attachment when subjected to a force.

D. Install ceiling, floor, roof, and wall openings and sleeves required by installation. Before proceeding with drilling, punching, or cutting, check location first for concealed products that could potentially be damaged. Patch, flash, grout, seal, and refinish openings to match adjacent condition.

E. Install products in locations that are accessible and that will permit calibration and maintenance from floor, equipment platforms, or catwalks. Where ladders are required for Owner's access, confirm unrestricted ladder placement is possible under occupied condition.

3.4 ELECTRIC POWER

A. Furnish and install electrical power to products requiring electrical connections.

B. Furnish and install circuit breakers. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers."

C. Furnish and install power wiring. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

D. Furnish and install raceways. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems."

3.5 INSTRUMENTS, GENERAL INSTALLATION REQUIREMENTS

A. Mounting Location:

1. Rough-in: Outline instrument-mounting locations before setting instruments and routing cable, wiring, tubing, and conduit to final location.
2. Install switches and transmitters for air and liquid flow associated with individual air-handling units and connected ductwork and piping near air-handlings units co-located in air-handling unit system control panel, to provide service personnel a single and convenient location for inspection and service.
3. Install liquid flow switches and transmitters for indoor applications in mechanical equipment rooms. Do not locate in user-occupied space unless indicated specifically on Drawings.
4. Install airflow switches and transmitters for indoor applications in mechanical equipment rooms. Do not locate in user-occupied space unless indicated specifically on Drawings.
5. Mount switches and transmitters not required to be mounted within system control panels on walls, floor-supported freestanding pipe stands, or floor-supported structural support frames. Use manufacturer mounting brackets to accommodate field mounting. Securely support and brace products to prevent vibration and movement.
6. Install instruments in liquid and liquid-sealed-piped services below their process connection point. Slope tubing down to instrument with a slope of 2 percent.

3.6 FLOW INSTRUMENTS INSTALLATION

A. Airflow Sensors:

1. Install sensors in straight sections of duct with manufacturer-recommended straight duct upstream and downstream of sensor.
2. Installed sensors shall be accessible for visual inspection and service. Install access door(s) in duct or equipment located upstream of sensor, to allow service personnel to hand clean sensors.

B. Liquid and Steam Sensors:

1. Install sensors in straight sections of piping with manufacturer-recommended straight piping upstream and downstream of sensor.
2. Alert manufacturer where installation cannot accommodate recommended clearance, and solicit recommendations for field modifications to installation, such as flow straighteners, to improve condition.
3. Install pipe reducers for in-line sensors smaller than line size. Position reducers at distance from sensor to avoid interference and impact on accuracy.

4. Install in-line sensors with flanges or unions to provide drop-in and -out installation.

C. Liquid Flow Meters:

1. Install meters in straight sections of piping with manufacturer-recommended straight piping upstream and downstream of sensor.
2. Install pipe reducers for in-line meters smaller than line size. Install reducers at distance from meter to avoid interference and impact on accuracy.
3. Install in-line meters with flanges or unions to provide drop-in and -out installation.
4. Insertion Meters:

    a. Install meter in top dead center of horizontal pipe positioned in an accessible location to allow for inspection and replacement.
    b. In applications where top-dead-center location is not possible due to field constraints, install meter at location along top half of pipe if acceptable by manufacturer for mounting orientation.

D. Liquid Switches:

1. Install switch in top dead center of horizontal pipe positioned in an accessible location to allow for inspection and replacement.
2. In applications where top-dead-center location is not possible due to field constraints, install switch at location along top half of pipe if switch is acceptable by manufacturer for mounting orientation.

E. Transmitters:

1. Install airflow transmitters serving an air system in a single location adjacent to or within system control panel.
2. Install liquid flow transmitters, not integral to sensors, in vicinity of sensor. Where multiple flow transmitters serving same system are located in same room, co-locate transmitters by system to provide service personnel a single and convenient location for inspection and service.

3.7 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Each piece of wire, cable, and tubing shall have the same designation at each end for operators to determine continuity at points of connection. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

B. Install engraved phenolic nameplate with instrument identification.

3.8 CLEANING

A. Remove grease, mastic, adhesives, dust, dirt, stains, fingerprints, labels, and other foreign materials from exposed interior and exterior surfaces.

B. Wash and shine glazing.

C. Polish glossy surfaces to a clean shine.

3.9 CHECKOUT PROCEDURES

A. Description:

1. Check out installed products before continuity tests, leak tests, and calibration.
2. Check instruments for proper location and accessibility.
3. Check instruments for proper installation with respect to direction of flow, elevation, orientation, insertion depth, or other applicable considerations that will impact performance.
4. Check instrument tubing for proper isolation, fittings, slope, dirt legs, drains, material, and support.

B. Flow Instrument Checkout:

1. Verify that sensors are installed correctly with respect to flow direction.
2. Verify that sensor attachment is properly secured and sealed.
3. Verify that processing tubing attachment is secure and isolation valves have been provided.
4. Inspect instrument tag against approved submittal.
5. Verify that recommended upstream and downstream distances have been maintained.

3.10 ADJUSTMENT, CALIBRATION, AND TESTING

A. Description:

1. Calibrate each instrument installed that is not factory calibrated and provided with calibration documentation.
2. Provide a written description of proposed field procedures and equipment for calibrating each type of instrument. Submit procedures before calibration and adjustment.
3. For each analog instrument, make a three-point test of calibration for both linearity and accuracy.
4. Equipment and procedures used for calibration shall meet instrument manufacturer's recommendations.
5. Provide diagnostic and test equipment for calibration and adjustment.
6. Field instruments and equipment used to test and calibrate installed instruments shall have accuracy at least twice the instrument accuracy being calibrated. For example, an installed instrument with an accuracy of 1 percent shall be checked by an instrument with an accuracy of 0.5 percent.
7. Calibrate each instrument according to instrument instruction manual supplied by manufacturer.
8. If after-calibration-indicated performance cannot be achieved, replace out-of-tolerance instruments.
9. Comply with field-testing requirements and procedures indicated by ASHRAE Guideline 11, "Field Testing of HVAC Control Components," in the absence of specific requirements, and to supplement requirements indicated.

B. Analog Signals:

1. Check analog voltage signals using a precision voltage meter at zero, 50, and 100 percent.
2. Check analog current signals using a precision current meter at zero, 50, and 100 percent.
3. Check resistance signals for temperature sensors at zero, 50, and 100 percent of operating span using a precision-resistant source.

C. Digital Signals:

1. Check digital signals using a jumper wire.
2. Check digital signals using an ohmmeter to test for contact.

D. Sensors: Check sensors at zero, 50, and 100 percent of Project design values.

E. Switches: Calibrate switches to make or break contact at set points indicated.

F. Transmitters:

1. Check and calibrate transmitters at zero, 50, and 100 percent of Project design values.
2. Calibrate resistance temperature transmitters at zero, 50, and 100 percent of span using a precision-resistance source.

3.11 MAINTENANCE SERVICE

A. Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 24 months' full maintenance by manufacturer's authorized service representative. Include annual preventive maintenance, repair or replacement of worn or defective components, cleaning, and adjusting as required for proper operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.

3.12 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain instrumentation and control devices.

B. Coordinate video with operation and maintenance manuals and classroom instruction for use by Owner in operating, maintaining, and troubleshooting.

C. Record videos on DVD disks.

D. Owner shall have right to make additional copies of video for internal use without paying royalties.

END OF SECTION

SECTION 230923.16 - GAS INSTRUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes the Following Gas Instruments:

1. Carbon-dioxide sensors and transmitters.

B. Related Requirements:

1. Section 230923 "Direct-Digital Control System for HVAC" for control equipment and software, relays, electrical power devices, uninterruptible power supply units, wire, and cable.

1.3 DEFINITIONS

A. NDIR: Nondispersive infrared.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Product Data: For each type of product, including the following:

1. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
2. Installation instructions, including factor affecting performance.
3. Product description with complete technical data, performance curves, product specification sheets.

D. Shop Drawings:

1. Include plans, elevations, sections, and mounting details.
2. Include diagrams for power, signal, and control wiring.
3. Number-coded identification system for unique identification of wiring, cable, and tubing ends.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Coordination Drawings: Plan drawings and corresponding product installation details, drawn to scale, on which wall-mounted instruments located in finished space are shown and coordinated with each other, showing relationship to light switches, fire alarm devices, and other installed devices using input from installers of the items involved.

C. Product Test Reports: For each product, for tests performed by manufacturer and witnessed by a qualified testing agency or a qualified testing agency.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Operation and Maintenance Data: For gas instruments to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 CARBON-DIOXIDE SENSORS AND TRANSMITTERS

A. Description:

1. NDIR technology or equivalent technology providing long-term stability and reliability.
2. Two-wire, 4-20 mA output signal, linearized to carbon-dioxide concentration in ppm.

B. Construction:

1. House electronics in an ABS plastic enclosure. Provide equivalent of NEMA 250, Type 1 enclosure for wall-mounted space applications and NEMA 250, Type 4 for duct-mounted applications.
2. Equip with digital display for continuous indication of carbon-dioxide concentration.

C. Performance:

1. Measurement Range: Zero to 2000 ppm.

2. Accuracy: Within 2 percent of reading, plus or minus 30 ppm.
3. Repeatability: Within 1 percent of full scale.
4. Temperature Dependence: Within 0.05 percent of full scale over an operating range of 25 to 110 deg F.
5. Long-Term Stability: Within 5 percent of full scale after more than five years.
6. Response Time: Within 60 seconds.
7. Warm-up Time: Within five minutes.

D. Provide calibration kit. Turn over to Owner at start of warranty period.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for instruments installed in piping to verify actual locations of connections before installation.

C. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.

D. Prepare written report, endorsed by Installer, listing conditions detrimental to performance.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Furnish and install products required to satisfy more stringent of all requirements indicated.

B. Install products level, plumb, parallel, and perpendicular with building construction.

C. Fastening Hardware:

1. Stillson wrenches, pliers, and other tools that cause injury to or mar surfaces of rods, nuts, and other parts are prohibited for work of assembling and tightening nuts.
2. Tighten bolts and nuts firmly and uniformly. Do not overstress threads by using excessive force or oversized wrenches.
3. Lubricate threads of bolts, nuts, and screws with graphite and oil before assembly.

D. Install products in locations that are accessible and that permit calibration and maintenance from floor, equipment platforms, or catwalks. Where ladders are required for Owner's access, confirm unrestricted ladder placement is possible under occupied condition.

3.3 ELECTRICAL POWER

A. Furnish and install electrical power to products requiring electrical connections.

B. Furnish and install circuit breakers. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers."

C. Furnish and install power wiring. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

D. Furnish and install raceways. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems."

3.4 INSTRUMENTS, GENERAL INSTALLATION REQUIREMENTS

A. Mounting Height:

1. Mount instruments in user-occupied space to match mounting height of light switches unless otherwise indicated on Drawings. Mounting height shall comply with codes and accessibility requirements.

B. Seal penetrations to ductwork, plenums, and air-moving equipment to comply with duct static-pressure class and leakage and seal classes indicated, using neoprene gaskets or grommets.

3.5 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Each piece of wire, cable, and tubing shall have the same designation at each end for operators to determine continuity at points of connection. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

B. Install engraved nameplate with instrument identification on face.

3.6 CHECKOUT PROCEDURES

A. Check out installed products before continuity tests, leak tests, and calibration.

B. Check instruments for proper location and accessibility.

C. Check instruments for proper installation on elevation, orientation, insertion depth, or other applicable considerations that impact performance.

D. Check instrument tubing for proper isolation, fittings, slope, dirt legs, drains, material, and support.

3.7 ADJUSTMENT, CALIBRATION, AND TESTING

A. Description:

1. Calibrate each instrument installed that is not factory calibrated and provided with calibration documentation.

2. Provide a written description of proposed field procedures and equipment for calibrating each type of instrument. Submit procedures before calibration and adjustment.
3. For each analog instrument, perform a three-point calibration test for both linearity and accuracy.
4. Equipment and procedures used for calibration shall comply with instrument manufacturer's written recommendations.
5. Provide diagnostic and test equipment for calibration and adjustment.
6. Field instruments and equipment used to test and calibrate installed instruments shall have an accuracy of at least twice the instrument accuracy being calibrated. For example, an installed instrument with an accuracy of 1 percent shall be checked by an instrument with an accuracy of 0.5 percent.
7. Calibrate each instrument according to instrument instruction manual supplied by manufacturer.
8. If, after calibration, indicated performance cannot be achieved, replace out-of-tolerance instruments.
9. Comply with field-testing requirements and procedures in ASHRAE Guideline 11, "Field Testing of HVAC Control Components," in the absence of specific requirements, and to supplement requirements indicated.

B. Analog Signals:

1. Check analog voltage signals using a precision voltage meter at zero, 50, and 100 percent.
2. Check analog current signals using a precision current meter at zero, 50, and 100 percent.
3. Check resistance signals for temperature sensors at zero, 50, and 100 percent of operating span using a precision-resistant source.

C. Digital Signals:

1. Check digital signals using a jumper wire.
2. Check digital signals using an ohmmeter to test for contact.

D. Sensors: Check sensors at zero, 50, and 100 percent of Project design values.

E. Switches: Calibrate switches to make or break contact at set points indicated.

F. Transmitters:

1. Check and calibrate transmitters at zero, 50, and 100 percent of Project design values.
2. Calibrate resistance temperature transmitters at zero, 50, and 100 percent of span using a precision-resistance source.

3.8 MAINTENANCE SERVICE

A. Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by manufacturer's authorized service representative. Include quarterly preventive maintenance, repair or replacement of worn or defective components, cleaning, and adjusting as required for proper operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.

END OF SECTION

SECTION 230923.19 - MOISTURE INSTRUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes moisture switches, sensors, and transmitters.

B. Related Requirements:

1. Section 230923 "Direct-Digital Control System for HVAC" for control equipment and software, relays, electrical power devices, uninterruptible power supply units, wire, and cable.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Product Data: For each type of product, including the following:

1. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
2. Product description with complete technical data, performance curves, and product specification sheets.

D. Shop Drawings:

1. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
2. Include diagrams for power, signal, and control wiring.
3. Include number-coded identification system for unique identification of wiring, cable, and tubing ends.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Operation and Maintenance Data: To include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MOISTURE SENSORS AND TRANSMITTERS

A. Sensor and Transmitter without Display:

1. Performance:

a. Accuracy including non-linearity, hysteresis, and repeatability: Within 2 percent from zero to 90 percent relative humidity and within 3 percent from 90 to 95 percent relative humidity when operating at 68 deg F.
b. Relative Humidity Range:

1) Duct: Zero to 100 percent.
2) Space: Zero to 95 percent relative.

c. Factory calibrated and NIST traceable with certificate included.

2. Construction for Space Applications:

a. Housing with integral sensor.
b. Housing shall be ABS plastic or powder-coated aluminum.
c. Enclosure: NEMA 250, Type 4.
d. Provide housing with a wall-mounting plate.

3. Construction for Duct and Equipment Applications:

a. Housing with integral sensor.
b. Duct Sensor Body: 300 series stainless steel.
c. Provide sensor with sintered stainless-steel filter for duct applications.
d. Housing shall be cast aluminum.
e. Enclosure: NEMA 250, Type 4.

4. Output Signal: Two-wire, 4- to 20-mA output signal with drive capacity of at least 500 ohms at 24-V dc.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.

C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Install products level, plumb, parallel, and perpendicular with building construction.

B. Properly support instruments, wiring, and conduit to comply with requirements indicated. Brace all products to prevent lateral movement and sway or a break in attachment when subjected to a force.

C. Fastening Hardware:

1. Stillson wrenches, pliers, and other tools that cause injury to or mar surfaces of rods, nuts, and other parts are prohibited for work of assembling and tightening nuts.
2. Tighten bolts and nuts firmly and uniformly. Do not overstress threads by excessive force or by oversized wrenches.

D. Install products in locations that are accessible and that permit calibration and maintenance from floor, equipment platforms, or catwalks. Where ladders are required for Owner's access, confirm unrestricted ladder placement is possible under occupied condition.

3.3 ELECTRIC POWER

A. Furnish and install electrical power to products requiring electrical connections.

B. Furnish and install circuit breakers. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers."

C. Furnish and install power wiring. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

D. Furnish and install raceways. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems."

3.4 MOISTURE INSTRUMENTS INSTALLATION

A. Mounting Location: Rough-in instrument-mounting locations before setting instruments and routing, cable, wiring, tubing, and conduit to final location.

B. Mounting Height:

1. Mount instruments in user-occupied space to match mounting height of light switches unless otherwise indicated on Drawings. Mounting height shall comply with codes and accessibility requirements.
2. Mount switches and transmitters located in mechanical equipment rooms and other similar space not subject to code, state, and Federal accessibility requirements within a range of 42 to 72 inchesabove the adjacent floor, grade, or service catwalk or platform.

    a. Make every effort to mount at 60 inches.

3.5 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Each piece of wire, cable, and tubing shall have the same designation at each end for operators to determine continuity at points of connection. Comply with requirements for identification specified in Section "Identification for Electrical Systems."

B. Install engraved nameplate with instrument identification on face of ceiling directly below instruments concealed above ceilings.

3.6 CHECKOUT PROCEDURES

A. Check installed products before continuity tests and calibration.

B. Check instruments for proper location and accessibility.

C. Check instruments for proper installation on direction of flow, elevation, orientation, insertion depth, or other applicable considerations that impact performance.

3.7 ADJUSTMENT, CALIBRATION, AND TESTING

A. Description:

1. Calibrate each instrument installed that is not factory calibrated and provided with calibration documentation.
2. Provide a written description of proposed field procedures and equipment for calibrating each type of instrument. Submit procedures before calibration and adjustment.
3. For each analog instrument, make a three-point test of calibration for both linearity and accuracy.
4. Equipment and procedures used for calibration shall meet instrument manufacturer's written instructions.
5. Provide diagnostic and test equipment for calibration and adjustment.

6. Field instruments and equipment used to test and calibrate installed instruments shall have accuracy at least twice the instrument accuracy being calibrated. For example, an installed instrument with an accuracy of 1 percent shall be checked by an instrument with an accuracy of 0.5 percent.
7. Calibrate each instrument according to instrument instruction manual supplied by manufacturer.
8. If after calibration indicated performance cannot be achieved, replace out-of-tolerance instruments.
9. Comply with field-testing requirements and procedures indicated by ASHRAE Guideline 11, "Field Testing of HVAC Control Components," in the absence of specific requirements, and to supplement requirements indicated.

B. Analog Signals:

1. Check analog voltage signals using a precision voltage meter at zero, 50, and 100 percent.
2. Check analog current signals using a precision current meter at zero, 50, and 100 percent.
3. Check resistance signals for temperature sensors at zero, 50, and 100 percent of operating span using a precision-resistance source.

C. Digital Signals:

1. Check digital signals using a jumper wire.
2. Check digital signals using an ohmmeter to test for contact.

D. Sensors: Check sensors at zero, 50, and 100 percent of Project design values.

E. Transmitters:

1. Check and calibrate transmitters at zero, 50, and 100 percent of Project design values.
2. Calibrate resistance temperature transmitters at zero, 50, and 100 percent of span using a precision-resistance source.

3.8 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain instrumentation and control devices.

END OF SECTION

SECTION 230923.23 - PRESSURE INSTRUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Air-pressure sensors.
2. Air-pressure switches.
3. Air-pressure transmitters.
4. Liquid-pressure switches.
5. Liquid-pressure transmitters.

B. Related Requirements:

1. Section 230923 "Direct-Digital Control System for HVAC" for control equipment and software, relays, electrical power devices, uninterruptible power supply units, wire, and cable.

1.3 DEFINITIONS

A. HART: Highway addressable remote transducer protocol is the global standard for sending and receiving digital information across analog wires between smart devices and control or monitoring systems through bi-directional communication that provides data access between intelligent field instruments and host systems. A host can be any software application from technician's hand-held device or laptop to a control, asset management, safety, or other system using any control platform.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Product Data: For each type of product, including the following:

1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.

2. Operating characteristics; electrical characteristics; and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
3. Product description with complete technical data, performance curves, and product specification sheets.
4. Installation instructions, including factors affecting performance.

D. Shop Drawings:

1. Include plans, elevations, sections, and mounting details.
2. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Number-coded identification system for unique identification of wiring, cable, and tubing ends.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Coordination Drawings: Plan drawings and corresponding product installation details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Product installation location shown in relationship to room, duct, pipe, and equipment.
2. Wall-mounted instruments located in finished space, showing relationship to light switches, fire alarm devices, and other installed devices.
3. Size and location of wall access panels for instruments installed behind walls.
4. Size and location of ceiling access panels for instruments installed in accessible ceilings.

C. Product Certificates: For each product requiring a certificate.

D. Product Test Reports: For each product requiring test performed by manufacturer and witnessed by a qualified testing agency or a qualified testing agency.

E. Source quality-control reports.

F. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Operation and Maintenance Data: For instruments to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Environmental Conditions:

1. Instruments shall operate without performance degradation under the ambient environmental temperature, pressure, humidity, and vibration conditions specified and encountered for installed location.

    a. If instrument alone cannot comply with requirement, install instrument in a protective enclosure that is isolated and protected from conditions impacting performance. Enclosure shall be internally insulated, electrically heated, filtered, and ventilated as required by instrument and application.

2.2 AIR-PRESSURE SENSORS

A. Duct Traverse Static Pressure Sensor:

1. Sensor shall traverse the duct cross section and have at least one pickup point every 6 inches along length of sensor.
2. Construct sensor of 18-gage Type T6063-T5 extruded and anodized aluminum.
3. Sensor supported with threaded rod, sealing washer, and nut at one end and a mounting plate with gasket at other end.
4. Mounting plate with threaded, NPS 3/8 compression fitting for connection to tubing.
5. Accuracy within 1 percent of actual operating static pressure.
6. Dual offset static sensor design shall provide accurate sensing of duct static pressure in the presence of turbulent and rotational airflows with a maximum 30 degree yaw and pitch.
7. Suitable for velocities of 100 to 10000 fpm and temperatures of up to 200 deg F.
8. Sensor air resistance shall be less than 0.1 times the velocity pressure at probe-operating velocity.
9. Suitable for flat oval, rectangular, and round duct configurations.

B. Outdoor Static Pressure Sensor:

1. Sensor with no moving parts.
2. Operation not affected and impaired by rain and snow.
3. Sensing plates constructed of 0.1406-inch Type 316 stainless steel.
4. Accuracy within:

    a. 1 percent of the actual outdoor atmospheric pressure when subjected to varying horizontal radial wind velocities up to 40 mph.
    b. 2 percent of the actual outdoor atmospheric pressure while subjected to varying radial wind velocities up to 40 mph with approach angles up to 30 degrees to horizontal.

c. 3 percent of the actual outdoor atmospheric pressure while subjected to varying radial wind velocities up to 40 mph with approach angles up to 60 degrees to horizontal.
d. Threaded,NPS 2 connection.

C. Space Static Pressure Sensor for Wall Mounting:

1. Stainless-steel wall plate with perforated center arranged to sense space static pressure. Exposed surfaces are provided with brush finish.
2. Wall plate provided with screws and sized to fit standard single-gang electrical box.
3. Back of sensor plate fitted with multiple sensing ports, pressure impulse suppression chamber, airflow shielding, and 0.125-inch fitting for tubing connection.
4. Performance: Within 1 percent of actual room static pressure in vicinity of sensor while being subjected to an air velocity of 1000 fpm from a 360-degree radial source.

D. Space Static Pressure Sensor for Recessed Ceiling Mounting:

1. Stainless-steel round plate with perforated center arranged to sense space static pressure. Exposed surfaces provided with brush finish.
2. Sensor intended for flush mount on face of ceiling with pressure chamber recessed in ceiling plenum.
3. Back of sensor plate fitted with multiple sensing ports, pressure impulse suppression chamber, airflow shielding, and 0.125-inch fitting for concealed tubing connection.
4. Performance: Within 1 percent of actual room static pressure in vicinity of sensor while being subjected to an air velocity of 1000 fpm from a 360-degree radial source.

2.3 AIR-PRESSURE SWITCHES

A. Air-Pressure Differential Switch with Set-Point Indicator:

1. Diaphragm operated to actuate an SPDT snap switch.
2. Electrical Connections: Three-screw configuration, including one screw for common operation and two screws for field-selectable normally open or closed operation.
3. Enclosure Conduit Connection: Knock out or threaded connection.
4. User Interface: Screw-type set-point adjustment with enclosed set-point indicator and scale.
5. High and Low Process Connections: Threaded, NPS 1/8.
6. Enclosure:

a. Dry Indoor Installations: NEMA 250, Type 1.
b. Outdoor and Wet Indoor Installations: NEMA 250, Type 4.
c. Hazardous Environments: Explosion proof.

7. Operating Data:

a. Electrical Rating: 15 A at 120- to 480-V ac.
b. Pressure Limits:

1) Continuous: 10 psig.
2) Surge: 25 psig.

c. Temperature Limits: Minus 30 to 110 deg F.
d. Operating Range: Approximately 2 times set point.
e. Repeatability: Within 1 percent.
f. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Air-Pressure Differential Indicating Switch:

1. Combination gage with low- and high-limit switches.
2. Nominal 4-inch-diameter analog indication with white dial face, graduated black markings, pointer to indicate measured value, and a separate adjustable pointer for each switch set point.
3. Switch zero and set-point adjustment screws or knobs on the dial face.
4. Each switch used as a safety limit shall have a manual reset button local to switch.
5. Switch Type: Each set point shall have two Form C relays, DPDT.
6. Electrical Connections: Screw terminals.
7. Enclosure Conduit Connection: NPS 3/4 threaded connection.
8. High and Low Process Connections: Threaded, NPS 1/8.
9. Enclosure:

a. Dry Indoor Installations: NEMA 250, Type 1.
b. Outdoor and Wet Indoor Installations: NEMA 250, Type 4.
c. Hazardous Environments: Explosion proof.

10. Operating Data:

a. Electrical Rating: 10 A at 120- to 240-V ac.
b. Pressure Limits: 25 psig.
c. Temperature Limits: 20 to 120 deg F.
d. Operating Range: Approximately twice normal operating range unless otherwise required for application.
e. Accuracy:

1) 4 percent for ranges through 0.5 in. wg.
2) 2 percent for ranges 1 in. wg and greater.

f. Repeatability: Within 1 percent of full scale.
g. Switch Deadband: One pointer width and within 1 percent of full scale for each switch set point.
h. Power Supply: 24 or 120-V ac, 50/60 Hz.
i. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.4 AIR-PRESSURE TRANSMITTERS

A. Air-Pressure Differential Transmitter:

1. Performance:

a. Range: Approximately 2 times set point.
b. Accuracy: Within 0.5 percent of the full-scale range.

c. Hysteresis: Within 0.10 percent of full scale.
d. Repeatability: Within 0.05 percent of full scale.
e. Stability: Within 1 percent of span per year.
f. Overpressure: 10 psig.
g. Temperature Limits: Zero to 150 deg F.
h. Compensate Temperature Limits: 40 to 150 deg F.
i. Thermal Effects: 0.033 percent of full scale per degree F.
j. Shock and vibration shall not harm the transmitter.

2. Output Signals:

a. Analog Current Signal:

1) Two-wire, 4- to 20-mA dc current source.
2) Signal capable of operating into 800-ohm load.

b. Analog Voltage Signal:

1) Three wire, zero to 5 or 10 V.
2) Minimum Load Resistance: 1000 ohms.

3. Display: Four-digit digital display with minimum 0.4-inch-high numeric characters.
4. Operator Interface: Zero and span adjustments located behind cover.
5. Construction:

a. Plastic casing with removable plastic cover.
b. Threaded, NPS 1/4 swivel fittings for connection to copper tubing or NPS 3/16 barbed fittings for connection to polyethylene tubing. Fittings on bottom of instrument case.
c. Screw terminal block for wire connections.
d. Vertical plane mounting.
e. NEMA 250, Type 4.
f. Provide mounting bracket suitable for installation.

2.5 LIQUID-PRESSURE SWITCHES

A. Liquid-Pressure Differential Switch with Set-Point Indicator:

1. Description:

a. Brass or Type 316 stainless-steel double opposing bellows operate to actuate a SPDT snap switch.
b. Electrical Connections: Screw terminal.
c. Enclosure Conduit Connection: Knock out or threaded connection.
d. User Interface: Thumbscrew set-point adjustment with enclosed set-point indicator and scale.
e. High and Low Process Connections: Threaded, NPS 1/8.
f. Enclosure:

1) Dry Indoor Installations: NEMA 250, Type 1.
2) Outdoor and Wet Indoor Installations: NEMA 250, Type 4.

3) Hazardous Environments: Explosion proof.

g. Operating Data:

1) Electrical Rating: 15 A at 120- to 240-V ac.
2) Pressure Limits: At least 5 times full-scale range, but not less than system design pressure rating.
3) Temperature Limits: Minus 10 to 180 deg F.
4) Operating Range: Approximately 2 times set point.
5) Deadband: Fixed.

2.6 LIQUID-PRESSURE TRANSMITTERS

A. Liquid-Pressure Differential Transmitter:

1. Performance:

a. Range: Approximately 2 times the set point.
b. Span: Adjustable plus or minus one milliamp, noninteractive.
c. Accuracy: Within 0.25 percent of full scale.
d. Hysteresis: Within 0.1 percent of full scale.
e. Repeatability: Within 0.05 percent of full scale.
f. Maximum Working Pressure: 250 psig.
g. Temperature Limits: Zero to 175 deg F.
h. Compensate Temperature Limits: 30 to 150 deg F.
i. Thermal Effects: 0.02 percent of full scale per degree F.
j. Response Time: 30 to 50 ms.
k. Shock and vibration shall not harm the transmitter.

2. Analog Output Current Signal:

a. Two-wire, 4- to 20-mA dc current source.
b. Signal capable of operating into 1000-ohm load.

3. Analog Output Voltage Signal:

a. Three wire, zero to 5 or 10 V or 2 to 10 V.
b. Minimum Load Resistance: 1000 ohms.

4. Operator Interface:

a. Zero and span adjustments located behind cover.
b. Bleed screws on side of body, two screws on low-pressure side, and one screw on high-pressure side, for air in line and pressure cavity.

5. Construction:

a. Aluminum and stainless-steel enclosure with removable cover.
b. Wetted parts of transmitter constructed of 17-4 PH or 300 Series stainless steel.
c. Threaded, NPS 1/4 process connections on side of instrument enclosure.

d. Knock out for 1/2-inch nominal conduit connection on side of instrument enclosure.
e. Screw terminal block for wire connections.
f. NEMA 250, Type 4.
g. Mounting Bracket: Appropriate for installation.

6. Provide transmitter with three-valve manifold. Construct manifold of brass, bronze, or stainless steel. Provide manifold with NPS 1/4 NPT process connections.

2.7 SOURCE QUALITY CONTROL

A. Factory Tests: Test and inspect assembled pressure instruments, as indicated by instrument requirements. Affix standards organization's certification and label.

B. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for instruments installed in piping to verify actual locations of connections before installation.

C. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.

D. Prepare written report, endorsed by Installer, listing conditions detrimental to performance.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Install products level, plumb, parallel, and perpendicular with building construction.

B. Properly support instruments, tubing, piping wiring, and conduit to comply with requirements indicated. Brace all products to prevent lateral movement, sway, or a break in attachment when subjected to a force.

C. Provide ceiling, floor, roof, wall openings, and sleeves required by installation. Before proceeding with drilling, punching, or cutting, check location first for concealed products that could potentially be damaged. Patch, flash, grout, seal, and refinish openings to match adjacent condition.

D. Fastening Hardware:

1. Stillson wrenches, pliers, and other tools that cause injury to or mar surfaces of rods, nuts, and other parts are prohibited for work of assembling and tightening nuts.
2. Tighten bolts and nuts firmly and uniformly. Do not to overstress threads by using excessive force or oversized wrenches.

E. Install products in locations that are accessible and that permit calibration and maintenance from floor, equipment platforms, or catwalks. Where ladders are required for Owner's access, confirm unrestricted ladder placement is possible under occupied condition.

3.3 ELECTRICAL POWER

A. Furnish and install electrical power to products requiring electrical connections.

B. Furnish and install circuit breakers. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers."

C. Furnish and install power wiring. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

D. Furnish and install raceways. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems."

3.4 PRESSURE INSTRUMENT INSTALLATION

A. Mounting Location:

1. Rough-in: Outline instrument-mounting locations before setting instruments and routing, cable, wiring, tubing, and conduit to final location.
2. Install switches and transmitters for air and liquid pressure associated with individual air-handling units and associated connected ductwork and piping near air-handlings units co-located in air-handling unit system control panel, to provide service personnel a single and convenient location for inspection and service.
3. Install liquid pressure switches and transmitters for indoor applications in mechanical equipment rooms. Do not locate in user-occupied space unless indicated specifically on Drawings.
4. Install air-pressure switches and transmitters for indoor applications in mechanical equipment rooms. Do not locate in user-occupied space unless indicated specifically on Drawings.
5. Mount switches and transmitters not required to be mounted within system control panels on walls, floor-supported freestanding pipe stands, or floor-supported structural support frames. Use manufacturer mounting brackets to accommodate field mounting. Securely support and brace products to prevent vibration and movement.
6. Install instruments (except pressure gages) in liquid and liquid-sealed piped services below their process connection point. Slope tubing down to instrument with a slope of 2 percent.
7. Install instruments in dry gas and noncondensable vapor piped services above their process connection point. Slope process connection lines up to instrument with a minimum slope of 2 percent.

B. Seal penetrations to ductwork, plenums, and air-moving equipment to comply with duct static pressure class and leakage and seal classes indicated using neoprene gaskets or grommets.

C. Duct Pressure Sensors:

1. Install sensors using manufacturer's recommended upstream and downstream distances.
2. Unless indicated on Drawings, locate sensors approximately 67 percent of distance of longest duct pressure drop run. Location of sensors shall be submitted and approved before installation.
3. Install mounting hardware and gaskets to make sensor installation airtight.
4. Route tubing from the sensor to transmitter.
5. Use compression fittings at terminations.
6. Install sensor in accordance with manufacturer's instructions.
7. Support sensor to withstand maximum air velocity, turbulence, and vibration encountered to prevent instrument failure.

D. Outdoor Pressure Sensors:

1. Install roof-mounted sensor in least-noticeable location and as far away from exterior walls as possible.
2. Locate wall-mounted sensor in an inconspicuous location.
3. Submit sensor location for approval before installation.
4. Verify signal from sensor is stable and consistent to all connected transmitters. Modify installation to achieve proper signal.
5. Route outdoor signal pipe full size of sensor connection to transmitters. Install branch connection of size required to match to transmitter.
6. Install sensor signal pipe with dirt leg and drain valve below roof penetration.
7. Insulate signal pipe with flexible elastomeric insulation as required to prevent condensation.
8. Connect roof-mounted signal pipe exposed to outdoors to building grounding system.

E. Air-Pressure Differential Switches:

1. Install air-pressure sensor in system for each switch connection. Install sensor in an accessible location for inspection and replacement.
2. A single sensor may be used to share a common signal to multiple pressure instruments.
3. Install access door in duct and equipment to access sensors that cannot be inspected and replaced from outside.
4. Route NPS 3/8 tubing from sensor to switch connection.
5. Do not mount switches on rotating equipment.
6. Install switches in a location free from vibration, heat, moisture, or adverse effects, which could damage the switch and hinder accurate operation.
7. Install switches in an easily accessible location serviceable from floor.
8. Install switches adjacent to system control panel if within 50 feet; otherwise, locate switch in vicinity of system connection.

F. Liquid-Pressure Differential Switches:

1. Where process connections are located in mechanical equipment room, install switch in convenient and accessible location near system control panel.

2. Where process connections are installed outside mechanical rooms, route processing tubing to mechanical room housing system control panel and locate switch near system control panel.
3. Where multiple switches serving same system are installed in same room, install switches by system to provide service personnel a single and convenient location for inspection and service.
4. System process tubing connection shall be full size of switch connection, but not less than NPS 1/2. Install bushing if required to mate switch to system connection.
5. Connect process tubing from point of system connection and extend to switch.
6. Install isolation valves in process tubing as close to system connection as practical.
7. Install dirt leg and drain valve at each switch connection.
8. Do not mount switches on rotating equipment.
9. Install switches in a location free from vibration, heat, moisture, or adverse effects, which could damage the switch and hinder accurate operation.
10. Install switches in an easily accessible location serviceable from floor.

G. Liquid-Pressure Transmitters:

1. Where process connections are installed in mechanical equipment room, install transmitter in convenient and accessible location near system control panel.
2. Where process connections are installed outside mechanical rooms, route processing tubing to mechanical room housing system control panel and locate transmitter near system control panel.
3. Where multiple transmitters serving same system are installed in same room, install transmitters by system to provide service personnel a single and convenient location for inspection and service.
4. System process tubing connection shall be full size of switch connection, but not less than NPS 1/2. Install bushing if required to mate switch to system connection.
5. Connect process tubing from point of system connection and extend to transmitter.
6. Install isolation valves in process tubing as close to system connection as practical.
7. Install dirt leg and drain valve at each transmitter connection.
8. Do not mount transmitters on equipment.
9. Install in a location free from vibration, heat, moisture, or adverse effects, which could damage and hinder accurate operation.

3.5 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Each piece of wire, cable, and tubing shall have the same designation at each end for operators to determine continuity at points of connection. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

B. Install engraved nameplate with instrument identification and on face of ceiling directly below instruments concealed above ceilings.

3.6 CHECKOUT PROCEDURES

A. Check out installed products before continuity tests, leak tests, and calibration.

B. Check instruments for proper location and accessibility.

C. Check instruments for proper installation with respect to direction of flow, elevation, orientation, insertion depth, or other applicable considerations that impact performance.

3.7 ADJUSTMENT, CALIBRATION, AND TESTING

A. Description:

1. Calibrate each instrument installed that is not factory calibrated and provided with calibration documentation.
2. Provide a written description of proposed field procedures and equipment for calibrating each type of instrument. Submit procedures before calibration and adjustment.
3. For each analog instrument, perform a three-point calibration test for both linearity and accuracy.
4. Equipment and procedures used for calibration shall comply with instrument manufacturer's recommendations.
5. Provide diagnostic and test equipment for calibration and adjustment.
6. Field instruments and equipment used to test and calibrate installed instruments shall have accuracy at least twice the instrument accuracy being calibrated. For example, an installed instrument with an accuracy of 1 percent shall be checked by an instrument with an accuracy of 0.5 percent.
7. Calibrate each instrument according to instrument instruction manual supplied by manufacturer.
8. If, after calibration, indicated performance cannot be achieved, replace out-of-tolerance instruments.
9. Comply with field-testing requirements and procedures indicated by ASHRAE Guideline 11, "Field Testing of HVAC Control Components," in the absence of specific requirements, and to supplement requirements indicated.

B. Analog Signals:

1. Check analog voltage signals using a precision voltage meter at zero, 50, and 100 percent.
2. Check analog current signals using a precision current meter at zero, 50, and 100 percent.

C. Digital Signals:

1. Check digital signals using a jumper wire.
2. Check digital signals using an ohmmeter to test for contact.

D. Sensors: Check sensors at zero, 50, and 100 percent of project design values.

E. Switches: Calibrate switches to make or break contact at set points indicated.

F. Transmitters:

1. Check and calibrate transmitters at zero, 50, and 100 percent of project design values.

3.8 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.9 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain instrumentation and control devices.

END OF SECTION

SECTION 230923.27 - TEMPERATURE INSTRUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Air temperature sensors.
2. Air temperature switches.
3. Air temperature RTD transmitters.
4. Liquid temperature sensors.
5. Liquid temperature switches.

B. Related Requirements:

1. Section 230923 "Direct-Digital Control System for HVAC" for control equipment and software, relays, electrical power devices, uninterruptible power supply units, wire, and cable.

1.3 DEFINITIONS

A. HART (Highway Addressable Remote Transducer) Protocol: The global standard for sending and receiving digital information across analog wires between smart devices and control or monitoring systems through bidirectional communication that provides data access between intelligent field instruments and host systems. A host can be any software application from a technician's hand-held device or laptop to a plant's process control, asset management, safety, or other system using any control platform.

B. RTD: Resistance temperature detector.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Product Data: For each type of product, including the following:

1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
3. Product description with complete technical data, performance curves, and product specification sheets.
4. Installation operation and maintenance instructions, including factors affecting performance.

D. Shop Drawings:

1. Include plans, elevations, sections, and mounting details.
2. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.
4. Include number-coded identification system for unique identification of wiring, cable, and tubing ends.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Coordination Drawings: Plan drawings and corresponding product installation details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Product installation location shown in relationship to room, duct, pipe, and equipment.
2. Wall-mounted instruments located in finished space showing relationship to light switches, fire-alarm devices, and other installed devices.
3. Sizes and locations of wall access panels for instruments installed behind walls.
4. Sizes and locations of ceiling access panels for instruments installed in inaccessible ceilings.

C. Product Certificates: For each product requiring a certificate.

D. Product Test Reports: For each product, for tests performed by manufacturer and witnessed by a qualified testing agency or a qualified testing agency.

E. Field quality-control reports.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of the Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Furnish extra materials and parts that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

C. Provide two matching product(s) in Project inventory for each unique size and type of temperature instrument provided.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Environmental Conditions:

1. Instruments shall operate without performance degradation under the ambient environmental temperature, pressure, humidity, and vibration conditions specified and encountered for installed location.

    a. If instrument alone cannot meet requirement, install instrument in a protective enclosure that is isolated and protected from conditions impacting performance. Enclosure shall be internally insulated, electrically heated, filtered, and ventilated as required by instrument and application.

2.2 AIR TEMPERATURE SENSORS

A. Platinum RTDs: Common Requirements:

1. 100 or 1000 ohms at zero deg C and a temperature coefficient of 0.00385 ohm/ohm/deg C.
2. Two-wire, PTFE-insulated, 22-gage stranded copper leads.
3. Performance Characteristics:

    a. Range: Minus 50 to 275 deg F.
    b. Interchangeable Accuracy: At 32 deg F within 0.5 deg F.
    c. Repeatability: Within 0.5 deg F.
    d. Self-Heating: Negligible.

4. Transmitter Requirements:

    a. Transmitter required for each 100-ohm RTD.
    b. Transmitter optional for 1000-ohm RTD, contingent on compliance with end-to-end control accuracy.

B. Platinum RTD, Single-Point Air Temperature Duct Sensors:

1. 100 or 1000 ohms.
2. Temperature Range: Minus 50 to 275 deg F
3. Probe: Single-point sensor with a stainless-steel sheath.
4. Length: As required by application to achieve tip at midpoint of air tunnel, up to 18 inches.

5. Enclosure: Junction box with removable cover; NEMA 250, Type 1 for indoor applications and Type 4 for outdoor applications.
6. Gasket for attachment to duct or equipment to seal penetration airtight.
7. Conduit Connection: 1/2-inch

C. Platinum RTD, Air Temperature Averaging Sensors:

1. 100 or 1000 ohms.
2. Temperature Range: Minus 50 to 275 deg F
3. Multiple sensors to provide average temperature across entire length of sensor.
4. Rigid probe of aluminum, brass, copper, or stainless-steel sheath.
5. Flexible probe of aluminum, brass, copper, or stainless-steel sheath and formable to a 4-inch radius.
6. Length: As required by application to cover entire cross section of air tunnel.
7. Enclosure: Junction box with removable cover; NEMA 250, Type 1 for indoor applications and Type 4 for outdoor applications.
8. Gasket for attachment to duct or equipment to seal penetration airtight.
9. Conduit Connection: 1/2-inch

D. Platinum RTD Outdoor Air Temperature Sensors:

1. 100 or 1000 ohms.
2. Temperature Range: Minus 50 to 275 deg F
3. Probe: Single-point sensor with a stainless-steel sheath.
4. Solar Shield: Stainless steel.
5. Enclosure: NEMA 250, Type 4 or 4X junction box or combination conduit and outlet box with removable cover and gasket.
6. Conduit Connection: 1/2-inch trade size.

E. Platinum RTD Space Air Temperature Sensors:

1. 100 or 1000 ohms.
2. Temperature Range: Minus 50 to 212 deg F
3. Sensor assembly shall include a temperature sensing element mounted under a bright white, non-yellowing, plastic or flush, brushed-aluminum cover.
4. Provide a mounting plate that is compatible with the surface shape that it is mounted to and electrical box used.
5. Concealed wiring connection.

F. Thermal Resistors (Thermistors): Common Requirements:

1. 10,000 ohms at 25 deg C and a temperature coefficient of 23.5 ohms/ohm/deg C.
2. Two-wire, PTFE-insulated, 22-gage stranded copper leads.
3. Performance Characteristics:

    a. Range: Minus 50 to 275 deg F.
    b. Interchangeable Accuracy: At 77 deg F within 0.5 deg F.
    c. Repeatability: Within 0.5 deg F.
    d. Drift: Within 0.5 deg F over 10 years.
    e. Self-Heating: Negligible.

4. Transmitter optional, contingent on compliance with end-to-end control accuracy.

G. Thermistor, Single-Point Duct Air Temperature Sensors:

1. Temperature Range: Minus 50 to 275 deg F
2. Probe: Single-point sensor with a stainless-steel sheath.
3. Length: As required by application to achieve tip at midpoint of air tunnel, up to 18 inches.
4. Enclosure: Junction box with removable cover; NEMA 250, Type 1 for indoor applications and Type 4 for outdoor applications.
5. Gasket for attachment to duct or equipment to seal penetration airtight.
6. Conduit Connection: 1/2- inch trade size

H. Thermistor Averaging Air Temperature Sensors:

1. Temperature Range: Minus 50 to 275 deg F
2. Multiple sensors to provide average temperature across entire length of sensor.
3. Rigid probe of aluminum, brass, copper, or stainless-steel sheath.
4. Flexible probe of aluminum, brass, copper, or stainless-steel sheath and formable to a 4-inch radius.
5. Length: As required by application to cover entire cross section of air tunnel.
6. Enclosure: Junction box with removable cover; NEMA 250, Type 1 for indoor applications and Type 4 for outdoor applications.
7. Gasket for attachment to duct or equipment to seal penetration airtight.
8. Conduit Connection: 1/2-inch trade size.

I. Thermistor Outdoor Air Temperature Sensors:

1. Temperature Range: Minus 50 to 275 deg F
2. Probe: Single-point sensor with a stainless-steel sheath.
3. Solar Shield: Stainless steel.
4. Enclosure: NEMA 250, Type 4 or 4X junction box or combination conduit and outlet box with removable cover and gasket.
5. Conduit Connection: 1/2-inch trade size.

J. Thermistor Space Air Temperature Sensors:

1. Temperature Range: Minus 50 to 212 deg F
2. Sensor assembly shall include a temperature sensing element mounted under a bright white, non-yellowing, plastic or flush, brushed-aluminum cover.
3. Provide a mounting plate that is compatible with the surface shape that it is mounted to and electrical box used.
4. Concealed wiring connection.

K. Space Air Temperature Sensors for Use with DDC Controllers Controlling Terminal Units:

1. 100- or 1000-ohm platinum RTD or thermistor.
2. Thermistor:

    a. Pre-aged, burned in, and coated with glass; inserted in a metal sleeve; and entire unit encased in epoxy.
    b. Thermistor drift shall be less than plus or minus 0.5 deg F over 10 years.

3. Temperature Transmitter Requirements:

a. Mating transmitter required with each 100-ohm RTD.
b. Mating transmitters optional for 1000-ohm RTD and thermistor, contingent on compliance with end-to-end control accuracy.

4. Provide digital display of sensed temperature.
5. Provide sensor with local control.

a. Local override to turn HVAC on.
b. Local adjustment of temperature set point.
c. Both features shall be capable of manual override through control system operator.

2.3 AIR TEMPERATURE SWITCHES

A. Thermostat and Switch for Low Temperature Control in Duct Applications:

1. Description:

a. Two-position control.
b. Field-adjustable set point.
c. Manual or automatic reset as indicated on Drawings.
d. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2. Performance:

a. Operating Temperature Range: 15 to 55 deg F.
b. Temperature Differential: 5 deg F, non-adjustable and additive.
c. Enclosure Ambient Temperature: Minus 20 to 140 deg F.
d. Sensing Element Maximum Temperature: 250 deg F.
e. Voltage: 120-V ac.
f. Current: 16 FLA.
g. Switch Type: Two SPDT snap switches operate on coldest 12-inchsection along element length.

3. Construction:

a. Vapor-Filled Sensing Element: Nominal 20 feetlong.
b. Dual Temperature Scale: Fahrenheit and Celsius visible on face.
c. Set-Point Adjustment: Screw.
d. Enclosure: Painted metal, NEMA 250, Type 1.
e. Electrical Connections: Screw terminals.
f. Conduit Connection: 1/2-inch trade size.

2.4 AIR TEMPERATURE RTD TRANSMITTERS

A. Source Limitations: Obtain temperature-measuring sensors and transmitters and airflow from single manufacturer.

B. House electronics in NEMA 250 enclosure.

1. Duct: Type 1.
2. Outdoor: Type 4 or Type 4X.
3. Space: Type 1.

C. Conduit Connection: 1/2-inch

D. Functional Characteristics:

1. Input:

a. 100-ohm platinum RTD temperature coefficient of 0.00385 ohm/ohm/deg C, two-wire sensors.
b. 1000-ohm platinum RTD temperature coefficient of 0.00385 ohm/ohm/deg C, two-wire sensors.

2. Span (Adjustable):

a. Space: 40 to 90 deg F.
b. Supply Air Cooling and Heating: 40 to 120 deg F.
c. Supply Air Cooling Only: 40 to 90 deg F.
d. Supply Air Heating Only: 40 to 120 deg F.
e. Exhaust Air: 50 to 100 deg F.
f. Return Air: 50 to 100 deg F.
g. Mixed Air: Minus 40 to 140 deg F.
h. Outdoor: Minus 40 to 140 deg F.

3. Output: 4- to 20-mA dc, linear with temperature; RFI insensitive; minimum drive load of 600 ohms at 24-V dc .
4. Zero and span field adjustments, plus or minus 5 percent of span. Minimum span of 50 deg F.
5. Match sensor with temperature transmitter and factory calibrate together.

E. Performance Characteristics:

1. Calibration Accuracy: Within 0.1 percent of the span.
2. Stability: Within 0.2 percent of the span for at least 6 months.
3. Combined Accuracy: Within 0.5 percent.

2.5 LIQUID TEMPERATURE SENSORS, COMMERCIAL GRADE

A. RTD:

1. Description:

a. Platinum with a value of 100 or 1000 ohms at zero deg C and a temperature coefficient of 0.00385 ohm/ohm/deg C.
b. Encase RTD in a stainless-steel sheath with a 0.25-inch OD.
c. Sensor Length: 4, 6, or 8 inchesas required by application.
d. Process Connection: Threaded, NPS 1/2
e. Two-stranded copper lead wires.
f. Powder-coated steel enclosure, NEMA 250, Type 4.

g. Conduit Connection: 1/2-inch
h. Performance Characteristics:

1) Range: Minus 40 to 210 deg F.
2) Interchangeable Accuracy: Within 0.54 deg F at 32 deg F.

B. Thermowells:

1. Stem: Straight or stepped shank formed from solid bar stock.
2. Material: Brass.
3. Process Connection: Threaded, NPS 3/4.
4. Sensor Connection: Threaded, NPS 1/2.
5. Bore: Sized to accommodate sensor with tight tolerance between sensor and well.
6. Furnish thermowells installed in insulated pipes and equipment with an extended neck.
7. Length: 4, 6, or 8 inchesas required by application.
8. Thermowells furnished with heat-transfer compound to eliminate air gap between wall of sensor and thermowell and to reduce time constant.

2.6 LIQUID TEMPERATURE SWITCHES

A. Thermostat and Switch for Temperature Control in Pipe Applications:

1. Description:

a. Two-position control.
b. Field-adjustable set point.
c. Manual reset.
d. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2. Performance:

a. Operating Temperature Range: 65 to 200 deg F.
b. Temperature Differential Deadband: 5 to 30 deg F, adjustable.
c. Enclosure Ambient Temperature: 150 deg F.
d. Sensing Element Pressure Rating: 200 psig.
e. Voltage: 120-V ac.
f. Current: 8 FLA.
g. Switch Type: SPDT snap switch.

3. Construction:

a. Vapor-Filled Immersion Element: Copper, nominal 3 incheslong.
b. Temperature Scale: Fahrenheit, visible on face.
c. Set-Point Adjustment: Screw.
d. Enclosure: Painted metal, NEMA 250, Type 1.
e. Electrical Connections: Screw terminals.
f. Conduit Connection: 3/4-inch.

2.7 LIQUID TEMPERATURE TRANSMITTERS, COMMERCIAL GRADE

A. House electronics in NEMA 250, Type 4 enclosure.

B. Enclosure Connection: 1/2-inch trade size.

C. Functional Characteristics:

1. Input: 100-ohm platinum RTD temperature coefficient of 0.00385 ohm/ohm/deg C, two- or three-wire sensors.
2. Default Span (Adjustable):

    a. Chilled Water: Zero to 100 deg F.
    b. Condenser Water: Zero to 120 deg F.
    c. Heating Hot Water: 32 to 212 deg F.
    d. Heat Recovery: Zero to 120 deg F.

3. Output: 4- to 20-mA dc, linear with temperature; RFI insensitive; minimum drive load of 600 ohms at 24-V dc.
4. Zero and span field adjustments, plus or minus 5 percent of span. Minimum span of 50 deg F.
5. Match sensor with temperature transmitter and factory calibrate together. Each matched sensor and transmitter set shall include factory calibration data traceable to NIST.

D. Performance Characteristics:

1. Calibration Accuracy: Within 0.1 percent of the span.
2. Stability: Within 0.2 percent of the span for at least 6 months.
3. Combined Accuracy: Within 0.5 percent.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for instruments installed in piping to verify actual locations of connections before installation.

C. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.

D. Prepare written report, endorsed by Installer, listing conditions detrimental to performance.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Install products level, plumb, parallel, and perpendicular with building construction.

B. Properly support instruments, tubing, piping, wiring, and conduit to comply with requirements indicated. Brace all products to prevent lateral movement and sway or a break in attachment when subjected to a force.

C. Fastening Hardware:

1. Stillson wrenches, pliers, and other tools that cause injury to or mar surfaces of rods, nuts, and other parts are prohibited for work of assembling and tightening nuts.
2. Tighten bolts and nuts firmly and uniformly. Do not overstress threads by excessive force or by oversized wrenches.

D. Install products in locations that are accessible and that permit calibration and maintenance from floor, equipment platforms, or catwalks. Where ladders are required for Owner's access, confirm unrestricted ladder placement is possible under occupied condition.

3.3 ELECTRIC POWER

A. Furnish and install electrical power to products requiring electrical connections.

B. Furnish and install circuit breakers. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers."

C. Furnish and install power wiring. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

D. Furnish and install raceways. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems."

3.4 TEMPERATURE INSTRUMENT INSTALLATIONS

A. Mounting Location:

1. Roughing In:

a. Outline instrument mounting locations before setting instruments and routing cable, wiring, tubing, and conduit to final location.
b. Provide independent inspection to confirm that proposed mounting locations comply with requirements indicated and approved submittals.

1) Indicate dimensioned locations with mounting height for all surface-mounted products on Shop Drawings.
2) Do not begin installation without submittal approval of mounting location.

c. Complete installation rough-in only after confirmation by independent inspection is complete and approval of location is documented for review by Owner and Architect on request.

2. Install switches and transmitters for air and liquid temperature associated with individual air-handling units and associated connected ductwork and piping near air-handling units co-located in air-handling unit system control panel to provide service personnel a single and convenient location for inspection and service.
3. Install liquid temperature switches and transmitters for indoor applications in mechanical equipment rooms. Do not locate in user-occupied space unless indicated specifically on Drawings.
4. Install air temperature switches and transmitters for indoor applications in mechanical equipment rooms. Do not locate in user-occupied space unless indicated specifically on Drawings.
5. Mount switches and transmitters on walls, floor-supported freestanding pipe stands, or floor-supported structural support frames. Use manufacturer's mounting brackets to accommodate field mounting. Securely support and brace products to prevent vibration and movement.

B. Special Mounting Requirements:

1. Temperature instruments having performance impacted by temperature of mounting substrate shall be isolated with an insulating barrier located between instrument and substrate to eliminate effect. Where instruments requiring insulation are located in finished space, conceal insulating barrier in a cover matching the instrument cover.

C. Mounting Height:

1. Mount temperature instruments in user-occupied space to match mounting height of light switches unless otherwise indicated on Drawings. Mounting height shall comply with codes and accessibility requirements.
2. Mount switches and transmitters located in mechanical equipment rooms and other similar space not subject to code or state and Federal accessibility requirements within a range of 42 to 54 inches above the adjacent floor, grade, or service catwalk or platform.

D. Seal penetrations to ductwork, plenums, and air-moving equipment to comply with duct static-pressure class and leakage and seal classes indicated using neoprene gaskets or grommets.

E. Space Temperature Sensor Installation:

1. Conceal assembly in an electrical box of sufficient size to house sensor and transmitter, if provided.
2. Install electrical box with a faceplate to match sensor cover if sensor cover does not completely cover electrical box.
3. In finished areas, recess electrical box within wall.
4. In unfinished areas, electrical box may be surface mounted if electrical light switches are surface mounted. Use a cast-aluminum electric box for surface-mounted installations.
5. Align electrical box with other electrical devices such as visual alarms and light switches located in the vicinity to provide a neat and well-thought-out arrangement. Where possible, align in both horizontal and vertical axis.

F. Outdoor Air Temperature Sensor Installation:

1. Mount sensor in a discrete location facing north.
2. Protect installed sensor from solar radiation and other influences that could impact performance.

3. If required to have a transmitter, mount transmitter remote from sensor in an accessible and serviceable location indoors.

G. Single-Point Duct Temperature Sensor Installation:

1. Install single-point-type, duct-mounted, supply- and return-air temperature sensors. Install sensors in ducts with sensitive portion of the element installed in center of duct cross section and located to sense near average temperature. Do not exceed 24 inches in sensor length.
2. Install return-air sensor in location that senses return-air temperature without influence from outdoor or mixed air.
3. Rigidly support sensor to duct and seal penetration airtight.
4. If required to have transmitter, mount transmitter remote from sensor at accessible and serviceable location.

H. Averaging Duct Temperature Sensor Installation:

1. Install averaging-type air temperature sensor for temperature sensors located within air-handling units, similar equipment, and large ducts with air tunnel cross-sectional area of 20 sq. ft. and larger.
2. Install sensor length to maintain coverage over entire cross-sectional area. Install multiple sensors where required to maintain the minimum coverage.
3. Fasten and support sensor with manufacturer-furnished clips to keep sensor taut throughout entire length.
4. If required to have transmitter, mount transmitter in an accessible and serviceable location.

I. Low-Limit Air Temperature Switch Installation:

1. Install multiple low-limit switches to maintain coverage over entire cross-sectional area of air tunnel.
2. Fasten and support sensing element with manufacturer-furnished clips to keep element taut throughout entire length.
3. Mount switches outside of airstream at a location and mounting height to provide easy access for switch set-point adjustment and manual reset.
4. Install on entering side of cooling coil unless otherwise indicated on Drawings.

J. Liquid Temperature Sensor Installation:

1. Assembly shall include sensor, thermowell.
2. For pipe NPS 4 and larger, install sensor and thermowell length to extend into pipe between 50 to 75 percent of pipe cross section.
3. For pipe smaller than NPS 4:

    a. Install reducers to increase pipe size to NPS 4at point of thermowell installation.
    b. For pipe sizes NPS 2-1/2 and NPS 3, thermowell and sensor may be installed at pipe elbow or tee to achieve manufacturer-recommended immersion depth in lieu of increasing pipe size.
    c. Minimum insertion depth shall be 2-1/2 inches.

4. Install matching thermowell.
5. Fill thermowell with heat-transfer fluid before inserting sensor.

6. Tip of spring-loaded sensors shall contact inside of thermowell.
7. For insulated piping, install thermowells with extension neck to extend beyond face of insulation.
8. Install thermowell in top dead center of horizontal pipe positioned in an accessible location to allow for inspection and replacement. If top dead center location is not possible due to field constraints, install thermowell at location along top half of pipe.
9. For applications with transmitters, mount transmitter remote from sensor in an accessible and serviceable location from floor.

3.5 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Each piece of wire, cable, and tubing shall have the same designation at each end for operators to determine continuity at points of connection. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

B. Install engraved nameplate with instrument identification.

3.6 CLEANING

A. Remove grease, mastic, adhesives, dust, dirt, stains, fingerprints, labels, and other foreign materials from exposed interior and exterior surfaces.

B. Wash and shine glazing.

C. Polish glossy surfaces to a clean shine.

3.7 CHECK-OUT PROCEDURES

A. Check installed products before continuity tests, leak tests, and calibration.

B. Check temperature instruments for proper location and accessibility.

C. Verify sensing element type and proper material.

D. Verify location and length.

E. Verify that wiring is correct and secure.

3.8 ADJUSTMENT, CALIBRATION, AND TESTING

A. Description:

1. Calibrate each instrument installed that is not factory calibrated and provided with calibration documentation.
2. Provide a written description of proposed field procedures and equipment for calibrating each type of instrument. Submit procedures before calibration and adjustment.

3. For each analog instrument, make a three-point test of calibration for both linearity and accuracy.
4. Equipment and procedures used for calibration shall meet instrument manufacturer's written instructions.
5. Provide diagnostic and test equipment for calibration and adjustment.
6. Field instruments and equipment used to test and calibrate installed instruments shall have accuracy at least twice the instrument accuracy being calibrated. For example, an installed instrument with an accuracy of 1 percent shall be checked by an instrument with an accuracy of 0.5 percent.
7. Calibrate each instrument according to instrument instruction manual supplied by manufacturer.
8. If after calibration indicated performance cannot be achieved, replace out-of-tolerance instruments.
9. Comply with field-testing requirements and procedures indicated by ASHRAE Guideline 11, "Field Testing of HVAC Control Components," in the absence of specific requirements and to supplement requirements indicated.

B. Analog Signals:

1. Check analog voltage signals using a precision voltage meter at zero, 50, and 100 percent.
2. Check analog current signals using a precision current meter at zero, 50, and 100 percent.
3. Check resistance signals for temperature sensors at zero, 50, and 100 percent of operating span using a precision-resistance source.

C. Digital Signals:

1. Check digital signals using a jumper wire.
2. Check digital signals using an ohmmeter to test for contact.

D. Sensors: Check sensors at zero, 50, and 100 percent of Project design values.

E. Switches: Calibrate switches to make or break contact at set points indicated.

F. Transmitters:

1. Check and calibrate transmitters at zero, 50, and 100 percent of Project design values.
2. Calibrate resistance temperature transmitters at zero, 50, and 100 percent of span using a precision-resistance source.

3.9 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Perform according to manufacturer's written instruction.
2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

B. Prepare test and inspection reports.

3.10 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.11 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain temperature instruments.

END OF SECTION

SECTION 230923.53 – VARIABLE-FREQUENCY MOTOR CONTROLLERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes separately enclosed, preassembled, combination VFCs, rated 600 V and less, for speed control of three-phase, squirrel-cage induction motors.

1.3 DEFINITIONS

A. CPT: Control power transformer.

B. DDC: Direct digital control.

C. EMI: Electromagnetic interference.

D. LED: Light-emitting diode.

E. NC: Normally closed.

F. NO: Normally open.

G. OCPD: Overcurrent protective device.

H. PID: Control action, proportional plus integral plus derivative.

I. RFI: Radio-frequency interference.

J. VFC: Variable-frequency motor controller.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type and rating of VFC indicated. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include dimensions and finishes for VFCs.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

C. Shop Drawings: For each VFC indicated.

1. Include mounting and attachment details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Certificates: For each VFC from manufacturer.

C. Source quality-control reports.

D. Field quality-control reports.

E. Sample Warranty: For special warranty.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For VFCs to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. Manufacturer's written instructions for testing and adjusting thermal-magnetic circuit breaker and motor-circuit protector trip settings.
b. Manufacturer's written instructions for setting field-adjustable overload relays.
c. Manufacturer's written instructions for testing, adjusting, and reprogramming microprocessor control modules.
d. Manufacturer's written instructions for setting field-adjustable timers, controls, and status and alarm points.

1.7 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace VFCs that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. General Requirements for VFCs:

1. VFCs and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
2. Comply with NEMA ICS 7, NEMA ICS 61800-2, and UL 508A.

B. Application: Variable torque for centrifugal fans.

C. VFC Description: Variable-frequency motor controller, consisting of power converter that employs pulse-width-modulated inverter, factory built and tested in an enclosure, with integral disconnecting means and overcurrent and overload protection; listed and labeled by an NRTL as a complete unit; arranged to provide self-protection, protection, and variable-speed control of one or more three-phase induction motors by adjusting output voltage and frequency.

1. Units suitable for operation of NEMA MG 1, Design A and Design B motors, as defined by NEMA MG 1, Section IV, Part 30, "Application Considerations for Constant Speed Motors Used on a Sinusoidal Bus with Harmonic Content and General Purpose Motors Used with Adjustable-Voltage or Adjustable-Frequency Controls or Both."
2. Units suitable for operation of inverter-duty motors as defined by NEMA MG 1, Section IV, Part 31, "Definite-Purpose Inverter-Fed Polyphase Motors."
3. Listed and labeled for integrated short-circuit current (withstand) rating by an NRTL acceptable to authorities having jurisdiction.

D. Design and Rating: Match load type, such as fans, blowers, and pumps; and type of connection used between motor and load such as direct or through a power-transmission connection.

E. Output Rating: Three phase; 10 to 60 Hz, with voltage proportional to frequency throughout voltage range; maximum voltage equals input voltage.

F. Unit Operating Requirements:

1. Ambient Temperature Rating: Not less than 32 deg F and not exceeding 104 deg F.
2. Humidity Rating: Less than 95 percent (noncondensing).
3. Altitude Rating: Not exceeding 3300 feet.
4. Overload Capability: 1.1 times the base load current for 60 seconds; minimum of 1.8 times the base load current for three seconds.
5. Starting Torque: Minimum 100 percent of rated torque from 3 to 60 Hz.

G. Inverter Logic: Microprocessor based, isolated from all power circuits.

H. Isolated Control Interface: Allows VFCs to follow remote-control signal over a minimum 40:1 speed range.

I. Internal Adjustability Capabilities:

1. Minimum Speed: 5 to 25 percent of maximum rpm.
2. Maximum Speed: 80 to 100 percent of maximum rpm.
3. Acceleration: 0.1 to 999.9 seconds.

4. Deceleration: 0.1 to 999.9 seconds.
5. Current Limit: 30 to minimum of 150 percent of maximum rating.

J. Self-Protection and Reliability Features:

1. Surge Suppression: Factory installed as an integral part of the VFC, complying with UL 1449 SPD, Type 1 or Type 2.
2. Loss of Input Signal Protection: Selectable response strategy, including speed default to a percent of the most recent speed, a preset speed, or stop; with alarm.
3. Under- and overvoltage trips.
4. Inverter overcurrent trips.
5. Critical frequency rejection, with three selectable, adjustable deadbands.
6. Instantaneous line-to-line and line-to-ground overcurrent trips.
7. Loss-of-phase protection.
8. Reverse-phase protection.
9. Short-circuit protection.
10. Motor-overtemperature fault.

K. Automatic Reset/Restart: Attempt three restarts after drive fault or on return of power after an interruption and before shutting down for manual reset or fault correction; adjustable delay time between restart attempts.

L. Bidirectional Autospeed Search: Capable of starting VFC into rotating loads spinning in either direction and returning motor to set speed in proper direction, without causing damage to drive, motor, or load.

2.2 CONTROLS AND INDICATION

A. Status Lights: Door-mounted LED indicators displaying the following conditions:

1. Power on.
2. Run.
3. Overvoltage.
4. Line fault.
5. Overcurrent.
6. External fault.

B. Indicating Devices: Digital display mounted flush in VFC door and connected to display VFC parameters including, but not limited to:

1. Output frequency (Hz).
2. Motor speed (rpm).
3. Motor status (running, stop, fault).
4. Motor current (amperes).
5. Motor torque (percent).
6. Fault or alarming status (code).
7. PID feedback signal (percent).
8. DC-link voltage (V dc).
9. Set point frequency (Hz).
10. Motor output voltage (V ac).

C. Control Signal Interfaces:

1. Remote Signal Inputs: Capability to accept any of the following speed-setting input signals from the DDC system for HVAC or other control systems:

   a. 0- to 10-V dc.
   b. 4- to 20-mA dc.

2. Remote Indication Interface: A minimum of two programmable dry-circuit relay outputs (120-V ac, 1 A) for remote indication of the following:

   a. Motor running.
   b. Set point speed reached.
   c. Fault and warning indication (overtemperature or overcurrent).
   d. PID high- or low-speed limits reached.

2.3 ENCLOSURES

A. VFC Enclosures: NEMA 250, to comply with environmental conditions at installed location.

   1. Dry and Clean Indoor Locations: Type 1.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, surfaces, and substrates to receive VFCs, with Installer present, for compliance with requirements for installation tolerances, and other conditions affecting performance of the Work.

B. Examine VFC before installation. Reject VFCs that are wet, moisture damaged, or mold damaged.

C. Examine roughing-in for conduit systems to verify actual locations of conduit connections before VFC installation.

D. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Wall-Mounting Controllers: Install with tops at uniform height and with disconnect operating handles not higher than 79 inches above finished floor, unless otherwise indicated, and by bolting units to wall or mounting on lightweight structural-steel channels bolted to wall.

3.3 CONTROL WIRING INSTALLATION

A. Install wiring between VFCs and existing building DDC system. Comply with requirements in Section 230923 "Direct Digital Control (DDC) System for HVAC."

B. Bundle, train, and support wiring in enclosures.

3.4 IDENTIFICATION

A. Identify VFCs, components, and control wiring. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
2. Label each VFC with engraved nameplate.
3. Label each enclosure-mounted control and pilot device.

3.5 FIELD QUALITY CONTROL

A. The General Contractor shall engage a testing agent to perform tests and inspections with the assistance of a factory-authorized service representative.

B. Tests and Inspections:

1. Inspect VFC, wiring, components, connections, and equipment installation. Test and adjust controllers, components, and equipment.
2. Test continuity of each circuit.
3. Verify that voltages at VFC locations are within 10 percent of motor nameplate rated voltages. If outside this range for any motor, notify University before starting the motor(s).
4. Test each motor for proper phase rotation.
5. Perform tests according to the Inspection and Test Procedures for Adjustable Speed Drives stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
6. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
7. Test and adjust controls, remote monitoring, and safeties. Replace damaged and malfunctioning controls and equipment.

C. VFCs will be considered defective if they do not pass tests and inspections.

D. Prepare test and inspection reports. Include notation of deficiencies detected, remedial action taken, and observations made after remedial action.

3.6 STARTUP SERVICE

A. Perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.

3.7 ADJUSTING

A. Program microprocessors for required operational sequences, status indications, alarms, event recording, and display features. Clear events memory after final acceptance testing and prior to Substantial Completion.

3.8 DEMONSTRATION

A. Train University's maintenance personnel to adjust, operate, reprogram, and maintain VFCs.

END OF SECTION

SECTION 231123 - NATURAL-GAS PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Pipes, tubes, and fittings.
2. Manual gas shutoff valves.

B. Provide modifications to existing building natural gas service provided by Maine Natural Gas.

1.2 DEFINITIONS

A. CWP: Cold working pressure.

B. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. An example includes rooftop locations.

C. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Piping specialties.
2. Valves. Include pressure rating, capacity, settings, and electrical connection data of selected models.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Welding certificates.

1.5 QUALITY ASSURANCE

A. Steel Support Welding Qualifications: Qualify procedures and personnel in accordance with

AWS D1.1/D1.1M, "Structural Welding Code - Steel."

B. Pipe Welding Qualifications: Qualify procedures and operators in accordance with the ASME Boiler and Pressure Vessel Code.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Handling Flammable Liquids: Remove and dispose of liquids from existing natural-gas piping in accordance with requirements of authorities having jurisdiction.

B. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.

C. Store and handle pipes and tubes having factory-applied protective coatings to avoid damaging coating, and protect from direct sunlight.

1.7 COORDINATION

A. Coordinate requirements for piping identification for natural-gas piping. Comply with requirements in Section 220553 "Identification of HVAC Piping and Equipment."

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Comply with NFPA 54.

B. Minimum Operating-Pressure Ratings:

1. Piping and Valves: 100 psig minimum unless otherwise indicated.

C. Natural-Gas System Pressure within Buildings:

1. Single Pressure: More than 0.5 psig, but not more than 2 psig.

D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 PIPES, TUBES, AND FITTINGS

A. Steel Pipe: ASTM A53/A53M, black steel, Schedule 40, Type E or S, Grade B.

1. Malleable-Iron Threaded Fittings: ASME B16.3, Class 150, standard pattern.
2. Wrought-Steel Welding Fittings: ASTM A234/A234M for butt welding and socket welding.
3. Unions: ASME B16.39, Class 150, malleable iron with brass-to-iron seat, ground joint,

and threaded ends.

4. Forged-Steel Flanges and Flanged Fittings: ASME B16.5, minimum Class 150, including bolts, nuts, and gaskets of the following material group, end connections, and facings:

    a. Material Group: 1.1.
    b. End Connections: Threaded or butt welding to match pipe.
    c. Lapped Face: Not permitted underground.
    d. Gasket Materials: ASME B16.20, metallic, flat, asbestos free, aluminum O-rings, and spiral-wound metal gaskets.
    e. Bolts and Nuts: ASME B18.2.1, carbon steel aboveground and stainless steel underground.

2.3 PIPING SPECIALTIES

A. Y-Pattern Strainers:

1. Body: ASTM A126, Class B, cast iron with bolted cover and bottom drain connection.
2. End Connections: Threaded ends for NPS 2 and smaller; flanged ends for NPS 2-1/2 and larger.
3. Strainer Screen: 60-mesh startup strainer and perforated stainless steel basket with 50 percent free area.
4. CWP Rating: 125 psig.

2.4 JOINING MATERIALS

A. Joint Compound and Tape: Suitable for natural gas.

B. Welding Filler Metals: Comply with AWS D10.12/D10.12M for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

2.5 MANUAL GAS SHUTOFF VALVES

A. General Requirements for Metallic Valves, NPS 2 (DN 50) and Smaller: Comply with ASME B16.33.

1. CWP Rating: 125 psig.
2. Threaded Ends: Comply with ASME B1.20.1.
3. Listed and labeled by an NRTL acceptable to authorities having jurisdiction for valves 1 inch and smaller.
4. Service Mark: Valves NPS 1-1/4 to NPS 2 having initials "WOG" permanently marked on valve body.

B. General Requirements for Metallic Valves, NPS 2-1/2 (DN 65) and Larger: Comply with ASME B16.38.

1. CWP Rating: 125 psig.
2. Flanged Ends: Comply with ASME B16.5 for steel flanges.
3. Service Mark: Initials "WOG" permanently marked on valve body.

C. Two-Piece, Full-Port, Bronze Ball Valves with Bronze Trim: MSS SP-110.

1. Body: Bronze, complying with ASTM B584.
2. Ball: Chrome-plated bronze.
3. Stem: Bronze; blowout proof.
4. Seats: Reinforced TFE; blowout proof.
5. Packing: Threaded-body packnut design with adjustable-stem packing.
6. Ends: Threaded or socket.
7. CWP Rating: 600 psig.
8. Listing: Valves NPS 1 and smaller are to be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
9. Service: Suitable for natural-gas service with "WOG" indicated on valve body.

D. Cast-Iron, Lubricated Plug Valves: MSS SP-78.

1. Body: Cast iron, complying with ASTM A126, Class B.
2. Plug: Bronze or nickel-plated cast iron.
3. Seat: Coated with thermoplastic.
4. Stem Seal: Compatible with natural gas.
5. Ends: Threaded or flanged as indicated in "Underground, Manual Gas Shutoff Valve Schedule" and "Aboveground, Manual Gas Shutoff Valve Schedule" articles.
6. Operator: Square head or lug type with tamperproof feature where indicated.
7. Pressure Class: 125 psig.
8. Listing: Valves NPS 1 and smaller are to be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
9. Service: Suitable for natural-gas service with "WOG" indicated on valve body.

2.6 PRESSURE REGULATORS

A. General Requirements:

1. Single stage and suitable for natural gas.
2. Steel jacket and corrosion-resistant components.
3. Elevation compensator.
4. End Connections: Threaded for regulators NPS 2 and smaller; flanged for regulators NPS 2-1/2 and larger.

B. Appliance Pressure Regulators: Comply with ANSI Z21.18.

1. Body and Diaphragm Case: Die-cast aluminum.
2. Springs: Zinc-plated steel; interchangeable.
3. Diaphragm Plate: Zinc-plated steel.
4. Seat Disc: NBR.
5. Seal Plug: UV-stabilized, mineral-filled nylon.
6. Factory-Applied Finish: Minimum three-layer polyester and polyurethane paint finish.
7. Regulator may include vent limiting device, instead of vent connection, if approved by authorities having jurisdiction.
8. Maximum Inlet Pressure: 2 psig.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in for natural-gas piping system to verify actual locations of piping connections before equipment installation.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Close equipment shutoff valves before turning off natural gas to premises or piping section.

B. Inspect natural-gas piping in accordance with NFPA 54 to determine that natural-gas utilization devices are turned off in piping section affected.

C. Comply with NFPA 54 requirements for preventing accidental ignition.

3.3 INSTALLATION OF OUTDOOR PIPING

A. Comply with NFPA 54 for installation and purging of natural-gas piping.

B. Install fittings for changes in direction and branch connections.

3.4 INSTALLATION OF INDOOR PIPING

A. Comply with NFPA 54 for installation and purging of natural-gas piping.

B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.

C. Arrange for pipe spaces, chases, slots, sleeves, and openings in building structure during progress of construction, to allow for mechanical installations.

D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

E. Locate valves for easy access. Do not locate valves within return air plenums.

F. Install natural-gas piping at uniform grade of 2 percent down toward drip and sediment traps.

G. Install piping free of sags and bends.

H. Install fittings for changes in direction and branch connections.

I. Verify final equipment locations for roughing-in.

J. Comply with requirements in Sections specifying gas-fired appliances and equipment for roughing-in requirements.

K. Drips and Sediment Traps: Install drips at points where condensate may collect. Locate where accessible to permit cleaning and emptying. Do not install where condensate is subject to freezing.

1. Construct drips and sediment traps using tee fitting with bottom outlet plugged or capped. Use nipple a minimum length of 3 pipe diameters, but not less than 3 inches long and same size as connected pipe. Install with space below bottom of drip to remove plug or cap.

L. Extend relief vent connections for line regulators to outdoors and terminate with weatherproof vent cap.

M. Use eccentric reducer fittings to make reductions in pipe sizes. Install fittings with level side down.

N. Connect branch piping from top or side of horizontal piping.

O. Install unions in pipes NPS 2 and smaller, adjacent to each valve, at final connection to each piece of equipment. Unions are not required at flanged connections.

P. Do not use natural-gas piping as grounding electrode.

Q. Install strainer on inlet of each line-pressure regulator.

R. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 230500 "Common Work Results for HVAC."

S. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 230500 "Common Work Results for HVAC."

T. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 230500 "Common Work Results for HVAC."

3.5 INSTALLATION OF VALVES

A. Install manual gas shutoff valve for each gas appliance.

3.6 PIPING JOINT CONSTRUCTION

A. Ream ends of pipes and tubes and remove burrs.

B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

C. Threaded Joints:

1. Thread pipe with tapered pipe threads complying with ASME B1.20.1.
2. Cut threads full and clean using sharp dies.
3. Ream threaded pipe ends to remove burrs and restore full inside diameter of pipe.
4. Apply appropriate tape or thread compound to external pipe threads unless dryseal threading is specified.
5. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.

D. Welded Joints:

1. Construct joints in accordance with AWS D10.12/D10.12M, using qualified processes and welding operators.
2. Bevel plain ends of steel pipe.
3. Patch factory-applied protective coating as recommended by manufacturer at field welds and where damage to coating occurs during construction.

3.7 INSTALLATION OF HANGERS AND SUPPORTS

A. Comply with requirements in Section 230529 "Hangers and Supports for HVAC Piping and Equipment" for hangers, supports, and anchor devices.

B. Install hangers for steel piping, with maximum horizontal spacing and minimum rod diameters, to comply with MSS SP-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

C. Support horizontal piping within 12 inches of each fitting.

D. Support vertical runs of steel piping to comply with MSS SP-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.8 PIPING CONNECTIONS

A. Connect to utility's gas main according to utility's procedures and requirements.

B. Install natural-gas piping electrically continuous, and bonded to gas-appliance equipment grounding conductor of the circuit powering the appliance in accordance with NFPA 70.

C. Where installing piping adjacent to appliances, allow space for service and maintenance of appliances.

D. Connect piping to appliances using manual gas shutoff valves and unions. Install valve within 72 inches of each gas-fired appliance and equipment. Install union between valve and appliances or equipment.

3.9 LABELING AND IDENTIFICATION

A. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for piping and valve identification.

3.10 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. Test, inspect, and purge natural gas in accordance with NFPA 54 and authorities having jurisdiction.
2. Natural-gas piping will be considered defective if it does not pass tests and inspections.

B. Prepare test and inspection reports.

3.11 OUTDOOR PIPING SCHEDULE

A. Aboveground natural-gas piping is to be one of the following:

1. Steel pipe with malleable-iron fittings and threaded joints.
2. Steel pipe with wrought-steel fittings and welded joints.

3.12 INDOOR PIPING SCHEDULE FOR SYSTEM PRESSURES LESS THAN 0.5 PSIG (3.45 kPa)

A. Aboveground, distribution piping is to be one of the following:

1. Steel pipe with malleable-iron fittings and threaded joints.
2. Steel pipe with wrought-steel fittings and welded joints.

3.13 INDOOR PIPING SCHEDULE FOR SYSTEM PRESSURES MORE THAN 0.5 PSIG (3.45 kPa) AND LESS THAN 5 PSIG (34.5 kPa)

A. Aboveground, distribution piping is to be one of the following:

1. Steel pipe with malleable-iron fittings and threaded joints.
2. Steel pipe with steel welding fittings and welded joints.

3.14 ABOVEGROUND, MANUAL GAS SHUTOFF VALVE SCHEDULE

A. Distribution piping valves for pipe sizes NPS 2 and smaller are to be the following:

1. Two-piece, full-port, bronze ball valves with bronze trim.

B. Distribution piping valves for pipe sizes NPS 2-1/2 and larger are to be one of the following:

1. Two-piece, full-port, bronze ball valves with bronze trim.
2. Cast-iron, lubricated plug valve.

C. Valves in branch piping for single appliance are to be the following:

1. Two-piece, full-port, bronze ball valves with bronze trim.

END OF SECTION

SECTION 232113 – HYDRONIC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes pipe and fitting materials and joining methods for the following:

1. Copper tube and fittings.
2. Steel pipe and fittings.
3. Joining materials.
4. Transition fittings.
5. Dielectric fittings.
6. Bypass chemical feeder.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied. For each type of the following:

1. Pipe.
2. Fittings.
3. Joining materials.
4. Bypass chemical feeder.

C. Piping Schedule: Identify type of material fittings, and joining method to be used for each piping application and size range.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Piping layout, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Suspended ceiling components.
2. Other building services.
3. Structural members.

C. Qualification Data: For Installer.

D. Welding certificates.

E. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Steel Support Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

B. Pipe Welding: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code: Section IX.

1. Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation.
2. Certify that each welder has passed AWS qualification tests for welding processes involved and that certification is current.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Hydronic piping components and installation shall be capable of withstanding the following minimum working pressure and temperature unless otherwise indicated:

1. Glycol Heating, Hot-Water Heating, Glycol Cooling, and Chilled Water Piping: 100 psig at 200 deg F.
2. Makeup-Water Piping: 150 psig at 150 deg F.
3. Condensate-Drain Piping: 180 deg F.
4. Air-Vent Piping: 200 deg F.
5. Safety-Valve-Inlet and -Outlet Piping: Equal to the pressure of the piping system to which it is attached.

2.2 COPPER TUBE AND FITTINGS

A. Drawn-Temper Copper Tubing: ASTM B 88, Type L.

B. DWV Copper Tubing: ASTM B 306, Type DWV.

C. Wrought-Copper, Solder Joint Pressure Fittings, Unions, and Flanges: ASME B16.22.

D. Bronze Flanges: ASTM B16.24, Class 150, with solder joint ends.

E. Copper Unions:

1. MSS SP-123.
2. Cast-copper: Alloy, hexagonal stock body.
3. Ball-and-socket, metal-to-metal seating surfaces.

4. Solder-joint or threaded ends.

F. Pressure-Seal-Joint Fittings, Copper or Bronze - Domestic Water:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Apollo Valves; a part of Aalberts Integrated Piping Systems
b. Copper Press Brand; Merit Brass Company
c. Elkhart Brass Mfg. Co., Inc
d. Mueller Streamline Co.; a company of Mueller Industries
e. NIBCO INC.
f. Viega LLC

2. Source Limitations: Obtain pressure-seal-joint fittings, copper or bronze, from single manufacturer.
3. Housing: Copper.
4. O-Rings and Pipe Stops: EPDM.
5. Tools: Manufacturer's special tools.
6. Minimum 200 psig working-pressure rating at 250 deg F.

2.3 STEEL PIPE AND FITTINGS

A. Steel Pipe: ASTM A 53/A 53M, black steel with plain ends; welded and seamless, Grade B, and wall thickness as indicated in "Piping Applications" Article.

B. Malleable-Iron Threaded Fittings: ASME B16.3, Classes 150 and 300 as indicated in “Piping Applications” Article.

C. Malleable-Iron Unions: ASME B16.39; Classes 150, 250, and 300 as indicated in "Piping Applications" Article.

D. Cast-Iron Pipe Flanges and Flanged Fittings: ASME B16.1, Classes 25, 125, and 250; raised ground face, and bolt holes spot faced as indicated in "Piping Applications" Article.

E. Steel Pipe Nipples: ASTM A 733, made of same materials and wall thicknesses as pipe in which they are installed.

2.4 PLASTIC PIPE AND FITTINGS

A. PVC Plastic Pipe: ASTM D 1785, with wall thickness as indicated in "Piping Applications" Article.

1. PVC Plastic Pipe Fittings: Socket-type pipe fittings, ASTM D 2466 for Schedule 40 pipe.

2.5 JOINING MATERIALS

A. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.

1. ASME B16.21, nonmetallic, flat, asbestos free, 1/8-inch maximum thickness unless otherwise indicated.

a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.

B. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.

C. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.

D. Flux: ASTM B813, water flushable.

E. Welding Filler Metals: Comply with AWS D10.12M/D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

F. Gasket Material: Thickness, material, and type suitable for fluid to be handled and working temperatures and pressures.

2.6 DIELECTRIC FITTINGS

A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.

B. Dielectric Unions:

1. Description:

a. Standard: ASSE 1079.
b. Pressure Rating: 125 psig minimum at 180 deg F.
c. End Connections: Solder-joint copper alloy and threaded ferrous.

C. Dielectric Flanges:

1. Description:

a. Standard: ASSE 1079.
b. Factory-fabricated, bolted, companion-flange assembly.
c. Pressure Rating: 125 psig minimum at 180 deg F.
d. End Connections: Solder-joint copper alloy and threaded ferrous; threaded solder-joint copper alloy and threaded ferrous.

D. Dielectric-Flange Insulating Kits:

1. Description:

a. Nonconducting materials for field assembly of companion flanges.

b. Pressure Rating: 150 psig.
c. Gasket: Neoprene or phenolic.
d. Bolt Sleeves: Phenolic or polyethylene.
e. Washers: Phenolic with steel backing washers.

E. Dielectric Nipples:

1. Description:

a. Standard: IAPMO PS 66.
b. Electroplated steel nipple, complying with ASTM F 1545.
c. Pressure Rating: 300 psig at 225 deg F.
d. End Connections: Male threaded or grooved.
e. Lining: Inert and noncorrosive, propylene.

2.7 BYPASS CHEMICAL FEEDER

A. Description: Welded steel construction; 125-psig working pressure; 5-gal. capacity; with fill funnel and inlet, outlet, and drain valves.

1. Chemicals: Specially formulated, based on analysis of makeup water, to prevent accumulation of scale and corrosion in piping and connected equipment.

B. Propylene Glycol: Industrial grade with corrosion inhibitors and environmental-stabilizer additives for mixing with water in systems indicated to contain antifreeze or glycol solutions.

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS

A. Glycol heating, hot-water heating, glycol cooling, and chilled water piping, aboveground, NPS 2 and smaller, shall be any of the following:

1. Type L, drawn-temper copper tubing, wrought-copper fittings, and soldered joints.
2. Type L, drawing-temper copper tubing, copper pressure-seal-joint fitting and pressure-sealed joints.
3. Schedule 40, Grade B steel pipe; Class 150, malleable-iron fittings; cast-iron flanges and flange fittings; and threaded joints.

B. Glycol heating, hot-water heating, glycol cooling, and chilled water piping, aboveground, NPS 2-1/2 and larger, shall be the following:

1. Schedule 40 steel pipe, cast-iron flanges and flange fittings, and welded and flanged joints.

C. Makeup-water piping installed aboveground shall be any of the following:

1. Type L, drawn-temper copper tubing, wrought-copper fittings, and soldered joints.
2. Type L, drawing-temper copper tubing, copper pressure-seal-joint fitting and pressure-sealed joints.

D. Condensate-Drain Piping: Type DWV, drawn-temper copper tubing, wrought-copper fittings, and soldered joints or Schedule 40 PVC plastic pipe and fittings and solvent-welded joints.

E. Air-Vent Piping:

1. Inlet: Same as service where installed.
2. Outlet: Copper tubing with soldered joints.

F. Safety-Valve-Inlet and -Outlet Piping for Hot-Water Piping: Same materials and joining methods as for piping specified for the service in which safety valve is installed.

3.2 PIPING INSTALLATIONS

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.

B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

E. Install piping to permit valve servicing.

F. Install piping at indicated slopes.

G. Install piping free of sags and bends.

H. Install fittings for changes in direction and branch connections.

I. Install piping to allow application of insulation.

J. Select system components with pressure rating equal to or greater than system operating pressure.

K. Install groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.

L. Install drains, consisting of a tee fitting, NPS 3/4 ball valve, and short NPS 3/4 threaded nipple with cap, at low points in piping system mains and elsewhere as required for system drainage.

M. Install piping at a uniform grade of 0.2 percent upward in direction of flow.

N. Reduce pipe sizes using eccentric reducer fitting installed with level side up.

O. Install branch connections to mains using tee fittings in main pipe, with the branch connected to the bottom of the main pipe. For up-feed risers, connect the branch to the top of the main pipe.

P. Install valves according to the following:

1. Section 230523.12 "Ball Valves for HVAC Piping."
2. Section 230523.13 “Butterfly Valves for HVAC Piping.”
3. Section 230523.14 "Check Valves for HVAC Piping."
4. Section 230523.15 "Gate Valves for HVAC Piping."

Q. Install unions in piping, NPS 2 and smaller, adjacent to valves, at final connections of equipment, and elsewhere as indicated.

R. Install flanges in piping, NPS 2-1/2 and larger, at final connections of equipment and elsewhere as indicated.

S. Install shutoff valve immediately upstream of each dielectric fitting.

T. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for identifying piping.

U. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 230517 "Sleeves and Sleeve Seals for HVAC Piping."

V. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 230517 "Sleeves and Sleeve Seals for HVAC Piping."

W. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 230518 "Escutcheons for HVAC Piping."

3.3 DIELECTRIC FITTING INSTALLATION

A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.

B. Dielectric Fittings for NPS 2 and Smaller: Use dielectric nipples or unions.

C. Dielectric Fittings for NPS 2-1/2 to NPS 4: Use dielectric flange kits or nipples.

D. Dielectric Fittings for NPS 5 and Larger: Use dielectric flange kits.

3.4 HANGERS AND SUPPORTS

A. Comply with requirements in Section 230529 "Hangers and Supports for HVAC Piping and Equipment" for hanger, support, and anchor devices. Comply with the following requirements for maximum spacing of supports.

B. Comply with requirements in Section 230548.13 "Vibration Controls for HVAC" for vibration isolation requirements.

C. Install the following pipe attachments:

1. Adjustable steel clevis hangers for individual horizontal piping less than 20 feet long.

2. Adjustable roller hangers and spring hangers for individual horizontal piping 20 feet or longer.
3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal piping 20 feet or longer, supported on a trapeze.
4. Spring hangers to support vertical runs.
5. Provide copper-clad hangers and supports for hangers and supports in direct contact with copper pipe.
6. On plastic pipe, install pads or cushions on bearing surfaces to prevent hanger from scratching pipe.

D. Install hangers for steel piping with the following maximum spacing and minimum rod sizes:

1. NPS 3/4: Maximum span, 7 feet.
2. NPS 1: Maximum span, 7 feet.
3. NPS 1-1/2: Maximum span, 9 feet.
4. NPS 2: Maximum span, 10 feet.
5. NPS 2-1/2: Maximum span, 11 feet.
6. NPS 3 and Larger: Maximum span, 12 feet.

E. Install hangers for drawn-temper copper piping with the following maximum spacing and minimum rod sizes:

1. NPS 3/4: Maximum span, 5 feet; minimum rod size, 1/4 inch.
2. NPS 1: Maximum span, 6 feet; minimum rod size, 1/4 inch.
3. NPS 1-1/4Maximum span, 7 feet; minimum rod size, 3/8 inch.
4. NPS 1-1/2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
5. NPS 2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
6. NPS 2-1/2: Maximum span, 9 feet; minimum rod size, 3/8 inch.
7. NPS 3 and Larger: Maximum span, 10 feet; minimum rod size, 3/8 inch.

F. Plastic Piping Hanger Spacing: Space hangers according to pipe manufacturer's written instructions for service conditions. Avoid point loading. Space and install hangers with the fewest practical rigid anchor points.

G. Support vertical runs at roof, at each floor, and at 10-foot intervals between floors.

3.5 PIPE JOINT CONSTRUCTION

A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.

B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

C. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.

D. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:

1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.

E. Welded Joints: Construct joints according to AWS D10.12M/D10.12, using qualified processes and welding operators according to "Quality Assurance" Article.

F. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.

G. Pressure-Sealed Joints for Copper Tubing: Join copper tube and pressure seal-fittings with tools and procedure recommended by pressure seal-fitting manufacturer. Leave insertion marks on pipe after assembly.

H. Plastic Piping Solvent-Cemented Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
2. PVC Nonpressure Piping: Join according to ASTM D 2855.

3.6 TERMINAL EQUIPMENT CONNECTIONS

A. Sizes for supply and return piping connections shall be the same as or larger than equipment connections.

B. Install control valves in accessible locations close to connected equipment.

C. Install bypass piping with globe valve around control valve. If parallel control valves are installed, only one bypass is required.

D. Install ports for pressure gages and thermometers at coil and equipment inlet and outlet connections. Comply with requirements in Section 230519 "Meters and Gages for HVAC Piping."

3.7 CHEMICAL TREATMENT

A. Perform an analysis of makeup water to determine type and quantities of chemical treatment needed to keep system free of scale, corrosion, and fouling, and to sustain the following water characteristics:

1. pH: 9.0 to 10.5.
2. "P" Alkalinity: 100 to 500 ppm.
3. Boron: 100 to 200 ppm.
4. Soluble Copper: Maximum of 0.20 ppm.
5. Total Suspended Solids: Maximum of 10 ppm.
6. Ammonia: Maximum of 20 ppm.

B. Install bypass chemical feeders in each hydronic system where indicated.

1. Install in upright position with top of funnel not more than 48 inches above the floor.
2. Install feeder in minimum NPS 3/4 bypass line, from main with full-size, full-port, ball valve in the main between bypass connections.
3. Install NPS 3/4 pipe from chemical feeder drain to nearest equipment drain and include a full-size, full-port, ball valve.

C. Fill system with fresh water and add liquid alkaline compound with emulsifying agents and detergents to remove grease and petroleum products from piping. Circulate solution for a minimum of 24 hours, drain, clean strainer screens, and refill with fresh water.

D. Add initial chemical treatment and maintain water quality in ranges noted above for the first year of operation.

E. Fill systems that have antifreeze or glycol solutions with the following concentrations:

1. Glycol Heating-Water Piping: Minimum of 35 percent propylene glycol.
2. Glycol Cooling Water Piping: Minimum of 35 percent propylene glycol.

3.8 FIELD QUALITY CONTROL

A. Prepare hydronic piping according to ASME B31.9 and as follows:

1. Leave joints, including welds, uninsulated and exposed for examination during test.
2. Provide temporary restraints for expansion joints that cannot sustain reactions due to test pressure. If temporary restraints are impractical, isolate expansion joints from testing.
3. Flush hydronic piping systems with clean water; then remove and clean or replace strainer screens.
4. Isolate equipment from piping. If a valve is used to isolate equipment, its closure shall be capable of sealing against test pressure without damage to valve. Install blinds in flanged joints to isolate equipment.
5. Install safety valve, set at a pressure no more than one-third higher than test pressure, to protect against damage by expanding liquid or other source of overpressure during test.

B. Perform the following tests on hydronic piping:

1. Use ambient temperature water as a testing medium unless there is risk of damage due to freezing. Another liquid that is safe for workers and compatible with piping may be used.
2. While filling system, use vents installed at high points of system to release air. Use drains installed at low points for complete draining of test liquid.
3. Isolate expansion tanks and determine that hydronic system is full of water.
4. Subject piping system to hydrostatic test pressure that is not less than 1.5 times the system's working pressure. Test pressure shall not exceed maximum pressure for any vessel, pump, valve, or other component in system under test. Verify that stress due to pressure at bottom of vertical runs does not exceed 90 percent of specified minimum yield strength or 1.7 times the "SE" value in Appendix A in ASME B31.9, "Building Services Piping."
5. After hydrostatic test pressure has been applied for at least 10 minutes, examine piping, joints, and connections for leakage. Eliminate leaks by tightening, repairing, or replacing components, and repeat hydrostatic test until there are no leaks.
6. Prepare written report of testing.

C. Perform the following before operating the system:

1. Open manual valves fully.
2. Inspect pumps for proper rotation.
3. Set makeup pressure-reducing valves for required system pressure.
4. Inspect air vents at high points of system and determine if all are installed and operating freely (automatic type), or bleed air completely (manual type).
5. Set temperature controls so all coils are calling for full flow.
6. Inspect and set operating temperatures of hydronic equipment, such as boilers, chillers, cooling towers, to specified values.
7. Verify lubrication of motors and bearings.

END OF SECTION

SECTION 232116 – HYDRONIC PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes the following:

1. Hydronic specialty valves.
2. Air-control devices.
3. Strainers.
4. Connectors.
5. Packaged glycol make-up unit.

B. Related Requirements:

1. Section 230523.12 "Ball Valves for HVAC Piping" for specification and installation requirements for ball valves common to most piping systems.
2. Section 230523.13 “Butterfly Valves for HVAC Piping” for specification and installation requirements for butterfly valves common to most piping systems.
3. Section 230523.15 "Gate Valves for HVAC Piping" for specification and installation requirements for gate valves common to most piping systems.
4. Section 230923.11 "Control Valves" for automatic control valve and sensor specifications, installation requirements, and locations.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of the following. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Hydronic Specialty Valves: Include flow and pressure drop curves based on manufacturer's testing for calibrated-orifice balancing valves and automatic flow-control valves.
2. Air-control devices.
3. Strainers.
4. Connectors.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For air-control devices, hydronic specialties, and special-duty valves to include in emergency, operation, and maintenance manuals.

1.5 MAINTENANCE SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Differential Pressure Meter: For each type of balancing valve and automatic flow control valve, include flowmeter, probes, hoses, flow charts, and carrying case.

1.6 QUALITY ASSURANCE

A. Pipe Welding: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code: Section IX.

1. Safety valves and pressure vessels shall bear the appropriate ASME label. Fabricate and stamp air separators and expansion tanks to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.

PART 2 - PRODUCTS

2.1 HYDRONIC SPECIALTY VALVES

A. Bronze, Calibrated-Orifice, Balancing Valves:

1. Body: Bronze, ball or plug type with calibrated orifice or venturi.
2. Ball: Brass or stainless steel.
3. Plug: Resin.
4. Seat: PTFE.
5. End Connections: Threaded or socket.
6. Pressure Gage Connections: Integral seals for portable differential pressure meter.
7. Handle Style: Lever, with memory stop to retain set position.
8. CWP Rating: Minimum 125 psig.
9. Maximum Operating Temperature: 250 deg F.

B. Cast-Iron or Steel, Calibrated-Orifice, Balancing Valves:

1. Body: Cast-iron or steel body, ball, plug, or globe pattern with calibrated orifice or venturi.
2. Ball: Brass or stainless steel.
3. Stem Seals: EPDM O-rings.
4. Disc: Glass and carbon-filled PTFE.
5. Seat: PTFE.

6. End Connections: Flanged or grooved.
7. Pressure Gage Connections: Integral seals for portable differential pressure meter.
8. Handle Style: Lever, with memory stop to retain set position.
9. CWP Rating: Minimum 125 psig.
10. Maximum Operating Temperature: 250 deg F.

C. Diaphragm-Operated, Pressure-Reducing Valves: ASME labeled.

1. Body: Bronze or brass.
2. Disc: Glass and carbon-filled PTFE.
3. Seat: Brass.
4. Stem Seals: EPDM O-rings.
5. Diaphragm: EPT.
6. Low inlet-pressure check valve.
7. Inlet Strainer: Removable without system shutdown.
8. Valve Seat and Stem: Noncorrosive.
9. Valve Size, Capacity, and Operating Pressure: Selected to suit system in which installed, with operating pressure and capacity factory set and field adjustable.

D. Diaphragm-Operated Safety Valves: ASME labeled.

1. Body: Bronze or brass.
2. Disc: Glass and carbon-filled PTFE.
3. Seat: Brass.
4. Stem Seals: EPDM O-rings.
5. Diaphragm: EPT.
6. Wetted, Internal Work Parts: Brass and rubber.
7. Inlet Strainer: Removable without system shutdown.
8. Valve Seat and Stem: Noncorrosive.
9. Valve Size, Capacity, and Operating Pressure: Comply with ASME Boiler and Pressure Vessel Code: Section IV, and selected to suit system in which installed, with operating pressure and capacity factory set and field adjustable.

2.2 AIR-CONTROL DEVICES

A. Manual Air Vents:

1. Body: Bronze.
2. Internal Parts: Nonferrous.
3. Operator: Screwdriver or thumbscrew.
4. Inlet Connection: NPS 1/2.
5. Discharge Connection: NPS 1/8.
6. CWP Rating: 150 psig.
7. Maximum Operating Temperature: 225 deg F.

B. Automatic Air Vents:

1. Body: Bronze or cast iron.
2. Internal Parts: Nonferrous.
3. Operator: Noncorrosive metal float.
4. Inlet Connection: NPS 1/2.
5. Discharge Connection: NPS 1/4.

6. CWP Rating: 150 psig.
7. Maximum Operating Temperature: 240 deg F.

C. Bladder-Type Expansion Tanks:

1. Tank: Welded steel, rated for 125-psig working pressure and 375 deg F maximum operating temperature. Factory test after taps are fabricated and supports installed and are labeled according to ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.
2. Bladder: Securely sealed into tank to separate air charge from system water to maintain required expansion capacity.
3. Air-Charge Fittings: Schrader valve, stainless steel with EPDM seats.

D. Tangential-Type Air Separators:

1. Tank: Welded steel; ASME constructed and labeled for 125-psig minimum working pressure and 375 deg F maximum operating temperature.
2. Air Collector Tube: Perforated stainless steel, constructed to direct released air into expansion tank.
3. Tangential Inlet and Outlet Connections: Threaded for NPS 2 and smaller; flanged connections for NPS 2-1/2 and larger.
4. Blowdown Connection: Threaded.
5. Size: Match system flow capacity.

2.3 STRAINERS

A. Y-Pattern Strainers:

1. Body: ASTM A 126, Class B, cast iron with bolted cover and bottom drain connection.
2. End Connections: Threaded ends for NPS 2 and smaller; flanged ends for NPS 2-1/2 and larger.
3. Strainer Screen: Stainless-steel, mesh strainer, or perforated stainless-steel basket.
4. CWP Rating: 125 psig.

B. Magnetic Strainers:

1. Body: 304L stainless steel with bolted cover and bottom drain connection.
2. End Connections: Flanged, ASME B16.5 Class 150.
3. Magnets: High power NdFeB
4. Pocket Sleeves: 304L stainless steel.
5. CWP Rating: 125 psig.
6. Provide ASME approved basis-of-design filter, Grundfoss MagFilter, or approved equivalent.

2.4 CONNECTORS

A. Stainless-Steel Bellow, Flexible Connectors:

1. Body: Stainless-steel bellows with woven, flexible, bronze, wire-reinforcing protective jacket.
2. End Connections: Threaded or flanged to match equipment connected.
3. Performance: Capable of 3/4-inch misalignment.

4. CWP Rating: 150 psig.
5. Maximum Operating Temperature: 250 deg F.

2.5 PACKAGED GLYCOL MAKE-UP UNIT

A. Duplex packaged automatic glycol solution make up unit to provide make-up water to provide make-up water to two separate systems from common tank. The package shall consist of a base, 55 gallon polyethylene reservoir with removable lid and visible solution level scale in gallons and liters, y-strainer, isolation valve, duplex pumps, open drip-proof motor, pump isolation, check and balance valve, discharge pressure gage, motor contactor, pressure control and necessary interconnecting piping to service two separate connections to two separate systems. Pump shall start based on falling pressure. Green light shall indicate power supplied to unit. Unit shall include ¾ inch piping connection, low level cutout with red indicator light and 110 V contact for alarm indication, to stop running pump during low level condition.

PART 3 - EXECUTION

3.1 VALVE APPLICATIONS

A. Install shutoff-duty valves at each branch connection to supply mains and at supply connection to each piece of equipment.

B. Install calibrated-orifice, balancing valves at each branch connection to return main.

C. Install calibrated-orifice, balancing valves in the return pipe of each heating or cooling terminal.

D. Install check valves at each pump discharge and elsewhere as required to control flow direction.

E. Install safety valves at hot-water generators and elsewhere as required by ASME Boiler and Pressure Vessel Code. Install drip-pan elbow on safety-valve outlet and pipe without valves to the outdoors; pipe drain to nearest floor drain or as indicated on Drawings. Comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1, for installation requirements.

F. Install pressure-reducing valves at makeup-water connection to regulate system fill pressure for hydronic systems without glycol.

3.2 HYDRONIC SPECIALTIES INSTALLATION

A. Install manual air vents at high points in piping, at heat-transfer coils, and elsewhere as required for system air venting.

B. Install automatic air vents at high points of system piping in mechanical equipment rooms only. Install manual vents at heat-transfer coils and elsewhere as required for air venting.

C. Install piping from boiler air outlet, air separator, or air purger to expansion tank with a 2 percent upward slope toward tank.

D. Install tangential air separator in pump suction. Install blowdown piping with gate or full-port ball valve; extend full size to nearest floor drain.

E. Install expansion tanks on the floor. Vent and purge air from hydronic system, and ensure that tank is properly charged with air to suit system Project requirements.

END OF SECTION

SECTION 232123 – HYDRONIC PUMPS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Close-coupled, in-line centrifugal pumps.
2. Separately coupled, base-mounted, end-suction centrifugal pumps.
3. Automatic condensate pump units.

1.3 DEFINITIONS

A. Buna-N: Nitrile rubber.

B. EPT: Ethylene propylene terpolymer.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of pump. Include certified performance curves and rated capacities, operating characteristics, furnished specialties, final impeller dimensions, and accessories for each type of product indicated. Indicate pump's operating point on curves. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

C. Shop Drawings: For each pump.

1. Show pump layout and connections.
2. Include setting drawings with templates for installing foundation and anchor bolts and other anchorages.
3. Include diagrams for power, signal, and control wiring.

D. Provide equipment cut sheets to General Contractor for inclusion in project coordination drawings. Include all equipment dimensions, noting manufacturer's clearance requirements, as well as location and sizes of all equipment connections.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Warranty: Sample of special warranty.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For pumps to include in emergency, operation, and maintenance manuals.

1.7 WARRANTY

A. Special Warranty: Manufacturer’s standard form in which manufacturer agrees to repair or replace components of centrifugal pumps that fail in material or workmanship within specified warranty period.

1. Extended Warranty Period:

a. For Parts: Two years.
b. For Labor: Two years.

PART 2 - PRODUCTS

2.1 CLOSE-COUPLED, IN-LINE CENTRIFUGAL PUMPS

A. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by the following:

1. Grundfos Pumps Corporation.

B. Description: Factory-assembled and -tested, centrifugal, overhung-impeller, close-coupled, in-line pump as defined in HI 1.1-1.2 and HI 1.3; designed for installation with pump and motor shafts mounted horizontally or vertically.

C. Capacities and Characteristics: As scheduled on Drawings.

D. Pump Construction:

1. Casing: Radially split, cast iron, with threaded gage tappings at inlet and outlet, replaceable bronze wear rings, and threaded companion-flange connections.
2. Impeller: ASTM B 584, cast bronze; statically and dynamically balanced, keyed to shaft, and secured with a locking cap screw. For constant-speed pumps, trim impeller to match specified performance.
3. Pump Shaft: Steel, with copper-alloy shaft sleeve.
4. Pump Bearings: Permanently lubricated ball bearings.

E. Motor: Single speed and rigidly mounted to pump casing.

1. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
2. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."

a. Enclosure: Open, dripproof.
b. Motor Bearings: Permanently lubricated ball bearings.
c. Efficiency: Premium efficient.

2.2 SEPARATELY COUPLED, BASE-MOUNTED, END-SUCTION CENTRIFUGAL PUMPS

A. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by the following:

1. Grundfos Pumps Corporation.

B. Description: Factory-assembled and -tested, centrifugal, overhung-impeller, separately coupled, end-suction pump as defined in HI 1.1-1.2 and HI 1.3; designed for base mounting, with pump and motor shafts horizontal.

C. Capacities and Characteristics: As scheduled on Drawings.

D. Pump Construction:

1. Casing: Radially split, cast iron, with replaceable bronze wear rings, threaded gage tappings at inlet and outlet, drain plug at bottom and air vent at top of volute, and flanged connections. Provide integral mount on volute to support the casing, and provide attached piping to allow removal and replacement of impeller without disconnecting piping or requiring the realignment of pump and motor shaft.
2. Impeller: ASTM B 584, cast bronze; statically and dynamically balanced, keyed to shaft, and secured with a locking cap screw. For pumps not frequency-drive controlled, trim impeller to match specified performance.
3. Pump Shaft: Steel, with copper-alloy shaft sleeve.
4. Pump Bearings: Grease-lubricated ball bearings in cast-iron housing with grease fittings.

E. Shaft Coupling: Molded-rubber insert and interlocking spider capable of absorbing vibration. Couplings shall be drop-out type to allow disassembly and removal without removing pump shaft or motor.

F. Coupling Guard: Dual rated; ANSI B15.1, Section 8; OSHA 1910.219 approved; steel; removable; attached to mounting frame.

G. Mounting Frame: Welded-steel frame and cross members, factory fabricated from ASTM A 36/A 36M channels and angles. Fabricate to mount pump casing, coupling guard, and motor.

H. Motor: Single speed, secured to mounting frame, with adjustable alignment.

1. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
2. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."

    a. Enclosure: Open, dripproof.
    b. Motor Bearings: Permanently lubricated ball bearings.
    c. Efficiency: Premium efficient.

2.3 AUTOMATIC CONDENSATE PUMP UNITS

A. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:

1. Beckett Corporation.
2. Hartell Pumps; Milton Roy.
3. Little Giant Pump Co.
4. Mepco, LLC.

B. Description: Packaged units with corrosion-resistant pump, plastic tank with cover, and automatic controls. Include factory- or field-installed check valve and a 72-inch- minimum, electrical power cord with plug.

C. Capacities and Characteristics: As scheduled on Drawings.

2.4 PUMP SPECIALTY FITTINGS

A. Suction Diffuser:

1. Angle pattern.
2. 175-psig pressure rating, cast or ductile-iron body and end cap, pump-inlet fitting.
3. Bronze startup and bronze or stainless-steel permanent strainers.
4. Bronze or stainless-steel straightening vanes.
5. Drain plug.
6. Factory-fabricated support.

B. Triple-Duty Valve: Not allowed.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine equipment foundations and anchor-bolt locations for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for piping systems to verify actual locations of piping connections before pump installation.

C. Examine foundations and inertia bases for suitable conditions where pumps are to be installed.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PUMP INSTALLATION

A. Comply with HI 1.4 and HI 2.4.

B. Install pumps to provide access for periodic maintenance including removing motors, impellers, couplings, and accessories.

C. Independently support pumps and piping so weight of piping is not supported by pumps and weight of pumps is not supported by piping.

D. Automatic Condensate Pump Units: Install units for collecting condensate and extend to open drain.

E. Equipment Mounting:

1. Install base-mounted pumps on cast-in-place concrete equipment bases. Comply with requirements for equipment bases and foundations specified in Section 033000 "Cast-in-Place Concrete."
2. Comply with requirements for vibration isolation devices specified in Section 230548.13 "Vibration Controls for HVAC."

F. Equipment Mounting: Install in-line pumps with continuous-thread hanger rods and spring hangers with vertical-limit stop of size required to support weight of in-line pumps.

1. Comply with requirements for hangers and supports specified in Section 230529 "Hangers and Supports for HVAC Piping and Equipment."

3.3 ALIGNMENT

A. Perform alignment service.

B. Comply with requirements in Hydronics Institute standards for alignment of pump and motor shaft. Add shims to the motor feet and bolt motor to base frame. Do not use grout between motor feet and base frame.

C. Comply with pump and coupling manufacturers' written instructions.

D. After alignment is correct, tighten foundation bolts evenly but not too firmly. Completely fill baseplate with nonshrink, nonmetallic grout while metal blocks and shims or wedges are in place. After grout has cured, fully tighten foundation bolts.

3.4 CONNECTIONS

A. Where installing piping adjacent to pump, allow space for service and maintenance.

B. Connect piping to pumps. Install valves that are same size as piping connected to pumps.

C. Install suction and discharge pipe sizes equal to or greater than diameter of pump nozzles.

D. Install check, shut-off, and balancing valves with memory stop on discharge side of pumps.

E. Install suction diffuser, Y-type strainer, and shutoff valve on suction side of pumps.

F. Install flexible connectors on suction and discharge sides of base-mounted pumps between pump casing and valves.

G. Install pressure gages on pump suction and discharge or at integral pressure-gage tapping, or install single gage with multiple-input selector valves.

H. Install check valve and gate or ball valve on each condensate pump unit discharge.

I. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."

J. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

3.5 STARTUP SERVICE

A. Engage a factory-authorized service representative to perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.
2. Check piping connections for tightness.
3. Clean strainers on suction piping.
4. Perform the following startup checks for each pump before starting:

    a. Verify bearing lubrication.
    b. Verify that pump is free to rotate by hand and that pump for handling hot liquid is free to rotate with pump hot and cold. If pump is bound or drags, do not operate until cause of trouble is determined and corrected.
    c. Verify that pump is rotating in the correct direction.

5. Prime pump by opening suction valves and closing drains, and prepare pump for operation.
6. Start motor.
7. Open discharge valve slowly.

3.6 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain hydronic pumps. Provide one hour of training for each pump provided.

END OF SECTION

SECTION 233113 - METAL DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Single-wall rectangular ducts and fittings.
2. Single-wall round ducts and fittings.
3. Sheet metal materials.
4. Duct liner.
5. Sealants and gaskets.
6. Hangers and supports.

B. Related Sections:

1. Section 230593 "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing requirements for metal ducts.
2. Section 233300 "Air Duct Accessories" for dampers, duct-mounting access doors and panels, turning vanes, and flexible ducts.

1.3 PERFORMANCE REQUIREMENTS

A. Delegated Duct Design: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" and performance requirements and design criteria indicted in "Duct Schedule" Article.

B. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied. For each type of the following products:

1. Sealants and gaskets.

2. Adhesives.
3. Duct liner.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Duct installation in congested spaces, indicating coordination with general construction, building components, and other building services. Indicate proposed changes to duct layout.
2. Suspended ceiling components.
3. Structural members to which duct will be attached.
4. Size and location of initial access modules for acoustical tile.
5. Penetrations of smoke barriers and fire-rated construction.
6. Items penetrating finished ceiling including the following:

    a. Luminaires.
    b. Air outlets and inlets.
    c. Speakers.
    d. Sprinklers.
    e. Access panels.
    f. Perimeter moldings.

C. Delegated-Design Submittal:

1. Sheet metal thicknesses.
2. Joint and seam construction and sealing.
3. Reinforcement details and spacing.
4. Materials, fabrication, assembly, and spacing of hangers and supports.

D. Field quality-control reports.

1.6 QUALITY ASSURANCE

A. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and System Start-up."

B. ASHRAE/IES Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6.4.4 - "HVAC System Construction and Insulation."

PART 2 - PRODUCTS

2.1 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS

A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.

B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

D. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 4, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.2 SINGLE-WALL ROUND DUCTS AND FITTINGS

A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Ductmate Industries, Inc.
b. Lindab Inc.
c. McGill AirFlow LLC.
d. SEMCO LLC.
e. Sheet Metal Connectors, Inc.
f. Spiral Manufacturing Co., Inc.
g. Stamped Fittings Inc.

B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

1. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.

C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-2, "Round Duct Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

1. Fabricate round ducts larger than 90 inches in diameter with butt-welded longitudinal seams.

D. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.3 SHEET METAL MATERIALS

A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

B. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.

1. Galvanized Coating Designation: G90.
2. Finishes for Surfaces Exposed to View: Mill phosphatized.

C. Reinforcement Shapes and Plates: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.

1. Where black- and galvanized-steel shapes and plates are used to reinforce aluminum ducts, isolate the different metals with butyl rubber, neoprene, or EPDM gasket materials.

D. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.4 DUCT LINER

A. Flexible Elastomeric Duct Liner: Preformed, cellular, closed-cell, sheet materials complying with ASTM C534/C534M, Type II, Grade 1; and with NFPA 90A or NFPA 90B.

1. Source Limitations: Obtain flexible elastomeric duct liner from single manufacturer.
2. Surface-Burning Characteristics: Maximum flame-spread index of 25 and maximum smoke-developed index of 50 when tested in accordance with UL 723; certified by an NRTL.
3. Liner Adhesive: As recommended by insulation manufacturer and complying with NFPA 90A or NFPA 90B.

a. Adhesive: As recommended by adhesive manufacturer and with a VOC content of 80 g/L or less.

B. Shop Application of Duct Liner: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 7-11, "Flexible Duct Liner Installation."
1. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
3. Butt transverse joints without gaps, and coat joint with adhesive.
4. Fold and compress liner in corners of rectangular ducts or cut and fit to ensure butted-edge overlapping.
5. Do not apply liner in rectangular ducts with longitudinal joints, except at corners of ducts, unless duct size and dimensions of standard liner make longitudinal joints necessary.

2.5 SEALANT AND GASKETS

A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.

B. Water-Based Joint and Seam Sealant:

1. Application Method: Brush on.
2. Solids Content: Minimum 65 percent.
3. Shore A Hardness: Minimum 20.
4. Water resistant.
5. Mold and mildew resistant.
6. VOC: Maximum 75 g/L (less water).
7. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
8. Service: Indoor or outdoor.
9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.

C. Flanged Joint Sealant: Comply with ASTM C 920.

1. General: Single-component, acid-curing, silicone, elastomeric.
2. Type: S.
3. Grade: NS.
4. Class: 25.
5. Use: O.
6. Sealant shall have a VOC content of 420 g/L or less.

D. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.

E. Round Duct Joint O-Ring Seals:

1. Seal shall provide maximum leakage class of 3 cfm/100 sq. ft. at 1-inch wg and shall be rated for10-inch wg static-pressure class, positive or negative.
2. EPDM O-ring to seal in concave bead in coupling or fitting spigot.

3. Double-lipped, EPDM O-ring seal, mechanically fastened to factory-fabricated couplings and fitting spigots.

2.6 HANGERS AND SUPPORTS

A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.

B. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."

C. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A 603.

D. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.

E. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.

F. Trapeze and Riser Supports:

1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.

PART 3 - EXECUTION

3.1 DUCT INSTALLATION

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and Coordination Drawings.

B. Install ducts according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" unless otherwise indicated.

C. Install ducts in maximum practical lengths.

D. Install ducts with fewest possible joints.

E. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.

F. Unless otherwise indicated, install ducts vertically and horizontally, and parallel and perpendicular to building lines.

G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.

H. Install ducts with a clearance of 1 inch, plus allowance for insulation thickness.

I. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.

J. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.

K. Where ducts pass through fire-rated interior partitions and exterior walls, install fire dampers. Comply with requirements in Section 233300 "Air Duct Accessories" for fire dampers.

L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials. Comply with SMACNA's "IAQ Guidelines for Occupied Buildings Under Construction," Appendix G, "Duct Cleanliness for New Construction Guidelines."

3.2 INSTALLATION OF EXPOSED DUCTWORK

A. Protect ducts exposed in finished spaces from being dented, scratched, or damaged.

B. Trim duct sealants flush with metal. Create a smooth and uniform exposed bead. Do not use two-part tape sealing system.

C. Maintain consistency, symmetry, and uniformity in the arrangement and fabrication of fittings, hangers and supports, duct accessories, and air outlets.

D. Repair or replace damaged sections and finished work that does not comply with these requirements.

3.3 REQUIREMENTS FOR DUCTWORK EXPOSED TO WEATHER

A. All external joints are to be welded or have secure watertight mechanical connections. Seal all openings to provide weatherproof construction.

B. Construct ductwork to resist external loads of wind, snow, ice, and other effects of weather. Provide necessary supporting structures.

C. Single Wall:

1. Ductwork is to be galvanized steel.
2. Where ducts have external insulation, provide weatherproof aluminum or self-adhesive asphaltic jacket. See Section 230713 "Duct Insulation."

3.4 DUCT SEALING

A. Seal ducts for duct static-pressure, seal classes, and leakage classes specified in "Duct Schedule" Article according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

3.5 HANGER AND SUPPORT INSTALLATION

A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 5, "Hangers and Supports."

B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.

1. Where practical, install concrete inserts before placing concrete.
2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.

C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.

D. Hangers Exposed to View: Threaded rod and angle or channel supports.

E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet.

F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

3.6 CONNECTIONS

A. Make connections to equipment with flexible connectors complying with Section 233300 "Air Duct Accessories."

B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

3.7 PAINTING

A. Paint interior of metal ducts that are visible through registers and grilles and that do not have duct liner. Apply one coat of flat, black, latex paint over a compatible galvanized-steel primer. Paint materials and application requirements are specified in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."

3.8 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Duct System Cleanliness Tests:

1. Visually inspect duct system to ensure that no visible contaminants are present.
2. Test sections of metal duct system, chosen randomly by Owner, for cleanliness according to "Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems."

    a. Acceptable Cleanliness Level: Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm.

C. Duct system will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

3.9 DUCT CLEANING

A. Clean new duct system(s) which do not pass the duct system cleanliness test before testing, adjusting, and balancing.

B. Use service openings for entry and inspection.

1. Create new openings and install access panels appropriate for duct static-pressure class if required for cleaning access. Provide insulated panels for insulated or lined duct. Patch insulation and liner as recommended by duct liner manufacturer. Comply with Section 233300 "Air Duct Accessories" for access panels and doors.
2. Disconnect and reconnect flexible ducts as needed for cleaning and inspection.
3. Remove and reinstall ceiling to gain access during the cleaning process.

C. Particulate Collection and Odor Control:

1. When venting vacuuming system inside the building, use HEPA filtration with 99.97 percent collection efficiency for 0.3-micron-size (or larger) particles.
2. When venting vacuuming system to outdoors, use filter to collect debris removed from HVAC system, and locate exhaust downwind and away from air intakes and other points of entry into building.

D. Clean the following components by removing surface contaminants and deposits:

1. Air outlets and inlets (registers, grilles, and diffusers).
2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.
3. Air-handling unit internal surfaces and components including mixing box, coil section, air wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.
4. Coils and related components.
5. Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and mechanical equipment rooms.
6. Supply-air ducts, dampers, actuators, and turning vanes.
7. Dedicated exhaust and ventilation components and makeup air systems.

E. Mechanical Cleaning Methodology:

1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.
2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
4. Clean coils and coil drain pans according to NADCA 1992. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.
5. Provide drainage and cleanup for wash-down procedures.
6. Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus is present. Apply antimicrobial agents according to manufacturer's written instructions after removal of surface deposits and debris.

3.10 START UP

A. Air Balance: Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC."

3.11 DUCT SCHEDULE

A. Fabricate ducts with galvanized sheet steel except as otherwise indicated and as follows:

B. Supply and Outside-Air Ducts:

1. Ducts Connected to Terminal Units:

    a. Pressure Class: Positive 2-inch wg.
    b. Minimum SMACNA Seal Class: A.
    c. SMACNA Leakage Class for Rectangular: 24.
    d. SMACNA Leakage Class for Round: 12.

2. Ducts Connected to Variable-Air-Volume Air-Handling Units:

    a. Pressure Class: Positive 4-inch wg.
    b. Minimum SMACNA Seal Class: A.
    c. SMACNA Leakage Class for Rectangular: 6.
    d. SMACNA Leakage Class for Round and Flat Oval: 6.

C. Return Ducts:

1. Ducts Connected to Terminal Units:

    a. Pressure Class: Positive or negative 2-inch wg.
    b. Minimum SMACNA Seal Class: A.
    c. SMACNA Leakage Class for Rectangular: 24.
    d. SMACNA Leakage Class for Round and Flat Oval: 12.

2. Ducts Connected to Air-Handling Units:

a. Pressure Class: Positive or negative 3-inch wg.
b. Minimum SMACNA Seal Class: A.
c. SMACNA Leakage Class for Rectangular: 24.
d. SMACNA Leakage Class for Round and Flat Oval: 12.

D. Exhaust Ducts:

1. Ducts Connected to Fans Exhausting (ASHRAE 62.1, Class 1 and 2) Air:

a. Pressure Class: Negative 2-inch wg.
b. Minimum SMACNA Seal Class: B if negative pressure, and A if positive pressure.
c. SMACNA Leakage Class for Rectangular: 12.
d. SMACNA Leakage Class for Round: 6.

2. Ducts Connected to Air-Handling Units:

a. Pressure Class: Positive or negative 3-inch wg.
b. Minimum SMACNA Seal Class: B if negative pressure, and A if positive pressure.
c. SMACNA Leakage Class for Rectangular: 12.
d. SMACNA Leakage Class for Round and Flat Oval: 6.

E. Intermediate Reinforcement:

1. Galvanized-Steel Ducts: Galvanized steel.

a. Exposed to Airstream: Match duct material.
b. Not Exposed to Airstream: Match duct material.

F. Liner:

1. Terminal Unit Return Plenum and Transfer Ducts: Flexible elastomeric, 1-inch thick.

G. Elbow Configuration:

1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-2, "Rectangular Elbows."

a. Radius Type RE 1 with minimum 1.5 radius-to-diameter ratio.
b. Radius Type RE 3 with minimum 1.0 radius-to-diameter ratio and two vanes.
c. Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-3, "Vanes and Vane Runners," and Figure 4-4, "Vane Support in Elbows."

2. Round Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-4, "Round Duct Elbows."

a. Minimum Radius-to-Diameter Ratio and Elbow Segments: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 3-1, "Mitered Elbows." Elbows with less than 90-degree change of direction have proportionately fewer segments.

1) Radius-to Diameter Ratio: 1.5.

b. Round Elbows, 12 Inches and Smaller in Diameter: Stamped or pleated.
c. Round Elbows, 14 Inches and Larger in Diameter: Standing seam.

H. Branch Configuration:

1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-6, "Branch Connection."

a. Rectangular Main to Rectangular Branch: 45-degree entry.
b. Rectangular Main to Round Branch: Spin in.

2. Round: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees." Saddle taps are permitted in existing duct.

a. Velocity 1000 to 1500 fpm or Lower: Conical tap.
b. Velocity 1500 fpm or Higher: 45-degree lateral.

END OF SECTION

SECTION 233300 - AIR DUCT ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Backdraft dampers.
2. Manual volume dampers.
3. Fire dampers.
4. Turning vanes.
5. Duct-mounted access doors.
6. Flexible connectors.
7. Duct accessory hardware.

B. Related Requirements:

1. Section 233346 "Flexible Ducts" for insulated and non-insulated flexible ducts.
2. Section 284621.11 "Addressable Fire-Alarm System" for duct-mounted fire and smoke detectors.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted access panels and access doors required for access to duct accessories are shown and coordinated with each other, using input from Installers of the items involved.

C. Source quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTION

A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."

B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

2.2 MATERIALS

A. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.

1. Galvanized Coating Designation: G90.
2. Exposed-Surface Finish: Mill phosphatized.

B. Extruded Aluminum: Comply with ASTM B 221 (ASTM B 221M), Alloy 6063, Temper T6.

C. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.

D. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.3 BACKDRAFT DAMPERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Geenheck Fan Corporation.
b. Nailor Industries Inc.
c. Pottorff.
d. Ruskin Company.

B. Description: Gravity balanced.

C. Maximum Air Velocity: 3000 fpm.

D. Maximum System Pressure: 3-inch wg.

E. Frame: Hat-shaped, 0.05-inch-thick, galvanized sheet steel, with welded corners or mechanically attached and mounting flange.

F. Blades: Multiple single-piece blades, off-center pivoted or end pivoted, maximum 6-inch width, 0.025-inch-thick, roll-formed aluminum with sealed edges.

G. Blade Action: Parallel.

H. Blade Seals: Extruded vinyl, mechanically locked.

I. Blade Axles:

1. Material: Stainless steel.
2. Diameter: 0.20 inch.

J. Tie Bars and Brackets: Aluminum.

K. Return Spring: Adjustable tension.

L. Bearings: Synthetic pivot bushings.

M. Accessories:

1. Adjustment device to permit setting for varying differential static pressure.
2. Counterweights and spring-assist kits for vertical airflow installations.
3. Electric actuators.
4. Chain pulls.
5. Screen Mounting: Front mounted in sleeve.

    a. Sleeve Thickness: 20 gage minimum.
    b. Sleeve Length: 6 inches minimum.

6. Screen Mounting: Rear mounted.
7. Screen Material: Galvanized steel.
8. Screen Type: Bird.
9. 90-degree stops.

2.4 MANUAL VOLUME DAMPERS

A. Standard, Steel, Manual Volume Dampers:

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Flexmaster U.S.A., Inc.
b. Nailor Industries Inc.
c. Pottorff.

d. Ruskin Company.

2. Standard leakage rating, with linkage outside airstream.
3. Suitable for horizontal or vertical applications.
4. Frames:

a. Frame: Hat-shaped, 0.094-inch-thick, galvanized sheet steel.
b. Mitered and welded corners.
c. Flanges for attaching to walls and flangeless frames for installing in ducts.

5. Blades:

a. Multiple or single blade.
b. Parallel- or opposed-blade design.
c. Stiffen damper blades for stability.
d. Galvanized-steel, 0.064 inch thick.

6. Blade Axles: Galvanized steel.
7. Bearings:

a. Molded synthetic.
b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.

8. Tie Bars and Brackets: Galvanized steel.

C. Jackshaft:

1. Size: 1-inch diameter.
2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.

D. Damper Hardware:

1. Zinc-plated, die-cast core with dial and handle made of 3/32-inch- thick zinc-plated steel, and a 3/4-inch hexagon locking nut.
2. Include center hole to suit damper operating-rod size.
3. Include elevated platform for insulated duct mounting.

2.5 FIRE DAMPERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Arrow United Industries
b. Geenheck Fan Corporation.
c. Nailor Industries Inc.
d. NCA Manufacturing, Inc.
e. Pottorff.

f. Ruskin Company.

B. Type: Static; rated and labeled according to UL 555 by an NRTL.

C. Fire Rating: 1-1/2 hours.

D. Frame: Curtain type with blades outside airstream except where located behind grille where blades may be inside airstream; fabricated with roll-formed, 0.034-inch- thick galvanized steel; with mitered and interlocking corners.

E. Mounting Sleeve: Factory- or field-installed, galvanized sheet steel.

1. Minimum Thickness: 0.05 or 0.138 inch thick, as indicated, and of length to suit application.
2. Exception: Omit sleeve where damper-frame width permits direct attachment of perimeter mounting angles on each side of wall or floor; thickness of damper frame must comply with sleeve requirements.

F. Mounting Orientation: Vertical or horizontal as indicated.

G. Blades: Roll-formed, interlocking, 0.034-inch-thick, galvanized sheet steel. In place of interlocking blades, use full-length, 0.034-inch-thick, galvanized-steel blade connectors.

H. Horizontal Dampers: Include blade lock and stainless-steel closure spring.

I. Heat-Responsive Device: Replaceable, 165 deg F rated, fusible links.

2.6 TURNING VANES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Aero-Dyne Sound Control Co.
b. Ductmate Industries, Inc.
c. Duro Dyne Inc.
d. METALAIRE, Inc.
e. SEMCO LLC.

B. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.

1. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.

C. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 4-3, "Vanes and Vane Runners," and 4-4, "Vane Support in Elbows."

D. Vane Construction: Single wall.

2.7 DUCT-MOUNTED ACCESS DOORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. Aire Technologies.
   b. Ductmate Industries, Inc.
   c. Flexmaster U.S.A., Inc.
   d. Geenheck Fan Corporation.
   e. McGill AirFlow LLC.
   f. Nailor Industries Inc.
   g. Pottorff.

B. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 7-2, "Duct Access Doors and Panels," and 7-3, "Access Doors - Round Duct."

   1. Door:

      a. Double wall, rectangular.
      b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
      c. Vision panel.
      d. Hinges and Latches: 1-by-1-inchbutt or piano hinge and cam latches.
      e. Fabricate doors airtight and suitable for duct pressure class.

   2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
   3. Number of Hinges and Locks:

      a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
      b. Access Doors up to 18 Inches Square: Two hinges and two sash locks.

2.8 FLEXIBLE CONNECTORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. Ductmate Industries, Inc.
   b. Duro Dyne Inc.
   c. JP Lamborn Co.
   d. Ventfabrics, Inc.

B. Materials: Flame-retardant or noncombustible fabrics.

C. Coatings and Adhesives: Comply with UL 181, Class 1.

D. Metal-Edged Connectors: Factory fabricated with a fabric strip 3-1/2 inches wide attached to two strips of 2-3/4-inch-wide, 0.028-inch-thick, galvanized sheet steel or 0.032-inch-thick aluminum sheets. Provide metal compatible with connected ducts.

E. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.

1. Minimum Weight: 26 oz./sq. yd..
2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
3. Service Temperature: Minus 40 to plus 200 deg F.

F. Outdoor System, Flexible Connector Fabric: Glass fabric double coated with weatherproof, synthetic rubber resistant to UV rays and ozone.

1. Minimum Weight: 24 oz./sq. yd.
2. Tensile Strength: 530 lbf/inch in the warp and 440 lbf/inch in the filling.
3. Service Temperature: Minus 50 to plus 250 deg F.

G. Thrust Limits: Combination coil spring and elastomeric insert with spring and insert in compression, and with a load stop. Include rod and angle-iron brackets for attaching to fan discharge and duct.

1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
2. Outdoor Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.

2.9 DUCT ACCESSORY HARDWARE

A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.

B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts.

B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and stainless-steel accessories in stainless-steel ducts.

C. Compliance with ASHRAE/IESNA 90.1-2004 includes Section 6.4.3.3.3 - "Shutoff Damper Controls," restricts the use of backdraft dampers, and requires control dampers for certain

applications. Install backdraft dampers at inlet of exhaust fans or exhaust ducts as close as possible to exhaust fan unless otherwise indicated.

D. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channel of same depth as liner, and terminate liner with nosing at hat channel.

1. Install steel volume dampers in steel ducts.

E. Set dampers to fully open position before testing, adjusting, and balancing.

F. Install test holes at fan inlets and outlets and elsewhere as indicated.

G. Install fire dampers according to UL listing.

H. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:

1. At duct coils.
2. At outdoor-air intakes and mixed-air plenums.
3. Downstream from control dampers, backdraft dampers, and equipment.
4. Adjacent to and close enough to fire dampers, to reset or reinstall fusible links. Access doors for access to fire dampers having fusible links shall be pressure relief access doors and shall be outward operation for access doors installed upstream from dampers and inward operation for access doors installed downstream from dampers.
5. At each change in direction and at maximum 50-foot spacing.
6. Upstream and downstream from turning vanes.
7. Elsewhere as indicated.

I. Install access doors with swing against duct static pressure.

J. Access Door Sizes:

1. One-Hand or Inspection Access: 8 by 5 inches.
2. Two-Hand Access: 12 by 12 inches.
3. Head and Hand Access: 18 by 10 inches.
4. Head and Shoulders Access: 21 by 14 inches.

K. Label access doors according to Section 230553 "Identification for HVAC Piping and Equipment" to indicate the purpose of access door.

L. Install flexible connectors to connect ducts to equipment.

M. Connect air terminal units to supply ducts directly.

N. Connect diffusers to ducts directly or with maximum 60-inch lengths of flexible duct clamped or strapped in place.

O. Connect flexible ducts to metal ducts with draw bands and adhesive plus sheet metal screws.

P. Install duct test holes where required for testing and balancing purposes.

3.2 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. Operate dampers to verify full range of movement.
2. Inspect locations of access doors and verify that purpose of access door can be performed.
3. Operate fire dampers to verify full range of movement and verify that proper heat-response device is installed.
4. Inspect turning vanes for proper and secure installation.
5. Operate remote damper operators to verify full range of movement of operator and damper.

END OF SECTION

SECTION 233346 - FLEXIBLE DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Insulated flexible ducts.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTION

A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."

B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

C. Comply with the Air Diffusion Council's "ADC Flexible Air Duct Test Code FD 72-R1."

D. Comply with ASTM E 96/E 96M, "Test Methods for Water Vapor Transmission of Materials."

2.2 INSULATED FLEXIBLE DUCTS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Flexmaster U.S.A., Inc.

b. McGill AirFlow LLC.
c. Thermaflex; a Flex-Tek Group company.
d. Ward Industries; a brand of Hart & Cooley, Inc.

B. Insulated, Flexible Duct: UL 181, Class 1, two-ply vinyl film supported by helically wound, spring-steel wire; fibrous-glass insulation; aluminized vapor-barrier film.

1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
2. Maximum Air Velocity: 4000 fpm.
3. Temperature Range: Minus 10 to plus 160 deg F.
4. Insulation R-Value: Comply with ASHRAE/IES 90.1 (minimum R-value = 4.4).
5. Continuous inner liner.

2.3 FLEXIBLE DUCT CONNECTORS

A. Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action or nylon strap in sizes 3 through 18 inches, to suit duct size.

B. Non-Clamp Connectors: Adhesive.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install flexible ducts according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts.

B. Install in indoor applications only. Flexible ductwork should not be exposed to UV lighting.

C. Connect diffusers to ducts directly or with a 60-inch maximum length of flexible duct clamped or strapped in place.

D. Connect flexible ducts to metal ducts with draw bands and adhesive plus sheet metal screws.

E. Install duct test holes where required for testing and balancing purposes.

F. Installation:

1. Install ducts fully extended.
2. Do not bend ducts across sharp corners.
3. Bends of flexible ducting shall not exceed a minimum of one duct diameter.
4. Avoid contact with metal fixtures, water lines, pipes, or conduits.
5. Install flexible ducts in a direct line, without sags, twists, or turns.

G. Supporting Flexible Ducts:

1. Suspend flexible ducts with bands 1-1/2 inches wide or wider and spaced a maximum of 48 inches apart. Maximum centerline sag between supports shall not exceed 1/2 inch per 12 inches.

2. Install extra supports at bends placed approximately one duct diameter from center line of the bend.
3. Ducts may rest on ceiling joists or truss supports. Spacing between supports shall not exceed the maximum spacing per manufacturer's written installation instructions.
4. Vertically installed ducts shall be stabilized by support straps at a maximum of 72 inches o.c.

END OF SECTION

SECTION 233600 – AIR TERMINAL UNITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Shutoff, single-duct air terminal units.
2. Casing liner.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of air terminal unit. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for air terminal units.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

C. Shop Drawings: For air terminal units.

1. Include plans, elevations, sections, and mounting details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.
4. Hangers and supports, including methods for duct and building attachment and vibration isolation.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Ceiling suspension assembly members.

2. Size and location of initial access modules for acoustic tile.
3. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.

C. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For air terminal units to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. Instructions for resetting minimum and maximum air volumes.
b. Instructions for adjusting software set points.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and System Start-up."

B. ASHRAE Compliance: Applicable requirements in ASHRAE/IES 90.1, "Section 6 - Heating, Ventilating, and Air Conditioning."

2.2 SHUTOFF, SINGLE-DUCT AIR TERMINAL UNITS

A. Configuration: Volume-damper assembly inside unit casing with control components inside a protective metal shroud.

B. Casing: 0.040-inch-thick galvanized steel, single wall.

1. Casing Liner: Comply with requirements in "Casing Liner" Article for flexible elastomeric duct liner.
2. Air Inlet: Round stub connection or S-slip and drive connections for duct attachment.
3. Air Outlet: S-slip and drive connections.
4. Access: Removable panels for access to parts requiring service, adjustment, or maintenance; with airtight gasket.
5. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

C. Volume Damper: Galvanized steel with peripheral gasket and self-lubricating bearings.

1. Maximum Damper Leakage: AHRI 880 rated, 2 percent of nominal airflow at 3-inch wg inlet static pressure.
2. Damper Position: Normally open.

D. Hydronic Heating Coils: Copper tube, with mechanically bonded aluminum fins spaced no closer than 0.1 inch, and rated for a minimum working pressure of 200 psig and a maximum entering-water temperature of 220 deg F. Include manual air vent and drain valve.

E. Control devices shall be compatible with temperature controls system specified in Section 230923 "Direct Digital Control (DDC) System for HVAC."

1. Factory-installed multipoint velocity sensor at air inlet.

F. Controls:

1. Suitable for operation with duct pressures between 0.25- and 3.0-inch wg inlet static pressure.

2.3 CASING LINER

A. Casing Liner: Flexible elastomeric duct liner fabricated of preformed, cellular, closed-cell, sheet materials complying with ASTM C 534, Type II, Grade 1; and with NFPA 90A or NFPA 90B.

1. Minimum Thickness: 3/4 inch.
2. Surface-Burning Characteristics: Maximum flame-spread index of 25 and maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
3. Liner Adhesive: As recommended by insulation manufacturer and complying with NFPA 90A or NFPA 90B.

2.4 SOURCE QUALITY CONTROL

A. Factory Tests: Test assembled air terminal units according to AHRI 880.

1. Label each air terminal unit with plan number, nominal airflow, maximum and minimum factory-set airflows, and AHRI certification seal.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT INSTALLATION

A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Ch. 5, "Hangers and Supports" and with Section 230529 "Hangers and Supports for HVAC Piping and Equipment."

B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.

1. Coordinate locations of concrete inserts with locations of radiant tubing in second floor slab prior to installation.

2. Where practical, install concrete inserts before placing concrete.
3. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
4. Use powder-actuated concrete fasteners for standard-weight aggregate concretes and for slabs more than 4 inches thick.
5. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes and for slabs less than 4 inches thick.

C. Hangers Exposed to View: Threaded rod and angle or channel supports.

D. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

3.2 TERMINAL UNIT INSTALLATION

A. Install air terminal units according to NFPA 90A, "Standard for the Installation of Air Conditioning and Ventilating Systems."

B. Install air terminal units level and plumb. Maintain sufficient clearance for normal service and maintenance.

C. Install wall-mounted thermostats.

3.3 CONNECTIONS

A. Where installing piping adjacent to air terminal unit, allow space for service and maintenance.

B. Hot-Water Piping: Comply with requirements in Section 232113 "Hydronic Piping" and Section 232116 Hydronic Piping Specialties," and connect heating coils to supply with shutoff valve, strainer, control valve, and union or flange; and to return with balancing valve and union or flange.

C. Comply with requirements in Section 233113 "Metal Ducts" for connecting ducts to air terminal units.

3.4 IDENTIFICATION

A. Label each air terminal unit with plan number, nominal airflow, and maximum and minimum factory-set airflows. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for equipment labels.

3.5 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. After installing air terminal units and after electrical circuitry has been energized, test for compliance with requirements.
2. Leak Test: After installation, fill water coils and test for leaks. Repair leaks and retest until no leaks exist.

3. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

B. Air terminal unit will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.6 STARTUP SERVICE

A. Perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.
2. Verify that inlet duct connections are as recommended by air terminal unit manufacturer to achieve proper performance.
3. Verify that controls and control enclosure are accessible.
4. Verify that control connections are complete.
5. Verify that nameplate and identification tag are visible.
6. Verify that controls respond to inputs as specified.

3.7 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain air terminal units.

END OF SECTION

SECTION 233713.13 - AIR DIFFUSERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes ceiling, wall, and duct-mounted diffusers.

B. Related Requirements:

1. Section 233300 "Air Duct Accessories" for fire dampers and volume-control dampers not integral to diffusers.
2. Section 233713.23 "Registers and Grilles" for adjustable-bar register and grilles, fixed-face registers and grilles, and linear bar grilles.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
2. Diffuser Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Ceiling suspension assembly members.
2. Method of attaching hangers to building structure.
3. Size and location of initial access modules for acoustical tile.
4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.

5. Duct access panels.

C. Source quality-control reports.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

A. Diffusers, registers, and grilles are scheduled on the Drawings.

B. Color shall be white, unless otherwise noted on schedules on the Drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas where diffusers are installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install diffusers level and plumb.

B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. Fors units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.

C. Install diffusers with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

3.3 ADJUSTING

A. After installation, adjust diffusers to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION

SECTION 233713.23 - REGISTERS AND GRILLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes ceiling, wall, and duct-mounted registers and grilles.

B. Related Requirements:

1. Section 233300 "Air Duct Accessories" for fire dampers and volume-control dampers not integral to registers and grilles.
2. Section 233713.13 "Air Diffusers" for various types of air diffusers.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
2. Register and Grille Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Ceiling suspension assembly members.
2. Method of attaching hangers to building structure.
3. Size and location of initial access modules for acoustical tile.
4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
5. Duct access panels.

C. Source quality-control reports.

PART 2 - PRODUCTS

2.1 sMANUFACTURED UNITS

A. Diffusers, registers, and grilles are scheduled on the Drawings.

B. Color shall be white, unless noted on schedules on the Drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas where registers and grilles are installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install registers and grilles level and plumb.

B. Outlets and Inlets Locations: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.

C. Install registers and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

3.3 ADJUSTING

A. After installation, adjust registers and grilles to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION

SECTION 235123 – GAS VENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Listed double-wall vents.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for product.

C. Shop Drawings: For vents.

1. Include plans, elevations, sections, and attachment details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Detail fabrication and assembly of hangers and seismic restraints.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Welding certificates.

C. Sample Warranty: For special warranty.

1.5 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel according to the following:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel," for hangers and supports.
2. AWS D9.1/D9.1M, "Sheet Metal Welding Code," for shop and field welding of joints and seams in vents.

B. Certified Sizing Calculations: Manufacturer shall certify venting system sizing calculations.

PART 2 - PRODUCTS

2.1 LISTED TYPE B VENTS

A. Description: Double-wall metal vents tested according to UL 441 and rated for 480 deg F continuously for Type B; with neutral or negative flue pressure complying with NFPA 211.

B. Construction: Inner shell and outer jacket separated by at least a 1/4-inch airspace.

C. Inner Shell: ASTM B 209, Type 1100 aluminum or ASTM B 209, Type 3003 aluminum or ASTM B 209, Type 3105 aluminum.

D. Outer Jacket: Galvanized steel.

E. Accessories: Tees, elbows, increasers, draft-hood connectors, terminations, adjustable roof flashings, storm collars, support assemblies, thimbles, firestop spacers, and fasteners; fabricated from similar materials and designs as vent-pipe straight sections; all listed for same assembly.

1. Termination: Round chimney top designed to exclude minimum 98 percent of rainfall.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLICATION

A. Listed Type B Vents: Vents for certified gas appliances.

3.3 INSTALLATION OF LISTED VENTS

A. Coordinate installation of roof curbs, equipment supports, and roof penetrations. These items are specified in Section 077200 "Roof Accessories."

B. Comply with minimum clearances from combustibles and minimum termination heights according to product listing or NFPA 211, whichever is most stringent.

C. Seal between sections of positive-pressure vents according to manufacturer's written installation instructions, using sealants recommended by manufacturer.

D. Support vents at intervals recommended by manufacturer to support weight of vents and all accessories, without exceeding appliance loading.

E. Lap joints in direction of flow.

3.4 CLEANING

A. After completing system installation, including outlet fittings and devices, inspect exposed finish. Remove burrs, dirt, and construction debris, and repair damaged finishes.

END OF SECTION

SECTION 235216 – CONDENSING BOILERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes high-mass, gas-fired, condensing boilers, trim, and accessories for generating hot water.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for boilers.
2. Include rated capacities, operating characteristics, and furnished specialties and accessories.

C. Shop Drawings: For boilers, boiler trim, and accessories.

1. Include plans, elevations, sections, and mounting and attachment details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Source quality-control reports.

C. Field quality-control reports.

D. Sample Warranty: For special warranty.

E. Other Informational Submittals:

1. ASME Stamp Certification and Report: Submit "A," "S," or "PP" stamp certificate of authorization, as required by authorities having jurisdiction, and document hydrostatic testing of piping external to boiler.
2. CSA B51 pressure vessel Canadian Registration Number (CRN).

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For boilers to include in emergency, operation, and maintenance manuals.

1.6 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace components of boilers that fail in materials or workmanship within specified warranty period.

1. Warranty Period for Condensing Boilers:

a. Leakage and Materials: 10 years from date of Substantial Completion.
b. Heat Exchanger Damaged by Thermal Stress and Corrosion: Nonprorated for years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. ASME Compliance: Fabricate and label boilers to comply with 2010 ASME Boiler and Pressure Vessel Code.

C. ASHRAE/IES 90.1 Compliance: Boilers shall have minimum efficiency according to "Gas and Oil Fired Boilers - Minimum Efficiency Requirements."

D. DOE Compliance: Minimum efficiency shall comply with 10 CFR 430, Subpart B, Appendix N.

E. UL Compliance: Test boilers for compliance with UL 795. Boilers shall be listed and labeled by a testing agency acceptable to authorities having jurisdiction.

F. CSA Compliance: Test boilers for compliance with CSA B51.

G. International Energy Conservation Code: Boiler efficiencies shall be in compliance with the 2021 IECC.

2.2 FORCED-DRAFT, FIRE-TUBE CONDENSING BOILERS

A. Description: Factory-fabricated, -assembled, and -tested, fire-tube condensing boiler with heat exchanger sealed pressure tight, built on a steel base, including insulated jacket; flue-gas vent; combustion-air intake connections; water supply, return, and condensate drain connections; and controls. Water-heating service only.

B. Heat Exchanger: Nonferrous, corrosion-resistant combustion chamber.

C. Pressure Vessel: Carbon steel with welded heads and tube connections.

D. Burner: Natural gas, forced draft.

E. Blower: Centrifugal fan to operate during each burner firing sequence and to prepurge and postpurge the combustion chamber.

1. Motors: Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."

a. Motor Sizes: Minimum size as indicated; if not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.

F. Gas Train: Combination gas valve with manual shutoff and pressure regulator.

G. Ignition: Spark ignition with 100 percent main-valve shutoff with electronic flame supervision.

H. Casing:

1. Jacket: Sheet metal, with snap-in or interlocking closures.
2. Control Compartment Enclosures: NEMA 250, Type 1A.
3. Finish: Baked-enamel or powder-coated protective finish.
4. Insulation: Minimum 2-inch-thick, mineral-fiber insulation surrounding the heat exchanger.
5. Combustion-Air Connections: Inlet and vent duct collars.

I. Capacities and Characteristics: As scheduled on Drawings.

2.3 TRIM

A. Include devices sized to comply with ASME B31.1.

B. Aquastat Controllers: Operating, firing rate, and high limit.

C. Safety Relief Valve: ASME rated.

D. Pressure and Temperature Gage: Minimum 3-1/2-inch-diameter, combination water-pressure and -temperature gage. Gages shall have operating-pressure and -temperature ranges, so normal operating range is about 50 percent of full range.

E. Boiler Air Vent: Automatic.

F. Drain Valve: Minimum NPS 3/4 hose-end gate valve.

2.4 CONTROLS

A. Refer to Section 230923 "Direct Digital Control (DDC) System for HVAC."

B. Boiler operating controls shall include the following devices and features:

1. Control transformer.
2. Set-Point Adjust: Set points shall be adjustable.
3. Sequence of Operation: Electric, factory-fabricated and field-installed panel to control burner firing rate to maintain discharge water temperature.

    a. Include automatic, alternating-firing sequence for multiple boilers to ensure maximum system efficiency throughout the load range and to provide equal runtime for boilers.

C. Burner Operating Controls: To maintain safe operating conditions, burner safety controls limit burner operation.

1. High Cutoff: Automatic reset stops burner if operating conditions rise above maximum boiler design temperature.
2. Low-Water Cutoff Switch: Electronic probe shall prevent burner operation on low water. Cutoff switch shall be manual-reset type.
3. Blocked Inlet Safety Switch: Manual-reset pressure switch field mounted on boiler combustion-air inlet.
4. Audible Alarm: Factory mounted on control panel with silence switch; shall sound alarm for above conditions.

D. Building Automation System Interface: Factory installed hardware and software to enable building automation system to monitor, control, and display boiler status and alarms.

1. Hardwired Points:

    a. Monitoring: On/off status, common trouble alarm.
    b. Control: On/off operation, hot-water-supply temperature set-point adjustment.

2. A communication interface with building automation system shall enable building automation system operator to remotely control and monitor the boiler from an operator workstation. Control features available, and monitoring points displayed, locally at boiler control panel shall be available through building automation system.

2.5 ELECTRICAL POWER

A. Controllers, Electrical Devices, and Wiring: Electrical devices and connections are specified in electrical Sections.

B. Single-Point Field Power Connection: Factory-installed and -wired switches, motor controllers, transformers, and other electrical devices necessary shall provide a single-point field power connection to boiler.

1. House in NEMA 250, Type 1 enclosure.
2. Wiring shall be numbered and color coded to match wiring diagram.
3. Install factory wiring outside of an enclosure in a metal raceway.
4. Field power interface shall be to circuit breaker.
5. Provide each motor with overcurrent protection.

2.6 VENTING KITS

A. Kit: Complete system, ASTM A 959, Type 29-4C stainless steel, pipe, vent terminal, thimble, indoor plate, vent adapter, condensate trap and dilution tank, and sealant.

B. Combustion-Air Intake: Complete system, stainless steel, pipe, vent terminal with screen, inlet air coupling, and sealant.

2.7 SOURCE QUALITY CONTROL

A. Burner and Hydrostatic Test: Factory adjust burner to eliminate excess oxygen, carbon dioxide, oxides of nitrogen emissions, and carbon monoxide in flue gas and to achieve combustion efficiency; perform hydrostatic test.

B. Test and inspect factory-assembled boilers, before shipping, according to 2010 ASME Boiler and Pressure Vessel Code.

C. Allow Owner access to source quality-control testing of boilers. Notify Architect 14 days in advance of testing.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in for concrete equipment bases, anchor-bolt sizes and locations, and piping and electrical connections to verify actual locations, sizes, and other conditions affecting performance of the Work.

1. Final boiler locations indicated on Drawings are approximate. Determine exact locations before roughing-in for piping and electrical connections.

B. Examine mechanical spaces for suitable conditions where boilers will be installed.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 BOILER INSTALLATION

A. Equipment Mounting:

1. Install boilers on cast-in-place concrete equipment base(s). Comply with requirements for equipment bases and foundations specified in Section 033000 "Cast-in-Place Concrete."

2. Comply with requirements for vibration isolation devices specified in Section 230548.13 "Vibration Controls for HVAC."
3. Secure boilers to concrete equipment base.

B. Install gas-fired boilers according to NFPA 54.

C. Assemble and install boiler trim.

D. Install electrical devices furnished with boiler but not specified to be factory mounted.

E. Install control wiring to field-mounted electrical devices.

3.3 CONNECTIONS

A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties.

B. Install piping adjacent to boiler to allow service and maintenance.

C. Install piping from equipment drain connection to nearest floor drain. Piping shall be at least full size of connection.

D. Connect gas piping to boiler gas-train inlet with union. Piping shall be at least full size of gas-train connection. Provide a reducer if required.

E. Connect hot-water piping to supply- and return-boiler tappings with shutoff valve and union or flange at each connection.

F. Install piping from safety relief valves to nearest floor drain.

G. Boiler Venting:

1. Install flue venting kit and combustion-air intake.
2. Connect full size to boiler connections.

H. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."

I. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

3.4 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.

1. Perform installation and startup checks according to manufacturer's written instructions.
2. Leak Test: Hydrostatic test. Repair leaks and retest until no leaks exist.
3. Operational Test: Start units to confirm proper motor rotation and unit operation. Adjust air-fuel ratio and combustion.

4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

    a. Check and adjust initial operating set points and high- and low-limit safety set points of fuel supply, water level, and water temperature.
    b. Set field-adjustable switches and circuit-breaker trip ranges as indicated.

B. Boiler will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

D. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.5 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain boilers. Refer to Section 017900 "Demonstration and Training."

END OF SECTION

SECTION 235700 - HEAT EXCHANGERS FOR HVAC

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Gasketed-plate heat exchangers.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.

1. Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Sample Warranty: For manufacturer's warranty.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and maintenance data.

1.5 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of heat exchangers that fail in materials or workmanship within specified warranty period.

1. Warranty Periods: From date of Substantial Completion.

a. Plate Heat Exchangers:

1) Flat-Plate Type: One year.

PART 2 - PRODUCTS

2.1 GASKETED-PLATE HEAT EXCHANGERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Alfa Laval Inc.

B. Configuration: Freestanding assembly, consisting of frame support, top and bottom carrying and guide bars, fixed and movable end plates, tie rods, individually removable plates, and one-piece gaskets. Floor-mounted heat exchangers must have integral legs with mounting feet.

C. Construction: Fabricate and label heat exchangers to comply with ASME Boiler and Pressure Vessel Code, Section VIII, "Pressure Vessels," Division 1.

D. Frame:

1. Capacity to accommodate 100 percent additional plates.
2. Painted carbon steel with provisions for anchoring to support.

E. Top and Bottom Carrying and Guide Bars: Painted carbon steel, aluminum, or stainless steel.

1. Fabricate attachment of heat-exchanger support bars and guide bars with reinforcement strong enough to resist heat-exchanger movement during seismic event when heat-exchanger support bars and guide bars are anchored to building structure.

F. End-Plate Material: Painted carbon steel.

G. Tie Rods and Nuts: Stainless steel.

H. Plate Material: 0.024 inch thick before stamping; 300 psi titanium.

I. Gasket Materials: NBR HT.

J. Piping Connections: Factory fabricated of materials compatible with heat-exchanger shell. Attach tappings to shell before testing and labeling.

PART 3 - EXECUTION

3.1 INSTALLATION OF HEAT EXCHANGER, GENERAL

A. Equipment Mounting:

1. Install floor-mounted heat exchangers on equipment bases. Install all heat exchangers level and plumb in accordance with manufacturer's recommendations.

3.2 INSTALLATION OF GASKETED-PLATE HEAT EXCHANGER

A. Install floor-mounted gasketed-plate heat exchangers on cast-in-place concrete equipment base, and fasten legs to base.

B. Install metal shroud over installed gasketed-plate heat exchanger in accordance with manufacturer's written instructions.

3.3 PIPING CONNECTIONS

A. Comply with requirements for piping specified in Section 232113 "Hydronic Piping" and Section 232116 "Hydronic Piping Specialties." Drawings indicate general arrangement of piping, fittings, and specialties.

B. Maintain manufacturer's recommended clearances for tube removal, service, and maintenance.

C. Install piping adjacent to heat exchangers to allow space for service and maintenance of heat exchangers. Arrange piping for easy removal of heat exchangers.

D. Install shutoff valves at heat-exchanger inlet and outlet connections.

E. Install pressure-relief valves on heat-exchanger tube outlet piping before any isolation valves.

F. Pipe pressure-relief valves, full size of valve connection, to floor drain.

G. Install thermometer on each heat-exchanger fluid inlet and outlet piping. Comply with requirements for thermometers specified in Section 230500 "Common Work Results for HVAC."

H. Install pressure gauges on each heat-exchanger fluid inlet and outlet piping. Comply with requirements for pressure gauges specified in Section 230500 "Common Work Results for HVAC."

3.4 CLEANING

A. After completing system installation, including outlet fitting and devices, inspect exposed finish. Remove burrs, dirt, and construction debris, and repair damaged finishes.

B. Isolate heat exchangers from piping before flushing piping. If a valve is used to isolate equipment, its closure shall be capable of sealing against test pressure without damage to valve. Install blind flanges in flanged joints to isolate equipment.

C. Flush heat-exchanger piping systems with clean water; then remove and clean or replace strainer screens before reopening flow to heat exchangers.

3.5 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Tests and Inspections:

1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

C. Heat exchanger will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

END OF SECTION

SECTION 236423.13 - AIR-COOLED, REVERSIBLE, SCROLL WATER CHILLERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes packaged, air-cooled, reversible, electric-motor-driven, scroll water chillers with heat recovery.

1.2 DEFINITIONS

A. BAS: Building automation system.

B. COP: Coefficient of performance. The ratio of the rate of heat removal to the rate of energy input using consistent units for any given set of rating conditions.

C. DDC: Direct digital control.

D. EER: Energy-efficiency ratio. The ratio of the cooling capacity given in Btu/h to the total power input given in watts at any given set of rating conditions.

E. GFI: Ground fault interrupt.

F. IPLV: Integrated part-load value. A single-number part-load efficiency figure of merit for a single chiller calculated per the method defined by AHRI 550/590 and referenced to AHRI standard rating conditions.

G. I/O: Input/output.

H. kW/Ton: The ratio of total power input of the chiller in kilowatts to the net refrigerating capacity in tons at any given set of rating conditions.

I. NPLV: Nonstandard part-load value. A single number part-load efficiency figure of merit for a single chiller calculated per the method defined by AHRI 550/590 and intended for operating conditions other than the AHRI standard rating conditions.

J. SCCR: Short-circuit current rating.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include refrigerant, rated capacities, operating characteristics, and furnished specialties and accessories.
2. Performance at AHRI standard conditions and at conditions indicated.
3. Performance at AHRI standard unloading conditions.
4. Minimum evaporator flow rate.
5. Refrigerant capacity of water chiller.
6. Oil capacity of water chiller.
7. Fluid capacity of evaporator.
8. Characteristics of safety relief valves.
9. Electrical data.

C. Sustainable Design Submittals:

1. Product Data: For refrigerants, indicating compliance with refrigerant management practices.
2. Product Data: For energy performance.

D. Shop Drawings: Complete set of manufacturer's prints of water chiller assemblies, control panels, sections and elevations, and unit isolation. Include the following:

1. Assembled unit dimensions.
2. Weight and load distribution.
3. Required clearances for maintenance and operation.
4. Size and location of piping and wiring connections.
5. Diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings:

1. Plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

a. Structural supports.
b. Piping roughing-in requirements.
c. Wiring roughing-in requirements, including spaces reserved for electrical equipment.
d. Access requirements, including working clearances for mechanical controls and electrical equipment, and tube pull and service clearances.

C. Certificates: For certification required in "Quality Assurance" Article.

D. Installation instructions, including any remote panel installation instructions.

E. Source quality-control reports.

F. Startup service reports.

G. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For each water chiller to include in emergency, operation, and maintenance manuals.

C. Spare Parts List: Recommended spare parts list with quantity for each.

D. Touchup Paint Description: Detailed description of paint used in application of finish coat to allow for procurement of a matching paint.

E. Instructional Videos: Including those that are prerecorded and those that are recorded during training.

1.6 QUALITY ASSURANCE

A. Multi-pipe modules shall be constructed in accordance with the UL 60335 2-40 and NEC standards and be UL or ETL listed.

B. Multi-pipe modules shall be rated and tested in accordance with AHRI 550/590 – Standard for Water Chilling Packages.

C. Multi-pipe modules shall meet the safety standards of ANSI/ASHRAE 15 – Safety Standard for Refrigerated Systems.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Ship water chillers from the factory fully charged with refrigerant and filled with oil.

B. Comply with manufacturer’s installation instructions for rigging, unloading, and transporting multi-pipe modules.

C. Protect multi-pipe modules on site from physical damage after unloading.

1.8 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of water chillers that fail in materials or workmanship within specified warranty period.

B. Entire Multi-Pipe System: One-year parts and refrigerant.

C. Compressors: Five-year parts.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. AHRI Rating: Rate water chiller performance according to requirements in AHRI 550/590.

B. ASHRAE Compliance: ASHRAE 15 for safety code for mechanical refrigeration.

C. Comply with NFPA 70.

D. Operation Following Loss of Normal Power:

1. Equipment, associated factory- and field-installed controls, and associated electrical equipment and power supply connected to backup power system shall automatically return equipment and associated controls to the operating state occurring immediately before loss of normal power without need for manual intervention by an operator when power is restored either through a backup power source, or through normal power if restored before backup power is brought on-line.
2. Provide means and methods required to satisfy requirement even if not explicitly indicated.

E. Outdoor Installations:

1. Chiller shall be suitable for outdoor installation indicated. Provide adequate weather protection to ensure reliable service life over a 25-year period with minimal degradation due to exposure to outdoor ambient conditions.

2.2 AIR-COOLED, REVERSIBLE, SCROLL WATER CHILLERS WITH HEAT RECOVERY

A. Basis-of-Design Product: Subject to compliance with requirements, provide Trane unit scheduled on drawings, or comparable product by one of the following:

1. Carrier Global Corporation
2. Daikin Applied
3. WaterFurnace International, Inc.
4. YORK; brand of Johnson Controls International plc, Building Solutions North America

2.3 MANUFACTURED UNITS

A. Description: The air-cooled, reversible, scroll water chiller with heat recovery shall consist of individual multi-pipe modules that are assembled on site. Each module shall be completely factory wired and tested prior to shipment. Each module shall include two vapor injection scroll compressors in a tandem compressor set, a brazed plate evaporator, a brazed plate condenser, air-source/sink coil, and controls. The controls shall also be designed to operate on a distributed primary control system which allows each individual secondary microprocessor to operate on its own temperature sensor if there is a failure of the primary microprocessor.

B. General: Each multi-pipe module shall be assembled on a galvanized steel, formed sheet metal frame and be enclosed with epoxy painted galvanized sheet metal panels. The multi-pipe modules shall be shipped as individual modules and assembled on site. Each module shall be fully charged with refrigerant and factory tested for capacity and controller functions prior to shipment.

1. The electrical supply conduit for each module shall be factory assembled and shipped with each module for field connection into the power distribution panel on the primary module. This provides a single point of power connection for all the modules.

C. Frame: Frame shall be constructed of formed galvanized 12-gauge sheet metal externally coated with white painted finish. The coating provides a minimum of 1000 hours of salt spray protection.

D. Cabinet: Cabinet panels are made of formed galvanized sheet metal externally coated with white painted finish. The cabinet enclosure shall include easily removable access panels for service. Access panels shall be removable via stainless steel fasteners and retaining clips. Modules shall not require access via sheet metal screws or protruding threaded fasteners.

E. Electrical Panels: Each module shall have a high voltage electrical panel where power to each module is connected and a low voltage electrical panel for the module's controller and communication wiring In addition, if the system has single point power, a power distribution panel shall be provided containing a system lug for the incoming single power supply, a circuit breaker for each module for branch circuit over-current protection and a phase monitor wired back to the primary module for protection against low voltage, phase imbalance, phase loss, and phase reversal.

F. Compressors: Single circuit with two hermetically sealed vapor injected scroll compressors in a tandem compressor set. Each compressor shall be furnished with a crankcase heater, oil level sight glass, suction gas-cooled motor with solid-state sensors in the windings for overload protection, and in-line circuit breaker. Compressors shall be mounted to the steel frame with rubber-in-shear isolators. Liquid injected scroll compressors are not acceptable.

The vapor injection scroll compressors are used with an economized vapor compression cycle offering more heat delivered and a better COP than with a conventional cycle. The cooling provided by inter-stage injection allows the operation of the compressor over a larger operating envelope providing higher heat delivery temperatures at low evaporating temperatures and resulting in larger heating capacities and higher efficiency.

G. Heat Exchangers: Single circuit, cold and hot fluid brazed plate heat evaporator and condenser in each multi-pipe module. Each is constructed of 316 stainless steel plates and copper brazing and shall be insulated with ¾" closed cell insulation. The supply and return fluid piping connections to each heat exchanger shall include an electronic and manual isolation valve to allow servicing of each module individually while the remaining modules continue to operate and to allow for variable flow. The fluid connections to each heat exchanger shall use roll grooved couplings for service convenience and ease of installation.

H. Electronic control valves: Each module's brazed plate heat exchangers branch line shall include an electronic isolation valve that allows system flow to the active modules to match the cooling or heating requirements to the system load. The valves shall have a minimum opening cycle time of not less than 30 seconds between the fully closed and open position. The valves shall have a minimum close off pressure of 75 psi and a maximum working pressure of 300 psi.

I. Filters: A 40-mesh industrial grade filter strainer shall be factory installed between the header system and each brazed plate heat exchanger inlet. The strainer shall be serviceable by closing the electronic and manual valves to remove each strainer for cleaning without shutting down fluid flow or power to the entire system and allowing the remaining modules to continue to operate. In-line strainers that require complete system shutdown for service and isolation are not acceptable.

J. Air Coil Fan Motors: The air coil fan motors shall be variable speed, maintenance free, and highly efficient Electronically Commutated Motors (ECM) with energy reduction capabilities.

K. Air Coil: Aluminum fins mechanically bonded to coppers tubes with integral subcooling circuits. Fin spacing shall not exceed 16 fins per inch. The air coil shall function as an evaporator or condenser depending on the operational mode.

L. Drain Pan: Factory-provided drain pans underneath the air coils shall be provided to divert water away from the modules during heating mode while in the defrost cycle.

M. Expansion Valves: Each module will have 4 expansion valves; one for defrost, one for cooling mode, and two for heating mode with one on each air coil.

N. Ball Valve: Each module shall contain a refrigeration actuated ball valve to allow for operation in either heating mode, cooling mode, simultaneous heating and cooling mode, and defrost mode.

O. Refrigerant piping: Piping shall be Type K seamless copper, shall have ¾" closed cell insulation on all piping except liquid line, solenoid valves for compressor pumpdown, and Schrader service valves in the suction, discharge, and liquid lines. Each module shall contain a single refrigeration circuit.

P. Fluid Piping: The fluid piping shall be Schedule 10 steel and have ¾" closed cell insulation to maintain fluid temperature. Each module shall have service valves for the independent isolation of each heat exchanger, without affecting the fluid flow to the remaining modules. Each module shall connect to the adjacent module using roll grooved steel couplings and neoprene gaskets. Any type of module-to-module connection external to the modules is unacceptable.

Q. Flow switches: Factory installed and tested thermal dispersion flow sensor on each brazed plate heat exchanger.

R. Assembly of all modules on a single galvanized frame for shipment to the jobsite as a single unit.

S. Sound-reduction package shall have the following:

1. Acoustic enclosure around compressors.
2. Reduced-speed fans with acoustic treatment.
3. Designed to reduce sound level without affecting performance.

2.4 INSULATION

A. Factory-applied insulation over all cold surfaces of chiller capable of forming condensation. Components shall include, but not be limited to, evaporator, evaporator water boxes including nozzles, refrigerant suction pipe from evaporator to compressor, cold surfaces of compressor, refrigerant-cooled motor, and auxiliary piping.

2.5 ELECTRICAL

A. Factory installed and wired, and functionally tested at factory before shipment.

B. Factory-installed and -wired switches, motor controllers, transformers, and other electrical devices necessary shall provide a single-point field power connection to water chiller.

C. House in a unit-mounted, NEMA enclosure with hinged access door with lock and key or padlock and key.

D. Wiring shall be numbered and color-coded to match wiring diagram.

2.6 CONTROLS

A. Factory installed and wired, and functionally tested at factory before shipment.

B. Standalone, microprocessor based, with all memory stored in nonvolatile memory so that reprogramming is not required on loss of electrical power.

C. Enclosure: Share enclosure with electrical power devices or provide a separate enclosure of matching construction.

D. Controls: The primary multi-pipe module shall incorporate the primary microprocessor controller. The primary microprocessor shall communicate with the remaining secondary microprocessors in each module via a local network communications protocol. The primary microprocessor shall include a phase monitor to protect against low voltage, phase unbalance, phase loss, and phase reversal conditions. The primary controller shall read all analog and fault port values from all secondary module controllers.

Each multi-pipe control system shall include operational switches for each compressor; high and low pressure transmitters to provide indication of refrigeration pressures; high and low refrigeration pressure alarms that shut down the responsible compressor(s); anti-short cycling compressor timers; minimum compressor run timers; and connection to Building Automation System.

E. Programmable Logic Controller (PLC)

The PLC shall provide the following minimum functions and alarms:

1. Adjustable fluid temperature set point.
2. Multiple stage compressor control, including compressor rotation to provide equal compressor run time.

3. Reset temperature control set point based on decreased load.
4. High and low fluid temperature alarm set points.
5. Fluid inlet and outlet temperature
6. Suction and discharge refrigeration pressures
7. Compressor run status.
8. Current alarm status
9. Demand load
10. Compressor run hours.
11. Number of compressors starts.
12. Alarm logging of previous 2000 alarms with time and date of each occurrence
13. Remote start/stop input.
14. Dry contact for general alarm
15. 'Smart' compressor demand distribution algorithm across chiller bank, which seamlessly allows unavailable modules to be placed out of sequence and available modules to be placed back in sequence.
16. BMS interface with the automatic variable flow control
17. Minimum flow control for fluid loops even with no compressors running.
18. 'Smart' compressor rotation algorithm within a module which accounts for compressor availability and safety timers.
19. Stand-alone fail-safe mode for each module should Primary module fail, allowing the chiller system to remain operating.
20. Remote hard wired set point capabilities.

F. Interface Panel

A smart operator 7" touch screen interface panel with graphical display shall be installed on the primary module to allow operation and alarm monitoring, adjustment of user set points, and controlled temperatures trending. Primary microprocessor controller provides current alarm status, alarm logging of the previous 2000 alarms, fluid temperatures for each module, refrigeration pressure on each refrigeration circuit, compressor run hours, current status display, remote on/off, and general alarm contacts.

G. The primary controller shall pass these values to the Building Automation System via BACnet protocols.

H. Defrost Controls:

1. Defrost module delay timer shall allow a maximum of 50% of modules to be in defrost mode simultaneously in order to minimize heating capacity derate.

2.7 SOURCE QUALITY CONTROL

A. Factory test and inspect evaporator according to ASME Boiler and Pressure Vessel Code: Section VIII, Division 1. Stamp with ASME label.

B. For water chillers located outdoors, rate sound power level according to AHRI 370 procedure.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Before water chiller installation, examine roughing-in for equipment support, anchor-bolt sizes and locations, piping, controls, and electrical connections to verify actual locations, sizes, and other conditions affecting water chiller performance, maintenance, and operations.

1. Water chiller locations indicated on Drawings are approximate. Determine exact locations before roughing-in for piping, controls, and electrical connections.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 WATER CHILLER INSTALLATION

A. Install chiller in accordance with manufacturer’s recommendations where shown on the drawings and other provided installation documents.

B. Install water chillers on support structure indicated.

C. Equipment Mounting:

1. Comply with requirements for vibration isolation devices specified in Section 230548.13 "Vibration Controls for HVAC."

D. Maintain manufacturer's recommended clearances for service and maintenance.

E. Maintain clearances required by governing code.

F. Chiller manufacturer's factory-trained service personnel shall charge water chiller with refrigerant if not factory charged and fill with oil if not factory installed.

G. Install separate devices furnished by manufacturer and not factory installed.

3.3 PIPING CONNECTIONS

A. Comply with requirements in Section 232113 "Hydronic Piping" and Section 232116 "Hydronic Piping Specialties." Drawings indicate general arrangement of piping, fittings, and specialties.

B. Where installing piping adjacent to chillers, allow space for service and maintenance.

C. Evaporator Fluid Connections:

1. Connect to evaporator inlet with shutoff valve, strainer, flexible connector, thermometer, and plugged tee with pressure gage.
2. Connect to evaporator outlet with shutoff valve, balancing valve, flexible connector, flow switch, thermometer, plugged tee with pressure gage, and drain connection with valve.
3. Make connections to water chiller with a union or flange.

D. Connect each drain connection with a drain valve, full size of drain connection.

E. Connect each chiller vent connection with an automatic vent, full size of vent connection.

3.4 ELECTRICAL POWER CONNECTIONS

A. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."

3.5 CONTROLS CONNECTIONS

A. Install control and electrical power wiring to field-mounted control devices.

B. Connect control wiring between chillers and other equipment to interlock operation as required to provide a complete and functioning system.

C. Connect control wiring between chiller control interface and DDC system for remote monitoring and control of chillers. Comply with requirements in Section 230923 "Direct Digital Control (DDC) System for HVAC."

3.6 PIPING FLUSHING PROCEDURE

A. Prior to connecting the multipipe unit to the building fluid loop, the piping shall be flushed with a detergent and hot water (110-130 F) mixture to remove previously accumulated dirt and other organic residue. In old piping systems with heavy encrustation of inorganic materials, consult a water treatment specialist for proper passivation and/or removal of these contaminants.

B. Prior to flushing, install a 30 mesh or finer Y-type strainer or equivalent in the system piping. During the flushing process, examine and clean the strainer periodically as necessary to remove collected residue. The flushing process shall take not less than 6 hours or until the strainers, when examined after each flushing, are clean. Old systems with heavy encrustation shall be flushed for a minimum of 24 hours or until the strainers run clean. Detergent and acid concentrations shall be used in strict accordance with the respective chemical manufacturer’s instructions. After flushing with detergent and/or dilute acid concentrations, the system loop shall be purged with clean water for at least one hour to ensure that all residual cleaning chemicals have been flushed out.

3.7 STARTUP SERVICE

A. Engage a factory-authorized service representative to perform startup service.

B. Inspect field-assembled components, equipment installation, and piping and electrical connections for proper assemblies, installations, and connections.

C. Complete installation and startup checks according to manufacturer's written instructions and perform the following:

1. Verify that refrigerant charge is sufficient and water chiller has been leak tested.
2. Verify that pumps are installed and functional.
3. Verify that thermometers and gages are installed.
4. Operate water chiller for run-in period.
5. Check bearing lubrication and oil levels.
6. Verify that refrigerant pressure relief device for chillers installed indoors is vented outside.
7. Verify proper motor rotation.
8. Verify static deflection of vibration isolators, including deflection during water chiller startup and shutdown.
9. Verify and record performance of chilled- and heat recovery condenser-water flow and low-temperature interlocks.
10. Verify and record performance of water chiller protection devices.
11. Test and adjust controls and safeties. Replace damaged or malfunctioning controls and equipment.

D. Visually inspect chiller for damage before starting. Repair or replace damaged components, including insulation. Do not start chiller until damage that is detrimental to operation has been corrected.

E. Prepare a written startup report that records results of tests and inspections.

3.8 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain water chillers. Video record the training sessions and provide electronic copy to Owner.

1. Instructor shall be factory trained and certified.
2. Provide not less than eight hours of training.
3. Train personnel in operation and maintenance and to obtain maximum efficiency in plant operation.
4. Provide instructional videos showing general operation and maintenance that are coordinated with operation and maintenance manuals.
5. Obtain Owner sign-off that training is complete.
6. Owner training shall be held at Project site.

END OF SECTIONs

SECTION 237343.16 - OUTDOOR, SEMI-CUSTOM AIR-HANDLING UNITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes outdoor, semi-custom air-handling units that are factory assembled using multiple section components; including:

1. Unit casings.
2. Fan, drive, and motor section.
3. Coil section.
4. Air filtration section.
5. Dampers.
6. Air-to-air energy recovery units.
7. Intake and relief air openings.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

1. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.
2. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
3. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
4. Include unit dimensions and weight.
5. Include cabinet material, metal thickness, finishes, insulation, and accessories.
6. Fans:

    a. Include certified fan-performance curves with system operating conditions indicated.
    b. Include certified fan-sound power ratings.
    c. Include fan construction and accessories.
    d. Include motor ratings, electrical characteristics, and motor accessories.

7. Include certified coil-performance ratings with system operating conditions indicated.
8. Include dampers, including housings, linkages, and operators.

B. Shop Drawings: For each outdoor, semi-custom air-handling unit.

1. Include plans, elevations, sections, and mounting and attachment details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Detail fabrication and assembly of outdoor, semi-custom air-handling units, as well as procedure and diagrams.
4. Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Source quality-control reports.

C. Startup service reports.

D. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For air-handling units to include in emergency, operation, and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Filters: One set for each air-handling unit.
2. Gaskets: One set for each access door.

1.7 WARRANTY

A. Warranty: Manufacturer agrees to repair or replace components of outdoor, semi-custom, air-handling unit that fail in materials or workmanship within specified warranty period.

1. Warranty Period for Entire Unit: Manufacturer's standard but not less than two years from date of Substantial Completion.
2. Warranty Period for Heat Wheels: Not less than five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. NFPA Compliance: Comply with NFPA 90A for design, fabrication, and installation of air-handling units and components.

C. ASHRAE 62.1 Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."

D. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

E. Casing Leakage Performance: ASHRAE 111, Class 6 leakage or better at plus or minus 8-inch wg.

2.2 CAPACITIES AND CHARACTERISTICS

A. As scheduled on drawings.

2.3 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Carrier Global Corporation.
2. Daikin Applied.
3. Trane.
4. YORK; brand of Johnson Controls International plc, Building Solutions North America.

B. Source Limitations: Obtain from single source from single manufacturer.

2.4 UNIT CASINGS

A. Frame: Modular and providing overall structural integrity without reliance on casing panels for structural support.

B. Base Rail:

1. Material: Galvanized steel.
2. Height: 6 inches.

C. Casing Joints: Hermetically sealed at each corner and around entire perimeter.

D. Double-Wall Construction:

1. Outside Casing Wall:

    a. Material: Galvanized Steel.
    b. Factory Finish: Provide manufacturer's painted or baked-on finish suitable for outdoor installation.

2. Inside Casing Wall:

    a. Material, Galvanized Steel: Minimum 18 gauge thick.

E. Roof: Cross-broken and pitched with "C" caps over joints to provide watertight seal.

F. Piping Vestibule: Insulated with same insulation and thickness as casing, 30 inches deep by full width of piping connections.

G. Casing Insulation:

1. Materials: Injected polyurethane foam insulation.
2. Casing Panel R-Value: Minimum R-13.
3. Insulation Thickness: 2 inches.
4. Thermal Break: Provide continuity of insulation with no through-casing metal in casing walls, floors, or roofs of air-handling unit.

H. Airstream Surfaces: Surfaces in contact with airstream shall comply with requirements in ASHRAE 62.1.

I. Static-Pressure Classifications:

1. For Unit Sections Upstream of Fans: Minus 4-inch wg.
2. For Unit Sections Downstream and Including Fans: 4-inch wg.

J. Doors and Windows:

1. Doors:

    a. Fabrication: Formed and reinforced, double-wall and insulated panels of same materials and thicknesses as casing.
    b. Hinges: A minimum of two ball-bearing hinges or stainless-steel piano hinge and two wedge-lever latches, operable from inside and outside. Arrange doors to be opened against airflow. Provide safety latch retainers on doors so that doors do not open uncontrollably.
    c. Gasket: Neoprene, applied around entire perimeters of panel frames.
    d. Size: Large enough to allow for unobstructed access for inspection and maintenance of air-handling unit's internal components. At least 24 inches wide by full height of unit casing up to a maximum height of 60 inches.

2. Locations and Applications:

    a. Fan Section: Doors.
    b. Coil Section: Doors.
    c. Access Section: Doors.
    d. Access Sections Immediately Upstream and Downstream of Coil Sections: Doors.

e. Damper Section: Doors.
f. Filter Section: Doors large enough to allow periodic removal and installation of filters.

3. Service Lights: LED vaporproof luminaire with individual switched junction box located inside, adjacent to each access door and panel.

a. Locations: Fan section.

4. Convenience Outlets: One 20-A duplex GFCI receptacle per location with junction box located on outside casing wall.

K. Condensate Drain Pans:

1. Location: Each type of cooling coil or energy recovery wheel.
2. Construction:

a. Double-wall, galvanized-steel or noncorrosive polymer sheet with space between walls filled with foam insulation and moisture-tight seal.

3. Slope: Minimum 0.125-in./ft. slope, to comply with ASHRAE 62.1, in at least two planes to collect condensate from cooling coils (including coil piping connections, coil headers, and return bends) and from humidifiers and to direct water toward drain connection.
4. Length: Extend drain pan downstream from leaving face for distance to comply with ASHRAE 62.1.
5. Width: Entire width of water producing device.
6. Depth: A minimum of 2 inches deep.
7. Pan-Top Surface Coating for Galvanized-Steel Drain Pans: Asphaltic waterproofing compound.
8. Units with stacked coils shall have an intermediate drain pan to collect condensate from top coil.

2.5 FAN, DRIVE, AND MOTOR SECTION

A. Fan and Drive Assemblies: Statically and dynamically balanced and designed for continuous operation at maximum-rated fan speed and motor horsepower.

B. Fans: Centrifugal, galvanized steel; mounted on solid-steel shaft.

1. Shafts: With field-adjustable alignment.

a. Turned, ground, and polished hot-rolled steel with keyway.

2. Housings, Plenum Fans: Steel frame and panel; fabricated without fan scroll and volute housing. Provide inlet screens for Type SWSI fans.
3. Plenum Fan Arrays: Uncontained as defined in AHRI 430. Steel or aluminum frame with inlet cone and structural framing around each fan built into an array of multiple fans.
4. Mounting: For internal vibration isolation. Factory-mount fans with manufacturer's standard restrained vibration isolation mounting devices having a minimum static deflection of 1 inch.
5. Shaft Lubrication Lines: Extended to a location outside the casing.

6. Flexible Connector: Factory fabricated with a fabric strip minimum 3-1/2 inches wide, attached to two strips of minimum 2-3/4-inch-wide by 0.028-inch-thick, galvanized-steel sheet.

    a. Flexible Connector Fabric: Glass fabric, double coated with neoprene. Fabrics, coatings, and adhesives shall comply with UL 181, Class 1.

        1) Fabric Minimum Weight: 26 oz./sq. yd..
        2) Fabric Minimum Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
        3) Fabric Minimum Service Temperature Range: Minus 40 to plus 200 deg F.

C. Drive, Direct: Factory-mounted, direct drive.

D. Motors:

1. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
2. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.
3. Enclosure Type: Open, dripproof.
4. Efficiency: Premium efficient as defined in NEMA MG 1.
5. Controllers, Electrical Devices, and Wiring: Comply with requirements for electrical devices and connections specified in electrical Sections.
6. Mount unit-mounted disconnect switches on interior of unit.

E. Variable-Frequency Motor Controller: Serving each fan individually in fan array.

1. Manufactured Units: Pulse-width modulated; variable torque for inverter-duty motors.
2. Output Rating: Three phase; 10 to 60 Hz, with voltage proportional to frequency throughout voltage range; maximum voltage equals input voltage.
3. Unit Operating Requirements:

    a. Internal Adjustability:

        1) Minimum Speed: 5 to 25 percent of maximum rpm.
        2) Maximum Speed: 80 to 100 percent of maximum rpm.
        3) Acceleration: 0.1 to 999.9 seconds.
        4) Deceleration: 0.1 to 999.9 seconds.
        5) Current Limit: 30 to minimum of 150 percent of maximum rating.

    b. Self-Protection and Reliability Features:

        1) Surge suppression.
        2) Loss of input signal protection.
        3) Under- and overvoltage trips.
        4) Variable-frequency motor controller and motor-overload/overtemperature protection.
        5) Critical frequency rejection.
        6) Loss-of-phase protection.
        7) Reverse-phase protection.

8) Motor-overtemperature fault.

c. Bidirectional autospeed search.
d. Torque boost.
e. Motor temperature compensation at slow speeds.

1) Panel-mounted operator station.
2) Historical logging information and displays.
3) Digital indicating devices.

f. Control Signal Interface: Electric.
g. Proportional Integral Directive (PID) control interface.
h. DDC system for HVAC Protocols for Network Communications: ASHRAE 135.

4. Line Conditioning:

a. Input line conditioning.
b. Output filtering.
c. EMI/RFI filtering.

2.6 COIL SECTION

A. General Requirements for Coil Section:

1. Comply with AHRI 410.
2. Fabricate coil section to allow removal and replacement of coil for maintenance and to allow in-place access for service and maintenance of coil(s).
3. For multizone units, provide air deflectors and air baffles to balance airflow across coils.
4. Coils shall not act as structural component of unit.

B. Heating Coils:

1. Glycol-Heating Water Coils:

a. Piping Connections: Same end of coil.
b. Tube Material: Copper.
c. Fin Type: Plate.
d. Fin Material: Aluminum.
e. Fin and Tube Joint: Mechanical bond.
f. Headers:

1) Cast iron with drain and air vent tappings.
2) Seamless copper tube with brazed joints, prime coated.
3) Fabricated steel, with brazed joints, prime coated.
4) Provide insulated cover to conceal exposed outside casings of headers.

g. Coil Working-Pressure Ratings: 200 psig, 325 deg F.
h. Coating: None.

C. Cooling Coils:

1. Glycol-Cooling Water Coil:

    a. Piping Connections: Same end of coil.
    b. Tube Material: Copper.
    c. Fin Type: Plate.
    d. Fin Material: Aluminum.
    e. Fin and Tube Joint: Mechanical bond.
    f. Headers:

        1) Cast iron with drain and air vent tappings.
        2) Seamless copper tube with brazed joints, prime coated.
        3) Fabricated steel, with brazed joints, prime coated.
        4) Provide insulated cover to conceal exposed outside casings of headers.

    g. Coatings: None.
    h. Working-Pressure Ratings: 200 psig, 325 deg F.

2.7 AIR FILTRATION SECTION

A. Panel Filters:

1. Description: Pleated factory-fabricated, self-supported, disposable air filters with holding frames.
2. Filter Unit Class: UL 900.
3. Media: Interlaced glass, synthetic, or cotton fibers coated with nonflammable adhesive.
4. Filter-Media Frame: Beverage board with perforated metal retainer, or metal grid, on outlet side.

B. Adhesive, Sustainability Projects: As recommended by air-filter manufacturer and with a VOC content of 80 g/L or less.

C. Side-Access Filter Mounting Frames:

1. Particulate Air Filter Frames: Match inner casing and outer casing material, and insulation thickness. Galvanized steel track.

    a. Prefilters: Incorporate an integral 2-inch-thick track with same access as primary filter.
    b. Sealing: Incorporate positive-sealing device to ensure seal between gasketed material on channels to seal top and bottom of filter cartridge frames to prevent bypass of unfiltered air.

2.8 DAMPERS

A. Dampers: Comply with requirements in Section 230923.12 "Control Dampers."

B. Damper Operators: Comply with requirements in Section 230923.12 "Control Dampers."

2.9 AIR-TO-AIR ENERGY RECOVERY UNITS

A. Energy Recovery Wheels:

1. Casing:

a. Integral purge section limiting carryover of exhaust air to between 0.05 percent at 1.6-inch wg and 0.20 percent at 4-inch wg differential pressure.
b. Casing seals on periphery of rotor, on duct divider, and on purge section.
c. Support vertical rotors on grease-lubricated ball bearings with extended grease fittings. Mount horizontal rotors on tapered roller bearing.

2. Rotor or Polymer: Segmented wheel, strengthened with radial spokes, with nontoxic, noncorrosive, silica-gel desiccant coating.
3. Drive: Fractional horsepower motor and gear reducer, with speed changed by variable-frequency controller. Permanently lubricated wheel bearings.
4. Controls:

a. Variable-frequency controller, factory mounted and wired, permitting input of field connected 4- to 20-mA or 1- to 10-V control signal.

2.10 INTAKE AND EXHAUST AIR OPENINGS

A. Provide hood, including moisture eliminator, over all unit intake and exhaust openings. Match material and finish of casing exterior.

2.11 MATERIALS

A. Steel:

1. ASTM A36/A36M for carbon structural steel.
2. ASTM A568/A568M for steel sheet.

B. Stainless Steel:

1. Manufacturer's standard grade for casing.
2. Manufacturer's standard type, ASTM A240/A240M for bare steel exposed to airstream or moisture.

C. Galvanized Steel: ASTM A653/A653M.

D. Aluminum: ASTM B209.

E. Comply with Section 230546 "Coatings for HVAC" for corrosion-resistant coating.

2.12 SOURCE QUALITY CONTROL

A. AHRI 430 Certification: Test, rate, and label air-handling units and their components in accordance with AHRI 430.

B. Fan Operating Limits: Classify fans in accordance with AMCA 99, Section 14.

C. Water Coils: Factory tested to 300 psig according to AHRI 410 and ASHRAE 33.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine casing insulation materials and filter media before air-handling unit installation. Reject insulation materials and filter media that are wet, moisture damaged, or mold damaged.

C. Examine roughing-in for hydronic and condensate drainage piping systems and electrical services to verify actual locations of connections before installation.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Roof: Install on elevated structural steel frame, level and secure. Secure units to upper structural members and provide elastomeric vibration isolation pads at each securement point.

B. Arrange installation of units to provide access space around air-handling units for service and maintenance.

C. Do not operate fan system until filters (temporary or permanent) are in place. Replace temporary filters used during construction and testing, with new, clean filters.

D. Connect duct to air-handling units with flexible connections. Comply with requirements in Section 233300 "Air Duct Accessories."

3.3 PIPING CONNECTIONS

A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties.

B. Where installing piping adjacent to air-handling unit, allow space for service and maintenance.

C. Connect piping to air-handling units mounted on vibration isolators with flexible connectors.

D. Connect condensate drain pans using NPS 1-1/4, ASTM B88, Type L copper tubing. Extend to nearest equipment or roof drain. Construct deep trap at connection to drain pan and install cleanouts at changes in direction.

E. Glycol-Heating and Glycol-Cooling Water Piping: Comply with applicable requirements in Section 232113 "Hydronic Piping" and Section 232116 "Hydronic Piping Specialties." Install shutoff valve and union or flange at each coil supply connection. Install balancing valve and union or flange at each coil return connection.

3.4 ELECTRICAL CONNECTIONS

A. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."

C. Install electrical devices furnished by manufacturer, but not factory mounted, according to NFPA 70 and NECA 1.

3.5 CONTROL CONNECTIONS

A. Install control and electrical power wiring to field-mounted control devices.

B. Connect control wiring according to Section 260523 "Control-Voltage Electrical Power Cables."

3.6 STARTUP SERVICE

A. Engage a factory-authorized service representative to perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.
2. Verify that shipping, blocking, and bracing are removed.
3. Verify that unit is secure on mountings and supporting devices and that connections to piping, ducts, and electrical systems are complete. Verify that proper thermal-overload protection is installed in motors, controllers, and switches.
4. Verify proper motor rotation direction, free fan wheel rotation, and smooth bearing operations. Reconnect fan drive system, align belts, and install belt guards.
5. Verify that bearings and other moving parts are lubricated with factory-recommended lubricants.
6. Verify that zone dampers fully open and close for each zone.
7. Verify that outdoor- and return-air mixing dampers open and close, and maintain minimum outdoor-air setting.
8. Comb coil fins for parallel orientation.
9. Install new, clean filters.
10. Verify that manual and automatic volume control and fire and smoke dampers in connected duct systems are in fully open position.

B. Starting procedures for air-handling units include the following:

1. Energize motor; verify proper operation of motor, drive system, and fan wheel. Adjust fan to indicated rpm.
2. Measure and record motor electrical values for voltage and amperage.
3. Manually operate dampers from fully closed to fully open position and record fan performance.

3.7 ADJUSTING

A. Adjust damper linkages for proper damper operation.

B. Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC" for air-handling system testing, adjusting, and balancing.

C. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.8 CLEANING

A. After completing system installation and testing, adjusting, and balancing air-handling unit and air-distribution systems and after completing startup service, clean air-handling units internally to remove foreign material and construction dirt and dust. Clean fan wheels, cabinets, dampers, coils, and filter housings, and install new, clean filters.

3.9 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.

B. Perform the following tests and inspections:

1. Leak Test: After installation, fill water and steam coils with water, and test coils and connections for leaks.
2. Fan Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
4. Air-handling unit and components will be considered defective if unit or components do not pass tests and inspections.
5. Prepare test and inspection reports.

3.10 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner’s maintenance personnel to adjust, operate, and maintain air-handling units. Provide 16 hours of training.

END OF SECTION

SECTION 238126 – SPLIT-SYSTEM AIR-CONDITIONERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes split-system air-conditioning and heat-pump units consisting of separate evaporator-fan and compressor-condenser components.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product indicated. Include rated capacities, operating characteristics, and furnished specialties and accessories. Include performance data in terms of capacities, outlet velocities, static pressures, sound power characteristics, motor requirements, and electrical characteristics. On data submittal sheets were more than one product is described, clearly annotate which product(s) is to be supplied.

C. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.

1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
2. Wiring Diagrams: For power, signal, and control wiring.

D. Provide equipment cut sheets to General Contractor for inclusion in project coordination drawings. Include all equipment dimensions, noting manufacturer’s clearance requirements, as well as location and sizes of all equipment connections.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Field quality-control reports.

C. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For split-system air-conditioning units to include in emergency, operation, and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Filters: One set(s) for each A/C unit.

1.7 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. ASHRAE Compliance:

1. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 4 - "Outdoor Air Quality," Section 5 - "Systems and Equipment," Section 6 - " Procedures," and Section 7 - "Construction and System Start-up."

C. ASHRAE/IES Compliance: Applicable requirements in ASHRAE/IES 90.1.

1.8 COORDINATION

A. Coordinate sizes and locations of roof curbs, equipment supports, and roof penetrations with actual equipment provided.

1.9 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of split-system air-conditioning units that fail in materials or workmanship within specified warranty period.

1. Warranty Period:

a. For Compressor: Five year(s) from date of Substantial Completion.
b. For Parts: Five year(s) from date of Substantial Completion.
c. For Labor: Two year(s) from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Trane Mitsubishi product indicated on Drawings or comparable product by one of the following:

1. Carrier Corporation; a unit of United Technologies Corp.
2. Fujitsu General American, Inc.
3. SANYO North America Corporation.
4. YORK; a Johnson Controls company.
5. Samsung.

2.2 INDOOR UNITS (5-TONS OR LESS)

A. Wall-Mounted, Evaporator-Fan Components:

1. Cabinet: Casing shall have a smooth front, while finish with removable panels on front and ends, and discharge drain pans with drain connection.
2. Refrigerant Coil: Copper tube, with mechanically bonded aluminum fins and thermal-expansion valve. Comply with ARI 206/110.
3. Fan: Direct drive, centrifugal.
4. Fan Motors:

    a. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
    b. Multitapped, multispeed with internal thermal protection and permanent lubrication.
    c. Enclosure Type: Totally enclosed, fan cooled.
    d. NEMA Premium (TM) efficient motors as defined in NEMA MG 1.
    e. Controllers, Electrical Devices, and Wiring: Comply with requirements for electrical devices and connections specified in electrical Sections.

5. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
6. Condensate Drain Pans:

    a. Single-wall, galvanized steel sheet.
    b. Drain Connection: Located at lowest point of pan and sized to prevent overflow.
    c. Provide manufacturer’s integral condensate lift pump, or separate lift pump integrated in lineset cover assembly.

7. Filters: Permanent, cleanable.

2.3 OUTDOOR UNITS (5-TONS OR LESS)

A. Air-Cooled, Compressor-Condenser Components:

1. Casing: Steel, finished with baked enamel in color selected by Architect, with removable panels for access to controls, weep holes for water drainage, and mounting holes in base. Provide brass service valves, fittings, and gage ports on exterior of casing.
2. Compressor: Hermetically sealed with crankcase heater and mounted on vibration isolation device. Compressor motor shall have thermal- and current-sensitive overload devices, start capacitor, relay, and contactor.

    a. Compressor Type: DC inverter-driven twin rotary.
    b. Refrigerant: R-454B
    c. Refrigerant Coil: Copper tube, with mechanically bonded aluminum fins and liquid subcooler. Comply with ARI 206/110.

3. Fan: Aluminum-propeller type, directly connected to motor.
4. Motor: Permanently lubricated, with integral thermal-overload protection.
5. Low Ambient Kit: Permits operation down to 0 deg F.

2.4 ACCESSORIES

A. Thermostat: Low voltage with subbase to control compressor and evaporator fan, with the following features:

1. Compressor time delay.
2. 24-hour time control of system stop and start.
3. Liquid-crystal display indicating temperature, set-point temperature, time setting, operating mode, and fan speed.
4. Fan-speed selection including auto setting.

B. Automatic-reset timer to prevent rapid cycling of compressor.

C. Refrigerant Line Kits: Soft-annealed copper suction and liquid lines factory cleaned, dried, pressurized, and sealed; factory-insulated suction line with flared fittings at both ends.

D. Drain Hose: For condensate.

2.5 REFRIGERANTS

A. ASHRAE 34, R-454B: Blend of R-32 (hydrofluorocarbon) and R-1234yf (hydrofluoroolefin).

2.6 REFRIGERANT LINESET COVERS

A. Interior Lineset Covers:

1. Interior linear duct designed specifically for enclosing refrigerant linesets. Fabricate from rigid polyvinyl chloride with rounded edges and snap in place fittings for a smooth finish. Cover shall be easily removable for future access without damaging duct assembly.

B. Exterior Lineset Covers:

1. Exterior heavy duty linear duct designed specifically for enclosing refrigerant linesets. Fabricate from heavy duty, rigid, polyvinyl chloride a UV and weather resistant exterior. Straight lengths of round duct shall be two piece units with snap lock seams. Fitting and splice covers shall be heavy duty, two-piece fittings secured with manufacturer's stainless steel screws.
2. Provide stainless steel escutcheon around duct penetration of exterior wall.
3. Finish Color: Ivory.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install units level and plumb.

B. Install evaporator-fan components using manufacturer's standard mounting devices securely fastened to building structure.

C. Install roof-mounted, compressor-condenser components on equipment supports specified in Section 077200 "Roof Accessories." Anchor units to supports with removable, cadmium-plated fasteners.

D. Equipment Mounting:

1. Comply with requirements for vibration isolation devices specified in Section 230548.13 "Vibration Controls for HVAC."

E. Install and connect precharged refrigerant tubing to component's quick-connect fittings. Install tubing to allow access to unit.

3.2 PIPING INSTALLATION

A. Install refrigerant piping according to ASHRAE 15.

B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicted otherwise. Where piping is indicated to be exposed, provide lineset covers.

D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

E. Install piping adjacent to machines to allow service and maintenance.

F. Install piping free of sags and bends.

G. Select system components with pressure rating equal to or greater than system operating pressure.

H. Install piping as short and direct as possible, with a minimum number of bends.

I. Install piping with adequate clearance between pipe and adjacent walls and hangers or between pipes for insulation installation.

J. Identify refrigerant piping according to Section 230553 "Identification for HVAC Piping and Equipment."

K. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 230517 "Sleeves and Sleeve Seals for HVAC Piping."

L. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 230518 "Escutcheons for HVAC Piping."

3.3 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, start-up, and adjust components, assemblies, and equipment installations, including connections.

B. Mechanical Contractor shall engage the manufacturer’s factory-authorized service representative to perform the following tests and inspections.

C. Tests and Inspections:

1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
2. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

D. Remove and replace malfunctioning units and retest as specified above.

E. Prepare test and inspection reports.

3.4 STARTUP SERVICE

A. Engage a factory-authorized service representative to perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.
2. Perform BacNet interface startup and programming. Coordinate with DDC Contractor for programming requirements.

3.5 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain units.

B. Provide 2 hours of training per unit.

END OF SECTION

SECTION 238219 - FAN COIL UNITS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Ductless fan coil units.
2. Ducted fan coil units.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include rated capacities, operating characteristics, and furnished specialties and accessories.

C. Shop Drawings:

1. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
2. Include diagrams for power, signal, and control wiring.

D. Provide equipment cut sheets to General Contractor for inclusion in project coordination drawings. Include all equipment dimensions, noting manufacturer’s clearance requirements, as well as location and sizes of all equipment connections.

1.3 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For fan coil units to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. Maintenance schedules and repair part lists for motors, coils, integral controls, and filters.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Fan Coil Unit Filters: Furnish two spare filters for each filter installed.

1.5 QUALITY ASSURANCE

A. Comply with NFPA 70.

B. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."

C. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

1.6 COORDINATION

A. Coordinate layout and installation of fan coil units and suspension system components with other construction that penetrates or is supported by ceilings, including light fixtures, HVAC equipment, fire-suppression-system components, and partition assemblies.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Factory-packaged and -tested units rated according to AHRI 440, ASHRAE 33, and UL 1995.

2.2 DUCTLESS FAN COIL UNITS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Trane, Inc., or comparable products scheduled on Drawings, by one of the following:

1. Carrier Global Corporation
2. Daikin Applied
3. Dunham-Bush, Inc
4. ENVIRO-TEC; brand of Johnson Controls International plc, Building Solutions North America
5. Nailor Industries Inc
6. Titus; brand of Johnson Controls International plc, Global Products

7. USA Coil & Air
8. YORK; brand of Johnson Controls International plc, Building Solutions North America

B. Coil Section Insulation:

1. 1/2-inch- thick, matte-finish, closed-cell foam complying with ASTM C1071 and attached with adhesive complying with ASTM C916.
2. Surface-Burning Characteristics: Insulation and adhesive shall have a combined maximum flame-spread index of 25 and smoke-developed index of 50 when tested according to ASTM E84 by a qualified testing agency.
3. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

C. Drain Pans: Plastic. Fabricate pans and drain connections to comply with ASHRAE 62.1.

D. Chassis: Galvanized steel where exposed to moisture, with baked-enamel finish and removable access panel where exposed. Floor-mounting units shall have leveling screws.

E. Cabinet: Steel with baked-enamel finish in manufacturer's standard paint color as selected by Architect where exposed.

1. Vertical Unit Front Panels: Removable, steel, with steel discharge grille and channel-formed edges, cam fasteners, and insulation on back of panel.
2. Horizontal Unit Bottom Panels: Fastened to unit with cam fasteners and hinge and attached with safety chain; with integral stamped discharge grilles.
3. Steel recessing flanges for recessing fan coil units into ceiling or wall.

F. Filters: Minimum arrestance and a minimum efficiency reporting value (MERV) according to ASHRAE 52.2 and all addendums.

1. MERV Rating: 6 when tested according to ASHRAE 52.2.
2. Pleated Cotton-Polyester Media: 90 percent arrestance and MERV 7.

G. Hydronic Coils: Copper tube, with mechanically bonded aluminum fins spaced no closer than 0.1 inch, rated for a minimum working pressure of 200 psig and a maximum entering-water temperature of 220 deg F. Include manual air vent and drain valve.

H. Fan and Motor Board: Removable.

1. Fan: Forward curved, double width, centrifugal; directly connected to motor. Thermoplastic or painted-steel wheels, and aluminum, painted-steel, or galvanized-steel fan scrolls.
2. Motor: Permanently lubricated, multispeed; resiliently mounted on motor board. Comply with requirements in Section 230500 "Common Work Results for HVAC."
3. Wiring Termination: Connect motor to chassis wiring with plug connection.

I. Control devices are specified in Section 230923 "Direct Digital Control (DDC) System for HVAC".

J. Electrical Connection: Factory wire motors and controls for a single electrical connection.

K. Capacities and Characteristics: As scheduled on Drawings.

2.3 DUCTED FAN COIL UNITS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Trane Inc., or comparable products scheduled on Drawings by one of the following:

1. Carrier Global Corporation
2. Daikin Applied
3. Dunham-Bush, Inc
4. ENVIRO-TEC; brand of Johnson Controls International plc, Building Solutions North America
5. Nailor Industries Inc
6. Titus; brand of Johnson Controls International plc, Global Products
7. USA Coil & Air
8. YORK; brand of Johnson Controls International plc, Building Solutions North America

B. Coil Section Insulation:

1. 1/2-inch- thick, matte-finish, closed-cell foam complying with ASTM C1071 and attached with adhesive complying with ASTM C916.
2. Surface-Burning Characteristics: Insulation and adhesive shall have a combined maximum flame-spread index of 25 and smoke-developed index of 50 when tested according to ASTM E84 by a qualified testing agency.
3. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

C. Drain Pans: Plastic. Fabricate pans and drain connections to comply with ASHRAE 62.1.

D. Chassis: Galvanized steel where exposed to moisture, with baked-enamel finish and removable access panel where exposed.

E. Cabinets: Steel with baked-enamel finish in manufacturer's standard paint color.

F. Filters: Minimum arrestance and a minimum efficiency reporting value (MERV) according to ASHRAE 52.2 and all addendums.

G. MERV Rating: 6 when tested according to ASHRAE 52.2.

1. Pleated Cotton-Polyester Media: 90 percent arrestance and MERV 7.

H. Hydronic Coils: Copper tube, with mechanically bonded aluminum fins spaced no closer than 0.1 inch, rated for a minimum working pressure of 200 psig and a maximum entering-water temperature of 220 deg F. Include manual air vent and drain.

I. Direct-Driven Fans: Double width, forward curved, centrifugal; with permanently lubricated, multispeed motor resiliently mounted in the fan inlet. Aluminum or painted-steel wheels, and painted-steel or galvanized-steel fan scrolls.

1. Motors: Comply with requirements in Section 230500 "Common Work Results for HVAC."

J. Control devices are specified in Section 230923 "Direct Digital Control (DDC) System for HVAC."

K. Electrical Connection: Factory wire motors and controls for a single electrical connection.

L. Capacities and Characteristics: As scheduled on Drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, with Installer present, to receive fan coil units for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for piping and electrical connections to verify actual locations before fan coil unit installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF FAN COIL UNITS

A. Install fan coil units level and plumb.

B. Install fan coil units to comply with NFPA 90A.

C. Suspend fan coil units from structure with elastomeric hangers. Vibration isolators are specified in Section 230548 "Vibration and Seismic Controls for HVAC Piping and Equipment."

D. Install new filters in each fan coil unit within two weeks after Substantial Completion.

3.3 CONNECTIONS

A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties. Specific connection requirements are as follows:

1. Install piping adjacent to machine to allow service and maintenance.
2. Connect piping to fan coil unit factory hydronic piping package. Install piping package if shipped loose.
3. Connect condensate drain to indirect waste.

    a. Install condensate trap of adequate depth to seal against fan pressure. Install cleanouts in piping at changes of direction.

B. Connect supply-air and return-air ducts to fan coil units with flexible duct connectors specified in Section 233300 "Air Duct Accessories." Comply with safety requirements in UL 1995 for duct connections.

C. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."

D. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and

Cables."

3.4 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
2. Test and adjust controls and safety devices. Replace damaged and malfunctioning controls and equipment.

B. Remove and replace malfunctioning units and retest as specified above.

3.5 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain fan coil units.

END OF SECTION

SECTION 238229 - RADIATORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes flat-pipe steel radiators.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include rated capacities, operating characteristics, furnished specialties, and accessories.

C. Shop Drawings:

1. Include plans, elevations, sections, and details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Indicate location and size of each field connection.
4. Indicate location and arrangement of piping valves and specialties.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Field quality-control reports.

C. Provide equipment cut sheets to General Contractor for inclusion in project coordination drawings. Include all equipment dimensions, noting manufacturer’s clearance requirements, as well as location and sizes of all equipment connections. Coordination drawing requirements are in Section 013100 “Project Management and Coordination.”

PART 2 - PRODUCTS

2.1 FLAT-PIPE STEEL RADIATORS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Sterling product scheduled on Drawings, or comparable product by one of the following:

1. Quincy Hydronic Technology Inc
2. Runtal North America, Inc.
3. Zehnder Group, Inc.

B. Heating Elements: Steel, welded and formed into flat, square, steel header with minimum thickness of 0.109 inch. Include threaded piping and air-vent connections.

1. Working Pressure:

a. 56 psig; 0.048 inch.

C. Mounting: Wall brackets or floor pedestals as scheduled on Drawings with maximum spacing of 36 inches.

D. Finish: Baked-enamel finish in manufacturer's standard color as selected by Architect.

E. Accessories:

1. Steel piping and trim covers finished to match radiator finish.
2. Manufacturer’s screw on air vent.
3. Manufacturer’s perforated top grille finished to match radiator finish.

F. Capacity and Characteristics: As scheduled on Drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas to receive radiators for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for hydronic-piping connections to verify actual locations before installation of radiators.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install units level and plumb.

B. Install piping covers.

3.3 CONNECTIONS

A. Piping installation requirements are specified in Section 232113 "Hydronic Piping" and Section 232116 "Hydronic Piping Specialties." Drawings indicate general arrangement of piping, fittings, and specialties.

B. Connect radiators and components to piping according to Section 232113 "Hydronic Piping" and Section 232116 Hydronic Piping Specialties."

1. Install shutoff valves on inlet and outlet, and balancing valve on outlet.

C. Install control valves as required by Section 230923.11 "Control Valves."

D. Install piping adjacent to radiators to allow service and maintenance.

3.4 FIELD QUALITY CONTROL

A. Perform the following field tests and inspections:

1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.

B. Units will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports.

END OF SECTION

SECTION 238236 – FINNED-TUBE RADIATION HEATERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes, finned-tube radiation heaters.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: On data submittal sheets where more than one product is to be described, clearly annotate which product(s) is to be supplied. For each type of product.

1. Include rated capacities, operating characteristics, furnished specialties, and accessories.

C. Shop Drawings:

1. Include plans, elevations, sections, and details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include details and dimensions of custom-fabricated enclosures.
4. Indicate location and size of each field connection.
5. Indicate location and arrangement of piping valves and specialties.
6. Indicate location and arrangement of integral controls.
7. Include enclosure joints, corner pieces, access doors, and other accessories.
8. Include diagrams for power, signal, and control wiring.

D. Color Samples for Initial Selection: For finned-tube radiation heaters with factory-applied color finishes.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Floor plans and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Structural members, including wall construction, to which finned-tube radiation heaters will be attached.
2. Method of attaching finned-tube radiation heaters to building structure.
3. Penetrations of fire-rated wall and floor assemblies.

C. Field quality-control reports.

PART 2 - PRODUCTS

2.1 HOT-WATER FINNED-TUBE RADIATION HEATERS

A. Products: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

1. Sterling HVAC Products; a Mestek company.
2. Vulcan Radiator; a Master Company.

B. Performance Ratings: Rate finned-tube radiation heaters according to Hydronics Institute's "I=B=R Testing and Rating Standard for Finned-Tube (Commercial) Radiation."

C. Heating Elements: Copper tubing mechanically expanded into flanged collars of evenly spaced aluminum fins resting on element supports. One end of tube shall be belled.

1. Refer to schedules on Drawings for finned-tube radiation heater details

D. Element Supports: Ball-bearing cradle type to permit longitudinal movement on enclosure brackets.

E. Front Panel: Minimum 0.0528-inch-thick steel.

F. Floor-Mounted Pedestals: Conceal insulated piping at maximum 36-inch spacing. Pedestal-mounted back panel shall be solid panel matching front panel. Provide stainless-steel escutcheon for floor openings at pedestals.

G. Support Brackets: Locate at maximum 36-inch spacing to support front panel and element. Provide alternate cradle to allow the return pipe to run below the element.

H. Finish: Baked-enamel finish in manufacturer's custom color as selected by Architect.

I. Access Doors: Factory made, permanently hinged with tamper-resistant fastener, minimum size 6 by 7 inches, integral with enclosure.

J. Enclosure Style: Flat top.

K. Accessories: Filler sections, corners, relay sections, and splice plates all matching the enclosure and grille finishes.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas to receive finned-tube radiation heaters for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for hydronic-piping connections to verify actual locations before installation of finned-tube radiation heaters.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 FINNED-TUBE RADIATION HEATER INSTALLATION

A. Install units level and plumb.

B. Install enclosure continuously around corners, using outside and inside corner fittings.

C. Join sections with splice plates and filler pieces to provide continuous enclosure.

D. Install access doors for access to valves.

E. Install enclosure continuously from wall to wall.

F. Terminate enclosures with manufacturer's end caps except where enclosures are indicated to extend to adjoining walls.

G. Install valves within reach of access door provided in enclosure.

H. Install air-seal gasket between wall and recessed flanges or front cover of fully recessed unit.

3.3 CONNECTIONS

A. Piping installation requirements are specified in Section 232113 "Hydronic Piping" and Section 232116 "Hydronic Piping Specialties." Drawings indicate general arrangement of piping, fittings, and specialties.

B. Connect hot-water finned-tube radiation heaters and components to piping according to Section 232113 "Hydronic Piping" and Section 232116 "Hydronic Piping Specialties."

1. Install shutoff valves on inlet and outlet, and balancing valve on outlet.

C. Install control valves as required by Section 230923.11 "Control Valves."

D. Install piping adjacent to finned-tube radiation heaters to allow service and maintenance.

3.4 FIELD QUALITY CONTROL

A. Perform the following field tests and inspections:

1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.

B. Units will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports.

END OF SECTION

SECTION 238239.13 - CABINET UNIT HEATERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Cabinet unit heaters with centrifugal fans and hot-water heating coils.

1.2 DEFINITIONS

A. CWP: Cold working pressure.

B. DDC: Direct digital control.

C. PTFE: Polytetrafluoroethylene plastic.

D. TFE: Tetrafluoroethylene plastic.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied.

1. Include rated capacities, operating characteristics, furnished specialties, and accessories.

C. Shop Drawings:

1. Include plans, elevations, sections, and details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include location and size of each field connection.
4. Include details of anchorages and attachments to structure and to supported equipment.
5. Include equipment schedules to indicate rated capacities, operating characteristics, furnished specialties, and accessories.
6. Indicate location and arrangement of piping valves and specialties.
7. Wiring Diagrams: Power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Field quality-control reports.

C. Provide equipment cut sheets to General Contractor for inclusion in project coordination drawings. Include all equipment dimensions, noting manufacturer's clearance requirements, as well as location and sizes of all equipment connections. Coordination drawing requirements are in Section 013100 "Project Management and Coordination."

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 "Submittal Procedures" and the individual sections specifying the work.

B. Operation and Maintenance Data: For cabinet unit heaters to include in emergency, operation, and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Cabinet Unit-Heater Filters: Furnish one spare filter for each filter installed.

PART 2 - PRODUCTS

2.1 CABINET UNIT HEATERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Trane product scheduled on Drawings, or comparable product by one of the following:

1. Airtherm; a Mestek company
2. Carrier Global Corporation
3. Engineered Air
4. Marley Engineered Products
5. Rosemex Products
6. Sterling
7. USA Coil & Air

B. Heaters: Factory-assembled and -tested unit complying with AHRI 440.

C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 PERFORMANCE REQUIREMENTS

A. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."

B. ASHRAE/IESNA 90.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

2.3 COIL SECTION INSULATION

A. Insulation Materials:

1. Duct-Liner-Type, Glass-Fiber Insulation: ASTM C1071; surfaces exposed to airstream are to have aluminum-foil facing or erosion-resistant coating to prevent erosion of glass fibers.

    a. Thickness: 1/2 inch.
    b. Thermal Conductivity (k-Value): 0.26 Btu x in./h x sq. ft. at 75 deg F mean temperature.
    c. Fire-Hazard Classification: Maximum flame-spread index of 25 and smoke-developed index of 50 when tested in accordance with ASTM E84.
    d. Adhesive: Comply with ASTM C916 and with NFPA 90A or NFPA 90B.
    e. Airstream Surfaces: Surfaces in contact with the airstream comply with requirements in ASHRAE 62.1.

2. Flexible Elastomeric Insulation: Comply with NFPA 90A or NFPA 90B. Unicellular polyethylene thermal plastic, preformed sheet insulation complying with ASTM C534, Type II, except for density.

    a. Thickness: 1/2 inch.
    b. Thermal Conductivity (k-Value): 0.24 Btu x in./h x sq. ft. at 75 deg F mean temperature.
    c. Fire-Hazard Classification: Maximum flame-spread index of 25 and smoke-developed index of 50 when tested in accordance with ASTM C411.
    d. Adhesive: As recommended by insulation manufacturer and complying with NFPA 90A or NFPA 90B.

    e. Airstream Surfaces: Surfaces in contact with the airstream comply with requirements in ASHRAE 62.1.

2.4 CABINETS

A. Material: Steel with baked-enamel finish with manufacturer's standard paint, in color selected by Architect.

1. Vertical Unit, Exposed Front Panels: Minimum 0.0528-inch-thick galvanized sheet steel, removable panels with channel-formed edges secured with tamperproof cam fasteners.
2. Horizontal Unit, Exposed Bottom Panels: Minimum 0.0528-inch-thick galvanized sheet steel, removable panels secured with tamperproof cam fasteners and safety chain.
3. Control Access Door: Key operated.
4. Base: Minimum 0.0528-inch-thick steel, finished to match cabinet, 4 inches high with leveling bolts.

2.5 FILTERS

A. Minimum Efficiency Reporting Value: In accordance with ASHRAE 52.2.

B. Material:

1. Pleated cotton-polyester media, MERV 7.

2.6 COILS

A. Hot-Water Coil: Copper tube, with mechanically bonded aluminum fins spaced no closer than 0.1 inch and rated for a minimum working pressure of 200 psig and a maximum entering-water temperature of 220 deg F. Include manual air vent and drain.

2.7 CONTROLS

A. Fan and Motor Board: Removable.

1. Fan: Forward curved, double width, centrifugal, directly connected to motor; thermoplastic or painted-steel wheels and aluminum, painted-steel, or galvanized-steel fan scrolls.
2. Motor: Permanently lubricated, multispeed; resiliently mounted on motor board. Comply with requirements in Section 230500 "Common Work Results for HVAC."
3. Wiring Terminations: Connect motor to chassis wiring with plug connection.

B. Control devices and operational sequences are specified in Section 230923 "Direct Digital Control (DDC) System for HVAC".

C. Electrical Connection: Factory-wired motors and controls for a single field connection.

2.8 CAPACITIES AND CHARACTERISTICS

A. As scheduled on Drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas to receive cabinet unit heaters for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for piping and electrical connections to verify actual locations before unit-heater installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF CABINET UNIT HEATERS

A. Install cabinet unit heaters to comply with NFPA 90A.

B. Suspend cabinet unit heaters from structure with elastomeric hangers. Vibration isolators are specified in Section 230548.13 "Vibration Controls for HVAC."

C. Install new filters in each fan-coil unit within two weeks of Substantial Completion.

3.3 CONNECTIONS

A. Piping installation requirements are specified in Section 232113 "Hydronic Piping" and Section 232116 "Hydronic Piping Specialties." Drawings indicate general arrangement of piping, fittings, and specialties.

B. Install piping adjacent to machine to allow service and maintenance.

C. Comply with safety requirements in UL 1995.

D. Unless otherwise indicated, install union and ball valve on supply-water connection and union, ball valve, and calibrated balancing valve on return-water connection of cabinet unit heater. Hydronic specialties are specified in Section 232113 “Hydronic Piping” and Section 232116 "Hydronic Piping Specialties."

E. Ground equipment in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

F. Connect wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

3.4 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.

B. Units will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports.

3.5 ADJUSTING

A. Adjust initial temperature set points.

3.6 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain cabinet unit heaters.

END OF SECTION

SECTION 238239.16 – PROPELLER UNIT HEATERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes propeller unit heaters with hot-water coils.

1.3 DEFINITIONS

A. CWP: Cold working pressure.

B. PTFE: Polytetrafluoroethylene plastic.

C. TFE: Tetrafluoroethylene plastic.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: On data submittal sheets where more than one product is described, clearly annotate which product(s) is to be supplied. For each type of product.

1. Include rated capacities, operating characteristics, furnished specialties, and accessories.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Floor plans, reflected ceiling plans, and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Suspended ceiling components.
2. Structural members to which cabinet unit heaters will be attached.
3. Method of attaching hangers to building structure.
4. Size and location of initial access modules for acoustical tile.
5. Items penetrating finished ceiling, including the following:

a. Lighting fixtures.

b. Air outlets and inlets.
c. Speakers.
d. Sprinklers.
e. Access panels.

C. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For propeller unit heaters to include in emergency, operation, and maintenance manuals.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:

1. Sterling; a Mestek company.
2. Modine Manufacturing Co.
3. Trane.

2.2 DESCRIPTION

A. Assembly including casing, coil, fan, and motor in vertical and horizontal discharge configuration with adjustable discharge louvers.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.3 PERFORMANCE REQUIREMENTS

A. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."

B. ASHRAE/IESNA 90.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

2.4 HOUSINGS

A. Finish: Manufacturer's standard baked enamel applied to factory-assembled and -tested propeller unit heaters before shipping.

B. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

C. Discharge Louver: Adjustable fin diffuser for horizontal units and conical diffuser for vertical units.

2.5 COILS

A. General Coil Requirements: Test and rate hot-water propeller unit-heater coils according to ASHRAE 33.

B. Hot-Water Coil: Copper tube, minimum 0.025-inch wall thickness, with mechanically bonded aluminum fins spaced no closer than 0.1 inch and rated for a minimum working pressure of 200 psig and a maximum entering-water temperature of 325 deg F, with manual air vent. Test for leaks to 350 psig underwater.

2.6 FAN AND MOTOR

A. Fan: Propeller type with aluminum wheel directly mounted on motor shaft in the fan venturi.

B. Motor: Permanently lubricated. Comply with requirements in Section 230513 "Common Motor Requirements for HVAC Equipment."

2.7 CONTROLS

A. Control devices are specified in Section 230923 "Direct Digital Control (DDC) System for HVAC."

B. Operational control sequences are indicated on the Drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas to receive propeller unit heaters for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for piping and electrical connections to verify actual locations before unit-heater installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install propeller unit heaters to comply with NFPA 90A.

B. Install propeller unit heaters level and plumb.

C. Suspend propeller unit heaters from structure with all-thread hanger rods and elastomeric hangers. Hanger rods and attachments to structure are specified in Section 230529 "Hangers and Supports for HVAC Piping and Equipment."

3.3 CONNECTIONS

A. Drawings indicate general arrangement of piping, fittings, and specialties. Piping installation requirements are specified in the following Sections:

1. Section 232113 "Hydronic Piping."
2. Section 232116 "Hydronic Piping Specialties."

B. Install piping adjacent to machine to allow service and maintenance.

C. Connect piping to propeller unit heater's factory, hot-water piping package. Install the piping package if shipped loose.

D. Comply with safety requirements in UL 1995.

E. Unless otherwise indicated, install union and ball valve on supply-water connection and union and calibrated balancing valve on return-water connection of propeller unit heater. Hydronic specialties are specified in Section 232113 "Hydronic Piping" and Section 232116 "Hydronic Piping Specialties."

F. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."

G. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

3.4 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
2. Test and adjust controls and safety devices. Replace damaged and malfunctioning controls and equipment.

B. Units will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports.

3.5 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain propeller unit heaters. Provide one hour of training for each unit installed.

END OF SECTION

SECTION 260010 - SUPPLEMENTAL REQUIREMENTS FOR ELECTRICAL

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Requirements generally applicable to all electrical Work on the Project, including but not limited to Work specified in Divisions 26, 27, and 28.

1.2 REFERENCES

A. Abbreviations and Acronyms for Electrical Terms and Units of Measure:

1. 8P8C: An 8-position 8-contact modular jack.
2. A: Ampere, unit of electrical current.
3. AC or ac: Alternating current.
4. AFCI: Arc-fault circuit interrupter.
5. AIC: Ampere interrupting capacity.
6. AL, Al, or ALUM: Aluminum.
7. ASD: Adjustable-speed drive.
8. ATS: Automatic transfer switch.
9. AWG: American wire gauge; see ASTM B258.
10. BAS: Building automation system.
11. BIL: Basic impulse insulation level.
12. BIM: Building information modeling.
13. BMS: Building management system.
14. CAD: Computer-aided design or drafting.
15. CATV: Community antenna television.
16. CB: Circuit breaker.
17. cd: Candela, the SI fundamental unit of luminous intensity.
18. CO/ALR: Copper-aluminum, revised.
19. COPS: Critical operations power system.
20. CU or Cu: Copper.
21. CU-AL or AL-CU: Copper-aluminum.
22. dB: Decibel, a unitless logarithmic ratio of two electrical, acoustical, or optical power values.
23. dB(A-weighted) or dB(A): Decibel acoustical sound pressure level with A-weighting applied in accordance with IEC 61672-1.
24. dB(adjusted) or dBa: Decibel weighted absolute noise power with respect to 3.16 pW (minus 85 dBm).
25. dBm: Decibel absolute power with respect to 1 mW.
26. DC or dc: Direct current.
27. DCOA: Designated critical operations area.
28. DDC: Direct digital control (HVAC).
29. EGC: Equipment grounding conductor.
30. ELV: Extra-low voltage.

31. EMF: Electromotive force.
32. EMI: Electromagnetic interference.
33. EMP: Electrical maintenance program (operation and maintenance); electromagnetic pulse (transient analysis).
34. EPS: Emergency power supply.
35. EPSS: Emergency power supply system.
36. ESS: Energy storage system.
37. EV: Electric vehicle.
38. EVPE: Electric vehicle power export equipment.
39. EVSE: Electric vehicle supply equipment.
40. FACU: Fire-alarm control unit.
41. fc: Footcandle, an internationally recognized unit of illuminance equal to one lumen per square foot or 10.76 lx. The simplified conversion 1 fc = 10 lx in the Specifications is common practice and considered adequate precision for building construction activities. When there are conflicts, lux is the primary unit; footcandle is specified for convenience.
42. FLC: Full-load current.
43. ft: Foot.
44. ft-cd: Foot-candle, the antiquated U.S. standard unit of illuminance, equal to one international candle measured at a distance of one foot, that was superseded in 1948 by the unit "footcandle" when the SI unit candela (cd) replaced the international candle; see "fc."
45. FTP: File transfer protocol.
46. GEC: Grounding electrode conductor.
47. GFCI: Ground-fault circuit interrupter.
48. GFPE: Ground-fault protection of equipment.
49. GND: Ground.
50. HACR: Heating, air conditioning, and refrigeration.
51. HDPE: High-density polyethylene.
52. HID: High-intensity discharge.
53. HP or hp: Horsepower.
54. HVAC: Heating, ventilating, and air conditioning.
55. Hz: Hertz.
56. IBT: Intersystem bonding termination.
57. ICT: Information and communications technology.
58. inch: Inch. To avoid confusion, the abbreviation "in." is not used.
59. I/O: Input/output.
60. IP: Ingress protection rating (enclosures); Internet protocol (communications).
61. IR: Infrared.
62. IS: Intrinsically safe.
63. IT&R: Inspecting, testing, and repair.
64. ITE: Information technology equipment.
65. kAIC: Kiloampere interrupting capacity.
66. kcmil or MCM: One thousand circular mils.
67. kV: Kilovolt.
68. kVA: Kilovolt-ampere.
69. kvar: Kilovolt-ampere reactive.
70. kW: Kilowatt.
71. kWh: Kilowatt-hour.
72. LAN: Local area network.
73. lb: Pound (weight).
74. lbf: Pound (force).

75. LCD: Liquid-crystal display.
76. LCDI: Leakage-current detector-interrupter.
77. LED: Light-emitting diode.
78. Li-ion: Lithium-ion.
79. lm: Lumen, the SI-derived unit of luminous flux.
80. LNG: Liquefied natural gas.
81. LP-Gas: Liquefied petroleum gas.
82. LRC: Locked-rotor current.
83. LV: Low voltage.
84. lx: Lux, the SI-derived unit of illuminance equal to one lumen per square meter.
85. m: Meter.
86. MCC: Motor-control center.
87. MDC: Modular data center.
88. MG set: Motor-generator set.
89. MIDI: Musical instrument digital interface.
90. MLO: Main lugs only.
91. MPEG-2: Abbreviation for the ISO/IEC Moving Picture Experts Group's standard for generic coding of moving pictures and associated audio information (ISO/IEC 13818) released in 1995 and used for most over-the-air and satellite broadcast digital television.
92. MPEG-4: Abbreviation for the ISO/IEC Moving Picture Experts Group's standard framework for coding of audio-visual objects (ISO/IEC 14496) released in 1999, with digital rights management and more advanced compression algorithms than MPEG-2.
93. MOV: Metal-oxide varistor.
94. MV: Medium voltage.
95. MVA: Megavolt-ampere.
96. mW: Milliwatt.
97. MW: Megawatt.
98. MWh: Megawatt-hour.
99. N.C.: Normally closed.
100. Ni-Cd: Nickel-cadmium.
101. Ni-MH: Nickel-metal hydride.
102. NIU: Network interface unit.
103. N.O.: Normally open.
104. NPT: National (American) standard pipe taper.
105. OCPD: Overcurrent protective device.
106. ONT: Optical network terminal.
107. PC: Personal computer.
108. PCS: Power conversion system.
109. PCU: Power-conditioning unit.
110. PF or pf: Power factor.
111. PHEV: Plug-in hybrid electric vehicle.
112. PLC: Programmable logic controller.
113. PLFA: Power-limited fire alarm.
114. PoE: Power over Ethernet.
115. POTS: Plain old telephone service. See "public switched telephone network" definition.
116. PSTN: Public switched telephone network.
117. PV: Photovoltaic.
118. PVC: Polyvinyl chloride.
119. pW: Picowatt.
120. RFI: (electrical) Radio-frequency interference; (contract) Request for interpretation.
121. RMS or rms: Root-mean-square.

122. RPM or rpm: Revolutions per minute.
123. SCADA: Supervisory control and data acquisition.
124. SCCR: Short-circuit current rating.
125. SCR: Silicon-controlled rectifier.
126. SPD: Surge protective device.
127. sq.: Square.
128. SWD: Switching duty.
129. TCP/IP: Transmission Control Protocol/Internet Protocol.
130. TEFC: Totally enclosed fan-cooled.
131. TR: Tamper resistant.
132. TVSS: Transient voltage surge suppressor.
133. UL: (standards) UL Standards & Engagement Inc.; (product categories) UL, LLC.
134. UL CCN: UL Category Control Number.
135. UPS: Uninterruptible power supply.
136. USB: Universal serial bus.
137. UV: Ultraviolet.
138. V: Volt, unit of electromotive force.
139. V(ac): Volt, alternating current.
140. V(dc): Volt, direct current.
141. VA: Volt-ampere, unit of complex electrical power.
142. VAR: Volt-ampere reactive, unit of reactive electrical power.
143. VFC: Variable-frequency controller.
144. VOM: Volt-ohm-multimeter.
145. VoIP: Voice over Internet Protocol.
146. VPN: Virtual private network.
147. VRLA: Valve regulated lead acid; also called "sealed lead acid (SLA)" or "valve regulated sealed lead acid."
148. W: Watt, unit of real electrical power.
149. WAN: Wide area network.
150. Wh: Watt-hour, unit of electrical energy usage.
151. WPT: Wireless power transfer.
152. WPTE: Wireless power transfer equipment.
153. WR: Weather resistant.

B. Abbreviations and Acronyms for Electrical Raceway Types:

1. EMT: Electrical metallic tubing.
2. EMT-A: Aluminum electrical metallic tubing.
3. EMT-S: Steel electrical metallic tubing.
4. EMT-SS: Stainless steel electrical metallic tubing.
5. ENT: Electrical nonmetallic tubing.
6. EPEC: Electrical HDPE underground conduit (thin wall).
7. EPEC-A: Type A electrical HDPE underground conduit.
8. EPEC-B: Type B electrical HDPE underground conduit.
9. ERMC: Electrical rigid metal conduit.
10. ERMC-A: Aluminum electrical rigid metal conduit.
11. ERMC-S: Steel electrical rigid metal conduit.
12. ERMC-S-G: Galvanized-steel electrical rigid metal conduit.
13. ERMC-S-PVC: PVC-coated-steel electrical rigid metal conduit.
14. ERMC-SS: Stainless steel electrical rigid metal conduit.
15. FMC: Flexible metal conduit.

16. FMC-A: Aluminum flexible metal conduit.
17. FMC-S: Steel flexible metal conduit.
18. FMT: Steel flexible metallic tubing.
19. FNMC: Flexible nonmetallic conduit. See "LFNC."
20. HDPE: HDPE underground conduit (thick wall).
21. HDPE-40: Schedule 40 HDPE underground conduit.
22. HDPE-80: Schedule 80 HDPE underground conduit.
23. IMC: Steel electrical intermediate metal conduit.
24. LFMC: Liquidtight flexible metal conduit.
25. LFMC-A: Aluminum liquidtight flexible metal conduit.
26. LFMC-S: Steel liquidtight flexible metal conduit.
27. LFMC-SS: Stainless steel liquidtight flexible metal conduit.
28. LFNC: Liquidtight flexible nonmetallic conduit.
29. LFNC-A: Layered (Type A) liquidtight flexible nonmetallic conduit.
30. LFNC-B: Integral (Type B) liquidtight flexible nonmetallic conduit.
31. LFNC-C: Corrugated (Type C) liquidtight flexible nonmetallic conduit.
32. PVC: Rigid PVC conduit.
33. PVC-40: Schedule 40 rigid PVC conduit.
34. PVC-80: Schedule 80 rigid PVC Conduit.
35. PVC-A: Type A rigid PVC concrete-encased conduit.
36. PVC-EB: Type EB rigid PVC concrete-encased underground conduit.
37. RGS: See ERMC-S-G.
38. RMC: See ERMC.
39. RTRC: Reinforced thermosetting resin conduit.
40. RTRC-AG: Low-halogen, aboveground reinforced thermosetting resin conduit.
41. RTRC-AG-HW: Heavy wall, low-halogen, aboveground reinforced thermosetting resin conduit.
42. RTRC-AG-SW: Standard wall, low-halogen, aboveground reinforced thermosetting resin conduit.
43. RTRC-AG-XW: Extra heavy wall, low-halogen, aboveground reinforced thermosetting resin conduit.
44. RTRC-BG: Low-halogen, belowground reinforced thermosetting resin conduit.

C. Abbreviations and Acronyms for Electrical Single-Conductor and Multiple-Conductor Cable Types:

1. AC: Armored cable.
2. CATV: Coaxial general-purpose cable.
3. CATVP: Coaxial plenum cable.
4. CATVR: Coaxial riser cable.
5. CI: Circuit integrity cable.
6. CL2: Class 2 cable.
7. CL2P: Class 2 plenum cable.
8. CL2R: Class 2 riser cable.
9. CL2X: Class 2 cable, limited use.
10. CL3: Class 3 cable.
11. CL3P: Class 3 plenum cable.
12. CL3R: Class 3 riser cable.
13. CL3X: Class 3 cable, limited use.
14. CM: Communications general-purpose cable.
15. CMG: Communications general-purpose cable.

16. CMP: Communications plenum cable.
17. CMR: Communications riser cable.
18. CMUC: Under-carpet communications wire and cable.
19. CMX: Communications cable, limited use.
20. DG: Distributed generation cable.
21. FC: Flat cable.
22. FCC: Flat conductor cable.
23. FPL: Power-limited fire-alarm cable.
24. FPLP: Power-limited fire-alarm plenum cable.
25. FPLR: Power-limited fire-alarm riser cable.
26. IGS: Integrated gas spacer cable.
27. ITC: Instrumentation tray cable.
28. ITC-ER: Instrumentation tray cable, exposed run.
29. MC: Metal-clad cable.
30. MC-HL: Metal-clad cable, hazardous location.
31. MI: Mineral-insulated, metal-sheathed cable.
32. MTW: (machine tool wiring) Moisture-, heat-, and oil-resistant thermoplastic cable.
33. MV: Medium-voltage cable.
34. NM: Nonmetallic sheathed cable.
35. NMC: Nonmetallic sheathed cable with corrosion-resistant nonmetallic jacket.
36. NMS: Nonmetallic sheathed cable with signaling, data, and communications conductors, plus power or control conductors.
37. NPLF: Non-power-limited fire-alarm circuit cable.
38. NPLFP: Non-power-limited fire-alarm circuit cable for environmental air spaces.
39. NPLFR: Non-power-limited fire-alarm circuit riser cable.
40. NUCC: Nonmetallic underground HDPE conduit with conductors.
41. OFC: Conductive optical fiber general-purpose cable.
42. OFCG: Conductive optical fiber general-purpose cable.
43. OFCP: Conductive optical fiber plenum cable.
44. OFCR: Conductive optical fiber riser cable.
45. OFN: Nonconductive optical fiber general-purpose cable.
46. OFNG: Nonconductive optical fiber general-purpose cable.
47. OFNP: Nonconductive optical fiber plenum cable.
48. OFNR: Nonconductive optical fiber riser cable.
49. P: Marine shipboard cable.
50. PLTC: Power-limited tray cable.
51. PLTC-ER: Power-limited tray cable, exposed run.
52. PV: Photovoltaic cable.
53. RHH: (high heat) Thermoset rubber, heat-resistant cable.
54. RHW: Thermoset rubber, moisture-resistant cable.
55. SA: Silicone rubber cable.
56. SE: Service-entrance cable.
57. SER: Service-entrance cable, round.
58. SEU: Service-entrance cable, flat.
59. SIS: Thermoset cable for switchboard and switchgear wiring.
60. TBS: Thermoplastic cable with outer braid.
61. TC: Tray cable.
62. TC-ER: Tray cable, exposed run.
63. TC-ER-HL: Tray cable, exposed run, hazardous location.
64. THW: Thermoplastic, heat- and moisture-resistant cable.
65. THHN: Thermoplastic, heat-resistant cable with nylon jacket outer sheath.

66. THHW: Thermoplastic, heat- and moisture-resistant cable.
67. THWN: Thermoplastic, moisture- and heat-resistant cable with nylon jacket outer sheath.
68. TW: Thermoplastic, moisture-resistant cable.
69. UF: Underground feeder and branch-circuit cable.
70. USE: Underground service-entrance cable.
71. XHH: Cross-linked polyethylene, heat-resistant cable.
72. XHHW: Cross-linked polyethylene, heat- and moisture-resistant cable.

D. Definitions:

1. 8-Position 8-Contact (8P8C) Modular Jack: An unkeyed jack with up to eight contacts commonly used to terminate twisted pair and multiconductor Ethernet cable. Also called a "TIA-1096 miniature 8-position series jack" (8PSJ), or an "IEC 8877 8-pole jack."

    a. Be careful when suppliers use "RJ45" generically. Obsolete RJ45 jacks used for analog telephone cables have rejection keys. 8P8C jacks used for digital telephone cables and Ethernet cables do not have rejection keys.

2. Basic Impulse Insulation Level (BIL): Reference insulation level expressed in impulse crest voltage with a standard wave not longer than 1.5 times 50 microseconds and 1.5 times 40 microseconds.
3. Cable: In accordance with NIST NBS Circular 37 and IEEE standards, in the United States for the purpose of interstate commerce, the definition of "cable" is (1) a conductor with insulation, or a stranded conductor with or without insulation (single-conductor cable); or (2) a combination of conductors insulated from one another (multiple-conductor cable).
4. Communications Jack: A fixed connecting device designed for insertion of a communications cable plug.
5. Communications Outlet: One or more communications jacks, or cables and plugs, mounted in a box or ring, with a suitable protective cover.
6. Conductor: In accordance with NIST NBS Circular 37 and IEEE standards, in the United States for the purpose of interstate commerce, the definition of "conductor" is (1) a wire or combination of wires not insulated from one another, suitable for carrying an electric current; (2) (National Electrical Safety Code) a material, usually in the form of wire, cable, or bar, suitable for carrying an electric current; or (3) (general) a substance or body that allows a current of electricity to pass continuously along it.
7. Conduit: A structure containing one or more duct raceways.
8. Designated Seismic System: An architectural, electrical, or mechanical system and its components for which the component importance factor is greater than 1.0 when determined in accordance with Section 018123 "Facility Seismic and Wind Criteria."
9. Direct Buried: Installed underground without encasement in concrete or other protective material.
10. Duct Bank: An arrangement of conduit providing one or more continuous duct raceways between two points.
11. Duct Raceway: A single enclosed raceway for conductors or cable.
12. Electrical Service: The conductors and equipment for delivering electric energy from the serving utility to the wiring system of the premises served.
13. Enclosure: The case or housing of an apparatus, or the fence or wall(s) surrounding an installation, to prevent personnel from accidentally contacting energized parts or to protect the equipment from physical damage. Types of enclosures and enclosure covers include the following:

a. Cabinet: An enclosure that is designed for either surface mounting or flush mounting and is provided with a frame, mat, or trim in which a swinging door or doors are or can be hung.
b. Concrete Box: A box intended for use in poured concrete.
c. Conduit Body: A means for providing access to the interior of a conduit or tubing system through one or more removable covers at a junction or terminal point. In the United States, conduit bodies are listed in accordance with outlet box requirements.
d. Conduit Box: A box having threaded openings or knockouts for conduit, EMT, or fittings.
e. Cover Plate: A cover designed for protecting wiring devices installed in flush-mounted device boxes while permitting their safe operation; also called a faceplate or wallplate.
f. Cutout Box: An enclosure designed for surface mounting that has swinging doors or covers secured directly to and telescoping with the walls of the enclosure.
g. Device Box: A box with provisions for mounting a wiring device directly to the box.
h. Extension Ring: A ring intended to extend the sides of an outlet box or device box to increase the box depth, volume, or both.
i. Floor Box: A box mounted in the floor intended for use with a floor box cover and other components to complete the floor box enclosure.
j. Floor-Mounted Enclosure: A floor box and floor box cover assembly with means to mount in the floor that is sealed against the entrance of scrub water at the floor level.
k. Floor Nozzle: An enclosure used on a wiring system, intended primarily as a housing for a receptacle, provided with a means, such as a collar, for surface-mounting on a floor, which may or may not include a stem to support it above the floor level, and is sealed against the entrance of scrub water at the floor level.
l. Junction Box: A box with a blank cover that joins different runs of raceway or cable and provides space for connection and branching of the enclosed conductors.
m. Outlet Box: A box that provides access to a wiring system having pryout openings, knockouts, threaded entries, or hubs in either the sides or the back, or both, for the entrance of conduit, conduit or cable fittings, or cables, with provisions for mounting an outlet box cover, but without provisions for mounting a wiring device directly to the box.
n. Pedestal Floor Box Cover: A floor box cover that, when installed as intended, provides a means for typically vertical or near-vertical mounting of receptacle outlets above the floor's finished surface.
o. Pull Box: A box with a blank cover that joins different runs of raceway and provides access for pulling or replacing the enclosed cables or conductors.
p. Raised-Floor Box: A floor box intended for use in raised floors.
q. Recessed Access Floor Box: A floor box with provisions for mounting wiring devices below the floor surface.
r. Recessed Access Floor Box Cover: A floor box cover with provisions for passage of cords to recessed wiring devices mounted within a recessed floor box.
s. Ring: A sleeve, which is not necessarily round, used for positioning a recessed wiring device flush with the plaster, concrete, drywall, or other wall surface.
t. Ring Cover: A box cover, with raised center portion to accommodate a specific wall or ceiling thickness, for mounting wiring devices or luminaires flush with the surface.

u. Termination Box: An enclosure designed for installation of termination base assemblies consisting of bus bars, terminal strips, or terminal blocks with provision for wire connectors to accommodate incoming or outgoing conductors, or both.

14. Emergency Systems: Those systems legally required and classed as emergency by municipal, state, federal, or other codes, or by any governmental agency having jurisdiction that are designed to ensure continuity of lighting, electrical power, or both, to designated areas and equipment in the event of failure of the normal supply for safety to human life.
15. Fault Limited: Providing or being served by a source of electrical power that is limited to not more than 100 W when tested in accordance with UL 62368-1.

    a. The term "fault limited" is intended to encompass most Class 1, 2, and 3 power-limited sources complying with Article 725 of NFPA 70; Class ES1 and ES2 electrical energy sources that are Class PS1 electrical power sources (e.g., USB); and Class ES3 electrical energy sources that are Class PS1 and PS2 electrical power sources (e.g., PoE). See UL 62368-1 for discussion of classes of electrical energy sources and classes of electrical power sources.

16. High-Performance Building: A building that integrates and optimizes on a life-cycle basis all major high-performance attributes, including energy conservation, environment, safety, security, durability, accessibility, cost-benefit, productivity, sustainability, functionality, and operational considerations.
17. Jacket: A continuous nonmetallic outer covering for conductors or cables.
18. Luminaire: A complete lighting unit consisting of a light source such as a lamp, together with the parts designed to position the light source and connect it to the power supply. It may also include parts to protect the light source or the ballast or to distribute the light.
19. Mode: The terms "Active Mode," "Off Mode," and "Standby Mode" are used as defined in the Energy Independence and Security Act (EISA) of 2007.
20. Multi-Outlet Assembly: A type of surface, flush, or freestanding raceway designed to hold conductors, receptacles, and switches, assembled in the field or at the factory.
21. One-Line Diagram: A diagram that shows, by means of single lines and graphic symbols, the course of an electric circuit or system of circuits and the component devices or parts used therein. Also called "single-line diagram."
22. Plenum: A compartment or chamber to which one or more air ducts are connected and that forms part of the air distribution system.
23. Protective Device: A device that senses when an abnormal current flow, abnormal voltage potential, or other abnormal electrical waveform exists and then disconnects the affected portion of the circuit from the system. Common protective devices include fuses, circuit breakers, relays, ground-fault circuit interrupters, and arc-fault circuit interrupters.
24. Public Switched Telephone Network (PSTN): Analog telephone technology that uses twisted pair cables from a telephone-provider central office for the transmission medium. "PSTN" refers to the telephone network; "POTS" refers to the individual subscriber line.
25. Receptacle: A fixed connecting device arranged for insertion of a power cord plug. Also called a power jack.
26. Receptacle Outlet: One or more receptacles mounted in a box with a suitable protective cover.
27. Sheath: A continuous metallic covering for conductors or cables.
28. UL Category Control Number (CCN): An alphabetic or alphanumeric code used to identify product categories covered by UL's Listing, Classification, and Recognition Services.

29. Voice over Internet Protocol (VoIP): Digital telephone packet technology that uses the internet for its transmission medium.
30. Voltage Class: For specified circuits and equipment, voltage classes are defined as follows:

    a. Control Voltage: Having electromotive force between any two conductors, or between a single conductor and ground, that is supplied from a battery or other Class 2 or Class 3 power-limited source.
    b. Line Voltage: (1) (controls) Designed to operate using the supplied low-voltage power without transformation. (2) (transmission lines, transformers, SPDs) The line-to-line voltage of the supplying power system.
    c. Extra-Low Voltage (ELV): Not having electromotive force between any two conductors, or between a single conductor and ground, exceeding 30 V(ac rms), 42 V(ac peak), or 60 V(dc).
    d. Low Voltage (LV): Having electromotive force between any two conductors, or between a single conductor and ground, that is rated above 30 V but not exceeding 1000 V.
    e. Medium Voltage (MV): Having electromotive force between any two conductors, or between a single conductor and ground, that is rated about 1 kV but not exceeding 69 kV.
    f. High Voltage: (1) (circuits) Having electromotive force between any two conductors, or between a single conductor and ground, that is rated above 69 kV but not exceeding 230 kV. (2) (safety) Having sufficient electromotive force to inflict bodily harm or injury.

31. Wire: In accordance with NIST NBS Circular 37 and IEEE standards, in the United States for the purpose of interstate commerce, the definition of "wire" is a slender rod or filament of drawn metal. A group of small wires used as a single wire is properly called a "stranded wire." A wire or stranded wire covered with insulation is properly called an "insulated wire" or a "single-conductor cable." Nevertheless, when the context indicates that the wire is insulated, the term "wire" will be understood to include the insulation.

1.3 COORDINATION

A. Interruption of Existing Electrical Service: Do not interrupt electrical service to facilities occupied by Owner or others unless permitted under the following conditions:

1. Notify Architect and Owner no fewer than seven days in advance of proposed interruption of electrical service.
2. Do not proceed with interruption of electrical service without Owner's written permission.
3. Coordinate interruption with systems impacted by outage including, but not limited to, the following:

    a. Exercising generators.
    b. Emergency lighting.
    c. Elevators.
    d. Fire-alarm systems.
    e. Security systems.

1.4 PREINSTALLATION MEETINGS

A. Electrical Preconstruction Conference: Schedule conference with Architect and Owner, not later than 10 days after Notice to Proceed. Agenda topics include, but are not limited to, the following:

1. Electrical installation schedule.
2. Status of power system studies.

B. Electronic Safety and Security Preconstruction Conference: Schedule conference with Architect and Owner not later than 10 days after Notice to Proceed. Agenda topics include, but are not limited to, the following:

1. Installation schedule for security, fire-alarm, and other life-safety systems.
2. Monitoring services work coordination and monitoring service requests.

1.5 SEQUENCING

A. Conduct and submit results of power system studies before submitting product data and Shop Drawings for electrical equipment.

1.6 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Coordination Drawings for Ceiling Areas: Where indicated on drawings, provide reflected ceiling plan(s), supplemented by sections and other details, drawn to scale, in accordance with Section 013100 "Project Management and Coordination," on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Suspended ceiling components.
2. Structural members to which equipment and suspension systems will be attached.
3. Size and location of access panels on ceilings.
4. Elevation, size, and route of sprinkler piping.
5. Elevation, size, and route of plumbing piping.
6. Elevation, size, and route of ductwork.
7. Elevation, size, and route of cable tray.
8. Elevation, size, and route of conduit.
9. Elevation and size of wall-mounted and ceiling-mounted equipment.
10. Access panels.
11. Sprinklers.
12. Air inlets and outlets.
13. Control modules.
14. Luminaires.
15. Communications devices.
16. Speakers.
17. Security devices.
18. Fire-alarm devices.
19. Indicate clear dimensions for maintenance access in front of equipment.

20. Indicate dimensions of fully open access doors.

C. Coordination Drawings for Conduit and Cable Tray Routing: Routing plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of items involved:

1. Structural members in paths of conduit groups with common supports.
2. HVAC and plumbing items and architectural features in paths of conduit groups with common supports.
3. Equipment racks.
4. Light fixtures.
5. Architectural elements.

D. Coordination Drawings for Large Equipment Indoor Installations:

1. Location plan, drawn to scale, showing heavy equipment or truck access paths to loading dock or other freight access into building. Indicate available width and height of doors or openings.
2. Floor plan for entry floor and floor where equipment is located, drawn to scale, showing heavy equipment access paths for maintenance and replacement, with the following items shown and coordinated with each other, based on input from installers of the items involved:

    a. Dimensioned concrete bases, outlines of equipment, conduit entries, and grounding equipment locations.
    b. If freight elevator must be used, indicate width and height of door and depth of car. Indicate if large equipment must be tipped to use elevator.
    c. Dimensioned working clearances and dedicated areas below and around electrical equipment where obstructions and tripping hazards are prohibited.

3. Reflected ceiling plans for entry floor and floor where equipment is located, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:

    a. Support locations, type of support, and weight on each support. Locate structural supports for structure-supported raceways.
    b. Location of lighting fixtures, sprinkler piping and sprinklers, ducts and diffusers, and other obstructions, indicating available overhead clearance.
    c. Dimensioned working clearances and dedicated areas above and around electrical equipment where foreign systems and equipment are prohibited.

E. Coordination Drawings for Large Equipment Outdoor Installations:

1. Utilities site plan, drawn to scale, showing heavy equipment or truck access paths for maintenance and replacement, with the following items shown and coordinated with each other, based on input from installers of the items involved:

    a. Fences and walls, dimensioned concrete bases, outlines of equipment, conduit entries, and grounding and bonding locations.
    b. Indicate clear dimensions for fence gates and wall openings.
    c. Indicate depth and type of ground cover, and locations of trees, shrubbery, and other obstructions in access path.

d. Indicate clear height below tree branches, overhead lines, bridges, and other overhead obstructions in access path, or where cranes and hoists will be needed to handle large electrical equipment.
e. Support locations, type of support, and weight on each support. Locate structural supports for structure-supported raceways.
f. Dimensioned working clearances and dedicated areas around electrical equipment.

1.7 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Electrical Installation Schedule: At preconstruction meeting, and periodically thereafter as dates change, provide schedule for electrical installation Work to Owner and Architect including, but not limited to, milestone dates for the following activities:

1. Submission of power system studies.
2. Submission of specified coordination drawings.
3. Submission of action submittals specified in Division 26.
4. Orders placed for major electrical equipment.
5. Arrival of major electrical equipment on-site.
6. Preinstallation meetings specified in Division 26.
7. Utility service outages.
8. Utility service inspection and activation.
9. Mockup reviews.
10. Closing of walls and ceilings containing electrical Work.
11. System startup, testing, and commissioning activities for major electrical equipment.
12. System startup, testing, and commissioning activities for emergency lighting.
13. System startup, testing, and commissioning activities for automation systems (SCADA, BMS, lighting, HVAC, fire alarm, fire pump, etc.).
14. Pouring of concrete housekeeping pads for electrical equipment and testing of concrete samples.
15. Requests for special inspections.
16. Requests for inspections by authorities having jurisdiction.

C. Installation Schedule for Communications Systems: At preconstruction meeting, and periodically thereafter as dates change, provide schedule for installation of the communications Work to Owner and Architect including, but not limited to, milestone dates for the following activities:

1. Submission of specified coordination drawings.
2. Submission of action submittals specified in Division 27.
3. Orders placed for major equipment.
4. Arrival of major equipment on-site.
5. Preinstallation meetings specified in Division 27.
6. Telephone and internet service outages.
7. Telephone and internet service inspection and activation.
8. Mockup reviews.
9. Closing of walls and ceilings containing the communications Work.
10. System startup, testing, and commissioning activities for communications equipment.

11. System startup, testing, and commissioning activities for the Work specified in other divisions that depends on the Work specified in Division 27.
12. System startup, testing, and commissioning activities for automation systems (SCADA, BMS, lighting, HVAC, fire alarm, fire pump, etc.).
13. Requests for special inspections.
14. Requests for inspections by authorities having jurisdiction.

D. Installation Schedule for Security, Fire-Alarm, and Other Life-Safety Systems: At preconstruction meeting, and periodically thereafter as dates change, provide schedule for installation of security, fire-alarm, and the other life-safety Work to Owner and Architect including, but not limited to, milestone dates for the following activities:

1. Submission of specified coordination drawings.
2. Submission of action submittals specified in Division 28.
3. Orders placed for major equipment.
4. Arrival of major equipment on-site.
5. Preinstallation meetings specified in Division 28.
6. Security and fire-alarm system outages.
7. Security and fire-alarm system inspection and activation.
8. Mockup reviews.
9. Closing of walls and ceilings containing the security and fire-alarm Work.
10. System startup, testing, and commissioning activities for security and fire-alarm equipment.
11. System startup, testing, and commissioning activities for fire-alarm interfaces with the Work specified in other divisions.
12. System startup, testing, and commissioning activities for automation systems (SCADA, BMS, lighting, HVAC, fire alarm, fire pump, etc.).
13. Requests for special inspections.
14. Requests for inspections by authorities having jurisdiction.

1.8 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Operation and Maintenance Data:

1. Provide emergency operation, normal operation, and preventive maintenance manuals for each system, equipment, and device.

2. Include the following information:

a. Manufacturer's operating specifications.
b. User's guides for software and hardware.
c. Schedule of maintenance material items recommended to be stored at the Project site.
d. Detailed instructions covering operation under both normal and abnormal conditions.
e. Time-current curves for overcurrent protective devices and manufacturer's written instructions for testing and adjusting their settings.
f. List of load-current and overload-relay heaters with related motor nameplate data.

g. List of lamp types and photoelectric relays used on the Project, with ANSI and manufacturers' codes.
h. Manufacturer's instructions for setting field-adjustable components.
i. Manufacturer's instructions for testing, adjusting, and reprogramming microprocessor controls.
j. EPSS: Manufacturer's system checklists, maintenance schedule, and maintenance log sheets in accordance with NFPA 110.
k. Exterior pole inspection and repair procedures.

C. Software and Firmware Operational Documentation: Provide software and firmware operational documentation, including the following:

1. Software operating and upgrade manuals.
2. Names, versions, and website addresses for locations of installed software.
3. Device address list.
4. Printout of software application and graphic screens.
5. Testing and adjusting of panic and emergency power features.
6. For lighting controls, include the following:

a. Adjustments of scene preset controls, adjustable fade rates, and fade overrides.
b. Operation of adjustable zone controls.

PART 2 - PRODUCTS

2.1 SUBSTITUTION LIMITATIONS FOR ELECTRICAL EQUIPMENT

A. Substitution requests for electrical equipment will be entertained under the following conditions:

1. Substitution requests may be submitted for consideration prior to the Electrical Preconstruction Conference if accompanied by value analysis data indicating that substitution will comply with the Project performance requirements while significantly increasing value for Owner throughout life of facility.

2.2 SUBSTITUTION LIMITATIONS FOR COMMUNICATIONS EQUIPMENT

A. Substitution requests for communications equipment will be entertained under the following conditions:

1. Substitution requests may be submitted for consideration prior to the Communications Preconstruction Conference if accompanied by value analysis data indicating that substitution will comply with the Project performance requirements while significantly increasing value for Owner throughout life of facility.

2.3 SUBSTITUTION LIMITATIONS FOR ELECTRONIC SAFETY AND SECURITY EQUIPMENT

A. Substitution requests for electronic safety and security equipment will be entertained under the following conditions:

1. Substitution requests may be submitted for consideration prior to the Electronic Safety and Security Preconstruction Conference if accompanied by value analysis data indicating that substitution will comply with the Project performance requirements while significantly increasing value for Owner throughout life of facility.

PART 3 - EXECUTION

3.1 INSTALLATION OF ELECTRICAL WORK

A. Unless more stringent requirements are specified in the Contract Documents or manufacturers' written instructions, comply with NFPA 70 and NECA NEIS 1 for installation of electrical Work on the Project. Consult Architect for resolution of conflicting requirements.

3.2 CLOSEOUT ACTIVITIES

A. Training:

1. With assistance from factory-authorized service representatives, train Owner's maintenance personnel:

END OF SECTION

SECTION 260513 – MEDIUM-VOLTAGE CABLES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Cables.
2. Connectors.
3. Solid terminations.
4. Separable insulated connectors.
5. Splice kits.
6. Medium-voltage tapes.
7. Arc-proofing materials.
8. Fault indicators.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of cable. Include splices and terminations for cables and cable accessories.

C. Samples: 16 inch lengths for each type of cable specified.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Coordination Drawings: Indicate location of each cable, splice, and termination.

C. Material Certificates: For each type of cable and accessory.

D. Design Data: Cable pulling calculations, including conduit size and fill percentage, pulling tensions, cable sidewall pressure, jam probability, voltage drop, and ground wire sizing for each cable.

E. Source quality-control reports.

F. Field quality-control reports.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Comply with IEEE C2 and NFPA 70.

C. Source Limitations: Obtain cables and accessories from single source from single manufacturer.

2.2 CABLES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. General Cable; Prysmian Group North America.
2. Hendrix Wire and Cable; Marmon Holdings, Inc.; Berkshire Hathaway Inc.
3. Kerite Power Cable; Marmon Holdings, Inc.; Berkshire Hathaway Inc.
4. Okonite Company (The).
5. Prysmian Cables and Systems; Prysmian Group North America.
6. Southwire Company, LLC.

B. Cable Type: Type MV 105.

C. Conductor Insulation: Ethylene-propylene rubber.

1. Voltage Rating: 15 kV.
2. Insulation Thickness: 133 percent insulation level.

D. Conductor: Aluminum.

E. Comply with UL 1072, AEIC CS8, ICEA S-93-639/NEMA WC 74 and ICEA S-97-682.

F. Conductor Stranding: Compact round, concentric lay, Class B.

G. Shielding: Copper tape or solid copper wires, helically applied over semiconducting insulation shield.

H. Three-Conductor Cable Assembly: Three insulated, shielded conductors cabled together with ground conductors.

1. Circuit Identification: Color-coded tape (black, red, blue) under the metallic shielding.

I. Cable Jacket: Sunlight-resistant PVC.

2.3 CONNECTORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.
2. ABB, Electrification Business.
3. DSG-Canusa; Shawcor Ltd.
4. Eaton.
5. G&W Electric Company.
6. TE Connectivity Ltd.

B. Comply with ANSI C119.4 for connectors between aluminum conductors or for connections between aluminum to copper conductors.

C. Copper-Conductor Connectors: Aluminum barrel crimped connectors.

2.4 SOLID TERMINATIONS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.
2. ABB, Electrification Business.
3. DSG-Canusa; Shawcor Ltd.
4. G&W Electric Company.
5. Shawflex; Shawcor Ltd.
6. TE Connectivity Ltd.

B. Multiconductor Cable Sheath Seals: Type recommended by seal manufacturer for type of cable and installation conditions, including orientation.

1. Cold-shrink sheath seal kit with preformed sleeve openings sized for cable and insulated conductors.
2. Heat-shrink sheath seal kit with phase- and ground-conductor rejacketing tubes, cable-end sealing boot, and sealing plugs for unused ground-wire openings in boot.
3. Cast-epoxy-resin sheath seal kit with wraparound mold and packaged, two-part, epoxy-resin casting material.

C. Shielded-Cable Terminations: Comply with the following classes of IEEE 48. Insulation class shall be equivalent to that of cable. Include shield ground strap for shielded cable terminations.

1. Class 1 Terminations:

a. Modular type, furnished as a kit, with stress-relief tube; multiple, molded-silicone-rubber, insulator modules; shield ground strap; and compression-type connector.
b. Heat-shrink type with heat-shrink inner stress control and outer nontracking tubes; multiple, molded, nontracking skirt modules; and compression-type connector.
c. Modular type, furnished as a kit, with stress-relief shield terminator; multiple-wet-process, porcelain, insulator modules; shield ground strap; and compression-type connector.

d. Indoors: Kit with stress-relief tube, nontracking insulator tube, shield ground strap, compression-type connector, and end seal.

2. Class 2 Terminations, Indoors: Kit with stress-relief tube, nontracking insulator tube, shield ground strap, and compression-type connector. Include silicone-rubber tape; cold-shrink-rubber sleeve; or heat-shrink, plastic-sleeve moisture seal for end of insulation whether or not supplied with kits.
3. Class 3 Terminations: Kit with stress cone and compression-type connector.

2.5 SEPERABLE INSULATED CONNECTORS

A. Description: Modular system, complying with IEEE 386, with disconnecting, single-pole, cable terminators and with matching, stationary, plug-in, dead-front terminals designed for cable voltage and for sealing against moisture.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. 3M.
2. ABB (Electrification Products Division).
3. Adalet.
4. DSG-Canusa.
5. Eaton.
6. Engineered Products Company.
7. G&W Electric Company.
8. MP Husky USA Cable Tray & Cable Bus.
9. nVent (Raychem).
10. Scott Fetzer Co. (The).
11. TE Connectivity Ltd.

C. Terminations at Distribution Points: Modular type, consisting of terminators installed on cables and modular, dead-front, terminal junctions for interconnecting cables.

D. Load-Break Cable Terminators: Elbow-type units with 200 A load make/break and continuous-current rating; coordinated with insulation diameter, conductor size, and material of cable being terminated. Include test point on terminator body that is capacitance coupled.

E. Dead-Break Cable Terminators: Elbow-type unit with 200 A continuous-current rating; designed for de-energized disconnecting and connecting; coordinated with insulation diameter, conductor size, and material of cable being terminated. Include test point on terminator body that is capacitance coupled.

F. Dead-Front Terminal Junctions: Modular bracket-mounted groups of dead-front stationary terminals that mate and match with above cable terminators. Two-, three-, or four-terminal units as indicated, with fully rated, insulated, watertight conductor connection between terminals and complete with grounding lug, manufacturer's standard accessory stands, stainless steel mounting brackets, and attaching hardware.

1. Protective Cap: Insulating, electrostatic-shielding, water-sealing cap with drain wire.
2. Portable Feed-Through Accessory: Two-terminal, dead-front junction arranged for removable mounting on accessory stand of stationary terminal junction.

3. Grounding Kit: Jumpered elbows, portable feed-through accessory units, protective caps, test rods suitable for concurrently grounding three phases of feeders, and carrying case.
4. Standoff Insulator: Portable, single dead-front terminal for removable mounting on accessory stand of stationary terminal junction. Insulators suitable for fully insulated isolation of energized cable-elbow terminator.

G. Tool Set: Shotgun hot stick with energized terminal indicator, fault-indicator test tool, and carrying case.

2.6 SPLICE KITS

A. Description: For connecting medium voltage cables; type as recommended by cable or splicing kit manufacturer for the application.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.
2. ABB, Electrification Business.
3. DSG-Canusa; Shawcor Ltd.
4. Eaton.
5. Richards Manufacturing Co.
6. TE Connectivity Ltd.

C. Standard: Comply with IEEE 404.

D. Splicing Products: As recommended, in writing, by splicing kit manufacturer for specific sizes, materials, ratings, and configurations of cable conductors. Include all components required for complete splice, with detailed instructions.

1. Combination tape and cold-shrink-rubber sleeve kit with rejacketing by cast-epoxy-resin encasement or other waterproof, abrasion-resistant material.
2. Heat-shrink splicing kit of uniform, cross-section, polymeric construction with outer heat-shrink jacket.
3. Premolded, cold-shrink-rubber, in-line splicing kit.
4. Premolded, EPDM splicing body kit with cable joint sealed by interference fit of mating parts and cable.
5. Separable multiway splice system with all components for the required splice configuration.

2.7 MEDIUM-VOLTAGE TAPES

A. Description: Electrical grade, insulating tape rated for medium voltage application.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.
2. HellermannTyton.
3. Scapa Industrial; Scapa Group plc.

C. Ethylene/propylene rubber-based, 30 mil splicing tape, rated for 130 deg C operation. Minimum 3/4 inch wide.

2.8 ARC-PROOFING MATERIALS

A. Description: Fire retardant, providing arc flash protection.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.

C. Tape for First Course on Metal Objects: 10 mil thick, corrosion-protective, moisture-resistant, PVC pipe-wrapping tape.

D. Arc-Proofing Tape: Fireproof tape, flexible, conformable, intumescent to 0.3 inch thick, and compatible with cable jacket.

E. Glass-Cloth Tape: Pressure-sensitive adhesive type, 1 inch wide.

2.9 SOURCE QUALITY CONTROL

A. Test and inspect cables according to ICEA S-97-682 before shipping.

B. Test strand-filled cables for water-penetration resistance according to ICEA T-31-610, using a test pressure of 5 psig.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install cables according to IEEE 576.

B. Proof conduits prior to conductor installation by passing a wire brush mandrel and then a rubber duct swab through the conduit. Separate the wire brush and the rubber swab by 48 to 72 inch on the pull rope.

1. Wire Brush Mandrel: Consists of a length of brush approximately the size of the conduit inner diameter with stiff steel bristles and an eye on each end for attaching the pull ropes. If an obstruction is felt, pull the brush back and forth repeatedly to break up the obstruction.
2. Rubber Duct Swab: Consists of a series of rubber discs approximately the size of the conduit inner diameter on a length of steel cable with an eye on each end for attaching the pull ropes. Pull the rubber duct swab through the duct to extract loose debris from the duct.

C. Pull Conductors: Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.

1. Where necessary, use manufacturer-approved pulling compound or lubricant that does not deteriorate conductor or insulation.
2. Use pulling means, including fish tape, cable, rope, and basket-weave cable grips, that do not damage cables and raceways. Do not use rope hitches for pulling attachment to cable.
3. Use pull-in guides, cable feeders, and draw-in protectors as required to protect cables during installation.
4. Do not pull cables with ends unsealed. Seal cable ends with rubber tape.

D. Install exposed cables parallel and perpendicular to surfaces of exposed structural members and follow surface contours where possible.

E. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."

F. Install "buried-cable" warning tape 12 inch above cables.

G. In manholes, handholes, pull boxes, junction boxes, and cable vaults, train cables around walls by the longest route from entry to exit; support cables at intervals adequate to prevent sag.

H. Install sufficient cable length to remove cable ends under pulling grips. Remove length of conductor damaged during pulling.

I. Install cable splices at pull points and elsewhere as indicated; use standard kits. Use dead-front separable watertight connectors in manholes, and other locations subject to water infiltration.

J. Install terminations at ends of conductors, and seal multiconductor cable ends with standard kits.

K. Install separable insulated-connector components as follows:

1. Protective Cap: At each terminal junction, with one on each terminal to which no feeder is indicated to be connected.
2. Portable Feed-Through Accessory: At each terminal junction, with one on each terminal.
3. Standoff Insulator: At each terminal junction, with one on each terminal.

L. Arc Proofing: Unless otherwise indicated, arc proof medium-voltage cable at locations not protected by conduit, cable tray, direct burial, or termination materials. In addition to arc-proofing tape manufacturer's written instructions, apply arc proofing as follows:

1. Clean cable sheath.
2. Wrap metallic cable components with 10 mil pipe-wrapping tape.
3. Smooth surface contours with electrical insulation putty.
4. Apply arc-proofing tape in one half-lapped layer with coated side toward cable.
5. Band arc-proofing tape with two layers of 1 inch wide half-lapped, adhesive, glass-cloth tape at each end of the arc-proof tape.

M. Seal around cables passing through fire-rated elements according to Section 078413 "Penetration Firestopping."

N. Ground shields of shielded cable at one point only. Maintain shield continuity and connections to metal connection hardware at all connection points.

O. Identify cables according to Section 260553 "Identification for Electrical Systems." Identify phase and circuit number of each conductor at each splice, termination, pull point, and junction box. Arrange identification so that it is unnecessary to move the cable or conductor to read the identification.

3.2 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. Perform each visual and mechanical inspection and electrical test stated in NETA ATS. Certify compliance with test parameters.
2. After installing medium-voltage cables and before electrical circuitry has been energized, test for compliance with requirements.
3. Perform direct-current High Potential test of each new conductor according to NETA ATS, Ch. 7.3.3. Do not exceed cable manufacturer's recommended maximum test voltage.
4. Perform Partial Discharge test of each new conductor according to NETA ATS, Ch. 7.3.3 and to test equipment manufacturer's recommendations.
5. Perform Dissipation Factor test of each new conductor according to NETA ATS, Ch. 7.3.3 and to test equipment manufacturer's recommendations.

B. Medium-voltage cables will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports.

END OF SECTION

SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Copper building wire.
2. Metal-clad cable, Type MC.
3. Fire-resistant metal-clad cable, Type MC.
4. Fire-resistant mineral-insulated metal-sheathed cable, Type MI.
5. Connectors and splices.
6. Fire alarm wiring and cable.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
2. Section 260523 "Control-Voltage Electrical Power Cables" for control systems communications cables and Classes 1, 2, and 3 control cables.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product.

C. Product Schedule: Indicate type, use, location, and termination locations.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Field quality-control reports.

PART 2 - PRODUCTS

2.1 COPPER BUILDING WIRE

A. Description: Flexible, insulated and uninsulated, drawn copper current-carrying conductor with an overall insulation layer or jacket, or both, rated 600 V or less.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Alpha Wire Company.
2. American Bare Conductor.
3. Belden Inc.
4. Cerro Wire LLC.
5. Encore Wire Corporation.
6. General Cable; Prysmian Group North America.
7. Okonite Company (The).
8. Service Wire Co.
9. Southwire Company, LLC.
10. WESCO.

C. Standards:

1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
2. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."

D. Conductors: Copper, complying with ASTM B3 for bare annealed copper and with ASTM B8 for stranded conductors.

E. Conductor Insulation:

1. Type RHH and Type RHW-2: Comply with UL 44.
2. Type TC-ER: Comply with NEMA WC 70/ICEA S-95-658 and UL 1277.
3. Type THHN and Type THWN-2: Comply with UL 83.
4. Type THW and Type THW-2: Comply with NEMA WC-70/ICEA S-95-658 and UL 83.
5. Type XHHW-2: Comply with UL 44.

2.2 METAL-CLAD CABLE, TYPE MC

A. Description: A factory assembly of one or more current-carrying insulated conductors in an overall metallic sheath.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. AFC Cable Systems; Atkore International.
2. Alpha Wire Company.
3. American Bare Conductor.
4. Belden Inc.
5. Encore Wire Corporation.
6. General Cable; Prysmian Group North America.
7. Okonite Company (The).
8. Service Wire Co.
9. Southwire Company, LLC.
10. WESCO.

C. Standards:

1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
2. Comply with UL 1569.
3. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."

D. Circuits:

1. Single circuit with color-coded conductors.

E. Conductors: Copper, complying with ASTM B3 for bare annealed copper and with ASTM B8 for stranded conductors.

F. Ground Conductor: Insulated.

G. Conductor Insulation:

1. Type TFN/THHN/THWN-2: Comply with UL 83.
2. Type XHHW-2: Comply with UL 44.

H. Armor: Steel, interlocked.

2.3 FIRE-RESISTANT METAL-CLAD CABLE, TYPE MC, FOR USE IN ELECTRICAL CIRCUIT INTEGRITY SYSTEMS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Marmon Industrial Energy & Infrastructure; division of Marmon Electrical; a Berkshire Hathaway company
2. Prysmian Cables and Systems; Prysmian Group North America

B. Description: A factory assembly of one or more current-carrying insulated conductors in an overall metallic sheath.

C. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

1. Metal-Clad Cable: UL CCN PJAZ, including UL 1569.
2. Circuit Integrity: UL CCN FHJR, including UL 2196.

D. Standard Features:

1. Referenced Standard: Article 330 of NFPA 70.
2. Fire-Resistance Rating: 2 h.
3. Circuits: Single circuit.
4. Conductors: Copper.
5. Ground Conductor: Insulated

6. Armor: Steel, interlocked.
7. Jacket: PVC applied over armor.

2.4 FIRE-RESISTANT MINERAL-INSULATED METAL-SHEATHED CABLE, TYPE MI, FOR USE IN CIRCUIT INTEGRITY SYSTEMS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. PYROTENAX; brand of nVent Electrical plc
2. TEC International

B. Description: Solid copper conductors encased in compressed metal oxide with an outer metallic sheath, rated 600 V or less.

C. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

1. Mineral-Insulated Metal-Sheathed Cable: UL CCN PPKV, including UL Subject 504.
2. Circuit Integrity: UL CCN FHJR, including UL 2196.

D. Standard Features:

1. Referenced Standard: Article 332 of NFPA 70.
2. Fire-Resistance Rating: 2 h.
3. Conductors: Copper, complying with ASTM B3 for bare annealed copper.
4. Insulation: Compressed magnesium oxide
5. Sheath: Copper

2.5 FIRE-ALARM WIRE AND CABLE

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Allied Wire & Cable Inc.
2. CommScope, Inc.
3. Comtran Corporation.
4. Genesis; Resideo Technologies, Inc.
5. PYROTENAX; brand of nVent Electrical plc.
6. Prysmian Cables and Systems; Prysmian Group North America.
7. Radix Wire.
8. Rockbestos-Suprenant Cable Corp.
9. Superior Essex Inc.; subsidiary of LS Corp.
10. West Penn Wire; brand of Belden, Inc.
11. Cerro Wire LLC.

B. General Wire and Cable Requirements: NRTL listed and labeled as complying with NFPA 70, Article 760.

C. Signaling Line Circuits: Twisted, shielded pair, not less than size as recommended by system manufacturer.

D. Non-Power-Limited Circuits: Solid-copper conductors with 600 V rated, 75 deg C, color-coded insulation, and complying with requirements in UL 2196 for a two-hour rating.

1. Low-Voltage Circuits: No. 16 AWG, minimum, in pathway.
2. Line-Voltage Circuits: No. 12 AWG, minimum, in pathway.

2.6 CONNECTORS AND SPLICES

A. Description: Factory-fabricated connectors, splices, and lugs of size, ampacity rating, material, type, and class for application and service indicated; listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. 3M Electrical Products.
b. ABB, Electrification Business.
c. AFC Cable Systems; Atkore International.
d. Gardner Bender.
e. Hubbell Utility Solutions; Hubbell Incorporated.
f. Ideal Industries, Inc.
g. ILSCO.
h. NSi Industries LLC.
i. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
j. Service Wire Co.
k. TE Connectivity Ltd.

2. Lugs: One piece, seamless, designed to terminate conductors specified in this Section.

a. Material: Copper.
b. Type: Two hole with long barrels.
c. Termination: Compression.

B. Mineral-Insulated Metallic-Sheathed Cable Fittings:
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
a. TEC International
2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:
a. Type MI Cable Fittings: UL CCN PPYT, including UL 514B.
3. Standard Features: For copper sheathed cables, designed to connect conductors specified in this Section.

C. Metal-Clad Cable Fittings:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. ABB, Installation Products
    b. Adalet; division of Scott Fetzer Co.
    c. American Fittings Corp. (AMFICO)
    d. Arlington Industries, Inc.
    e. Bridgeport Fittings Inc.
    f. Crouse-Hinds; brand of Eaton, Electrical Sector
    g. Halex; division of Scott Fetzer Co.
    h. Killark; brand of Hubbell Electrical Solutions; Hubbell Incorporated
    i. O-Z/Gedney; brand of Appleton Group
    j. Service Wire Co.
    k. SIGMA Engineered Solutions

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

    a. Type MC Cable Connectors: UL CCN PJOX, including UL 514B.

3. Standard Features: For steel and aluminum sheathed cables, designed to connect conductors specified in this Section.

PART 3 - EXECUTION

3.1 CONDUCTOR MATERIAL APPLICATIONS

A. Service Entrance:

1. Copper.

B. Feeders:

1. Copper; solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.

C. Branch Circuits:

1. Copper. Solid for No. 12 AWG and smaller; stranded for No. 10 AWG and larger.

D. ASD Output Circuits Cable: Extra-flexible stranded for all sizes.

3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

A. Service Entrance: Type XHHW-2, single conductors in raceway.

B. Feeders: Type THHN/THWN-2, single conductors in raceway or Type XHHW-2, single conductors in raceway, Type MI cable, where indicated.

C. Exposed Branch Circuits: Type THHN/THWN-2, single conductors in raceway.

D. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN/THWN-2, single conductors in raceway or MC-Cable.

3.3 INSTALLATION, GENERAL

A. Conceal cables within conduits in finished walls and drywall. Provide cables within conduits above accessible ceilings, unless otherwise indicated.

B. Complete raceway installation between conductor and cable termination points according to Section 260533.13 "Conduits for Electrical Systems" prior to pulling conductors and cables.

C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.

D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.

E. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."

F. Use a maximum length of six feet of MC-Cable for fixture whips.

3.4 INSTALLATION OF FIRE-ALARM WIRE AND CABLE

A. Comply with NFPA 72.

B. Wiring Method: Install wiring in metal pathway according to Section 260533.13 “Conduits for Electrical Systems.” Install fire alarm cable serving the critical operations power system area in RGS conduit.

1. Install plenum cable in environmental airspaces, including plenum ceilings.
2. Cables must be riser-rated and must be a listed 2-hour electrical circuit protective system.
3. Fire-alarm circuits and equipment control wiring associated with fire-alarm system must be installed in a dedicated pathway system.

    a. Cables and pathways used for fire-alarm circuits, and equipment control wiring associated with fire-alarm system, may not contain any other wire or cable.

4. Signaling Line Circuits: Power-limited fire-alarm cables must not be installed in the same cable or pathway as signaling line circuits.

C. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with

fire-alarm system to terminal blocks. Mark each terminal according to system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.

D. Cable Taps: Use numbered terminal strips in junction, pull, and outlet boxes; cabinets; or equipment enclosures where circuit connections are made.

E. Color-Coding: Color-code fire-alarm conductors differently from the normal building power wiring. Use one color-code for alarm circuit wiring and another for supervisory circuits. Color-code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Paint fire-alarm system junction boxes and covers red.

F. Risers: Install at least two vertical cable risers to serve the fire-alarm system. Separate risers in close proximity to each other with a minimum one-hour-rated wall, so the loss of one riser does not prevent receipt or transmission of signals from other floors or zones.

G. Wiring to Remote Alarm Transmitting Device: 1 inch conduit between the fire-alarm control panel and the transmitter. Install number of conductors and electrical supervision for connecting wiring as needed to suit monitoring function.

3.5 CONNECTIONS

A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.

B. Make splices, terminations, and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.

C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inch of slack.

D. Comply with requirements in Section 284621.11 “Addressable Fire-Alarm Systems” for connecting, terminating, and identifying wires and cables.

3.6 IDENTIFICATION

A. Identify and color-code conductors and cables according to Section 260553 "Identification for Electrical Systems."

B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

3.7 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

A. Install sleeves and sleeve seals at penetrations of existing floor, roof, and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

3.8 FIRESTOPPING

A. Provide firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Section 078413 "Penetration Firestopping."

3.9 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. After installing conductors and cables and before electrical circuitry has been energized, test conductors feeding the following critical equipment and services for compliance with requirements:

    a. Emergency lighting.
    b. Fire alarm.
    c. Electronic security systems.
    d. Critical Operations Power Systems (COPS).

2. Perform each of the following visual and electrical tests:

    a. Inspect exposed sections of conductor and cable for physical damage and correct connection according to the single-line diagram.
    b. Test bolted connections for high resistance using one of the following:

        1) A low-resistance ohmmeter.
        2) Calibrated torque wrench.
        3) Thermographic survey.

    c. Inspect compression-applied connectors for correct cable match and indentation.
    d. Inspect for correct identification.
    e. Inspect cable jacket and condition.
    f. Insulation-resistance test on each conductor for ground and adjacent conductors. Apply a potential of 500 V(dc) for 300 V rated cable and 1000 V(dc) for 600 V rated cable for a one-minute duration.
    g. Continuity test on each conductor and cable.
    h. Uniform resistance of parallel conductors.

3. Initial Infrared Scanning: After Substantial Completion, but before Final Acceptance, perform an infrared scan of each splice in conductors No. 3 AWG and larger. Remove box and equipment covers so splices are accessible to portable scanner. Correct deficiencies determined during the scan.

    a. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
    b. Record of Infrared Scanning: Prepare a certified report that identifies switches checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

4. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each switch 11 months after date of Substantial Completion.

B. Cables will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports to record the following:

1. Procedures used.
2. Results that comply with requirements.
3. Results that do not comply with requirements, and corrective action taken to achieve compliance with requirements.

END OF SECTION

SECTION 260523 - CONTROL-VOLTAGE ELECTRICAL POWER CABLES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Category 6a balanced twisted pair cable.
2. Balanced twisted pair cable hardware.
3. Twin-axial data highway cable.
4. RS-485 cable.
5. Control cable.
6. Control-circuit conductors.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Source quality-control reports.

C. Field quality-control reports.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Flame Travel and Smoke Density in Plenums: As determined by testing identical products according to NFPA 262, by a qualified testing agency. Identify products for installation in plenums with appropriate markings of applicable testing agency.

1. Flame Travel Distance: 60 inch or less.
2. Peak Optical Smoke Density: 0.5 or less.
3. Average Optical Smoke Density: 0.15 or less.

C. Flame Travel and Smoke Density for Riser Cables in Non-Plenum Building Spaces: As determined by testing identical products according to UL 1666.

D. Flame Travel and Smoke Density for Cables in Non-Riser Applications and Non-Plenum Building Spaces: As determined by testing identical products according to UL 1685.

2.2 CATEGORY 6a BALANCED TWISTED PAIR CABLE

A. Description: Four-pair, balanced-twisted pair cable, certified to meet transmission characteristics of Category 6a cable at frequencies up to 500 MHz.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.
2. AMP NETCONNECT; a TE Connectivity Ltd. company.
3. Belden, Inc.
4. Berk-Tek Leviton; a Nexans/Leviton alliance.
5. CommScope, Inc.
6. General Cable; Prysmian Group North America.
7. Genesis Cable Products; Honeywell International, Inc.
8. Hitachi Cable America Inc.
9. Mohawk; a division of Belden Networking, Inc.
10. Prysmian Cables and Systems; Prysmian Group North America.
11. Superior Essex Inc.; subsidiary of LS Corp.
12. SYSTIMAX Solutions; a CommScope Inc. brand.

C. Standard: Comply with TIA-568-C.2 for Category 6a cables.

D. Conductors: 100 ohm, No. 23 AWG solid copper.

1. Lead Content: Less than 300 parts per million.

E. Shielding/Screening: Unshielded twisted pairs (UTP).

F. Cable Rating: Plenum.

G. Jacket: Yellow thermoplastic.

2.3 BALANCED TWISTED PAIR CABLE HARDWARE

A. Description: Hardware designed to connect, splice, and terminate balanced twisted pair copper communications cable.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.
2. American Technology Systems Industries, Inc.
3. AMP NETCONNECT; a TE Connectivity Ltd. company.
4. Belden, Inc.
5. Berk-Tek Leviton; a Nexans/Leviton alliance.
6. CommScope, Inc.
7. Dynacom Corporation.
8. General Cable; Prysmian Group North America.
9. Genesis Cable Products; Honeywell International, Inc.
10. Hubbell Premise Wiring; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
11. KRONE Incorporated.
12. Leviton Manufacturing Co., Inc.
13. Mohawk; a division of Belden Networking, Inc.
14. Molex Premise Networks.
15. Panduit Corp.
16. Prysmian Cables and Systems; Prysmian Group North America.
17. Siemon Co. (The).
18. Superior Essex Inc.; subsidiary of LS Corp.
19. SYSTIMAX Solutions; a CommScope Inc. brand.

C. General Requirements for Balanced Twisted Pair Cable Hardware:

1. Comply with the performance requirements of Category 6a.
2. Comply with TIA-568-C.2, IDC type, with modules designed for punch-down caps or tools.
3. Cables must be terminated with connecting hardware of same category or higher.

D. Source Limitations: Obtain balanced twisted pair cable hardware from single source from single manufacturer.

E. Cross-Connect: Modular array of connecting blocks arranged to terminate building cables and permit interconnection between cables.

1. Number of Terminals per Field: One for each conductor in assigned cables.

F. Patch Panel: Modular panels housing numbered jack units with IDC-type connectors at each jack location for permanent termination of pair groups of installed cables.

1. Features:

a. Universal T568A and T568B wiring labels.
b. Labeling areas adjacent to conductors.
c. Replaceable connectors.
d. 48 ports.

2. Construction: 16-gauge steel and mountable on 19 inch equipment racks.
3. Number of Jacks per Field: One for each four-pair conductor group of indicated cables, plus spares and blank positions adequate to suit specified expansion criteria.

G. Patch Cords: Factory-made, four-pair cables in lengths indicated; terminated with an eight-position modular plug at each end.

1. Patch cords must have bend-relief-compliant boots and color-coded icons to ensure performance. Patch cords must have latch guards to protect against snagging.
2. Patch cords must have color-coded boots for circuit identification.

H. Plugs and Plug Assemblies:

1. Male; eight position; color-coded modular telecommunications connector designed for termination of a single four-pair 100 ohm unshielded or shielded balanced twisted pair cable.
2. Comply with IEC 60603-7-1, IEC 60603-7-2, IEC 60603-7-3, IEC 60603-7-4, and IEC 60603-7.5.
3. Marked to indicate transmission performance.

I. Jacks and Jack Assemblies:

1. Female; eight position; modular; fixed telecommunications connector designed for termination of a single four-pair 100 ohm unshielded or shielded balanced twisted pair cable.
2. Designed to snap-in to a patch panel or faceplate.
3. Standards:

    a. Category 6a, unshielded balanced twisted pair cable must comply with IEC 60603-7-41.

4. Marked to indicate transmission performance.

J. Faceplate:

1. Two, Four, and Six port, as indicated, vertical single-gang faceplates designed to mount to single-gang wall boxes.
2. Faceplate: Thermoplastic, complying with requirements in Section 262726 "Wiring Devices."
3. For use with snap-in jacks accommodating any combination of balanced twisted pair and coaxial work area cords.

    a. Flush mounting jacks, positioning the cord at a 45-degree angle.

K. Legend:

1. Machine printed, in the field, using adhesive-tape label.
2. Snap-in, clear-label covers and machine-printed paper inserts.

2.4 RS-232 CABLE

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Allied Wire & Cable Inc.
2. Belden Inc.
3. General Cable; Prysmian Group North America.
4. Genesis Cable Products; Honeywell International, Inc.
5. Southwire Company, LLC.

B. PVC-Jacketed, TIA 232-F:

1. Nine, No. 22 AWG, stranded (7x30) tinned copper conductors.
2. Lead Content: Less than 300 parts per million.
3. Polypropylene insulation.
4. Aluminum foil-polyester tape shield with 100 percent shield coverage.
5. PVC jacket.
6. Conductors are cabled on common axis with No. 24 AWG, stranded (7x32) tinned copper drain wire.
7. NFPA 70 Type: Type CM.
8. Flame Resistance: Comply with UL 1581.

C. Plenum-Type, TIA 232-F:

1. Nine, No. 22 AWG, stranded (7x30) tinned copper conductors.
2. Lead Content: Less than 300 parts per million.
3. PE insulation.
4. Aluminum foil-polyester tape shield with 100 percent shield coverage.
5. Fluorinated ethylene propylene jacket.
6. Conductors are cabled on common axis with No. 24 AWG, stranded (7x32) tinned copper drain wire.
7. Flame Resistance: Comply with NFPA 262.

2.5 RS-485 CABLE

A. Standard Cable: NFPA 70, Type CMG.

1. Paired, two pairs, twisted, No. 22 AWG, stranded (7x30) tinned-copper conductors.
2. PVC insulation.
3. Unshielded.
4. PVC jacket.
5. Flame Resistance: Comply with UL 1685.
6. Lead Content: Less than 300 parts per million.

B. Plenum-Rated Cable: NFPA 70, Type CMP.

1. Paired, two pairs, No. 22 AWG, stranded (7x30) tinned-copper conductors.
2. Fluorinated ethylene propylene insulation.
3. Unshielded.
4. Fluorinated ethylene propylene jacket.

5. Flame Resistance: NFPA 262.
6. Lead Content: Less than 300 parts per million.

2.6 CONTROL CABLE

A. Paired Cable: NFPA 70, Type CMG.

1. Multi-pair, twisted, No. 16 AWG, stranded (19x29) tinned-copper conductors.
2. PVC insulation.
3. Unshielded.
4. PVC jacket.
5. Flame Resistance: Comply with UL 1685.
6. Lead Content: Less than 300 parts per million.

B. Plenum-Rated, Paired Cable: NFPA 70, Type CMP.

1. Multi-pair, twisted, No. 16 AWG, stranded (19x29) tinned-copper conductors.
2. PVC insulation.
3. Unshielded.
4. PVC jacket.
5. Flame Resistance: Comply with NFPA 262.
6. Lead Content: Less than 300 parts per million.

2.7 CONTROL-CIRCUIT CONDUCTORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Encore Wire Corporation.
2. General Cable; Prysmian Group North America.
3. Service Wire Co.
4. Southwire Company, LLC.

B. Class 1 Control Circuits: Stranded copper, Type THHN/THWN-2, complying with UL 83 in raceway.

C. Class 2 Control Circuits: Stranded copper, Type THHN/THWN-2, complying with UL 83 in raceway.

D. Class 3 Remote-Control and Signal Circuits: Stranded copper, Type THHN/THWN-2, complying with UL 83 in raceway.

E. Class 2 Control Circuits and Class 3 Remote-Control and Signal Circuits That Supply Critical Circuits: Circuit Integrity (CI) cable.

1. Smoke control signaling and control circuits.

2.8 SOURCE QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to evaluate cables.

B. Factory test twisted pair cables according to TIA-568-C.2.

C. Cable will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Test cables on receipt at Project site.

1. Test each pair of twisted pair cable for open and short circuits.

3.2 INSTALLATION OF RACEWAYS AND BOXES

A. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems" for raceway selection and installation requirements for boxes, conduits, and wireways as supplemented or modified in this Section.

1. Outlet boxes for telecommunications wiring must be no smaller than 4-11/16 inch square by 2-1/8 inch deep. Boxes must be provided with extension rings sized to bring edge of ring to within 1/8 inch of the finished wall surface.
2. Flexible metal conduit must not be used.

B. Comply with TIA-569-D for pull-box sizing and length of conduit and number of bends between pull points.

C. Install manufactured conduit sweeps and long-radius elbows.

D. Raceway Installation in Equipment Rooms:

1. Position conduit ends adjacent to a corner on backboard if a single piece of plywood is installed, or in the corner of the room if multiple sheets of plywood are installed around perimeter walls of the room.
2. Provide cable trays to route cables if conduits cannot be located in these positions.
3. Secure conduits to backboard if entering the room from overhead.
4. Provide conduits 48 inches above finished floor.
5. Provide metal conduits with grounding bushings and connect with grounding conductor to grounding system.

3.3 INSTALLATION OF CONDUCTORS AND CABLES

A. Comply with NECA 1.

B. General Requirements for Cabling:

1. Install cables in raceways.

    a. Finished spaces: conduit.
    b. Concealed, non-accessible; conduit.
    c. Concealed, accessible; conduit, cable tray, j-hook.

2. Comply with TIA-568-C Series of standards.
3. Comply with BICSI ITSIMM, Ch. 5, "Copper Structured Cabling Systems."
4. Terminate all conductors; cable must not contain unterminated elements. Make terminations only at indicated outlets, terminals, and cross-connect and patch panels.
5. Cables may not be spliced and must be continuous from terminal to terminal. Do not splice cable between termination, tap, or junction points.
6. Cables serving a common system may be grouped in a common raceway. Install network cabling and control wiring and cable in separate raceway from power wiring. Do not group conductors from different systems or different voltages.
7. Secure and support cables at intervals not exceeding 30 inch and not more than 6 inch from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
8. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIMM, Ch. 5, "Copper Structured Cabling Systems." Install lacing bars and distribution spools.
9. Do not install bruised, kinked, scored, deformed, or abraded cable. Remove and discard cable if damaged during installation and replace it with new cable.
10. Cold-Weather Installation: Bring cable to room temperature before dereeling. Do not use heat lamps for heating.
11. Pulling Cable: Comply with BICSI ITSIMM, Ch. 5, "Copper Structured Cabling Systems." Monitor cable pull tensions.
12. Support: Provide independent support as indicated. Do not allow cables to lie on removable ceiling tiles.
13. Provide and fasten securely in place with hardware specifically designed and installed so as to not damage cables.
14. Provide strain relief.
15. Allow extra length for connecting to terminals. Do not bend cables in a radius less than 10 times the cable OD. Use sleeves or grommets to protect cables from vibration at points where they pass around sharp corners and through penetrations.
16. Ground wire must be copper, and grounding methods must comply with IEEE C2. Demonstrate ground resistance.

C. Balanced Twisted Pair Cable Installation:

1. Comply with TIA-568-C.2.
2. Provide termination hardware as specified in Section 271513 "Communications Copper Horizontal Cabling" unless otherwise indicated.
3. Do not untwist balanced twisted pair cables more than 1/2 inch at the point of termination to maintain cable geometry.

D. Installation of Control-Circuit Conductors:

1. Provide wiring in raceways.
2. Use insulated spade lugs for wire and cable connection to screw terminals.

3. Comply with requirements specified in Section 260533 "Raceways and Boxes for Electrical Systems."

E. Open-Cable Installation:

1. Provide cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
2. Cable must not be run through or on structural members or in contact with pipes, ducts, or other potentially damaging items. Do not run cables between structural members and corrugated panels.

F. Separation from EMI Sources:

1. Comply with BICSI TDMM and TIA-569-D recommendations for separating unshielded copper voice and data communications cable from potential EMI sources including electrical power lines and equipment.
2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment must be as follows:

   a. Electrical Equipment or Circuit Rating Less Than 2 kVA: A minimum of 5 inch.
   b. Electrical Equipment or Circuit Rating between 2 and 5 kVA: A minimum of 12 inch.
   c. Electrical Equipment or Circuit Rating More Than 5 kVA: A minimum of 24 inch.

3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment must be as follows:

   a. Electrical Equipment or Circuit Rating Less Than 2 kVA: A minimum of 2-1/2 inch.
   b. Electrical Equipment or Circuit Rating between 2 and 5 kVA: A minimum of 6 inch.
   c. Electrical Equipment or Circuit Rating More Than 5 kVA: A minimum of 12 inch.

4. Separation between communications cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures must be as follows:

   a. Electrical Equipment or Circuit Rating Less Than 2 kVA: No requirement.
   b. Electrical Equipment or Circuit Rating between 2 and 5 kVA: A minimum of 3 inch.
   c. Electrical Equipment or Circuit Rating More Than 5 kVA: A minimum of 6 inch.

5. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or 5 HP and Larger: A minimum of 48 inch.
6. Separation between Communications Cables and Fluorescent Fixtures: A minimum of 5 inch.

3.4 CONTROL-CIRCUIT CONDUCTORS

A. Minimum Conductor Sizes:

1. Class 1 remote-control and signal circuits; No 14 AWG.
2. Class 2 low-energy, remote-control, and signal circuits; No. 16 AWG.
3. Class 3 low-energy, remote-control, alarm, and signal circuits; No 12 AWG.

3.5 FIRESTOPPING

A. Comply with requirements in Section 078413 "Penetration Firestopping."

B. Comply with TIA-569-D, Annex A, "Firestopping."

C. Comply with BICSI TDMM, "Firestopping" Chapter.

3.6 GROUNDING

A. For data communication wiring, comply with TIA-607-B and with BICSI TDMM, "Bonding and Grounding (Earthing)" Chapter.

B. For control-voltage wiring and cabling, comply with requirements in Section 260526 "Grounding and Bonding for Electrical Systems."

3.7 IDENTIFICATION

A. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

B. Identify data and communications system components, wiring, and cabling according to TIA-606-B; label printers must use label stocks, laminating adhesives, and inks complying with UL 969.

C. Identify each wire on each end and at each terminal with a number-coded identification tag. Each wire must have a unique tag.

3.8 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. Visually inspect cable jacket materials for UL or third-party certification markings. Inspect cabling terminations to confirm color-coding for pin assignments, and inspect cabling connections to confirm compliance with TIA-568-C.1.
2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
3. Test cabling for direct-current loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination, but not after cross-connection.

    a. Test instruments must meet or exceed applicable requirements in TIA-568-C.2. Perform tests with a tester that complies with performance requirements in its "Test Instruments (Normative)" Annex, complying with measurement accuracy

specified in its "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.

B. Document data for each measurement. Print data for submittals in a summary report that is formatted using Table 10.1 in BICSI TDMM as a guide, or transfer the data from the instrument to the computer, save as text files, print, and submit.

C. End-to-end cabling will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

END OF SECTION

SECTION 260526 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Grounding and bonding conductors.
2. Grounding and bonding clamps.
3. Grounding and bonding bushings.
4. Grounding and bonding hubs.
5. Grounding and bonding connectors.
6. Intersystem bonding bridge grounding connector.
7. Grounding and bonding busbars.
8. Grounding (earthing) electrodes.
9. Grounding electrode enclosures.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Shop Drawings: Plans showing dimensioned locations of grounding features described in "Field Quality Control for Grounding and Bonding of Electrical Power" Article, including the following:

1. Grounding electrode access enclosures.
2. Grounding electrodes.
3. Grounding arrangements and connections for separately derived systems.
4. Interconnection with lighting protection system.

D. Field quality-control reports.

PART 2 - PRODUCTS

2.1 GROUNDING AND BONDING CONDUCTORS

A. Equipment Grounding Conductor:

1. General Characteristics: 600 V, THHN/THWN-2 or THWN-2, copper or tinned-copper wire or cable, green color, in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. ASTM - Bare Copper Grounding and Bonding Conductor:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ERICO; brand of nVent Electrical plc.
b. Harger Lightning & Grounding; business of Harger, Inc.

2. Referenced Standards: Complying with one or more of the following:

a. Soft or Annealed Copper Wire: ASTM B3.
b. Concentric-Lay Stranded Copper Conductor: ASTM B8.
c. Tin-Coated Soft or Annealed Copper Wire: ASTM B33.

2.2 GROUNDING AND BONDING CLAMPS

A. Description: Clamps suitable for attachment of grounding and bonding conductors to grounding electrodes, pipes, tubing, and rebar. Grounding and bonding clamps specified in this article are also suitable for use with communications applications.

B. Performance Criteria:

1. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2. Listing Criteria:

a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.
b. Grounding and Bonding Equipment for Communications: UL CCN KDSH; including UL 467.

C. UL KDER - Exothermically Welded Connection:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. ALLTEC LLC.
c. Continental Industries; brand of Hubbell Utility Solutions; Hubbell Incorporated.
d. Crouse-Hinds; brand of Eaton, Electrical Sector.
e. ERICO; brand of nVent Electrical plc.
f. Harger Lightning & Grounding; business of Harger, Inc.
g. Burndy; brand of Hubbell Electrical Solutions; Hubbell Incorporated.

2. General Characteristics: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.

2.3 GROUNDING AND BONDING CONNECTORS

A. Source Limitations: Obtain products from single manufacturer.

B. Performance Criteria:

1. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2. Listing Criteria:

a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.
b. Grounding and Bonding Equipment for Communications: UL CCN KDSH; including UL 467.

C. UL KDER - Crimped Lug Pressure-Type Grounding and Bonding Busbar Terminal:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Harger Lightning & Grounding; business of Harger, Inc.
c. ILSCO.
d. Burndy; brand of Hubbell Electrical Solutions; Hubbell Incorporated.

D. UL KDER - Crimped Pressure-Type Grounding and Bonding Cable Connector:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Burndy; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
c. ILSCO.
d. allG Fabrication (formerly ALT).

2. General Characteristics: Crimp-and-compress connectors that bond to conductor when connector is compressed around conductor.

a. Tinned copper, C and H shaped.

E. UL KDER - Split-Bolt Pressure-Type Grounding and Bonding Cable Connector:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.

b. ERICO; brand of nVent Electrical plc.
c. Greaves Corp.; Essex Products Group, Inc.
d. allG Fabrication (formerly ALT).
e. Burndy; brand of Hubbell Electrical Solutions; Hubbell Incorporated.

2. General Characteristics: Bolts that surround cable and bond to cable under compression when nut is tightened.

a. Tinned copper.

2.4 INTERSYSTEM BONDING BRIDGE GROUNDING CONNECTORS

A. Description: Devices that provide means for connecting communications systems grounding and bonding conductors at service equipment or at disconnecting means for buildings or structures.

B. Performance Criteria:

1. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2. Listing Criteria:

a. Grounding and Bonding Equipment for Communications: UL CCN KDSH; including UL 467.

C. UL KDSH - Two-Piece Intersystem Bonding Bridge Grounding Connector:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Burndy; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
b. Crouse-Hinds; brand of Eaton, Electrical Sector.
c. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.

2. General Characteristics: Copper body and polycarbonate cover; four terminating points.

2.5 GROUNDING AND BONDING BUSBARS

A. Description: Miscellaneous grounding and bonding devices that serve as common connection for multiple grounding and bonding conductors.

B. Performance Criteria:

1. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2. Listing Criteria:

a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.

2.6 GROUNDING (EARTHING) ELECTRODES

A. Performance Criteria:

1. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2. Listing Criteria:

a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.

B. UL KDER - Rod Electrode:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Continental Industries; brand of Hubbell Utility Solutions; Hubbell Incorporated.
c. ERICO; brand of nVent Electrical plc.
d. Galvan Industries, Inc.; Electrical Products Division, LLC.
e. Harger Lightning & Grounding; business of Harger, Inc.
f. allG Fabrication (formerly ALT).

2. General Characteristics: Copper-clad steel; 3/4 inch by 10 ft.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine facility's grounding electrode system and equipment grounding for compliance with requirements for maximum ground-resistance level and other conditions affecting performance of grounding and bonding of electrical system.

B. Inspect test results of grounding system measured at point of electrical service equipment connection.

C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

D. Proceed with connection of electrical service equipment only after unsatisfactory conditions have been corrected.

3.2 SELECTION OF GROUNDING AND BONDING PRODUCTS

A. Grounding and Bonding Conductors:

1. Provide solid conductor for 8 AWG and smaller, and stranded conductors for 6 AWG and larger unless otherwise indicated.

B. Grounding and Bonding Connectors:

1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
2. Underground Connections: Welded connectors except at test wells and as otherwise indicated.
3. Connections to Structural Steel: Welded connectors.

C. Grounding and Bonding Busbars: Provide in electrical equipment rooms, in rooms housing service equipment in MDF, IDF, and Server Rooms, and elsewhere as indicated on Drawings.

3.3 INSTALLATION OF GROUNDING AND BONDING

A. Comply with manufacturer's published instructions.

B. Reference Standards:

1. Ground Bonding Common with Lightning Protection System: Comply with NFPA 780 and UL 96 when interconnecting with lightning protection system. Bond electrical power system ground directly to lightning protection system grounding conductor at closest point to electrical service grounding electrode. Use bonding conductor sized same as system grounding electrode conductor, and install in conduit.
2. Consult Designer for resolution of conflicting requirements.

C. Special Techniques:

1. Grounding and Bonding Conductors:

a. Route along shortest and straightest paths possible unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.
b. Underground Grounding Conductors:

1) Bury at least 30 inch below grade.
2) Duct-Bank Grounding Conductor: Bury 12 inch above duct bank when indicated as part of duct-bank installation.

2. Grounding and Bonding Connectors: Make connections so possibility of galvanic action or electrolysis is minimized. Select connectors, connection hardware, conductors, and connection methods so metals in direct contact are galvanically compatible.

    a. Use electroplated or hot-tin-coated materials to ensure high conductivity and to make contact points closer in order of galvanic series.
    b. Make connections with clean, bare metal at points of contact.
    c. Make aluminum-to-steel connections with stainless steel separators and mechanical clamps.
    d. Make aluminum-to-galvanized-steel connections with tin-plated copper jumpers and mechanical clamps.
    e. Coat and seal connections having dissimilar metals with inert material to prevent future penetration of moisture to contact surfaces.
    f. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance except where routed through short lengths of conduit.

        1) Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate adjacent parts.
        2) Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install bonding so vibration is not transmitted to rigidly mounted equipment.
        3) Use exothermic-welded connectors for outdoor locations; if disconnect-type connection is required, use bolted clamp.

    g. Grounding and Bonding for Piping:

        1) Metal Water Service Pipe: Install insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes; use bolted clamp connector or bolt lug-type connector to pipe flange by using one of lug bolts of flange. Where dielectric main water fitting is installed, connect grounding conductor on street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
        2) Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with bolted connector.
        3) Bond each aboveground portion of gas piping system downstream from equipment shutoff valve.

    h. Bonding Interior Metal Ducts: Bond metal air ducts to equipment grounding conductors of associated fans, blowers, electric heaters, and air cleaners. Install tinned bonding jumper to bond across flexible duct connections to achieve continuity.

3. Grounding and Bonding Busbars:

    a. Install busbar horizontally, on insulated spacers 2 inch minimum from wall, 6 inch above finished floor unless otherwise indicated.
    b. Where busbars are indicated on both sides of doorways, route bonding conductor up to top of door frame, across top of doorway, and down; connect to continuation of horizontal busbar.

4. Electrodes:

    a. Ground Rods: Drive rods until tops are 2 inch below finished floor or final grade unless otherwise indicated.

        1) Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating if any.
        2) Use exothermic welds for below-grade connections.

    b. For grounding electrode system, install at least three rods spaced at least one-rod length from each other and located at least same distance from other grounding electrodes, and connect to service grounding electrode conductor.
    c. Test Wells: Ground rod driven through drilled hole in bottom of handhole. Handholes are specified in Section 260543 "Underground Ducts and Raceways for Electrical Systems," and must be at least 12 inch deep, with cover.

        1) Install at least one test well for each service unless otherwise indicated. Install at ground rod electrically closest to service entrance. Set top of test well flush with finished grade or floor.

5. Grounding at Service:

    a. Equipment grounding conductors and grounding electrode conductors must be connected to ground busbar. Install main bonding jumper between neutral and ground buses.

6. Grounding Separately Derived Systems:

    a. Permanent Generators: Install grounding electrode(s) at location of permanent generators having switched neutral connections. Electrode must be connected to equipment grounding conductor and frame of generator.

7. Grounding Underground Distribution System Components:

    a. Duct-Bank Grounding Conductor: Bury 12 inch above duct bank when indicated as part of duct-bank installation.
    b. Comply with IEEE C2 grounding requirements.
    c. Grounding Manholes and Handholes: Install driven ground rod through manhole or handhole floor, close to wall, and set rod depth so 4 inch will extend above finished floor. If necessary, install ground rod before manhole is placed and provide 1/0 AWG bare, tinned-copper conductor from ground rod into manhole through waterproof sleeve in manhole wall. Protect ground rods passing through concrete floor with double wrapping of pressure-sensitive insulating tape or heat-shrunk insulating sleeve from 2 inch above to 6 inch below concrete. Seal floor opening with waterproof, nonshrink grout.

8. Equipment Grounding and Bonding:

    a. Install insulated equipment grounding conductors with feeders and branch circuits.
    b. Install insulated equipment grounding conductors with the following items, in addition to those required by NFPA 70:

1) Feeders and branch circuits.
2) Lighting circuits.
3) Receptacle circuits.
4) Single-phase motor and appliance branch circuits.
5) Flexible raceway runs.

c. Air-Duct Equipment Circuits: Install insulated equipment grounding conductor to duct-mounted electrical devices operating at 120 V and more, including air cleaners, heaters, dampers, humidifiers, and other duct electrical equipment. Bond conductor to each unit and to air duct and connected metallic piping.
d. Water Heater, Heat-Tracing, and Antifrost Heating Cables: Install separate insulated equipment grounding conductor to each electric water heater and heat-tracing cable. Bond conductor to heater units, piping, connected equipment, and components.
e. Isolated Equipment Enclosure Circuits: For designated equipment supplied by branch circuit or feeder, isolate equipment enclosure from supply circuit raceway with nonmetallic raceway fitting listed for the purpose. Install fitting where raceway enters enclosure, and install separate insulated equipment grounding conductor. Isolate conductor from raceway and from panelboard grounding terminals. Terminate at equipment grounding conductor terminal of applicable derived system or service unless otherwise indicated.

3.4 FIELD QUALITY CONTROL FOR GROUNDING AND BONDING

A. Tests and Inspections:

1. After installing grounding system but before permanent electrical circuits have been energized, test for compliance with requirements.
2. Inspect physical and mechanical condition. Verify tightness of accessible, bolted, electrical connections with calibrated torque wrench in accordance with manufacturer's published instructions.
3. Test completed grounding system at each location where maximum ground-resistance level is specified, at service disconnect enclosure grounding terminal, at ground test wells, and at individual ground rods. Make tests at ground rods before conductors are connected.

    a. Measure ground resistance no fewer than two full days after last trace of precipitation and without soil being moistened by means other than natural drainage or seepage and without chemical treatment or other artificial means of reducing natural ground resistance.
    b. Perform tests by fall-of-potential method in accordance with IEEE Std 81.
    c. Excessive Ground Resistance: If resistance to ground exceeds specified values, notify Designer promptly and include recommendations to reduce ground resistance.

4. Prepare dimensioned Drawings locating each test well, ground rod and ground-rod assembly, and other grounding electrodes. Identify each by letter in alphabetical order, and key to record of tests and observations. Include number of rods driven and their depth at each location, and include observations of weather and other phenomena that may affect test results. Describe measures taken to improve test results.

B. Nonconforming Work:

1. Grounding system will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective components and retest.

C. Collect, assemble, and submit test and inspection reports.

1. Report measured ground resistances that exceed the following values:

a. Power and Lighting Equipment or System with Capacity of 500 kVA and Less: 10 Ω.
b. Power Distribution Units or Panelboards Serving Electronic Equipment: 1 Ω.
c. Manhole Grounds: 10 Ω.

3.5 PROTECTION

A. After installation, protect grounding and bonding cables and equipment from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Designer.

END OF SECTION

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Support, anchorage, and attachment components.
2. Fabricated metal equipment support assemblies.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data:

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for the following:

a. Slotted support systems, hardware, and accessories.
b. Clamps.
c. Hangers.
d. Sockets.
e. Eye nuts.
f. Fasteners.
g. Anchors.
h. Saddles.
i. Brackets.

2. Include rated capacities and furnished specialties and accessories.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame Rating: Class 1.
2. Self-extinguishing according to ASTM D635.

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

A. Steel Slotted Support Systems: Preformed steel channels and angles with minimum 13/32 inch diameter holes at a maximum of 8 inch on center in at least one surface.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Allied Tube & Conduit; Atkore International.
c. CADDY; brand of nVent Electrical plc.
d. Cooper B-line; brand of Eaton, Electrical Sector.
e. Flex-Strut Inc.
f. G-Strut.
g. Gripple Inc.
h. Haydon Corporation.
i. MIRO Industries Inc.
j. Metal Ties Innovation.
k. Rocket Rack; Robroy Industries.
l. Unistrut; Atkore International.
m. Wesanco, Inc.

2. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
3. Material for Channel, Fittings, and Accessories: Galvanized steel.
4. Channel Width: Selected for applicable load criteria.
5. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
6. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.
7. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
8. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

B. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.

C. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for nonarmored electrical conductors or cables in riser conduits. Plugs must have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body must be made of malleable iron.

D. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:

1. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.

a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1) Cooper B-line; brand of Eaton, Electrical Sector.
2) Empire Industries, Inc.
3) Hilti, Inc.
4) ITW Ramset/Red Head; Illinois Tool Works, Inc.
5) MKT Fastening, LLC.

2. Concrete Inserts: Steel or malleable-iron, slotted support system units are similar to MSS Type 18 units and comply with MFMA-4 or MSS SP-58.
3. Clamps for Attachment to Steel Structural Elements: MSS SP-58 units are suitable for attached structural element.
4. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM F3125/F3125M, Grade A325.
5. Toggle Bolts: All steel springhead type.
6. Hanger Rods: Threaded steel.

PART 3 - EXECUTION

3.1 SELECTION

A. Comply with the following standards for selection and installation of hangers and supports, except where requirements on Drawings or in this Section are stricter:

1. NECA NEIS 101
2. NECA NEIS 102.

B. Comply with requirements for raceways specified in Section 260533.13 "Conduits for Electrical Systems."

C. Comply with requirements for boxes specified in Section 260533.16 "Boxes and Covers for Electrical Systems."

D. Maximum Support Spacing and Minimum Hanger Rod Size for Raceways: Space supports for EMT, and ERMC as required by NFPA 70. Minimum rod size must be 1/4 inch in diameter.

E. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2 inch and smaller raceways serving branch circuits and communication systems above suspended ceilings, and for fastening raceways to trapeze supports.

3.2 INSTALLATION OF SUPPORTS

A. Comply with NECA NEIS 101 for installation requirements except as specified in this article.

B. Raceway Support Methods: In addition to methods described in NECA NEIS 1, EMT and ERMC may be supported by openings through structure members, in accordance with NFPA 70.

C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits.

Minimum static design load used for strength determination must be weight of supported components plus 200 lb.

D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:

1. To Wood: Fasten with lag screws or through bolts.
2. To New Concrete: Bolt to concrete inserts.
3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
4. To Existing Concrete: Expansion anchor fasteners.
5. To Light Steel: Sheet metal screws.
6. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate.

E. Drill holes for expansion anchors in concrete at locations and to depths that avoid the need for reinforcing bars.

3.3 PAINTING

A. Touchup:

1. Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.

   a. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.

2. Comply with requirements in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting" for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.

B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A780.

END OF SECTION

SECTION 260533.13 - CONDUITS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Type EMT duct raceways and elbows.
2. Type ERMC/RGS duct raceways.
3. Type FMC duct raceways.
4. Type LFMC duct raceways.
5. Fittings for conduit, tubing, and cable.
6. Joint compounds.
7. Solvent cements.

B. Related Requirements:

1. Section 018116 "Facility Environmental Requirements" specifies temperature, humidity, acoustical, and other field conditions applicable to the Work specified in this Section.
2. Section 260010 "Supplemental Requirements for Electrical" specifies additional coordination, scheduling, sequencing, submittal, and installation requirements applicable to the Work for electrical, communications, and electronic safety and security systems on the Project, including wiring methods.
3. Section 078413 "Penetration Firestopping" specifies firestopping referenced by this Section.
4. Section 260519 "Low-Voltage for Electrical Power Conductors and Cables" specifies nonmetallic underground conduit with conductors (Type NUCC).
5. Section 260529 "Hangers and Supports for Electrical Systems" specifies conduit hangers and supports referenced by this Section.
6. Section 260543 "Underground Ducts and Raceways for Electrical Systems" specifies exterior duct banks, manholes, and underground utility construction.
7. Section 260553 "Identification for Electrical Systems" specifies electrical equipment labels.

1.2 REFERENCES

A. Abbreviations and Acronyms for Electrical Raceway Types:

1. EMT: Electrical metallic tubing.
2. EMT-S: Steel electrical metallic tubing.
3. ERMC: Electrical rigid metal conduit.
4. ERMC-S: Steel electrical rigid metal conduit.
5. FMC: Flexible metal conduit.
6. FMC-S: Steel flexible metal conduit.
7. LFMC: Liquidtight flexible metal conduit.
8. LFMC-S: Steel liquidtight flexible metal conduit.
9. PVC-40: Schedule 40 rigid PVC conduit.

B. Definitions:

1. Conduit: A structure containing one or more duct raceways.
2. Direct Buried: Installed underground without encasement in concrete or other protective material.
3. Duct Bank: An arrangement of conduit providing one or more continuous duct raceways between two points.
4. Duct Raceway: A single enclosed raceway for conductors or cable.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Field quality-control reports.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Manufacturer's published instructions.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Products or components listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2.2 TYPE EMT DUCT RACEWAYS AND ELBOWS

A. UL FJMX - Steel Electrical Metal Tubing (EMT-S) and Elbows:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Allied Tube & Conduit; Atkore International.
b. Calconduit; Atkore International.
c. Emerson Electric Co., Automation Solutions.
d. Picoma; Zekelman Industries.
e. Republic Conduit; Nucor Corporation, Nucor Tubular Products.
f. Topaz Lighting & Electric.

g. Western Tube; Zekelman Industries.
h. Wheatland Tube; Zekelman Industries.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN FJMX; including UL 797.

3. Standard Features:

a. Material: Steel.
b. Exterior Coating: Zinc.
c. Interior Coating: Zinc.
d. Minimum Trade Size: 3/4".

4. Other Available Features Required by the Project:

a. Colors: As indicated on the Drawings.

2.3 TYPE ERMC DUCT RACEWAYS, ELBOWS, COUPLINGS, AND NIPPLES

A. UL DYIX - Galvanized-Steel Electrical Rigid Metal Conduit (ERMC-S-G), Elbows, Couplings, and Nipples:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Allied Tube & Conduit; Atkore International.
b. Calconduit; Atkore International.
c. Crouse-Hinds; brand of Eaton, Electrical Sector.
d. Killark; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
e. Patriot Aluminum Products, LLC.
f. Republic Conduit; Nucor Corporation, Nucor Tubular Products.
g. Rymco USA brand; manufactured and listed by subsidiary Conduit S.A. de C.V.
h. Topaz Lighting & Electric.
i. Western Tube; Zekelman Industries.
j. Wheatland Tube; Zekelman Industries.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN DYIX; including UL 6.

3. Standard Features:

a. Exterior Coating: Zinc.
b. Interior Coating: Zinc.
c. Minimum Trade Size: 3/4".

2.4 TYPE FMC DUCT RACEWAYS

A. UL DXUZ - Steel Flexible Metal Conduit (FMC-S):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ABB, Electrification Business.
b. Anaconda Sealtite; Anamet Electrical, Inc.
c. Electri-Flex Company.
d. International Metal Hose Co.
e. Penn Aluminum Conduit & EMT; Penn Aluminum International LLC; Berkshire Hathaway.
f. Topaz Lighting & Electric.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN DXUZ; including UL 1.

3. Standard Features:

a. Material: Steel.
b. Minimum Trade Size: 3/4".

4. Other Available Features Required by the Project:

a. Colors: As indicated on the Drawings.

2.5 TYPE LFMC DUCT RACEWAYS

A. UL DXHR - Steel Liquidtight Flexible Metal Conduit (LFMC-S):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ABB, Electrification Business.
b. Anaconda Sealtite; Anamet Electrical, Inc.
c. Electri-Flex Company.
d. International Metal Hose Co.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN DXHR; including UL 360.

3. Standard Features:

a. Material: Steel.
b. Minimum Trade Size: 3/4".

4. Other Available Features Required by the Project:

a. Colors: As indicated on the Drawings.

2.6 TYPE PVC DUCT RACEWAYS AND FITTINGS

A. UL DZYR - Schedule 40 Rigid PVC Conduit (PVC-40) and Fittings:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Calconduit; Atkore International.
c. JM Eagle.
d. NAPCO; Westlake Chemical Corp.
e. National Pipe and Plastic, Inc. (Oldcastle).
f. Opti-Com Manufacturing Network, Inc (OMNI).
g. Topaz Lighting & Electric.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN DZYR; including UL 651.

3. Standard Features:

a. Dimensional Specifications: Schedule 40.
b. Minimum Trade Size: 1”.

2.7 FITTINGS FOR CONDUIT, TUBING, AND CABLE

A. UL FKAV - Fittings for Type EMT Duct Raceways:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ABB, Electrification Business.
b. Allied Tube & Conduit; Atkore International.
c. Appleton; Emerson Electric Co., Automation Solutions.
d. Calconduit; Atkore International.
e. Crouse-Hinds; brand of Eaton, Electrical Sector.
f. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
g. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.

h. Southwire Company, LLC.
i. Topaz Lighting & Electric.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN FKAV; including UL 514B.

3. Standard Features:

a. Material: Steel.
b. Coupling Method: Compression coupling.
c. Expansion and Deflection Fittings: UL 651 with flexible bonding jumper.

B. UL ILNR - Fittings for Type FMC Duct Raceways:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. American Fittings Corp. (AMFICO).
b. Liquid Tight Connector Co.
c. Southwire Company, LLC.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN ILNR; including UL 514B.

C. UL DXAS - Fittings for Type LFMC Duct Raceways:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Arlington Industries, Inc.
b. Liquid Tight Connector Co.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN DXAS; including UL 514B.

PART 3 - EXECUTION

3.1 SELECTION OF CONDUITS FOR ELECTRICAL SYSTEMS

A. Unless more stringent requirements are specified in the Contract Documents or manufacturer's published instructions, comply with NFPA 70 for selection of duct raceways. Consult Architect for resolution of conflicting requirements.

B. Outdoors:

1. Exposed: ERMC/RGS.
2. Concealed Aboveground: ERMC/RGS.
3. Direct Buried: PVC-40.
4. Concrete Encased in Trench: PVC-40.
5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.

C. Indoors:

1. Exposed: EMT.
2. Concealed in Ceilings and Interior Walls and Partitions: EMT.
3. Damp or Wet Locations: ERMC/RGS.
4. Critical Operations Power System: ERMC/RGS.
5. Wiring for HVAC, Fire Alarm, Security, Emergency Communications, and Signaling Systems serving the Critical Operations Power System: ERMC/RGS.
6. Conduits must be concealed in finished spaces. Provide interior conduit coordination drawing. Provide underslab conduit coordination drawing.

D. Duct Fittings: Select fittings in accordance with NEMA FB 2.10 guidelines.

1. ERMC: Provide threaded-type fittings unless otherwise indicated.

3.2 INSTALLATION OF CONDUITS FOR ELECTRICAL SYSTEMS

A. Comply with manufacturer's published instructions.

B. Reference Standards for Installation: Unless more stringent installation requirements are specified in the Contract Documents or manufacturer's published instructions, comply with the following:

1. Electrical Construction: ICC IBC, ICC IFC, NFPA 1, NFPA 70, and NECA NEIS 1.
2. Electrical Safety: NFPA 70E.
3. Commissioning of Active and Passive Fire Protection Features: NFPA 3 and NFPA 4.
4. Grounding and Bonding: NECA NEIS 331 and Article 250 of NFPA 70.
5. Communications Work: BICSI N1.
6. Life Safety and Means of Egress Work: NFPA 101.
7. Emergency and Standby Power Work: NFPA 110, NFPA 111, and NECA NEIS 416.
8. Work in Confined Spaces: NFPA 350.
9. Work in Basements and Other Developed Subterranean Spaces: NFPA 520.
10. Type EMT-S: Article 358 of NFPA 70 and NECA NEIS 101.

11. Type ERMC-S: Article 344 of NFPA 70 and NECA NEIS 101.
12. Type FMC-S: Article 348 of NFPA 70 and NECA NEIS 101.
13. Type LFMC: Article 350 of NFPA 70 and NECA NEIS 101.
14. Expansion Fittings: NEMA FB 2.40.
15. Consult Architect for resolution of conflicting requirements.

C. Special Installation Techniques:

1. General Requirements for Installation of Duct Raceways:

a. Complete duct raceway installation before starting conductor installation.
b. Make bends in duct raceway using large-radius preformed ells except for parallel bends. Field bending must be in accordance with NFPA 70 minimum radii requirements. Provide only equipment specifically designed for material and size involved.
c. Conceal conduit within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
d. Support conduit within 12 inch of enclosures to which attached.
e. Install duct sealing fittings at accessible locations in accordance with NFPA 70 and fill them with listed sealing compound. For concealed duct raceways, install fitting in flush steel box with blank cover plate having finish similar to that of adjacent plates or surfaces. Install duct sealing fittings in accordance with NFPA 70.
f. Install devices to seal duct raceway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal interior of duct raceways at the following points:

1) Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
2) Where an underground service duct raceway enters a building or structure.
3) Conduit extending from interior to exterior of building.
4) Conduit extending into pressurized duct raceway and equipment.
5) Conduit extending into pressurized zones that are automatically controlled to maintain different pressure set points.
6) Where otherwise required by NFPA 70.

g. Do not install conduits within 2 inch of the bottom side of a metal deck roof.
h. Keep duct raceways at least 6 inch away from parallel runs of flues and steam or hot-water pipes. Install horizontal duct raceway runs above water and steam piping.
i. Cut conduit perpendicular to the length. For conduits metric designator 53 (trade size 2) and larger, use roll cutter or a guide to make cut straight and perpendicular to the length. Ream inside of conduit to remove burrs.
j. Install pull wires in empty duct raceways. Provide polypropylene or monofilament plastic line with not less than 200 lb tensile strength. Leave at least 12 inch of slack at both ends of pull wire. Cap underground duct raceways designated as spare above grade alongside duct raceways in use.
k. Install duct raceways square to the enclosure and terminate at enclosures without hubs with locknuts on both sides of enclosure wall. Install locknuts hand tight, plus one-quarter turn more.

1) Termination fittings with shoulders do not require two locknuts.

l. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to metric designator 35 (trade size 1-1/4) and insulated throat metal bushings on metric designator 41 (trade size 1-1/2) and larger conduits terminated with locknuts. Install insulated throat metal grounding bushings on service conduits.

2. Types ERMC:

a. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound that maintains electrical conductivity to threads of duct raceway and fittings before making up joints. Follow compound manufacturer's published instructions.

3. Types FMC, LFMC:

a. Provide a maximum of 72 inch of flexible conduit for recessed and semirecessed luminaires, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.

4. Types PVC:

a. Do not install Type PVC, Type HDPE, or Type EPEC conduit where ambient temperature exceeds 122 deg F. Conductor ratings must be limited to 75 deg C except where installed in a trench outside buildings with concrete encasement, where 90 deg C conductors are permitted.
b. Comply with manufacturer's published instructions for solvent welding and fittings.
c. Join joints with solvent cement in accordance with manufacturer's published instructions and allowed to cure before handling. Joints to be bent, pushed, or pulled must set for minimum 24 h after joining.

5. Stub-ups to Above Recessed Ceilings:

a. Provide EMT for duct raceways.
b. Provide a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.

6. Duct Fittings: Install fittings in accordance with NEMA FB 2.10 guidelines.

a. EMT: Provide compression, fittings. Comply with NEMA FB 2.10.
b. Flexible Conduit: Provide only fittings listed for use with flexible conduit type. Comply with NEMA FB 2.20.

7. Expansion-Joint Fittings:

a. Install in runs of aboveground ERMC and EMT conduit that are located where environmental temperature change may exceed 100 deg F and that have straight-run length that exceeds 100 ft.

8. Identification: Provide labels for conduit assemblies, duct raceways, and associated electrical equipment.

a. Provide warning signs.

D. Interfaces with Other Work:

1. Firestop penetrations of fire-rated floor and wall assemblies.
2. Provide conduit hangers and supports.

3.3 FIELD QUALITY CONTROL OF CONDUITS FOR ELECTRICAL SYSTEMS

A. Tests and Inspections:

1. Perform manufacturer's recommended tests and inspections.
2. Conduit Placement:

a. Verify that center-line location and offsets are in accordance with the Drawings.
b. Verify that hangers and supports for conduits are attached to structure.
c. Verify that nuts on bolts or hanger rods are secure.
d. Verify that space between raceways and cored holes are filled with non-shrinking grout or other approved material indicated on the Drawings and the Specifications.
e. Verify that expansion devices are installed at locations indicated on the Drawings and the Specifications.
f. Verify that ends are cut square to provide flush-butting surfaces when spliced and inside edges are free of burrs that could impede installation of cables.
g. Verify minimum separation of utilities, or that approved mechanical protection has been provided to surrounding conduit(s) where minimum separation cannot be achieved.

3. Document all changes on Record Drawings.

B. Nonconforming Work:

1. Conduit will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

C. Field Quality-Control Reports: Collect, assemble, and submit test and inspection reports.

3.4 CLEANING

A. Verify that bentonite or other drilling fluids are contained and removed, and site is restored to its original or improved condition.

3.5 PROTECTION

A. Protect coatings, finishes, and cabinets from damage and deterioration.

1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION

SECTION 260533.16 - BOXES AND COVERS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Metallic outlet boxes, device boxes, rings, and covers.
2. Junction boxes and pull boxes.
3. Cover plates for device boxes.
4. Hoods for outlet boxes.

B. Products Installed, but Not Furnished, under This Section:

1. See Section 260553 "Identification for Electrical Systems" for electrical equipment labels.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data:

1. Metallic outlet boxes, device boxes, rings, and covers.
2. Junction boxes and pull boxes.
3. Cover plates for device boxes.
4. Hoods for outlet boxes.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Manufacturers' Published Instructions:

1. Metallic outlet boxes, device boxes, rings, and covers.
2. Junction boxes and pull boxes.
3. Cover plates for device boxes.
4. Hoods for outlet boxes.

PART 2 - PRODUCTS

2.1 METALLIC OUTLET BOXES, DEVICE BOXES, RINGS, AND COVERS

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Listing Criteria: UL CCN QCIT; including UL 514A.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

C. UL QCIT - Metallic Outlet Boxes and Covers:

1. Description: Box having pryout openings, knockouts, threaded entries, or hubs in either the sides of the back, or both, for entrance of conduit, conduit or cable fittings, or cables, with provisions for mounting outlet box cover, but without provisions for mounting wiring device directly to box.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. ABB, Electrification Business.
    b. Appleton; Emerson Electric Co., Automation Solutions.
    c. Arlington Industries, Inc.
    d. Crouse-Hinds; brand of Eaton, Electrical Sector.
    e. Hubbell Premise Wiring; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    f. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    g. Killark; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    h. MonoSystems, Inc.
    i. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
    j. Pass & Seymour; Legrand North America, LLC.
    k. Patriot Aluminum Products, LLC.
    l. Plasti-Bond; Robroy Industries.
    m. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    n. Spring City Electrical Manufacturing Company.
    o. Topaz Lighting & Electric.
    p. Wiremold; Legrand North America, LLC.

3. Options:

    a. Material: Cast metal.

b. Sheet Metal Depth: Minimum 1.5 inch.
c. Cast-Metal Depth: Minimum 1.8 inch.
d. Luminaire Outlet Boxes and Covers: Nonadjustable, listed and labeled for attachment of luminaire weighing up to 50 lb.

D. UL QCIT - Metallic Conduit Bodies:

1. Description: Means for providing access to interior of conduit or tubing system through one or more removable covers at junction or terminal point. In the United States, conduit bodies are listed in accordance with outlet box requirements.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Appleton; Emerson Electric Co., Automation Solutions.
c. Crouse-Hinds; brand of Eaton, Electrical Sector.
d. Killark; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
e. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
f. Pass & Seymour; Legrand North America, LLC.
g. Patriot Aluminum Products, LLC.
h. Plasti-Bond; Robroy Industries.
i. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
j. Topaz Lighting & Electric.

E. UL QCIT - Metallic Device Boxes:

1. Description: Box with provisions for mounting wiring device directly to box.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Appleton; Emerson Electric Co., Automation Solutions.
c. Arlington Industries, Inc.
d. Crouse-Hinds; brand of Eaton, Electrical Sector.
e. Hubbell Premise Wiring; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
f. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
g. Killark; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
h. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
i. Patriot Aluminum Products, LLC.
j. Plasti-Bond; Robroy Industries.
k. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
l. Topaz Lighting & Electric.

3. Options:

a. Material: Cast metal.

b. Sheet Metal Depth: minimum 1.5 inch.
c. Cast-Metal Depth: minimum 1.8 inch.

F. UL QCIT - Metallic Extension Rings:

1. Description: Ring intended to extend sides of outlet box or device box to increase box depth, volume, or both.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Appleton; Emerson Electric Co., Automation Solutions.
c. Cooper B-line; brand of Eaton, Electrical Sector.
d. Crouse-Hinds; brand of Eaton, Electrical Sector.
e. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
f. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
g. Pass & Seymour; Legrand North America, LLC.
h. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
i. Topaz Lighting & Electric.

G. UL QCIT - Metallic Floor Boxes and Floor Box Covers:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. AFC Cable Systems; Atkore International.
c. Arlington Industries, Inc.
d. Arrow Hart, Wiring Devices; Eaton, Electrical Sector.
e. FSR Inc.
f. Hubbell Premise Wiring; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
g. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
h. Leviton Manufacturing Co., Inc.
i. Pass & Seymour; Legrand North America, LLC.
j. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
k. Wiremold; Legrand North America, LLC.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. UL CCN QCIT; including UL 514A.

3. Standard Features: Box mounted in floor with floor box cover and other components to complete floor box enclosure.

a. Provide voltage barrier for power and communications.
b. Provide metal cover flush with finished door.

2.2 JUNCTION BOXES AND PULL BOXES

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
2. Listing Criteria: UL CCN BGUZ; including UL 50 and UL 50E.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

C. UL BGUZ - Indoor Sheet Metal Junction and Pull Boxes:

1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Adalet.
b. Appleton; Emerson Electric Co., Automation Solutions.
c. Cooper B-line; brand of Eaton, Electrical Sector.
d. FSR Inc.
e. Hoffman; brand of nVent Electrical plc.
f. Hubbell Industrial Controls; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
g. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
h. Milbank Manufacturing Company.
i. N J Sullivan Company.
j. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
k. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
l. Spring City Electrical Manufacturing Company.
m. Square D; Schneider Electric USA.

3. Options:

a. Degree of Protection: Type 1.

D. UL BGUZ - Indoor Cast-Metal Junction and Pull Boxes:

1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Adalet.
    b. Appleton; Emerson Electric Co., Automation Solutions.
    c. Crouse-Hinds; brand of Eaton, Electrical Sector.
    d. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.

3. Options:

    a. Degree of Protection: Type 1.

E. UL BGUZ - Outdoor Sheet Metal Junction and Pull Boxes:

1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Adalet.
    b. Appleton; Emerson Electric Co., Automation Solutions.
    c. Cooper B-line; brand of Eaton, Electrical Sector.
    d. FSR Inc.
    e. Hoffman; brand of nVent Electrical plc.
    f. Hubbell Industrial Controls; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    g. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    h. Milbank Manufacturing Company.
    i. N J Sullivan Company.
    j. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
    k. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    l. Spring City Electrical Manufacturing Company.
    m. Square D; Schneider Electric USA.

3. Options:

    a. Degree of Protection: Type 3R.

F. UL BGUZ - Outdoor Cast-Metal Junction and Pull Boxes:

1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Adalet.
b. Appleton; Emerson Electric Co., Automation Solutions.
c. Crouse-Hinds; brand of Eaton, Electrical Sector.
d. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.

3. Options:

a. Degree of Protection: Type 3R.

2.3 COVER PLATES FOR DEVICES BOXES

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
2. Listing Criteria: UL CCN QCIT or UL CCN QCMZ; including UL 514D.
3. Wallplate-Securing Screws: Metal with head color to match wallplate finish.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

C. UL QCIT or QCMZ - Metallic Cover Plates for Device Boxes:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Appleton; Emerson Electric Co., Automation Solutions.
c. Arrow Hart, Wiring Devices; Eaton, Electrical Sector.
d. Crouse-Hinds; brand of Eaton, Electrical Sector.
e. Hubbell Premise Wiring; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
f. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
g. Intermatic, Inc.
h. Leviton Manufacturing Co., Inc.
i. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
j. Panduit Corp.
k. Pass & Seymour; Legrand North America, LLC.
l. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
m. Topaz Lighting & Electric.
n. Wiremold; Legrand North America, LLC.

2. Options:

a. Damp and Wet Locations: Listed, labeled, and marked for location and use. Provide gaskets and accessories necessary for compliance with listing.
b. Wallplate Material: 0.032 inch thick, color selected by Architect.

D. UL QCIT or QCMZ - Nonmetallic Cover Plates for Device Boxes:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Appleton; Emerson Electric Co., Automation Solutions.
c. Arlington Industries, Inc.
d. Arrow Hart, Wiring Devices; Eaton, Electrical Sector.
e. Crouse-Hinds; brand of Eaton, Electrical Sector.
f. Hubbell Premise Wiring; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
g. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
h. Intermatic, Inc.
i. Leviton Manufacturing Co., Inc.
j. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
k. Panduit Corp.
l. Pass & Seymour; Legrand North America, LLC.
m. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
n. Topaz Lighting & Electric.
o. Wiremold; Legrand North America, LLC.

2. Options:

a. Damp and Wet Locations: Listed, labeled, and marked for location and use. Provide gaskets and accessories necessary for compliance with listing.
b. Wallplate Material: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device.
c. Color: Color selected by architect.

2.4 HOODS FOR OUTLET BOXES

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
2. Listing Criteria:

a. UL CCN QCIT or UL CCN QCMZ; including UL 514D.
b. Receptacle, Hood, Cover Plate, Gaskets, and Seals: UL 498 Supplement SA when mated with box or enclosure complying with UL 514A, UL 514C, or UL 50E.

3. Mounts to box using fasteners different from wiring device.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

C. UL QCIT or QCMZ - Extra-Duty, While-in-Use Hoods for Outlet Boxes:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Allied Tube & Conduit; Atkore International.
c. Appleton; Emerson Electric Co., Automation Solutions.
d. Arlington Industries, Inc.
e. Arrow Hart, Wiring Devices; Eaton, Electrical Sector.
f. Intermatic, Inc.
g. Leviton Manufacturing Co., Inc.
h. Raco Taymac Bell; brand of Hubbell Electrical Solutions; Hubbell Incorporated.

2. Additional Characteristics: Marked "Extra-Duty" in accordance with UL 514D.
3. Options:

a. Provides clear, weatherproof, "while-in-use" cover.
b. Manufacturer may combine nonmetallic device box with hood as extra-duty rated assembly.

PART 3 - EXECUTION

3.1 PREPARATION

A. Shop Drawings: Prepare and submit the following:

1. Shop Drawings for Floor Boxes: Show that floor boxes are located to avoid interferences and are structurally allowable. Indicate floor thickness at location where boxes are embedded in concrete floors and underfloor clearances where boxes are installed in raised floors.

3.2 SELECTION OF BOXES AND COVERS FOR ELECTRICAL SYSTEMS

A. Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with NFPA 70 for selection of boxes and enclosures. Consult Designer for resolution of conflicting requirements.

B. Degree of Protection:

1. Outdoors:

a. Type 3R unless otherwise indicated.
b. Locations Exposed to Hosedown: Type 4.
c. Locations Aboveground Where Mechanism Must Operate When Ice Covered: Type 3S.

2. Indoors:

a. Type 1 unless otherwise indicated.
b. Damp or Dusty Locations: Type 2.
c. Locations Exposed to Airborne Dust, Lint, Fibers, or Flyings: Type 4.
d. Locations Exposed to Hosedown: Type 4.

3.3 INSTALLATION OF BOXES AND COVERS FOR ELECTRICAL SYSTEMS

A. Comply with manufacturer's published instructions.

B. Reference Standards for Installation: Unless more stringent installation requirements are specified in Contract Documents or manufacturers' published instructions, comply with the following:

1. Outlet, Device, Pull, and Junction Boxes: Article 314 of NFPA 70.
2. Consult Designer for resolution of conflicting requirements.

C. Special Installation Techniques:

1. Provide boxes in wiring and raceway systems wherever required for pulling of wires, making connections, and mounting of devices or fixtures.
2. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to bottom of box unless otherwise indicated.
3. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surfaces to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box, whether installed indoors or outdoors.
4. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
5. Locate boxes so that cover or plate will not span different building finishes.
6. Support boxes in recessed ceilings independent of ceiling tiles and ceiling grid.
7. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for purpose.
8. Fasten junction and pull boxes to, or support from, building structure. Do not support boxes by conduits.
9. Set metal floor boxes level and flush with finished floor surface.
10. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to ensure a continuous ground path.
11. Boxes and Enclosures in Areas or Walls with Acoustical Requirements:

a. Seal openings and knockouts in back and sides of boxes and enclosures with acoustically rated putty.
b. Provide gaskets for wallplates and covers.

12. Identification: Provide labels for boxes and associated electrical equipment.

    a. Identify field-installed conductors, interconnecting wiring, and components.
    b. Provide warning signs.
    c. Label each box with engraved metal or laminated-plastic nameplate.

3.4 CLEANING

A. Remove construction dust and debris from boxes before installing wallplates, covers, and hoods.

3.5 PROTECTION

A. After installation, protect boxes from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Designer.

END OF SECTION

SECTION 260533.23 - SURFACE RACEWAYS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Surface metal raceways and fittings.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" specifies additional coordination, scheduling, sequencing, submittal, and installation requirements applicable to the Work for electrical, communications, and electronic safety and security systems on the Project, including wiring methods.
2. Section 260526 "Grounding and Bonding for Electrical Systems" specifies grounding and bonding referenced by this Section.
3. Section 260553 "Identification for Electrical Systems" specifies warning signs referenced by this Section.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

C. Sustainable Design Submittals:

1. Product data for sustainable design features for each type of product.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturer's published instructions.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Products or components listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2.2 SURFACE METAL RACEWAYS AND FITTINGS

A. UL RJBT - Surface Metal Raceways and Fittings with Metal Covers:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    b. MonoSystems, Inc.
    c. Wiremold; Legrand North America, LLC.

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

    a. UL CCN RJBT; including UL 5.

3. Standard Features:

    a. Aluminum base with snap-on covers.
    b. Wiring Channels: Single and Dual. Multiple channels must be capable of housing a standard 20 to 30 A device flush within the raceway.

4. Sustainable Design Features:

    a. Corporate Sustainability Report: Third-party verified corporate sustainability report is publicly available from manufacturer, which includes environmental impacts of extraction operations and activities associated with product and its supply chain.
    b. Regional Materials (LEED): Provide documentation if product is sourced (extracted, manufactured, purchased) within 100 mi of the Project site.

PART 3 - EXECUTION

3.1 INSTALLATION OF SURFACE RACEWAYS FOR ELECTRICAL SYSTEMS

A. Comply with manufacturer's published instructions.

B. Reference Standards for Installation: Unless more stringent installation requirements are specified in Contract Documents or manufacturers' published instructions, comply with the following:

1. Electrical Construction: ICC IBC, ICC IFC, NFPA 1, NFPA 70, and NECA NEIS 1.
2. Electrical Safety: NFPA 70E.
3. Grounding and Bonding: NECA NEIS 331 and Article 250 of NFPA 70.
4. Communications Work: BICSI N1.
5. Work in Confined Spaces: NFPA 350.
6. Work in Basements and Other Developed Subterranean Spaces: NFPA 520.
7. Surface Metal Raceway: Article 386 of NFPA 70.
8. Consult Architect for resolution of conflicting requirements.

C. Special Installation Techniques:

1. Install surface raceways only where indicated on Drawings.
2. Install surface raceway with a minimum 2 inch radius control at bend points.
3. Secure surface raceway with screws or other anchor-type devices at intervals not exceeding 48 inch and with no less than two supports per straight raceway section. Support surface raceway in accordance with manufacturer's published instructions. Tape and glue are unacceptable support methods.

D. Interfaces with Other Work:

1. Identification: Provide labels for surface raceways and associated electrical equipment.

a. Identify field-installed conductors, interconnecting wiring, and components.
b. Provide warning signs.

2. Paint to match adjacent surface where required.

3.2 FIELD QUALITY CONTROL OF SURFACE RACEWAYS

A. Tests and Inspections:

1. Perform manufacturer's recommended tests and inspections.
2. Perform tests and inspections recommended by standards listed in "Reference Standards for Installation" Paragraph.

B. Nonconforming Work:

1. Boxes and covers will be considered defective if they do not pass tests and inspections.

2. Remove and replace defective units and retest.

C. Field Quality-Control Reports: Collect, assemble, and submit test and inspection reports.

3.3 CLEANING

A. Remove construction dust and debris from surface raceways before installing covers.

3.4 PROTECTION

A. After installation, protect surface raceways from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

END OF SECTION

SECTION 260536 - CABLE TRAYS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Metal cable trays.
2. Cable tray accessories.

B. Products Installed, but Not Furnished, under This Section:

1. Section 078413 "Penetration Firestopping" specifies firestopping products installed under this Section.
2. Section 260526 "Grounding and Bonding for Electrical Systems" specifies grounding and bonding products installed under this Section.
3. Section 260553 "Identification for Electrical Systems" specifies electrical equipment labels and warning signs installed by this Section.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Metal cable trays.
2. Cable tray accessories.

C. Shop Drawings:

1. Cable tray fabrication drawings, diagrams, and supporting documents.

D. Field quality-control reports.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturers' published instructions.

C. Field Reports:

1. Factory test reports.
2. Manufacturer's field reports for field quality-control support.

PART 2 - PRODUCTS

2.1 METAL CABLE TRAYS

A. Description: This product category covers metal cable trays and metal cable tray systems intended for field assembly and for use in accordance with Article 392 of NFPA 70.

B. Performance Criteria:

1. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2. Listing Criteria: UL CCN CYNW; including NEMA VE 1 and suitability for use as equipment grounding conductors in accordance with Sections 392.60(A) and 392.60(B) of NFPA 70.

C. UL CYNW - Ladder Cable Tray:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. ABB, Electrification Business.
b. Cooper B-line; brand of Eaton, Electrical Sector.
c. Cope; Atkore International.

2. Source Limitations: Obtain products from single manufacturer.
3. General Characteristics:

a. Configuration: Two longitudinal side rails with transverse rungs swaged or welded to side rails, complying with NEMA VE 1.
b. Radius-Fitting Rung Spacing: 9 inch at center of tray's width.
c. Minimum Cable-Bearing Surface for Rungs: 7/8 inch width with radius edges.
d. No portion of the rungs must protrude below the bottom plane of side rails.
e. Structural Performance of Each Rung: Capable of supporting a maximum cable load, with a safety factor of 1.5, plus a 200 lb. concentrated load, when tested in accordance with NEMA VE 1.
f. Splicing Assemblies: Bolted type using serrated flange locknuts.
g. Splice-Plate Capacity: Splices located within support span must not diminish rated loading capacity of cable tray.

4. Materials and Finishes (Aluminum):

a. Materials: Alloy 6063-T6 in accordance with ANSI H35.1/H 35.1M for extruded components, and Alloy 5052-H32 or Alloy 6061-T6 in accordance with ANSI H35.1/H 35.1M for fabricated parts.
b. Hardware: Chromium-zinc-plated steel, ASTM F1136.

5. Options:

    a. Width: 12 inch unless otherwise indicated on Drawings.
    b. Minimum Usable Load Depth: 4 inch.
    c. Straight Section Lengths: 10 ft, except where shorter lengths are required to facilitate tray assembly.
    d. Rung Spacing: 9 inch on center.
    e. Fitting Minimum Radius: 12 inch.
    f. Class Designation: Comply with NEMA VE 1, Class 12B.

D. UL CYNW - Wire-Mesh Cable Tray:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Cablofil; Legrand North America, LLC.
    b. Cooper B-line; brand of Eaton, Electrical Sector.
    c. Cope; Atkore International.
    d. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    e. MonoSystems, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. General Characteristics:

    a. Configuration: Galvanized-steel wire mesh, complying with NEMA VE 1.
    b. Structural Performance: Capable of supporting a maximum cable load, with a safety factor of 1.5, plus a 200 lb. concentrated load, when tested in accordance with NEMA VE 1.
    c. Splicing Assemblies: Bolted type using serrated flange locknuts.
    d. Splice-Plate Capacity: Splices located within support span must not diminish rated loading capacity of cable tray.

4. Materials and Finishes (Steel):

    a. Straight Sections and Fittings: Steel complies with the minimum mechanical properties of ASTM A1011/A1011M, SS, Grade 33.
    b. Steel Tray Splice Plates: ASTM A1011/A1011M, HSLAS, Grade 50, Class 1.
    c. Fasteners: Steel complies with the minimum mechanical properties of ASTM A510/A510M, Grade 1008.
    d. Finish:

        1) Hot-dip galvanized after fabrication, complying with ASTM A123/A123M, Class B2, with galvanized, ASTM B633 hardware.

5. Options:

    a. Width: As indicated on Drawings.
    b. Minimum Usable Load Depth: As indicated on Drawings.
    c. Straight Section Lengths: 12 ft, except where shorter lengths are required to facilitate tray assembly.

d. Class Designation: Comply with NEMA VE 1, Class 12B.

2.2 CABLE TRAY ACCESSORIES

A. Fittings: Tees, crosses, risers, elbows, and other fittings as indicated, of same materials and finishes as cable tray.

B. Cable tray supports and connectors, including bonding jumpers, as recommended by cable tray manufacturer.

2.3 SOURCE QUALITY CONTROL

A. Product Data: Prepare and submit catalog cuts, brochures, diagrams, schedules, and performance data illustrating size, physical appearance, and other characteristics of product.

1. Include data indicating dimensions and finishes for each type of cable tray indicated.

B. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

PART 3 - EXECUTION

3.1 PREPARATION

A. Shop Drawings: Prepare and submit the following for each cable tray system:

1. Cable Tray Fabrication Drawings, Diagrams, and Supporting Documents:

a. Show fabrication and installation details of cable trays, including plans, elevations, and sections of components and attachments to other construction elements. Designate components and accessories, including clamps, brackets, hanger rods, splice-plate connectors, expansion-joint assemblies, straight lengths, and fittings.
b. Include load calculations to show that dead and live loads do not exceed manufacturer's rating for tray and its support elements.
c. Cable tray layout, showing cable tray route to scale, with relationship between the tray and adjacent structural, electrical, and mechanical elements. Include the following:

1) Vertical and horizontal offsets and transitions.
2) Clearances for access above and to sides of cable trays.
3) Vertical elevation of cable trays above the floor or bottom of ceiling structure.

3.2 INSTALLATION OF CABLE TRAYS

A. Install cable tray and support systems in accordance with NEMA VE 2.

B. Install cable tray as a complete system, including fasteners, hold-down clips, support systems, adjustable horizontal and vertical splice plates, elbows, reducers, tees, crosses, cable dropouts, adapters, covers, and bonding.

C. Install cable tray, so that the tray is accessible for cable installation and splices are accessible for inspection and adjustment.

D. Remove burrs and sharp edges from cable trays.

E. Join aluminum cable tray with splice plates; use four square-neck carriage bolts and locknuts.

F. Fasten cable tray supports to building structure.

G. Design fasteners and supports to carry cable tray, cables, and a concentrated load of 200 lb. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems."

H. Construct supports from channel members, threaded rods, and other appurtenances furnished by cable tray manufacturer. Arrange supports in trapeze or wall-bracket form as required by application.

I. Support assembly to prevent twisting from eccentric loading.

J. Do not install more than one cable tray splice between supports.

K. Support trapeze hangers for wire-basket trays with 3/8 inch diameter rods.

L. Install expansion connectors where cable trays cross building expansion joints and in cable tray runs that exceed recommended dimensions. Space connectors and set gaps in accordance with applicable standard.

M. Make changes in direction and elevation using manufacturer's recommended fittings.

N. Make cable tray connections using manufacturer's recommended fittings.

O. Seal penetrations through fire and smoke barriers. Provide re-enterable products.

P. Install capped metal sleeves for future cables through firestop-sealed cable tray penetrations of fire and smoke barriers.

Q. Install cable trays with enough workspace to permit access for installing cables.

R. Install warning signs in visible locations on or near cable trays after cable tray installation.

3.3 CABLE TRAY GROUNDING

A. Ground cable trays in accordance with NFPA 70 unless additional grounding is specified.

B. Bond cable trays to power source for cables contained within with bonding conductors sized in accordance with Article 250 of NFPA 70.

3.4 INSTALLATION OF CABLES

A. Install cables only when each cable tray run has been completed and inspected.

B. Fasten cables on horizontal runs with cable clamps or cable ties. Tighten clamps only enough to secure the cable, without indenting the cable jacket. Install cable ties with a tool that includes an automatic pressure-limiting device.

C. Fasten cables on vertical runs to cable trays every 18 inch.

D. Fasten and support cables that pass from one cable tray to another or drop from cable trays to equipment enclosures. Fasten cables to the cable tray at the point of exit and support cables independent of the enclosure. The cable length between cable trays or between cable tray and enclosure must be no more than 72 inch.

3.5 FABRICATION OF CONNECTION POINTS

A. Remove paint from all connection points before making connections. Repair paint after the connections are completed.

B. Connect raceways to cable trays in accordance with requirements in NEMA VE 2 and NEMA FG 1.

3.6 INSTALLATION OF CABLE TRAY MARKINGS AND SIGNS

A. Ladder Cable Trays: Provide warning signs to prevent use as personnel ladder.

1. Lettering: 1-1/2 inch high.
2. Legend: "WARNING! NOT TO BE USED AS WALKWAY, LADDER, OR SUPPORT FOR LADDERS OR PERSONNEL."

3.7 FIELD QUALITY CONTROL

A. Field tests and inspections must be witnessed by authorities having jurisdiction.

B. Tests and Inspections:

1. After installing cable trays and after electrical circuitry has been energized, survey for compliance with requirements.
2. Visually inspect cable insulation for damage. Correct sharp corners, protuberances in cable trays, vibrations, and thermal expansion and contraction conditions, which may cause or have caused damage.
3. Verify that the number, size, and voltage of cables in cable trays do not exceed that permitted by NFPA 70. Verify that power circuits are not installed in cable trays.
4. Verify that there are no intruding items, such as pipes, hangers, or other equipment, in the cable tray.
5. Remove dust deposits, industrial process materials, trash of any description, and any blockage of tray ventilation.

6. Visually inspect each cable tray joint and each ground connection for mechanical continuity. Check bolted connections between sections for corrosion. Clean and retorque in suspect areas.
7. Check for improperly sized or installed bonding jumpers.
8. Check for missing, incorrect, or damaged bolts, bolt heads, or nuts. When found, replace with specified hardware.
9. Perform visual and mechanical checks for adequacy of cable tray grounding; verify that all takeoff raceways are bonded to cable trays. Test entire cable tray system for continuity. Maximum allowable resistance is 1 Ω.

C. Nonconforming Work:

1. Cable tray will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

D. Field Quality-Control Reports: Collect, assemble, and submit test and inspection reports.

3.8 PROTECTION

A. Protect installed cable trays and cables.

1. Install temporary protection for cables in open trays to safeguard exposed cables against falling objects or debris during construction. Temporary protection for cables and cable tray can be constructed of wood or metal materials and must remain in place until the risk of damage is over.
2. Repair damage to galvanized finishes with zinc-rich paint recommended by cable tray manufacturer.

END OF SECTION

SECTION 260543 - UNDERGROUND DUCTS AND RACEWAYS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Direct buried conduit, duct, and duct accessories.
2. Handholes and boxes for exterior underground wiring.
3. Manholes for exterior underground wiring.
4. Utility structure accessories.
5. Precast concrete transformer bases.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" specifies additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
2. Section 260519 "Low-Voltage for Electrical Power Conductors and Cables" specifies nonmetallic underground conduit with conductors (Type NUCC).

1.2 DEFINITIONS

A. Duct: A single raceway or multiple raceways, installed singly or as components of a duct bank.

B. Duct Bank: Two or more ducts installed in parallel, direct buried or with additional casing materials such as concrete.

C. Handhole: An underground chamber containing electrical cables, sized such that personnel are not required to enter in order to access the cables.

D. Manhole: An underground chamber containing electrical cables and equipment, sized to provide access with working space clearances.

E. Trafficways: Locations where vehicular or pedestrian traffic is a normal course of events.

F. GRC: Galvanized rigid (steel) conduit.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Coordination Meeting(s): For underground ducts and raceways. Conduct meeting(s) as videoconference or at Project site before installation of communications conduit.

1. Attendees: Installers, administrants for field tests and inspections, and Owner’s telecommunications representatives. Notify Architect and Owner of scheduled meeting dates.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include duct-bank materials, including spacers and miscellaneous components.
2. Include duct, conduits, and their accessories, including elbows, end bells, bends, fittings, and solvent cement.
3. Include accessories for handholes, boxes, and other utility structures.

C. Shop Drawings:

1. Precast or Factory-Fabricated Concrete Structures:

a. Include plans, elevations, sections, and details, including attachments to other Work.
b. Include duct entry provisions, including locations and duct sizes, and methods and materials for waterproofing duct entry locations.
c. Include reinforcement details.
d. Include frame and cover design and manhole chimneys.
e. Include grounding details.
f. Include dimensioned locations of cable rack inserts, pulling-in and lifting irons, sumps, and other accessories.
g. Include joint details.

2. Factory-Fabricated Handholes and Boxes Other Than Precast Concrete:

a. Include dimensioned plans, sections, and elevations, and fabrication and installation details.
b. Include duct entry provisions, including locations and duct sizes, and methods and materials for waterproofing duct entry locations.
c. Include cover design.
d. Include grounding details.
e. Include dimensioned locations of cable rack inserts, pulling-in and lifting irons, and other accessories.

3. Transformer pad.

D. Field quality-control reports.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

C. Field Reports:

1. Factory Test Reports: For handholes and boxes.
2. Manufacturer's field reports for field quality-control support.

1.6 FIELD CONDITIONS

A. Interruption of Existing Electrical or Communications Service: Do not interrupt electrical or communications service to facilities occupied by Owner or others unless permitted under the following conditions, and then only after arranging to provide temporary electrical service according to requirements indicated:
   1. Notify Architect and Owner no fewer than five business days in advance of proposed interruption of electrical or communications service.
   2. Do not proceed with interruption of electrical or communications service without Owner's written permission.

B. Ground Water: Assume ground-water level is 4-feet below grade level unless a lower water table is noted on Drawings.

PART 2 - PRODUCTS

2.1 TYPE ERMC-S RACEWAYS, ELBOWS, COUPLINGS, AND NIPPLES

A. Performance Criteria:

   1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
   2. General Characteristics: UL 6, UL CCN DYIX, ANSI C80.1, Schedule 40.

2.2 TYPE PVC RACEWAYS AND FITTINGS

A. Performance Criteria:

   1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
   2. General Characteristics: Type EPC-40-PVC RNC, complying with NEMA TC 2 and UL 651, with matching fittings complying with NEMA TC 3 by same manufacturer as duct.

2.3 SOLVENT CEMENTS

A. Performance Criteria:

   1. As recommended by conduit manufacturer.
   2. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
   3. General Characteristics: As recommended by conduit manufacturer in accordance with UL 514B and UL CCN DWTT.

2.4 DUCT ACCESSORIES

A. Duct Spacers: Factory-fabricated, rigid, PVC interlocking spacers; sized for type and size of duct with which used, and selected to provide minimum duct spacing indicated while supporting duct during concreting or backfilling.

B. Underground-Line Warning Tape: Comply with requirements for underground-line warning tape specified in Section 312000 "Earth Moving."

2.5 HANDHOLES AND BOXES FOR EXTERIOR UNDERGROUND WIRING

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
2. General Characteristics:

    a. ASTM C858 for design and manufacturing processes.
    b. SCTE 77, Tier 22.

B. Polymer Concrete Handholes and Boxes with Polymer Concrete Cover:

1. Description: Molded of sand, concrete, and aggregate, bound together with polymer resin, and reinforced with steel or fiberglass or combination.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Armorcast Products Company; brand of Hubbell Utility Solutions; Hubbell Incorporated.
    b. MacLean Highline.
    c. NewBasis.
    d. Oldcastle Infrastructure Inc.; CRH Americas.
    e. Quazite; brand of Hubbell Utility Solutions; Hubbell Incorporated.

3. Configuration: Units must be designed for flush burial and have open bottom unless otherwise indicated.
4. Cover: Weatherproof, secured by tamper-resistant locking devices and having structural load rating consistent with enclosure and installed location.

    a. Cover Finish: Nonskid finish must have minimum coefficient of friction of 0.50.
    b. Cover Legend: Molded lettering, "ELECTRIC" or “COMMUNICATIONS.”

5. Conduit Entrance Provisions: Conduit-terminating fittings must mate with entering ducts for secure, fixed installation in enclosure wall.
6. Duct Entrance Provisions: Duct-terminating fittings must mate with entering duct for secure, fixed installation in enclosure wall.
7. Handholes 12 inch wide by 24 inch long and larger must have factory-installed inserts for cable racks and pulling-in irons.
8. Options:

a. Color: Gray or green.

C. High-Density Polyethylene (HDPE) Boxes:

1. Description: Injection molded of HDPE or copolymer-polypropylene. Cover must be made of polymer concrete.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Nordic Fiberglass, Inc.
b. Oldcastle Infrastructure Inc.; CRH Americas.
c. PenCell Plastics; brand of Hubbell Utility Solutions; Hubbell Incorporated.
d. Quazite; brand of Hubbell Utility Solutions; Hubbell Incorporated.

3. Configuration: Units must be designed for flush burial and have open bottom unless otherwise indicated.
4. Cover: Weatherproof, secured by tamper-resistant locking devices and having structural load rating consistent with enclosure.

a. Cover Finish: Nonskid finish must have minimum coefficient of friction of 0.50.
b. Cover Legend: Molded lettering, "ELECTRIC" or “COMMUNICATIONS.”

5. Duct Entrance Provisions: Duct-terminating fittings must be installed perpendicular to box wall and mate with entering duct for secure, fixed installation in enclosure wall without putting stress on box wall or fitting.
6. Options:

a. Color: Gray or green.

2.6 MANHOLES FOR EXTERIOR UNDERGROUND WIRING

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
2. General Characteristics:

a. ASTM C858 for design and manufacturing processes.
b. SCTE 77.

B. Precast Concrete Manholes:

1. Description: One-piece units and units with interlocking mating sections, complete with accessories, hardware, and features.
2. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Carder Concrete Products.
b. Elmhurst-Chicago Stone Co.

c. Oldcastle Infrastructure Inc.; CRH Americas.
d. Rinker Group, Ltd.
e. Riverton Concrete Products.
f. Smith-Midland Corporation.
g. Utility Concrete Products, LLC.
h. Utility Vault Co.
i. Wausau Tile, Inc.

3. Knockout Panels: Precast openings in walls, arranged to match dimensions and elevations of approaching duct, plus additional 12 inch vertically and horizontally to accommodate alignment variations.

   a. At locations indicated.
   b. Knockout panels must be located no less than 6 inch from interior surfaces of walls, floors, or roofs of manholes, but close enough to corners to facilitate racking of cables on walls.
   c. Knockout panel opening must have cast-in-place, welded-wire fabric reinforcement for field cutting and bending to tie in to concrete envelopes of duct.
   d. Knockout panel must be framed with at least two additional No. 3 steel reinforcing bars in concrete around each opening.
   e. Knockout panels must be 1-1/2 to 2 inch thick.

4. Ground Rod Sleeve: Provide 3 inch PVC sleeve in manhole floors 2 inch from wall adjacent to, but not underneath, duct entering structure.
5. Joint Sealant: Asphaltic-butyl material with adhesion, cohesion, flexibility, and durability properties necessary to withstand maximum hydrostatic pressures at installation location with ground-water level at grade.
6. Source Quality Control: Test and inspect in accordance with ASTM C1037.

2.7 UTILITY STRUCTURE ACCESSORIES

A. Description: Utility equipment and accessory items used for utility structure access and utility support, listed and labeled for intended use and application

B. Manhole Frames, Covers, and Chimney Components: Comply with structural design loading specified for manhole.

1. Frame and Cover: Weatherproof, gray cast iron complying with ASTM A48/A48M, Class 30B with milled cover-to-frame bearing surfaces; diameter, as indicated.

   a. Cover Finish: Nonskid finish must have minimum coefficient of friction of 0.50.
   b. Special Covers: Recess in face of cover designed to accept finish material in paved areas.

2. Cover Legend: Cast in; “ELECTRIC.”
   Manhole Chimney Components: Precast concrete rings with dimensions matched to those of roof opening.

   a. Mortar for Chimney Ring and Frame and Cover Joints: Comply with ASTM C270, Type M, except for quantities less than 2.0 cu. ft where packaged mix complying with ASTM C387/C387M, Type M, may be used.

b. Seal joints watertight using preformed plastic or rubber complying with ASTM C990. Install sealing material in accordance with sealant manufacturers' published instructions.

C. Pulling Eyes in Concrete Walls: Eyebolt with reinforcing-bar fastening insert, 2 inch diameter eye, and 1-by-4 inch bolt.

1. Working Load Embedded in 6 inch (150 mm), 4000 psi (27.6 MPa) Concrete: 13,000 lbf minimum tension.

D. Pulling Eyes in Nonconcrete Walls: Eyebolt with reinforced fastening, 1-1/4 inch diameter eye, rated 2500 lbf minimum tension.

E. Pulling-in and Lifting Irons in Concrete Floors: 7/8 inch diameter, hot-dip galvanized, bent steel rod; stress relieved after forming; fastened to reinforcing rod; and with exposed triangular opening.

1. Ultimate Yield Strength: 40,000 lbf shear and 60,000 lbf tension.

F. Bolting Inserts for Concrete Utility Structure Cable Racks and Other Attachments: Flared, threaded inserts of noncorrosive, chemical-resistant, nonconductive thermoplastic material; 1/2 inch ID by 2-3/4 inch deep, flared to 1-1/4 inch minimum at base.

1. Tested Ultimate Pullout Strength: 12,000 lbf minimum.

G. Ground Rod Sleeve: 3 inch PVC sleeve in manhole floors 2 inch from wall adjacent to, but not underneath, ducts routed from facility. Seal annular space with watertight mechanical seal.

H. Expansion Anchors for Installation after Concrete Is Cast: Zinc-plated, carbon-steel-wedge type with stainless steel expander clip with 1/2 inch bolt, 5300 lbf rated pullout strength, and minimum 6800 lbf rated shear strength.

2.8 DUCT SEALING

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB, Electrification Business.
2. American Polywater Corporation.
3. CommScope, Inc.
4. Gardner Bender.
5. Ideal Industries, Inc.
6. NSi Industries LLC.
7. TE Connectivity Ltd.

B. Duct-Sealing Compound: Nonhardening, safe for contact with human skin, not deleterious to cable insulation, and workable at temperatures as low as 35 deg F. Compound must be capable of withstanding temperature of 300 deg F without slump and adhering to clean surfaces of plastic ducts, metallic conduit, conduit and duct coatings, concrete, masonry, lead, cable sheaths, cable jackets, insulation materials, and common metals. Duct sealing compound must be removable without damaging ducts or cables.

C. Inflatable Duct-Sealing System: Wraparound inflatable bladder that seals ducts that are empty or containing conductors against air and water infiltration. System is suitable for use in steel, plastic, or concrete ducts and penetrations.

2.9 TRANSFORMER PAD

A. Precast concrete transformer pad and accessories in accordance with Central Maine Power's written requirements as indicated on Drawings.

2.10 SOURCE QUALITY CONTROL

A. Factory Tests for Handholes and Boxes:

1. Factory Tests and Inspections: Perform the following tests and inspections on handholes and boxes, by, or under supervision of, qualified electrical testing laboratory recognized by authorities having jurisdiction, before delivering to site. Affix label with name and date of manufacturer's or qualified testing laboratory's certification of system compliance.

    a. Precast Concrete Utility Structures: Test and inspect in accordance with ASTM C1037.
    b. Polymer Concrete and Nonconcrete Handhole and Pull-Box Prototypes: Test prototypes of handholes and boxes for compliance with SCTE 77. Strength tests must be for specified tier ratings of products supplied. Testing machine pressure gages must have current calibration certification, complying with ISO 9000 and ISO 10012, and traceable to NIST standards.

PART 3 - EXECUTION

3.1 PREPARATION

A. Coordinate layout and installation of duct, duct bank, manholes, handholes, and boxes with final arrangement of other utilities, site grading, and surface features as determined in field. Notify Architect if there is conflict between areas of excavation and existing structures or archaeological sites to remain.

B. Coordinate elevations of duct and duct-bank entrances into manholes, handholes, and boxes with final locations and profiles of duct and duct banks, as determined by coordination with other utilities, underground obstructions, and surface features. Revise locations and elevations as required to suit field conditions and to ensure that duct and duct bank will drain to manholes and handholes, and as approved by Architect.

C. Clear and grub vegetation to be removed, and protect vegetation to remain in accordance with Section 311000 "Site Clearing." Remove and stockpile topsoil for reapplication in accordance with Section 311000 "Site Clearing."

3.2 SELECTION OF UNDERGROUND DUCTS

A. Aboveground Conduit and Underground Vertical Conduit Bends; GRC, unless indicated otherwise.

B. Duct for Electrical Cables More Than 600 V: PVC-40, direct buried unless otherwise indicated.

C. Duct for Electrical Feeders 600 V and Less: PVC-40, direct buried unless otherwise indicated.

D. Duct for Electrical Branch Circuits: PVC-40, direct buried unless otherwise indicated.

3.3 SELECTION OF UNDERGROUND ENCLOSURES

A. Manholes, Handholes and Boxes:

1. Communications Structures and Units in Roadways and Other Deliberate Traffic Paths: Precast concrete, AASHTO HB 17, H-20 structural load rating.
2. Units in Driveway, Parking Lot, and Off-Roadway Locations, Subject to Occasional, Nondeliberate Loading by Heavy Vehicles: Polymer concrete, SCTE 77, Tier 22 or High-density plastic, SCTE 77, Tier 22 structural load rating.
3. Cover design load must not exceed load rating of handhole or box.

3.4 EARTHWORK

A. Excavation and Backfill: Comply with Section 312000 "Earth Moving," but do not use heavy-duty, hydraulic-operated, compaction equipment.

B. Restore surface features at areas disturbed by excavation, and re-establish original grades unless otherwise indicated. Replace removed sod immediately after backfilling is completed.

C. Restore areas disturbed by trenching, storing of dirt, cable laying, and other work. Restore vegetation and include necessary topsoiling, fertilizing, liming, seeding, sodding, sprigging, and mulching. Comply with Section 329200 "Turf and Grasses" and Section 329300 "Plants."

D. Cut and patch existing pavement in path of underground duct, duct bank, and underground structures in accordance with "Cutting and Patching" Article in Section 017300 "Execution."

3.5 INSTALLATION OF DUCTS AND DUCT BANKS

A. Reference Standards:

1. Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with NEMA TCB 2 for installation of underground ducts and duct banks.
2. Consult Architect for resolution of conflicting requirements.

B. Special Techniques:

1. Slope: Pitch duct minimum slope of 1:300 down toward manholes and handholes and away from buildings and equipment. Slope duct from high point between two manholes to drain in both directions.
2. Curves and Bends:

    a. Use 5-degree angle couplings for small changes in direction. Use manufactured long sweep bends with minimum radius of 48 inch, both horizontally and vertically, at other locations unless otherwise indicated.
    b. Field bending must be in accordance with NFPA 70 minimum radii requirements, except bends over 45 degrees must be made with minimum radius of 48 inch. Use only equipment specifically designed for material and size involved. Use PVC heating bender for bending PVC conduit.

3. Joints: Use solvent-cemented joints in nonmetallic duct and fittings and make watertight in accordance with manufacturer's published instructions. Stagger couplings so those of adjacent duct do not lie in same plane. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with minimum 3 inch of concrete for minimum of 12 inch on each side of coupling.

    a. Install insulated grounding bushings on steel raceway terminations that are less than 12 inch below grade or floor level and do not terminate in hubs.

4. End Bell Entrances to Manholes and Concrete and Polymer Concrete Handholes: Use end bells, spaced approximately 10 inch o.c. for 5 inch duct, and vary proportionately for other duct sizes.

    a. Begin change from regular spacing to end-bell spacing 10 ft from end bell, without reducing duct slope and without forming trap in line.
    b. Grout end bells into structure walls from both sides to provide watertight entrances.

5. Building Wall Penetrations: Make transition from underground duct to steel raceway at least 10 ft outside building wall, without reducing duct line slope away from building and without forming trap in line. Use fittings manufactured for transition to steel raceway type installed. Install steel raceway penetrations of building walls as specified in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."
6. Install manufactured steel raceway elbows for stub-ups at poles unless otherwise indicated. Encase elbows for stub-up ducts throughout length of elbow.

    a. Couple steel elbows to ducts with adapters designed for this purpose, and encase coupling with minimum 3 inch of concrete for minimum of 12 inch on each side of coupling.

7. Sealing: Provide temporary closure at terminations of duct with pulled cables. Seal spare duct at terminations. Use sealing compound and plugs to withstand at least 15 psig hydrostatic pressure.
8. Pulling Cord: Install 200 lbf test nylon cord in empty ducts.
9. Concrete-Encased Ducts and Duct Bank:

    a. Excavate trench bottom to provide firm and uniform support for duct. Prepare trench bottoms as specified in Section 312000 "Earth Moving" for trench bottoms.
    b. Width: As indicated.

c. Depth: As indicated.
d. Support duct on duct spacers coordinated with duct size, duct spacing, and outdoor temperature.
e. Spacer Installation: Place spacers close enough to prevent sagging and deforming of duct, with not less than four spacers per 20 ft of duct. Place spacers within 24 inch of duct ends. Stagger spacers approximately 6 inch between tiers. Secure spacers to earth and to duct to prevent floating during concreting. Tie entire assembly together using fabric straps; do not use tie wires or reinforcing steel that may form conductive or magnetic loops around ducts or duct groups.
f. Minimum Space between Ducts: 3 inch between edge of duct and exterior envelope wall, 2 inch between ducts for like services, and 4 inch between power and communications ducts.
g. Elbows:

    1) Use manufactured steel elbows for stub-ups and at changes of direction in duct unless otherwise indicated. Extend encasement throughout length of elbow.

h. Stub-ups to Outdoor Equipment: Extend concrete-encased steel raceway horizontally minimum of 60 inch from edge of equipment base.

    1) Stub-ups must terminate in coupling installed flush with finished floor and minimum 3 inch from conduit side to edge of slab.

i. Stub-ups to Indoor Equipment: Extend concrete-encased steel raceway horizontally minimum of 60 inch from edge of wall. Install insulated grounding bushings on terminations at equipment.

    1) Stub-ups must be minimum 4 inch above finished floor and no less than 3 inch from conduit side to edge of slab.

j. Reinforcement: Reinforce concrete-encased duct where crossing disturbed earth and where indicated. Arrange reinforcing rods and ties without forming conductive or magnetic loops around ducts or duct groups.
k. Forms: Use walls of trench to form side walls of duct bank where soil is self-supporting and concrete envelope can be poured without soil inclusions; otherwise, use forms.
l. Concrete Cover: Install minimum of 3 inch of concrete cover between edge of duct to exterior envelope wall, 2 inch between duct of like services, and 4 inch between power and communications ducts.
m. Place minimum 6 inch of aggregate subbase or aggregate base above concrete encasement of duct.
n. Concreting Sequence: Pour each run of envelope between manholes or other terminations in one continuous operation.

    1) Start at one end and finish at other, allowing for expansion and contraction of duct as its temperature changes during and after pour. Use expansion fittings installed in accordance with manufacturer's published instructions, or use other specific measures to prevent expansion-contraction damage.
    2) If more than one pour is necessary, terminate each pour in vertical plane and install 3/4 inch reinforcing-rod dowels extending minimum of 18 inch into concrete on both sides of joint near corners of envelope.

o. Pouring Concrete: Comply with requirements in "Concrete Placement" Article in Section 033000 "Cast-in-Place Concrete." Place concrete carefully during pours to prevent voids under and between duct and at exterior surface of envelope. Do not allow heavy mass of concrete to fall directly onto ducts. Allow concrete to flow around duct and rise up in middle, uniformly filling open spaces. Do not use power-driven agitating equipment unless specifically designed for duct-installation application.

10. Direct-Buried Duct and Duct Bank:

a. Excavate trench bottom to provide firm and uniform support for duct. Comply with requirements in Section 312000 "Earth Moving" for preparation of trench bottoms.
b. Width: As indicated.
c. Depth: As indicated.
d. Set elevation of top of duct bank as indicated.
e. Place minimum 3 inch of sand as bed for duct. Place sand to minimum of 6 inch above top level of duct.
f. Support ducts on duct spacers coordinated with duct size, duct spacing, and outdoor temperature.
g. Spacer Installation: Place spacers close enough to prevent sagging and deforming of duct, with not less than five spacers per 20 ft of duct. Place spacers within 24 inch of duct ends. Stagger spacers approximately 6 inch between tiers. Secure spacers to earth and to ducts to prevent floating during concreting. Tie entire assembly together using fabric straps; do not use tie wires or reinforcing steel that may form conductive or magnetic loops around ducts or duct groups.
h. Install duct with minimum of 3 inch between ducts for like services and 6 inch between power and communications duct.
i. Install manufactured steel elbows for stub-ups, at building entrances, and at changes of direction in duct direction unless otherwise indicated. Encase elbows for stub-up ducts throughout length of elbow.

1) Couple RNC duct to steel raceway with adapters designed for this purpose, and encase coupling with minimum 3 inch of concrete.
2) Stub-ups to Outdoor Equipment: Extend concrete-encased steel raceway horizontally minimum of 60 inch from edge of base. Install insulated grounding bushings on terminations at equipment.

a) Stub-ups must terminate in coupling installed flush with finished base and minimum 3 inch from conduit side to edge of base.

3) Stub-ups to Indoor Equipment: Extend concrete-encased steel raceway horizontally on exterior of wall minimum of 60 inch from edge of wall. Install insulated grounding bushings on terminations at equipment.
4) Stub-ups through interior floors must be minimum 4 inch above finished floor and no less than 3 inch from conduit side to edge of equipment pad or floor slab.

j. After installing first tier of duct, backfill and compact. Start at tie-in point and work toward end of duct run, leaving ducts at end of run free to move with expansion and contraction as temperature changes during this process. Repeat procedure after placing each tier. After placing last tier, hand place backfill to

4 inch over duct and hand tamp. Firmly tamp backfill around ducts to provide maximum supporting strength. Use hand tamper only. After placing controlled backfill over final tier, make final duct connections at end of run and complete backfilling with normal compaction. Comply with requirements in Section 312000 "Earth Moving" for installation of backfill materials.

11. Underground-Line Warning Tape: Bury detectable underground line specified in Section 312000 “Earth Moving” no less than 12 inch above concrete-encased duct and duct banks and approximately 12 inch below grade. Align tape parallel to and within 3 inch of centerline of duct bank. Provide additional warning tape for each 12 inch increment of duct-bank width over nominal 18 inch. Space additional tapes 12 inch apart, horizontally across width of ducts.
12. Ground ducts and duct banks in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

3.6 INSTALLATION OF CONCRETE MANHOLES, HANDHOLES, AND BOXES

A. Reference Standards:

1. Precast Concrete Handholes: Comply with ASTM C891 unless otherwise indicated.
2. Consult Architect for resolution of conflicting requirements.

B. Special Techniques:

1. Precast Concrete Handholes and Manholes:

   a. Install units level and plumb and with orientation and depth coordinated with connecting duct to minimize bends and deflections required for proper entrances.
   b. Unless otherwise indicated, support units on level bed of crushed stone or gravel graded from 1 inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.
   c. Field-cut openings for conduits in accordance with enclosure manufacturer's published instructions. Cut wall of enclosure with tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.

2. Elevations:

   a. Manhole Roof: Install with rooftop at least 15 inch below finished grade.
   b. Manhole Frame: In paved areas and trafficways, set frames flush with finished grade. Set other manhole frames 1 inch above finished grade.
   c. Handhole Covers: In paved areas and trafficways, set surface flush with finished grade. Set covers of other handholes 1 inch above finished grade.
   d. Where indicated, cast handhole cover frame integrally with handhole structure.

3. Manhole Access: Circular opening in manhole roof; sized to match cover size.

   a. Install chimney, constructed of precast concrete collars and rings, and cast-iron frame to connect cover with manhole roof opening. Provide moisture-tight joints and waterproof grouting for frame and chimney.

4. Waterproofing: Apply waterproofing to exterior surfaces of manholes after concrete has cured at least three days. After duct has been connected and grouted, and before backfilling, waterproof joints and connections, and touch up abrasions and scars. Waterproof exterior of manhole chimneys after mortar has cured at least three days.
5. Hardware: Install removable hardware, including pulling eyes, cable stanchions, and cable arms, as required for installation and support of cables and conductors and as indicated.
6. Field-Installed Bolting Anchors in Manholes and Concrete Handholes: Do not drill deeper than 3-7/8 inch for manholes and 2 inch for handholes, for anchor bolts installed in field. Use minimum of two anchors for each cable stanchion.
7. Ground manholes, handholes, and boxes in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

3.7 INSTALLATION OF HANDHOLES AND BOXES OTHER THAN PRECAST CONCRETE

A. Special Techniques:

1. Install handholes and boxes level and plumb and with orientation and depth coordinated with connecting duct, to minimize bends and deflections required for proper entrances. Use box extension if required to match depths of duct, and seal joint between box and extension as recommended by manufacturer.
2. Unless otherwise indicated, support units on level bed of crushed stone or gravel, graded from 1/2 inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.
3. Elevation: In paved areas and trafficways, set cover flush with finished grade. Set covers of other handholes 1 inch above finished grade.
4. Install removable hardware, including pulling eyes, cable stanchions, cable arms, and insulators, as required for installation and support of cables and conductors and as indicated. Select arm lengths to be long enough to provide spare space for future cables, but short enough to preserve adequate working clearances in enclosure.
5. Field cut openings for duct in accordance with enclosure manufacturer's published instructions. Cut wall of enclosure with tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.
6. For enclosures installed in asphalt paving and subject to occasional, nondeliberate, heavy-vehicle loading, form and pour concrete ring encircling, and in contact with enclosure entry, and with top surface screeded to top of box cover frame. Bottom of ring must rest on compacted earth.

    a. Concrete: 3000 psi, 28-day strength, complying with Section 033000 "Cast-in-Place Concrete," with troweled finish.
    b. Dimensions: As indicated.

7. Ground handholes and boxes in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

3.8 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Demonstrate capability and compliance with requirements on completion of installation of underground duct, duct bank, and utility structures.
2. Pull solid aluminum or wood test mandrel through duct to prove joint integrity and adequate bend radii, and test for out-of-round duct. Provide minimum 12 inch long mandrel equal to duct size minus 1/4 inch. If obstructions are indicated, remove obstructions and retest.
3. Test manhole and handhole grounding to ensure electrical continuity of grounding and bonding connections. Measure and report ground resistance as specified in Section 260526 "Grounding and Bonding for Electrical Systems."

B. Nonconforming Work:

1. Underground ducts, raceways, and structures will be considered defective if they do not pass tests and inspections.
2. Correct deficiencies and retest as specified above to demonstrate compliance.

C. Field Quality-Control Reports: Collect, assemble, and submit test and inspection reports.

3.9 CLEANING

A. Pull leather-washer-type duct cleaner, with graduated washer sizes, through full length of duct until duct cleaner indicates that duct is clear of dirt and debris. Follow with rubber duct swab for final cleaning and to assist in spreading lubricant throughout ducts.

B. Clean internal surfaces of manholes, including sump, and building interiors affected by Work.

1. Sweep floor, removing dirt and debris.
2. Remove foreign material.

END OF SECTION

SECTION 260544 - SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Round sleeves.
2. Rectangular sleeves.
3. Sleeve seal systems.
4. Grout.
5. Pourable sealants.
6. Foam sealants.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
2. Section 078413 "Penetration Firestopping" for penetration firestopping installed in fire-resistance-rated walls, horizontal assemblies, and smoke barriers, with and without penetrating items.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product.

C. Sustainable Design Submittals:

1. Product Data: For sealants, indicating VOC content.
2. Laboratory Test Reports: For sealants, indicating compliance with requirements for low-emitting materials.

PART 2 - PRODUCTS

2.1 SLEEVE-SEAL SYSTEMS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Advance Products & Systems, LLC.
2. American Polywater Corporation.

3. BWM Company.
4. CALPICO, Inc.
5. Flexicraft Industries.
6. GPT; a division of EnPRO Industries.
7. Metraflex Company (The).
8. Proco Products, Inc.
9. Roxtec Inc.

B. General Characteristics: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable or between raceway and cable.

C. Options:

1. Sealing Elements: EPDM rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
2. Pressure Plates: Carbon steel.
3. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating, of length required to secure pressure plates to sealing elements.

PART 3 - EXECUTION

3.1 INSTALLATION OF SLEEVES FOR NON-FIRE-RATED ELECTRICAL PENETRATIONS

A. Sleeves for Conduits Penetrating Above-Grade, Non-Fire-Rated, Concrete and Masonry-Unit Floors and Walls:

1. Use metallic conduit or cast pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
2. Size pipe sleeves to provide 1/4 inch annular clear space between sleeve and raceway or cable, unless sleeve seal system is to be installed.
3. Provide sleeves for wall penetrations unless core-drilled holes or formed openings are used. Cut sleeves to length for mounting flush with both surfaces of walls. Deburr after cutting.
4. Install sleeves for floor penetrations. Extend sleeves installed in floors 6 inch above finished floor level.

B. Sleeves for Conduits Penetrating Non-Fire-Rated Wall Assemblies:

1. Use metal conduit sleeves.
2. Seal space outside of sleeves with approved joint compound for wall assemblies.

C. Roof-Penetration Sleeves: Seal penetration of individual raceways and cables with flexible boot-type flashing units applied in coordination with roofing work.

3.2 INSTALLATION OF RECTANGULAR SLEEVES AND SLEEVE SEALS

A. Install sleeves in existing walls without compromising structural integrity of walls. Do not cut structural elements without reinforcing the wall to maintain the designed weight bearing and wall stiffness.

B. Install conduits and cable with no crossings within the sleeve.

C. Fill opening around conduits and cables with expanding foam without leaving voids.

D. Provide metal sheet covering at both wall surfaces and finish to match surrounding surfaces. Metal sheet must be same material as sleeve.

3.3 INSTALLATION OF SLEEVE-SEAL SYSTEMS

A. Install sleeve-seal systems in sleeves in exterior concrete or masonry walls and slabs-on-grade at raceway entries into building.

B. Install type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

END OF SECTION

SECTION 260553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Labels.
2. Bands and tubes.
3. Tapes and stencils.
4. Tags.
5. Signs.
6. Cable ties.
7. Miscellaneous identification products.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data:

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for electrical identification products.

C. Identification Schedule: For each piece of electrical equipment and electrical system components provide an index of nomenclature for electrical equipment and system components used in identification signs and labels.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Comply with ASME A13.1 and IEEE C2.

B. Comply with 29 CFR 1910.144 for color identification of hazards; 29 CFR 1910.145 for danger, caution, warning, and safety instruction signs and tags; and the following:

1. Ceiling-mounted hangers, supports, cable trays, and raceways must be finished, painted, or suitably marked safety yellow where less than 7.7 ft above finished floor.

C. Signs, labels, and tags required for personnel safety must comply with the following standards:

1. Safety Colors: NEMA Z535.1.
2. Facility Safety Signs: NEMA Z535.2.
3. Safety Symbols: NEMA Z535.3.
4. Product Safety Signs and Labels: NEMA Z535.4.
5. Safety Tags and Barricade Tapes for Temporary Hazards: NEMA Z535.5.

D. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, must comply with UL 969.

E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.

2.2 COLOR AND LEGEND REQUIREMENTS

A. Raceways and Cables Carrying Circuits at 1000 V or Less:

1. Black letters on orange field.
2. Legend: Indicate voltage and system or service type.

B. Color-Coding for Phase- and Voltage-Level Identification, 1000 V or Less: Use colors listed below for ungrounded feeder and branch-circuit conductors.

1. Color must be factory applied.
2. Colors for 208Y/120 V Circuits:

a. Phase A: Black.
b. Phase B: Red.
c. Phase C: Blue.

3. Colors for 480Y/277V Circuits:

a. Phase A: Brown.
b. Phase B: Orange
c. Phase C: Yellow.

4. Color for Neutral: White.
5. Color for Equipment Grounds: Green.

C. Warning Label Colors:

1. Identify system voltage with black letters on orange background.

D. Warning labels and signs must include, but are not limited to, the following legends:

1. Workspace Clearance Warning: "WARNING - OSHA REGULATION - AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR 3 FEET MINIMUM."

E. Equipment Identification Labels:

1. Black letters on white field.

2.3 LABELS

A. Vinyl Wraparound Labels: Preprinted, flexible labels laminated with clear, weather- and chemical-resistant coating and matching wraparound clear adhesive tape for securing label ends.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Brady Corporation.
b. Champion America.
c. emedco.
d. Grafoplast Wire Markers.
e. HellermannTyton.
f. LEM Products Inc.
g. Marking Services, Inc.
h. Panduit Corp.
i. Seton Identification Products; a Brady Corporation company.

B. Snap-Around Labels: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeves, with diameters sized to suit diameters and that stay in place by gripping action.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Brady Corporation.
b. HellermannTyton.
c. Marking Services, Inc.
d. Panduit Corp.
e. Seton Identification Products; a Brady Corporation company.

C. Self-Adhesive Wraparound Labels: Preprinted, 3 mil thick, vinyl flexible label with acrylic pressure-sensitive adhesive.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. A'n D Cable Products.
    b. Brady Corporation.
    c. Brother International Corporation.
    d. emedco.
    e. Grafoplast Wire Markers.
    f. Ideal Industries, Inc.
    g. LEM Products Inc.
    h. Marking Services, Inc.
    i. Panduit Corp.
    j. Seton Identification Products; a Brady Corporation company.

2. Self-Lamination: Clear; UV-, weather- and chemical-resistant; self-laminating, protective shield over legend. Labels sized such that clear shield overlaps entire printed legend.
3. Marking for Labels:

    a. Machine-printed, permanent, waterproof, black ink recommended by printer manufacturer.

D. Self-Adhesive Labels: Vinyl, thermal, transfer-printed, 3 mil thick, multicolor, weather- and UV-resistant, pressure-sensitive adhesive labels, configured for intended use and location.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. A'n D Cable Products.
    b. Brady Corporation.
    c. Brother International Corporation.
    d. emedco.
    e. Grafoplast Wire Markers.
    f. HellermannTyton.
    g. Ideal Industries, Inc.
    h. LEM Products Inc.
    i. Marking Services, Inc.
    j. Panduit Corp.
    k. Seton Identification Products; a Brady Corporation company.

2. Minimum Nominal Size:

    a. 1-1/2 by 6 inch for raceway and conductors.
    b. 3-1/2 by 5 inch for equipment.
    c. As required by authorities having jurisdiction.

2.4 BANDS AND TUBES

A. Snap-Around, Color-Coding Bands: Slit, pretensioned, flexible, solid-colored acrylic sleeves, 2 inch long, with diameters sized to suit diameters and that stay in place by gripping action.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Brady Corporation.
    b. HellermannTyton.
    c. Marking Services, Inc.
    d. Panduit Corp.

B. Heat-Shrink Preprinted Tubes: Flame-retardant polyolefin tubes with machine-printed identification labels, sized to suit diameter and shrunk to fit firmly. Full shrink recovery occurs at maximum of 200 deg F. Comply with UL 224.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Brady Corporation.
    b. Panduit Corp.

2.5 TAPES AND STENCILS

A. Marker Tapes: Vinyl or vinyl-cloth, self-adhesive wraparound type, with circuit identification legend machine printed by thermal transfer or equivalent process.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Carlton Industries, LP.
    b. Champion America.
    c. HellermannTyton.
    d. Ideal Industries, Inc.
    e. Marking Services, Inc.
    f. Panduit Corp.

B. Self-Adhesive Vinyl Tape: Colored, heavy duty, waterproof, fade resistant; not less than 3 mil thick by 1 to 2 inch wide; compounded for outdoor use.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Brady Corporation.
    b. Carlton Industries, LP.
    c. emedco.
    d. Marking Services, Inc.

C. Floor Marking Tape: 2 inch wide, 5 mil pressure-sensitive vinyl tape, with yellow and black stripes and clear vinyl overlay.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Carlton Industries, LP.
    b. Seton Identification Products; a Brady Corporation company.

2.6 TAGS

A. Nonmetallic Preprinted Tags: Polyethylene tags, 0.015 inch thick, color-coded for phase and voltage level, with factory printed permanent designations; punched for use with self-locking cable tie fastener.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Brady Corporation.
    b. Carlton Industries, LP.
    c. emedco.
    d. Grafoplast Wire Markers.
    e. LEM Products Inc.
    f. Marking Services, Inc.
    g. Panduit Corp.
    h. Seton Identification Products; a Brady Corporation company.

2.7 SIGNS

A. Laminated Acrylic or Melamine Plastic Signs:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Brady Corporation.
    b. Carlton Industries, LP.
    c. emedco.
    d. Marking Services, Inc.
    e. Seton Identification Products; a Brady Corporation company.

2. Engraved legend.
3. Thickness:

    a. For signs up to 20 sq. inch, minimum 1/16 inch thick.
    b. For signs larger than 20 sq. inch, 1/8 inch thick.
    c. Engraved legend with colors as follows:

        1) Normal Power: Black letters on white face.
        2) Optional Standby Power: Black letters on yellow face.
        3) Emergency Power: White letters on red face.

4) Critical Operations Power Systems (COPS): White letters on blue face.

d. Punched or drilled for mechanical fasteners with 1/4 inch grommets in corners for mounting.

e. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.

2.8 CABLE TIES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. HellermannTyton.
2. Ideal Industries, Inc.
3. Marking Services, Inc.
4. Panduit Corp.

B. General-Purpose Cable Ties: Fungus inert, self-extinguishing, one piece, self-locking, and Type 6/6 nylon.

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 deg F in accordance with ASTM D638: 12,000 psi.
3. Temperature Range: Minus 40 to plus 185 deg F.
4. Color: Black, except where used for color-coding.

C. Plenum-Rated Cable Ties: Self-extinguishing, UV stabilized, one piece, and self-locking.

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 deg F in accordance with ASTM D638: 7000 psi.
3. UL 94 Flame Rating: 94V-0.
4. Temperature Range: Minus 50 to plus 284 deg F.
5. Color: Black.

2.9 MISCELLANEOUS IDENTIFICATION PRODUCTS

A. Paint: Comply with requirements in painting Sections for paint materials and application requirements. Retain paint system applicable for surface material and location.

B. Fasteners for Labels and Signs: Self-tapping, stainless steel screws or stainless steel machine screws with nuts and flat and lock washers.

PART 3 - EXECUTION

3.1 PREPARATION

A. Self-Adhesive Identification Products: Before applying electrical identification products, clean substrates of substances that could impair bond, using materials and methods recommended by manufacturer of identification product.

3.2 INSTALLATION

A. Verify and coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and operation and maintenance manual. Use consistent designations throughout Project.

B. Install identifying devices before installing acoustical ceilings and similar concealment.

C. Verify identity of item before installing identification products.

D. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and operation and maintenance manual.

E. Apply identification devices to surfaces that require finish after completing finish work.

F. Install signs with approved legend to facilitate proper identification, operation, and maintenance of electrical systems and connected items.

G. System Identification for Raceways and Cables under 1000 V: Identification must completely encircle cable or conduit. Place identification of two-color markings in contact, side by side.

1. Secure tight to surface of conductor, cable, or raceway.

H. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, and signal connections.

I. Emergency Operating Instruction Signs: Install instruction signs with white legend on red background with minimum 3/8 inch high letters for emergency instructions at equipment used for emergency lighting.

J. Elevated Components: Increase sizes of labels, signs, and letters to those appropriate for viewing from floor.

K. Accessible Fittings for Raceways: Identify cover of junction and pull box of the following systems with wiring system legend and system voltage. System legends must be as follows:

1. "EMERGENCY POWER."
2. “NORMAL POWER.”
3. “OPTIONAL STANDBY POWER.”
4. “COPS POWER.”
5. “FIRE ALARM.”
6. “COMMUNICATIONS.”
7. “SECURITY.”
8. “LIGHTING.”

L. Vinyl Wraparound Labels:

1. Secure tight to surface of raceway or cable at location with high visibility and accessibility.
2. Attach labels that are not self-adhesive type with clear vinyl tape, with adhesive appropriate to location and substrate.

M. Snap-Around Labels: Secure tight to surface at location with high visibility and accessibility.

N. Self-Adhesive Wraparound Labels: Secure tight to surface at location with high visibility and accessibility.

O. Self-Adhesive Labels:

1. Install unique designation label that is consistent with wiring diagrams, schedules, and operation and maintenance manual.
2. Unless otherwise indicated, provide single line of text with 1/2 inch high letters on 1-1/2 inch high label; where two lines of text are required, use labels 2 inch high.

P. Snap-Around Color-Coding Bands: Secure tight to surface at location with high visibility and accessibility.

Q. Heat-Shrink, Preprinted Tubes: Secure tight to surface at location with high visibility and accessibility.

R. Marker Tapes: Secure tight to surface at location with high visibility and accessibility.

S. Self-Adhesive Vinyl Tape: Secure tight to surface at location with high visibility and accessibility.

1. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for minimum distance of 6 inch where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding.

T. Nonmetallic Preprinted Tags:

1. Place in location with high visibility and accessibility.
2. Secure using cable ties.

U. Metal-Backed Butyrate Signs:

1. Attach signs that are not self-adhesive type with mechanical fasteners appropriate to location and substrate.
2. Unless otherwise indicated, provide single line of text with 1/2 inch high letters on 1-1/2 inch high sign; where two lines of text are required, use labels 2 inch high.

V. Laminated Acrylic or Melamine Plastic Signs:

1. Attach signs that are not self-adhesive type with mechanical fasteners appropriate to location and substrate.
2. Unless otherwise indicated, provide single line of text with 1/2 inch high letters on 1-1/2 inch high sign; where two lines of text are required, use labels 2 inch high.

W. Cable Ties: General purpose, for attaching tags, except as listed below:

1. Outdoors: UV-stabilized nylon.
2. In Spaces Handling Environmental Air: Plenum rated.

3.3 IDENTIFICATION SCHEDULE

A. Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment. Install access doors or panels to provide view of identifying devices.

B. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, pull points, and locations of high visibility. Identify by system and circuit designation.

C. Accessible Raceways MI Cables, and Metal-Clad Cables, 1000 V or Less, for Feeder, and Branch Circuits, More Than 30 A and 120 V to Ground: Identify with self-adhesive raceway labels.

1. Locate identification at changes in direction, at penetrations of walls and floors, at 50 ft maximum intervals in straight runs, and at 25 ft maximum intervals in congested areas.

D. Accessible Fittings for Raceways and Cables within Buildings: Identify cover of junction and pull box of the following systems with self-adhesive labels containing wiring system legend and system voltage. System legends must be as follows:

1. "EMERGENCY POWER."
2. "NORMAL POWER."
3. “OPTIONAL STANDBY POWER.”
4. “COPS POWER.”
5. “FIRE ALARM.”
6. “COMMUNICATIONS.”
7. “SECURITY.”
8. “LIGHTING.”

E. Power-Circuit Conductor Identification, 1000 V or Less: For conductors in pull and junction boxes use self-adhesive wraparound labels snap-around labels to identify phase.

1. Locate identification at changes in direction, at penetrations of walls and floors, at 50 ft maximum intervals in straight runs, and at 25 ft maximum intervals in congested areas.

F. Control-Circuit Conductor Identification: For conductors and cables in pull and junction boxes, use self-adhesive labels with conductor or cable designation, origin, and destination.

G. Control-Circuit Conductor Termination Identification: For identification at terminations, provide self-adhesive labels with conductor designation.

H. Auxiliary Electrical Systems Conductor Identification: Self-adhesive vinyl tape that is uniform and consistent with system used by manufacturer for factory-installed connections.

1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.

I. Workspace Indication: Apply floor marking tape to finished surfaces. Show working clearances in direction of access to live parts. Workspace must comply with NFPA 70 and 29 CFR 1926.403 unless otherwise indicated. Do not install at flush-mounted panelboards and similar equipment in finished spaces.

J. Instructional Signs: Self-adhesive labels, including color code for grounded and ungrounded conductors.

K. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting: Self-adhesive labels.

1. Apply to exterior of door, cover, or other access.
2. For equipment with multiple power or control sources, apply to door or cover of equipment, including, but not limited to, the following:

a. Controls with external control power connections.
b. Control panels.
c. Telecommunications panels.
d. Security panels.
e. Lighting control panels.
f. Energy management control panels.

L. Operating Instruction Signs: Laminated acrylic or melamine plastic signs.

M. Emergency Operating Instruction Signs: Self-adhesive labels with white legend on red background with minimum 3/8 inch high letters for emergency instructions at equipment used for emergency operations.

N. Equipment Identification Labels:

1. Indoor Equipment: Engraved.
2. Equipment to Be Labeled:

a. Switchboards and Panelboards: Typewritten directory of circuits in location provided by manufacturer.
b. Enclosures and electrical cabinets.
c. Access doors and panels for concealed electrical items.
d. Enclosed switches.
e. Enclosed circuit breakers.
f. Enclosed controllers.
g. Variable-speed controllers.
h. Push-button stations.
i. Contactors.
j. Remote-controlled switches, dimmer modules, and control devices.
k. Transfer switches.
l. Portable generator connection.
m. Transformers.
n. Generator.
o. Lighting control panels.
p. Fire alarm control unit.
q. Monitoring and control equipment.

END OF SECTION

SECTION 260573 - POWER SYSTEM STUDIES

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of this Section Includes:

1. Short-circuit study.
2. Overcurrent protective device coordination study.
3. Load-flow and voltage-drop study.
4. Motor-starting study.
5. Arc-flash hazard study.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" specifies additional requirements applicable to coordinating, scheduling, and sequencing of the Work specified in this Section.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For power system analysis software to be used for studies.

1. Product Certificates: For power system study software applications, include certificate stating compliance with specified requirements, signed by software manufacturer.

C. Power System Study Reports:

1. Submit reports after approval of system protective devices submittals. Submittals must be in digital form.
2. Submit short-circuit study input data, including completed computer-program input data sheets.
3. Submit coordination study input data, including completed computer-program input data sheets.

    a. Submit load-flow, voltage-drop, and motor-starting data with coordination study.

4. Submit arc-flash study input data, including completed computer-program input data sheets.
5. Submit study report for action prior to receiving final approval of distribution equipment submittals. If formal completion of studies will cause delay in equipment manufacturing, obtain approval from Architect for preliminary submittal of sufficient study data to ensure that selection of devices and associated characteristics is satisfactory.
6. Submit revised one-line diagram, reflecting field investigation results and results of short-

circuit study.

D. Data files for studies in format compatible with Owner's power system analysis software.

E. Digital-twin models.

1.3 QUALITY ASSURANCE

A. Submittals for power system studies must be signed and sealed by qualified electrical professional engineer responsible for their preparation.

B. Studies must be performed using commercially developed and distributed software designed specifically for power system analysis.

C. Software algorithms must comply with requirements of standards and guides specified in this Section.

D. Manual calculations are unacceptable.

PART 2 - PRODUCTS

2.1 POWER SYSTEM ANALYSIS SOFTWARE

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Power Tools for Windows (PTW); brand of SKM Systems Analysis, Inc.

B. Standard Features:

1. Power System Analysis:

a. Power-systems-analysis software applications must have analytical capability to calculate "mandatory," "very desirable," and "desirable" features as listed in IEEE 3002 series standards.
b. Computer software application must be capable of plotting and diagramming time-current-characteristic curves as part of its output. Computer software program must report device settings and ratings of overcurrent protective devices and must demonstrate selective coordination by computer-generated, time-current coordination plots.
c. Computer software application must be designed to perform arc-flash analysis or have function, component, or add-on module designed to perform arc-flash analysis.

2. Analysis Standards:

a. Short-Circuit Current Analysis: In accordance with IEEE 3002.3.
b. Device Coordination Analysis: In accordance with IEEE 3004.3 and IEEE 3004.5.
c. Load-Flow Analysis: In accordance with IEEE 3002.2.

d. Motor-Starting Analysis: In accordance with IEEE 3002.7.
e. Harmonic Analysis: In accordance with IEEE 3002.8.
f. Transient Stability Analysis: In accordance with IEEE P3002.9.
g. Arc-Flash Hazard Analysis: In accordance with IEEE 1584.

3. Capable of printing arc-flash hazard warnings for equipment on weather- and UV-resistant, pressure-sensitive adhesive labels complying with NFPA 70E.

a. Label must have orange header with wording, "WARNING, ARC-FLASH HAZARD," and must include the following information taken directly from arc-flash hazard study:

1) Equipment designation.
2) Nominal voltage.
3) Protection boundaries.

a) Arc-flash boundary.
b) Restricted approach boundary.
c) Limited approach boundary.

4) Arc-flash PPE category.
5) Required minimum arc rating of PPE in Cal/cm squared.
6) Available incident energy.
7) Working distance.
8) Engineering report number, revision number, and issue date.

C. Other Available Features Required by the Project:

1. Simultaneous faults.
2. Explicit negative sequence.
3. Mutual coupling in zero sequence.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Collect and analyze data for power system studies.

1. Verify completeness of data supplied in one-line diagram on Drawings. Call discrepancies to Architect's attention.
2. For equipment included as Work on the Project, use characteristics submitted under provisions of action submittals and information submittals for the Project.
3. For equipment that is existing to remain, obtain required.
4. Gather and tabulate required input data to support power system studies. Comply with requirements in Section 017839 "Project Record Documents" for recording circuit protective device characteristics. Record data on Record Document copy of one-line diagram. Comply with recommendations in IEEE 3002 series standards as to amount of detail that is required to be acquired in field. Field data gathering must be by, or under supervision of, qualified electrical professional engineer. Data include, but are not limited to, the following:

a. Product data for the Project's overcurrent protective devices involved in overcurrent protective device coordination studies. Use equipment designation tags that are consistent with electrical distribution system diagrams, overcurrent protective device submittals, input and output data, and recommended device settings.
b. Electrical power utility impedance at service.
c. Power sources and ties.
d. Short-circuit current at each system bus (three phase and line to ground).
e. Full-load current of loads.
f. Voltage level at each bus.
g. For transformers, include kVA, primary and secondary voltages, connection type, impedance, X/R ratio, taps measured in percent, and phase shift.
h. For reactors, provide manufacturer and model designation, voltage rating, and impedance.
i. For circuit breakers and fuses, provide manufacturer and model designation. List type of breaker, type of trip and available range of settings, SCCR, current rating, and breaker settings.
j. Generator short-circuit current contribution data, including short-circuit reactance, rated kVA, rated voltage, and X/R ratio.
k. For relays, provide manufacturer and model designation, current transformer ratios, potential transformer ratios, and relay settings.
l. Maximum demands from service meters.
m. Busway manufacturer and model designation, current rating, impedance, lengths, and conductor material.
n. Motor horsepower and NEMA MG 1 code letter designation.
o. Low-voltage cable sizes, lengths, number, conductor material, and conduit material (magnetic or nonmagnetic).
p. Medium-voltage cable sizes, lengths, conductor material, cable construction.
q. Derating factors.

3.2 PREPARATION

A. Preparation of Data for Short-Circuit Study:

1. Verify completeness of data supplied on one-line diagram. Call discrepancies to Architect's attention.
2. For equipment included as Work on the Project, use characteristics submitted under provisions of action submittals and information submittals for the Project.
3. Prepare one-line diagram of modeled power system, showing the following:

a. Protective device designations and ampere ratings.
b. Conductor types, sizes, and lengths.
c. Transformer kVA and voltage ratings.
d. Motor and generator designations and kVA ratings.
e. Switchboard and panelboard designations and ratings.
f. Derating factors and environmental conditions.
g. Revisions to electrical equipment required by study.

B. Preparation of Data for Overcurrent Protective Device Coordination Study:

1. Prepare data sheets to supplement electrical distribution system one-line diagram, cross-referenced with tag numbers on diagram, indicating the following:

    a. Special load considerations, including starting inrush currents and frequent starting and stopping.
    b. Transformer characteristics, including primary protective device, magnetic inrush current, and overload capability.
    c. Motor full-load current, locked rotor current, service factor, starting time, type of start, and thermal-damage curve.
    d. Generator thermal-damage curve.
    e. Ratings, types, and settings of utility company's overcurrent protective devices.
    f. Special overcurrent protective device settings or types stipulated by utility company.
    g. Time-current-characteristic curves of devices indicated to be coordinated.
    h. Manufacturer, frame size, interrupting rating in amperes root mean square (rms) symmetrical, ampere or current sensor rating, long-time adjustment range, short-time adjustment range, and instantaneous adjustment range for circuit breakers.
    i. Manufacturer and type, ampere-tap adjustment range, time-delay adjustment range, instantaneous attachment adjustment range, and current transformer ratio for overcurrent relays.
    j. Switchboards and panelboards ampacity, and SCCR in amperes rms symmetrical.
    k. Identify series-rated interrupting devices for condition where available fault current is greater than interrupting rating of downstream equipment. Obtain device data details to allow verification that series application of these devices complies with NFPA 70 and UL 489 requirements.

2. Examine the Project's overcurrent protective device submittals for compliance with electrical distribution system coordination requirements and other conditions affecting performance of the Work. Devices to be coordinated are indicated on Drawings.
3. Proceed with coordination study only after relevant equipment submittals have been assembled. Overcurrent protective devices that have not been submitted and approved prior to coordination study may not be used in study.

C. Preparation of Data for Arc-Flash Hazard Study:

1. Assemble data from short-circuit study and overcurrent protective device coordination study.
2. Proceed with arc-flash study only after relevant equipment submittals have been assembled. Overcurrent protective devices that have not been submitted and approved prior to arc-flash study may not be used in study.

3.3 SHORT-CIRCUIT STUDY

A. Base study on device characteristics supplied by device manufacturer.

B. Extent of electrical power system to be studied is the electrical distribution system including MV components of this project.

C. Begin short-circuit current analysis at service, extending down to system overcurrent protective devices as follows:

1. To normal system low-voltage load buses where fault current is 5 kA or less.
2. Exclude equipment supplied by single transformer smaller than 75 kVA.

D. Study electrical distribution system from normal and alternate power sources throughout electrical distribution system for the Project. Study cases of system-switching configurations and alternate operations that could result in maximum fault conditions.

E. Include AC fault-current decay from induction motors, synchronous motors, and asynchronous generators and apply to low- and medium-voltage, three-phase AC systems. Also account for fault-current DC decrement to address asymmetrical requirements of interrupting equipment.

F. Calculate short-circuit momentary and interrupting duties for three-phase bolted fault and single line-to-ground fault at equipment indicated on one-line diagram.

1. For grounded systems, provide bolted line-to-ground fault-current study for areas as defined for three-phase bolted fault short-circuit study.

G. Include in report identification of protective device applied outside its capacity.

3.4 OVERCURRENT PROTECTIVE DEVICE COORDINATION STUDY

A. Base study on device characteristics supplied by device manufacturer.

B. Extent of electrical power system to be studied is the electrical distribution system including MV components of this project.

C. Begin analysis at service, extending down to system overcurrent protective devices as follows:

1. To normal system low-voltage load buses where fault current is 5 kA or less.

D. Study electrical distribution system from normal and alternate power sources throughout electrical distribution system for the Project. Study cases of system-switching configurations and alternate operations that could result in maximum fault conditions.

E. Transformer Primary Overcurrent Protective Devices:

1. Device must not operate in response to the following:

a. Inrush current when first energized.
b. Self-cooled, full-load current or forced-air-cooled, full-load current, whichever is specified for that transformer.
c. Permissible transformer overloads in accordance with IEEE C57.96 if required by unusual loading or emergency conditions.

2. Device settings must protect transformers in accordance with IEEE C57.12.00, for fault currents.

F. Motor Protection:

1. Select protection for low-voltage motors in accordance with IEEE 3004.8 and NFPA 70.
2. Select protection for motors served at voltages more than 600 V in accordance with IEEE

620.

G. Conductor Protection: Protect cables against damage from fault currents in accordance with ICEA P-32-382, ICEA P-45-482, and protection recommendations in IEEE 3004.7. Demonstrate that equipment withstands maximum short-circuit current for time equivalent to tripping time of primary relay protection or total clearing time of fuse. To determine temperatures that damage insulation, use curves from cable manufacturers or from listed standards indicating conductor size and short-circuit current.

H. Generator Protection: Select protection in accordance with manufacturer's published instructions and IEEE C37.102.

I. Include AC fault-current decay from induction motors, synchronous motors, and asynchronous generators and apply to low- and medium-voltage, three-phase AC systems. Also account for fault-current DC decrement, to address asymmetrical requirements of interrupting equipment.

J. Include coordination of ground-fault protection devices.

K. Calculate short-circuit momentary and interrupting duties for three-phase bolted fault and single line-to-ground fault at equipment indicated on one-line diagram.

1. For grounded systems, provide bolted line-to-ground fault-current study for areas as defined for three-phase bolted fault short-circuit study.

L. Protective Device Evaluation:

1. Evaluate equipment and protective devices and compare to short-circuit ratings.
2. Adequacy of panelboard bus bars to withstand short-circuit stresses.
3. Application of series-rated devices must be recertified, complying with requirements in NFPA 70.
4. Include in report identification of protective device applied outside its capacity.

3.5 LOAD-FLOW AND VOLTAGE-DROP STUDY

A. Perform load-flow and voltage-drop study to determine steady-state loading profile of system. Analyze power system performance two times as follows:

1. Determine load flow and voltage drop based on full-load currents.
2. Determine load flow and voltage drop based on 80 percent of design capacity of load buses.
3. Prepare load-flow and voltage-drop analysis and report to show power system components that are overloaded, or might become overloaded; show bus voltages that are less than as prescribed by NFPA 70.

3.6 MOTOR-STARTING STUDY

A. Perform motor-starting study to analyze transient effect of system's voltage profile during motor starting. Calculate significant motor-starting voltage profiles and analyze effects of motor starting on power system stability.

B. Prepare motor-starting study report, noting light flicker for limits proposed by IEEE 1453, and voltage sags so as not to affect operation of other utilization equipment on system supplying motor.

3.7 ARC-FLASH HAZARD STUDY

A. Comply with NFPA 70E, including Annex D, for arc-flash hazard study.

B. Preparatory Studies: Obtain short-circuit study and overcurrent protective device coordination study results prior to starting arc-flash hazard study.

C. Calculate maximum and minimum contributions of fault-current size.

1. Maximum calculation must assume maximum contribution from utility and must assume motors to be operating under full-load conditions.

2. Calculate arc-flash energy at 85 percent of maximum short-circuit current in accordance with IEEE 1584 recommendations.
3. Calculate arc-flash energy at 38 percent of maximum short-circuit current in accordance with NFPA 70E recommendations.
4. Calculate arc-flash energy with utility contribution at minimum and assume no motor contribution.

D. Calculate arc-flash protection boundary and incident energy at locations in electrical distribution system where personnel could perform work on energized parts.

E. Include low-voltage equipment locations.

F. Calculate limited, restricted, and prohibited approach boundaries for each location.

G. Incident energy calculations must consider accumulation of energy over time when performing arc-flash calculations on buses with multiple sources. Iterative calculations must account for changing current contributions, as sources are interrupted or decremented with time. Fault contribution from motors and generators must be decremented as follows:

1. Fault contribution from induction motors must not be considered beyond three to five cycles.
2. Fault contribution from synchronous motors and generators must be decayed to match actual decrement of each as closely as possible (for example, contributions from permanent magnet generators will typically decay from 10 p.u. to 3 p.u. after 10 cycles).

H. Arc-flash energy must generally be reported for maximum of line or load side of circuit breaker. However, arc-flash computation must be performed and reported for both line and load side of circuit breaker as follows:

1. When circuit breaker is in separate enclosure.
2. When line terminals of circuit breaker are separate from work location.

I. Base arc-flash calculations on actual overcurrent protective device clearing time. Cap maximum clearing time at two seconds based on IEEE 1584, Section B.1.2.

3.8 POWER SYSTEM STUDY REPORTS

A. Preparation of Power System Study Reports: Prepare and submit the following:

1. Short-Circuit Study Report Contents:

a. Executive summary of study findings.
b. Study descriptions, purpose, basis, and scope. Include case descriptions, definition of terms, and guide for interpretation of results.
c. One-line diagram of modeled power system, showing the following:

1) Protective device designations and ampere ratings.
2) Conductor types, sizes, and lengths.
3) Transformer kVA and voltage ratings.
4) Motor and generator designations and kVA ratings.
5) Switchboard and panelboard designations and ratings.
6) Derating factors and environmental conditions.
7) Revisions to electrical equipment required by study.

d. Comments and recommendations for system improvements or revisions in written document, separate from one-line diagram.
e. Short-Circuit Study Input Data:

1) One-line diagram of system being studied.
2) Power sources available.
3) Manufacturer, model, and interrupting rating of protective devices.
4) Conductors.
5) Transformer data.

f. Protective Device Evaluation:

1) Evaluate equipment and protective devices and compare to available short-circuit currents. Verify that equipment withstand ratings exceed available short-circuit current at equipment installation locations.
2) Tabulations of circuit breaker, fuse, and other protective device ratings versus calculated short-circuit duties.
3) For 600 V overcurrent protective devices, ensure that interrupting ratings are equal to or higher than calculated 1/2-cycle symmetrical fault current.
4) For devices and equipment rated for asymmetrical fault current, apply multiplication factors listed in standards to 1/2-cycle symmetrical fault current.
5) Verify adequacy of phase conductors at maximum three-phase bolted fault currents; verify adequacy of equipment grounding conductors and grounding electrode conductors at maximum ground-fault currents. Ensure that short-circuit withstand ratings are equal to or higher than calculated 1/2-cycle symmetrical fault current.

g. Short-Circuit Study Output Reports:

1) Low-Voltage Fault Report: Three-phase and unbalanced fault calculations, showing the following for each overcurrent device location:

a) Voltage.
b) Calculated fault-current magnitude and angle.
c) Fault-point X/R ratio.
d) Equivalent impedance.

2) Momentary Duty Report: Three-phase and unbalanced fault calculations, showing the following for each overcurrent device location:

a) Voltage.
b) Calculated symmetrical fault-current magnitude and angle.
c) Fault-point X/R ratio.
d) Calculated asymmetrical fault currents based on fault-point X/R ratio; based on calculated symmetrical value multiplied by 1.6; and based on calculated symmetrical value multiplied by 2.7.

3) Interrupting Duty Report: Three-phase and unbalanced fault calculations, showing the following for each overcurrent device location:

a) Voltage.
b) Calculated symmetrical fault-current magnitude and angle.
c) Fault-point X/R ratio.
d) No AC Decrement (NACD) ratio.
e) Equivalent impedance.
f) Multiplying factors for 2-, 3-, 5-, and 8-cycle circuit breakers rated on symmetrical basis.
g) Multiplying factors for 2-, 3-, 5-, and 8-cycle circuit breakers rated on total basis.

2. Overcurrent Protection Device Coordination Study Report Contents:

a. Executive summary of study findings.
b. Study descriptions, purpose, basis, and scope. Include case descriptions, definition of terms, and guide for interpretation of results.
c. One-line diagram of modeled power system, showing the following:

1) Protective device designations and ampere ratings.
2) Conductor types, sizes, and lengths.
3) Transformer kVA and voltage ratings.
4) Motor and generator designations and kVA ratings.
5) Switchboard and panelboard designations.
6) Revisions to electrical equipment required by study.

d. Report recommended settings of protective devices, ready to be applied in field. Use manufacturer's data sheets for recording recommended setting of overcurrent protective devices when available.

1) Phase and Ground Relays:

a) Device tag.
b) Relay current transformer ratio and tap, time dial, and instantaneous pickup value.

c) Recommendations on improved relaying systems, if applicable.

2) Circuit Breakers:

a) Adjustable pickups and time delays (long time, short time, and ground).
b) Adjustable time-current characteristic.
c) Adjustable instantaneous pickup.
d) Recommendations on improved trip systems, if applicable.

3) Fuses: Show current rating, voltage, and class.

e. Time-Current Coordination Curves: Determine settings of overcurrent protective devices to achieve selective coordination. Graphically illustrate that adequate time separation exists between devices installed in series, including power utility company's upstream devices. Prepare separate sets of curves for switching schemes and for emergency periods where power source is local generation. Show the following information:

1) Device tag and title, one-line diagram with legend identifying portion of system covered.
2) Terminate device characteristic curves at point reflecting maximum symmetrical or asymmetrical fault current to which device is exposed.
3) Identify device associated with each curve by manufacturer type, function, and, if applicable, tap, time delay, and instantaneous settings recommended.
4) Plot the following listed characteristic curves, as applicable:

a) Power utility's overcurrent protective device.
b) Medium-voltage equipment overcurrent relays.
c) Medium- and low-voltage fuses including manufacturer's minimum melt, total clearing, tolerance, and damage bands.
d) Low-voltage equipment circuit-breaker trip devices, including manufacturer's tolerance bands.
e) Transformer full-load current, magnetizing inrush current, and ANSI through-fault protection curves.
f) Cables and conductors damage curves.
g) Ground-fault protective devices.
h) Motor-starting characteristics and motor damage points.
i) Generator short-circuit decrement curve and generator damage point.

5) Maintain selectivity for tripping currents caused by overloads.
6) Maintain maximum achievable selectivity for tripping currents caused by overloads on series-rated devices.
7) Provide adequate time margins between device characteristics such that selective operation is achieved.
8) Comments and recommendations for system improvements.

3. Arc-Flash Hazard Study Report Contents:

a. Executive summary of study findings.
b. Study descriptions, purpose, basis, and scope. Include case descriptions, definition

of terms, and guide for interpretation of results.

c. One-line diagram, showing the following:

1) Protective device designations and ampere ratings.
2) Conductor types, sizes, and lengths.
3) Transformer kVA and voltage ratings, including derating factors and environmental conditions.
4) Motor and generator designations and kVA ratings.
5) Switchboard panelboard designations, and ratings.

d. Short-circuit study output data.

e. Overcurrent protective device coordination study report contents.

f. Arc-Flash Study Output Reports:

1) Interrupting Duty Report: Three-phase and unbalanced fault calculations, showing the following for each equipment location included in report:

a) Voltage.
b) Calculated symmetrical fault-current magnitude and angle.
c) Fault-point X/R ratio.
d) No AC Decrement (NACD) ratio.
e) Equivalent impedance.
f) Multiplying factors for 2-, 3-, 5-, and 8-cycle circuit breakers rated on symmetrical basis.
g) Multiplying factors for 2-, 3-, 5-, and 8-cycle circuit breakers rated on total basis.

g. Incident Energy and Flash Protection Boundary Calculations:

1) Arcing fault magnitude.
2) Protective device clearing time.
3) Duration of arc.
4) Arc-flash boundary.
5) Restricted approach boundary.
6) Limited approach boundary.
7) Working distance.
8) Incident energy.
9) Hazard risk category.
10) Recommendations for arc-flash energy reduction.

h. Fault study input data, case descriptions, and fault-current calculations including definition of terms and guide for interpretation of computer printout.

3.9 FIELD ADJUSTMENT FOR DEVICE COORDINATION

A. Adjust relay and protective device settings in accordance with recommended settings provided by coordination study. Field adjustments must be completed by engineering service division of equipment manufacturer under "Startup and Acceptance Testing" contract portion.

B. Make minor modifications to equipment as required to accomplish compliance with protective device coordination studies.

C. Testing and adjusting must be by qualified low-voltage electrical testing and inspecting agency.

1. Perform each visual and mechanical inspection and electrical test stated in NETA ATS. Certify compliance with test parameters. Perform NETA tests and inspections for adjustable overcurrent protective devices.

3.10 WARNING LABELING OF ARC-FLASH HAZARDS

A. Apply arc-flash label on front cover for each equipment included in study, including each piece of equipment listed below:

1. Medium-voltage switches.
2. Switchboards.
3. Panelboards.
4. Low voltage transformers.
5. Safety switches.
6. Control panels.

B. Base arc-flash label data on highest values calculated at each location.

C. Machine print warning labels with no handwritten or field-applied markings.

D. Install arc-flash warning labels under direct supervision and control of qualified electrical professional engineer.

E. Indicate on record Drawings location of equipment where personnel could be exposed to arc-flash hazard during their work.

1. Indicate arc-flash energy.
2. Indicate protection level required.

END OF SECTION

SECTION 260800 - COMMISSIONING OF ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Electrical equipment including the following:

   a. Transformers.
   b. Primary and secondary service electrical systems.
   c. Distribution and branch-circuit panelboards.
   d. Lightning protection systems.
   e. Grounding systems.
   f. Generator.

2. Controls and instrumentation, including the following:

   a. Equipment monitoring systems.
   b. Energy monitoring and control systems.
   c. Electrical metering and metering system.
   d. Lighting control systems.
   e. Security systems.
   f. Fire-alarm systems.

B. Related Requirements:

1. Section 019113 "General Commissioning Requirements" for general Cx process requirements and CxA responsibilities.
2. Section 260010 "Supplemental Requirements for Electrical" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.

1.2 DEFINITIONS

A. BoD: Basis-of-Design Document, as defined in Section 019113 "General Commissioning Requirements."

B. Cx: Commissioning, as defined in Section 019113 "General Commissioning Requirements."

C. CxA: Commissioning Authority, as defined in Section 019113 "General Commissioning Requirements."

D. OPR: Owner's Project Requirements, as defined in Section 019113 "General Commissioning Requirements."

E. "Systems," "Assemblies," "Subsystems," "Equipment," and "Components": Where these terms are used together or separately, they mean "as-built" systems, assemblies, subsystems, equipment, and components.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Construction Checklists by CxA: Draft construction checklists will be created by CxA for Contractor review.

C. Construction Checklists by Contractor: Include the following and comply with requirements in Section 019113 "General Commissioning Requirements" for construction checklists:

1. Instrumentation and control for electrical systems.
2. Instrumentation and control for lighting control systems.
3. Low-voltage power cables.
4. Control voltage power cables.
5. Electrical feeders and branch circuits.
6. Liquid-filled transformers.
7. Dry-type transformers.
8. Switchboard assemblies rated 1200 A or greater.
9. Low-voltage motor starters.
10. Low-voltage surge protective devices.
11. Medium-voltage power cables.
12. Metering devices.
13. Molded-case circuit breakers.
14. Low-voltage power circuit breakers.
15. Grounding systems.
16. Ground-fault protection systems.
17. Panelboards.
18. Receptacles and devices.
19. Engine generators.
20. Automatic transfer switches.
21. Battery systems.
22. Battery chargers.
23. Lighting.
24. Vehicle charging equipment.

1.4 QUALITY ASSURANCE

A. Testing Equipment and Instrumentation Quality and Calibration: For test equipment and instrumentation required to perform electrical Cx work, perform the following:

1. Submit test equipment and instrumentation list. For each equipment or instrument, identify the following:

a. Equipment/instrument identification number.
b. Planned Cx application or use.

c. Manufacturer, make, model, and serial number.
d. Calibration history, including certificates from agencies that calibrate the equipment and instrumentation.

2. Test equipment and instrumentation must meet the following criteria:

a. Capable of testing and measuring performance within the specified acceptance criteria.
b. Be calibrated at manufacturer's recommended intervals with current calibration tags permanently affixed to the instrument being used.
c. Be maintained in good repair and operating condition throughout duration of use on Project.
d. Be recalibrated/repaired if dropped or damaged in any way since last calibrated.

B. Proprietary Test Instrumentation and Tools:

1. Equipment Manufacturer's Proprietary Instrumentation and Tools: For installed equipment included in the Cx process, test instrumentation and tools manufactured or prescribed by equipment manufacturer to service, calibrate, adjust, repair, or otherwise work on its equipment or required as a condition of equipment warranty, perform the following:

a. Submit proprietary instrumentation and tools list. For each instrument or tool, identify the following:

1) Instrument or tool identification number.
2) Equipment schedule designation of equipment for which the instrument or tool is required.
3) Manufacturer, make, model, and serial number.
4) Calibration history, including certificates from agencies that calibrate the instrument or tool, where appropriate.

b. Include a separate list of proprietary test instrumentation and tools in operation and maintenance manuals.
c. Electrical proprietary test instrumentation and tools become property of Owner at the time of Substantial Completion.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 CONSTRUCTION CHECKLISTS

A. Prepare detailed construction checklists for electrical systems, subsystems, equipment, and components. Complete and submit construction checklists.

3.2 CONSTRUCTION CHECKLIST REVIEW

A. Review and provide written comments on draft construction checklists. CxA will create required draft construction checklists and provide them to Contractor.

B. Return draft Construction Checklist review comments within 10 days of receipt.

C. When review comments have been resolved, CxA will provide final construction checklists, marked "Approved for Use, (date)."

D. Use only construction checklists, marked "Approved for Use, (date)."

3.3 GENERAL TESTING REQUIREMENTS

A. Certify that electrical systems, subsystems, and equipment have been installed, calibrated, and started and that they are operating according to the Contract Documents and approved Shop Drawings and submittals.

B. Certify that electrical instrumentation and control systems have been completed and calibrated, that they are operating according to the Contract Documents and approved Shop Drawings and submittals, and that pretest set points have been recorded.

C. Set systems, subsystems, and equipment into operating mode to be tested according to approved test procedures (for example, normal shutdown, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).

D. Measure capacities and effectiveness of systems, assemblies, subsystems, equipment, and components, including operational and control functions to verify compliance with acceptance criteria.

E. Test systems, assemblies, subsystems, equipment, and components operating modes, interlocks, control responses, and responses to abnormal or emergency conditions, and response according to acceptance criteria.

F. Construction Checklists: Prepare and submit detailed construction checklists for electrical systems, subsystems, equipment, and components.

1. Contributors to development of construction checklists must include, but are not limited to, the following:

a. Electrical systems and equipment installers.
b. Electrical instrumentation and controls installers.

G. Perform tests using design conditions, whenever possible.

1. Simulated conditions may, with approval of Architect, be imposed using an artificial load when it is impractical to test under design conditions. Before simulating conditions, calibrate testing instruments. Provide equipment to simulate loads. Set simulated conditions as directed by CxA, and document simulated conditions and methods of simulation. After tests, return configurations and settings to normal operating conditions.

2. Cx test procedures may direct that set points be altered when simulating conditions is impractical.
3. Cx test procedures may direct that sensor values be altered with a signal generator when design or simulating conditions and altering set points are impractical.

H. If tests cannot be completed because of a deficiency outside the scope of the electrical system, document the deficiency and report it to Owner. After deficiencies are resolved, reschedule tests.

I. If seasonal testing is specified, complete appropriate initial performance tests and documentation and schedule seasonal tests.

J. Coordinate schedule with, and perform Cx activities at the direction of the CxA.

K. Comply with Construction Checklist requirements, including material verification, installation checks, startup, and performance tests requirements specified in Sections specifying electrical systems and equipment.

L. Provide qualified testing and inspecting agency personnel in accordance with Section 260010 "Supplemental Requirements for Electrical," instrumentation, tools, and equipment to complete and document the following:

1. Performance tests.
2. Demonstration of a sample of performance tests.
3. Cx tests.
4. Cx test demonstrations.

3.4 Cx TESTS FOR ELECTRICAL SYSTEMS

A. Verification of Electrical System Operation:

1. Prerequisites: Acceptance of results for construction checklists for Division 26 electrical components associated with electrical system.
2. Equipment and Systems to Be Tested: Division 26 electrical equipment.
3. Test Purpose: Verify operation of electrical system.
4. Test Conditions: Energize components of electrical system, one at a time.
5. Acceptance Criteria: Proper operation of electrical system over a 24-hour period.

B. Verification of Control and Instrumentation:

1. Prerequisites: Acceptance of results for construction checklists.

a. Section 260923 "Lighting Control Devices."
b. Section 260943.23 "Relay-Based Lighting Controls."
c. Section 262713 "Electricity Metering."
d. Division 28 systems.

C. Test Purpose: Verify operation of control and monitoring systems for Normal and Essential electrical systems.

D. Test Conditions:

1. Energize components of Normal electrical system.
2. Test operation of equipment.

E. Acceptance Criteria: Operation of equipment according to OPR.

END OF SECTION

SECTION 260923 - LIGHTING CONTROL DEVICES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Outdoor photoelectric switches.
2. Daylight-harvesting controls.
3. Business occupancy and vacancy sensors.
4. Storage occupancy sensors.
5. Emergency lighting controls.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" specifies additional coordination, scheduling, sequencing, submittal, and installation requirements applicable to the Work for electrical, communications, and electronic safety and security systems on the Project, including wiring methods.
2. Section 260526 "Grounding and Bonding for Electrical Systems" specifies grounding and bonding of lighting control devices referenced by this Section.
3. Section 260529 "Hangers and Supports for Electrical Systems" specifies hangers and supports referenced by this Section.
4. Section 260553 "Identification for Electrical Systems" specifies electrical equipment labels and warning signs referenced by this Section.
5. Section 262726 "Wiring Devices" for wall-box dimmers and manual light switches.

1.2 DEFINITIONS

A. BCELTS: Branch circuit emergency lighting transfer switch.

B. DPDT: Double pole double throw.

C. DPST: Double pole single throw.

D. N.C.: Normally closed.

E. N.O.: Normally open.

F. PIR: Passive infrared.

G. SPDT: Single pole double throw.

H. SPST: Single pole single throw.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Product Listing: Include copy of unexpired approval letter, on letterhead of qualified electrical testing agency, certifying product's compliance with specified listing criteria.

a. If listed manufacturer differs from selling manufacturer, indicate relationship between entities on submittal. Clearly indicate which entity warrants product performance and fitness for purpose.
b. Listing criteria identified in approval letter must match specified listing criteria. UL label indicating approval of equipment's enclosure is not considered approval of equipment for intended application.
c. Product identification in approval letter must match product branding and model numbers in submittal. Approval letters for discontinued or superseded products are unacceptable for submitted product.

2. Include manufacturer's sample extended warranty language.

C. Shop Drawings: Prepare and submit the following:

1. Show installation details for the following:

a. Occupancy sensors.
b. Vacancy sensors.

2. Interconnection diagrams showing field-installed wiring.
3. Diagrams for power, signal, and control wiring.

D. Field quality-control reports.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturer's published instructions.

C. Field Reports:

1. Manufacturer's field reports for field quality-control support.
2. Field reports for software and firmware upgrades.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Warranty documentation.

C. Software and firmware service agreement.

1.6 WARRANTY

A. Special Manufacturer Extended Warranty: Manufacturer warrants that lighting control devices perform in accordance with specified requirements and agrees to provide repair or replacement of components or products that fail to perform as specified within extended-warranty period. Warranty must convey to Owner upon acceptance of the Work.

1. Failures include, but are not limited to, the following:

a. Faulty operation of lighting control software.
b. Faulty operation of lighting control devices.

2. Initial Extended-Warranty Period: Three years from date of Substantial Completion; full coverage for labor, materials, and equipment.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements:

1. Products or components listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Must comply with CCR Title 24.

2.2 OUTDOOR PHOTOELECTRIC SWITCHES

A. UL WJFX - Solid-State, Low-Voltage, Outdoor Photoelectric Switch:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Eaton.
b. Intermatic, Inc.
c. Leviton Manufacturing Co., Inc.
d. NSi Industries LLC.
e. TE Connectivity Ltd.
f. nLight; Acuity Brands Lighting, Inc.

2. Source Limitations: Obtain products from single manufacturer.

3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

    a. Plug-in, Locking-Type Photocontrols: UL CCN WJFX, including UL 773.

4. Standard Features:

    a. Solid state; one set of N.O. dry contacts rated for 24 V(dc) at 1 A and 24 V(ac) at 1 A, to operate connected load, and compatible with lighting control system.
    b. Light-Level Monitoring Range: 1.5 to 10 fc, with an adjustment for turn-on and turn-off levels within that range.
    c. Time Delay: Thirty-second minimum, to prevent false operation.
    d. Mounting: 1/2 inch threaded male conduit.
    e. Failure Mode: Luminaire stays ON.
    f. Power Pack:

        1) Dry contacts rated for 20 A driver or LED load at 120 and 277 V(ac), for tungsten at 120 V(ac), and for at 120 V(ac). Sensor has 24 V(dc), 150 mA, Class 2 power source.

            a) LED status lights to indicate load status.
            b) Plenum rated.

        2) Digital controller capable:

            a) With integral current monitoring.
            b) Plenum rated.

2.3 DAYLIGHT-HARVESTING CONTROLS

A. UL WJCT - Daylight-Harvesting Control Switch:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Eaton.
    b. Hubbell Control Solutions; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    c. Leviton Manufacturing Co., Inc.
    d. Lithonia Lighting; Acuity Brands Lighting, Inc.
    e. NSi Industries LLC.
    f. Sensor Switch, Inc.
    g. TE Connectivity Ltd.
    h. WattStopper; Legrand North America, LLC.
    i. nLight; Acuity Brands Lighting, Inc.

2. Source Limitations: Obtain products from single manufacturer.

3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

    a. Photoelectric Switches: UL CCN WJCT, including UL 773A.

4. Standard Features:

    a. System operates indoor lighting.
    b. Ceiling-Mounted Switching Controls:

        1) Solid-state, light-level sensor unit, withpower pack, that detects changes in indoor lighting levels that are perceived by the eye.

    c. Operating Ambient Conditions: Dry interior conditions, 32 to 120 deg F.
    d. Sensor Output:

        1) Contacts rated to operate the associated power pack, complying with UL 773A. Sensor must be powered by the power pack.
        2) Digital signal compatible with power pack.

    e. Power Pack:

        1) Dry contacts rated for 20 A driver or LED load at 120 and 277 V(ac). Sensor has 24 V(dc), 150 mA, Class 2 power source.

            a) LED status lights to indicate load status.
            b) Plenum rated.

        2) Digital controller capable. Sensor has 24 V(dc) Class 2 power source.

            a) With integral current monitoring
            b) Plenum rated.

    f. General Space Sensors Light-Level Monitoring Range: 10 to 200 fc, with an adjustment for turn-on and turn-off levels within that range.
    g. Atrium Space Sensors Light-Level Monitoring Range: 100 to 1000 fc, with an adjustment for turn-on and turn-off levels within that range.
    h. Skylight Sensors Light-Level Monitoring Range: 1000 to 10 000 fc, with an adjustment for turn-on and turn-off levels within that range.
    i. Time Delay: Adjustable from 5 to 300 seconds to prevent cycling.
    j. Set-Point Adjustment: Equip with deadband adjustment of 25, 50, and 75 percent above the "on" set point, or provide with separate adjustable "on" and "off" set points.
    k. Test Mode: User selectable, overriding programmed time delay to allow settings check.
    l. Control Load Status: User selectable to confirm that load wiring is correct.
    m. Indicator: Two digital displays to indicate the beginning of on-off cycles.

5. Sequence of Operation: As daylight increases, the lights are turned off at a predetermined level. As daylight decreases, the lights are turned on at a predetermined level.

a. Lighting control set point is based on two lighting conditions:

1) When no daylight is present.
2) When significant daylight is present (target level).

b. System programming is done with two handheld, remote-control tools.

B. UL WJCT - Daylight-Harvesting Digital Control Dimmer:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Deep Roof Lighting.
b. Eaton.
c. Hubbell Control Solutions; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
d. Leviton Manufacturing Co., Inc.
e. Lithonia Lighting; Acuity Brands Lighting, Inc.
f. WattStopper; Legrand North America, LLC.
g. nLight; Acuity Brands Lighting, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. Photoelectric Switches: UL CCN WJCT, including UL 773A.

4. Standard Features:

a. Sensing daylight and electrical lighting levels, the system adjusts the indoor electrical lighting levels. As daylight increases, lights are dimmed.
b. System programming is done with two handheld, remote-control tools.

1) Initial setup tool.
2) Tool for occupants to adjust the target levels by increasing the set point up to 25 percent, or by minimizing the electric lighting level.

c. Ceiling-Mounted Dimming Controls: Solid-state, light-level sensor unit, with power pack, to detect changes in indoor lighting levels that are perceived by the eye.
d. Sensor Output: 0-10 V(dc) to operate luminaires. Sensor is powered by controller unit.
e. Light-Level Sensor Set-Point Adjustment Range: 20 to 60 fc.
f. Power Pack: Digital controller capable. Sensor has 24 V(dc) Class 2 power source.

1) With integral current monitoring.
2) Plenum rated.

5. Sequence of Operation: Lighting control set point is based on the following two lighting conditions:

a. When no daylight is present (target level).
b. When significant daylight is present.

2.4 BUSINESS OCCUPANCY AND VACANCY SENSORS

A. Passive-Infrared (PIR) Occupancy or Vacancy Sensor:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

   a. ADT Security Services, Inc.
   b. Ademco; Honeywell.
   c. Cooper Lighting Solutions; Signify North America Corp.
   d. Crestron Electronics, Inc.
   e. Honeywell Security Group.
   f. Hubbell Control Solutions; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
   g. Leviton Manufacturing Co., Inc.
   h. Lithonia Lighting; Acuity Brands Lighting, Inc.
   i. Lutron Electronics Co., Inc.
   j. Napco Security Technologies, Inc.
   k. Pass & Seymour; Legrand North America, LLC.
   l. RAB Lighting.
   m. WattStopper; Legrand North America, LLC.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for one of the following UL product categories:

   a. Photoelectric Controls: UL CCN WJCT, including UL 773A.
   b. Energy Management Equipment: UL CCN PAZX, including UL 916 or UL 60730-1.
   c. Intrusion Detection Units: UL CCN ANSR, including UL 639.

4. Standard Features:

   a. Ceiling-mounted, solid-state indoor occupancy and vacancy sensors.
   b. Power pack.
   c. Hardwired connection to switch.
   d. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A Sensor is powered from the power pack.
   e. Power Pack: Dry contacts rated for 20 A driver or LED load at 120 and 277 V(ac),. Sensor has 24 V(dc), 150 mA, Class 2 power source.
   f. Mounting:

      1) Sensor: Suitable for mounting in any position in a standard device box or outlet box.
      2) Relay: Externally mounted through a 1/2 inch knockout in a standard electrical enclosure.

3) Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.

g. Indicator: Digital display, to show when motion is detected during testing and normal operation of sensor.
h. Bypass Switch: Override the "on" function in case of sensor failure.
i. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc; turn lights off when selected lighting level is present.
j. Detector Sensitivity: Detect occurrences of 6 inch minimum movement of any portion of a human body that presents a target of not less than 36 sq. inch.

1) Detection Coverage (Room, Ceiling Mounted): Detect occupancy anywhere in a circular area of 1000 sq. ft when mounted on a 96 inch high ceiling.
2) Detection Coverage (Corridor, Ceiling Mounted): Detect occupancy within 90 ft when mounted on a 10 ft high ceiling.
3) Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 1000 sq. ft, 2000 sq. ft, or 3000 sq. ft when mounted 48 inch above finished floor.

5. Operation:

a. Occupancy Sensor: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
b. Vacancy Sensor: Unless otherwise indicated, lights are manually turned on and sensor turns lights off when the room is unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
c. Combination Sensor: Unless otherwise indicated, sensor must be programmed to turn lights on when coverage area is occupied and turn them off when unoccupied, or to turn off lights that have been manually turned on; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.

B. Ultrasonic Occupancy or Vacancy Sensor:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Cooper Lighting Solutions; Signify North America Corp.
b. Eaton.
c. Hubbell Control Solutions; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
d. Lutron Electronics Co., Inc.
e. WattStopper; Legrand North America, LLC.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for one of the following UL product categories:

a. Appliance Controls: UL CCN ATNZ, including UL 60730-1.

b. Energy Management Equipment: UL CCN PAZX, including UL 916 or UL 60730-1.
c. Intrusion Detection Units: UL CCN ANSR, including UL 639.

4. Standard Features:

a. Ceiling-mounted, solid-state indoor occupancy and vacancy sensors.
b. Power pack.
c. Hardwired connection to switch.
d. Power Pack: Dry contacts rated for 20 A driver or LED load at 120 and 277 V(ac). Sensor has 24 V(dc), 150 mA, Class 2 power source.
e. Mounting:

1) Sensor: Suitable for mounting in any position in a standard device box or outlet box.
2) Relay: Externally mounted through a 1/2 inch knockout in a standard electrical enclosure.
3) Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.

f. Indicator: Digital display, to show when motion is detected during testing and normal operation of sensor.
g. Bypass Switch: Override the "on" function in case of sensor failure.
h. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc; turn lights off when selected lighting level is present.
i. Detector Sensitivity: Detect a person of average size and weight moving not less than 12 inch in either a horizontal or a vertical manner at an approximate speed of 12 inch/s.

1) Detection Coverage (Small Room): Detect occupancy anywhere within a circular area of 600 sq. ft when mounted on a 96 inch high ceiling.
2) Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft when mounted on a 96 inch high ceiling.
3) Detection Coverage (Large Room): Detect occupancy anywhere within a circular area of 2000 sq. ft when mounted on a 96 inch high ceiling.
4) Detection Coverage (Corridor): Detect occupancy anywhere within 90 ft when mounted on a 10 ft high ceiling in a corridor not wider than 14 ft.
5) Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 1000 sq. ft, 2000 sq. ft, or 3000 sq. ft when mounted 84 inch above finished floor.

5. Operation:

a. Occupancy Sensor: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
b. Vacancy Sensor: Unless otherwise indicated, lights are manually turned on and sensor turns lights off when the room is unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
c. Combination Sensor: Unless otherwise indicated, sensor must be programmed to turn lights on when coverage area is occupied and turn them off when unoccupied,

or to turn off lights that have been manually turned on; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.

C. Dual-Technology, Passive-Infrared (PIR) and Ultrasonic, Occupancy or Vacancy Sensor:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

   a. Cooper Lighting Solutions; Signify North America Corp.
   b. HLI Solutions; brand of GE Current, a Daintree Company.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for one of the following UL product categories:

   a. Energy Management Equipment: UL CCN PAZX, including UL 916 or UL 60730-1.
   b. Appliance Controls: UL CCN ATNZ, including UL 60730-1.
   c. Intrusion Detection Units: UL CCN ANSR, including UL 639.

4. Standard Features:

   a. Ceiling and wall-mounted, solid-state indoor occupancy and vacancy sensors.
   b. Power pack.
   c. Hardwired connection to switch.
   d. Sensitivity Adjustment: Separate for each sensing technology.
   e. Detector Sensitivity: Detect occurrences of 6 inch minimum movement of any portion of a human body that presents a target of not less than 36 sq. inch, and detect a person of average size and weight moving not less than 12 inch in either a horizontal or a vertical manner at an approximate speed of 12 inch/s.

      1) Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft when mounted on a 96 inch high ceiling.
      2) Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 1000 sq. ft, 2000 sq. ft, or 3000 sq. ft when mounted 48 inch above finished floor.

5. Operation:

   a. Occupancy Sensor: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
   b. Vacancy Sensor: Unless otherwise indicated, lights are manually turned on and sensor turns lights off when the room is unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
   c. Combination Sensor: Unless otherwise indicated, sensor must be programmed to turn lights on when coverage area is occupied and turn them off when unoccupied, or to turn off lights that have been manually turned on; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.

D. Dual-Technology, Passive-Infrared (PIR) and Passive-Acoustic, Occupancy or Vacancy Sensor:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

   a. HLI Solutions; brand of GE Current, a Daintree Company.
   b. Lithonia Lighting; Acuity Brands Lighting, Inc.
   c. SensorWorx; brand of BLP Technologies, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for one of the following UL product categories:

   a. Energy Management Equipment: UL CCN PAZX, including UL 916 or UL 60730-1.
   b. Appliance Controls: UL CCN ATNZ, including UL 60730-1.
   c. Intrusion Detection Units: UL CCN ANSR, including UL 639.

4. Standard Features:

   a. Ceiling-mounted, solid-state indoor occupancy and vacancy sensors.
   b. Power pack.
   c. Hardwired connection to switch.
   d. Sensitivity Adjustment: Separate for each sensing technology.
   e. Detector Sensitivity: Detect occurrences of 6 inch minimum movement of any portion of a human body that presents a target of not less than 36 sq. inch, and detect a person of average size and weight moving not less than 12 inch in either a horizontal or a vertical manner at an approximate speed of 12 inch/s.

      1) Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft when mounted on a 96 inch high ceiling.
      2) Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 1000 sq. ft, 2000 sq. ft, or 3000 sq. ft when mounted 48 inch above finished floor.

5. Operation:

   a. Occupancy Sensor: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
   b. Vacancy Sensor: Unless otherwise indicated, lights are manually turned on and sensor turns lights off when the room is unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
   c. Combination Sensor: Unless otherwise indicated, sensor must be programmed to turn lights on when coverage area is occupied and turn them off when unoccupied, or to turn off lights that have been manually turned on; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.

2.5 STORAGE OCCUPANCY SENSORS

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

   a. Hubbell Control Solutions; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
   b. nLight; Acuity Brands Lighting, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

   a. Photoelectric Controls: UL CCN WJCT, including UL 773A.

4. Standard Features:

   a. Solid-State Unit: Designed to operate with the lamp and ballasts or drivers indicated.
   b. Power: Line voltage.

      1) Operating Ambient Conditions: 32 to 149 deg F.
      2) Mounting: Threaded pipe.
      3) Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.
      4) Detector Technology: PIR.

   c. Detector Coverage: User selectable by interchangeable PIR lenses, suitable for mounting heights from 12 to 50 ft.

5. Operation: Turn lights on when coverage area is occupied, and to half-power when unoccupied; with a time delay for turning lights to half-power that is adjustable over a minimum range of 1 to 16 minutes.
6. Accessories: Obtain manufacturer's installation and maintenance kit with laser alignment tool for sensor positioning and power port connectors.

B. Ceiling-Mounted, Solid-State, Extreme-Temperature Occupancy Sensor:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

   a. Eaton.
   b. Sensor Switch, Inc.
   c. nLight; Acuity Brands Lighting, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. Photoelectric Controls: UL CCN WJCT, including UL 773A.

4. Standard Features:

a. Operating Ambient Conditions: From minus 40 to plus 125 deg F.
b. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A. Sensor is powered from the power pack.
c. Separate Power Pack: Dry contacts rated for 20 A driver or LED load at 120 and 277 V(ac), for 13 A tungsten at 120 V(ac), and for 1 hp at 120 V(ac). Sensor has 24 V(dc), 150 mA, Class 2 power source.
d. Mounting:

1) Sensor: Suitable for mounting in any position in a standard device box or outlet box.
2) Relay: Externally mounted through a 1/2 inch knockout in a standard electrical enclosure.
3) Time-Delay and Sensitivity Adjustments: Recessed and concealed behind cover.

e. Bypass Switch: Override the "on" function in case of sensor failure.
f. Automatic Light-Level Sensor: Adjustable from 2 to 10 fc; keep lighting off when selected lighting level is present.
g. Detector Technology: PIR. Ceiling mounted; detect occupants in coverage area by their heat and movement.

1) Detector Sensitivity: Detect occurrences of 6 inch minimum movement of any portion of a human body that presents a target of not less than 36 sq. inch.
2) Detection Coverage (Room): Detect occupancy anywhere in a circular area of 1500 sq. ft when mounted on a 96 inch high ceiling.
3) Detection Coverage (High Bay): Detect occupancy within 25 ft when mounted on a 25 ft high ceiling.

5. Operation: Turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 30 minutes.

2.6 EMERGENCY LIGHTING CONTROLS

A. UL FTBR - Automatic Load Control Relay:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Bodine; Signify North America; Signify Holding.
b. Chloride; Signify North America; Signify Holding.
c. HLI Solutions; brand of GE Current, a Daintree Company.
d. Intelligent Lighting Controls Inc.
e. Lithonia Lighting; Acuity Brands Lighting, Inc.
f. WattStopper; Legrand North America, LLC.

g. nLight; Acuity Brands Lighting, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

   a. Emergency Lighting and Power Equipment: UL CCN FTBR, including UL 924.

4. Standard Features:

   a. N.C., electrically held relay.
   b. Coil Rating: 120 277 V.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine lighting control devices before installation. Reject lighting control devices that are wet, moisture damaged, or mold damaged.

B. Examine walls and ceilings for suitable conditions where lighting control devices will be installed.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 SELECTION OF CONDUCTORS AND CABLES

A. Power Wiring to Supply Side of Remote-Control Power Sources: Not smaller than 12 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. Classes 2 and 3 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than 18 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

C. Class 1 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than 14 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

3.3 INSTALLATION OF LIGHTING CONTROL DEVICES

A. Comply with manufacturer's published instructions.

B. Reference Standards for Installation: Unless more stringent installation requirements are specified in the Contract Documents or manufacturer's published instructions, comply with the following:

1. Electrical Construction: ICC IBC, ICC IFC, NFPA 1, NFPA 70, and NECA NEIS 1.
2. Electrical Maintenance: NFPA 70B.
3. Electrical Safety: NFPA 70E.
4. Grounding and Bonding: NECA NEIS 331 and Article 250 of NFPA 70.
5. Communications Work: BICSI N1.
6. Life Safety and Means of Egress Work: NFPA 101.
7. Work in Basements and Other Developed Subterranean Spaces: NFPA 520.
8. Consult Architect for resolution of conflicting requirements.

C. Special Installation Techniques:

1. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression systems, and partition assemblies.
2. Install and aim sensors in locations to achieve not less than 90 percent coverage of areas indicated. Do not exceed coverage limits specified in manufacturer's instructions.
3. Installation of Industrial Control Switches: Mount electrically held lighting contactors with elastomeric isolator pads to eliminate structure-borne vibration unless contactors are installed in an enclosure with factory-installed vibration isolators.
4. Installation of Wiring:

    a. Conduit: Minimum conduit size is 1/2 inch.
    b. Wiring within Enclosures: Separate power-limited and nonpower-limited conductors in accordance with conductor manufacturer's published instructions.
    c. Size conductors in accordance with lighting control device manufacturer's published instructions unless otherwise indicated.
    d. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, device, and outlet boxes; terminal cabinets; and equipment enclosures.

D. Interfaces with Other Work:

1. Identification: Provide labels for lighting control devices and associated electrical equipment.

    a. Identify field-installed conductors, interconnecting wiring, and components.
    b. Label each enclosure with engraved metal or laminated-plastic nameplate.
    c. Identify controlled circuits in lighting contactors.
    d. Identify circuits or luminaires controlled by photoelectric and occupancy sensors at each sensor.
    e. Label time switches and contactors with a unique designation.

3.4 FIELD QUALITY CONTROL

A. Administrant for Electrical Power Tests and Inspections:

1. Engage factory-authorized service representative to administer and perform tests and inspections on components, assemblies, and equipment installations, including connections.

B. Administrant for Lighting Tests and Inspections:

1. Engage factory-authorized service representative to administer and perform tests and inspections on components, assemblies, and equipment installations, including connections.

C. Field tests must be witnessed by Architect.

D. Tests and Inspections:

1. Operational Test: After installing time switches and sensors, and after electrical circuitry has been energized, start units to confirm proper unit operation.
2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

E. Nonconforming Work:

1. Lighting control devices will be considered defective if they do not pass tests and inspections.
2. Remove and replace defective units and retest.

F. Field Quality-Control Reports: Collect, assemble, and submit test and inspection reports.

3.5 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting lighting control devices to suit actual occupied conditions. Provide up to two visits to the Project site during other-than-normal occupancy hours for this purpose. Some of the Work may be required during hours of darkness.

1. For occupancy and motion sensors, verify operation at outer limits of detector range. Set time delay to suit Owner's operations.
2. For daylighting controls, adjust set points and deadband controls to suit Owner's operations.
3. Align high-bay occupancy sensors using manufacturer's laser aiming tool.

3.6 CLOSEOUT ACTIVITIES

A. Demonstration:

1. With assistance from factory-authorized service representatives, demonstrate to Owner's maintenance and clerical personnel and building occupants how to operate the following systems and equipment:

a. Lighting control devices.

B. Training:

1. With assistance from factory-authorized service representatives, train Owner's maintenance personnel on the following topics:

a. How to adjust, operate, and maintain lighting control devices.

3.7 MAINTENANCE

A. Software and Firmware Service Agreement:

1. Technical Support: Beginning at Substantial Completion, verify that software and firmware service agreement includes software support for two years.
2. Upgrade Service: At Substantial Completion, update software and firmware to latest version. Install and program software upgrades that become available within two years from date of Substantial Completion. Verify upgrading software includes operating system and new or revised licenses for using software.

    a. Upgrade Notice: Not less than 30 days; to allow Owner to schedule and access the system.

3. Field Reports for Software and Firmware Upgrades: Prepare and submit report after each update, documenting upgrades installed.

END OF SECTION

SECTION 260943.23 - RELAY-BASED LIGHTING CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Lighting control relay panels.
2. Networked lighting control panels.
3. Manual switches and cover plates.
4. Field-mounted signal sources.
5. Conductors and cables.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.

1.2 DEFINITIONS

A. Monitoring: Acquisition, processing, communication, and display of equipment status data, metered electrical parameter values, power quality evaluation data, event and alarm signals, tabulated reports, and event logs.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for control modules, power distribution components, relays, manual switches and cover plates, and conductors and cables.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
3. Sound data including results of operational tests of central dimming controls.
4. Operational documentation for software and firmware.

C. Shop Drawings: For each relay panel and related equipment.

1. Include dimensioned plans, elevations, sections, and details. Show tabulations of installed devices, equipment features, and ratings.
2. Detail enclosure types and details for types other than Type 1.
3. Detail wiring partition configuration, current, and voltage ratings.

4. Short-circuit current rating of relays.
5. Address Drawing: Reflected ceiling plan and floor plans, showing connected luminaires, address for each luminaire, and luminaire groups. Base plans on construction plans, using the same legend, symbols, and schedules.
6. Point List and Data Bus Load: Summary list of all control devices, sensors, ballasts, and other loads. Include percentage of rated connected load and device addresses.
7. Wire Termination Diagrams and Schedules: Coordinate nomenclature and presentation with Drawings and block diagram. Differentiate between manufacturer-installed and field-installed wiring.
8. Block Diagram: Show interconnections between components specified in this Section and devices furnished with power distribution system components. Indicate data communication paths and identify networks, data buses, data gateways, concentrators, and other devices to be used. Describe characteristics of network and other data communication lines.
9. Submit evidence that lighting controls are compatible with connected monitoring and control devices and systems specified in.

    a. Show interconnecting signal and control wiring, and interface devices that show compatibility of inputs and outputs.
    b. For control interfaces and adapters, list network protocols and provide statements from manufacturers that input and output devices comply with interoperability requirements of the protocol.

D. Field quality-control reports.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Sample warranties.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Handle and prepare panels for installation in accordance with NECA 407.

1.6 WARRANTY

A. Special Manufacturer Extended Warranty: Manufacturer warrants that components of standalone multipreset modular dimming controls perform in accordance with specified requirements and agrees to provide repair or replacement of components that fail to perform as specified within extended warranty period.

1. Initial Extended Warranty Period: Two year(s) from date of Substantial Completion, for labor, materials, and equipment.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Sequence of Operations: Input signal from field-mounted manual switches, or digital signal sources, must open or close one or more lighting control relays in the lighting control panels. Any combination of inputs must be programmable to any number of control relays.

B. Surge Protective Device: Factory installed as an integral part of control components or field-mounted surge suppressors complying with UL 1449, SPD Type 2.

C. Electrical Components, Devices, and Accessories: Listed and labeled in accordance with NFPA 70 by qualified electrical testing laboratory recognized by authorities having jurisdiction and marked for intended location and application.

D. Comply with 47 CFR 15, Subparts A and B, for Class A digital devices.

E. Comply with UL 916.

2.2 LIGHTING CONTROL RELAY PANELS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB, Electrification Business.
2. Intermatic, Inc.
3. Leviton Manufacturing Co., Inc.
4. Lithonia Lighting; Acuity Brands Lighting, Inc.
5. Lutron Electronics Co., Inc.
6. Philips; Signify North America; Signify Holding.
7. Siemens Industry, Inc., Energy Management Division.
8. Touch-Plate Technologies.
9. WattStopper; Legrand North America, LLC.

B. Description: Standalone lighting control panel using mechanically latched relays to control lighting and appliances.

C. Lighting Control Panel:

1. A single enclosure with incoming lighting branch circuits, control circuits, switching relays, and on-board timing and control unit.
2. A vertical barrier separating branch circuits from control wiring.

D. Control Unit: Contain the power supply and electronic control for operating and monitoring individual relays.

1. Timing Unit:

a. 365-day calendar, astronomical clock, and automatic adjustments for daylight savings and leap year.

b. Clock configurable for 12-hour (A.M./P.M.) or 24-hour format.
c. Four independent schedules, each having 24 time periods.
d. Schedule periods settable to the minute.
e. Day-of-week, day-of-month, day-of-year with one-time or repeating capability.
f. 10 special date periods.

2. Sequencing Control with Override:

a. Automatic sequenced on and off switching of selected relays at times set at the timing unit, allowing timed overrides from external switches.
b. Sequencing control must operate relays one at a time, completing the operation of all connected relays in not more than 10 seconds.
c. Override control must allow any relay connected to it to be switched on or off by a field-deployed manual switch or by an automatic switch, such as an occupancy sensor.
d. Override control "blink warning" must warn occupants approximately five minutes before actuating the off sequence.

3. Nonvolatile memory must retain all setup configurations. After a power failure, the controller must automatically reboot and return to normal system operation, including accurate time of day and date.

E. Relays:

1. Electrically operated, mechanically held single-pole switch, rated at 20 A at 277 V. Short-circuit current rating must be not less than 5 kA. Control must be three-wire, 24 V(ac).

F. Power Supply: NFPA 70, Class 2, sized for connected equipment, plus 20 percent spare capacity. Powered from a dedicated branch circuit of the panelboard that supplies power to the line side of the relays, sized to provide control power for the local panel-mounted relays, bus system, control-voltage inputs, field-installed occupancy sensors, and photo sensors.

G. Operator Interface:

1. Integral alphanumeric keypad and digital display, and intuitive drop-down menus to assist in programming.
2. Log and display relay on-time.
3. Connect relays to one or more time and sequencing schemes.

2.3 NETWORKED LIGHTING CONTROL PANELS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB, Electrification Business.
2. Intermatic, Inc.
3. Lithonia Lighting; Acuity Brands Lighting, Inc.
4. Lutron Electronics Co., Inc.
5. Touch-Plate Technologies.
6. WattStopper; Legrand North America, LLC.

B. Description: Lighting control panels using mechanically latched relays to control lighting and appliances. The panels must be capable of being interconnected with digital communications to appear to the operator as a single lighting control system.

C. Lighting Control Panels:

1. A single enclosure with incoming lighting branch circuits, control circuits, switching relays, and on-board timing and control unit.
2. A vertical barrier separating branch circuits from control wiring.

D. Main Control Unit: Installed in the main lighting control panel only; powered from the branch circuit of the standard control unit.

1. Ethernet Communications: Comply with TCP/IP protocol. The main control unit must provide for programming of all control functions of the main and all networked slave lighting control panels including timing, sequencing, and overriding.
2. Web Server: Display information listed below over a standard Web-enabled server for displaying information over a standard browser.

    a. A secure, password-protected login screen for modifying operational parameters, accessible to authorized users via Web page interface.
    b. Panel summary showing the master and slave panels connected to the controller.
    c. Controller diagnostic information.
    d. Show front panel mimic screens for setting up controller parameters, input types, zones, and operating schedules. These mimic screens must also allow direct breaker control and zone overrides.

3. Timing Unit:

    a. 365-day calendar, astronomical clock, and automatic adjustments for daylight savings and leap year.
    b. Clock configurable for 12-hour (A.M./P.M.) or 24-hour format.
    c. Four independent schedules, each having 24 time periods.
    d. Schedule periods settable to the minute.
    e. Day-of-week, day-of-month, day-of-year with one-time or repeating capability.
    f. 16 special date periods.

4. Time Synchronization: The timing unit must be updated not less than every hour(s) with the network time server.
5. Sequencing Control with Override:

    a. Automatic sequenced on and off switching of selected relays at times set at the timing unit, allowing timed overrides from external switches.
    b. Sequencing control must operate relays one at a time, completing the operation of all connected relays in not more than 10 seconds.
    c. Override control must allow any relay connected to it to be switched on or off by a field-deployed manual switch or by an automatic switch, such as an occupancy sensor.
    d. Override control "blinking warning" must warn occupants approximately five minutes before actuating the off sequence.
    e. Activity log, storing previous relay operation, including the time and cause of the change of status.

f. Download firmware to the latest version offered by manufacturer.

E. Standard Control Unit, Installed in All Lighting Control Panels: Contain electronic controls for programming the operation of the relays in the control panel, contain the status of relays, and contain communications link to enable the digital functions of the main control unit. Comply with UL 916.

1. Electronic control for operating and monitoring individual relays, and display relay on-time.
2. Nonvolatile memory must retain all setup configurations. After a power failure, the controller must automatically reboot and return to normal system operation.
3. Integral keypad and digital-display front panel for local setup, including the following:

a. Blink notice, time adjustable from software.
b. Ability to log and display relay on-time.
c. Capability for accepting downloadable firmware so that the latest production features may be added in the future without replacing the module.

F. Relays:

1. Electrically operated, mechanically held single-pole switch, rated at 20 A at 277 V. Short-circuit current rating must be not less than 5 kA. Control must be three-wire, 24 V(ac) digital control network.

G. Power Supply: NFPA 70, Class 2, UL listed, sized for connected equipment, plus not less than 20 percent spare capacity. Powered from a dedicated branch circuit of the panelboard that supplies power to the line side of the relays, sized to provide control power for the local panel-mounted relays, bus system, control-voltage inputs, field-installed occupancy sensors, and control-voltage photo sensors.

H. Operator Interface: At the main control unit, provide interface for a tethered connection of for configuring all networked lighting control panels using setup software designed for the specified operating system. Include one portable device for initial programming of the system and training of Owner's personnel. That device must remain the property of Owner.

I. Software:

1. Menu-driven data entry.
2. Online and offline programming and editing.
3. Provide for entry of the room or space designation for the load side of each relay.
4. Monitor and control all relays, showing actual relay state and the name of the automatic actuating control, if any.
5. Size the software appropriate to the system.

2.4 MANUAL SWITCHES AND COVER PLATES

A. Push-Button Switches: Modular, momentary contact, three wire, for operating one or more relays and to override automatic controls.

1. Match color and style specified in Section 262726 "Wiring Devices."
2. Integral green LED pilot light to indicate when circuit is on.

B. Cover Plates: Single and multigang cover plates as specified in Section 262726 "Wiring Devices."

C. Legend: Engraved or permanently silk-screened on cover plate where indicated. Use designations indicated on Drawings.

2.5 FIELD-MOUNTED SIGNAL SOURCES

A. Daylight Harvesting Switching Controls: Comply with Section 260923 "Lighting Control Devices." Control power may be taken from the lighting control panel, and signal must be compatible with the relays.

B. Indoor Occupancy Sensors and Extreme-Temperature Occupancy Sensors: Comply with Section 260923 "Lighting Control Devices." Control power may be taken from the lighting control panel, and signal must be compatible with the relays.

2.6 CONDUCTORS AND CABLES

A. Power Wiring to Supply Side of Class 2 Power Source: Not smaller than No. 12 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. Classes 2 and 3 Control Cables: Multiconductor cable with copper conductors not smaller than No. 18 AWG. Comply with requirements in Section 260523 "Control-Voltage Electrical Power Cables."

C. Class 1 Control Cables: Multiconductor cable with copper conductors not smaller than No. 14 AWG. Comply with requirements in Section 260523 "Control-Voltage Electrical Power Cables."

D. Twisted-Pair Data Cable: Category 6.

1. Comply with requirements for twisted pair cabling in Section 260523 "Control-Voltage Electrical Power Cables."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Receive, inspect, handle, and store panels in accordance with NECA 407.

B. Examine panels before installation. Reject panels that are damaged or rusted or have been subjected to water saturation.

C. Examine elements and surfaces to receive panels for compliance with installation tolerances and other conditions affecting performance of the Work.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF WIRING

A. Wiring Methods:

1. Install conductors and cables concealed in accessible ceilings, walls, and floors where possible.
2. Conceal raceway and cables except in unfinished spaces.
3. Provide plenum-rated cable, where installed exposed or in open cable tray, within environmental airspaces, including plenum ceilings.
4. Comply with requirements for raceways specified in Section 260533.13 "Conduits for Electrical Systems."

B. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Install lacing bars and distribution spools.

3.3 INSTALLATION OF PANELS

A. Install panels and accessories in accordance with NECA 407.

B. Mount panel cabinet plumb and rigid without distortion of box.

C. Install filler plates in unused spaces.

3.4 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

B. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs complying with Section 260553 "Identification for Electrical Systems."

C. Create a directory to indicate loads served by each relay; incorporate Owner's final room designations. Obtain approval before installing. Use a PC or typewriter to create directory; handwritten directories are unacceptable.

D. Lighting Control Panel Nameplates: Label each panel with a nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

3.5 FIELD QUALITY CONTROL

A. Field tests must be witnessed by Architect.

B. Tests and Inspections:

C. Nonconforming Work:

1. Lighting control panel will be considered defective if it does not pass tests and inspections.
2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.

D. Prepare test and inspection reports, including a certified report that identifies lighting control panels and describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations made after remedial action.

E. Manufacturer Services:

1. Engage factory-authorized service representative to perform field tests and inspections.

3.6 SYSTEM STARTUP

A. Engage a factory-authorized service representative to perform startup service.

1. Complete installation and startup checks in accordance with manufacturer's instructions.
2. Confirm correct communications wiring, initiate communications between panels, and program the lighting control system in accordance with approved configuration schedules, time-of-day schedules, and input override assignments.

3.7 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.8 MAINTENANCE

A. Software and Firmware Service Agreement:

1. Technical Support: Beginning at Substantial Completion, verify that software and firmware service agreement includes software support for two years.
2. Upgrade Service: At Substantial Completion, update software and firmware to latest version. Install and program software upgrades that become available within two years from date of Substantial Completion. Verify upgrading software includes operating system and new or revised licenses for using software.

    a. Upgrade Notice: No fewer than 30 days to allow Owner to schedule and access the system and to upgrade computer equipment if necessary.

3. Upgrade Reports: Prepare written report after each update, documenting upgrades installed.

END OF SECTION

SECTION 261219 – PAD-MOUNTED, LIQUID-FILLED, MEDIUM-VOLTAGE TRANSFORMERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Pad-mounted, liquid-filled, medium-voltage distribution transformers, with primary and secondary bushings within or without air-terminal enclosures.

1.2 DEFINITIONS

A. Bushing: An insulating structure including a central conductor, or providing a central passage for a conductor, with provision for mounting on a barrier, conducting or otherwise, for the purpose of insulating the conductor from the barrier and conducting current from one side of the barrier to the other.

B. Bushing Elbow: An insulated device used to connect insulated conductors to separable insulated connectors on dead-front, pad-mounted transformers and to provide a fully insulated connection. This is also called an "elbow connector."

C. Bushing Insert: That component of a separable insulated connector that is inserted into a bushing well to complete a dead-front, load break or nonload break, separable insulated connector (bushing).

D. Bushing Well: A component of a separable insulated connector, either permanently welded or clamped to an enclosure wall or barrier, having a cavity that receives a replaceable component (bushing insert) to complete the separable insulated connector (bushing).

E. Elbow Connector: See "bushing elbow" above.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

B. Preinstallation Coordination Meeting(s): For transformer. Conduct meeting(s) at Project site.

1. Attendees: Installers, fabricators, representatives of manufacturers, and administrants for field tests and inspections. Notify Architect, Construction Manager, and BGS's Commissioning Authority of scheduled meeting dates.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of product.

a. Include rated capacities, operating characteristics, and furnished specialties and accessories.

C. Shop Drawings:

1. For pad-mounted, liquid-filled, medium-voltage transformers.

a. Include plans and elevations showing major components and features.

1) Include plan view and cross section of equipment base, showing clearances, required workspace, and locations of penetrations for grounding and conduits.

b. Include details of equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of field connections.
c. Include single-line diagram.
d. Include list of materials.
e. Include nameplate data.
f. Manufacturer's published time-current curves of transformer line-side fuses, with transformer damage curve, inrush curve, and thru fault current indicated.

D. Field Quality-Control Submittals:

1. Field quality-control reports.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Certificates: For transformers, signed by product manufacturer.

C. Source quality-control reports.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Electrical Components, Devices, and Accessories: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

B. Comply with IEEE C2.

C. Comply with IEEE C57.12.00.

2.2 PERFORMANCE REQUIREMENTS

A. Windings Material: Aluminum or copper.

B. Surge Arresters: Comply with IEEE C62.11, Distribution Class; metal-oxide-varistor type, fully shielded, separable-elbow type, suitable for plugging into inserts provided in line-side section of transformer. Connected in each phase of incoming circuit and ahead of disconnecting device.

C. Winding Connections: Connection of windings and terminal markings must comply with IEEE C57.12.70.

D. Efficiency: Comply with 10 CFR 431, Subpart K.

E. Insulation: Transformer kVA rating must be as follows: Average winding temperature rise above 30 deg C ambient temperature must not exceed 65 deg C and 80 deg C hottest-spot temperature rise at rated kVA when tested in accordance with IEEE C57.12.90, using combination of connections and taps that give highest average winding temperature rise.

F. Tap Changer: External handle, for de-energized operation.

G. Tank: Sealed, with welded-on cover. Designed to withstand internal pressure of not less than 7 psi without permanent distortion and 15 psig without rupture. Comply with IEEE C57.12.36.

H. Enclosure Integrity: Comply with IEEE C57.12.28 for pad-mounted enclosures that contain energized electrical equipment in excess of 600 V that may be exposed to public.

I. Mounting: Integral skid mounting frame, suitable to allow skidding or rolling of transformer in any direction, and with provision for anchoring frame to pad.

J. Insulating Liquids:

1. Less-Flammable Liquids:

a. Edible-Seed-Oil-Based Dielectric: Listed and labeled by qualified electrical testing laboratory recognized by authorities having jurisdiction as complying with NFPA 70 requirements for fire point of not less than 300 deg C when tested in accordance with ASTM D92. Liquid must be biodegradable and nontoxic, having passed Organisation for Economic Co-operation and Development G.L.203 with zero mortality, and must be certified by U.S. Environmental Protection Agency as biodegradable, meeting Environmental Technology Verification requirements.

K. Sound level must comply with NEMA TR 1 requirements.

L. Corrosion Protection:

1. Base and Cabinets of Two Compartment Transformers: Fabricate from steel in, not less than No. 13 U.S. gage. Coat transformer with manufacturer's standard green color coating complying with requirements of IEEE C57.12.28, in manufacturer's standard color green.

2.3 THREE-PHASE TRANSFORMERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ERMCO-ECI.
2. Eaton.
3. GE Power; General Electric Company.
4. Hitachi ABB Power Grids Ltd.; ABB & Hitachi Joint Venture.
5. Howard Industries, Inc.
6. Prolec GE; A Xignux and General Electric Company Joint Venture.

B. Description:

1. Electrical Components, Devices, and Accessories: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Comply with IEEE C57.12.26.

C. Compartment Construction:

1. Double-Compartment Construction: Individual compartments for line- and load-side sections, formed by steel isolating barriers that extend full height and depth of compartments, with hinged, lift-off doors and three-point latching, with stop in open position and provision for padlocking.

D. Primary Fusing: Designed and rated to provide thermal protection of transformer by sensing overcurrent and high liquid temperature.

1. 150 kV BIL current-limiting fuses, conforming to requirements of IEEE C37.47.
2. Interrupting Rating: 50 000 A(rms sym) at system voltage.
3. Fuse Assembly: Bayonet-type, liquid-immersed, expulsion fuses in series with liquid-immersed, partial-range, current-limiting fuses. Bayonet fuse must sense both high currents and high oil temperature to provide thermal protection to transformer. Connect current-limiting fuses ahead of radial-feed load-break switch.
4. Provide bayonet fuse assembly with oil retention valve and external drip shield inside housing to eliminate or minimize oil spills. Valve must close when fuse holder is removed and external drip shield is installed.
5. Provide conspicuously displayed warning adjacent to bayonet fuse(s), cautioning against removing or inserting fuses unless transformer has been de-energized and tank pressure has been released.

E. Line-Side Section: Dead-front design.

1. To connect primary cable, use separable insulated connectors; coordinated with and complying with requirements of Section 260513 "Medium-Voltage Cables." Bushings must be one-piece units, with ampere and BIL ratings same as connectors.
2. Bushing inserts:

a. Conform to requirements of IEEE 386.
b. Rated at 200 A, with voltage class matching connectors. Provide parking stand near bushing wells.

c. Provide insulated protective caps for insulating and sealing out moisture from unused bushing inserts.

3. Bushing wells configured for loop-feed application.
4. Access to liquid-immersed fuses.
5. Dead-front surge arresters.
6. Tap-changer operator.
7. Load-Break Switch:

a. Loop-feed sectionalizing switches, using three two-position, liquid-immersed-type switches for closed transition loop-feed and sectionalizing operation. Voltage class and BIL must match that of separable connectors, with continuous current rating and load-break rating of 200 A, and make-and-latch rating of 12 kA(rms sym). Switch operation must be as follows:

1) Position I: Line A connected to line B and both lines connected to transformer.
2) Position II: Transformer connected to line A only.
3) Position III: Transformer connected to line B only.
4) Position IV: Transformer disconnected and line A not connected to line B.
5) Position V: Transformer disconnected and line A connected to line B.

8. Ground pad.

F. Load-Side Section:

1. Bushings with spade terminals drilled for terminating number of conductors indicated on Drawings, and lugs that comply with requirements of Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

G. Capacities and Characteristics:

1. Power Rating: As indicated on Drawings.
2. Voltage Ratings: V - 480Y/277 V.
3. Taps: Comply with IEEE C57.12.26 requirements.
4. Transformer BIL (kV): Comply with IEEE C57.12.26 requirements.
5. Minimum Tested Impedance (Percent) at 85 deg C: 4.03.
6. Comply with FM Global Class No. 3990.
7. Comply with UL listing requirements for combination classification and listing for transformer and less-flammable insulating liquid.

H. Transformer Accessories:

1. Drain and filter connection.
2. Filling and top filter press connections.
3. Pressure-vacuum gauge.
4. Dial-type analog thermometer with alarm contacts.
5. Automatically resetting pressure-relief device. Device flow must be as recommended by manufacturer.
6. Stainless steel ground connection pads.
7. Machine-engraved nameplate, made of anodized aluminum or stainless steel.

2.4 WARNING LABELS AND SIGNS

A. Comply with requirements for labels and signs specified in Section 260553 "Identification for Electrical Systems."

1. High-Voltage Warning Label: Provide self-adhesive warning signs on outside of line-side compartment door(s). Sign legend must be "DANGER HIGH VOLTAGE" printed in two lines of nominal 2 inch high letters. Word "DANGER" must be in white letters on red background and words "HIGH VOLTAGE" must be in black letters on white background.
2. Arc Flash Warning Label: Provide self-adhesive warning signs on outside of line-side compartment door(s), warning of potential electrical arc flash hazards and appropriate personal protective equipment required.

2.5 SOURCE QUALITY CONTROL

A. Testing Administrant: Engage qualified electrical testing agency to evaluate transformer.

B. Testing: Test and inspect transformer in accordance with IEEE C57.12.90.

C. Factory Tests and Inspections: Perform the following tests and inspections, by, or under supervision of, qualified electrical testing laboratory recognized by authorities having jurisdiction, before delivering to site. Affix label with name and date of manufacturer's certification of system compliance on control units.

1. Resistance.
2. Turns ratio, polarity, and phase relation.
3. Transformer no-load losses and excitation current at 100 percent of ratings.
4. Transformer impedance voltage and load loss.
5. Operation of devices.
6. Lightning impulse.
7. Low frequency.
8. Leak.
9. Perform Optional Tests:

    a. Transformer no-load losses and excitation current at 110 percent of ratings.
    b. Insulation power factor.
    c. Applied potential, except that this test is not required for single-phase transformers or for three-phase Y-Y-connected transformers.
    d. Induced potential.
    e. Resistance measurements of windings on rated voltage connection and at tap extreme connections.
    f. Ratios on rated voltage connection and at tap extreme connections.
    g. Polarity and phase relation on rated voltage connection.
    h. No-load loss at rated voltage on rated voltage connection.
    i. Exciting current at rated voltage on rated voltage connection.
    j. Impedance.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine pad-mounted, liquid-filled, medium-voltage transformers upon delivery.

1. Upon delivery of transformers and prior to unloading, inspect equipment for damage that may have occurred during shipment or storage.
2. Verify that tie rods and chains are undamaged and tight, and that blocking and bracing is tight. Verify that there is no evidence of load shifting in transit, and that readings from transportation shock recorders, if equipped, are within manufacturer's recommendations.
3. Verify that there is no indication of external damage and no dents or scratches in doors and sill, tank walls, radiators and fins, or termination provisions.
4. Verify that there is no evidence of insulating-liquid leakage on transformer surfaces, at weld seams, on line- or load-side bushing parts, and at transformer base.
5. Verify that there is positive pressure or vacuum on tank. Check pressure gauge; it is required to read other than zero.
6. Compare transformers and accessories received with bill of materials to verify that shipment is complete. Verify that transformers and accessories conform with manufacturer's quotation and shop drawings. If shipment is incomplete or does not comply with Project requirements, notify manufacturer in writing immediately.
7. Verify presence of polychlorinated biphenyl content labeling.
8. Unload transformers carefully, observing packing label warnings and handling instructions.
9. Open termination compartment doors and inspect components for damage or displaced parts, loose or broken connections, cracked or chipped insulators, bent mounting flanges, dirt or foreign material, and water or moisture.

B. Handling:

1. Handle transformers carefully, in accordance with manufacturer recommendations, to avoid damage to enclosure, termination compartments, base, frame, tank, and internal components. Do not subject transformers to impact, jolting, jarring, or rough handling.
2. Protect transformer termination compartments against entrance of dust, rain, and snow.
3. Transport transformers upright, to avoid internal stresses on core and coil mounting assembly and to prevent trapping air in windings. Do not tilt or tip transformers.
4. Verify that transformer weights are within rated capacity of handling equipment.
5. Use only manufacturer-recommended points for lifting, jacking, and pulling. Use lifting lugs when lifting transformers.
6. Use jacks only at corners of tank base plate.
7. Use nylon straps of same length to balance and distribute weight when handling transformers with crane.
8. Use spreaders or lifting beam to obtain vertical lift and to protect transformer from straps bearing against enclosure. Lifting cable pull angles may not be greater than 15 degrees from vertical.
9. Exercise care not to damage tank base structure when handling transformer using skids or rollers. Use skids to distribute stresses over tank base when using rollers under large transformers.

C. Storage:

1. Store transformers in accordance with manufacturer's recommendations.
2. Transformers may be stored outdoors. If possible, store transformers at final installation locations on concrete pads. If dry concrete surfaces are unavailable, use pallets of adequate strength to protect transformers from direct contact with ground. Ensure transformer is level.
3. Ensure that transformer storage location is clean and protected from severe conditions. Protect transformers from dirt, water, contamination, and physical damage. Do not store transformers in presence of corrosive or explosive gases. Protect transformers from weather when stored for more than three months.
4. Store transformers with compartment doors closed.
5. Regularly inspect transformers while in storage and maintain documentation of storage conditions, noting discrepancies or adverse conditions. Verify that effective pressure seal is maintained using pressure gauges. Visually check for insulating-liquid leaks and rust spots.

D. Examine areas and space conditions for compliance with requirements for pad-mounted, liquid-filled, medium-voltage transformers and other conditions affecting performance of the Work.

E. Examine roughing-in of conduits and grounding systems to verify the following:

1. Wiring entries comply with layout requirements.
2. Entries are within conduit-entry tolerances specified by manufacturer, and no feeders will cross section barriers to reach load or line lugs.

F. Examine concrete bases for suitable conditions for transformer installation.

G. Pre-Installation Checks:

1. Verify removal of shipping bracing after placement.
2. Remove sample of insulating liquid in accordance with ASTM D923. Insulating-liquid values must comply with NETA ATS, Table 100.4. Sample must be tested for the following:

a. Dielectric Breakdown Voltage: ASTM D877 or ASTM D1816.
b. Acid Neutralization Number: ASTM D974.
c. Specific Gravity: ASTM D1298.
d. Interfacial Tension: ASTM D971.
e. Color: ASTM D1500.
f. Visual Condition: ASTM D1524.
g. Water in Insulating Liquids: Comply with ASTM D1533.
h. Power Factor or Dissipation Factor: ASTM D924.

H. Verify that ground connections are in place and that requirements in Section 260526 "Grounding and Bonding for Electrical Systems" have been met. Maximum ground resistance must be 5 Ω at transformer location.

I. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install transformers on concrete equipment base(s).

B. Transformer must be installed level and plumb and must tilt less than 1.5 degrees while energized.

C. Maintain minimum clearances and workspace at equipment in accordance with manufacturer's published instructions and IEEE C2.

3.3 CONNECTIONS

A. Provide ground ring and ground rods around the transform pad and ground equipment in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

1. For counterpoise, use tinned bare copper cable not smaller than 4/0 AWG, buried not less than 30 inch below grade interconnecting grounding electrodes. Bond surge arrester and neutrals directly to transformer enclosure and then to grounding electrode system with bare copper conductors, sized as shown. Keep lead lengths as short as practicable, with no kinks or sharp bends.
2. Fence and equipment connections may not be smaller than 4 AWG. Ground fence at gate posts and corner posts and at intervals not exceeding 10 ft. Bond gate sections to fence posts using 1/8 by 1 inch tinned flexible braided copper strap and clamps.
3. Make joints in grounding conductors and loops by exothermic weld or compression connector.
4. Terminate grounding and bonding conductors on common equipment grounding terminal on transformer enclosure.
5. Complete transformer tank grounding and lightning arrester connections prior to making other electrical connections.

B. Connect wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

1. Maintain air clearances between energized live parts and between live parts and ground for exposed connections in accordance with manufacturer recommendations.
2. Bundle associated phase, neutral, and equipment grounding conductors together within transformer enclosure. Arrange conductors such that there is not excessive strain that could cause loose connections. Allow adequate slack for expansion and contraction of conductors.

C. Terminate medium-voltage cables in incoming section of transformers in accordance with Section 260513 "Medium-Voltage Cables."

3.4 SIGNS AND LABELS

A. Comply with installation requirements for labels and signs specified in Section 260553 "Identification for Electrical Systems."

B. Install warning signs as required to comply with 29 CFR 1910.269.

3.5 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. General Field-Testing Requirements:

    a. Comply with provisions of "Testing and Test Methods" Chapter in NFPA 70B.
    b. Perform visual and mechanical inspections and electrical tests. Certify compliance with test parameters.
    c. After installing transformer but before primary is energized, verify that grounding system at transformer is tested at specified value or less.
    d. After installing transformer and after electrical circuitry has been energized, test for compliance with requirements.
    e. Visual and Mechanical Inspection:

        1) Verify equipment nameplate data complies with Contract Documents.
        2) Inspect bolted electrical connections for high resistance using one of the following two methods:

            a) Use low-resistance ohmmeter to compare bolted connection resistance values to values of similar connections. Investigate values that deviate from those of similar bolted connections by more than 50 percent of lowest value.
            b) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method in accordance with manufacturer's published data or NETA ATS, Table 100.12. Bolt-torque levels must be in accordance with manufacturer's published data. In absence of manufacturer's published data, use NETA ATS, Table 100.12.

2. Medium-Voltage Surge Arrester Field Tests:

    a. Visual and Mechanical Inspection:

        1) Inspect physical and mechanical condition.
        2) Verify arresters are clean.
        3) Verify that ground leads on devices are individually attached to ground bus or ground electrode.

    b. Electrical Test:

        1) Perform insulation-resistance test on arresters, phase terminal-to-ground. Apply voltage in accordance with manufacturer's published data. In absence of manufacturer's published data, comply with NETA ATS, Table 100.1. Replace units that fail to comply with recommended minimum insulation resistance listed in that table.
        2) Perform watts-loss test. Evaluate watts-loss values by comparison with similar units and test equipment manufacturer's published data.

3. Liquid-Filled Transformer Field Tests:

    a. Visual and Mechanical Inspection:

        1) Test dew point of tank gases if applicable.
        2) Inspect anchorage, alignment, and grounding.
        3) Verify bushings are clean.

4) Verify that liquid level in tanks is within manufacturer's published tolerances.
5) Perform specific inspections and mechanical tests recommended by manufacturer.
6) Verify presence of transformer surge arresters and that their ratings are as specified.
7) Verify that as-left tap connections are as specified.

b. Electrical Tests:

1) Perform insulation-resistance tests winding-to-winding and windings-to-ground. Apply voltage in accordance with manufacturer's published data. In absence of manufacturer's published data, comply with NETA ATS, Table 100.5. Calculate polarization index; value of index may not be less than 1.0.
2) Perform power-factor or dissipation-factor tests on windings in accordance with test equipment manufacturer's published data. Maximum winding insulation power-factor/dissipation-factor values must be in accordance with manufacturer's published data. In absence of manufacturer's published data, comply with NETA ATS, Table 100.3.
3) Measure core insulation resistance at 500 V(dc) if core is insulated and core ground strap is removable. Core insulation-resistance values may not be less than 1 MΩ at 500 V(dc).
4) Perform power-factor or dissipation-factor tip-up test on windings greater than 2.5 kV.
5) Perform Optional Field Tests:

a) Perform turns-ratio tests at tap positions. Turns-ratio test results may not deviate by more than one-half percent from either adjacent coils or calculated ratio. If test fails, replace transformer.
b) Perform excitation-current test on each phase. Typical excitation-current test data pattern for three-legged core transformer is two similar current readings and one lower current reading. Investigate and correct if test shows different pattern.
c) Measure resistance of windings at tap connections, and record temperature-corrected winding-resistance values in Operations and Maintenance Manual.
d) Perform applied-voltage test on line- and load-side windings-to-ground. Comply with IEEE C57.12.91, Sections 10.2 and 10.9. This test is not required for single-phase transformers and for three-phase wye-wye-connected transformers.

6) Verify correct secondary voltage, phase-to-phase and phase-to-neutral, after energization and prior to loading.
7) Remove sample of insulating liquid in accordance with ASTM D923, and perform dissolved-gas analysis in accordance with IEEE C57.104 or ASTM D3612.

B. Nonconforming Work:

1. Equipment and devices will be considered defective if they do not pass tests and inspections.

2. Remove and replace malfunctioning units and retest.

C. Prepare test and inspection reports. Record as-left set points of adjustable devices.

3.6 FOLLOW-UP SERVICE

A. Voltage Monitoring and Adjusting: After Substantial Completion, if requested by BGS, but not more than six months after Final Acceptance, perform the following voltage monitoring:

1. During period of normal load cycles as evaluated, perform seven days of three-phase voltage recording at outgoing section of transformers. Use voltmeters with calibration traceable to National Institute of Science and Technology standards and with chart speed of not less than 1 inch per hour. Voltage unbalance greater than 1 percent between phases, or deviation of phase voltage from nominal value by more than plus or minus 5 percent during test period, is unacceptable.
2. Corrective Action: If test results are unacceptable, perform the following corrective action, as appropriate:

    a. Adjust transformer taps.
    b. Prepare written request for voltage adjustment by electric utility.

3. Retests: Repeat monitoring, after corrective action is performed, until satisfactory results are obtained.
4. Report:

    a. Prepare written report covering monitoring performed and corrective action taken.

B. Infrared Inspection: Perform survey during periods of maximum possible loading. Remove necessary covers prior to inspection.

1. After Substantial Completion, but not more than 60 days after Final Acceptance, perform infrared inspection of transformer's electrical power connections.
2. Instrument: Inspect distribution systems with imaging equipment capable of detecting minimum temperature difference of 1 deg C at 30 deg C.
3. Record of Infrared Inspection: Prepare certified report that identifies testing technician and equipment used, and lists results as follows:

    a. Description of equipment to be tested.
    b. Discrepancies.
    c. Temperature difference between area of concern and reference area.
    d. Probable cause of temperature difference.
    e. Areas inspected. Identify inaccessible and unobservable areas and equipment.
    f. Identify load conditions at time of inspection.
    g. Provide photographs and thermograms of deficient area.

4. Act on inspection results in accordance with recommendations of NETA ATS, Table 100.18. Correct possible and probable deficiencies as soon as possible. Retest until deficiencies are corrected.

END OF SECTION

SECTION 262213 - LOW-VOLTAGE DISTRIBUTION TRANSFORMERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Distribution, dry-type transformers with nominal primary and secondary rating of 600 V and less, with capacities up to 1500 kVA.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data:

1. For each type of product.

a. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type and size of transformer.
b. Include rated nameplate data, capacities, weights, dimensions, minimum clearances, installed devices and features, and performance for each type and size of transformer.

C. Shop Drawings:

1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of field connections.
2. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment.
3. Include diagrams for power, signal, and control wiring.

D. Field Quality-Control Submittals:

1. Field quality-control reports.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Manufacturers' Published Instructions: Record copy of official installation and testing instructions issued to Installer by manufacturer for the following:

1. Transformer temporary heating, working clearances, anchoring, torque values, and insulation-resistance testing.

C. Source quality-control reports.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Inspection: On receipt, inspect for and note shipping damage to packaging and transformer.

1. If manufacturer packaging is removed for inspection, and transformer will be stored after inspection, re-package transformer using original or new packaging materials that provide protection equivalent to manufacturer's packaging.

B. Storage: Store in warm, dry, and temperature-stable location in original shipping packaging.

C. Temporary Heating: Apply temporary heat in accordance with manufacturer's published instructions within enclosure of ventilated-type units, throughout periods during which equipment is not energized and when transformer is not in space that is continuously under normal control of temperature and humidity.

D. Handling: Follow manufacturer's instructions for lifting and transporting transformers.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB, Electrification Business.
2. Acme Electric; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
3. Dongan Electric Manufacturing Company.
4. Eaton.
5. Federal Pacific.
6. Hammond Power Solutions Inc.
7. Jefferson Electric, Inc.
8. Lincoln Electric Products Co., Inc.
9. MGM Transformer Company.
10. Mag-Tran; a division of Quality Transformer & Electronics.
11. Marcus Transformer LTD.
12. Micron Industries Corporation.

13. Mirus International Inc.
14. Powersmiths International Corp.; Socomec Group.
15. Prolec GE; A Xignux and General Electric Company Joint Venture.
16. Rex Power Magnetics.
17. Siemens Industry, Inc., Energy Management Division.
18. SolaHD; Emerson Electric Co., Automation Solutions.
19. Square D; Schneider Electric USA.
20. TEMCo Transformers.

B. Source Limitations: Obtain each type of transformer from single source from single manufacturer.

2.2 GENERAL TRANSFORMER REQUIREMENTS

A. Description: Factory-assembled and -tested, air-cooled units for 60 Hz service.

B. Electrical Components, Devices, and Accessories: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

C. Transformers Rated 15 kVA and Larger:

1. Comply with 10 CFR 431 (DOE 2016) efficiency levels.
2. Marked as compliant with DOE 2016 efficiency levels by qualified electrical testing laboratory recognized by authorities having jurisdiction.

D. Shipping Restraints: Paint or otherwise color-code bolts, wedges, blocks, and other restraints that are to be removed after installation and before energizing. Use fluorescent colors that are easily identifiable inside transformer enclosure.

2.3 DISTRIBUTION TRANSFORMERS

A. Comply with NFPA 70, and list and label as complying with UL 1561.

B. Cores: Electrical grade, non-aging silicon steel with high permeability and low hysteresis losses.

1. One leg per phase.
2. Core volume must allow efficient transformer operation at 10 percent above nominal tap voltage.
3. Grounded to enclosure.

C. Coils: Continuous windings without splices except for taps.

1. Coil Material: Aluminum or copper.
2. Internal Coil Connections: Brazed or pressure type.
3. Terminal Connections: Welded or bolted.

D. Enclosure: Ventilated.

1. Core and coil must be encapsulated within resin compound using vacuum-pressure impregnation process to seal out moisture and air.
2. KVA Ratings: Based on convection cooling only and not relying on auxiliary fans.
3. Wiring Compartment: Sized for conduit entry and wiring installation.
4. Environmental Protection:

    a. Indoor: UL 50E, Type 2.

5. Finish Color: Gray weather-resistant enamel.

E. Taps for Transformers 25 kVA and Larger: Two 2.5 percent taps above and four 2.5 percent taps below normal full capacity.

F. Insulation Class, 30 kVA and Larger: 220 deg C, UL-component-recognized insulation system with maximum of 115 deg C rise above 40 deg C ambient temperature.

G. Grounding: Provide ground-bar kit or ground bar installed on inside of transformer enclosure.

H. Electrostatic Shielding: Windings must have independent, single, full-width copper electrostatic shield arranged to minimize interwinding capacitance.

1. Arrange coil leads and terminal strips to minimize capacitive coupling between input and output terminals.
2. Include special terminal for grounding shield.

I. Wall Brackets: Manufacturer's standard brackets.

J. Low-Sound-Level Requirements: Maximum sound levels when factory tested in accordance with IEEE C57.12.91, as follows:

1. 9.01 to 30.00 kVA: 45 dB(A-weighted).
2. 30.01 to 50.00 kVA: 45 dB(A-weighted) for K-factors of 1, 4, and 9.
3. 50.01 to 150.00 kVA: 50 dB(A-weighted) for K-factors of 1, 4, and 9.

2.4 IDENTIFICATION

A. Nameplates:

1. Engraved, laminated-acrylic or melamine plastic signs for distribution transformers, mounted with corrosion-resistant screws. Nameplates and label products are specified in Section 260553 "Identification for Electrical Systems."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine conditions for compliance with enclosure- and ambient-temperature requirements for transformers.

B. Verify that field measurements are as needed to maintain working clearances required by NFPA 70 and manufacturer's published instructions.

C. Examine walls, floors, roofs, and concrete bases for suitable mounting conditions where transformers will be installed.

D. Verify that ground connections are in place and requirements in Section 260526 "Grounding and Bonding for Electrical Systems" have been met. Maximum ground resistance must be 5 Ω at location of transformer.

E. Environment: Enclosures must be rated for environment in which they are located.

F. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install wall-mounted transformers level and plumb with wall brackets fabricated by transformer manufacturer.

1. Coordinate installation of wall-mounted and structure-hanging supports with actual transformer provided.

B. Anchor floor-mounted transformers in accordance with manufacturer's published instructions, seismic requirements applicable to Project, and requirements in Section 260529 "Hangers and Supports for Electrical Systems."

C. Secure transformer to concrete base in accordance with manufacturer's published instructions.

D. Secure covers to enclosure and tighten bolts to manufacturer-recommended torques to reduce noise generation.

E. Remove shipping bolts, blocking, and wedges.

3.3 CONNECTIONS

A. Ground equipment in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

B. Connect wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

C. Tighten electrical connectors and terminals in accordance with manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.

D. Provide flexible connections at conduit and conductor terminations and supports to eliminate sound and vibration transmission to building structure.

3.4 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. Small (Up to 167 kVA Single-Phase or 500 kVA Three-Phase) Dry-Type Transformer Field Tests:

a. Visual and Mechanical Inspection.

1) Inspect physical and mechanical condition.
2) Inspect anchorage, alignment, and grounding.
3) Verify that resilient mounts are free and that shipping brackets have been removed.
4) Verify that unit is clean.
5) Perform specific inspections and mechanical tests recommended by manufacturer.
6) Verify that as-left tap connections are as specified.
7) Verify presence of surge arresters and that their ratings are as specified.

b. Electrical Tests:

1) Measure resistance at windings, taps, and bolted connections.
2) Perform insulation-resistance tests winding-to-winding and windings-to-ground. Apply voltage in accordance with manufacturer's published data. In absence of manufacturer's published data, comply with NETA ATS, Table 100.5. Calculate polarization index: value of index may not be less than 1.0.
3) Perform turns-ratio tests at tap positions. Test results may not deviate by more than one-half percent from either adjacent coils or calculated ratio. If test fails, replace transformer.
4) Verify correct secondary voltage, phase-to-phase and phase-to-neutral, after energization and prior to loading.

B. Test Labeling: On completion of satisfactory testing of units, attach dated and signed "Satisfactory Test" label to tested components.

C. Nonconforming Work:

1. Transformer will be considered defective if it does not pass tests and inspections.
2. Remove and replace units that do not pass tests or inspections and retest as specified above.

D. Assemble and submit test and inspection reports.

3.5 ADJUSTING

A. Record transformer secondary voltage at unit for at least 48 hours of typical occupancy period. Adjust transformer taps to provide optimum voltage conditions at secondary terminals. Optimum is defined as not exceeding nameplate voltage plus 5 percent and not being lower than nameplate voltage minus 3 percent at maximum load conditions. Submit recording and tap settings as test results.

B. Output Settings Report: Prepare written report recording output voltages and tap settings.

3.6 CLEANING

A. Vacuum dirt and debris; do not use compressed air to assist in cleaning.

END OF SECTION

SECTION 262413 - SWITCHBOARDS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Switchboards.
2. Disconnecting and overcurrent protective devices.
3. Accessory components and features.

B. Related Requirements

1. Section 260010 "Supplemental Requirements for Electrical" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.

1.2 COORDINATION

A. Coordinate layout and installation of switchboards and components with other construction that penetrates walls or is supported by them, including electrical and other types of equipment, raceways, piping, encumbrances to workspace clearance requirements, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

B. Coordinate sizes and locations of concrete bases with actual equipment provided.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Switchboards.
2. Overcurrent protective devices.
3. Surge protection devices.
4. Ground-fault protection devices.
5. Accessories.
6. Other components.
7. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings, accessories, and finishes.

C. Shop Drawings: For each switchboard and related equipment.

1. Include dimensioned plans, elevations, sections, and details, including required clearances and service space around equipment. Show tabulations of installed devices, equipment features, and ratings.
2. Detail enclosure types for types other than UL 50E, Type 1.
3. Detail bus configuration, current, and voltage ratings.
4. Detail short-circuit current rating of switchboards and overcurrent protective devices.
5. Include descriptive documentation of optional barriers specified for electrical insulation and isolation.
6. Detail utility company's metering provisions with indication of approval by utility company.
7. Include evidence of listing, by qualified electrical testing laboratory recognized by authorities having jurisdiction, for series rating of installed devices.
8. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
9. Include time-current coordination curves for each type and rating of overcurrent protective device included in switchboards. Submit on translucent log-log graft paper; include selectable ranges for each type of overcurrent protective device.
10. Include diagram and details of proposed mimic bus.
11. Include schematic and wiring diagrams for power, signal, and control wiring.

D. Field Quality-Control Submittals:

1. Field Quality-Control Reports:

a. Test procedures used.
b. Test results that comply with requirements.
c. Results of failed tests and corrective action taken to achieve test results that comply with requirements.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturers' Published Instructions: Record copy of official installation and testing instructions issued to Installer by manufacturer for the following:

1. Handling, storing, and providing temporary heat.
2. Mounting accessories and anchoring devices.
3. Testing and adjusting overcurrent protective devices.

C. Sample warranties.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Warranty documentation.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver switchboards in sections or lengths that can be moved past obstructions in delivery path.

B. Remove loose packing and flammable materials from inside switchboards and install temporary electric heating (250 W per section) to prevent condensation.

C. Handle and prepare switchboards for installation in accordance with NECA 400.

1.7 WARRANTY

A. Special Manufacturer Extended Warranty: Manufacturer warrants that switchboard performs in accordance with specified requirements and agrees to provide repair or replacement of components that fail to perform as specified within extended-warranty period.

1. Initial Extended-Warranty Period: Three years from date of Substantial Completion; full coverage for labor, materials, and equipment.

PART 2 - PRODUCTS

2.1 SWITCHBOARDS

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Square D; Schneider Electric USA.

B. Source Limitations: Obtain switchboards, overcurrent protective devices, components, and accessories from single source from single manufacturer.

C. Product Selection: Drawings indicate dimensions of electrical space where equipment must be installed. Adjust switchboard arrangement to fit within available space and as required based on coordination drawings.

D. Electrical Components, Devices, and Accessories: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

E. Comply with NEMA PB 2.

F. Comply with NFPA 70.

G. Comply with UL 891.

H. Front-Connected, Front-Accessible Switchboards:

1. Main Devices: Fixed, individually mounted.
2. Branch Devices: Panel mounted.
3. Sections front and rear aligned.

I. Nominal System Voltage: 480Y/277 V.

J. Main-Bus Continuous: As indicated.

K. Indoor Enclosures: Steel, UL 50E, Type 1.

L. Enclosure Finish for Indoor Units: Factory-applied finish in manufacturer's standard gray finish over rust-inhibiting primer on treated metal surface.

M. Barriers: Between adjacent switchboard sections.

N. Insulation and isolation for main bus of main section and main and vertical buses of feeder sections.

O. Service Entrance Rating: Switchboards intended for use as service entrance equipment may contain from one to six service disconnecting means with overcurrent protection, neutral bus with disconnecting link, grounding electrode conductor terminal, and main bonding jumper.

P. Bus Transition and Incoming Pull Sections: Matched and aligned with basic switchboard.

Q. Removable, Hinged Rear Doors and Compartment Covers: Secured by standard bolts, for access to rear interior of switchboard.

R. Hinged Front Panels: Allow access to circuit breaker, metering, accessory, and blank compartments.

S. Pull Box on Top and Sides of Switchboard:

1. Adequate ventilation to maintain temperature in pull box within same limits as switchboard.
2. Set back from front to clear circuit-breaker removal mechanism.
3. Removable covers may form top, front, and sides. Top covers at rear must be easily removable for drilling and cutting.
4. Bottom must be insulating, fire-resistive material with separate holes for cable drops into switchboard.
5. Cable supports must be arranged to facilitate cabling and adequate to support cables indicated, including those for future installation.

T. Buses and Connections: Three phase, four wire unless otherwise indicated.

1. Provide phase bus arrangement A, B, C from front to back, top to bottom, and left to right when viewed from front of switchboard.
2. Phase- and Neutral-Bus Material:

    a. Hard-drawn copper of 98 percent conductivity.

3. Tin-plated aluminum feeder circuit-breaker line connections.
4. Load Terminals: Insulated, rigidly braced, runback bus extensions, of same material as through buses, equipped with compression connectors for outgoing circuit conductors. Provide load terminals for future circuit-breaker positions at full-ampere rating of circuit-breaker position.

5. Ground Bus: Minimum-size required by UL 891, hard-drawn copper of 98 percent conductivity, equipped with compression connectors for feeder and branch-circuit ground conductors.
6. Disconnect Links:

    a. Isolate neutral bus from incoming neutral conductors.
    b. Bond neutral bus to equipment-ground bus for switchboards utilized as service equipment or separately derived systems.

7. Neutral Buses: 100 percent of ampacity of phase buses unless otherwise indicated, equipped with compression connectors for outgoing circuit neutral cables. Brace bus extensions for busway feeder neutral bus.
8. Isolation Barrier Access Provisions: Permit checking of bus-bolt tightness.

U. Future Devices: Equip compartments with mounting brackets, supports, bus connections, and appurtenances at full rating of circuit-breaker compartment.

V. Bus-Bar Insulation: Factory-applied, flame-retardant, tape wrapping of individual bus bars or flame-retardant, spray-applied insulation. Minimum insulation temperature rating of 105 deg C.

2.2 DISCONNECTING AND OVERCURRENT PROTECTIVE DEVICES

A. Molded-Case Circuit Breaker (MCCB): Comply with UL 489, with interrupting capacity to meet available fault currents.

1. Thermal-Magnetic Circuit Breakers: Inverse time-current element for low-level overloads and instantaneous magnetic trip element for short circuits. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
2. Adjustable Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
3. GFCI Circuit Breakers: Single- and double-pole configurations with Class A ground-fault protection (6 mA trip).
4. Ground-Fault Equipment Protection (GFEP) Circuit Breakers: Class B ground-fault protection (30 mA trip).
5. MCCB Features and Accessories:

    a. Standard frame sizes, trip ratings, and number of poles.
    b. Lugs: Compression style, suitable for number, size, trip ratings, and conductor material.
    c. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and high-intensity discharge (HID) lighting circuits.
    d. Ground-Fault Protection: Integrally mounted relay and trip unit with adjustable pickup and time-delay settings, push-to-test feature, and ground-fault indicator.
    e. Zone-Selective Interlocking: Integral with electronic trip unit; for interlocking ground-fault protection function.
    f. Undervoltage Trip: Set to operate at 35 to 75 percent of rated voltage without intentional time delay.
    g. Auxiliary Contacts: One SPDT switch with "a" and "b" contacts; "a" contacts mimic circuit-breaker contacts, "b" contacts operate in reverse of circuit-breaker contacts.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Receive, inspect, handle, and store switchboards in accordance with NECA 400.

1. Lift or move panelboards with spreader bars and manufacturer-supplied lifting straps following manufacturer's published instructions.
2. Use rollers, slings, or other manufacturer-approved methods if lifting straps are not furnished.
3. Protect from moisture, dust, dirt, and debris during storage and installation.
4. Install temporary heating during storage in accordance with manufacturer's published instructions.

B. Examine switchboards before installation. Reject switchboards that are moisture damaged or physically damaged.

C. Examine elements and surfaces to receive switchboards for compliance with installation tolerances and other conditions affecting performance of the Work or that affect performance of equipment.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Installation Pathway: Remove and replace access fencing, doors, lift-out panels, and structures to provide pathway for moving switchboards into place.

3.3 INSTALLATION

A. Comply with manufacturer's published instructions.

B. Reference Standards:

1. Switchboards and Accessories: Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with NECA 400.
2. Consult Architect for resolution of conflicting requirements.

C. Special Techniques:

1. Equipment Mounting: Install switchboards on concrete.

a. Install conduits entering underneath switchboard, entering under vertical section where conductors will terminate. Install with couplings flush with concrete base. Extend 2 inch above concrete base after switchboard is anchored in place.
b. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete floor.
c. Place and secure anchorage devices. Use setting drawings, templates, diagrams, published instructions, and directions furnished with items to be embedded.

d. Install anchor bolts to elevations required for proper attachment to switchboards.
e. Anchor switchboard to building structure at top of switchboard if required or recommended by manufacturer.

2. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, straps and brackets, and temporary blocking of moving parts from switchboard units and components.
3. Operating Instructions: Frame and mount printed basic operating instructions for switchboards, including control and key interlocking sequences and emergency procedures. Fabricate frame of finished wood or metal and cover instructions with clear acrylic plastic. Mount on front of switchboards.
4. Install filler plates in unused spaces of panel-mounted sections.
5. Install overcurrent protective devices, surge protection devices, and instrumentation.

a. Set field-adjustable switches and circuit-breaker trip ranges.

3.4 CONNECTIONS

A. Bond conduits entering underneath switchboard to equipment ground bus with bonding conductor sized in accordance with NFPA 70.

B. Support and secure conductors within switchboard in accordance with NFPA 70.

C. Extend insulated equipment grounding cable to busway ground connection and support cable at intervals in vertical run.

3.5 IDENTIFICATION

A. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

B. Switchboard Nameplates: Label each switchboard compartment with nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

C. Device Nameplates: Label each disconnecting and overcurrent protective device and each meter and control device mounted in compartment doors with nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

D. Service Equipment Label: Labeled, by qualified electrical testing laboratory recognized by authorities having jurisdiction, for use as service equipment for switchboards with one or more service disconnecting and overcurrent protective devices.

3.6 FIELD QUALITY CONTROL

A. Testing Preparation:

B. Tests and Inspections:

1. Acceptance Testing:

    a. Test insulation resistance for each switchboard bus, component, connecting supply, feeder, and control circuit. Open control and metering circuits within switchboard, and remove neutral connection to surge protection and other electronic devices prior to insulation test. Reconnect after test.
    b. Test continuity of each circuit.

2. Test ground-fault protection of equipment for service equipment in accordance with NFPA 70.
3. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
4. Correct malfunctioning units on-site where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
5. Perform the following infrared scan tests and inspections, and prepare reports:

    a. Initial Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform infrared scan of each switchboard. Remove front panels so joints and connections are accessible to portable scanner.
    b. Follow-up Infrared Scanning: Perform additional follow-up infrared scan of each switchboard 11 months after date of Substantial Completion.
    c. Instruments and Equipment:

        1) Use infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.

6. Test and adjust controls, remote monitoring, and safeties. Replace damaged and malfunctioning controls and equipment.

C. Nonconforming Work:

1. Switchboard will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

D. Collect, assemble, and submit test and inspection reports, including certified report that identifies switchboards included and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

E. Manufacturer Services:

1. Engage factory-authorized service representative to perform field tests and inspections.

3.7 ADJUSTING

A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.

3.8 PROTECTION

A. Temporary Heating: Apply temporary heat, to maintain temperature in accordance with manufacturer's published instructions, until switchboard is ready to be energized and placed into service.

END OF SECTION

SECTION 262416 - PANELBOARDS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Panelboards.
2. Disconnecting and overcurrent protective devices.

B. Related Requirements:

1. Section 018116 "Facility Environmental Requirements" specifies temperature, humidity, acoustical, and other field conditions applicable to the Work specified in this Section.
2. Section 260010 "Supplemental Requirements for Electrical" specifies additional abbreviations, definitions, submittals, qualifications, testing agencies, and other requirements applicable to the Work for electrical, communications, and electronic safety and security systems on Project, including wiring methods.
3. Section 260529 "Hangers and Supports for Electrical Systems" specifies concrete bases and supports for panelboards installed by this Section.
4. Section 260553 "Identification for Electrical Systems" specifies electrical equipment labels and warning signs installed by this Section.
5. Section 260573 "Power System Studies" specifies short-circuit current studies, overcurrent protective device coordination studies, and arc-flash hazard analysis studies.
6. Section 264313 "Surge Protective Devices for Low-Voltage Electrical Power Circuits" specifies Type 1 and Type 2 surge protective devices installed by this Section.

1.2 DEFINITIONS

A. MCCB: Molded-case circuit breaker.

B. VPR: Voltage protection rating.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. In addition to information identified in Section 013300 "Submittal Procedures," submit the following:

1. Product Listing: Include copy of unexpired approval letter, on letterhead of qualified electrical testing agency, certifying product's compliance with specified listing criteria.
2. Include manufacturer's sample extended warranty language.

C. Shop Drawings: For each panelboard and related equipment:

1. Include dimensioned plans, elevations, sections, and details.
2. Show tabulations of installed devices with nameplates, conductor termination sizes, equipment features, and ratings.
3. Detail enclosure types including mounting and anchorage, environmental protection, knockouts, corner treatments, covers and doors, gaskets, hinges, and locks.
4. Detail bus configuration, current, and voltage ratings.
5. Short-circuit current rating of panelboards and overcurrent protective devices.
6. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
7. Include wiring diagrams for power, signal, and control wiring.
8. Key interlock scheme drawing and sequence of operations.

D. Field quality-control reports.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Panelboard Schedules: For installation in panelboards. Submit final versions after load balancing.

C. Manufacturer's published instructions.

D. Field Reports:

1. Manufacturer's field reports for field quality-control support.
2. Field reports for voltage monitoring and adjusting.
3. Field reports for infrared scanning.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Warranty documentation.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Remove loose packing and flammable materials from inside panelboards; install temporary electric heating (250 W per panelboard) to prevent condensation.

B. Handle and prepare panelboards for installation in accordance with NEMA PB 1.

1.7 WARRANTY

A. Special Installer Extended Warranty: Installer warrants that fabricated and installed panelboards perform in accordance with specified requirements and agrees to repair or replace components or products that fail to perform as specified within extended-warranty period.

1. Extended-Warranty Period: Two years from date of Substantial Completion; full coverage for labor, materials, and equipment.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Products or components listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

B. Product Selection: Drawings indicate maximum dimensions of electrical space where equipment is must be installed.

C. Comply with NEMA PB 1.

D. Enclosures: Flush and Surface-mounted, dead-front cabinets.

1. Rated for environmental conditions at installed location.

a. Indoor Dry and Clean Locations: UL 50E, Type 1.

2. Height: 7 ft maximum.
3. Front: Secured to box with concealed trim clamps. For surface-mounted fronts, match box dimensions; for flush-mounted fronts, overlap box. Trims must cover live parts and may have no exposed hardware.
4. Hinged Front Cover: Entire front trim hinged to box and with standard door within hinged trim cover. Trims must cover live parts and may have no exposed hardware.
5. Skirt for Surface-Mounted Panelboards: Same gage and finish as panelboard front with flanges for attachment to panelboard, wall, and ceiling or floor.
6. Gutter Extension and Barrier: Same gage and finish as panelboard enclosure; integral with enclosure body. Arrange to isolate individual panel sections.
7. Finishes:

a. Panels and Trim: Steel and galvanized steel, factory finished immediately after cleaning and pretreating with manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat.
b. Back Boxes: Same finish as panels and trim.

E. Phase, Neutral, and Ground Buses:

1. Material: Tin-plated aluminum.

a. Plating must run entire length of bus.
b. Bus must be fully rated for entire length.

2. Interiors must be factory assembled into unit. Replacing switching and protective devices may not disturb adjacent units or require removing main bus connectors.
3. Equipment Ground Bus: Adequate for feeder and branch-circuit equipment grounding conductors; bonded to box.

F. Conductor Connectors: Suitable for use with conductor material and sizes.

1. Material: Tin-plated aluminum.
2. Terminations must allow use of 75 deg C rated conductors without derating.
3. Size: Lugs suitable for indicated conductor sizes, with additional gutter space, if required, for larger conductors.
4. Main and Neutral Lugs: Mechanical type, with lug on neutral bar for each pole in panelboard.
5. Ground Lugs and Bus-Configured Terminators: Mechanical type, with lug on bar for each pole in panelboard.

G. Quality-Control Label: Panelboards or load centers must be labeled, by qualified electrical testing laboratory recognized by authorities having jurisdiction, for use as service equipment with one or more main service disconnecting and overcurrent protective devices. Panelboards or load centers must have meter enclosures, wiring, connections, and other provisions for utility metering. Coordinate with utility company for exact requirements.

H. Future Devices: Panelboards or load centers must have mounting brackets, bus connections, filler plates, and necessary appurtenances required for future installation of devices.

1. Percentage of Future Space Capacity: 20 percent.

I. Panelboard Short-Circuit Current Rating:

1. Fully rated to interrupt symmetrical short-circuit current available at terminals. Assembly listed, by qualified electrical testing laboratory recognized by authorities having jurisdiction, for 100 percent interrupting capacity.

a. Panelboards and overcurrent protective devices rated 240 V or less must have short-circuit ratings as shown on Drawings, but not less than 10 000 A(rms) symmetrical.
b. Panelboards and overcurrent protective devices rated above 240 V and less than 600 V must have short-circuit ratings as shown on Drawings, but not less than 14 000 A(rms) symmetrical.

2.2 PANELBOARDS

A. Panelboards:

1. Manufacturers: Subject to compliance with requirements, provide products by the following:

a. Square D; Schneider Electric USA.

2. Source Limitations: Obtain products from single manufacturer. Distribution panelboards must be Square D I-Line. Branch circuit panelboards must be NQOD.

3. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

    a. Distribution, and Lighting and Appliance Branch-Circuit Type Panelboards: UL CCN QEUY; including UL 67 and NEMA PB 1.

4. Standard Features:

    a. Doors: Secured with vault-type latch with tumbler lock; keyed alike.

        1) For doors more than 36 inch high, provide two latches, keyed alike.

    b. Mains: As indicated.

        1) Location: Convertible between top and bottom.
        2) Main Breaker: Main lug interiors up to 400 A must be field convertible to main breaker.

    c. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes 125 A and Smaller: Bolt-on circuit breakers.
    d. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes Larger Than 125 A: Bolt-on circuit breakers.
    e. Branch Overcurrent Protective Devices: Fused switches.

5. Other Available Features Required by Project:
    a. Full-Sized Neutral: Equipped with full-capacity bonding strap for service entrance applications. Mount electrically isolated from enclosure.
    b. Extra-Capacity Neutral Bus: Neutral bus rated 200 percent of phase bus and listed and labeled, by qualified electrical testing laboratory recognized by authorities having jurisdiction, as suitable for nonlinear loads in electronic-grade panelboards and others designated on Drawings. Connectors must be sized for double-sized or parallel conductors as indicated on Drawings.
    c. Do not mount neutral bus in gutter.
    d. Feed-Through Lugs: Mechanical type, suitable for use with conductor material. Locate at opposite end of bus from incoming lugs or main device.
    e. Subfeed (Double) Lugs: Mechanical type suitable for use with conductor material. Locate at same end of bus as incoming lugs or main device.
    f. Extra-Capacity Neutral Lugs: Rated 200 percent of phase lugs mounted on extra-capacity neutral bus.
    g. Split Bus: Vertical buses divided into individual vertical sections.

2.3 DISCONNECTING AND OVERCURRENT PROTECTIVE DEVICES

A. Manufacturers: Subject to compliance with requirements, product products by the following:

    1. Square D; Schneider Electric USA.

B. MCCB: Comply with UL 489, with interrupting capacity to meet available fault currents. Type NQOD for power and lighting panelboards.

1. Thermal-Magnetic Circuit Breakers:

    a. Inverse time-current element for low-level overloads.
    b. Instantaneous magnetic trip element for short circuits.
    c. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.

2. Adjustable Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
3. Current-Limiting Circuit Breakers: Frame sizes 400 A and smaller; let-through ratings less than NEMA FU 1, RK-5.
4. GFCI Circuit Breakers: Single- and double-pole configurations with Class A ground-fault protection (6 mA trip).
5. GFPE Circuit Breakers: Class B ground-fault protection (30 mA trip).
6. Arc-Fault Circuit Interrupter Circuit Breakers: Comply with UL 1699; 120/240 V, single-pole configuration.
7. Subfeed Circuit Breakers: Vertically mounted.
8. MCCB Features and Accessories:

    a. Standard frame sizes, trip ratings, and number of poles.
    b. Breaker handle indicates tripped status.
    c. UL listed for reverse connection without restrictive line or load ratings.
    d. Lugs: Mechanical style, suitable for number, size, trip ratings, and conductor materials.
    e. Ground-Fault Protection: Remote-mounted relay and trip unit with adjustable pickup and time-delay settings, push-to-test feature, and ground-fault indicator.
    f. Shunt Trip: 120 V trip coil energized from separate circuit, set to trip at 75 percent of rated voltage.
    g. Handle Padlocking Device: Fixed attachment, for locking circuit-breaker handle in on or off position.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify actual conditions with field measurements prior to ordering panelboards to verify that equipment fits in allocated space in, and comply with, minimum required clearances specified in NFPA 70.

B. Receive, inspect, handle, and store panelboards in accordance with NEMA PB 1.1.

C. Examine panelboards before installation. Reject panelboards that are damaged, rusted, or have been subjected to water saturation.

D. Examine elements and surfaces to receive panelboards for compliance with installation tolerances and other conditions affecting performance of the Work.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Comply with manufacturer's published instructions.

B. Reference Standards:

1. Panelboards: Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with NEMA PB 1.1.
2. Consult Architect for resolution of conflicting requirements.

C. Special Techniques:

1. Equipment Mounting:

   a. Attach panelboard to vertical finished or structural surface behind panelboard.
   b. Mount surface-mounted panelboards to steel slotted supports 5/8 inch in depth. Orient steel slotted supports vertically.
   c. Provide seismic control devices.

2. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from panelboards.
3. Provide mounting and anchoring devices.
4. Mount top of trim 7.5 ft above finished floor unless otherwise indicated.
5. Mount panelboard cabinet plumb and rigid without distortion of box.
6. Mount recessed panelboards with fronts uniformly flush with wall finish and mating with back box.
7. Install overcurrent protective devices and controllers not already factory installed.

   a. Set field-adjustable, circuit-breaker trip ranges.
   b. Tighten bolted connections and circuit breaker connections using calibrated torque wrench or torque screwdriver in accordance with manufacturer's published instructions.

8. Make grounding connections and bond neutral for services and separately derived systems to ground. Make connections to grounding electrodes, separate grounds for isolated ground bars, and connections to separate ground bars.
9. Install filler plates in unused spaces.
10. Arrange conductors in gutters into groups and bundle and wrap with wire ties.

D. Interfaces with Other Work:

1. Coordinate layout and installation of panelboards and components with other construction that penetrates walls or is supported by them, including electrical and other types of equipment, raceways, piping, encumbrances to workspace clearance requirements, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

3.3 IDENTIFICATION

A. Identify field-installed conductors, interconnecting wiring, and components.

B. Install warning signs.

C. Panelboard Nameplates: Label each panelboard with nameplate.

D. Device Nameplates: Label each branch circuit device in power panelboards with nameplate.

E. Panelboard Label: Manufacturer's name and trademark, voltage, amperage, number of phases, and number of poles must be located on interior of panelboard door.

F. Breaker Labels: Faceplate must list current rating, UL and IEC certification standards, and AIC rating.

G. Circuit Directory:

1. Provide directory card inside panelboard door, mounted in transparent card holder.

    a. Circuit directory must identify specific purpose with detail sufficient to distinguish it from other circuits.

2. Provide computer-generated circuit directory mounted inside panelboard door with transparent plastic protective cover.

    a. Circuit directory must identify specific purpose with detail sufficient to distinguish it from other circuits.

3. Create directory to indicate installed circuit loads; incorporate Owner's final room designations. Obtain approval before installing. Handwritten directories are not acceptable. Install directory inside panelboard door.

3.4 FIELD QUALITY CONTROL

A. Administrant for Low-Voltage Electrical Tests and Inspections:

1. Administer and perform tests and inspections.

B. Acceptance Testing Preparation:

1. Test insulation resistance for each panelboard bus, component, connecting supply, feeder, and control circuit.
2. Test continuity of each circuit.

C. Tests and Inspections:

1. Perform each visual and mechanical inspection and electrical test for low-voltage air circuit breakers stated in NETA ATS, Paragraph 7.6 Circuit Breakers. Certify compliance with test parameters.
2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.

D. Nonconforming Work:

1. Panelboards will be considered defective if they do not pass tests and inspections.
2. Remove and replace defective units and retest.

E. Field Quality-Control Reports: Collect, assemble, and submit test and inspection reports.

1. Include certified report that identifies panelboards included and that describes scanning results, with comparisons of two scans. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.5 ADJUSTING

A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.

B. Set field-adjustable circuit-breaker trip ranges.

3.6 PROTECTION

A. Temporary Heating: Prior to energizing panelboards, apply temporary heat to maintain temperature in accordance with manufacturer's published instructions.

END OF SECTION

SECTION 262713 - ELECTRICITY METERING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Electricity meters.
2. Work to accommodate utility company revenue meters, and Designer's electricity meters used to manage electrical power system.

1.2 DEFINITIONS

A. KY or KYZ Pulse: Term used by metering industry to describe method of measuring consumption of electricity (kWh) that is based on relay opening and closing in response to rotation of disk in meter. Electronic meters generate pulses electronically.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of meter.
2. For metering infrastructure components.
3. For metering software.

C. Shop Drawings: For electricity-metering equipment.

1. Include elevation views of front panels of control and indicating devices and control stations.
2. Include diagrams for power, signal, and control wiring.
3. Wire Termination Diagrams and Schedules: Include diagrams for power, signal, and control wiring. Identify terminals and wiring designations and color-codes to facilitate installation, operation, and maintenance. Indicate recommended types, wire sizes, and circuiting arrangements for field-installed wiring, and show circuit protection features. Differentiate between manufacturer-installed and field-installed wiring.
4. Include series-combination rating data for modular meter centers with main disconnect device.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturers' Published Instructions: Record copy of official installation instructions issued to Installer by manufacturer for the following:

1. Installation of metering equipment.

C. Sample warranties.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Contracts:

1. Software and firmware service agreement.

C. Warranty documentation.

1.6 WARRANTY

A. Special Installer Extended Warranty: Installer warrants that fabricated and installed metering equipment performs in accordance with specified requirements and agrees to repair or replace components or products that fail to perform as specified within extended-warranty period.

1. Extended-Warranty Period: Two years from date of Substantial Completion; full coverage for labor, materials, and equipment.

B. Special Manufacturer Extended Warranty: Manufacturer warrants that metering equipment performs in accordance with specified requirements and agrees to provide repair or replacement of components or products that fail to perform as specified within extended-warranty period.

1. Initial Extended-Warranty Period: Three years from date of Substantial Completion; full coverage for labor, materials, and equipment.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Electrical Components, Devices, and Accessories: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

B. Comply with UL 916.

2.2 ELECTRICITY METERS

A. System Description: Able to meter designated activity loads, with or without external alarm, control, and communication capabilities, or other optional features.

B. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Square D; Schneider Electric USA.

C. General Requirements for Meters:

1. ION 6200 PowerLogic.
2. Comply with NEMA ANSI C12.1 and NEMA ANSI C12.20, 0.5 accuracy class.
3. Ambient Temperature: Minus 22 deg F to plus 158 deg F.
4. Humidity: Zero to 95 percent, noncondensing.
5. Capacities and Characteristics:

a. Circuit: 480/277V and 120/208V.
b. Measure: kWh, onboard LED display.
c. Remote-Reading Options: As indicated.

6. Certify that meters comply with NEMA ANSI C12.20 requirements by laboratory accredited by the National Voluntary Laboratory Accreditation Program (NVLAP) of the National Institute of Standards and Technology (NIST). Laboratory must use test equipment that is certified annually and is traceable to NIST standards.
7. Enclosure: Supplied by meter manufacturer, UL 50E, Type 1 minimum, with provisions for locking or sealing.
8. Identification: Comply with requirements in Section 260553 "Identification for Electrical Systems."
9. Onboard Nonvolatile Data Storage: kWh, until reset.
10. Sensors: Current-sensing type, supplied by electronic meter manufacturer, with current or voltage output, selected for optimum range and accuracy for meters indicated for this application.

a. Type: solid core, complying with recommendation of meter manufacturer.

D. kWhd Meter: Electronic single-phase meters, measuring electricity use and demand. Demand must be integrated over 15-minute interval.

1. Voltage and Phase Configuration: Meter must be designed for use on circuits with voltage rating and phase configuration indicated for its application.
2. Display: LCD with characters not less than 0.25 inch high, indicating the following:

a. Accumulative kWh.
b. Current time and date.
c. Current demand.
d. Historic peak demand.
e. Time and date of historic peak demand.

3. Retain accumulated kWh and historic peak demand in nonvolatile memory, for 36 months.

E. KY and KYZ Pulse Totalizer:

1. Pulse Totalizer: Instrument for demand and billing applications where one or more utility revenue meters stream KY or KYZ energy pulses. Instrument must totalize kWh accumulated over user-selected period and must log maximum and minimum kWhd for that period. Record each period with date/time stamp. Time period must be user selected from one to 60 minutes.

a. Pulse Input: One, individually programmable, KYZ Form C (three-wire) contact pulse channels. Pulse interval, pulse rate, and minimum pulse width must be field adjustable, set for pulse stream provided by utility revenue meter.
b. Data Totalizing Capacity of Each Channel: Not less than 149 days at 15-minute intervals.
c. Instrument Power: User selectable, 120 V(ac).
d. Clock: Line frequency.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Comply with manufacturer's published instructions.

B. Reference Standards:

1. Install arc-flash labels as required by NFPA 70.

C. Special Techniques:

1. Wiring Methods:

a. Comply with requirements in Section 260533.16 “Boxes and Covers for Electrical Systems.”
b. Minimum conduit size is 3/4 inch.

3.2 IDENTIFICATION

A. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

1. Series Combination Warning Label: Self-adhesive labels, with text as required by NFPA 70.
2. Equipment Identification Labels: Self-adhesive labels with clear protective overlay. For residential meters, provide additional card holder suitable for printed, weather-resistant card with occupant's name.

3.3 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. Coordinate with the Schneider representative to program and set up meters in accordance with the Government requirements and specifications.
2. Equipment and Software Setup:

    a. Set meter date and time clock.
    b. Test, calibrate, and connect pulse metering system.
    c. Set and verify billing demand interval for demand meters.
    d. Report settings and calibration results.
    e. Set up reporting and billing software, insert billing location names and initial constant values and variable needed for billing computations.

3. Connect load of known power rating, 1.5 kW minimum, to circuit supplied by metered feeder.
4. Turn off circuits supplied by metered feeder and secure them in off condition.
5. Run test load continuously for eight hours minimum, or longer, to obtain measurable meter indication. Use test-load placement and setting that ensures continuous, safe operation.
6. Check and record meter reading at end of test period and compare with actual electricity used, based on test-load rating, duration of test, and sample measurements of supply voltage at test-load connection. Record test results.
7. Generate test report and billing for each tenant or activity from meter reading tests.

B. Nonconforming Work:

1. Electricity metering will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

C. Collect, assemble, and submit test and inspection reports.

3.4 PROTECTION

A. After installation, protect metering equipment from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Designer.

END OF SECTION

SECTION 262726 - WIRING DEVICES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. General-use switches.
2. General-grade single straight-blade receptacles.
3. Receptacles with ground-fault protective devices.
4. Locking receptacles.

B. Related Requirements:

1. Section 260923 "Lighting Control Devices" for occupancy sensors, timers, control-voltage switches, and control-voltage dimmers.

1.2 ALLOWANCES

A. See Section 012100 "Allowances" for description of allowances affecting items specified in this Section.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Product Data:

1. General-use switches.
2. General-grade single straight-blade receptacles.
3. Receptacles with ground-fault protective devices.
4. Connectors, cords, and plugs.

C. Field quality-control reports.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 010000 "Administrative Provisions" and the individual sections specifying the work.

B. Manufacturers' Instructions: Record copy of official installation instructions issued to Installer by manufacturer for the following:

1. Single straight-blade receptacles.
2. Receptacles with GFCI device.

PART 2 - PRODUCTS

2.1 GENERAL-USE SWITCHES

A. Toggle Switch:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Arrow Hart, Wiring Devices; Eaton, Electrical Sector.
    b. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
    c. Leviton Manufacturing Co., Inc.
    d. Pass & Seymour; Legrand North America, LLC.

2. Regulatory Requirements:

    a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

3. General Characteristics:

    a. Reference Standards: UL CCN WMUZ and UL 20.

4. Options:

    a. Device Color: As selected by Architect.
    b. Configuration:

        1) General-duty, 120-277 V, 20 A, single pole.

5. Accessories:

    a. Cover Plate: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device; from same manufacturer as wiring device.
    b. Securing Screws for Cover Plate: Metal with head color matching wallplate finish.

2.2 GENERAL-GRADE DUPLEX STRAIGHT-BLADE RECEPTACLES

A. Duplex Straight-Blade Receptacle:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Arrow Hart, Wiring Devices; Eaton, Electrical Sector.
    b. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated.

c. Leviton Manufacturing Co., Inc.
d. Pass & Seymour; Legrand North America, LLC.

2. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

3. General Characteristics:

a. Reference Standards: UL CCN RTRT and UL 498.

4. Options:

a. Device Color: As selected by Architect. Identify receptacles on the Critical Operations Power System per Government direction and NFPA 70, Article 708.
b. Configuration:

1) General-duty, NEMA 5-20R.

5. Accessories:

a. Cover Plate: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device; from same manufacturer as wiring device.
b. Securing Screws for Cover Plate: Metal with head color matching wallplate finish.

B. Wired Half-Controlled Duplex Straight-Blade Receptacle:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Hubbell Lighting; brand of Hubbell Electrical Solutions; Hubbell Incorporated
b. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated
c. Pass & Seymour; Legrand North America, LLC

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. Receptacles with Integral Switching Means: UL CCN RTXI and UL Subject 498B.
b. Marked in accordance with NFPA 70.

3. Standard Features:

a. Device Color: As selected by the Architect.
b. Configuration: NEMA 5-20R.

4. Accessories:

a. Cover Plate: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device; from same manufacturer as wiring device.
b. Securing Screws for Cover Plate: Metal with head color matching wallplate finish.

2.3 GROUND-FAULT PROTECTIVE DEVICES

A. General-Grade, Duplex Straight-Blade Receptacle with GFCI Device:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Arrow Hart, Wiring Devices; Eaton, Electrical Sector
b. Leviton Manufacturing Co., Inc.
c. Pass & Seymour; Legrand North America, LLC

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. Outlet Branch-Circuit Type GFCIs: UL CCN KCXX, UL 498 and UL 943.

3. Standard Features:

a. Device Color: As selected by the Architect.
b. Configuration: Heavy-duty, NEMA 5-20R.
c. Non-Feed Through.

4. Accessories:

a. Cover Plate: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device; from same manufacturer as wiring device.
b. Securing Screws for Cover Plate: Metal with head color matching wallplate finish.

B. General-Grade, Weather-Resistant, Tamper-Resistant Duplex Straight-Blade Receptacle with GFCI Device:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Arrow Hart, Wiring Devices; Eaton, Electrical Sector
b. Hubbell Wiring Device-Kellems; brand of Hubbell Electrical Solutions; Hubbell Incorporated
c. Leviton Manufacturing Co., Inc.
d. Pass & Seymour; Legrand North America, LLC

2. Listing Criteria: Investigated, labeled, and marked by qualified electrical testing laboratory in accordance with guide information and standards specified for the following UL product categories:

a. Receptacle GFCIs: UL CCN KCXS, UL 498, and UL 943.

3. Standard Features:

a. Device Color: As selected by the Architect.
b. Configuration: Heavy-duty, NEMA 5-20R.
c. Non-Feed Through.

4. Accessories:

a. Cover Plate: Weatherproof, while-in-use cover.

PART 3 - EXECUTION

3.1 INSTALLATION OF STRAIGHT-BLADE RECEPTACLES

A. Comply with manufacturer's instructions.

B. Reference Standards:

1. Unless more stringent requirements are specified in Contract Documents or manufacturers' instructions, comply with installation instructions in NECA NEIS 130.
2. Mounting Heights: Unless otherwise indicated in Contract Documents, comply with mounting heights recommended in NECA NEIS 1.
3. Receptacle Orientation: Unless otherwise indicated in Contract Documents, orient receptacle to match configuration diagram in NEMA WD 6.
4. Consult Designer for resolution of conflicting requirements.

C. Identification:

1. Identify cover or cover plate for device with panelboard identification and circuit number in accordance with Section 260553 "Identification for Electrical Systems."

a. Mark cover or cover plate using hot, stamped, or engraved machine printing with black-filled lettering, and provide durable wire markers or tags inside device box or outlet box.

D. Interfaces with Other Work:

1. Do not install Type 3 SPD, including surge-protected relocatable taps and power strips, on branch circuit downstream of GFCI device.

3.2 FIELD QUALITY CONTROL OF SWITCHES

A. Nonconforming Work:

1. Unit will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

B. Assemble and submit test and inspection reports.

3.3 FIELD QUALITY CONTROL OF STRAIGHT-BLADE RECEPTACLES

A. Tests and Inspections:

1. Insert and remove test plug to verify that device is securely mounted.
2. Verify polarity of hot and neutral pins.
3. Measure line voltage.
4. Measure percent voltage drop.
5. Measure grounding circuit continuity; impedance must be not greater than 2 ohms.

B. Nonconforming Work:

1. Device will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

C. Assemble and submit test and inspection reports.

3.4 FIELD QUALITY CONTROL OF CONNECTORS, CORDS, AND PLUGS

A. Tests and Inspections:

1. Perform tests and inspections indicated in manufacturer's instructions.

B. Nonconforming Work:

1. Unit will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

C. Assemble and submit test and inspection reports.

3.5 PROTECTION

A. Devices:

1. Schedule and sequence installation to minimize risk of contamination of wires and cables, devices, device boxes, outlet boxes, covers, and cover plates by plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other materials.
2. After installation, protect wires and cables, devices, device boxes, outlet boxes, covers, and cover plates from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Designer.

END OF SECTION

SECTION 262813 – FUSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Cartridge fuses rated 600 V ac and less for use in the following:

a. Control circuits.
b. Enclosed controllers.
c. Enclosed switches.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for spare-fuse cabinets. Include the following for each fuse type indicated:

1. Ambient Temperature Adjustment Information: If ratings of fuses have been adjusted to accommodate ambient temperatures, provide list of fuses with adjusted ratings.

a. For each fuse having adjusted ratings, include location of fuse, original fuse rating, local ambient temperature, and adjusted fuse rating.
b. Provide manufacturer's technical data on which ambient temperature adjustment calculations are based.

2. Dimensions and manufacturer's technical data on features, performance, electrical characteristics, and ratings.
3. Current-limitation curves for fuses with current-limiting characteristics.
4. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse. Submit in electronic format suitable for use in coordination software and in PDF format.
5. Coordination charts and tables and related data.
6. Fuse sizes for elevator feeders and elevator disconnect switches.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For fuses to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017700 "Closeout Procedures," include the following:

1. Ambient temperature adjustment information.
2. Current-limitation curves for fuses with current-limiting characteristics.
3. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse used on the Project. Submit in electronic format suitable for use in coordination software and in PDF format.
4. Coordination charts and tables and related data.

1.5 FIELD CONDITIONS

A. Where ambient temperature to which fuses are directly exposed is less than 40 deg F or more than 100 deg F, apply manufacturer's ambient temperature adjustment factors to fuse ratings.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Bussmann, an Eaton business.
2. Edison; a brand of Bussmann by Eaton.
3. Littelfuse, Inc.
4. Mersen USA.

B. Source Limitations: Obtain fuses, for use within a specific product or circuit, from single source from single manufacturer.

2.2 CARTRIDGE FUSES

A. Characteristics: NEMA FU 1, current-limiting, nonrenewable cartridge fuses with voltage ratings consistent with circuit voltages.

1. Type RK-5: 600-V, zero- to 600-A rating, 200 kAIC, time delay.
2. Type CC: 600-V, zero- to 30-A rating, 200 kAIC, time delay.
3. Type J: 600-V, zero- to 600-A rating, 200 kAIC, time delay.
4. Type L: 600-V, 601- to 6000-A rating, 200 kAIC, time delay.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

C. Comply with NEMA FU 1 for cartridge fuses.

D. Comply with NFPA 70.

E. Coordinate fuse ratings with utilization equipment nameplate limitations of maximum fuse size and with system short-circuit current levels.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine fuses before installation. Reject fuses that are moisture damaged or physically damaged.

B. Examine holders to receive fuses for compliance with installation tolerances and other conditions affecting performance, such as rejection features.

C. Examine utilization equipment nameplates and installation instructions. Install fuses of sizes and with characteristics appropriate for each piece of equipment.

D. Evaluate ambient temperatures to determine if fuse rating adjustment factors must be applied to fuse ratings.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 FUSE APPLICATIONS

A. Cartridge Fuses:

1. Feeders: Class L, time delay, Class RK5, time daly, or Class J, time delay.
2. Motor Branch Circuits: Class RK5, time delay.
3. Large Motor Branch (601-4000 A): Class L, time delay.
4. Other Branch Circuits: Class RK5, time delay.
5. Control Transformer Circuits: Class CC, time delay, control transformer duty.
6. Provide open-fuse indicator fuses or fuse covers with open fuse indication.

3.3 INSTALLATION

A. Install fuses in fusible devices. Arrange fuses so rating information is readable without removing fuse.

3.4 IDENTIFICATION

A. Install labels complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems" and indicating fuse replacement information inside of door of each fused switch and adjacent to each fuse block, socket, and holder.

END OF SECTION

SECTION 262816 - ENCLOSED SWITCHES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Fusible switches.
2. Nonfusible switches.
3. Enclosures.

1.3 DEFINITIONS

A. NC: Normally closed.

B. NO: Normally open.

C. SPDT: Single pole, double throw.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of enclosed switch, accessory, and component indicated. Include nameplate ratings, dimensioned elevations, sections, weights, and manufacturers' technical data on features, performance, electrical characteristics, ratings, accessories, and finishes.

1. Enclosure types and details for types other than NEMA 250, Type 1.
2. Current and voltage ratings.
3. Short-circuit current ratings (interrupting and withstand, as appropriate).
4. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices, accessories, and auxiliary components.
5. Include time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device. Provide in PDF and electronic format.

C. Shop Drawings: For enclosed switches.

1. Include equipment device sizes, dimensions, details, and attachments to other work.

2. Include wiring diagrams for power, signal, and control wiring.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Operation and Maintenance Data: For enclosed switches and circuit breakers to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

   a. Manufacturer's written instructions for testing and adjusting enclosed switches and circuit breakers.
   b. Time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device. Provide in PDF and electronic format.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Fuses: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.
2. Fuse Pullers: Two for each size and type.

1.8 FIELD CONDITIONS

A. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:

1. Ambient Temperature: Not less than minus 22 deg F and not exceeding 104 deg F.
2. Altitude: Not exceeding 6600 feet.

1.9 WARRANTY

A. Manufacturer's Warranty: Manufacturer and Installer agree to repair or replace components that fail in materials or workmanship within specified warranty period.

1. Warranty Period: One year(s) from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS

A. Source Limitations: Obtain enclosed switches, overcurrent protective devices, components, and accessories, within same product category, from single manufacturer.

B. Product Selection for Restricted Space: Drawings indicate maximum dimensions for enclosed switches, including clearances between enclosures, and adjacent surfaces and other items. Comply with indicated maximum dimensions.

C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and application.

D. Comply with NFPA 70.

2.2 FUSIBLE SWITCHES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB Inc.
2. Eaton.
3. General Electric Company.
4. SIEMENS Industry, Inc.; Energy Management Division.
5. Square D; by Schneider Electric.

B. Type HD, Heavy Duty:

1. Single throw.
2. Two pole and three pole.
3. 240-V ac and 600V.
4. UL 98 and NEMA KS 1, horsepower rated, with clips or bolt pads to accommodate specified fuses.
5. Lockable handle with capability to accept three padlocks, and interlocked with cover in closed position. Lockable in open and closed position.

C. Accessories:

1. Equipment Ground Kit: Internally mounted and labeled for copper ground conductors.
2. Class R Fuse Kit: Provides rejection of other fuse types when Class R fuses are specified.
3. Hookstick Handle: Allows use of a hookstick to operate the handle.

4. No hookstick needs to be provided.
5. Lugs: Mechanical type, suitable for number, size, and conductor material.
6. Provide shunt trip disconnect switch for elevators.

2.3 NONFUSIBLE SWITCHES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB Inc.
2. Eaton.
3. General Electric Company.
4. SIEMENS Industry, Inc.; Energy Management Division.
5. Square D; by Schneider Electric.

B. Type GD, General Duty, Three Pole, Single Throw, 240-V ac, 30 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, lockable handle with capability to accept two padlocks, and interlocked with cover in closed position. Lockable in open and closed position.

C. Type HD, Heavy Duty, Three Pole, Single Throw, 240-V ac and 600V, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position. Lockable in open and closed position.

D. Accessories:

1. Equipment Ground Kit: Internally mounted and labeled for copper ground conductors.
2. Class R Fuse Kit: Provides rejection of other fuse types when Class R fuses are specified.
3. Lugs: Mechanical type, suitable for number, size, and conductor material.

2.4 ENCLOSURES

A. Enclosed Switches: UL 489, NEMA KS 1, NEMA 250, and UL 50, to comply with environmental conditions at installed location.

B. Enclosure Finish: The enclosure must be finished with gray baked enamel paint.

C. Operating Mechanism: The cover interlock mechanism must have an externally operated override. The override must not permanently disable the interlock mechanism, which must return to the locked position once the override is released. The tool used to override the cover interlock mechanism must not be required to enter the enclosure in order to override the interlock.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine elements and surfaces to receive enclosed switches for compliance with installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

1. Commencement of work must indicate Installer's acceptance of the areas and conditions as satisfactory.

3.2 ENCLOSURE ENVIRONMENTAL RATING APPLICATIONS

A. Enclosed Switches: Provide enclosures at installed locations with the following environmental ratings.

1. Indoor, Dry and Clean Locations: NEMA 250, Type 1.
2. Outdoor Locations: NEMA 250, Type 3R.
3. Other Wet or Damp, Indoor Locations: NEMA 250, Type 4.

3.3 INSTALLATION

A. Coordinate layout and installation of switches, and components with equipment served and adjacent surfaces. Maintain minimum NFPA 70 required workspace clearances and required clearances for equipment access doors and access panels.

B. Install individual wall-mounted switches with tops at uniform height unless otherwise indicated.

C. Temporary Lifting Provisions: Remove temporary lifting of eyes, channels, and brackets and temporary blocking of moving parts from enclosures and components.

D. Install fuses in fusible devices.

E. Comply with NFPA 70 and NECA 1.

3.4 IDENTIFICATION

A. Comply with requirements in Section 260553 "Identification for Electrical Systems."

1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
2. Label each enclosure with engraved metal or laminated-plastic nameplate.

3.5 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Tests and Inspections for Switches:

1. Visual and Mechanical Inspection:

a. Inspect physical and mechanical condition.
b. Inspect anchorage, alignment, grounding, and clearances.
c. Verify that the unit is clean.

d. Verify blade alignment, blade penetration, travel stops, and mechanical operation.
e. Verify that fuse sizes and types match the equipment served, Specifications and Drawings.
f. Verify that each fuse has adequate mechanical support and contact integrity.
g. Inspect bolted electrical connections for high resistance using one of the two following methods:

1) Use a low-resistance ohmmeter.

a) Compare bolted connection resistance values to values of similar connections. Investigate values that deviate from those of similar bolted connections by more than 50 percent of the lowest value.

2) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method in accordance with manufacturer's published data or NETA ATS Table 100.12.

a) Bolt-torque levels must be in accordance with manufacturer's published data. In the absence of manufacturer's published data, use NETA ATS Table 100.12.

h. Verify that operation and sequencing of interlocking systems is as described in the Specifications and as indicated.
i. Verify correct phase barrier installation.
j. Verify lubrication of moving current-carrying parts and moving and sliding surfaces.

2. Electrical Tests:

a. Perform resistance measurements through bolted connections with a low-resistance ohmmeter. Compare bolted connection resistance values to values of similar connections. Investigate values that deviate from adjacent poles or similar switches by more than 50 percent of the lowest value.
b. Measure contact resistance across each switchblade fuseholder. Drop values must not exceed the high level of the manufacturer's published data. If manufacturer's published data are not available, investigate values that deviate from adjacent poles or similar switches by more than 50 percent of the lowest value.
c. Perform insulation-resistance tests for one minute on each pole, phase-to-phase and phase-to-ground with switch closed, and across each open pole. Apply voltage in accordance with manufacturer's published data. In the absence of manufacturer's published data, use Table 100.1 from the NETA ATS. Investigate values of insulation resistance less than those published in Table 100.1 or as recommended in manufacturer's published data.
d. Measure fuse resistance. Investigate fuse-resistance values that deviate from each other by more than 15 percent.
e. Perform ground fault test according to NETA ATS 7.14 "Ground Fault Protection Systems, Low-Voltage."

C. Enclosed switches will be considered defective if they do not pass tests and inspections.

D. Prepare test and inspection reports.

1. Test procedures used.
2. Include identification of each enclosed switch tested and describe test results.
3. List deficiencies detected, remedial action taken, and observations after remedial action.

3.6 ADJUSTING

A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.

END OF SECTION

SECTION 263213.13 - DIESEL-ENGINE-DRIVEN GENERATOR SETS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Diesel-engine-driven generator sets.
2. Diesel engine.
3. Diesel fuel-oil system.
4. Control and monitoring.
5. Generator overcurrent and fault protection.
6. Generator, exciter, and voltage regulator.
7. Load bank.
8. Outdoor engine generator enclosure.
9. Remote radiator motors.
10. Vibration isolation devices.

B. Related Requirements:

1. Section 263600 "Transfer Switches" for transfer switches including sensors and relays to initiate automatic-starting and -stopping signals for engine generators.

1.2 DEFINITIONS

A. Operational Bandwidth: The total variation from the lowest to highest value of a parameter over the range of conditions indicated, expressed as a percentage of the nominal value of the parameter.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
2. Include thermal damage curve for generator.
3. Include time-current characteristic curves for generator protective device.
4. Include fuel consumption in gallons per hour at 0.8 power factor at 0.5, 0.75, and 1.0 times generator capacity.
5. Include generator efficiency at 0.8 power factor at 0.5, 0.75, and 1.0 times generator capacity.

6. Include airflow requirements for cooling and combustion air in cubic feet per minute at 0.8 power factor, with air-supply temperature of 95, 80, 70, and 50 deg F. Provide Drawings indicating requirements and limitations for location of air intake and exhausts.
7. Include generator characteristics, including, but not limited to, kilowatt rating, efficiency, reactances, and short-circuit current capability.

C. Shop Drawings:

1. Include plans and elevations for engine generator and other components specified. Indicate access requirements affected by height of subbase fuel tank.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Identify fluid drain ports and clearance requirements for proper fluid drain.
4. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include base weights.
5. Include diagrams for power, signal, and control wiring. Complete schematic, wiring, and interconnection diagrams showing terminal markings for engine generators and functional relationship between all electrical components.

A. Delegated Design Submittal: In addition to submittals listed above, indicate compliance with performance requirements and design criteria, including analysis data signed and sealed by qualified professional engineers responsible for their preparation.

1. Drawings showing location of each device, and installation details as need to comply with listing conditions of device.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For Installer manufacturer and testing agency.

C. Source Quality-Control Reports: Including, but not limited to, the following:

1. Certified summary of prototype-unit test report.
2. Certified Test Reports: For components and accessories that are equivalent, but not identical, to those tested on prototype unit.
3. Certified Summary of Performance Tests: Certify compliance with specified requirement to meet performance criteria for sensitive loads.
4. Report of factory test on units to be shipped for this Project, showing evidence of compliance with specified requirements.
5. Report of sound generation.
6. Report of exhaust emissions showing compliance with applicable regulations.
7. Certified Torsional Vibration Compatibility: Comply with NFPA 110.

D. Field quality-control reports.

E. Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For packaged engine generators to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. List of tools and replacement items recommended to be stored at Project for ready access. Include part and drawing numbers, current unit prices, and source of supply.
b. Operating instructions laminated and mounted adjacent to generator location.
c. Training plan.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.

B. Testing Agency Qualifications: Accredited by NETA.

1. Testing Agency's Field Supervisor: Certified by NETA to supervise on-site testing.

1.7 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace components of packaged engine generators and associated auxiliary components that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 DIESEL-ENGINE-DRIVEN GENERATOR SETS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Caterpillar, Inc.; Electric Power Division.
2. Cummins Power Generation.
3. Rehlko Power Systems.

B. Source Limitations: Obtain packaged engine generators and auxiliary components from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. B11 Compliance: Comply with B11.19.

B. NFPA Compliance:

1. Comply with NFPA 37.
2. Comply with NFPA 70.
3. Comply with NFPA 110 requirements for Level 1 EPSS.

C. UL Compliance: Comply with UL 2200.

D. Engine Exhaust Emissions: Comply with EPA Tier 2 requirements and applicable state and local government requirements.

E. Noise Emission: Comply with applicable state and local government requirements for maximum noise level at adjacent property boundaries due to sound emitted by engine generator including engine, engine exhaust, engine cooling-air intake and discharge, and other components of installation.

F. Environmental Conditions: Engine generator system shall withstand the following environmental conditions without mechanical or electrical damage or degradation of performance capability:

1. Ambient Temperature: 41 to 104 deg F.
2. Relative Humidity: Zero to 95 percent.
3. Altitude: Sea level to 1000 feet.

2.3 ENGINE GENERATOR ASSEMBLY DESCRIPTION

A. Factory-assembled and -tested, water-cooled engine, with brushless generator and accessories.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.

C. Power Rating: Standby.

D. EPSS Class for the COPS Branch: Engine generator must be classified as a Class 72 according to NFPA 110. The COPS branch is rated for 50 kW of the total generator capacity. Fuel capacity, at 100% load, for 72 hours is required for this portion of the system.

E. Service Load: As indicated on drawings.

F. Power Factor: 0.8, lagging.

G. Frequency: 60 Hz.

H. Voltage: 480-V ac.

I. Phase: Three-phase, four wire, wye.

J. Induction Method: Naturally aspirated.

K. Governor: Adjustable isochronous, with speed sensing.

L. Mounting Frame: Structural steel framework to maintain alignment of mounted components without depending on concrete foundation. Provide lifting attachments sized and spaced to prevent deflection of base during lifting and moving.

M. Capacities and Characteristics:

1. Power Output Ratings: Nominal ratings as indicated at 0.8 power factor excluding power required for the continued and repeated operation of the unit and auxiliaries.
2. Nameplates: For each major system component to identify manufacturer's name and address, and model and serial number of component.

N. Engine Generator Performance for Sensitive Loads:

1. Oversizing generator compared with the rated power output of the engine is permissible to meet specified performance.

    a. Nameplate Data for Oversized Generator: Show ratings required by the Contract Documents rather than ratings that would normally be applied to generator size installed.

2. Steady-State Voltage Operational Bandwidth: 1 percent of rated output voltage from no load to full load.
3. Transient Voltage Performance: Not more than 10 percent variation for 50 percent step-load increase or decrease. Voltage shall recover and remain within the steady-state operating band within 0.5 second.
4. Steady-State Frequency Operational Bandwidth: Plus or minus 0.25 percent of rated frequency from no load to full load.
5. Steady-State Frequency Stability: When system is operating at any constant load within the rated load, there shall be no random speed variations outside the steady-state operational band and no hunting or surging of speed.
6. Transient Frequency Performance: Less than 2-Hz variation for 50 percent step-load increase or decrease. Frequency shall recover and remain within the steady-state operating band within three seconds.
7. Output Waveform: At no load, harmonic content measured line to neutral shall not exceed 2 percent total with no slot ripple. Telephone influence factor, determined according to NEMA MG 1, shall not exceed 50 percent.
8. Sustained Short-Circuit Current: For a three-phase, bolted short circuit at system output terminals, system shall supply a minimum of 300 percent of rated full-load current for not less than 10 seconds and then clear the fault automatically, without damage to winding insulation or other generator system components.
9. Excitation System: Performance shall be unaffected by voltage distortion caused by nonlinear load.

    a. Provide permanent magnet excitation for power source to voltage regulator.

10. Start Time:

    a. Comply with NFPA 110, Type 10 system requirements.
    b. 10 seconds.

2.4 DIESEL ENGINE

A. Fuel: ASTM D975, diesel fuel oil, Grade 2-D S15.

B. Rated Engine Speed: 1800 rpm.

C. Lubrication System: Engine or skid-mounted.

1. Filter and Strainer: Rated to remove 90 percent of particles 5 micrometers and smaller while passing full flow.
2. Thermostatic Control Valve: Control flow in system to maintain optimum oil temperature. Unit shall be capable of full flow and is designed to be fail-safe.
3. Crankcase Drain: Arranged for complete gravity drainage to an easily removable container with no disassembly and without use of pumps, siphons, special tools, or appliances.

D. Jacket Coolant Heater: Electric-immersion type, factory installed in coolant jacket system. Comply with UL 499 and with NFPA 110 requirements for Level 1 equipment for heater capacity.

E. Integral Cooling System: Closed loop, liquid cooled, with radiator factory mounted on engine generator set mounting frame and integral engine-driven coolant pump.

1. Coolant: Solution of 50 percent ethylene-glycol-based antifreeze and 50 percent water, with anticorrosion additives as recommended by engine manufacturer.
2. Size of Radiator: Adequate to contain expansion of total system coolant from cold start to 110 percent load condition.
3. Expansion Tank: Constructed of welded steel plate and rated to withstand maximum closed-loop coolant system pressure for engine used. Equip with gage glass and petcock.
4. Temperature Control: Self-contained, thermostatic-control valve modulates coolant flow automatically to maintain optimum constant coolant temperature as recommended by engine manufacturer.
5. Coolant Hose: Flexible assembly with inside surface of nonporous rubber and outer covering of aging-, UV-, and abrasion-resistant fabric.

a. Rating: 50-psig maximum working pressure with coolant at 180 deg F, and noncollapsible under vacuum.
b. End Fittings: Flanges or steel pipe nipples with clamps to suit piping and equipment connections.

F. Muffler/Silencer:

1. Commercial type, sized as recommended by engine manufacturer and selected with exhaust piping system to not exceed engine manufacturer's engine backpressure requirements.

a. Minimum sound attenuation of 12 dB at 500 Hz.
b. Sound level measured at a distance of 25 feet from exhaust discharge after installation is complete shall be 90 dBA or less.

G. Air-Intake Filter: Heavy-duty, engine-mounted air cleaner with replaceable dry-filter element and "blocked filter" indicator.

H. Starting System: 24-V electric, with negative ground.

1. Components: Sized so they are not damaged during a full engine-cranking cycle with ambient temperature at maximum specified in "Performance Requirements" Article.
2. Cranking Motor: Heavy-duty unit that automatically engages and releases from engine flywheel without binding.
3. Cranking Cycle: As required by NFPA 110 for system level specified.
4. Battery: Lead acid, with capacity within ambient temperature range specified in "Performance Requirements" Article to provide specified cranking cycle at least three times without recharging.
5. Battery Cable: Size as recommended by engine manufacturer for cable length indicated. Include required interconnecting conductors and connection accessories.
6. Battery Compartment: Factory fabricated of metal with acid-resistant finish and thermal insulation. Thermostatically controlled heater shall be arranged to maintain battery above 50 deg F regardless of external ambient temperature within range specified in "Performance Requirements" Article. Include accessories required to support and fasten batteries in place. Provide ventilation to exhaust battery gases.
7. Battery Stand: Factory-fabricated, two-tier metal with acid-resistant finish designed to hold the quantity of battery cells required and to maintain the arrangement to minimize lengths of battery interconnections.
8. Battery-Charging Alternator: Factory mounted on engine with solid-state voltage regulation and 35-A minimum continuous rating.
9. Battery Charger: Current-limiting, automatic-equalizing, and float-charging type designed for lead-acid batteries. Unit shall comply with UL 1236 and include the following features:

    a. Operation: Equalizing-charging rate of 10 A shall be initiated automatically after battery has lost charge until an adjustable equalizing voltage is achieved at battery terminals. Unit shall then be automatically switched to a lower float-charging mode and shall continue to operate in that mode until battery is discharged again.
    b. Automatic Temperature Compensation: Adjust float and equalize voltages for variations in ambient temperature from minus 40 to 140 deg F to prevent overcharging at high temperatures and undercharging at low temperatures.
    c. Automatic Voltage Regulation: Maintain constant output voltage regardless of input voltage variations up to plus or minus 10 percent.
    d. Ammeter and Voltmeter: Flush mounted in door. Meters shall indicate charging rates.
    e. Safety Functions: Sense abnormally low battery voltage and close contacts providing low battery voltage indication on control and monitoring panel. Sense high battery voltage and loss of ac input or dc output of battery charger. Either condition shall close contacts that provide a battery-charger malfunction indication at system control and monitoring panel.
    f. Enclosure and Mounting: NEMA 250, Type 1, wall-mounted cabinet.

2.5 DIESEL FUEL-OIL SYSTEM

A. Comply with NFPA 37.

B. Piping: Fuel-oil piping shall be Schedule 40 black steel, complying with requirements in Section 231113 "Facility Fuel-Oil Piping." Cast iron, aluminum, copper, and galvanized steel shall not be used in the fuel-oil system.

C. Main Fuel Pump: Mounted on engine to provide primary fuel flow under starting and load conditions.

D. Fuel Filtering: Remove water and contaminants larger than 1 micron.

E. Relief-Bypass Valve: Automatically regulates pressure in fuel line and returns excess fuel to source.

F. Subbase-Mounted, Double-Wall, Fuel-Oil Tank: Factory installed and piped, complying with UL 142 fuel-oil tank. Features include the following:

1. Tank level indicator.
2. Fuel-Tank Capacity: 24 hour run time at full 100 percent capacity.
3. Leak detection in interstitial space.
4. Vandal-resistant fill cap.
5. Containment Provisions: Comply with requirements of authorities having jurisdiction.

2.6 CONTROL AND MONITORING

A. Automatic Starting System Sequence of Operation: When mode-selector switch on the control and monitoring panel is in the automatic position, remote-control contacts in one or more separate automatic transfer switches initiate starting and stopping of engine generator. When mode-selector switch is switched to the on position, engine generator starts. The off position of same switch initiates engine generator shutdown. When engine generator is running, specified system or equipment failures or derangements automatically shut down engine generator and initiate alarms.

B. Manual Starting System Sequence of Operation: Switching on-off switch on the generator control panel to the on position starts engine generator. The off position of same switch initiates engine generator shutdown. When engine generator is running, specified system or equipment failures or derangements automatically shut down engine generator and initiate alarms.

C. Provide minimum run time control set for 15 minutes with override only by operation of a remote emergency-stop switch.

D. Comply with UL 508A.

E. Configuration:

1. Operating and safety indications, protective devices, basic system controls, and engine gages shall be grouped in a common control and monitoring panel mounted on the engine generator. Mounting method shall isolate the control panel from engine generator vibration. Panel shall be powered from the engine generator battery.
2. Operating and safety indications, protective devices, basic system controls, and engine gages shall be grouped in a common wall-mounted control and monitoring panel. Panel shall be powered from the engine generator battery.
3. Operating and safety indications, protective devices, basic system controls, engine gages, instrument transformers, generator disconnect switch or circuit breaker, and other indicated components shall be grouped in a combination control and power panel. Control and monitoring section of panel shall be isolated from power sections by steel barriers. Panel shall be powered from the engine generator battery. Panel features shall include the following:

a. Wall-Mounting Cabinet Construction: Rigid, self-supporting steel unit complying with NEMA ICS 6.

F. Control and Monitoring Panel:

1. Digital engine generator controller with integrated LCD display, controls, and microprocessor, capable of local and remote control, monitoring, and programming, with battery backup.
2. Analog control panel with dedicated gages and indicator lights for the instruments and alarms indicated below.
3. Instruments: Located on the control and monitoring panel and viewable during operation.

a. Engine lubricating-oil pressure gage.
b. Engine-coolant temperature gage.
c. DC voltmeter (alternator battery charging).
d. Running-time meter.
e. AC voltmeter, connected to a phase selector switch.
f. AC ammeter, connected to a phase selector switch.
g. AC frequency meter.
h. Generator-voltage adjusting rheostat.

4. Controls and Protective Devices: Controls, shutdown devices, and common alarm indication, including the following:

a. Cranking control equipment.
b. Run-Off-Auto switch.
c. Control switch not in automatic position alarm.
d. Overcrank alarm.
e. Overcrank shutdown device.
f. Low-water temperature alarm.
g. High engine temperature prealarm.
h. High engine temperature.
i. High engine temperature shutdown device.
j. Overspeed alarm.
k. Overspeed shutdown device.
l. Low fuel main tank.

1) Low-fuel-level alarm must be initiated when the level falls below that required for 72 hours of operation for the COPS system.

m. Coolant low-level alarm.
n. Coolant low-level shutdown device.
o. Coolant high-temperature prealarm.
p. Coolant high-temperature alarm.
q. Coolant low-temperature alarm.
r. Coolant high-temperature shutdown device.
s. EPS load indicator.
t. Battery high-voltage alarm.
u. Low cranking voltage alarm.
v. Battery-charger malfunction alarm.
w. Battery low-voltage alarm.
x. Lamp test.

y. Contacts for local and remote common alarm.
z. Low-starting air pressure alarm.
aa. Low-starting hydraulic pressure alarm.
bb. Remote manual stop shutdown device.
cc. Air shutdown damper alarm when used.
dd. Air shutdown damper shutdown device when used.
ee. Generator overcurrent-protective-device not-closed alarm.
ff. Hours of operation.
gg. Engine generator metering, including voltage, current, hertz, kilowatt, kilovolt ampere, and power factor.

G. Engine Generator Metering: Comply with Section 262713 "Electricity Metering."

H. Connection to Datalink:

1. A separate terminal block, factory wired to Form C dry contacts, for each alarm and status indication.
2. Provide connections for datalink transmission of indications to remote data terminals via Ethernet.

I. Common Remote Panel with Common Audible Alarm: Include necessary contacts and terminals in control and monitoring panel. Remote panel shall be powered from the engine generator battery.

J. Remote Alarm Annunciator: An LED indicator light labeled with proper alarm conditions shall identify each alarm event, and a common audible signal shall sound for each alarm condition. Silencing switch in face of panel shall silence signal without altering visual indication. Connect so that after an alarm is silenced, clearing of initiating condition will reactivate alarm until silencing switch is reset. Cabinet and faceplate are surface- or flush-mounting type to suit mounting conditions indicated.

1. Overcrank alarm.
2. Low water-temperature alarm.
3. High engine temperature prealarm.
4. High engine temperature alarm.
5. Low lube oil pressure alarm.
6. Overspeed alarm.
7. Low fuel main tank alarm.
8. Low coolant level alarm.
9. Low cranking voltage alarm.
10. Contacts for local and remote common alarm.
11. Audible-alarm silencing switch.
12. Air shutdown damper when used.
13. Run-Off-Auto switch.
14. Control switch not in automatic position alarm.
15. Fuel tank derangement alarm.
16. Fuel tank high-level shutdown of fuel supply alarm.
17. Lamp test.
18. Low-cranking voltage alarm.
19. Generator overcurrent-protective-device not-closed alarm.

K. Supporting Items: Include sensors, transducers, terminals, relays, and other devices and include wiring required to support specified items. Locate sensors and other supporting items on engine or generator unless otherwise indicated.

L. Remote Emergency-Stop Switch: Flush; wall mounted unless otherwise indicated; and labeled. Push button shall be protected from accidental operation.

M. Provide generator engine start module to monitor the control wires between the generator and each of the automatic transfer switches. Generator must start upon loss of control wiring.

2.7 GENERATOR OVERCURRENT AND FAULT PROTECTION

A. Overcurrent protective devices shall be coordinated to optimize selective tripping when a short circuit occurs.

1. Overcurrent protective devices for the entire EPSS shall be coordinated to optimize selective tripping when a short circuit occurs. Coordination of protective devices shall consider both utility and EPSS as the voltage source.
2. Overcurrent protective devices for the EPSS shall be accessible only to authorized personnel.

B. Generator Overcurrent Protective Device:

1. Molded-case circuit breaker, thermal-magnetic type; 100 percent rated; complying with UL 489:

a. Tripping Characteristic: Designed specifically for generator protection.
b. Trip Rating: Matched to generator output rating.
c. Shunt Trip: Connected to trip breaker when engine generator is shut down by other protective devices.
d. Mounting: Adjacent to, or integrated with, control and monitoring panel.

C. Generator Protector: Microprocessor-based unit shall continuously monitor current level in each phase of generator output, integrate generator heating effect over time, and predict when thermal damage of alternator will occur. When signaled by generator protector or other engine generator protective devices, a shunt-trip device in the generator disconnect switch shall open the switch to disconnect the generator from load circuits. Protector performs the following functions:

1. Initiates a generator overload alarm when generator has operated at an overload equivalent to 110 percent of full-rated load for 60 seconds. Indication for this alarm is integrated with other engine generator malfunction alarms. Contacts shall be available for load shed functions.
2. Under single- or three-phase fault conditions, regulates generator to 300 percent of rated full-load current for up to 10 seconds.
3. As overcurrent heating effect on the generator approaches the thermal damage point of the unit, protector switches the excitation system off, opens the generator disconnect device, and shuts down the engine generator.
4. Senses clearing of a fault by other overcurrent devices and controls recovery of rated voltage to avoid overshoot.

D. Ground-Fault Indication: Comply with NFPA 70, "Emergency System" signals for ground fault.

1. Indicate ground fault with other engine generator alarm indications.
2. Trip generator protective device on ground fault.

2.8 GENERATOR, EXCITER, AND VOLTAGE REGULATOR

A. Comply with NEMA MG 1.

B. Drive: Generator shaft shall be directly connected to engine shaft. Exciter shall be rotated integrally with generator rotor.

C. Electrical Insulation: Class H or Class F.

D. Stator-Winding Leads: Brought out to terminal box to permit future reconnection for other voltages if required. Provide 12-lead alternator.

E. Range: Provide limited broad extended range of output voltage by adjusting the excitation level.

F. Construction shall prevent mechanical, electrical, and thermal damage due to vibration, overspeed up to 125 percent of rating, and heat during operation at 110 percent of rated capacity.

G. Enclosure: Dripproof.

H. Instrument Transformers: Mounted within generator enclosure.

I. Voltage Regulator: Solid-state type, separate from exciter, providing performance as specified and as required by NFPA 110.

1. Adjusting Rheostat on Control and Monitoring Panel: Provide plus or minus 5 percent adjustment of output-voltage operating band.
2. Maintain voltage within 30 percent on one step, full load.
3. Provide anti-hunt provision to stabilize voltage.
4. Maintain frequency within 10 percent and stabilize at rated frequency within 5 seconds.

J. Windings: Two-thirds pitch stator winding and fully linked amortisseur winding.

K. Subtransient Reactance: 12 percent, maximum.

2.9 LOAD BANK

A. Description:

1. Permanent, radiator-mounted, resistive unit capable of providing a balanced three-phase, delta-connected load to engine generator at 50 percent rated-system capacity. Unit shall be capable of selective control of load in 25 percent steps of load-bank rating and with minimum step changes of approximately 5 and 10 percent available.

B. Resistive Load Elements: Corrosion-resistant chromium alloy with ceramic and stainless-steel supports. Elements shall be double insulated and designed for repetitive on-off cycling. Elements shall be mounted in removable aluminized-steel heater cases. Galvanized steel is prohibited. Element's maximum resistance shall be between 100 and 105 percent of rated resistance.

C. Load-Bank Heat Dissipation: Integral fan with totally enclosed motor shall provide uniform cooling airflow through load elements. Airflow and coil operating current shall be such that, at maximum load, with ambient temperature at the upper end of specified range, load-bank elements operate at not more than 50 percent of maximum continuous temperature rating of resistance elements.

D. Load-Element Switching: Remote-controlled contactors switch groups of load elements. Contactor coils are rated 120 V. Contactors shall be located in a separate NEMA 250, Type 3R enclosure within load-bank enclosure, accessible from exterior through hinged doors with tumbler locks.

E. Contactor Enclosures: Heated by thermostatically controlled strip heaters to prevent condensation.

F. Load-Bank Enclosures: NEMA 250, Type 3R, aluminized steel complying with NEMA ICS 6. Louvers at cooling-air intake and discharge openings shall prevent entry of rain and snow. Openings for airflow shall be screened with 1/2-inch-square, galvanized-steel mesh. Reactive load bank shall include automatic shutters at air intake and discharge. Components other than resistive elements shall receive exterior epoxy coating with compatible primer. Comply with requirements in Section 099600 "High-Performance Coatings."

G. Protective Devices: Power input circuits to load banks shall be fused, and fuses shall be selected to coordinate with generator circuit breaker. Fuse blocks shall be located in contactor enclosure. Cooling airflow and overtemperature sensors shall automatically shut down and lock out load bank until manually reset. Safety interlocks on access panels and doors shall disconnect load power, control, and heater circuits. Fan motor shall be separately protected by overload and short-circuit devices. Short-circuit devices shall be noninterchangeable fuses with 200,000-A interrupting capacity.

H. Load-Bank Remote-Control Panel: Separate from load bank in NEMA 250, Type 1 enclosure with a control power switch and pilot light, and switches controlling groups of load elements.

I. Control Sequence: Control panel may be preset for adjustable single-step loading of generator during automatic exercising.

2.10 OUTDOOR ENGINE GENERATOR ENCLOSURE

A. Description:

1. Vandal-resistant, sound-attenuating, weatherproof steel housing; wind resistant up to 100 mph. Multiple panels shall be lockable and provide adequate access to components requiring maintenance. Panels shall be removable by one person without tools. Instruments and control shall be mounted within enclosure.
2. Prefabricated or pre-engineered, galvanized-steel-clad, integral structural-steel-framed; erected on concrete foundation.

B. Structural Design and Anchorage: Comply with ASCE/SEI 7 for wind loads up to 100 mph.

C. Hinged Doors: With padlocking provisions.

D. Space Heater: Thermostatically controlled and sized to prevent condensation.

E. Lighting: Provide weather-resistant LED lighting with 30 fc average maintained.

F. Thermal Insulation: Manufacturer's standard materials and thickness selected in coordination with space heater to maintain winter interior temperature within operating limits required by engine generator components.

G. Muffler Location: Within enclosure.

H. Engine-Cooling Airflow through Enclosure: Maintain temperature rise of system components within required limits when unit operates at 110 percent of rated load for two hours with ambient temperature at top of range specified in system service conditions.

1. Louvers: Fixed-engine, cooling-air inlet and discharge. Stormproof and drainable louvers prevent entry of rain and snow.
2. Automatic Dampers: At engine cooling-air inlet and discharge. Dampers shall be closed to reduce enclosure heat loss in cold weather when unit is not operating.
3. Ventilation: Provide temperature-controlled exhaust fan interlocked to prevent operation when engine is running.

I. Interior Lights with Switch: Factory-wired, vapor-proof luminaires within housing; arranged to illuminate controls and accessible interior. Arrange for external electrical connection.

1. AC lighting system and connection point for operation when remote source is available.
2. DC lighting system for operation when remote source and generator are both unavailable.

J. Convenience Outlets: Factory-wired, GFCI. Arrange for external electrical connection.

2.11 VIBRATION ISOLATION DEVICES

A. Elastomeric Isolator Pads: Oil- and water-resistant elastomer or natural rubber, arranged in single or multiple layers, molded with a nonslip pattern and galvanized-steel baseplates of sufficient stiffness for uniform loading over pad area, and factory cut to sizes that match requirements of supported equipment.

1. Material: Standard neoprene separated by steel shims.
2. Minimum Deflection: 1 inch.

B. Comply with requirements in Section 233113 "Metal Ducts" for vibration isolation and flexible connector materials for exhaust shroud and ductwork.

C. Vibration isolation devices shall not be used to accommodate misalignments or to make bends.

2.12 FINISHES

A. Indoor and Outdoor Enclosures and Components: Manufacturer's standard finish over corrosion-resistant pretreatment and compatible primer.

2.13 SOURCE QUALITY CONTROL

A. Prototype Testing: Factory test engine generator using same engine model, constructed of identical or equivalent components and equipped with identical or equivalent accessories.

1. Tests: Comply with IEEE 115 and with NFPA 110, Level 1 Energy Converters.

B. Project-Specific Equipment Tests: Before shipment, factory test engine generator and other system components and accessories manufactured specifically for this Project. Perform tests at rated load and power factor. Include the following tests:

1. Test components and accessories furnished with installed unit that are not identical to those on tested prototype to demonstrate compatibility and reliability.
2. Test generator, exciter, and voltage regulator as a unit.
3. Full load run.
4. Maximum power.
5. Voltage regulation.
6. Transient and steady-state governing.
7. Single-step load pickup.
8. Safety shutdown.
9. Provide 14 days' advance notice of tests and opportunity for observation of tests by Owner's representative.
10. Report factory test results within 10 days of completion of test.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, equipment bases, and conditions, with Installer present, for compliance with requirements for installation and other conditions affecting packaged engine generator performance.

B. Examine roughing-in for piping systems and electrical connections. Verify actual locations of connections before packaged engine generator installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Comply with NECA 1 and NECA 404.

B. Comply with packaged engine generator manufacturers' written installation and alignment instructions and with NFPA 110.

C. Equipment Mounting:

1. Coordinate size and location of concrete bases for packaged engine generators. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified with concrete.

D. Install packaged engine generator to provide access, without removing connections or accessories, for periodic maintenance.

3.3 CONNECTIONS

A. Connect fuel, cooling-system, and exhaust-system piping adjacent to packaged engine generator to allow space for service and maintenance.

B. Connect cooling-system water piping to engine generator and heat exchanger with flexible connectors.

C. Connect engine exhaust pipe to engine with flexible connector.

D. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."

E. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables." Provide a minimum of one 90-degree bend in flexible conduit routed to the engine generator from a stationary element.

F. Balance single-phase loads to obtain a maximum of 10 percent unbalance between any two phases. Update associated panelboard directories to reflect adjustments made.

3.4 IDENTIFICATION

A. Identify system components according to Section 260553 "Identification for Electrical Systems."

3.5 FIELD QUALITY CONTROL

A. Testing Agency:

1. Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
2. Perform tests and inspections with the assistance of a factory-authorized service representative.
3. Provide diesel fuel for testing and commissioning. Tank must be left full at the completion of tests and commissioning.

B. Tests and Inspections:

1. Testing agency must perform tests recommended by manufacturer and each visual and mechanical inspection and electrical and mechanical test listed in first two subparagraphs below, as specified in NETA ATS. Certify compliance with test parameters.

    a. Visual and Mechanical Inspection:

        1) Compare equipment nameplate data with Drawings and the Specifications.
        2) Inspect physical and mechanical condition.
        3) Inspect anchorage, alignment, and grounding.
        4) Verify that the unit is clean.

    b. Electrical and Mechanical Tests:

        1) Perform insulation-resistance tests according to IEEE 43.

            a) Machines Larger Than 200 hp: Test duration shall be 10 minutes. Calculate polarization index.
            b) Machines 200 hp or Less: Test duration shall be one minute. Calculate the dielectric-absorption ratio.

        2) Test protective relay devices.
        3) Verify phase rotation, phasing, and synchronized operation as required by the application.
        4) Functionally test engine shutdown for low oil pressure, overtemperature, overspeed, and other protection features as applicable.
        5) Perform vibration test for each main bearing cap.
        6) Verify correct functioning of the governor and regulator.

2. NFPA 110 Acceptance Tests: Perform tests required by NFPA 110 that are additional to those specified here, including, but not limited to, single-step full-load pickup test.
3. Battery Tests: Equalize charging of battery cells according to manufacturer's written instructions. Record individual cell voltages.

    a. Measure charging voltage and voltages between available battery terminals for full-charging and float-charging conditions. Check electrolyte level and specific gravity under both conditions.
    b. Test for contact integrity of all connectors. Perform an integrity load test and a capacity load test for the battery.
    c. Verify acceptance of charge for each element of the battery after discharge.
    d. Verify that measurements are within manufacturer's specifications.

4. Battery-Charger Tests: Verify specified rates of charge for both equalizing and float-charging conditions.
5. System Integrity Tests: Methodically verify proper installation, connection, and integrity of each element of engine generator system before and during system operation. Check for air, exhaust, and fluid leaks.
6. Exhaust-System Back-Pressure Test: Use a manometer with a scale exceeding 40-inch wg. Connect to exhaust line close to engine exhaust manifold. Verify that back pressure at full-rated load is within manufacturer's written allowable limits for the engine.
7. Exhaust Emissions Test: Comply with applicable government test criteria.

8. Voltage and Frequency Transient Stability Tests: Use recording oscilloscope to measure voltage and frequency transients for 50 and 100 percent step-load increases and decreases, and verify that performance is as specified.
9. Harmonic-Content Tests: Measure harmonic content of output voltage at 25 and 100 percent of rated linear load. Verify that harmonic content is within specified limits.
10. Noise Level Tests: Measure A-weighted level of noise emanating from engine generator installation, including engine exhaust and cooling-air intake and discharge, at four locations 25 feet from edge of the generator enclosure, and compare measured levels with required values.

C. Coordinate tests with tests for transfer switches and run them concurrently.

D. Test instruments shall have been calibrated within the past 12 months, traceable to NIST Calibration Services, and adequate for making positive observation of test results. Make calibration records available for examination on request.

E. Leak Test: After installation, charge exhaust, coolant, and fuel systems and test for leaks. Repair leaks and retest until no leaks exist.

F. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation for generator and associated equipment.

G. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

H. Remove and replace malfunctioning units and retest as specified above.

I. Retest: Correct deficiencies identified by tests and observations, and retest until specified requirements are met.

J. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation resistances, time delays, and other values and observations. Attach a label or tag to each tested component indicating satisfactory completion of tests.

3.6 MAINTENANCE SERVICE

A. Initial Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by skilled employees of manufacturer's authorized service representative. Include quarterly preventive maintenance and exercising to check for proper starting, load transfer, and running under load. Include routine preventive maintenance as recommended by manufacturer and adjusting as required for proper operation. Parts shall be manufacturer's authorized replacement parts and supplies.

3.7 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain packaged engine generators.

END OF SECTION

SECTION 263600 - TRANSFER SWITCHES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Contactor-type automatic transfer switches.
2. Manual transfer switches.
3. Transfer switch accessories.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Contactor-type automatic transfer switches.
2. Manual transfer switches.
3. Transfer switch accessories.

C. Product Data Submittals: For each product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for transfer switches.
2. Include rated capacities, operating characteristics, electrical characteristics, and accessories.

D. Shop Drawings:

1. Include plans, elevations, sections, details showing minimum clearances, conductor entry provisions, gutter space, and installed features and devices.
2. Include material lists for each switch specified.
3. Single-Line Diagram: Show connections between transfer switch, bypass/isolation switch, power sources, and load; and show interlocking provisions for each combined transfer switch and bypass/isolation switch.
4. Riser Diagram: Show interconnection wiring between transfer switches, bypass/isolation switches, annunciators, and control panels.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For manufacturer-authorized service representative and testing agency.

C. Field quality-control reports.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For each type of product to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. Features and operating sequences, both automatic and manual.
b. List of all factory settings of relays; provide relay-setting and calibration instructions, including software, where applicable.

1.5 QUALITY ASSURANCE

A. Testing Agency Qualifications:

1. Member company of NETA.

a. Testing Agency’s Field Supervisor: Certified by NETA to supervise onsite testing.

1.6 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace components of transfer switch or transfer switch components that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Comply with NEMA ICS 1.

C. Comply with NFPA 110.

D. Comply with UL 1008 unless requirements of these Specifications are stricter.

E. Indicated Current Ratings: Apply as defined in UL 1008 for continuous loading and total system transfer, including tungsten filament lamp loads not exceeding 30 percent of switch ampere rating, unless otherwise indicated.

F. Tested Fault-Current Closing and Short-Circuit Ratings: Adequate for duty imposed by protective devices at installation locations in Project under the fault conditions indicated, based on testing according to UL 1008.

1. Where transfer switch includes internal fault-current protection, rating of switch and trip unit combination shall exceed indicated fault-current value at installation location.
2. Short-time withstand capability for 30 cycles.

G. Repetitive Accuracy of Solid-State Controls: All settings shall be plus or minus 2 percent or better over an operating temperature range of minus 20 to plus 70 deg C.

H. Resistance to Damage by Voltage Transients: Components shall meet or exceed voltage-surge withstand capability requirements when tested according to IEEE C62.62. Components shall meet or exceed voltage-impulse withstand test of NEMA ICS 1.

I. Electrical Operation: Accomplish by a nonfused, momentarily energized solenoid or electric-motor-operated mechanism. Switches for emergency or standby purposes shall be mechanically and electrically interlocked in both directions to prevent simultaneous connection to both power sources unless closed transition.

J. Neutral Switching: Provide neutral pole switched simultaneously with phase poles.

K. Heater: Equip switches exposed to outdoor temperatures and humidity, and other units indicated, with an internal heater. Provide thermostat within enclosure to control heater.

L. Annunciation, Control, and Programming Interface Components: Devices at transfer switches for communicating with remote programming devices, annunciators, or annunciator and control panels shall have communication capability matched with remote device.

M. Factory Wiring: Train and bundle factory wiring and label, consistent with Shop Drawings, by color-code or by numbered or lettered wire and cable with printed markers at terminations. Color-coding and wire and cable markers are specified in Section 260553 "Identification for Electrical Systems."

1. Designated Terminals: Pressure type, suitable for types and sizes of field wiring indicated.
2. Power-Terminal Arrangement and Field-Wiring Space: Suitable for top, side, or bottom entrance of feeder conductors as indicated.
3. Control Wiring: Equipped with lugs suitable for connection to terminal strips.
4. Accessible via front access.

N. Enclosures: General-purpose NEMA 250, Type 1 or Type 3R (where located outside), complying with NEMA ICS 6 and UL 508, unless otherwise indicated.

2.2 CONTACTOR-TYPE AUTOMATIC TRANSFER SWITCHES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB, Electrification Business.
2. ASCO Power Technologies.

3. Caterpillar, Inc.; Electric Power Division.
4. Cummins Power Generation.
5. Eaton.
6. Rehlko Power Systems.
7. Russelectric, Inc.

B. Comply with Level 1 equipment according to NFPA 110.

C. Switch Characteristics: Designed for continuous-duty repetitive transfer of full-rated current between active power sources.

1. Limitation: Switches using molded-case switches or circuit breakers or insulated-case circuit-breaker components are unacceptable.
2. Switch Action: Double throw; mechanically held in both directions.
3. Contacts: Silver composition or silver alloy for load-current switching. Contactor-style automatic transfer-switch units, rated 600 A and higher, shall have separate arcing contacts.
4. Conductor Connectors: Suitable for use with conductor material and sizes.
5. Material: Hard-drawn copper, 98 percent conductivity.
6. Main and Neutral Lugs: Mechanical type.
7. Ground Lugs and Bus-Configured Terminators: Mechanical type.
8. Ground bar.
9. Connectors shall be marked for conductor size and type according to UL 1008.

D. Automatic Delayed-Transition Transfer Switches (ATS-OS): Pauses or stops in intermediate position to momentarily disconnect both sources, with transition controlled by programming in the automatic transfer-switch controller. Interlocked to prevent the load from being closed on both sources at the same time.

1. Adjustable Time Delay: For override of normal-source voltage sensing to delay transfer and engine start signals for alternative source. Adjustable from zero to six seconds, and factory set for one second.
2. Sources shall be mechanically and electrically interlocked to prevent closing both sources on the load at the same time.
3. Fully automatic break-before-make operation with center off position.

E. Automatic Closed-Transition Transfer Switches (ATS-EM and ATS-COPS): Connect both sources to load momentarily. Transition is controlled by programming in the automatic transfer-switch controller.

1. Fully automatic make-before-break operation when transferring between two available power sources.
2. Load transfer without interruption, through momentary interconnection of both power sources not exceeding 100 ms.
3. Initiation of No-Interruption Transfer: Controlled by in-phase monitor and sensors confirming both sources are present and acceptable.

    a. Automatic transfer-switch controller takes active control of generator to match frequency, phase angle, and voltage.
    b. Controls ensure that closed-transition load transfer closure occurs only when the two sources are within plus or minus 5 electrical degrees maximum, and plus or minus 5 percent maximum voltage difference.

4. Failure of power source serving load initiates automatic break-before-make transfer.

F. Manual Switch Operation: A manual operator shall be provided for maintenance purposes only with switch de-energized and door open. Transfer time is same as for electrical operation. Control circuit automatically disconnects from electrical operator during manual operation.

G. Electric Nonautomatic Switch Operation: Electrically actuated by push buttons designated "Normal Source" and "Alternative Source." Switch shall be capable of transferring load in either direction with either or both sources energized.

H. Signal-Before-Transfer Contacts: A set of normally open/normally closed dry contacts operates in advance of retransfer to normal source. Interval shall be adjustable from 1 to 30 seconds.

I. Digital Communication Interface: Matched to capability of remote annunciator or annunciator and control panel.

J. Automatic Transfer-Switch Controller Features:

1. Controller operates through a period of loss of control power.
2. Undervoltage Sensing for Each Phase of Normal and Alternate Source: Sense low phase-to-ground voltage on each phase. Pickup voltage shall be adjustable from 85 to 100 percent of nominal, and dropout voltage shall be adjustable from 75 to 98 percent of pickup value. Factory set for pickup at 90 percent and dropout at 85 percent.
3. Voltage/Frequency Lockout Relay: Prevent premature transfer to generator. Pickup voltage shall be adjustable from 85 to 100 percent of nominal. Factory set for pickup at 90 percent. Pickup frequency shall be adjustable from 90 to 100 percent of nominal. Factory set for pickup at 95 percent.
4. Time Delay for Retransfer to Normal Source: Adjustable from zero to 30 minutes, and factory set for 10 minutes. Override shall automatically defeat delay on loss of voltage or sustained undervoltage of emergency source, provided normal supply has been restored.
5. Test Switch: Simulate normal-source failure.
6. Switch-Position Pilot Lights: Indicate source to which load is connected.
7. Source-Available Indicating Lights: Supervise sources via transfer-switch normal- and emergency-source sensing circuits.

    a. Normal Power Supervision: Green light with nameplate engraved "Normal Source Available."
    b. Emergency Power Supervision: Red light with nameplate engraved "Emergency Source Available."

8. Unassigned Auxiliary Contacts: Two normally open, single-pole, double-throw contacts for each switch position, rated 10 A at 240-V ac.
9. Transfer Override Switch: Overrides automatic retransfer control so transfer switch will remain connected to emergency power source regardless of condition of normal source. Pilot light indicates override status.
10. Engine Starting Contacts: One isolated and normally closed, and one isolated and normally open; rated 10 A at 32-V dc minimum.
11. Engine Shutdown Contacts:

    a. Time delay adjustable from zero to five minutes, and factory set for five minutes. Contacts shall initiate shutdown at remote engine-generator controls after retransfer of load to normal source.

12. Engine-Generator Exerciser: Solid-state, programmable-time switch starts engine generator and transfers load to it from normal source for a preset time, then retransfers and shuts down engine after a preset cool-down period. Initiates exercise cycle at preset intervals adjustable from 7 to 30 days. Running periods shall be adjustable from 10 to 30 minutes. Factory settings shall be for 7-day exercise cycle, 20-minute running period, and 5-minute cool-down period. Exerciser features include the following:

    a. Exerciser Transfer Selector Switch: Permits selection of exercise with and without load transfer.
    b. Push-button programming control with digital display of settings.
    c. Integral battery operation of time switch when normal control power is unavailable.

K. Large-Motor-Load Power Transfer:

1. In-Phase Monitor: Factory-wired, internal relay controls transfer so contacts close only when the two sources are synchronized in phase and frequency. Relay shall compare phase relationship and frequency difference between normal and emergency sources and initiate transfer when both sources are within 15 electrical degrees, and only if transfer can be completed within 60 electrical degrees. Transfer shall be initiated only if both sources are within 2 Hz of nominal frequency and 70 percent or more of nominal voltage.
2. Motor Disconnect and Timing Relay Controls: Designated starters in loss of power scenario shall disconnect motors before transfer and reconnect them selectively at an adjustable time interval after transfer. Control connection to motor starters shall be through wiring external to automatic transfer switch. Provide adjustable time delay between 1 and 60 seconds for reconnecting individual motor loads. Provide relay contacts rated for motor-control circuit inrush and for actual seal currents to be encountered.

2.3 MANUAL TRANSFER SWITCHES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Caterpillar, Inc.; Electric Power Division.
2. Eaton.
3. ESL Power Systems, Inc.
4. Russelectric, Inc.

B. Manually Operated: Molded case circuit breaker type meeting UL 498. Mechanically interlocked. Manual handles provide quick-make, quick-break manual-switching action. Switch shall be capable of transferring load in either direction with either or both sources energized.

C. Handle cover to prevent unauthorized use.

D. Switch Characteristics: Designed for continuous-duty repetitive transfer of full-rated current between active power sources.

1. Switch Action: Two mechanically interlocked molded case circuit breakers.
2. Contacts: Silver composition or silver alloy for load-current switching.
3. Conductor Connectors: Suitable for use with conductor material and sizes.
4. Material: Tin-plated aluminum or hard-drawn copper, 98 percent conductivity.

5. Main and Neutral Lugs: Mechanical type.
6. Ground Lugs and Bus-Configured Terminators: Mechanical type.
7. Connectors shall be marked for conductor size and type according to UL 1008.

2.4 TRANSFER SWITCH ACCESSORIES

A. Bypass/Isolation Switches:

1. Source Limitations: Same manufacturer as transfer switch in which installed.
2. Comply with requirements for Level 1 equipment according to NFPA 110.
3. Description: Manual type, arranged to select and connect either source of power directly to load, isolating transfer switch from load and from both power sources. Include the following features for each combined automatic transfer switch and bypass/isolation switch:

    a. Means to lock bypass/isolation switch in the position that isolates transfer switch with an arrangement that permits complete electrical testing of transfer switch while isolated. Interlocks shall prevent transfer-switch operation, except for testing or maintenance, while automatic transfer switch is isolated.
    b. Provide means to make power available to transfer-switch control circuit for testing and maintenance purposes.
    c. Drawout Arrangement for Transfer Switch: Provide physical separation from live parts and accessibility for testing and maintenance operations. Transfer switch and bypass/isolation switch shall be in isolated compartments.
    d. Transition:

        1) Provide closed-transition operation when transferring from main transfer switch to bypass/isolation switch on the same power source.

    e. Bypass/Isolation Switch Current, Voltage, Closing, and Short-Circuit Withstand Ratings: Equal to or greater than those of associated automatic transfer switch, and with same phase arrangement and number of poles.
    f. Contact temperatures of bypass/isolation switches shall not exceed those of automatic transfer-switch contacts when they are carrying rated load.
    g. Manual Control: Constructed so load bypass and transfer-switch isolation can be performed by one person in no more than two operations in 15 sections or less. Operating handles must be externally operated.
    h. Automatic and Nonautomatic Control: Automatic transfer-switch controller shall also control the bypass/isolation switch.
    i. Legend: Manufacturer's standard legend for control labels and instruction signs shall describe operating instructions.
    j. Maintainability: Fabricate to allow convenient removal of major components from front without removing other parts or main power conductors.

4. Interconnection of Bypass/Isolation Switches with Automatic Transfer Switches: Factory-installed copper bus bars; plated at connection points and braced for the indicated available short-circuit current.

2.5 SOURCE QUALITY CONTROL

A. Factory Tests: Test and inspect components, assembled switches, and associated equipment according to UL 1008. Ensure proper operation. Check transfer time and voltage, frequency, and time-delay settings for compliance with specified requirements. Perform dielectric strength test complying with NEMA ICS 1.

B. Prepare test and inspection reports.

1. For each of the tests required by UL 1008, performed on representative devices, for systems. Include results of test for the following conditions:

a. Overvoltage.
b. Undervoltage.
c. Loss of supply voltage.
d. Reduction of supply voltage.
e. Alternative supply voltage or frequency is at minimum acceptable values.
f. Temperature rise.
g. Dielectric voltage-withstand; before and after short-circuit test.
h. Overload.
i. Contact opening.
j. Endurance.
k. Short circuit.
l. Short-time current capability.
m. Receptacle withstand capability.
n. Insulating base and supports damage.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Floor-Mounting Switch: Anchor to floor by bolting. Wall-Mounted Switch: Anchor to wall via steel slotted strut support.

1. Install transfer switches on cast-in-place concrete equipment base(s).
2. Provide workspace and clearances required by NFPA 70.

B. Identify components according to Section 260553 "Identification for Electrical Systems."

C. Set field-adjustable intervals and delays, relays, and engine exerciser clock.

D. Comply with NECA 1.

3.2 CONNECTIONS

A. Wiring to Remote Components: Match type and number of cables and conductors to generator sets, motor controls, control, and communication requirements of transfer switches as recommended by manufacturer. Increase raceway sizes at no additional cost to Owner if necessary to accommodate required wiring.

B. Wiring Method: Install cables in raceways and cable trays except within electrical enclosures. Conceal raceway and cables except in unfinished spaces.

1. Comply with requirements for raceways specified in Section 260533.13 "Conduits for Electrical Systems."

C. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii.

D. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."

E. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

F. Connect twisted pair cable according to Section 260523 "Control-Voltage Electrical Power Cables."

G. Route and brace conductors according to manufacturer's written instructions and Section 260529 "Hangers and Supports for Electrical Systems." Do not obscure manufacturer's markings and labels.

H. Final connections to equipment shall be made with liquidtight, flexible metallic conduit no more than 18 inches in length.

I. Provide wiring and connections between the automatic transfer switch engine start modules and the generator engine start module.

3.3 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Test Agency must perform the following tests and inspections:

1. After installing equipment, test for compliance with requirements according to NETA ATS.
2. Visual and Mechanical Inspection:

a. Compare equipment nameplate data with Drawings and Specifications.
b. Inspect physical and mechanical condition.
c. Inspect anchorage, alignment, grounding, and required clearances.
d. Verify that the unit is clean.
e. Verify appropriate lubrication on moving current-carrying parts and on moving and sliding surfaces.
f. Verify that manual transfer warnings are attached and visible.
g. Verify tightness of all control connections.
h. Inspect bolted electrical connections for high resistance using one of the following methods, or both:

1) Use of low-resistance ohmmeter.

2) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method according to manufacturer's published data.

i. Perform manual transfer operation.
j. Verify positive mechanical interlocking between normal and alternate sources.
k. Perform visual and mechanical inspection of surge arresters.
l. Inspect control power transformers.

1) Inspect for physical damage, cracked insulation, broken leads, tightness of connections, defective wiring, and overall general condition.
2) Verify that primary and secondary fuse or circuit-breaker ratings match Drawings.
3) Verify correct functioning of drawout disconnecting contacts, grounding contacts, and interlocks.

3. Electrical Tests:

a. Perform insulation-resistance tests on all control wiring with respect to ground.
b. Perform a contact/pole-resistance test. Compare measured values with manufacturer's acceptable values.
c. Verify settings and operation of control devices.
d. Calibrate and set all relays and timers.
e. Verify phase rotation, phasing, and synchronized operation.
f. Perform automatic transfer tests.
g. Verify correct operation and timing of the following functions:

1) Normal source voltage-sensing and frequency-sensing relays.
2) Engine start sequence.
3) Time delay on transfer.
4) Alternative source voltage-sensing and frequency-sensing relays.
5) Automatic transfer operation.
6) Interlocks and limit switch function.
7) Time delay and retransfer on normal power restoration.
8) Engine cool-down and shutdown feature.

4. Measure insulation resistance phase-to-phase and phase-to-ground with insulation-resistance tester. Include external annunciation and control circuits. Use test voltages and procedure recommended by manufacturer. Comply with manufacturer's specified minimum resistance.

a. Check for electrical continuity of circuits and for short circuits.
b. Inspect for physical damage, proper installation and connection, and integrity of barriers, covers, and safety features.
c. Verify that manual transfer warnings are properly placed.
d. Perform manual transfer operation.

5. After energizing circuits, perform each electrical test for transfer switches stated in NETA ATS and demonstrate interlocking sequence and operational function for each switch at least three times.

a. Simulate power failures of normal source to automatic transfer switches and retransfer from emergency source with normal source available.

b. Simulate loss of phase-to-ground voltage for each phase of normal source.
c. Verify time-delay settings.
d. Verify pickup and dropout voltages by data readout or inspection of control settings.
e. Test bypass/isolation unit functional modes and related automatic transfer-switch operations.
f. Perform contact-resistance test across main contacts and correct values exceeding 500 microhms and values for one pole deviating by more than 50 percent from other poles.
g. Verify proper sequence and correct timing of automatic engine starting, transfer time delay, retransfer time delay on restoration of normal power, and engine cool-down and shutdown.

6. Ground-Fault Tests: Coordinate with testing of ground-fault protective devices for power delivery from both sources.

a. Verify grounding connections and locations and ratings of sensors.

C. Coordinate tests with tests of generator and run them concurrently.

D. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation and contact resistances and time delays. Attach a label or tag to each tested component indicating satisfactory completion of tests.

E. Transfer switches will be considered defective if they do not pass tests and inspections.

F. Remove and replace malfunctioning units and retest as specified above.

G. Prepare test and inspection reports.

3.4 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain transfer switches and related equipment.

B. Training shall include testing ground-fault protective devices and instructions to determine when the ground-fault system shall be retested. Include instructions on where ground-fault sensors are located and how to avoid negating the ground-fault protection scheme during testing and circuit modifications.

C. Coordinate this training with that for generator equipment.

END OF SECTION

SECTION 264113 - LIGHTNING PROTECTION FOR STRUCTURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Lightning protection system for ordinary structures.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each product.

C. Shop Drawings:

1. Include layouts of the lightning protection system, with details of the components to be used in the installation.
2. Include raceway locations needed for the installation of conductors.
3. Details of air terminals, ground rods, ground rings, conductor supports, splices, and terminations, including concealment requirements.
4. Include roof attachment details, coordinated with roof installation.
5. Calculations required by NFPA 780 for bonding of metal bodies.

D. Delegated Design Submittal: In addition to submittals listed above, indicate compliance with performance requirements and design criteria, including analysis data signed and sealed by qualified professional engineers responsible for their preparation.

1. Drawings showing location of each device, and installation details as need to comply with listing conditions of device.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Coordination Drawings: Lightning protection system Shop Drawings, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Lightning protection cabling attachments to roofing systems and accessories.
2. Lightning protection strike termination device attachment to roofing systems, coordinated with the roofing system manufacturer.
3. Lightning protection system components penetrating roofing and moisture protection systems and system components, coordinated with the roofing system manufacturer.

C. Qualification Data: For Installer.

D. Product Certificates: For each type of roof adhesive for attaching the roof-mounted air terminal assemblies, approved by the roofing-material manufacturer.

E. Field quality-control reports.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For lightning protection system to include in maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. Dimensioned site plan showing dimensioned route of the ground loop conductor and the ground rod locations. Comply with requirements of Section 017839 "Project Record Documents."
b. A system testing and inspection record, listing the results of inspections and ground resistance tests, as recommended by NFPA 780, Annex D.

C. Completion Certificate:

1. UL Master Label Certificate.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: UL-listed installer, category OWAY or LPI Master Installer.

PART 2 - PRODUCTS

2.1 LIGHTNING PROTECTION FOR STRUCTURES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ERICO; brand of nVent Electrical plc.
2. East Coast Lightning Equipment Inc.
3. Harger Lightning & Grounding; business of Harger, Inc.
4. Heary Bros. Lightning Protection Co. Inc.
5. Independent Protection Co.
6. National Lightning Protection.
7. Preferred Lightning Protection.
8. Robbins Lightning, Inc.
9. Thompson Lightning Protection, Inc.
10. VFC Lightning Protection.

11. allG Fabrication (formerly ALT).

2.2 PERFORMANCE REQUIREMENTS

A. NFPA Lightning Protection Standard: Comply with NFPA 780 requirements for Class I buildings.

B. UL Lightning Protection Standard: Comply with UL 96A requirements for Class I buildings.

C. Lightning Protection Components, Devices, and Accessories: Listed and labeled by a qualified testing agency as complying with UL 96, and marked for intended location and application.

2.3 MATERIALS

A. Air Terminals:

1. Aluminum unless otherwise indicated.
2. 3/8-inch diameter by 10 inches long.
3. Pointed tip.
4. Integral base support.

B. Air Terminal Bracing:

1. Aluminum.
2. 1/4-inch diameter rod.

C. Class I Main Conductors:

1. Stranded Copper: 27,400 circular mils in diameter.

D. Secondary Conductors:

1. Aluminum: 41,400 circular mils in diameter.

E. Ground Rods:

1. Material: Copper-clad steel.

F. Conductor Splices and Connectors: Compression fittings that are installed with hydraulically operated tools, or exothermic welds, approved for use with the class type.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install lightning protection components and systems according to UL 96A.

B. Install conductors with direct paths from air terminals to ground connections. Avoid bends less than 90 degrees and 8 inches in radius and narrow loops.

C. Conceal conductors within normal view from exterior locations at grade within 200 feet of building. Comply with requirements for concealed installations in UL 96A.

1. Roof penetrations required for down conductors and connections to structural-steel framework shall be made using listed through-roof fitting and connector assemblies with solid rods and appropriate roof flashings. Use materials approved by the roofing manufacturer for the purpose. Conform to the methods and materials required at roofing penetrations of the lightning protection components to ensure compatibility with the roofing specifications and warranty.
2. Install conduit where necessary to comply with conductor concealment requirements.
3. Air Terminals on Single-Ply Membrane Roofing: Comply with adhesive manufacturer's written instructions.

D. Ground Ring Electrode: The conductor shall be not less than the main-size lightning conductor.

3.2 CONNECTIONS

A. Aboveground concealed connections, and connections in earth or concrete, shall be done by exothermic welds or by high-compression fittings listed for the purpose.

B. Aboveground exposed connections shall be done using the following types of connectors, listed and labeled for the purpose: exothermic weld.

C. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance, except where routed through short lengths of conduit.

1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
2. Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install bonding so vibration is not transmitted to rigidly mounted equipment.

3.3 CORROSION PROTECTION

A. Do not combine materials that can form an electrolytic couple that will accelerate corrosion in the presence of moisture unless moisture is permanently excluded from junction of such materials.

B. Use conductors with protective coatings where conditions would cause deterioration or corrosion of conductors.

3.4 FIELD QUALITY CONTROL

A. Special Inspections: Engage a qualified special inspector to perform the following special inspections:

1. Perform inspections as required to obtain a UL Master Label for system.
2. Perform inspections to obtain an LPI certification.

B. Prepare test and inspection reports and certificates.

END OF SECTION

SECTION 264313 – SURGE PROTECTION FOR LOW-VOLTAGE ELECTRICAL POWER CIRCUITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes field-mounted SPDs for low-voltage (120 to 600 V) power distribution and control equipment.

1.3 DEFINITIONS

A. Inominal: Nominal discharge current.

B. MCOV: Maximum continuous operating voltage.

C. Mode(s), also Modes of Protection: The pair of electrical connections where the VPR applies.

D. MOV: Metal-oxide varistor; an electronic component with a significant non-ohmic current-voltage characteristic.

E. OCPD: Overcurrent protective device.

F. SCCR: Short-circuit current rating.

G. SPD: Surge protective device.

H. VPR: Voltage protection rating.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
2. Copy of UL Category Code VZCA certification, as a minimum, listing the tested values for VPRs, Inominal ratings, MCOVs, type designations, OCPD requirements, model numbers, system voltages, and modes of protection.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Field quality-control reports.

C. Sample Warranty: For manufacturer's special warranty.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: For SPDs to include in maintenance manuals.

1.7 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to replace or repair SPDs that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 GENERAL SPD REQUIREMENTS

A. SPD with Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Comply with NFPA 70.

C. Comply with UL 1449.

D. MCOV of the SPD shall be the nominal system voltage.

2.2 SERVICE ENTRANCE AND TRANSFER SWITCH SUPPRESSOR

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB USA.
2. Advanced Protection Technologies Inc. (APT).
3. Eaton.
4. Emerson Electric Co.
5. GE Zenith Controls.
6. LEA International.

7. Leviton Manufacturing Co., Inc.
8. PowerLogics, Inc.
9. Schneider Electric USA, Inc.
10. SIEMENS Industry, Inc.; Energy Management Division.

B. SPDs: Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 1449, Type 1 and Type 2, as indicated.

1. SPDs with the following features and accessories:

a. Integral disconnect switch.
b. Internal thermal protection that disconnects the SPD before damaging internal suppressor components.
c. Indicator light display for protection status.
d. Form-C contacts rated at 5 A and 250-V ac, one normally open and one normally closed, for remote monitoring of protection status. Contacts shall reverse on failure of any surge diversion module or on opening of any current-limiting device. Coordinate with building power monitoring and control system.
e. Surge counter.

C. Comply with UL 1283.

D. Peak Surge Current Rating: The minimum single-pulse surge current withstand rating per phase shall not be less than 200 kA. The peak surge current rating shall be the arithmetic sum of the ratings of the individual MOVs in a given mode.

E. Protection modes and UL 1449 VPR for grounded wye circuits with 480/277 V and 208Y/120 V as indicated, three-phase, four-wire circuits shall not exceed the following:

1. Line to Neutral: 700 V for 208Y/120 V, 1200 V for 480Y/277 V.
2. Line to Ground: 1200 V for 208Y/120 V, 1200 V for 480Y/277 V.
3. Line to Line: 1000 V for 208Y/120 V, 2000 V for 480Y/277 V.

F. SCCR: Equal or exceed 100 kA.

G. Inominal Rating: 20 kA.

2.3 PANEL SUPPRESSORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. ABB USA.
2. Advanced Protection Technologies Inc. (APT).
3. Eaton.
4. Emerson Electric Co.
5. GE Zenith Controls.
6. LEA International.
7. Leviton Manufacturing Co., Inc.

8. PowerLogics, Inc.
9. Schneider Electric USA, Inc.
10. SIEMENS Industry, Inc.; Energy Management Division.

B. SPDs: Comply with UL 1449, Type 1.

1. Include LED indicator lights for power and protection status.
2. Internal thermal protection that disconnects the SPD before damaging internal suppressor components.
3. Include Form-C contacts rated at 5 A and 250-V ac, one normally open and one normally closed, for remote monitoring of protection status. Contacts shall reverse on failure of any surge diversion module or on opening of any current-limiting device. Coordinate with building power monitoring and control system.

C. Peak Surge Current Rating: The minimum single-pulse surge current withstand rating per phase shall not be less than 100 kA. The peak surge current rating shall be the arithmetic sum of the ratings of the individual MOVs in a given mode.

D. Comply with UL 1283.

E. Protection modes and UL 1449 VPR for grounded wye circuits with 480/277 V and 208/120 V, three-phase, four-wire circuits shall not exceed the following:

1. Line to Neutral: 700 V for 208Y/120 V, 1200 V for 480Y/277 V.
2. Line to Ground: 1200 V for 208Y/120 V, 1200 V for 480Y/277 V.
3. Neutral to Ground: 1200 V for 208Y/120 V, 1200 V for 480Y/277 V.
4. Line to Line: 1000 V for 208Y/120 V, 2000 V for 480Y/277 V.

F. SCCR: Equal or exceed 100 kA.

G. Inominal Rating: 20 kA.

2.4 ENCLOSURES

A. Indoor Enclosures: NEMA 250, Type 1.

2.5 CONDUCTORS AND CABLES

A. Power Wiring: Same size as SPD leads, complying with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. Class 2 Control Cables: Multiconductor cable with copper conductors not smaller than No. 18 AWG, complying with Section 260523 "Control Voltage Electrical Power Cables."

C. Class 1 Control Cables: Multiconductor cable with copper conductors not smaller than No. 14 AWG, complying with Section 260523 "Control Voltage Electrical Power Cables."

PART 3 - EXECUTION

3.1 INSTALLATION

A. Comply with NECA 1.

B. Install an OCPD or disconnect as required to comply with the UL listing of the SPD.

C. Install SPDs with conductors between suppressor and points of attachment as short and straight as possible, and adjust circuit-breaker positions to achieve shortest and straightest leads. Do not splice and extend SPD leads unless specifically permitted by manufacturer. Do not exceed manufacturer's recommended lead length. Do not bond neutral and ground.

D. Use crimped connectors and splices only. Wire nuts are unacceptable.

E. Wiring:

1. Power Wiring: Comply with wiring methods in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
2. Controls: Comply with wiring methods in Section 260523 "Control Voltage Electrical Power Cables."

3.2 FIELD QUALITY CONTROL

A. Perform the following tests and inspections with the assistance of a factory-authorized service representative.

1. Compare equipment nameplate data for compliance with Drawings and Specifications.
2. Inspect anchorage, alignment, grounding, and clearances.
3. Verify that electrical wiring installation complies with manufacturer's written installation requirements.

B. An SPD will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.3 STARTUP SERVICE

A. Complete startup checks according to manufacturer's written instructions.

B. Do not perform insulation-resistance tests of the distribution wiring equipment with SPDs installed. Disconnect SPDs before conducting insulation-resistance tests, and reconnect them immediately after the testing is over.

C. Energize SPDs after power system has been energized, stabilized, and tested.

3.4 DEMONSTRATION

A. Train maintenance personnel to operate and maintain SPDs.

END OF SECTION

SECTION 265000 - LIGHTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Luminaires.
2. Luminaire fittings.

B. Related Requirements:

1. Section 018116 "Facility Environmental Requirements" specifies basis-of-design environmental conditions and performance criteria that are applicable to product selection and installation of the Work on the Project.
2. Section 260010 "Supplemental Requirements for Electrical" specifies additional requirements applicable to coordinating, scheduling, and sequencing of the Work specified in this Section.
3. Section 260519 "Low-Voltage Electrical Power Conductors and Cables" and Section 260523 "Control-Voltage Electrical Power Cables" specifies wiring connections installed by this Section.
4. Section 260529 "Hangers and Supports for Electrical Systems" specifies channel and angle supports installed by this Section.
5. Section 260553 "Identification for Electrical Systems" specifies electrical equipment labels and warning signs installed by this Section.
6. Section 260923 "Lighting Control Devices" specifies automatic control of lighting, including time switches, photoelectric relays, occupancy sensors, and multipole lighting relays and contactors installed by this Section.

1.2 DEFINITIONS

A. BUG Rating: Backlight, uplight, and glare rating for light pollution from exterior luminaires.

B. Correlated Color Temperature (CCT): The absolute temperature (in kelvins) of a blackbody whose chromaticity (color quality) most nearly resembles that of the light source.

C. Color Rendering Index (CRI): The measure of the degree of color shift objects undergo when illuminated by the light source as compared with the color of those same objects when illuminated by a reference light source. The lower the CRI of a light source, the more difficult it is to identify colors and stripes on electronic components and wiring.

D. IDA: International Dark-Sky Association.

E. IES: Illuminating Engineering Society.

F. LPD: Lighting power density.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Luminaires: Include the following additional information:

a. Product Listing: Include copy of unexpired approval letter, on letterhead of qualified electrical testing agency, certifying product's compliance with specified listing criteria.

1) If listed manufacturer differs from selling manufacturer, indicate relationship between entities on submittal. Clearly indicate which entity warrants product performance and fitness for purpose.
2) Listing criteria identified in approval letter must match specified listing criteria. Approval of only equipment's enclosure is not considered approval of equipment for intended application.
3) Product identification in approval letter must match product branding and model numbers in submittal. Approval letters for similar products are not acceptable.

b. Product Certificates: Include product certificates stating compliance with standards listed below, signed by manufacturer or fabricator.

1) Manufacturers' Certified Data: Photometric data certified by manufacturer's laboratory with current accreditation under National Voluntary Laboratory Accreditation Program (NVLAP) for Energy Efficient Lighting Products.
2) Testing Agency Certified Data: For luminaires indicated on Lighting Fixture Schedule on the Drawings, photometric data certified by qualified independent testing laboratory. Photometric data for remaining luminaires must be certified by manufacturer.

c. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
d. Include operating characteristics, electrical characteristics, and furnished accessories.
e. Include schedule of submitted lighting products. Arrange schedule and accompanying product data in order by luminaire and lamp designations indicated on the Drawings.
f. Include battery and charger data for emergency lighting units.
g. Include ballast factor.
h. Include life, output (lumens, CCT, and CRI), and energy-efficiency data.
i. Include photometric data and adjustment factors obtained from qualified laboratory tests.
j. Include manufacturer's sample warranty language.

2. Luminaire Fittings: Include the following additional information:

a. Product Listing: Include copy of unexpired approval letter, on letterhead of qualified electrical testing agency, certifying product's compliance with specified listing criteria.

1) If listed manufacturer differs from selling manufacturer, indicate relationship between entities on submittal. Clearly indicate which entity warrants product performance and fitness for purpose.
2) Listing criteria identified in approval letter must match specified listing criteria. Approval of only equipment's enclosure is not considered approval of equipment for intended application.
3) Product identification in approval letter must match product branding and model numbers in submittal. Approval letters for similar products are not acceptable.

b. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
c. Include operating characteristics, electrical characteristics, and furnished accessories.
d. Include schedule of submitted lighting products. Arrange schedule and accompanying product data in order by luminaire and lamp designations indicated on the Drawings.
e. Include manufacturer's sample warranty language.

C. Shop Drawings: Prepare and submit the following:

1. Drawings, Diagrams, and Supporting Documents for Custom Luminaires:

a. Include plans, elevations, sections, and mounting and attachment details.
b. Include details of luminaire assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
c. Include diagrams for power, signal, and control wiring.

D. Sustainable Design Submittals:

1. Product data for sustainable design features for each type of product.
2. ASHRAE/IES 90.1 LPD Compliance Documentation: Prepare plans and calculations demonstrating that as-constructed lighting power density complies with mandatory provisions of ASHRAE/IES 90.1 and that as-constructed lighting, including daylighting and controls, improves on baseline energy performance. If included with the Project, indicate locations of energy meters for lighting loads.

E. Field quality-control reports.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturers' published instructions.

C. Field Reports:

1. Manufacturer's field reports for field quality-control support.
2. Manufacturer's field reports for system startup support.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Warranty documentation.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Protect exposed surface finishes on lighting equipment by applying strippable, temporary protective covering before shipping.

1.7 WARRANTY FOR LUMINAIRES

A. Special Manufacturer Extended Warranty: Manufacturer warrants that luminaires perform in accordance with specified requirements and agrees to provide repair or replacement of products that fail to perform as specified within extended-warranty period.

1. Extended-Warranty Period: Five years from date of Substantial Completion; full coverage for labor, materials, and equipment.

1.8 WARRANTY FOR BATTERIES

A. Special Manufacturer Extended Warranty for Batteries: Manufacturer warrants that batteries perform in accordance with specified requirements and agrees to provide repair or replacement of batteries that fail to perform as specified within extended-warranty period.

1. Initial Extended-Warranty Period for Li-ion Batteries: Three years from date of Substantial Completion; full coverage for materials only, free on board origin, freight prepaid.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Products or components listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

B. Provide products listed in lighting fixtures schedule. Fixtures in schedule are basis of design. Alternate fixtures are acceptable provided the alternate meets the performance and aesthetic standards of the basis of design.

2.2 LUMINAIRES

A. Luminaire:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

    a. Albeo; brand of GE Current, a Daintree company; American Industrial Partners (AIP).
    b. Alera Lighting; brand of GE Current, a Daintree company; American Industrial Partners (AIP).
    c. Amerlux.
    d. Architectural Area Lighting; brand of GE Current, a Daintree company; American Industrial Partners (AIP).
    e. Atlas Lighting Products.
    f. Columbia Lighting; brand of GE Current, a Daintree company; American Industrial Partners (AIP).
    g. Cooper Lighting Solutions; Signify North America Corp.
    h. Deco Lighting.
    i. Digital Lumens.
    j. E-conolight.
    k. Kim Lighting; brand of GE Current, a Daintree company; American Industrial Partners (AIP).
    l. LMPG Inc.
    m. Lighting Services, Inc.
    n. Lightolier; brand of Signify North America Corp.
    o. Lithonia Lighting; Acuity Brands Lighting, Inc.
    p. Luraline Lighting.
    q. OSRAM SYLVANIA.
    r. Philips; Signify North America; Signify Holding.
    s. Pure Lighting Manufacturing Ltd.
    t. PureEdge Lighting.
    u. RAB Lighting.
    v. Selux Corporation.
    w. Specialty Lighting Industries, Inc.
    x. Visa Lighting.
    y. West Durable Lighting.
    z. Zumtobel Lighting, Inc.; Zumtobel Group.
2. Listing Criteria:

    a. LED Luminaires: UL CCN IFAM; including UL 1598.
    b. Marked in accordance with UL CCN HYXT, including UL 1598, for compatible power supply, installation location, and environmental conditions.

3. Luminaire Description: .
4. Standard Features:

a. Openings: Doors, frames, and access panels must operate smoothly, not leak light under operating conditions, and permit relamping without use of tools or parts falling from enclosure.
b. Nominal Operating Voltage: 120 V(ac) 277 V(ac).
c. CRI: 80+.
d. Ballast or Driver Location: Internal Remote.

e. LED Luminaires (UL CCN IFAM):

1) Output Intensity: As indicated in lighting fixture schedule.
2) Rated Life: 50 000 hours to L70.
3) CCT: As indicated in lighting fixture schedule.

5. Sustainable Design Features:

a. Mercury Content: For fluorescent, mercury vapor, metal halide, high-pressure-sodium, neon, and argon lamps, submit data indicating mercury content and lamp life.
b. Backlight, Uplight, and Glare (BUG) Ratings: Exterior luminaire meets IES LM-11 recommended BUG ratings at luminaire's intended location.
c. IDA/IES Five Principles Ready:

1) Exterior luminaire is adjustable to illuminate only to extent necessary for its intended purpose.
2) Exterior luminaire is aimable.
3) Exterior luminaire is dimmable.
4) Exterior luminaire is controllable to turn on only when needed.
5) Exterior luminaire has warm color temperature.

d. Corporate Sustainability Report: Third-party verified corporate sustainability report is publicly available from manufacturer, which includes environmental impacts of extraction operations and activities associated with product and its supply chain.
e. Regional Materials (LEED): Provide documentation if product is sourced (extracted, manufactured, purchased) within 100 mi of the Project site.

B. UL FTBR or FTBV - Emergency Lighting and Power Equipment:

1. Standard Features:

a. Charger: Fully automatic, solid-state, constant-current type with sealed power transfer relay.
b. Status and Test Indication: Visible and accessible without opening luminaire or entering ceiling space.

1) Indicator Light: LED indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.
2) Test Push-Button: Push-to-test button in unit housing simulates loss of normal power and demonstrates unit operability.

c. Nominal Operating Voltage: 120 V(ac) 277 V(ac).
d. Mounting: Wall with universal junction box adaptor.

2. Sustainable Design Features:

   a. Mercury Content: For fluorescent, mercury vapor, metal halide, high-pressure-sodium, neon, and argon lamps, submit data indicating mercury content and lamp life.
   b. Corporate Sustainability Report: Third-party verified corporate sustainability report is publicly available from manufacturer, which includes environmental impacts of extraction operations and activities associated with product and its supply chain.
   c. Regional Materials (LEED): Provide documentation if product is sourced (extracted, manufactured, purchased) within 100 mi of the Project site.

3. Other Available Features Required by the Project:

   a. External-Type Emergency Power Unit: Self-contained, modular, battery-inverter unit, suitable for powering one or more lamps, remote mounted from luminaire.

      1) Emergency Connection: Operate continuously. Connect unswitched circuit to battery-inverter unit and switched circuit to luminaire driver.
      2) Operation: Relay automatically turns lamp on when power-supply circuit voltage drops to 80 percent of nominal voltage or below. Lamp automatically disconnects from battery when voltage approaches deep-discharge level. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
      3) Battery Type: Ni-Cd.
      4) Charger: Fully automatic, solid-state, constant-current type.
      5) Housing: Type 1 enclosure listed for installation inside, on top of, or remote from luminaire. Remote assembly must be located no less than half of distance recommended by driver manufacturer, whichever is less.
      6) Test Push-Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
      7) LED Indicator Light: Indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.
      8) Remote Test: Switch in handheld remote device aimed in direction of tested unit initiates coded infrared signal. Signal reception by factory-installed infrared receiver in tested unit triggers simulation of loss of its normal power supply, providing visual confirmation of either proper or failed emergency response.

C. UL FWBO - Exit Fixture:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

   a. Amerlux.
   b. Cooper Lighting Solutions; Signify North America Corp.
   c. Evenlite, Inc.
   d. Hubbell Lighting; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
   e. Lithonia Lighting; Acuity Brands Lighting, Inc.
   f. Philips; Signify North America; Signify Holding.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria:

    a. Exit Fixtures: UL CCN FWBO; including UL 924, NFPA 101, NFPA 5000, and ICC IBC.
    b. Marked in accordance with UL CCN HYXT, including UL 1598, for compatible power supply, installation location, and environmental conditions.

4. Standard Features:

    a. Nominal Operating Voltage: 120 V(ac) 277 V(ac).
    b. Light Source: LED; 50,000 hours minimum rated life.
    c. Legend Color: Red.
    d. Internal emergency power unit.
    e. Battery Type: Ni-Cd.

5. Sustainable Design Features:

    a. Mercury Content: For fluorescent, mercury vapor, metal halide, high-pressure-sodium, neon, and argon lamps, submit data indicating mercury content and lamp life.
    b. Corporate Sustainability Report: Third-party verified corporate sustainability report is publicly available from manufacturer, which includes environmental impacts of extraction operations and activities associated with product and its supply chain.
    c. Regional Materials (LEED): Provide documentation if product is sourced (extracted, manufactured, purchased) within 100 mi of the Project site.

2.3 LUMINAIRE FITTINGS

A. Luminaire Support Accessories:

1. Standard Features:

    a. Sized and rated for luminaire weight.
    b. Capable of maintaining luminaire position after cleaning and relamping.
    c. Capable of supporting luminaire without causing deflection of ceiling or wall.
    d. Capable of supporting horizontal force equal to 100 percent of luminaire weight and vertical force equal to 400 percent of luminaire weight.

2. Sustainable Design Features:

    a. Corporate Sustainability Report: Third-party verified corporate sustainability report is publicly available from manufacturer, which includes environmental impacts of extraction operations and activities associated with product and its supply chain.
    b. Regional Materials (LEED): Provide documentation if product is sourced (extracted, manufactured, purchased) within 100 mi of the Project site.

3. Other Available Features Required by the Project:

a. Wires: ASTM A641/A641M, Class 3, soft temper, zinc-coated steel, 12 gage wire supports adjustable in length.
b. Aircraft Cables: 5/32 inch diameter aircraft cable supports adjustable to in length.
c. Single-Stem Hangers: 1/2 inch nominal diameter steel tubing with swivel ball fittings and ceiling canopy. Finish same as luminaire.
d. Rod Hangers: 3/16 inch nominal diameter, cadmium-plated, threaded steel rod.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for luminaire to verify actual locations of luminaire and electrical connections before luminaire installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF LIGHTING

A. Comply with manufacturer's published instructions.

B. Reference Standards for Installation: Unless more stringent installation requirements are specified in Contract Documents or manufacturers' published instructions, comply with the following:

1. Electrical Construction: ICC IBC, ICC IFC, NFPA 1, NFPA 70, and NECA NEIS 1.
2. Grounding and Bonding: NECA NEIS 331 and Article 250 of NFPA 70.
3. Work in Confined Spaces: NFPA 350.
4. Work in Basements and Other Developed Subterranean Spaces: NFPA 520.
5. Installation of Indoor Lighting Systems: NECA NEIS 500.
6. Installation of Exterior Lighting Systems: NECA NEIS 501.
7. Installation of Luminaires, Lampholders, and Lamps: Article 410 of NFPA 70.
8. Installation of Lighting for Sensitive Electronic Equipment: Article 647 of NFPA 70.
9. Installation of Emergency Lighting and Exit Signs: ICC IBC, NFPA 101, and Parts IV and V in Article 700 of NFPA 70.
10. Consult Architect for resolution of conflicting requirements.

C. Special Installation Techniques:

1. Install luminaires level, plumb, and square with finished floor or grade unless otherwise indicated.
2. Install luminaires at height and aiming angle as indicated on the Drawings.
3. Coordinate layout and installation of luminaires with other construction.
4. Exterior Bollard and Pole Mounted Luminaires:

a. Align units for optimum directional alignment of light distribution.
b. Refer to civil drawings for site fixture installation details.

5. Exterior Corrosion Prevention:

    a. Do not use aluminum in contact with earth or concrete. When in direct contact with dissimilar metals, protect aluminum with insulating fittings or treatment.
    b. When embedding steel conduits in concrete, wrap conduit with 10 mil thick, pipe-wrapping plastic tape applied with a 50 percent overlap.

6. Flush-Mounted Luminaire Support:

    a. Secured to outlet box.
    b. Attached to ceiling structural members at four points equally spaced around circumference of luminaire.
    c. Trim ring flush with finished surface.

7. Wall-Mounted Luminaire Support: Attached to structural members in walls.

    a. Do not attach luminaires directly to gypsum board.

8. Suspended Luminaire Support:

    a. Ceiling Mount:

        1) Two wires.
        2) Two aircraft cables.

    b. Pendants and Rods: Where longer than 48 inch, brace to limit swinging.
    c. Stem-Mounted, Single-Unit Luminaires: Suspend with twin-stem hangers. Support with approved outlet box and accessories that hold stem and provide damping of luminaire oscillations. Support outlet box vertically to building structure using approved devices.
    d. Continuous Rows of Luminaires: Provide tubing or stem for wiring at one point and wire support for suspension for each unit length of luminaire chassis, including one at each end.
    e. Do not use ceiling grid as support for pendant luminaires. Connect support wires or rods to building structure.

9. Ceiling-Grid-Mounted Luminaire Support:

    a. Install ceiling support system rods or wires, independent of the ceiling suspension devices, for each luminaire. Locate not more than 6 inch from luminaire corners.
    b. Support Clips: Fasten to luminaires and to ceiling grid members at or near each luminaire corner with clips that are UL listed for application.
    c. Luminaires of Sizes Smaller than Ceiling Grid: Install as indicated on reflected ceiling plans or center in acoustical panel, and support luminaires independently with no fewer than two 3/4 inch metal channels spanning and secured to ceiling tees.

10. Remote Mounting of Ballasts or Drivers: Do not exceed distance between ballast or driver and luminaire recommended by ballast or driver manufacturer.
11. Emergency Power Units: Secure with approved fasteners in four or more locations, spaced near corners of unit.
12. Install wiring connections for luminaires.

13. Identification: Provide labels for luminaires and associated electrical equipment.

    a. Identify field-installed conductors, interconnecting wiring, and components.
    b. Provide warning signs.
    c. Label each enclosure with engraved metal or laminated-plastic nameplate.

D. Systems Integration: Integrate lighting control devices and equipment with electrical power connections for operation of luminaires as specified.

3.3 FIELD QUALITY CONTROL OF LIGHTING

A. Tests and Inspections:

1. Perform manufacturer's recommended tests and inspections.
2. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
3. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery power and retransfer to normal.
4. Verify operation of photoelectric controls.
5. Exterior Illumination Tests:

    a. Measure light intensities at night. Use photometers with calibration referenced to NIST standards.

B. Nonconforming Work:

1. Luminaire will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

C. Field Quality-Control Reports: Collect, assemble, and submit test and inspection reports.

3.4 SYSTEM STARTUP

A. Perform startup service.

1. Complete installation and startup checks in accordance with manufacturer's published instructions.
2. Charge emergency power units and batteries minimum of 24 hours and conduct one-hour discharge test.

3.5 ADJUSTING

A. Luminaire Aiming Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting aiming direction of luminaires to suit occupied conditions. Make up to two visits to the Project's site during other-than-normal hours for this purpose. Some of the Work may be required during hours of darkness.

1. During adjustment visits, inspect all luminaires. Replace lamps or luminaires that are defective.

2. Parts and supplies must be manufacturer's authorized replacement parts and supplies.
3. Adjust aim of luminaires in presence of Architect.

3.6 CLOSEOUT ACTIVITIES

A. Training:

1. Train Owner's maintenance personnel on the following topics:

a. How to adjust, operate, and maintain luminaires.

3.7 PROTECTION

A. After installation, protect lighting equipment from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

END OF SECTION

Electrical Requirements and recommendations
These are not intended to overrule any NEC code requirement.
2025

Remove all abandoned not in use wiring, devices and equipment to source of supply.

Remove exposed abandoned conduit, BX, MC, romex, and boxes, including above accessible ceilings.

Disconnect and remove all abandoned straps, clips, outlets and devices.

Install blank covers where needed.

All feeders and branch circuits SHALL BE stranded wire. Except in MC.

Use type THHN/THWN or XHHW-2 for panel board feeds

Wire shall not be smaller than 12 AWG for power and lighting circuits, and not smaller than 18 AWG for control wiring.

Color code all service, and feeders.

Branch circuits shall be color-coded the entire run or at every junction box.

Color code ungrounded conductors operating at 120 volts to ground black, red and blue for phases A, B, and C and at 277 volts, brown, orange and yellow respectively.

Use a separate neutral for each circuit and label the circuit number in every panelboard, gutter,
Pull box, outlet and junction boxes, and at each load connection.

Install wire markers on each conductor in panelboards, gutters, pull boxes, outlet and junction boxes, and at load connections.

Use 10 AWG conductors for 20 amperes, 120-volt branch circuit home runs longer than 75 feet; and for 20 amperes, 277-volt branch circuit home runs longer than 200 feet.

No time clocks at ALL

One photo cell and it shall be Fisher Pierce, Mod. 7790B-SSS, 105-285VAC. To control lighting contactor that shall be Cutler-Hammer Eaton ECC04C8A8A

Auto/Off/Manual ON” Switch on contactor to by-pass photo cell for all exterior lights

Use ONLY Chloride CMF25WWTB2 Emergency Lighting Battery Units or EQUIVALENT,and connect to lighting circuit associated with the location of emergency light.
No battery backup Exit Signs in buildings if connected to generator.

All Honeywell, Security, Fire panels and devices SHALL BE connected to generator, if generator is connected to building.

All egress lighting and exit signs SHALL BE connected to generator if gen is connected to building.

If generator is not available the use of battery drivers (bodine) is not permitted.

All lighting in rooms should be controlled with occupancy/vacancy motion sensors .Electrical rooms and mechanical spaces shall have hard wired switching .
Stairwells shall have motion sensor lighting with 10% light until motion is detected than 100% light.
No Bluetooth lighting controls will be allowed.

All interior lights shall be dimmable. 35k in office areas, 40k in lobby's, mechanical rooms and stair wells.

Main Electrical Distribution Panelboard SHALL BE Square D. I-Line.

All Electrical Distribution Panelboard breakers SHALL BE professionally labeled

A ION6200 PowerLogic meter SHALL BE installed on All Main Electrical Panel boards with voltage sensor leads connected under main voltage lugs and connected to the Ethernet. Schneider rep will program and setup meters and setup communications with PowerLogic server.

A ION 6200 PowerLogic meter, CT's and Enclosure, Part # 9761E622R1G0B1B, SHALL BE installed on ALL generator transfer switches and connected to load side with voltage sensor leads connected under main voltage lugs. Connected to the Ethernet. Schneider rep will program and setup meters and setup communications, Logging, Alarm limits as all other existing devices are on PowerLogic server.

All Power & Lighting Panelboards SHALL BE Square D. ONLY. NQOD ONLY.

All Electrical panelboard covers, surface trims, SHALL BE hinged.

All electrical panel breaker spaces on index cards SHALL BE labeled with room numbers that they feed

All Circuit Breakers, except Square D I Line, SHALL BE two forms of visible trip indication. The breaker handle shall reside in a position between On and Off. In addition, there SHALL BE a red VISI-TRIP indicator appearing in the clear window of the circuit breaker housing.

All Conductors feeding Main Panels and all panels shall be copper conductors, not Aluminum.

Arc Flash study on whole building

Arc Flash labels with study ratings for that device printed on each label on exterior of ALL panels and disconnects

NEC 70E Study SHALL BE done
And:
A. Apply one arc-flash label with study ratings for that device printed on each label for 600-V ac, 480-V ac, and applicable 208-V ac panelboards and disconnects and for each of the following locations:
1. Motor-control center. 2. Low-voltage switchboard. 3. Switchgear. 4. Medium-voltage switch. 5. Control panel.

All switches, receptacles and plates SHALL BE Ivory or Brown in color. No white

All Receptacles SHALL BE labeled with Panel ID and Circuit Number with Label Maker on exterior of cover.

Four spare 3/4" conduits extended above ceiling in EVERY electrical panelboard.

All motor starters SHALL BE Square D

All disconnects SHALL BE Square D

All VFD's SHALL BE Square D

No “Hand Holes” or underground splices. Use above ground boxes on pedestals or mounted to building.

All Lighting shall be LED,

No inground lighting of any kind.

Each stairwell landing shall have a receptacle

Each hallway shall have a receptacle at least every 25 feet

No interior light fixtures installed out of reach of 8’ step ladder for instance over stairways, the intent here is to be able to fix light without renting a lift or using cherry picker to reach light

Parking lot lighting shall be:
Lithonia DSXOLED40C 700 50K T5M MVOLT SPUMBA DDBXD

East Campus sidewalk poles shall be:
Holophane Unique Solutions Washington Postlite
Cat# WA175MH27A3A4-F1, was MH, All have been changed LED with TOPAZ LPT80/850/INT/E39 bulbs
13’-6” Ridgefield cast iron steel pole
Cat# RF14/16-C15/RAL6014
16” Dia. Base

No Electric Hand Dryers

All mod-furniture electrically hard wired to building shall be wired by contractor

All break rooms with kitchenettes or counters for microwaves and toasters shall have at least four dedicated circuits/receptacles above counters.

There will be no lighting controls operated by Bluetooth technology.

SECTION 271100 - COMMUNICATIONS EQUIPMENT ROOM FITTINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Backboards.
2. Boxes, enclosures, and cabinets.

B. Related Requirements:

1. Section 260536 "Cable Trays for Electrical Systems" for cable trays and accessories.
2. Section 260526 “Grounding and Bonding for Electrical Systems.”

1.3 DEFINITIONS

A. Access Provider: An operator that provides a circuit path or facility between the service provider and user. An access provider can also be a service provider.

B. BICSI: Building Industry Consulting Service International.

C. Service Provider: The operator of a telecommunications transmission service delivered through access provider facilities.

D. TGB: Telecommunications grounding bus bar.

E. TMGB: Telecommunications main grounding bus bar.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for equipment racks and cabinets.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

C. Shop Drawings: For communications equipment room fittings. Include plans, elevations, sections, details, and attachments to other work.

1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
2. Equipment Racks and Cabinets: Include workspace requirements and access for cable connections.
3. Grounding: Indicate location of grounding bus bar and its mounting detail showing standoff insulators and wall mounting brackets.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Qualification Data: For Installer, qualified layout technician, installation supervisor, and field inspector.

PART 2 - PRODUCTS

2.1 BACKBOARDS

A. Backboards: Plywood, fire-retardant treated, 3/4 by 48 by 96 inches.

B. Backboard Paint: Black fire-retardant paint.

2.2 GROUND BUS

A. Provide TMGB and TGB in communications rooms.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Comply with NECA 1.

B. Comply with BICSI's "Telecommunications Distribution Methods Manual" for layout of communications equipment spaces.

C. Comply with BICSI's "Information Technology Systems Installation Methods Manual" for installation of equipment in communications equipment spaces.

D. Coordinate location of power raceways and receptacles with locations of communications equipment requiring electrical power to operate.

E. Backboards:

1. Install from 6 inches to 8 feet, 6 inches above finished floor. Ensure that fire-rating stamp is visible after installation.
2. Paint all sides of backboard with two coats of paint, leaving fire rating stamp visible.
3. Comply with requirements for backboard installation in BICSI's "Information Technology Systems Installation Methods Manual" and TIA-569-D.

3.2 FIRESTOPPING

A. Comply with requirements in Section 078413 "Penetration Firestopping."

B. Comply with TIA-569-D, Annex A, "Firestopping."

C. Comply with BICSI's "Information Technology Systems Installation Methods Manual," "Firestopping Practices" Ch.

END OF SECTION

SECTION 271323 - COMMUNICATIONS OPTICAL FIBER BACKBONE CABLING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Type OFNP optical fiber cable.
2. Optical fiber cable connecting hardware, patch panels, and cross-connects.

1.2 DEFINITIONS

A. Conductive Cable: Cable containing non-current-carrying electrically-conductive members such as metallic strength members and metallic vapor barriers.

B. Cross-Connect: A facility enabling termination of cable elements and their interconnection or cross-connection.

C. Type OFNP: Nonconductive cable for use in plenums, ducts, and other spaces used for environmental air.

1.3 COORDINATION

A. Coordinate layout and installation of telecommunications pathways and cabling with Owner's telecommunications and LAN equipment and service suppliers.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data:

1. For each type of product.

C. Shop Drawings:

1. System Labeling Schedules:

a. Electronic copy of labeling schedules that are part of cabling and asset identification system of software.

2. Cabling administration drawings and printouts.
3. Wiring diagrams showing typical schematic arrangement, including the following:

a. Telecommunications rooms plans and elevations.
b. Telecommunications pathways.
c. Telecommunications system access points.
d. Telecommunications grounding system.
e. Cross-connects.
f. Patch panels.
g. Patch cords.

4. Cross-Connect and Patch-Panel Drawings: Detail mounting assemblies and show elevations and physical relationship between installed components.

D. Certificates:

1. For each type of product.

E. Field Quality-Control Submittals:

1. Optical fiber cable testing plan.
2. Field quality-control reports.

F. Sustainable Design Submittals:

1. Product Data: For each conductor and cable indicating lead content.
2. Environmental Product Declaration: For each product.
3. Health Product Declaration: For each product.
4. Sourcing of Raw Materials: Corporate sustainability report for each manufacturer.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Source Quality-Control Submittals:

1. Source quality-control reports.

1.6 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Maintenance Data: For optical fiber cable, splices, and connectors.

C. Maintenance Contracts:

1. Software service agreement.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Environmental Limitations: Do not deliver or install cables and connecting materials until wet-work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during remainder of construction period.

B. Test cables upon receipt at Project site.

1. Test optical fiber cable to determine continuity of strand end to end. Use optical fiber flashlight or optical loss test set.
2. Test optical fiber cable while on reels. Use optical time domain reflectometer to verify cable length and locate cable defects, splices, and connector, including loss value of each. Retain test data and include record in maintenance data.

PART 2 - PRODUCTS

2.1 TYPE OFNP OPTICAL FIBER CABLE

A. Description: This category covers jacketed optical fiber cable for use in vertical runs in plenums, ducts, or other spaces used for environmental air within buildings in accordance with Article 770 of NFPA 70 containing no electrically conductive materials.

B. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Listing Criteria: UL CCN QAYK; including UL 1651.
3. General Characteristics:

a. Performance: TIA-568.3.
b. Inside Plant Mechanical Properties: ICEA S-83-596.
c. Inside-Outside Plant Mechanical Properties: ICEA S-104-696.
d. Jacket:

1) Cable cordage jacket, fiber, unit, and group color in accordance with TIA-598.
2) Imprinted with fiber count, fiber type, and aggregate length at regular intervals not to exceed 40 inch.

C. Type OFNP, Designation OM4, Multimode Optical Fiber Cable:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Belden Inc.
b. CommScope, Inc.

c. Corning Optical Communications; Corning Incorporated.
d. Hitachi Cable America Inc.
e. Mohawk; a division of Belden Networking, Inc.
f. Superior Essex Inc.; subsidiary of LS Corp.
g. TE Connectivity Ltd.

2. Source Limitations: Obtain products from single manufacturer.
3. Additional Characteristics:

a. Construction: TIA-492AAAD; 850 nm laser-optimized, 50 µm core diameter, 125 µm cladding diameter.
b. Minimum Overfilled Modal Bandwidth-Length Product: 3500 MHz-km at 850 nm wavelength; 500 MHz-km at 1300 nm wavelength.
c. Minimum Effective Modal Bandwidth-Length Product: 4700 MHz-km at 850 nm wavelength.

4. Options:

a. Configuration: 12-fiber, tight buffer, optical fiber cable.
b. Maximum Attenuation: 3.50 dB/km at 850 nm wavelength; 1.5 dB/km at 1300 nm wavelength.
c. Jacket Color: Aqua.

2.2 OPTICAL FIBER CABLE HARDWARE

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. American Technology Systems Industries, Inc.
2. Bel Fuse Inc.
3. Belden Inc.
4. Berk-Tek, a Leviton Company.
5. CommScope, Inc.
6. Corning Optical Communications; Corning Incorporated.
7. Dynacom Corporation.
8. Hubbell Premise Wiring; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
9. Molex Premise Networks.
10. Optical Cable Corporation (OCC).
11. Siemon Co. (The).

B. Performance Criteria:

1. Fiber Optic Connector Intermateability Standard (FOCIS) specifications of TIA-604 series.
2. TIA-568.3.

C. Cross-Connects and Patch Panels: Modular panels housing multiple-numbered, duplex cable connectors.

1. Number of Connectors per Field: One for each fiber of cable or cables assigned to field, plus spares and blank positions adequate to suit specified expansion criteria.

D. Patch Cords: Factory-made, dual-fiber cables in 36 inch lengths.

E. Connector Type: Coordinate with building IT staff for fiber optic connector type.

F. Plugs and Plug Assemblies:

1. Male; color-coded modular telecommunications connector designed for termination of single optical fiber cable.
2. Insertion loss not more than 0.25 dB.
3. Marked to indicate transmission performance.

G. Jacks and Jack Assemblies:

1. Female; quick-connect, simplex and duplex; fixed telecommunications connector designed for termination of single optical fiber cable.
2. Insertion loss not more than 0.25 dB.
3. Marked to indicate transmission performance.
4. Designed to snap-in to patch panel or faceplate.

2.3 SOURCE QUALITY CONTROL

A. Owner will witness required factory tests. Notify Architect at least 14 days before date of tests and indicate their approximate duration.

B. Testing Administrant: Engage qualified testing agency to evaluate cables.

C. Factory Tests and Inspections:

1. Test and inspect multimode optical fiber cables, by, or under supervision of, qualified electrical testing laboratory recognized by authorities having jurisdiction, in accordance with TIA-526-14 and TIA-568.3 before delivering to site. Affix label with name and date of manufacturer's certification of system compliance.
2. Test and inspect pre-terminated optical fiber cable assemblies, by, or under supervision of, qualified electrical testing laboratory recognized by authorities having jurisdiction, in accordance with TIA-526-14 and TIA-568.3 before delivering to site. Affix label with name and date of manufacturer's certification of system compliance.

D. Nonconforming Work:

1. Cables that do not pass tests and inspections will be considered defective.

E. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 PREPARATION

A. Coordinate backbone cabling with protectors and demarcation point provided by communications service provider.

3.2 SELECTION OF OPTICAL FIBER TYPE

A. Installed in Vertical Shaft or Floor-to-Floor Riser:

1. Nonconductive:

a. Type OFNP.

B. Installed in Plenum, Duct, or Other Space Handling Environmental Air:

1. Nonconductive:

a. Type OFNP.

C. Installed in Location Other Than Riser or Plenum:

1. Nonconductive: Type OFNP in metallic conduit.

3.3 INSTALLATION OF OPTICAL FIBER BACKBONE CABLES

A. Optical fiber backbone cabling system must provide interconnections between communications equipment rooms, main terminal space, and entrance facilities in telecommunications cabling system structure. Cabling system consists of backbone cables, intermediate and main cross-connects, mechanical terminations, and patch cords or jumpers used for backbone-to-backbone cross-connection.

B. Backbone cabling cross-connects may be located in communications equipment rooms or at entrance facilities. Bridged taps and splitters may not be used as part of backbone cabling.

C. Comply with BICSI N1, NECA NEIS 1, and NECA NEIS 301.

D. Backbone cabling system must comply with transmission standards in TIA-568.1.

E. Telecommunications Pathways and Spaces: Comply with TIA-569.

F. Wiring Methods:

1. Not in Raceway: Conceal conductors and cables in accessible ceilings, walls, and floors where possible.

a. Install plenum cable in environmental airspaces, including plenum ceilings.

b. Comply with requirements for pathways specified in Section 270528 "Pathways for Communications Systems."

2. In Enclosures: Bundle, lace, and train cables within enclosures. Connect to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools.

G. Optical Fiber Cabling Installation:

1. Comply with TIA-568.1 and TIA-568.3.
2. Comply with BICSI ITSIMM, Ch. 6, "Cable Termination Practices."
3. Terminate all cables; no cable may contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.
4. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inch and not more than 6 inch from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
5. Install lacing bars to restrain cables, to prevent straining connections, and to prevent bending cables to smaller radii than minimums recommended by manufacturer.
6. Bundle, lace, and train cable to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIMM, "Cabling Termination Practices" Chapter. Use lacing bars and distribution spools.
7. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
8. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps may not be used for heating.
9. In communications equipment room, provide 10 ft long service loop on each end of cable.
10. Pulling Cable: Comply with BICSI ITSIMM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
11. Cable may be terminated on connecting hardware that is rack or cabinet mounted.

H. Open-Cable Installation:

1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
2. Cable may not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.

I. Installation of Cable Exposed under Raised Floors:

1. Install plenum-rated cable only.
2. Install cabling after flooring system has been installed in raised floor areas.
3. Coil cable 6 ft long not less than 12 inch in diameter below each feed point.

J. Group connecting hardware for cables into separate logical fields.

3.4 FIRESTOPPING

A. Comply with requirements in Section 078413 "Penetration Firestopping."

B. Comply with TIA-569, Annex A, "Firestopping."

C. Comply with BICSI ITSIMM, "Firestopping" Chapter.

3.5 GROUNDING

A. Install grounding in accordance with BICSI ITSIMM, "Grounding (Earthing), Bonding, and Electrical Protection" Chapter.

B. Comply with TIA-607 and NECA/BICSI-607.

C. Locate grounding bus bar to minimize length of bonding conductors. Fasten to wall allowing at least 2 inch clearance behind grounding bus bar. Connect grounding bus bar with minimum 4 AWG grounding electrode conductor from grounding bus bar to suitable electrical building ground.

D. Bond metallic equipment to grounding bus bar, using not smaller than 6 AWG equipment grounding conductor.

3.6 IDENTIFICATION

A. Identify system components, wiring, and cabling complying with TIA-606. Comply with requirements for identification specified in Section 270553 "Identification for Communications Systems."

1. Administration Class: Class 1.
2. Color-code cross-connect fields and apply colors to voice and data service backboards, connections, covers, and labels.

B. Paint and label colors for equipment identification must comply with TIA-606 for Class 2 level of administration.

C. Comply with requirements in Section 271523 "Communications Optical Fiber Horizontal Cabling" for cable and asset management software.

D. Cable Schedule: Install in prominent location in each equipment room and wiring closet. List incoming and outgoing cables and their designations, origins, and destinations. Protect with rigid frame and clear plastic cover. Furnish electronic copy of final comprehensive schedules for Project.

E. Cabling Administration Drawings: Show building floor plans with cabling administration-point labeling. Identify labeling convention and show labels for telecommunications closets, backbone pathways and cables, terminal hardware and positions, horizontal cables, work areas and workstation terminal positions, grounding buses and pathways, and equipment grounding conductors.

F. Cable and Wire Identification:

1. Label each cable within 4 inch of each termination and tap, where it is accessible in cabinet or junction or outlet box, and elsewhere as indicated.
2. Each wire connected to building-mounted devices is not required to be numbered at device if color of wire is consistent with associated wire connected and numbered within panel or cabinet.
3. Exposed Cables and Cables in Cable Trays and Wire Troughs: Label each cable at intervals not exceeding 15 ft.
4. Label each unit and field within distribution racks and frames.
5. Identification within Connector Fields in Equipment Rooms and Wiring Closets: Label each connector and each discrete unit of cable-terminating and connecting hardware. Where similar jacks and plugs are used for both voice and data communication cabling, use different color for jacks and plugs of each service.

G. Labels must be preprinted or computer-printed type with printing area and font color that contrasts with cable jacket color but still complies with requirements in TIA 606, for the following:

1. Flexible vinyl or polyester that flexes as cables are bent.

3.7 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. Visually inspect optical fiber jacket materials for qualified electrical testing laboratory certification markings. Inspect cabling terminations in communications equipment rooms for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA-568.1.
2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
3. Optical Fiber Cable Tests:

    a. Test instruments must meet or exceed applicable requirements in TIA-568.1. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
    b. Link End-to-End Attenuation Tests:

        1) Horizontal and multimode backbone link measurements: Test at 850 or 1300 nm in one direction in accordance with TIA-526-14, Method B, One Reference Jumper.
        2) Attenuation test results for backbone links must be less than 2.0 dB. Attenuation test results must be less than those calculated in accordance with equation in TIA-568.1.

B. Nonconforming Work:

1. Cables will be considered defective if they do not pass tests and inspections.
2. Remove and replace defective cables and retest.

C. Collect, assemble, and submit test and inspection reports.

1. Data for each measurement must be documented.
2. Data for field quality-control report submittals must be printed in summary report that is formatted similar to Table 10.1 in BICSI TDMM, or transferred from instrument to computer, saved as text files, and printed and submitted.

D. Manufacturer Services:

1. Engage factory-authorized service representative to support field tests and inspections.

END OF SECTION

SECTION 271513 - COMMUNICATIONS COPPER HORIZONTAL CABLING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Category 6a twisted pair cable.
2. Twisted pair cable hardware, including plugs and jacks.
3. Cable management system.
4. Cabling identification products.
5. Grounding provisions for twisted pair cable.
6. Source quality control requirements for twisted pair cable.

1.2 DEFINITIONS

A. Cross-Connect: A facility enabling the termination of cable elements and their interconnection or cross-connection.

B. EMI: Electromagnetic interference.

C. FTP: Shielded twisted pair.

D. F/FTP: Overall foil screened cable with foil screened twisted pair.

E. F/UTP: Overall foil screened cable with unscreened twisted pair.

F. IDC: Insulation displacement connector.

G. LAN: Local area network.

H. Jack: Also commonly called an "outlet," it is the fixed, female connector.

I. Plug: Also commonly called a "connector," it is the removable, male telecommunications connector.

J. RCDD: Registered Communications Distribution Designer.

K. Screen: A metallic layer, either a foil or braid, placed around a pair or group of conductors.

L. Shield: A metallic layer, either a foil or braid, placed around a pair or group of conductors.

M. S/FTP: Overall braid screened cable with foil screened twisted pair.

N. S/UTP: Overall braid screened cable with unscreened twisted pairs.

O. UTP: Unscreened (unshielded) twisted pair.

1.3 COPPER HORIZONTAL CABLING DESCRIPTION

A. Horizontal cable cabling system must provide interconnections between Distributor A, Distributor B, or Distributor C, and the equipment outlet, otherwise known as "Cabling Subsystem 1," in the telecommunications cabling system structure. Cabling system consists of horizontal cables, intermediate and main cross-connects, mechanical terminations, and patch cords or jumpers used for horizontal-to-horizontal cross-connection.

1. TIA-568-C.1 requires that a minimum of two equipment outlets be installed for each work area.
2. Horizontal cabling must contain no more than one transition point or consolidation point between the horizontal cross-connect and the telecommunications equipment outlet.
3. Bridged taps and splices must not be installed in the horizontal cabling.

B. A work area is approximately 100 sq. ft., and includes the components that extend from the equipment outlets to the station equipment.

C. The maximum allowable horizontal cable length is 295 feet. This maximum allowable length does not include an allowance for the length of 16 feet to the workstation equipment or in the horizontal cross-connect.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product.

C. Shop Drawings: Reviewed and stamped by RCDD.

1. System Labeling Schedules:

    a. Electronic copy of labeling schedules, in software and format selected by Owner.
    b. Electronic copy of labeling schedules that are part of cabling and asset identification system of software.

2. Cabling administration Drawings and printouts.
3. Wiring diagrams and installation details of telecommunications equipment, to show location and layout of telecommunications equipment, including the following:

    a. Telecommunications rooms plans and four wall elevations.
    b. Telecommunications pathways.
    c. Telecommunications system access points.
    d. Telecommunications grounding system.
    e. Telecommunications conductor drop locations.
    f. Typical telecommunications details.
    g. Mechanical, electrical, fire protection, and plumbing systems.

D. Twisted pair cable testing plan.

E. Sustainable Design Submittals:

1. Product Data: For each conductor and cable indicating lead content.
2. Environmental Product Declaration: For each product.
3. Health Product Declaration: For each product.
4. Sourcing of Raw Materials: Corporate sustainability report for each manufacturer.

F. Field Quality-Control Submittals:

1. Field quality-control reports.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Qualification Data: For RCDD, Installer, installation supervisor, and field inspector.

C. Product Certificates: For each type of product.

D. Source quality-control reports.

1.6 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Maintenance Data: For splices and connectors to include in maintenance manuals.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.

1. Layout Responsibility: Preparation of Shop Drawings and cabling administration Drawings, cabling administration Drawings, and field testing program development by an RCDD.
2. Installation Supervision: Installation must be under the direct supervision of Level 2 Installer, who must be present at all times when Work of this Section is performed at Project site.
3. Testing Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.

B. Testing Agency Qualifications: Testing agency must have personnel certified by BICSI on staff.

1. Testing Agency's Field Supervisor: Currently certified by BICSI as an RCDD.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Test cables upon receipt at Project site.

1. Test each pair of twisted pair cable for open and short circuits.

1.9 PROJECT CONDITIONS

A. Environmental Limitations: Do not deliver or install cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.10 COORDINATION

A. Coordinate layout and installation of telecommunications pathways and cabling with Government's telecommunications and LAN equipment and service suppliers via the Contracting Officer.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. General Performance: Horizontal cabling system must comply with transmission standards in TIA-568-C.1, when tested according to test procedures of this standard.

B. Telecommunications Pathways and Spaces: Comply with TIA-569-D.

C. Grounding: Comply with TIA-607-B.

2.2 GENERAL CABLE CHARACTERISTICS

A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with the applicable standard and NFPA 70 for the following types:

1. Communications, Plenum Rated:

    a. Type CMP complying with UL 1685, Type CMP in listed plenum communications raceway, or Type CMP in listed cable routing assembly.
    b. Type CM, Type CMG, Type CMP, Type CMR, or Type CMX in metallic conduit installed according to NFPA 70, Article 300.22, "Wiring in Ducts, Plenums, and Other Air-Handling Spaces."

B. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: 25 or less.
2. Smoke-Developed Index: 50 or less.

C. RoHS compliant.

2.3 CATEGORY 6a TWISTED PAIR CABLE

A. Description: Four-pair, balanced-twisted pair cable, certified to meet transmission characteristics of Category 6 cable at frequencies up to 500 MHz.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.
2. AMP NETCONNECT; a TE Connectivity Ltd. company.
3. Belden, Inc.
4. Berk-Tek Leviton; a Nexans/Leviton alliance.
5. CommScope, Inc.
6. General Cable; Prysmian Group North America.
7. Genesis Cable Products; Honeywell International, Inc.
8. Hitachi Cable America Inc.
9. Mohawk; a division of Belden Networking, Inc.
10. Prysmian Cables and Systems; Prysmian Group North America.
11. Superior Essex Inc.; subsidiary of LS Corp.
12. SYSTIMAX Solutions; a CommScope Inc. brand.

C. Standard: Comply with NEMA WC 66/ICEA S-116-732 and TIA-568-C.2 for Category 6 cables.

D. Conductors: 100-ohm, 23 AWG solid copper.

1. Lead Content: Less than 300 parts per million.

E. Shielding/Screening: Unshielded twisted pairs (UTP).

F. Cable Rating: Plenum.

G. Jacket: Blue thermoplastic.

2.4 TWISTED PAIR CABLE HARDWARE

A. Description: Hardware designed to connect, splice, and terminate twisted pair copper communications cable.

B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. 3M.
2. American Technology Systems Industries, Inc.
3. AMP NETCONNECT; a TE Connectivity Ltd. company.
4. Belden, Inc.
5. Berk-Tek Leviton; a Nexans/Leviton alliance.
6. CommScope, Inc.
7. General Cable; Prysmian Group North America.
8. Genesis Cable Products; Honeywell International, Inc.
9. Hubbell Premise Wiring; brand of Hubbell Electrical Solutions; Hubbell Incorporated.

10. Leviton Manufacturing Co., Inc.
11. Mohawk; a division of Belden Networking, Inc.
12. Molex Premise Networks.
13. Panduit Corp.
14. Prysmian Cables and Systems; Prysmian Group North America.
15. Siemon Co. (The).
16. Superior Essex Inc.; subsidiary of LS Corp.
17. SYSTIMAX Solutions; a CommScope Inc. brand.

C. General Requirements for Twisted Pair Cable Hardware:

1. Comply with the performance requirements of Category 6a.
2. Comply with TIA-568-C.2, IDC type, with modules designed for punch-down caps or tools.
3. Cables must be terminated with connecting hardware of same category or higher.

D. Source Limitations: Obtain twisted pair cable hardware from single source from single manufacturer.

E. Connecting Blocks:

1. 110-style IDC for Category 6a.
2. Provide blocks for the number of cables terminated on the block, plus 25 percent spare, integral with connector bodies, including plugs and jacks where indicated.

F. Cross-Connect: Modular array of connecting blocks arranged to terminate building cables and permit interconnection between cables.

1. Number of Terminals per Field: One for each conductor in assigned cables.

G. Patch Panel: Modular panels housing numbered jack units with IDC-type connectors at each jack location for permanent termination of pair groups of installed cables.

1. Features:

a. Universal T568A and T568B wiring labels.
b. Labeling areas adjacent to conductors.
c. Replaceable connectors.
d. 48 ports.

2. Construction: 16-gauge steel and mountable on 19-inch equipment racks.
3. Number of Jacks per Field: One for each four-pair conductor group of indicated cables, plus spares and blank positions adequate to suit specified expansion criteria.

H. Patch Cords: Factory-made, four-pair cables in 36-inch and 48-inchlengths; terminated with an eight-position modular plug at each end.

1. Patch cords must have bend-relief-compliant boots and color-coded icons to ensure performance. Patch cords must have latch guards to protect against snagging.
2. Patch cords must have color-coded boots for circuit identification.

I. Plugs and Plug Assemblies:

1. Male; eight position; color-coded modular telecommunications connector designed for termination of a single four-pair, 100-ohm, unshielded or shielded twisted pair cable.
2. Standard: Comply with TIA-568-C.2.
3. Marked to indicate transmission performance.

J. Jacks and Jack Assemblies:

1. Female; eight position; modular; fixed telecommunications connector designed for termination of a single four-pair, 100-ohm, unshielded or shielded twisted pair cable.
2. Designed to snap-in to a patch panel or cover plate.
3. Standard: Comply with TIA-568-C.2.
4. Marked to indicate transmission performance.

K. Cover Plate:

1. Multi-port port, vertical single gang cover plates designed to mount to single gang wall boxes.
2. Metal Cover Plate: Stainless steel, complying with requirements in Section 260533 "Raceway and Boxes for Electrical Systems."
3. For use with snap-in jacks accommodating any combination of twisted pair, optical fiber, and coaxial work area cords.

    a. Flush mounting jacks, positioning the cord at a 45-degree angle.

L. Legend:

1. Machine printed, in the field, using adhesive-tape label.
2. Snap-in, clear-label covers and machine-printed paper inserts.

2.5 IDENTIFICATION PRODUCTS

A. Comply with TIA-606-B and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.

2.6 SOURCE QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to evaluate cables.

B. Factory test cables on reels according to TIA-568-C.1.

C. Factory test twisted pair cables according to TIA-568-C.2.

D. Cable will be considered defective if it does not pass tests and inspections.

E. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 WIRING METHODS

A. Routing:

1. Install cables in raceways, open J-hooks, and cable trays as indicated, except within consoles, cabinets, desks, and counters. Conceal raceway and cables, except in unfinished spaces.

    a. Install plenum cable in environmental air spaces, including plenum ceilings.
    b. Comply with requirements for raceways and boxes specified in Section 270528 "Pathways for Communications Systems."

2. Conceal conductors and cables in ceilings, walls, and below floors.
3. Provide wiring above accessible ceilings.

B. Wiring within Enclosures: Bundle, lace, and train cables within enclosures. Connect to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools. Install conductors parallel with or at right angles to sides and back of enclosure.

3.2 INSTALLATION OF PATHWAYS

A. Comply with requirements for demarcation point, cabinets, and racks specified in Section 271100 "Communications Equipment Room Fittings."

B. Comply with Section 270528 "Pathways for Communications Systems."

C. Comply with Section 270536 "Cable Trays for Communications Systems."

D. Drawings indicate general arrangement of pathways and fittings.

3.3 INSTALLATION OF TWISTED-PAIR HORIZONTAL CABLES

A. Comply with NECA 1 and NECA/BICSI 568.

B. General Requirements for Cabling:

1. Comply with TIA-568-C.0, TIA-568-C.1, and TIA-568-C.2.
2. Comply with BICSI's "Information Transport Systems Installation Methods Manual (ITSIMM), Ch. 5, "Copper Structured Cabling Systems," "Cable Termination Practices" Section.
3. Install 110-style IDC termination hardware unless otherwise indicated.
4. Do not untwist twisted pair cables more than 1/2 inch from the point of termination to maintain cable geometry.
5. Terminate conductors; no cable must contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.

6. Consolidation points may be used only for making a direct connection to equipment outlets:

    a. Do not use consolidation point as a cross-connect point, as a patch connection, or for direct connection to workstation equipment.
    b. Locate consolidation points for twisted-pair cables at least 49 feet from communications equipment room.

7. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
8. Install lacing bars to restrain cables, prevent straining connections, and prevent bending cables to smaller radii than minimums recommended by manufacturer.
9. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI Information Transport Systems Installation Methods Manual, Ch. 5, "Copper Structured Cabling Systems," "Cable Termination Practices" Section. Use lacing bars and distribution spools.
10. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation, and replace it with new cable.
11. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps must not be used for heating.
12. In the communications equipment room, install a 10-foot- long service loop on each end of each cable.
13. Pulling Cable: Comply with BICSI Information Transport Systems Installation Methods Manual, Ch. 5, "Copper Structured Cabling Systems," "Pulling and Installing Cable" Section. Monitor cable pull tensions.

C. Open-Cable Installation:

1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
2. Suspend twisted pair cabling, not in a wireway or pathway, a minimum of 8 inches above ceilings by cable supports not more than 48 inches apart.
3. Cable must not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.

D. Group connecting hardware for cables into separate logical fields.

E. Separation from EMI Sources:

1. Comply with recommendations from BICSI's "Telecommunications Distribution Methods Manual" and TIA-569-D for separating unshielded copper communication cable from potential EMI sources, including electrical power lines and equipment.
2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment must be as follows:

    a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches.
    b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches.
    c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches.

3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment must be as follows:

    a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
    b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
    c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.

4. Separation between communications cables in grounded metallic raceways, power lines, and electrical equipment located in grounded metallic conduits or enclosures must be as follows:

    a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
    b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
    c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.

5. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches.
6. Separation between Communications Cables and Fluorescent Fixtures: A minimum of 5 inches.

3.4 FIRESTOPPING

A. Comply with requirements in Section 078413 "Penetration Firestopping."

B. Comply with TIA-569-D, Annex A, "Firestopping."

C. Comply with "Firestopping Systems" Article in BISCI's "Telecommunications Distribution Methods Manual."

3.5 GROUNDING

A. Comply with requirements in Section 270526 "Grounding and Bonding for Communications Systems" for grounding conductors and connectors.

B. Install grounding according to the "Grounding, Bonding, and Electrical Protection" chapter in BICSI's "Telecommunications Distribution Methods Manual."

C. Comply with TIA-607-B and NECA/BICSI-607.

D. Locate grounding bus bar to minimize the length of bonding conductors. Fasten to wall, allowing at least a 2-inch clearance behind the grounding bus bar. Connect grounding bus bar to suitable electrical building ground, using a minimum No. 4 AWG grounding electrode conductor.

E. Bond metallic equipment to the grounding bus bar, using not smaller than a No. 6 AWG equipment grounding conductor.

3.6 IDENTIFICATION

A. Identify system components, wiring, and cabling complying with TIA-606-B. Comply with requirements for identification specified in Section 270553 "Identification for Communications Systems."

1. Administration Class: Class 2.
2. Color-code cross-connect fields and apply colors to voice and data service backboards, connections, covers, and labels.

B. Paint and label colors for equipment identification must comply with TIA-606-B for Class 2 level of administration, including optional identification requirements of this standard.

C. Cable Schedule: Install in a prominent location in each equipment room and wiring closet. List incoming and outgoing cables and their designations, origins, and destinations. Protect with rigid frame and clear plastic cover. Furnish an electronic copy of final comprehensive schedules for Project.

D. Cabling Administration Drawings: Show building floor plans with cabling administration-point labeling. Identify labeling convention and show labels for telecommunications closets, terminal hardware and positions, horizontal cables, work areas and workstation terminal positions, grounding buses and pathways, and equipment grounding conductors.

E. Cable and Wire Identification:

1. Label each cable within 4 inches of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
2. Each wire connected to building-mounted devices is not required to be numbered at the device if wire color is consistent with associated wire connected and numbered within panel or cabinet.
3. Exposed Cables and Cables in Cable Trays and Wire Troughs: Label each cable at intervals not exceeding 15 feet.
4. Label each terminal strip, and screw terminal in each cabinet, rack, or panel.

    a. Individually number wiring conductors connected to terminal strips, and identify each cable or wiring group, extended from a panel or cabinet to a building-mounted device, with the name and number of a particular device.
    b. Label each unit and field within distribution racks and frames.

5. Identification within Connector Fields in Equipment Rooms and Wiring Closets: Label each connector and each discrete unit of cable-terminating and -connecting hardware. Where similar jacks and plugs are used for both voice and data communication cabling, use a different color for jacks and plugs of each service.

F. Labels must be preprinted or computer-printed type, with a printing area and font color that contrast with cable jacket color but still comply with TIA-606-B requirements for the following:

1. Cables use flexible vinyl or polyester that flexes as cables are bent.

3.7 FIELD QUALITY CONTROL

A. Field tests and inspections must be witnessed by Contracting Officer.

B. Tests and Inspections:

1. Visually inspect jacket materials for NRTL certification markings. Inspect cabling terminations in communications equipment rooms for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA-568-C.1.
2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
3. Test twisted pair cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross-connection.

    a. Test instruments must meet or exceed applicable requirements in TIA-568-C.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.

C. Data for each measurement must be documented. Data for submittals must be printed in a summary report that is formatted similarly to Table 10.1 in BICSI's "Telecommunications

Distribution Methods Manual," or must be transferred from the instrument to the computer, saved as text files, printed, and submitted.

D. Nonconforming Work:

1. End-to-end cabling will be considered defective if it does not pass tests and inspections.
2. Remove and replace cabling where test results indicate that they do not comply with specified requirements.

E. Collect, assemble, and submit test and inspection reports.

F. Manufacturer Services:

1. Engage factory-authorized service representative to support and supervise field tests and inspections.

END OF SECTION

SECTION 275119 - SOUND MASKING SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Networked sound masking systems.
2. Standalone sound masking systems.

B. Related Requirements:

1. Section 260010 "Supplemental Requirements for Electrical" specifies additional requirements applicable to coordinating, scheduling, and sequencing of the Work specified in this Section.
2. Section 260533.13 "Conduit for Electrical Systems" specifies raceways installed by this Section.
3. Section 260533.16 "Boxes and Covers for Electrical Systems" specifies boxes installed by this Section.
4. Section 260553 "Identification for Electrical Systems" specifies electrical equipment labels and warning signs installed by this Section.
5. Section 271513 "Communications Copper Horizontal Cabling" specifies network cabling, loudspeaker cabling, and Class 2 control cabling installed by this Section.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Product Listing: Include copy of unexpired approval letter, on letterhead of qualified electrical testing agency, certifying product's compliance with specified listing criteria.

   a. If listed manufacturer differs from selling manufacturer, indicate relationship between entities on submittal. Clearly indicate which entity warrants product performance and fitness for purpose.
   b. Listing criteria identified in approval letter must match specified listing criteria. UL label indicating approval of equipment's enclosure is not considered approval of equipment for intended application.
   c. Product identification in approval letter must match product branding and model numbers in submittal. Approval letters for discontinued or superseded products are not acceptable for submitted product.

2. Include manufacturer's sample extended warranty language.

C. Shop Drawings: Prepare and submit the following:

1. Include plans, elevations, sections, details, and attachments to other work.
2. Include schematic of system and floor plan indicating quantity, type, and location of components.
3. Include diagrams for power, signal, and control wiring.
4. Include details supplementing assembly and installation instructions with dimensions, weights, loads, required clearances, methods of field assembly, components, and location and rating of each field connection.
5. Shop drawings for installation of loudspeakers and cabling connecting to fire-alarm EVACS or mass notification systems must be prepared and signed by certified NICET FAS Senior Engineering Technician or NICET IBPSC Design Technician.

D. Field quality-control reports.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturer's published instructions.

C. Field Reports:

1. Manufacturer's field reports for field quality-control support.
2. Manufacturer's field reports for system startup support.
3. Field reports for software and firmware upgrades.

1.4 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Warranty documentation.

1.5 REGULATORY AGENCY APPROVALS

A. Submittals for sound masking systems connected to fire alarm require approval by authorities having jurisdiction and must be signed and sealed by qualified life safety professional engineer responsible for their preparation. Submit for action by Architect prior to submitting for approval by authorities having jurisdiction.

B. Submittals for sound masking systems connected to fire alarm require action by Architect prior to submitting for approval by authorities having jurisdiction.

1.6 WARRANTY FOR SOUND MASKING SYSTEMS

A. Special Installer Extended Warranty: Installer warrants that fabricated and installed sound masking systems perform in accordance with specified requirements and agrees to repair or replace components or products that fail to perform as specified within extended-warranty

period.

1. Extended-Warranty Period: Four years from date of Substantial Completion; full coverage for labor, materials, and equipment.

B. Special Manufacturer Extended Warranty: Manufacturer warrants that sound masking systems perform in accordance with specified requirements and agrees to repair or replace components or products that fail to perform as specified within extended-warranty period.

1. Extended-Warranty Period: Ten years from date of Substantial Completion; full coverage for materials only, free on board origin, freight prepaid.

1.7 WARRANTY FOR BATTERIES

A. Special Manufacturer Extended Warranty for Batteries: Manufacturer warrants that batteries perform in accordance with specified requirements and agrees to repair or replace batteries that fail to perform as specified within extended-warranty period.

1. Initial Extended-Warranty Period for Li-ion Batteries: Five years from date of Substantial Completion; full coverage for materials only, free on board origin, freight prepaid.
2. Follow-On Extended-Warranty Period for Li-ion Batteries: Ten years from date of Substantial Completion; prorated coverage for materials only, free on board origin, freight prepaid.
3. Extended-Warranty Period for Ni-MH Batteries: Three years from date of Substantial Completion; prorated coverage for materials only, free on board origin, freight prepaid.
4. Extended-Warranty Period for Ni-Cd Batteries: Five years from date of Substantial Completion; prorated coverage for materials only, free on board origin, freight prepaid.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Products or components listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2.2 NETWORKED SOUND MASKING SYSTEMS

A. Description: Electronic noise generators and associated controls for simultaneously operating multiple loudspeakers throughout facility.

B. UL AZOT - Multi-Room Sound Masking System :

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Biamp
b. K. R. Moeller Associates Ltd
c. Lencore Acoustics Corp.; business of Emmis Communications Corp.
d. Soft dB, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria:

a. Audio Equipment: Comply with one of the following:

1) UL CCN AZOT; including UL 62368-1.
2) UL CCN AZSQ; including UL 60065 or UL 6500.
3) UL CCN AZJX; including UL 813.

b. Suitable for Installation in Air-Handling Spaces: UL CCN BHZF; including UL 2043.

4. Standard Features:

a. Reference Standards: Complies with principles and recommended test methods described in ASTM E1374.

5. Other Available Features Required by the Project:

a. Loudspeaker Mounting: Ceiling or Plenum.
b. Loudspeaker Controller Mounting: Wall or Plenum.
c. Network Control Panel Mounting: Wall, Plenum, or Rack.
d. Provide input for connection to supervised fire-alarm N.O. contact that when closed causes network controller to mute sound masking equipment.
e. Masking Sound Frequency Range: 20 Hz to 20 kHz, with equalizers for adjusting the masking sound spectrum at third-octave resolution.
f. Masking Sound Volume Adjustment: Digital control, adjustable in 1.5 dB increments over the range of 34 to 82.5 dB(A-weighted), or a continuous adjustment within that range.
g. Remote central volume control.

C. UL AZOT - Single-Room Sound Masking System:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Biamp
b. K. R. Moeller Associates Ltd
c. Lencore Acoustics Corp.; business of Emmis Communications Corp.
d. Soft dB, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria:

a. Audio Equipment: Comply with one of the following:

1) UL CCN AZOT; including UL 62368-1.
2) UL CCN AZSQ; including UL 60065 or UL 6500.
3) UL CCN AZJX; including UL 813.

b. Suitable for Installation in Air-Handling Spaces: UL CCN BHZF; including UL 2043.

4. Standard Features:

a. Reference Standards: Complies with principles and recommended test methods described in ASTM E1374.

5. Other Available Features Required by the Project:

a. Loudspeaker Mounting: Ceiling or Plenum.
b. Loudspeaker Controller Mounting: Wall or Plenum.
c. Provide input for connection to supervised fire-alarm N.O. contact that, when closed, mutes sound masking equipment.

2.3 STANDALONE SOUND MASKING SYSTEMS

A. Description: Self-contained loudspeaker with electronic noise generator and associated controls.

B. UL UEAY - Standalone Sound Masking Loudspeakers:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Atlas Sound LP
b. Biamp
c. Lencore Acoustics Corp.; business of Emmis Communications Corp.
d. Lowell Manufacturing Co.

2. Source Limitations: Obtain products from single manufacturer.
3. Listing Criteria:

a. Sound Masking Loudspeakers: UL CCN UEAY; including UL 1480A.
b. Suitable for Installation in Air-Handling Spaces: UL CCN BHZF; including UL 2043.

4. Standard Features:

a. Reference Standards: Complies with principles and recommended test methods described in ASTM E1374.

5. Other Available Features Required by the Project:

a. Loudspeaker Mounting: Ceiling or Plenum.
b. Loudspeaker Controller Mounting: Wall or Plenum.
c. Provide input for connection to supervised fire-alarm N.O. contact that when

closed mutes loudspeaker.

PART 3 - EXECUTION

3.1 INSTALLATION OF SOUND MASKING SYSTEMS

A. Comply with manufacturer's published instructions.

B. Reference Standards for Installation:

1. Electrical Construction: ICC IBC, ICC IFC, NFPA 1, NFPA 70, and NECA NEIS 1.
2. Fire Alarm and Premises Security Work: NFPA 72 and NECA NEIS 305.
3. Communications Work: BICSI N1.
4. Life Safety and Means of Egress Work: NFPA 101.
5. Audio Equipment and Wiring Methods: Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with Article 640 of NFPA 70.
6. Consult Architect for resolution of conflicting requirements.

C. Special Installation Techniques:

1. Loudspeaker Installation above Ceiling: Suspend with chains from building structure above ceilings, so bottom of assembly is 6 to 8 inch above upper plane of finished ceiling material. Use eyebolts on speaker assemblies for attachment. Suspend independently from structure, not to supports for components of other building systems.
2. Zoned Loudspeaker Connections: For two- or three-channel systems, connect loudspeaker assemblies alternatively, so masking sound is redundant throughout coverage zones.
3. Wiring Methods:

    a. Cable in Raceway: Install cables in raceways and cable trays, except within consoles, cabinets, desks, and counters and unless otherwise indicated.

        1) Except raceways are not required in accessible indoor ceiling spaces and attics.
        2) Except raceways are not required in hollow gypsum board partitions.
        3) Conceal raceways and wiring, except in unfinished spaces.

    b. Concealed Cable: Conceal conductors and cables in accessible ceilings, walls, and floors where possible.
    c. Exposed Cable: Install parallel to building lines, follow surface contours, and support as recommended by manufacturer.

        1) Install plenum cable in environmental air-handling spaces, including plenum ceilings.

    d. Within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools.

4. Grounding: As recommended by manufacturers unless more stringent requirements are indicated. Ground equipment and conductors to eliminate shock hazard and to minimize ground loops, common-mode returns, noise pickup, cross talk, and other impairments with a maximum of 5 Ω to ground at main equipment location.
5. Impedance Matching: For system components, including connecting cable, provide end-to-end level and impedance-matched signal paths. Use matching networks and balancing devices at connections where necessary to avoid mismatches.
6. Splices, Taps, and Terminations: Make splices, taps, and terminations on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.
7. Identification: Provide labels for vehicle charging equipment and associated electrical equipment.

    a. Use color-coded conductors, and apply wire- and cable-marking tape to designate wires and cables, so media are identified in coordination with system wiring diagrams.
    b. Label loudspeakers as to channel, zone, and address.
    c. Identify field-installed conductors, interconnecting wiring, and components.
    d. Provide warning signs.
    e. Label each enclosure with engraved metal or laminated-plastic nameplate.

D. Interfaces with Other Work:

1. Coordinate quantity and arrangement of sound masking system components with ceiling space configuration and with components occupying ceiling space, including structural members, pipes, air-distribution components, raceways, cable trays, luminaires, and other items.
2. Coordinate installation of raceways and boxes with installation of cabling for sound masking system.
3. Coordinate installation of network cabling, loudspeaker cabling, and Class 2 control cabling with installation of sound masking equipment.

E. Systems Integration:

1. Integrate sound masking system with fire-alarm system for muting non-emergency audio broadcast in event of fire or other emergency.
2. Final connection to FACU will be completed by fire-alarm system Installer.

3.2 FIELD QUALITY CONTROL OF SOUND MASKING SYSTEMS

A. Administrant for Communications Tests and Inspections:

1. Owner will engage qualified communications testing and inspecting agency to administer and perform tests and inspections.
2. Engage qualified communications testing and inspecting agency to administer and perform tests and inspections.
3. Engage factory-authorized service representative to administer and perform tests and inspections on components, assemblies, and equipment installations, including connections.
4. Administer and perform tests and inspections with assistance of factory-authorized service representative.

B. Acceptance Testing Preparation:

1. Pretesting: Tune, align, and adjust system, and pretest components, wiring, and functions to verify compliance with specified material, installation, and performance requirements. Correct deficiencies and retest until satisfactory performance and conditions are achieved.

C. Field tests and inspections must be witnessed by Architect and Tenant.

D. Tests and Inspections:

1. Perform manufacturer's recommended tests and inspections.
2. Operational Test: Start system to confirm proper operation. Remove malfunctioning units, replace with new units, and retest. Make initial sound-spectrum and -level adjustments for each zone.
3. Inspection: Verify that units and controls are properly labeled and interconnecting wires and terminals are identified.
4. Masking Sound Power Level Adjustments: Adjust independently for each space to minimum level between 40 and 50 dB (A-weighted) that will provide speech privacy between adjacent workstations while complying with other system requirements.

E. Final Acceptance Testing: Provide a minimum of 10 days' notice of acceptance test performance schedule. Schedule tests after pretesting has been successfully completed.

1. Perform sound masking evaluation tests in accordance with ASTM E1130, with measurements and calculations in accordance with ASA S3.5.
2. Tests and Calibration Conditions: Spaces are to be completely furnished, but unoccupied; lights and HVAC systems must be on; HVAC system testing and balancing are to be completed; and electronic ballasts, lighting relay panels, and low-voltage transformers must be in place.
3. Test Conditions: Complying with ASTM E1130 and calculated in accordance with ASA S3.5.
4. Instrumentation: Use a professional-quality, sound-level meter with octave-band filters and documentation of recent calibration against recognized standards. Comply with ASA S1.4 Part 1.
5. System Tests: Include the following for each system zone:

a. Loudspeaker Circuit Impedance Test: Measure impedance at 1000 Hz with amplifier disconnected, using a professional impedance meter or bridge. Locate and correct faults denoted by abnormal readings.
b. Ambient Sound-Level Tests: With system off, measure ambient sound level in one-third octave bands. Also measure ambient sound level as a single, wide-band, A-weighted reading.
c. System Noise Test: With masking-noise signal on and amplifiers adjusted at a working level 10 dB above ambient sound level, check for hum, buzz, rattle, or other operating deficiencies.
d. Spatial Uniformity Test: Measure sound level at locations no greater than 15 ft on center throughout covered spaces to determine compliance with specified performance level.
e. Frequency Response Adjustment and Test: Adjust one-third octave frequency bands and other unit filters to provide response. Adjust to meet requirement of space speech intelligibility and quality of background sound. Comply with ASA

S3.2, CTA-426, and ASTM E1110.

6. Adjust level of masking sound that is appropriate for area and overall volume.
7. Adjust level of masking sound for each space, so one-third octave band centered at 500 Hz has final selected sound-power level for that space. Measure deviation from listed values in one-third octave bands from 100 to 1000 Hz. Measured values must not deviate from those listed by more than 4 dB for open-plan areas and 8 dB for enclosed offices. The total of individual band deviations in eight bands must not exceed 16 dB for open-plan areas and 30 dB for enclosed offices.
8. Walk-Through Test: People in covered spaces cannot discern loudspeaker locations.

F. Record test observations, readings, and corrective actions. Report test results in accordance with ASTM E1130.

G. Record final control settings and programming, and final tap setting of loudspeaker-matching transformers. Record final sound-level measurements and observations.

H. Nonconforming Work:

1. Units will be considered defective if they do not pass tests and inspections.
2. Remove and replace defective units and retest.

I. Field Quality-Control Reports: Collect, assemble, and submit test and inspection reports.

J. Manufacturer Services: Engage factory-authorized service representative to support field tests and inspections.

1. Manufacturer's Field Reports for Field Quality-Control Support: Prepare and submit report after each visit by factory-authorized service representative, documenting activities performed at the Project site.

3.3 SYSTEM STARTUP

A. Perform startup service.

1. Complete installation and startup checks in accordance with manufacturer's published instructions.

B. Manufacturer Services: Engage factory-authorized service representative to support system startup.

1. Manufacturer's Field Reports for System Startup Support: Prepare and submit report after each visit by factory-authorized service representative, documenting activities performed at the Project site.

3.4 ADJUSTING

A. Sound Masking Adjustments: Adjust sound masking devices to suit actual occupied conditions.

3.5 CLOSEOUT ACTIVITIES

A. Training:

1. With assistance from factory-authorized service representatives, train Owner's maintenance personnel on the following topics:

    a. How to adjust, operate, and maintain sound masking system equipment specified in this Section.

3.6 PROTECTION

A. After installation, protect sound masking equipment from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

3.7 MAINTENANCE

A. Sound Masking Readjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in readjusting system to suit actual occupied conditions. Provide up to two visits to the Project site during other-than-normal occupancy hours for this purpose.

B. Software and Firmware Service Agreement:

1. Technical Support: Beginning at Substantial Completion, verify that software and firmware service agreement includes software and firmware support for two years.
2. Upgrade Service: At Substantial Completion, update software and firmware to latest version. Install and program software and firmware upgrades that become available within two years from date of Substantial Completion.

    a. Upgrade Notice: No fewer than 30 days to allow Owner to schedule and access the system.

3. Field Reports for Software and Firmware Upgrades: Prepare and submit report after each update, documenting upgrades installed.

END OF SECTION

SECTION 281000 - ACCESS CONTROL

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Access control system.

B. Related Requirements:

1. Section 260011 "Facility Performance Requirements for Electrical" specifies seismic-load, wind-load, acoustical, and other field conditions applicable to Work specified in this Section.
2. Section 280010 "Supplemental Requirements for Electronic Safety and Security" specifies additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
3. Section 013100 "Project Management and Coordination" specifies preinstallation conference procedures.
4. Section 087100 "Door Hardware" specifies the following:

    a. Electric strike(s).
    b. Delayed-egress electromagnetic lock(s).
    c. Electromechanical lock(s).
    d. Self-contained electronic lock(s).
    e. Exit lock(s) and alarm(s).
    f. Auxiliary electrified door hardware.

5. Section 087113 "Power Door Operators" specifies the following:

    a. Door operator controls.
    b. Panic exit device(s).
    c. Electric strike(s).
    d. Auxiliary electrified door hardware.

6. Section 281400 "Access Control System Hardware" specifies the following:

    a. Access control system server(s).
    b. Access control system DGP(s).
    c. Access control system door controller(s).
    d. Access control system input/output interface(s).
    e. Access control system power supply and battery charger(s).
    f. Access control system workstation(s).

7. Section 281500 "Integrated Access Control Hardware Devices" specifies the following:

    a. Swipe card reader(s).
    b. Door lock keypad(s).

c. Combination card reader(s) and keypad(s).
d. Access control cards.
e. Electrically controlled single-point latch(es).
f. Electrically controlled three-point latch(es).
g. Type 1 high-security electronic lock(s).
h. Type 1F high-security combination lock(s).
i. Panic hardware with special locking arrangement for fire-rated door(s).
j. NFC access control device(s).
k. Electronic key management system unit(s).

1.2 DEFINITIONS

A. DGP: Data gathering panel.

B. NFC: Near field communications.

C. REX: Request-to-exit.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

B. Preinstallation Coordination Meeting(s): For access control. Conduct meeting(s) as videoconference before.

1. Attendees: Installers, fabricators, representatives of manufacturers, and administrants for field tests and inspections. Notify Architect, Construction Manager, and Owner's Commissioning Authority of scheduled meeting dates.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Shop Drawings:

1. Project general notes.
2. Head-end hardware, equipment, and device locations.
3. Block diagram and cable/conduit routing illustrating end-to-end system wiring.
4. End-to-end system communications details.
5. Secondary power calculations

C. Field quality-control reports.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Sample warranties.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Manufacturers' Published Instructions: Record copy of official installation and testing instructions issued to Installer by manufacturer for the following:

1. Installation and programming instructions for operating system software, including all applicable software add-ons.
2. Installation and programming instructions for antivirus and security protection software.
3. Manufacturer's recommended setup and testing procedure for operating system software and applicable software add-ons.
4. Troubleshooting instructions for operating system software and applicable software add-ons.
5. Manufacturer's recommended setup and testing procedure for antivirus and security protection software.
6. Troubleshooting instructions for antivirus and security protection software.
7. Installation instructions for access control system servers.
8. Installation instructions for access control system DGPs.
9. Installation instructions for access control system input/output interface.
10. Installation instructions for access control system door controllers.
11. Installation instructions for access control system workstation.
12. Installation instructions for access control system power supplies and battery chargers.
13. Installation instructions for access control system printers.
14. Manufacturer's recommended testing and inspection procedure for operation of access control system servers, panels, input/output interfaces, door controllers, and workstations.
15. Manufacturer's recommended testing and inspection procedure for operation of access control system power supplies and battery chargers.
16. Manufacturer's recommended testing and inspection procedure for operation of access control system printers.
17. Installation instructions for integrated credential readers and entry management devices.
18. Printing, programming, and handling instructions for access control credentials.
19. Installation instructions for electrified locking devices and accessories.
20. Installation instructions for egress management devices.
21. Installation instructions for access control remote devices.
22. Installation instructions for telephone entry systems.
23. Installation instructions for intercom entry systems.
24. Installation instructions for electronic key management systems.
25. Installation instructions for access control electronic turnstiles and mobility systems.
26. Manufacturer's recommended tests and inspections for integrated credential readers and entry management devices.
27. Manufacturer's recommended tests and inspections for electrified locking devices and accessories.
28. Manufacturer's recommended tests and inspections for egress management devices.
29. Manufacturer's recommended tests and inspections for access control remote devices.
30. Manufacturer's recommended tests and inspections for telephone entry systems.
31. Manufacturer's recommended tests and inspections for intercom entry systems.

32. Manufacturer's recommended tests and inspections for electronic key management systems.
33. Manufacturer's recommended tests and inspections for access control electronic turnstiles and mobility systems.
34. Manufacturer's recommended testing and inspection procedure for end-to-end operation of access control system software, hardware, and integrated hardware devices.

C. Warranty documentation.

1.7 WARRANTY FOR ACCESS CONTROL SYSTEM

A. Special Manufacturer Extended Warranty: Manufacturer warrants that components of access control system perform in accordance with specified requirements and agrees to provide repair or replacement of components that fail to perform as specified within extended-warranty period.

1. Initial Extended-Warranty Period: Three years from date of Substantial Completion; full coverage for labor, materials, and equipment.

1.8 WARRANTY FOR BATTERIES

A. Special Manufacturer Extended Warranty for Batteries: Manufacturer warrants that batteries perform in accordance with specified requirements and agrees to provide repair or replacement of batteries that fail to perform as specified within warranted cycle life.

1. Initial Extended-Warranty Period for Li-ion Batteries: Three years from date of Substantial Completion; full coverage for materials only, free on board destination, freight prepaid.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 INSTALLATION OF ACCESS CONTROL SYSTEM

A. Description: Access control system provides a means of regulating or controlling physical entry into an area, or access to or use of a device by electrical, electronic, and/or mechanical means. Typical access control system includes a card reader at a controlled door, which reads a user credential and sends the collected data to a centrally located DGP over the cabling infrastructure. DGP may hold a user database onboard or may communicate with a user database over the network. If user is authorized for access at a controlled door, DGP signals the electronic lock at the door to unlock. If user credential is not authorized according to user database, the door remains locked and access is denied. In addition to card readers and electronic locks, access control systems may include various other connected devices programmed for a desired function.

B. Performance Criteria:

1. Regulatory Requirements:

    a. Components listed and labeled in accordance with NFPA 70 and NFPA 72, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
    b. Comply with NFPA 1, NFPA 730, NFPA 731, and ICC IBC.
    c. Certification: Provide certificate, authorized under UL Certification Service, that access control system installation complies with installation requirements of UL CCN ALOV.

2. Listing Criteria: UL CCN ALOV and UL CCN ALVY; including UL 294.
3. Consult Architect for resolution of conflicting requirements.

C. Selection of Access Control System Components:

1. Source Limitations: Obtain components for access control system from sources approved by manufacturer warranting performance of entire system. Existing system is Honeywell.
2. Provide the following specified products with the access control system:

    a. Access Control Software and Database Management:

        1) Access control system unit operating system software.
        2) Access control system unit antivirus and security protection software.
        3) Visitor management database software.
        4) Mobile credential validation database software.
        5) Access control system supplementary computer equipment operating system software.
        6) Access control system supplementary computer equipment antivirus and security protection software.
        7) Credential card personalization software.
        8) Credential card printer and encoder software.

3. Operation:

    a. Exchange database information directly with DGPs.

D. Special Techniques:

1. Comply with manufacturer's published instructions.
2. Mounting Heights: Mount field devices in accessible locations in accordance with United States Access Board ADA-ABA Accessibility Guidelines standards.
3. Wiring Methods:

    a. Backbone Cable Type: [**Single-mode fiber**] [**and**] [**or**] [**multi-mode fiber**] [**or**] [**copper**] <**Insert cable type**>.
    b. Cable Type: [**Shielded**] [**Unshielded**] <**Insert cable size**>.
    c. Analog Maximum Cable Length: [**1000 ft**] <**Insert cable length**>.
    d. Digital Maximum Cable Length: [**300 ft**] [**500 ft**] <**Insert cable length**>.

E. Interfaces with Other Work:

1. Coordinate with Section 087100 "Door Hardware" for interfacing access control system devices with door hardware.
2. Coordinate with Section 142100 "Electric Traction Elevators" for interfacing access control system with elevator controls.

F. Systems Integration:

1. Coordinate with Section 283100 "Intrusion Detection" for integrating access control system with intrusion detection system.
2. Coordinate with Section 282000 "Video Surveillance" for integrating access control system with video surveillance controls.

3.2 FIELD QUALITY CONTROL OF ACCESS CONTROL SYSTEM COMPONENTS

A. Acceptance Testing Preparation:

1. <**Insert requirements**>.

B. Field tests and inspections must be witnessed by Architect.

C. Tests and Inspections:

1. Perform manufacturer's recommended tests and inspections for access control system components.
2. Perform industry standard tests and inspections for power supplies, batteries, and other standby power provisions.
3. Engage factory-authorized service representative to test end-to-end system connection and functionality.
4. Verify monitoring of access control system status and diagnostics information.

D. Nonconforming Work:

1. Access control equipment will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

E. Collect, assemble, and submit test and inspection reports.

F. Manufacturer Services:

1. Engage factory-authorized service representative to perform field tests and inspections.

3.3 SYSTEM STARTUP

A. Engage a factory-authorized service representative to perform startup service.

1. Complete installation and startup checks in accordance with manufacturer's published instructions.

3.4 ADJUSTING

A. Control Sensor Adjustments: Adjust control devices to suit actual occupied conditions.

1. For proximity motion sensors, verify operation at outer limits of detector range. Set time delay to suit Owner's operations.

3.5 PROTECTION

A. After installation, protect access control system components from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

3.6 MAINTENANCE

A. Control Sensor Readjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in readjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

END OF SECTION

SECTION 281400 - ACCESS CONTROL SYSTEM HARDWARE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Access control system units.
2. Access control system power supplies and battery chargers.
3. Access control system supplementary computer equipment.

B. Related Requirements:

1. Section 260011 "Facility Performance Requirements for Electrical" for seismic-load, wind-load, acoustical, and other field conditions applicable to Work specified in this Section.
2. Section 281500 "Integrated Access Control Hardware Devices" for access control field devices controlled by hardware specified in this Section.

1.2 DEFINITIONS

A. DGP: Data gathering panel.

B. LAN: Local area network.

C. RAID: Redundant array of inexpensive disks; redundant array of independent disks.

D. RAM: Random-access memory.

E. WAN: Wide area network.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Coordination Meeting(s): For access control system hardware. Conduct meeting(s) as videoconference or at Project site before.

1. Attendees: Installers, fabricators, representatives of manufacturers, representatives from telecommunications, Owner's security representatives, IT representatives, and administrants for field tests and inspections. Notify Architect, Construction Manager, and Owner's Commissioning Authority of scheduled meeting dates.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data:

1. Access control system units.
2. Access control system power supplies and battery chargers.
3. Access control system supplementary computer equipment.

C. Shop Drawings:

1. Project general notes.
2. Hardware and equipment locations.
3. Block diagram and cable/conduit routing.
4. System communications details.
5. Hardware and equipment installation details.
6. Secondary power calculations.

D. Field quality-control reports.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Manufacturers' Published Instructions: Record copy of official installation and testing instructions issued to Installer by manufacturer for the following:

1. Installation instructions for access control system servers.
2. Installation instructions for access control system DGPs.
3. Installation instructions for access control system input/output interface.
4. Installation instructions for access control system door controllers.
5. Installation instructions for access control system workstation.
6. Manufacturer's recommended testing and inspection procedure for operation of access control system servers, panels, input/output interfaces, door controllers, and workstations.
7. Installation instructions for access control system power supplies and battery chargers.
8. Manufacturer's recommended testing and inspection procedure for operation of access control system power supplies and battery chargers.
9. Installation instructions for access control system printers.
10. Manufacturer's recommended testing and inspection procedure for operation of access control system printers.

C. Sample warranties.

1.6 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Warranty documentation.

1.7 WARRANTY FOR ACCESS CONTROL SYSTEM HARDWARE

A. Special Manufacturer Extended Warranty: Manufacturer warrants that access control system hardware perform in accordance with specified requirements and agrees to provide repair or replacement of components or products that fail to perform as specified within extended-warranty period.

1. Initial Extended-Warranty Period: Three years from date of Substantial Completion; full coverage for labor, materials, and equipment.

1.8 WARRANTY FOR BATTERIES

A. Special Manufacturer Extended Warranty for Batteries: Manufacturer warrants that batteries perform in accordance with specified requirements and agrees to provide repair or replacement of batteries that fail to perform as specified within extended-warranty period.

1. Initial Extended-Warranty Period for Li-ion Batteries: Three years from date of Substantial Completion; full coverage for materials only, free on board destination, freight prepaid.

PART 2 - PRODUCTS

2.1 ACCESS CONTROL SYSTEM UNITS

A. Description: This category covers head end units for access control systems, providing a means of regulating or controlling physical entry into an area, or access to or use of device by electrical, electronic, and/or mechanical means. Access control systems are investigated as complete configuration based upon manufacturer's specified system components. Access control systems are intended to comply with applicable life safety access and egress requirements.

B. Performance Criteria:

1. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70 and NFPA 72, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
b. Comply with NFPA 1, NFPA 730, NFPA 731, and ICC IBC.

2. Listing Criteria: UL CCN ALVY; including UL 294.

C. Access Control System Server: The Access Control/Security and DVM System shall be an extension of the existing Honeywell Enterprise Building Integrator System with host server hardware located in Augusta, ME.

1. Accessories:

a. Provide Lantronix UDS1100 with 500-171-R to RS485 screw terminal adapter.

D. Access Control System DGPs: Altronix AL1024ULACM8.

1. Source Limitations: Obtain products from.
2. Additional Characteristics:

a. Data ports for connection to LAN and downstream DGPs.
b. Integral terminal blocks secured to enclosure.
c. Enclosure lock with tamper switch and monitoring.

3. Options:

a. Input Voltage: 120 V(ac).
b. Battery Backup: 12 V.
c. DGP Communication: Ethernet TIA-485 or composite.
d. Mounting: Wall mount or rack mount.

E. Access Control System Door Controllers: Altronix AL1024ULACM8.

1. Source Limitations: Obtain products from single manufacturer.
2. Additional Characteristics:

a. Data ports for connection to LAN and downstream controllers.
b. Integral terminal blocks for connection of inputs/outputs to field devices.
c. Controller Inputs:

1) Auxiliary input.
2) Door contact.
3) Cabinet tamper.
4) Power monitor.

d. Controller Outputs:

1) Auxiliary output.
2) Door strike.
3) Door operators.
4) Credential readers.

3. Options:

a. Input Voltage: 12 to 24 V(dc).
b. Controller Communication: Ethernet TIA-232 TIA-485 or composite.
c. Mounting: Cabinet mount or wall.

F. Access Control System Input/Output Interface: Altronix.

1. Source Limitations: Obtain products from single manufacturer.
2. Additional Characteristics:

a. Input Voltage: 12 to 24 V(dc).
b. Data ports for connection to LAN and downstream panels/controllers.
c. Integral terminal blocks for connection of inputs/outputs to field devices.
d. Inputs:

1) Auxiliary inputs from building systems.
2) Door contact.
3) Cabinet tamper.
4) Power monitor.

e. Outputs:

1) Auxiliary outputs to building systems.
2) Door strike.
3) Credential readers.
4) Audible devices.

3. Options:

a. Communication: Ethernet TIA-232 TIA-485 or composite.
b. Mounting: Cabinet mount or wall.

2.2 ACCESS CONTROL SYSTEM POWER SUPPLIES AND BATTERY CHARGERS

A. Description: This category covers power supplies and battery chargers for access control system units, controllers, input/output interfaces, workstations, printers, and encoders.

B. Performance Criteria:

1. Regulatory Requirements:

a. Listed and labeled in accordance with NFPA 70 and NFPA 72, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
b. Comply with NFPA 1, NFPA 730, NFPA 731, and ICC IBC.

2. Listing Criteria: UL CCN ALVY; including UL 294.

C. Access Control System Power Supply and Battery Charger:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Altronix Corp.
b. Honeywell Commercial Security; Honeywell International, Inc.

2. Source Limitations: Obtain products from single manufacturer.
3. Additional Characteristics:

a. Input Voltage: 120 V(ac).
b. Output Voltage: 12 to 24 V(dc).
c. Network connection for remote supervision, management, and testing.
d. Enclosure lock with tamper switch and monitoring.
e. Built-in battery charger.

4. Accessories:

    a. DIN rails for mounting.

PART 3 - EXECUTION

3.1 INSTALLATION OF ACCESS CONTROL SYSTEM HARDWARE

A. Comply with manufacturer's published instructions.

B. Reference Standards:

1. Installation of Access Control System Hardware and Wiring: Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with requirements in guide information for UL CCN ALVY.
2. Consult Architect and Owner for resolution of conflicting requirements.

C. Interfaces with Other Work:

1. Coordinate installation of new products for access control system hardware with existing conditions.

3.2 FIELD QUALITY CONTROL OF ACCESS CONTROL SYSTEM HARDWARE

A. Acceptance Testing Preparation:

1. Prepare manufacturers recommended tests and reports. Perform tests and generator reports.

B. Field tests and inspections must be witnessed by Architect authorities having jurisdiction.

C. Tests and Inspections:

1. Perform manufacturer's recommended tests and inspections.

D. Nonconforming Work:

1. Hardware and components will be considered defective if they do not pass tests and inspections.
2. Remove and replace defective units and retest.

E. Collect, assemble, and submit test and inspection reports.

F. Manufacturer Services:

1. Engage factory-authorized service representative to perform field tests and inspections.

3.3 SYSTEM STARTUP

A. Engage a factory-authorized service representative to perform startup service.

1. Complete installation and startup checks in accordance with manufacturer's published instructions.

3.4 PROTECTION

A. After installation, protect access control system hardware from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

END OF SECTION

SECTION 281500 - INTEGRATED ACCESS CONTROL HARDWARE DEVICES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Integrated credential readers and entry management.
2. Access control credentials.
3. Electrified locking devices and accessories.
4. Egress management devices.
5. Access control remote devices.
6. Electronic key management systems.

1.2 DEFINITIONS

A. NFC: Near Field Communications.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Coordination Meeting(s): For integrated access control hardware devices. Conduct meeting(s) as videoconference or at Project site before.

1. Attendees: Installers, fabricators, representatives of manufacturers, representatives from telecommunications, Owner's security representatives, IT representatives, and administrants for field tests and inspections. Notify Architect, Construction Manager, and Owner's Commissioning Authority of scheduled meeting dates.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data:

1. Integrated Credential Readers and Entry Management:

a. Credential readers.
b. Keypads.
c. Combination reader devices.

2. Access Control Credentials:

a. Access control cards.

3. Electrified Locking Devices and Accessories:

    a. Electrically controlled single-point locks and latches.
    b. Electrically controlled two- and three-point locks and latches.
    c. High-security electronic locks.
    d. Status monitoring and egress devices.

4. Egress Management Devices:

    a. Panic hardware with special locking arrangement.
    b. Fire-exit hardware with special locking arrangement.

5. Access Control Remote Devices:

    a. NFC access control devices.

6. Electronic Key Management Systems:

    a. Electronic key management system units.

C. Shop Drawings:

1. Project general notes.
2. Device layout.
3. Block diagram and cable/conduit routing.
4. System communications details.
5. System mounting details.
6. Secondary power calculations.

D. Field quality-control reports.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Manufacturers' Published Instructions: Record copy of official installation and testing instructions issued to Installer by manufacturer for the following:

1. Installation instructions for integrated credential readers and entry management devices.
2. Manufacturer's recommended tests and inspections for integrated credential readers and entry management devices.
3. Printing, programming, and handling instructions for access control credentials.
4. Installation instructions for electrified locking devices and accessories.
5. Manufacturer's recommended tests and inspections for electrified locking devices and accessories.
6. Installation instructions for egress management devices.
7. Manufacturer's recommended tests and inspections for egress management devices.
8. Installation instructions for access control remote devices.
9. Manufacturer's recommended tests and inspections for access control remote devices.
10. Installation instructions for electronic key management systems.

11. Manufacturer's recommended tests and inspections for electronic key management systems.

C. Sample warranties.

1.6 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Maintenance Contracts:

1. Software and firmware service agreements.

C. Warranty documentation.

1.7 WARRANTY

A. Integrated Credential Readers and Entry Management Devices Warranty:

1. Special Manufacturer Extended Warranty: Manufacturer warrants that integrated credential readers and entry management devices perform in accordance with specified requirements and agrees to provide repair or replacement of components or products that fail to perform as specified within extended-warranty period.

a. Initial Extended-Warranty Period: Three years from date of Substantial Completion; full coverage for labor, materials, and equipment.

B. Electrified Locking Devices and Accessories Warranty:

1. Special Manufacturer Extended Warranty: Manufacturer warrants that electrified locking devices and accessories perform in accordance with specified requirements and agrees to provide repair or replacement of components or products that fail to perform as specified within extended-warranty period.

a. Initial Extended-Warranty Period: Three years from date of Substantial Completion; full coverage for labor, materials, and equipment.

PART 2 - PRODUCTS

2.1 INTEGRATED CREDENTIAL READERS AND ENTRY MANAGEMENT

A. Swipe Card Reader:

1. Provide HID Signo Priority Seos Profile Reader, Model 20, 20k, 40, 40k.

a. 40NKS-02-000000.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Comply with manufacturer's published instructions.

B. Special Techniques:

1. Cable Type: Shielded.
2. Analog Maximum Cable Length: 1000 ft.
3. Digital Maximum Cable Length: 300 ft.

C. Interfaces with Other Work:

1. Coordinate access control credentials with integrated credential readers and access control system architecture.
2. Egress Management Interfaces:

a. Coordinate with Section 282000 "Video Surveillance" for automatic video feed callup upon delayed egress activation.

3.2 FIELD QUALITY CONTROL

A. Field tests and inspections must be witnessed by Architect and authorities having jurisdiction.

B. Tests and Inspections:

1. Perform manufacturer's recommended tests and inspections.

C. Nonconforming Work:

1. Device will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

D. Collect, assemble, and submit test and inspection reports.

E. Manufacturer Services:

1. Engage factory-authorized service representative to perform field tests and inspections.

3.3 PROTECTION

A. After installation, protect integrated access control hardware devices from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

END OF SECTION

SECTION 282000 - VIDEO SURVEILLANCE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes a video surveillance system consisting of cameras, digital video recorder, data transmission wiring, and a control station with its associated equipment.

B. Related Requirements:

1. Section 283100 "Intrusion Detection" to integrate video surveillance used for intrusion detection.

1.3 DEFINITIONS

A. AGC: Automatic gain control.

B. BNC: Bayonet Neill-Concelman - type of connector.

C. B/W: Black and white.

D. CCD: Charge-coupled device.

E. FTP: File transfer protocol.

F. IP: Internet protocol.

G. LAN: Local area network.

H. MPEG: Moving picture experts group.

I. NTSC: National Television System Committee.

J. PC: Personal computer.

K. PTZ: Pan-tilt-zoom.

L. RAID: Redundant array of independent disks.

M. TCP: Transmission control protocol - connects hosts on the Internet.

N. UPS: Uninterruptible power supply.

O. WAN: Wide area network.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product indicated. Include dimensions and data on features, performance, electrical characteristics, ratings, and finishes.

C. Shop Drawings: For video surveillance. Include plans, elevations, sections, details, and attachments to other work.

1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
2. Functional Block Diagram: Show single-line interconnections between components for signal transmission and control. Show cable types and sizes.
3. Dimensioned plan and elevations of equipment racks, control panels, and consoles. Show access and workspace requirements.
4. UPS: Sizing calculations.
5. Wiring Diagrams: For power, signal, and control wiring.

D. Design Data: Include an equipment list consisting of every piece of equipment by model number, manufacturer, serial number, location, and date of original installation. Add pretesting record of each piece of equipment, listing name of person testing, date of test, set points of adjustments, name and description of the view of preset positions, description of alarms, and description of unit output responses to an alarm.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Field quality-control reports.

C. Product Warranty: Sample of special warranty.

1.6 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Operation and Maintenance Data: For cameras, power supplies, infrared illuminators, monitors, videotape recorders, digital video recorders, video switches, and control-station components to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

1. Lists of spare parts and replacement components recommended to be stored at the site for ready access.

1.7 PROJECT CONDITIONS

A. Environmental Conditions: Capable of withstanding the following environmental conditions without mechanical or electrical damage or degradation of operating capability:

1. Control Station: Rated for continuous operation in ambient temperatures of 60 to 85 deg F and a relative humidity of 20 to 80 percent, noncondensing.
2. Interior, Controlled Environment: System components, except central-station control unit, installed in temperature-controlled interior environments shall be rated for continuous operation in ambient temperatures of 36 to 122 deg F dry bulb and 20 to 90 percent relative humidity, noncondensing. Use NEMA 250, Type 1 enclosures.
3. Exterior Environment: System components installed in locations exposed to weather shall be rated for continuous operation in ambient temperatures of minus 30 to plus 122 deg F dry bulb and 20 to 90 percent relative humidity, condensing. Rate for continuous operation when exposed to rain as specified in NEMA 250, winds up to 85 mph and snow cover up to 24 inches thick. Use NEMA 250, Type 3R enclosures.
4. Security Environment: Camera housing for use in high-risk areas where surveillance equipment may be subject to physical violence.

1.8 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of cameras, equipment related to camera operation, and control-station equipment that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Three years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SYSTEM REQUIREMENTS

A. Video-signal format shall comply with NTSC standard, composite interlaced video. Composite video-signal termination shall be 75 ohms.

B. Surge Protection: Protect components from voltage surges originating external to equipment housing and entering through power, communication, signal, control, or sensing leads. Include surge protection for external wiring of each conductor's entry connection to components.

C. Tamper Protection: Tamper switches on enclosures, control units, pull boxes, junction boxes, cabinets, and other system components shall initiate a tamper-alarm signal when unit is opened or partially disassembled. Control-station, control-unit alarm display shall identify tamper alarms and indicate locations.

2.2 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Comply with NECA 1.

C. Comply with NFPA 70.

D. Electronic data exchange between video surveillance system with an access-control system shall comply with SIA TVAC.

2.3 CAMERAS

A. Provide Axis Cameras with Motion Detection:

1. Refer to Camera Schedule on Drawings.

2.4 POWER SUPPLIES

A. Low-voltage power supplies matched for voltage and current requirements of cameras and accessories, and of type as recommended by manufacturer of camera, infrared illuminator, and lens.

1. Enclosure: NEMA 250, Type 1.

2.5 CAMERA-SUPPORTING EQUIPMENT

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Bosch Security Systems, Inc.
2. CBC (AMERICA) Corp.
3. COP-USA.
4. Crest Electronics, Inc.
5. ELMO.
6. Elbex Ltd.
7. EverFocus Electronics Corporation.
8. Honeywell Commercial Security; Honeywell International, Inc.
9. Ikegami Electronics (USA) Inc.
10. Interlogix; Carrier Global Corporation.
11. Merit Li-Lin (USA) Corp.
12. Moog, Inc.
13. Panasonic Corporation of North America.
14. Pelco.
15. SANYO North America Corporation.
16. Samsung Opto-Electronics.
17. Telpix Electronics, Inc.

18. Tyco Security Products; brand of Johnson Controls International plc, Building Solutions North America.
19. Vicon Industries, Inc.
20. Video Mount Products.
21. Visiontech.
22. Wren Associates Limited.

B. Minimum Load Rating: Rated for load in excess of the total weight supported times a minimum safety factor of two.

C. Pan Units: Motorized automatic-scanning units arranged to provide remote-controlled manual and automatic camera panning action, and equipped with matching mounting brackets.

1. Scanning Operation: Silent, smooth, and positive.
2. Stops: Adjustable without disassembly, to limit the scanning arc.

D. Pan-and-Tilt Units: Motorized units arranged to provide remote-controlled aiming of cameras with smooth and silent operation, and equipped with matching mounting brackets.

1. Panning Rotation: 0 to 355 degrees, with adjustable stops.
2. Tilt Movement: 90 degrees, plus or minus 5 degrees, with adjustable stops.
3. Speed: 12 degrees per second in both horizontal and vertical planes.
4. Wiring: Factory prewired for camera and zoom lens functions and pan-and-tilt power and control.
5. Built-in encoders or potentiometers for position feedback, and thermostat-controlled heater.
6. Pan-and-tilt unit shall be available with preset positioning capability to recall the position of a specific scene.

E. Mounting Brackets for Fixed Cameras: Type matched to items supported and mounting conditions. Include manual pan-and-tilt adjustment.

2.6 IP VIDEO SYSTEMS

A. The System shall be an extension of the existing Honeywell Enterprise Building Integrator System with host server hardware located in Augusta, ME.

B. Cameras must connect to the LAN and terminate in the Honeywell Digital Video Manager.

C. Provide CAT6 cable. Terminate with RJ45 jack using EIA/TIA568B standard.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine pathway elements intended for cables. Check raceways and other elements for compliance with space allocations, installation tolerance, hazards to camera installation, and other conditions affecting installation.

B. Examine roughing-in for LAN, WAN, and IP network before device installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 WIRING

A. Comply with requirements in Section 260533.13 “Conduits for Electrical Systems.”

B. Wiring Method: Install cables in raceways unless otherwise indicated.

1. Except raceways are not required in accessible indoor ceiling spaces and attics.
2. Except raceways are not required in hollow gypsum board partitions.
3. Conceal raceways and wiring except in unfinished spaces.

C. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools.

D. Splices, Taps, and Terminations: For power and control wiring, use numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.

E. For communication wiring, comply with the following:

1. Section 271513 "Communications Copper Horizontal Cabling."

F. Grounding: Provide independent-signal circuit grounding recommended in writing by manufacturer.

3.3 VIDEO SURVEILLANCE SYSTEM INSTALLATION

A. Install cameras and infrared illuminators level and plumb.

B. Install cameras with 84-inch-minimum clear space below cameras and their mountings. Change type of mounting to achieve required clearance.

C. Set pan unit and pan-and-tilt unit stops to suit final camera position and to obtain the field of view required for camera. Connect all controls and alarms, and adjust.

D. Install power supplies and other auxiliary components at control stations unless otherwise indicated.

E. Install tamper switches on components indicated to receive tamper switches, arranged to detect unauthorized entry into system-component enclosures and mounted in self-protected, inconspicuous positions.

F. Avoid ground loops by making ground connections only at the control station.

1. For 12- and 24-V dc cameras, connect the coaxial cable shields only at the monitor end.

3.4 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.

B. Perform tests and inspections.

1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

C. Tests and Inspections:

1. Inspection: Verify that units and controls are properly installed, connected, and labeled, and that interconnecting wires and terminals are identified.
2. Pretesting: Align and adjust system and pretest components, wiring, and functions to verify that they comply with specified requirements. Conduct tests at varying lighting levels, including day and night scenes as applicable. Prepare video-surveillance equipment for acceptance and operational testing as follows:

    a. Prepare equipment list described in "Informational Submittals" Article.
    b. Verify operation of auto-iris lenses.
    c. Set back-focus of fixed focal length lenses. At focus set to infinity, simulate nighttime lighting conditions by using a dark glass filter of a density that produces a clear image. Adjust until image is in focus with and without the filter.
    d. Set back-focus of zoom lenses. At focus set to infinity, simulate nighttime lighting conditions by using a dark glass filter of a density that produces a clear image. Additionally, set zoom to full wide angle and aim camera at an object 50 to 75 feet away. Adjust until image is in focus from full wide angle to full telephoto, with the filter in place.
    e. Set and name all preset positions; consult Owner's personnel.
    f. Set sensitivity of motion detection.
    g. Connect and verify responses to alarms.
    h. Verify operation of control-station equipment.

3. Test Schedule: Schedule tests after pretesting has been successfully completed and system has been in normal functional operation for at least 14 days. Provide a minimum of 10 days' notice of test schedule.
4. Operational Tests: Perform operational system tests to verify that system complies with Specifications. Include all modes of system operation. Test equipment for proper operation in all functional modes.

D. Video surveillance system will be considered defective if it does not pass tests and inspections.

E. Prepare test and inspection reports.

3.5 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to

two visits to Project during other-than-normal occupancy hours for this purpose. Tasks shall include, but are not limited to, the following:

1. Check cable connections.
2. Check proper operation of cameras and lenses. Verify operation of auto-iris lenses and adjust back-focus as needed.
3. Adjust all preset positions; consult Owner's personnel.
4. Recommend changes to cameras, lenses, and associated equipment to improve Owner's use of video surveillance system.
5. Provide a written report of adjustments and recommendations.

3.6 CLEANING

A. Clean installed items using methods and materials recommended in writing by manufacturer.

B. Clean video-surveillance-system components, including camera-housing windows, lenses, and monitor screens.

3.7 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain video-surveillance equipment.

END OF SECTION

SECTION 283100 - INTRUSION DETECTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Intrusion detection with communication links to perform monitoring, alarm, and control functions.
2. Integration of other electronic and electrical systems and equipment.

B. Related Sections:

1. Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for power cabling between master control units and field-mounted devices and control units.
2. Section 282000 "Video Surveillance" for CCTV cameras that are used as devices for video motion detection.

1.3 DEFINITIONS

A. CCTV: Closed-circuit television.

B. PIR: Passive infrared.

C. RFI: Radio-frequency interference.

D. UPS: Uninterruptible power supply.

E. Control Unit: System component that monitors inputs and controls outputs through various circuits.

F. Master Control Unit: System component that accepts inputs from other control units and may also perform control-unit functions. The unit has limited capacity for the number of protected zones and is installed at an unattended location or at a location where it is not the attendant's primary function to monitor the security system.

G. Monitoring Station: Facility that receives signals and has personnel in attendance at all times to respond to signals. A central station is a monitoring station that is listed.

H. Protected Zone: A protected premises or an area within a protected premises that is provided with means to prevent an unwanted event.

I. Standard Intruder: A person who weighs 100 lb or less and whose height is 60 inches or less; dressed in a long-sleeved shirt, slacks, and shoes.

J. Standard-Intruder Movement: Any movement, such as walking, running, crawling, rolling, or jumping, of a "standard intruder" in a protected zone.

K. Systems Integration: The bringing together of components of several systems containing interacting components to achieve indicated functional operation of combined systems.

L. Zone. A defined area within a protected premises. It is a space or area for which an intrusion must be detected and uniquely identified. The sensor or group of sensors must then be assigned to perform the detection, and any interface equipment between sensors and communication must link to master control unit.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: Components for sensing, detecting, systems integration, and control, including dimensions and data on features, performance, electrical characteristics, ratings, and finishes.

C. Shop Drawings: Detail assemblies of standard components that are custom assembled for specific application on this Project.

1. Functional Block Diagram: Show single-line interconnections between components including interconnections between components specified in this Section and those furnished under other Sections. Indicate methods used to achieve systems integration. Indicate control, signal, and data communication paths and identify networks control interface devices and media to be used. Describe characteristics of network and other data communication lines.

    a. Indicate methods used to achieve systems integration.
    b. Indicate control, signal, and data communication paths and identify PLCs, networks, control interface devices, and media to be used.
    c. Describe characteristics of network and other data communication lines.
    d. Describe methods used to protect against power outages and transient voltages including types and ratings of isolation and surge suppression devices used in data, communication, signal, control, and ac and dc power circuits.

2. Raceway Riser Diagrams: Detail raceway runs required for intrusion detection and for systems integration. Include designation of devices connected by raceway, raceway type and size, and type and size of wire and cable fill for each raceway run.
3. Site and Floor Plans: Indicate final outlet and device locations, routing of raceways, and cables inside and outside the building. Include room layout for master control-unit console, terminal cabinet and racks.
4. Master Control-Unit Console Layout: Show required artwork and device identification.
5. Device Address List: Coordinate with final system programming.

6. System Wiring Diagrams: Include system diagrams unique to Project. Show connections for all devices, components, and auxiliary equipment. Include diagrams for equipment and for system with all terminals and interconnections identified.
7. Details of surge-protection devices and their installation.
8. Sensor detection patterns and adjustment ranges.

D. Design Data: Include method of operation and supervision of each component and each type of circuit. Show sequence of operations for manually and automatically initiated system or equipment inputs. Description must cover this specific Project; manufacturer's standard descriptions for generic systems are unacceptable.

E. Samples for Initial Selection: For units with factory-applied color finishes.

F. Samples for Verification: For each type of exposed finish required.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Qualification Data: For Installer intrusion detection systems integrator testing agency.

C. Field quality-control reports.

1. Anchor inspection reports documenting inspections of built-in and cast-in anchors.

D. Product Warranty: Sample of special warranty.

E. Field Test Reports: Test plan and report defining all tests required to ensure that system meets technical, operational, and performance specifications within 60 days of date of Contract award.

F. Evaluation Reports: Examination reports documenting inspections of substrates, areas, and conditions.

1.6 CLOSEOUT SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Operation and Maintenance Data: For intrusion detection system to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

1. Data for each type of product, including features and operating sequences, both automatic and manual.
2. Master control-unit hardware and software data.

1.7 QUALITY ASSURANCE

A. Installer Qualifications:

1. An employer of workers, at least one of whom is a Certified Alarm Technician, Level 1.
2. Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
3. Layout Responsibility: Preparation of Shop Drawings and cabling administration Drawings by a Technician.
4. Installation Supervision: Installation shall be under the direct supervision of Technician, who shall be present at all times when Work of this Section is performed at Project site.
5. Testing Supervisor: Currently certified by BICSI as a Technician to supervise on-site testing.

B. Intrusion Detection Systems Integrator Qualifications: An experienced intrusion detection equipment supplier and Installer who has completed systems integration work for installations similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

1. At least one of whom is a Certified Systems Integrator.

C. Testing Agency Qualifications: Certified by BICSI.

1. Testing Agency's Field Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.

1.8 PROJECT CONDITIONS

A. Environmental Conditions: Capable of withstanding the following environmental conditions without mechanical or electrical damage or degradation of operating capability:

1. Altitude: Sea level to 4000 feet.
2. Master Control Unit: Rated for continuous operation in an ambient of 60 to 85 deg F and a relative humidity of 20 to 80 percent, noncondensing.
3. Interior, Controlled Environment: System components, except master control unit, installed in temperature-controlled interior environments shall be rated for continuous operation in ambients of 36 to 122 deg F dry bulb and 20 to 90 percent relative humidity, noncondensing.
4. Interior, Uncontrolled Environment: System components installed in non-temperature-controlled interior environments shall be rated for continuous operation in ambients of 0 to 122 deg F dry bulb and 20 to 90 percent relative humidity, noncondensing.
5. Exterior Environment: System components installed in locations exposed to weather shall be rated for continuous operation in ambients of minus 30 to plus 122 deg F dry bulb and 20 to 90 percent relative humidity, condensing. Comply with UL 294 and UL 639 for outdoor-use equipment. Rate for continuous operation when exposed to rain as specified in NEMA 250, winds up to 85 mph and snow cover up to 24 inches thick.

1.9 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer and Installer agree to repair or replace components of intrusion detection devices and equipment that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 FUNCTIONAL DESCRIPTION OF SYSTEM

A. Description: Modular, microprocessor-based controls, intrusion sensors and detection devices, and communication links to perform monitoring, alarm, and control functions.

B. Supervision: System components shall be continuously monitored for normal, alarm, supervisory, and trouble conditions. Indicate deviations from normal conditions at any location in system. Indication includes identification of device or circuit in which deviation has occurred and whether deviation is an alarm or malfunction.

1. Alarm Signal: Display at master control unit and actuate audible and visual alarm devices.
2. Trouble Condition Signal: Distinct from other signals, indicating that system is not fully functional. Trouble signal shall indicate system problems such as battery failure, open or shorted transmission line conductors, or control-unit failure.
3. Supervisory Condition Signal: Distinct from other signals, indicating an abnormal condition as specified for the particular device or control unit.

C. System Control: Master control unit shall directly monitor intrusion detection units and connecting wiring.

D. System Control: Master control unit shall directly monitor intrusion detection devices, perimeter detection units, and connecting wiring in a multiplexed distributed control system or as part of a network.

E. System shall automatically reboot program without error or loss of status or alarm data after any system disturbance.

F. Operator Commands:

1. Help with System Operation: Display all commands available to operator. Help command, followed by a specific command, shall produce a short explanation of the purpose, use, and system reaction to that command.
2. Acknowledge Alarm: To indicate that alarm message has been observed by operator.
3. Place Protected Zone in Access: Disable all intrusion-alarm circuits of a specific protected zone. Tamper circuits may not be disabled by operator.
4. Place Protected Zone in Secure: Activate all intrusion-alarm circuits of a protected zone.
5. Protected Zone Test: Initiate operational test of a specific protected zone.
6. System Test: Initiate system-wide operational test.
7. Print reports.

G. Timed Control at Master Control Unit: Allow automatically timed "secure" and "access" functions of selected protected zones.

H. Automatic Control of Related Systems: Alarm or supervisory signals from certain intrusion detection devices control the following functions in related systems:

1. Switch selected lights.
2. Switch signal to selected monitor from CCTV camera in vicinity of sensor signaling an alarm.

I. Printed Record of Events: Print a record of alarm, supervisory, and trouble events on system printer. Sort and report by protected zone, device, and function. When master control unit receives a signal, print a report of alarm, supervisory, or trouble condition. Report type of signal (alarm, supervisory, or trouble), protected zone description, date, and time of occurrence. Differentiate alarm signals from other indications. When system is reset, report reset event with the same information concerning device, location, date, and time. Commands shall initiate the reporting of a list of current alarm, supervisory, and trouble conditions in system or a log of past events.

J. Response Time: Two seconds between actuation of any alarm and its indication at master control unit.

K. Circuit Supervision: Supervise all signal and data transmission lines, links with other systems, and sensors from master control unit. Indicate circuit and detection device faults with both protected zone and trouble signals, sound a distinctive audible tone, and illuminate an LED. Maximum permissible elapsed time between occurrence of a trouble condition and indication at master control unit is 20 seconds. Initiate an alarm in response to opening, closing, shorting, or grounding of a signal or data transmission line.

L. Programmed Secure-Access Control: System shall be programmable to automatically change status of various combinations of protected zones between secure and access conditions at scheduled times. Status changes may be preset for repetitive, daily, and weekly; specially scheduled operations may be preset up to a year in advance. Manual secure-access control stations shall override programmed settings.

M. Manual Secure-Access Control: Coded entries at manual stations shall change status of associated protected zone between secure and access conditions.

2.2 SYSTEM COMPONENT REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Control Units, Devices, and Communications with Monitoring Station: Listed and labeled by a qualified testing agency for compliance with SIA CP-01.

C. FM Global Compliance: FM-Approved and -labeled intrusion detection devices and equipment.

D. Comply with NFPA 70.

E. Compatibility: Detection devices and their communication features, connecting wiring, and master control unit shall be selected and configured with accessories for full compatibility with the following equipment:

1. Door hardware specified in Section 087111 “Door Hardware.”
2. Video surveillance system specified in Section 282000 "Video Surveillance."

F. Surge Protection: Protect components from voltage surges originating external to equipment housing and entering through power, communication, signal, control, or sensing leads. Include surge protection for external wiring of each conductor entry connection to components.

1. Minimum Protection for Communication, Signal, Control, and Low-Voltage Power Lines: Listed and labeled by a qualified testing agency for compliance with NFPA 731.

G. Intrusion Detection Units: Listed and labeled by a qualified testing agency for compliance with UL 639.

H. Interference Protection: Components shall be unaffected by radiated RFI and electrical induction of 15 V/m over a frequency range of 10 to 10,000 MHz and conducted interference signals up to 0.25-V rms injected into power supply lines at 10 to 10,000 MHz.

I. Tamper Protection: Tamper switches on detection devices, control units, annunciators, pull boxes, junction boxes, cabinets, and other system components shall initiate a tamper-alarm signal when unit is opened or partially disassembled and when entering conductors are cut or disconnected. Master control-unit alarm display shall identify tamper alarms and indicate locations.

J. Self-Testing Devices: Automatically test themselves periodically, but not less than once per hour, to verify normal device functioning and alarm initiation capability. Devices transmit test failure to master control unit.

K. Antimasking Devices: Automatically check operation continuously or at intervals of a minute or less, and use signal-processing logic to detect blocking, masking, jamming, tampering, or other operational dysfunction. Devices transmit detection of operational dysfunction to master control unit as an alarm signal.

L. Addressable Devices: Transmitter and receivers shall communicate unique device identification and status reports to master control unit.

M. Remote-Controlled Devices: Individually and remotely adjustable for sensitivity and individually monitored at master control unit for calibration, sensitivity, and alarm condition.

2.3 ENCLOSURES

A. Interior Sensors: Enclosures that protect against dust, falling dirt, and dripping noncorrosive liquids.

B. Interior Electronics: NEMA 250, Type 12.

C. Exterior Electronics: NEMA 250, Type 4X, stainless steel.

D. Screw Covers: Where enclosures are readily accessible, secure with security fasteners of type appropriate for enclosure.

2.4 SECURE AND ACCESS DEVICES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Bosch Security Systems, Inc.
2. Corby Industries, Inc.
3. Crow Electronic Engineering, Inc.
4. DAQ Electronics, Inc.
5. Digital Security Controls Ltd.
6. Edwards; Carrier Global Corporation.
7. Honeywell International Inc.
8. Visonic Inc.

B. Keypad and Display Module: Arranged for entering and executing commands for system-status changes and for displaying system-status and command-related data.

C. Key-Operated Switch: Change protected zone between secure and access conditions.

2.5 DOOR SWITCHES

A. Provide:

1. GE Interlogix – 1078C
2. GE Interlogix – 1085T
3. GE Interlogix – 1045T
4. GE Interlogix – 2315A-L (overhead doors)
5. GE Interlogix – 3010 (panel tamper)
6. GE Interlogix – 3012 (panel tamper)
7. GRI TRC-20 (panel tamper)

B. Description: Balanced-magnetic switch, complying with UL 634, installed on frame with integral overcurrent device to limit current to 80 percent of switch capacity. Bias magnet and minimum of two encapsulated reed switches shall resist compromise from introduction of foreign magnetic fields.

2.6 PIR SENSORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Aleph America Corporation.
2. Bosch Security Systems, Inc.
3. Crow Electronic Engineering, Inc.
4. Digital Security Controls Ltd.
5. Honeywell International Inc.

6. Interlogix; Carrier Global Corporation.
7. Visonic Inc.

B. Listed and labeled by a qualified testing agency for compliance with SIA PIR-01.

C. Description: Sensors detect intrusion by monitoring infrared wavelengths emitted from a human body within their protected zone and by being insensitive to general thermal variations.

1. Wall-Mounted Unit Maximum Detection Range: 125 percent of indicated distance for individual units and not less than 50 feet.
2. Ceiling-Mounted Unit Spot-Detection Pattern: Full 360-degree conical.
3. Ceiling-Mounted Unit Pattern Size: 84-inch diameter at floor level for units mounted 96 inches above floor; 18-foot diameter at floor level for units mounted 25 feet above floor.

D. Device Performance:

1. Sensitivity: Adjustable pattern coverage to detect a change in temperature of 2 deg F or less, and standard-intruder movement within sensor's detection patterns at any speed between 0.3 to 7.5 fps across two adjacent segments of detector's field of view.
2. Test Indicator: LED test indicator that is not visible during normal operation. When visible, indicator shall light when sensor detects an intruder. Locate test enabling switch under sensor housing cover.
3. Remote Test: When initiated by master control unit, start a test sequence for each detector element that simulates standard-intruder movement within sensor's detection patterns, causing an alarm.

2.7 SECURITY FASTENERS

A. Operable only by tools produced for use on specific type of fastener by fastener manufacturer or other licensed fabricator. Drive system type, head style, material, and protective coating as required for assembly, installation, and strength.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of intrusion detection.

B. Examine roughing-in for embedded and built-in anchors to verify actual locations of intrusion detection connections before intrusion detection installation.

C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of intrusion detection.

D. Inspect built-in and cast-in anchor installations, before installing intrusion detection, to verify that anchor installations comply with requirements. Prepare inspection reports.

1. Remove and replace anchors where inspections indicate that they do not comply with requirements. Reinspect after repairs or replacements are made.
2. Perform additional inspections to determine compliance of replaced or additional anchor installations. Prepare inspection reports.

E. For material whose orientation is critical for its performance as a ballistic barrier, verify installation orientation.

F. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 SYSTEM INTEGRATION

A. Integrate intrusion detection system with the following systems and equipment:

1. Electronic door hardware.
2. Access control.
3. Video surveillance.

3.3 SYSTEM INSTALLATION

A. Comply with UL 681 and NFPA 731.

B. Equipment Mounting: Install master control unit on finished floor with tops of cabinets not more than 72 inches above the finished floor.

C. Install wall-mounted equipment, with tops of cabinets not more than 72 inches above the finished floor.

D. Security Fasteners: Where accessible to inmates, install intrusion detection components using security fasteners with head style appropriate for fabrication requirements, strength, and finish of adjacent materials except that a maximum of two different sets of tools shall be required to operate security fasteners for Project. Provide stainless-steel security fasteners in stainless-steel materials.

3.4 WIRING INSTALLATION

A. Wiring Method: Install wiring in metal raceways according to Section 260533.13 “Conduits for Electrical Systems," except in accessible indoor ceiling spaces and in interior hollow gypsum board partitions where cable may be used. Conceal raceways and wiring except in unfinished spaces and as indicated. Minimum conduit size shall be 1/2 inch. Control and data transmission wiring shall not share conduit with other building wiring systems.

B. Wiring Method: Cable, concealed in accessible ceilings, walls, and floors when possible.

C. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points. Use lacing bars and distribution spools. Separate power-limited and non-power-limited conductors as recommended in writing by manufacturer. Install conductors parallel with or at right angles to sides and back of enclosure. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with intrusion system to terminal blocks. Mark each terminal

according to system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.

D. Wires and Cables:

1. Conductors: Size as recommended in writing by system manufacturer unless otherwise indicated.
2. 120-V Power Wiring: Install according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables" unless otherwise indicated.
3. Control and Signal Transmission Conductors: Install unshielded, twisted-pair cable unless otherwise indicated or if manufacturer recommends shielded cable, according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
4. Data and Television Signal Transmission Cables: Install according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

E. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.

F. Install power supplies and other auxiliary components for detection devices at control units unless otherwise indicated or required by manufacturer. Do not install such items near devices they serve.

G. Identify components with engraved, laminated-plastic or metal nameplate for master control unit and each terminal cabinet, mounted with corrosion-resistant screws. Nameplates and label products are specified in Section 270553 "Identification for Communications Systems."

3.5 IDENTIFICATION

A. Install instructions frame in a location visible from master control unit.

3.6 GROUNDING

A. Ground system components and conductor and cable shields to eliminate shock hazard and to minimize ground loops, common-mode returns, noise pickup, cross talk, and other impairments.

B. Signal Ground Terminal: Locate at main equipment rack or cabinet. Isolate from power system and equipment grounding. Provide 5-ohm ground. Measure, record, and report ground resistance.

3.7 FIELD QUALITY CONTROL

A. Pretesting: After installation, align, adjust, and balance system and perform complete pretesting to determine compliance of system with requirements in the Contract Documents. Correct deficiencies observed in pretesting. Replace malfunctioning or damaged items with new ones and retest until satisfactory performance and conditions are achieved. Prepare forms for systematic recording of acceptance test results.

1. Report of Pretesting: After pretesting is complete, provide a letter certifying that installation is complete and fully operable; include names and titles of witnesses to preliminary tests.

B. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.

C. Perform tests and inspections.

1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

D. Tests and Inspections: Comply with provisions in NFPA 731, Ch. 9, "Testing and Inspections."

1. Inspection: Verify that units and controls are properly labeled and interconnecting wires and terminals are identified.
2. Test Methods: Intrusion detection systems and other systems and equipment that are associated with detection and accessory equipment shall be tested according to Table "Test Methods" and Table "Test Methods of Initiating Devices."

E. Documentation: Comply with provisions in NFPA 731, Ch. 4, "Documentation."

F. Tag all equipment, stations, and other components for which tests have been satisfactorily completed.

3.8 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to three visits to Project during other-than-normal occupancy hours for this purpose. Visits for this purpose shall be in addition to any required by warranty.

3.9 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain the intrusion detection system. Comply with documentation provisions in NFPA 731, Ch. 4, "Documentation and User Training."

END OF SECTION

SECTION 284621.11 - ADDRESSABLE FIRE-ALARM SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Addressable fire-alarm system.
2. Fire-alarm control unit (FACU).
3. Manual fire-alarm boxes.
4. System smoke detectors.
5. Duct smoke detectors.
6. Carbon monoxide detectors.
7. Heat detectors.
8. Fire-alarm notification appliances.
9. Fire-alarm remote annunciators.
10. Fire-alarm addressable interface devices.

B. Related Requirements:

1. Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for cables and conductors for fire-alarm systems.

1.3 DEFINITIONS

A. DACT: Digital alarm communicator transmitter.

B. EMT: Electrical metallic tubing.

C. FACU: Fire-alarm control unit.

D. Mode: The terms "Active Mode," "Off Mode," and "Standby Mode" are used as defined in the 2007 Energy Independence and Security Act (EISA).

E. NICET: National Institute for Certification in Engineering Technologies.

F. PC: Personal computer.

G. Voltage Class: For specified circuits and equipment, voltage classes are defined as follows:

1. Control Voltage: Listed and labeled for use in remote-control, signaling, and power-limited circuits supplied by a Class 2 or Class 3 power supply having rated output not greater than 150 V and 5 A, allowing use of alternate wiring methods complying with NFPA 70, Article 725.
2. Low Voltage: Listed and labeled for use in circuits supplied by a Class 1 or other power supply having rated output not greater than 1000 V, requiring use of wiring methods complying with NFPA 70, Article 300, Part I.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Division 01 Section “Submittal Procedures” and the individual sections specifying the work.

B. Approved Permit Submittal: Submittals must be approved by authorities having jurisdiction after submitting them to Architect for initial review.

C. Product Data: For each type of product, including furnished options and accessories.

1. Include construction details, material descriptions, dimensions, profiles, and finishes.
2. Include rated capacities, operating characteristics, and electrical characteristics.

D. Shop Drawings: For fire-alarm system.

1. Comply with recommendations and requirements in "Documentation" section of "Fundamentals" chapter in NFPA 72.
2. Include plans, elevations, sections, and details, including details of attachments to other Work.
3. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and locations. Indicate conductor sizes, indicate termination locations and requirements, and distinguish between factory and field wiring.
4. Annunciator panel details.
5. Detail assembly and support requirements.
6. Include voltage drop calculations for notification-appliance circuits.
7. Include battery-size calculations.
8. Include input/output matrix.
9. Include written statement from manufacturer that equipment and components have been tested as a system and comply with requirements in this Section and in NFPA 72.
10. Include performance parameters and installation details for each detector.
11. Include floor plans to indicate final outlet locations showing address of each addressable device. Show size and route of cable and conduits and point-to-point wiring diagrams.

E. Delegated Design Submittal: For notification appliances and smoke detectors, in addition to submittals listed above, indicate compliance with performance requirements and design criteria, including analysis data signed and sealed by qualified professional engineer responsible for their preparation.

1. Drawings showing location of each notification appliance, smoke detector, carbon monoxide detector, pull stations, ratings of each, and installation details as needed to comply with listing conditions of device.

2. Design Calculations: Calculate requirements for selecting spacing and sensitivity of detection, complying with NFPA 72. Calculate spacing and intensities for strobe signals and sound-pressure levels for audible appliances.
3. Indicate audible appliances required to produce square wave signal per NFPA 72.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Division 01 Section “Submittal Procedures” and the individual sections specifying the work.

B. Field quality-control reports.

C. Qualification Statements: For Installer.

D. Sample Warranty: Submittal must include line item pricing for replacement parts and labor.

1.6 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Division 01 Section “Submittal Procedures” and the individual sections specifying the work.

B. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following and deliver copies to authorities having jurisdiction:

    a. Comply with "Records" section of "Inspection, Testing and Maintenance" chapter in NFPA 72.
    b. Provide "Fire-Alarm and Emergency Communications System Record of Completion Documents" in accordance with "Completion Documents" Article in "Documentation" section of "Fundamentals" chapter in NFPA 72.
    c. Complete wiring diagrams showing connections between devices and equipment. Each conductor must be numbered at every junction point with indication of origination and termination points.
    d. Riser diagram.
    e. Device addresses.
    f. Record copy of site-specific software.
    g. Provide "Inspection and Testing Form" in accordance with "Inspection, Testing and Maintenance" chapter in NFPA 72, and include the following:

        1) Equipment tested.
        2) Frequency of testing of installed components.
        3) Frequency of inspection of installed components.
        4) Requirements and recommendations related to results of maintenance.
        5) Manufacturer's user training manuals.

    h. Manufacturer's required maintenance related to system warranty requirements.
    i. Abbreviated operating instructions for mounting at FACU and each annunciator unit.

C. Software and Firmware Operational Documentation:

1. Software operating and upgrade manuals.
2. Program Software Backup: On USB media and approved online or cloud solution.
3. Device address list.
4. Printout of software application and graphic screens.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Submittals shall comply with the requirements of Division 01 Section "Submittal Procedures" and the individual sections specifying the work.

B. Extra Stock Material: For each location, furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Lamps for Strobe Units: Quantity equal to 10 percent of amount installed, but no fewer than one unit.
2. Smoke Detectors, Heat Detectors, and Carbon Monoxide Detectors: Quantity equal to 10 percent of amount of each type installed, but no fewer than one unit of each type.
3. Detector Bases: Quantity equal to two percent of amount of each type installed, but no fewer than one unit of each type.
4. Keys and Tools: One extra set for access to locked or tamperproofed components.
5. Audible and Visual Notification Appliances: One of each type installed.
6. Fuses: Two of each type installed in system. Provide in box or cabinet with compartments marked with fuse types and sizes.

1.8 QUALITY ASSURANCE

A. Installer Qualifications:

1. Personnel must be trained and certified by manufacturer for installation of units required for this Project.
2. Installation must be by personnel certified by NICET as fire-alarm Level III or Level IV technician.
3. Obtain certification by NRTL in accordance with NFPA 72.
4. Licensed or certified by authorities having jurisdiction.

1.9 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace fire-alarm system equipment and components that fail because of defects in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 ADDRESSABLE FIRE-ALARM SYSTEM

A. Description:

1. Noncoded, UL-certified addressable system, with multiplexed signal transmission and horn-and-strobe notification for evacuation.

B. Performance Criteria:

1. Regulatory Requirements:

a. Fire-Alarm Components, Devices, and Accessories: Listed and labeled by a NRTL in accordance with NFPA 70 and NFPA 72 for use with selected fire-alarm system and marked for intended location and application.

2. General Characteristics:

a. Automatic sensitivity control of certain smoke detectors.
b. Fire-alarm signal initiation must be by one or more of the following devices and systems:

1) Manual stations.
2) Heat detectors.
3) Smoke detectors.
4) Duct smoke detectors.
5) Carbon monoxide detectors.
6) Automatic sprinkler system water flow.
7) Dry system pressure flow switch.

c. Fire-alarm signal must initiate the following actions:

1) Continuously operate alarm notification appliances.
2) Identify alarm and specific initiating device at FACU, connected network control panels, off-premises network control panels, and remote annunciators.
3) Transmit alarm signal to remote alarm receiving station.
4) Unlock electric door locks in designated egress paths.
5) Switch HVAC equipment controls to fire-alarm mode.
6) Close smoke dampers in air ducts of designated air-conditioning duct systems.
7) Recall elevators to primary or alternate recall floors.
8) Activate elevator power shunt trip.
9) Activate emergency lighting control.
10) Record events in system memory.

d. Supervisory signal initiation must be by one or more of the following devices and actions:

1) Valve supervisory switch.

2) High- or low-air-pressure switch of dry-pipe sprinkler system.
3) Elevator shunt-trip supervision.
4) Independent fire-detection and -suppression systems.
5) Zones or individual devices have been disabled.
6) FACU has lost communication with network.

e. System trouble signal initiation must be by one or more of the following devices and actions:

1) Open circuits, shorts, and grounds in designated circuits.
2) Opening, tampering with, or removing alarm-initiating and supervisory signal-initiating devices.
3) Loss of communication with addressable sensor, input module, relay, control module, remote annunciator, printer interface, or Ethernet module.
4) Loss of primary power at FACU.
5) Ground or single break in internal circuits of FACU.
6) Abnormal ac voltage at FACU.
7) Break in standby battery circuitry.
8) Failure of battery charging.
9) Abnormal position of switch at FACU or annunciator.
10) Hose cabinet door open.

f. System Supervisory Signal Actions:

1) Initiate notification appliances.
2) Identify specific device initiating event at FACU, connected network control panels, off-premises network control panels, and remote annunciators.
3) After time delay of 200 seconds, transmit trouble or supervisory signal to remote alarm receiving station.
4) Transmit system status to building management system.

g. Network Communications:

1) Provide network communications for fire-alarm system in accordance with fire-alarm manufacturer's written instructions.
2) Provide network communications pathway per manufacturer's written instructions and requirements in NFPA 72 and NFPA 70.

2.2 FIRE-ALARM CONTROL UNIT (FACU)

A. Manufacturers: Subject to compliance with requirements, provide products by Honeywell International, Inc. to match existing campus systems.

B. Description: Field-programmable, microprocessor-based, modular, power-limited design with electronic modules.

C. Performance Criteria:

1. Regulatory Requirements: Comply with NFPA 72 and UL 864.
2. General Characteristics:

a. System software and programs must be held in nonvolatile flash, electrically erasable, programmable, read-only memory, retaining information through failure of primary and secondary power supplies.
b. Include real-time clock for time annotation of events on event recorder and printer.
c. Provide communication between FACU and remote circuit interface panels, annunciators, and displays.
d. FACU must be listed for connection to central-station signaling system service.
e. Provide nonvolatile memory for system database, logic, and operating system and event history. System must require no manual input to initialize in the event of complete power down condition. FACU must provide minimum 500-event history log.
f. Addressable Initiation Device Circuits: FACU must indicate which communication zones have been silenced and must provide selective silencing of alarm notification appliance by building communication zone.

    1) Addressable Control Circuits for Operation of Notification Appliances and Mechanical Equipment: FACU must be listed for releasing service.

g. Fire-Alarm Annunciator: Arranged for interface between human operator at FACU and addressable system components including annunciation and supervision. Display alarm, supervisory, and component status messages and programming and control menu.

    1) Annunciator and Display: LCD, 80 characters, minimum.
    2) Keypad: Arranged to permit entry and execution of programming, display, and control commands.

h. Initiating-Device, Notification-Appliance, and Signaling-Line Circuits:

    1) Pathway Class Designations: NFPA 72, Class B.
    2) Pathway Survivability: Level 1.
    3) Install no more than 50 addressable devices on each signaling-line circuit.
    4) Install fault circuit isolators to comply with circuit performance requirements of NFPA 72 or with manufacturer's written instructions, whichever is more conservative.

i. Serial Interfaces:

    1) One RS 485 port for remote annunciators, Ethernet module, or multi-interface module (printer port).
    2) One USB or RS 232 port for PC configuration.

j. Notification-Appliance Circuit:

    1) Audible appliances must sound in three-pulse temporal pattern, as defined in NFPA 72. CO detectors must sound in temporal 4 pattern.
    2) Visual alarm appliances must flash in synchronization where multiple appliances are in same field of view, as defined in NFPA 72.

k. Transmission to Remote Alarm Receiving Station: Automatically transmit alarm, supervisory, and trouble signals to remote alarm station. Provide transmitter

capable of being connected to the campus fiber optic loop. Connection to loop by others.

l. Primary Power: 24 V(dc) obtained from 120 V(ac) service and power-supply module. Initiating devices, notification appliances, signaling lines, trouble signals, supervisory and transmitters must be powered by 24 V(dc) source.
m. Alarm current draw of entire fire-alarm system must not exceed 80 percent of power-supply module rating.
n. Secondary Power: 24 V(dc) supply system with batteries, automatic battery charger, and automatic transfer switch.
o. Batteries: Sealed lead calcium.

D. Accessories:

1. Instructions: Computer printout or typewritten instruction card mounted behind plastic or glass cover in stainless steel or aluminum frame. Include interpretation and describe appropriate response for displays and signals. Briefly describe functional operation of system under normal, alarm, and trouble conditions.

2.3 MANUAL FIRE-ALARM BOXES

A. Manufacturers: Subject to compliance with requirements, provide products by Honeywell International, Inc. to match existing campus systems.

B. General Requirements for Manual Fire-Alarm Boxes: Comply with UL 38. Boxes must be finished in red with molded, raised-letter operating instructions in contrasting color; must show visible indication of operation; and must be mounted on recessed outlet box. If indicated as surface mounted, provide manufacturer's surface back box.

1. Double-action mechanism requiring two actions to initiate alarm, pull-lever type; with integral addressable module arranged to communicate manual-station status (normal, alarm, or trouble) to FACU.
2. Station Reset: Key- or wrench-operated switch. Comply with municipal fire department for each site.
3. Material: Manual stations made of Lexan polycarbonate.
4. Able to be used in indoor areas.
5. Comply with city or town fire department requirements for each town, each system.

2.4 SYSTEM SMOKE DETECTORS

A. Photoelectric Smoke Detectors:

1. Manufacturers: Subject to compliance with requirements, provide products by Honeywell International, Inc. to match existing campus systems.
2. Performance Criteria:

a. Regulatory Requirements:

1) NFPA 72.

b. General Characteristics:

1) Detectors must be four or two-wire type.
2) Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to FACU.
3) Base Mounting: Detector and associated electronic components must be mounted in twist-lock module that connects to fixed base. Provide terminals in fixed base for connection to building wiring.
4) Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
5) Integral Visual-Indicating Light: LED type, indicating detector has operated and power-on status.
6) Detector address must be accessible from FACU and must be able to identify detector's location within system and its sensitivity setting.
7) Operator at FACU, having designated access level, must be able to manually access the following for each detector:

    a) Primary status.
    b) Device type.
    c) Present average value.
    d) Present sensitivity selected.
    e) Sensor range (normal, dirty, etc.).

8) Detector must have functional humidity range within 10 to 90 percent relative humidity.
9) Color: White.
10) Remote Control: Unless otherwise indicated, detectors must be digital-addressable type, individually monitored at FACU for calibration, sensitivity, and alarm condition and individually adjustable for sensitivity by FACU.
11) Multiple levels of detection sensitivity for each sensor.
12) Sensitivity levels based on time of day.

2.5 DUCT SMOKE DETECTORS

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Honeywell International, Inc.

B. Description: Photoelectric-type, duct-mounted smoke detector.

C. Performance Criteria:

1. Regulatory Requirements:

    a. NFPA 72.
    b. UL 268A.

2. General Characteristics:

    a. Detectors must be four-wire type.
    b. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to FACU.

c. Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
d. Integral Visual-Indicating Light: LED type, indicating detector has operated and power-on status.
e. Detector address must be accessible from FACU and must be able to identify detector's location within system and its sensitivity setting.
f. Operator at FACU, having designated access level, must be able to manually access the following for each detector:

1) Primary status.
2) Device type.
3) Present average value.
4) Present sensitivity selected.
5) Sensor range (normal, dirty, etc.).

g. Weatherproof Duct Housing Enclosure: NEMA 250, Type 4X; NRTL listed for use with supplied detector for smoke detection in HVAC system ducts.
h. Each sensor must have multiple levels of detection sensitivity.
i. Sampling Tubes: Design and dimensions as recommended by manufacturer for specific duct size, air velocity, and installation conditions where applied.
j. Relay Fan Shutdown: Fully programmable relay rated to interrupt fan motor-control circuit.

2.6 CARBON MONOXIDE DETECTORS

A. Manufacturers: Subject to compliance with requirements, provide products by Honeywell International, Inc. to match existing campus systems.

B. Description: Carbon monoxide detector listed for connection to fire-alarm system.

C. Performance Criteria:

1. Regulatory Requirements:

a. NFPA 72
b. NFPA 720.
c. UL 2075.

2. General Characteristics:

a. Mounting: Adapter plate for outlet box mounting.
b. Testable by introducing test carbon monoxide into sensing cell.
c. Detector must provide alarm contacts and trouble contacts.
d. Detector must send trouble alarm when nearing end-of-life, power supply problems, or internal faults.
e. Locate, mount, and wire in accordance with manufacturer's written instructions.
f. Provide means for addressable connection to fire-alarm system.
g. Test button simulates alarm condition.

2.7 HEAT DETECTORS

A. Combination-Type Heat Detectors:

1. Manufacturers: Subject to compliance with requirements, provide products by the following:

a. Honeywell International, Inc.

2. Performance Criteria:

a. Regulatory Requirements:

1) NFPA 72.
2) UL 521.

b. General Characteristics:

1) Temperature sensors must test for and communicate sensitivity range of device.

c. Actuated by fixed temperature of 135 deg F or rate of rise that exceeds 15 deg F per minute unless otherwise indicated.
d. Mounting: Twist-lock base interchangeable with smoke-detector bases.
e. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to FACU.
f. Detector must have functional humidity range of 10 to 90 percent relative humidity.
g. Color: White.

B. Fixed-Temperature-Type Heat Detectors:

1. Manufacturers: Subject to compliance with requirements, provide products by the following:

a. Honeywell International, Inc.

2. Performance Criteria:

a. Regulatory Requirements:

1) NFPA 72.
2) UL 521.

b. General Characteristics:

1) Actuated by temperature that exceeds fixed temperature of 190 deg F.
2) Mounting: Twist-lock base interchangeable with smoke-detector bases.
3) Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to FACU.
4) Detector must have functional humidity range of 10 to 90 percent.
5) Color: White.

2.8 FIRE-ALARM NOTIFICATION APPLIANCES

A. Fire-Alarm Audible Notification Appliances:

1. Manufacturers: Subject to compliance with requirements, provide products by Honeywell International, Inc. to match existing campus systems.
2. Description: Horns that cannot output voice messages.
3. Performance Criteria:

a. Regulatory Requirements:

1) NFPA 72.

b. General Characteristics:

1) Connected to notification-appliance signal circuits, zoned as indicated, equipped for mounting as indicated, and with screw terminals for system connections.
2) Audible notification appliances must have functional humidity range of 10 to 95 percent relative humidity.
3) Horns: Electric-vibrating-polarized type, 24 V(dc); with provision for housing operating mechanism behind grille. Comply with UL 464. Horns must produce sound-pressure level of 90 dB(A-weighted), measured 10 ft. from horn, using coded signal prescribed in UL 464 test protocol.
4) Combination Devices: Factory-integrated audible and visible devices in single-mounting assembly, equipped for mounting as indicated, and with screw terminals for system connections.

B. Fire-Alarm Visible Notification Appliances:

1. Manufacturers: Subject to compliance with requirements, provide products by Honeywell International, Inc. to match existing campus systems.
2. Performance Criteria:

a. Regulatory Requirements:

1) NFPA 72.
2) UL 1971.

b. General Characteristics:

1) Rated Light Output:

a) 15/30/75/110 cd, selectable in field.

2) Clear or nominal white polycarbonate lens mounted on aluminum faceplate.
3) Mounting: Wall mounted unless otherwise indicated.
4) For units with guards to prevent physical damage, light output ratings must be determined with guards in place.
5) Flashing must be in temporal pattern, synchronized with other units.
6) Strobe Leads: Factory connected to screw terminals.
7) Mounting Faceplate: Factory finished, white. Labeled: Alert.

2.9 FIRE-ALARM REMOTE ANNUNCIATORS

A. Manufacturers: Subject to compliance with requirements, provide products by Honeywell International, Inc. to match existing campus systems.
B. Performance Criteria:

1. Regulatory Requirements:

a. NFPA 72.

2. General Characteristics:

a. Annunciator functions must match those of FACU for alarm, supervisory, and trouble indications. Manual switching functions must match those of FACU, including acknowledging, silencing, resetting, and testing.

1) Mounting: Surface cabinet, NEMA 250, Type 1.

b. Display Type and Functional Performance: Alphanumeric display and LED indicating lights must match those of FACU. Provide controls to acknowledge, silence, reset, and test functions for alarm, supervisory, and trouble signals.

2.10 FIRE-ALARM ADDRESSABLE INTERFACE DEVICES

A. Manufacturers: Subject to compliance with requirements, provide products by Honeywell International, Inc. to match existing campus systems.
B. Performance Criteria:

1. Regulatory Requirements:

a. NFPA 72.

2. General Characteristics:

a. Include address-setting means on module.
b. Store internal identifying code for control panel use to identify module type.
c. Listed for controlling HVAC fan motor controllers.
d. Monitor Module: Microelectronic module providing system address for alarm-initiating devices for wired applications with normally open contacts.
e. Control Module:

1) Operate notification devices.
2) Operate solenoids for use in sprinkler service.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and conditions for compliance with requirements for ventilation, temperature, humidity, and other conditions affecting performance of the Work.

1. Verify that manufacturer's written instructions for environmental conditions have been permanently established in spaces where equipment and wiring are installed, before installation begins.

B. Examine roughing-in for electrical connections to verify actual locations of connections before installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Preinstallation Testing: Perform verification of functionality of installed components of existing system prior to starting work. Document equipment or components not functioning as designed.

B. Interruption of Existing Fire-Alarm Service: Do not interrupt fire-alarm service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary guard service in accordance with requirements indicated:

1. Notify Contract Administrator no fewer than twenty-one days in advance of proposed interruption of fire-alarm service.
2. Do not proceed with interruption of fire-alarm service without Contract Administrator’s written permission.
3. Coordinate outages with local fire department. Comply with outage requirements.

C. Protection of In-Place Conditions: Protect devices during construction unless devices are placed in service to protect facility during construction.

3.3 INSTALLATION OF EQUIPMENT

A. Comply with NECA 305, NFPA 72, NFPA 101, and requirements of authorities having jurisdiction for installation and testing of fire-alarm equipment. Install electrical wiring to comply with requirements in NFPA 70 including, but not limited to, Article 760, "Fire Alarm Systems."

1. Devices are not permitted to be placed in service before other trades have completed cleanup.
2. Devices installed, but not yet placed, in service must be protected from construction dust, debris, dirt, moisture, and damage in accordance with manufacturer's written storage instructions.

B. Install wall-mounted equipment, with tops of cabinets not more than 78 inch above finished floor.

C. Manual Fire-Alarm Boxes:

1. Install manual fire-alarm box in normal path of egress within 60 inch of exit doorway.
2. Mount manual fire-alarm box on background of contrasting color.
3. Operable part of manual fire-alarm box must be between 42 and 48 inch above floor level. Devices must be mounted at same height unless otherwise indicated.

D. Smoke Detector Spacing:

1. Comply with "Smoke-Sensing Fire Detectors" section in "Initiating Devices" chapter in NFPA 72, for smoke-detector spacing.
2. Comply with “Heat-Sensing Fire Detectors” section in “Initiating Devices” chapter in NFPA 72, for heat detector spacing.
3. Smooth ceiling spacing must not exceed 30 ft.
4. Spacing of detectors for irregular areas, for irregular ceiling construction, and for high ceiling areas must be determined in accordance with Annex A or Annex B in NFPA 72.
5. HVAC: Locate detectors not closer than 36 inch from air-supply diffuser or return-air opening.
6. Lighting Fixtures: Locate detectors not closer than 12 inch from lighting fixture and not directly above pendant mounted or indirect lighting.

E. Install cover on each smoke detector that is not placed in service during construction. Cover must remain in place except during system testing. Remove cover prior to system turnover.

F. Remote Status and Alarm Indicators: Install in visible location near each smoke detector, sprinkler water-flow switch, and valve-tamper switch that is not readily visible from normal viewing position.

G. Audible Alarm-Indicating Devices: Install not less than 6 inch below ceiling. Install horns on flush-mounted back boxes with device-operating mechanism concealed behind grille. Install devices at same height unless otherwise indicated.

H. Visible Alarm-Indicating Devices: Install adjacent to each alarm horn, or as a combination unit, and at least 6 inch below ceiling. Install devices at same height unless otherwise indicated.

I. Device Location-Indicating Lights: Locate in public space near device they monitor.

J. Duct Smoke Detectors: Comply with NFPA 72 and NFPA 90A. Install sampling tubes so they extend full width of duct. Tubes more than 36 inch long must be supported at both ends.

1. Do not install smoke detector in duct smoke-detector housing during construction. Install detector only during system testing and prior to system turnover.

3.4 ELECTRICAL CONNECTIONS

A. Connect wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. Ground equipment in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

C. Install electrical devices furnished by manufacturer, but not factory mounted, in accordance with NFPA 70 and NECA 1.

D. Install nameplate for each electrical connection, indicating electrical equipment designation and circuit number feeding connection.

1. Nameplate must be laminated acrylic or melamine plastic signs, red background with engraved white letters, as specified in Section 260553 "Identification for Electrical Systems."

3.5 CONTROL CONNECTIONS

A. Install control and electrical power wiring to field-mounted control devices.

B. Install nameplate for each control connection, indicating field control panel designation and I/O control designation feeding connection.

3.6 PATHWAYS

A. Pathways must be installed in EMT or ERMC-S in accordance with Section 260533.13 "Conduits for Electrical Systems."

B. Exposed conduit and boxes must be painted red enamel.

3.7 CONNECTIONS

A. Make addressable connections with supervised interface device to the following devices and systems. Install interface device less than 36 inch from device controlled. Make addressable confirmation connection when such feedback is available at device or system being controlled.

1. Supervisory connections at valve supervisory switches.

3.8 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

B. Install framed instructions in location visible from FACU.

3.9 GROUNDING

A. Ground FACU and associated circuits in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."

B. Ground shielded cables at control panel location only. Insulate shield at device location.

3.10 FIELD QUALITY CONTROL

A. Field tests must be witnessed by authorities having jurisdiction.

B. Administrant for Tests and Inspections:

1. Engage factory-authorized service representative to administer and perform tests and inspections on components, assemblies, and equipment installations, including connections.

C. Tests and Inspections:

1. Visual Inspection: Conduct visual inspection prior to testing.

a. Inspection must be based on completed record Drawings and system documentation that is required by "Completion Documents, Preparation" table in "Documentation" section of "Fundamentals" chapter in NFPA 72.
b. Comply with "Visual Inspection Frequencies" table in "Inspection" section of "Inspection, Testing and Maintenance" chapter in NFPA 72; retain "Initial/Reacceptance" column and list only installed components.

2. System Testing: Comply with "Test Methods" table in "Testing" section of "Inspection, Testing and Maintenance" chapter in NFPA 72.
3. Test audible appliances for public operating mode in accordance with manufacturer's written instructions. Perform test using portable sound-level meter complying with Type 2 requirements in ASA S1.4 Part 1/IEC 61672-1.
4. Test audible appliances for private operating mode in accordance with manufacturer's written instructions.
5. Test visible appliances for public operating mode in accordance with manufacturer's written instructions.
6. Factory-authorized service representative must prepare "Fire Alarm System Record of Completion" in "Documentation" section of "Fundamentals" chapter in NFPA 72 and "Inspection and Testing Form" in "Records" section of "Inspection, Testing and Maintenance" chapter in NFPA 72.

D. Reacceptance Testing: Perform reacceptance testing to verify proper operation of added or replaced devices and appliances.

E. Fire-alarm system will be considered defective if it does not pass tests and inspections.

F. Prepare test and inspection reports.

G. Maintenance Test and Inspection: Perform tests and inspections listed for weekly, monthly, quarterly, and semiannual periods. Use forms developed for initial tests and inspections.

H. Annual Test and Inspection: One year after date of Substantial Completion, test fire-alarm system complying with visual and testing inspection requirements in NFPA 72. Use forms developed for initial tests and inspections.

3.11 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain fire-alarm system. Provide video recording of training to Owner.

3.12 SOFTWARE SERVICE AGREEMENT

A. Comply with UL 864.

B. Technical Support: Beginning at Substantial Completion, service agreement must include software support for two years.

C. Upgrade Service: At Substantial Completion, update software to latest version. Install and program software upgrades that become available within two years from date of Substantial Completion. Upgrading software must include operating system and new or revised licenses for using software.

1. Upgrade Notice: At least 30 days to allow Owner to schedule access to system and to upgrade computer equipment if necessary.


END OF SECTION

Appendix - _A	Appendix A - CR's, DS's, EDR, REX Button, EOLRPKG
Appendix - _B	Appendix B - PS Monitoring, Panel Tampers, Panic, Blue Strobe Shunt
Appendix - _C1	Appendix C - PDO Integration with BEA MC-25
Appendix - _C2	Appendix C - PDO Integration with BEA Br3-X
Appendix - _C3	Appendix C - PDO Integration with BEA Br2-900 ----DRAFT
Appendix - _D	Appendix D - Inovonics Wireless Panic EN4216MR
Appendix - _E	Appendix E - Inovonics Wireless Panic EN4232MR
~~Appendix - _F~~	~~Appendix F - ECS Viking Wiring / Mounting~~ Viking ECS No Longer Used June 2021
Appendix - _G	Appendix G - ECS Talk-a-Phone Wiring
Appendix - _H	Appendix H - Restroom Privacy System (BEA 10RESTROOM KIT w/PAM-2 Relay)
Appendix - _I	Appendix I - Recommended Panel and Wire Way Mounting Configuration
Appendix - _j	Appendix J - System Riser and Wire Legend
Appendix - _K	Appendix K - Panel Level Riser Diagram Typical
Appendix - _L	Appendix L - Single Door Single Card Reader Devices
Appendix - _M	Appendix M - Single Door Dual Card Reader Devices
Appendix - _N	Appendix N - Inovonics Wire Colors & Programming Instructions (two pages)
Appendix - _O-S	Appendix O - S - Lantronix, IQ200, IQ8, SAM and OUT Board Outlines
Appendix - _T	Appendix T - ASR Zone Interconnect and Lock Down / Schedule Suspension

Abbreviations

ACMx	Access Control Module (in Lock Power Supply) "x" refers to number of in/outputs
ASR	Access Secure Reader
CMF	CCTV - Fixed
CR	Card Reader
CS	Counter Status
DO	Door Opener see PDO
DS	Door Position Switch
ECL	Electrified Cylindrical Lock
ECS	Emergency Call Station
EDR	Emergency Door Release
EEB	Emergency Egress Button
ELR	Electric Latch Retraction
EML	Electrified Mortise Lock
EOL EOLR	End Of Line End Of Line Resistor
ES	Electric Strike
FACP	Fire Alarm Control Panel
GND	Ground
LK	Lock
KB	Knox Box
ML	Magnetic Lock
MOV	Metal Oxide Varistor
PB	Panic Button
PCSC	Manufacture of the Access Control Panels
PDO	Handicapped Power Door Operator
PS	Power Supply
PTZ	CCTV - Pan Tilt Zoom
RDR	Reader Terminals on PCSC Boards
REX	Request to Exit
RFQ	Request For Quote
RS485	Communications Protocol
RXB	Request to Exit Button
RXM	Request to Exit Motion
SHD	Shield or Drain Conductor
SI	Sense Input
SoM	State of Maine
TS	Terminal Server
TSB	Touch Sense Bar
TSH	Touch Sense Handle
WPB	Wireless Panic Button
WPC	Wireless Panic Control Unit
WPR	Wireless Panic Repeater

xx CSxx, CRxx, DSxx, SIxx etc. xx references a point number designated on circuit board drawings



State of Maine
Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld

RFQ 18A-bld-date

Document Revisions

2025-02-24	Modified C to C1, C2 & C3 - New PDO module versions
2022-01-27	Updated B, Blue Strobe Shunt. Add Appendixes O - S
2021-11-10	Updated I-N, Crossed out F
2021-05-03	Updated A, Replaced I, Add N
2020-05-15	Added Appendix K-M
2020-02-24	Renaming Items and updated Talk-a-Phone
2020-02-04	Replaced "Duress" with "Panic"
2019-12-20	Inovonics Wiring / Programming Documentation added
2019-08-22	Restroom Privacy System - Completed
2019-06-17	Restroom Privacy System - DRAFT
2019-05-13	Split REX Button and Break Glass for clarification
2018-06-12	Alter Appendix Pg #'s, add 2nd Inovonics, add Talk a Phone
2017-06-19	Chang ECB to ECS, Alter Appendix Pg #'s
2017-04-14	Updated Abbreviations, add SI points
2017-04-06	Significant Revisions To All
2017-03-15	Original Document Set


Title Sheet, Index, Abbreviations, Notes

Drawing Number BCC-bld-01 - 01




Use of PCSC p/n EOLRPKG
highly recommended.
EOL Resistors are to be installed
at the device, NOT at the panel.

Single Door Switch Wiring



Use of PCSC p/n EOLRPKG
highly recommended.
EOL Resistors are to be Installed
at the device, NOT at the panel.

Two Door Switch Wiring




HID 5355 Card Reader
HID 5365 uses pigtail, safely isolate unused conductors


Card Reader Wiring Standard




EOLRPKG




Lock Down / Sch Suspend




ASR Wiring Specific Wiring



Emergency Door Release



Emergency Egress Button aka Request to Exit Button



Two Card Readers on one point

State of Maine

Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety

Document Revisions


2021-05-03 Lock Down / Sch Suspend
2021-03-05 ASR Wiring
2020-02-24 Rename EBU to EDR
2019-05-13 Clarified Emerg. Btn & Break Glass
2019-03-11 Added ASR Wiring
2017-04-11

Not all devices are used in all projects


Appendix A

- Card Reader
- Two CR's in Parallel
- Door Position Switches
- Emergency Door Release
- Emergency Egress Button aka Request to Exit Button
- EOLRPKG


Drawing Number Appendix - _A




Power Supply Monitoring




Fail Safe or Magnetic Lock Wiring



PCSC & Power Supply Panel Tamper Switches




Fail Secure Lock Wiring



SI xx EOL Resistors are to be installed at the device, NOT at the panel.

Ademco 269R Panic Switch



SI xx EOL Resistors are to be installed at the device, NOT at the panel.

All three will flash when another panic is triggered. However, if this panic is triggerted the sbrobe will be shunted and potentially not escalate the situation requiring the panic activation, yet all other strobes will flash.

Ademco 269R Panic Switch w BLUE STROBE Shunt

State of Maine

Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety

Document Revisions


2022-01-27 Panic Strobe Shunt
2018-07-19 Change AC & Battery supervision, split into two.
2017-04-11

Not all devices are used in all projects

Appendix B

- Power Supply Monitoring
- PCSC & PS Panel Tampers
- Panic Switch
- Fail Safe / Fail Secure

Drawing Number Appendix - _B



Sequence of Operation Narrative

Overall principle is for the exterior actuator button to only work when the facility is unlocked and thus keeping the operator from applying pressure to the lock hardware placing the PDO into safety or shutdown modes.

The interior actuator button will work at all times and signal the PCSC panel of someone's need to exit. The BEA MC-25 relay module provides a dry contact to the PCSC panel and a short time later then signals the PDO to operate.

DIP switches must be set in the MC-25 for a long delay between relay one and relay two.

BEA is the manufacturer of the MC-25 and is available from many sources, not only PDO installers.

State of Maine
Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety


Document Revisions

2017-05-24 Added Operation Narrative
2017-04-11

Not all devices are used in all projects

Appendix C1 PDO Integration with BEA MC-25

Drawing Number Appendix - _C1



Sequence of Operation Narrative

Overall principle is for the exterior actuator button to only work when the facility is unlocked and thus keeping the operator from applying pressure to the lock hardware placing the PDO into safety or shutdown modes.

The interior actuator button will work at all times and signal the PCSC panel of someone's need to exit. The BEA Br3-X module provides a dry contact to the PCSC panel and a short time later then signals the PDO to operate.

Programming must be set in the Br3-X for a long delay between relay one and relay two.

BEA is the manufacturer of the Br3-X and is available from many sources, not only PDO installers.

State of Maine
Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety

Document Revisions

2025-02-24 New Page


Not all devices are used in all projects


Appendix C2 PDO Integration with BEA BR3-X


Drawing Number Appendix - _C2

dn - Day Night Mode

Power Door Operator (PDO)







Sequence of Operation Narrative

Overall principle is for the exterior actuator button to only work when the facility is unlocked and thus keeping the operator from applying pressure to the lock hardware placing the PDO into safety or shutdown modes.

The interior actuator button will work at all times and signal the PCSC panel of someone's need to exit. The BEA Br3-X module provides a dry contact to the PCSC panel and a short time later then signals the PDO to operate.

Programming must be set in the Br3-X for a long delay between relay one and relay two.

BEA is the manufacturer of the Br3-X and is available from many sources, not only PDO installers.

State of Maine
Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety


Document Revisions


2025-02-24 New Page

Not all devices are used in all projects

Appendix C3 PDO Integration with BEA Br2-900

Drawing Number Appendix - _C3





Warning: Incorrect connections may cause damage to the Inovonics unit.

General Wiring Notes for Inovonics Wireless System

1 - 12VDC for the Controller must be supplied from the same PCSC IQ panel where the associated SI points are monitored. The GND is common throughout power and inputs.

2 - 12VDC for Repeaters from a PCSC IQ Power Supply or battery backed up power supply pre-approved by owner.

3 - Neither Control or Repeaters shall be mounted above ceilings.

4 - After installation, test transmitter signal strength and document that it meets Inovonics minimum specifications.

5 - Required Points: Relays 1 & 6; Jam, Tamper and Reset

State of Maine

Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety


Document Revisions

2017-07-13 Corrected Jam & Power Loss wiring
2017-05-14 General wiring notes added
2017-04-11

Not all devices are used in all projects

Appendix D
Inovonics Wireless Panic Hardware
EN4216MR

Drawing Number Appendix - _D



General Wiring Notes for Inovonics Wireless System


1 - 12VDC for the Controller must be supplied from the same PCSC IQ panel where the associated SI points are monitored. The GND is common throughout power and inputs.

2 - 12VDC for Repeaters from a PCSC IQ Power Supply or battery backed up power supply pre-approved by owner.

3 - Neither Control or Repeaters shall be mounted above ceilings.

4 - After installation, test transmitter signal strength and document that it meets Inovonics minimum specifications.

5 - Required Points: Relays 1 & 6; Jam, Tamper and Reset



State of Maine
Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety

Document Revisions

2018-06-07

Not all devices are used in all projects

Appendix E
Inovonics Wireless Panic Hardware
EN4232MR

Drawing Number Appendix - _E

ELECTRICAL NOTES

120VAC
- Provide 120VAC from an un-switched source with preference to emergency generator powered source where available.
- LED Blue Light: 7.8W
- Install a single pole service disconnect switch inside the enclosure, or Ideal PowerPlug^{tm} etc.
- Low voltage cabling may not be combined in the same AC conduit.

GROUNDING
- Connect earth ground to the supplied lug.
- Provide a 24" minimum 16 ga. green lead for connection to the ETP-500E.

TELEPHONE
- Analog POTS terminated with RJ11 jack
- See Talk-a-Phone documentation for cable size and type


SECURITY LIFE SAFETY MONITORING
- One pair conductors such as 22/2 or 22/6 OAS

CONDUIT KNOCKOUTS
- The Wall Mount unit has two $\frac{3}{4}$" knockouts located on the bottom and two on the back.

TERMINATIONS

LED Beacon
- Gray color jacketed cable
  White - 120VAC neutral
  Black - 120VAC line via service switch


Telephone
- Ground
  Green to Ground lead
- To LED
  Orange to LED Orange
  Black to LED Black
- Monitoring using End of Line Resistor Pack
  Red and White to two EOLPKG black leads




ETP-WME
"Wall Mount"

MOUNTING HEIGHT

Wall Mount enclosure shall be mounted so that the call button is no higher than 48" max. FFE.




ETP-MTE
"Tower"



Two 1 $\frac{1}{4}$" conduit stub above foundation >12".
Conduits stub out side of foundation >18" below finished grade.
Use sweeping 90 degree bends.

See Talk-a-Phone foundation construction specifications for rebar.



State of Maine
Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety

Document Revisions

2021-03-31 Added Foundation Data
2020-02-23 Added Wire Terminations
2018-06-12 Original

Not all devices are used in all projects

Appendix G Emergency Call Station Talk-a-Phone

Drawing Number Appendix - _G

EQUIPMENT NECESSARY

Control Module
- Manufacturer - BEA
  Model "10RESTROOM KIT"


Relay
- Manufacturer - Firelite, SSU, Potter
  Model "PAM2"

OPERATION NARRATIVE

- Card Reader allows access to authorized users.
- User enters, lets the door close and then depresses the "Push to Lock" button.
- The green indicator will illuminate on the "Push to Lock" button and outside on the "Occupied" indicator.
- During the occupied time the Card Reader will not allow another user to access regardless of their access rights. Card Reader will not even beep.
- When the user opens the door the Privacy System resets to normal operation.

PROGRAMMING

1. Depress INCR and FUNC at same time for four seconds. Release and display flashes FF OO FF....
2. Depress FUNC repeatedly to cycle through functions until nL is displayed.
3. FF OO will repleate for about five seconds then nL remains. This is all the programming necessary.



State of Maine
Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety


Document Revisions

2019-09-09 Corrected DPS NO/NC
2019-08-22 Original

Not all devices are used in all projects

Appendix H Restroom Privacy System

Drawing Number Appendix - _H



NOT TO SCALE

State of Maine

Building Control Center

Project Appendix

Reference RFQ Security, Access Control and Life Safety

Document Revisions

2023-12-08 Updated details for couplings
2021-05-03

Not all devices are used in all projects

Appendix I


Recommended Panel and Wire Way Mounting Configuration

Drawing Number Appendix - _I

WIRE & CABLE LEGEND:

CABLE	DESCRIPTION	APPLICATION
A	6 CONDUCTORS, STR, SHIELDED, #22 AWG	CARD READER WIRING
B	2 CONDUCTORS, STR, SHIELDED, #22 AWG	DOOR CONTACT & DO PUSH BUTTON
C	4 CONDUCTORS, STR, SHIELDED, #22 AWG	REQUEST TO EXIT MOTION
D	4 CONDUCTORS, STR, SHIELDED, #18 AWG	LOCK POWER / ASR ZONE INTERCONNECT
E	2 CONDUCTORS, STR, SHIELDED, #22 AWG	RS-485 COMM. & FIRE ALARM CONNECTION
F	RG-59U COAXIAL, 95% COPPER SHIELD, #20 AWG	ANALOG VIDEO FOR ELEVATORS
G	4 PAIRS, SOLID, JACKETED, #24 - CERT. CAT6	NETWORK CABLE
S	SmartWire (R) (1A,1B,1C,1D in composite cable)	SmartWire Part #: 4461230

QUANTITY OF CABLE TYPE — 1G
CABLE TYPE



State of Maine
Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld

RFQ 18A-bld-date

Document Revisions

2022-10-11 Add ASR Zone Interconnect
2020-05-12


SYSTEM RISER

WIRE LEGEND

Drawing Number Appendix - _J


WIRE & CABLE LEGEND:

CABLE	DESCRIPTION	APPLICATION
A	6 CONDUCTORS, STR, SHIELDED, #22 AWG	CARD READER WIRING
B	2 CONDUCTORS, STR, SHIELDED, #22 AWG	DOOR CONTACT & DO PUSH BUTTON
C	4 CONDUCTORS, STR, SHIELDED, #22 AWG	REQUEST TO EXIT MOTION
D	4 CONDUCTORS, STR, SHIELDED, #18 AWG	LOCK POWER / ASR ZONE INTERCONNECT
E	2 CONDUCTORS, STR, SHIELDED, #22 AWG	RS-485 COMM. & FIRE ALARM CONNECTION
F	RG-59U COAXIAL, 95% COPPER SHIELD, #20 AWG	ANALOG VIDEO FOR ELEVATORS
G	4 PAIRS, SOLID, JACKETED, #24 - CERT. CAT6	NETWORK CABLE
S	SmartWire (R) (1A,1B,1C,1D in composite cable)	SmartWire Part #: 4461230



DEVICE LEGEND

CR	CARD READER
DO	DOOR OPERATOR (ADA)
DS	DOOR SWITCH / CONTACT
EDR	EMERGENCY DOOR RELEASE
HN	HORN / SIREN
JB	JUNCTION BOX
KB	KNOX BOX
LK	LOCK
PB	PUSH BUTTON (ADA)
PN	PANIC BUTTON
PT	POWER TRANSFER i.e. HINGE
RX	REQUEST TO EXIT



State of Maine
Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld


RFQ 18A-bld-date


Document Revisions

2022-10-11 Add ASR Zone Interconnect
2020-05-14

PANEL LEVEL RISER DIAGRAM TYPICAL

Drawing Number Appendix - _K





SECURE SIDE

UNSECURE SIDE

State of Maine
Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld

RFQ 18A-bld-date


Document Revisions


2020-05-14

SINGLE DOOR

SINGLE CARD READER
Electrified Lock

Drawing Number Appendix - _L





State of Maine
Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld

RFQ 18A-bld-date

Document Revisions

2017-04-11

SINGLE DOOR

ASYLUM OR DUAL OCCUPANCY CARD READER OPENING

Drawing Number Appendix - _M

Appendix _N
Inovonics Wiring Colors & Programming Instructions

Inovonics Panic System Controller Wire Colors

(recommended)

	Cable One
R	+
Bk	- (also jumper to all relay Commons)
W	NC1 (relay 1)
Bu	NC2 (relay 2)
Bn	NC3 (relay 3)
Gn	NC4 (relay 4)

	Cable Two
R	NC5 (relay 5)
Bk	NC6 (relay 6 – this relay must be wired, "Common Wireless Device Trouble" point) Low Batt, Supervision, Tamper
W	Jamming
Bu	Reset
Bn	Tamper
Gn	Controller Power Loss

Inovonics EN4216MR Programing Instructions

See official Inovonics installation documents for complete instructions.
This Instruction document is not intended to provide any instruction contrary to Inovonics and is a *work-in-progress*.
Constructive critique is welcome to improve this and all Building Control Center project documents.

- Each transmitter shall be programed to an individual relay output.

- Words in **bold font** reference buttons to press
- UPPERCASE are the displayed text on the controller

1 – From the start screen, press the **enter** button to access the receiver's menu
2 – Use the **up** and **down** buttons to navigate to the INSTALL & SERVICE menu; press **enter**
3 – Enter the password using the **up** and **down** buttons; press enter to move to next position
After entering 3446; press **enter** again to access SETUP POINT

<u>Configure each device</u>

4 – With POINT SETUP displayed; press **enter** and the display will now add the point number 01 through 16
5 – Use the **up** and **down** buttons to display the point number you wish to program; press **enter**
6 – The display will indicate the TX NOT REGSTR'D (Registered); press **enter**
Note "NOT" is displayed when no transmitter is programmed for the point and "NOT" will be missing if a transmitter has previously been programmed to the point
7 – Press **enter** three times accepting 60 MIN for SPV TIME (Supervision time)
8 – Use the **up** and **down** buttons to select SECURITY or REPEATER; press **enter**
Program transmitters to the same point number as the output relay where possible.
It is preferable to have only one wireless transmitter per output point where possible.
Program Repeaters to the upper point numbers such as 12-16.

For Security devices

9 – Press **enter** to accept 1 ALARM INPUT

10 – Use the **up** and **down** buttons to select ALARM OUT "Relay" number for this point; press **enter**

11 – Use the **up** and **down** buttons to select ALARM LATCHING (this will keep a point in alarm until "reset") ; press **enter**
"Inactive, Tamper and Low Battery" all report to OUT 06 FAULT relay

12 – Press **enter** to accept assignment of INACTIVE OUT 06

13 – Press **enter** to accept assignment of INACTIVE FOLLOWER

14 – Press **enter** to accept assignment of TAMPER OUT 06

15 – Press **enter** to accept assignment of TAMPER LATCHING

16 – Press **enter** to accept assignment of LOW BATT OUT 06

17 – Press **enter** to accept assignment of LOW LATCHING

18 – Use the **up** and **down** buttons to enter brief description TEXT: ; press **enter** repeatedly to get to next step
Eight characters may be entered as a point description

19 – REGISTER TX? Use the **up** and **down** buttons to choose Y; press **enter** to enroll a wireless transmitter or; press **enter** to be taken to the next SETUP POINT

- Depress the "**reset**" button on the transmitter, NOT the normal activation button.
- TX REG'D (DIGITS); press **enter** to get to next step

For Repeaters

- From step 8 above -

21 – Press **enter** to accept assignment of INACTIVE OUT 06

22 – Press **enter** to accept assignment of INACTIVE FOLLOWER

23 – Press **enter** to accept assignment of TAMPER OUT 06

24 – Press **enter** to accept assignment of TAMPER LATCHING

25 – Press **enter** to accept assignment of LOW BATT OUT 06

26 – Press **enter** to accept assignment of LOW LATCHING

27 – Use the **up** and **down** buttons to select 06 for AC LOSS OUT 06; press **enter**

28 – Press **enter** to accept assignment of AC LOSS FOLLOWER

29 – Use the **up** and **down** buttons to enter brief description TEXT: ; press **enter** repeatedly to get to next step
Eight characters may be entered as a point description


30 – REGISTER TX? Use the **up** and **down** buttons to choose Y; press **enter** to enroll a wireless transmitter or; press **enter** to be taken to the next SETUP POINT

- Depress the "**reset**" button on the transmitter, NOT the normal activation button.
- TX REG'D (DIGITS); press **enter** to get to next step

When configuration is complete, press **back** a couple times until EXIT? N is displayed; use the **up** and **down** buttons to enter Y; press **enter**

These Settings good for project to project unless otherwise noted.
1 & 2 = 5 Volt Card Reader
2 & 3 = 12 Volt Card Reader
4 & 5, 7 & 8, 10 & 11 = 5 Wire Wiegand Data Format

1 & 2 = for middle of bus
2 & 3 = for end of bus



Device & Wiring Notes for all projects

All REX devices - NO (Normally Open) with no Supervision.

All DS, Panic, Panic etc. devices - NC (Normally Closed) with Supervision.

Panel enclosure Tamper switches may all be wired in series with SI13, no Supervision.

Power Supply Monitoring for all PS's, no Supervision.

State of Maine
Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld


RFQ 18A-bld-date

Document Revisions

2023-12- 8 RS-485 wiring outward now connected to same as incoming
2022-01-27 Label Standard Allocated Point Descriptions
2018-03-23 Re-label SI13 for clarity of purpose
2017-08-03 Wiring for TS redrawn to indicate not to terminate on IQ power terminal block
2017-04-11

PCSC IQ200

Drawing Number Appendix - _O



State of Maine

Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld

RFQ 18A-bld-date


Document Revisions

2022-01-27 Label Standard Allocated Point Descriptions
2020-05-20 5W / 4W Warning
2017-04-11

PCSC IQ 8 Up

IQ 4 Up similar

Drawing Number Appendix - _P



State of Maine

Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld


RFQ 18A-bld-date

Document Revisions

2022-01-27 Label Standard Allocated Point Descriptions
2020-04-22 Correct FACP to T Terminal
2017-04-11

ACM8

Drawing Number Appendix - _Q



SI56 - SI71 are unsupervised inputs, no EOL resistors are used on these points

State of Maine

Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld

RFQ 18A-bld-date


Document Revisions

2022-01-27 Label Standard Allocated Point Descriptions
2017-04-11

PCSC IQ OUT

IQ ALM does not have CS points

Drawing Number Appendix - _R



State of Maine

Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld

RFQ 18A-bld-date

Document Revisions

2022-01-27 Label Standard Allocated Point Descriptions
2017-04-11

PCSC SAM


Drawing Number Appendix - _S

WIRE & CABLE LEGEND:


CABLE	DESCRIPTION	APPLICATION
A	6 CONDUCTORS, STR, SHIELDED, #22 AWG	CARD READER WIRING
B	2 CONDUCTORS, STR, SHIELDED, #22 AWG	DOOR CONTACT & DO PUSH BUTTON
C	4 CONDUCTORS, STR, SHIELDED, #22 AWG	REQUEST TO EXIT MOTION
D	4 CONDUCTORS, STR, SHIELDED, #18 AWG	LOCK POWER / ASR ZONE INTERCONNECT
E	2 CONDUCTORS, STR, SHIELDED, #22 AWG	RS-485 COMM. & FIRE ALARM CONNECTION
F	RG-59U COAXIAL, 95% COPPER SHIELD, #20 AWG	ANALOG VIDEO FOR ELEVATORS
G	4 PAIRS, SOLID, JACKETED, #24 - CERT. CAT6	NETWORK CABLE
S	SmartWire (R) (1A,1B,1C,1D in composite cable)	SmartWire Part #: 4461230


QUANTITY OF CABLE TYPE — 1G
CABLE TYPE

Bottom View of Relay



Top View of Relay Base





State of Maine
Building Control Center

Project Name

Street
Augusta, ME 04330

Building Code bld

RFQ 18A-bld-date

Document Revisions

2022-10-11

ASR Zone Interconnect and Lock Down / Schedule Suspension

Drawing Number Appendix - _T

SECTION 311000 - SITE CLEARING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Protecting existing vegetation to remain.
2. Removing existing vegetation.
3. Clearing and grubbing.
4. Stripping and stockpiling topsoil.
5. Removing above- and below-grade site improvements.
6. Disconnecting, capping or sealing, and removing site utilities.
7. Temporary erosion and sedimentation control.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for temporary erosion- and sedimentation-control measures.

1.2 DEFINITIONS

A. Subsoil: Soil beneath the level of subgrade; soil beneath the topsoil layers of a naturally occurring soil profile, typified by less than 1 percent organic matter and few soil organisms.

B. Surface Soil: Soil that is present at the top layer of the existing soil profile. In undisturbed areas, surface soil is typically called "topsoil," but in disturbed areas such as urban environments, the surface soil can be subsoil.

C. Topsoil: Top layer of the soil profile consisting of existing native surface topsoil or existing in-place surface soil; the zone where plant roots grow. Its appearance is generally friable, pervious, and black or a darker shade of brown, gray, or red than underlying subsoil; reasonably free of subsoil, clay lumps, gravel, and other objects larger than 2 inches in diameter; and free of weeds, roots, toxic materials, or other nonsoil materials.

D. Tree-Protection Zone: Area surrounding individual trees or groups of trees to be protected during construction and indicated according to requirements in Section 015639 "Temporary Tree and Plant Protection.".

E. Vegetation: Trees, shrubs, groundcovers, grass, and other plants.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.4 MATERIAL OWNERSHIP

A. Except for materials indicated to be stockpiled or otherwise remain Owner's property, cleared materials shall become Contractor's property and shall be removed from Project site.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Existing Conditions: Documentation of existing trees and plantings, adjoining construction, and site improvements that establishes preconstruction conditions that might be misconstrued as damage caused by site clearing.

1. Use sufficiently detailed photographs or video recordings.
2. Include plans and notations to indicate specific wounds and damage conditions of each tree or other plant designated to remain.

C. Record Drawings: Identifying and accurately showing locations of capped utilities and other subsurface structural, electrical, and mechanical conditions.

1.6 FIELD CONDITIONS

A. Traffic: Minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during site-clearing operations.

1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction.
2. Provide alternate routes around closed or obstructed trafficways if required by Owner or authorities having jurisdiction.

B. Salvageable Improvements: Carefully remove items indicated to be salvaged and store on Owner's premises where indicated.

C. Utility Locator Service: Notify Dig Safe System and OK-to-Dig for area where Project is located before site clearing.

D. Do not commence site clearing operations until temporary erosion- and sedimentation-control and plant-protection measures are in place.

E. Tree- and Plant-Protection Zones: Protect according to requirements in Section 015639 "Temporary Tree and Plant Protection."

F. Soil Stripping, Handling, and Stockpiling: Perform only when the soil is dry or slightly moist.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Satisfactory Soil Material: Requirements for satisfactory soil material are specified in Section 312000 "Earth Moving."

1. Obtain approved borrow soil material off-site when satisfactory soil material is not available on-site.

PART 3 - EXECUTION

3.1 PREPARATION

A. Protect and maintain benchmarks and survey control points from disturbance during construction.

B. Verify that trees, shrubs, and other vegetation to remain or to be relocated have been flagged and that protection zones have been identified and enclosed according to requirements in Section 015639 "Temporary Tree and Plant Protection."

C. Protect existing site improvements to remain from damage during construction.

1. Restore damaged improvements to their original condition, as acceptable to Owner.

3.2 TEMPORARY EROSION AND SEDIMENTATION CONTROL

A. Provide temporary erosion- and sedimentation-control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to erosion- and sedimentation-control Drawings and requirements of authorities having jurisdiction.

B. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross protection zones.

C. Inspect, maintain, and repair erosion- and sedimentation-control measures during construction until permanent vegetation has been established.

D. Remove erosion and sedimentation controls, and restore and stabilize areas disturbed during removal.

3.3 TREE AND PLANT PROTECTION

A. Protect trees and plants remaining on-site according to requirements in Section 015639 "Temporary Tree and Plant Protection."

B. Repair or replace trees, shrubs, and other vegetation indicated to remain or be relocated that are damaged by construction operations according to requirements in Section 015639 "Temporary Tree and Plant Protection."

3.4 EXISTING UTILITIES

A. Locate, identify, disconnect, and seal or cap utilities indicated to be removed or abandoned in place.

1. Arrange with utility companies to shut off indicated utilities.

B. Locate, identify, and disconnect utilities indicated to be abandoned in place.

C. Interrupting Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others, unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:

1. Notify Architect not less than five days in advance of proposed utility interruptions.
2. Do not proceed with utility interruptions without Architect's written permission.

D. Excavate for and remove underground utilities indicated to be removed.

3.5 CLEARING AND GRUBBING

A. Remove obstructions, trees, shrubs, and other vegetation to permit installation of new construction.

1. Do not remove trees, shrubs, and other vegetation indicated to remain or to be relocated.
2. Grind down stumps and remove roots larger than 2 inches in diameter, obstructions, and debris to a depth of 18 inches below exposed subgrade where indicated.
3. Use only hand methods or air spade for grubbing within protection zones.
4. Chip removed tree branches and dispose of off-site.
5. Remove shrub stumps and roots by hand excavation where indicated.

B. Fill depressions caused by clearing and grubbing operations with satisfactory soil material unless further excavation or earthwork is indicated.

1. Place fill material in horizontal layers not exceeding a loose depth of 8 inches, and compact each layer to a density equal to adjacent original ground.

3.6 TOPSOIL STRIPPING

A. Remove sod and grass before stripping topsoil.

B. Strip topsoil to depth indicated on Drawings in a manner to prevent intermingling with underlying subsoil or other waste materials.

1. Remove subsoil and nonsoil materials from topsoil, including clay lumps, gravel, and other objects larger than 2 inches in diameter; trash, debris, weeds, roots, and other waste materials.

C. Stockpile topsoil away from edge of excavations without intermixing with subsoil or other materials. Grade and shape stockpiles to drain surface water. Cover to prevent windblown dust and erosion by water.

1. Limit height of topsoil stockpiles to 72 inches.
2. Do not stockpile topsoil within protection zones.
3. Dispose of surplus topsoil. Surplus topsoil is that which exceeds quantity indicated to be stockpiled or reused.

3.7 SITE IMPROVEMENTS

A. Remove existing above- and below-grade improvements as indicated and necessary to facilitate new construction.

3.8 DISPOSAL OF SURPLUS AND WASTE MATERIALS

A. Remove surplus soil material, unsuitable topsoil, obstructions, demolished materials, and waste materials including trash and debris, and legally dispose of them off Owner's property.

B. Separate recyclable materials produced during site clearing from other nonrecyclable materials. Store or stockpile without intermixing with other materials, and transport them to recycling facilities. Do not interfere with other Project work.

END OF SECTION

SECTION 312000 - EARTH MOVING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Preparing subgrades for slabs-on-grade, pavements, turf and grasses.
2. Excavating and backfilling for structures.
3. Subbase course and base course for asphalt paving.
4. Excavating and backfilling trenches for utilities.
5. Subdrainage.

B. Related Requirements:

1. Section 013200 "Construction Progress Documentation" for recording preexcavation and earth-moving progress.
2. Section 311000 "Site Clearing" for site stripping, grubbing, stripping and stockpiling topsoil, and removal of above- and below-grade improvements and utilities.
3. Section 312319 “Dewatering” for dewatering requirements.
4. Section 329200 "Turf and Grasses" for finish grading in turf and grass areas, including preparing and placing planting soil for turf areas.
5. Section 329115 “Soil Preparation (Performance Specification)” for planting soils according to performance requirements of the mixes.

1.2 DEFINITIONS

A. Backfill: Soil material or controlled low-strength material used to fill an excavation.

1. Initial Backfill: Backfill placed beside and over pipe in a trench, including haunches to support sides of pipe.
2. Final Backfill: Backfill placed over initial backfill to fill a trench.

B. Base Course: Aggregate layer placed between the subbase course and hot-mix asphalt paving.

C. Bedding Course: Aggregate layer placed over the excavated subgrade in a trench before laying pipe or conduits.

D. Borrow Soil: Satisfactory soil imported from off-site for use as fill or backfill.

E. Drainage Course: Aggregate layer supporting the slab-on-grade that also minimizes upward capillary flow of pore water.

F. Excavation: Removal of material encountered above subgrade elevations and to lines and dimensions indicated.

1. Authorized Additional Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions as directed by Architect. Authorized additional excavation and replacement material will be paid for according to Contract provisions for changes in the Work.
2. Bulk Excavation: Excavation more than 10 feet in width and more than 30 feet in length.
3. Unauthorized Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions without direction by Architect. Unauthorized excavation, as well as remedial work directed by Architect, will be without additional compensation.

G. Fill: Soil materials used to raise existing grades.

H. MDOT: Maine Department of Transportation.

I. MDOT SHS: MDOT Standard Specifications, highways, and bridges.

J. Rock:

1. Rock material in beds, ledges, unstratified masses, conglomerate deposits, and boulders of rock material that exceed 1 cu. yd. for bulk excavation or 3/4 cu. yd. for footing, trench, and pit excavation that cannot be removed by rock-excavating equipment equivalent to the following in size and performance ratings, without systematic drilling, ram hammering, ripping, or blasting, when permitted:

   a. Equipment for Footing, Trench, and Pit Excavation: Late-model, track-mounted hydraulic excavator; equipped with a 42-inch-maximum-width, short-tip-radius rock bucket; rated at not less than 138-hp flywheel power with bucket-curling force of not less than 28,700 lbf and stick-crowd force of not less than 18,400 lbf with extra-long reach boom.

   b. Equipment for Bulk Excavation: Late-model, track-mounted loader; rated at not less than 230-hp flywheel power and developing a minimum of 47,992-lbf breakout force with a general-purpose bare bucket.

K. Structures: Buildings, footings, foundations, retaining walls, manholes, slabs, tanks, curbs, mechanical and electrical appurtenances, or other fabricated stationary features constructed above or below the ground surface.

L. Subbase Course: Aggregate layer placed between the subgrade and base course for hot-mix asphalt pavement, or aggregate layer placed between the subgrade and a cement concrete pavement or a cement concrete or hot-mix asphalt walk.

M. Subgrade: Uppermost surface of an excavation or the top surface of a fill or backfill immediately below subbase, drainage fill, drainage course, or topsoil materials.

N. Utilities: On-site underground pipes, conduits, ducts, and cables as well as underground services within buildings.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct preexcavation conference at Project site.

1. Review methods and procedures related to earthmoving, including, but not limited to, the following:

    a. Personnel and equipment needed to make progress and avoid delays.
    b. Coordination of Work with utility locator service.
    c. Coordination of Work and equipment movement with the locations of tree- and plant-protection zones.
    d. Extent of trenching by hand or with air spade.
    e. Field quality control.

1.4 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type product.

C. Material Test Reports: For each on-site and borrow soil material proposed for fill and backfill as follows:

1. Gradation according to ASTM C136 and ASTM C117.
2. Laboratory compaction curve according to ASTM D1557.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Qualification Data: For qualified testing agency.

C. Blasting is prohibited.

D. Preexcavation Photographs or Videotape: Show existing conditions of adjoining construction and site improvements, including finish surfaces that might be misconstrued as damage caused by earth-moving operations. Submit before earth moving begins.

1.6 FIELD CONDITIONS

A. Traffic: Minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during earth-moving operations.

1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction.
2. Provide alternate routes around closed or obstructed traffic ways if required by Owner or authorities having jurisdiction.

B. Utility Locator Service: Notify "Dig Safe System" and “OK-to-Dig” for area where Project is located before beginning earth-moving operations.

C. Do not commence earth-moving operations until temporary site fencing and erosion- and sedimentation-control measures specified in Section 015000 "Temporary Facilities and Controls" and Section 311000 "Site Clearing" are in place.

D. Do not commence earth-moving operations until plant-protection measures specified in Section 015639 "Temporary Tree and Plant Protection" are in place.

E. The following practices are prohibited within protection zones:

1. Storage of construction materials, debris, or excavated material.
2. Parking vehicles or equipment.
3. Foot traffic.
4. Erection of sheds or structures.
5. Impoundment of water.
6. Excavation or other digging unless otherwise indicated.
7. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated.

F. Do not direct vehicle or equipment exhaust towards protection zones.

G. Prohibit heat sources, flames, ignition sources, and smoking within or near protection zones.

PART 2 - PRODUCTS

2.1 SOIL MATERIALS

A. General: Provide borrow soil materials when sufficient satisfactory soil materials are not available from excavations.

B. Satisfactory Soils: Soil Classification Groups GW, GP, GM, SW, SP, and SM according to ASTM D2487, or a combination of these groups; free of rock or gravel larger than 3 inches in any dimension, debris, waste, frozen materials, vegetation, and other deleterious matter.

C. Unsatisfactory Soils: Soil Classification Groups GC, SC, CL, ML, OL, CH, MH, OH, and PT according to ASTM D2487, or a combination of these groups.

1. Unsatisfactory soils also include satisfactory soils not maintained within 2 percent of optimum moisture content at time of compaction.

D. Subbase Material: Material meeting the requirements of MDOT SHS Section 703.06, Aggregate for Base and Subbase, Type D.

E. Base Course: Material meeting the requirements of MDOT SHS Section 703.06, Aggregate for Base and Subbase, Type A.

F. Bedding Course: Naturally or artificially graded mixture of natural or crushed gravel and natural or crushed sand; ASTM D 2321, Class IB or II; except with 100 percent passing a 1-inch sieve and not more than 8 percent passing a No. 200 sieve.

G. Drainage Course/Crushed Stone: Shall be rock of uniform quality and shall consist of angular fragments of quarried rock, free from soft disintegrated pieces or other objectionable matter and meeting the requirements of MDOT SHS 703.13 Crushed Stone, 3/4 inch.

2.2 GEOTEXTILES

A. Subsurface Drainage Geotextile: Nonwoven needle-punched geotextile, manufactured for subsurface drainage applications, made from polyolefins or polyesters; with elongation greater than 50 percent; complying with AASHTO M 288 and the following, measured per test methods referenced:

1. Survivability:

a. Class 2; AASHTO M 288.

b. As follows:

1) Grab Tensile Strength: 157 lbf; ASTM D4632.
2) Tear Strength: 56 lbf; ASTM D4533.
3) CBR Puncture Strength: 400 lbs; ASTM D6241.

c. Apparent Opening Size: No. 70 sieve, maximum; ASTM D4751.
d. Permittivity: 1.5 per second, minimum; ASTM D4491.
e. UV Stability: 50 percent after 500 hours' exposure; ASTM D4355.
f. Flow Rate: 110 g/min/f^2

2.3 ACCESSORIES

A. Detectable Warning Tape: Acid- and alkali-resistant, polyethylene film warning tape manufactured for marking and identifying underground utilities, a minimum of 6 inches wide and 4 mils thick, continuously inscribed with a description of the utility, with metallic core encased in a protective jacket for corrosion protection, detectable by metal detector when tape is buried up to 30 inches deep; colored as follows:

1. Red: Electric.
2. Yellow: Gas, oil, steam, and dangerous materials.
3. Orange: Telephone and other communications.
4. Blue: Water systems.
5. Green: Sewer systems.

PART 3 - EXECUTION

3.1 PREPARATION

A. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by earth-moving operations.

B. Protect and maintain erosion and sedimentation controls during earth-moving operations.

C. Protect subgrades and foundation soils from freezing temperatures and frost. Remove temporary protection before placing subsequent materials.

3.2 DEWATERING

A. Provide dewatering system of sufficient scope, size, and capacity to control hydrostatic pressures and to lower, control, remove, and dispose of ground water and permit excavation and construction to proceed on dry, stable subgrades.

B. Prevent surface water and ground water from entering excavations, from ponding on prepared subgrades, and from flooding Project site and surrounding area.

C. Protect subgrades from softening, undermining, washout, and damage by rain or water accumulation.

1. Reroute surface water runoff away from excavated areas. Do not allow water to accumulate in excavations. Do not use excavated trenches as temporary drainage ditches.

D. Dispose of water removed by dewatering in a manner that avoids endangering public health, property, and portions of work under construction or completed. Dispose of water and sediment in a manner that avoids inconvenience to others.

3.3 EXPLOSIVES

A. Explosives:

1. Do not use explosives.

3.4 EXCAVATION, GENERAL

A. Unclassified Excavation: Excavate to subgrade elevations regardless of the character of surface and subsurface conditions encountered. Unclassified excavated materials may include rock, soil materials, and obstructions. No changes in the Contract Sum or the Contract Time will be authorized for rock excavation or removal of obstructions.

1. If excavated materials intended for fill and backfill include unsatisfactory soil materials and rock, replace with satisfactory soil materials.
2. Remove rock to lines and grades indicated to permit installation of permanent construction without exceeding the following dimensions:

a. 24 inches outside of concrete forms other than at footings.
b. 12 inches outside of concrete forms at footings.
c. 6 inches outside of minimum required dimensions of concrete cast against grade.
d. Outside dimensions of concrete walls indicated to be cast against rock without forms or exterior waterproofing treatments.
e. 6 inches beneath bottom of concrete slabs-on-grade.

f. 6 inches beneath pipe in trenches and the greater of 24 inches wider than pipe or 42 inches wide.

3.5 EXCAVATION FOR STRUCTURES

A. Excavate to indicated elevations and dimensions within a tolerance of plus or minus 1 inch. If applicable, extend excavations a sufficient distance from structures for placing and removing concrete formwork, for installing services and other construction, and for inspections.

1. Excavation for Underground Tanks, Basins, and Mechanical or Electrical Utility Structures: Excavate to elevations and dimensions indicated within a tolerance of plus or minus 1 inch. Do not disturb bottom of excavations intended as bearing surfaces.

B. Excavations at Edges of Tree- and Plant-Protection Zones:

1. Excavate by hand or with an air spade to indicated lines, cross sections, elevations, and subgrades. If excavating by hand, use narrow-tine spading forks to comb soil and expose roots. Do not break, tear, or chop exposed roots. Do not use mechanical equipment that rips, tears, or pulls roots.
2. Cut and protect roots according to requirements in Section 015639 "Temporary Tree and Plant Protection."

3.6 EXCAVATION FOR WALKS AND PAVEMENTS

A. Excavate surfaces under walks and pavements to indicated lines, cross sections, elevations, and subgrades.

3.7 EXCAVATION FOR UTILITY TRENCHES

A. Excavate trenches to indicated gradients, lines, depths, and elevations.

B. Excavate trenches to uniform widths to provide the following clearance on each side of pipe or conduit. Excavate trench walls vertically from trench bottom to 12 inches higher than top of pipe or conduit unless otherwise indicated.

1. Clearance: 12 inches each side of pipe or conduit.

C. Trench Bottoms:

1. Excavate trenches 6 inches deeper than bottom of pipe and conduit elevations to allow for bedding course. Hand-excavate deeper for bells of pipe.

a. Excavate trenches 6 inches deeper than elevation required in rock or other unyielding bearing material to allow for bedding course.

D. Trenches in Tree- and Plant-Protection Zones:

1. Hand-excavate to indicated lines, cross sections, elevations, and subgrades. Use narrow-tine spading forks to comb soil and expose roots. Do not break, tear, or chop exposed roots. Do not use mechanical equipment that rips, tears, or pulls roots.

2. Do not cut main lateral roots or taproots; cut only smaller roots that interfere with installation of utilities.
3. Cut and protect roots according to requirements in Section 015639 "Temporary Tree and Plant Protection."

3.8 EXCAVATION FOR ELEVATOR CYLINDER

A. Drill well hole plumb in elevator pit to accommodate installation of elevator-cylinder assembly. Coordinate with applicable requirements for diameter and tolerances in Section 142410 "Hydraulic Elevator Modernization."

B. Provide well casing as necessary to retain walls of well hole.

3.9 SUBGRADE INSPECTION

A. Notify Architect when excavations have reached required subgrade.

B. If Architect determines that unsatisfactory soil is present, continue excavation and replace with compacted backfill or fill material as directed.

C. Proof-roll subgrade below with a pneumatic-tired and loaded 10-wheel, tandem-axle dump truck weighing not less than 15 tons to identify soft pockets and areas of excess yielding. Do not proof-roll wet or saturated subgrades.

1. Completely proof-roll subgrade in one direction. Limit vehicle speed to 3 mph.
2. Excavate soft spots, unsatisfactory soils, and areas of excessive pumping or rutting, as determined by Architect, and replace with compacted backfill or fill as directed.

D. Authorized additional excavation and replacement material will be paid for according to Contract provisions for changes in the Work.

E. Reconstruct subgrades damaged by freezing temperatures, frost, rain, accumulated water, or construction activities, as directed by Architect, without additional compensation.

3.10 UNAUTHORIZED EXCAVATION

A. Fill unauthorized excavation under foundations or wall footings by extending bottom elevation of concrete foundation or footing to excavation bottom, without altering top elevation. Lean concrete fill, with 28-day compressive strength of 2500 psi, may be used when approved by Architect.

1. Fill unauthorized excavations under other construction, pipe, or conduit as directed by Architect.

3.11 STORAGE OF SOIL MATERIALS

A. Stockpile borrow soil materials and excavated satisfactory soil materials without intermixing. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.

1. Stockpile soil materials away from edge of excavations. Do not store within drip line of remaining trees and tree and plant protection zones.

3.12 BACKFILL

A. Place and compact backfill in excavations promptly, but not before completing the following:

1. Construction below finish grade including, where applicable, utilities and structures.
2. Surveying locations of underground utilities for Record Documents.
3. Testing and inspecting underground utilities.
4. Removing concrete formwork.
5. Removing trash and debris.
6. Removing temporary shoring, bracing, and sheeting.
7. Installing permanent or temporary horizontal bracing on horizontally supported walls.

B. Place backfill on subgrades free of mud, frost, snow, or ice.

3.13 UTILITY TRENCH BACKFILL

A. Place backfill on subgrades free of mud, frost, snow, or ice.

B. Place and compact bedding course on trench bottoms and where indicated. Shape bedding course to provide continuous support for bells, joints, and barrels of pipes and for joints, fittings, and bodies of conduits.

C. Trenches under Footings: Backfill trenches excavated under footings and within 18 inches of bottom of footings with satisfactory soil; fill with concrete to elevation of bottom of footings. Concrete is specified in Section 033000 "Cast-in-Place Concrete."

D. Backfill voids with satisfactory soil while removing shoring and bracing.

E. Initial Backfill:

1. Soil Backfill: Place and compact initial backfill of bedding course, free of particles larger than 1 inch in any dimension, to a height of 6 inches over the pipe or conduit.

a. Carefully compact initial backfill under pipe haunches and compact evenly up on both sides and along the full length of piping or conduit to avoid damage or displacement of piping or conduit. Coordinate backfilling with utilities testing.

F. Final Backfill:

1. Soil Backfill: Place and compact final backfill of satisfactory soil to final subgrade elevation.

G. Warning Tape: Install warning tape directly above utilities, 12 inches below finished grade, except 6 inches below subgrade under pavements and slabs.

3.14 SOIL FILL

A. Plow, scarify, bench, or break up sloped surfaces steeper than 1 vertical to 4 horizontal so fill material will bond with existing material.

B. Place and compact fill material in layers to required elevations as follows:

1. Under grass and planted areas, use satisfactory soil material.
2. Under walks and pavements, use satisfactory soil material.
3. Under footings and foundations, use concrete.

C. Place soil fill on subgrades free of mud, frost, snow, or ice.

3.15 SOIL MOISTURE CONTROL

A. Uniformly moisten or aerate subgrade and each subsequent fill or backfill soil layer before compaction to within 2 percent of optimum moisture content.

1. Do not place backfill or fill soil material on surfaces that are muddy, frozen, or contain frost or ice.
2. Remove and replace, or scarify and air dry, otherwise satisfactory soil material that exceeds optimum moisture content by 2 percent and is too wet to compact to specified dry unit weight.

3.16 COMPACTION OF SOIL BACKFILLS AND FILLS

A. Place backfill and fill soil materials in layers not more than 8 inches in loose depth for material compacted by heavy compaction equipment and not more than 4 inches in loose depth for material compacted by hand-operated tampers.

B. Place backfill and fill soil materials evenly on all sides of structures to required elevations and uniformly along the full length of each structure.

C. Compact soil materials to not less than the following percentages of maximum dry unit weight according to ASTM D1557:

1. Under structures, building slabs, steps, and pavements, existing subgrade beneath parking area to be re-paved, scarify and recompact top 12 inches of existing subgrade and each layer of backfill or fill soil material at 95 percent.
2. Under walkways, scarify and recompact top 6 inches below subgrade and compact each layer of backfill or fill soil material at 92 percent.
3. Under turf or unpaved areas, scarify and recompact top 6 inches below subgrade and compact each layer of backfill or fill soil material at 85 percent.
4. For utility trenches, compact each layer of initial and final backfill soil material at 85 percent.

3.17 GRADING

A. General: Uniformly grade areas to a smooth surface, free of irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and elevations indicated.

1. Provide a smooth transition between adjacent existing grades and new grades.
2. Cut out soft spots, fill low spots, and trim high spots to comply with required surface tolerances.

B. Site Rough Grading: Slope grades to direct water away from buildings and to prevent ponding. Finish subgrades to elevations required to achieve indicated finish elevations, within the following subgrade tolerances:

1. Turf or Unpaved Areas: Plus or minus 1 inch.
2. Walks: Plus or minus 1 inch.
3. Pavements: Plus or minus 1/2 inch.

C. Grading inside Building Lines: Finish subgrade to a tolerance of 1/2 inch when tested with a 10-foot straightedge.

3.18 SUBSURFACE DRAINAGE

A. Subsurface Drain: Place subsurface drainage geotextile around perimeter of subdrainage trench. Place a 6-inch course of crushed stone on subsurface drainage geotextile to support subdrainage pipe. Encase subdrainage pipe in a minimum of 12 inches of crushed, placed in compacted layers 6 inches thick, and wrap in subsurface drainage geotextile, overlapping sides and ends at least 6 inches.

3.19 SUBBASE AND BASE COURSES UNDER PAVEMENTS AND WALKS

A. Place subbase course and base course on subgrades free of mud, frost, snow, or ice.

B. On prepared subgrade, place subbase course and base course under pavements and walks as follows:

1. Place base course material over subbase course under hot-mix asphalt pavement.
2. Shape subbase course and base course to required crown elevations and cross-slope grades.
3. Place subbase course and base course 6 inches or less in compacted thickness in a single layer.
4. Place subbase course and base course that exceeds 6 inches in compacted thickness in layers of equal thickness, with no compacted layer more than 6 inches thick or less than 3 inches thick. Scarify existing subgrade to a depth of 3 inches in areas that require less than 3 inches of fill.
5. Compact subbase course and base course at optimum moisture content to required grades, lines, cross sections, and thickness to not less than 95 percent of maximum dry unit weight according to ASTM D698.

3.20 DRAINAGE COURSE UNDER CONCRETE SLABS-ON-GRADE

A. Place drainage course on subgrades free of mud, frost, snow, or ice.

B. On prepared subgrade, place and compact drainage course under cast-in-place concrete slabs-on-grade as follows:

1. Place drainage course 12 inches in compacted thickness in two layers.

3.21 FIELD QUALITY CONTROL

A. Special Inspections: Contractor will engage a qualified special inspector to perform the following special inspections:

1. Determine prior to placement of fill that site has been prepared in compliance with requirements.
2. Determine that fill material classification and maximum lift thickness comply with requirements.
3. Determine, during placement and compaction, that in-place density of compacted fill complies with requirements.

B. Testing Agency: Contractor will engage a qualified geotechnical engineering testing agency to perform tests and inspections.

C. Allow testing agency to inspect and test subgrades and each fill or backfill layer. Proceed with subsequent earth moving only after test results for previously completed work comply with requirements.

D. Testing agency will test compaction of soils in place according to ASTM D1556, ASTM D2167, ASTM D2937, and ASTM D6938, as applicable. Tests will be performed at the following locations and frequencies:

1. Paved and Building Slab Areas: At subgrade and at each compacted fill and backfill layer, at least one test for every 2000 sq. ft. or less of paved area or building slab but in no case fewer than three tests.
2. Trench Backfill: At each compacted initial and final backfill layer, at least one test for every 150 feet or less of trench length but no fewer than two tests.

E. When testing agency reports that subgrades, fills, or backfills have not achieved degree of compaction specified, scarify and moisten or aerate, or remove and replace soil materials to depth required; recompact and retest until specified compaction is obtained.

3.22 PROTECTION

A. Protecting Graded Areas: Protect newly graded areas from traffic, freezing, and erosion. Keep free of trash and debris.

B. Repair and reestablish grades to specified tolerances where completed or partially completed surfaces become eroded, rutted, settled, or where they lose compaction due to subsequent construction operations or weather conditions.

1. Scarify or remove and replace soil material to depth as directed by Architect; reshape and recompact.

C. Where settling occurs before Project correction period elapses, remove finished surfacing, backfill with additional soil material, compact, and reconstruct surfacing.

1. Restore appearance, quality, and condition of finished surfacing to match adjacent work, and eliminate evidence of restoration to greatest extent possible.

3.23 DISPOSAL OF SURPLUS AND WASTE MATERIALS

A. Remove surplus satisfactory soil and waste materials, including unsatisfactory soil, trash, and debris, and legally dispose of them off Owner's property.

B. Transport surplus satisfactory soil to designated storage areas on Owner's property. Stockpile or spread soil as directed by Architect.

1. Remove waste materials, including unsatisfactory soil, trash, and debris, and legally dispose of them off Owner's property.

END OF SECTION

SECTION 312319 - DEWATERING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Construction dewatering.

B. Related Requirements:

1. Section 312000 "Earth Moving" for excavating, backfilling, site grading, and controlling surface-water runoff and ponding.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Verify availability of Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
2. Review condition of site to be dewatered, including coordination with temporary erosion-control measures and temporary controls and protections.
3. Review proposed site clearing and excavations.
4. Review existing utilities and subsurface conditions.
5. Review observation and monitoring of dewatering system.

1.3 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Field Quality-Control Submittals:

1. Field quality-control reports.

C. Qualification Statements: For Installer.

D. Existing Conditions: Using photographs, show existing conditions of adjacent construction and site improvements that might be misconstrued as damage caused by dewatering operations. Submit before Work begins.

1.4 QUALITY ASSURANCE

A. Qualifications:

1. Installer: An experienced installer that has specialized in design of dewatering systems and dewatering work.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Dewatering Performance: Design, furnish, install, test, operate, monitor, and maintain dewatering system of sufficient scope, size, and capacity to control hydrostatic pressures and to lower, control, remove, and dispose of groundwater and permit excavation and construction to proceed on dry, stable subgrades.

1. Continuously monitor and maintain dewatering operations to ensure erosion control, stability of excavations and constructed slopes, prevention of flooding in excavation, and prevention of damage to subgrades and permanent structures.
2. Prevent surface water from entering excavations by grading, dikes, or other means.
3. Accomplish dewatering without damaging existing buildings, structures, and site improvements adjacent to excavation.
4. Remove dewatering system when no longer required for construction.

PART 3 - EXECUTION

3.1 PREPARATION

A. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by dewatering operations.

1. Prevent surface water and subsurface or groundwater from entering excavations, from ponding on prepared subgrades, and from flooding site or surrounding area.
2. Protect subgrades and foundation soils from softening and damage by rain or water accumulation.

B. Install dewatering system to ensure minimum interference with roads, streets, walks, and other adjacent occupied and used facilities.

1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction. Provide alternate routes around closed or obstructed traffic ways if required by authorities having jurisdiction.

C. Provide temporary grading to facilitate dewatering and control of surface water.

D. Protect and maintain temporary erosion and sedimentation controls, which are specified in Section 015000 "Temporary Facilities and Controls," during dewatering operations.

3.2 INSTALLATION

A. Install dewatering system utilizing methods complete with pump equipment, standby power and pumps, filter material gradation, valves, appurtenances, water disposal, and surface-water controls.

1. Use filters or other means to prevent pumping of fine sands or silts from the subsurface.

B. Place dewatering system into operation to lower water to specified levels before excavating below groundwater level. Ground water is anticipated to be 4-feet below existing grades.

C. Provide sumps, sedimentation tanks, and other flow-control devices as required by authorities having jurisdiction.

D. Provide standby equipment on-site, installed and available for immediate operation, to maintain dewatering on continuous basis if any part of system becomes inadequate or fails.

3.3 OPERATION

A. Operate system continuously until structures have been constructed and fill materials have been placed or until dewatering is no longer required.

B. Operate system to lower and control groundwater to permit excavation, construction of structures, and placement of fill materials on dry subgrades. Drain water-bearing strata above and below bottom of foundations, drains, sewers, and other excavations.

C. Dispose of water removed by dewatering in a manner that avoids endangering public health, property, and portions of work under construction or completed. Dispose of water and sediment in a manner that avoids inconvenience to others.

3.4 FIELD QUALITY CONTROL

A. Provide continual observation to ensure that subsurface soils are not being removed by the dewatering operation.

3.5 PROTECTION

A. Protect and maintain dewatering system during dewatering operations.

B. Promptly repair damages to adjacent facilities caused by dewatering.

END OF SECTION

SECTION 321216 - ASPHALT PAVING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Hot-mix asphalt paving.
2. Hot-mix asphalt patching.
3. Slipform concrete curb.

B. Related Requirements:

1. Section 024119 "Selective Demolition" for demolition and removal of existing asphalt pavement.
2. Section 312000 "Earth Moving" for subgrade preparation, fill material, separation geotextiles, unbound-aggregate subbase and base courses, and aggregate pavement shoulders.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review methods and procedures related to hot-mix asphalt paving including, but not limited to, the following:

a. Review requirements for protecting paving work, including restriction of traffic during installation period and for remainder of construction period.

1.3 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: Include technical data and tested physical and performance properties.

C. Hot-Mix Asphalt Designs:

1. Certification, by authorities having jurisdiction, of approval of each hot-mix asphalt design proposed for the Work.
2. For each hot-mix asphalt design proposed for the Work.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Qualification Data: For paving-mix manufacturer and testing agency.

C. Material Certificates:

1. Aggregates.
2. Asphalt binder.
3. Tack coat.

D. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Manufacturer Qualifications: A paving-mix manufacturer registered with and approved by Maine DOT.

B. Testing Agency Qualifications: Qualified in accordance with ASTM D3666 for testing indicated.

C. Regulatory Requirements: Comply with materials, workmanship, and other applicable requirements Maine DOT Standard Specifications for asphalt paving work.

1. Measurement and payment provisions and safety program submittals included in standard specifications do not apply to this Section.

1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not apply asphalt materials if subgrade is wet or excessively damp, if rain is imminent or expected before time required for adequate cure, or if the following conditions are not met:

1. Tack Coat: Minimum surface temperature of 60 deg F.
2. Asphalt and Binder Course: Minimum surface temperature of 40 deg F and rising at time of placement.
3. Asphalt Wearing Course: Minimum surface temperature of 60 deg F at time of placement.

PART 2 - PRODUCTS

2.1 AGGREGATES

A. General: Use materials and gradations that have performed satisfactorily in previous installations.

B. Coarse Aggregate: Maine DOT Subsection 703.07, for 0.3 to 3 (18,000 lbs) ESAL's.

C. Mineral Filler: AASHTO M 17, rock or slag dust, hydraulic cement, or other inert material.

2.2 ASPHALT MATERIALS

A. Asphalt Binder: AASHTO M 320 PG 64-28 binder designation.

B. Tack Coat: AASHTO M 140 emulsified asphalt, or AASHTO M 208 cationic emulsified asphalt, slow setting, diluted in water, of suitable grade and consistency for application.

C. Water: Potable.

2.3 AUXILIARY MATERIALS

A. Recycled Materials for Hot-Mix Asphalt Mixes: Reclaimed asphalt pavement as permitted by Maine DOT provided performance is equal to hot-mix asphalt paving produced from all new materials.

B. Sand: AASHTO M 29, Grade No. 2 or No. 3.

2.4 MIXES

A. Recycled Content of Hot-Mix Asphalt: As permitted by Maine DOT, Subsection 401.03.

1. Surface Course Limit: Recycled content no more than 15 percent by weight.

B. Hot-Mix Asphalt: Maine DOT, Section 401, dense-graded, hot-laid, hot-mix asphalt plant mixes complying with the following requirements:

1. Provide mixes with a history of satisfactory performance in geographical area where project is located.
2. Binder Course: Grading Type 12.5 mm.
3. Wearing Course: Grading Type 9.5mm.

2.5 SLIPFORM CONCRETE CURB

A. Slipform concrete curb conforming to Maine DOT Subsection 609.05, with materials conforming to Maine DOT Subsection 502.05 and a minimum compressive strength of 4,000 psi, concrete Class A.

2.6 CURING COMPOUND

A. A clear, waterborne, membrane-forming curing compound. ASTM C1315, Type 1, Class A curing/sealing compound. Curing/sealing compound selected shall be approved for use on slipform concrete curbing by Maine DOT.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify that subgrade is dry and in suitable condition to begin paving.

B. Proceed with paving only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Protection: Provide protective materials, procedures, and worker training to prevent asphalt materials from spilling, coating, or building up on curbs, driveway aprons, manholes, and other surfaces adjacent to the Work.

B. Proof-roll subgrade below pavements with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding. Do not proof-roll wet or saturated subgrades.

1. Completely proof-roll subgrade in one direction, repeating proof-rolling in direction perpendicular to first direction. Limit vehicle speed to 3 mph.
2. Excavate soft spots, unsatisfactory soils, and areas of excessive pumping or rutting, as determined by Architect, and replace with compacted backfill or fill as directed.

3.3 PATCHING

A. Tack Coat: Before placing patch material, apply tack coat uniformly to vertical asphalt surfaces abutting the patch. Apply at a rate of 0.05 to 0.15 gal./sq. yd.

1. Allow tack coat to cure undisturbed before applying hot-mix asphalt paving.
2. Avoid smearing or staining adjoining surfaces, appurtenances, and surroundings. Remove spillages and clean affected surfaces.

3.4 SURFACE PREPARATION

A. Ensure that prepared subgrade has been proof-rolled and is ready to receive paving. Immediately before placing asphalt materials, remove loose and deleterious material from substrate surfaces.

3.5 HOT-MIX ASPHALT PLACEMENT

A. Machine place hot-mix asphalt on prepared surface, spread uniformly, and strike off. Place asphalt mix by hand in areas inaccessible to equipment in a manner that prevents segregation of mix. Place each course to required grade, cross section, and thickness when compacted.

1. Place hot-mix asphalt binder course in number of lifts and thicknesses indicated.
2. Place hot-mix asphalt surface course in single lift.

3. Spread mix at a minimum temperature of 250 deg F.
4. Begin applying mix along centerline of crown for crowned sections and on high side of one-way slopes unless otherwise indicated.
5. Regulate paver machine speed to obtain smooth, continuous surface free of pulls and tears in asphalt-paving mat.

B. Place paving in consecutive strips not less than 10 feet wide unless infill edge strips of a lesser width are required.

1. After first strip has been placed and rolled, place succeeding strips and extend rolling to overlap previous strips. Overlap mix placement about 1 to 1-1/2 inches from strip to strip to ensure proper compaction of mix along longitudinal joints.
2. Complete a section of asphalt base course and binder course before placing asphalt surface course.

C. Promptly correct surface irregularities in paving course behind paver. Use suitable hand tools to remove excess material forming high spots. Fill depressions with hot-mix asphalt to prevent segregation of mix; use suitable hand tools to smooth surface.

3.6 JOINTS

A. Construct joints to ensure a continuous bond between adjoining paving sections. Construct joints free of depressions, with same texture and smoothness as other sections of hot-mix asphalt course.

1. Clean contact surfaces and apply tack coat to joints.
2. Offset longitudinal joints, in successive courses, a minimum of 6 inches.
3. Offset transverse joints, in successive courses, a minimum of 24 inches.
4. Construct transverse joints at each point where paver ends a day's work and resumes work at a subsequent time. Construct these joints using either "bulkhead" or "papered" method in accordance with AI MS-22, for both "Ending a Lane" and "Resumption of Paving Operations."
5. Compact joints as soon as hot-mix asphalt will bear roller weight without excessive displacement.
6. Compact asphalt at joints to a density within 2 percent of specified course density.

3.7 COMPACTION

A. General: Begin compaction as soon as placed hot-mix paving will bear roller weight without excessive displacement. Compact hot-mix paving with hot hand tampers or with vibratory-plate compactors in areas inaccessible to rollers.

1. Complete compaction before mix temperature cools to 185 deg F.

B. Breakdown Rolling: Complete breakdown or initial rolling immediately after rolling joints and outside edge. Examine surface immediately after breakdown rolling for indicated crown, grade, and smoothness. Correct laydown and rolling operations to comply with requirements.

C. Intermediate Rolling: Begin intermediate rolling immediately after breakdown rolling while hot-mix asphalt is still hot enough to achieve specified density. Continue rolling until hot-mix asphalt course has been uniformly compacted to the following density:

1. Average Density, Rice Test Method: 92 percent of reference maximum theoretical density in accordance with ASTM D2041/D2041M, but not less than 90 percent or greater than 96 percent.

D. Finish Rolling: Finish roll paved surfaces to remove roller marks while hot-mix asphalt is still warm.

E. Edge Shaping: While surface is being compacted and finished, trim edges of pavement to proper alignment. Bevel edges while asphalt is still hot; compact thoroughly.

F. Repairs: Remove paved areas that are defective or contaminated with foreign materials and replace with fresh, hot-mix asphalt. Compact by rolling to specified density and surface smoothness.

G. Protection: After final rolling, do not permit vehicular traffic on pavement until it has cooled and hardened.

H. Erect barricades to protect paving from traffic until mixture has cooled enough not to become marked.

3.8 SLIPFORM CONCRETE CURBS

A. Place curb in accordance with Maine DOT Subsection 609.05.

3.9 INSTALLATION TOLERANCES

A. Pavement Thickness: Compact each course to produce thickness indicated within the following tolerances:

1. Binder Course: Plus or minus 1/2 inch.
2. Surface Course: Plus 1/4 inch, no minus.

B. Pavement Surface Smoothness: Compact each course to produce surface smoothness within the following tolerances as determined by using a 10-foot straightedge applied transversely or longitudinally to paved areas:

1. Binder Course: 1/4 inch.
2. Surface Course: 1/8 inch.

3.10 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Thickness: In-place compacted thickness of hot-mix asphalt courses will be determined in accordance with ASTM D3549/D3549M.

C. Surface Smoothness: Finished surface of each hot-mix asphalt course will be tested for compliance with smoothness tolerances.

D. In-Place Density: Testing agency will take samples of uncompacted paving mixtures and compacted pavement in accordance with ASTM D979/D979M or AASHTO T 168.

1. Reference maximum theoretical density will be determined by averaging results from four samples of hot-mix asphalt-paving mixture delivered daily to site, prepared in accordance with ASTM D2041/D2041M, and compacted in accordance with job-mix specifications.
2. In-place density of compacted pavement will be determined by testing core samples in accordance with ASTM D1188 or ASTM D2726/D2726M.

a. One core sample will be taken for every 1000 sq. yd. or less of installed pavement, with no fewer than three cores taken.
b. Field density of in-place compacted pavement may also be determined by nuclear method in accordance with ASTM D2950/D2950M and coordinated with ASTM D1188 or ASTM D2726/D2726M.

E. Replace and compact hot-mix asphalt where core tests were taken.

F. Remove and replace or install additional hot-mix asphalt where test results or measurements indicate that it does not comply with specified requirements.

3.11 WASTE HANDLING

A. General: Handle asphalt-paving waste in accordance with approved waste management plan required in Section 017419 "Construction Waste Management and Disposal."

END OF SECTION

SECTION 321373 - CONCRETE PAVING JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Cold-applied joint sealants.
2. Joint-sealant backer materials.
3. Primers.

1.2 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. Concrete pavement joint sealants.
2. Joint-sealant backer materials.

1.3 QUALITY ASSURANCE

A. Qualifications:

1. Installers: Entity that employs installers and supervisors who are trained and approved by manufacturer.

1.4 FIELD CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain joint sealants from single manufacturer for each sealant type.

2.2 JOINT SEALANTS, GENERAL

A. Compatibility: Provide joint sealants, backer materials, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.

2.3 COLD-APPLIED JOINT SEALANTS

A. Single Component, Pourable, Urethane, Elastomeric Joint Sealant: ASTM C920, Type S, Grade P, Class 25, for Use T.

B. Single Component, Non-Sag, Urethane, Elastomeric Joint Sealant: ASTM C920, Type S, Grade NS, Class 35, use NT, T, O, M, G.

2.4 JOINT-SEALANT BACKER MATERIALS

A. Joint-Sealant Backer Materials: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by joint-sealant manufacturer, based on field experience and laboratory testing.

B. Round Backer Rods for Cold-Applied Joint Sealants: ASTM D5249, Type 3, of diameter and density required to control joint-sealant depth and prevent bottom-side adhesion of sealant.

C. Backer Strips for Cold-Applied Joint Sealants: ASTM D5249; Type 2; of thickness and width required to control joint-sealant depth, prevent bottom-side adhesion of sealant, and fill remainder of joint opening under sealant.

D. Joint Fillers: ASTM D1751, asphalt-saturated cellulosic fiber or ASTM D8139, semirigid, closed-cell polypropylene foam in preformed strips.

2.5 PRIMERS

A. Primers: Product recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Before installing joint sealants, clean out joints immediately to comply with joint-sealant manufacturer's written instructions.

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.

B. Joint Priming: Prime joint substrates where indicated or where recommended in writing by joint-sealant manufacturer, based on preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

3.3 INSTALLATION OF JOINT SEALANTS

A. Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated unless more stringent requirements apply.

B. Joint-Sealant Installation Standard: Comply with recommendations in ASTM C1193 for use of joint sealants as applicable to materials, applications, and conditions.

C. Install joint-sealant backers to support joint sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of joint-sealant backer materials.
2. Do not stretch, twist, puncture, or tear joint-sealant backer materials.
3. Remove absorbent joint-sealant backer materials that have become wet before sealant application and replace them with dry materials.

D. Install joint sealants immediately following backer material installation, using proven techniques that comply with the following:

1. Place joint sealants so they fully contact joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

E. Tooling of Nonsag Joint Sealants: Immediately after joint-sealant application and before skinning or curing begins, tool sealants in accordance with the following requirements to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint:

1. Remove excess joint sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by joint-sealant manufacturer and that do not discolor sealants or adjacent surfaces.

F. Provide joint configuration to comply with joint-sealant manufacturer's written instructions unless otherwise indicated.

3.4 CLEANING AND PROTECTION

A. Clean off excess joint sealant as the Work progresses, by methods and with cleaning materials approved in writing by joint-sealant manufacturers.

B. Protect joint sealants, during and after curing period, from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately and replace with joint sealant so installations in repaired areas are indistinguishable from the original work.

3.5 PAVING-JOINT-SEALANT SCHEDULE

A. Joints within concrete paving:

1. Joint Location:

    a. Expansion and isolation joints in concrete walks.
    b. Contraction joints in concrete walks.
    c. Other joints as indicated.

2. Joint Sealant: Single component, pourable, urethane, elastomeric joint sealant.
3. Joint-Sealant Color: Manufacturer's standard.

B. Vertical and sloping joints in concrete walks.

1. Joint Location:

    a. Expansion and isolation joints in concrete walks.
    b. Contraction joints in concrete walks.
    c. Other joints as indicated.

2. Joint Sealant: Single component, non-sag, urethane, elastomeric joint sealant.
3. Joint-Sealant Color: Manufacturer's standard.

END OF SECTION

SECTION 321723 - PAVEMENT MARKINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Painted markings applied to asphalt paving.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: Include technical data and tested physical and performance properties.

1. Pavement-marking paint, latex.

1.3 FIELD CONDITIONS

A. Environmental Limitations: Proceed with pavement marking only on clean, dry surfaces and at a minimum ambient or surface temperature of 55 deg F for water-based materials, and not exceeding 95 deg F.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Accessibility Standard: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design".

2.2 PAVEMENT-MARKING PAINT

A. Pavement-Marking Paint, Latex: MPI #97, latex traffic-marking paint.

1. Color: As indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify that pavement-marking substrate is dry and in suitable condition to begin pavement marking in accordance with manufacturer's written instructions.

B. Proceed with pavement marking only after unsatisfactory conditions have been corrected.

3.2 PAVEMENT MARKING

A. Allow asphalt paving or concrete surfaces to age for a minimum of 30 days before starting pavement marking.

B. Sweep and clean surface to eliminate loose material and dust.

C. Apply paint with mechanical equipment to produce pavement markings, of dimensions indicated, with uniform, straight edges. Apply at manufacturer's recommended rates to provide a minimum wet film thickness of 15 mils.

1. Apply graphic symbols and lettering with paint-resistant, die-cut stencils, firmly secured to asphalt paving or concrete surface. Mask an extended area beyond edges of each stencil to prevent paint application beyond stencil. Apply paint so that it cannot run beneath stencil.

3.3 PROTECTING AND CLEANING

A. Protect pavement markings from damage and wear during remainder of construction period.

B. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

END OF SECTION

SECTION 323113 - CHAIN LINK FENCES AND GATES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Chain-link fence framework.
2. Chain-link fence fabric.
3. Chain-link fittings.
4. Chain-link wires and ties.
5. Privacy slats.

B. Related Requirements:

1. Section 033000 "Cast-in-Place Concrete" for cast-in-place concrete for post footings.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data:

1. For each type of product.

a. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for the following:
b. Fence and gate posts, rails, and fittings.
c. Chain-link fabric, reinforcements, and attachments.
d. Accessories: Privacy slats.
e. Gates and hardware.

C. Shop Drawings: For each type of fence and gate assembly.

1. Include plans, elevations, sections, post spacing, and attachments to other work.
2. Include accessories, hardware, gate operation, and operational clearances.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Certificates: For each type of chain-link fence and gate.

C. Product Test Reports: For framework strength in accordance with ASTM F1043, for tests performed by manufacturer, and witnessed by a qualified testing agency or a qualified testing agency.

1.5 FIELD CONDITIONS

A. Field Measurements: Verify layout information for chain-link fences and gates shown on Drawings in relation to property survey and existing structures. Verify dimensions by field measurements.

1.6 WARRANTY

A. Special Warranty: Installer agrees to repair or replace components of fences and gates that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Failure to comply with performance requirements.
b. Deterioration of metals, metal finishes, and other materials beyond normal weathering.

2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 CHAIN-LINK FENCES, GENERAL

A. CLFMI Publications: Comply with the CLFMI Product Manual unless modified by requirements in the Contract Documents.

B. Chain-Link Fence and Gate Assemblies: Include materials applicable for a complete assembly of application types, consisting of commercial, industrial, and security chain-link fences and gates.

1. Source Limitations: Obtain chain-link fence and gate components from single source or manufacturer.

2.2 CHAIN-LINK FENCE FRAMEWORK

A. Posts and Rails: ASTM F1043 for framework, including rails, braces, and line; terminal; and corner posts. Provide members with minimum dimensions and wall thicknesses in accordance with ASTM F1043 based on the following:

1. Fence Height: As indicated on Drawings.

a. Line Post: As indicated on Drawings.
b. End, Corner, and Pull Posts: As indicated on Drawings.

2. Heavy-Industrial-Strength Material: Round steel pipe with a minimum yield strength of 50,000 psi.
3. Horizontal Framework Members: As indicated on Drawings and in accordance with ASTM F1043.

a. Top Rail: As indicated on Drawings.
b. Bottom Rail and Middle Rail: As indicated on Drawings.

4. Brace Rails: As indicated on Drawings and in accordance with ASTM F1043.
5. Metallic Coating for Steel Framework:

a. Type A: Not less than minimum 0.9 oz./sq. ft. average zinc coating in accordance with ASTM A123/A123M.

6. Polymer coating over metallic coating.

a. Color: Black, in accordance with ASTM F934.

2.3 CHAIN-LINK FENCE FABRIC

A. General: Provide fabric in one-piece heights measured between top and bottom of outer edge of selvage knuckle or twist in accordance with "CLFMI Product Manual" and requirements indicated below:

1. Fabric Height: As indicated on Drawings.
2. Steel Wire for Fabric: Wire diameter of 9 gauge.

a. Mesh Size: 2 inches.
b. Zinc-Coated Fabric: ASTM A392, Type II, Class 1, 1.2 oz./sq. ft. with zinc coating applied before weaving.
c. Polymer-Coating Over Zinc Coated Fabric: Steel Wire: 9 gauge. Steel Wire with coating complying with ASTM F668. Color: Black.

3. Selvage: Knuckled at both selvages.

2.4 CHAIN-LINK FITTINGS

A. Provide fittings in accordance with ASTM F626.

B. Post Caps: Provide for each post.

1. Provide line post caps with loop to receive tension wire or top rail.

C. Rail and Brace Ends: For each gate, corner, pull, and end post.

D. Rail Fittings: Provide the following:

1. Top Rail Sleeves: Pressed-steel or round-steel tubing not less than 6 inches long.
2. Rail Clamps: Line and corner boulevard clamps for connecting bottom rails to posts.

E. Tension and Brace Bands: Pressed steel.

F. Tension Bars: Steel, length not less than 2 inches shorter than full height of chain-link fabric. Provide one bar for each gate and end post, and two for each corner and pull post, unless fabric is integrally woven into post.

G. Tie Wires, Clips, and Fasteners: In accordance with ASTM F626.

1. Standard Round Wire Ties: For attaching chain-link fabric to posts, rails, and frames, in accordance with the following:

a. Hot-Dip Galvanized Steel: 9 gauge wire; galvanized coating thickness matching coating thickness of chain-link fence fabric.

H. Finish:

1. Metallic Coating for Pressed Steel or Cast Iron: Not less than 1.2 oz./sq. ft. of zinc.

a. Polymer coating over metallic coating complying with ASTM F668; color: black.

2.5 CHAIN-LINK WIRE AND TIES

A. Metallic-Coated Steel Wire: 9 gauge, marcelled tension wire in accordance with ASTM A817 or ASTM A824, with the following metallic coating:

1. Type II: Zinc coated (galvanized) by hot-dip process, with the following minimum coating weight:

a. Class 1: Not less than 1.2 oz./sq. ft. of uncoated wire surface.

B. Polymer-Coated Steel Wire: 9 gauge, tension wire in accordance with ASTM F1664, Class 2a over zinc-coated steel wire.

1. Coating: Complying with ASTM F668; Color: Black.

2.6 CHAIN-LINK SWING GATES

A. General: ASTM F900 for gate posts and single and double swing gate types.

1. Gate Leaf Width: As indicated.
2. Framework Member Sizes and Strength: Based on gate fabric height as indicated.
3. Polymer-coated over zinc coating to match fence framework and fabric.

B. Swing Gate Pipe and Tubing:

1. Swing Gate Posts: Round tubular steel.
2. Gate Frames and Bracing: Round tubular steel.

3. Coating: Complying with ASTM F668. Color: Black.

C. Swing Frame Corner Construction: Welded.

D. Swing Gate Hardware:

1. Hinges: 180-degree outward swing.
2. Latch: Permitting operation from both sides of gate with provision for padlocking accessible from both sides of gate.

2.7 LEAF GATES

A. General: ASTM F 900 for all gate members

1. Gate Leaf Width: As indicated.
2. Framework Member Sizes and Strength: As indicated.

B. Pipe and Tubing:

1. Coating: Complying with ASTM F668. Color: Black.
2. Gate Posts: Round tubular steel.
3. Gate Frames and Bracing: Round tubular steel.

C. Frame Corner Construction: Welded.

D. Hardware:

1. Hinges: 180-degree outward swing, unless indicated otherwise on Drawings.
2. Latch: Permitting operation from both sides of gate with provision for padlocking accessible from both sides of gate.
3. Lock: Manufacturer's standard internal device. Obtain padlocks from Owner.

2.8 ACCESSORIES

A. Privacy Slats:

1. Tubular Polyethylene Slats: Minimum 0.023-inch-thick tubular polyethylene, manufactured for chain-link fences from virgin polyethylene with UV inhibitor, sized to fit mesh specified for direction indicated, with vandal-resistant fasteners and lock strips.
2. Color: Black.

2.9 GROUT AND ANCHORING CEMENT

A. Nonshrink, Nonmetallic Grout: Factory-packaged, nonstaining, noncorrosive, nongaseous grout complying with ASTM C1107/C1107M. Provide grout, recommended in writing by manufacturer, for exterior applications.

B. Anchoring Cement: Factory-packaged, nonshrink, nonstaining, hydraulic-controlled expansion cement formulation for mixing with water at Project site to create pourable anchoring, patching, and grouting compound. Provide formulation that is resistant to erosion from water exposure without needing protection by a sealer or waterproof coating, and that is recommended in writing by manufacturer for exterior applications.

2.10 CONCRETE

A. Concrete Post Footings: Minimum 28-day compressive strength of 4,000 psi.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and conditions, with Installer present, for compliance with requirements for site clearing, earthwork, pavement work, and other conditions affecting performance of the Work.

1. Do not begin installation before final grading is completed unless otherwise permitted by Architect.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Stake locations of fence lines, gates, and terminal posts. Do not exceed intervals of 500 feet or line of sight between stakes. Indicate locations of utilities, lawn sprinkler system, underground structures, benchmarks, and property monuments.

3.3 INSTALLATION OF CHAIN-LINK FENCES

A. Install chain-link fencing in accordance with ASTM F567 and more stringent requirements specified.

1. Install fencing on established boundary lines inside property line.

B. Post Excavation: Drill or hand-excavate holes for posts to diameters and spacings indicated, in firm, undisturbed soil.

C. Post Setting: Set corner, terminal and pull posts in concrete at indicated spacing into firm, undisturbed soil.

1. Verify that posts are set plumb, aligned, and at correct height and spacing, and hold in position during setting with concrete or mechanical devices.
2. Concrete Fill: Place concrete around posts to dimensions indicated and vibrate or tamp for consolidation. Protect aboveground portion of posts from concrete splatter.

a. Concealed Concrete: Place top of concrete below grade as indicated on Drawings to allow covering with surface material.

D. Mechanically drive line posts into soil to depth as indicated. Protect post top to prevent distortion.

E. Terminal Posts: Install terminal end, corner, and gate posts in accordance with ASTM F567 and terminal pull posts at changes in horizontal or vertical alignment of 15 degrees or more. For runs exceeding 500 feet, space pull posts an equal distance between corner or end posts.

F. Line Posts: Space line posts uniformly at 10 feet o.c. maximum.

G. Post Bracing and Intermediate Rails: Install in accordance with ASTM F567, maintaining plumb position and alignment of fence posts. Diagonally brace terminal posts to adjacent line posts with truss rods and turnbuckles. Install braces at end and gate posts and at both sides of corner and pull posts.

1. Locate horizontal braces at midheight of fabric 72 inches or higher, on fences with top rail, and at two-third fabric height on fences without top rail. Install so posts are plumb when diagonal rod is under proper tension.

H. Top Rail: Install in accordance with ASTM F567, maintaining plumb position and alignment of fence posts. Run rail continuously through line post caps, bending to radius for curved runs and terminating into rail end attached to posts or post caps fabricated to receive rail at terminal posts. Provide expansion couplings as recommended in writing by fencing manufacturer.

I. Intermediate and Bottom Rails: Secure to posts with fittings.

J. Chain-Link Fabric: Apply fabric to outside of enclosing framework. Leave 2-inch bottom clearance between finish grade or surface and bottom selvage unless otherwise indicated. Pull fabric taut and tie to posts, rails, and tension wires. Anchor to framework so fabric remains under tension after pulling force is released.

K. Tension or Stretcher Bars: Thread through fabric and secure to end, corner, pull, and gate posts, with tension bands spaced not more than 15 inches o.c.

L. Tie Wires: Use wire of proper length to firmly secure fabric to line posts and rails. Attach wire at one end to chain-link fabric, wrap wire around post a minimum of 180 degrees, and attach other end to chain-link fabric in accordance with ASTM F626. Bend ends of wire to minimize hazard to individuals and clothing.

1. Maximum Spacing: Tie fabric to line posts at 12 inches o.c. and to braces at 24 inches o.c.

M. Fasteners: Install nuts for tension bands and carriage bolts on the side of fence opposite the fabric side.

N. Privacy Slats: Install slats in direction indicated, securely locked in place.

1. Per manufacturer’s written instructions for privacy factor of 80 to 85.

3.4 INSTALLATION OF GATES

A. Install gates in accordance with manufacturer's written instructions, level, plumb, and secure for full opening without interference. Attach fabric as for fencing on swing gates. Attach hardware using tamper-resistant or concealed means. Install ground-set items in concrete for anchorage. Adjust hardware for smooth operation.

3.5 ADJUSTING

A. Gates: Adjust gates to operate smoothly, easily, and quietly, free of binding, warp, excessive deflection, distortion, nonalignment, misplacement, disruption, or malfunction, throughout entire operational range. Confirm that latches and locks engage accurately and securely without forcing or binding.

B. Lubricate hardware and other moving parts.

3.6 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain chain-link fences and gates.

END OF SECTION

SECTION 329115 - SOIL PREPARATION (PERFORMANCE SPECIFICATION)

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes planting soils specified according to performance requirements of the mixes.

B. Related Requirements:

1. Section 311000 "Site Clearing" for topsoil stripping and stockpiling.
2. Section 329200 "Turf and Grasses" for placing planting soil for turf and grasses.

1.3 DEFINITIONS

A. AAPFCO: Association of American Plant Food Control Officials.

B. Backfill: The earth used to replace or the act of replacing earth in an excavation. This can be amended or unamended soil as indicated.

C. CEC: Cation exchange capacity.

D. Compost: The product resulting from the controlled biological decomposition of organic material that has been sanitized through the generation of heat and stabilized to the point that it is beneficial to plant growth.

E. Duff Layer: A surface layer of soil, typical of forested areas, that is composed of mostly decayed leaves, twigs, and detritus.

F. Imported Soil: Soil that is transported to Project site for use.

G. Layered Soil Assembly: A designed series of planting soils, layered on each other, that together produce an environment for plant growth.

H. Manufactured Soil: Soil produced by blending soils, sand, stabilized organic soil amendments, and other materials to produce planting soil.

I. NAPT: North American Proficiency Testing Program. An SSSA program to assist soil-, plant-, and water-testing laboratories through interlaboratory sample exchanges and statistical evaluation of analytical data.

J. Organic Matter: The total of organic materials in soil exclusive of undecayed plant and animal tissues, their partial decomposition products, and the soil biomass; also called "humus" or "soil organic matter."

K. Planting Soil: Existing, on-site soil; imported soil; or manufactured soil that has been modified as specified with soil amendments and perhaps fertilizers to produce a soil mixture best for plant growth.

L. RCRA Metals: Hazardous metals identified by the EPA under the Resource Conservation and Recovery Act.

M. SSSA: Soil Science Society of America.

N. Subgrade: Surface or elevation of subsoil remaining after excavation is complete, or the top surface of a fill or backfill before planting soil is placed.

O. Subsoil: Soil beneath the level of subgrade; soil beneath the topsoil layers of a naturally occurring soil profile, typified by less than 1 percent organic matter and few soil organisms.

P. Surface Soil: Soil that is present at the top layer of the existing soil profile. In undisturbed areas, surface soil is typically called "topsoil"; but in disturbed areas such as urban environments, the surface soil can be subsoil.

Q. USCC: U.S. Composting Council.

1.4 ACTION SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Product Data: For each type of product.

1. Include recommendations for application and use.
2. Include test data substantiating that products comply with requirements.
3. Include sieve analyses for aggregate materials.
4. Material Certificates: For each type of imported soil and soil amendment and fertilizer before delivery to the site, according to the following:

    a. Manufacturer's qualified testing agency's certified analysis of standard products.
    b. Analysis of fertilizers, by a qualified testing agency, made according to AAPFCO methods for testing and labeling and according to AAPFCO's SUIP #25.
    c. Analysis of nonstandard materials, by a qualified testing agency, made according to SSSA methods, where applicable.

C. Sustainable Design Submittals:

1. Regional Materials.

D. Samples: For each bulk-supplied material, 1-quart volume of each in sealed containers labeled with content, source, and date obtained. Each Sample shall be typical of the lot of material to be furnished; provide an accurate representation of composition, color, and texture.

1.5 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Qualification Data: For each testing agency.

C. Preconstruction Test Reports: For preconstruction soil analyses specified in "Preconstruction Testing" Article.

D. Field quality-control reports.

1.6 QUALITY ASSURANCE

A. Testing Agency Qualifications: An independent, state-operated, or university-operated laboratory; experienced in soil science, soil testing, and plant nutrition; with the experience and capability to conduct the testing indicated; and that specializes in types of tests to be performed.

1. Multiple Laboratories: At Owner's option, work may be divided among qualified testing laboratories specializing in physical testing, chemical testing, and fertility testing.

1.7 PRECONSTRUCTION TESTING

A. Preconstruction Testing Service: Owner will engage a qualified testing agency to perform preconstruction soil analyses on existing, on-site soil and imported soil.

B. Preconstruction Soil Analyses: For each unamended soil type, perform testing on soil samples and furnish soil analysis and a written report containing soil-amendment and fertilizer recommendations by a qualified testing agency performing the testing according to "Soil-Sampling Requirements" and "Testing Requirements" articles.

1. Have testing agency identify and label samples and test reports according to sample collection and labeling requirements.

1.8 SOIL-SAMPLING REQUIREMENTS

A. General: Extract soil samples according to requirements in this article.

B. Sample Collection and Labeling: Have samples taken and labeled by state-certified, -licensed, or -registered soil scientist under the direction of the testing agency.

1. Number and Location of Samples: Minimum of eight representative soil samples from varied locations for each soil to be used or amended for landscaping purposes.
2. Procedures and Depth of Samples: According to soil testing agency.
3. Division of Samples: Split each sample into two, equal parts. Send half to the testing agency and half to Owner for its records.
4. Labeling: Label each sample with the date, location keyed to a site plan or other location system, visible soil condition, and sampling depth.

1.9 TESTING REQUIREMENTS

A. General: Perform tests on soil samples according to requirements in this article.

B. Physical Testing:

1. Soil Texture: Soil-particle, size-distribution analysis by one of the following methods according to SSSA's "Methods of Soil Analysis - Part 1-Physical and Mineralogical Methods":

a. Sieving Method: Report sand-gradation percentages for very coarse, coarse, medium, fine, and very fine sand; and fragment-gradation (gravel) percentages for fine, medium, and coarse fragments; according to USDA sand and fragment sizes.
b. Hydrometer Method: Report percentages of sand, silt, and clay.

2. Bulk Density: Analysis according to core method of SSSA's "Methods of Soil Analysis - Part 1-Physical and Mineralogical Methods."
3. Total Porosity: Calculate using particle density and bulk density according to SSSA's "Methods of Soil Analysis - Part 1-Physical and Mineralogical Methods."

C. Chemical Testing:

1. CEC: Analysis by sodium saturation at pH 7 according to SSSA's "Methods of Soil Analysis - Part 3- Chemical Methods."

D. Fertility Testing: Soil fertility analysis according to standard laboratory protocol of SSSA NAPT NEC-67, including the following:

1. Percentage of organic matter.
2. CEC, calcium percent of CEC, and magnesium percent of CEC.
3. Soil reaction (acidity/alkalinity pH value).
4. Buffered acidity or alkalinity.
5. Nitrogen ppm.
6. Phosphorous ppm.
7. Potassium ppm.
8. Manganese ppm.
9. Manganese-availability ppm.
10. Zinc ppm.
11. Zinc availability ppm.
12. Copper ppm.
13. Sodium ppm.
14. Soluble-salts ppm.
15. Presence and quantities of problem materials including salts and metals cited in the Standard protocol. If such problem materials are present, provide additional recommendations for corrective action.
16. Lead scan.
17. Other deleterious materials, including their characteristics and content of each.

E. Organic-Matter Content: Analysis using loss-by-ignition method according to SSSA's "Methods of Soil Analysis - Part 3-Chemical Methods."

F. Recommendations: Based on the test results, state recommendations for soil treatments and soil amendments to be incorporated to produce satisfactory planting soil suitable for healthy, viable plants indicated. Include, at a minimum, recommendations for nitrogen, phosphorous, and potassium fertilization, and for micronutrients.

1. Fertilizers and Soil Amendment Rates: State recommendations in weight per 1000 sq. ft. for 6-inchdepth of soil.
2. Soil Reaction: State the recommended liming rates for raising pH or sulfur for lowering pH according to the buffered acidity or buffered alkalinity in weight per 1000 sq. ft. for 6-inchdepth of soil.

1.10 DELIVERY, STORAGE, AND HANDLING

A. Packaged Materials: Deliver packaged materials in original, unopened containers showing weight, certified analysis, name and address of manufacturer, and compliance with state and Federal laws if applicable.

B. Bulk Materials:

1. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
2. Provide erosion-control measures to prevent erosion or displacement of bulk materials, discharge of soil-bearing water runoff, and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
3. Do not move or handle materials when they are wet or frozen.
4. Accompany each delivery of bulk fertilizers and soil amendments with appropriate certificates.

PART 2 - PRODUCTS

2.1 PLANTING SOILS SPECIFIED ACCORDING TO PERFORMANCE REQUIREMENTS

A. Planting-Soil Type: Existing, on-site surface soil, with the duff layer, if any, retained; and stockpiled on-site; modified to produce viable planting soil. Using preconstruction soil analyses and materials specified in other articles of this Section, amend existing, on-site surface soil to become planting soil complying with the following requirements:

1. Particle Size Distribution by USDA Textures: Classified as sandy loam or loam soil according to USDA textures.
2. Percentage of Organic Matter: Minimum 6 percent by volume.
3. Soil Reaction: pH of 6 to 7.
4. CEC of Total Soil: Minimum 10 meq/100 mL at pH of 7.0.
5. CEC of Clay Fraction: Maximum 15 meq/100 mL at pH of 7.0.
6. Soluble-Salt Content: 5 to 10 dS/m measured by electrical conductivity.
7. Bulk Density: 1.2 g/cu. cm to 1.4 g/cu. cm at 85 percent compaction.
8. Total Porosity: Minimum 50 percent at 85 percent compaction.
9. Macro Porosity: Minimum 10 percent at 85 percent compaction.

B. Planting-Soil Type: Imported, naturally formed soil from off-site sources and consisting of sandy loam or loam soil according to USDA textures; and modified to produce viable planting soil. Amend imported soil with materials specified in other articles of this Section to become planting soil complying with the following requirements:

1. Sources: Take imported, unamended soil from sources that are naturally well-drained sites where topsoil occurs at least 4 inches deep, not from bogs, or marshes; and that do not contain undesirable organisms; disease-causing plant pathogens; or obnoxious weeds and invasive plants including, but not limited to, quackgrass, Johnsongrass, poison ivy, nutsedge, nimblewill, Canada thistle, bindweed, bentgrass, wild garlic, ground ivy, perennial sorrel, and bromegrass.
2. Additional Properties of Imported Soil before Amending: Minimum of 6 percent organic-matter content, friable, and with sufficient structure to give good tilth and aeration. Clean soil to be of the following:

    a. Unacceptable Materials: Concrete slurry, concrete layers or chunks, cement, plaster, building debris, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, acid, and other extraneous materials that are harmful to plant growth.
    b. Unsuitable Materials: Stones, roots, plants, sod, clay lumps, and pockets of coarse sand that exceed a combined maximum of 8 percent by dry weight of the imported soil.
    c. Large Materials: Stones, clods, roots, clay lumps, and pockets of coarse sand exceeding 2 inches in any dimension.

3. Percentage of Organic Matter: Minimum 6 percent by volume.
4. Soil Reaction: pH of 6 to 7.
5. CEC of Total Soil: Minimum 10 meq/100 mL at pH of 7.0.
6. CEC of Clay Fraction: Maximum 15 meq/100 mL at pH of 7.0.
7. Soluble-Salt Content: 5 to 10 dS/m measured by electrical conductivity.
8. Bulk Density: 1.2 g/cu. cm to 1.4 g/cu. cm at 85 percent compaction.
9. Total Porosity: Minimum 50 percent at 85 percent compaction.
10. Macro Porosity: Minimum 10 percent at 85 percent compaction.

2.2 INORGANIC SOIL AMENDMENTS

A. Lime: ASTM C602, agricultural liming material containing a minimum of 80 percent calcium carbonate equivalent and as follows:

1. Class: T, with a minimum of 99 percent passing through a No. 8 sieve and a minimum of 75 percent passing through a No. 60 sieve.
2. Form: Provide lime in form of ground mollusk shells.

B. Sulfur: Granular, biodegradable, and containing a minimum of 90 percent elemental sulfur, with a minimum of 99 percent passing through a No. 6 sieve and a maximum of 10 percent passing through a No. 40 sieve.

C. Iron Sulfate: Granulated ferrous sulfate containing a minimum of 20 percent iron and 10 percent sulfur.

D. Agricultural Gypsum: Minimum 90 percent calcium sulfate, finely ground with 90 percent passing through a No. 50 sieve.

E. Sand: Clean, washed, natural or manufactured, free of toxic materials, and according to ASTM C33/C33M.

2.3 ORGANIC SOIL AMENDMENTS

A. Compost: Well-composted, stable, and weed-free organic matter produced by composting feedstock, and bearing USCC's "Seal of Testing Assurance," and as follows:

1. Feedstock: Limited to leaves.
2. Reaction: pH of 5.5 to 8.
3. Soluble-Salt Concentration: Less than 4 dS/m.
4. Moisture Content: 35 to 55 percent by weight.
5. Organic-Matter Content: 50 to 60 percent of dry weight.
6. Particle Size: Minimum of 98 percent passing through a 1-inch sieve.

B. Sphagnum Peat: Partially decomposed sphagnum peat moss, finely divided or of granular texture with 100 percent passing through a 1/2-inch sieve, a pH of 3.4 to 4.8, and a soluble-salt content measured by electrical conductivity of maximum 5 dS/m.

C. Wood Derivatives: Shredded and composted, nitrogen-treated sawdust, ground bark, or wood waste; of uniform texture and free of chips, stones, sticks, soil, or toxic materials.

D. Manure: Well-rotted, unleached, stable or cattle manure containing not more than 25 percent by volume of straw, sawdust, or other bedding materials; free of toxic substances, stones, sticks, soil, weed seed, debris, and material harmful to plant growth.

2.4 FERTILIZERS

A. Commercial Fertilizer: Commercial-grade complete fertilizer of neutral character, consisting of fast- and slow-release nitrogen, 50 percent derived from natural organic sources of urea formaldehyde, phosphorous, and potassium in the following composition:

1. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified testing agency.

B. Slow-Release Fertilizer: Granular or pelleted fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorus, and potassium in the following composition:

1. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified testing agency.

C. Chelated Iron: Commercial-grade FeEDDHA for dicots and woody plants, and commercial-grade FeDTPA for ornamental grasses and monocots.

PART 3 - EXECUTION

3.1 GENERAL

A. Place planting soil and fertilizers according to requirements in other Specification Sections.

B. Verify that no foreign or deleterious material or liquid such as paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, or acid has been deposited in planting soil.

C. Proceed with placement only after unsatisfactory conditions have been corrected.

3.2 PREPARATION OF UNAMENDED, ON-SITE SOIL BEFORE AMENDING

A. Excavation: Excavate soil from designated area(s) to a depth of 6 inches and stockpile until amended.

B. Unacceptable Materials: Clean soil of concrete slurry, concrete layers or chunks, cement, plaster, building debris, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, acid, and other extraneous materials that are harmful to plant growth.

C. Unsuitable Materials: Clean soil to contain a combined maximum of 8 percent by dry weight of stones, roots, plants, sod, clay lumps, and pockets of coarse sand.

D. Screening: Pass unamended soil through a 3-inch sieve to remove large materials.

3.3 PLACING AND MIXING PLANTING SOIL OVER EXPOSED SUBGRADE

A. General: Apply and mix unamended soil with amendments on-site to produce required planting soil. Do not apply materials or till if existing soil or subgrade is frozen, muddy, or excessively wet.

B. Subgrade Preparation: Till subgrade to a minimum depth of 8 inches. Remove stones larger than 2 inches in any dimension and sticks, roots, rubbish, and other extraneous matter and legally dispose of them off Owner's property.

1. Apply, add soil amendments, and mix approximately half the thickness of unamended soil over prepared, loosened subgrade according to "Mixing" Paragraph below. Mix thoroughly into top 2 inches of subgrade. Spread remainder of planting soil.

C. Mixing: Spread unamended soil to total depth of 6 inches, but not less than required to meet finish grades after mixing with amendments and natural settlement. Do not spread if soil or subgrade is frozen, muddy, or excessively wet.

1. Amendments: Apply soil amendments and fertilizer, if required, evenly on surface, and thoroughly blend them with unamended soil to produce planting soil.

a. Mix lime and sulfur with dry soil before mixing fertilizer.
b. Mix fertilizer with planting soil no more than seven days before planting.

2. Lifts: Apply and mix unamended soil and amendments in lifts not exceeding 8 inches in loose depth for material compacted by compaction equipment, and not more than 4 inches in loose depth for material compacted by hand-operated tampers.

D. Compaction: Compact each blended lift of planting soil to 75 to 82 percent of maximum Standard Proctor density according to ASTM D698.

E. Finish Grading: Grade planting soil to a smooth, uniform surface plane with loose, uniformly fine texture. Roll and rake, remove ridges, and fill depressions to meet finish grades.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.

B. Perform the following tests:

1. Compaction: Test planting-soil compaction after placing each lift and at completion using a densitometer or soil-compaction meter calibrated to a reference test value based on laboratory testing according to ASTM D698. Space tests at no less than one for each 2000 sq. ft. of in-place soil or part thereof.
2. Performance Testing: For each amended planting-soil type, demonstrating compliance with specified performance requirements. Perform testing according to "Soil-Sampling Requirements" and "Testing Requirements" articles.

C. Soil will be considered defective if it does not pass tests.

D. Prepare test reports.

E. Label each sample and test report with the date, location keyed to a site plan or other location system, visible conditions when and where sample was taken, and sampling depth.

3.5 PROTECTION

A. Protect areas of in-place soil from additional compaction, disturbance, and contamination. Prohibit the following practices within these areas except as required to perform planting operations:

1. Storage of construction materials, debris, or excavated material.
2. Parking vehicles or equipment.
3. Vehicle traffic.
4. Foot traffic.
5. Erection of sheds or structures.
6. Impoundment of water.
7. Excavation or other digging unless otherwise indicated.

B. If planting soil or subgrade is overcompacted, disturbed, or contaminated by foreign or deleterious materials or liquids, remove the planting soil and contamination; restore the subgrade as directed by Architect and replace contaminated planting soil with new planting soil.

3.6 CLEANING

A. Protect areas adjacent to planting-soil preparation and placement areas from contamination. Keep adjacent paving and construction clean and work area in an orderly condition.

B. Remove surplus soil and waste material including excess subsoil, unsuitable materials, trash, and debris and legally dispose of them off Owner's property unless otherwise indicated.

END OF SECTION

SECTION 329200 - TURF AND GRASSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Seeding.
2. Hydroseeding.
3. Sodding.

1.3 DEFINITIONS

A. Finish Grade: Elevation of finished surface of planting soil.

B. Pesticide: A substance or mixture intended for preventing, destroying, repelling, or mitigating a pest. Pesticides include insecticides, miticides, herbicides, fungicides, rodenticides, and molluscicides. They also include substances or mixtures intended for use as a plant regulator, defoliant, or desiccant.

C. Pests: Living organisms that occur where they are not desired or that cause damage to plants, animals, or people. Pests include insects, mites, grubs, mollusks (snails and slugs), rodents (gophers, moles, and mice), unwanted plants (weeds), fungi, bacteria, and viruses.

D. Planting Soil: Existing, on-site soil; imported soil; or manufactured soil that has been modified with soil amendments and perhaps fertilizers to produce a soil mixture best for plant growth. See Section 329115 "Soil Preparation (Performance Specification)" and drawing designations for planting soils.

E. Subgrade: The surface or elevation of subsoil remaining after excavation is complete, or the top surface of a fill or backfill before planting soil is placed.

F. Partial Shade: An area of the site that receives more than four hours of sun each day during the growing season.

G. Shade: An area of the site that receives less than four hours of sun each day during the growing season.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Certification of Grass Seed: From seed vendor for each grass-seed monostand or mixture, stating the botanical and common name, percentage by weight of each species and variety, and percentage of purity, germination, and weed seed. Include the year of production and date of packaging.

1. Certification of each seed mixture for turfgrass sod. Include identification of source and name and telephone number of supplier.

C. Product Certificates: For fertilizers, from manufacturer.

D. Pesticides and Herbicides: Product label and manufacturer's application instructions specific to Project.

1.5 CLOSEOUT SUBMITTALS

A. Submittals shall comply with the requirements of Section 013300 “Submittal Procedures” and the individual sections specifying the work.

B. Maintenance Data: Recommended procedures to be established by Owner for maintenance of turf during a calendar year. Submit before expiration of required maintenance periods.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: A qualified landscape installer whose work has resulted in successful turf establishment.

1. Professional Membership: Installer shall be a member in good standing of either the National Association of Landscape Professionals or AmericanHort.
2. Experience: Five years' experience in turf installation in addition to requirements in Section 014000 "Quality Requirements."
3. Installer's Field Supervision: Require Installer to maintain an experienced full-time supervisor on Project site when work is in progress.
4. Pesticide Applicator: State licensed, commercial.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Seed and Other Packaged Materials: Deliver packaged materials in original, unopened containers showing weight, certified analysis, name and address of manufacturer, and indication of compliance with state and Federal laws, as applicable.

B. Sod: Harvest, deliver, store, and handle sod according to requirements in "Specifications for Turfgrass Sod Materials" and "Specifications for Turfgrass Sod Transplanting and Installation" sections in TPI's "Guideline Specifications to Turfgrass Sodding." Deliver sod within 24 hours of harvesting and in time for planting promptly. Protect sod from breakage and drying.

C. Bulk Materials:

1. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
2. Provide erosion-control measures to prevent erosion or displacement of bulk materials; discharge of soil-bearing water runoff; and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
3. Accompany each delivery of bulk materials with appropriate certificates.

1.8 FIELD CONDITIONS

A. Planting Restrictions: Plant during one of the following periods. Coordinate planting periods with initial maintenance periods to provide required maintenance from date of planting completion.

1. Spring Planting: April 15-May 20.
2. Fall Planting: August 15-October 1.

B. Weather Limitations: Proceed with planting only when existing and forecasted weather conditions permit planting to be performed when beneficial and optimum results may be obtained. Apply products during favorable weather conditions according to manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 SEED

A. Grass Seed: Fresh, clean, dry, new-crop seed complying with AOSA's "Rules for Testing Seeds" for purity and germination tolerances.

B. Seed Species:

1. Quality, Non-State Certified: Seed of grass species as listed below for solar exposure, with not less than 85 percent germination, not less than 95 percent pure seed, and not more than 0.5 percent weed seed:
2. Sun and Partial Shade, Cool-Season Grass: Proportioned by weight as follows:

a. 50 percent Kentucky bluegrass (Poa pratensis).
b. 30 percent chewings red fescue (Festuca rubra variety).
c. 10 percent perennial ryegrass (Lolium perenne).
d. 10 percent redtop (Agrostis alba).

3. Shade, Cool-Season Grass: Proportioned by weight as follows:

a. 50 percent chewings red fescue (Festuca rubra variety).
b. 35 percent rough bluegrass (Poa trivialis).
c. 15 percent redtop (Agrostis alba).

2.2 TURFGRASS SOD

A. Turfgrass Sod: Complying with "Specifications for Turfgrass Sod Materials" in TPI's "Guideline Specifications to Turfgrass Sodding." Furnish viable sod of uniform density, color, and texture that is strongly rooted and capable of vigorous growth and development when planted.

B. Turfgrass Species, Cool-Season Grass: Sod of grass species as follows, with not less than 85 percent germination, not less than 95 percent pure seed, and not more than 0.5 percent weed seed:

1. Sun and Partial Shade: Bluegrass/Fescue Mix.
2. Shade: Tall Fescue.

2.3 FERTILIZERS

A. Slow-Release Fertilizer: Granular or pelleted fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorus, and potassium in the following composition:

1. Composition:

a. Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing laboratory.

2.4 MULCHES

A. Straw Mulch: Provide air-dry, clean, mildew- and seed-free, salt hay or threshed straw of wheat, rye, oats, or barley.

B. Sphagnum Peat Mulch: Partially decomposed sphagnum peat moss, finely divided or of granular texture, and with a pH range of 3.4 to 4.8.

C. Compost Mulch: Well-composted, stable, and weed-free organic matter, pH range of 5.5 to 8; moisture content 35 to 55 percent by weight; 100 percent passing through 1-inch sieve; soluble salt content of 2 to 5 decisiemens/m; not exceeding 0.5 percent inert contaminants and free of substances toxic to plantings; and as follows:

1. Organic Matter Content: 50 to 60 percent of dry weight.
2. Feedstock: Agricultural, food, or industrial residuals; yard trimmings; or source-separated or compostable mixed solid waste.

D. Fiber Mulch: Biodegradable, dyed-wood, cellulose-fiber mulch; nontoxic and free of plant-growth or germination inhibitors; with a maximum moisture content of 15 percent and a pH range of 4.5 to 6.5.

E. Nonasphaltic Tackifier: Colloidal tackifier recommended by fiber-mulch manufacturer for slurry application; nontoxic and free of plant-growth or germination inhibitors.

F. Asphalt Emulsion: ASTM D977, Grade SS-1; nontoxic and free of plant-growth or germination inhibitors.

2.5 PESTICIDES

A. General: Pesticide, registered and approved by the EPA, acceptable to authorities having jurisdiction, and of type recommended by manufacturer for each specific problem and as required for Project conditions and application. Do not use restricted pesticides unless authorized in writing by authorities having jurisdiction.

B. Pre-Emergent Herbicide (Selective and Nonselective): Effective for controlling the germination or growth of weeds within planted areas at the soil level directly below the mulch layer.

C. Post-Emergent Herbicide (Selective and Nonselective): Effective for controlling weed growth that has already germinated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas to be planted for compliance with requirements and other conditions affecting installation and performance of the Work.

1. Verify that no foreign or deleterious material or liquid such as paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, or acid has been deposited in soil within a planting area.
2. Suspend planting operations during periods of excessive soil moisture until the moisture content reaches acceptable levels to attain the required results.
3. Uniformly moisten excessively dry soil that is not workable or which is dusty.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

C. If contamination by foreign or deleterious material or liquid is present in soil within a planting area, remove the soil and contamination as directed by Architect and replace with new planting soil.

3.2 PREPARATION

A. Protect structures; utilities; sidewalks; pavements; and other facilities, trees, shrubs, and plantings from damage caused by planting operations.

1. Protect adjacent and adjoining areas from hydroseeding and hydromulching overspray.
2. Protect grade stakes set by others until directed to remove them.

B. Install erosion-control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways.

3.3 TURF AREA PREPARATION

A. General: Prepare planting area for soil placement and mix planting soil according to Section 329115 "Soil Preparation (Performance Specification)."

B. Placing Planting Soil: Place and mix planting soil in place over exposed subgrade.

1. Reduce elevation of planting soil to allow for soil thickness of sod.

C. Moisten prepared area before planting if soil is dry. Water thoroughly and allow surface to dry before planting. Do not create muddy soil.

D. Before planting, obtain Architect's acceptance of finish grading; restore planting areas if eroded or otherwise disturbed after finish grading.

3.4 SEEDING

A. Sow seed with spreader or seeding machine. Do not broadcast or drop seed when wind velocity exceeds 5 mph.

1. Evenly distribute seed by sowing equal quantities in two directions at right angles to each other.
2. Do not use wet seed or seed that is moldy or otherwise damaged.
3. Do not seed against existing trees. Limit extent of seed to outside edge of planting saucer.

B. Sow seed at a total rate of 3 to 4 lb/1000 sq. ft..

C. Rake seed lightly into top 1/8 inch of soil, roll lightly, and water with fine spray.

D. Protect seeded areas with slopes exceeding 1:4 with erosion-control blankets and 1:6 with erosion-control fiber mesh installed and stapled according to manufacturer's written instructions.

E. Protect seeded areas with erosion-control mats where indicated on Drawings; install and anchor according to manufacturer's written instructions.

F. Protect seeded areas with slopes not exceeding 1:6 by spreading straw mulch. Spread uniformly at a minimum rate of 2 tons/acre to form a continuous blanket 1-1/2 inches in loose thickness over seeded areas. Spread by hand, blower, or other suitable equipment.

1. Anchor straw mulch by crimping into soil with suitable mechanical equipment.
2. Bond straw mulch by spraying with asphalt emulsion at a rate of 10 to 13 gal./1000 sq. ft. Take precautions to prevent damage or staining of structures or other plantings adjacent to mulched areas. Immediately clean damaged or stained areas.

3.5 HYDROSEEDING

A. Hydroseeding: Mix specified seed, slow-release fertilizer, and fiber mulch in water, using equipment specifically designed for hydroseed application. Continue mixing until uniformly blended into homogeneous slurry suitable for hydraulic application.

1. Mix slurry with fiber-mulch manufacturer's recommended tackifier.
2. Spray-apply slurry uniformly to all areas to be seeded in a one-step process. Apply slurry at a rate so that mulch component is deposited at not less than 1500-lb/acre dry weight, and seed component is deposited at not less than the specified seed-sowing rate.

3.6 SODDING

A. Lay sod within 24 hours of harvesting unless a suitable preservation method is accepted by Architect prior to delivery time. Do not lay sod if dormant or if ground is frozen or muddy.

B. Lay sod to form a solid mass with tightly fitted joints. Butt ends and sides of sod; do not stretch or overlap. Stagger sod strips or pads to offset joints in adjacent courses. Avoid damage to soil or sod during installation. Tamp and roll lightly to ensure contact with soil, eliminate air pockets, and form a smooth surface. Work sifted soil or fine sand into minor cracks between pieces of sod; remove excess to avoid smothering sod and adjacent grass.

1. Lay sod across slopes exceeding 1:3.
2. Anchor sod on slopes exceeding 1:6 with wood pegs or steel staples spaced as recommended by sod manufacturer but not less than two anchors per sod strip to prevent slippage.

C. Saturate sod with fine water spray within two hours of planting. During first week after planting, water daily or more frequently as necessary to maintain moist soil to a minimum depth of 1-1/2 inches below sod.

3.7 TURF RENOVATION

A. Renovate existing turf where indicated.

B. Renovate turf damaged by Contractor's operations, such as storage of materials or equipment and movement of vehicles.

1. Reestablish turf where settlement or washouts occur or where minor regrading is required.
2. Install new planting soil as required.

C. Remove sod and vegetation from diseased or unsatisfactory turf areas; do not bury in soil.

D. Remove topsoil containing foreign materials, such as oil drippings, fuel spills, stones, gravel, and other construction materials resulting from Contractor's operations, and replace with new planting soil.

E. Mow, dethatch, core aerate, and rake existing turf.

F. Remove weeds before seeding. Where weeds are extensive, apply selective herbicides as required. Do not use pre-emergence herbicides.

G. Remove waste and foreign materials, including weeds, soil cores, grass, vegetation, and turf, and legally dispose of them off Owner's property.

H. Till stripped, bare, and compacted areas thoroughly to a soil depth of 6 inches.

I. Apply soil amendments and initial fertilizer required for establishing new turf and mix thoroughly into top 4 inches of existing soil. Install new planting soil to fill low spots and meet finish grades.

1. Soil Amendment(s): According to requirements of Section 329115 "Soil Preparation (Performance Specification)."
2. Initial Fertilizer: Commercial fertilizer applied according to manufacturer's recommendations.

J. Apply seed and protect with straw mulch as required for new turf.

K. Water newly planted areas and keep moist until new turf is established.

3.8 TURF MAINTENANCE

A. General: Maintain and establish turf by watering, fertilizing, weeding, mowing, trimming, replanting, and performing other operations as required to establish healthy, viable turf. Roll, regrade, and replant bare or eroded areas and remulch to produce a uniformly smooth turf. Provide materials and installation the same as those used in the original installation.

1. Fill in as necessary soil subsidence that may occur because of settling or other processes. Replace materials and turf damaged or lost in areas of subsidence.
2. In areas where mulch has been disturbed by wind or maintenance operations, add new mulch and anchor as required to prevent displacement.
3. Apply treatments as required to keep turf and soil free of pests and pathogens or disease. Use integrated pest management practices whenever possible to minimize the use of pesticides and reduce hazards.

B. Watering: Install and maintain temporary piping, hoses, and turf-watering equipment to convey water from sources and to keep turf uniformly moist to a depth of 4 inches.

1. Schedule watering to prevent wilting, puddling, erosion, and displacement of seed or mulch. Lay out temporary watering system to avoid walking over muddy or newly planted areas.
2. Water turf with fine spray at a minimum rate of 1 inch per week unless rainfall precipitation is adequate.

C. Mow turf as soon as top growth is tall enough to cut. Repeat mowing to maintain specified height without cutting more than one-third of grass height. Remove no more than one-third of grass-leaf growth in initial or subsequent mowings. Do not delay mowing until grass blades bend over and become matted. Do not mow when grass is wet. Schedule initial and subsequent mowings to maintain the following grass height:

1. Mow Kentucky bluegrass, annual ryegrass, and chewings red fescue to a height of 1-1/2 to 2 inches.
2. Mow turf-type tall fescue to a height of 2 to 3 inches.

3.9 SATISFACTORY TURF

A. Turf installations shall meet the following criteria as determined by Architect:

1. Satisfactory Seeded Turf: At end of maintenance period, a healthy, uniform, close stand of grass has been established, free of weeds and surface irregularities, with coverage exceeding 90 percent over any 10 sq. ft. and bare spots not exceeding 5 by 5 inches.
2. Satisfactory Sodded Turf: At end of maintenance period, a healthy, well-rooted, even-colored, viable turf has been established, free of weeds, open joints, bare areas, and surface irregularities.

B. Use specified materials to reestablish turf that does not comply with requirements, and continue maintenance until turf is satisfactory.

3.10 PESTICIDE APPLICATION

A. Apply pesticides and other chemical products and biological control agents according to requirements of authorities having jurisdiction and manufacturer's written recommendations. Coordinate applications with Owner's operations and others in proximity to the Work. Notify Owner before each application is performed.

B. Post-Emergent Herbicides (Selective and Nonselective): Apply only as necessary to treat already-germinated weeds and according to manufacturer's written recommendations.

3.11 CLEANUP AND PROTECTION

A. Promptly remove soil and debris created by turf work from paved areas. Clean wheels of vehicles before leaving site to avoid tracking soil onto roads, walks, or other paved areas.

B. Remove surplus soil and waste material, including excess subsoil, unsuitable soil, trash, and debris, and legally dispose of them off Owner's property.

C. Erect temporary fencing or barricades and warning signs as required to protect newly planted areas from traffic. Maintain fencing and barricades throughout initial maintenance period and remove after plantings are established.

D. Remove nondegradable erosion-control measures after grass establishment period.

3.12 MAINTENANCE SERVICE

A. Turf Maintenance Service: Provide full maintenance by skilled employees of landscape Installer. Maintain as required in "Turf Maintenance" Article. Begin maintenance immediately after each area is planted and continue until acceptable turf is established, but for not less than the following periods:

1. Seeded Turf: 60 days from date of Substantial Completion.

    a. When initial maintenance period has not elapsed before end of planting season, or if turf is not fully established, continue maintenance during next planting season.

2. Sodded Turf: 30 days from date of Substantial Completion.

END OF SECTION

SECTION 333115 - SITE SANITARY SEWERAGE PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. PVC pipe and fittings.
2. Nonpressure-type transition couplings.
3. Manholes.
4. Concrete.

1.2 DEFINITIONS

A. PVC: Polyvinyl chloride.

1.3 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product.

C. Shop Drawings: For manholes. Include plans, elevations, sections, details, and frames and covers.

1.4 INFORMATIONAL SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Certificates: For each type of pipe and fitting.

C. Field quality-control reports.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Protect pipe, pipe fittings, and seals from dirt and damage.

B. Handle manholes in accordance with manufacturer's written rigging instructions.

1.6 QUALITY ASSURANCE

A. Provide materials bearing label, stamp, or other markings of specified testing agency.

1.7 FIELD CONDITIONS

A. Interruption of Existing Sanitary Sewerage Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service in accordance with requirements indicated:

1. Notify Owner no fewer than seven days in advance of proposed interruption of service.
2. Do not proceed with interruption of service without Owner's written permission.

PART 2 - PRODUCTS

2.1 PVC PIPE AND FITTINGS

A. PVC Type PSM Gravity Sewer Piping:

1. Pipe: ASTM D3034, SDR 35, PVC Type PSM sewer pipe with bell-and-spigot ends for gasketed joints.
2. Fittings: ASTM D3034, PVC with bell ends.
3. Gaskets: ASTM F477, elastomeric seals.

2.2 NONPRESSURE-TYPE TRANSITION COUPLINGS

A. Comply with ASTM C1173, elastomeric, sleeve-type, reducing or transition coupling; for joining underground nonpressure piping. Include ends of same sizes as piping to be joined and include corrosion-resistant-metal tension band and tightening mechanism on each end.

B. Sleeve Materials:

1. For Plastic Pipes: ASTM F477, elastomeric seal or ASTM D5926, PVC.
2. For Dissimilar Pipes: ASTM D5926, PVC or other material compatible with pipe materials being joined.

C. Shielded, Flexible Couplings:

1. Source Limitations: Obtain shielded, flexible couplings from single manufacturer.
2. Description: ASTM C1460, elastomeric or rubber sleeve with full-length, corrosion-resistant outer shield and corrosion-resistant-metal tension band and tightening mechanism on each end.

2.3 MANHOLES

A. Standard Precast Concrete Manholes:

1. Standard: ASTM C478/C478M.
2. Description: Precast, reinforced concrete, of depth indicated, with provision for sealant joints.
3. Diameter: 48 inches minimum unless otherwise indicated.
4. Ballast: Increase thickness of precast concrete sections or add concrete to base section, as required to prevent flotation.

5. Base Section: 6-inch minimum thickness for floor slab and 5-inch minimum thickness for walls and base riser section; with separate base slab or base section with integral floor.
6. Riser Sections: 4-inch minimum thickness, of length to provide depth indicated.
7. Top Section: Offset flat-slab-top.
8. Joint Sealant: ASTM C990, bitumen or butyl rubber.
9. Resilient Pipe Connectors: ASTM C923/C923M, cast or fitted into manhole walls, for each pipe connection.
10. Steps: ASTM A615/A615M, deformed, 1/2-inch steel reinforcing rods encased in ASTM D4101, PP; wide enough to allow worker to place both feet on one step and designed to prevent lateral slippage off step. Cast or anchor steps into sidewalls at 12-inch intervals. Omit steps if total depth from floor of manhole to finished grade is less than 60 inches.
11. Grade Rings: Reinforced-concrete rings, 6- to 9-inch total thickness, with diameter matching manhole frame and cover, and with height as required to adjust manhole frame and cover to indicated elevation and slope.
12. Concrete: Minimum 4,000 psi.

B. Manhole Frames and Covers:

1. Description: Ferrous; 24-inch ID by 7- to 9-inch riser, with 4-inch-minimum-width flange and 26-inch-diameter cover. Include indented top design with lettering cast into cover, using wording equivalent to "SANITARY SEWER."
2. Material: ASTM A48/A48M, Class 35 gray iron unless otherwise indicated.
3. Design Load: Heavy duty.

2.4 CONCRETE

A. Concrete is specified in Section 033000 “Cast-in-Place Concrete.”

B. Manhole Channels and Benches: Factory or field formed from concrete. Portland cement design mix, 4000 psi minimum, with 0.45 maximum water/cementitious materials ratio. Include channels and benches in manholes.

1. Channels: Concrete invert, formed to same width as connected piping, with height of vertical sides to three-fourths of pipe diameter. Form curved channels with smooth, uniform radius and slope.

    a. Invert Slope: 2 percent through manhole.

2. Benches: Concrete, sloped to drain into channel.

    a. Slope: 4 percent.

PART 3 - EXECUTION

3.1 EARTHWORK

A. Excavating, trenching, and backfilling are specified in Section 312000 "Earth Moving."

3.2 INSTALLATION OF PIPING

A. General Locations and Arrangements: Drawing plans and details to indicate general location and arrangement of underground sanitary sewer piping. Location and arrangement of piping layout take into account design considerations. Install piping as indicated, to extent practical. Where specific installation is not indicated, follow piping manufacturer's written instructions.

B. Install piping beginning at low point, true to grades and alignment indicated with unbroken continuity of invert. Place bell ends of piping facing upstream. Install gaskets, seals, sleeves, and couplings in accordance with manufacturer's written instructions for using lubricants, cements, and other installation requirements.

C. Install manholes for changes in direction unless fittings are indicated. Use fittings for branch connections unless direct tap into existing sewer is indicated.

D. Install proper size increasers, reducers, and couplings where different sizes or materials of pipes and fittings are connected. Reducing size of piping in direction of flow is prohibited.

E. Install gravity-flow, nonpressure, drainage piping in accordance with the following:

1. Install piping pitched down in direction of flow, at minimum slope of 2 percent unless otherwise indicated.
2. Install PVC Type PSM sewer piping in accordance with ASTM D2321 and ASTM F1668.

3.3 PIPE JOINT CONSTRUCTION

A. Join gravity-flow, nonpressure, drainage piping in accordance with the following:

1. Join PVC Type PSM sewer piping in accordance with ASTM D2321 and ASTM D3034 for elastomeric-seal joints or ASTM D3034 for elastomeric-gasket joints.
2. Join dissimilar pipe materials with nonpressure-type, flexible couplings.
3. Use nonpressure flexible couplings where required to join gravity-flow, nonpressure sewer piping unless otherwise indicated.

    a. Shielded flexible couplings for pipes of same or slightly different OD.
    b. Unshielded, increaser/reducer-pattern, flexible couplings for pipes with different OD.

3.4 INSTALLATION OF MANHOLES

A. General: Install manholes complete with appurtenances and accessories indicated.

B. Install precast concrete manhole sections with sealants in accordance with ASTM C891.

C. Form continuous concrete channels and benches between inlets and outlet.

D. Set tops of frames and covers flush with finished surface of manholes that occur in pavements.

3.5 CONCRETE PLACEMENT

A. Place cast-in-place concrete in accordance with ACI 318.

3.6 CONNECTIONS

A. Connect nonpressure, gravity-flow drainage piping to building's sanitary building drains specified in Section 221316 "Sanitary Waste and Vent Piping and Radon Piping."

B. Make connections to existing piping and underground manholes.

1. Use commercially manufactured wye fittings for piping branch connections. Remove section of existing pipe, install wye fitting into existing piping, and encase entire wye fitting plus 6-inch overlap with not less than 6 inches of concrete with 28-day compressive strength of 3000 psi.
2. Make branch connections from side into existing piping, NPS 4 to NPS 20. Remove section of existing pipe, install wye fitting into existing piping, and encase entire wye with not less than 6 inches of concrete with 28-day compressive strength of 3000 psi.
3. Make branch connections from side into existing piping, NPS 21 or larger, or to underground manholes by coring an opening into existing unit large enough to allow a flexible connector. Cut end of connection pipe passing through pipe or structure wall to conform to shape of, and be flush with, inside wall unless otherwise indicated.
4. Protect existing piping and manholes to prevent debris from entering while making tap connections. Remove debris or other extraneous material that may accumulate.

3.7 CLOSING ABANDONED SANITARY SEWER SYSTEMS

A. Abandoned Piping: Fill abandoned underground piping with flowable fill. Close open ends of abandoned underground piping indicated to remain in place. Include closures strong enough to withstand hydrostatic and earth pressures that may result after ends of abandoned piping have been closed. Use either procedure below:

1. Close open ends of piping with at least 8-inch- thick, brick masonry bulkheads.
2. Close open ends of piping with threaded metal caps, plastic plugs, or other acceptable methods suitable for size and type of material being closed. Do not use wood plugs.

B. Backfill to grade in accordance with Section 312000 "Earth Moving."

3.8 IDENTIFICATION

A. Comply with requirements in Section 312000 "Earth Moving" for underground utility identification devices. Arrange for installation of green warning tapes directly over piping and at outside edges of underground manholes.

1. Use detectable warning tape over nonferrous piping and over edges of underground manholes.

3.9 FIELD QUALITY CONTROL

A. Inspect interior of piping to determine whether line displacement or other damage has occurred. Inspect after approximately 24 inches of backfill is in place, and again at completion of Project.

1. Submit separate report for each system inspection.
2. Defects requiring correction include the following:

    a. Alignment: Less than full diameter of inside of pipe is visible between structures.
    b. Deflection: Flexible piping with deflection that prevents passage of ball or cylinder of size not less than 92.5 percent of piping diameter.
    c. Damage: Crushed, broken, cracked, or otherwise damaged piping.
    d. Infiltration: Water leakage into piping.
    e. Exfiltration: Water leakage from or around piping.

3. Replace defective piping using new materials, and repeat inspections until defects are within allowances specified.
4. Reinspect and repeat procedure until results are satisfactory.

B. Test new piping systems, and parts of existing systems that have been altered, extended, or repaired, for leaks and defects.

1. Do not enclose, cover, or put into service before inspection and approval.
2. Test completed piping systems in accordance with requirements of authorities having jurisdiction.
3. Schedule tests and inspections by authorities having jurisdiction with at least 24 hours' advance notice.
4. Submit separate report for each test.

5. Air Tests: Test sanitary sewerage in accordance with requirements of authorities having jurisdiction, UNI-B-6, and the following:

    a. Test plastic gravity sewer piping in accordance with ASTM F1417.

6. Manholes: Perform vacuum testing per the current edition of the Greater Augusta Utility District Construction Specifications and Procedures.

C. Leaks and loss in test pressure constitute defects that must be repaired.

D. Replace leaking piping using new materials, and repeat testing until leakage is within allowances specified.

3.10 CLEANING

A. Clean dirt and superfluous material from interior of piping. Flush with potable water.

END OF SECTION

SECTION 334200 - STORMWATER CONVEYANCE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Corrugated-PE pipe and fittings.
2. PVC pipe and fittings.
3. Perforated-wall pipes and fittings.
4. Nonpressure transition couplings.
5. Manholes.

1.2 ACTION SUBMITTALS

A. Submittals must comply with the requirements of the Construction Contract Clauses, Section 013300 "Submittal Procedures" and the individual Sections specifying the work.

B. Product Data: For each type of product.

C. Shop Drawings:

1. Manholes: Include plans, elevations, sections, details, frames, and covers.

1.3 INFORMATIONAL SUBMITTALS

A. Field quality-control reports.

1.4 QUALITY ASSURANCE

A. Piping materials are to bear label, stamp, or other markings of specified testing agency.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Do not store plastic pipe, and fittings in direct sunlight.

B. Protect pipe, pipe fittings, and seals from dirt and damage.

C. Handle manholes in accordance with manufacturer's written rigging instructions.

1.6 FIELD CONDITIONS

A. Interruption of Existing Storm Drainage Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service in accordance with requirements indicated:

1. Notify Owner no fewer than seven days in advance of proposed interruption of service.
2. Do not proceed with interruption of service without Owner's written permission.

PART 2 - PRODUCTS

2.1 CORRUGATED-PE PIPE AND FITTINGS

A. Source Limitations: Obtain corrugated-PE pipe and fittings from single manufacturer.

B. Corrugated-PE Drainage Pipe and Fittings NPS 3 to NPS 10 (DN 80 to DN 250): AASHTO M 252, Type S, with smooth waterway and gasketed bell and spigot joints.

C. Fittings: AASHTO M252, AASHTO M294, or ASTM F2306, PE with bell ends for gasketed, watertight joints.

D. Gaskets: ASTM F 477, elastomeric.

2.2 PVC PIPE AND FITTINGS

A. PVC Type PSM Sewer Piping:

1. Pipe: ASTM D3034, SDR 35, PVC Type PSM sewer pipe with bell-and-spigot ends for gasketed joints.
2. Fittings: ASTM D3034, PVC with bell ends.
3. Gaskets: ASTM F477, elastomeric seals.

2.3 PERFORATED-WALL PIPES AND FITTINGS

A. Perforated PE Pipe and Fittings:

1. NPS 6 and Smaller: ASTM F405 or AASHTO M 252, Type CP; corrugated, for coupled joints.
2. Couplings: Manufacturer's standard, band type.

B. Perforated PVC Sewer Pipe and Fittings: ASTM D2729, bell-and-spigot ends, for loose joints.

2.4 NONPRESSURE TRANSITION COUPLINGS

A. Comply with ASTM C1173, elastomeric, sleeve-type, reducing or transition coupling, for joining underground nonpressure piping. Include ends of same sizes as piping to be joined, and corrosion-resistant-metal tension band and tightening mechanism on each end.

B. Sleeve Materials:

1. For Plastic Pipes: ASTM F477, elastomeric seal or ASTM D5926, PVC.
2. For Dissimilar Pipes: ASTM D5926, PVC or other material compatible with pipe materials being joined.

C. Shielded, Flexible Couplings:

1. Description: ASTM C1460, elastomeric or rubber sleeve with full-length, corrosion-resistant outer shield and corrosion-resistant-metal tension band and tightening mechanism on each end.

2.5 MANHOLES

A. Standard Precast Concrete Manholes:

1. Description: ASTM C478, precast, reinforced concrete, of depth indicated, with provision for sealant joints.
2. Diameter: 48 inches minimum unless otherwise indicated.
3. Base Section: 6-inch minimum thickness for floor slab and 4-inch minimum thickness for walls and base riser section, and separate base slab or base section with integral floor.
4. Riser Sections: 4-inch minimum thickness, and lengths to provide depth indicated.
5. Top Section: Eccentric-cone type unless concentric-cone or flat-slab-top type is indicated, and top of cone of size that matches grade rings.
6. Joint Sealant: ASTM C990, bitumen or butyl rubber.
7. Resilient Pipe Connectors: ASTM C923, cast or fitted into manhole walls, for each pipe connection.
8. Steps: ASTM A615/A615M, deformed, 1/2-inch steel reinforcing rods encased in ASTM D4101, PP, wide enough to allow worker to place both feet on one step and designed to prevent lateral slippage off step. Cast or anchor steps into sidewalls at 12- to 16-inch intervals. Omit steps if total depth from floor of manhole to finished grade is less than 60 inches.
9. Grade Rings: Reinforced-concrete rings, 6- to 9-inch total thickness, to match diameter of manhole frame and cover, and height as required to adjust manhole frame and cover to indicated elevation and slope.

B. Manhole Frames and Covers:

1. Description: Ferrous; 24-inch ID by 7- to 9-inch riser with 4-inch-minimum width flange and 26-inch-diameter cover. Include indented top design with lettering cast into cover, using wording equivalent to "STORM SEWER."
2. Material: ASTM A48/A48M, Class 35 gray iron unless otherwise indicated.
3. Design Load: Heavy duty.

PART 3 - EXECUTION

3.1 EARTHWORK

A. Excavation, trenching, and backfilling are specified in Section 312000 "Earth Moving."

3.2 INSTALLATION OF PIPING

A. General Locations and Arrangements: Drawing plans and details indicate general location and arrangement of underground storm drainage piping. Location and arrangement of piping layout take into account design considerations. Install piping as indicated, to extent practical. Where specific installation is not indicated, follow piping manufacturer's written instructions.

B. Install piping beginning at low point, true to grades and alignment indicated with unbroken continuity of invert. Place bell ends of piping facing upstream. Install gaskets, seals, sleeves, and couplings in accordance with manufacturer's written instructions for use of lubricants, cements, and other installation requirements.

C. Install manholes for changes in direction unless fittings are indicated. Use fittings for branch connections unless direct tap into existing sewer is indicated.

D. Install proper size increasers, reducers, and couplings where different sizes or materials of pipes and fittings are connected. Reducing size of piping in direction of flow is prohibited.

E. Install gravity-flow, nonpressure drainage piping in accordance with the following:

1. Install piping pitched down in direction of flow.
2. Install PE corrugated sewer piping in accordance with ASTM D2321.
3. Install PVC sewer piping in accordance with ASTM D2321 and ASTM F1668.

F. Underdrain: Install piping pitched down in direction of flow, as indicated.

1. Lay perforated pipe with perforations down.

3.3 PIPE JOINT CONSTRUCTION

A. Join gravity-flow, nonpressure drainage piping in accordance with the following:

1. Join corrugated-PE piping in accordance with ASTM D3212 for push-on joints.
2. Join PVC sewer piping in accordance with ASTM D2321 and ASTM D3034 for elastomeric-seal joints or ASTM D3034 for elastomeric-gasketed joints.
3. Join dissimilar pipe materials with nonpressure-type flexible couplings.

3.4 INSTALLATION OF MANHOLES

A. General: Install manholes, complete with appurtenances and accessories indicated.

B. Install precast concrete manhole sections with sealants in accordance with ASTM C891.

C. Where specific manhole construction is not indicated, follow manhole manufacturer's written instructions.

D. Set tops of frames and covers flush with finished surface of manholes that occur in pavements.

3.5 CONCRETE PLACEMENT

A. Place cast-in-place concrete in accordance with ACI 318.

3.6 CONNECTIONS

A. Connect nonpressure, gravity-flow drainage piping in building's storm building drains specified in Section 221414 "Storm Drainage Piping."

B. Make connections to existing piping and underground manholes.

1. Use commercially manufactured wye fittings for piping branch connections. Remove section of existing pipe; install wye fitting into existing piping; and encase entire wye fitting, plus 6-inch overlap, with not less than 6 inches of concrete with 28-day compressive strength of 3000 psi.
2. Make branch connections from side into existing piping, NPS 4 to NPS 20. Remove section of existing pipe, install wye fitting into existing piping, and encase entire wye with not less than 6 inches of concrete with 28-day compressive strength of 3000 psi.
3. Make branch connections from side into existing piping, NPS 21 or larger, or to underground manholes and structures by cutting into existing unit and creating an opening large enough to allow 3 inches of concrete to be packed around entering connection. Cut end of connection pipe passing through pipe or structure wall to conform to shape of and be flush with inside wall unless otherwise indicated. On outside of pipe, manhole, or structure wall, encase entering connection in 6 inches of concrete for minimum length of 12 inches to provide additional support of collar from connection to undisturbed ground.

    a. Use concrete that will attain a minimum 28-day compressive strength of 3000 psi unless otherwise indicated.
    b. Use epoxy-bonding compound as interface between new and existing concrete and piping materials.

4. Protect existing piping, manholes, and structures to prevent concrete or debris from entering while making tap connections. Remove debris or other extraneous material that may accumulate.

C. Pipe couplings, expansion joints, and deflection fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.

1. Use nonpressure-type flexible couplings where required to join gravity-flow, nonpressure sewer piping unless otherwise indicated.

    a. Shielded flexible couplings for same or minor difference OD pipes.
    b. Unshielded, increaser/reducer-pattern, flexible couplings for pipes with different OD.

3.7 CLOSING ABANDONED STORM DRAINAGE SYSTEMS

A. Abandoned Piping: Close open ends of abandoned underground piping indicated to remain in place. Include closures strong enough to withstand hydrostatic and earth pressures that may result after ends of abandoned piping have been closed. Use either procedure below:

1. Close open ends of piping with at least 8-inch- thick, brick masonry bulkheads.
2. Close open ends of piping with threaded metal caps, plastic plugs, or other acceptable methods suitable for size and type of material being closed. Do not use wood plugs.

B. Backfill to grade in accordance with Section 312000 "Earth Moving."

3.8 IDENTIFICATION

A. Materials and their installation are specified in Section 312000 "Earth Moving." Arrange for installation of green warning tape directly over piping and at outside edge of underground structures.

1. Use detectable warning tape over nonferrous piping and over edges of underground structures.

3.9 FIELD QUALITY CONTROL

A. Inspect interior of piping to determine whether line displacement or other damage has occurred. Inspect after approximately 24 inches of backfill is in place, and again at completion of Project.

1. Submit separate reports for each system inspection.
2. Defects requiring correction include the following:

    a. Alignment: Less than full diameter of inside of pipe is visible between structures.
    b. Deflection: Flexible piping with deflection that prevents passage of ball or cylinder of size not less than 92.5 percent of piping diameter.
    c. Damage: Crushed, broken, cracked, or otherwise damaged piping.
    d. Infiltration: Water leakage into piping.
    e. Exfiltration: Water leakage from or around piping.

3. Replace defective piping using new materials, and repeat inspections until defects are within allowances specified.
4. Reinspect and repeat procedure until results are satisfactory.

B. Test new piping systems, and parts of existing systems that have been altered, extended, or repaired, for leaks and defects.

1. Do not enclose, cover, or put into service before inspection and approval.
2. Submit separate report for each test.
3. Gravity-Flow Storm Drainage Piping: Test in accordance with requirements of UNI-B-6 and the following:

    a. Test plastic piping in accordance with ASTM F1417.

C. Leaks and loss in test pressure constitute defects that must be repaired.

D. Replace leaking piping using new materials, and repeat testing until leakage is within allowances specified.

3.10 CLEANING

A. Clean interior of piping of dirt and superfluous materials. Flush with potable water.

END OF SECTION



231 Main Street, Biddeford, ME 04005 TEL 207.283.0193 FAX 207.283.4283 www.oakpoint.com
85 Middle Street, Portsmouth, NH 03801 TEL 603.431.4849 FAX 603.431.1870