

May 10, 2021

Addendum 3G

Notice to all holders of Bid Documents for **Chamberlain St Parking Lot Improvements, Chamberlain St, Augusta, Maine – BGS# 3172**

The following changes are to be incorporated into the Contract Documents for Chamberlain Street Parking Lot Improvements, Chamberlain St., Augusta, Maine – BREM# 3172:

Addendum 3

1. On sheet 4 (Construction Details and Notes), the curb installation drawing calls for bituminous or slipform curb, but it shows a 6"x18" curb. We have revised the detail to a slipform concrete curb on binder pavement for curbing.
2. Gravels and pavements are to be tested. The larger parking area to have gravels and pavements tested in 10 random locations throughout the site for each lift to obtain a 95% compaction. The smaller parking area to have gravels and pavements tested in 5 random locations throughout the site.
3. The charging stations, blue boxes, and security cameras are to be purchased by the Owner. The Contractor is to run conduit/power to each location. The Contractor is also required to install the bases for the charging station and blue boxes.

Please remember to acknowledge this addendum 3 and date May 10, 2021 in the Contractor Bid form (Section 00 41 13).