

RIVERVIEW PSYCHIATRIC CENTER TRANSFER SWITCH REPLACEMENT AUGUSTA, MAINE


ALLIED PROJECT No. 23015



LOCATION MAP

ISSUED FOR BID 21 APRIL, 2023





160 Veranda Street Portland, Maine 04103

T: 207.221.2260 F: 207.221.2266 Web: www.allied-eng.com





on− -\23015_E.dwg Apr 20, 2023 - 3:56pm






PHOTO #6 - ATS - EE (EXISTING INTERIOR LOWER) DO NOT SCALE

CUMMINS MODEL# OTPCG-5564556 SERIAL #G020392701 EXISTING ATS 2000 A 3¢ 480V 3 POLES FRONT ATS (ER) (ER) (S) 4" CONDUITS 2000A FEEDER (TYPICAL) NOTE: REPRESENTATIVE FOR
EXISTING EQUIPMENT SERVICE IS DOUG COURSER OF CUMMINS (PHONE NO. (207) 577-8646)

EXISTING ATS DETAIL

DO NOT SCALE

DO NOT SCALE

STEP	DESCRIPTION	EC	RPC	AEI	VEN
	Listed below is an outline/schematic version of the expected work plan. The contractor will assemble a work plan for review and comment by the owner and the engineer of record prior to initiating any procurement effort. The contractor shall set up a work plan meeting to acquire input from the owner and the design team. The work plan will include as a minimum each of the step listed		141 0	71	VEIN
GENERAL	below (however should elaborate with more detail, steps and information. Include in the workplan each step beginning with investigation work and following through to close-out; step ID and description, approximate duration, if shut-down required, quantity of staff utilized, tools and equipment required for step, loads at risk, contingency plans, date and time of day for step	R			
GENERAL	The columns listed to the right identify, electrical contractor (EC) and/or CM if utilized, Riverview Psychiatric Center (RPC), allied engineering (AEI) and vendor (VEN). When columns are selected in indicates team members that shall be included in a particular set; (R) denotes responsible party, (X) denotes team members to be included and coordinated with	R			
GENERAL	The maximum acceptable shut down period for the loads served by the MD-EE switchboard is 2 hours. The power shut downs can only occur during the 4AM to 6AM and 7PM to 9PM time slots. The power shut downs can only occur during the fall or the spring cooling/heating seasons. The power shuts down can only occur during the 5 day standard work week.	R			
GENERAL	The proposed temporary generator size is 750 KW (480 volt, rated, three phase) provided with sufficient fuel storage to eliminate or minimize scheduled refueling during operation. The temporary generator shall not be run overnight. All work associated with connecting temporary cables, disconnecting temporary cables, removing old ATS-EE and installing new ATS shall be completed within 4AM to 9PM of a single work day.	R			
GENERAL	The electrical contractor shall have on-site the necessary material to temporarily make up a normal feeder to lad feeder splice inside the existing ATS-EE (or new ATS unit) as a contingency should a serious issue occur during the work related to removing the existing ATS-EE or installing the new ATS unit	R			
DDE CON					
PRE-CON	Schedule time to visit site with owner to review work area, lay down area, access requirements for on-site staff and proposed				
1	temporary generator location	R	X		
2	Develop DRAFT of the proposed work plan and schedule time to review the DRAFT with owner and the engineer	R	Х	Х	
3	Revise and reissue FINAL work plan based on review meeting for DRAFT of work plan	R	Х	Х	
4	Issue APPROVED work plan to team based on the owner and engineer comments to the FINAL work plan	R			
5	Schedule time for 2 hour shut down of ATS-EE unit in order to deenergize ATS-EE, remove access panels and take measurements and photos of existing bussing heights and conduit entry points for each feeder. Contractor may include vendor technician if they have preselected one.	R	x	Х	
6	On scheduled shutdown disarm generator start signal from ATS-EE to the generator control panel (ensure the start signal for the other three ATS units have been maintained operational). OPEN the dedicated respective 2000A circuit breaker in MDE and MD switchgear to isolate ATS-EE for safe removal of access panels and information gathering at ATS-EE. Test to ensure ATS-EE components are deenergized. Proceed with necessary investigation and measurement. Once investigation work is complete close up access panels and CLOSE the two isolating switchgear breakers.	R	X	Х	
7	Schedule time for 2 hour shut down of MD-EE to remove access panels and gather information to determine means and methods for connecting temporary generator cables to switchboard for supporting building loads during ATS replacement step	R	Х	Х	
8	On scheduled shutdown disarm generator start signal from ATS-EE to the generator control panel (ensure the start signal for the other three ATS units have been maintained operational). OPEN the dedicated respective 2000A circuit breaker in MDE and MD switchgear to isolate ATS-EE and MD-EE for safe removal of access panels and information gathering at MD-EE. Test to ensure MD-EE components are deenergized. Proceed with necessary investigation and measurement. Once investigation work is complete close up access panels and CLOSE the two isolating switchgear breakers.	R	X	Х	
PROCURE					
9	Provide information gathered from measurement survey to vendor to ensure a unit will be constructed that will fit in the same footprint and not require any new feeders; reusing the existing feeders within the ATS enclosure	R			X
10	Provide copy of any questions or comments received from the vendor to the owner and engineer	R	Х	Х	
11	Have vendor produce submittal / shop drawing package for review and comment by the project team	R	Х	Х	Х
EACTORY					
FACTORY	Evocute the page gary pro-demonstration energiand and expedit, tests, at the factory to answer all factories and account of				
12	Execute the necessary pre-demonstration operational and capacity tests, at the factory, to ensure all features and components of the equipment is functioning as required	R			Х
13	Demonstrate to representative(s) of the project team the functionality of the unit, at the factory (or designated test site), prior to packaging for shipment. The minimum team member representation with be the design engineer and the electrical contractor project manager and installation superintendent for the electrical contractor	R		X	X

WORK SEQUENCE, SHUT DOWN PREPARATION AND CONTINGENCY PLAN REQUIREMENT NOTES

STEP	DESCRIPTION	EC	RPC	AEI	VEN
ISTALLATION					
14	Review with installation team, owner and engineer the Approved work plan 2 weeks prior to the first scheduled step	R	Х		
15	Have all required equipment, fuel, temporary generator and construction materials safely secured on site, especially the replacement ATS unit and anything required to execute contingency plans	R			Х
16	Remove the existing door leading from the exterior to the stand-by power electrical room. Work with the owner to safely store the removed door for reinstallation and for owner acceptable means to secure the opening during times when electrical contractor staff is on site and off site.	R	Х		
17	Move the replacement ATS unit into position within the emergency electrical room such that it can be easily moved into place and also not impede the related work clearance needed for working about and removing the existing ATS-EE. Set up ramps over the temporary cables that will permit the removal of the existing ATS-EE unit.	R			
18	Schedule time for 2 hour shut down of MD-EE to remove access panels, disconnect load feeder, make safe and connect the temporary generator flexible cables.	R	Х		
19	On scheduled shutdown disarm generator start signal from ATS-EE to the generator control panel (ensure the start signal for the other three ATS units have been maintained operational). OPEN the dedicated respective 2000A circuit breaker in MDE and MD switchgear to isolate ATS-EE and MD-EE for safe removal of access panels to gain access for connecting temporary cables. Test to ensure MD-EE components are deenergized. Proceed with connection of temporary cables. Bring generator on line and confirm MS-EE loads are now safely supported by the temporary generator.	R	x	Х	
20	The respective dedicated circuit breakers in MDE and MD shall remain OPEN and secured by proper LOTO methods. The start signal for ATS-EE shall remain disconnected. The loads served by MD-EE switchboard are now supported by the temporary generator. The removal and replacement of the existing ATS-EE can now begin.				
21	Disconnect the normal, emergency and load feeders from the existing ATS-EE. Remove existing ATS-EE unit completely out of the work zone.	R			
22	Clean up and inspect the existing feeder conductor termination points; make ready for connection to new ATS lugs. Set the new ATS unit in place. Make up the terminations from the existing normal, emergency and load feeders to the respective termination lugs on the new ATS unit. Check for proper torque and ensure all grounding and component/control wiring has been completed. Secure all access panels	R			
23	Schedule time for 2 hour shut down of MD-EE to disconnect temporary cables and reconnect the existing load feeder.	R	Х		
24	On scheduled shutdown disarm generator start signal from the new ATS to the generator control panel (ensure the start signal for the other three ATS units have been maintained operational). Shut down the temporary generator (unit will run through its cool down procedure). Confirm the dedicated respective 2000A circuit breaker in MDE and MD switchgear are still OPEN to isolate ATS-EE and MD-EE for safe removal of the temporary cables. Test to ensure MD-EE components are deenergized. Proceed with disconnection of temporary cables.	R	х	Х	
25	Remove the LOTO methods on the respective dedicated circuit breakers in MDE and MD and CLOSE these two breakers. Re-terminate the start signal from the new ATS unit to the generator control panel. The loads served by MD-EE switchboard are now supported by new ATS unit. Run the new ATS unit through a normal to emergency and emergency to normal power transfer operation.	R	х	Х	
26	Reinstall the existing door leading from the exterior to the stand-by power electrical room. Ensure all access and security system associated with the reinstalled door are returned to proper full functionality	R	Х		
27	Clear all equipment, tools, generator, cables and debris from work zone	R	Х		
CLOSE-OUT					
28	Provide owner with demonstration on operation and maintenance task for the new ATS; utilize a factory trained technician	R	Х		Х
29	Provide an O and M submittal package for the new ATS unit. It shall be reviewed by design team prior to providing the owner with a final copy	R	х	Х	Х

ISSUED FOR BID

E-500