
Harriman

York Middle School Window Replacement Phase 2 York, Maine

Project No. 23590

February 29, 2024

Construction Documents



PROFESSIONAL SEAL PAGE



This Page Left Intentionally Blank

YORK MIDDLE SCHOOL WINDOW REPLACEMENT – PHASE 2 YORK, MAINE

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

C		TT/	TAC	1
•	EC	ш	ЛN	Ι.

1-A - Instructions to Bidders (Public School Projects)

SECTION 2. FORMS:

2-A -	Notice to Building Contractors (Public School Projects)
2-B1 -	Proposal Form For General Contractors (Public School Projects)
2-C1 -	Form of General Contract Bid Bond
2-C2 -	Form of General Contract Performance Bond
2-C3 -	Form of General Contract Payment Bond

State of Maine Construction Contract (Public School Project)

SECTION 3.

2-E -

3-A - State of Maine Standard General Conditions and Contract Work for Public School Projects

3-B - Supplementary Conditions

DIVISION 01 - GENERAL REQUIREMENTS

011000 - Summary 013100 - Submittal Procedures

DIVISION 02 - EXISTING CONDITIONS

024119 - Selective Demolition

DIVISION 03 – 06 – NOT USED

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

079200 - Joint Sealants

DIVISION 08 - OPENINGS

084523 - Fiberglass-Sandwich-Panel Assemblies

085200 - Fiberglass Replacement Windows

085201 - Replacement Window Screens

DIVISIONS 9 – 33 – NOT USED

TABLE OF CONTENTS Page 1

LIST OF DRAWINGS

G00-1 COVER SHEET

ARCHITE	CTURAL DRAWINGS
A10-1	FIRST FLOOR PLAN
A10-2	SECOND FLOOR PLAN
A10-3	THIRD FLOOR PLAN
A20-1	EXTERIOR ELEVATIONS
A55-1	WINDOW ELEVATIONS
A55-2	WINDOW DETAILS

TABLE OF CONTENTS Page 2

SECTION 1-A INSTRUCTIONS TO BIDDERS (PUBLIC SCHOOL PROJECT)

- 1. At the time of the opening of proposals, each bidder will be presumed to have inspected the site and to have read and be thoroughly familiar with the plans and contract documents, including all addenda. The failure or omission of any bidder to receive or examine any form, instrument, or document shall in no way relieve any bidder from any obligation in respect to his proposal. The Owner reserves the right to accept or reject any or all proposals as may best serve the interest of the Owner.
- 2. (a) General Contractors shall use the proposal form for General Contractor included in the specification. One (1) copy shall be filled out and signed and sent to the Owner in a sealed envelope to arrive on or before the time specified in the "Notice to Building Contractors" Section 2-A.
 - (b) Telegraphic proposal from the General Contractors will not be considered, but modifications by telegram of proposals already submitted will be considered, if received prior to the hour set for receipt of proposals. If the telegram discloses the amount of the proposal submitted, the proposal will be declared invalid.
- 3. Subject to the Owner's right, reserved herein, to accept or reject any or all proposals, the General Contractor will be selected on the basis of the sum of the lowest acceptable proposal plus such of the alternates as the Owner desires to use.
- 4. The Owner is exempt from the payment of Federal Excise Tax on articles not for resale and the Federal Transportation Tax on all shipments. The Contractor shall quote less these taxes.
- 5. Maine State Sales and Use Tax should not be included in your quotation as the Owner is exempt from the payment of such taxes. All Contractors and Sub-Contractors should refer to State of Maine, Bureau of Taxation "Sales and Use Tax Division" for latest bulletin covering Sales and Use Tax Regulations.
- 6. No proposal may be withdrawn during a period of thirty (30) calendar days immediately following the opening of the General contract proposals.
- 7. No contract may be assigned, sublet or transferred without the written consent of the Owner.
- 8. (a) All foreign corporations intending to do business in the State of Maine must comply with the provisions of Title 13-A M.R.S.A., Chapter 12. Any foreign corporation receiving notice of award of contract shall contact the Secretary of State for the purpose of complying with this statute.

- (b) All individuals not residents of the State of Maine are subject to the provisions of Title 14, M.R.S.A., Section 704-A.
- (c) It may be necessary for the General Contractor to submit to the Owner documentary evidence that the provisions have been complied with.
- 9. The selected General Contractor will be required to furnish a 100% performance bond and a 100% payment bond to cover the execution of his contract in conformity with the form of bonds shown in sections 2-C2 and 2-C3.
- 10. General Contractors may be required to furnish a statement of their business experience, record of accomplishments, and financial responsibility at the discretion of the Owner.
- 11. (a) The date of completion is stated in the proposal form section 2-B-1 and in the contract form section 2-E. If the Contractor finds it impossible to complete the work on or before the said date of completion, he may make a written request to the Owner for an extension of time setting forth therein the reasons for the request. If the Owner finds that the work was delayed because of conditions beyond the control and without the fault of the Contractor he may extend the date of completion in such amount as, in his judgment, the conditions warrant. The said new date of completion shall then be in full force and affect the same as though it were the original date of completion.
 - (b) Time is an essential element of the contract and it is important that the work be pressed vigorously to completion. The cost to the Owner of administration of the Contract, inspection and supervision will be increased as the time occupied in the work is lengthened.
- 12. (a) The proposal shall be based on the materials, methods, equipment and products as specified.
 - (b) Any materials, methods, equipment and products not herein specified but deemed worthy of consideration by any General Contractor or Sub-Contractor, may be introduced by a separate letter attached to his proposal. He shall state the cost comparison with the specified methods, equipment and products and the reason for the suggested substitution.
 - (c) It shall be understood by the General Contractor or Sub-Contractor that the attached letter describing the proposed change will not be used in determining the low General or Sub-Contract proposal submitted unless the General or Sub-Contractor shall have submitted their list of proposed changes to the Designer 10 days prior to the date set for the receipt of their respective proposals, the Designer shall have issued an addendum related to the change(s) proposed, and the Contractor shall have received written approval by the Designer.

13. <u>Employment Practices</u>

(a) Listing of job vacancies; Executive Order No. 5, dated December 6, 1971, requires that "the Contractor, or any Sub-Contractor holding a contract directly under the

Contractor, shall, to the maximum feasible, list all its suitable employment openings with the Maine Employment Security Commission."

- (b) "This provision shall not apply to employment openings which the Contractor proposed to fill from its own organization."
- (c) Two copies of a "Quarterly Report of New Hires" shall be prepared by the 7th of January, April, July and October for the calendar quarter to which data pertains and sent to the local office of the Maine Employment Security Commission.
- (d) A copy of the reporting form is attached to these Instructions to Bidders. These may be obtained from the nearest office of M.E.S.C. serving the area.
- 14. Code of Fair Practices; Executive Order No. 11, dated July 1, 1972, requires that every State contract for public works contain the following provisions: "During the performance of this contract, the Contractor agrees as follows:
 - (a) The Contractor will not discriminate against any employee or applicant for employment because of race, color, religious creed, sex, national origin, ancestry or age. Such action shall include, but not be limited to the following: employment upgrading, demotions, transfers, recruitment or recruitment advertising; layoffs or terminations; rates of pay or other forms of compensation; and selection of training including apprenticeship.
 - (b) The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor; state that all qualified applicants will receive consideration for employment without regard to race, color, religious creed, sex, national origin, ancestry or age.
 - (c) The Contractor will send to each labor union or representative of the workers with which he has a collective or bargaining agreement, or other contract or understanding, whereby he is furnished with labor for the performance of his contract, a notice, to be provided by the contracting department or agency, advising the said labor union or workers' representative of the Contractors commitment under this section and shall post copies of the notice in conspicuous places available to employees and to applicants for employment."
 - (d) The Contractor will cause the foregoing provisions to be inserted in all contracts for any work covered by this agreement so that such provisions will be binding upon each Sub-Contractor.
- 15. <u>OSHA</u> Safety Regulations. This project is subject to compliance with all requirements of the Occupational Safety and Health Administration, Volume 36, No. 105 of the Federal Register, U.S. Department of Labor published Saturday, May 29, 1971 as amended.
- 16. Any proposal that contains an escalation clause will be invalid.

- 17. Any and all Designer interpretations and/or clarifications of bidding documents must be in the form of written addenda issued from the Designer office to all bidders who are on record at the Designer office not later than 72 hours prior to scheduled receipt of bids. (No verbal interpretations and/or clarifications shall be allowed as a substitute for written addenda.)
- 18. Questions by the bidder concerning alternate work descriptions/content/completeness and bidding process must be clarified with the Designer to assure the proper bidding and execution of all work intended under the alternate. This clarification must be in the form of a written addendum as described in item 19 above.
- 19. Preparation of General Contract Bid Proposal.
 - (a) General contract bidders are responsible for the completeness of their bid proposal on form issued with bidding document.
- (b) Proposal must show cost of work specified including work specified; in any and all legally issued addenda.
 - (c) Any General contract proposal which fails to include the cost of work specified in an alternate may be declared informal if the Owner elects to include said alternate in the General contract.
 - (d) Proposal is to acknowledge all addenda that may have been legally issued. (Failure to acknowledge may be cause to have bid declared informal.)
 - (e) Indicate time for completion of the work, if required.
 - (f) Include corporate/partnership information as required.
 - (g) Proposal must be signed in ink.
 - (h) Proposal must be accompanied by required certified or cashier's check or a duly signed and executed bid bond.

SECTION 2-A

NOTICE TO BUILDING CONTRACTORS (PUBLIC SCHOOL PROJECTS)

Sealed proposals in envelopes plainly marked, Proposal For:

York Middle School Window Replacement Phase 2

Brief Job Description: The work consists of window replacement at York Middle School.

Addressed to: Mr. Chris Rynne

York School Department

469 US Route 1 York, ME 03909

Email: crynne@yorkschools.org

Phone: (207) 363-3403 x10033

Proposals will be opened and read aloud at 2:00 pm on March 19, 2024, at the office of the Superintendent of Schools. Bids received after 2:00 pm will not be considered and will be returned unopened. Proposals may also be emailed to Chris Rynne, by 2:00 pm on March 19, 2024, at crynne@yorkschools.org.

A mandatory pre-bid conference for General Contractors, to review project scope and bid requirements, will be held inside the main entrance of York Middle School on Tuesday, March 12, 2024 at 2:00 p.m. Attendance is required by General Contractors to bid the project.

The owner reserves the right to waive all formalities, and reject any and all proposals or to accept any proposal. Proposals shall be submitted upon the form provided by the architect.

General Contractors and Subcontractors can download Bid Documents from the BGS site at https://www.maine.gov/dafs/brem/business-opportunities.

This Page Left Intentionally Blank

SECTION 2-B1

PROPOSAL FORM FOR GENERAL CONTRACTORS (PUBLIC SCHOOL PROJECTS)

BIDD	ER:
TO:	Mr. Chris Rynne York School Department 469 US Route 1 York, ME 03909
A.	Having carefully examined the form of contract, general conditions, special provisions and plan and specifications dated February 29, 2024, Prepared by: Harriman, Architects + Engineers for the York Middle School Window Replacement Phase 2 as well as the premises and condition affecting the work, we the undersigned propose to furnish all labor, equipment, and material necessary for and reasonably incidental to the construction and completion of this proposal for the amount of:
\$	
В.	This proposal includes the following addenda to the drawings and specifications: Addendum No, Dated Addendum No, Dated
C.	The undersigned agrees, if this proposal is accepted, to sign a contract and deliver it, along with the bonds and affidavits of all insurance specified within twelve (12) calendar days after the date of notification of such acceptance, except if the 12th day falls on a holiday, a Saturday or Sunday then the conditions will be fulfilled if the required documents are received before 12 o'clock noon on the day following the holiday, or the Monday following the Saturday or Sunday, and as a guarantee thereof, herewith submits a certified or cashier's check or bid bond as required.

D.	The undersigned agrees, if awarded the contract, to substantially complete the work on August 19, 2024 in accordance with Section 011000.
	Signed
	Ву
	Address
NOTE:	If bidder is a corporation, write State of incorporation, and if a partnership, give full names of all s.

Contractor Bid Form

Bid Proposal Schedule of Values

Div.	Description of Work	Cost
1	General Requirements	\$
2	Existing Conditions	\$
3	Concrete	\$
4	Masonry	\$
5	Steel	\$
6	Carpentry	\$
7	Thermal and Moisture Protection	\$
8	Openings	\$
9	Finishes	\$
10	Specialties	\$
11	Equipment	\$
12	Furnishings	\$
13	Special Construction	\$
14	Conveying Equipment	\$
21	Fire Suppression	\$
22	Plumbing	\$
23	HVAC	\$
26	Electrical	\$
27	Communications	\$
28	Electronic Safety and Security	\$
31	Earthwork	\$
32	Exterior Improvements	\$
33	Utilities	\$

	Subtotal:	\$
Mark-Ups		
General Conditions		
Bonds and Insurances		
	Subtotal:	\$
	BASE BID SUBMISSION TOTAL:	\$

This Page Left Intentionally Blank

SECTION 2-C1 SHORT FORM FORM OF GENERAL CONTRACT BID BOND

(Public School Projects)

KNOW ALL MEN BY THESE PRESENTS, THAT WE, THE UNDERSIGNED

(1),
(2)
OFAND STATE OF
AS PRINCIPAL AND (3)
AS SURETY, ARE HEREBY HELD AND FIRMLY BOUND UNTO (4)
IN THE PENAL SUM OF FIVE PERCENT OF THE BID AMOUNT
FOR THE PAYMENT OF WHICH, WELL AND TRULY TO BE MADE, WE HEREBY JOINTLY AND
SEVERALLY BIND OURSELVES, OUR HEIRS, EXECUTORS, ADMINISTRATORS, SUCCESSORS AND
ASSIGNS, SIGNED THIS (5)DAY OF20
THE CONDITION OF THE ABOVE OBLIGATION IS SUCH THAT WHEREAS THE
PRINCIPAL HAS SUBMITTED TO (6) OWNER
A CERTAIN PROPOSAL, ATTACHED HERETO AND HEREBY MADE A PART HEREOF, TO ENTER INTO
A CONTRACT IN WRITING, FOR THE CONSTRUCTION OF (7)
NOW THEREFORE:
(A) IF SAID PROPOSAL SHALL BE REJECTED, OR, IN THE ALTERNATE,
(B) IF SAID PROPOSAL SHALL BE ACCEPTED AND THE PRINCIPAL SHALL EXECUTE AND DELIVER
A CONTRACT IN THE FORM OF CONTRACT ATTACHED HERETO (PROPERLY COMPLETED IN
ACCORDANCE WITH SAID PROPOSAL) AND SHALL FURNISH A BOND FOR HIS FAITHFUL
PERFORMANCE OF SAID CONTRACT, AND FOR THE PAYMENT OF ALL PERSONS PERFORMING
LABOR OR FURNISHING MATERIAL IN CONNECTION THEREWITH, AND SHALL IN ALL OTHER
RESPECTS PERFORM THE AGREEMENT CREATED BY THE ACCEPTANCE OF SAID PROPOSAL, THEN
THIS OBLIGATION SHALL BE VOID, OTHERWISE THE SAME SHALL REMAIN IN FORCE AND EFFECT:
IT BEING EXPRESSLY UNDERSTOOD AND AGREED THAT THE LIABILITY OF THE SURETY FOR ANY

Page 1 of 2

PS-28/C-2/74

Rev 4-27-94, 2-5-02, 9-25-09, 2-21-12

Section 2-C1

AND ALL CLAIMS HEREUNDER SHALL, IN NO EVENT, EXCEED THE PENAL AMOUNT OF THIS OBLIGATION AS HEREIN STATED.

THE SURETY, FOR VALUE RECEIVED HEREBY STIPULATES AND AGREES THAT THE
OBLIGATION OF SAID SURETY AND ITS BOND SHALL BE IN NO WAY IMPAIRED OR AFFECTED BY
ANY EXTENSION OF TIME WITHIN WHICH THE PRINCIPAL MAY ACCEPT SUCH PROPOSAL: AND
SAID SURETY DOES HEREBY WAIVE NOTICE OF ANY SUCH EXTENSION.

IN WITNESS WHEREOF, THE PRINCIPAL AND THE SURETY HAVE HEREUNTO SET THEIR HANDS AND SEALS, AND SUCH OF THEM AS ARE CORPORATIONS HAVE CAUSED THEIR CORPORATE SEALS TO BE HERETO AFFIXED AND THESE PRESENTS TO BE SIGNED BY THEIR PROPER OFFICES, THE DAY AND YEAR FIRST SET ABOVE.

SIGNED AND SEALED THIS (5) _		DAY OF	20
WITNESS:	CONTRA	ACTOR:	
	_ By		(L.S.)
	_ By		(L.S.)
	_ By		(L.S.)
WITNESS:	SURETY	<u>;</u>	
	_ By		(L.S.)
	_ By		(L.S.)
APPROVED AS TO FORM		, 20	<u>-</u> •
BY_			
(Owner's A	Attorney)		

Legend

- (1) Correct name of contractor.
- (2) A corporation, a partnership, or an individual, as the case may be.
- (3) Correct name of surety.
- (4) Treasurer of the municipality or school administrative district, as the case may be.
- (5) Same date as that of proposal.
- (6) Owner shall be the municipality or school administrative district, as the case may be.
- (7) Name of project as designated in the contract documents.

If contractor is a partnership, all partners should execute bond. A power of attorney document, together with a statement that it still is in full force and effect shall be provided by the person executing this bond.

SECTION 2-C2

LONG FORM FORM OF GENERAL CONTRACT PERFORMANCE BOND

(Public School Projects)

KNOW ALL MEN BY	THESE PRES	ENTS THAT (1)		
		(2)		
OF		AND STATE OF		
AS PRINCIPAL, AND (3)				
A CORPORATION DULY OR	GANIZED UN	DER THE LAWS OF	THE STATE OF_	
AND HAVING A USUAL PLA	ACE OF BUSIN	NESS IN		AS
SURETY, ARE HELD AND F	IRMLY BOUN	D UNTO THE (4)		
AS OBLIGEE, IN THE PENAL	L SUM OF			DOLLARS
(\$), TO BE PA	AID SAID		
OR HIS SUCCESSORS IN OF	FICE, FOR WI	HICH PAYMENT WEI	LL AND TRULY T	O BE MADE,
PRINCIPAL AND SURETY B	IND THEMSE	LVES, THEIR HEIRS,	EXECUTORS AN	ID
ADMINISTRATORS, SUCCE	SSORS AND A	ASSIGNS, JOINTLY A	ND SEVERALLY	BY THESE
PRESENTS.				
THE CONDITION OF	THIS OBLIGA	ATION IS SUCH THAT	Γ IF THE PRINCIP	'AL SHALL
PROMPTLY AND FAITHFUL	LY PERFORM	I THE CONTRACT E	NTERED INTO ON	N THE
(5)D	OAY OF		A.D. 20	FOR THE
CONSTRUCTION OF (6)				
THEN THIS OBLIGATION SE	HALL BE NUL	L AND VOID: OTHE	RWISE IT SHALL	REMAIN IN
FULL FORCE AND EFFECT.				
THE SURETY HEREB	BY WAIVES N	OTICE OF ANY ALTI	ERATION OR EXT	ΓENSION OF
TIME MADE BY THE (7) OW	NER.			
SIGNED AND SEALE BGS-29/C1-2/74 Rev. 9-25-09, 2-21-12	D THIS (5)	DAY OF_Page 2 of 2		20 Sec. 2-C

WITNESSES:		CONTRACTOR	
		Ву	(L.S.)
		By	(L.S.)
		Ву	(L.S.)
WITNESSES:		SURETY:	
By			
By			
APPROVED AS TO FORM			, 20
BY			
	(Owner's At	torney)	

Legend

- (1) Correct name of contractor.
- (2) A corporation, a partnership, or an individual, as the case may be.
- (3) Correct name of surety.
- (4) Treasurer of the State of Maine.
- (5) Same date as that of contract.
- (6) Name of project as designated in contract documents.
- (7) Owner shall be the State of Maine.

If contractor is a partnership, all partners should execute bond. A power of attorney document, together with a statement that it still is in full force and effect shall be provided by the person executing this bond.

SECTION 2-C3

SHORT FORM FORM OF GENERAL CONTRACT PAYMENT BOND

(Public School Projects)

KNOW ALL MEN BY THESE PRESENT	fS THAT (1)			
	(2)			
OF	AND STATE OF			
AS PRINCIPAL AND (3)				
A CORPORATION DULY ORGANIZED UNDER	R THE LAWS OF THE	E STATE OF		
AND HAVING A USUAL PLACE OF BUSINESS	S IN	AS SURETY ARE HELD AND		
FIRMLY BOUND UNTO THE (4)		IN THE SUM OF		
	DOLLARS, (\$) FOR THE USE		
AND BENEFITS OF CLAIMANTS* AS HEREIN	BELOW DEFINED,	THE PAYMENT WHEREOF		
PRINCIPAL AND SURETY BIND THEMSELVE	S, THEIR HEIRS, EX	ECUTORS AN ADMINISTRATORS,		
SUCCESSORS AND ASSIGNS, JOINTLY AND S	SEVERALLY BY TH	ESE PRESENTS. THE CONDITION OF		
THIS OBLIGATION IS SUCH THAT IF THE PRI	NCIPAL SHALL PRO	OMPTLY SATISFY ALL CLAIMS AND		
DEMANDS INCURRED FOR ALL LABOR AND	MATERIAL, USED	OR REQUIRED BY HIM IN		
CONNECTION WITH THE WORK CONTEMPL	ATED IN THE CONT	RACT ENTERED INTO ON THE		
(5)DAY OF	_A.D. 20FOR TH	E CONSTRUCTION OF		
(6)		, AND SHALL FULLY		
REIMBURSE THE OBLIGEE FOR ALL OUTLA	Y AND EXPENSE W	HICH SAID OBLIGEE MAY INCUR IN		
MAKING GOOD ANY DEFAULT OF SAID PRI	NCIPAL, THEN THIS	OBLIGATION BE NULL AND VOID:		
OTHERWISE, IT SHALL REMAIN IN FULL FO	RCE AND EFFECT.			
* A claimant is defined as one having a dir	ect contract with the p	rincipal or with a subcontractor of the		

* A claimant is defined as one having a direct contract with the principal or with a subcontractor of the principal for labor, material, or both, used or reasonably required for use in the performance of the contract.

SIGNED AND SEALED TH	IS (5)DAY OF	20
WITNESSES:	CONTRACTOR:	
	BY	(L.S.)
	BY	(L.S.)
	BY	(L.S.)
WITNESSES:	SURETY	(L.S.)
	BY	(L.S.)
	BY	(L.S.)
APPROVED AS TO FORM	, 20	
BY		
(C	wner's Attorney)	

Legend

- (1) Correct name of contractor.
- (2) A corporation, a partnership, or an individual, as the case may be.
- (3) Correct name of surety.
- (4) Treasurer of the municipality or school administrative district, as the case may be.
- (5) Same date as that of contract.
- (6) Name of project as designated in the contract documents.

If the contractor is partnership, all partners should execute bond. A power of attorney document, together with a statement that it still is in full force and effect shall be provided by the person executing this bond.

SECTION 2-E

STATE OF MAINE CONSTRUCTION CONTRACT (Public School Project)

THIS AGREEMENT made the <u>date</u> of <u>month</u> in the year <u>2024</u> by and between the <u>York</u> <u>School Department</u> hereinafter called the *Owner*, and <u>Contractor company name</u> hereinafter called the <u>Contractor</u>.

WITNESSETH, That the *Owner* and the *Contractor* for the consideration hereinafter named agree as follows:

ARTICLE 1 SCOPE OF WORK

- § 1.1 The *Contractor* shall furnish all of the materials and perform all the work described in the specifications and shown on the drawings for the project entitled: *York Middle School Window Replacement Phase 2*.
- § 1.2 The specifications and the drawings have been prepared by <u>Harriman</u>, acting as Designer and named in the documents as the Architect or Engineer. This firm has responsibilities for defining the scope of work governed by their agreement with the *Owner*, the specifications and the drawings, and the General Conditions and Special Provisions of the contract.

ARTICLE 2 COMPLETION DATE

§ 2.1 The work to be performed under this contract shall be completed on or before <u>August</u> <u>19, 2024</u>. For each calendar day the project remains uncompleted \$750.00 shall be charged as liquidated damages.

ARTICLE 3 CONTRACT SUM

§ 3.1 The *Owner* shall pay the *Contractor* for the performance of the contract, subject to additions and deductions provided by approved Change Orders in current funds as follows: *amount in words* dollars and <u>00</u>cents, \$0.00

ARTICLE 4 CONTRACT BONDS

- § 4.1 Contract bonds are not required if the contract amount is less than \$100,000 unless bonds are specifically mandated by the contract documents.
- **§ 4.2** On this project, the *Contractor* **shall** furnish the *Owner* the appropriate contract bonds in the amount of 100% of the contract amount.

ARTICLE 5 PROGRESS PAYMENTS

§ 5.1 The *Owner* shall make payments on account of the contract as provided therein as follows: Each month 95% of the value, based on contract prices of labor and materials incorporated in the work and of materials suitably stored at the site thereof up to the first day of that month, as certified by the Architect or Engineer.

§ 5.2 The *Owner* may cause the *Contractor* to be paid such portion of the amount retained hereunder as he deems advisable.

ARTICLE 6 FINAL PAYMENT

§ 6.1 Final payment shall be due 60 days after completion and acceptance of the work, provided the *Contractor* has submitted evidence satisfactory to the *Owner* that all payrolls, material bills and other indebtedness connected with the work has been paid.

ARTICLE 7 CONTRACT DOCUMENTS

§ 7.1 The General Conditions of the contract, Special Provisions, the written specifications and the drawings, and any Addenda, together with this agreement, form the contract; they are as fully a part of the contract as if hereto attached or herein repeated.

§ 7.2 Specifications: date of issuance

§ 7.3 Drawings: each sheet number and title

§ 7.4 Addenda: each addenda number and date, or "none"

ARTICLE 8 OTHER PROVISIONS

§ 8.1 None

The *Owner* and the *Contractor* hereby agree to the full performance of the covenants herein.

IN WITNESS WHEREOF the parties hereby execute this agreement the day and year first above written.

OWNER	CONTRACTOR

(Signature) (Date)	(Signature) (Date)		
(Printed name and title)	(Printed name and title)		
York School Department			
(School Administrative Unit name)	(Contractor company name)		

SECTION 3-A

STATE OF MAINE

STANDARD GENERAL CONDITIONS AND CONTRACT WORK

For

PUBLIC SCHOOL PROJECTS

Revised 11-08-01 1 of 29

October 17, 1988

Rev. 12/21/92; 4/20/99, 11/08/01

ARTICLE	INDEX TO ARTICLES OF GENERAL CONDITIONS DESCRIPTION	PAGE
1	Definitions	4
2	Intent, Correlation and Execution of Documents	6
3	Detail, Drawings and Instructions	7
4	Copies Furnished	8
5	Shop Drawings	8
6	Drawings and Specifications	8
7	Ownership of Drawings	8
8	Samples	8
9	Materials, Appliance, Employees	9
10	Royalties and Patents	10
11	Surveys, Permits, Laws, Taxes and Regulations	10
12	Labor and Wages	11
13	Condition and Care of Site and Protection of Work	11
14	Inspection of Work	12
15	Superintendence: Supervision	13
16	Changes in the Work	13
17	Claims for Extra Cost	15
18	Deductions for Uncorrected Work	15
19	Delays and Extension of Time	15
20	Corrections of Work	16
21	Owner's Right to Do Work	16
22	Owner's Right to Terminate Contract	16
23	The Contractor's Right to Stop Work or Terminate	10
	Contract	17
24	Payments	17
25	Payments withheld	19
26	Contractor's Insurance Requirements	19
27	Contract Bonds	21
28	Damages	22
29	Liens	22
30	Assignment	23
31	Mutual Responsibility of Contractors	23
32	Separate Contracts	23
33	Subcontracts	23
34	Relations of Contractor and Sub-Contractors	24

Revised 11-08-01 2 of 30

ARTICLE	DESCRIPTION	PAGE
35	Designer's Status	25
36	Cash Allowance	25
37	Uses of Premises	26
38	Cutting, Patching, and Digging	26
39	Layout of Work	26
40	Workmanship	27
41	Cleaning Up	27
42	Dispute Resolution	28
43	Completion Time and Liquidated Damages	28

Revised 11-08-01 3 of 30

ARTICLE 1. **DEFINITIONS**

Whenever the following terms are used in these specifications or the contract, the intent and meaning shall be interpreted as follows:

<u>Designer</u>: The project Architect and/or Engineer whose name appears on the plans and/or specifications for the project, acting directly or through an authorized representative.

<u>Bid Security</u>: The security designated in the proposal, furnished by bidders as a guaranty of good faith to enter into a contract with the state, should a contract be awarded to that bidder.

<u>Bidder</u>: Any individual, partnership, or corporation submitting a proposal for the performance of the work described under the terms of the contract, acting directly or through a duly authorized representative.

Bureau: The Bureau of General Services.

<u>Calendar Days</u>: Consecutive days, as occurring on a calendar, taking into account the day of the week, month, year, and any religious, national or local holidays.

<u>Change Order</u>: A written agreement between the Owner and the Contractor, operating as a supplement to the contract, covering correction of: omissions, errors, and discrepancies between the plans and the proposal or estimates; or any alterations in the plans; or additional requirements; work, materials, and incidentals required to complete the construction of the project in an acceptable manner, and setting forth the basis of compensation for that supplemental work, if any. Before any change order modifies or becomes a part of the work, it must be duly signed by the Contractor, and the Owner, and approved by the Bureau of General Services and the Designer.

<u>Clerk of the Works</u>: The authorized representative of the Designer.

<u>Contract</u>: A written agreement between the Owner and the successful bidder, by which the Contractor is bound to perform the work specified, in accordance with plans, specifications, general conditions, and special provisions, that are a part of the contract documents, together with all supplemental agreements by which the Owner is bound to compensate the Contractor at mutually established and accepted rates or prices.

<u>Contract Bond</u>: The approved forms of security furnished by the Contractor and his surety, or sureties, which guarantee the faithful performance of all the terms of the contract and the payment of all bills, for labor, materials and equipment by the Contractor.

<u>Contract Documents</u>: The contract documents consist of the contract, general conditions, special provisions, the plans and specifications including all addenda, change orders, and all other modifications thereof, that were incorporated in the documents

Revised 11-08-01 4 of 30

subsequent to their execution.

<u>Contractor</u>: The individual, partnership, or corporation undertaking the execution of the general contract work under the terms of the contract with the Owner, acting directly or through a duly authorized representative.

<u>Director of the Bureau of General Services</u>: The State Director of the Bureau of General Services or his/her duly authorized representative.

<u>Final Completion:</u> The stage of the Work when the Work has been fully completed in accordance with the terms and conditions of the Contract Documents.

Owner: School Administrative Unit, acting through its duly authorized representative.

Owner's Representative:

<u>Plans</u>: All official drawings or reproductions of drawings pertaining to the work provided for in the contract and such working plans as may be furnished or approved by the Owner or Designer from time to time.

<u>Project</u>: The entire improvement proposed by the Owner to be constructed in part or in whole pursuant to these specifications and contract documents. Where the word "Job" appears it shall mean the project.

<u>Proposal or Bid</u>: The written offer of the bidder, on a form prescribed to perform the work specified.

<u>Provide</u>: The word "provide" shall mean, "furnish and install," including connections to services if required, unless specified otherwise.

<u>Sub-Contractor</u>: The individual, the firm or corporation undertaking the execution of any part of the work under the terms of the contract by virtue of a written agreement between itself and the Contractor.

<u>Substantial Completion:</u> The stage in the progress of the Work when the Work or designated portion thereof is sufficiently complete in accordance with the Contract Documents so the Owner can occupy or utilize the Work for its intended use. Minor corrections and repairs that can be performed while the Owner has occupied the building and without undue annoyance to personnel will be acceptable under the definition of Substantial Completion. It shall also include major final cleaning required under the Contract, removal of all surplus equipment and material not required for completion of remaining work, and the placement of remaining materials and equipment in convenient locations as approved by the Owner.

<u>Superintendent</u>: The representative of the Contractor, authorized by the Contractor to receive and fulfill instructions from the Designer.

Revised 11-08-01 5 of 30

<u>Supplemental Agreement</u>: A supplemental agreement is any agreement entered into between the Contractor and the Owner with the approval of the Bureau and the Designer subsequent to the execution of the contract.

<u>Surety</u>: The individual, partnership, or corporation who is bound jointly and severally with the Contractor and sub-Contractor to insure his faithful performance of the contract and for his payment of the bills for labor, materials and equipment by the Contractor and Sub-Contractors.

Work: See Project.

ARTICLE 2. INTENT, CORRELATION AND EXECUTION OF DOCUMENTS

The intent of the Contract Documents is to prescribe a complete work or improvement. The Plans, including all revisions, General Conditions for Contract Work, Special Provisions, Instructions to Bidders, Proposal, Contract, Contract Bonds, and all other sections of the specifications, including all addenda, all dated and on file in the Bureau of General Services, prior to the time set for receiving proposals as prepared by the Designer, shall each become a part of the Contract Documents, and all proposals must be based on a full compliance therewith. Any Supplemental Agreements entered into subsequent to the Contract will become a part of said Contract.

The contract documents are complementary, and what is called for by any one shall be as binding as if called for by all. The intention of the documents is that, unless otherwise specified, the Contractor shall furnish all labor, materials, equipment, items, articles, tools, transportation, insurance, services, necessary supplies, operations or methods and incidentals that may be reasonably required to construct and complete the project, facility or improvement in a manner necessary for the proper execution of the work. Any deviations from the plans which may be required by the exigencies of the construction, or because of error, will in all cases, be determined by the Designer, and authorized in writing subject to approval by the Owner and Bureau of General Services. Materials or work described in words, which so applied, have a well-known technical or trade meaning shall be held to refer to such recognized standards. Since the plans and specifications cover the dimensions and features of the work and do not set forth the analysis of the design, it is the duty of the Contractor fulfilling them to ascertain the true intent in any case where it is doubtful.

Work not covered under any heading, section, branch, class or trade of the specifications, shall not be supplied unless it is shown on the drawings or is reasonably inferable there from as being necessary to produce the intended results.

The Contractor shall take no advantage of any apparent error or omission in the plans and specifications, and the Designer shall be permitted to make such corrections and interpretations as may be deemed necessary for the fulfillment of the intent of the plans and specifications. Where errors or omissions appear in the contract documents, the Contractor shall promptly notify the Designer in writing of such errors or omissions. Inconsistencies in the contract documents are to be reported before proposals are received, whenever found.

Revised 11-08-01 6 of 30

Should the Drawings or the Specifications disagree in themselves or with each other, the Contractor shall provide the better quality or greater quantity of work and/or materials unless otherwise directed by written addendum to the Contract Documents.

The Contractor shall, upon his acceptance of a contract and before commencing work, contact the Designer and request a preconstruction conference. The purpose of this conference shall be as follows:

- 1. To introduce the members of the Designer's firm and the representative of the Owner and define their responsibilities in connection with this project.
- 2. To emphasize any special provisions applicable to the project.
- 3. To establish the work progress schedule and set up procedures for prompt review of all required shop drawings. If the Contract Sum exceeds \$ 10,000,000, the Contractor shall supply the Owner with the planned Critical Path Method ("CPM") schedule prior to the submission of the first payment requisition. The Contractor shall supply the Owner monthly with CPM "as built" schedule updates. The update shall include the dates of activities' start and completion; percent of work remaining for activities started but not completed; narrative report indicating a listing of monthly progress; any changes to critical path activities from the prior update; sources of delay and potential problems; and work planned for the next month. If any date is more than fifteen (15) days behind, the Contractor must submit a recovery schedule. When a Change Order is proposed, the Contractor must identify all schedule impacts which result from the Change Order.
- 4. To provide the Contractor with opportunity to discuss points of doubt and any apparent inconsistencies noted in the plans and specifications before proceeding to purchase material or execute the work.

During the further progress of work, regular meetings will be held at time intervals appropriate in the judgment of the Designer to review the work progress schedule, general project progress and any other questions, which might affect the execution of this contract.

ARTICLE 3: **DETAIL DRAWINGS AND INSTRUCTIONS**

The Designer shall furnish, with reasonable promptness, additional instructions by means of drawings or otherwise, that are necessary for the proper execution of the work. All such drawings and instruction shall be consistent with the contract documents, shall be true developments thereof, and shall be reasonably inferable there from.

The work shall be executed in conformity therewith and the Contractor shall do no work without proper drawings and instructions except as allowed by Article 13.

Revised 11-08-01 7 of 30

Immediately after being awarded the contract, the Contractor shall prepare an estimated progress schedule and submit same for Designer's approval. It shall indicate the dates for starting and completion of the various stages of construction.

ARTICLE 4: COPIES FURNISHED

Unless otherwise provided in the contract documents the Contractor will be furnished, free of charge, 10 copies of all drawings, and specifications.

ARTICLE 5: SHOP DRAWINGS

The Contractor shall check and verify all field measurements and shall submit with such promptness as to cause no delay in the Contractor's own work or in that of any other Contractor, adequate copies, checked and approved by the Contractors of all shop drawings and schedules required for the work of the various trades. The Designer shall check and approve, with reasonable promptness, such scheduled drawings only for conformance with the design concept of the project and compliance with the information given in the contract documents. The Contractor shall make any corrections required by the Designer, and shall file with the Designer two corrected copies, and shall furnish such other copies as may be needed. The Designers approval of such drawings or schedules shall not relieve the Contractor from responsibility for deviations from drawings or specifications, unless the Contractors have, in writing, called the Designer's attention to such deviations at the time of submission and secured the Designer's written approval; nor shall it relieve the Contractors from responsibility for errors in shop drawings or schedules.

ARTICLE 6: **DRAWINGS AND SPECIFICATIONS**

The Contractor shall keep, in good order, one copy of all drawings and specifications on the work, which will be made available to the Designer and to his representative.

ARTICLE 7: OWNERSHIP OF DRAWINGS

All drawings, specifications and copies thereof furnished by the Designer are the property of the Designer. They are not to be used on other work without written permission from the Designer, and, with the exception of the signed contract set, are to be returned to the Designer upon request, or at the completion of the work.

ARTICLE 8: SAMPLES

The Contractor shall furnish for review, with reasonable promptness, all samples as directed by the Designer. The Designer shall check and review such samples, with reasonable promptness, only for conformance with the design concept of the project and for compliance with the project and for compliance with the information given in the contract documents. The work shall be in accordance with reviewed samples.

Revised 11-08-01 8 of 30

ARTICLE 9: MATERIALS, APPLIANCE, EMPLOYEES

Unless otherwise stipulated, the Contractor shall provide and pay for all materials, labor, water, tools, equipment, light, power, transportation and facilities necessary for the execution and completion of the work.

Whenever an article or material is defined by describing a proprietary product, or by using the name of a manufacturer, the term "Or Approved Equal", if not inserted, shall be implied. The specific article or material mentioned shall be understood to establish minimum standards as to the type, function, standard of design, durability, efficiency and quality desired and shall not be construed to exclude other manufacturers' products of comparable quality, design and efficiency.

Materials and models of items, which the Contractor alleges to be equal to the materials and methods of items named in the specifications, shall be subject to the written approval by the Designer. If the alleged equals are to receive consideration in the bid award, written approval shall be received from the Designer at least ten days prior to the established bid opening dates. The use of alternate items will not be permitted without the approval of the Owner and Designer. All approved substitutions shall be in writing and approved by the Designer. The Contractor shall not be relieved of the responsibility to furnish articles or materials equal in quality, design and efficiency to those specified because of the approval of such alternate items by the Designer. The Designer's approval or rejection of a proposed substitution may be based on any of the previous considerations, and his decision may or may not express reasons for rejection and shall be final. Requests for substitutions shall originate and be submitted by the Contractor, not a Sub-Contractor. The materials or equipment shall be sufficiently described to enable the Designer to easily identify salient features.

Any material or products not specified in the bidding documents but being worthy of consideration may be introduced by the Contractor, or Sub-Contractor. The Contractor's submission shall include a cost comparison with the specified material and the reason for the suggested substitution. The basic proposal shall be as specified.

It shall be understood by the general Contractor or Sub-Contractor that the attached letter describing the proposed changes will not be used in determining the low general Contractor or Sub-Contractor proposal submitted, unless the general Contractor or Sub-Contractor has submitted its list to the Designer 10 days prior to the date set for the receipt of their respective proposals and has received written approval by the Designer five days prior to the opening of the bid.

The Contractor shall guarantee his work against any defects in workmanship and materials for a period of one year from the date of the written acceptance of the project.

Materials and equipment shall be new, free from defects, perfect and complete, unless otherwise stipulated. Materials or equipment specified or shown on the drawings shall be applied or installed according to the directions with the manufacturer, or the recommendations of an association dealing primarily with the material, unless specifically designated otherwise. The scope of the direction furnished shall include the application of

Revised 11-08-01 9 of 30

experienced personnel to each trade involved. In no case shall the installation be below the standard recommended by the manufacturer or association.

The Contractor shall be responsible to the Owner for the suitability of materials and equipment furnished and for full compliance with the specification.

The Contractor shall promptly pay all his employees when their pay is due, shall promptly pay when due all bills for materials, supplies and services going into the work, and all bills for insurance, workmen's compensation coverage, federal and state unemployment compensation, and Social Security charges applicable to said project.

Before final settlement is made, the Contractor shall furnish to the Owner affidavits that all said payments have been made.

The Contractor shall at all times enforce strict discipline and good order among his employees, and shall not employ on the work any unfit person or anyone not skilled in the work assigned to him.

ARTICLE 10: ROYALTIES AND PATENTS

The Contractor shall, for all time, secure to the Owner the free and undisputed right to the use of any and all patented articles or methods used in the work and shall defend at his own expense any and all suits for infringement or alleged infringement of such patents, and in the event of adverse award under patent suits, the Contractor shall pay such awards and hold the Owner harmless in connection with any patent suits that may arise as a result of installations made by the Contractor, or to any awards made thereunder.

ARTICLE 11: SURVEYS, PERMITS, LAWS, TAXES AND REGULATIONS

The Owner shall furnish all surveys unless otherwise specified.

Permits and licenses necessary for the prosecution of the work shall be secured and paid for by the Contractor. Easements for permanent structures or permanent changes in existing facilities shall be secured and paid for by the Owner, unless otherwise specified.

The Contractor shall give all notices and comply with all laws, ordinances, rules and regulations bearing on the conduct of the work as drawn and specified. If the Contractor observes that the drawings and specifications are at variance therewith, the Contractor shall promptly notify the Designer in writing and any necessary changes shall be adjusted as provided in the contract for changes in the work. If the Contractor performs any work knowing it to be contrary to such laws, ordinances, rules and regulations and without such notice to the Designer, the Contractor shall bear all costs arising there from.

Adherence to the Code of Federal Regulations 29 CFR Part 1926 and 29 CFR Part 1910 as adopted by the State Board of Occupational Safety and Health is required by statute.

Revised 11-08-01 10 of 30

The State is exempt from the payment of Federal Excise Taxes on articles not for resale and for the Federal Transportation Tax on all shipments. All quotes from the Contractor and Sub-Contractors shall be free of these taxes. The State is exempt from the payment of Maine State Sales and Use Taxes. All quotes from the Contractor and Sub- Contractors shall be free of these taxes.

In execution and performance of the Contract, the Contractor and all subcontractors agree to be aware of and to comply with the requirements and regulations of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et. seq.)

ARTICLE 12: LABOR AND WAGES

All Contractors and Sub-Contractors shall conform to the labor laws of the State of Maine, and all other laws, ordinances and legal requirements affecting the Work in Maine.

In the employment of laborers, preference shall first be given to residents of the State of Maine who are qualified to perform the work to which the employment relates, and if they cannot be obtained in sufficient numbers, then to citizens of the United States, who may reside in other states.

ARTICLE 13: CONDITIONS AND CARE OF SITE AND PROTECTION OF THE WORK

The Contractor shall continuously maintain adequate protection of all work from damage and shall protect the property from injury or loss for the duration of this contract, and shall make good any such damage, injury or loss. He shall adequately protect adjacent property as provided by law and the contract documents.

The Contractor shall take all necessary precautions for the safety of employees on the work, and shall comply with all applicable provisions of federal, state and municipal safety laws and building codes, and shall prevent accidents or injury to persons on, about or adjacent to the premises where the work is being performed. The Contractor shall erect and properly maintain all necessary safeguards for the protection of workmen and the public at all times, as required by the condition and progress of the work, and shall post danger signs warning against all hazards created by the construction process, such as (but not limited to) protruding nails, hoists, well holes, elevator hatchways, scaffolding, window openings, stairways and falling materials. The Contractor shall designate a responsible member of his organization on the work, whose duty shall be the prevention of accidents. The Contractor shall report the name and position of any person so designated to the Designer.

The Contractor shall return to conditions existing prior to the start of work on the project, all aspects of the site that have not been altered, removed, or otherwise changed permanently by the work. The Contractor shall protect all existing buildings, structures, or other features from damage by any operation in connection with the project. Utilities encountered shall be protected and maintained in service until removed or abandoned.

Revised 11-08-01 11 of 30

The Contractor shall exercise care in his work around such utilities as may be shown on the plot plan or otherwise found. Such utilities are not to be moved, replaced or abandoned.

The Contractor shall protect existing trees, and other aspects of the site, which will remain a permanent part of the site from damage during grading, excavation, filling, trucking, etc. If necessary, tree trunks shall be boxed, and barricades set up at sufficient distance to prevent damage to major tree branches.

Should the work or material of this or any other Contractor employed by the Owner become damaged when reasonably protected, the same shall be replaced by the Contractor causing the damage at no expense to the Owner.

In an emergency potentially affecting health or life or of serious damage to property or of adjoining property, the Contractor, without special instruction or authorization from the Designer or Owner, is hereby permitted to act on his own discretion, to prevent such threatened loss or injury, and the Contractor shall so act, without appeal, if so authorized or instructed. Any compensation claimed by the Contractor on account of emergency work, shall be determined by agreement.

ARTICLE 14: INSPECTION OF WORK

The Designer and his representatives, the Bureau of General Services representatives and the Owner, shall at all times have access to the work whenever it is in preparation or progress. The Contractor shall provide proper facilities for such access and for inspection.

If the specifications, the Designer's instructions, laws, ordinances or any public authority require any work to be specially tested or approved, the Contractor shall give the Designer timely notice of its readiness for observation by the Designer or inspection by another authority, and if the inspection is by another authority than the Designer, on the date fixed for such inspection, required certificates of inspection shall be secured by the Contractor. Observations by the Designer shall be promptly made, and where practicable, prior to work is covered or buried. If any work which will ultimately be covered, is covered prior to approval or consent of the Designer, it must, if requested by the Designer, be uncovered for examination at the Contractor's expense.

Re-examination of questioned work may be ordered by the Designer, and, if so ordered, the work must be uncovered by the Contractor. If such work were found in accordance with the contract documents, the Owner shall pay the cost of the reexamination and replacement. If such work were found not in accordance with the contract documents, the Contractor shall pay such cost, unless it is found that the defect in the work was caused by a Contractor employed as provided in Article 32, and in that event the Owner shall pay such cost.

Revised 11-08-01 12 of 30

The Bureau of General Services, through its representatives shall make periodic inspections of the work during the course of construction and make recommendations to the Designer, when employed. The Designer shall provide adequate inspection of materials, equipment, methods and changes in plans on all projects under his supervision.

ARTICLE 15: SUPERINTENDENCE: SUPERVISION

The Contractor shall have, during the progress of all work, a competent superintendent and any necessary assistants. The superintendent shall not be changed except with the consent of the Owner unless a superintendent proves to be unsatisfactory to the Contractor and ceases to be in his employ. The superintendent shall represent the Contractor and all directions given to the superintendent in the absence of the Contractor shall be as binding as if given directly to the Contractor. Important directions shall be confirmed in writing to the Contractor. Other directions shall be confirmed on written request in each case. The Designer shall not be responsible for the acts or omissions of the superintendent or his assistants.

The Contractor shall give efficient supervision to the work using his best skill and attention. He shall carefully study and compare all drawings, specifications and other instructions and shall at once report to the Designer any error, inconsistency or omission which he may discover, but he shall not be liable to the Owner for any damage resulting from any errors or deficiencies in the contract documents or other instructions by the Designer.

ARTICLE 16: CHANGES IN THE WORK

The Owner reserves the right to increase or decrease any or all of the items of work indicated in the plans, proposal, and contract, or the elimination of any one or more of such items, without invalidating the contract. As the work progresses, the Owner may make such alterations in the plans, in the character of the work, or in the specified coordination of two or more concurrent contracts, as may be considered necessary or desirable in order to complete the construction. Such changes shall in no way invalidate the contract. All such work shall be executed under the conditions of the original contract except that any claim for extension of the time caused thereby shall be adjusted at the time of the ordering of such change.

In giving instructions, the Designer shall have authority to make minor changes in the work, not involving extra cost, and not inconsistent with the purposes of the building or project, but otherwise, except in an emergency endangering life or property, no extra work or change shall be made unless in pursuance of a duly signed change order.

Should the Contractor encounter during the progress of the work, latent conditions at the site materially differing from those shown on the drawings or in the specifications, or unknown conditions of an unusual nature differing materially from those already encountered in such work, the attention of the Designer shall be immediately called for such conditions before they are disturbed. The Designer shall promptly investigate the conditions and if they do so materially differ, the contract shall, with the approval of the Owner and the Bureau be modified by a change order to provide for any increase or decrease in cost resulting from such conditions

Revised 11-08-01 13 of 30

Should such alterations be productive of increased unit cost, or result in decreased unit cost to the Contractor, a fair and equitable sum therefore shall be agreed upon in writing before such work is begun, and shall be added to or deducted from the contract amount, as the case may be, by means of a written change order. The change order shall state the nature of the change, the location, the itemized estimate of unit quantities, the basis for payment, and the reason for the change. Such change order to be on approved forms.

When the change order has been properly signed by all parties and encumbered, it shall become a part of the contract.

The value of any such extra work or change shall be determined in one or more of the following ways:

- A. By estimate and acceptance in a lump sum.
- B. By unit prices named in the contract or subsequently agreed upon.
- C. By cost and percentage or by cost and a fixed fee.

If none of the above methods is agreed upon, the Contractor, provided he receives an order as above, shall proceed with the work.

Under case (C.), he shall keep and present in such form as the Designer may direct, a correct account of the cost, together with vouchers. In any case, the Designer shall certify to the amount, including reasonable allowance for overhead and profit, due to the Contractor. Pending final determination of value, payments on account of changes shall be made on the Designer's certificate.

If the price of a change order cannot be agreed upon, nothing contained herein shall prevent the Designer, with approval from the Owner and BGS, from directing the Contractor to make a change in the work, with the price to be determined on either a cost and percentage basis or under the dispute resolution provision of this contract.

If the price of a change order cannot be agreed upon, an Owner and/or Designer initiated Construction Change Directive can order a change in the work prior to an agreement on the adjusted Contract Sum or Contract Time. The Cost of the work is to be determined by: 1) a cost and percentage basis 2) lump sum 3) unit prices or

4) under the Dispute Resolution provision of this contract.

When the subparagraphs (A) and (C) above are used to determine the value of the work, the allowance for overhead and profit combined, included in the total expense to the Owner, shall be based upon the following schedule:

For the Contractor, for any work performed by his own forces, 20% of the cost; For each Sub-Contractor, for work performed by his own forces, 20% of the cost; For the Contractor, for work performed by his Sub-Contractor, 10% of the amount due the Sub-Contractor.

Revised 11-08-01 14 of 30

Cost shall be limited to the following: Cost of materials, cost of delivery, cost of labor, including Social Security, old age and unemployment insurance (labor cost may include a pro ratio share of foremen's time, only in case an extension of contract time is granted on account of the change); workmen's compensation insurance; rental value of power tools and equipment.

Overhead shall include the following; bond premium, supervision, wages of timekeepers, watchmen and clerks, small tools, incidental, general office expense, and all other expenses not included in "cost".

If the net value of a change results in a credit from the Contractor or Sub- Contractor the credit given shall be the net cost without overhead or profit. The cost as used herein shall include all items of labor, materials and equipment.

ARTICLE 17: CLAIMS FOR EXTRA COST

If the Contractor claims that any instructions by drawings or otherwise involve extra cost under this contract, he shall give the Designer written notice thereof within 10 days after the receipt of such instructions, and in any event before proceeding to execute the work, except in emergency endangering life or property, and the procedure shall then be as provided for in Section 16, "changes in work." No such claim shall be valid unless so made.

ARTICLE 18: DEDUCTIONS FOR UNCORRECTED WORK

If the Designer and Owner deem it inexpedient to correct work injured or done not in accordance with the contract, an equitable deduction from the contract amount shall be made therefore.

ARTICLE 19: DELAYS AND EXTENSION OF TIME

If the Contractor is delayed at any time in the progress of the work by any act or neglect of the Owner or the Designer, or of any employee of either, or by any separate Contractor employed by the Owner, or by changes ordered in the work or by strikes, lockouts, fire, unusual delay in transportation, unavoidable casualties Or by causes beyond the Contractor's control, or by any cause which the Designer shall decide to justify the delay, then the time of completion shall be extended for such reasonable time as the Designer may decide. Inclement weather or other natural causes shall not be reason to allow additional time under this contract.

No such extension shall be made for delay occurring more than seven days before claim therefore is made in writing to the Designer. In case of a continuing cause of delay, only one claim is necessary.

If no schedule or agreement stating the dates upon which drawings shall be furnished is made, then no claim for delay shall be allowed on account of failure to furnish drawings until two weeks after demand for such drawings and not then unless such claim be

Revised 11-08-01 15 of 30

reasonable.

This article does not exclude the recovery of damages for delay by either party under other provisions in the contract document. The amount of Contractor's delay damages shall be limited to the Costs, overhead and profit items enumerated in Article 16. Recovery of delay damages is conditioned upon compliance with the notice requirements of Article 17.

ARTICLE 20: CORRECTION OF WORK

The Contractor shall promptly remove from the premises all work condemned by the Designer as failing to conform to the contract, whether incorporated or not, and the Contractor shall promptly replace and re-execute his own work in accordance with the contract and without expense to the Owner and shall bear the expense of making good all work of other Contractors destroyed or damaged by such removal or replacement.

If the Contractor does not remove such condemned work within a reasonable time, fixed by written notice, the Owner may remove it and may store the material at the expense of the Contractor. If the Contractor does not pay the expenses of such removal within ten days time, thereafter, the Owner may, upon ten days written notice, sell such materials at auction or at private sale and shall account for the net proceeds thereof, after deducting all the costs and expenses that should have been borne by the Contractor.

The Contractor shall remedy any defects due to faulty materials or workmanship and pay for any damage to other work resulting therefrom, which shall appear within a period of one year from the date of final payment, or from the date of the Owner's substantial usage or occupancy of the project, whichever is earlier, and in accordance with the terms of any special guarantees provided in the contract. The Owner shall give notice of observed defects with reasonable promptness. All questions arising under this article will be decided by the Designer, notwithstanding final payment.

ARTICLE 21: OWNER'S RIGHT TO DO WORK

If the Contractor should neglect to prosecute the work properly or fail to perform any provisions of this contract, the Owner, after three days written notice to the Contractor may, without prejudice to any other remedy may make good such deficiencies

and may deduct the cost thereof from the payment; then or thereafter due the Contractor, provided, however, that the Designer shall approve both such action and the amount charged to the Contractor.

ARTICLE 22: OWNER'S RIGHT TO TERMINATE CONTRACT

If the Contractor should be adjudged bankrupt, or if the Contractor should make a general assignment for the benefit of it's creditors, or if a receiver should be appointed on of account the Contractor's insolvency, or if the Contractor should persistently or repeatedly

Revised 11-08-01 16 of 30

refuse or should fail, except in cases for which extension of time is provided, to supply enough properly skilled workmen or proper materials or if the Contractor should fail to make prompt payment to Sub-Contractors or for material, or labor, or persistently disregard laws, ordinance or the instructions of the Designer, or otherwise be guilty of a substantial violation of any provision of the contract, then the Owner, upon the certificate of the Designer that sufficient cause exists to justify such action, may without prejudice to any other right or remedy and after giving the Contractor and the Contractor's surety seven days written notice, terminate the employment of the Contractor and take possession of the premises and of all materials, tools and appliances thereon and finish the work by whatever method the Owner may deem expedient. In such case the Contractor shall not be entitled to receive any further payment until the work is finished. If the unpaid balance of the contract amount shall exceed the expense of finishing the work including compensation for additional Designer, managerial and administrative services, such excess shall be paid to the Contractor. If such expense shall exceed such unpaid balance, the Contractor shall pay the difference to the Owner. The expense incurred through the Contractor's default, shall be certified by the Designer.

ARTICLE 23: THE CONTRACTOR'S RIGHT TO STOP WORK OR TERMINATE CONTRACT

If the work should be stopped under an order of any court, or other public authority, for a period of thirty days, through no act or fault of the Contractor or of anyone employed by him, then the Contractor, may, upon seven days written notice to the Owner and the Designer, terminate this contract and recover from the Owner, payment for all work executed and any proven loss sustained upon any plant or materials and reasonable profit and damage.

Should the Designer fail to issue any certificate for payment, through no fault of the Contractor, within seven days after the Contractor's formal request for payment or if the Owner should fail to pay to the Contractor within 30 days after presentation, any sum certified by the Designer, then the Contractor may, upon seven days' written notice to the Owner and the Designer, stop the work or terminate this Contractor as set out in the preceding paragraph.

ARTICLE 24: PAYMENTS

The Contractor shall, before the first application for payment, submit to the Designer in triplicate a "contract cost breakdown" form acceptable to the Designer, if required, this form shall be supported by such evidence as to its correctness as the Designer may direct and, shall be reviewed by the Designer and unless found to be in error, used as a basis for payments.

The Contractor shall submit to the Designer an application for each payment on the latest revision of the BGS "Requisition for payment" form, and, if required, receipts or other vouchers, showing his payments of materials and labor, including payments to sub-Contractors as required by Article 34.

Revised 11-08-01 17 of 30

Application for payment as the Work progresses may be made of the Owner but no more often than once a month, unless due to unusual circumstance the Owner may approve more frequent payment. Said requisition for payments shall be based on the proportionate quantities of the various classes of work completed or incorporated in the Work, in accordance with the Work progress schedule and the value thereof determined from the contract cost breakdown. Payments, upon authorization of the Designer, may be made on account of materials not incorporated in the Work but delivered and suitably stored at the site. Such payments shall be conditioned upon submission by the Contractor of bills of sale, or such other procedure as will adequately protect the Owner's interest including applicable insurance.

In the event any materials are delivered but not yet incorporated in the Work, have been included in any said "Requisition for Payment" and payment thereon made and said materials thereafter deteriorate, become damaged or destroyed or for any reason whatsoever become unsuitable or unavailable for use in the Work, then the full amount allowed therefore in any previous "Requisition for Payment", shall be deducted from the gross value of any subsequent payment or final payment unless the Contractor shall satisfactorily replace said material.

After said "Requisition for Payment" has been prepared by the Contractor in the required number of copies, it shall be submitted to the Designer for review. The Designer shall verify and approve the "Requisition for Payment", and forward all copies to the Owner for processing for payment by the Owner.

No certificate issued nor payment made to the Contractor, nor partial or entire use or occupancy of the Work by the Owner, shall be an acceptance of any Work or materials not in accordance with this contract. Except for those claims previously made by either party and still unsettled, the making and acceptance of the final payment shall constitute a waiver of all claims by the Owner, other than those arising form unsettled liens, those not complying with the requirements of the plans and specifications, those covered by warranties, and of all claims by the Contractor.

Title 5 M.R.S.A. Section 1746 as amended provides that in any contract awarded for any public improvement, the State shall withhold 5% of the money due the Contractor until the project under the contract has been accepted by or for the State, except that when the contract has been *substantially completed* the State may, upon request, further reduce the amounts withheld if it deems it desirable and prudent, or except when the Contractor elects to deposit with the Treasurer of the State certain Government Bonds as provided in Chapter 437, Public Laws of 1967.

With each monthly requisition the Contractor shall release and indemnify the owner from and against all liens on the project through the requisition date and shall supply partial lien waivers from all subcontractors through the date of the prior requisition.

All payments to be made in accordance with Title 10 MRSA Chapter 201-A "An Act to Ensure Prompt and Equitable Payment for Construction Services".

Revised 11-08-01 18 of 30

ARTICLE 25. PAYMENTS WITHHELD

The Designer may withhold or, on account of subsequently discovered evidence, nullify the whole or a part of any certificate to such extent as may be necessary in his reasonable opinion to protect the Owner from loss on account of:

- A. Defective work not remedied.
- B. Claims filed or reasonable evidence indicating probable filing of claims
- C. Failure of the Contractor to make payments properly to Sub-Contractors for materials or labor.
- D. A reasonable doubt that the contract can be completed for the balance then unpaid.
- E. Damage to another Contractor.
- F. Damage to the premises or Work.
- G. Failure to carry out the Work in accordance with the Contract Documents.

When the above grounds are removed, payments shall be made for amounts withheld because of them.

ARTICLE 26. CONTRACTOR'S INSURANCE REQUIREMENTS

The Contractor shall not commence work under this contract until the Contractor has obtained all insurance required under this article and such insurance has been approved by the Owner, nor shall the Contractor allow any Sub-Contractor to commence work on a subcontract until all similar insurance required of the Sub-Contractor has been so obtained and approved.

The State and the Owner does not warrant or represent that the insurance required under this paragraph constitutes an insurance portfolio which adequately addresses all risks faced by the Contractor or its Sub-Contractors. The Contractor and Sub-Contractors of every tier shall satisfy themselves as to the existence, extent and adequacy of insurance prior to commencement of work.

The Contractor and any Sub-Contractor shall procure and maintain for the duration of the Project insurance of the types and limits set forth under this paragraph and such insurance as will protect themselves from claims which may arise out of or result from the Contractor's or Sub-Contractor's execution of the work, whether such execution be by themselves or by anyone directly or indirectly employed by any of them or by anyone for whose acts any of them may be liable. The insurance coverage provided by the Contractor and any Sub-Contractor will be primary coverage. All required insurance coverages shall be placed with carriers authorized to conduct business in the State of Maine by the Maine Bureau of Insurance.

Revised 11-08-01 19 of 30

A. Workers' Compensation Insurance

Worker's compensation insurance for all employees on site in accordance with the statutory workers' compensation law of the State of Maine.

Minimum acceptable limits for Employer's Liability are:

Bodily Injury By Accident \$500,000

Bodily Injury by Disease \$500,000 Each Employee Bodily Injury by Disease \$500,000 Policy Limit.

B. Liability Insurance

1. General Liability Insurance

General liability insurance shall be on a form providing coverage not less than that of the 1996 occurrence version of the Insurance Services Office (ISO) Commercial General Liability Policy. This insurance shall cover bodily injury and property damage liability for all hazards of the Project including premise and operations, products and completed operations, contractual, and personal injury liabilities. It shall include collapse and underground coverage - as well as explosion coverage if explosion hazards exist.

Aggregate limits shall apply on a per location or project basis.

Minimum acceptable limits are:

General aggregate limit: \$2,000,000
Products and completed operations \$1,000,000
Each occurrence limit: \$1,000,000
Personal injury aggregate: \$1,000,000

2. Automobile Liability Insurance

Automobile liability insurance against claims for bodily injury, death or property damage resulting from the maintenance, Ownership or use of all owned, nonowned and hired automobiles, trucks and trailers.

Minimum acceptable limit is \$1,000,000 any one accident or loss.

3. Owners Protective Liability

For Contracts exceeding \$50,000 in total Contract amount, Contractor shall secure an Owners Protective Liability policy naming the Owner as the Named Insured.

Minimum acceptable limits are:

General aggregate limit: \$2,000,000 Each occurrence limit: \$1,000,000

4. Pollution Liability

In the event that any disruption, handling, abatement, remediation, encapsulation, removal, transport, or disposal of contaminated or hazardous material is required, the

Revised 11-08-01 20 of 30

Contractor or its Sub-Contractor shall secure a pollution liability policy in addition to any other coverages contained in this section. The insurance shall be provided on an occurrence based policy and shall remain in effect for the duration of the Project.

Minimum acceptable limit is \$1,000,000 per occurrence.

C. Property Insurance

Unless otherwise waived in writing by the Owner, the Contractor shall procure and maintain Builder's Risk insurance naming the Owner, Contractor and any Sub-Contractor as insureds as their interest may appear. Covered causes of loss form shall be all Risks of Direct Physical Loss, endorsed to include flood, earthquake, transit and sprinkler leakage where sprinkler coverage is applicable. Unless specifically authorized in writing by the Owner, the limit of insurance shall not be less than the initial contract amount and coverage shall apply during the entire contract period and until the work is accepted by the Owner.

D. Certificates of Insurance

Four original copies of all certificates of insurance in a form and issued by companies acceptable to the Owner shall be provided to the Designer prior to commencement of work. The certificates shall name the Owner as certificate holder and shall contain a provision that coverage afforded under the insurance policies will not be canceled or materially changed unless at least thirty (30) days prior written notice by registered letter has been given to the Owner.

ARTICLE 27: CONTRACT BONDS

The Contractor shall furnish to the Owner and State upon execution of the contract, a contract performance bond and a contract payment bond; each for the full amount of the contract and issued by a surety company or surety companies authorized to do business in the State of Maine as approved by the Owner and State. The bonds shall be in accordance with and executed on the forms furnished in the specifications. The bonds shall allow for any addition or deductions to the contract.

The contract bonds shall continue in effect for the applicable periods limiting actions as provided by, as applicable, 14 MRSA Section 871 or Section 752 to protect the Owner's interest and to assure settlement of claims for the payment of all bills for labor, materials, and equipment by the Contractor.

The Contractor shall submit to the Bureau of General Services through the Designer, copies of the Contract Performance Bond and Contract Payment Bond for each of the Filed Sub-Bid Subcontractors that were required to submit Bid Bonds.

Revised 11-08-01 21 of 30

ARTICLE 28: DAMAGES

- 1. The Contractor shall indemnify and hold harmless the Owner and the Designer and their agents and employees from and against all claims, damages, losses, and expenses including attorneys' fees arising out of or resulting from the performance of the work, provided that any such claim, damage, loss, or expense (a) is attributable to bodily injury sickness, disease or death, or injury to or destruction to tangible property (other than the work itself) including the loss of use resulting therefrom, and (b) is caused in whole or in part by a negligent act or omission of the Contractor, any Sub-Contractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, regardless of whether or not it is caused in part by a party indemnified hereunder.
- 2. In any and all claims against the Owner or the Designer or any of their agents or employees, by any employee of the Contractor, any Sub-Contractor, anyone directly or indirectly employed by any of them, or anyone for whose acts any of them may be liable, the indemnification obligation under paragraph 1 shall not be limited in any way by any limitation on the amount or type of damages, compensation, or benefits payable by or for the Contractor or any Sub-Contractor under Workmen's Compensation Acts, disability benefit acts, or other employee benefit acts.
- 3. The obligations of the Contractor under paragraph 1 shall not exceed the liability of the Designer, the Designer's agents or employees arising out of:
 - (a) The preparation or approval of maps, drawings, opinions, reports, surveys, change orders, designs or specifications; or
 - (b) The giving of or the failure to give directions or instructions by the Designer, the Contractor, agents or employees provided such giving or failure to give is the primary cause of the injury or damage.

ARTICLE 29: LIENS

Neither the final payment nor any part of the retained percentage shall become due until the Contractor, shall deliver to the Owner a complete release of all liens arising out of this contract, or receipts in full in lieu thereof, and, an affidavit that so far as the Contractor has knowledge or information the releases and receipts include all the labor and material for which a lien could be filed; but the Contractor, may if any Sub- Contractor refuses to furnish a release or receipt in full, furnish a bond satisfactory to the Owner, to indemnify him against any lien. If any lien remains unsatisfied after all the payments are made, the Contractor shall refund to the Owner all moneys that the latter may be compelled to pay in discharging such lien, including all cost and reasonable attorney's fee.

Revised 11-08-01 22 of 30

ARTICLE 30: ASSIGNMENT

Neither party to the contract shall assign the Contractor or sublet it as a whole without the written consent of the other, nor shall the Contractor assign any money due or to become due to him hereunder, without the previous written consent of the Owner.

ARTICLE 31: MUTUAL RESPONSIBILITY OF CONTRACTORS

Should the Contractor cause damage to any separate Contractor on the work, the Contractor agrees, upon due notice, to settle with such Contractor by agreement or arbitration, if he will so settle. If such separate Contractor sues the Owner or Designer on account of any damage alleged to have been so sustained, the Owner or Designer shall notify the Contractor, who shall defend such proceedings at the Contractor's expense and if any judgment against the Owner or Designer arises therefrom, the Contractor shall pay or satisfy it and pay all costs incurred by the Owner or Designer.

ARTICLE 32: SEPARATE CONTRACTS

The Owner reserves the right to let other contracts in connection with this work under similar general conditions. The Contractor shall afford other Contractors reasonable opportunity for the introduction and storage of their materials and the execution of their work, and shall properly connect and coordinate his work with theirs.

If any part of the Contractor's work depends on proper execution or results upon the work of any other Contractor, the Contractor shall inspect and promptly report to the Designer any defects in such work that render it unsuitable for such proper execution and results. The Contractor's failure so to inspect and report shall constitute an acceptance of the other Contractor's work as fit and proper for the reception of his work, except as to defects which may develop in Contractor's work after the execution of the Contractor's work.

To insure the proper execution of the Contractor's subsequent work the Contractor shall measure work already in place and shall at once report to the Designer any discrepancy between the executed work and the drawings.

ARTICLE 33: SUBCONTRACTS

The Contractor shall not sublet any part of this contract without the written permission of the Owner.

The Contractor shall submit in writing to the Designer for approval a complete list of the names of all particular items of work he proposes to furnish and the names of the Sub-Contractors to whom the Contractor proposes to sublet work. The Sub-Contractors named shall be reputable firms of recognized standings with a record of satisfactory work. The Contractor shall not employ any Sub-Contractor or use any material that requires approval by any Specification Section until they have been approved, or where there is reason to believe the work will not be accomplished in accordance with the contract documents. The complete list of Sub-Contractors and materials must be submitted for approval to the Designer and

Revised 11-08-01 23 of 30

Owner.

The Designer shall, on request, furnish to any Sub-Contractor, wherever practicable, evidence of the amounts certified on his account.

The Contractor agrees that he is as fully responsible to the Owner for the acts and omissions of his Sub-Contractor and of persons either directly or indirectly employed by them, as he is for the acts and omissions of persons directly employed by him.

Nothing contained in the contract documents shall create any contractual relation between any Sub-Contractor and the Owner.

ARTICLE 34: RELATIONS OF CONTRACTOR AND SUB-CONTRACTOR

The Contractor agrees to bind every Sub-Contractor and every Sub-Contractor agrees to be bound by the terms of the contract documents, as far as they are applicable to his work, including the following provisions of this article, unless specifically noted to the contrary in a subcontract approved in writing as adequate by the Owner or Designer.

The Sub-Contractor agrees:

- A. To be bound to the Contractor by the terms of the contract documents, and to assume toward the Contractor all the obligations and responsibilities that the Contractor, by those documents, assumes toward the Owner.
- B. To submit to the Contractor applications for payment in such reasonable time as to enable the Contractor to apply for payment as specified.
- C. To make all claims for extras, for extensions of time and for damages for delays or otherwise, to the Contractor in the manner provided in the general conditions for like claims by the Contractor upon the Owner, except that the time for making claims for extra cost is one week.

The Contractor agrees:

- D. To be bound to the Sub-Contractor by all the obligations that the Owner assumes to the Contractor under the contract documents, and by all the provisions thereof affirming remedies and redress to the Contractor from the Owner.
- E. To pay the Sub-Contractor, upon the payment of certificates, the amount allowed to the Contractor on account of the Sub-Contractor's work to the extent of the Sub-Contractor's interest therein.
- F. To pay the Sub-Contractor, upon the payment of certificates, if issued otherwise as in section E above, so that at all times the Sub-Contractor's total payments shall be as large in proportion to the value of the work done by the Sub-

Revised 11-08-01 24 of 30

Contractor.

- G. To pay the Sub-Contractor to such extent as may be provided by the contract Documents or the subcontract, if either of these provide for earlier or larger payments than the above.
- H. To pay the Sub-Contractor on demand for subcontract work or materials as far as executed and fixed in place, less the retained percentage, at the time the certificate should issue, even though the Designer fails to issue it for any cause not the fault of the Sub-Contractor.
- I. To make no demand for liquidated damages or penalty for delay in any sum in excess of such amount as may be specifically named in the subcontract.
- J. That no claim for services rendered or materials furnished by the Contractor to the Sub-Contractor shall be valid unless written notice thereof is given by the Contractor to the Sub-Contractor during the first ten days of the calendar month following that in which the claim originated.
- K. To give the Sub-Contractor an opportunity to present and to submit evidence in any progress conference or disputes involving subcontract work.
- L. To pay the Sub-Contractor a just share of any fire insurance money received by him, the Contractor, under Article 26 of the General Conditions.

ARTICLE 35: DESIGNER'S STATUS

The Designer shall be the Owner's representative during the construction period and he shall observe the work in progress on behalf of the Owner. He shall have authority to act on behalf of the Owner only to the extent expressly provided in the contract documents or otherwise in writing, which shall be shown to the Contractor. He shall have authority to stop the work whenever such stoppage may be necessary in his reasonable opinion to insure the proper execution of the contract.

The Designer shall be, in the first instance, the interpreter of the conditions of the contract and the judge of its performance. The Designer shall side neither with the Owner nor with the Contractor, but shall use the Designer's powers under the contract to enforce its faithful performance by both.

In case of the termination of the employment of the Designer, the Owner shall appoint a capable and reputable Designer whose status under the contract shall be that of the former Designer.

ARTICLE 36: CASH ALLOWANCES

The Contractor shall include the contract sum and all allowances named in the contract documents and shall cause the work so covered to be done by such Contractors and for such

Revised 11-08-01 25 of 30

sums as the Designer may direct, the contract amount being adjusted in conformity therewith. The Contractor declares that the contract amount includes such sums for expenses and profit on account of cash allowances, as he deems proper. No demand for expenses or profit other than those included in the contract shall be allowed. The Contractor shall not be required to employ for any such work, persons against whom the Contractor has a reasonable objection.

ARTICLE 37: USES OF PREMISES

The Contractor shall confine his apparatus; the storage of materials and the operations of his workmen to limits indicated by law, ordinances, permits or directions of the Designer, and as required by the Contract Documents, and shall not unreasonably encumber the premises with his materials.

The Contractor shall not load or permit any part of the structure to be loaded with a weight which will endanger its safety. The Contractor shall enforce the Designer's instructions regarding signs, advertisements, fires, and smoking.

If any part of the building is completed and ready for occupancy, the Owner may, by written and mutual consent, without prejudice to any of the Owner's rights or the rights of the Contractor enter in and make use of such completed parts of the building. Such use or occupancy shall in no case be construed as an acceptance of any work or materials.

ARTICLE 38: CUTTING, PATCHING AND DIGGING

The Contractor shall do all cutting, fitting or patching of his work that may be required to make its several parts come together properly and fit it to receive or be received by work of other Contractors shown upon, or reasonable implied by, the drawings and specifications for the completed structure, and he shall make good after them as the Designer may direct.

Any cost caused by defective or ill-timed work shall be borne by the party responsible therefore. The Contractor shall not endanger any work by cutting, excavating or otherwise, and shall not cut or alter the work of any other Contractor save with the consent of the Designer. Cutting, drilling, or patching work of Contractors other than the general Contractor shall be done only with the permission and instruction of the general Contractor and Designer. Cutting of structural members must be approved by the Designer. All cutting, patching, and digging of other Contractors in or about the building shall be done under the supervision of the general Contractor who shall be responsible to see that the work is neatly done, and in a manner that will not endanger the structure or harm the component parts, and that patching and back filling shall be done to restore the structure and surfaces to its original condition.

ARTICLE 39: LAYOUT OF WORK

The Contractor shall be responsible for the correct staking out of the new work on the site, and shall employ a competent engineer/surveyor to locate the building on the site. He shall run the axis lines locating the work, establish correct datum points, and check each line

Revised 11-08-01 26 of 30

and point on the site to insure their correctness. All such lines and points shall be carefully preserved throughout the construction.

The Contractor shall lay out all work from dimensions given on plans. The Contractor shall take measurements and verify dimensions of existing or old work, if any, that affect his work or to which his work is to be fitted. The Contractor alone shall be responsible for the correctness of all measurements and shall verify all grades, lines, levels, elevations and dimensions shown on the drawings and report any errors or inconsistencies to the Designer prior to commencing work.

ARTICLE 40: WORKMANSHIP

All workmanship, materials or equipment, either at the site or intended for it shall conform with all respects with the requirements of all the contract documents, and shall be strictly first class, workmanlike installation and the best obtainable from the crafts and trades. Incomplete or careless workmanship will not be allowed. In all cases the materials, equipment and work shall be equal to or better than the grade specified and the best of their kind that is obtainable for the purpose for which they are intended. The Designer's decision on the quality of work shall be final.

All labor shall be performed by mechanics skilled in their respective trades. Prior to submitting a proposal, the Contractor shall become familiar with the local labor conditions, skilled and unskilled.

If, in the opinion of the Contractor, any work is indicated on the drawings or specified in such manner as would make it impossible to produce work of the highest quality, or should discrepancies appear between drawings, or drawings and specifications, the Contractor shall refer the same in writing to the Designer for interpretation before proceeding with the work.

If the Contractor fails to make such reference, no excuse will be entertained thereafter for failure to carry out the work in the satisfactory manner.

The Contractor shall guarantee the Contractor's work against any defects in workmanship and materials for a period of one year from the date of the written final acceptance of the project.

ARTICLE 41: CLEANING UP

The Contractor shall at all times keep the premises free from accumulation of waste materials or rubbish caused by his employees or work, and at the completion of the work he shall remove all his rubbish from and about the building and all his tools, scaffolding and surplus materials and shall leave his work "Broom Clean" or its equivalent, unless more exactly specified.

In case of failure to comply by the Contractor, the Owner may perform the cleanup and deduct the cost from any monies due the Contractor.

Revised 11-08-01 27 of 30

ARTICLE 42: DISPUTE RESOLUTION

If, in the performance of this contract, there arises a dispute between the Contractor and the Owner that cannot be resolved by the parties to the contract, the dispute shall be referred to the Director of the Bureau of General Services who, at his/her discretion, will submit the dispute to non-binding Alternate Dispute Resolution (ADR) or binding arbitration. If the parties in dispute are not satisfied with the results of ADR the Owner or the Contractor may resubmit the dispute to the Director of the Bureau of General Services for binding arbitration.

In any non-binding Alternative Dispute Resolution (ADR) or binding arbitration between the Owner and the Contractor, the Owner may elect to consolidate related claims between the Owner and the Designer. Any mediator and/or arbitrator shall be subject to the mutual approval of the Owner, the Contractor and, as applicable, the Designer, such approval not to be unreasonably withheld by any party.

ARTICLE 43: COMPLETION TIME AND LIQUIDATED DAMAGES

a) The Date(s) of Completion is stated in the Proposal Form Section 2-B and in the Contract Form Section 2-E. If the Contractor finds it impossible to complete the Work on or before the said Date(s) of Completion, he make a written request to the Owner for an Extension of Time setting forth therein the reasons for the request. If the Owner finds that the Work was delayed because of conditions beyond the control and without the fault of the Contractor he may extend the Date(s) of Completion which will then be in full force and effect, the same as though it was the original Date(s) of Completion. b) Time is an essential element of the Contract and it is important the Work be pressed vigorously to Completion. The cost to the Owner of Administration of the Contract, inspection and supervision will be increased as the time occupied in the Work, is lengthened. c) For each calendar day that the Work shall remain uncompleted after the Date(s) of Completion specified in the Contract, the amount per day, listed below in the Schedule of Liquidated damages, shall be deducted from any money due the Contractor, not as a penalty but as liquidated damages, provided, however that due account shall be taken of any adjustment of the Date(s) of Completion granted under the provisions of Paragraph (a) above. d) The Contractor shall expressly be prohibited from filing delay claims or attempting to recover damages for its scheduled early completion. The Owner and Designer have not requested accelerated schedules and cannot accommodate the Contractor if he chooses to accelerate the Work. The Owner and Designer have designed the Project to be done in an orderly fashion which allows for bad weather, minor changes in the Work, and an orderly submittal and review process of materials and workmanship. Any Contractor choosing to bid the project with accelerated completions, earlier than those allowed by the phasing plan, has a duty to inform the project owner of the Contractor's intention to achieve early completion and he shall also note early completion as a qualification on his bid form. The Owner reserves the right to reject all bids containing limitations or qualifications.

Revised 11-08-01 28 of 30

SCHEDULE OF LIQUIDATED DAMAGES

<u>Damages</u>		Amount of Liquidated	
		<u>Per Day</u>	
Original Contract Amount			
More than	\$ 100,000 and less than \$ 3,000,000	\$ 750.00	
More than	\$ 3,000,000 and less than \$ 7,000,000	\$ 1000.00	
More than	\$ 7,000,000 and less than \$ 10,000,000	\$ 1500.00	
More than	\$ 10,000,000	\$ 1500.00 plus \$ 150 per \$ 1,000,000	

Revised 11-08-01 29 of 30

This Page Left Intentionally Blank

Revised 11-08-01 30 of 30

3-B - SUPPLEMENTARY CONDITIONS

These Supplementary Conditions supplement and, as applicable, amend The State of Maine Standard General Conditions and Contract Work for Public School Projects (the "General Conditions").

- 1. The parties recognize that the Project is locally funded, and that the role of the Bureau of General Services for locally funded projects is primarily advisory. Accordingly, notwithstanding anything to the contrary in the contract documents, submission to or review or approval by the Bureau of General Services shall not be required, except to the extent such submission, review or approval is required by state law or regulation for locally funded school construction projects. Furthermore, wherever used in the contract documents, "Bureau" and "Bureau of General Services" shall mean the Owner, unless the specific provision of the contract documents is in fulfillment of a state law or regulation that must be complied with in the case of a locally funded school construction project.
- 2. Revise the sixth paragraph of ARTICLE 9 to read "The Contractor warrants and guarantees his work against any defects in workmanship and materials for a period of one year from the date of the written acceptance of the project.
- 3. Revise last sentence in the first paragraph of Article 19 to read "Inclement weather or other natural causes shall not be reason to allow additional time under this contract, with the exception of tornado, earthquake, flood, or similar event that causes catastrophic damage and delay."
- 4. The release of liens required by Article 24, Payments, of the General Conditions shall be in the form of Exhibit A and Exhibit B to these Supplementary Conditions. Final lien waiver and accompanying affidavit required by Article 29, Liens, shall be substantially in the form of AIA Documents G706 and G706A and shall be accompanied by final releases of lien for each subcontractor and supplier as specified therein. Final releases for each Phase shall be submitted by the Contractor upon final completion of each of Phase 1 and of Phase 2, respectively.
- 5. ARTICLE 26: CONTRACTOR'S INSURANCE REQUIREMENTS, Paragraphs A, B, C and D are deleted in their entirety and replaced with the following:

"A. Workers' Compensation Insurance

Worker's compensation insurance for all employees on site in accordance with the statutory workers' compensation law of the State of Maine. (Provide Owner as Additional Insured and Waiver of Subrogation endorsements if available from the insurance carrier)

Minimum acceptable limits for Employer's Liability are:

Bodily Injury By Accident \$500,000

Bodily Injury by Disease \$500,000 Each Employee Bodily Injury by Disease \$500,000 Policy Limit.

B. Liability Insurance

1. General Liability Insurance

General liability insurance shall be on a form providing coverage not less than that of the Insurance Services Office (ISO) Commercial General Liability Policy, CG 00 01 12 04, Endorsements: CG 2010 – Additional Insured (naming the City and School Dept.), CG2503-General Aggregate Per Project, and CG2404 (if not included in form) Waiver of Transfer of Rights of recovery. This insurance shall cover bodily injury and property damage liability for all hazards of the Project including premise and operations, products and completed operations, contractual, and personal injury liabilities. It shall include collapse and underground coverage as well as explosion coverage if explosion hazards exist. Aggregate limits shall apply on a per location or project basis.

Minimum acceptable limits are:

General aggregate limit: \$2,000,000
Products and completed operations aggregate: \$1,000,000
Each occurrence limit: \$1,000,000
Personal injury aggregate: \$1,000,000

2. Automobile Liability Insurance

Automobile liability insurance against claims for bodily injury, death or property damage resulting from the maintenance, Ownership or use of all owned, nonowned and hired automobiles, trucks and trailers.

Minimum acceptable limit is \$1,000,000 any one accident or loss.

3. Owners Protective Liability

For Contracts exceeding \$50,000 in total Contract amount, Contractor shall secure an Owners Protective Liability policy naming the Owner as the Named Insured.

Minimum acceptable limits are:

General aggregate limit: \$2,000,000 Each occurrence limit: \$1.000.000

4. Pollution Liability

In the event that any disruption, handling, abatement, remediation, encapsulation, removal, transport, or disposal of contaminated or hazardous material is required, the Contractor or its Sub-Contractor shall secure a pollution liability policy in addition to any other coverages contained in this section. The insurance shall be provided on an occurrence based policy and shall remain in effect for the duration of the Project. If not available and a claims made policy is provided, include an extended reporting period of three years after project completion.

Minimum acceptable limit is \$1,000,000 per occurrence.

5. Commercial Umbrella/Excess Liability Insurance: \$10,000,000

C. Property Insurance

The Owner will provide the Builder's Risk insurance.

D. Certificates of Insurance

Four original copies of all certificates of insurance in a form and issued by companies acceptable to the Owner shall be provided to the Designer prior to commencement of work. The Owner shall be listed on the certificates as an additional insured, and certificate shall include Waiver of Subrogation in favor of the Owner. The certificates shall name the Owner as certificate holder and shall contain a provision that coverage afforded under the insurance policies will not be canceled or materially changed unless at least thirty (30) days prior written notice by registered letter has been given to the Owner. Cancellation Notice of 30 days shall be specifically endorsed to the policies."

7. ARTICLE 42: DISPUTE RESOLUTION, is deleted in its entirety and replaced with the following:

"ARTICLE 42: DISPUTE RESOLUTION

If, in the performance of this contract, there arises a dispute between the Contractor and the Owner that cannot be resolved by the parties to the contract, the parties shall submit the dispute to

a single mediator selected by parties. The parties agree to mediate the dispute in good faith for not more than one day at a date, time and place in Cumberland County, Maine specified by the mediator. The parties shall equally share the costs and fees of the mediator, but shall otherwise bear their own costs of mediation. If the parties are unable to agree upon a mediator or otherwise fail to resolve their differences through mediation, then either party may demand arbitration pursuant to the Maine Uniform Arbitration Act, 14, M.R.S.A. §5927-5949. There shall be one arbitrator selected by the parties. If the parties cannot agree upon an arbitrator within thirty (30) days of a demand for arbitration, then either party may apply to Maine Superior Court for selection of an arbitrator. The arbitrator selected shall conduct the arbitration proceeding. All issues which relate to the controversy or dispute shall be resolved in the arbitration, which shall be final and binding provided that in any arbitration the arbitrator shall be bound by and follow the substantive laws of Maine. The arbitration hearing shall be conducted in Maine and shall not exceed two days unless agreed by the parties or ordered by the arbitrator. The parties shall equally share the costs and fees of the arbitrator, but shall otherwise bear their own costs of arbitration except that if the arbitrator determines that either party has acted unreasonably or in bad faith, the arbitrator may require that party to reimburse the other party for its reasonable costs, including but not limited to arbitration costs and reasonable attorney's fees.

•

In any binding arbitration between the Owner and the Contractor, the Owner may elect to consolidate related claims between the Owner and the Designer, in which case the selection of the arbitrator shall also be subject to approval of the Designer."

8. ARTICLE 43: COMPLETION TIME AND LIQUIDATED DAMAGES The Owner shall be entitled to actual damages if Owner's actual damages exceed the liquidated damages provided by Article 43 of the General Conditions.

SECTION 3 - B

EXHIBIT A PARTIAL LIEN WAIVER

	as Contractor under a Contract by and between
the undersigned and the York School Departme furnished labor or materials, or both, for the pr York Middle School Window Replacement Phase	emises owned by Owner and located on or about
The undersigned hereby certifies to the Owner that is now due and payable to the und	through the date set forth below, the sum of \$ lersigned, with retainage due but not yet payable, in the \$ due upon completion (or as it
becomes due) of the Contract by and between the u	due upon completion (or as it undersigned and Owner, and
equipment used, engaged or employed by the unde	contractors or suppliers of labor, services, material or resigned directly or indirectly, have been paid in full, or requisition submitted to Owner herewith, with respect ough the date set forth below; and
undersigned hereby agrees to indemnify and hold (or whose work or materials partial payment is to be with or who are otherwise entitled to payment and the Dwner harmless from any and all claims by any party lls furnished, caused to be furnished or intended to be
to the undersigned in connection with the Premises hereby release the Owner of all claims, demands an Premises and project through the date set forth belo	ow; and does hereby waive and release any lien or right vements, on account of any and all labor or materials,
Dated	Dated
Witness	Contractor
State of Maine County of	
Then personally appeared before me the above-nar to be a free act and deed.	med Contractor and acknowledged the foregoing
	Notary Public
Dated	Print Name
Note: This Partial Lien Waiver and all attached F	Partial Lien Waivers from subcontractors and suppliers

must be dated not more than ten (10) days before Contractor's payment requisition.

SECTION 3 - B

EXHIBIT B PARTIAL LIEN WAIVER

(Subcontractor and Suppliers)

The undersigned,	pursuant to a Contract or Agreement with , has furnished or caused to be furnished labor or materials, or both, for
<u>.</u>	School Department and located on or about the York Middle School
Window Replacement Phase 2 Pro	oject, York, ME ("Premises"); and
is now due and p amount of \$ and w becomes due) of the Contract or A the undersigned shall and does he	to the Owner that through the date set forth below, the sum of \$ ayable to the undersigned, with retainage due but not yet payable, in the with a balance of \$ due upon completion (or as it agreement with the Contractor; and upon receipt of the sums now due reby release the Contractor from all claims, demands and actions on for the Premises through the date set forth below; and
services, material or equipment us been paid in full, or otherwise sati through the date set forth below; a	owner that all Contractor that all subcontractors or suppliers of labor, sed, engaged or employed by the undersigned directly or indirectly, have asfied with respect to labor or materials furnished to the Premises and the undersigned hereby agrees to indemnify and hold the Owner and all claims by any party whatsoever in connection with the labor or gned; and
to the undersigned in connection whereby release the Owner of all cl. Premises and project through the to lien the Premises, including any	nowledge full performance by the Owner of all obligations due or owing with the Premises and the project through the date set forth below; does aims, demands and actions arising out or in connection with the date set forth below; and does hereby waive and release any lien or right y building improvements, on account of any and all labor or materials, ted into the Premises through the date set forth below.
Dated	Dated
Witness	Subcontractor / Supplier
	By: Its

Note: This Partial Lien Waiver and all attached Partial Lien Waivers from subcontractors and suppliers must be dated not more than ten (10) days before Contractor's payment requisition.

This Page Left Intentionally Blank

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Work covered by the Contract Documents.
 - 2. Type of the Contract.
 - 3. Work schedule.
 - 4. Work under other contracts.
 - 5. Owner-furnished products.
 - 6. Owner's occupancy requirements.
 - 7. Specification formats and conventions.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

- A. Project Identification: York Middle School Window Replacement Phase 2.
 - 1. Project Location: York, Maine.
- B. Owner: York School District.
- C. Architect: Harriman, Auburn Business Park, 46 Harriman Drive, Auburn, ME 04210.

1.4 TYPE OF CONTRACT

A. Project will be constructed under a single prime contract.

1.5 WORK SCHEDULE

- A. Schedule:
 - 1. Work may begin on June 20, 2024 and all work shall be substantially complete on or before August 19, 2024.
- B. Do not disturb adjacent spaces during hours of operation.
- C. Time: The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.

1.6 OWNER-FURNISHED PRODUCTS

- A. Owner will furnish products indicated and/or as specified. The Work includes providing support systems to receive Owner's equipment.
 - 1. Contractor is responsible for protecting Owner-furnished items from damage during storage and handling, including damage from exposure to the elements.
 - 2. Contractor shall install and otherwise incorporate Owner-furnished items into the Work.

1.7 OWNER'S OCCUPANCY REQUIREMENTS

- A. Full Owner Occupancy: Owner will occupy site and premises during entire construction period with the exception of areas under construction. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's day-to-day operations. Maintain existing exits, unless otherwise indicated
 - 1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and authorities having jurisdiction.
 - 2. Provide not less than 72 hours' notice to Owner of activities that will affect Owner's operations.

1.8 SPECIFICATION FORMATS AND CONVENTIONS

- A. Specification Format: The Specifications are organized into Divisions and Sections using the CSI/CSC's "MasterFormat" numbering system.
 - 1. Section Identification: The Specifications use Section numbers and titles to help cross-referencing in the Contract Documents. Sections in the Project Manual are in numeric sequence; however, the sequence is incomplete because all available Section numbers are not used. Consult the table of contents at the beginning of the Project Manual to determine numbers and names of Sections in the Contract Documents.
 - 2. Division 01: Sections in Division 01 govern the execution of the Work of all Sections in the Specifications.
- B. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
 - Abbreviated Language: Language used in the Specifications and other Contract
 Documents is abbreviated. Words and meanings shall be interpreted as appropriate.
 Words implied, but not stated, shall be inferred as the sense requires. Singular words
 shall be interpreted as plural, and plural words shall be interpreted as singular where
 applicable as the context of the Contract Documents indicates.
 - 2. Imperative mood and streamlined language are generally used in the Specifications. Requirements expressed in the imperative mood are to be performed by Contractor. Occasionally, the indicative or subjunctive mood may be used in the Section Text for clarity to describe responsibilities that must be fulfilled indirectly by Contractor or by others when so noted.
 - a. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.

1.9 MISCELLANEOUS PROVISIONS

- A. Material safety data sheets shall be made available in accordance with OSHA requirements.
- B. No asbestos containing materials shall be used in the work.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

This Page Left Intentionally Blank

SECTION 013300 - SUBMITTAL PROCEDURES (2023)

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.

B. Related Requirements:

1. Division 01 to 33 Sections for specific requirements for submittals in those Sections.

1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."
- C. File Transfer Protocol (FTP): Communications protocol that enables transfer of files to and from another computer over a network and that serves as the basis for standard Internet protocols. An FTP site is a portion of a network located outside of network firewalls within which internal and external users are able to access files.
- D. Portable Document Format (PDF): An open standard file format used for representing documents in a device-independent and display resolution-independent fixed-layout document format.

1.4 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Architect's Electronic Document Files: Copies of the Contract Drawings in electronic format will be made available by the Architect to those requesting same in accordance with the "Agreement Between Harriman (Architect & Engineer of Record) and Owner or Contractor for Release of Electronic Documents" form attached to the end of this section. Agreement form shall be filled out and signed by each party requesting electronic documents before electronic media is released to them.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 2. Submit all submittal items required for each specification section concurrently.

- 3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
- 4. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- 5. No products shall be incorporated into the work unless they have been approved by the Contractor and Architect. No work will be paid for until required submittals for applicable work have been submitted and approved.
- C. Submittals Schedule: Comply with requirements in Division 01 Section "Construction Progress Documentation" for list of submittals and time requirements for scheduled performance of related construction activities.
- D. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - 1. Initial Review: Allow 14 calendar days minimum for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 - 3. Resubmittal Review: Allow 14 calendar days minimum for review of each resubmittal.
 - 4. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 21 calendar days minimum for initial review of each submittal.
- E. Electronic Submittals: **Architect is using Newforma software to process electronic submittals**. Submittals must be sent for review individually (one submittal per email). Identify and incorporate information in each electronic submittal file as follows:
 - 1. Assemble complete submittal package into single files incorporating submittal requirements of a single specification section and transmittal form.
 - a. Provide a separate transmittal form for Product Data, a separate transmittal form for Shop Drawings, and a separate transmittal form for Informational Submittals required by each Specification Section.
 - b. Maximum File Size: A single file size, up to 18 MB can be received. Contact Architect for instructions if file exceeds 18 MB.
 - c. For each transmittal, attach one single PDF only. Where multiple PDFs are required for a transmittal, utilize a combine feature to merge the PDFs into a single PDF.
 - 1) Unacceptable Formats: In order to process the transmittals in Newforma, the single PDF file protocol must be followed. Transmittals zip files or grouped PDFs cannot be electronically processed and will be returned without action for correction and resubmittal.
 - 2) Submittals will be returned without action for correction and resubmittal if:
 - a) Submittal does not have an electronic Transmittal Form.
 - b) Multiple specification sections are contained within a single Transmittal form. Submittals must be separated into individual Specification Sections.
 - c) Submittal does not include the Contractors' signed reviewed stamp

- 2. Name file with submittal number or other unique identifier, including revision identifier.
 - a. File name shall use project identifier and Specification Section number followed by a dash and then a sequential number (e.g., LNHS-061000-01). Resubmittals shall include an alphabetic suffix after another dash (e.g., LNHS-061000-01-A).
- 3. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Architect.
- 4. Transmittal Form for Electronic Submittals: Use electronic form acceptable to Owner, containing the following information:
 - a. Project name.
 - b. Date.
 - c. Name and address of Architect.
 - d. Name of Contractor.
 - e. Name of firm or entity that prepared submittal.
 - f. Names of subcontractor, manufacturer, and supplier.
 - g. Submittal number or other unique identifier, including revision identifier.
 - Submittal number shall use Specification Section number followed by a decimal point and then a sequential number (e.g., 061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., 061000.01.A).
 - h. Specification Section number and title.
 - i. Drawing number and detail references, as appropriate.
 - j. Location(s) where product is to be installed, as appropriate.
 - k. Related physical samples submitted directly.
 - 1. Indication of full or partial submittal.
 - m. Other necessary identification.
- F. Options: Identify options requiring selection by Architect.
- G. Deviations and Additional Information: On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements in the Contract Documents, including minor variations and limitations. Include same identification information as related submittal.
- H. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
 - 1. Note date and content of previous submittal.
 - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 - 3. Resubmit submittals until they are marked with appropriate notation from Architect's action stamp.
- I. Architect will return all processed submittals through the Newforma file transfer procedure. Contractor will be responsible for incorporating the processed submittals into their file management systems as appropriate.
- J. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- K. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with appropriate notation from Architect's action stamp.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements: Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.
 - 1. Submit electronic submittals by either of the following methods:
 - a. Via email as PDF electronic file to **constructadmin@harriman.com**.
 - 1) Architect will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.
 - b. Post electronic submittals as PDF electronic files directly to Architect's FTP site specifically established for Project.
 - 1) Architect will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.
 - 2. Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
 - a. Provide a digital signature with digital certificate on electronically submitted certificates and certifications where indicated.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
 - 1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
 - 2. Mark each copy of each submittal to show which products and options are applicable.
 - 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.
 - g. Notation of coordination requirements.
 - h. Availability and delivery time information.
 - 4. For equipment, include the following in addition to the above, as applicable:
 - a. Wiring diagrams showing factory-installed wiring.
 - b. Printed performance curves.
 - c. Operational range diagrams.
 - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
 - 5. Submit Product Data before or concurrent with Samples.
 - 6. Submit Product Data in the following format:
 - a. PDF electronic file.
 - 7. Do not submit Material Safety Data Sheets (MSDSs).
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
 - 1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Dimensions.
 - b. Identification of products.

- c. Schedules.
- d. Compliance with specified standards.
- e. Notation of coordination requirements.
- f. Notation of dimensions established by field measurement.
- g. Relationship and attachment to adjoining construction clearly indicated.
- h. Seal and signature of professional engineer if specified.
- 2. Submit Shop Drawings in the following format:
 - PDF electronic file.
- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
 - 1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
 - 2. Identification: Attach label on unexposed side of Samples that includes the following:
 - a. Generic description of Sample.
 - b. Product name and name of manufacturer.
 - c. Sample source.
 - d. Number and title of applicable Specification Section.
 - e. Specification paragraph number and generic name of each item.
 - 3. For projects where electronic submittals are required, provide corresponding electronic submittal of Sample transmittal, digital image file illustrating Sample characteristics, and identification information for record.
 - 4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
 - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
 - 5. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
 - a. Number of Samples: Submit one full set(s) of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.
 - 6. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
 - a. Number of Samples: Submit two sets of Samples. Architect will retain one Sample sets; remainder will be returned.
 - 1) Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.

- 2) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.
- E. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
 - 1. Type of product. Include unique identifier for each product indicated in the Contract Documents or assigned by Contractor if none is indicated.
 - 2. Manufacturer and product name, and model number if applicable.
 - 3. Number and name of room or space.
 - 4. Location within room or space.
 - 5. Submit product schedule in the following format:
 - a. PDF electronic file.
- F. Coordination Drawing Submittals: Comply with requirements specified in Section 013100 "Project Management and Coordination."
- G. Contractor's Construction Schedule: Comply with requirements specified in Section 013200 "Construction Progress Documentation."
- H. Application for Payment and Schedule of Values: Comply with requirements specified in Section 012900 "Payment Procedures."
- I. Test and Inspection Reports and Schedule of Tests and Inspections Submittals: Comply with requirements specified in Section 014000 "Quality Requirements."
- J. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Section 017700 "Closeout Procedures."
- K. Maintenance Data: Comply with requirements specified in Section 017823 "Operation and Maintenance Data."
- L. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- M. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.
- N. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
- O. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.

- P. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
- Q. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
- R. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
- S. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- T. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
 - 1. Name of evaluation organization.
 - 2. Date of evaluation.
 - 3. Time period when report is in effect.
 - 4. Product and manufacturers' names.
 - 5. Description of product.
 - 6. Test procedures and results.
 - 7. Limitations of use.
- U. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- V. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- W. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- X. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.
- Y. Material Safety Data Sheets (MSDSs): Submit information directly to Owner at end of the project; do not submit to Architect. Maintain copy at the site for the duration of the construction.
 - 1. Architect will not review submittals that include MSDSs and will return them.

2.2 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
 - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF electronic file paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
 - 1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Contractor to mark submittal with their approval stamp before submitting to Architect.
 - 1. The Contractor shall review submittals for completeness and compliance with the Contract Documents. If submittal contains substitutions, Contractor shall process substitutions in accordance with Division 01 Section "Substitutions and Product Options," and not part of specified Shop Drawings or Product Data submittals. Contractor is responsible for keeping Subcontractors on time with the submittal schedule. If the Contractor submits submittals that are repeatedly rejected, requiring the Architect to perform multiple reviews of the same submittal because of the failure to properly prepare and complete the submittals:
 - a. Owner will compensate Architect for such additional services.
 - b. Owner will deduct the amount of such compensation from the final payment to the Contractor.
- B. Project Closeout and Maintenance Material Submittals: See requirements in Section 017700 "Closeout Procedures."
- C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S ACTION

- A. General: Architect will not review submittals that do not bear Contractor's submittal stamp and will return them without action.
- B. Action Submittals: Architect will review each submittal, make marks to indicate corrections or revisions required, and return it. Architect will stamp each submittal with an appropriate mark to indicate status.

- 1. The Architect's marking of "Reviewed, Furnish as Corrected or similar verbiage means submittal has been reviewed for general conformance to the contract documents only and does not mean unqualified acceptance. The Contractor is fully responsible for compliance with the contract documents.
- C. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- D. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.
- E. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- F. Submittals not required by the Contract Documents will be returned by the Architect without action.

END OF SECTION 013300

This Page Left Intentionally Blank

SECTION 024119 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Demolition and removal of selected portions of building or structure.

1.3 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Carefully detach from existing construction, in a manner to prevent damage, and deliver to Owner.
- C. Remove and Reinstall: Detach items from existing construction, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Existing items of construction that are not to be permanently removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.4 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition waste becomes property of Contractor.
- B. Historic items, relics, antiques, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, and other items of interest or value to Owner that may be uncovered during demolition remain the property of Owner.
 - 1. Carefully salvage in a manner to prevent damage and promptly return to Owner.

1.5 FIELD CONDITIONS

- A. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
 - 1. Hazardous materials will be removed by Owner before start of the Work.

2. If suspected hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials will be removed by Owner under a separate contract.

PART 2 - EXECUTION

2.1 EXAMINATION

A. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.

2.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.

2.3 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
 - Neatly cut openings and holes plumb, square, and true to dimensions required. Use
 cutting methods least likely to damage construction to remain or adjoining construction.
 Use hand tools or small power tools designed for sawing or grinding, not hammering and
 chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to
 remain.
 - 2. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 - 3. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
 - 4. Dispose of demolished items and materials promptly.

B. Removed and Reinstalled Items:

- 1. Clean and repair items to functional condition adequate for intended reuse.
- 2. Protect items from damage during transport and storage.
- C. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and reinstalled in their original locations after selective demolition operations are complete.

2.4 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

A. Resilient Floor Coverings: Remove floor coverings and adhesive according to recommendations in RFCI's "Recommended Work Practices for the Removal of Resilient Floor Coverings."

2.5 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Project site.
 - 1. Do not allow demolished materials to accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
 - 3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
- B. Burning: Do not burn demolished materials.
- C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

2.6 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

PART 3 - EXECUTION - NOT USED

END OF SECTION 024119

This Page Left Intentionally Blank

SECTION 079200 – JOINT SEALANTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes joint sealants for the following applications, including those specified by reference to this Section:
 - 1. Exterior joints in the following vertical surfaces and horizontal nontraffic surfaces:
 - a. Joints between different materials listed above.
 - b. Perimeter joints between materials listed above and frames of doors, windows and louvers.
 - c. Other joints as indicated.
 - 2. Interior joints in the following vertical surfaces and horizontal nontraffic surfaces:
 - a. Perimeter joints of exterior openings where indicated.
 - b. Other joints as indicated.
- B. Related Sections include the following:
 - 1. Division 07 Section "Sheet Metal Flashing and Trim" for sealing joints related to flashing and sheet metal for roofing.

1.3 PERFORMANCE REQUIREMENTS

- A. Provide joint sealants that have been produced and installed to establish and maintain watertight and airtight continuous seals without causing staining or deterioration of joint substrates.
- B. Provide joint sealants for interior applications that establish and maintain airtight and water-resistant continuous joint seals without staining or deteriorating joint substrates.

1.4 SUBMITTALS

- A. Product Data: For each joint-sealant product indicated.
 - 1. Include manufacturer's installation instructions.
- B. Samples for Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.
- C. Joint-Sealant Schedule: Include the following information:
 - 1. Joint-sealant application, joint location, and designation.
 - 2. Joint design, including width and depth of joint sealant, and backer rod or bond-breaker size and location.
 - 3. Joint-sealant manufacturer and product name.
 - 4. Joint-sealant formulation.

- 5. Joint-sealant color.
- 6. Primer for each substrate type.
- 7. Solvent wipe cleaner for each substrate type.
- 8. For sealants and sealant primers used inside the weatherproofing system, including printed statement of VOC content.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an experienced Installer who has completed joint sealant applications similar in materials, design, and extent to that indicated for Project that have resulted in construction with a record of successful in-service performance.
- B. Source Limitations: Obtain each type of joint sealant through one source from a single manufacturer.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to Project site in original unopened containers or bundles with labels indicating manufacturer, product name and designation, color, expiration period for use, shelf/pot life, curing time, and mixing instructions for multi-component materials.
- B. Store and handle materials in compliance with manufacturer's recommendations to prevent their deterioration or damage due to moisture, high or low temperatures, contaminants, or other causes.
- C. Remove and replace materials, at no cost to Owner, that cannot be applied within their stated shelf life.

1.7 PROJECT CONDITIONS

- A. Environmental Conditions: Do not proceed with installation of joint sealants under the following conditions:
 - 1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
 - 2. When joint substrates are wet.
 - 3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
 - 4. Contaminants capable of interfering with adhesion have not yet been removed from joint substrates.
- B. Joint Width Conditions: Do not proceed with installation of joint sealants where joint widths are less than allowed by joint sealant manufacturer for application indicated.
- C. Joint Substrate Conditions: Do not proceed with installation of joint sealants until contaminants capable of interfering with their adhesion are removed from joint substrates.

1.8 SEQUENCING AND SCHEDULING

A. Coordinate Work of this Section with interfacing and adjoining Work for proper sequencing of each installation to ensure a weathertight installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Products: Subject to compliance with requirements, provide one of the products listed in other Part 2 articles.

2.2 MATERIALS, GENERAL

- A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by sealant manufacturer, based on testing and field experience.
- B. Exposed Joint Sealants: Products exposed to view in interior public areas shall be paintable. Mechanical, electrical and elevator machine rooms are not considered public spaces.
- C. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.3 JOINT SEALANTS

- A. VOC Content of Sealants and Primers:
 - 1. Exterior Sealants and Primers: Provide exterior sealants and sealant primers that comply with the following limits for VOC content when calculated according to South Coast Air Quality Management District Rule No. 1168:
 - a. Architectural Sealants: 250 g/L.

Sealant Primers, Porous: 775 g/L.

- 2. Interior Sealants and Primers: Provide interior sealants and sealant primers that comply with the following limits for VOC content when calculated according to South Coast Air Quality Management District Rule No. 1168:
 - a. Sealants:
 - 1) Architectural: 250 g/L.
 - b. Sealant Primers:
 - 1) Architectural, Nonporous: 250 g/L
 - 2) Architectural, Porous: 775 g/L.
 - 3) Other: 750 g/L.
- B. Type 1 General Purpose Exterior Sealant: Polyurethane; ASTM C920, Type S, Grade NS, Class 25; single component.
 - 1. Products:
 - a. Sonolastic NP-1; Sonneborn, Division of ChemRex Inc.
 - b. Dymonic; Tremco.
 - c. Sikaflex-1a; Sika Corporation, Inc.
 - d. Dynatrol 1; Pecora Corporation.
 - e. Vulkem 116; Tremco.

- C. Type 2 General Purpose Exterior Sealant: Single-component, nonsag, neutral-curing silicone joint sealant; ASTM C 920, Type S, Grade NS, Class 50, for Use NT. Shall be no staining on granite, precast concrete and brick per ASTM C 1248.
 - 1. Products:
 - a. Dow Corning Corporation; 795.
 - b. GE Advanced Materials Silicones; SilPruf NB SCS9000.
 - c. Pecora Corporation; 864NST.
 - d. Tremco Incorporated; Spectrem 3.
- D. Type 3 General Purpose Interior Sealant: Acrylic emulsion latex; ASTM C834, single component, paintable.
 - 1. Products:
 - a. Tremflex 834: Tremco.
 - b. AC-20; Pecora Corporation.
 - c. Chem-Calk 600; Bostik Findley.

2.4 JOINT-SEALANT BACKING

- A. General: Provide sealant backings (backer rods) of material and type that are nonstaining; are compatible with joint substrates, sealants, primers, and other joint fillers; and are approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
- B. Plastic Foam Joint Fillers (Backer Rod): ASTME C 1330, Type C, preformed, compressible, resilient, nonstaining, nonwaxing, nonextruding strips of flexible plastic foam of material indicated below and of size, shape, and density to control sealant depth and otherwise contribute to producing optimum sealant performance:
 - 1. Closed-cell polyethylene foam, nonabsorbent to liquid water and gas, nonoutgassing in unruptured state.
- C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint where such adhesion would result in sealant failure. Provide self-adhesive tape where applicable.

2.5 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:
 - 1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
 - 2. Clean concrete, masonry, unglazed surfaces of ceramic tile, and similar porous joint substrate surfaces by brushing, grinding, blast cleaning, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air.
 - 3. Remove laitance and form-release agents from concrete.
 - 4. Clean metal, glass, porcelain enamel, glazed surfaces of ceramic tile, and other nonporous surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants.
- B. Joint Priming: Prime joint substrates, where indicated or recommended in writing by joint-sealant manufacturer, based on preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
 - 1. Simulated stone and concrete surfaces shall be primed.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
- B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Installation of Sealant Backings (Backer Rods): Install sealant backings to comply with the following requirements:

- 1. Install sealant backings of type indicated to provide support of sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 - a. Do not leave gaps between ends of sealant backings.
 - b. Do not stretch, twist, puncture, or tear sealant backings.
 - c. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.
- 2. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and joint fillers or backs of joints.
- D. Installation of Sealants: Install sealants using proven techniques that result in sealants directly contacting and fully wetting joint substrates, completely filling recesses provided for each joint configuration, and providing uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability. Install sealants at the same time sealant backings and primers are installed.
 - 1. Place sealants so they directly contact and fully wet joint substrates.
 - 2. Completely fill recesses in each joint configuration.
 - 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- E. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
 - 1. Remove excess sealant from surfaces adjacent to joints.
 - 2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
 - 3. Provide concave joint configuration per Figure 5A in ASTM C 1193, unless otherwise indicated.

3.4 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.5 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.6 JOINT-SEALANT SCHEDULE

A. Control, Expansion, and Soft Joints between Exterior Simulated Stone Veneer and Adjacent Work: Type 2; colors as selected. Prime simulated stone.

- B. Joints between Exterior Metal Frames, Windows, Trim and Adjacent Work: Type 2; colors as selected.
 - 1. Do not use in contact with PVC trim.
- C. Under Exterior Door Thresholds: Type 1.
- D. Exterior Joints for Which No Other Sealant Type is Indicated: Type 3; colors as selected.
- E. Concealed Interior Perimeter Joints of Exterior Openings: Type 1.
- F. Exposed Interior Perimeter Joints of Exterior Openings: Type 4; colors as selected.
- G. Joints between Interior Simulated Stone Veneer and Adjacent Work: Type 2; colors as selected.
- H. Interior Ceramic Tile Expansion, Control, Contraction, and Isolation Joints in Horizontal Traffic Surfaces: Type 5; color as selected.
- I. Control and Expansion Joints in Interior Concrete Slabs and Floors Left Exposed: Type 5; colors as selected.
- J. Joints between Plumbing Fixtures and Walls and Floors and Between Countertops and Walls: Type 4; colors as selected.
- K. Interior Joints for Which No Other Sealant is Indicated: Type 3; colors as selected.

END OF SECTION 079200

This Page Left Intentionally Blank

SECTION 084523 - FIBERGLASS-SANDWICH-PANEL ASSEMBLIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes aluminum-framed assemblies incorporating fiberglass-sandwich panels as follows:
 - 1. Wall assemblies.
- B. Related Sections include the following:
 - 1. Division 07 Section "Joint Sealants" for sealants installed at perimeters of assemblies.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

- A. General: Submit in accordance with Division 01 Section "Submittal Procedures."
- B. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for aluminum components of panel assemblies.
- C. Shop Drawings: For panel assemblies.
 - 1. Include plans, elevations, sections, details, and attachments to other work.
 - 2. Include details of provisions for assembly expansion and contraction and for draining moisture within the assembly to the exterior.
- D. Delegated-Design Submittal: For panel assemblies indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional structural engineer responsible for their preparation.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer and manufacturer.
- B. Product Test Reports: For each fiberglass-sandwich-panel assembly, for tests performed by a qualified, independent testing agency. Reports shall verify that materials meet all performance requirements of this specification. Previously completed test reports will be acceptable if current and indicative of products used on this project. Test reports shall confirm assemblies meet or exceed the following:
 - 1. Burn Extent: ASTM D 635.
 - 2. Color Difference: ASTM D 2244 in accordance with ASTM D 1435.
 - 3. Impact Strength: UL 972.

- 4. Bond Tensile Strength: ASTM C 297.
- 5. Bond Shear Strength: ASTM D 1002.
- 6. Beam Bonding Strength: ASTM E 72.
- 7. Insulation U-Factor: NFRC 100.
- 8. NFRC System U-Factor Certification: NFRC 700.
- 9. Solar Heat Gain Coefficient: NFRC or Calculations.
- 10. Accelerated Aging: ASTM D 1037.
- 11. Flame Spread and Smoke Developed: ASTM E 84 or UL 723.
- 12. Condensation Resistance Factor: AAMA 1503.1.
- C. Submit proof of regular, independent quality control monitoring under a building code review and listing program.
- D. Evaluation Reports: For fiberglass-sandwich-panel assemblies from ICC-ES.
- E. Sample Warranties: For special warranties.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For panel assemblies to include in maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Manufacturer Qualifications: For fiberglass-sandwich panels, a qualified manufacturer whose facilities, processes, and products are monitored by an independent, accredited quality-control agency for compliance with applicable requirements in ICC-ES AC04 or ICC-ES AC177. Manufacturer of fiberglass-sandwich-panel assemblies shall have continuously fabricated assemblies for not less than 10 years and shall show evidence of these materials being satisfactorily used on at least 6 projects of similar size, scope and location with at least 5 projects having successful in-service performance for not less than 10 years.
- B. Installer Qualifications: Entity capable of performing work of this Section and who is acceptable to manufacturer; has been in business of erecting translucent panels for not less than 5 years; and can evidence a record of successful in-service performance.
- C. Professional Engineer Qualifications: A professional structural engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of kind indicated. Engineering services are defined as those performed for installations of fiberglass-sandwich panel assemblies that are similar to those indicated for this Project in material, design, and extent.
- D. Product Options: Information on Drawings and in Specifications establishes requirements for assemblies' aesthetic effects and performance characteristics. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction. Performance characteristics are indicated by criteria subject to verification by one or more methods including testing conducted by an independent testing agency and in-service performance.
 - 1. Do not modify intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If modifications are proposed, submit comprehensive explanatory data to Architect for review.

1.8 PROJECT CONDITIONS

A. Field Measurements: Indicate measurements on Shop Drawings.

1.9 PRODUCT HANDLING

A. Store panels on long edge on blocking several inches above ground and under cover to prevent warping.

1.10 WARRANTY

- A. Manufacturer's Special Warranty: Manufacturer agrees to repair or replace fiberglass-sandwich panels that exhibit defects in materials or workmanship within specified warranty period.
 - 1. Defects include, but are not limited to, the following:
 - a. Fiberbloom.
 - b. Discoloration of exterior face sheet of more than 3.0 units Delta E units when measured according ASTM D 2244 at 5 degrees facing south without a protective film or coating to ensure long-term color stability. Color stability shall be unaffected by abrasion or scratching.
 - c. Delamination of panel face sheets from panel cores.
 - 2. Warranty Period:
 - a. Fiberbloom: 25 years from date of Substantial Completion.
 - b. Discoloration of Exterior Face Sheet: 5 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional structural engineer, as defined in Section 014000 "Quality Requirements," to design fiberglass-sandwich-panel assemblies.
- B. Structural Loads: Assemblies shall comply with the requirements of IBC 2009 and the following:
 - 1. Wind Speed and Exposure: As indicated by structural design data on Drawings.
 - 2. Wind Pressure for Wall Panels:
 - a. Corner Pressures: Positive 13 lbf/sq. ft. and negative 18 lbf/sq. ft.
 - b. Field-of-Building Pressures: Positive 13 lbf/sq. ft. and negative 15 lbf/sq. ft.
 - 3. Seismic Loads: As indicated by earthquake design data on Drawings.
 - 4. Load Combinations: Calculate according to requirements of IBC 2009.

C. Deflection Limits:

- 1. Vertical Panel Assemblies: Limited to 1/90 of clear span for each assembly component.
- D. Water Penetration under Static Pressure: Provide panel assemblies that do not evidence water penetration through fixed glazing and framing areas when tested according to ASTM E 331 at a minimum static-air-pressure difference of 20 percent of positive wind-load design pressure, but not less than 15 lbf/sq. ft..

- E. Fiberglass-Sandwich-Panel Adhesive: Shall be heat and pressure resin-type engineered for structural sandwich panel use. Adhesive shall comply with testing requirements specified by International Code Council, "Acceptance Criteria for Sandwich Panel Adhesives."
 - 1. Compatible with facing and core materials.
 - 2. Tensile Strength: Not less than 750 psi per ASTM C 297after two exposures to six cycles each of the aging conditions prescribed by ASTM D 1037.
 - 3. Shear Strength: After exposure to 5 separate aging conditions per ASTM D 1002 shall be as follows:
 - a. 540 psi at 50 percent relative humidity at 73 deg F.
 - b. 182 deg F: 100 psi.
 - c. After accelerated aging per ASTM D 1037 at room temperature: 800 psi.
 - d. After accelerated aging per ASTM D 1037 at 182 deg F: 250 psi.
- F. Thermal Movements: Allow for thermal movements from ambient- and surface-temperature changes. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.
- G. Energy Performance: Provide panel assemblies with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below and certified and labeled according to NFRC:
 - 1. Thermal Transmittance (U-Factor): Fixed glazing and framing areas shall have U-factor of not more than 0.23 Btu/sq. ft. x h x deg F as determined according to NFRC 100.
 - 2. Solar Heat Gain Coefficient (SHGC): Fixed glazing and framing areas shall have a SHGC of no greater than 0.28 as determined according to NFRC 200.
 - 3. Air Infiltration: Maximum air leakage through fixed glazing and framing areas of 0.01 cfm/sq. ft. of fixed wall area as determined according to ASTM E 283 at a minimum static-air-pressure differential of 6.24 lbf/sq. ft..

2.2 FIBERGLASS-SANDWICH-PANEL ASSEMBLIES

- A. Fiberglass-Sandwich-Panel Assemblies: Translucent assemblies that are supported by aluminum framing and glazed with fiberglass-sandwich panels.
 - 1. Products:
 - a. Kalwall Corporation; contact: David L'Heureux, (800) 258-9777.
 - 1) Walls: Kalwall Translucent Panel System.
 - b. Major Industries, Inc.; contact: Mary Kimball (518) 462-4041.
 - 1) Walls: Guardian 275.

2.3 FIBERGLASS-SANDWICH PANELS

- A. Fiberglass-Sandwich Panels: Uniformly colored, translucent, thermoset, fiberglass-reinforced-polymer face sheets bonded to both sides of a grid core.
- B. Panel Thickness: 2-3/4 inches.
- C. Grid Core: Mechanically interlocked, extruded-aluminum I-beams, with a minimum flange width of 7/16 inch.
 - 1. Extruded Aluminum: ASTM B 221, in alloy and temper recommended in writing by manufacturer.
 - 2. I-Beam Construction: Thermally broken, extruded aluminum.

3. Grid Pattern: Inline rectangle, nominal 12 by 24 inches, symmetrical about panel centerlines.

D. Exterior Face Sheet:

- 1. Thickness: 0.070 inch.
- 2. Color: Crystal. Thickness shall not vary more than 10 percent.
- 3. Protective Weathering Surface: Integral, embedded-glass erosion barrier. Plastic film overlays are not acceptable.

E. Interior Face Sheet, Wall Panels:

- 1. Thickness: 0.045 inch.
 - a. Thickness shall not vary more than 10 percent.
- 2. Color: White.

F. Panel Strength:

- 1. Maximum Panel Deflection: 3-1/2 inches when a 4-by-12-foot panel is tested according to ASTM E 72 at 34 lbf/sq. ft., with a maximum 0.090-inch set deflection after five minutes.
- 2. Panel Support Strength: Capable of supporting, without failure, a 300-lbf concentrated load when applied to a 3-inch-diameter disk according to ASTM E 661.

G. Panel Performance:

- 1. Self-Ignition Temperature: 650 deg F or more according to ASTM D 1929.
- 2. Smoke-Developed Index: 450 or less according to ASTM E 84, or 75 or less according to ASTM D 2843.
- 3. Combustibility Classification: Class CC1 based on testing according to ASTM D 635.
- 4. Color Change: Not more than 3.0 units Delta E, when measured according to ASTM D 2244, after outdoor weathering compliant with procedures in ASTM D 1435.
 - a. Outdoor Weathering Conditions: Sixty months in southern Florida.

2.4 ALUMINUM FRAMING SYSTEMS

- A. Components: Manufacturer's standard extruded-aluminum members of thickness required and reinforced as required to support imposed loads.
 - 1. Construction: Thermally broken, extruded aluminum.
- B. Aluminum: Alloy and temper recommended in writing by manufacturer for type of use and finish indicated.
 - 1. Sheet and Plate: ASTM B 209.
 - 2. Extruded Bars, Rods, Profiles, and Tubes: ASTM B 221.
 - 3. Extruded Structural Pipe and Tubes: ASTM B 429.
 - 4. Structural Profiles: ASTM B 308.
- C. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning skylight components.
- D. Fasteners and Accessories: Manufacturer's standard, corrosion-resistant, nonstaining, and nonbleeding fasteners and accessories; compatible with adjacent materials.
 - 1. At closures, retaining caps, or battens, use ASTM A 193, 300 series stainless-steel screws.

- 2. Use self-locking devices where fasteners are subject to loosening or turning out from thermal and structural movements, wind loads, or vibration.
- 3. At movement joints, use slip-joint linings, spacers, and sleeves of material and type recommended in writing by manufacturer.
- E. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts complying with ASTM A 123 or ASTM A 153requirements.
- F. Anchor Bolts: ASTM A 307, Grade A, hot-dip zinc coating, ASTM A 153/A 153M, Class C.
- G. Concealed Flashing: Corrosion-resistant, nonstaining, nonbleeding flashing compatible with adjacent materials.
- H. Exposed Flashing and Closures: Aluminum sheet not less than 0.040 inch thick, finished to match framing.
- I. Custom Flashing at Tower Corners: Custom bent, aluminum sheet flashing, not less than 0.063 inch thick, by fiberglass-sandwich-panel assemblies; flashing finished to match framing.
- J. Framing Gaskets: Manufacturer's standard.
- K. Frame-System Sealants: As recommended in writing by manufacturer.
 - 1. Sealants used inside the weatherproofing system shall comply with the requirements of the South Coast Air Quality Management District (SCAQMD) Rule No. 1168 as follows:
 - a. Architectural Sealants: 250 g/L.
 - b. Sealant Primers:
 - 1) Architectural, Nonporous: 250 g/L.
 - 2) Architectural, Porous: 775 g/L.
 - 3) Other: 750 g/L.
- L. Corrosion-Resistant Coating: Cold-applied asphalt mastic, compounded for 15-mil dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

2.5 FABRICATION

- A. Frame System Fabrication:
 - 1. Fabricate components before finishing.
 - 2. Fabricate components that, when assembled, have the following characteristics:
 - a. Profiles that are sharp, straight, and free of defects or deformations.
 - b. Accurately fitted joints with ends coped or mitered.
 - c. Internal guttering systems or other means to drain water passing through joints, and moisture migrating within assembly to exterior.
 - 3. Fabricate sill closures with weep holes and for installation as continuous component.
 - 4. Reinforce components as required to receive fastener threads.
- B. Panel Fabrication: Factory assemble and seal panels.
 - 1. Laminate face sheets to grid core under a controlled process using heat and pressure to produce straight adhesive bonding lines that cover width of core members and that have sharp edges. Tape bond systems shall not be allowed.

- a. White spots indicating lack of bond at intersections of grid-core members are limited in number to four for every 40 sq. ft. of panel and limited in diameter to 3/64 inch.
- 2. Fabricate with grid pattern that is symmetrical about centerlines of each panel.
- 3. Fabricate panel to allow condensation within panel to escape.
- 4. Reinforce panel corners.

2.6 ALUMINUM FINISHES

A. Clear Anodic Finish: AAMA 611, AA-M12C22A31, Class II, 0.010 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. General: Comply with manufacturer's written instructions.
 - 1. Do not install damaged components.
 - 2. Fit joints between aluminum components to produce hairline joints free of burrs and distortion.
 - 3. Rigidly secure nonmovement joints.
 - 4. Install anchors with separators and isolators to prevent metal corrosion, electrolytic deterioration, and immobilization of moving joints.
 - 5. Seal joints watertight unless otherwise indicated. Clean all aluminum surfaces prior to applying sealants.
 - 6. Fastening and sealing shall be in strict accordance with approved manufacturer's Shop Drawings.
- B. Metal Protection: Where aluminum components will contact dissimilar materials, protect against galvanic action by painting contact surfaces with corrosion-resistant coating or by installing nonconductive spacers as recommended in writing by manufacturer for this purpose.
- C. Install components plumb and true in alignment with established lines and elevations.

- D. Erection Tolerances: Install panel assemblies to comply with the following maximum tolerances:
 - 1. Alignment: Limit offset from true alignment to 1/32 inch where surfaces abut in line, edge to edge, at corners, or where a reveal or protruding element separates aligned surfaces by less than 3 inches; otherwise, limit offset to 1/8 inch.
 - 2. Location and Plane: Limit variation from true location and plane to 1/8 inch in 12 feet, but no greater than 1/2 inch over total length.
- E. After work is completed on adjacent materials, carefully inspect translucent panel installation and make adjustments necessary to insure proper installation and weathertight conditions.

END OF SECTION 084523

SECTION 085200 - FIBERGLASS REPLACEMENT WINDOWS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Single-hung windows.
- B. Related sections include the following:
 - 1. Division 07 Section "Joint Sealants".

1.3 ACTION SUBMITTALS

- A. Product Data: Manufacturer's product data and installation guides.
- B. Shop Drawings: Drawings indicating direction of operable parts, typical jamb, head and sill conditions, flashing, trim details, mullion details and special mullion reinforcement details.
- C. Color Samples: Selection and verification samples, including the following:
 - 1. Hardware: Samples indicating typical finish on window hardware.
 - 2. Exterior Cladding: Submit color samples of exterior cladding.

1.4 INFORMATIONAL SUBMITTALS

- A. Quality Assurance/Control Submittals:
 - 1. Performance Data: Manufacturer's published performance data for specified products.

1.5 CLOSEOUT SUBMITTALS

- A. Warranty documents specified herein.
- B. Owner's Manual: Bound manual clearly identified with project name, location, and completion date. Identify type and size of units installed. Provide recommendations for periodic inspections, care, and maintenance. Identify common causes of damage with instructions for temporary repair.

1.6 QUALITY ASSURANCE

A. Certifications:

- 1. Window and Door Manufacturers Association (WDMA). Products shall be certified and labeled per WDMA Hallmark Certification Program to the AAMA/WDMA/CSA 101/I.S.2/A440 industry standard.
- 2. Insulating Glass Units: Provide insulating glass units permanently marked with certification label of Insulating Glass Certification Council (IGCC) indicating compliance.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Comply with manufacturer's ordering instructions and lead time requirements to avoid construction delays.
- B. Delivery: Deliver materials in manufacturer's original unopened, undamaged containers with identification labels intact.
- C. Storage and Protection: Store materials protected from exposure to harmful environmental conditions and at temperature and humidity conditions recommended by the manufacturer.
- D. Store materials and accessories off ground, under cover, and protected from weather and construction activities.

1.8 WARRANTY

- A. Project Warranty: Refer to Conditions of the Contract for project Warranty provisions.
- B. Manufacturer's Warranty: Submit, for Owner's acceptance, manufacturer's standard limited warranty document. Manufacturer's limited warranty is in addition to, and not a limitation of, other rights Owner may have under contract documents.
 - 1. Window Unit and Finish: 10 years from date of Substantial Completion.
 - 2. Insulating Glass: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURER

- A. Provide products as follows:
 - 1. Factory-assembled Ultrex® units as manufactured by Integrity Windows & Doors, West Fargo, North Dakota
 - 2. Factory-assembled Impervia and Reserve fiberglass units as manufactured by Pella Corporation, Des Moines, Iowa. Units to be glazed with standard Advanced Low-e argon (Cardinal 272) glazing.

a.

2.2 PERFORMANCE REQUIREMENTS

Α.

Product	Air Tested to psf	Water Tested to psf	Certification Rating	Design Pressure (DP)	Max Overall Width	Max Overall Height
IICA	1.56	7.52	LC-PG50-C	50.13	36.000	71.125
IIAWN	1.56	7.52	LC-PG50-AP	50.13	48.000	47.125
IICAP / IICAT	1.56	7.52	LC-PG50-AP	50.13	72.000	59.125
IICAP / IICAT	1.56	7.52	LC-PG50-AP	50.13	56.000	71.125

B.

2.3 MANUFACTURED UNITS

- A. Proprietary Products/Systems: Fiberglass windows, including the following:
 - 1. Factory-assembled Ultrex®. Integrity Insert Single Hung window.
 - 2. Factory-assembled Ultrex®. Integrity casement window.
 - 3. Related picture units.
 - 4. Factory-assembled Ultrex®. Integrity glider window.

2.4 MATERIALS

A. Frame Description

- 1. Ultrex®, a fiberglass pultrusion. Exterior and Interior 0.075" (2mm) thick.
- 2. Frame thickness: 7/8" (22mm) head jamb and composite side jamb, 25/32" (20mm) sill with 8 degree bevel

B. Sash Description

- 1. Ultrex®, a fiberglass pultrusion. Exterior and Interior 0.075" 92mm) thick for operating units and 0.080" (2mm) thick for picture units.
- 2. Composite sash thickness: 1-3/8" (35mm) for operating units,
- 3. Operable sash tilt to interior for cleaning and removal

C. Weatherstripping:

- 1. Jamb: Foam filled bulb with flexible TPE skin, to match interior color
- 2. Parting Stop: PVC with flexible hinged seal to match interior color
- 3. Bottom Sash: Beige, "V" shaped profile, vinyl foam filled with flexible TPE skin
- 4. Check Rail: PVC with flexible hinged wand seal. Color: Beige
- 5. Stationary Units: Continuous, foam weather strip at perimeter of sash. Color: Gray

D. Glazing

- 1. Select quality complying with ASTM C 1036. Insulating glass SIGMA/IGCC when tested in accordance with ASTM E 2190. STC/OITC ratings are tested to the stated performance level in accordance with ASTM E 90-09.
- 2. Glazing Method: 11/16" (18mm) Insulating glass altitude adjusted
- 3. Glass Type: $Lo\bar{E}2 272$ ® with Argon Gas, Tempered as required
- 4. Glazing Seal: Silicone bedding on interior, silicone bedding on exterior
- 5. Obscure "Frosted" glass as noted on Plans.

E. Hardware

- 1. Balance system: Coil spring block and tackle with nylon cord and fiber filled nylon clutch
- 2. Lock: zinc die-cast lock and keeper
 - a. Color: Satin Nickel
 - b. Extended Sizes: two locks
- 3. Lift
 - a. Color: Satin Nickel
 - b. Extended Sizes: two lifts
- 4. Sash Hanger: fixed upper sash only
 - a. Color: White,

F. Insect Screen

- 1. Factory-installed (removable): half screen or full screen
 - a. Standard screen mesh material: 18 x 16: Charcoal Fiberglass

2. Frame Color: Stone White

2.5 ACCESSORIES

- A. Installation Accessories: Package of installation hardware for operable units consisting of:
 - 1. Six #8 x 2" Torx® truss head installation screws
 - 2. Six jamb hole plugs
 - 3. One sash lift (two sash lifts on extended sizes)
 - 4. Two #7 x ³/₄" Phillips flat head screws (for sash lift) (Four screws on extended sizes)
 - 5. Keeper pile weather strip (EverWoodTM only) (two weather strip on extended sizes)
 - 6. EverWoodTM test strip (EverWoodTM only)
 - 7. Paint and Stain Instructions (EverWoodTM only)
- B. Sill Installation Filler
 - 1. 108' lengths
- C. Mulling Accessories
 - 1. Exterior mull cover
 - 2. Mull post
 - 3. Interior mull cover
 - 4. Shipping bracket assembly
 - 5. #10 x 1 1/8" screws
 - Foam block kit

2.6 GRILLES

- A. Full Divided Light Grilles: Fixed exterior and interior grilles with an anodized aluminum muntin bar, 1/2 inch (13 mm) wide, to match spacer within insulated glass unit where indicated on Drawings.
 - 1. Exterior Grille: Provide Fibrex® material exterior grilles where indicated on Drawings. Install grilles on exterior of glass with adhesive tape to simulate true divided light muntin bars in the following color:
 - a. Color: White.
 - 2. Interior grille: Provide profiled Fibrex® material grilles applied with adhesive tape to interior glass surface.
 - a. Color: White.
 - 3. Width: 1-1/8 inch (29 mm).
- B. Polyurethane Foam Insulation (Minimal Expansive): Single- or two-component, UL classified sealant, to insulate, seal, fill, and stop air infiltration; shall not expand to the point to cause pressure on window jambs.
 - 1. R-Value: ASTM C 518, not less than 4.0 per inch of thickness.
 - 2. Fire-Test-Response Characteristics: ASTM E 84, as follows:
 - a. Flame Spread: Not greater than 10.
 - b. Smoke Developed: Not greater than 20.
 - 3. Products:
 - a. Dow Chemical Company (The); Great Stuff PRO Window & Door.
 - b. Fomo Products Inc.; Handi-Seal Window and Door Sealant.
 - c. Convenience Products; No-Warp Foam Window & Door Insulating Sealant.

2.7 INSECT SCREENS

- A. Insect Screens: Provide venting sash with an insect screen at single-hung windows, including attachment hardware. Provide insect screens at all operable windows.
 - 1. Frames: Lower sash height 0.024 inch (0.61 mm) rolled aluminum frame with chromate conversion coating. Provide matching corner locks and latch retainers.
 - a. Insect Screen Cloth: 18 by 16 (1.0 by 1.1 mm) count per sq. inch aluminum mesh, gunmetal finish.
 - b. Frame Finish: High-bake polyester finish in the following color:
 - 1) Color: White.
 - c. Provide lift handles on screens in casement windows to permit easy removal for egress.

2.8 FABRICATION

- A. Preservative Treatment: Treat wood sash and frame members after machining with a water repellent preservative per WDMA I.S.4.
- B. A-Series Single-Hung Units, Gliders, Picture Units and Casement Units:
 - 1. Outer Frame: Fibrex material.
 - 2. Outer Frame: Extruded Fibrex material adhesively bonded corner keys.
 - 3. Sill: Fibrex material.
 - 4. Bond outer frame members and sill to wood base frame with adhesive.
 - 5. Jamb and Head Jamb Liners (Pine):
 - a. Side Jamb Liner: Solid pine filler attached to a rigid PVC vinyl extrusion.
 - b. Head Jamb Liner: Solid pine head parting stop and interior aesthetic filler with rigid PVC vinyl head liner.
 - 6. Sash Components:
 - a. Exterior Sash: Pultruded fiberglass material with adhesively bonded PVC corner keys.
 - b. Interior Sash: Pultruded fiberglass material with adhesively bonded PVC corner keys.
 - 7. Factory applied weatherstripping.
- C. Glazing: Factory glazed with glazing sealant.
- D. Weatherstripping: Factory-applied to unit frame. Field-applied interlocking weatherstripping at panel meeting stiles.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Site Verification of Conditions: Verify that site conditions are acceptable for installation of units, including the following:
 - 1. Rough openings are square, plumb, and dimensions are correct.
 - 2. Sill plates are level.
- B. Do not proceed with installation of units until unacceptable conditions are corrected.

3.2 INSTALLATION

A. General:

- 1. Comply with the instructions and recommendations of window manufacturer.
- 2. Remove unit components, parts, accessories, and installation guides from carton.
- 3. Inspect unit components and verify that components are not damaged and that parts are included before disposing of carton.
- 4. Multiple units shall be factory assembled.
- 5. Field-assemble multiple units that are too large for shipping before installation per manufacturer's installation guides.

B. Interface With Other Work:

- 1. Perform installation per Manufacturer's installation guides.
- 2. Install units level, plumb, square, true to line, without distortion, anchored securely in place to structural support, and in proper relation to wall flashing and other adjacent construction. Install drip cap at head of single units and joined assemblies.
- 3. Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials.
- 4. Install insulation in shim space around unit perimeter to maintain continuity of building insulation. Do not overfill.
- 5. Hold back exterior siding or other finish materials from edge of unit to allow for expansion and contraction and installation of proper joint sealant with backing materials. Seal perimeter of unit after exterior finish is applied per requirements of Division 07 "Joint Sealants" Section.
- 6. Finish interior units per requirements specified in related sections. Refer to, and comply with, additional requirements in manufacturer's installation guides.
- 7. Install optional hardware and unit accessories after cleaning.
- 8. Seal between perimeter of window and air/vapor barrier with continuous low-expanding foam sealant, approximately 1 inch in depth.

C. Site Tolerances:

1. Adjust operation, insect screens, hardware, and accessories for a tight fit at contact points and weatherstripping for smooth operation and weathertight closure.

3.3 CLEANING

- A. Clean units using cleaning material and methods specifically recommended by window manufacturer.
- B. Remove excess sealants, glazing materials, dirt, and other substances.
- C. Avoid damaging protective coatings and finishes.
- D. Remove debris from work site and properly dispose of debris.

3.4 PROTECTION

A. Protect installed work from damage due to subsequent construction activity on site.

END OF SECTION 085200

PART 1 - GENERAL

1.1 INTENT

- A. Provide insect screens to existing single hung windows.
- B. Contractor will take note that the major work includes the replacement of the insect screens. The minor work includes the correction of the installation and the age deficiencies that exist in the sash and frames. Some of the corrections will need to be addressed to achieve the minimum performance requirements of the contract documents.

1.2 SUBMITTALS

- A. PRODUCT DATA: Submit samples of material to be used with manufacturer's product literature for all replacement components to be installed in existing windows demonstrating compliance with specified requirements.
- B. SAMPLES: Submit full size operating samples of each replacement component required.
- C. MOCK-UP: Prior to contract awarding, the contractor of choice will be asked to do a mock-up of one window based on the contract documents. The test mock-up will be used as a basis of acceptability of quality of workmanship.
- D. All projects involving any on-site labor over \$50,000.00 is subject to Maine State Department of Labor Prevailing Rate Schedules. By accepting this project, you are agreeing to all applicable State and Federal Laws and Regulations, including the Maine State Department of Labor Prevailing Rate Schedule.

1.3 QUALITY ASSURANCE

- A. QUALIFICATIONS: Pre-qualifications for screen installation contractors. Contractors seeking to submit bids on this project must specialize in the screen manufacture and installation industry. Contractors must have the minimum qualifications.
 - 1. Contractors must have a minimum of three years, non-subcontracted labor, in screen installation.
 - 2. Contractor to submit list of 10 completed screen installation projects including names, addresses, phone numbers, and contact people.
 - 3. All on-site laborers must be OSHA-10 certified and current in their certifications.

1.4 WARRANTY

A. INSTALLER WARRANTY: Minimum of one (1) year warranty covering parts and labor on all completed insect screen construction units due to manufacturer defect.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. For convenience, details and specifications have been based on products by Architectural Screens/ Window Repair Systems, Inc. (800) 842-0974.

2.2 COMPONENTS

- A. Fiberglass fabric (insect): 18 x 16 mesh of 0.011" diameter charcoal fiberglass mesh screen cloth. Secure by vinyl spine to a nominal 5/16" x 1-1/8" x .055" wall thickness extruded tubular aluminum frame.
- B. Extruded tubular aluminum frame is to match the color of existing windows. Color is to be powdercoated and meet exterior conditions.
- C. Solid aluminum corners keys stamped into tubular aluminum frame; other corner key materials not acceptable.
- D. Provide and install replacement insect screens in existing tracks with mounting hardware at locations indicated by York School Department.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Remove lower sash if necessary.
- B. Clean debris from side styles, jambs, interlock, and sill dam.
- C. Install new insect screens.

END OF SECTION 085201

