


ARCHITECTURAL DESIGNS BY



896 Bangor Street
Hodgdon, Maine
04730-9422

e-mail rkervin@ainop.com
Cell Phone 207-538-6778
Tel 207-532-3247

NOTICE TO CONTRACTORS - ADDENDUM #1

May 16, 2019

PROJECT:

Gymnasium Maintenance Project
Project No. BREM 2954
NMCC, 33 Edgemont Drive
Presque Isle, Maine

GENERAL CONTRACTORS:

- 1) Rick Nadeau, A&L Construction, P.O. Box 1613, Presque Isle, Maine
- 2) Steve McHatten, PNM Construction, 104 Edgemont Drive, Presque Isle, Maine

SPECIFICATIONS:

SECTION 01 73 20

Selective Demolition

Work to be done by Others- **Not** part of Project Bid:

1. *Removal of bleachers, wall pads, lower curtain located in Northeast corner of Gymnasium and it's track.*

Other Items:

1. *No concrete block work to be removed in Training Room behind Electrical Panel PG. Electrician to utilize existing conduits to existing junction box located near ceiling joist for new electrical work and shall remove unused wires if found in existing conduits to be used by Electrical Contractor for this Project, as needed.*
2. *Contractor to remove **Existing Track** formerly used by Divider Curtain from bottom chord of ceiling joist for installation of new Divider Curtain track.*
3. *Prior to Work protect existing floor in Corridor from Gymnasium to Exit doors with Tyvek over 1/8" hardboard (4' x 8' sheets) taped to floor along path of travel. Provide same protection of Lobby floor for bleacher delivery thru Lobby doors to Gymnasium doors at Southeast corner of Gymnasium during day of bleacher delivery only.*

SECTION 03 30 20

Cast-in-Place Concrete & Concrete Block Work

REVISE:

PART 2-CONCRETE BLOCK WORK

1.2 Summary

- A. *Remove and replace existing block as needed for pump hose access for floor underlayment installation. No concrete block work required at Electrical Panel PG.*
- B. *Coordinate block removal time with Floor Underlayment Installers.*
- C. *New electrical wenchers for basketball backstops to be located on frame supports for each of the six (6) backstops. Upon removal of existing backstop manual wenchers and their wall mounts, patch anchor holes in concrete block prior to painting walls.*

SECTION 09 62 40

Polyurethane Floor System

PART 2-PRODUCTS

2.02 Manufacturers

ADD:

A. Contacts for price quote on Polyurethane Floor System and for ARDEX Premium Self-Leveling Underlayment SECTION 03 30 00 are Tony or John Carbone at American Sports Floors Tel# 781-871-0878, e-mail <Asfestimating@verizon.net>.

SECTION 09 91 00

Painting

Painting Work in this Section to be done by Others- Not part of Project Base Bid Amount:

ADD:

PART 3-EXECUTION

3.6 Coordination

General Contractor shall provide scheduling times available to Painting Contractor for any required or remaining finish painting or touch-up work prior to installation of new gymnasium floor.

SECTION 12 66 13

Telescopic Bleachers

PART 2-PRODUCTS

2.01 Manufacturers

ADD:

C. Contact person for price quote on Telescopic Bleachers and for Gymnasium Equipment SECTION 11 66 23 is Mike Ward at Tel# 603-341-6967 e-mail <mikeward@rhlco.com>.