

MARQUARDT BUILDING IMPROVEMENTS

ADDENDUM #2

June 11, 2020

The following items hereby modify, amend and supersede the plans and specifications dated May 14, 2020 for the above referenced project. The following items are hereby made part of the contract documents by reference and shall be as binding as though inserted in their entirety in the locations specified herein.

It shall be the responsibility of the Contractor to notify all Subcontractors and Suppliers proposed to be used for the various parts of the Work of any changes or modifications contained in this Addendum.

	Spec Section	Title	Description
2 - 1	21 10 00	Sprinklers	The service contractor for the existing system is PD Industries Inc. DBA Maine Fire Protection Services.
2 - 2	21 10 00	Sprinklers	Item 1.3.A.2: Delete this item in its entirety. A standpipe system is not required. Work is solely in the bathrooms themselves.
2 - 3	21 10 00	Sprinklers	Items 1.5.A + B: Submittals are not required. Provide documentation as required by the State Fire Marshal to the State Fire Marshal.
2 - 4	21 10 00	Sprinklers	The 2014 shop drawings issued with Addendum were for information only to show the locations of the risers. They are not part of the contract. Markups on them are only a record of directives to the 2014 sprinkler contractor.

	Drawing	Title	Description
2 - 5	A 1.1	Floor Plan	At Keyed Note #1 add the following sentence: "At each window apron, remove the apron to allow for tile removal and installation. Provide nailers behind to match thickness of tile and reinstall the removed apron. Patch and paint.

End of Addendum #2