

***SECTION 17: Wastewater Disposal***

Kingfish Maine proposes to construct an enclosed recirculating aquaculture system (RAS) facility with multiple buildings, together with adjunct facilities and equipment on a property at 9 Mason Bay Road in Jonesport. This facility comprises facilities for staff and residential accommodations for staff. Appended to this section are designs for system 1 and system 2, including Subsurface Wastewater Disposal Design Applications (HHE 200 form) for the proposed subsurface wastewater disposal systems designed by Natalie Marceau, Licensed Site Evaluator #411 and by William T. Lane, PE 7577 for the engineered system. This submission includes the applications and supporting documentation.

**APPENDIX 17A**  
WASTEWATER DISPOSAL SYSTEM 2 DESIGN

# SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Maine Dept. Health & Human Services  
Division of Health Engineering, 10 SHS  
(207) 287-2070 Fax: (207) 287-4172

PROPERTY LOCATION		>> CAUTION: LPI APPROVAL REQUIRED <<	
City, Town, or Plantation	JONESPORT	Town/City _____	Permit # _____
Street or Road	DUN GARVIN ROAD	Date Permit Issued ___/___/___	Fee: \$ _____ Double Fee Charged [ ]
Subdivision, Lot #		L.P.I. # _____	

OWNER/APPLICANT INFORMATION		Fee: \$ _____ state min fee \$ _____ Locally adopted fee copy [ ] Owner [ ] Town [ ] State	
Name (last, first, MI)	KINGFISH MAINE, INC.	The Subsurface Wastewater Disposal System shall not be installed until a Permit is issued by the Local Plumbing Inspector. The Permit shall authorize the owner or installer to install the disposal system in accordance with this application and the Maine Subsurface Wastewater Disposal Rules.	
Mailing Address of Owner/Applicant	33 SALMON FARM ROAD FRANKLIN, ME 04634		
Daytime Tel. #	(502) 387-8673	Municipal Tax Map # <u>8</u> Lot # <u>23</u>	

OWNER OR APPLICANT STATEMENT	CAUTION: INSPECTION REQUIRED
I state and acknowledge that the information submitted is correct to the best of my knowledge and understand that any falsification is reason for the Department and/or Local Plumbing Inspector to deny a Permit.	I have inspected the installation authorized above and found it to be in compliance with the Subsurface Wastewater Disposal Rules Application.
_____ Signature of Owner or Applicant      Date	_____ Local Plumbing Inspector Signature      (1st) date approved
	_____ (2nd) date approved

PERMIT INFORMATION		
<b>TYPE OF APPLICATION</b> <input checked="" type="checkbox"/> 1. First Time System <input type="checkbox"/> 2. Replacement System Type replaced: _____ Year installed: _____ <input type="checkbox"/> 3. Expanded System <input type="checkbox"/> a. <25% Expansion <input type="checkbox"/> b. ≥25% Expansion <input type="checkbox"/> 4. Experimental System <input type="checkbox"/> 5. Seasonal Conversion	<b>THIS APPLICATION REQUIRES</b> <input checked="" type="checkbox"/> 1. No Rule Variance <input type="checkbox"/> 2. First Time System Variance <input type="checkbox"/> a. Local Plumbing Inspector Approval <input type="checkbox"/> b. State & Local Plumbing Inspector Approval <input type="checkbox"/> 3. Replacement System Variance <input type="checkbox"/> a. Local Plumbing Inspector Approval <input type="checkbox"/> b. State & Local Plumbing Inspector Approval <input type="checkbox"/> 4. Minimum Lot Size Variance <input type="checkbox"/> 5. Seasonal Conversion Permit	<b>DISPOSAL SYSTEM COMPONENTS</b> <input checked="" type="checkbox"/> 1. Complete Non-engineered System <input type="checkbox"/> 2. Primitive System (graywater & alt. toilet) <input type="checkbox"/> 3. Alternative Toilet, specify: _____ <input type="checkbox"/> 4. Non-engineered Treatment Tank (only) <input type="checkbox"/> 5. Holding Tank, _____ gallons <input type="checkbox"/> 6. Non-engineered Disposal Field (only) <input type="checkbox"/> 7. Separated Laundry System <input type="checkbox"/> 8. Complete Engineered System (2000 gpd or more) <input type="checkbox"/> 9. Engineered Treatment Tank (only) <input type="checkbox"/> 10. Engineered Disposal Field (only) <input type="checkbox"/> 11. Pre-treatment, specify: _____ <input type="checkbox"/> 12. Miscellaneous Components
<b>SIZE OF PROPERTY</b> ± 93.2 <input type="checkbox"/> SQ. FT. <input checked="" type="checkbox"/> ACRES	<b>DISPOSAL SYSTEM TO SERVE</b> <input type="checkbox"/> 1. Single Family Dwelling Unit, No. of Bedrooms: _____ <input type="checkbox"/> 2. Multiple Family Dwelling, No. of Units: _____ <input checked="" type="checkbox"/> 3. Other: <u>STORE (BUILDING #12)</u> (specify) Current Use <input type="checkbox"/> Seasonal <input type="checkbox"/> Year Round <input checked="" type="checkbox"/> Undeveloped	<b>TYPE OF WATER SUPPLY</b> <input type="checkbox"/> 1. Drilled Well <input type="checkbox"/> 2. Dug Well <input type="checkbox"/> 3. Private PROPOSED PUBLIC DRILLED WELLS <input checked="" type="checkbox"/> 4. Public <input type="checkbox"/> 5. Other
<b>SHORELAND ZONING</b> <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		

DESIGN DETAILS (SYSTEM LAYOUT SHOWN ON PAGE 3)			
<b>TREATMENT TANK</b> <input checked="" type="checkbox"/> 1. Concrete <input checked="" type="checkbox"/> a. Regular <input type="checkbox"/> b. Low Profile <input type="checkbox"/> 2. Plastic <input type="checkbox"/> 3. Other: _____ CAPACITY: <u>1,500</u> GAL.	<b>DISPOSAL FIELD TYPE &amp; SIZE</b> <input type="checkbox"/> 1. Stone Bed <input type="checkbox"/> 2. Stone Trench <input checked="" type="checkbox"/> 3. Proprietary Device <input checked="" type="checkbox"/> a. cluster array <input type="checkbox"/> c. Linear <input checked="" type="checkbox"/> b. regular load <input type="checkbox"/> d. H-20 load <input type="checkbox"/> 4. Other: _____ SIZE: _____ <input type="checkbox"/> sq. ft. <input type="checkbox"/> lin. ft. type: <u>21 ELJEN GSF MODULES</u>	<b>GARBAGE DISPOSAL UNIT</b> <input checked="" type="checkbox"/> 1. No <input type="checkbox"/> 2. Yes <input type="checkbox"/> 3. Maybe If Yes or Maybe, specify one below: <input type="checkbox"/> a. multi-compartment tank <input type="checkbox"/> b. ___ tanks in series <input type="checkbox"/> c. increase in tank capacity <input checked="" type="checkbox"/> d. Filter on Tank Outlet	<b>DESIGN FLOW</b> <u>385</u> gallons per day BASED ON: <input type="checkbox"/> 1. Table 4A (dwelling unit(s)) <input checked="" type="checkbox"/> 2. Table 4C (other facilities) SHOW CALCULATIONS for other facilities 1 PUBLIC TOILET @ 325 GPD 5 EMPLOYEES @ 12 GPD PER EMPLOYEE
<b>SOIL DATA &amp; DESIGN CLASS</b> PROFILE <u>4</u> / <u>D</u> at Observation Hole # <u>1</u> Depth <u>12</u> " of Most Limiting Soil Factor	<b>DISPOSAL FIELD SIZING</b> <input checked="" type="checkbox"/> 1. Medium---2.6 sq. ft. / gpd <input type="checkbox"/> 2. Medium---Large 3.3 sq. ft. / gpd <input type="checkbox"/> 3. Large---4.1 sq. ft. / gpd <input type="checkbox"/> 4. Extra Large---5.0 sq. ft. / gpd	<b>EFFLUENT/EJECTOR PUMP</b> <input checked="" type="checkbox"/> 1. Not Required <input type="checkbox"/> 2. May Be Required <input type="checkbox"/> 3. Required Specify only for engineered systems DOSE: _____ gallons	<input type="checkbox"/> 3. Section 4G (meter readings) ATTACH WATER METER DATA LATITUDE AND LONGITUDE at center of disposal area Lat. <u>44</u> d <u>33</u> m <u>16.1</u> s Lon. <u>67</u> d <u>34</u> m <u>38.2</u> s if g.p.s, state margin of error: _____

SITE EVALUATOR STATEMENT		
I certify that on <u>2/10/21</u> (date) I completed a site evaluation on this property and state that the data reported are accurate and that the proposed system is in compliance with the State of Maine Subsurface Wastewater Disposal Rules (10-144A CMR 241).		
_____ Site Evaluator Signature	_____ SE #	_____ Date
Natalie Marceau (GARTLEY & DORSKY ENGINEERING & SURVEYING)	(207) 236-4365	nmarceau@gartleydorsky.com
Site Evaluator Name Printed	Telephone Number	E-mail Address

**Note: Changes to or deviations from the design should be confirmed with the Site Evaluator.**

HHE-200 Rev. 11/2013

**SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION**

Department of Human Services  
 Division of Health Engineering  
 (207) 287-5672 Fax: (207) 287-3165



Town, City, Plantation  
 JONESPORT

Street, Road, Subdivision  
 DUN GARVIN ROAD

Owner's Name  
 KINGFISH MAINE, INC.


**SITE PLAN** Scale 1" = 100 ft. or as shown

**SITE LOCATION PLAN**



±300' PUBLIC WELL SETBACK

THE PROPOSED DISPOSAL AREA CONSISTS OF 3 ROWS OF 7 ELJEN GEOTEXTILE SAND FILTER MODULES (TOTAL 21 MODULES). ROWS SHALL BE 1' APART AND INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.



**SOIL DESCRIPTION AND CLASSIFICATION (Location of Observation Holes Shown Above)**

Observation Hole  Test Pit  Boring  
 O " Depth of Organic Horizon Above Mineral Soil

Depth Below Mineral Soil Surface (inches)	Texture	Consistency	Color	Mottling
0	LOAM	FRIABLE	DARK BROWN	NONE
10	LOAMY SAND		STRONG BROWN	COMMON MEDIUM DISTINCT LIGHT OLIVE BROWN
20			LIGHT OLIVE BROWN	
30	BOTTOM OF TEST PIT			
40				
50				

Soil Classification	Slope	Limiting Factor	<input checked="" type="checkbox"/> Ground Water
4 D	±4 %	12 "	<input type="checkbox"/> Restrictive Layer
Profile Condition			<input type="checkbox"/> Bedrock
			<input type="checkbox"/> Pit Depth

Observation Hole  Test Pit  Boring  
 " Depth of Organic Horizon Above Mineral Soil

Depth Below Mineral Soil Surface (inches)	Texture	Consistency	Color	Mottling
0				
10				
20				
30				
40				
50				


Soil Classification	Slope	Limiting Factor	<input type="checkbox"/> Ground Water
Profile Condition	%	"	<input type="checkbox"/> Restrictive Layer
			<input type="checkbox"/> Bedrock
			<input type="checkbox"/> Pit Depth

*Natalie Marsau*  
 Site Evaluator Signature

411  
 SE #

3/1/21  
 Date

<b>SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION</b>		Department of Human Services Division of Health Engineering (207) 287-5672 Fax: (207) 287-3165
Town, City, Plantation JONESPORT	Street, Road, Subdivision DUN GARVIN ROAD	Owner's Name KINGFISH MAINE, INC.




<b>FILL REQUIREMENTS</b>	<b>CONSTRUCTION ELEVATIONS</b>	<b>ELEVATION REFERENCE POINT</b>
Depth of Fill (Upslope) 31"-35"	Finished Grade Elevation SEE SECTION-A	Location & Description: NAIL 56" ABOVE GRADE IN 9" BIRCH TREE
Depth of Fill (Downslope) 37"-41"	Top of Distribution Pipe or Proprietary Device SEE SECTION-A	Reference Elevation: 0"
	Bottom of Disposal Area SEE SECTION-A	

<b>DISPOSAL AREA CROSS SECTION</b>		<b>SCALE</b>
(SEE ATTACHED SECTION)		Horizontal 1" = N/A ft. Vertical 1" = N/A ft.
<b>DISTANCES:</b>		
<b>ELEVATION REFERENCE POINT (ERP):</b> NAIL 56" ABOVE GRADE IN 9" BIRCH TREE		
<b>REFERENCE POINT A.:</b> NAIL 39" ABOVE GRADE IN EMERA POLE # 121897		
ERP TO A: 13'-1"	REFERENCE POINT A TO A: 38'-5"	
ERP TO B: 32'-7"	REFERENCE POINT A TO B: 66'-2"	
ERP TO C: 24'-1"	REFERENCE POINT A TO C: 41'-6"	
ERP TO D: 38'-3"	REFERENCE POINT A TO D: 68'-1"	

<i>Natalie Marceau</i>	411	3/1/21	Page 3 of 4 HHE-200 Rev. 8/01
Site Evaluator Signature	SE #	Date	

# SECTION-A

## GEOTEXTILE SAND FILTER CROSS SECTION



THE SYSTEM CONSISTS OF 3 ROWS OF 7 MODULES PER ROW, EACH ROW SEPARATED BY 1 FOOT.

**GEOTEXTILE SAND FILTER NOTES:**

1. THIS SYSTEM COMPLIES WITH AND MUST BE INSTALLED IN ACCORDANCE WITH THE GEOTEXTILE SAND FILTER DESIGN MANUAL (BY ELJEN CORPORATION), AND ALL MAINE SUBSURFACE RULES.
2. INSTALLATION SHALL NOT TAKE PLACE WHEN THE GROUND IS FROZEN OR SATURATED.
3. TOPSOIL OR ORGANICS MUST BE REMOVED FROM LEACH FIELD AND FILL SLOPE EXTENSIONS PRIOR TO FILL PLACEMENT.
4. THE AREA UNDER THE DISPOSAL AREA MUST BE THOROUGHLY SCARIFIED BY ROTOTILLER, HARROW OR BACKHOE TEETH. THE SOIL SHOULD BE BROKEN UP TO A DEPTH OF 6 INCHES.
5. THERE SHALL BE 4" MINIMUM TRANSITIONAL HORIZON BETWEEN BACKFILL AND THE NATURAL SOIL WHICH IS A MIXTURE OF BACKFILL AND NATURAL SOIL. THE TRANSITIONAL HORIZON SHALL BE UNDER THE DISPOSAL SYSTEM AND EXTEND FROM FILL EXTENSION TO FILL EXTENSION.
6. THE 6" SAND LAYER BELOW THE MODULES SHALL BE MEDIUM TO COARSE SAND MEETING ASTM C33 SPECIFICATIONS. FOR COMPLETE SPECIFICATIONS SEE GEOTEXTILE SAND FILTER DESIGN MANUAL.
7. BACKFILL SHALL BE GRAVELLY COARSE SAND AND SHALL MEET SPECIFICATIONS OF TABLE 11A OF THE SUBSURFACE RULES.
8. ANY SYSTEM WHICH IS MORE THAN 18" BELOW FINISHED GRADE AS MEASURED FROM THE TOP OF THE MODULES SHALL BE VENTED.
9. FINAL GRADES SHALL BE LOAMED (4" MIN), MULCHED AND SEEDED.
10. SINGLE FAMILY DWELLINGS SHALL HAVE ACCESS OPENINGS FOR SEPTIC TANKS WITHIN 6 INCHES OF FINISHED GRADE AND BE WATERTIGHT, PER SECTION 6F(2) OF THE SUBSURFACE CODE. ALL OTHER FACILITIES SHALL HAVE ACCESS OPENINGS FOR TREATMENT TANKS AND PUMP STATION LOCATED AT FINISHED GRADE AND HAVE A WATER TIGHT RISER OF THE SAME MATERIALS AS THE TREATMENT TANK OR PUMP STATION. H-20 CONSTRUCTION IS REQUIRED IN TRAFFIC AREAS. SEE SECTION 6F(3) OF THE SUBSURFACE CODE.
11. THE DRILLING OF ANY WELL SHALL BE A MINIMUM OF 50' FROM ANY WATER TIGHT SEPTIC TANK AND 100' FROM ANY LEACH FIELD.
12. THIS SYSTEM IS NOT DESIGNED FOR BACKWASH FROM ANY WATER TREATMENT SYSTEM OR TO BE DRIVEN ON.

### ELEVATIONS

ELEV. REF. PT. (ERP)	0"		
	ROW 1	ROW 2	ROW 3
FINISHED GRADE	-25"	-25"	-25"
TOP OF IN-DRAIN UNIT	-37"	-37"	-37"
BOTTOM OF IN-DRAIN UNIT	-44"	-44"	-44"
BOTTOM OF SAND	-50"	-50"	-50"

SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Owner/Applicant: KINGFISH MAINE, INC.

Town: JONESPORT

Street: DUN GARVIN ROAD

Detail Scale: 1" = 5'

**Gartley & Dorsky**  
ENGINEERING SURVEYING

59B Union Street P.O. Box 1031 Camden, ME 04843-1031  
Ph (207) 236-4365 Fax (207) 236-3055 Toll Free 1-888-282-4365  
165 Main Street Suite 2F P.O. Box 1072 Damariscotta, Maine 04543  
Ph. (207) 790-5005

*Natalie Marzouk*

Site Evaluator Signature

411

SE #

3/1/21

Date

S-1

Page 4 of 4

HHE-200 Rev. 8/01

**APPENDIX 17B**  
WASTEWATER DISPOSAL SYSTEM 1 DESIGN



**Maine Department of Health and Human Services  
Division of Environmental Health  
Subsurface Wastewater Program**

**APPLICATION FOR ENGINEERED  
SUBSURFACE WASTEWATER DISPOSAL SYSTEM**

Please complete the following Sections. Please print or type.

**Applicant/Owner**

Company Name: Kingfish Maine, Inc.

Contact Person: Megan Sorby

Address: 33 Salmon Farm Road

Town/City: Franklin State/Province: ME Zip/Postal Code: 04634

Country: Washington

Telephone: (502) 387-8673 Fax: \_\_\_\_\_

e-mail: m.sorby@kingfish-maine.com

**Design Engineer**

Company Name: Gartley & Dorsky Engineering & Surveying

Contact Person: William Lane

Address: PO Box 1031

Town/City: Camden State: ME Zip Code: 04843

Telephone: (207) 236-4365 Fax: (207) 236-3055

e-mail: blane@gartleydorsky.com

**1. Property Location**

Town/City: Jonesport County: Washington

Tax Map and Lot Number: Map 8 Lot 23

Attach as **“Exhibit A”** a copy of the relevant section of the USGS 7.5’ topographic map, if available, or 15’ topographic map showing the location of the proposed engineered disposal system.



## 2. Project Description

Provide a brief written description of the proposal. Use a separate sheet if necessary.

Kingfish Maine, Inc. proposes to develop a land-based recirculating aquaculture system to grow Dutch Yellowtail at a 93 acre property on Mason Bay Road in Jonesport, Maine. The proposed engineered septic design serves 16 bedrooms for residential units and up to 128 employees. The design includes four 4000-gallon septic tanks (totaling 12000 gallons of tank compacity).

---

## 3. Design Flow

The design flow for this project is: 4000 gallons per day. Provide design flow calculations and assumptions used in the calculations. Use a separate sheet if necessary.

16 bedroom (within 4 buildings) at 90gpd per bedroom = 1440gpd;

128 employees (with shower) at 20gpd per employee = 2560 gpd

---

---

---

---

## 4. Mounding Analysis

Submit as “**Exhibit B**” an analysis of the proposed system design showing that there is adequate vertical separation between the bottom of the disposal field and any mounded water table. Include all calculations and assumptions used.

## 5. Transmissivity Analysis

Submit as “**Exhibit C**” an analysis of the proposed system design showing that there are sufficient suitable soils down-gradient to prevent the effluent from surfacing within 50 feet of the disposal field. Include all calculations and assumptions used.

## 6. HHE-200 and Variance Form(s)

Submit as “**Exhibit D**” a complete HHE-200 Form, and variance forms if applicable, signed by a Professional Engineer. The design engineer may reference associated plans and soil test pit logs on pages 2 and 3 of the HHE-200 Form.

This project requires:

- a First Time System Variance to the Maine Subsurface Wastewater Disposal Rules.
- a Replacement System Variance to the Maine Subsurface Wastewater Disposal Rules.
- no variance to the Maine Subsurface Wastewater Disposal Rules.

## 7. Operations and Maintenance Manual

Submit as “**Exhibit E**” an operations and maintenance manual for the owner with written recommendations for the operation and maintenance of the system, including inspection schedules, pumping schedules, and record keeping procedures.

**8. Soil and Site Conditions**

Submit as "Exhibit F" soil test pit logs prepared by a licensed Site Evaluator. The test pits shall be of sufficient number to accurately describe the site conditions under the proposed disposal area and the down gradient fill extension.

**9. Plans**

Submit as "Exhibit G" plans for the proposed engineered disposal system meeting provisions of Section 1102 of the Maine Subsurface Wastewater Disposal Rules. Two sets of plans are required, or one set of plans and one set of copies no larger than 11" x 17". Plans may be submitted for review purposes on a floppy disk or compact disc in *AutoDesk* AUTOCAD \*.dwg format (rev. 14 or lower), but a signed and stamped hard copy will be required upon final approval.


The plans shall also specify the latitude and longitude of the center of the disposal area(s), expressed as degrees, minutes, and seconds. If this data is obtained from an electronic GIS device, provide the device's margin of error.

**10. Review Fee**

Submit a check or money order in the amount of \$100.00 U.S. made payable to the Treasurer of the State of Maine.

I, William Lane, am the design engineer for the subject design.  
(print name)

I state that the information submitted is correct to the best of my knowledge and understand that any falsification is reason for the Department to deny the project.

  
\_\_\_\_\_  
Signature of Design Engineer

7877  
\_\_\_\_\_  
P.E. License Number

3/29/21  
\_\_\_\_\_  
Date

**Please note: To ensure a timely review of the project, make sure that the application is complete when submitted to the Division of Health Engineering.**

**Incomplete applications can not be processed, and will be returned to the design engineer for completion, unprocessed.**

**EXHIBIT A**

**Topographic Location Map**



**EXHIBIT B & C**

**Mounding Analysis & Transmissivity Analysis**

March 20, 2021

Megan Sorby  
Tom Sorby  
Kingfish Maine, Inc.  
33 Salmon Farm Road  
Franklin, ME 04

**RE: Subsurface Wastewater Disposal System 1 – Mounding Analysis                      Project 2019-412**  
**Kingfish Maine RAS Facility**

Dear Megan and Tom:

We have completed a Mounding Analysis for the proposed primary wastewater disposal system at Kingfish Maine in Jonesport, Maine. The proposed system is are designated as Disposal Field 1 on the site plan enclosed. We also include copies of test pit logs with soil profile information.

The design flow for the systems is 4,000 gallons per day (gpd) which will be split between two discrete sections of the disposal field. The disposal fields sections are each 31 X 56 feet in size and utilize Eljen GSF standard modules arranged in 8 rows of 14 modules (total 224 units).

The mounding calculations are derived from the United States Geological Survey (USGS) Scientific Investigation Report 2010-5102. The analytical model is based on a Solution to the Hantush Equation (1967).

Input parameters to the model include recharge rate, specific yield, initial saturated thickness of the aquifer, field size, time and horizontal hydraulic conductivity. The values used for each input parameter are as follows:

The per field recharge rate is 0.154 feet per day based on 2,000 gpd (267 cubic feet per day) design flow and a field size of 1,736 square feet. The recharge rate is considered constant. If actual design flow is less, mounding predictions would be lower than predicted.

Specific yield is 0.26 (dimensionless) and reflects the ability of a soil to drain water and is a ratio of the volume of water that drains from a unit volume of the soil compared to the volume of soil. Reference values were derived from US Department of the Interior Geological Survey Water Supply Paper 1662-D.

Initial saturated thickness of the aquifer is on the order of 22 feet. These values are derived from the exploration data. Test pits (Nos. 16 to 21) encountered no limiting bedrock condition at depths of 34". In the adjacent geotechnical investigation's boring (B15), depth to bedrock in field was generally greater than 23 feet. In general, overburden in this section of the property is consistent with this finding. As a result, overburden is conservatively assigned to be 20 feet thick in the vicinity of the disposal field.

Test pit logs indicate variable depths to mottling (seasonal high water table) of 12 inches below ground surface. For mounding calculations, a depth to water table of 12 inches below ground surface (bgs) was assigned. Given a conservative overburden of 20 feet, an initial saturated thickness of 19 feet was used. A thicker overburden would result in less predicted mounding.

Field size is 56 X 31 feet. Time was set at 365 days (1 year). A 1-year timeframe allow sufficient time for the system to achieve a steady state.

Horizontal hydraulic Conductivity was varied between 1 and 10 feet per day as a sensitivity analysis of the predicted mounding values. Hydraulic conductivity of the material underlying the disposal field is the primary factor controlling the predicted height of the mound. As such, multiple sources of information were reviewed to develop an estimate of hydraulic conductivity. The model uses a 10:1 ratio of horizontal to vertical permeability.

Hydraulic conductivity values published in Groundwater and Wells, Second Edition, Driscoll, 1986 (Figure 5.14) were largely derived from water well testing data and are considered to represent horizontal hydraulic conductivity values for a range of geologic materials. Values of 3 to 30 feet per day overlap the descriptions of Glacial Till and fine Sand. Medium to coarse sand values are considerably higher.

Review of the test pits and boring indicate that for sizing purposes a profile 5D soil was used. In the geotechnical report, the native material is characterized as fluvial soils consisting of loose to dense sand and gravel with varying portions of silt. From a soil series perspective, the NRCS soil survey indicates the material is Kinsman sand. Published Ksat values are reported as moderately high to very high: 1.42 to 14.17 in/hr (2.8 to 28.3). More conservative published information for sands list "permeability" as 5 cm per hour (~4 feet per day). These values are likely partially derived from laboratory testing. Values may be biased to a vertical permeability related to infiltration of water vertically through the soil. For model input, these values appear to be applicable to vertical hydraulic conductivity values. Factored scaling for horizontal conductivity will be employed as enumerated in the protocol basis.

Simulations were run using horizontal hydraulic conductivity values of 30, 10 and 5 feet per day to assess the variation in predicted mounding. Other model parameters remained fixed in each of the simulations.

- Using a horizontal hydraulic conductivity of 30 feet per day (corresponding vertical hydraulic conductivity of 3 feet per day) and the most conservative thickness of overburden results in a predicted groundwater mound of approximately 0.35 feet above the initial groundwater level at the center of the disposal field.
- Similarly, using a horizontal hydraulic conductivity of 10 feet per day (corresponding vertical hydraulic conductivity of 1 foot per day), results in a predicted groundwater mound of approximately .9 feet above the initial groundwater level at the center of the disposal field.
- Using a horizontal hydraulic conductivity of 5 feet per day (corresponding vertical hydraulic conductivity of 0.5 feet per day), results in a very conservative predicted groundwater mound of approximately 1.55 feet above the initial groundwater level at the center of the disposal field.

Based on available information and interpretations of site conditions, the simulation using 30 feet per day as a horizontal hydraulic conductivity reasonably represents conditions for disposal field 1 to account for mounding effects and potential overlap of mounding effects between the adjacent fields. Subsurface rules require separations to seasonal groundwater, which in this instance control. In conformance with the subsurface rules, the Table 4F minimum 24 inch vertical separation must be maintained between the Seasonal High Water Table and Eljen InDrain units.

Very truly yours,  
**Gartley & Dorsky, Engineering & Surveying Inc.**

A handwritten signature in black ink, appearing to read 'W. T. Lane', with a large, stylized flourish at the end.

William T. Lane, P.E.  
Vice President

enclosure: Hantush spreadsheets



This spreadsheet will calculate the height of a groundwater mound beneath a stormwater infiltration basin. More information can be found in the U.S. Geological Survey Scientific Investigations Report 2010-5102 "Simulation of groundwater mounding beneath hypothetical stormwater infiltration basins".

The user must specify infiltration rate (R), specific yield (Sy), horizontal hydraulic conductivity (Kh), basin dimensions (x, y), duration of infiltration period (t), and the initial thickness of the saturated zone (hi(0)), height of the water table if the bottom of the aquifer is the datum). For a square basin the half width equals the half length (x = y). For a rectangular basin, if the user wants the water-table changes perpendicular to the long side, specify x as the short dimension and y as the long dimension. Conversely, if the user wants the values perpendicular to the short side, specify y as the short dimension, x as the long dimension. All distances are from the center of the basin. Users can change the distances from the center of the basin at which water-table aquifer thickness are calculated.

Cells highlighted in yellow are values that can be changed by the user. Cells highlighted in red are output values based on user-specified inputs. **The user MUST click the blue "Re-Calculate Now" button each time ANY of the user-specified inputs are changed** otherwise necessary iterations to converge on the correct solution will not be done and values shown will be incorrect. Use consistent units for all input values (for example, feet and days)

**Input Values**

0.1540	R
0.260	Sy
5.00	K
28.000	x
15.500	y
365.000	t
19.000	hi(0)

use consistent units (e.g. feet & days or inches & hours)

**Recharge (infiltration) rate (feet/day)**  
**Specific yield, Sy (dimensionless, between 0 and 1)**  
**Horizontal hydraulic conductivity, Kh (feet/day)\***  
**1/2 length of basin (x direction, in feet)**  
**1/2 width of basin (y direction, in feet)**  
**duration of infiltration period (days)**  
**initial thickness of saturated zone (feet)**

**Conversion Table**

inch/hour	feet/day
0.67	1.33
2.00	4.00
hours	days
36	1.50

In the report accompanying this spreadsheet (USGS SIR 2010-5102), vertical soil permeability (ft/d) is assumed to be one-tenth horizontal hydraulic conductivity (ft/d).

20.547	h(max)
1.547	Δh(max)


**maximum thickness of saturated zone (beneath center of basin at end of infiltration period)**  
**maximum groundwater mounding (beneath center of basin at end of infiltration period)**

Ground-water Mounding, in feet  
 Distance from center of basin in x direction, in feet

1.547	0
1.451	20
1.238	40
1.138	50
1.054	60
0.986	70
0.927	80
0.876	90
0.830	100
0.752	120



**Re-Calculate Now**



**Disclaimer**

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

This spreadsheet will calculate the height of a groundwater mound beneath a stormwater infiltration basin. More information can be found in the U.S. Geological Survey Scientific Investigations Report 2010-5102 "Simulation of groundwater mounding beneath hypothetical stormwater infiltration basins".

The user must specify infiltration rate (R), specific yield (Sy), horizontal hydraulic conductivity (Kh), basin dimensions (x, y), duration of infiltration period (t), and the initial thickness of the saturated zone (hi(0)), height of the water table if the bottom of the aquifer is the datum). For a square basin the half width equals the half length (x = y). For a rectangular basin, if the user wants the water-table changes perpendicular to the long side, specify x as the short dimension and y as the long dimension. Conversely, if the user wants the values perpendicular to the short side, specify y as the short dimension, x as the long dimension. All distances are from the center of the basin. Users can change the distances from the center of the basin at which water-table aquifer thickness are calculated. Cells highlighted in yellow are values that can be changed by the user. Cells highlighted in red are output values based on user-specified inputs. **The user MUST click the blue "Re-Calculate Now" button each time ANY of the user-specified inputs are changed** otherwise necessary iterations to converge on the correct solution will not be done and values shown will be incorrect. Use consistent units for all input values (for example, feet and days)

Input Values		use consistent units (e.g. feet & days or inches & hours)	Conversion Table		
			inch/hour	feet/day	
0.1540	R	Recharge (infiltration) rate (feet/day)	0.67	1.33	
0.260	Sy	Specific yield, Sy (dimensionless, between 0 and 1)			
10.00	K	Horizontal hydraulic conductivity, Kh (feet/day)*	2.00	4.00	In the report accompanying this spreadsheet (USGS SIR 2010-5102), vertical soil permeability (ft/d) is assumed to be one-tenth horizontal hydraulic conductivity (ft/d).
28.000	x	1/2 length of basin (x direction, in feet)			
15.500	y	1/2 width of basin (y direction, in feet)	hours	days	
365.000	t	duration of infiltration period (days)	36	1.50	
19.000	hi(0)	initial thickness of saturated zone (feet)			
19.862	h(max)	maximum thickness of saturated zone (beneath center of basin at end of infiltration period)			
0.862	Δh(max)	maximum groundwater mounding (beneath center of basin at end of infiltration period)			


Ground-water Mounding, in feet

Distance from center of basin in x direction, in feet

0.862	0
0.822	20
0.732	40
0.686	50
0.644	60
0.608	70
0.578	80
0.552	90
0.529	100
0.489	120



Re-Calculate Now



### Disclaimer

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

This spreadsheet will calculate the height of a groundwater mound beneath a stormwater infiltration basin. More information can be found in the U.S. Geological Survey Scientific Investigations Report 2010-5102 "Simulation of groundwater mounding beneath hypothetical stormwater infiltration basins".

The user must specify infiltration rate (R), specific yield (Sy), horizontal hydraulic conductivity (Kh), basin dimensions (x, y), duration of infiltration period (t), and the initial thickness of the saturated zone (hi(0)), height of the water table if the bottom of the aquifer is the datum). For a square basin the half width equals the half length (x = y). For a rectangular basin, if the user wants the water-table changes perpendicular to the long side, specify x as the short dimension and y as the long dimension. Conversely, if the user wants the values perpendicular to the short side, specify y as the short dimension, x as the long dimension. All distances are from the center of the basin. Users can change the distances from the center of the basin at which water-table aquifer thickness are calculated. Cells highlighted in yellow are values that can be changed by the user. Cells highlighted in red are output values based on user-specified inputs. **The user MUST click the blue "Re-Calculate Now" button each time ANY of the user-specified inputs are changed** otherwise necessary iterations to converge on the correct solution will not be done and values shown will be incorrect. Use consistent units for all input values (for example, feet and days)

Input Values		use consistent units (e.g. feet & days or inches & hours)	Conversion Table	
			inch/hour	feet/day
0.1540	R	Recharge (infiltration) rate (feet/day)	0.67	1.33
0.260	Sy	Specific yield, Sy (dimensionless, between 0 and 1)		
30.00	K	Horizontal hydraulic conductivity, Kh (feet/day)*	2.00	4.00
28.000	x	1/2 length of basin (x direction, in feet)		
15.500	y	1/2 width of basin (y direction, in feet)	hours	days
365.000	t	duration of infiltration period (days)	36	1.50
19.000	hi(0)	initial thickness of saturated zone (feet)		

19.350	h(max)	maximum thickness of saturated zone (beneath center of basin at end of infiltration period)
0.350	Δh(max)	maximum groundwater mounding (beneath center of basin at end of infiltration period)


Ground-water Mounding, in feet

Distance from center of basin in x direction, in feet

0.350	0
0.344	20
0.326	40
0.315	50
0.304	60
0.293	70
0.283	80
0.274	90
0.266	100
0.252	120



Re-Calculate Now



**Disclaimer**

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

**EXHIBIT D**

**HHE200 Form**

# SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Maine Dept. Health & Human Services  
 Division of Health Engineering, 10 SHS  
 (207) 287-2070 Fax: (207) 287-4172

PROPERTY LOCATION		>> CAUTION: LPI APPROVAL REQUIRED <<	
City, Town, or Plantation	JONESPORT	Town/City _____	Permit # _____
Street or Road	DUN GARVIN ROAD	Date Permit Issued ___/___/___	Fee: \$ _____ Double Fee Charged [ ]
Subdivision, Lot #			L.P.I. # _____


OWNER/APPLICANT INFORMATION		Fee: \$ _____ state min fee \$ _____ Locally adopted fee copy [ ] Owner [ ] Town [ ] State  The Subsurface Wastewater-Disposal System shall not be installed until a Permit is issued by the Local Plumbing Inspector. The Permit shall authorize the owner or installer to install the disposal system in accordance with this application and the Maine Subsurface Wastewater Disposal Rules.
Name (last, first, MI)	KINGFISH MAINE, INC.	
Mailing Address of Owner/Applicant	33 SALMON FARM ROAD FRANKLIN, ME 04634	
Daytime Tel. #	(502) 387-8673	
		Municipal Tax Map # <u>8</u> Lot # <u>23</u>

OWNER OR APPLICANT STATEMENT	CAUTION: INSPECTION REQUIRED
I state and acknowledge that the information submitted is correct to the best of my knowledge and understand that any falsification is reason for the Department and/or Local Plumbing Inspector to deny a Permit.  _____ Signature of Owner or Applicant      Date	I have inspected the installation authorized above and found it to be in compliance with the Subsurface Wastewater Disposal Rules Application.  _____ Local Plumbing Inspector Signature      (1st) date approved  _____ (2nd) date approved

PERMIT INFORMATION		
<b>TYPE OF APPLICATION</b> <input checked="" type="checkbox"/> 1. First Time System <input type="checkbox"/> 2. Replacement System Type replaced: _____ Year installed: _____ <input type="checkbox"/> 3. Expanded System <input type="checkbox"/> a. <25% Expansion <input type="checkbox"/> b. ≥25% Expansion <input type="checkbox"/> 4. Experimental System <input type="checkbox"/> 5. Seasonal Conversion	<b>THIS APPLICATION REQUIRES</b> <input checked="" type="checkbox"/> 1. No Rule Variance <input type="checkbox"/> 2. First Time System Variance <input type="checkbox"/> a. Local Plumbing Inspector Approval <input type="checkbox"/> b. State & Local Plumbing Inspector Approval <input type="checkbox"/> 3. Replacement System Variance <input type="checkbox"/> a. Local Plumbing Inspector Approval <input type="checkbox"/> b. State & Local Plumbing Inspector Approval <input type="checkbox"/> 4. Minimum Lot Size Variance <input type="checkbox"/> 5. Seasonal Conversion Permit	<b>DISPOSAL SYSTEM COMPONENTS</b> <input type="checkbox"/> 1. Complete Non-engineered System <input type="checkbox"/> 2. Primitive System (graywater & alt. toilet) <input type="checkbox"/> 3. Alternative Toilet, specify: _____ <input type="checkbox"/> 4. Non-engineered Treatment Tank (only) <input type="checkbox"/> 5. Holding Tank, _____ gallons <input type="checkbox"/> 6. Non-engineered Disposal Field (only) <input type="checkbox"/> 7. Separated Laundry System <input checked="" type="checkbox"/> 8. Complete Engineered System (2000 gpd or more) <input type="checkbox"/> 9. Engineered Treatment Tank (only) <input type="checkbox"/> 10. Engineered Disposal Field (only) <input type="checkbox"/> 11. Pre-treatment, specify: _____ <input type="checkbox"/> 12. Miscellaneous Components
<b>SIZE OF PROPERTY</b> ± 93.2 <input type="checkbox"/> SQ. FT. <input checked="" type="checkbox"/> ACRES	<b>DISPOSAL SYSTEM TO SERVE</b> <input type="checkbox"/> 1. Single Family Dwelling Unit, No. of Bedrooms: _____ <input checked="" type="checkbox"/> 2. Multiple Family Dwelling, No. of Units: <u>4</u> <input checked="" type="checkbox"/> 3. Other: <u>AQUACULTURE</u> (TOTAL 16 BEDROOMS) (specify) Current Use <input type="checkbox"/> Seasonal <input type="checkbox"/> Year Round <input checked="" type="checkbox"/> Undeveloped	<b>TYPE OF WATER SUPPLY</b> <input checked="" type="checkbox"/> 1. Drilled Well <input type="checkbox"/> 2. Dug Well <input type="checkbox"/> 3. Private <input checked="" type="checkbox"/> 4. Public <input type="checkbox"/> 5. Other <b>PROPOSED</b>

DESIGN DETAILS (SYSTEM LAYOUT SHOWN ON PAGE 3)			
<b>TREATMENT TANK</b> <input checked="" type="checkbox"/> 1. Concrete <input checked="" type="checkbox"/> a. Regular (3) 4,000 GAL <input type="checkbox"/> b. Low Profile <input type="checkbox"/> 2. Plastic <input type="checkbox"/> 3. Other: _____ CAPACITY: <u>2,000</u> GAL.	<b>DISPOSAL FIELD TYPE &amp; SIZE</b> <input type="checkbox"/> 1. Stone Bed <input type="checkbox"/> 2. Stone Trench <input checked="" type="checkbox"/> 3. Proprietary Device <input type="checkbox"/> a. cluster array <input type="checkbox"/> c. Linear <input checked="" type="checkbox"/> b. regular load <input type="checkbox"/> d. H-20 load <input type="checkbox"/> 4. Other: _____ SIZE: _____ <input type="checkbox"/> sq. ft. <input type="checkbox"/> lin. ft. type: <u>224 ELJEN GSF MODULES</u>	<b>GARBAGE DISPOSAL UNIT</b> <input checked="" type="checkbox"/> 1. No <input type="checkbox"/> 2. Yes <input type="checkbox"/> 3. Maybe If Yes or Maybe, specify one below: <input type="checkbox"/> a. multi-compartment tank <input type="checkbox"/> b. _____ tanks in series <input type="checkbox"/> c. increase in tank capacity <input checked="" type="checkbox"/> d. Filter on Tank Outlet <b>EFFLUENT/EJECTOR PUMP</b> <input type="checkbox"/> 1. Not Required <input type="checkbox"/> 2. May Be Required <input checked="" type="checkbox"/> 3. Required Specify only for engineered systems DOSE: _____ gallons	<b>DESIGN FLOW</b> <u>4000</u> gallons per day BASED ON: <input checked="" type="checkbox"/> 1. Table 4A (dwelling unit(s)) <input checked="" type="checkbox"/> 2. Table 4C (other facilities) SHOW CALCULATIONS for other facilities 16 BEDROOM (4 UNITS) @ 90 GPD 28 EMPLOYEES WITH SHOWER @ 20 GPD PER EMPLOYEE  <input type="checkbox"/> 3. Section 4G (meter readings) ATTACH WATER METER DATA LATITUDE AND LONGITUDE at center of disposal area Lat. <u>44</u> d <u>33</u> m <u>19.9</u> s Lon. <u>67</u> d <u>34</u> m <u>18.0</u> s if g.p.s, state margin of error: _____
<b>SOIL DATA &amp; DESIGN CLASS</b> PROFILE CONDITION <u>5 / D</u> at Observation Hole # <u>16-21</u> Depth <u>12</u> " of Most Limiting Soil Factor			

SITE EVALUATOR STATEMENT		
I certify that on <u>11/23/20</u> (date) I completed a site evaluation on this property and state that the data reported are accurate and that the proposed system is in compliance with the State of Maine Subsurface Wastewater Disposal Rules (10-144A CMR 241).		
_____ Site Evaluator Signature	_____ SE #	_____ Date
Natalie Marceau (GARTLEY & DORSKY ENGINEERING & SURVEYING)	(207) 236-4365	nmarceau@gartleydorsky.com
Site Evaluator Name Printed	Telephone Number	E-mail Address
Note: Changes to or deviations from the design should be confirmed with the Site Evaluator.		

<b>SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION</b>		Department of Human Services Division of Health Engineering (207) 287-5672 Fax: (207) 287-3165
Town, City, Plantation JONESPORT	Street, Road, Subdivision DUN GARVIN ROAD	Owner's Name KINGFISH MAINE, INC.
<b>SUBSURFACE WASTEWATER DISPOSAL PLAN</b>		SCALE: 1" = _____ FT.
SEE CIVIL SITE PLAN		
<b>FILL REQUIREMENTS</b> Depth of Fill (Upslope) _____ Depth of Fill (Downslope) _____	<b>CONSTRUCTION ELEVATIONS</b> Finished Grade Elevation _____ Top of Distribution Pipe or Proprietary Device _____ Bottom of Disposal Area _____	<b>ELEVATION REFERENCE POINT</b> Location & Description: _____ Reference Elevation: _____
<b>DISPOSAL AREA CROSS SECTION</b>		<b>SCALE</b> Horizontal 1" = _____ ft. Vertical 1" = _____ ft.
SEE ATTACHED DETAIL SHEET		
 Site Evaluator Signature	411 SE #	3/25/21 Date

**EXHIBIT E**

**Operations & Maintenance Manual**

*KINGFISH MAINE*  
*Engineered Septic System*  
*Operation and Maintenance Manual*

**ENGINEERED SEPTIC SYSTEM MAINTENANCE**

Septic system 1 collects, distributes, and disposes of wastewater from the Kingfish Maine RAS Facility in Jonesport, Maine. This manual addresses the maintenance of the engineered septic system. Please refer to the Construction Plans, Sections and Details and the HHE 200 forms for this system.

**PART 1: RESPONSIBILITY FOR MAINTENANCE**

The Owner of the property, Kingfish Maine, Inc, is responsible for inspecting and maintaining the engineered septic system. For the purposes of this maintenance plan, the term ‘owner’ will be used for the responsible entity/entities accordingly. All components of the septic system must be kept in good working order. All specified maintenance must be completed by the designated party, and any/all cleaning and repair must be completed immediately upon detection.

**PART 2: MAINTENANCE**

The following tasks must be completed on a regular basis to maintain the system and fulfill the warranty requirements:

- **Septic Tanks**  
The three septic tanks (tanks 1-1 through 1-3) as shown on the plan should be inspected annually by a licensed septic waste removal contractor. The tanks should be pumped if the sludge in the bottom of the tank exceeds one foot in thickness.
- **Distribution Boxes, Distribution Chamber, Pump Station, Manholes**  
The distribution boxes, distribution chamber, pump station, and manholes should be inspected on an annual basis by the owner to make certain they are in good working order. These components should be cleaned, as needed.
- **Septic Tank Filter**  
The filters at the septic tank should be inspected on a quarterly basis by the owner. The filter should be cleaned on an annual basis, either by the owner or a licensed contractor.
- **Field Perimeter**  
The perimeter of leachfields 1A and 1B should be inspected at times of high usage, by the owner, to confirm that no breakthrough has occurred in the fill slope.
- **Risers for System Components**  
Risers to the septic tanks, pump chambers and distribution chambers should be inspected quarterly by the owner to determine if groundwater is infiltrating the system.
- **Plugs in Wastewater lines**  
Records should be kept of wastewater lines that become plugged. The cleanout that was used to access the plugged line and what was found in the line should be recorded whenever a line is plugged.

A record of inspections and maintenance or corrective measures (Part 3) shall be kept by the owner.



*KINGFISH MAINE*  
*Engineered Septic System*  
*Operation and Maintenance Manual*

**PART 3: RECORD KEEPING**

The owner shall inspect and maintain the septic system as required by the following tables below. Any maintenance or inspections that are not performed puts the system at risk for failure. A maintenance contract shall be signed to maintain the components of the system that requires the expertise of a professional who understands the function of each system component as shown below.

**Engineered septic System  
 MAINTENANCE LOG**

How to Complete:

1. Complete the specified maintenance on the prescribed frequency
2. Initial all areas that are satisfactory or initial performed maintenance
3. Note any deficiencies or required maintenance items
4. Maintain this record on file for DHHS review, as requested
5. Contact Gartley & Dorsky for additional copies of these Maintenance Logs

**MAINTENANCE TASKS**

Work Task	Frequency	By Whom	Date & Initials	Date & Initials	Date & Initials	Date & Initials
Inspect Septic Tanks	Annually	Licensed Septic Tank Contractor				
Pump Septic Tanks	When sludge level exceeds 1' thick	Licensed Septic Tank Contractor				
Inspect Septic Tanks Filters	Quarterly	Owner				
Replace Septic Tanks Filters	As needed (annually at minimum)	Owner or Licensed Septic Tank Contractor				
Inspect the Grease Trap	Semi-annual	Owner or Licensed Septic Tank Contractor				
Keep Records of plugged wastewater lines	As needed	Owner and Septic Tank Contractor				
Inspect Distribution Boxes and drop boxes	Annually	Owner				
Risers to septic tanks, pump stations and distribution chambers	Quarterly	Owner				
Inspect Field Perimeter	Time of high usage	Owner				
Inspect for Potential Erosion or Crushing Problems	As Needed	Owner				

Notes: Gartley & Dorsky Engineering & Surveying shall be notified of any changes that affect design conditions.

**REVIEWED AND ACKNOWLEDGED BY OWNER: BY: \_\_\_\_\_**

*KINGFISH MAINE  
Engineered Septic System  
Operation and Maintenance Manual*

**CONTACTS**

DESIGN/INSPECTION

William Lane, P.E.  
Vice President  
Gartley & Dorsky Engineering & Surveying  
PO Box 1031  
Camden, ME 04843  
Tel: 207.236.4365  
Fax: 207.236.3055  
Email: [blane@gartleydorsky.com](mailto:blane@gartleydorsky.com)  
Web: <http://www.gartleydorsky.com>

SITE EVALUATOR

Natalie Marceau  
Gartley & Dorsky Engineering & Surveying  
PO Box 1031  
Camden, ME 04843  
Tel: 207.236.4365  
Fax: 207.236.3055  
Email: [nmarceau@gartleydorsky.com](mailto:nmarceau@gartleydorsky.com)  
Web: <http://www.gartleydorsky.com>

EARTHWORK CONTRACTOR/INSTALLER

TBD

**EXHIBIT F**

**Soil & Site Conditions**

<b>SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION</b>		Department of Human Services Division of Health Engineering (207) 287-5672 Fax: (207) 287-3165
Town, City, Plantation JONESPORT	Street, Road, Subdivision DUN GARVAN ROAD	Owner's Name KINGFISH MAINE, INC.

**SOIL DESCRIPTION AND CLASSIFICATION**

Observation Hole 16  Test Pit  Boring  
 | " Depth of Organic Horizon Above Mineral Soil

Texture	Consistency	Color	Mottling
LOAMY SAND	FRIABLE	DARK BROWN	NONE
		STRONG BROWN	COMMON MEDIUM DISTINCT STRONG BROWN
SAND		YELLOWISH BROWN	
BOTTOM OF TEST PIT			

Soil Classification <u>5</u> <u>D</u> Profile Condition	Slope <u>±3</u> %	Limiting Factor <u>12</u> "	<input checked="" type="checkbox"/> Ground Water <input type="checkbox"/> Restrictive Layer <input type="checkbox"/> Bedrock <input type="checkbox"/> Pit Depth
---	----------------------	--------------------------------	--

Observation Hole 17  Test Pit  Boring  
 | " Depth of Organic Horizon Above Mineral Soil

Texture	Consistency	Color	Mottling
LOAMY SAND	FRIABLE	DARK BROWN	NONE
		STRONG BROWN	COMMON MEDIUM DISTINCT STRONG BROWN
SAND		YELLOWISH BROWN	
BOTTOM OF TEST PIT			

Soil Classification <u>5</u> <u>D</u> Profile Condition	Slope <u>±3</u> %	Limiting Factor <u>12</u> "	<input checked="" type="checkbox"/> Ground Water <input type="checkbox"/> Restrictive Layer <input type="checkbox"/> Bedrock <input type="checkbox"/> Pit Depth
---	----------------------	--------------------------------	--

**SOIL DESCRIPTION AND CLASSIFICATION**

Observation Hole 18  Test Pit  Boring  
 | " Depth of Organic Horizon Above Mineral Soil

Texture	Consistency	Color	Mottling
LOAMY SAND	FRIABLE	DARK BROWN	NONE
		STRONG BROWN	COMMON MEDIUM DISTINCT STRONG BROWN
SAND		YELLOWISH BROWN	
BOTTOM OF TEST PIT			

Soil Classification <u>5</u> <u>D</u> Profile Condition	Slope <u>±3</u> %	Limiting Factor <u>12</u> "	<input checked="" type="checkbox"/> Ground Water <input type="checkbox"/> Restrictive Layer <input type="checkbox"/> Bedrock <input type="checkbox"/> Pit Depth
---	----------------------	--------------------------------	--

Observation Hole 19  Test Pit  Boring  
 | " Depth of Organic Horizon Above Mineral Soil

Texture	Consistency	Color	Mottling
LOAMY SAND	FRIABLE	DARK BROWN	NONE
		STRONG BROWN	COMMON MEDIUM DISTINCT STRONG BROWN
SAND		YELLOWISH BROWN	
BOTTOM OF TEST PIT			

Soil Classification <u>5</u> <u>D</u> Profile Condition	Slope <u>±3</u> %	Limiting Factor <u>12</u> "	<input checked="" type="checkbox"/> Ground Water <input type="checkbox"/> Restrictive Layer <input type="checkbox"/> Bedrock <input type="checkbox"/> Pit Depth
---	----------------------	--------------------------------	--

<u><i>Natalie Marceau</i></u>	<u>411</u>	<u>3/25/21</u>
Site Evaluator Signature	SE #	Date

<b>SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION</b>		Department of Human Services Division of Health Engineering (207) 287-5672 Fax: (207) 287-3165
Town, City, Plantation JONESPORT	Street, Road, Subdivision DUN GARVAN ROAD	Owner's Name KINGFISH MAINE, INC.

**SOIL DESCRIPTION AND CLASSIFICATION**

Observation Hole 20  Test Pit  Boring  
 \_\_\_\_\_ " Depth of Organic Horizon Above Mineral Soil

Texture	Consistency	Color	Mottling
LOAMY SAND	FRIABLE	DARK BROWN	NONE
		STRONG BROWN	COMMON MEDIUM DISTINCT STRONG BROWN
SAND		YELLOWISH BROWN	
BOTTOM OF TEST PIT			

Soil Classification <u>5</u> <u>D</u> Profile Condition	Slope <u>±3</u> %	Limiting Factor <u>12</u> "	<input checked="" type="checkbox"/> Ground Water <input type="checkbox"/> Restrictive Layer <input type="checkbox"/> Bedrock <input type="checkbox"/> Pit Depth
---	----------------------	--------------------------------	--

Observation Hole 21  Test Pit  Boring  
 \_\_\_\_\_ " Depth of Organic Horizon Above Mineral Soil

Texture	Consistency	Color	Mottling
LOAMY SAND	FRIABLE	DARK BROWN	NONE
		STRONG BROWN	COMMON MEDIUM DISTINCT STRONG BROWN
SAND		YELLOWISH BROWN	
BOTTOM OF TEST PIT			

Soil Classification <u>5</u> <u>D</u> Profile Condition	Slope <u>±3</u> %	Limiting Factor <u>12</u> "	<input checked="" type="checkbox"/> Ground Water <input type="checkbox"/> Restrictive Layer <input type="checkbox"/> Bedrock <input type="checkbox"/> Pit Depth
---	----------------------	--------------------------------	--

**SOIL DESCRIPTION AND CLASSIFICATION**

Observation Hole 22  Test Pit  Boring  
 \_\_\_\_\_ " Depth of Organic Horizon Above Mineral Soil

Texture	Consistency	Color	Mottling
LOAMY SAND	FRIABLE	DARK BROWN	NONE
		STRONG BROWN	COMMON MEDIUM DISTINCT STRONG BROWN
SAND		YELLOWISH BROWN	
BOTTOM OF TEST PIT			

Soil Classification <u>5</u> <u>D</u> Profile Condition	Slope <u>±3</u> %	Limiting Factor <u>12</u> "	<input checked="" type="checkbox"/> Ground Water <input type="checkbox"/> Restrictive Layer <input type="checkbox"/> Bedrock <input type="checkbox"/> Pit Depth
---	----------------------	--------------------------------	--

Observation Hole 23  Test Pit  Boring  
 \_\_\_\_\_ " Depth of Organic Horizon Above Mineral Soil

Texture	Consistency	Color	Mottling
LOAMY SAND	FRIABLE	DARK BROWN	NONE
		STRONG BROWN	COMMON MEDIUM DISTINCT STRONG BROWN
SAND		YELLOWISH BROWN	
BOTTOM OF TEST PIT			

Soil Classification <u>5</u> <u>D</u> Profile Condition	Slope <u>±3</u> %	Limiting Factor <u>12</u> "	<input checked="" type="checkbox"/> Ground Water <input type="checkbox"/> Restrictive Layer <input type="checkbox"/> Bedrock <input type="checkbox"/> Pit Depth
---	----------------------	--------------------------------	--

<u>Natalie Marceau</u>	411	3/25/21
Site Evaluator Signature	SE #	Date

**EXHIBIT G**

**Engineered Disposal System Plans**

**SYSTEM 1B LOCATION**


DISTANCES:	AA	BB	CC	DD
ELEVATION REFERENCE POINT (ERP)	104.1'	157.9'	117.8'	167.3'
REFERENCE POINT A	108.2'	164.0'	112.2'	166.8'
REFERENCE POINT B	107.3'	160.0'	98.7'	154.3'

**SYSTEM 1A LOCATION**

DISTANCES:	A	B	C	D
ELEVATION REFERENCE POINT (ERP)	41.5'	87.3'	68.9'	103.2'
REFERENCE POINT A	34.3'	90.3'	45.4'	95.1'
REFERENCE POINT B	50.9'	91.7'	27.7'	81.1'

- SEPTIC SYSTEM NOTES:**
- BOTH SYSTEMS CONSIST OF 11 ROWS GEOTEXTILE SAND FILTERS SEPARATED BY 1 FOOT.
  - THIS SYSTEM COMPLIES WITH AND MUST BE INSTALLED IN ACCORDANCE WITH THE GEOTEXTILE SAND FILTER DESIGN MANUAL (BY ELJEN CORPORATION), AND ALL MAINE SUBSURFACE RULES.
  - INSTALLATION SHALL NOT TAKE PLACE WHEN THE GROUND IS FROZEN OR SATURATED.
  - TOPSOIL OR ORGANICS MUST BE REMOVED FROM LEACH FIELD AND FILL SLOPE EXTENSIONS PRIOR TO FILL PLACEMENT.
  - THE TOP OF THE NATURAL SOIL SHALL BE SCARIFIED BY ROTOTILLER, HARROW OR BACKHOE TEETH.
  - THERE SHALL BE 4" MINIMUM TRANSITIONAL HORIZON BETWEEN BACKFILL AND THE NATURAL SOIL WHICH IS A MIXTURE OF BACKFILL AND NATURAL SOIL. THE TRANSITIONAL HORIZON SHALL BE UNDER THE DISPOSAL SYSTEM AND EXTEND FROM FILL EXTENSION TO FILL EXTENSION.
  - THE 6" SAND LAYER BELOW THE MODULES SHALL BE MEDIUM TO COARSE SAND MEETING ASTM C33 SPECIFICATIONS. FOR COMPLETE SPECIFICATIONS SEE GEOTEXTILE SAND FILTER DESIGN MANUAL.
  - BACKFILL SHALL BE GRAVELLY COARSE SAND AND SHALL MEET SPECIFICATIONS OF TABLE 11A OF THE SUBSURFACE RULES.
  - FINAL GRADES SHALL BE LOAMED (4" MIN), MULCHED AND SEEDED.
  - ALL SEPTIC TANKS SHALL HAVE ACCESS OPENINGS, CONSISTING OF CAST IRON FRAMES AND SOLID COVERS, LOCATED AT FINISHED GRADE AND HAVE A WATERTIGHT RISER (PER SECTION 6F(2) OF THE SUBSURFACE CODE) OF THE SAME MATERIALS AS THE SEPTIC TANK. H-20 CONSTRUCTION IS REQUIRED IN TRAFFIC AREAS. SEE SECTION 6F(3) OF THE SUBSURFACE CODE.
  - THE DRILLING OF ANY WELLS WITH WATER USAGE OF 2000 OR MORE GALLONS PER DAY OR PUBLIC WATER SYSTEM WELLS SHALL BE A MINIMUM OF 150' FROM ANY WATER TIGHT SEPTIC TANK AND 300' FROM ANY LEACH FIELD.
  - THE DRILLING OF ANY WELLS WITH WATER USAGE UNDER 2000 GALLONS PER DAY OR NOT PUBLIC WATER SYSTEM WELLS SHALL BE A MINIMUM OF 100' FROM ANY WATER TIGHT SEPTIC TANK AND 300' FROM ANY LEACH FIELD.
  - THIS SYSTEM IS NOT DESIGNED FOR BACKWASH FROM ANY WATER TREATMENT SYSTEM.
  - THE SYSTEMS SHALL NOT BE DRIVEN ON.


**ENGINEERED SEPTIC FIELD SCHEMATIC**  
SCALE: 1" = 20'



**SYSTEM 1A ELEVATIONS**

ELEV. REF. PT. (ERP)	32.74'							
FINISHED GRADE	31.57'	31.43'	31.29'	31.15'	31.01'	30.87'	30.73'	30.57'
TOP OF IN-DRAIN UNIT	30.57'	30.43'	30.29'	30.15'	30.01'	29.87'	29.73'	29.57'
BOTTOM OF IN-DRAIN UNIT	29.97'	29.83'	29.69'	29.55'	29.41'	29.27'	29.13'	28.97'
BOTTOM OF SAND	29.49'	29.33'	29.19'	29.05'	28.91'	28.77'	28.63'	28.47'



**SYSTEM 1A SCHEMATIC CROSS SECTION**  
SCALE: 1" = 20'



**SYSTEM 1B ELEVATIONS**

ELEV. REF. PT. (ERP)	32.74'							
FINISHED GRADE	31.82'	31.69'	31.56'	31.43'	31.3'	31.17'	31.04'	30.91'
TOP OF IN-DRAIN UNIT	30.82'	30.69'	30.56'	30.43'	30.3'	30.17'	30.04'	29.91'
BOTTOM OF IN-DRAIN UNIT	30.22'	30.09'	29.96'	29.83'	29.7'	29.57'	29.44'	29.31'
BOTTOM OF SAND	29.72'	29.59'	29.46'	29.33'	29.2'	29.07'	28.94'	28.81'

**SYSTEM 1B SCHEMATIC CROSS SECTION**  
SCALE: 1" = 20'







**PUMP STATION SCHEDULE**

DESCRIPTION	ELEVATION*	FLOAT NO.	NOTES
FINISH GRADE	T.B.D.	---	
4" PVC IN	T.B.D.	---	
2" FORCE MAIN OUT	T.B.D.	---	
HIGH WATER ALARM	T.B.D.	⊙	
LAG PUMP ON	T.B.D.	⊙	
LEAD PUMP ON	T.B.D.	⊙	
ALL PUMPS OFF	T.B.D.**		

\* VERIFY ELEVATIONS WITH FINAL SEPTIC SYSTEM DESIGN. \*\* VERIFY MINIMUM PUMP SUBMERGENCE OPERATION DEPTH WITH PUMP MANUFACTURER.

PUMP CONTROL SCHEME: LEAD/LAG/ALTERNATE  
PROVIDE SECURE HANDS/OFF AUTO CONTROL FOR EACH MOTOR

- NOTE:**
- PROVIDE REMOTELY MOUNTED NEMA IV CONTROL PANEL (COORDINATE LOCATION WITH OWNER).
  - FURNISH PUMP MOTOR BRANCH PROTECTION, MOTOR STARTER, AND MOTOR OVERLOAD PROTECTION.
  - THIS PUMP STATION LAYOUT IS SCHEMATIC. SHOP DRAWINGS AND PUMP INFORMATION, INCLUDING PUMP CURVE GRAPH, SHALL BE PROVIDED TO ENGINEER FOR REVIEW PRIOR TO ORDERING THE PUMP STATION.
  - THE PUMP STATION SHALL BE INSPECTED PRIOR TO BACKFILLING.
  - LEAK TEST OR VACUUM TEST SHALL BE CONDUCTED IN ACCORDANCE WITH TESTING STANDARDS FOR MANHOLES.
  - IF INSPECTION INDICATES WORK DOES NOT MEET REQUIREMENTS, STATION SHALL BE REMOVED AND REPAIRED.



**Gartley & Dorsky ENGINEERING SURVEYING**  
59 Union Street, Unit 1, P.O. Box 1031 Camden, ME 04843-1031  
Ph (207) 236-4365 Fax (207) 236-3055 Toll Free 1-888-282-4365  
105 Main Street, Suite 2D P.O. Box 1072 Dunsmuirville, Maine 04843  
Ph (207) 790-5405

**CIVIL DETAILS**  
SCALE: AS NOTED  
DATE: MARCH 25, 2021  
DRAWN BY: LP  
CHECKED BY: WTL

**KINGFISH MAINE**  
CLIENT PROJECT: DUN GARVIN ROAD  
LOCATION: DUN GARVIN ROAD  
TOWN: JONESPORT COUNTY: WASHINGTON STATE: MAINE

PROJ. NO. 2019-412  
**C20**

**APPENDIX 17C**  
Mounding Analysis



March 20, 2021

Megan Sorby  
Tom Sorby  
Kingfish Maine, Inc.  
33 Salmon Farm Road  
Franklin, ME 04

**RE: Subsurface Wastewater Disposal System 1 – Mounding Analysis                      Project 2019-412**  
**Kingfish Maine RAS Facility**

Dear Megan and Tom:

We have completed a Mounding Analysis for the proposed primary wastewater disposal system at Kingfish Maine in Jonesport, Maine. The proposed system is are designated as Disposal Field 1 on the site plan enclosed. We also include copies of test pit logs with soil profile information.

The design flow for the systems is 4,000 gallons per day (gpd) which will be split between two discrete sections of the disposal field. The disposal fields sections are each 31 X 56 feet in size and utilize Eljen GSF standard modules arranged in 8 rows of 14 modules (total 224 units).

The mounding calculations are derived from the United States Geological Survey (USGS) Scientific Investigation Report 2010-5102. The analytical model is based on a Solution to the Hantush Equation (1967).

Input parameters to the model include recharge rate, specific yield, initial saturated thickness of the aquifer, field size, time and horizontal hydraulic conductivity. The values used for each input parameter are as follows:

The per field recharge rate is 0.154 feet per day based on 2,000 gpd (267 cubic feet per day) design flow and a field size of 1,736 square feet. The recharge rate is considered constant. If actual design flow is less, mounding predictions would be lower than predicted.

Specific yield is 0.26 (dimensionless) and reflects the ability of a soil to drain water and is a ratio of the volume of water that drains from a unit volume of the soil compared to the volume of soil. Reference values were derived from US Department of the Interior Geological Survey Water Supply Paper 1662-D.

Initial saturated thickness of the aquifer is on the order of 22 feet. These values are derived from the exploration data. Test pits (Nos. 16 to 21) encountered no limiting bedrock condition at depths of 34". In the adjacent geotechnical investigation's boring (B15), depth to bedrock in field was generally greater than 23 feet. In general, overburden in this section of the property is consistent with this finding. As a result, overburden is conservatively assigned to be 20 feet thick in the vicinity of the disposal field.

Test pit logs indicate variable depths to mottling (seasonal high water table) of 12 inches below ground surface. For mounding calculations, a depth to water table of 12 inches below ground surface (bgs) was assigned. Given a conservative overburden of 20 feet, an initial saturated thickness of 19 feet was used. A thicker overburden would result in less predicted mounding.

Field size is 56 X 31 feet. Time was set at 365 days (1 year). A 1-year timeframe allow sufficient time for the system to achieve a steady state.

Horizontal hydraulic Conductivity was varied between 1 and 10 feet per day as a sensitivity analysis of the predicted mounding values. Hydraulic conductivity of the material underlying the disposal field is the primary factor controlling the predicted height of the mound. As such, multiple sources of information were reviewed to develop an estimate of hydraulic conductivity. The model uses a 10:1 ratio of horizontal to vertical permeability.

Hydraulic conductivity values published in Groundwater and Wells, Second Edition, Driscoll, 1986 (Figure 5.14) were largely derived from water well testing data and are considered to represent horizontal hydraulic conductivity values for a range of geologic materials. Values of 3 to 30 feet per day overlap the descriptions of Glacial Till and fine Sand. Medium to coarse sand values are considerably higher.

Review of the test pits and boring indicate that for sizing purposes a profile 5D soil was used. In the geotechnical report, the native material is characterized as fluvial soils consisting of loose to dense sand and gravel with varying portions of silt. From a soil series perspective, the NRCS soil survey indicates the material is Kinsman sand. Published Ksat values are reported as moderately high to very high: 1.42 to 14.17 in/hr (2.8 to 28.3). More conservative published information for sands list "permeability" as 5 cm per hour (~4 feet per day). These values are likely partially derived from laboratory testing. Values may be biased to a vertical permeability related to infiltration of water vertically through the soil. For model input, these values appear to be applicable to vertical hydraulic conductivity values. Factored scaling for horizontal conductivity will be employed as enumerated in the protocol basis.

Simulations were run using horizontal hydraulic conductivity values of 30, 10 and 5 feet per day to assess the variation in predicted mounding. Other model parameters remained fixed in each of the simulations.

- Using a horizontal hydraulic conductivity of 30 feet per day (corresponding vertical hydraulic conductivity of 3 feet per day) and the most conservative thickness of overburden results in a predicted groundwater mound of approximately 0.35 feet above the initial groundwater level at the center of the disposal field.
- Similarly, using a horizontal hydraulic conductivity of 10 feet per day (corresponding vertical hydraulic conductivity of 1 foot per day), results in a predicted groundwater mound of approximately .9 feet above the initial groundwater level at the center of the disposal field.
- Using a horizontal hydraulic conductivity of 5 feet per day (corresponding vertical hydraulic conductivity of 0.5 feet per day), results in a very conservative predicted groundwater mound of approximately 1.55 feet above the initial groundwater level at the center of the disposal field.

Based on available information and interpretations of site conditions, the simulation using 30 feet per day as a horizontal hydraulic conductivity reasonably represents conditions for disposal field 1 to account for mounding effects and potential overlap of mounding effects between the adjacent fields. Subsurface rules require separations to seasonal groundwater, which in this instance control. In conformance with the subsurface rules, the Table 4F minimum 24 inch vertical separation must be maintained between the Seasonal High Water Table and Eljen InDrain units.

Very truly yours,  
**Gartley & Dorsky, Engineering & Surveying Inc.**

A handwritten signature in black ink, appearing to read 'W. T. Lane', with a large, stylized flourish at the end.

William T. Lane, P.E.  
Vice President

enclosure: Hantush spreadsheets

This spreadsheet will calculate the height of a groundwater mound beneath a stormwater infiltration basin. More information can be found in the U.S. Geological Survey Scientific Investigations Report 2010-5102 "Simulation of groundwater mounding beneath hypothetical stormwater infiltration basins".

The user must specify infiltration rate (R), specific yield (Sy), horizontal hydraulic conductivity (Kh), basin dimensions (x, y), duration of infiltration period (t), and the initial thickness of the saturated zone (hi(0)), height of the water table if the bottom of the aquifer is the datum). For a square basin the half width equals the half length (x = y). For a rectangular basin, if the user wants the water-table changes perpendicular to the long side, specify x as the short dimension and y as the long dimension. Conversely, if the user wants the values perpendicular to the short side, specify y as the short dimension, x as the long dimension. All distances are from the center of the basin. Users can change the distances from the center of the basin at which water-table aquifer thickness are calculated. Cells highlighted in yellow are values that can be changed by the user. Cells highlighted in red are output values based on user-specified inputs. **The user MUST click the blue "Re-Calculate Now" button each time ANY of the user-specified inputs are changed** otherwise necessary iterations to converge on the correct solution will not be done and values shown will be incorrect. Use consistent units for all input values (for example, feet and days)

**Input Values**

0.1540	R
0.260	Sy
5.00	K
28.000	x
15.500	y
365.000	t
19.000	hi(0)

use consistent units (e.g. feet & days or inches & hours)

**Recharge (infiltration) rate (feet/day)**  
**Specific yield, Sy (dimensionless, between 0 and 1)**  
**Horizontal hydraulic conductivity, Kh (feet/day)\***  
**1/2 length of basin (x direction, in feet)**  
**1/2 width of basin (y direction, in feet)**  
**duration of infiltration period (days)**  
**initial thickness of saturated zone (feet)**

**Conversion Table**

inch/hour	feet/day
0.67	1.33
2.00	4.00
hours	days
36	1.50

In the report accompanying this spreadsheet (USGS SIR 2010-5102), vertical soil permeability (ft/d) is assumed to be one-tenth horizontal hydraulic conductivity (ft/d).

20.547	h(max)
1.547	Δh(max)


**maximum thickness of saturated zone (beneath center of basin at end of infiltration period)**  
**maximum groundwater mounding (beneath center of basin at end of infiltration period)**

Ground-water Mounding, in feet  
 Distance from center of basin in x direction, in feet

1.547	0
1.451	20
1.238	40
1.138	50
1.054	60
0.986	70
0.927	80
0.876	90
0.830	100
0.752	120



**Re-Calculate Now**



**Disclaimer**

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

This spreadsheet will calculate the height of a groundwater mound beneath a stormwater infiltration basin. More information can be found in the U.S. Geological Survey Scientific Investigations Report 2010-5102 "Simulation of groundwater mounding beneath hypothetical stormwater infiltration basins".

The user must specify infiltration rate (R), specific yield (Sy), horizontal hydraulic conductivity (Kh), basin dimensions (x, y), duration of infiltration period (t), and the initial thickness of the saturated zone (hi(0)), height of the water table if the bottom of the aquifer is the datum). For a square basin the half width equals the half length (x = y). For a rectangular basin, if the user wants the water-table changes perpendicular to the long side, specify x as the short dimension and y as the long dimension. Conversely, if the user wants the values perpendicular to the short side, specify y as the short dimension, x as the long dimension. All distances are from the center of the basin. Users can change the distances from the center of the basin at which water-table aquifer thickness are calculated. Cells highlighted in yellow are values that can be changed by the user. Cells highlighted in red are output values based on user-specified inputs. **The user MUST click the blue "Re-Calculate Now" button each time ANY of the user-specified inputs are changed** otherwise necessary iterations to converge on the correct solution will not be done and values shown will be incorrect. Use consistent units for all input values (for example, feet and days)

**Input Values**

0.1540	R
0.260	Sy
10.00	K
28.000	x
15.500	y
365.000	t
19.000	hi(0)

use consistent units (e.g. feet & days or inches & hours)

**Recharge (infiltration) rate (feet/day)**  
**Specific yield, Sy (dimensionless, between 0 and 1)**  
**Horizontal hydraulic conductivity, Kh (feet/day)\***  
**1/2 length of basin (x direction, in feet)**  
**1/2 width of basin (y direction, in feet)**  
**duration of infiltration period (days)**  
**initial thickness of saturated zone (feet)**

**Conversion Table**

inch/hour	feet/day
0.67	1.33
2.00	4.00
hours	days
36	1.50

In the report accompanying this spreadsheet (USGS SIR 2010-5102), vertical soil permeability (ft/d) is assumed to be one-tenth horizontal hydraulic conductivity (ft/d).

19.862	h(max)
0.862	Δh(max)


**maximum thickness of saturated zone (beneath center of basin at end of infiltration period)**  
**maximum groundwater mounding (beneath center of basin at end of infiltration period)**

Ground-water Mounding, in feet  
 Distance from center of basin in x direction, in feet

0.862	0
0.822	20
0.732	40
0.686	50
0.644	60
0.608	70
0.578	80
0.552	90
0.529	100
0.489	120



**Re-Calculate Now**



**Disclaimer**

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

This spreadsheet will calculate the height of a groundwater mound beneath a stormwater infiltration basin. More information can be found in the U.S. Geological Survey Scientific Investigations Report 2010-5102 "Simulation of groundwater mounding beneath hypothetical stormwater infiltration basins".

The user must specify infiltration rate (R), specific yield (Sy), horizontal hydraulic conductivity (Kh), basin dimensions (x, y), duration of infiltration period (t), and the initial thickness of the saturated zone (hi(0), height of the water table if the bottom of the aquifer is the datum). For a square basin the half width equals the half length (x = y). For a rectangular basin, if the user wants the water-table changes perpendicular to the long side, specify x as the short dimension and y as the long dimension. Conversely, if the user wants the values perpendicular to the short side, specify y as the short dimension, x as the long dimension. All distances are from the center of the basin. Users can change the distances from the center of the basin at which water-table aquifer thickness are calculated. Cells highlighted in yellow are values that can be changed by the user. Cells highlighted in red are output values based on user-specified inputs. **The user MUST click the blue "Re-Calculate Now" button each time ANY of the user-specified inputs are changed** otherwise necessary iterations to converge on the correct solution will not be done and values shown will be incorrect. Use consistent units for all input values (for example, feet and days)

**Input Values**

0.1540	R
0.260	Sy
30.00	K
28.000	x
15.500	y
365.000	t
19.000	hi(0)

use consistent units (e.g. feet & days or inches & hours)

**Recharge (infiltration) rate (feet/day)**  
**Specific yield, Sy (dimensionless, between 0 and 1)**  
**Horizontal hydraulic conductivity, Kh (feet/day)\***  
**1/2 length of basin (x direction, in feet)**  
**1/2 width of basin (y direction, in feet)**  
**duration of infiltration period (days)**  
**initial thickness of saturated zone (feet)**

**Conversion Table**

inch/hour	feet/day
0.67	1.33
2.00	4.00
hours	days
36	1.50

In the report accompanying this spreadsheet (USGS SIR 2010-5102), vertical soil permeability (ft/d) is assumed to be one-tenth horizontal hydraulic conductivity (ft/d).

19.350	h(max)
0.350	Δh(max)


**maximum thickness of saturated zone (beneath center of basin at end of infiltration period)**  
**maximum groundwater mounding (beneath center of basin at end of infiltration period)**

Ground-water Mounding, in feet  
 Distance from center of basin in x direction, in feet

0.350	0
0.344	20
0.326	40
0.315	50
0.304	60
0.293	70
0.283	80
0.274	90
0.266	100
0.252	120



**Re-Calculate Now**



**Disclaimer**

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

**APPENDIX 17D**

Nitrate Study

## Nitrate-Nitrogen Impact Assessment

In accordance with Department of Human Services Subsurface Waste Water Disposal Rules (10 CMR 241) requirements, Gartley & Dorsky has prepared this nitrate-nitrogen impact assessment for the wastewater disposal systems supporting the proposed Kingfish Maine RAS facility in Jonesport, Maine.

Topography slopes from a high point east of Mason Bay Road east to the waters of Chandler Bay. Please refer to the Site Plan for the siting and facility layout.

Pertinent data for this assessment was obtained from the following sources:

- 1) On-site test pits,
- 2) Review of disposal system design by Natalie Marceau, Licensed Site Evaluator #411,
- 3) Geotechnical Report prepared by SW Cole
- 4) USGS topographical map
- 5) Maine Surficial Geology Map

Based on soil classifications made during excavation of test pits, native surficial geology is fluvial till. Test Pits 20-23 reported a medium sand loam to depths greater than 32 inches feet below ground surface (bgs). Bedrock was not encountered in any test pit. Test Pit logs are included in this section.

Several approaches have been developed to assess the potential impact of subsurface waste disposal systems with respect to nitrate concentrations in ground water. They range from simple loading calculations to dilution effects based on geology, recharge rates and water quality; to analytical dispersion calculations. We have evaluated potential nitrate impacts for based on each of these approaches.

### Screening/General Loading Assessment

This assessment has been developed by the Department of Human Services, Division of Health Engineering. A copy of their guidance is included as Attachment 2. This approach uses a number of simplifying assumptions and utilizes a loading vs. overall site square footage matrix. Essentially, the approach determines a minimum area needed to allow attenuation of nitrate concentrations in effluent discharges from the system.

Based on the soil characteristics encountered in test pit excavations, a 5D soil profile/condition has been assigned to the disposal field sites. Using the matrix in Table F-1 of the Health Engineering guidance (Attachment 2), a minimum of 82 square feet of site area is needed per gallon of daily flow to reduce the concentration of nitrate in effluent from an average of 40 milligrams per liter (mg/l) to acceptable levels per the department – less than 10 mg/l. As the facility is adjacent to tidal waters, the value is conservative. Counting available area



Assuming that 4,385 gallons per day is the total design flow for the proposed disposal fields, a total site square footage of 353,570 sq. ft. or approximately 8.25 acres of land is required for nitrate attenuation. The actual site acreage 93.2 acres or approximately 11 times greater than the minimum. On this basis, the site is acceptable with respect to nitrate-nitrogen impacts.

### Mixing/Dilution Assessment

A mixing/dilution calculation approach is described in Section 14.B.2.(d) of the Maine Department of Environmental Protection (DEP) Site Location Permit Application. This approach is used as an alternate method to evaluate nitrate-nitrogen impacts on development Sites that utilize on-site subsurface wastewater disposal systems. Kingfish Maine's project is subject to Site Location Permit requirements. Because of sufficient undeveloped and buffer area on the majority of the property nitrate evaluations by mixing/dilution are appropriate for assessment.

The following information was used in the calculation of mixing and dilution:

- The project area is 93 acres in size and contain slopes on the order of 3 to 8%.
- National Weather Service records indicate that average annual precipitation is approximately 46 inches. A conservative drought condition (60%) of 27.6 inches was assessed.
- Site soils were classified as hydrologic soil group A. Based on this classification and Table d(ii) of the Site Location Application, a recharge rate of 43% of average annual precipitation has been selected for the Site, conservatively applied to the area outside the development area, or 2,758,526 sf. Owing to provisions of the Site Law and Stormwater Law, the development footprint is diverted to stormwater features that effectively manage stormwater but may inhibit recharge. Conservatively, these areas are excluded.
- A design flow of 4,000 gpd has been established for system 1 and 385 gpd for system 2.
- Initial concentration of Nitrate-Nitrogen for effluent from the wastewater disposal system is assumed to be 40 mg/l, which is typical of domestic wastewater. Background is estimated at 2.0 mg/l.
- Concentration of Nitrate-Nitrogen in precipitation is assumed to be 0.5 mg/l as recommended by DEP.

$$Cd = \frac{Qe Ce + Qr Cr}{Qe + Qr}$$

Where:

Cd = the diluted nitrate concentration

Qe = volume of effluent in liters per year (6,058,643 liters)

Ce = nitrate concentration of effluent (40 mg/l)

Qr = volume of recharge over 2,758,526 sf from precipitation in liters (142,750,830 liters)

Cr = nitrate concentration in recharge (0.5 mg/l)

Systemwide Nitrate By Dilution	Waste Flow GPD	Qe (Yearly) Liters	Ce mg/l	Undeveloped Parcel Area SF	Drought Rainfall Inches	Recharge Percent	Qr (Yearly) Liters	Cr mg/l
	4385	6,058,643	40	2,758,526	27.6	43%	77253390	0.5

$$Cd = \frac{QeCe + QrCr}{Qe + Qr} = \frac{280972429}{83312033} = 3.4$$

Cd = 3.4 mg/l, indicating diluted concentrations are at or below the review standard of 8 mg/l.