

Weaver Wind Project

MDEP Site Location of Development/NRPA Combined Application

SECTION 17: WASTEWATER

17.0 WASTEWATER

During the project construction phase, temporary toilet facilities will be used and service of the facilities will be provided by a licensed wastewater transporter. Washwater from concrete deliveries during construction of turbine foundations will be disposed of on the turbine pad or in upland disturbed areas. The wind turbines and electrical collector system operation will not produce wastewater.