

**OPERATIONS
AND
ROUTINE MAINTENANCE WORK**

CASCO BAY BRIDGE

PORTLAND – SOUTH PORTLAND

2020

Updated 05/15/2020

STATE PROJECT

MAINTENANCE & OPERATIONS

BIDDING INSTRUCTIONS

1. Use pen and ink to complete all paper Bids. Signatures shall be original. Stamped and copied signatures will not be accepted. Bids are not accepted by email or FAX.

NOTE: Electronic Bids will not be accepted for this bid.

2. As a minimum, the following must be received prior to the time of Bid opening: a) a copy of the Notice to Contractors, b) the completed Acknowledgement of Bid Amendments form, c) the completed Schedule of Items in Appendix A, d) all of the proposal requirements called for in Appendix A, including but not limited to the Proposal Worksheet, the Company's Qualifications and Experience, the Company's Safety Record and knowledge of Coast Guard regulations, and references, e) two copies of the completed and signed Contract Agreement for Transportation Related Maintenance Work form, f) the completed Contractor Information Sheet, and g) any other certifications or Bid requirements listed in the Bid Documents/RFP as due by Bid opening.
3. Include prices for all items to be bid in the Schedule of Items.
4. All Bid Packages which are mailed or sent express, shall be provided in double (one envelope inside the other) envelopes, for security and other reasons. The *Inner Envelope* shall have the following information provided on it:

Bid Enclosed - Do Not Open

WIN or Title: Casco Bay Bridge Operations and Routine Maintenance Work

Towns, Regions or Location: Portland – South Portland

Date of Bid Opening:

Name of Contractor with mailing address and telephone number:

In Addition to the usual address information, the *Outer Envelope* should have written or typed on it:

Double Envelope: Bid Enclosed

WIN or Title: Casco Bay Bridge Operations and Routine Maintenance Work

Towns, Regions or Location: Portland – South Portland

Date of Bid Opening:

Name of Contractor:

If a paper Bid is to be sent express, please take note that overnight services do not always arrive in time and that delivery may be affected by carrier volume, weather and other factors. Packages using express services should be sent directly to the DOT Headquarters Building, Maine Department of Transportation, 24 Child Street, Augusta. "FedEx First Overnight" delivery is suggested as the package is delivered directly to the DOT Headquarters Building, Mailroom, 24 Child Street, Augusta. Allow extra days for U.S. Postal Service Express Mail which has proven not to be reliable and sometimes does not deliver directly to the DOT Headquarters Building but instead delivers to the State of Maine Mail Distribution Center.

If a paper bid is to be mailed, the mailing address is Maine Department of Transportation, 16 State House Station, Augusta, ME 04333-0016. Allow additional working days for this mail to pass through the state mail system in addition to the US Postal Service as this mail is not delivered directly to the Department of Transportation.

If a paper Bid is to be hand carried, deliver directly to the "Public Entrance" which is located on the Capitol Street side of the DOT Headquarters Building in Augusta. <http://www.maine.gov/mdot/contact>. Hand-carried Bids may be in one envelope, and should be marked with the following information:

Bid Enclosed: Do Not Open

WIN or Title: Casco Bay Bridge Operations and Routine Maintenance Work

Towns, Regions or Location: Portland – South Portland

Date of Bid Opening:

Name of Contractor:

*If you need further information regarding Bid preparation, call the DOT Contracts Section at (207) 624-3410.
For complete bidding requirements, refer to Section 102 of the Maine Department of Transportation, Standard
Specifications, March 2020 Edition.*

NOTICE

The Maine Department of Transportation is attempting to improve the way Bid Amendments/Addendums are handled, and allow for an electronic downloading of bid packages from our website, while continuing to maintain an optional plan holders list.

Prospective bidders, subcontractors or suppliers who wish to download a copy of the bid package and receive a courtesy notification of project specific bid amendments must fill out the on-line plan holder registration form and provide an email address to the MDOT Contracts mailbox at: MDOT.contracts@maine.gov. Each bid package will require a separate request.

Additionally, interested parties will be responsible for reviewing and retrieving the Bid Amendments from our web site, and acknowledging receipt and incorporating those Bid Amendments in their bids using the Acknowledgement of Bid Amendment Form.

STATE OF MAINE DEPARTMENT OF TRANSPORTATION
Bid Guaranty-Bid Bond Form

KNOW ALL MEN BY THESE PRESENTS THAT _____

_____, of the City/Town of _____ and State of _____

as Principal, and _____ as Surety, a

Corporation duly organized under the laws of the State of _____ and having a usual place of

Business in _____ and hereby held and firmly bound unto the Treasurer of

the State of Maine in the sum of _____, for payment which Principal and Surety bind

themselves, their heirs, executors, administrators, successors and assigns, jointly and severally.

The condition of this obligation is that the Principal has submitted to the Maine Department of

Transportation, hereafter Department, a certain bid, attached hereto and incorporated as a

part herein, to enter into a written contract for the construction of _____

_____ and if the Department shall accept said bid

and the Principal shall execute and deliver a contract in the form attached hereto (properly

completed in accordance with said bid) and shall furnish bonds for this faithful performance of

said contract, and for the payment of all persons performing labor or furnishing material in

connection therewith, and shall in all other respects perform the agreement created by the

acceptance of said bid, then this obligation shall be null and void; otherwise it shall remain in full

force, and effect.

Signed and sealed this _____ day of _____ 20_____

WITNESS:

WITNESS

PRINCIPAL:

By _____

By: _____

By: _____

SURETY:

By _____

By: _____

Name of Local Agency: _____

NOTICE

Bidders:

Please use the attached “Request for Information” form when submitting questions concerning specific Contracts that have been advertised for Bid, include additional numbered pages as required. RFI’s may be faxed to 207-624-3431, submitted electronically through the Departments web page of advertised projects by selecting the RFI tab on the project details page or via e-mail to RFI-Contracts.MDOT@maine.gov.

These are the only allowable mechanisms for answering Project specific questions. Maine DOT will not be bound to any answers to Project specific questions received during the Bidding phase through other processes.

When submitting RFIs by Email please follow the same guidelines as stated on the “Request for Information” form and include the word “RFI” along with the Project name and Identification number in the subject line.

Vendor Registration

Prospective Bidders must register as a vendor with the Department of Administrative & Financial Services if the vendor is awarded a contract. Vendors will not be able to receive payment without first being registered. Vendors/Contractors will find information and register through the following link –

<http://www.maine.gov/purchases/venbid/index.shtml>

CONTRACTOR INFORMATION

Contractor Name: _____

Mailing Address: _____

Vendor Customer Number: _____

Contact Information (Primary Contact): _____

Phone: _____ **Cell Phone:** _____

Fax: _____

Email: _____

Mailing Address (if different from above): _____

The company has the following organizational structure:

Sole Proprietorship

Limited Liability Company

Partnership

Joint Venture

Corporation

Other: _____

(Date)

(Signature)

(Name and Title Printed)

**STATE OF MAINE DEPARTMENT OF TRANSPORTATION
NOTICE TO CONTRACTORS**

Sealed Bids addressed to the Maine Department of Transportation, Augusta, Maine 04333 and endorsed on the wrapper "Bids for Casco Bay Bridge Operations and Routine Maintenance Work in the cities of PORTLAND & SOUTH PORTLAND" will be received from contractors at the Reception Desk, MaineDOT Building, Capitol Street, Augusta, Maine, until 11:00 o'clock A.M. (prevailing time) on December 9, 2020 and at that time and place, publicly opened and read. Bids will be accepted from all bidders. **Electronic Bidding will not be available.** The highest scored responsive bidder must demonstrate successful completion of projects of similar size and scope to be considered for the award of this contract.

Description: Casco Bay Bridge Operations and Routine Maintenance Work.

Location: In Cumberland County, project is located on the Casco Bay Bridge, Portland – South Portland

Outline of Work: Bridge operations and other incidental work.

Bidders may be on operations and/or routine maintenance. Each section will be awarded separately. The basis of award will be determined using the criteria set forth in the Proposal Evaluation section of the Appendix A.

For general information regarding Bidding and Contracting procedures, contact George Macdougall at (207) 624-3410. Our webpage at <http://www.maine.gov/mdot/contractors/> contains a copy of the Schedule of Items, Plan Holders List, written portions of bid amendments, bid results and an electronic form for RFI submittal. For Project-specific information fax all questions to Gail Iler/Joe Prescott at (207) 624-3431, use electronic RFI form or email questions to RFI-Contracts.MDOT@maine.gov, project name and identification number should be in the subject line. Questions received after 12:00 noon of Friday prior to bid date will not be answered. Bidders shall not contact any other Departmental staff for clarification of Contract provisions, and the Department will not be responsible for any interpretations so obtained. TTY users call Maine Relay 711.

Bid Documents, specifications and bid forms can be viewed and obtained digitally at no cost at <http://www.maine.gov/mdot/contractors/>. They may be seen at the MaineDOT Building in Augusta, Maine and at the Department of Transportation's Regional Office in Scarborough. They can be obtained at no cost at the Department at 24 Child Street, Augusta, ME, between the hours of 8:00 a.m. to 4:30 p.m., may be requested by telephone at (207) 624-3536 between the hours of 8:00 a.m. to 4:30 p.m., or from Maine Department of Transportation, Attn.: Mailroom, 16 State House Station, Augusta, Maine 04333-0016.

Each Bid must be made upon blank forms provided by the Department and must be accompanied by a bid bond at 5% of the bid amount or an official bank check, cashier's check, certified check, certificate of deposit, or United States postal money order in the amount of **\$145,000.00** payable to Treasurer, State of Maine as a Bid guarantee. A Contract Payment Surety Bond, each in the amount of 100 percent of the Contract price, will be required of the successful Bidder. Performance bonds will not be required.

This Contract is subject to all applicable State Laws.

All work shall be governed by *State of Maine, Department of Transportation, Standard Specifications, March 2020 Edition*, price \$10 [\$15 by mail], and *Standard Details, March 2020 Edition*, price \$10 [\$15 by mail]. They also may be purchased by telephone at (207) 624-3536 between the hours of 8:00 a.m. to 4:30 p.m. *Standard Detail* updates can be found at <http://www.maine.gov/mdot/contractors/publications/>.

The right is hereby reserved to the MaineDOT to reject any or all bids.

Augusta, Maine
November 18, 2020



JOYCE NOEL TAYLOR, P. E.

CTM: _____
TEDOCS# _____
CSN _____

MAINE DEPARTMENT OF TRANSPORTATION
CONTRACT AGREEMENT
TRANSPORTATION RELATED MAINTENANCE WORK

This CONTRACT is made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (“Department” or “MaineDOT”), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address of 16 State House Station, Augusta, Maine 04333-0016, and _____ (“Contractor”) a corporation or other legal entity organized under the laws of the State of _____, with its principal place of business located at _____, with a mailing address of _____, and a telephone number of _____ .

The Vendor Customer Number of the Contractor is _____.

The following attachments are hereby incorporated into this Contract by reference:

Appendix A – Special Provisions - Request for Proposals and Specifications of Work to be Performed

Appendix B – Special Provisions for State Funded Transportation Related Maintenance Work

The Department and the Contractor, in consideration of the mutual promises set forth in this Contract Agreement (hereinafter “Contract”) hereby agree as follows:

A. The Work.

The Contractor agrees to complete all work described in Appendix A – Special Provision - Specifications of Work to be Performed, and under the terms of the Contract for **Casco Bay Bridge Operations and Routine Maintenance Work**, in the cities of **Portland and South Portland**, Maine.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools, supplies, facilities, permanent materials and temporary materials and services required to perform the Work including quality control, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

This contract commences on March 7, 2021 or upon contract execution, whichever is latest and expires on March 6, 2026 unless extended under the terms of this contract. At the Department's discretion and upon mutual agreement with the Contractor, the Contract may be extended for time and money, under all the terms of this contract, at bid prices for agreed periods of time up to five (5) additional years.

C. Price.

The quantities given in the Schedule of Items of the Bid Package will be used as the basis for determining the original Contract amount and for determining the amounts of the required Payment Surety Bond, and that the amount of this offer is

Operations - _____

\$ _____

Maintenance - _____

\$ _____.

Payment Bond each being 100% of the amount of this Contract.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the State of Maine, Department of Transportation, *Standard Specifications, March 2020 Edition* as updated through advertisement, Division 100 - General Conditions, Special Provisions, Contract Agreement, Appendices and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

1. All of the statements, representations, covenants, and certifications required or set forth in the Contract are still complete and accurate as of the date of this contract.
2. The Contractor knows of no legal, contractual, or financial impediment that prevents Contractor from entering into this Contract.

3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Contract Agreement.

The undersigned, having carefully examined the site of work, scope of work, State of Maine, Department of Transportation, *Standard Specifications, March 2020 Edition*, Division 100 - General Conditions, Special Provisions, Contract Agreement, Appendices and Contract Bonds contained herein, hereby agrees to supply all the services, materials, tools, equipment and labor to complete the whole of the work in strict accordance with the terms and conditions of this Contract at the prices agreed to in Appendix A.

The Contractor agrees to perform the work required at the prices specified above in accordance with the terms of this Contract and to provide the appropriate insurance and bonds.

Contractor also agrees:

First: Contractor agrees to perform extra work, not described in Appendix A, which may be ordered by the Department, and to accept as full compensation the amount determined upon basis as provided in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.

Third: Contractor understands that Work may commence upon Contract Execution, unless provided elsewhere in this contract and that Work must be completed within the time limits given in this Contract.

Fourth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Fifth: The Contractor hereby certifies, to the best of its knowledge and belief that: the Contractor has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

Sixth: Contractor further agrees to provide insurance as required by this Contract.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby executes this Contract and thereby binds itself to all covenants, terms, and obligations contained in the Contract Documents.

CONTRACTOR

Date

(Signature of Legally Authorized Representative
of the Contractor)

(Name and Title Printed)

G. Award.

Your offer is hereby accepted for (see marked boxes):

Operations \$ _____
Maintenance \$ _____

The original contract amount is: \$ _____
_____.

This award consummates the Contract, and the documents referenced herein.

MAINE DEPARTMENT OF TRANSPORTATION

Date

By: Bruce A. Van Note, Commissioner

Witness

CTM: _____
TEDOCS# _____
CSN _____

MAINE DEPARTMENT OF TRANSPORTATION
CONTRACT AGREEMENT
TRANSPORTATION RELATED MAINTENANCE WORK

This CONTRACT is made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (“Department” or “MaineDOT”), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address of 16 State House Station, Augusta, Maine 04333-0016, and _____ (“Contractor”) a corporation or other legal entity organized under the laws of the State of _____, with its principal place of business located at _____, with a mailing address of _____, and a telephone number of _____ .

The Vendor Customer Number of the Contractor is _____.

The following attachments are hereby incorporated into this Contract by reference:

Appendix A – Special Provisions - Request for Proposals and Specifications of Work to be Performed

Appendix B – Special Provisions for State Funded Transportation Related Maintenance Work

The Department and the Contractor, in consideration of the mutual promises set forth in this Contract Agreement (hereinafter “Contract”) hereby agree as follows:

A. The Work.

The Contractor agrees to complete all work described in Appendix A – Special Provision - Specifications of Work to be Performed, and under the terms of the Contract for **Casco Bay Bridge Operations and Routine Maintenance Work**, in the cities of **Portland and South Portland**, Maine.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools, supplies, facilities, permanent materials and temporary materials and services required to perform the Work including quality control, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

This contract commences on March 7, 2021 or upon contract execution, whichever is latest and expires on March 6, 2026 unless extended under the terms of this contract. At the Department's discretion and upon mutual agreement with the Contractor, the Contract may be extended for time and money, under all the terms of this contract, at bid prices for agreed periods of time up to five (5) additional years.

C. Price.

The quantities given in the Schedule of Items of the Bid Package will be used as the basis for determining the original Contract amount and for determining the amounts of the required Payment Surety Bond, and that the amount of this offer is

Operations - _____

\$ _____

Maintenance - _____

\$ _____.

Payment Bond each being 100% of the amount of this Contract.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the State of Maine, Department of Transportation, *Standard Specifications, March 2020 Edition* as updated through advertisement, Division 100 - General Conditions, Special Provisions, Contract Agreement, Appendices and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

1. All of the statements, representations, covenants, and certifications required or set forth in the Contract are still complete and accurate as of the date of this contract.
2. The Contractor knows of no legal, contractual, or financial impediment that prevents Contractor from entering into this Contract.

3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Contract Agreement.

The undersigned, having carefully examined the site of work, scope of work, State of Maine, Department of Transportation, *Standard Specifications, March 2020 Edition*, Division 100 - General Conditions, Special Provisions, Contract Agreement, Appendices and Contract Bonds contained herein, hereby agrees to supply all the services, materials, tools, equipment and labor to complete the whole of the work in strict accordance with the terms and conditions of this Contract at the prices agreed to in Appendix A.

The Contractor agrees to perform the work required at the prices specified above in accordance with the terms of this Contract and to provide the appropriate insurance and bonds.

Contractor also agrees:

First: Contractor agrees to perform extra work, not described in Appendix A, which may be ordered by the Department, and to accept as full compensation the amount determined upon basis as provided in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.

Third: Contractor understands that Work may commence upon Contract Execution, unless provided elsewhere in this contract and that Work must be completed within the time limits given in this Contract.

Fourth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Fifth: The Contractor hereby certifies, to the best of its knowledge and belief that: the Contractor has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

Sixth: Contractor further agrees to provide insurance as required by this Contract.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby executes this Contract and thereby binds itself to all covenants, terms, and obligations contained in the Contract Documents.

CONTRACTOR

Date

(Signature of Legally Authorized Representative
of the Contractor)

(Name and Title Printed)

G. Award.

Your offer is hereby accepted for (see marked boxes):

Operations \$ _____
Maintenance \$ _____

The original contract amount is: \$ _____
_____.

This award consummates the Contract, and the documents referenced herein.

MAINE DEPARTMENT OF TRANSPORTATION

Date

By: Bruce A. Van Note, Commissioner

Witness

CTM: _____

TEDOCS# _____

CSN _____

MAINE DEPARTMENT OF TRANSPORTATION
CONTRACT AGREEMENT
TRANSPORTATION RELATED MAINTENANCE WORK

This CONTRACT is made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (“Department” or “MaineDOT”), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and **ABC COMPANY** (“Contractor”) a corporation or other legal entity organized under the laws of the State of ME, with its principal place of business located at 123 ANY STREET, TOWN, ST 00000, with a mailing address of PO BOX XXX, TOWN, ST 00000, and a telephone number of (123)456-7890 .

The Vendor Customer Number of the Contractor is VC00000000 .

The following attachments are hereby incorporated into this Contract by reference:

- Appendix A – Special Provision - Specifications of Work to be Performed
- Appendix B – Special Provisions for State Funded Transportation Related Maintenance Work

The Department and the Contractor, in consideration of the mutual promises set forth in this Contract Agreement (hereinafter “Contract”) hereby agree as follows:

A. The Work.

The Contractor agrees to complete all work described in Appendix A – Special Provision - Specifications of Work to be Performed, and under the terms of the Contract for **Heating Services**, in **Regions 2, 3 & 4**, Maine.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools, supplies, facilities, permanent materials and temporary materials and services required to perform the Work including quality control, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

This contract commences on December 15, 2018 or when executed, whichever is latest and expires on **December 15, 2019** unless extended under the terms of this contract. At the Department's discretion and upon mutual agreement with the Contractor, the Contract may be extended for time and money, under all the terms of this contract, at bid prices for agreed periods of time up to approximately four (4) additional years.

C. Price.

The quantities given in the Schedule of Items in Appendix A will be used as the basis for determining the original Contract amount, and that the amount of this offer is

Section 1 - \$ (Place bid here in alphabetical form such as One Hundred Two dollars)

\$ (repeat bid here in numerical terms, such as \$102.00)

Section 2 \$ (Place bid here in alphabetical form such as Two Hundred dollars)

\$ (repeat bid here in numerical terms, such as \$200.00) .

The Maine DOT does not guarantee the use of any or all of the Contract amount.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the State of Maine, Department of Transportation, *Standard Specifications, March 2020 Edition* as updated through advertisement, Division 100 - General Conditions, Special Provisions, Contract Agreement and Appendices. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

1. All of the statements, representations, covenants, and certifications required or set forth in the Contract are still complete and accurate as of the date of this contract.
2. The Contractor knows of no legal, contractual, or financial impediment that prevents Contractor from entering into this Contract.
3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Contract Agreement.

The undersigned, having carefully examined the site of work, scope of work, State of Maine, Department of Transportation, *Standard Specifications, March 2020 Edition*, Division 100 - General Conditions, Special Provisions, Contract Agreement and Appendices contained herein, hereby agrees to supply all the services, materials, tools, equipment and labor to complete the whole of the work in strict accordance with the terms and conditions of this Contract at the prices agreed to in Appendix A.

The Contractor agrees to perform the work required at the prices specified above in accordance with the terms of this Contract and to provide the appropriate insurance.

Contractor also agrees:

First: Contractor agrees to perform extra work, not described in Appendix A, which may be ordered by the Department, and to accept as full compensation the amount determined upon basis as provided in the contract documents.

Second: Contractor understands that Work may commence upon Contract Execution, unless provided elsewhere in this contract and that Work must be completed within the time limits given in this Contract.

Third: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Fourth: The Contractor hereby certifies, to the best of its knowledge and belief that: the Contractor has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

Fifth: Contractor further agrees to provide insurance as required by this Contract.

BOND # _____

CONTRACT PAYMENT BOND
(Surety Company Form)

KNOW ALL MEN BY THESE PRESENTS: That _____
_____ **in the State of** _____, as principal,
and.....
a corporation duly organized under the laws of the State of and having a
usual place of business in
as Surety, are held and firmly bound unto the Treasurer of the State of Maine for the use
and benefit of claimants as herein below defined, in the sum of
_____ **and 00/100 Dollars (\$** _____ **)**
for the payment whereof Principal and Surety bind themselves, their heirs, executors and
administrators, successors and assigns, jointly and severally by these presents.

The condition of this obligation is such that if the Principal designated as Contractor in
the Contract to construct Project Number _____ in the Municipality of
_____ promptly satisfies all claims and demands incurred for all
labor and material, used or required by him in connection with the work contemplated by
said Contract, and fully reimburses the obligee for all outlay and expense which the
obligee may incur in making good any default of said Principal, then this obligation shall
be null and void; otherwise it shall remain in full force and effect.

A claimant is defined as one having a direct contract with the Principal or with a
Subcontractor of the Principal for labor, material or both, used or reasonably required for
use in the performance of the contract.

Signed and sealed this day of, 20 .. .

WITNESS:

SIGNATURES:

CONTRACTOR:

Signature.....

.....

Print Name Legibly

Print Name Legibly

SURETY:

Signature.....

.....

Print Name Legibly

Print Name Legibly

SURETY ADDRESS:

NAME OF LOCAL AGENCY:

.....

ADDRESS

.....

.....

TELEPHONE

.....



**APPENDIX A
 SPECIAL PROVISIONS
 REQUEST FOR PROPOSALS
 AND
 SPECIFICATIONS OF WORK TO BE PERFORMED**

Contractor _____

SCHEDULE OF ITEMS

- The Bid must be Delivered to the precise location and by the precise time set forth in the Notice to Contractors or any applicable Bid Amendment.
- Required unit prices, lump sum prices and/or bid amounts must be provided and legible.
- Do not make handwritten changes to the bid documents.

Each Item shall be awarded separately. Bidders shall bid one or more Items.

Item Description	Estimated Quantities & Units	Unit Price \$/Per Year	Total Bid Amount \$/Per Line Item for 5 years
Casco Bay Bridge Operations	5 Years	\$	\$
Casco Bay Bridge Routine Maintenance	5 Years	\$	\$

- **Paper bids must be signed in pen and ink. Signatures shall be original. Stamped and copied signatures will not be accepted.**

Signature *Date*

(Print Respondent's Name and Title)

**Electronic bidding will NOT be available
for this bid.**

**Bids will NOT be accepted
by email or fax.**

**SIGNED PAPER BIDS ARE REQUIRED
and may be
mailed, sent express or hand delivered.**

The Maine Department of Transportation is soliciting bid proposals to provide operations and routine maintenance for the Casco Bay Bridge. Contractor may enter into a 5-year contract beginning on March 7, 2021 or upon contract execution, whichever is later.

I. SCOPE OF WORK

This is operations and maintenance work involving the computerized operation and routine maintenance of a large and complex movable bridge. Responsibilities involve conducting day-to-day operation of the bridge and using a computer system to regulate passage of oceangoing vessels. Tasks include troubleshooting technical problems to maintain passage capability and monitoring a multi-camera security system to comply with federal security requirements. This location is on major thoroughfare with heavy vehicular traffic and requirements for frequent openings. The frequency of the openings has averaged 2.3 openings per 24 hours and openings require approximately 15 minutes to complete. The Contractor and the employees are responsible for ensuring the immediate, safe, secure, and proper operations of the bridge during assigned hours. Operations work is performed under general supervision.

Maintenance includes routine maintenance in accordance with the schedules provided by the Department in this contract. Maintenance work is performed under general supervision.

Operations. This work will include labor and management to operate the Casco Bay Bridge in compliance with applicable Coast Guard regulations. The Contractor shall staff the bridge with two (2) Bridge Operations Technicians to operate the bridge at all times. Bridge Operations Technicians may not leave until their replacement shows up. Bridge Operations Technicians may not work more than two (2), consecutive, 8-hour shifts. Bridge Operations Technicians must remain awake and alert at all times.

Bridge Operations Technician duties include the following:

- Looks and listens for radio contact and signals from approaching vessels and communicates by radio in order to implement passage/closure procedures
- Watch and warn approaching vehicular and pedestrian traffic prior to and during the operation of the draw bridge and ensure there are no vehicles or pedestrians on the draw span or between the gates when the draw is being operated.
- Operates computer console in order to open and close bridge for vessel passage.
- Troubleshoots technical problems on computer system in order to permit timely vessel passage.
- Operates multi-camera security system in order to monitor security as required by federal regulations.
- Records information on passage vessel in manual and computer logs in order to document bridge usage, including the names of the vessels which pass through the draw, their size, the direction of travel and the time.
- Hand crank traffic and pedestrian gates to open and close if the gates fail to operate using the electrical/mechanical system.
- Cleans facility control tower, kitchen area, restrooms, and locker area.
- Housekeeping around the tender's building as described in this RFP.
- Picking up and disposing of litter along the curb.
- Shoveling snow as described below.
- Reports repair needs to MaineDOT representative designated in order to initiate repair process.

- Instructs and mentors new Bridge Operations Technicians in order to fully train on bridge processes and equipment use.
- Notifies the MaineDOT representative(s) designated of accidents and issues immediately.

Training will be provided by the MaineDOT for the first year. The Contractor shall be responsible for training after the first year. Bridge Operations Technicians shall pass a MaineDOT Casco Bay Bridge Operator Certification Test, administered by the MaineDOT, covering Casco Bay Bridge policies and procedures and applicable Coast Guard regulations prior to operating the control panel and within the first three months of employment.

All operations shall be in accordance with MaineDOT policies and procedures and the Casco Bay Bridge Operators Manual.

The Contractor shall provide supervision. The Contractor shall provide two or more contact numbers to the MaineDOT for conflict resolution and to handle issues to ensure that a supervisor is available and can be contacted 24 hours seven days a week.

The MaineDOT will provide two-way handheld radios. The Department is responsible for providing the phone lines and phones.

The MaineDOT will provide computers which are only to be used for performing Work under this contract. No other uses will be allowed.

The Contractor shall maintain a list of available personnel meeting the qualifications set forth in this bid and their contact information. Special requirements, such as passage of a background check, may be required of the awarded Contractor and their staff prior to the beginning of any work being performed by the Contractor's staff; this also may include any additional staff that is added.

The Contractor shall furnish all materials and cleaning supplies. The materials furnished shall include, but not be limited to, paper towels, toilet paper, and hand soap, waste can liners and light tubes/bulbs. Cleaning products will be certified as a "green" product". Using any other product will need the approval from the Contract Administrator before using. Fixture deodorant/sanitizers are not acceptable. The Contractor will be able to use the available cabinet space for the storage of supplies and materials.

The Contractor will be responsible for the removal of trash and waste from the site and the cost of disposal services.

Cleaning will be done as described in the attached Cleaning Checklist. Cleaning shall be performed at least weekly, but more often, if needed. The Contractor shall email the completed checklists weekly to the MaineDOT representative designated. This work includes, but is not limited to:

- Empty wastebaskets, collect trash.
- Sweep and/or vacuum all floors.
- Maintain all entry floor mats and runners.
- Complete hygienic cleaning of rest rooms.
- Re-stock rest room and pantry supplies.

- Wash interior windows, door glass and mirrors.
- Clean walls, partitions, and woodwork.
- Dust computer console and monitors, counters, furniture, windows and other dust collecting surfaces.
- Clean and disinfect kitchen pantries.
- Wash readily accessible exterior glass (weather permitting).
- Clean locker rooms.

The MaineDOT will have primary responsibility for removing snow and ice from the bridge. However, there will be times when the Department will not have cleared the snow and ice when shifts are changing and the Contractor will be required to shovel or clear snow and ice between the control tower and their vehicles and apply salt as needed and from in front and around the pedestrian gates.

The Draw Tenders' building is a two story structure which is accessed from the employee parking lot off the northbound lane from South Portland. The employees lounge is separated from the control room by a single flight of stairs. Employees have the freedom to move about the building and are encouraged to do so periodically. Kitchen facilities and are available. The Contractor shall be responsible for replacing the television and/or recliners, as appropriate or necessary. Only Bridge Operations Technicians, Bridge Maintenance Technicians, their supervisors, authorized MaineDOT personnel and other persons authorized by MaineDOT representatives designated are permitted in the Draw Tenders' building or in the bridge. Bridge Operator Technicians shall make sure all contractors personnel, including those from other companies, sign in and sign out when entering the Draw Tenders' Building and in the bridge. The Contractor shall send a copy of the sign in sheet by email to the MaineDOT representative designated monthly. The public and employee's family members are not allowed in the building nor the bridge.

Maintenance. This work will include labor and management to perform routine maintenance and inspections on the Casco Bay Bridge. The Contractor shall staff the bridge with Bridge Maintenance Technicians as needed to meet the requirements of this contract.

All Routine Maintenance work, inspections and service shall be performed under the supervision of designated MaineDOT representatives for the first year. The Contractor must notify the Department at least 48 hours prior to performing maintenance, inspections and service work. The Department may determine, on a case by case basis, that certain tasks may be performed without supervision. At the Department's discretion, the Department may extend the requirement that work be performed under the supervision of designated MaineDOT representatives beyond the first year.

All maintenance work is to be documented and documentation and reports are to be emailed to MaineDOT representative designated.

Maintenance shall include the following:

1. Monthly walk through and inspections of bridge and generator room. Clean all trash from pit areas and wipe excess grease from machinery well during monthly walkthroughs.
2. Lubricate Machinery in accordance with the lubrication schedules.
3. Service span-locks every three months.
4. Grease rack/pinion during monthly walk through.
5. Service air buffers every 3 months.
6. Service trunnion bearings every 6 months.
7. Service 13inch brake wheel couplers every 6 months.
8. Service large kop flex couplings every 6 months.
9. Service pinion bearings every 6 months.
10. Service shifter coupling on aux drive every 6 months.
11. Service and inspect all traffic gates and pedestrian gates every 3 months.
12. Clean up oil and grease, trash and debris from the machinery room and surrounding areas biweekly.
13. Check leaking oil reducer buckets every two weeks to see if they are nearly full or if the rate of leakage has increased. If the bucket is nearly full, recycle oil back into the reducers as directed by MaineDOT. If the rate of leakage has increased, notify the MaineDOT representative designated. Change packing seals when determined by MaineDOT. There are 20 seals. Add fluid, Mobil 360, if needed.
14. Change navigation lightbulbs within 12 hours after an employee notices or the Contractor is notified by the Department or others. The Contractor shall furnish and install lights as needed. The Contractor shall maintain the current stock levels of 100 watt bulbs with a maximum wattage of 100.
15. Change traffic gate lights within two days when more than three lights are out on any gate. The Contractor shall furnish and install lights as needed. The Contractor shall maintain the current stock levels
16. Change flood lightbulbs in stairwells, walkways, etc. within 12 hours after an employee notices or the Contractor is notified by the Department or others. The Contractor shall furnish and install lights as needed. The Contractor shall maintain the current stock levels of Halogen light bulbs.
17. Check all warning lights for proper operation (1) every three months and (2) when the control panel indicates there is an issue or (3) when there is a complaint that lights aren't working. If any lights are not working notify the MaineDOT representative designated.
18. Clean live load shoes by removing rust, rocks, snow, ice, debris or anything else once every three months and whenever something is preventing the bridge from closing and seating properly. Scrape rust from live load shoes and coat with Fluid film every three months.
19. Clean and paint with zinc all rusting parts conduit, brake handles and anything starting to show rust.
20. Annually, check tabs holding the catwalk flooring down and replace all the broken steel tabs holding the catwalk flooring down with new stainless ones. Replacement clips shall be furnished by the Contractor and approved by the MaineDOT prior to installation.
21. Set heater switches up and down as seasonally appropriate.

The Contractor shall provide all equipment and tools necessary for the proper and safe accomplishment of the work. Equipment shall be well maintained and in good working order. The Contractor shall furnish all materials and supplies required to perform the maintenance work. The materials and supplies furnished must be approved by the Department prior to use. If any product named is no longer available, the Department approve use of the newly selected product.

Bridge Maintenance Technicians shall pass a MaineDOT Casco Bay Bridge Operator Certification Test covering Casco Bay Bridge policies and procedures and applicable Coast Guard regulations within the first three months of employment.

The Contractor will be responsible for disposal of rags, trash, oil, etc. and for the cost of disposal services of all materials resulting from their duties in this contract.

The Contractor shall notify and contact the MaineDOT representative, when as a result of performing routine maintenance, it is discovered that anything may not be working properly or needs repair or should be checked.

When it is determined by the Department that extra work is required, the Department may request the Contractor to perform the service. The Contractor will be compensated as per Section 109.7 Force Account Work of the Standard Specifications.

General Operations and Maintenance. The Contractor shall notify and contact the MaineDOT representative, when as a result of performing routine operations, it is discovered that anything may not be working properly or needs repair or should be checked.

When it is determined by the Department that extra work is required, the Department may request the Contractor to perform the service. The Contractor will be compensated as per Section 109.7 Force Account Work of the Standard Specifications.

MaineDOT will maintain and furnish to the Contractor an updated list/procedure of MaineDOT designated representatives to contact regarding this work. “MaineDOT designated representatives” may include persons other than those employed by MaineDOT.

No personnel employed by the Contractor are to open electrical cabinets or panels.

II. REQUIREMENTS

Contractor Requirements:

1. The Contractor must have 5 or more years of experience in the maintenance of machine operated moveable bridges.
2. The Contractor must have knowledge and experience involving Coast Guard regulations for navigable waterways including 33 CFR 117.
3. After the first year, the Contractor shall have a training program for employees in Casco Bay Bridge Operations and applicable Coast Guard Regulations. The Contractor will be financially responsible for this training and cost for this training.

4. The Contractor shall create an updated training manual for the Maintenance program covered by this contract. The training manual shall be submitted and accepted to and accepted by the MaineDOT one year from the award of the contract. The training manual shall be submitted electronically and using Microsoft Word®.
5. The Contractor shall create an updated training manual for the Bridge Operation Technician program covered by this contract. The training manual shall be submitted and accepted to the MaineDOT one year from the award of the contract. The training manual shall be submitted electronically and using Microsoft Word®.
6. The Contractor must have an employee safety plan. The Apparent Successful Bidder must furnish a copy of a compliant Company Safety Plan prior to award. The Contractor's Safety Plan shall identify and address job hazards of the expected contract work and shall comply with all applicable federal, State, and local laws governing safety including all applicable laws and regulations of OSHA.
7. The Contractor must maintain, per OSHA and Department of Labor Standards, complete and current set of MSDS (Material Safety Data Sheets) MSDS sheets shall be placed in a 3-ring binder and clearly marked and accessible. A Contractor with employees who are, or may be, exposed to hazardous chemicals known to be present in their workplaces, must develop, implement, and maintain at each workplace a written hazard communication program.
8. The Contractor shall train employees annually on Lock-Out/Tag-Out Procedures and Spill Prevention. The certificate verifying the employee's receipt of this training will be furnished to the Department and displayed on site. The Contractor will be financially responsible for this training and cost for this training.
9. The Contractors designated Supervisor shall be able to apply, possess and maintain a valid TWIC® (Transportation Work Identification Credential)
10. Any and all request for substitution or revisions of materials or procedures used shall be made in writing to the MaineDOT representative and none of the substitutions or revisions shall occur without written approval from the MaineDOT representative.
11. DRUG FREE WORKPLACE. By signing the Contract, the Contractor certifies that it shall maintain a drug-free workplace by:
 - Publishing a statement notifying their employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited on MaineDOT property and specifying the actions that will be taken against employees for violation of such prohibition.
 - Notifying their employees that as a condition of employment under the Agreement that the employee will abide by the terms of the statement and notify the employer of any criminal drug conviction for a violation occurring in the workplace no later than five (5) days after such conviction.
 - The Provider shall notify the MaineDOT Agreement Administrator within ten (10) days of receipt of a notice of criminal drug convictions occurring in the workplace by their employee, or otherwise receiving actual notice of such conviction.

Minimum Bridge Operations Technician Requirements:

The following is a list of the Minimum Requirements for employees to be allowed to perform bridge operations for MaineDOT under this contract.

1. Knowledge of basic computer operations.
2. Knowledge of applicable laws, rules, regulations, policies, procedures, paperwork, terminology, and core operations.
3. Ability to operate applicable specialized equipment upon completion of appropriate training.
4. Ability to read, write, hear, understand and follow basic oral and written instructions given in English, read and understand electronic readouts (LCDs) which display error messages, use a phone, a cell phone and the marine radio clearly and concisely and communicate with other employees, Department personnel and the public using written and oral skills.
5. Ability to effectively give/obtain basic, non-technical information.
6. Ability to gather and compile information.
7. Ability to use applicable computer programs.
8. Ability to maintain computerized and manual information.
9. Ability to identify operating malfunctions and take corrective action in accordance with established procedures.
10. Ability to work with timelines and schedules.
11. Ability to clean facilities and equipment as required.
12. Ability to remain calm and utilize good decision making skills in stressful situations, including in the event of an emergency, such as the bridge cannot open and a boat is coming.
13. Must be medically certified that he or she is qualified to operate the bridge.
14. Ability to perform work requiring physical exertion will be required and ability to get to required access points. Employees must be able to climb a flight of stairs a minimum of six (6) times per shift, climb over a 3' high jersey barrier, climb up and down a vertical ladder in cases of emergency evacuation, work outside in all weather conditions, withstand long periods of inactivity, be able to reach switches to the far left and far right simultaneously on the control panel, turn, hold and operate switches and levers on the controls, hand crank pedestrian and traffic gates, and shovel snow.
15. Employees must be included in a compliant drug and alcohol testing program.
16. Employees must be willing to submit and pass a criminal background check.
17. Ability to communicate effectively to others either in person, over the phone and by radio, in an emergency situation.
18. Ability to perform assigned work effectively with minimum supervision.
19. Employees must have knowledge of all state and federal laws, codes and regulations and OSHA requirements pertaining to the operations and must be familiar with MaineDOT safety policies and operation practices, the Contractor's Safety Plan and the procedures to be followed in case of an accident.
20. Employees must have completed and passed training and be willing to comply with these policies and procedures in Personnel Protection Equipment, Lock-Out/Tag-Out Procedures and Spill Prevention.
21. Employees must have a cellular phone and the ability to be contacted 24/7 for emergency situations.

22. All employees working this contract working this contract must complete the OSHA 10 Hour General Industry safety course and the Contractor's supervisors must have completed the OSHA 30-hour General Industry safety course.

Minimum Bridge Maintenance Technician Requirements:

The following is a list of the Minimum Requirements for employees to be allowed to perform bridge maintenance for MaineDOT under this contract.

1. Knowledge of basic computer operations.
2. Knowledge of applicable laws, rules, regulations, policies, procedures, paperwork, terminology, and core operations.
3. Ability to operate applicable specialized equipment upon completion of appropriate training.
4. Ability to read, write, hear, understand and follow basic oral and written instructions given in English, and communicate with other employees, Department personnel and the public using written and oral skills.
5. Ability to communicate effectively orally and in writing to explain procedures that need to be performed by others.
6. Ability to prepare and keep accurate records relating to preventative maintenance, repairs, and upgrades performed.
7. Ability to gather and compile information.
8. Ability to use applicable computer programs.
9. Ability to maintain computerized and manual information.
10. Ability to work with timelines and schedules.
11. Ability to clean facilities and equipment as required.
12. Ability to remain calm and utilize good decision making skills in stressful situations, including in the event of an emergency, such as the bridge cannot open and a boat is coming.
13. Must be medically certified that he or she is qualified to perform maintenance work on the bridge.
14. Ability to perform work requiring physical exertion will be required and ability to get to required access points. Employees must be able to climb a flight of stairs, climb over a 3' high jersey barrier, climb up and down a vertical ladder, and work outside in all weather conditions,
15. Employees must be included in a compliant drug and alcohol testing program.
16. Employees must be willing to submit to and pass criminal background check.
17. Ability to communicate effectively to others either in person, over the phone and by radio, in an emergency situation.
18. Ability to perform assigned work effectively with minimum supervision.
19. Employees must have knowledge of all Laws and OSHA requirements and must be familiar with MaineDOT safety polices and operation practices, the Contractors' Safety Plan, and the procedures to be followed in case of an accident.
20. Employees must have completed and passed training in Personnel Protection Equipment and Lock-Out/Tag-Out Procedures and be willing to comply with these policies.
21. Employees must have a cellular phone and the ability to be contacted 24/7 for emergency situations.
22. All employees working this contract must complete the OSHA 10 Hour General Industry safety course and the Contractor's supervisors must have completed the OSHA 30-hour General Industry safety course.

III. INVOICING, MEASUREMENT AND PAYMENT

Bridge operations and routine maintenance for the Casco Bay Bridge will be paid by the month, which payment includes two (2) bridge operations technician positions filled 24 hours a day, seven (7) days a week, all supervision and training required for the work, bridge maintenance technicians and all other labor, equipment, materials and supplies necessary to perform the work. No such payment will be made if, in the judgment of the Department, the Work is not proceeding in accordance with the provisions of the Contract.

IV. FAILURE TO PERFORM AND TERMINATION

Failure by the Contractor to provide two (2) alert and competent Bridge Operations Technicians at all times will result in the actions listed on the Deficiency and Penalty Table. If the Contractor fails to provide two (2) Bridge Operations Technicians at all times the Department may perform the Work with its own forces or enter into Contract with another entity for the performance of the Work, or use such other methods as in the opinion of the Department are required for to complete the Work.

Once a vessel requests an opening, the operators must immediately acknowledge the request and begin the opening process. If due to any act, omission, neglect or misconduct of the Contractor, the Contractor fails to open the drawbridge in time for a boat to pass, unnecessarily opens the draw, or lowers the drawbridge on a vessel, the Department will apply the actions listed on the Deficiency and Penalty table. Any and all penalties levied onto the MaineDOT as a result of the Contractors actions, shall be the responsibility of the Contractor.

Bridge Operators are required to watch and warn approaching vehicular and pedestrian traffic prior to and during the operation of the draw bridge and ensure there are no vehicles or pedestrians on the draw span or between the gates when the draw is being operated. Lowering the gates when there are vehicles or pedestrians between or under the gates will result in the actions listed on the Deficiency and Penalty table.

Only Bridge Operations Technicians, Bridge Maintenance Technicians, their supervisor and authorized MaineDOT personnel are permitted in the Draw Tenders' building. Allowing unauthorized personnel in the Draw Tenders' building will result in the actions listed on the Deficiency and Penalty table.

If the Contractor submits a walk through report which is not accurate regarding any work or inspection, reports that work has been performed which has not been performed, uses materials or products different than those specified without MaineDOT approval, performs maintenance work without notifying MaineDOT when required or does not report repairs needed or functions checked, it will result in the actions listed on the Deficiency and Penalty table.

The Contractor shall be considered to be in non-compliance if it, or any Subcontractors at any tier, fails to comply with the terms of this contract or pursuant to Section 104.3.7 – Laws to be Observed, any applicable Coast Guard law or regulation. The Contractor shall be responsible for any fines and penalties assessed by the Coast Guard due to such non-compliance. Such penalties may be withheld from the amounts otherwise due the Contractor.

DEFICIENCY AND PENALTY TABLE		
1 st Incident	The contractor SHALL NOTIFY THE Department immediately. The Department will issue a written warning.	The Maine DOT shall reduce the Contractors monthly payment by \$10,000.
2 nd Incident	The contractor SHALL NOTIFY THE Department immediately. The Department will issue a written warning.	The Maine DOT shall reduce the Contractors monthly payment by \$25,000.
3 rd Incident	The Department may (A) give written Notice of Default to the Contractor and terminate the Contract by written Notice of Termination, or (B) take prosecution of the Work away from the Contractor without violating the Contract.	The Maine DOT shall reduce the Contractors monthly payment by \$25,000.

Failure by the Contractor to perform the Contract requirements not specifically addressed elsewhere in this contract when required or to substantially meet other contractual requirements will result in the following actions. If the Contractor does not take corrective action within 2 days upon receipt of verbal warning, the Department will issue a written warning. If the Contractor receives more than three written warnings for the same or similar defects, the Department may (A) give written Notice of Default to the Contractor and immediately terminate the Contract by written Notice of Termination, or (B) take prosecution of the Work away from the Contractor without violating the Contract.

The Contractor is in Default of the Contract if the Contractor:

- A. Fails to provide labor, Equipment or Materials specified in the Contract,
- B. Fails to perform the Work with sufficient labor, Equipment, or Materials to comply with contract provisions,
- C. Fails to perform Work when specified in the Contract,
- D. Performs Defective Work, neglects or refuses to repair or correct Unacceptable Work when directed by the Department,
- E. Becomes insolvent or is declared bankrupt or commits any act of bankruptcy or insolvency that could affect the Work in any way,
- F. Allows any final judgement to stand against the Contractor unsatisfied for a period of ten Days
- G. Makes an assignment for the benefit of creditors without authorization by the Department,
- H. Continues to perform Work after the Department directs that Work be stopped, or
- I. In any other manner, fails to perform the Work in Substantial Conformity with any material provision of the Contract.

If Default occurs, the Department may give written Notice of Default to the Contractor. Failure to give Notice of Default is in no way a waiver by the Department of any provision of the Contract. In this event, the Department may enter into an Agreement with another entity for the Completion of the Work, or use such other methods as in the opinion of the Department are required for the Completion of the intent of the Contract in an acceptable and timely manner. Termination of the Contract or portion thereof shall not relieve the Contractor of its Contractual responsibilities for the Work completed (including warranty obligations), nor shall it relieve the Surety of its obligation for claims arising from the Work or the

Contract. The Department will pay for all Accepted items of Work as of the date of Termination at agreed upon prices. The Contractor shall make all Work records available to the Department upon request regarding payment under this Section.

If the contract is terminated, the Contractor shall be required to continue work under all terms of the contract for 60 days.

V. PROPOSAL SUBMISSION REQUIREMENTS

1. General Information

Bidders shall ensure that all information required herein is submitted with this proposal. Provision of inaccurate information or failure to provide all completed and required information may result in the Proposal being disqualified as non-responsive or receiving a reduced score. Bidders should be mindful of the Evaluation Criteria that are indicated in this RFP and shall provide information in the proposal that will permit an objective evaluation thereof. MaineDOT reserves the right to reject any or all bids.

Bidder's Proposal shall include all items listed in the "Bidding Instructions" and information requested in #3, Proposal Content, below.

2. Proposal Format

- a. Schedule of Items, Proposal Worksheet and Economic Impact Worksheet in the Bid Book are to be used for bid price submittal and qualification requirement information. No variations or alterations are to be made to these worksheets.
- b. Additional information requested in this Proposal should be typed or printed.
- c. Bidder's name should appear on all attachments submitted.
- d. Bidders are asked to respond to each Section below. Number each response of the Proposal to correspond to the relevant section.

3. Proposal Content

Section I – Company's Qualifications and Experience

- a. Present Company's history and experience of work related specifically to the Scope of Work in this RFP for Items bid.
- b. List all Technician Supervisors who will be performing Work under this contract, their experience and number of years performing work related specifically to the Scope of Work in this RFP
- c. Complete the Proposal Worksheet and Economic Impact Worksheet, answering all questions listed.

Section II – Bid Price

Complete the Schedule of Items. Bidders may bid one or both items.

Section III – Bidder’s Safety Record

Using your OSHA 300 Log and statements provided by your insurance, provide your workers’ compensation Experience Modification Rate, information regarding your company’s safety officer, department policies and procedures, and other supporting info. Please provide an electronic copy of your company safety manuals.

Section IV – References

Submit 3 references for each item bid – company Name, contact name & phone #, from previous customers that have had similar work performed by your company.

Section V – Bidder’s Knowledge of Coast Guard Regulations

For each Item bid, submit similar work performed by your company. Submit the employees who will be responsible for Work under this contract, their experience and number of years performing work related specifically to the Coast Guard regulations.

VI. PROPOSAL EVALUATION AND SCORING

Each Item will be awarded separately. Bidders may bid one or more items. Bidders shall submit all proposal requirements.

1. The scores will be based on a 100-point scale. An evaluation Committee will review each Proposal and score on the basis of the following weighted criteria

Criteria	Weight
Bidder’s Qualifications & Experience	50%
Costs (Stated in Appendix A Schedule of Items)	25%
Bidder’s Safety Record	5%
References	5%
Bidder’s Knowledge of Coast Guard Regulations	15%

2. The contract award(s) will be made to the bidder who receives the Committee’s highest score for each item following the final review.
3. The Evaluation Committee will be composed of at least 3 reviewers who will judge the merits of the Proposals in accordance with the criteria defined in this RFP. The goals of the evaluation process are to ensure fairness and objectivity in review of the Proposals and to ensure that the contract is awarded to the Bidder whose Proposal best satisfies the criteria of the RFP at a reasonable/competitive cost. MaineDOT reserves the right to communicate with Bidders, if

needed, to obtain clarification of information contained in the proposals received. Changes to Proposals will not be permitted during any interview/presentation process.

4. The Evaluation Committee will use a consensus approach to evaluate the Proposals. Members of the Evaluation Committee will not score the Proposals individually but instead will arrive at a consensus as to assignment of points on each category of each Proposal. The contract award will be made to the Bidder receiving the highest number of evaluation points based upon the Proposal's satisfaction of the criteria established in the RFP.

5. The Cost section will be scored as follows:

Scoring the Cost Proposal: The cost proposed for conducting all the functions specified in this RFP for one year will be assigned a score according to a mathematical formula. The lowest bid will be awarded 25 points. Proposals with higher bid values will be awarded proportionately fewer points calculated in comparison with the lowest bid.

The scoring formula is:

$$\frac{\text{(lowest submitted cost proposal divided by the cost of proposal being scored)}}{\text{pro-rated score}} \times 25 =$$

6. No Best and Final Offers: The State of Maine will not seek a best and final offer (BAFO) from any Bidder in this procurement process. All Bidders are expected to provide their best value pricing with the submission of their proposal.
7. Issuance of this RFP in no way constitutes a commitment by the State of Maine to award a contract, to pay costs incurred in the preparation of a response to this request, or to pay costs incurred in procuring or contracting for services, supplies, physical space, personnel or any other costs incurred by the Bidder.
8. Once scores are final, award will be made to the bidder whose proposal receives the Committee's highest score per location. The successful bidder will receive written notification of the award and the results will be posted on the MaineDOT website.
9. The information contained in proposals submitted for the State's consideration will be held in confidence until all evaluations are concluded and the award notification has been made. At that time, the full content of the proposals become public record and is therefore available for public inspection upon request.
10. By submitting a Proposal, the bidder agrees and assures that the specifications are adequate, and the bidder accepts the terms and conditions herein. Any exceptions should be noted in the Proposal. The State reserves the right to reject any or all proposals based on the exceptions presented, without obligation to communicate or negotiate with the bidder.
11. The details of the evaluation process will be provided to interested parties, upon request, after selection of the apparent successful proposal.

PROPOSAL WORKSHEET

Answer questions below by circling appropriate response:

1.	Contractor has knowledge and experience involving Coast Guard regulations for navigable waterways.	YES	NO
2.	Contractor has more than 5 years of experience in the maintenance of machine operated moveable bridges	YES	NO
3.	Contractor has a safety plan that identifies and addresses job hazards of the expected contract work and complies with all applicable federal, State, and local laws governing safety including all applicable laws and regulations of OSHA.	YES	NO
4.	Contractor will provide training programs and train employees in Lock-Out/Tag-Out Procedures and Spill Prevention & Bridge Operations.	YES	NO
5.	The Contractor will ensure employees possess all Personal Protective Equipment needed to perform job duties and comply with safety guidelines and procedures.	YES	NO

Bidders shall attach and provide information supporting “yes” answers to questions above.

SPECIAL PROVISIONS
FOR STATE FUNDED TRANSPORTATION RELATED MAINTENANCE WORK

1. **BENEFITS AND DEDUCTIONS** If the Contractor is an individual, the Contractor understands and agrees that he/she is an independent contractor for whom no Federal or State Income Tax will be deducted by the Department, and for whom no retirement benefits, survivor benefit insurance, group life insurance, vacation and sick leave, and similar benefits available to State employees will accrue. The Contractor further understands that annual information returns, as required by the Internal Revenue Code or State of Maine Income Tax Law, will be filed by the State Controller with the Internal Revenue Service and the State of Maine Bureau of Revenue Services, copies of which will be furnished to the Contractor for his/her Income Tax records.

2. **INDEPENDENT CAPACITY** In the performance of this Contract, the parties hereto agree that the Contractor, and any agents and employees of the Contractor shall act in the capacity of an independent contractor and not as officers or employees or agents of the State.

3. **DEPARTMENT'S REPRESENTATIVE** The Contract Administrator shall be the Department's representative during the period of this Contract. The Contract Administrator has authority to curtail Work if necessary to ensure proper execution of the Contract, to take actions needed to assure that the Contractor's Work conforms with the Contract, to decide questions regarding quality and acceptability of Work, to suspend Work, to reject Unacceptable or Unauthorized Work and to refuse to approve Progress and Final Payments until Unacceptable or Unauthorized Work is corrected. The Contract Administrator shall certify to the Department when payments under the Contract are due and the amounts to be paid. He/she shall make decisions on all claims of the Contractor. Unless authorized by the Contract Administrator, other Departmental employees are not authorized to alter or waive the provisions of the Contract or to issue instructions contrary to the Contract.

The Department has the authority to inspect all Materials and every detail of the Work. The Contractor shall provide the Department with safe access to all portions of the Work in Conformity with all applicable OSHA requirements. The Contractor shall furnish the Department with all information and assistance required to make a detailed inspection.

4. **CONTRACT ADMINISTRATOR** All progress reports, correspondence and related submissions from the Contractor shall be submitted to the Department's Project Manager who is designated as the Contract Administrator on behalf of the Department for this Contract, except where specified otherwise in this Contract.

5. **CHANGES IN THE WORK** The Department shall have the right to alter the nature and extent of the Work as provided in the Contract, the Contract Amount being adjusted accordingly. In no event shall Contractor fail or refuse to continue the performance of its obligations under this Contract because of the inability of the parties to agree on an adjustment or adjustments. Any changes to the Contract that affect scope, compensation, time, quality, or other Contract requirements shall be by written Contract Modification, signed by both parties.

6. **SUBCONTRACTS** The Contractor is responsible for assuring that its subcontractors have sufficient skill and experience to perform the pursuant to the Contract. The Contractor is responsible for subcontractors that it employs and for coordinating and managing its subcontractors. The Contractor agrees to indemnify, defend, and hold harmless MaineDOT from and against all claims and causes of action arising out of any act or omission of Contractor's subcontractors, their agents, representatives, and employees. The Contractor agrees to indemnify the MaineDOT and hold it harmless from any claims asserted by, against or on behalf of Contractor's subcontractors. Included in this release is the

Contractor's agreement to waive any claims against MaineDOT to recover losses allegedly suffered by a subcontractor. If Work under this Contract is performed pursuant to subcontracts, the Contractor's obligations are not diminished and the Contractor remains responsible for all Work under the Contract.

7. **SUBLETTING, ASSIGNMENT OR TRANSFER** The Contractor shall not sublet, sell, transfer, assign or otherwise dispose of this Contract or any portion thereof, or of its right, title or interest therein, without written request to and written consent of the Contract Administrator. No subcontracts or transfer of the Contract shall in any case release the Contractor of its liability under this Contract.

8. **EQUAL EMPLOYMENT OPPORTUNITY** During the performance of this Contract, the Contractor agrees as follows:

- a. The Contractor shall not discriminate against any employee or applicant for employment relating to this Contract because of race, color, religious creed, sex, national origin, ancestry, age, physical or mental disability, or sexual orientation, unless related to a bona fide occupational qualification. The Contractor shall take affirmative action to ensure that applicants are employed and employees are treated during employment, without regard to their race, color, religion, sex, age, national origin, physical or mental disability, or sexual orientation.

Such action shall include but not be limited to the following: employment, upgrading, demotions, or transfers; recruitment or recruitment advertising; layoffs or terminations; rates of pay or other forms of compensation; and selection for training including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applicants for employment notices setting forth the provisions of this nondiscrimination clause.

- b. The Contractor shall, in all solicitations or advertising for employees placed by or on behalf of the Contractor relating to this Contract, state that all qualified applicants shall receive consideration for employment without regard to race, color, religious creed, sex, national origin, ancestry, age, physical or mental disability, or sexual orientation.
- c. The Contractor shall send to each labor union or representative of the workers with which it has a collective bargaining Contract, or other Contract or understanding, whereby it is furnished with labor for the performance of this Contract a notice to be provided by the contracting agency, advising the said labor union or workers' representative of the Contractor's commitment under this section and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- d. The Contractor shall inform the contracting Department's Equal Employment Opportunity Coordinator of any discrimination complaints brought to an external regulatory body (Maine Human Rights Commission, EEOC, Office of Civil Rights) against their agency by any individual as well as any lawsuit regarding alleged discriminatory practice.
- e. The Contractor shall comply with all aspects of the Americans with Disabilities Act (ADA) in employment and in the provision of Work to include accessibility and reasonable accommodations for employees and clients.
- f. Contractors and subcontractors with contracts in excess of \$50,000 shall also pursue in good faith affirmative action programs.

- g. The Contractor shall cause the foregoing provisions to be inserted in any subcontract for any work covered by this Contract so that such provisions shall be binding upon each subcontractor, provided that the foregoing provisions shall not apply to contracts or subcontracts for standard commercial supplies or raw materials.

9. **EMPLOYMENT AND PERSONNEL** The Contractor shall not engage any person in the employ of any State Department or Agency in a position that would constitute a violation of 5 MRSA § 18 or 17 MRSA § 3104. The Contractor shall not engage on a full-time, part-time or other basis pursuant to this Contract any personnel who are or have been at any time during the period of this Contract in the employ of the State of Maine, except regularly retired employees, without the written consent of the Department. Further, the Contractor shall not engage on this project on a full-time, part-time or other basis during the period of this Contract any retired employee of MaineDOT who has not been retired for at least one year without the written consent. The Contractor shall cause the foregoing provisions to be inserted in any subcontract for any work covered by this Contract so that such provisions shall be binding upon each subcontractor, provided that the foregoing provisions shall not apply to contracts or subcontracts for standard commercial supplies or raw materials.

10. **STATE EMPLOYEES NOT TO BENEFIT** No individual employed by the State of Maine at the time this Contract is executed or any time thereafter shall be admitted to any share or part of this Contract or to any benefit that might arise therefrom directly or indirectly that would constitute a violation of 5 MRSA § 18 or 17 MRSA § 3104. No other individual employed by the State at the time this Contract is executed or at any time thereafter shall be admitted to any share or part of this Contract or to any benefit that might arise therefrom directly or indirectly due to his employment by or financial interest in the Contractor or any affiliate of the Contractor, without the written consent of the Department. The Contractor shall cause the foregoing provisions to be inserted in any subcontract for any work covered by this Contract so that such provisions shall be binding upon each subcontractor, provided that the foregoing provisions shall not apply to contracts or subcontracts for standard commercial supplies or raw materials.

11. **WARRANTY OF NO COLLUSION** The Contractor hereby certifies that it did not, directly or indirectly, enter into any agreement, participate in any collusion or otherwise take any action in restraint of competitive bidding in connection with this Contract. For breach or violation of this warranty, MaineDOT shall have the right to annul this Contract without liability. Further, MaineDOT shall have the right to recover the full amount of such fee, commission, gift, or the value of consideration that may have been transferred by the Contractor in violation of this clause.

12. **RECORDS; ACCESS** The Contractor and its subcontractors shall maintain all books, documents, payrolls, papers, accounting records and information of any type on any medium ("Project Records") that pertain to this Contract for such period as specified under Maine Uniform Accounting and Auditing Practices for Community Agencies (MAAP) rules. Upon request by MaineDOT, the Contractor and its subcontractors shall make Work Records available for inspection and must provide MaineDOT with copies at all reasonable times without cost or liability to MaineDOT.

13. **TERMINATION AND FAILURE TO PERFORM** The Department may terminate this Contract with or without cause upon 7 days written notice. Termination of the contract shall not relieve the Contractor of its contractual responsibilities for the work completed prior to termination (including warranty obligations), nor shall it relieve the Surety of its obligation for claims arising from the Work or the Contract. The Department will pay for all accepted items of Work completed prior to the date of Termination at agreed upon prices.

If for any reason the Contractor is unable to complete the work in an acceptable manner the Department may give written Notice of Default to the Contractor, which will outline the required remedies. Any

delay by the Department in providing a written Notice of Default shall in no way constitute a waiver by the Department of any provision of the Contract. If the Department determines the default is not curable, the notice of default shall also include the date of termination. Termination of the Contract or portion thereof shall not relieve the Contractor of its Contractual responsibilities for the Work completed.

In addition the Department may enter into an Agreement with another entity for the Completion of the Work, or use such other methods as in the opinion of the Department are required for the Completion of the intent of the Contract in an acceptable and timely manner.

14. **GOVERNMENTAL REQUIREMENTS** The Contractor warrants and represents that it will comply with all governmental ordinances, laws and regulations including all applicable laws and regulations of OSHA.

15. **GOVERNING LAW** This Contract shall be governed in all respects by the laws, statutes, and regulations of the United States of America and of the State of Maine. Any legal proceeding against the State regarding this Contract shall be brought in State of Maine administrative or judicial forums. The Contractor consents to personal jurisdiction in the State of Maine.

If, in the performance of this Agreement, there arises a dispute between the Contractor and MaineDOT that cannot be resolved by the parties to the Contract, the parties may agree to submit the dispute to non-binding Alternate Dispute Resolution. All disputes shall be governed by Maine law, and all actions shall be filed in the Kennebec Superior Court, in Augusta Maine.

16. **STATE HELD HARMLESS** The Contractor agrees to indemnify, defend and hold harmless the State, its officers, agents and employees from any and all claims, costs, expenses, injuries, liabilities, losses and damages of every kind and description (hereinafter in this paragraph referred to as "claims") resulting from or arising out of the performance of this Contract by the Contractor, its employees, agents or subcontractors. Claims to which this indemnification applies include, but are not limited to, the following: (i) claims suffered or incurred by any Contractor, subcontractor, materialman, laborer and any other person, firm, corporation or other legal entity providing work, services, materials, equipment or supplies in connection with the performance of this Contract; (ii) claims arising out of a violation or infringement of any proprietary right, copyright, trademark, right of privacy or other right arising out of publication, translation, development, reproduction, delivery, use, or disposition of any data, information or other matter furnished or used in connection with this Contract; (iii) Claims arising out of a libelous or other unlawful matter used or developed in connection with this Contract; (iv) claims suffered or incurred by any person who may be otherwise injured or damaged in the performance of this Contract; and (v) all legal costs and other expenses of defense against any asserted claims to which this indemnification applies. This indemnification does not extend to a claim that results solely and directly from (i) the Department's negligence or unlawful act, or (ii) action by the Contractor taken in reasonable reliance upon an instruction or direction given by an authorized person acting on behalf of the Department in accordance with this Contract.

The Department's employees and other representatives act solely as representatives of the Department when conducting and exercising authority granted to them under the Contract. Such persons have no liability either personally or as Department employees.

17. **NOTICE OF CLAIMS** The Contractor shall give the Contract Administrator immediate notice in writing of any legal action or suit filed related in any way to the Contract or which may affect the performance of duties under the Contract, and prompt notice of any claim made against the Contractor by any subcontractor which may result in litigation related in any way to the Contract or which may affect the performance of duties under the Contract.

18. **INSURANCE** The Contractor shall provide signed, valid, and enforceable certificate(s) of insurance complying with this Section. All insurance must be procured from insurance companies licensed or approved to do business in the State of Maine by the State of Maine, Bureau of Insurance. The Contractor shall pay all premiums and take all other actions necessary to keep required insurances in effect for the duration of the Contract obligations, excluding warranty obligations.

Workers' Compensation For all Work performed by the Contractor and any subcontractor, the Contractor and each subcontractor shall carry Workers' Compensation Insurance or shall qualify as a self-insurer with the State of Maine Workers' Compensation Board in accordance with the requirements of the laws of the State of Maine. If maritime exposures exist, coverage shall include United States Long Shore and Harbor Workers coverage.

Commercial General Liability With respect to all Work performed by the Contractor and any subcontractors, the Contractor and any subcontractors shall carry commercial general liability insurance in an amount not less than \$400,000.00 per occurrence and \$2,000,000.00 in the Aggregate. The coverage must include products, completed operations, and Contractual liability coverages. The Contractual liability insurance shall cover the Contractor's obligations to indemnify the Department as provided in this Contract. The coverage shall also include protection against damage claims due to use of explosives, collapse, and underground coverage if the Work involves such exposures. The Department shall be named as additional insured on the Commercial General Liability insurance policies carried by the Contractor that are applicable to the Work.

Automobile Liability The Contractor shall carry Automobile Liability Insurance covering the operation of all motor vehicles including any that are rented, leased, borrowed, or otherwise used in connection with the Project. The minimum limit of liability under this Section shall be \$400,000.00 per occurrence.

Claims. Each insurance policy shall include a provision requiring the insurer to investigate and defend all named insured's against any and all claims for death, bodily injury or property damage, even if groundless.

19. **SEVERABILITY** The invalidity or unenforceability of any particular provision or part thereof of this Contract shall not affect the remainder of said provision or any other provisions, and this Contract shall be construed in all respects as if such invalid or unenforceable provision or part thereof had been omitted.

20. **INTEGRATION** All terms of this Contract are to be interpreted in such a way as to be consistent at all times. If the Contractor discovers any ambiguity, error, omission, conflict, or discrepancy related to the Contract, the Contractor must notify MaineDOT of the ambiguity or waive claims resulting from any such ambiguity. In the case of ambiguity the following components of the Contract shall control in the following descending order of priority:

- Contract Agreement, Transportation Related Maintenance Work
- Bid Amendments (most recent to least recent)
- Appendix A – Special Provision Specifications of Work to be Performed or Request for Proposals
- Appendix B – Special Provisions for State Funded Transportation Related Maintenance Work
- Appendix C – Special Provisions
- Any remaining appendices in alphabetical order.
- Any remaining Special Provisions
- The Department's Notice to Contractors and any amendments

21. **FORCE MAJEURE** The Department may, at its discretion, excuse the performance of an obligation by a party under this Contract in the event that performance of that obligation by that party is prevented by an act of God, act of war, riot, fire, explosion, flood or other catastrophe, sabotage, severe shortage of fuel, power or raw materials, change in law, court order, national defense requirement, or strike or labor dispute, provided that any such event and the delay caused thereby is beyond the control of, and could not reasonably be avoided by, that party. The Department may, at its discretion, extend the time period for performance of the obligation excused under this section by the period of the excused delay together with a reasonable period to reinstate compliance with the terms of this Contract.

22. **FURNISHING OF OTHER PROPERTY RIGHTS, LICENSES AND PERMITS** The Contractor shall acquire, at its sole expense, all property rights outside the Project Limits needed for construction staging, yarding, construction, waste disposal, or other Project-related purpose. The Contractor shall also acquire, at its sole expense, all licenses, Permits and other permissions that are necessary or appropriate to perform the Work that are not furnished by the Department.

23. **ALLOWABLE WORK TIMES** Work can be performed at any time except Saturdays, Sundays, Holidays and state government closure days, unless expressly specified otherwise in this Contract. Holidays are defined as New Year's Day, Martin Luther King Day, President's Day, Patriot's Day, Memorial Day, Independence Day, Labor Day, Indigenous Peoples Day, Veterans Day, Thanksgiving Day, the Friday after Thanksgiving Day, and Christmas Day. If a Holiday occurs on a Sunday, the following Monday shall be considered a Holiday. If a Holiday occurs on a Saturday, the preceding Friday shall be considered a Holiday. Saturday, Sunday or Holiday work must be approved by the Department. The Contractor is solely responsible for the planning and execution of Work in order to complete the Work within the Contract Time.

24. **SET-OFF RIGHTS** MaineDOT shall have all of its common law, equitable and statutory rights of set-off. These rights shall include, but not be limited to, MaineDOT's right to withhold and take possession of monies due to the Contractor under this Contract up to any amounts the Contractor owes to the State of Maine pursuant to this Contract or any other contract, including any contract for a term commencing prior to the term of this Contract, plus any amounts that Contractor owes the State of Maine for any reason including, without limitation, tax delinquencies, fee delinquencies or monetary penalties relative thereto. MaineDOT shall exercise its set-off rights in accordance with normal State practices including, in cases of set-off pursuant to an audit, the finalization of such audit by the State agency, its representatives, or the State Controller.

25. **WORKERS AND EQUIPMENT** The Contractor shall at all times provide all superintendents, forepersons, laborers, inspectors, Subcontractors, subconsultants, Equipment, Materials, and Incidentals as needed to perform the Work in Conformance within the Contract Time. The Contractor shall provide all safeguards, safety devices, and protective Equipment and take all other action that is necessary to continuously and effectively protect the safety and health of all persons from hazards related to the Work.

Any person employed by the Contractor or by any Subcontractor or any officer or representative or agent of the Subcontractor, who, in the opinion of the Contract Administrator, is intemperate or disorderly, shall be removed immediately by the Contractor or Subcontractor employing such person. The employee shall not be employed again in any portion of the Work without prior approval from the Contract Administrator. Should the Contractor fail to remove such person or persons as required above or fail to furnish suitable and sufficient personnel for the proper prosecution of the Work, the Contract Administrator may suspend the Work by written notice until such orders are complied with.

All persons employed by or through the Contractor, except for registered trainees, shall have sufficient skill and experience to perform the Work properly. The Department may require that the Contractor discharge any such person who the Department determines jeopardizes safety of any person or the Project without cost or liability to the Department. If the Department determines that such person's performance jeopardizes the intent of the Contract otherwise, the Department may, but is not required, to notify the Contractor of such a determination. Such notice, or lack thereof, does not affect the Contractor's duties regarding Workers. Upon Receipt of such notice, the Contractor shall take any action it determines necessary to fulfill its obligations under the Contract.

26. ENVIRONMENTAL REQUIREMENTS

Temporary Soil Erosion and Water Pollution Control If the Work involves excavation or placement of soil, the Contractor shall stabilize the area on a daily basis and comply with all applicable federal, state, and local laws, rules, regulations, permit requirements and conditions.

Hazardous Materials If the Contractor encounters any condition that indicates the presence of uncontrolled petroleum or hazardous Materials, the Contractor shall immediately stop Work, notify the Department, treat any such conditions with extreme caution, and secure the area of potential hazard to minimize health risks to Workers and the public, and to prevent additional releases of contaminants into the environment. Such conditions include the presence of barrels, tanks, unexpected odors, discoloration of soil or water, an oily sheen on soil or water, excessively hot earth, smoke, or any other condition indicating uncontrolled petroleum or hazardous Materials. The Contractor shall continue Work in other areas of the Project unless otherwise directed by the Department. The Contractor shall comply with all federal, State, and local laws concerning the handling, storage, treatment, and disposal of uncontrolled petroleum or hazardous Material.

Waste Materials All waste materials shall be disposed of in accordance with all federal, State, and local laws.

Environmental Non-compliance - Remedies and Costs The Contractor shall be in non-compliance if it, or Subcontractors at any tier, fail to comply with the terms of this Contract or any applicable environmental or land use law or regulation including Project specific permit conditions.

If the Contractor is in non-compliance, the Department may, at its discretion:

- A. Withhold all Progress Payments, or any portion thereof, during the period the Contractor is in non-compliance;
- B. Remedy such non-compliance using State forces or another Contractor and deduct all costs incurred by the Department from Progress Payments. Such costs include direct costs, Project Engineering costs, and Contractor costs from amounts otherwise due the Contractor, and/or
- C. Suspend the Work for cause and without cost or liability to the Department. Said suspension shall continue until the Contractor has addressed all non-compliance issues as directed by the Department.

The Contractor shall be responsible for any fines and penalties assessed by environmental or land use regulatory agencies due to such non-compliance. Such penalties may be withheld from amounts otherwise due the Contractor.

27. **QUALITY AND STANDARDS** Materials and manufactured products incorporated into the work shall be new unless otherwise specified, free from defect, and in conformity with the contract. When material is fabricated or treated with another material or where any combination of materials is assembled to form a finished product, any or all of which are covered by specifications, the Department may reject the finished product if any of the components do not comply with the specifications. The Department may reject materials not conforming to the Specifications at any time, and the Contractor shall remove them immediately from the project site unless otherwise instructed by the Department. The Contractor shall not store or use rejected materials on any Department project.

If there is no applicable standard set forth in this contract for particular Work, then the Contractor shall perform that Work in accordance with industry standards prevailing at the time of bid. If the Department determines that Work is non-conforming, the Contractor shall remove, replace, or otherwise correct all unacceptable work as directed by the Department at the expense of the Contractor, without cost or liability to the Department.

28. **WARRANTY PROVISIONS** The Contractor unconditionally warrants and guarantees that the Work will be free from warranty defects for one year or as otherwise specified in this Contract. If the Department discovers any warranty defects during the warranty period, the Contractor agrees to perform all remedial work, at no additional cost or liability to the Department. Remedial Work will be completed within two weeks unless a more immediate response is required for safety or convenience, as determined by the Department.

The Contractor hereby assigns to the Department the right to enforce all manufacturer's warranties or guarantees on all materials, equipment or products purchased for the work that exceed the nature or duration of the warranty obligations assumed by the Contractor under this Contract.

The Contractor agrees that the warranty obligations provided by this Contract shall be reported as an outstanding obligation in the event of bankruptcy, dissolution, or the sale, merger, or cessation of operations of the Contractor.

29. **PAYMENT** The Contractor shall submit an itemized invoice to the Department for Work monthly, at the completion of the Work or as otherwise noted in the Contract documents for approval and payment. At a minimum, invoices shall include the following information:

- Contractor name, address & Contract Number
- Invoice Date & Number
- Dates of Work
- Description and Location of Work
- Quantities at the Prices contained in the Contractor's Bid

The Department will approve complete and correct invoices for accepted Work invoiced at bid prices. Payments to the Contractor shall be full compensation for furnishing all labor, equipment, materials, services, and incidentals used to perform all Work under the Contract in a complete and acceptable manner, and for all risk, loss, damage, or expense of any kind arising from the nature or execution of the Work. The Contractor shall pay all taxes, charges, fees, and allowances. Except as expressly provided otherwise in this Contract, all such taxes, charges, fees, and allowances are incidental to the Contract. Most items are exempt from Maine sales tax. The Contractor shall Bid in accordance with the Maine statutory exemption from sales tax. The Department may require that the Contractor submit backup documentation including copies of receipts, invoices, and itemized payments to Subcontractors. The Acceptance by the Contractor of the final payment, as evidenced by cashing of the final payment check, constitutes a release to the Department from all claims and liability under the Contract.

The Department may withhold payments claimed by the Contractor on account of:

- A. Incomplete, Inaccurate or Incorrect Invoices,
- B. Defective Work or Non-conforming Work,
- C. Damages for Non-conforming, Defective or Unauthorized Work or Equipment,
- D. Damage to a third party,
- E. Claims filed or reasonable evidence indicating probable filing of claims,
- F. Failure of the Contractor to make payments to Subcontractors or for Materials or labor, or failure of Subcontractors to make payments to Sub-Subcontractors or for Materials or labor,
- G. Regulatory non-compliance or enforcement,
- H. Failure to submit Documentation
- I. All other causes that the Department reasonably determines negatively affect the State's interest.

30. **RESPONSIBILITY FOR DAMAGE TO WORK** Except for damage to Project caused by Uncontrollable Events, the Contractor shall bear all risk of loss relating to the Work until Final Acceptance, regardless of cause, including completed Work, temporary Structures, and all other items or Materials not yet incorporated into the Work.

The Contractor shall, at its sole expense, rebuild, repair, restore, or replace such damaged Work or otherwise make good any losses that arise from such damage ("rebuilding, etc."). If the Contractor fails to Promptly commence and continue such rebuilding, etc., the Department may, upon 48 hours advance written notice, commence rebuilding, etc. of the damaged property without liability to the Department with its own forces or with Contracted forces and all costs will be deducted from amounts otherwise due the Contractor.

31. **RESPONSIBILITY FOR PROPERTY OF OTHERS** The Contractor shall not enter private property outside the Project Limits without first obtaining permission from the Owners.

The Contractor shall be responsible for all damage to public or private property of any kind resulting from any act, omission, neglect, or misconduct of the Contractor until Final Acceptance. The preceding sentence includes damage to vehicles passing through the Work area.

The Contractor shall, at its sole expense, rebuild, repair, restore, or replace such damaged property or otherwise make any good losses that arise from such damage ("rebuilding, etc."). If the Contractor fails to commence and continue such rebuilding, etc. in a timely manner, the Department may, upon 48 hours advance written notice, commence rebuilding, etc. of the damaged property without liability to the Department with its own forces or with Contracted forces, and all costs will be deducted from amounts otherwise due the Contractor.

32. **NOTICE REQUIRED** When the Contractor becomes aware of facts or circumstances that may cause the Contractor to seek additional compensation, time, or any other change in Contract requirements ("Issue"), then the Contractor shall notify the Contract Administrator within 48 hours and before commencing any part of the Work relating to the Issue. The notice must describe the basic nature and extent of the Issue.

The written notice or confirmation will be known as a "Notice of Issue for Consideration". The Contractor will not be entitled to any additional compensation, time, or any other change to Contract requirements without a timely Notice of Issue for Consideration.

33. **ENTIRE CONTRACT** This document contains the entire Contract of the parties, and neither party shall be bound by any statement or representation not contained herein. No waiver shall be deemed to have been made by any of the parties unless expressed in writing and signed by the waiving

party. The parties expressly agree that they shall not assert in any action relating to the Contract that any implied waiver occurred between the parties which is not expressed in writing. The failure of any party to insist in any one or more instances upon strict performance of any of the terms or provisions of the Contract, or to exercise an option or election under the Contract, shall not be construed as a waiver or relinquishment for the future of such terms, provisions, option or election, but the same shall continue in full force and effect, and no waiver by any party of any one or more of its rights or remedies under the Contract shall be deemed to be a waiver of any prior or subsequent rights or remedy under the Contract or at law.

SPECIAL PROVISIONS
ADDITIONS AND REVISIONS TO STANDARD SPECIFICATIONS

SPECIAL PROVISION SECTION 101
CONTRACT INTERPRETATION

101.2 Definitions Add the following:

“MaineDOT The Department of Transportation of the State of Maine, as established by 23 MRSA §4205 et seq. for the administration of Highway, Bridge, and other public Works; acting through the Commissioner and his/her duly authorized representatives.”

101.2 Definitions ADD the following:

“Apparent Highest Scored Bidder A Bidder that receives the Evaluation Committee’s highest total score using the weighted criteria in the bid documents. The Apparent Highest Scored Bidder may not be Awarded the Contract if a) the Bid is later found to be non-responsive in accordance with Section 102.11, b) the Bidder is found to be not responsible, c) the Bidder fails to comply with all applicable pre-Award Conditions, other pre-execution requirements of the Contract, d) consideration for Maine business enterprises results in low cost bids not being considered as the best-value for the State of Maine or e) the Department chooses not to Award a Contract.”

101.2 Definitions Apparent Low Bidder Delete the section in its entirety.

101.2 Definitions Apparent Successful Bidder Delete the section in its entirety and replace with the following:

“Apparent Successful Bidder The Bidder with the highest scored responsive Bid which regarding the consideration Maine business enterprise is considered as best-value for the State of Maine, all as determined by the Department. A responsive responsible Bidder, usually the Apparent Highest Scored Bidder, that is Awarded the Contract. The Department may not execute the Contract with the Apparent Successful Bidder if a) the Apparent Successful Bidder fails to comply with all applicable pre-Award conditions or other pre-execution requirements of the Contract or b) if the Department chooses not to Award a Contract.”

101.2 Definitions Contract Completion Date Delete the entire section and replace with the following:

“The required completion date of all Work pursuant to the Contract, except warranty work. The Contract Completion Date is usually on the Contract form.”

101.2 Definitions Contract Execution Delete the entire section and replace with the following:

“Execution of the Contract by the Commissioner or their authorized agent by signing the Contract form which action, upon written notification to the Contractor, forms a Contract as provided in Section 103.8 - Execution of Contract by Department.”

101.2 Definitions Successful Bidder Delete the section in its entirety and replace with the following:

“Successful Bidder The highest scored, responsive, responsible bidder, which regarding the consideration Maine business enterprise is considered as best-value for the State of Maine and to whom the Department intends to award the Contract. This status is evidenced by a “Notice of Intent to Award” Letter sent to the Successful Bidder.”

SPECIAL PROVISION SECTION 102
BIDDING

102.7.1 Location and Time Delete the entire section and replace with the following:

“The Bidder must Deliver its Bid and Bid Guaranty in a sealed envelope to the exact location and before the precise time (as determined by the Department) specified in the Notice to Contractors or any applicable Bid Amendment. The sealed envelope must be labeled with the Bidder's name, the Project or Work location, Title, and the words “Bid Enclosed”. As a minimum, the Bidder will submit a Bid Package consisting of the Notice to Contractors, the completed Acknowledgement of Bid Amendments form, the completed Schedule of Items, 2 copies of the completed Contract form, and any other Certifications or Bid Requirements listed in the Bid Book. For a related provision, see Section 102.11 - "Bid Responsiveness".

102.11.2 Curable Bid Defects Revise this section by adding the following:

“The Bidder only signs one of the Contract forms or the Bidder does not sign the Contract form but does sign the Schedule of Items.” and “If a submitted bid contains any additional conditions or alternate bidding language, the Bidder may cure the defect by removing all conditions and alternate language or the Department will reject the bid as non-responsive.”

102.11.2 Curable Bid Defects Change “Contract Agreement Offer and Award forms” to Contract form.

SPECIAL PROVISION SECTION 103
AWARD AND CONTRACTING

103.4 Notice of Award Delete the section in its entirety and replace with the following:

“The Department has 30 Days following Bid Opening to Deliver a written Notice of Intent to Award and request insurance certificates, special certifications, and other information from the Apparent Highest Scored Bidder. All items must be delivered to the Department’s Bureau of Maintenance and Operations. The Apparent Highest Scored Bidder is determined by using the weighted criteria described in the Request for Proposal. The award will be granted to the bidder with the Evaluation Committee’s highest total score if the bid is determined to be responsive, the pre-Award Conditions are met and the Department chooses to Award the Contract. Once these pre-execution conditions are met, the Department will execute the Contract and notify the Contractor of the award with a written Notice of Award. If the Department and the Apparent Successful Bidder agree, an extension beyond the 30 days of the Bid and Bid prices may occur and the Bid remains viable.

103.5 Award Conditions Replace the first paragraph with the following:

“The Apparent Successful Bidder must provide and/or perform all of the items listed in this Section 103.5 within 14 Days of Receipt of the Notice of Intent to Award. Unless indicated otherwise, all items must be Delivered to the Department’s Bureau of Maintenance & Operations.”

103.5.1 Performance and Payment Bonds Performance Bonds will not be required. Delete the entire section and replace with the following:

“Payment Bonds complying with Section 110.2.1 - Bonds.”

103.5.4 Execution of Contract By Bidder Delete the entire section and replace with the following:

“The properly completed and signed Contract form provided with the Bid constitutes the Bidder’s offer. Once the Department has received the bonds, insurance, and any other pre-award items required, the Department will sign and execute the Contract. The point of Contract execution is when the Contractor receives written notice that the contract has been signed by the Department and executed.”

SPECIAL PROVISION SECTION 104
GENERAL RIGHTS AND RESPONSIBILITIES

104.3.8A. Federal Wage Rates and Labor Laws Delete the entire section 104.3.8A. Federal Wage Rates do not apply to this work.

104.3.8B State Wage Rates and Labor Laws Delete the entire section 104.3.8B.

SUPPLEMENTAL SPECIFICATIONS
(Corrections, Additions, & Revisions to Standard Specifications – March 2020)

SECTION 104
GENERAL RIGHTS AND RESPONSIBILITIES

104.2.1 Furnishing of Right-of-Way Revise the last sentence in the first paragraph by removing “105.4.5 – Special Detours” and replacing it with “**105.4.5 – Maintenance of Existing Structures.**”.

SECTION 401
HOT MIX ASPHALT PAVEMENT

401.19 Contractor Quality Control Amend this Section by adding the following to the end:
“**Failure to comply with the approved QCP will result in work suspension and pay reductions as outlined in Section 106.4.6. The Quality Control Plan Value shall be the total bid value for all items covered by the QCP as identified in Special Provision 403.**”

SECTION 502
STRUCTURAL CONCRETE

502.09 Forms and Falsework Amend this subsection by adding the subsection title “**502.10 Placing Concrete**” after section “D” Removal of Forms and False work” and after the paragraph beginning with “2. Forms and False work, including blocking...”. So that a new subsection starts and reads:

502.10 Placing Concrete

A. **General Concrete shall not be placed until forms**”

502.1701 Quality Control, Method A and B Revise this Section so that the first paragraph and the first sentence of the second paragraph read:

502.17 Quality Control The Contractor shall control the quality of the concrete through testing, inspection, and practices which shall be described in the QCP, sufficient to assure a product meeting the Contract requirements. The QCP shall meet the requirements of Section 106, Quality, and this specification. No work under this item shall proceed until the QCP is submitted to and approved by the Department. Failure to comply with the approved QCP will result in work suspension and pay reductions as outlined in Section 106.4.6. The Quality Control Plan Value shall be the total bid value for all cast-in-place items covered by the QCP, using the P value listed in Special Provision 502. If no P value is listed, a value of \$350, or bid value per cubic yard, whichever is less, shall be used.

502.1701 Quality Control, Method A and B The QCP shall address all elements that affect the quality of the structural concrete including, but not limited to, the following: “

502.18, Method of Measurement, Revise Subsection ‘F’ by removing the word ‘transverse’ so that it reads: **“Saw cut grooving of concrete wearing surfaces, complete and accepted, will be measured for payment as one lump sum.”**

502.19, Basis of Payment, Revise the third paragraph by removing the word ‘transverse’ so that it reads: **“Saw cut grooving of concrete wearing surfaces will be paid for at the Contract Lump Sum Price, which shall be payment for furnishing all materials, labor, and equipment, including depth gauges and all incidentals, to satisfactorily complete the work.”**

535.24, Installation of Slabs, Beams, and Girders Revise the 5th paragraph by replacing “6.0 and 9.0” to “5.0 and 8.0” so it reads: **“Ready mixed grout shall achieve a design compressive strength of 6,000 psi at 28 days, have an entrained air content of between 5.0 and 8.0 percent, be non-shrink, flowable, and contain a non-shrink additive listed on the Department QPL for expansive cements.”**

535.25, Installation of Precast/Prestressed Deck Panels Revise the 2nd paragraph by replacing “6.0 and 9.0” to “5.0 and 8.0” so it reads: **“Ready mixed grout shall achieve a design compressive strength of 6,000 psi at 28 days, have an entrained air content of between 5.0 and 8.0 percent, be non-shrink, flowable, and contain a non-shrink additive listed on the Department QPL for expansive cements.”**

SECTION 506 SHOP APPLIED PROTECTIVE COATING – STEEL

506.13 Surface Preparation Amend this section by adding this paragraph to the end:

“Steel shall meet the requirements of SSPC SP8 Pickling prior to being immersed in the zinc tanks. Verification of the surface preparation shall be included in the QC documentation.”

SECTION 606 GUARDRAIL

Amend this section by replacing it with the following:

606.01 Description This work shall consist of furnishing and installing guardrail components in accordance with these specifications and in reasonably close conformity with the lines and grades shown on the plans or as established. Guardrail is designated as:

31” W-Beam Guardrail - Mid-Way Splice

Galvanized steel w-beam, 8” wood or composite offset blocks, galvanized steel posts

Thrie Beam

Galvanized steel thrie beam, 8” wood or composite offset blocks, galvanized steel posts

Median guardrail shall consist of two beams of the above types, mounted on single posts.

Bridge mounted guardrail shall consist of furnishing all labor, materials, and equipment necessary to install guardrail as shown on the plans. This work shall also include drilling for and installation of offset blocks if specified, and incidental hardware necessary for satisfactory completion of the work.

Remove and Reset and Remove, Modify, and Reset guardrail shall consist of removing the existing designated guardrail and resetting in a new location as shown on the plans or directed by the Resident. Remove, Modify, and Reset guardrail and Modify guardrail include the following guardrail modifications: Removing plate washers at all posts, except at anchorage assemblies as noted on the Standard Details, adding offset blocks, and other modifications as listed in the Construction Notes or General Notes. Modifications shall conform to the guardrail Standard Details.

Bridge Connection shall consist of the installation and attachment of beam guardrail to the existing bridge. This work shall consist of constructing a concrete end post or modifying an existing end post as required, furnishing, and installing a terminal connector, necessary hardware, and incidentals required to complete the work as shown on the plans. Bridge Transition shall consist of a bridge connection and furnishing and installing guardrail components as shown in the Standard Details.

606.02 Materials Materials shall meet the requirements specified in the following Sections of Division 700 - Materials:

Timber Preservative	708.05
Metal Beam Rail	710.04
Guardrail Posts	710.07
Guardrail Hardware	710.08

Guardrail components shall meet the applicable standards of "A Guide to Standardized Highway Barrier Hardware" prepared and approved by the AASHTO-AGC-ARTBA Joint Cooperative Committee, Task Force 13 Report.

Posts for underdrain delineators shall be "U" channel steel, 8 ft long, 2 ½ lb/ft minimum and have 3/8-inch round holes, 1-inch center to center for a minimum distance of 2 ft from the top of the post.

Reflectorized Flexible Guardrail Markers shall be mounted on all guardrails. A marker shall be mounted onto guardrail posts at the flared guardrail terminal end point and tangent point, both at the leading and trailing ends of each run of guardrail. The marker's flexible posts shall be gray with either silver-white or yellow reflectors (to match the edge line striping) at the tangents, red at leading ends, and green at trailing ends. Whenever the guardrail terminal is not flared, markers will only be required at the terminal end point. These shall be red or green as appropriate. Markers shall be installed on the protected side of guardrail posts unless otherwise approved by the Resident. Reflectorized flexible guardrail markers shall be from the Department's Qualified Products List of Delineators. The marker shall be gray, flexible, durable, and of a non-discoloring material to which 3-inch by 9-inch reflectors shall be applied, and capable of recovering from repeated impacts and meeting MASH 16 requirements. Reflective material shall meet the requirements of Section 719.01 for ASTM D 4956 Type III reflective sheeting. The marker shall be secured to the guardrail post with two fasteners, as shown in the Standard Details.

Reflectorized beam guardrail (“butterfly”-type) delineators shall be mounted on all “w”-beam guardrail. The delineators shall be mounted within the guardrail beam at guardrail posts. Delineators shall be fabricated from high-impact, ultraviolet & weather resistant thermoplastic. Reflectorized beam guardrail delineators shall be placed at approximately 62.5 ft intervals or every tenth post on tangents and at approximately 31.25 ft intervals or every fifth post on curves. Exact locations of the delineators shall be as directed by the Resident. On divided highways, the left-hand delineators shall be yellow, and the right-hand delineators shall be silver/white. On two directional highways, the right-hand side shall be silver/white, and no reflectorized delineator used on the left. All reflectors shall have reflective sheeting applied to only one side of the delineator facing the direction of traffic as shown in the Standard Details. Reflectorized sheeting for guardrail delineators shall meet the requirements of Section 719.01.

Single wood post shall be of cedar, white oak, or tamarack, well-seasoned, straight, and sound and have been cut from live trees. The outer and inner bark shall be removed, and all knots trimmed flush with the surface of the post. Posts shall be uniform taper and free of kinks and bends.

Single steel post shall conform to the requirements of Section 710.07 b.

Single steel pipe post shall be galvanized, seamless steel pipe conforming to the requirements of ASTM A120, Schedule No. 40, Standard Weight.

Acceptable multiple mailbox assemblies shall be listed on the Department’s Qualified Products List and shall be MASH 16 tested and approved.

Flared and Tangent w-beam guardrail terminals and guardrail offset blocks shall be from the Department’s Qualified Products List. Flared terminals shall be installed with a 4 ft offset as shown in the Manufacturer’s installation instructions.

Anchorage assemblies used to anchor trailing ends, radius guardrail, or other ends not exposed to traffic shall meet the applicable standards of "A Guide to Standardized Highway Barrier Hardware" prepared and approved by the AASHTO-AGC-ARTBA Joint Cooperative Committee, Task Force 13 Report, Drawing SEW02a.

Existing materials damaged or lost during adjusting, removing and resetting, or removing, modifying, and resetting, shall be replaced by the Contractor without additional compensation. Existing guardrail posts and guardrail beams found to be unfit for reuse shall be replaced when directed by the Resident.

606.03 Posts Posts for guardrail shall be set plumb in holes or they may be driven if suitable driving equipment is used to prevent battering and distorting the post. When posts are driven through pavement, the damaged area around the post shall be repaired with approved bituminous patching. Damage to lighting and signal conduit and conductors shall be repaired by the Contractor.

When set in holes, posts shall be on a stable foundation and the space around the posts, backfilled in layers with suitable material, thoroughly tamped.

The reflectorized flexible guardrail markers shall be set plumb with the reflective surface facing the oncoming traffic. Markers shall be installed on the protected side of guardrail posts. Markers, which become bent or otherwise damaged, shall be removed and replaced with new markers.

Single wood posts shall be set plumb in holes and backfilled in layers with suitable material, thoroughly tamped. The Resident will designate the elevation and shape of the top. The posts, that are not pressure treated, shall be painted two coats of good quality oil base exterior house paint.

Single steel posts shall be set plumb in holes as specified for single wood posts or they may be driven if suitable driving equipment is used to prevent battering and distorting the post.

Additional bolt holes required in existing posts shall be drilled or punched, but the size of the holes shall not exceed the dimensions given in the Standard Details. Metal around the holes shall be thoroughly cleaned and painted with two coats of approved aluminum rust resistant paint. Holes shall not be burned.

606.04 Rails Brackets and fittings shall be placed and fastened as shown on the plans. Rail beams shall be erected and aligned to provide a smooth, continuous barrier. Beams shall be lapped with the exposed end away from approaching traffic.

End assemblies shall be installed as shown on the plans and shall be securely attached to the rail section and end post.

All bolts shall be of sufficient length to extend beyond the nuts but not more than ½ inch. Nuts shall be drawn tight.

Additional bolt holes required in existing beams shall be drilled or punched, but the size of the holes shall not exceed the dimensions given in the Standard Details. Metal around the holes shall be thoroughly cleaned and painted with two coats of approved aluminum rust resistant paint. Holes shall not be burned.

606.045 Offset Blocks The same offset block material is to be provided for the entire project unless otherwise specified.

606.05 Shoulder Widening At designated locations the existing shoulder of the roadway shall be widened as shown on the plans. All grading, paving, seeding, and other necessary work shall be in accordance with the Specifications for the type work being done.

606.06 Mail Box Post Single wood post shall be installed at the designated location for the support of the mailbox. The multiple mailbox assemblies shall be installed at the designated location in accordance with the Standard Details and as recommended by the Manufacturer. Attachment of the mailbox to the post will be the responsibility of the home or business owner.

606.07 Abraded Surfaces All galvanized surfaces of new guardrail and posts, which have been abraded so that the base metal is exposed, and the threaded portions of all fittings and fasteners and cut ends of bolts shall be cleaned and painted with two coats of approved rust resistant paint.

606.08 Method of Measurement Guardrail will be measured by the linear foot from center to center of end posts along the gradient of the rail except where end connections are made to masonry or steel structures, in which case measurement will be as shown on the plans. When connected to radius rail, measurement will be to the end of the last tangent beam.

Guardrail terminal, reflectorized flexible guardrail marker, terminal end, anchorage assembly, bridge transition, bridge connection, multiple mailbox post, and single post will be measured by each unit of the kind specified and installed.

Widened shoulder will be measured as a unit of grading within the limits shown on the plans.

Excavation in solid rock for placement of posts will be paid under force account unless otherwise indicated in the Bid Documents.

606.09 Basis of Payment The accepted quantities of guardrail will be paid for at the contract unit price per linear foot for the type specified, complete in place. Reflectorized beam guardrail (“butterfly”-type) delineators will not be paid for directly but will be considered incidental to guardrail items. Reflectorized flexible guardrail marker, terminal end, anchorage assembly, bridge transition, bridge connection, multiple mailbox post, and single post will be paid for at the contract unit price each for the kind specified complete in place.

Guardrail terminals will be paid for at the contract price each, complete in place which price shall be full payment for furnishing and installing all components including the terminal section, posts, offset blocks, "w" beam, cable foundation posts, plates and for all incidentals necessary to complete the installation within the limits as shown on the Standard Details or the Manufacturer’s installation instructions. Pay limits for a flared terminal will be 37.5 feet. Pay limits for a tangent terminal will be 50 feet. Each guardrail terminal will be clearly marked with the Manufacturer’s name and model number to facilitate any future needed repair. Such payment shall also be full compensation for furnishing all material, excavating, backfilling holes, assembling, and all incidentals necessary to complete the work, except that for excavation for posts or anchorages in solid ledge rock, payment will be made under 109.7.5 – Force Account. Type III Retroreflective Adhesive Sheeting shall be applied to the approach buffer end sections and sized to substantially cover the end section. On all roadways, the ends shall be marked with alternating black and retroreflective yellow stripes. The stripes shall be 3 in wide and sloped down at an angle of 45 degrees toward the side on which traffic is to pass the end section. Guardrail terminals shall also include a set of installation drawings supplied to the Resident.

Anchorage to bridge end posts will be part of the bridge work. Connections thereto will be considered included in the unit bid price for guardrail.

Guardrail to be placed on a radius of curvature of 150 ft or less will be paid for under the designated radius pay item for the type guardrail being placed.

Widened shoulder will be paid for at the contract unit price each complete in place and will be full compensation for furnishing and placing, grading and compaction of aggregate subbase and any required fill material.

Adjust guardrail will be paid for at the contract unit price per linear foot and will be full compensation for adjusting to grade. Payment shall also include adjusting guardrail terminals where required.

Modify guardrail will be paid for at the contract unit price per linear foot and will be full compensation for furnishing and installing offset blocks, additional posts, and other specified modifications; removing, modifying, installing, and adjusting to grade existing posts and beams; removing plate washers and backup plates, and all incidentals necessary to complete the work. Payment shall also include removing and resetting guardrail terminals where required.

Remove and Reset guardrail will be paid for at the contract unit price per linear foot and will be full compensation for removing, transporting, storing, reassembling all parts, necessary cutting, furnishing new parts when necessary, reinstalling at the new location, and all other incidentals necessary to complete the work. Payment shall also include removing and resetting guardrail terminals when required.

Remove, Modify, and Reset guardrail will be paid for at the contract unit price per foot and will be full compensation for the requirements listed in Modify guardrail and Remove and Reset guardrail.

Bridge Connections will be paid for at the contract unit price each. Payment shall include, attaching the connection to the endpost including furnishing and placing concrete and reinforcing steel necessary to construct new endposts if required, furnishing and installing the terminal connector, and all miscellaneous hardware, labor, equipment, and incidentals necessary to complete the work.

Bridge Transitions will be paid for at the contract unit price each. Payment shall include furnishing and installing the thrie beam or “w”-beam terminal connector, doubled beam section, and transition section, where called for, posts, hardware, precast concrete transition curb, and any other necessary materials and labor, including the bridge connection as stated in the previous paragraph.

No payment will be made for guardrail removed, but not reset and all costs for such removal shall be considered incidental to the various contract pay items.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
606.1301 31” W-Beam Guardrail - Mid-Way Splice – Single Faced	Linear Foot
606.1302 31” W-Beam Guardrail - Mid-Way Splice – Double Faced	Linear Foot
606.1303 31” W-Beam Guardrail - Mid-Way Splice, 15’ Radius and Less	Linear Foot
606.1304 31” W-Beam Guardrail - Mid-Way Splice, Over 15’ Radius	Linear Foot
606.1305 31” W-Beam Guardrail - Mid-Way Splice Flared Terminal	Each
606.1306 31” W-Beam Guardrail - Mid-Way Splice Tangent Terminal	Each
606.1307 Bridge Transition (Asymmetrical) – Type IA	Each
606.1721 Bridge Transition - Type I	Each
606.1722 Bridge Transition - Type II	Each
606.1731 Bridge Connection - Type I	Each

606.1732	Bridge Connection - Type II	Each
606.178	Guardrail Beam	Linear Foot
606.25	Terminal Connector	Each
606.257	Terminal Connector - Thrie Beam	Each
606.259	Anchorage Assembly	Each
606.265	Terminal End-Single Rail - Galvanized Steel	Each
606.266	Terminal End-Single Rail - Corrosion Resistant Steel	Each
606.275	Terminal End-Double Rail - Galvanized Steel	Each
606.276	Terminal End-Double Rail - Corrosion Resistant Steel	Each
606.353	Reflectorized Flexible Guardrail Marker	Each
606.354	Remove and Reset Reflectorized Flexible Guardrail Marker	Each
606.356	Underdrain Delineator Post	Each
606.358	Guardrail, Modify	Linear Foot
606.362	Guardrail, Adjust	Linear Foot
606.365	Guardrail, Remove, Modify, and Reset	Linear Foot
606.366	Guardrail, Remove and Reset	Linear Foot
606.367	Replace Unusable Existing Guardrail Posts	Each
606.47	Single Wood Post	Each
606.48	Single Galvanized Steel Post	Each
606.50	Single Steel Pipe Post	Each
606.51	Multiple Mailbox Support	Each
606.568	Guardrail, Modify - Double Rail	Linear Foot
606.63	Thrie Beam Rail Beam	Linear Foot
606.64	Guardrail Thrie Beam - Double Rail	Linear Foot
606.65	Guardrail Thrie Beam - Single Rail	Linear Foot
606.66	Terminal End Thrie Beam	Each
606.70	Transition Section - Thrie Beam	Each
606.71	Guardrail Thrie Beam - 15 ft radius and less	Linear Foot
606.72	Guardrail Thrie Beam - over 15 ft radius	Linear Foot
606.73	Guardrail Thrie Beam - Single Rail Bridge Mounted	Linear Foot
606.74	Guardrail - Single Rail Bridge Mounted	Linear Foot
606.753	Widen Shoulder for Low Volume Guardrail End	Each
606.754	Widen Shoulder for Flared Guardrail Terminal	Each
606.78	Low Volume Guardrail End	Each
606.80	Buried-in-Slope Guardrail End	Each

SECTION 609 CURB

609.02 Materials Revise the paragraph beginning “The Contractor shall submit a concrete mix...” so that it reads:

“The Contractor shall submit a concrete mix design for the Portland Cement Concrete to the Resident, with a minimum designed compressive strength of 3000 psi concrete fill.”

609.03 Vertical Stone Curb, Terminal Section and Transition Sections and Portland Cement Concrete Curb, Terminal Sections and Transition Sections Revise this section by underlining the section number and title so that it reads in the spec book as:

“609.03 Vertical Stone Curb, Terminal Section and Transition Sections and Portland Cement Concrete Curb, Terminal Sections and Transition Sections”

Revise the last paragraph beginning with “The Contractor may elect...” so that it reads:

“The Contractor may elect to substitute concrete to backfill Stone Curbing or Stone Edging at their option. If the concrete backfill option is elected, the Concrete Fill shall meet the requirements of 609.02.”

SECTION 618 SEEDING

618.08 Mulching Revise this Section so that the third sentence reads: “Mulch for Seeding Method Number 1 shall only be cellulous fiber mulch Section 619.04 **(b)** or straw mulch Section 619.04 **(a)**.”

SECTION 626 FOUNDATIONS, CONDUIT, AND JUNCTION BOXES FOR HIGHWAY SIGNING, LIGHTING, AND SIGNALS

626.034 Concrete Foundations Revise this Section by changing ‘626.037’ to ‘**626.036**’ in the Second Paragraph which begins with “Foundations shall consist of cast-in-place...”.

Revise the 10th paragraph beginning with “Before placing concrete, the required elbows...” by removing “...**in accordance with Standard Specification 633.**”

SECTION 645 HIGHWAY SIGNING

Section 645.023 Sign Support Structures. Under letter “c.”, revise the fifth paragraph beginning with “In addition to the required details...” by removing the words ”**and foundation**” from the 5th sentence.

Section 645.08 Method of Measurement. Revise the second paragraph beginning with “Bridge-type, cantilever and...” by removing the words ”**including the foundation**” .

Section 645.09 Basis of Payment. Revise the third paragraph beginning with “The accepted bridge-type, cantilever and...” by removing the word ”**foundation**” from the second sentence. Add the following sentence to the end of the paragraph “**Conduits, Junction Boxes, and Foundations will be paid for under Section 626.**”

SECTION 652
MAINTENANCE OF TRAFFIC

652.4 Flaggers Revise the first paragraph of this section so that it reads:

“The Contractor shall furnish flaggers as required by the TCP or as otherwise specified by the Resident. All flaggers must have successfully completed a flagger test approved by the Department and administered by a Department-approved Flagger-Certifier who is employing that flagger. All flaggers must carry an official certification card with them while flagging that has been issued by their employer.”

SECTION 681
PRECAST AGGREGATE-FILLED, CONCRETE BLOCK GRAVITY WALL

681.08 Basis of Payment Amend this section by adding the Item Number “**681.10**” in front of the item “Precast Aggregate-Filled Concrete Block Gravity Wall” at the end of the section.

SECTION 703
AGGREGATES

Add the following to Section 703 - Aggregates

703.01 Fine Aggregate for Concrete Fine aggregate for concrete shall consist of natural sand or, when approved by the Resident, other inert materials with similar characteristics or combinations thereof, having strong, durable particles. Fine aggregate from different sources of supply shall not be mixed or stored in the same pile nor used alternately in the same class of construction or mix without permission of the Resident.

All fine aggregate shall be free from injurious amounts of organic impurities. Should the fine aggregate, when subjected to the colorimetric test for organic impurities, AASHTO T 21, produce a color darker than the reference standard color solution (laboratory designation Plate III), the fine aggregate shall be rejected.

Fine aggregate shall have a sand equivalent value of not less than 75 when tested in accordance with AASHTO T 176.

Fine aggregate sources shall meet the Alkali Silica Reactivity (ASR) requirements of Section 703.0201.

The fineness modulus shall not be less than 2.26 or more than 3.14. If this value is exceeded, the fine aggregate will be rejected unless suitable adjustments are made in proportions of coarse and fine aggregate. The fineness modulus of fine aggregate shall be determined by adding the cumulative percentages of material by weight retained on the following sieves: Nos. 4, 8, 16, 30, 50, 100 and dividing by 100.

Fine aggregate, from an individual source when tested for absorption as specified in AASHTO T 84, shall show an absorption of not more than 2.3 percent.

Sieve Designation	Percentage by Weight Passing Square Mesh Sieves
$\frac{3}{8}$ inch	100
No. 4	95-100
No. 8	80-100
No. 16	50-85
No. 30	25-60
No. 50	10-30
No. 100	2-10
No. 200	0-5.0

703.02 Coarse Aggregate for Concrete Coarse aggregate for concrete shall consist of crushed stone or gravel having hard, strong, durable pieces, free from adherent coatings and of which the composite blend retained on the $\frac{3}{8}$ inch sieve shall contain no more than 15 percent, by weight of flat and elongated particles when performed in accordance with test method ASTM D 4791, Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate, using a dimensional ratio of 1:5.

The coarse aggregate from an individual source shall have an absorption no greater than 2.0 percent by weight determined in accordance with AASHTO T 85 modified for weight of sample.

The composite blend shall have a Micro-Deval value of 18.0 percent or less as determined by AASHTO T 327 or not exceed 40 percent loss as determined by AASHTO T 96.

Coarse aggregate sources shall meet the Alkali Silica Reactivity (ASR) requirements of Section 703.0201.

Coarse aggregate shall conform to the requirements of the following table for the size or sizes designated and shall be well graded between the limits specified.

Sieve Designation	Percentage by Weight Passing Square Mesh Sieves			
	A	AA	S	LATEX
Grading	1 inch	¾ inch	1½ inch	½ inch
Aggregate Size	1 inch	¾ inch	1½ inch	½ inch
2 inch			100	
1½ inch	100		95-100	
1 inch	95-100	100	-	
¾ inch	-	90-100	35-70	100
½ inch	25-60	-	-	90-100
⅜ inch	-	20-55	10-30	40-70
No. 4	0-10	0-10	0-5	0-15
No. 8	0-5	0-5	-	0-5
No. 16	-	-	-	-
No. 50	-	-	-	-
No. 200	0 - 1.5	0 - 1.5	0 - 1.5	0 - 1.5

703.0201 Alkali Silica Reactive Aggregates All coarse and fine aggregates proposed for use in concrete shall be tested for Alkali Silica Reactivity (ASR) potential under AASHTO T 303 (ASTM C 1260), Accelerated Detection of Potentially Deleterious Expansion of Mortar Bars Due to Alkali-Silica Reaction, prior to being accepted for use. Acceptance will be based on testing performed by an accredited independent lab submitted to the Department. Aggregate submittals will be required on a 5-year cycle, unless the source or character of the aggregate in question has changed within 5 years from the last test date.

As per AASHTO T 303 (ASTM C 1260): Use of a particular coarse or fine aggregate will be allowed with no restrictions when the mortar bars made with this aggregate expand less than or equal to 0.10 percent at 30 days from casting. Use of a particular coarse or fine aggregate will be classified as potentially reactive when the mortar bars made with this aggregate expand greater than 0.10 percent at 30 days from casting. Use of this aggregate will only be allowed with the use of cement-pozzolan blends and/or chemical admixtures that result in mortar bar expansion of less than 0.10 percent at 30 days from casting as tested under ASTM C 1567.

Acceptable pozzolans and chemical admixtures that may be used when an aggregate is classified as potentially reactive include, but are not limited to the following:

- a. Class F Coal Fly Ash meeting the requirements of AASHTO M 295
- b. Ground Granulated Blast Furnace Slag (Grade 100 or 120) meeting the requirements of AASHTO M 302
- c. Densified Silica Fume meeting the requirements of AASHTO M 307
- d. Lithium-based admixtures
- e. Metakaolin

Pozzolans or chemical admixtures required to offset the effects of potentially reactive aggregates will be incorporated into the concrete at no additional cost to the Department.

703.05 Aggregate for Sand Leveling Aggregate for sand leveling shall be sand of hard durable particles free from vegetable matter, lumps or balls of clay and other deleterious substances. The aggregate shall meet the grading requirements of the following table.

Sieve Designation	Percentage by Weight Passing Square Mesh Sieves
3/8 inch	85-100
No. 200	0-5.0

703.06 Aggregate for Base and Subbase The following shall apply to Sections (a.) and (c.) below. The material shall have a Micro-Deval...” and replace with “The material shall have a minimum degradation value of 25.0 or less¹⁵ as determined by AASHTO T 327. If the Micro-Deval value exceeds 25.0, the Washington State Degradation DOT Test Method T 113T113, Method of Test for Determination of Degradation Value (January 2009 version) shall be performed), except that the test shall be performed on the reported degradation value will be the result of testing a single specimen from that portion of the sample that passes the 1/2 in sieve and is retained on the No. 10 sieve. If the material has a Washington Degradation value of less than 15, the material shall be rejected.

The material, minus any reclaimed asphalt pavement used in Section (b.) below shall have a Micro-Deval value of 25.0 or less as determined by AASHTO T 327. If the Micro-Deval value exceeds 25.0 the material may be used if it does not exceed 25 percent loss on AASHTO T 96, Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine. If AASHTO T 96 is used for acceptance of the material, the material shall be retested at intervals of 25%, 50% and 75% completion of the course.

Recycled Asphalt Pavement (RAP) shall not be used for or blended with aggregate base or subbase.

- a. Aggregate for base, Type A and B shall be crushed ledge or crushed gravel of hard durable particles free from vegetable matter, lumps or balls of clay and other deleterious substances. The gradation of the part that passes a 3 inch sieve shall meet the grading requirements of the following table:

Sieve Designation	Percentage by Weight Passing Square Mesh Sieves	
	Type A	Type B
1/2 inch	45-70	35-75
1/4 inch	30-55	25-60
No. 40	0-20	0-25
No. 200	0-6.0	0-6.0

At least 50 percent by weight of the material retained on the No. 4 sieve shall have at least one fractured face as tested by AASHTO T 335.

Type A aggregate for base shall only contain particles of rock that will pass the 2 inch square mesh sieve.

Type B aggregate for base shall only contain particles of rock that will pass the 4 inch square mesh sieve.

b. Aggregate for base, Type C shall be crushed ledge or crushed gravel of hard durable particles free from vegetable matter, lumps or balls of clay and other deleterious substances. The material shall meet the grading requirements of the following table:

Sieve Designation	Percentage by Weight Passing Square Mesh Sieves	
	Type C	
4 inches	100	
3 inches	90-100	
2 inches	75-100	
1 inch	50-80	
½ inch	30-60	
No. 4	15-40	
No. 200	0-6.0	

At least 50 percent by weight of the material coarser than the No. 4 sieve shall have at least one fractured face as tested by AASHTO T 335.

c. Aggregate for subbase shall be sand or gravel of hard durable particles free from vegetable matter, lumps or balls of clay and other deleterious substances. The gradation of the part that passes a 3 inch sieve shall meet the grading requirements of the following table:

Sieve Designation	Percentage by Weight Passing Square Mesh Sieves	
	Type D	Type E
½ in	35-80	
¼ inch	25-65	25-100
No. 40	0-30	0-50
No. 200	0-7.0	0-7.0

Type D aggregate for subbase gravel may contain up to 50 percent by weight Recycled Concrete Aggregate (RCA). When RCA is used, the portion of the resulting blend of gravel and RCA retained on a ½” square mesh sieve shall contain a total of no more than 5 percent by weight of other recycled materials such as brick, concrete masonry block, or asphalt pavement as determined by visual inspection.

RCA shall be substantially free of wood, metal, plaster, and gypsum board as defined in Note 9 in Section 7.4 of AASHTO M 319. RCA shall also be free of all substances that fall under the category of solid waste or hazardous materials.

Aggregate for subbase shall not contain particles of rock which will not pass the 6 inch square mesh sieve.

703.08 Recycled Asphalt Pavement Recycled asphalt pavement shall consist of salvaged asphalt materials from milled pavements or production waste that has been processed before use to meet the requirements of the job mix formula. It shall be free of winter sand, granular fill, construction debris, or other materials not generally considered asphalt pavement.

703.081 RAP for Asphalt Pavement Recycled Asphalt Pavement (RAP) may be introduced into hot-mix asphalt pavement at percentages approved by the Department according to the MaineDOT Policies and Procedures for HMA Sampling and Testing.

If approved by the Department, the Contractor shall provide documentation stating the source, test results for average residual asphalt content, and stockpile gradations showing RAP materials have been sized to meet the maximum aggregate size requirements of each mix designation. The Department will obtain samples for verification and approval prior to its use.

The maximum allowable percent of RAP shall be determined by the asphalt content, the percent passing the 0.075 mm sieve, the ratio between the percent passing the 0.075 mm sieve and the asphalt content, and Coarse Micro-Deval loss values as tested by the Department.

The maximum percentage of RAP allowable shall be the lowest percentage as determined according to Table 4 below:

Classification	Maximum RAP Percentage Allowed	Asphalt content standard deviation	Percent passing 0.075 mm sieve standard deviation	Percent passing 0.075 mm sieve / asphalt content ratio	Residual aggregate M-D loss value
Class III	10%	≤ 1.0	N/A	≤ 4.0	≤ 18
Class II	20%	≤ 0.5	≤ 1.0	≤ 2.8	
Class I	30%	≤ 0.3	≤ 0.5	≤ 1.8	

Table 4: Maximum Percent RAP According to Test Results

The Department will monitor RAP asphalt content and gradation during production by testing samples from the stockpile at approximately 15,000 T intervals (in terms of mix production). The

allowable variance limits (from the numerical average values used for mix designs) for this testing are determined based upon the maximum allowable RAP percentage and are shown below in Table 5.

Table 5: RAP Verification Limits

Classification	Asphalt content (compared to aim)	Percent passing 0.075 mm sieve (compared to aim)
Class III	± 1.5	± 2.0
Class II	± 1.0	± 1.5
Class I	± 0.5	± 0.7

For specification purposes, RAP will be categorized as follows:

Class III – A maximum of 10.0 percent of Class III RAP may be used in any base, intermediate base, surface, or shim mixture. A maximum of 20.0 percent of Class III RAP may be used in hand-placed mixes for item 403.209.

Class II – A maximum of 20.0 percent Class II RAP in any base, binder, surface, or shim course.

Class I – A maximum of 20.0 percent Class I RAP may be used in any base, intermediate base, surface, or shim mixture without requiring a change to the specified asphalt binder. A maximum of 30.0 percent Class I RAP may be used in in any base or intermediate base mixture provided that a PG 58-28 or PG 58-34 asphalt binder is used. A maximum of 30.0 percent Class I RAP may be used in any surface or shim mixture provided that PG 58-34 asphalt binder is used. Mixtures exceeding 20.0 percent Class I RAP must be evaluated and approved by the Department.

The Contractor may use up to two different RAP sources in any one mix design. The total RAP percentage of the mix shall not exceed the maximum allowed for the highest classification RAP source used (i.e. if a Class I & Class III used, total RAP must not exceed 30.0%). The blended RAP material must meet all the requirements of the classification for which the RAP is entered (i.e. 10% Class III with 20% Class I, blend must meet Class I criteria). The Department may take belt cuts of the blended RAP to verify the material meets these requirements. If the Contractor elects to use more than one RAP source in a design, the Contractor shall provide an acceptable point of sampling blended RAP material from the feed belt.

In the event that RAP source or properties change, the Contractor shall notify the Department of the change and submit new documentation stating the new source or properties a minimum of 72 hours prior to the change to allow for obtaining new samples and approval.

SECTION 710 FENCE AND GUARDRAIL

710.06 Fence Posts and Braces Revise the first Paragraph so that it reads:

“Wood posts shall be of cedar, white oak, or tamarack or other AWP A approved species, of the diameter or section and length shown on the plans.”

Remove the fourth paragraph which starts “ That portion of wood posts...”.

Revise the paragraph beginning with “Braces shall be of spruce, eastern hemlock ... so that it now reads:

“Braces shall be of spruce, eastern hemlock, Norway pine, pitch pine, or tamarack timbers or other AWP A approved species, or spruce, cedar, tamarack or other AWP A approved species round posts of sufficient length to make a diagonal brace between adjacent posts. All wood posts and braces shall be pressure-treated in accordance with AASHTO M 133 and AWP A U1, UC4A Commodity Specification B: Posts. “

710.07 Guardrail Posts Revise this section so that the first sentence of section a. reads:

“a. Wood posts shall be of Norway pine, southern yellow pine, pitch pine, Douglas fir, red pine, white pine, or eastern hemlock or other AWP A approved species.”

Revise the next paragraph so that it reads:

Wood posts and offset brackets shall be preservative treated in accordance with the requirements of AASHTO M 133 and AWP A U1, UC4A Commodity Specification B: Posts.

SECTION 712 MISCELLANEOUS HIGHWAY MATERIAL

712.061 Structural Precast Units Amend this section by adding the following sentence to the end of the first paragraph of the Construction subsection:

“Facilities certified by NPCA or PCI shall provide to the Fabrication Engineer a copy of their annual audit to include deficiency reports and corrective actions.”

Revise this section by changing the letter “b” of ASTM C1611 of the Concrete Testing subsection so that it reads:

“b. Air content shall be 5.0% to 8.0%.”

SECTION 720
STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND
TRAFFIC SIGNALS

720.12 Wood Sign Posts Revise the first sentence so that it reads:

Wood sign posts shall be rectangular, straight and sound timber, cut from live growing native spruce, red pine, hemlock, cedar trees or other AWPAs approved species, free from loose knots or other structurally weakening defects of importance, such as shake or holes or heart rot.

Revise the third paragraph that starts with “When pressure treated...” so that it reads:

All sign posts shall be pressure-treated in accordance with AASHTO M 133 and AWPAs Standard U1, UC4A, Commodity Specification A: Sawn Products.