PREQUALIFICATION FOR MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

STATEWIDE

PH20241120MDPB

2024

Updated 05/15/2020

STATE PROJECT

MAINTENANCE & OPERATIONS

BIDDING INSTRUCTIONS

1. Use pen and ink to complete all paper Bids. Signatures shall be original. Stamped and copied signatures will not be accepted. Bids are not accepted by email or FAX.

NOTE: Electronic Bids will not be accepted for this bid.

2. As a minimum, the following should be received prior to the time of Bid opening:

For a Paper Bid:

a) a copy of the Notice to Contractors, b) the completed Acknowledgement of Bid Amendments form, c) the completed Prequalification Application, d) two copies of the completed and signed Contract Agreement, Offer & Award form, e) the completed Prequalification Supplemental, if applicable, and f) any other certifications or Bid requirements listed in the Bid Documents as due by Bid opening.

3. All Bid Packages which are mailed or sent express, shall be provided in double (one envelope inside the other) envelopes, for security and other reasons. The *Inner Envelope* shall have the following information provided on it:

Bid Enclosed - Do Not Open

Title: Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and

Rehabilitation

Location: Statewide Date of Bid Opening:

Name of Contractor with mailing address and telephone number:

In Addition to the usual address information, the *Outer Envelope* should have written or typed on it:

Double Envelope: Bid Enclosed

Title: Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and

Rehabilitation

Location: Statewide Date of Bid Opening: Name of Contractor:

If a paper Bid is to be sent express, please take note that overnight services do not always arrive in time and that delivery may be affected by carrier volume, weather and other factors. Packages using express services should be sent to directly to the DOT Headquarters Building, Maine Department of Transportation, 24 Child Street, Augusta. "FedEx First Overnight" delivery is suggested as the package is delivered directly to the DOT Headquarters Building, Mailroom, 24 Child Street, Augusta. Allow extra days for U.S. Postal Service Express Mail which has proven not to be reliable and sometimes does not deliver directly to the DOT Headquarters Building but instead delivers to the State of Maine Mail Distribution Center.

If a paper bid is to be mailed, the mailing address is Maine Department of Transportation, 16 State House Station, Augusta, ME 04333-0016. Allow additional working days for this mail to pass through the state mail system in addition to the US Postal Service as this mail is not delivered directly to the Department of Transportation.

If a paper Bid is to be hand carried, deliver directly to the "Public Entrance" which is located on the Capitol Street side of the DOT Headquarters Building in Augusta. http://www.maine.gov/mdot/contact. Hand-carried Bids may be in one envelope, and should be marked with the following information:

Bid Enclosed: Do Not Open

Title: Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation

Location: Statewide Date of Bid Opening: Name of Contractor:

If you need further information regarding Bid preparation, call the DOT Contracts Section at (207) 624-3410.

For complete bidding requirements, refer to Section 102 of the Maine Department of Transportation, Standard Specifications, March 2020 Edition.

NOTICE

The Maine Department of Transportation is attempting to improve the way Bid Amendments/Addendums are handled, and allow for an electronic downloading of bid packages from our website, while continuing to maintain an optional plan holders list.

Prospective bidders, subcontractors or suppliers who wish to download a copy of the bid package and receive a courtesy notification of project specific bid amendments must fill out the on-line plan holder registration form and provide an email address to the MDOT Contracts mailbox at: MDOT.contracts@maine.gov. Each bid package will require a separate request.

Additionally, interested parties will be responsible for reviewing and retrieving the Bid Amendments from our web site, and acknowledging receipt and incorporating those Bid Amendments in their bids using the Acknowledgement of Bid Amendment Form.

NOTICE

Bidders:

Please use the attached "Request for Information" form when submitting questions concerning specific Contracts that have been advertised for Bid, include additional numbered pages as required. RFI's may be faxed to 207-624-3431, submitted electronically through the Departments web page of advertised projects by selecting the RFI tab on the project details page or via e-mail to RFI-Contracts.MDOT@maine.gov.

These are the only allowable mechanisms for answering Project specific questions. Maine DOT will not be bound to any answers to Project specific questions received during the Bidding phase through other processes.

When submitting RFIs by Email please follow the same guidelines as stated on the "Request for Information" form and include the word "RFI" along with the Project name and Identification number in the subject line.

State of Maine Department of Transportation

RFI No: _____

REQUEST FOR INFORMATION

	Date	Time	
Information Reques	sted for:		
WIN(S):	Town(s):	F	Bid Date:
Question(s):			
			
			· · · · · · · · · · · · · · · · · · ·
			-
			· · · · · · · · · · · · · · · · · · ·
Request by: Company Name:		Phone:()	
Email:		Fax: ()	

Complete this form and fax to 207-624-3431, Attn: Project Manager (name listed on the "Notice to Contractors"), or Email questions to RFI-Contracts.MDOT@maine.gov, Please include the word "RFI" along with the Project Name and Identification Number in the Subject line, or electronically by using the RFI Tab located on the Individual Projects Detail page.

Vendor Registration

Prospective Bidders must register as a vendor with the Department of Administrative & Financial Services if the vendor is awarded a contract. Vendors will not be able to receive payment without first being registered. Vendors/Contractors will find information and register through the following link –

http://www.maine.gov/purchases/venbid/index.shtml

CONTRACTOR INFORMATION

Contractor Name:	
Mailing Address:	
Vendor Customer Number:	
Contact Information (Primary Contact):	
Phone:	Cell Phone:
Fax:	
Email:	
Mailing Address (if different from above): _	
The company has the following organizationa	al structure:
☐ Sole Proprietorship	☐ Limited Liability Company
☐ Partnership	☐ Joint Venture
☐ Corporation	□ Other:
(Date)	(Signature)
	(Name and Title Printed)

STATE OF MAINE DEPARTMENT OF TRANSPORTATION NOTICE TO CONTRACTORS

Sealed Bids addressed to the Maine Department of Transportation, Augusta, Maine 04333 and endorsed on the wrapper "Bids for **Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation** in the State of Maine" will be received from contractors at the Reception Desk, MaineDOT Building, Capitol Street, Augusta, Maine, until 11:00 o'clock A.M. (prevailing time) on **December 11, 2024** and at that time and place, publicly opened and read. Bids will be accepted from all bidders. All applicants must have completed, or successfully complete, a <u>Marine Construction or Bridge Construction</u>, or project specific prequalification application to be considered for the award of this contract. **Electronic Bidding will not be available for this bid.**

Description: Prequalification Application for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation

Location: Statewide

Outline of Work: Perform Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation on an as needed basis and other incidental work.

Basis of Award: The Department and each prequalified contractor may enter into a Contract to perform work pursuant to Assignment Letters.

For general information regarding Bidding and Contracting procedures, contact George Macdougall at (207) 624-3410. Our webpage at http://www.maine.gov/mdot/contractors/ contains a copy of the Schedule of Items, Plan Holders List, written portions of bid amendments, bid results and an electronic form for RFI submittal. For Project-specific information fax all questions to John McDonough/Joe Prescott at (207) 624-3431, use electronic RFI form or email questions to RFI-Contracts.MDOT@maine.gov, project name and identification number should be in the subject line. Questions received after 12:00 noon of Friday (or if that Friday is a state holiday, Thursday) prior to bid date will not be answered. Bidders shall not contact any other Departmental staff for clarification of Contract provisions, and the Department will not be responsible for any interpretations so obtained. TTY users call Maine Relay 711.

Application packages, Documents, specifications and forms can be viewed and obtained digitally at no cost at http://www.maine.gov/mdot/contractors/. They may be obtained from the Maine Department of Transportation, Attn.: Mailroom, 24 Child Street, Augusta, Maine 04333-0016 or requested by telephone at (207) 624-3536.

There will be no bid bond, performance bond or payment bond required.

Each Bid must be made upon blank forms provided by the Department.

This Contract is subject to all applicable State Laws.

All work shall be governed by State of Maine, Department of Transportation, Standard Specifications, March 2020 Edition, price \$10 [\$15 by mail], and Standard Details, March 2020 Edition, price \$10 [\$15 by mail]. They also may be purchased by telephone at (207) 624-3536. Standard Detail updates can be found at http://www.maine.gov/mdot/contractors/publications/.

The right is hereby reserved to the MaineDOT to reject any or all bids.

Augusta, Maine November 20, 2024

> KYLE A. HALL DIRECTOR

BUREAU OF MAINTENANCE & OPERATIONS

Statewide
Prequalification for Marine Dock, Pier, Bridge and Facilities
Repair and Rehabilitation
April 14, 2011
Supersedes August 3, 2004

SPECIAL PROVISION 102.7.3 ACKNOWLEDGMENT OF BID AMENDMENTS

With this form, the Bidder acknowledges its responsibility to check for all Amendments to the Bid Package. For each Project under Advertisement, Amendments are located at http://www.maine.gov/mdot/contractors/. It is the responsibility of the Bidder to determine if there are Amendments to the Project, to download them, to incorporate them into their Bid Package, and to reference the Amendment number and the date on the form below. The Maine DOT will not post Bid Amendments any later than noon the day before Bid opening without individually notifying all the planholders.

Amendment Number	Date

The Contractor, for itself, its successors and assigns, hereby acknowledges that it has received all of the above referenced Amendments to the Bid Package.

	CONTRACTOR
Date	Signature of authorized representative
	(Name and Title Printed)

Electronic bidding will NOT be available for this bid.

Bids will NOT be accepted by email or fax.

SIGNED PAPER BIDS ARE REQUIRED and may be mailed, sent express or hand delivered.

For further information, see "BIDDING INSTRUCTIONS" which are located near the front of the bid book.

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the S	State of Maine,
acting through and by its Department of Transportation (Department), an a	agency of state
government with its principal administrative offices located at Child Street, A	lugusta, Maine,
with a mailing address at 16 State House Station, Augusta, Maine 04	333-0016, and
	(Contractor)
a corporation or other legal entity organized under the laws of the State of	, with

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, for <u>Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation</u> in the State of Maine. The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before the Completion Date given in the Assignment Letter. Work may be ordered by the Department after December 11 or contract execution, whichever is latest, and before **November 30, 2028.** The Contractor agrees to complete all Work, except warranty work, on or before **December 31, 2028**.

C. Price.

The original contract amount is <u>One Million Two Hundred Thousand Dollars and</u> <u>no cents (\$1,200,000.00)</u>. The actual Contract amount will be determined by the actual work assigned and performed at the rates established in the Assignment Letters. The MaineDOT does not guarantee the use of any or all of the contract amount.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, *Standard Specifications*, *March 2020 Edition*, *Standard Details March 2020 Edition* as updated through advertisement, Supplemental Specifications, Special Provisions, and Contract Agreement. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

- 1. All of the statements, representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in the Contract are still complete and accurate as of the date of this Agreement.
- 2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
- 3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the *Standard Specifications March 2020 Edition, Standard Details March 2020 Edition* as updated through advertisement, Supplemental Specifications, Special Provisions, and Contract Agreement; contained herein for construction of:

<u>Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation</u>

State of Maine, on which applications will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items."

The Offeror agrees to perform the work required at the price specified in the Assignment Letters in strict accordance with the terms of this solicitation, and to provide the appropriate insurance if this offer is accepted by the Government in writing.

As Offeror also agrees:

First: To do any extra work, not covered by the attached "Schedule of Items," which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the *Standard Specifications*, *March 2020 Edition*, and as addressed in the contract documents.

Second: To begin the and complete the Work in accordance with the time limits given in the Assignment Letters and within the time limits given in this Contract.

Third: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Fourth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby
execute of this Agreement and thereby binds itself to all covenants, terms, and obligations
contained in the Contract Documents.

		CONTRACTOR
	Date	(Signature of Legally Authorized Representative of the Contractor)
		(Name and Title Printed)
G.	Award.	
	Your offer is hereby accepted. documents referenced herein.	This award consummates the Contract, and the MAINE DEPARTMENT OF TRANSPORTATION
	Dut	D IZ-1- A H-11
	Date	By: Kyle A. Hall Director Bureau of Maintenance & Operations

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the S	State of Maine,
acting through and by its Department of Transportation (Department), an a	agency of state
government with its principal administrative offices located at Child Street, A	lugusta, Maine,
with a mailing address at 16 State House Station, Augusta, Maine 04	333-0016, and
	(Contractor)
a corporation or other legal entity organized under the laws of the State of	, with

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, for <u>Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation</u> in the State of Maine. The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before the Completion Date given in the Assignment Letter. Work may be ordered by the Department after December 11 or contract execution, whichever is latest, and before **November 30, 2028.** The Contractor agrees to complete all Work, except warranty work, on or before **December 31, 2028**.

C. Price.

The original contract amount is <u>One Million Two Hundred Thousand Dollars and</u> <u>no cents (\$1,200,000.00)</u>. The actual Contract amount will be determined by the actual work assigned and performed at the rates established in the Assignment Letters. The MaineDOT does not guarantee the use of any or all of the contract amount.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, *Standard Specifications*, *March 2020 Edition*, *Standard Details March 2020 Edition* as updated through advertisement, Supplemental Specifications, Special Provisions, and Contract Agreement. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

- 1. All of the statements, representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in the Contract are still complete and accurate as of the date of this Agreement.
- 2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
- 3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the *Standard Specifications March 2020 Edition, Standard Details March 2020 Edition* as updated through advertisement, Supplemental Specifications, Special Provisions, and Contract Agreement; contained herein for construction of:

<u>Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation</u>

State of Maine, on which applications will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items."

The Offeror agrees to perform the work required at the price specified in the Assignment Letters in strict accordance with the terms of this solicitation, and to provide the appropriate insurance if this offer is accepted by the Government in writing.

As Offeror also agrees:

First: To do any extra work, not covered by the attached "Schedule of Items," which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the *Standard Specifications*, *March 2020 Edition*, and as addressed in the contract documents.

Second: To begin the and complete the Work in accordance with the time limits given in the Assignment Letters and within the time limits given in this Contract.

Third: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Fourth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby
execute of this Agreement and thereby binds itself to all covenants, terms, and obligations
contained in the Contract Documents.

		CONTRACTOR
	Date	(Signature of Legally Authorized Representative of the Contractor)
		(Name and Title Printed)
G.	Award.	
	Your offer is hereby accepted. documents referenced herein.	This award consummates the Contract, and the MAINE DEPARTMENT OF TRANSPORTATION
	Dut	D IZ-1- A H-11
	Date	By: Kyle A. Hall Director Bureau of Maintenance & Operations

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (Department), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and

(Name of the firm bidding the job) (Contractor)

a corporation or other legal entity organized under the laws of the State of Maine, with its principal place of business located at (address of the firm bidding the job)

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, WIN 12345.00, for the Hot Mix Asphalt Overlay in the town city of South Nowhere, County of Washington, Maine. The Work includes construction maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before the Completion Date given in the Assignment Letter. Work may be ordered by the Department after December 11 or contract execution, whichever is latest, and before **November 30, 2024.** The Contractor agrees to complete all Work, except warranty work, on or before **December 31, 2024**.

C. Price.

The original contract amount is One Million Two Hundred Thousand Dollars and no cents (\$1,200,000.00). The actual Contract amount will be determined by the actual work assigned and performed at the rates established in the Assignment Letters. The MaineDOT does not guarantee the use of any or all of the contract amount.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, Standard Specifications, March 2020 Edition, Standard Details March 2020 Edition, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

- 1. All of the statements representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in Appendix A to Division 100 of the *Standard Specifications March 2020 Edition* (Federal Contract Provisions Supplement), and the Contract are still complete and accurate as of the date of this Agreement.
- 2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
- 3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the site of work, the Plans, *Standard Specifications, March 2020 Edition, Standard Details March 2020 Edition*, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds contained herein for construction of:

WIN 012345.00 South Nowhere, Hot Mix Asphalt Overlay

State of Maine, on which bids will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items."

The Offeror agrees to perform the work required at the price specified above and in accordance with the bids provided in the attached "Schedule of Items" in strict accordance with the terms of this solicitation, and to provide the appropriate insurance and bonds if this offer is accepted by the Government in writing.

As Offeror also agrees

First: To do any extra work, not covered by the attached "Schedule of Items," which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the *Standard Specifications*, *March 2020 Edition*, and as addressed in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.


Third: To begin the Work as stated in Section 107.2 of the *Standard Specifications March 2020 Edition* and complete the Work within the time limits given in the Special Provisions of this Contract.

Fourth: The Contractor will be bound to the Disadvantaged Business Enterprise (DBE) Requirements contained in the attached Notice (Additional Instructions to Bidders) and submit a completed Contractor's Disadvantaged Business Enterprise Utilization Plan with their bid.

Fifth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Sixth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby execute this Agreement and thereby binds itself to all covenants, terms, and obligations contained in the Contract Documents.



Non-federal Projects Only

NOTICE TO CONTRACTORS - PREFERRED EMPLOYEES

Sec. 1303. Public Works; minimum wage

In the employment of laborers in the construction of public works, including state highways, by the State or by persons contracting for the construction, preference must first be given to citizens of the State who are qualified to perform the work to which the employment relates and, if they can not be obtained in sufficient numbers, then to citizens of the United States. Every contract for public works construction must contain a provision for employing citizens of this State or the United States. The hourly wage and benefit rate paid to laborers employed in the construction of public works, including state highways, may not be less than the fair minimum rate as determined in accordance with section 1308. Any contractor who knowingly and willfully violates this section is subject to a fine of not less than \$250 per employee violation. Each day that any contractor employs a laborer at less than the wage and benefit minimum stipulated in this section constitutes a separate violation of this section. [1997, c. 757, §1 (amd).]

CONTRACTOR'S PREQUALIFICATION APPLICATION

For

MARINE DOCK, PIER, BRIDGE & FACILITIES REPAIR AND REHABILITATION

1. Basic Information

Name	of Contractor:
Conta	ct Person(s):
Telep	hone No: Cell No Fax No:
E-ma	1:
Addr	ess:
Vend	or Customer No:
2. <u>O</u>	ganizational Structure & History
2.1	The Contractor is duly organized under the laws of the State of
2.2	The Contractor has the following organizational structure.
	() individual () corporation () partnership () limited liability company () joint venture () other:
2.3	If organized in any state other than Maine or in a foreign country, are you compliance with all laws and regulations necessary to legally do business in the Sta of Maine?
2.4	Are you pre qualified for the Marine Construction and/or Bridge Construction categories by the Maine Department of Transportation? YES NO
2.5	Were you prequalified for Marine Dock, Pier, Bridge and Facilities Repair at Rehabilitation by the Maine Department of Transportation during the period of 201 – 2020? YES NO
2.6	If the response to 2.4 and 2.5 is "no", the Applicant must fill out the attache Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation Contractor Pregualification Supplemental.

CONTRACTOR'S PREQUALIFICATION APPLICATION

For

MARINE DOCK, PIER, BRIDGE & FACILITIES REPAIR AND REHABILITATION

2.7	Have you been denied pre qualification for the Marine Construction and/or Bridge Construction categories by the Maine Department of Transportation? YES NO
2.8	Within the last 5 years, has a contract of the Contractor (or any Predecessor Entities or Related Entities) been terminated or suspended for cause, has another party (e.g. surety) completed Work which the Contractor (or any Predecessor Entities or Related Entities) was originally responsible to perform, or has the Contractor (or any Predecessor Entities or Related Entities) been considered in default of a contract that was not cured within the time frame allowed by the contract? YES NO
	If the answer to any of questions in 2.8 is YES, please provide full details on attached sheets. Please feel free to include a written summary of your position on the matter.
2.9	Within the last 5 years, or since your last Prequalification Application has the Contractor (or any Predecessor Entities or Related Entities) been debarred for any reason by any federal, state, or local government or procurement agencies?
2.10	Using the Bidder's OSHA 300 Log and statements provided by applicable insurance, the Bidder must provide its workers' compensation Experience Modification Rate.
2.11	If a current, applicable copy of the Contractor's Safety Plan is not on file with the Department, the Contractor must submit an acceptable, project specific Safety Plan to the Department with the application, prior to prequalification.
3. <u>En</u>	nergency Response
	ne designated personnel be notified and equipment mobilized and be on site within eight or less when MaineDOT has an emergency? YES NO
4. <u>Co</u>	ntractor Requirements
Do yo YES	u meet all Contractor Requirements set forth in this Contract. NO

CONTRACTOR'S PREQUALIFICATION APPLICATION

For

MARINE DOCK, PIER, BRIDGE & FACILITIES REPAIR AND REHABILITATION

5. Certifications

By signing below, the person signing below hereby certifies as follows:

- 1. I have personal knowledge of all the information contained in this Application OR I am responsible for the accuracy of all such information
- 2. The information contained in this Application is true and complete.
- 3. I hereby authorize the Department to contact any person or entity necessary to verify or supplement any of the information requested by or provided in this Application without liability, and I hereby further authorize any person or entity contacted to provide any and all information requested without liability.
- 4. The Contractor has read, understands, and agrees to all terms of the Prequalification Procedure and this Application.
- 5. I am duly authorized by law and by the Contractor to sign this Application on behalf of the Contractor.

	CONTRACTOR
Date	[Signature]
	By:

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

[Legal N	Name of Contractor Applying for Prequalificati	on, hereafter "Contractor" or "you"]
*******	**************************************	************* <u>S</u>
categories by the Ma Dock, Pier, Bridge Transportation durin	aine Department of Transporta and Facilities Repair and Reh g the period of 2020 – 2024, r, Bridge and Facilities Re	Construction and/or Bridge Construction ation, or was not prequalified for Marine abilitation by the Maine Department of the Applicant must fill out the attached epair and Rehabilitation Contractor's
by the Maine Depa Bridge and Facilities	rtment of Transportation or w Repair and Rehabilitation by t f 2020 – 2024, the Applicant	on and/or Bridge Construction categories was prequalified for Marine Dock, Pier, the Maine Department of Transportation to does not need to fill out the attached
******	*********	**********
	1. Basic Informa	<u>ition</u>
Name of Contractor:		
Contact Person(s):		
Telephone No(s):	Cell No	Fax No:
E-mail:		
Mailing Address:		
Physical Address:		
Vendor Customer No.:		

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

2. Organizational Structure & History

2.1 The Contractor is duly organized under the laws of the State of	
2.2 The Contractor has the following organizational structure. () individual () corporation () partnership () limited liability company () joint venture () other:	
2.3 Please provide the year the Contractor (and not any Predecessor Entities or Rela Entities) was first organized.	ted
2.4 Please list all Predecessor Entities below (or on attached sheets if necessary).	
2.5 Please list all Related Entities below (or on attached sheets if necessary).	
2.6 If organized in any state other than Maine or in a foreign country, are you in compliant with all laws and regulations necessary to legally do business in the State of Maine?	nce
VFS NO	

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

3. Experience

- 3.1 The Bidder shall submit evidence of compliance with all Contractor Requirements set forth in this Contract.
- 3.2 <u>Summary of Contractor's Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation Experience.</u> With respect to each of the following Project Types, list the approximate number of years of experience that the Contractor has as a prime contractor or as a subcontractor with primary responsibility.

Project Type_	<u>Years</u>
Marine Dock, Pier and Facilities Repair and Rehabilitation	
Marine Bridge and Facilities Repair and Rehabilitation	

3.3 Most Recently Completed Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation Contracts. Please provide the following information regarding the last six contracts completed by the Contractor. Please list in reverse chronological order (most recently completed project first, next most recently completed project, etc.). [Please feel free to provide this information on attached sheets in another format as long as it contains all the information requested. Attach additional sheets as necessary.]

Contract	Were you	Project Type &	Month /	Name,	Please describe
Amount	the Prime	Location	Year	Address,	the work
	or a Sub?		Completed	Contact	activities your
				Person &	firm performed
				Tel. # of	relevant to the
				Owner	prequal
					category being
					applied for.

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

3.4 Contracts for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation In Progress. Please provide the following information regarding all contracts currently in progress, in descending order of contract amount. [Please feel free to provide this information on attached sheets in another format as long as it contains all the information requested. Attach additional sheets as necessary.]

Contract	Were you	Project Type &	Month /	Name,	Please describe
Amount	the Prime	Location	Year	Address,	the work
	or a Sub?		Completed	Contact	activities your
				Person &	firm performed
				Tel. # of	relevant to the
				Owner	prequal
					category being
					applied for.

Application		ges Within the last frotractor (or any Predeces st it?		•	1
		YES	NO		
liquidated d	lamages, the	full details on attache original contract time, Please feel free to inclu	and the num	ber of days for	which liquidated
3.6 <u>Termina</u>	ations / Suspe	ensions / Defaults			
	-	ears, or since your last P redecessor Entities or Re	elated Entities		
		YES	NU		

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

(b) Within the last five years, or since your last Prequalification Application has another party (e.g. surety) completed Work which the Contractor (or any Predecessor Entities or Related

Entities) was originally responsible to perform?

	YES	NO
	Related Entities	Prequalification Application has the Contractor been considered in default of a contract that the contract?
	YES	NO
• •	. , . ,	ES, please provide full details on attached mary of your position on the matter.
3.7 <u>Denial of Prequalification</u>	or Award	
• •	ocurement agency	qualification Application has any federal, y denied the Contractor (or any Predecessor
	YES	NO
state, or local government or p Entities or Related Entities) su	procurement ager bmitted the appa	Prequalification Application has any federal, ncy, after the Contractor (or any Predecessor arent low bid, refused to award a contract for tions, experience, competence, or financial
	YES	NO
<u> </u>		is YES, please provide full details on attached mary of your position on the matter.
3.8 <u>Debarments, Etc</u>		
•	Related Entities)	requalification Application has the Contractor been debarred for any reason by any federal, ies?
	YES	NO
		requalification Application has the Contractor refrained from bidding for any reason, such as

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

suspension	or agreement	not to bid,	or as pa	rt of the	e settlemer	nt of a	Dispute of	any	type	with
any federal	, state, or loca	l governme	nt or pro	curemei	nt agencies	s?				

YES NO
If the answer to either of questions 3.8(a) or (b) is YES, please provide full details on attached sheets. Please feel free to include a written summary of your position on the matter.
3.9 <u>Claims History</u> Within the last 5 years, or since your last Prequalification Application has the Contractor (or any Predecessor Entities or Related Entities) been a party to a Claim with an originally claimed amount in excess of \$50,000?
YES NO
If YES, please provide full details for each Claim on attached sheets including (a) whether the Claim was brought by or against the Contractor (or any Predecessor Entities or Related Entities), (b) the nature of the Dispute underlying the Claim, (c) originally claimed amounts, (d) the resolution of such Claims (including the amount) or if unresolved, the current status of such Claims, and (e) the name, address and phone number of the primary adverse party who can be contacted for additional information, and (f) a written summary of your position on the matter (if desired).
3.10 <u>Bid or Other Crimes</u> Within the last 10 years, has the Contractor (or any Predecessor Entities or Related Entities), or any officers, owners, or Key Personnel of the same ever been indicted on, convicted of, or plead or consented to a violation of a bid crime including bid collusion or any other crime involving fraud or knowing misrepresentation?
YES NO
If YES, please provide full details on attached sheets. Please feel free to include a written summary of your position on the matter.
4. Bonding
4.1 If the bid price for any single assignment exceeds \$125,000, is the Contractor capable of obtaining from a Qualifying Bonding Company a performance bond and a payment bond each in the amount of the bid prices that the Contractor will be submitting to the Department?
YES NO

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

5. Safety

5.1 Does the Contractor ha	ave a written safety	y program?
	YES	NO
Complete and attach the Sa	afety Supplemental	1.
5.2 Has your company s years?	ustained any work	related fatal accidents during the past (3) three
years.	YES	NO
If yes, please provide full you have done to prevent to		tal accident on attached sheets, and include what s from recurring.
5.3 Has your company rec	eived an OSHA (c	or state OSHA) citation within the last 5 years?
	YES	NO
If yes, the number and type	e of violation?	
5.4 Have you had an acc damage?	•	three years that caused over \$50,000 in property NO
TONES 1 '1 C II		
If YES, please provide full	details of each suc	ch accident on attached sheets.
6. <u>E</u>	nvironmental and	d Civil Rights Information
Application has the Contra	actor (or any Predec ral, state or local en	years, or since your last Prequalification cessor Entities or Related Entities) been found to nvironmental law or regulation in an
	YES	NO
If YES, please provide full	l details, including	a summary of your position, on attached sheets.

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

6.2 <u>Civil Rights Record.</u> Within	the last 5 years, or	or since your last Prequalification Application
has the Contractor (or any Pred	ecessor Entities	or Related Entities) had any findings and/or
rulings of sexual harassment, dis	crimination, or o	ther civil rights violations against it?
	YES	NO

If YES, please provide full details, including a summary of your position, on attached sheets.

Complete and attach the Equal Employment Opportunity/Civil Rights Supplemental.

Maine Department of Transportation

CONTRACTOR'S PREQUALIFICATION SUPPLEMENTAL

For

MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

10. Certifications Under Oath

This page must be signed, notarized, mailed or scanned and E-Mailed/Faxed to the Department of Transportation to complete the requirements of prequalification.

By signing below, the person signing below hereby certifies and swears, **ON OATH**, as follows.

- 1. I have personal knowledge of all the information contained in this Application OR I am responsible for the accuracy of all such information
- 2. The information contained in this Application is true and complete.
- 3. I hereby authorize the Department to contact any person or entity necessary to verify or supplement any of the information requested by or provided in this Application without liability, and I hereby further authorize any person or entity contacted to provide any and all information requested without liability.
- 4. The Contractor has read, understands, and agrees to all terms of the Prequalification Procedure and this Application.
- 5. I am duly authorized by law and by the Contractor to sign this Application on behalf of the Contractor.

Date	CONTRACTOR
Witness	[Signature]
	By: [Name and Title Printed]
State of County of	Date:
this instrument to be his or her free act	person who signed this page above and acknowledged and deed and the free act and deed of the Contractor, aTH, that the statements made under the section 10 re true and complete.
My Commission Expires:	
	[Signature of Notary Public] Name Printed:

Maine Department of Transportation Safety Supplemental

CONTRACTOR SAFETY QUESTIONNAIRE

A.	Using your OSHA 300	nat your company meet cer or recordkeeping forms and or the immediate past (3) the	d statements pro		
	Year		20	20	20
	1. Workers' compen	sation *EMR (interstate)			
	2. Total employee h	ours worked			
	(May be obtained	from OSHA from 300A)			
	3. Total number of c (columns G, H, I, 300)	cases J from the OSHA form			
	4. Total lost work da	ay cases			
	(column H from t	he OSHA form 300)			
	5. Total number of c	cases with job transfer or			
	restriction (colum	in I from OSHA form 300)			
	,	above x 200,000/ B above			
	7. *** TLWDI (D a	bove x 200,000/ B above			
	8. Total fatalities				
	(column G taken	off the OSHA form			
	*EMR= Experience Mo **TCIR= Total Case In ***TWDI= Total Lost V	cidents			
B.	Has your company susta	ained any work-related fata	lities during the	e past (3) three y	ears?
	Yes O No O				
	If yes, please provide fu and implemented to pre	all details of each fatality by vent reoccurrence.	y attachment, in	clude corrective	e actions identifie
C.	State to whom and how	often incident/accident rep	oort summaries a	are distributed.	
	CEO President	Monthly	Quarterly	Annually	No
	Manager of Constructi Site Managers				

Page 1 of 4 Revision Date: 09/2020

Maine Department of Transportation Safety Supplemental eived an OSHA (or state OSHA) citation within the last 5 years?

D.	Yes No
	If yes, provide the number and type of violation?
	if yes, provide the humber and type of violation.
E.	Are on site safety meetings conducted for field supervisors?
	Yes No No
	If yes, how often
F.	Does your company have a safety officer/department?
	Yes No No
	If yes,
	Name:
	Title:
	Telephone/Cell Phone #
	Email:
G.	Does your company conduct field safety inspections to determine compliance with applicable regulatory standards and company procedures?
	Yes No No
	If yes, who conducts these inspections?
	Name
	Title
	How Often?
Н.	Does your company have a written Safety and Health Policies, Program, and Procedure manual?
	Yes No No
	If yes, please provide electronic copy (CD, USB Flash Drive or e-mail attachment) for review.
I.	Has your company developed any job/site-specific policies and procedures manuals?
	Yes No No
	If yes, please provide electronic copy (CD, USB Flash Drive or e-mail attachment) for review.

Page 2 of 4 Revision Date: 09/2020

Maine Department of Transportation Safety Supplemental

J.		your company developed and utilized an orientation oyees would include those persons who are new to each		1 -	New
	Yes	O No O			
	If yes	s, does it include instruction and/or training in the follow	wing areas?		
			Yes	No	
	1. 2. 3. 4. 5. 6. 7. 8. 9. 10. 11 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25.	Personnel Protection Equipment Eye Protection Hearing Protection Respiratory Protection Fall Protection/Prevention Silica Exposure Control Lead Exposure Control Scaffolds/ Ladders/Aerial Lifts Working over or near Water Hot Work - Welding & Cutting Hand & Power Tool Safety Perimeter Guarding Fire Protection Emergency Response First Aid Procedures Hazard Communications, as per OSHA 1910.1200, including Safety Data Sheets (SDS) Electrical Safety Lock-Out/Tag-Out Procedures Trenching and Excavation Substance Abuse Rigging and Crane Safety Confined Spaces Work Zone Safety Traffic Control (MUTCD) COVID-19 Response and Procedures			
K.		your company have a formal Hazardous Communic 0.1200)?	cation progran	m as per OSHA 19	26.59
		Yes No No Compare provide in its entirety (note: 1910.1200 was update nonization Standard).	d in 2013 and	I must include the C	Global
L.	Does	your company have a foreman-supervisor's training pr	ogram?		
		Yes No			

Page 3 of 4 Revision Date: 09/2020

Maine Department of Transportation Safety Supplemental If yes, does it include instruction and/or training in the following areas?

							Yes	NO
1. 2. 3. 4. 5. 6. 7. 8. 9.	. F . E . H . F . C . S		Response Prostigation munication on and Prev Craft Safety Practices azard Analy cable, are fo	ocedures ention Meetings sis oremen train	ed in Process Sa in OSHA 1910.1	-		
M.	Are we	eekly craft sa		gs held? If y	yes, submit a sa	mple of meet	ting notes	
N.	Do you	hire subcor	ntractors?					
			n method us	equalification ed to qualify	n process? · lower-tier subc	contractors.		
O.	Yes (O No			years that cause			perty damage?
	perative	that all cont	tractors, sub		and lower-tier of			ll applicable
Please	print ar	nd sign belo	W.					
					Title:			
					Sign:			

Page 4 of 4 Revision Date: 09/2020

MAINE DEPARTMENT OF TRANSPORTION EQUAL EMPLOYMENT OPPORTUNITY/ CIVIL RIGHTS OFFICE SUPPLEMENTAL

- 1. Please submit your written Affirmative Action Plan with goals & timetables to correct any manifest imbalance in your employment of women & minorities. Plan must be signed by Company President or authorized representative & reflect current date. http://law.justia.com/cfr/title23/23-1.0.1.3.8.1.1.12.2.html
- 2. Please submit your Company's written sexual harassment policy that includes *sexual orientation. Policy must be signed by Company President or authorized representative & reflect current date.

http://www.mainelegislature.org/legis/statutes/26/title26sec807.html * http://www.mainelegislature.org/legis/statutes/5/title5sec4571.html

3. Does your Company provide sexual harassment training to employees & supervisors? If yes, how often & by whom?

http://www.mainelegislature.org/legis/statutes/26/title26sec807.html

- 4. Please submit your Company's non-discrimination policy. Policy must be signed by Company President or authorized representative and reflect current date.

 http://law.justia.com/cfr/title23/23-1.0.1.3.8.1.1.12.2.html
- 5. Within 5 years, has your Company had any findings of probable cause or court rulings of sexual harassment, discrimination, or other civil rights violations? If yes, please provide full details, including a summary statement of your position.

http://law.justia.com/cfr/title23/23-1.0.1.3.8.1.1.12.2.html

- 6. Does your company actively solicit bids/quotes from disadvantaged, minority, and/or women owned businesses? If no, why? Please refer to: Division 100–Appendix A-12 Federal Contract Provision Supplemental of the 2002 Standard Specification:

 http://maine.gov/mdot/contractors/publications/standardspec/
- 7. Describe the procedure you use to ensure your company is in compliance with Disadvantaged Business Enterprise (DBE) requirements. Please refer to: Division 100–Appendix A-12 Federal Contract Provision Supplemental of the 2002 Standard Specification:

 http://maine.gov/mdot/contractors/publications/standardspec/
- 8. Describe the procedure you use to ensure all subcontractors used by your company are in compliance with EEO laws.
- 9. Provide a list of all companies you solicit subcontract bids/quotes from.
- 10. What is the name of your company's EEO Officer. http://law.justia.com/cfr/title23/23-1.0.1.3.8.1.1.12.2.html
- 11. Provide a job description that outlines all EEO duties of your company EEO Officer.
- 12. What percentage of that person's time is spent on EEO duties?
- 13. Complete the attached Company Construction Workforce (EEO-1 Report)

EQUAL EMPLOYMENT OPPORTUNITY/CIVIL RIGHTS SUPPLEMENTAL MAINE DEPARTMENT OF TRANSPORTATION

Company Construction Workforce Report (EEO-1 Report)

ompany name	ear covered by report	

Report of employment statistics for the entire company workforce, by number of employees for each craft during the last calendar year.

POSITION	TOTAL	WHITE	FEMALES	HISPANIC	AMERICAN INDIAN OR ALASKAN NATIVE	ASIAN OR PACIFIC ISLANDER	BLACK	DISABLED	# OF RECALLS
Superintendent									
Operating Engineer									
Equipment Operator									
Mechanics									
Truck Drivers									
Ironworkers/Re-Rod									
Carpenters									
Const. Worker Bridge									
Const. Worker Highway									
Pipelayer									
Bridge-Maint. Worker									
Laborer, Semi-Skilled									
Laborer, Unskilled									
Foreperson, Bridge									
Foreperson, Highway									
Welder									
Other:									

STATE OF MAINE DEPARTMENT OF TRANSPORTATION CONTRACTOR PREQUALIFICATION PROCEDURE

MARINE DOCK, PIER, BRIDGE & FACILITIES REPAIR AND REHABILITATION

Contractors desiring to perform Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation and related work, except Capital Projects, bid or ordered between the dates given in the Special Provisions for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation must submit a properly completed Application by the date in the notice and sign a contract unless one of the exceptions to prequalification listed below of this Procedure applies.

All Contractors must be prequalified in accordance with the provisions of this Procedure to be eligible to be awarded a Contract, EXCEPT that such prequalification is not required if:

- 1. the estimate of work is \$ 5,000 or less;
- 2. the Contractor is contracted pursuant to a separate process specific to that project such as private equipment rental;
- 3. the Department waives the requirement for prequalification for good cause shown and in the best interest of the State.

The Bidder must honestly, accurately and completely supply all information requested in the Application. Bidders shall ensure that all information required herein is submitted. Provision of inaccurate information or failure to provide all completed and required information may result in the Bidder being determined to be "Not Qualified" or disqualified as non-responsive. A Committee shall review all information provided in the Application. Whenever the Committee determines that the nature or extent of the information provided in the Application is insufficient or indicates that the Bidder is not qualified, the Committee will, contact the Bidder to seek additional information. The Department reserves the right to communicate in writing with Bidders, if needed, to obtain additions to and/or clarification of information contained in the submittals received. The Bidder shall have 3 days to submit additions and clarifications. The Bidder will have no additional opportunity to submit or clarify information. The Department will not provide an opportunity for the Bidder to meet to present evidence.

The qualifications submitted will be checked for general conformance with the concept of the projects and compliance with the requirements set out in the Contract Documents. This review does not modify the Contractor's duty to comply with the contract documents.

The Committee shall evaluate all the information provided or obtained as a whole on a passfail basis to determine whether the Bidder is responsible and qualified. In doing so, the Committee will use the following descriptive categories.

Based on these submissions, the Department will make one of the following determinations:

QUALIFIED: Bidder qualified and submission reviewed. Sufficient information exists to determine that the Bidder is likely to respond to an

STATE OF MAINE DEPARTMENT OF TRANSPORTATION CONTRACTOR PREQUALIFICATION PROCEDURE MARINE DOCK, PIER, BRIDGE & FACILITIES REPAIR AND REHABILITATION

emergency and construct acceptable repairs in a timely manner using acceptable processes.

NOT QUALIFIED: Bidder is not qualified to properly carry out the terms of the Contract and/or the submission does not meet specifications and accepted standards and is not acceptable and/or the information demonstrates that it is unlikely that the Bidder can respond to an emergency or construct acceptable repairs in a timely manner using acceptable processes, as determined by the Department.

Grounds for Determination of "Not Qualified"

A finding by the Committee based upon substantial evidence that any one of the following conditions exists shall be sufficient grounds, though not mandatory grounds, for an overall determination of "Not Qualified". The Department will approve all Committee findings of "Not Qualified."

- (1) Not meeting contract Contractor Requirements.
- (2) Unsatisfactory and/or insufficient Bidder experience.
- (3) Number of personnel with applicable knowledge and experience significantly below industry standards.
- (4) Insufficient equipment to respond to emergencies.
- (5) Unlikely to respond and have Personnel and equipment on site within four hours.
- (6) Safety record, environmental record or civil rights record significantly below industry standards.
- (7) No Safety Plan or an unacceptable Safety Plan.
- (8) A denial of prequalification or award of contract, disbarment, or other irregularities with respect to any federal, state, or local government or procurement agencies.
- (9) A pattern of unsupported Claims.
- (10) Deceptive, evasive, misleading or fraudulent statements, or omissions contained in the Application, or otherwise regarding a claim on prior Contracts, on the Contractor's Prequalification Application, or the Post-Bid Qualifications submittals.

STATE OF MAINE DEPARTMENT OF TRANSPORTATION CONTRACTOR PREQUALIFICATION PROCEDURE

MARINE DOCK, PIER, BRIDGE & FACILITIES REPAIR AND REHABILITATION

- (11) Default(s) or termination(s) on past or current Contracts.
- (12) Failure to pay or settle all bills for labor, Materials or services on past or current Contracts.
- (13) Failure to provide Closeout Documentation on past or current Contracts.
- (14) Failure to fulfill warranty obligations on past or current Contracts.
- (15) Failure to comply with directives of the Department on past or current Contracts.
- (16) "Below Standard" performance as determined from the Department's Contractor's Performance Rating process.
- (17) Failure to accept an Award of a Contract made by the Department to the Contractor.
- (18) Failure to provide information requested by the Department pursuant to this Special Provision.
- (19) Any of the reasons contained in Section 102.02 of the "Rules Regarding Debarment of Contractors", Maine Department of Transportation Register 17-229, Chapter 102 (October 2, 1985).
- (20) Debarment or suspension by any federal, State, or local governmental procurement agency or the Contractor's Agreement to refrain from Bidding as part of the settlement with any such agencies.
- (21) Conviction of a bid or other crime or indictment with substantial evidence regarding the same.
- (22) Other serious misconduct that the Department reasonably determines will substantially and adversely affect the cost, quality or timeliness of Work, or the safety of Workers or the public.
- (23) Other substantial deficiencies that are clearly below industry standards and that clearly demonstrate that the Contractor is "Not Qualified".

If the Bidder is found to be qualified, the Department will deliver to the Bidder a "Notice of Prequalification". Once a Bidder has furnished Certificates of Insurance complying with the Standard Specifications and any other pre-executions conditions are met, the Department may

STATE OF MAINE DEPARTMENT OF TRANSPORTATION CONTRACTOR PREQUALIFICATION PROCEDURE MARINE DOCK, PIER, BRIDGE & FACILITIES REPAIR AND REHABILITATION

execute and award a contract. If the Department determines that the Bidder is not qualified, said Notice will also set forth the specific reasons therefore to the extent practical and no contract will be awarded.

Appeals and Definitions will be those described in the Maine Department of Transportation Contractor's Prequalification Procedure.

SPECIAL PROVISIONSFor

PREQUALIFICATION FOR MARINE DOCK, PIER, BRIDGE AND FACILITIES REPAIR AND REHABILITATION

Scope

The Maine Department of Transportation, Bureau of Maintenance & Operations is accepting prequalification applications from Contractors desiring to perform or bid on Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation. Work may be ordered by the Department after December 11, 2020 or contract execution, whichever is latest, and before **November 30, 2028.** The Contractor agrees to complete all Work, except warranty work, on or before **December 31, 2028**. The Contractor shall complete all Work, except warranty work, on or before the Completion Date given in the Assignment Letter.

Not all Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation will be done under these contracts. Capital Projects will be excluded. Work will also be done by the Department, under private equipment rental agreements, MaineDOT Agreement for Special Services and other means not associated with this solicitation. The dollar amount of this Contract is in no way a guarantee that the Department will Assign Work for any or all of the total amount.

Contractor Requirements

The Contractor shall be prequalified by the Maine DOT for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation.

The Department may require the Bidder to submit evidence of compliance with all Contractor Requirements set forth in this Contract.

The Contractor shall have successfully completed projects of similar size and scope and have sufficient experience in marine dock, pier, bridge and facilities repair, rehabilitation or construction, or the maintenance of machine operated moveable bridges. Said experience shall include, at a minimum, at least three (3) projects of equal or greater complexity than the work required by this Contract completed by the Bidder in the last five (5) years. Areas of experience shall include, but are not limited to, Work performed in or around water bodies in compliance with standards set by the Maine Department of Environmental Protection (MDEP). The Contractor must demonstrate or have demonstrated knowledge and experience involving Coast Guard regulations for navigable waterways including 33 CFR 117.

Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation October 31, 2024

A Contractor must furnish Certificates of Insurance complying with the Standard Specifications prior to award.

The Contractor shall perform the Work described in the Assignment Letters in a timely and efficient manner in compliance with the Assignment, specifications and this Contract.

The Bidder shall be able to comply with the Contract Requirements, be able to deliver according to the contract schedule, and have a history of satisfactory performance.

The Bidder must have a current, compliant and applicable Safety Plan on file with the Department or must submit, prior to prequalification, an acceptable, current, project specific Safety Plan to the Department which identifies and addresses job hazards of the expected contract work and complies with all applicable federal, State, and local laws governing safety including all applicable laws and regulations of Occupational Safety and Health Administration (OSHA).

Assignments

The Contract will obligate each Contractor to perform work pursuant to an Assignment depending upon the needs of the Department and according to the following terms.

As scheduled work with an estimate of \$10,000.00 or more arises, the Department will prepare a bid solicitation stating the nature of the Work, method of payment, and any time constraints. This will be sent to all Contractors under contract and prequalified for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation. If a submitted bid contains any additional conditions or alternate bidding language, the Bidder may cure the defect by removing all conditions and alternate language or the Department will reject the bid as non-responsive. The Work will be given to the lowest prequalified bidder with the ability to complete the Work (the "Assignment") in the allotted time. An Assignment Letter will then be sent to the successful bidder stating the price, payment, and schedule. The Work described in this letter will become part of the Contract.

If work arises for which the Contractor is responsible for traffic control, only prequalified contractors, that have previously submitted compliant Traffic Control Plans to the Department and with prior experience performing work in live traffic in accordance to the Manual on Uniform Traffic Control Devices (MUTCD) may bid.

As scheduled work with an estimate of less than \$10,000.00 arises, the Department will solicit quotes from a minimum of three Contractors prequalified for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation. If a submitted quote contains any additional conditions or alternate language, the Bidder may cure the defect by removing all conditions and alternate language or the Department will reject the bid as non-responsive. The Work will be given to the lowest prequalified bidder with the ability to complete the Work (the "Assignment") in the allotted time. The Department and the

Contractor shall mutually agree to the price, quantities and schedules prior to the Contractor beginning the Assignment. This Work will become part of the Contract.

In the case an emergency arises for which the response time does not allow for the preparation a bid solicitation, that the Department has determined the work required can best be addressed using one of these contracts, the Department will contact one of the Contractors Prequalified for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation. The Department will select a Contractor to call based on an evaluation of rates, experience and equipment, geographic proximity, response time and determination of what is in the best interest of the State. Upon mutual agreement, an Assignment Letter will then be sent stating the price, payment, and time. The Work (the "Assignment") described in this letter will become part of the Contract.

The Assignment Completion Date shall be the required completion date of all work pursuant to the Assignment and any authorized extensions provided by the Department in writing. All Work for each Assignment must be completed by the Assignment Completion Date.

Except as expressly provided otherwise in this Contract, the Contractor or, in case of default, its Surety, shall owe the Department the per diem amount specified in Section 107.7.2 - Schedule of Liquidated Damages, as well as any per diem amount of Supplemental Liquidated Damages as specified in the Assignment, for each Calendar Day that any portion of the Work remains incomplete after the Assignment Completion Date. Should the Contractor fail to complete the Work by the Assignment Completion Date, a deduction of the amount stipulated in the Contract as Liquidated and Supplemental Liquidated Damages will be made for each and every Calendar Day that such Work remains uncompleted. This amount will be deducted from any money due the Contractor under the Contract, and the Contractor will be liable for any Liquidated and Supplemental Liquidated Damages in excess of the amount due. Permitting the Contractor to continue and finish the work or any part thereof after the expiration of the Assignment Completion Date shall in no way operate as a waiver on the part of the Department of its rights to assess and recover Liquidated and Supplemental Liquidated Damages, or any other rights, under the Contract.

For each Assignment, Completion of Physical Work for the Assignment occurs when the Work in the Assignment is complete and has undergone a successful final inspection. Liquidated Damages will cease upon the Completion of Physical Work for the Assignment.

The Assignment will be Finally Accepted upon receipt and approval of the itemized invoice, and, when applicable, Certified Payroll Reports, the All Bills Paid Letter, and a Materials Certification letter.

If the Contractor fails to resolve issues and deliver the above documentation, within 30 Days of Completion Physical Work for the Assignment, the Department may

withhold payment and the Contractor may be refused the opportunity to accept future assignments under the Contract.

<u>Insurance</u>. The Contractor shall supply proof of insurance in accordance with State of Maine, Department of Transportation, *State of Maine Department of Transportation Standard Specifications, March 2020 Edition* before this Contract will be signed by the MDOT.

Allowable Work Times. Unless otherwise authorized, the Contractor shall perform work only during the following times Monday through Friday, 7:00 through 4:00 PM except for they may not work on holidays as defined in Appendix B nor state government closure days. The Contractor is solely responsible for the planning and execution of Work in order to complete the Work within the Contract Time.

<u>Contractor's Safety Program</u>. If a copy of the Contractor's Safety Plan is not on file with the Contracts Section of the Department, the Contractor must submit, prior to prequalification, a project specific Safety Plan to the Regional Office of the Department. The Contractor's Safety Plan shall identify and address job hazards of the expected contract work and shall comply with all applicable federal, State, and local laws governing safety including all applicable laws and regulations of OSHA.

<u>Wage Rates.</u> If an Assignment exceeds \$50,000, State Wage Rates will apply to that Work. Federal Wage Rates do not apply to Work performed under the Assignment.

Bonds. In the event an Assignment exceeds \$125,000 and the work consists of the construction or repair, payment and performance bonds shall be required prior to the Contractor being assigned the work. Bonds shall not be required for emergency work.

<u>Invoices and Payment.</u> The Contractor shall submit an itemized invoice to the Department for services monthly, at the completion of the Work or as otherwise noted in the Assignment Letter for approval and payment. At a minimum, invoices shall include the following information:

- ° Contractor name, address & Contract Number
- ° Invoice Date & Number
- Dates of Service
- Description and location of the Work.
- ° Amount Due

The Department pay based upon complete, correct and approved invoices for accepted Work invoiced at bid prices. The Department may require that the Contractor submit backup documentation including copies of receipts, invoices, and itemized payments to Subcontractors. Payments to the Contractor shall be full compensation for furnishing all labor, Equipment, Materials, services, and Incidentals used to perform all Work under the Contract in a complete and acceptable manner, and for all risk, loss, damage, or expense of any kind arising from the nature or execution of the Work.

The Department may withhold payments claimed by the Contractor on account of:

- ° Incomplete or incorrect invoices
- ° Defective or Non-conforming Work.
- ° Damage to a third party.
- ° Claims filed or reasonable evidence indicating probable filing of claims.
- ° The Contractor's failure pay Employees, Suppliers and/or Subcontractors.
- ° Regulatory non-compliance or enforcement.
- ° All other causes that the Department reasonably determines negatively affect the State's interest.

<u>Taxes and Fees.</u> The Contractor shall pay all taxes, charges, fees, and allowances. Most items are exempt from Maine sales tax. The Contractor shall Bid in accordance with the Maine statutory exemption from sales tax.

<u>Termination</u>. The Department may terminate this Contract with or without cause upon 7 days written notice. Termination of the contract shall not relieve the Contractor of its contractual responsibilities for the work completed prior to termination (including warranty obligations), nor shall it relieve the Surety of its obligation for claims arising from the Work or the Contract. The Department will pay for all accepted items of Work completed prior to the date of Termination at agreed upon prices.

Failure to Perform. If for any reason the Contractor is unable to complete the Work specified in the Assignment or Contract in an acceptable manner, fails to provide labor or Equipment, fails to perform the Work with sufficient labor, Equipment, or Materials to assure the timely Completion of the Work, fails to perform Work when required in the Assignment, performs Work in an unsatisfactory manner, or fails to meet other contractual requirements the Department may give written Notice of Default to the Contractor, which will outline the required remedies. Any delay by the Department in providing a written Notice of Default shall in no way constitute a waiver by the Department of any provision of the Contract. If the Department determines the default is not curable, the notice of default shall also include the date of termination. Termination of the Contract or portion thereof shall not relieve the Contractor of its Contractual responsibilities for the Work completed.

In addition the Department may complete the work with its own forces or enter into an Assignment with another entity for the Completion of the Work, or use such other methods as in the opinion of the Department are required for the Completion of the intent of the Contract in an acceptable and timely manner.

<u>Default and Termination of Assignment</u> The Contractor is in Default of the Assignment if the Contractor:

- A. Fails to adhere to obligations of the Assignment or Contractor Requirements.
- B. Fails to answer or reply to the Department within ½ hour of emergency notification of work.
- C. Fails to commence work or be onsite within 2 hours after accepting an emergency assignment.
- D. Fails to provide sufficient labor, Equipment, or Materials to assure the timely Completion of the Assignment.
- E. After work on assignment has commenced, fails to continuously work on assignment without Department approval.
- F. Performs Defective Work neglects or refuses to repair or correct Unacceptable Work when directed by the Department.
- G. Continues to perform Work after the Department directs that Work be stopped.

If Default and Termination of Assignment occurs, the Department may give written Notice of Default and Termination of Assignment to the Contractor. Failure to give Notice of Default is in no way a waiver by the Department of any provision of the Contract. In this event, the Department may award the Assignment to another Contractor for the Completion of the Work, or use such other methods as in the opinion of the Department are required for the Completion of the intent of the Assignment in an acceptable and timely manner.

Upon receiving a 2^{nd} Default and Termination of Assignment, the Department may, in addition, consider this 2^{nd} notification as a Default and Termination of Contract 2^{nd} Incident written warning.

<u>Default and Termination of Contract</u> The Contractor is in Default of the Contract if the Contractor:

- A. Fails to provide labor, Equipment or Materials specified in the Assignment or Contract,
- B. Fails to perform the Work with sufficient labor, Equipment, or Materials to assure the timely Completion of the Assignment,
- C. Fails to perform Work when specified in the Assignment.
- D. Performs Defective Work neglects or refuses to repair or correct Unacceptable Work when directed by the Department;
- E. Becomes insolvent or is declared bankrupt or commits any act of bankruptcy or insolvency that could affect the Work in any way,
- F. Discontinues the Work without the Department approval,
- G. Continues to perform Work after the Department directs that Work be stopped,
- H. In any other manner, fails to perform the Work in Substantial Conformity with any material provision of the Contract.

Prequalification for Marine Dock, Pier, Bridge and Facilities Repair and Rehabilitation October 31, 2024

Failure by the Contractor to perform the Work when required or to substantially meet other contractual requirements will result in the following actions:

1st Incident: If the Contractor does not take corrective action for a nonemergency Assignment within 2 days upon receipt of verbal warning, for an emergency Assignment within 2 hours after notification the Department will issue a written warning.

2nd Incident: The Department will issue a written warning.

3rd Incident: The Department may (A) give written Notice of Default to the Contractor and immediately terminate the Contract by written Notice of Termination, or (B) take prosecution of the Work away from the Contractor without violating the Contract (C) for if an emergency will count as 1st incident and no time to cure.

If Default occurs, the Department may give written Notice of Default to the Contractor. Failure to give Notice of Default is in no way a waiver by the Department of any provision of the Contract. In this event, the Department may enter into an Agreement with another entity for the Completion of the Work, or use such other methods as in the opinion of the Department are required for the Completion of the intent of the Assignment in an acceptable and timely manner. The Department will pay for all Accepted items of Work as of the date of Termination at agreed upon prices.

SPECIAL PROVISIONS ADDITIONS AND REVISIONS TO STANDARD SPECIFICATIONS

SPECIAL PROVISION SECTION 101 CONTRACT INTERPRETATION

<u>101.2 Definitions</u> Add the following:

<u>MaineDOT</u> The Department of Transportation of the State of Maine, as established by 23 MRSA §4205 et seq. for the administration of Highway, Bridge, and other public Works; acting through the Commissioner and his/her duly authorized representatives.

<u>101.2 Definitions Apparent Successful Bidder</u> Delete the section in its entirety and replace with the following:

"All Prequalified Bidders with the responsive responsible Bids as determined by the Department. A responsive responsible Bidder, that is Awarded the Contract. The Department may not execute the Contract with an Apparent Successful Bidder if a) the Apparent Successful Bidder fails to comply with all applicable pre-Award conditions or other pre-execution requirements of the Contract or b) if the Department chooses not to Award a Contract."

<u>101.2 Definitions Successful Bidder</u> Delete the section in its entirety and replace with the following:

"All responsive, responsible bidders to whom the Department intends to award the Contract. This status is evidenced by a "Notice of Intent to Award" Letter sent to the Successful Bidders."

SPECIAL PROVISION SECTION 102 BIDDING

102.6 Bid Guaranty Delete the entire section 102.6.

102.7.1 Location and Time Delete the entire section and replace with the following:

The Bidder must Deliver its Bid and Bid Guaranty in a sealed envelope to the exact location and before the precise time (as determined by the Department) specified in the Notice to Contractors or any applicable Bid Amendment. The sealed envelope must be labeled with the Bidder's name, the Project location, Title, and the words "Bid Enclosed". As a minimum, the Bidder will submit a Bid Package consisting of the Notice to Contractors, the completed Acknowledgement of Bid Amendments form, the completed Prequalification Application, 2 copies of the completed Contract form, and any other

Certifications or Bid Requirements listed in the Bid Book. For a related provision, see Section 102.11 - "Bid Responsiveness".

102.9 Bid Opening Delete the section in its entirety and replace with the following:

"Bids will be opened and publicly read at the time and place specified in the Notice to Contractors or any applicable Bid Amendments. The Department will read only the names of the Bidders. No other information will be made available prior to evaluation and award notification. Unit and lump sum prices are available for inspection by the Bidders immediately after Award. All Bids shall be sequestered until notification of award by the contracting agency after which time they become public record.

If, after the scheduled opening, the Department determines that there is not sufficient coverage of On-Call Services of the entire area being bid on, the Department may schedule a second bid opening date which extends the advertisement period of this Contract. Contractors will be notified of the new opening date by the normal Bid Amendment process. If the Bid Opening date is extended, any Bidders that have previously submitted Bids may choose to revise or not to revise their Bids. If the Bidder chooses to revise their Bid, they must resubmit a complete Bid Package which shall include a Bid and all other documents required in the Bid Documents and the original Bid will be returned to the Bidder. The Bid Package with the latest (newest) date shall replace all previously submitted packages.

The public reading of a Bid does not constitute a determination by the Department of whether the Bid is responsive or of whether the Bidder is responsible, though the Department may refuse to read Bids that are obviously non-responsive. Accordingly, the Department may reject a Bid as non-responsive and/or determine a Bidder is not responsible or ineligible to Bid even if that Bidder's Bid is read at Bid Opening."

<u>102.11.2 Curable Bid Defects</u> Revise this section by adding the following:

"The Bidder only signs one of the Contract forms or the Bidder does not sign the Contract form but does sign the Application." and "If a submitted bid contains any additional conditions or alternate bidding language, the Bidder may cure the defect by removing all conditions and alternate language or the Department will reject the bid as non-responsive."

SPECIAL PROVISION SECTION 103 AWARD AND CONTRACTING

103.5 Award Conditions Replace the first paragraph with the following:

Apparent Successful Bidder(s) must provide and/or perform all of the items listed in this Section 103.5 within 14 Days of Receipt of the Notice of Intent to Award. Unless indicated otherwise, all items must be Delivered to the Department's Bureau of Maintenance & Operations.

103.5.1 Performance and Payment Bonds Delete the entire section 103.5.1.

<u>103.5.4 Execution of Contract By Bidder</u> Delete the entire section and replace with the following:

"The properly completed and signed Contract form provided with the Bid constitutes the Bidder's offer. Once the Department has received the insurance, and any other pre-award items required, the Department will sign and execute the Contract. The point of Contract execution is when the Contractor receives written notice that the contract has been signed by the Department and executed."

SPECIAL PROVISION SECTION 105 GENERAL SCOPE OF WORK

105.2.2 Health and Safety Plan Delete the entire section and replace with the following:

A copy of the Contractor's Health and Safety Plan must be on file with the Department to be awarded a Contract. If a copy of the Contractor's Health and Safety Plan is not on file with the Contracts Section of the Department, the Contractor must submit a compliant copy of the Contractor's Health Safety Plan to the Department's Bureau of Maintenance & Operations in an electronic media format prior to Prequalification and Contract award.

THIS DOCUMENT MUST BE CLEARLY POSTED AT ALL CONSTRUCTION SITES FUNDED IN PART WITH STATE FUNDS

State of Maine Department of Labor - Bureau of Labor Standards Augusta, Maine 04333-0045 - Telephone (207) 623-7906

Wage Determination - In accordance with 26 MRS §1301 et. seq., this is a determination by the Bureau of Labor Standards, of the fair minimum wage rate to be paid to laborers and workers employed on the below titled project.

2024 Fair Minimum Wage Rates -- Heavy & Bridge Statewide

Occupational Title	Minimum Wage	Minimum Benefit	Total
Brickmasons And Blockmasons	\$35.00	\$0.86	\$35.86
Bulldozer Operator	\$31.50	\$7.53	\$39.03
Carpenter	\$30.65	\$4.81	\$35.46
Cement Masons And Concrete Finisher	\$22.67	\$2.21	\$24.88
Commercial Divers	\$30.00	\$4.62	\$34.62
Construction And Maintenance Painters	\$24.50	\$5.24	\$29.74
Construction Laborer	\$25.00	\$3.75	\$28.75
Crane And Tower Operators	\$33.44	\$7.53	\$40.97
Crushing Grinding And Polishing Machine Operators	\$23.00	\$4.94	\$27.94
Drywall And Ceiling Tile Installers	\$26.20	\$10.62	\$36.82
Earth Drillers - Except Oil And Gas	\$24.16	\$2.53	\$26.69
Electrical Power - Line Installer And Repairers	\$38.93	\$8.67	\$47.60
Electricians	\$34.50	\$10.23	\$44.73
Elevator Installers And Repairers	\$68.38	\$45.29	\$113.67
Excavating And Loading Machine And Dragline Operators	\$30.00	\$3.24	\$33.24
Excavator Operator	\$30.00	\$4.32	\$34.32
Fence Erectors	\$24.00	\$2.05	\$26.05
Flaggers	\$20.00	\$0.50	\$20.50
Floor Layers - Except Carpet/Wood/Hard Tiles	\$27.00	\$6.21	\$33.21
Glaziers	\$37.00	\$6.60	\$43.60
Grader/Scraper Operator	\$23.00	\$1.99	\$24.99
Hazardous Materials Removal Workers	\$21.50	\$1.54	\$23.04
Heating And Air Conditioning And Refrigeration Mechanics And Installers	\$32.00	\$5.46	\$37.46
Heavy And Tractor - Trailer Truck Drivers	\$27.00	\$2.90	\$29.90
Highway Maintenance Workers	\$20.00	\$0.00	\$20.00
Industrial Machinery Mechanics	\$32.00	\$0.96	\$32.96
Industrial Truck And Tractor Operators	\$30.00	\$2.90	\$32.90
Insulation Worker - Mechanical	\$24.05	\$3.59	\$27.64
Ironworker - Ornamental	\$27.75	\$4.50	\$32.25
Light Truck Or Delivery Services Drivers	\$22.84	\$1.25	\$24.09
Millwrights	\$33.50	\$8.54	\$42.04
Mobile Heavy Equipment Mechanics - Except Engines	\$29.50	\$4.92	\$34.42
Operating Engineers And Other Equipment Operators	\$28.00	\$2.67	\$30.67
Paver Operator	\$25.30	\$3.73	\$29.03
Pile-Driver Operators	\$32.75	\$1.95	\$34.70
Pipelavers	\$28.50	\$4.89	\$33.39
Plumbers Pipe Fitters And Steamfitters	\$36.00	\$20.11	\$56.11
Pump Operators - Except Wellhead Pumpers	\$31.49	\$32.08	\$63.57
Radio Cellular And Tower Equipment Installers	\$27.00	\$3.90	\$30.90
Reclaimer Operator	\$27.00	\$7.68	\$30.90
Reinforcing Iron And Rebar Workers	\$22.67	\$25.11	\$47.78
Riggers	\$31.25	\$7.68	\$38.93
Roofers	\$24.00	\$3.35	\$27.35
Screed/Wheelman	\$29.25	\$4.94	\$34.19
Screed/wheelman Sheet Metal Workers	\$29.25	\$4.94	\$34.19
Structural Iron And Steel Workers	\$27.38	\$6.74	\$34.12
Tapers	\$30.00	\$6.98	\$36.98
Telecommunications Equipment Installers And Repairers - Except Line Installers	\$28.00	\$1.71	\$29.71
	,	\$4.02	\$34.41
Telecommunications Line Installers And Repairers Tile And Marble Setters	\$26.00		
THE AND INITION SECTORS	\$27.75	\$6.73	\$34.48

Welders are classified as the trade to which welding is incidental (e.g. welding structural steel is Structural Iron and Steel Worker)

Apprentices – The minimum wage rates for registered apprentices are the rates recognized in the sponsorship agreement for registered apprentices working in the pertinent classification.

For any other specific trade on this project not listed above, contact the Bureau of Labor Standards for further clarification.

Title 26 §1310 requires that a clearly legible statement of all fair minimum wage and benefits rates to be paid the several classes of laborers, workers and mechanics employed on the construction on the public work must be kept posted in a prominent and easily accessible place at the site by each contractor and subcontractor subject to sections 1304 to 1313.

Appeal – Any person affected by the determination of these rates may appeal to the Commissioner of Labor by filing a written notice with the Commissioner stating the specific grounds of the objection within ten (10) days from the filing of these rates.

A true copy

Attest: South R. Cotheri

Scott R. Cotnoir Wage & Hour Director Bureau of Labor Standards

Expiration Date: 12-31-2024 Revision Date: 1-3-2024

2020 STANDARD DETAIL UPDATES

Standard Details and Standard Detail updates are available at: http://maine.gov/mdot/contractors/publications/standarddetail/

<u>Detail #</u>	<u>Description</u>	Revision Date
502(19)	Bridge Drains	3/17/2023
502(15)	Bridge Drains	3/17/2023
502(20)	Bridge Drains	3/17/2023
502(23)	Bridge Drains	3/17/2023
502(24)	Bridge Drains	3/17/2023
502(25)	Bridge Drains	3/17/2023
502(26)	Bridge Drains	3/17/2023
504(07)	Diaphragm & Crossframe Notes	3/17/2023
507(20)	Steel Approach Railing 3-Bar	2/11/2021
507(21)	Steel Approach Railing 3-Bar	2/11/2021
507(22)	Steel Approach Railing 3-Bar	2/11/2021
507(23)	Steel Approach Railing 3-Bar	2/11/2021
507(27)	Steel Approach Railing	2/11/2021
526(01)	Portable Concrete Barrier	1/14/2021
526(01A)	Portable Concrete Barrier	1/14/2021
526(01B)	Portable Concrete Barrier	1/14/2021
526(02)	Portable Concrete Barrier	1/14/2021
526(02A)	Portable Concrete Barrier	1/14/2021
526(03)	Portable Concrete Barrier	1/14/2021
526(04)	Portable Concrete Barrier	1/14/2021
526(04A)	Portable Concrete Barrier	1/14/2021
526(04B)	Portable Concrete Barrier	1/14/2021
526(05)	Permanent Concrete Barrier	3/17/2023
526(21)	Permanent Concrete Barrier	3/17/2023
526(22)	Concrete Transition Barrier	3/17/2023
526(38)	Concrete Transition Barrier	3/17/2023
526(39)	Texas Classic Rail	3/17/2023
526(55)	Texas Classic Rail	3/17/2023

603(10)	Concrete Pipe Ties	6/10/2021
605(01)	Underdrain	7/8/2022
605(01)	Underdrain Notes	7/8/2022
606(17)	Midway Splice Guardrail Transition	6/10/2022
606(23)	Standard Bridge Transition – Type "1"	2/11/2021
606(24)	Standard Bridge Transition – Type "1A"	2/11/2021
608(02)	Detectable Warnings	6/10/2021
609(09)	Precast Concrete Vertical Curb	2/11/2021
627(07)	Crosswalk	2/22/2022
627(08)	Crosswalk	2/22/2022
643(11)	ATCC Cabinet	12/14/2020
801(11)	Pedestrian Ramp Notes	11/20/2023
801(12)	Pedestrian Ramp Requirements	11/20/2023
801(13)	Ramp Length Table	11/20/2023
801(14)	Parallel Pedestrian Ramp	11/20/2023
801(15)	Perpendicular Pedestrian Ramp – Option 1	11/20/2023
801(16)	Parallel Pedestrian Ramp – Option 2A	11/20/2023
801(17)	Perpendicular Pedestrian Ramp – Option 2A	11/20/2023
801(18)	Parallel Pedestrian Ramp – Option 2B	11/20/2023
801(19)	Perpendicular Pedestrian Ramp – Option 2B	11/20/2023
801(20)	Parallel Pedestrian Ramp – Option 3	11/20/2023
801(21)	Perpendicular Pedestrian Ramp – Option 3	11/20/2023
801(22)	Side Street Pedestrian Ramp	11/20/2023
801(23)	Parallel Pedestrian Ramp – Esplanade	11/20/2023
801(24)	Perpendicular Pedestrian Ramp – Esplanade	11/20/2023
801(25)	Island Crossings	11/20/2023
801(26)	Blended Transition	11/20/2023
801(26)	Blended Transition	1/19/2024
801(27)	Pedestrian Ramp Adjacent to Driveway or Entrance	11/20/2023
802(05)	Roadway Culvert End Slope Treatment	1/03/2017

SUPPLEMENTAL SPECIFICATIONS

(Corrections, Additions, & Revisions to Standard Specifications – March 2020)

SECTION 101 CONTRACT INTERPRETATION

101.2 Definitions

Construction Easement revise this definition by removing it in its entirety and replace with; "A right acquired by the Department for a specific use of private property outside of the established Right-of-Way. Examples include but are not limited to Drainage Easements, Construction and Maintenance Easements, and Slope Easements. Construction Easement areas, including Temporary Construction Limits and Temporary Road Limits, outside of the Right-of-Way remain private property. No use other than to access and perform the specified work activity is permitted without written permission of the owner."

Construction Limit Line Remove this definition in its entirety.

<u>Holidays</u> Amend this paragraph by adding "**Juneteenth**" between 'Memorial Day' and 'Independence Day'.

<u>Plans</u> Revise this paragraph by removing "Standard Details, Supplemental Standard Details" from the first sentence.

Project Limits Revise this definition by removing it in its entirety and replacing it with: "Areas within the Right-of-Way, Construction Easements, or Temporary Construction Limits shown on the Plans or otherwise indicated in the Contract. If no Project Limits are indicated in the Contract, the Project Limits shall be determined by the Department. For a related Maine statute, see 23 MRSA § 653. "

Right-Of-Way Revise this definition by removing it in its entirety and replacing it with: "The area of land, property, or interest therein, acquired for or devoted to the Project or other purposes. Portions of the Right-of-Way may be used for storage of materials and equipment and the location of engineering facilities, subject to written approval by the Department."

Amend this Section by adding the following two definitions (that replace Construction Limit Line);

<u>Temporary Construction Limits</u> The area within which the Contractor may access and perform the Physical Work and outside of which Work may not be performed without written authorization by the property owner.

<u>Temporary Road Limits</u> The area within which the Contractor may construct and maintain a temporary detour for maintenance of traffic.

SECTION 102 BIDDING

<u>102.11 Bid Responsiveness</u> Revise the paragraph that states

"The Bid is not signed by a duly authorized representative of the Bidder." So that it reads:

"The Bid is not signed by a duly authorized representative of the Bidder.

- Properly submitted electronic bids meet this requirement.
- Paper bids must include at least one signed copy of the Contract Agreement Offer & Award form."

SECTION 103 AWARD AND CONTRACTING

103.3.1 Qualification Requirement for Award Revise this subsection so that it reads:

"103.3.1 Qualification Requirement for Award If the Notice to Contractors lists a Prequalification requirement, the Apparent Successful Bidder must successfully complete the Prequalification process as a condition of Award. The Apparent Successful Bidder who does not already hold an Annual Prequalification shall have 21 days to provide the Department with their Prequal documents or the Department may move on to the next low bidder."

<u>SECTION 104</u> GENERAL RIGHTS AND RESPONSIBILITIES

- 104.2.1 Furnishing of Right-of-Way Revise this subsection by removing it in its entirety and replace with the new subsection:
- <u>"104.2.1 Furnishing of Property Rights</u> The Department will secure all necessary rights to real property within the Project Limits shown on the Right-of-Way Plans that are provided with the Bid Documents. For related provisions, see Sections 104.3.2 Furnishing of Other Property Rights, Licenses and Permits and 105.4.5 Maintenance of Existing Structures. For related definitions, see Construction Easements and Right-of-Way."
- 104.3.2 Furnishing of Other Property Rights, Licenses and Permits Revise this subsection by replacing "104.2.1 Furnishing of Right-of-Way" with "104.2.1 Furnishing of Property Rights".

August 2, 2024

Supersedes: February 16, 2024

SECTION 105 GENERAL SCOPE OF WORK

105.10.2 Requirements Applicable to All Contracts Under section A, number 2, in the first sentence of the first paragraph, revise this Section by replacing the word "handicap" in two places with the word "disability" so it now reads:

"2) The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, State that all qualified applicants will receive consideration for employment without regard to race, color, sexual orientation, religious creed, sex, national origin, ancestry, age, physical disability, or mental disability."

SECTION 106 QUALITY

<u>106.6 Acceptance</u> Revise this Subsection by replacing the paragraph beginning with "Acceptance of Hot Mix Asphalt Pavement will be based" with:

"Acceptance of Hot Mix Asphalt Pavement will be based on Method A or C Statistical Acceptance, or Method B or D Acceptance as specified. The method of acceptance for each item is defined in Special Provision, Section 403, Hot Mix Asphalt Pavement. When items of Hot Mix Asphalt Pavement are not so designated, Method A will be utilized whenever there are more than 1000 tons per Hot Mix Asphalt Pavement item, and Method B will be utilized when there are less than or equal to 1000 tons per Hot Mix Asphalt Pavement item."

Revise Subsection "B" by removing it and replacing it with:

"B. Items not designated for Statistical Acceptance will utilize Method B or D Acceptance testing to validate the quality of the material incorporated into the Project. For material paid under Item 403.209 – Method D, or designated to be visually accepted, the Contractor shall provide the Department with a Certification Letter that indicates that the material supplied complies with the Specifications. Test results representative of the certified material shall be attached to the letter.

The Department will randomly sample and test the certified Material for properties noted in Table 1 of Section 502 - Structural Concrete or Table 14 of Section –401.21 Acceptance Method B & D. Material will be subject to rejection as noted in Structural Concrete Section 502.195 - Quality Assurance Method C Concrete or Hot Mix Asphalt, Section 401.2022 Pay Adjustment – Method B & D."

<u>106.7.1 Standard Deviation Method</u> Revise 106.7.1, subsection H by removing the following from the first paragraph:

"Method B: PF = [70 + (Quality Level * 0.33)] * 0.01"

August 2, 2024

Supersedes: February 16, 2024

<u>106.9.1 Warranty by Contractor</u> Revise the third paragraph of this section so that it reads:

"For a related provision regarding obligations regarding plantings, see section 621.36 – Maintenance Period."

SECTION 107 TIME

107.3.1 General Amend this paragraph by adding "Juneteenth" between 'Patriot's Day' and 'the Friday after Thanksgiving'.

SECTION 108 PAYMENT

<u>108.2.3 Mobilization Payments</u> Replace Standard Specification 108.2.3 – Mobilization Payments with the following:

"108.2.3 Mobilization Payments "Mobilization" includes the mobilization and demobilization of all resources as many times as necessary during the Work.

Percent Mobilization Bid will be determined by taking the amount Bid for Mobilization and dividing by the Total Contract Amount less Mobilization. Mob/(Total Contract – Mob).

Payment will be made at the following intervals:

% Mobilization Bid	% Mobilization Paid at Contract Award	% Mobilization Paid after the Department determines 50% of	% Mobilization Paid at Final Acceptance
		the work is Complete	
10% or less	50%	50%	
More than 10% to 15%	33%	33%	34%
More than15% to 20%	25%	25%	50%
More than 20% to 30%	15%	15%	70%
Greater than 30%	10%	10%	80%

August 2, 2024 Supersedes: February 16, 2024

<u>108.3 Retainage</u> Revise the third paragraph of this section so that it reads:

"Upon <u>Final Acceptance</u>, and determination by the department that there are no claims either by or on the Contractor or Subcontractors; no over payments by the department; no LDs due; and no disincentives due, the Department will reduce Retent to 1% of the original Contract Award amount, or \$100,000, whichever is less, as it deems desirable and prudent."

<u>108.4.1 Price Adjustment for Hot Mix Asphalt</u> Revise this section by removing it in its entirety and replacing it with the following:

"108.4.1 Price Adjustment for Hot Mix Asphalt: For each Contract, a price adjustment for performance graded binder will be made for the following pay items, when the total quantity of Hot Mix Asphalt included in these items is in excess of 500 tons, based on the estimated quantities of these items at the time of bid.

Item 403.102	Hot Mix Asphalt – Special Areas
Item 403.207	Hot Mix Asphalt - 19 mm
Item 403.2071	Hot Mix Asphalt - 19 mm (Polymer Modified)
Item 403.2072	Hot Mix Asphalt - 19 mm (Asphalt Rich Base)
Item 403.208	Hot Mix Asphalt - 12.5 mm
Item 403.2081	Hot Mix Asphalt - 12.5 mm (Polymer Modified)
Item 403.2084	Hot Mix Asphalt - 12.5 mm (Highly Modified HiMAP)
Item 403.209	Hot Mix Asphalt - 9.5 mm (sidewalks, drives, & incidentals)
Item 403.210	Hot Mix Asphalt - 9.5 mm
Item 403.2101	Hot Mix Asphalt - 9.5 mm (Polymer Modified)
Item 403.2104	Hot Mix Asphalt - 9.5 mm (Thin Lift Surface Treatment)
Item 403.21041	Hot Mix Asphalt - 9.5 mm (Polymer Modified Thin Lift Surface
	Treatment)
Item 403.211	Hot Mix Asphalt – Shim
Item 403.2111	Hot Mix Asphalt – Shim (Polymer Modified)
Item 403.212	Hot Mix Asphalt - 4.75 mm (Shim)
Item 403.213	Hot Mix Asphalt - 12.5 mm (base and intermediate course)
Item 403.2131	Hot Mix Asphalt - 12.5 mm (base and intermediate course
	Polymer Modified)
Item 403.2132	Hot Mix Asphalt - 12.5 mm (Asphalt Rich Base and intermediate course)
Item 403.301	Hot Mix Asphalt (Asphalt Rubber Gap-Graded)
Item 461.13	Light Capital Pavement
Item 461.210	9.5 mm HMA - Paver Placed Surface
Item 461.2101	Hot Mix Asphalt - 9.5 mm (Polymer Modified)
Item 461.216	Hot Mir A on hold (China)
Item 462.30	Hot Mix Asphalt (Shim)
1tem 402.30	Ultra-Thin Bonded Wearing Course

Price adjustments will be based on the variance in costs for the performance graded binder component of hot mix asphalt. They will be determined as follows:

The quantity of hot mix asphalt for each pay item will be multiplied by the performance graded binder percentages given in the table below times the difference in price between the base price and the period price of asphalt cement. Adjustments will be made upward or downward, as prices increase or decrease.

Item 403.102-6.2% Item 403.207-5.2% Item 403.2071–5.2% Item 403.2072-5.8% Item 403.208-5.6% Item 403.2081-5.6% Item 403.2084 – 6.2% Item 403.209–6.2% Item 403.210–6.2% Item 403.2101-6.2% Item 403.2104–6.2% Item 403.21041-6.2% Item 403.211–6.2% Item 403.2111-6.2% Item 403.212-6.8% Item 403.213-5.6% Item 403.2131-5.6% Item 403.2132-6.2% Item 403.301–6.2% Item 461.13–6.7% Item 461.210 – 6.4% Item 461.2101 - 6.4% Item 461.216 – 6.7% Item 462.30-0.0021 tons/SY Item 462.301-0.0021 tons/SY"

<u>SECTION 110</u> INDEMNIFICATION, BONDING, AND INSURANCE

110.3.9 Administrative & General Provisions Amend this subsection by adding "Automobile Liability" under letter A) Additional Insured to the list of exceptions.

SECTION 206 STRUCTURAL EXCAVATION

206.01 Description – Structural Earth Excavation, Below Grade delete the entire sentence and replace with "shall consist of the removal of excavation required for unknown or unanticipated subsurface condition. See 206.04 – Method of Measurement for pay limits."

<u>206.04 Method of Measurement</u> – <u>Drainage and Minor Structures</u> Paragraph 1, sentence 2, delete the remainder of the sentence beginning with "....provided the maximum allowable..."And replace with: "....in accordance with the following limits:"

- Vertical pay limits:
 - Below a plane parallel with and 12 inches below the bottom of the drainage or minor structure or
 - Below the excavation limits shown in the Bid Documents; whichever is greater.
- Horizontal pay limits The maximum allowable horizontal dimensions shall not exceed those bounded by vertical surfaces 18 inches outside the base, or extreme limits of, the structure, and to the vertical neat lines of underdrain trenches, as shown in the Contract Documents.

SECTION 401 HOT MIX ASPHALT PAVEMENT

401.19 Contractor Quality Control Amend this Section by adding the following to the end: "Failure to comply with the approved QCP will result in work suspension and pay reductions as outlined in Section 106.4.6. The Quality Control Plan Value shall be the total bid value for all items covered by the QCP as identified in Special Provision 403."

SECTION 501 FOUNDATION PILES

501.05 Method of Measurement

c. Piles in Place Revise the third paragraph by replacing the "10" with "20" so that it reads:

Unused pile cutoffs 20 feet or more in length, except those required to accommodate the Contractor's construction method, as discussed herein, will remain the property of the Department and will be stored at a bridge maintenance yard nearest the project. Hauling and unloading of piles will be done by the Contractor or by the Department, depending upon availability of services.

SECTION 502 STRUCTURAL CONCRETE

502.09 Forms and Falsework Amend this subsection by adding the subsection title "502.10 <u>Placing Concrete</u>" after section "D" Removal of Forms and False work" and after the paragraph beginning with "2. Forms and False work, including blocking...". So that a new subsection starts and reads: "502.10 Placing Concrete

A. General Concrete shall not be placed until forms"

502.1701 Quality Control, Method A and B Revise this Section so that the first paragraph and the first sentence of the second paragraph read:

"502.17 Quality Control The Contractor shall control the quality of the concrete through testing, inspection, and practices which shall be described in the QCP, sufficient to assure a product meeting the Contract requirements. The QCP shall meet the requirements of Section 106, Quality, and this specification. No work under this item shall proceed until the QCP is submitted to and approved by the Department. Failure to comply with the approved QCP will result in work suspension and pay reductions as outlined in Section 106.4.6. The Quality Control Plan Value shall be the total bid value for all cast-in-place items covered by the QCP, using the P value listed in Special Provision 502. If no P value is listed, a value of \$350, or bid value per cubic yard, whichever is less, shall be used.

<u>502.1701 Quality Control, Method A and B</u> The QCP shall address all elements that affect the quality of the structural concrete including, but not limited to, the following: "

<u>Section 502.1701, Quality Control</u>, Revise Table 4 of this Subsection by removing it in its entirety and replacing it with:

TABLE 4
METHOD A & B MINIMUM QUALITY CONTROL TESTING REQUIREMENTS *

TEST	TEST METHOD	SAMPLING	FREQUENCY		
		LOCATION			
Gradation	AASHTO T-27 & T-11	Stockpile	One set per proposed grading before production. One set every 100 yd ³ (Min. 1 set per month)		
Organic Impurities	AASHTO T-21	Stockpile	Once per fine aggregate per year **		
% Absorption	AASHTO T-84 & T-85	Stockpile	Once per aggregate per year		
Specific Gravity	AASHTO T-84 & T-85	Stockpile	Once per aggregate per year		
Total Moisture in Aggregate	AASHTO T-255	Stockpile	One set per day's production		

Free Water and Aggregate Wt.	N/A		One per day's production
% Entrained Air	AASHTO T-152	On Project	On first two loads and every third load thereafter provided consistent results are achieved
Compressive Strength	AASHTO T-22	On Project	One set per sublot
Compressive Strength	AASHTO T-22 @ 7days	On Project	One set per sublot

^{*} Additional QC testing will be required any time a process change occurs during a placement, including changes in type or dosage of admixture. Additional testing shall include, but is not limited to, entrained air testing.

502.18, Method of Measurement, Revise Subsection 'F' by removing the word 'transverse' so that it reads: "Saw cut grooving of concrete wearing surfaces, complete and accepted, will be measured for payment as one lump sum."

502.19, Basis of Payment, Revise the third paragraph by removing the word 'transverse' so that it reads: "Saw cut grooving of concrete wearing surfaces will be paid for at the Contract Lump Sum Price, which shall be payment for furnishing all materials, labor, and equipment, including depth gauges and all incidentals, to satisfactorily complete the work."

(Also see 535.24 and 535.25 for related changes)

SECTION 503 REINFORCING STEEL

<u>Section 503.07 Splicing</u> Revise this section by removing the table and following footnote and replacing them with:

Minimum Lap Splice Length (inches)										
	Bar Size									
Bar Type	#3	#4	#5	#6	#7	#8	#9	#10	#11	
Plain or Galvanized		20	24	29	38	47	59	72	85	
Epoxy or Dual Coated		24	36	43	56	71	88	107	128	
Stainless		24	30	36	47	59	73	89	107	
Low-carbon Chromium		32	39	47	63	78	97	119	142	

^{**} If the color produced is a laboratory designation Plate III, then the fine aggregate shall be tested once per month.

August 2, 2024

Supersedes: February 16, 2024

"The minimum lap splice lengths in the table above are based on the parameters below. When any of these parameters are altered, appropriate minimum lap splice lengths will be as shown on the Plans.

- Normal weight concrete
- Minimum 28-day concrete compressive strength from 4,000 psi to 10,000 psi
- Class B tension lap splice
- Minimum center-to-center spacing between bars of 6 inches
- Minimum clear cover of 2 inches
- Nominal reinforcing steel yield strengths
 - Low-carbon Chromium = 100 ksi
 - O Stainless = 75 ksi
 - \circ All others = 60 ksi
- Reinforcement with yield strengths greater than 75 ksi shall have beam transverse reinforcement and column ties provided over the required lap splice length in accordance with the current edition of the AASHTO LRFD Bridge Design Specifications

When lap splices are placed horizontally in an element where the concrete depth below the splice will be 12 inches, or more, the indicated lap splice lengths shall be multiplied by a factor of 1.3."

SECTION 506 SHOP APPLIED PROTECTIVE COATING – STEEL

<u>506.13 Surface Preparation</u> Amend this section by adding this paragraph to the end:

"Steel shall meet the requirements of SSPC SP8 Pickling prior to being immersed in the zinc tanks. Verification of the surface preparation shall be included in the QC documentation."

SECTION 523 BEARINGS

<u>523.051 Protective Coating</u> Revise this subsection by removing the paragraph beginning with "Anchor rods shall be galvanized…" and replacing with:

"Anchor rods shall be galvanized. When anchor rods are designated to secure bare unpainted steel or painted steel, a dielectric coating (epoxy or bituminous type coatings are acceptable) shall be applied to the anchor rod and/or adjacent steel to prevent contact between galvanized surfaces and painted or unpainted steel."

<u>523.22 Fabrication</u> Amend this subsection by adding the following: "Elastomeric Bearings shall be fabricated in accordance with AASHTO M251."

SECTION 526 CONCRETE BARRIER

Amend this section by deleting it in its entirety and replacing it with:

"526.01 Description This work shall consist of the furnishing, constructing, erecting, setting, resetting, and removal of concrete barrier and associated elements in accordance with these specifications, the Standard Details, and the lines and grades shown on the Plans or established by the Resident.

The types of concrete barrier are designated as follows:

<u>Portable Concrete Barrier Type I</u> Double faced removable barrier in accordance with the Standard Details.

Permanent Concrete Barrier Type II Double faced barrier as shown on the Plans.

<u>Permanent Concrete Barrier Type IIIa</u> Single faced barrier 32 inches high in accordance with the Standard Details or as shown on the Plans.

<u>Permanent Concrete Barrier Type IIIb</u> Single faced barrier 42 inches high in accordance with the Standard Details or as shown on the Plans.

<u>Permanent Concrete Transition Barrier</u> Barrier of various heights joining steel bridge rail to steel guardrail in accordance with the Standard Details or as shown on the Plans.

<u>Permanent Texas Classic Rail Barrier</u> Traffic rail or sidewalk rail, in accordance with the Standard Details or as shown on the Plans.

526.02 Materials

a. <u>Concrete</u> Concrete for barriers, both permanent and portable, shall have a design strength of 5,000 psi.

For cast-in-place barrier: The concrete shall be Class LP, in accordance with Standard Specification Section 502, Structural Concrete.

For precast barrier: The concrete shall meet the requirements of Standard Specification 712.061, Structural Precast Concrete Units, except that the stripping strength for precast barriers is 4,000 psi.

August 2, 2024

Supersedes: February 16, 2024

- b. <u>Reinforcing Steel</u> Reinforcing steel shall meet the requirements of Section 503, Reinforcing Steel.
- c. <u>Structural Steel</u> Plates and barrier connections shall meet the requirements specified in Standard Specification 504 Structural Steel and shall be hot dip galvanized after fabrication in accordance with Standard Specification 506, Shop Applied Protective Coating Steel
- d. <u>Bolts</u> Bolts shall meet the requirements specified in Section 713.02, High Strength Bolts.
- e. <u>Connecting Pins for Portable Concrete Barrier</u> Portable concrete barriers must be connected using a 1- inch diameter pin. The connecting pin must be smooth, not deformed, i.e., reinforcing bar may not be used, and shall meet the strength requirements of ASTM A449 steel. Materials with greater strength may be used with the approval of the Department.
- f. Anchor Pins for Portable Concrete Barrier Anchoring to concrete or asphalt will be required when specified on the Plans. When required, portable concrete barriers must be anchored using a 1½ inch diameter anchor pin. The anchor pin must be smooth, not deformed, i.e., reinforcing bar may not be used, and shall meet the strength requirements of ASTM A36 steel. Materials with greater strength may be used with the approval of the Department.
- g. <u>Device Crashworthiness</u> MaineDOT is transitioning to MASH2016 criteria for Portable Concrete Barrier on the following schedule:

New Portable Concrete Barrier shall be crash tested and/or evaluated to MASH2016 criteria.

Current Portable Concrete Barrier in useful serviceable condition that is successfully tested to NCHRP Report 350 or MASH2009 criteria may be utilized through December 31, 2029.

Other current Portable Concrete Barrier that is deemed acceptable by the Department may be utilized on projects off the National Highway System through December 31, 2024.

526.03 Construction Requirements

Cast-in-place barriers shall be fabricated in accordance with Standard Specification Section 502, Structural Concrete. Precast barriers shall be fabricated in accordance with Standard Specification 534, Precast Structural Concrete.

Concrete finish for permanent barrier shall be rubbed as defined in Standard Specification Section 502, Structural Concrete, 502.13 D2 or an approved equal.

Portable concrete barrier shall be generally free from fins and porous areas and shall present a neat and uniform appearance.

Permanent barrier shall have a protective coating applied in accordance with Standard Specification Section 515, Protective Coating for Concrete Surfaces.

Reflective delineators for concrete median barrier shall meet the requirements of Special Provision 645, Highway Signing.

Preformed Joint Filler shall meet the requirements specified in Subsection 705.01, Preformed Expansion Joint Filler.

Permissible dimensional tolerances for all concrete barriers shall be as follows:

- a. Cross-sectional dimensions shall not vary from design dimensions by more than ¼ inch. The vertical centerline shall not be out of plumb by more than ¼ inch.
- b. Longitudinal dimensions shall not vary from the design dimensions by more than \(^1\)/4 inch per 10 feet of barrier section and shall not exceed \(^3\)/4 inches per section.
- c. Location of anchoring holes shall not vary by more than ½ inch from the dimensions shown in the concrete barrier details on the Plans.
 - d. Surface straightness shall not vary more than ¼ inch under a 10-foot straightedge.
- e. The barrier shall have no significant cracking. Significant cracking is defined as fractures or cracks passing through the section, or any continuous crack extending for a length of 12 inches or more, regardless of position in the section.

<u>526.04 Method of Measurement</u> Permanent Concrete Barrier Type II, IIIa, IIIb, Texas Classic Rail, and Precast Median Barrier will be measured for payment by lump sum, complete in place.

Portable concrete barrier, both anchored and unanchored will be measured for payment by lump sum. Lump sum measurement will include verification of the installation and removal of all portable concrete at the completion of the Contractor's operations.

The Contractor shall replace sections of portable concrete barrier, including anchored barrier damaged by the traveling public when directed by the Resident. Replacement sections will be measured for payment in accordance with Standard Specification 109.7, Equitable Adjustments to Compensation and Time.

Transition barrier will be measured by each, complete in place.

<u>526.05 Basis of Payment</u> The accepted quantities of Concrete Barrier Type II, IIIa, IIIb, Texas Classic Rail, and Precast Median Barrier will be paid for at the Contract lump sum price for the type specified, complete in place.

The accepted quantities of Portable Concrete Barrier Type I, both anchored and unanchored will be paid for at the Contract lump sum price. Such payment shall be full compensation for furnishing all materials, assembling, moving, resetting, transporting, temporarily storing, removing barrier, furnishing new parts as necessary, and all incidentals necessary to complete the work.

Portable barrier shall become the property of the Contractor upon completion of the use of the barrier on the project and shall be removed from the project site by the Contractor.

Transition barrier will be paid for at the Contract price each, complete in place.

The accepted quantity of all types of concrete barrier, whether portable or permanent, will be paid for at the lump sum or per each price, as applicable, which payment shall be full compensation for all materials, including reinforcing steel, protective coating, reflective delineators, steel plates and hardware, equipment, labor and incidentals required, as necessary, to complete the work.

Payment will be made under:

	Pay Item	Pay Unit
526.301	Portable Concrete Barrier, Type I	Lump Sum
526.304	Portable Concrete Barrier, Anchored Type I	Lump Sum
526.312	Permanent Concrete Barrier Type II	Lump Sum
526.321	Permanent Concrete Barrier Type IIIa	Lump Sum
526.323	Texas Classic Rail	Lump Sum
526.331	Permanent Concrete Barrier Type IIIb	Lump Sum
526.34	Permanent Concrete Transition Barrier	Each
526.502	Precast Concrete Median Barrier	Lump Sum"

<u>SECTION 527</u> ENERGY ABSORBING UNIT

527.02 Materials Amend this section by deleting it in its entirety and replacing it with:

"MaineDOT is transitioning to MASH2016 criteria for Work Zone Traffic Control Devices on the following schedule:

Portable Crash Cushions will be crash tested and/or evaluated to MASH2016 criteria by January 1, 2030. Current Category 3 devices in useful serviceable condition that are successfully tested to NCHRP Report 350 or MASH2009 criteria may be utilized through December 31, 2029.

Work Zone Crash Cushions shall be selected from the Department's Qualified Products List of Crash Cushions/Impact Attenuators or approved equal."

SECTION 535 PRECAST, PRESTRESSED CONCRETE SUPERSTRUCTURE

535.22 Tolerances Amend this section by deleting it in its entirety and replacing it with: "Product dimensional tolerances shall be in conformance with the latest edition of PCI MNL-135, Tolerance Manual for Precast and Prestressed Concrete Construction, as applicable to the particular product (e.g., slab, I-girder, box beam), the Plans, and this Specification. Use Box Beam fabrication tolerances for voided or solid slab beams and use Double Tee tolerances for NEXT beams. In case of dispute, the Fabrication Engineer shall determine the allowable tolerance."

535.24 Installation of Slabs, Beams, and Girders Revise the 5th paragraph by replacing "6.0 and 9.0" to "5.0 and 8.0" so it reads: "Ready mixed grout shall achieve a design compressive strength of 6,000 psi at 28 days, have an entrained air content of between 5.0 and 8.0 percent, be non-shrink, flowable, and contain a non-shrink additive listed on the Department QPL for expansive cements."

535.25, Installation of Precast/Prestressed Deck Panels Revise the 2nd paragraph by replacing "6.0 and 9.0" to "5.0 and 8.0" so it reads: "Ready mixed grout shall achieve a design compressive strength of 6,000 psi at 28 days, have an entrained air content of between 5.0 and 8.0 percent, be non-shrink, flowable, and contain a non-shrink additive listed on the Department QPL for expansive cements."

SECTION 606 GUARDRAIL

Amend this section by replacing it with the following:

<u>606.01 Description</u> This work shall consist of furnishing and installing guardrail components in accordance with these specifications and in reasonably close conformity with the lines and grades shown on the plans or as established. Guardrail is designated as:

31" W-Beam Guardrail - Mid-Way Splice

Galvanized steel w-beam, 8" wood or composite offset blocks, galvanized steel posts Thrie Beam

Galvanized steel thrie beam, 8" wood or composite offset blocks, galvanized steel posts

Median guardrail shall consist of two beams of the above types, mounted on single posts.

Bridge mounted guardrail shall consist of furnishing all labor, materials, and equipment necessary to install guardrail as shown on the plans. This work shall also include drilling for and installation of offset blocks if specified, and incidental hardware necessary for satisfactory completion of the work.

Remove and Reset and Remove, Modify, and Reset guardrail shall consist of removing the existing designated guardrail and resetting in a new location as shown on the plans or directed by the Resident. Remove, Modify, and Reset guardrail and Modify guardrail include the following guardrail modifications: Removing plate washers at all posts, except at anchorage assemblies as noted on the Standard Details, adding offset blocks, and other modifications as listed in the Construction Notes or General Notes. Modifications shall conform to the guardrail Standard Details.

Bridge Connection shall consist of the installation and attachment of beam guardrail to the existing bridge. This work shall consist of constructing a concrete end post or modifying an existing end post as required, furnishing, and installing a terminal connector, necessary hardware, and incidentals required to complete the work as shown on the plans. Bridge Transition shall consist of a bridge connection and furnishing and installing guardrail components as shown in the Standard Details.

<u>606.02 Materials</u> Materials shall meet the requirements specified in the following Sections of Division 700 - Materials:

Timber Preservative	708.05
Metal Beam Rail	710.04
Guardrail Posts	710.07
Guardrail Hardware	710.08

Guardrail components shall meet the applicable standards of "A Guide to Standardized Highway Barrier Hardware" prepared and approved by the AASHTO-AGC-ARTBA Joint Cooperative Committee, Task Force 13 Report.

Posts for underdrain delineators shall be "U" channel steel, 8 ft long, 2 ½ lb/ft minimum and have 3/8-inch round holes, 1-inch center to center for a minimum distance of 2 ft from the top of the post.

Reflectorized Flexible Guardrail Markers shall be mounted on all guardrails. A marker shall be mounted onto guardrail posts at the flared guardrail terminal end point and tangent point, both at the leading and trailing ends of each run of guardrail. The marker's flexible posts shall be gray with either silver-white or yellow reflectors (to match the edge line striping) at the tangents, red at leading ends, and green at trailing ends. Whenever the guardrail terminal is not flared, markers will only be required at the terminal end point. These shall be red or green as appropriate. Markers shall be installed on the protected side of guardrail posts unless otherwise approved by the Resident. Reflectorized flexible guardrail markers shall be from the Department's Qualified Products List of Delineators. The marker shall be gray, flexible, durable, and of a non-discoloring material to which 3-inch by 9-inch reflectors shall be applied, and capable of recovering from repeated impacts and meeting MASH 16 requirements. Reflective material shall meet the requirements of Section 719.01 for ASTM D 4956 Type III reflective sheeting. The marker shall be secured to the guardrail post with two fasteners, as shown in the Standard Details.

Reflectorized beam guardrail reflectors shall be mounted on all "w" beam guardrail and shall be either the "butterfly" type or linear delineation system panels. "Butterfly" or linear delineation panels shall be installed at approximately 62.5 foot intervals on tangents (after every tenth post) and 31.25 feet on curves (after every fifth post), and shall be centered on the guardrail beam. On Divided highways, the left-hand delineators shall be yellow and the right-hand delineators shall be silver/ white. On two-way directional highways, the right-hand side will have silver / white reflectors and no reflectorized delineator used on the left. Delineators shall have reflective sheeting that meets or exceeds the requirements of Section 719.01.

"Butterfly" reflectors shall be fabricated from high-impact, ultraviolet & weather resistant thermoplastic. Aluminum, galvanized metal or other materials shall not be used. Reflective sheeting will be applied to only one side of the delineator facing the direction of traffic and shall be centered vertically on the guardrail beam as shown in the Standard Detail 606(7).

Linear delineation system panels shall be 1.5 inches wide by approximately 11 inches nominal length, with a minimum of 5 raised lateral ridges spaced at approximately 2.25 inches. The height of each ridge shall be 0.34 inches with a 45 degree profile and a 0.28 inches radius at the top. Sheeting shall be laminated to thin gauge aluminum with a pre-applied adhesive tape on the back. Panels shall not be installed over seams or bolt heads and shall be centered horizontally on the guardrail beam; linear delineation panels shall be attached to only one guardrail beam. The guardrail beam surface shall be cleaned and prepared according to the manufacturer's instructions. Air temperature and guardrail surface temperature must be a minimum of 50 degrees F (10 C) with rising temperature at the time of installation.

Exact locations of the either the "butterfly" type or the linear delineation panels shall be approved by the Resident prior to installation.

Single wood post shall be of cedar, white oak, or tamarack, well-seasoned, straight, and sound and have been cut from live trees. The outer and inner bark shall be removed, and all knots trimmed flush with the surface of the post. Posts shall be uniform taper and free of kinks and bends.

Single steel post shall conform to the requirements of Section 710.07 b.

Single steel pipe post shall be galvanized, seamless steel pipe conforming to the requirements of ASTM A120, Schedule No. 40, Standard Weight.

Acceptable multiple mailbox assemblies shall be listed on the Department's Qualified Products List and shall be MASH 16 tested and approved.

Flared and Tangent w-beam guardrail terminals and guardrail offset blocks shall be from the Department's Qualified Products List. Flared terminals shall be installed with a 4 ft offset as shown in the Manufacturer's installation instructions.

Anchorage assemblies used to anchor trailing ends, radius guardrail, or other ends not exposed to traffic shall meet the applicable standards of "A Guide to Standardized Highway Barrier Hardware" prepared and approved by the AASHTO-AGC-ARTBA Joint Cooperative Committee, Task Force 13 Report, Drawing SEW02a.

Existing materials damaged or lost during adjusting, removing and resetting, or removing, modifying, and resetting, shall be replaced by the Contractor without additional compensation. Existing guardrail posts and guardrail beams found to be unfit for reuse shall be replaced when directed by the Resident.

606.03 Posts Posts for guardrail shall be set plumb in holes or they may be driven if suitable driving equipment is used to prevent battering and distorting the post. When posts are driven through pavement, the damaged area around the post shall be repaired with approved bituminous patching. Damage to lighting and signal conduit and conductors shall be repaired by the Contractor.

When set in holes, posts shall be on a stable foundation and the space around the posts, backfilled in layers with suitable material, thoroughly tamped.

The reflectorized flexible guardrail markers shall be set plumb with the reflective surface facing the oncoming traffic. Markers shall be installed on the protected side of guardrail posts. Markers, which become bent or otherwise damaged, shall be removed and replaced with new markers.

Single wood posts shall be set plumb in holes and backfilled in layers with suitable material, thoroughly tamped. The Resident will designate the elevation and shape of the top. The posts, that are not pressure treated, shall be painted two coats of good quality oil base exterior house paint.

Single steel posts shall be set plumb in holes as specified for single wood posts or they may be driven if suitable driving equipment is used to prevent battering and distorting the post.

Additional bolt holes required in existing posts shall be drilled or punched, but the size of the holes shall not exceed the dimensions given in the Standard Details. Metal around the holes shall be thoroughly cleaned and painted with two coats of approved aluminum rust resistant paint. Holes shall not be burned.

<u>606.04 Rails</u> Brackets and fittings shall be placed and fastened as shown on the plans. Rail beams shall be erected and aligned to provide a smooth, continuous barrier. Beams shall be lapped with the exposed end away from approaching traffic.

End assemblies shall be installed as shown on the plans and shall be securely attached to the rail section and end post.

All bolts shall be of sufficient length to extend beyond the nuts but not more than ½ inch. Nuts shall be drawn tight.

Additional bolt holes required in existing beams shall be drilled or punched, but the size of the holes shall not exceed the dimensions given in the Standard Details. Metal around the holes shall be thoroughly cleaned and painted with two coats of approved aluminum rust resistant paint. Holes shall not be burned.

<u>606.045 Offset Blocks</u> The same offset block material is to be provided for the entire project unless otherwise specified.

<u>606.05 Shoulder Widening</u> At designated locations the existing shoulder of the roadway shall be widened as shown on the plans. All grading, paving, seeding, and other necessary work shall be in accordance with the Specifications for the type work being done.

606.06 Mail Box Post Single wood post shall be installed at the designated location for the support of the mailbox. The multiple mailbox assemblies shall be installed at the designated location in accordance with the Standard Details and as recommended by the Manufacturer. Attachment of the mailbox to the post will be the responsibility of the home or business owner.

<u>606.07 Abraded Surfaces</u> All galvanized surfaces of new guardrail and posts, which have been abraded so that the base metal is exposed, and the threaded portions of all fittings and fasteners and cut ends of bolts shall be cleaned and painted with two coats of approved rust resistant paint.

<u>606.08 Method of Measurement</u> Guardrail will be measured by the linear foot from center to center of end posts along the gradient of the rail except where end connections are made to masonry or steel structures, in which case measurement will be as shown on the plans. When connected to radius rail, measurement will be to the end of the last tangent beam.

Guardrail terminal, reflectorized flexible guardrail marker, terminal end, anchorage assembly, bridge transition, bridge connection, multiple mailbox post, and single post will be measured by each unit of the kind specified and installed.

Widened shoulder will be measured as a unit of grading within the limits shown on the plans.

Excavation in solid rock for placement of posts will be paid under force account unless otherwise indicated in the Bid Documents.

Reflectorized beam guardrail reflectors ("butterfly" type or linear delineation system panels) when identified by pay item, will be measured for payment by each.

606.09 Basis of Payment The accepted quantities of guardrail will be paid for at the contract unit price per linear foot for the type specified, complete in place. Reflectorized beam guardrail ("butterfly"-type) delineators will not be paid for directly but will be considered incidental to guardrail items. Reflectorized flexible guardrail marker, terminal end, anchorage assembly, bridge transition, bridge connection, multiple mailbox post, and single post will be paid for at the contract unit price each for the kind specified complete in place.

Guardrail terminals will be paid for at the contract price each, complete in place which price shall be full payment for furnishing and installing all components including the terminal section, posts, offset blocks, "w" beam, cable foundation posts, plates and for all incidentals necessary to complete the installation within the limits as shown on the Standard Details or the Manufacturer's installation instructions. Pay limits for a flared terminal will be 37.5 feet. Pay limits for a tangent terminal will be 50 feet. Each guardrail terminal will be clearly marked with the Manufacturer's name and model number to facilitate any future needed repair. Such payment shall also be full compensation for furnishing all material, excavating, backfilling holes, assembling, and all incidentals necessary to complete the work, except that for excavation for posts or anchorages in solid ledge rock, payment will be made under 109.7.5 – Force Account. Type III Retroreflective Adhesive Sheeting shall be applied to the approach buffer end sections and sized to substantially cover the end section. On all roadways, the ends shall be marked with alternating black and retroreflective yellow stripes. The stripes shall be 3 in wide and sloped down at an angle of 45 degrees toward the side on which traffic is to pass the end section. Guardrail terminals shall also include a set of installation drawings supplied to the Resident.

Anchorages to bridge end posts will be part of the bridge work. Connections thereto will be considered included in the unit bid price for guardrail.

Guardrail to be placed on a radius of curvature of 150 ft or less will be paid for under the designated radius pay item for the type guardrail being placed.

Widened shoulder will be paid for at the contract unit price each complete in place and will be full compensation for furnishing and placing, grading and compaction of aggregate subbase and any required fill material.

Adjust guardrail will be paid for at the contract unit price per linear foot and will be full compensation for adjusting to grade. Payment shall also include adjusting guardrail terminals where required.

Modify guardrail will be paid for at the contract unit price per linear foot and will be full compensation for furnishing and installing offset blocks, additional posts, and other specified modifications; removing, modifying, installing, and adjusting to grade existing posts and beams; removing plate washers and backup plates, and all incidentals necessary to complete the work. Payment shall also include removing and resetting guardrail terminals where required.

Remove and Reset guardrail will be paid for at the contract unit price per linear foot and will be full compensation for removing, transporting, storing, reassembling all parts, necessary cutting, furnishing new parts when necessary, reinstalling at the new location, and all other incidentals necessary to complete the work. Payment shall also include removing and resetting guardrail terminals when required.

Remove, Modify, and Reset guardrail will be paid for at the contract unit price per foot and will be full compensation for the requirements listed in Modify guardrail and Remove and Reset guardrail.

Bridge Connections will be paid for at the contract unit price each. Payment shall include, attaching the connection to the endpost including furnishing and placing concrete and reinforcing steel necessary to construct new endposts if required, furnishing and installing the terminal connector, and all miscellaneous hardware, labor, equipment, and incidentals necessary to complete the work.

Bridge Transitions will be paid for at the contract unit price each. Payment shall include furnishing and installing the thrie beam or "w"-beam terminal connector, doubled beam section, and transition section, where called for, posts, hardware, precast concrete transition curb, and any other necessary materials and labor, including the bridge connection as stated in the previous paragraph.

No payment will be made for guardrail removed, but not reset and all costs for such removal shall be considered incidental to the various contract pay items.

Reflectorized beam guardrail reflectors ("butterfly" type and the linear delineation panels) will not be paid for directly but will be considered incidental to all new guardrail items. The Contractor shall furnish and install either the "butterfly" type or linear delineation panels, at its discretion, for new guardrail items.

Reflectorized beam guardrail reflectors (either "butterfly" type or linear delineation system panels) will be paid for under the applicable pay items for installation in conjunction with Adjust, Modify, Remove and Reset, Remove Modify and Reset guardrail items. The accepted quantity of "butterfly" type or linear delineation system panels will be paid for at the contract unit price each for all work and materials furnished to install, complete in place, including all incidentals necessary to complete the work.

Payment will be made under:

Pay Item		Pay Unit
606.1301	31" W-Beam Guardrail - Mid-Way Splice - Single Faced	Linear Foot
606.1302	31" W-Beam Guardrail - Mid-Way Splice – Double Faced	Linear Foot
606.1303	31" W-Beam Guardrail - Mid-Way Splice, 15' Radius and Less	Linear Foot
606.1304	31" W-Beam Guardrail - Mid-Way Splice, Over 15' Radius	Linear Foot
606.1305	31" W-Beam Guardrail - Mid-Way Splice Flared Terminal	Each
606.1306	31" W-Beam Guardrail - Mid-Way Splice Tangent Terminal	Each
606.1307	Bridge Transition (Asymmetrical) – Type IA	Each
606.1721	Bridge Transition - Type I	Each
606.1722	Bridge Transition - Type II	Each
606.1731	Bridge Connection - Type I	Each
606.1732	Bridge Connection - Type II	Each
606.178	Guardrail Beam	Linear Foot
606.25	Terminal Connector	Each
606.257	Terminal Connector - Thrie Beam	Each
606.259	Anchorage Assembly	Each
606.265	Terminal End-Single Rail - Galvanized Steel	Each
606.266	Terminal End-Single Rail - Corrosion Resistant Steel	Each
606.275	Terminal End-Double Rail - Galvanized Steel	Each
606.276	Terminal End-Double Rail - Corrosion Resistant Steel	Each
606.352	Reflectorized Beam Guardrail Delineators ("Butterfly" type)	Each
606.3521	Linear Delineation System Panel	Each
606.353	Reflectorized Flexible Guardrail Marker	Each
606.354	Remove and Reset Reflectorized Flexible Guardrail Marker	Each
606.356	Underdrain Delineator Post	Each
606.358	Guardrail, Modify	Linear Foot
606.362	Guardrail, Adjust	Linear Foot
606.365	Guardrail, Remove, Modify, and Reset	Linear Foot
606.366	Guardrail, Remove and Reset	Linear Foot
606.367	Replace Unusable Existing Guardrail Posts	Each
606.3671	Replace Unusable Offset Blocks	Each
606.47	Single Wood Post	Each
606.48	Single Galvanized Steel Post	Each
606.50	Single Steel Pipe Post	Each
606.51	Multiple Mailbox Support	Each
606.568	Guardrail, Modify - Double Rail	Linear Foot
606.63	Thrie Beam Rail Beam	Linear Foot
606.64	Guardrail Thrie Beam - Double Rail	Linear Foot
606.65	Guardrail Thrie Beam - Single Rail	Linear Foot
606.66	Terminal End Thrie Beam	Each
606.70	Transition Section - Thrie Beam	Each
606.71	Guardrail Thrie Beam - 15 ft radius and less	Linear Foot
606.72	Guardrail Thrie Beam - over 15 ft radius	Linear Foot

606.73	Guardrail Thrie Beam - Single Rail Bridge Mounted	Linear Foot
606.74	Guardrail - Single Rail Bridge Mounted	Linear Foot
606.753	Widen Shoulder for Low Volume Guardrail End	Each
606.754	Widen Shoulder for Flared Guardrail Terminal	Each
606.78	Low Volume Guardrail End	Each
606.80	Buried-in-Slope Guardrail End	Each

SECTION 608 SIDEWALKS

<u>Section 608.022Detectable Warning Materials Standard</u> Revise this section by removing the last sentence of this section beginning with "Concrete..." and replacing it with "Concrete shall meet the requirements of Section 608.021, Sidewalk Materials, of this specification or may be a prepackaged concrete mix from the Department's Qualified Products List (QPL)."

SECTION 609 CURB

Remove this section in its entirety and replace with the following:

<u>609.01 Description</u> Construct or reset curb, gutter, or combination curb and gutter, paved ditch, and paved flume. The types of curb are designated as follows:

Type 1 - Stone curbing of quarried granite stone

Type 2 – Concrete Curbing

Type 3 - Bituminous curbing

Type 5 - Stone edging of quarried granite stone

609.02 Materials Except as provided below, the materials used shall meet the requirements of the following Sections of Division 700 - Materials:

Portland Cement and Portland Pozzolan Cement	701.01
Water	701.02
Air Entraining Chemical Admixture	701.03
Fine Aggregate for Concrete	703.01
Coarse Aggregate for Concrete	703.02
Joint Mortar	705.02
Reinforcing Steel	709.01
Stone Curbing and Edging	712.04
Epoxy Resin	712.35
Hot Mix Asphalt Curbing	712.36
Structural Precast Concrete Units (Concrete Curb)	712.061

The Contractor shall submit a concrete mix design for the Portland Cement Concrete to the Resident, for the uses specified below or in accordance with the Contract Documents.

Supersedes: February 16, 2024

Circular curb, terminal sections and transition sections shall be in reasonably close conformity with the shape and dimensions shown on the Plans and to the applicable material requirements herein for the type of curb specified.

Dowels shall be reinforcing steel deformed bars.

Concrete for Slipform Concrete Curb shall meet the requirements below:

- a. Class A, with the exception that permeability requirements shall be waived.
- b. Entrained air content of Slipform Concrete Curb shall be 4.0% to 7.0%
- c. Concrete temperature, prior to discharge, shall not exceed 90 F.
- d. Proposed mix designs may contain polypropylene fibers.
- e. Partially discharged loads may be retempered with water provided the maximum water to cement ratio is not exceeded.

609.03 Vertical Stone Curb, Terminal Section and Transition Sections and Portland Cement Concrete Curb, Terminal Sections and Transition Sections

- a. Installation The curb stone shall be set on a compacted foundation so that the front top arris line conforms to the lines and grades required. The foundation shall be prepared in advance of setting the stone by grading the proper elevation and shaping to conform as closely as possible to the shape of the bottom of the stone. The required spacing between stones shall be assured by the use of an approved spacing device to provide an open joint between stones of at least ½ inch and no greater than 5% inch.
- b. Backfilling All remaining spaces under the curb shall be filled with approved material and thoroughly hand tamped so the stones will have a firm uniform bearing on the foundation for the entire length and width. Any remaining excavated areas surrounding the curb shall be filled to the required grade with approved materials. This material shall be placed in layers not exceeding 8 inches in depth, loose measure and thoroughly tamped.

When backfill material infiltrates through the joints between the stones, small amounts of joint mortar or other approved material shall be placed in the back portion of the joint to prevent such infiltrating.

- c. Protection The curb shall be protected and kept in good condition. All exposed surfaces smeared or discolored shall be cleaned and restored to a satisfactory condition or the curb stone removed and replaced.
- d. Curb Inlets Curb placed adjacent to curb inlets shall be installed with steel dowels cemented into each stone with epoxy grout as shown in the Standard Details.

The epoxy grout shall be used in accordance with the manufacturer's instructions. The grout shall be forced into the hole, after which the dowel shall be coated with grout for one-half its length and inserted into the grout filled hole. The hole shall be completely filled with grout around the dowel. All tools and containers must be clean before using.

The Contractor may elect to substitute concrete to backfill Stone Curbing or Stone Edging at their option. If the concrete backfill option is elected, the Concrete Fill shall meet the requirements of 609.02. The Contractor shall submit a concrete design for the Portland Cement Concrete, with a minimum designated compressive strength of 3000 PSI meeting the requirements of Class S or Class Fill Concrete. The Contractor may elect to choose a Prepackaged Concrete Mix from the Departments Qualified Products list (QPL). Concrete backfill shall be completed in conformance with a Department supplied concrete backfill detail.

609.04 Bituminous Curb

- a. Preparation of Base Before placing the curb, the foundation course shall be thoroughly cleaned of all foreign and objectionable material. String or chalk lines shall be positioned on the prepared base to provide guidelines. The foundation shall be uniformly painted with tack coat at a rate of 0.04 to 0.14 gal/yd².
- b. Placing The curb shall be placed by an approved power operated extruding type machine using the shape mold called for. A tight bond shall be obtained between the base and the curb. The Resident may permit the placing of curbing by other than mechanical curb placing machines when short sections or sections with short radii are required. The resulting curbing shall conform in all respects to the curbing produced by the machine.
- c. When required, the curb shall be painted and coated with glass beads in accordance with Section 627 Pavement Marking. Curb designated to be painted shall not be sealed with bituminous sealing compound.
- d. Acceptance Curb may be accepted or rejected based on appearance concerning texture, alignment, or both. All damaged curb shall be removed and replaced at the Contractor's expense.
- e. Polyester fibers shall be uniformly incorporated into the dry mix at a rate of 0.25 percent of the total batch weight. Certification shall be provided from the supplier with each shipment meeting the following requirements:

Average Length $0.25 \text{ inches} \pm 0.005$ Average Diameter $0.0008 \text{ inches} \pm 0.0001$ Specific Gravity 1.32-1.40Melting Temperature 480 °F Minimum

609.05 Slipform Concrete Curb

Supersedes: February 16, 2024

a. Preparation of Base Before placing the curb, the foundation course shall be thoroughly cleaned of all foreign and objectionable material. The Contractor shall not place Slipform Concrete Curb on a wet or frozen foundation. The foundation (HMA or concrete) may be in a Saturated Surface Dry condition, but no standing water shall be allowed. String or chalk lines shall be positioned on the prepared foundation to provide guidelines. Prior to placing the curb, the foundation shall be uniformly coated with an epoxy resin adhesive that meets the requirements of AASHTO M 235, Type I, II, III, IV or V and has been tested by AASHTO Product Evaluation & Audit Solutions. The Contractor shall submit the epoxy resin adhesive that they propose to utilize with the concrete mix design. The epoxy resin adhesive must be approved prior to placement and used in accordance with manufacturer's recommendations.

<u>b. Placing</u> Concrete shall be placed with an approved Slipform machine that will produce a finished product according to the design specified in the Plans. For cold weather slip forming, the outside temperature must be at least 36°F and rising. The curb shall be placed on a firm, uniform foundation, shall conform to the section profile specified in the Plans, and shall match the appropriate grade. Expansion joints shall be placed in the curb where it meets rigid structures such as but not limited to building foundations, catch basin headers or fire hydrants. Contraction joints will be placed at 10-foot intervals using sawing methods, which shall cut 1 to 3 inches into the concrete. Contraction joints shall be cut between 1 and 7 days after placement of the concrete. Joints shall be constructed perpendicular to the subgrade and match other joints in roadways, sidewalks, or other structures when applicable.

c. Curing and Sealing Proper curing shall be provided using either a combination curing/sealing compound spray that meets ASTM 1315 Type 1-Class A, or a curing compound spray that meets ASTM 309 Type 1-D – Class A. Curing may also be accomplished by the methods specified in Standard Specification Section 502.14, Curing Concrete.

If a combination curing/sealing compound spray is not used, a separate sealing compound from the MaineDOT Qualified Products List for a Type 1c sealer shall be applied after the concrete has cured.

- d. Protection Slipform curb must be adequately protected after placement. The concrete shall be allowed to cure for at least 72 hours. During cold weather conditions, when temperatures drop below the required temperature of 36°F after placement, curbing shall be protected by concrete blankets or a combination of plastic sheeting and straw. After any placement of Slipform curb, regardless of weather conditions, the placed curb shall be adequately protected by traffic control devices as necessary.
 - <u>e. Marking</u> When required, the curb shall be painted and coated with glass beads in accordance with Section 627 Pavement Marking. Curb designated to be painted shall not be sealed unless a combination curing/sealing compound is used.
 - <u>f. Acceptance</u> Curb shall be accepted or rejected based on finish, alignment, entrained air content, and compressive strength. Concrete Quality Control and Acceptance

shall be done in accordance with Standard Specification Section 502, Method C. All damaged curb shall be removed and replaced at the Contractor's expense.

609.06 Stone Edging The curb shall be installed, backfilled and protected in accordance with Section 609.03, except as follows:

a. Slope The edging shall be set on a slope as shown on the Plans or as directed.

b. Joints Joints shall be open and not greater than 1½ inch in width.

609.07 Stone Bridge Curb

a. Installation Each stone and the bed upon which it is to be placed shall be cleaned and thoroughly wetted with water before placing the mortar for bedding and setting the stone. The stone shall be set on a fresh bed of joint mortar and well bedded before the mortar has set so that the front top arris line conforms to the line and grade required. Whenever temporary supporting wedges or other devices are used in setting the stones, they shall be removed before the mortar in the bed has become set, and the holes left by them shall be filled with mortar. Concrete behind the stones shall not be placed until the stones have been in place at least two days. Bedding and pointing mortar for joints shall be cured as required under Section 502 - Structural Concrete.

<u>b. Joints</u> Vertical joints shall be ½ inch in width plus or minus ⅓ inch. Whenever possible, the face and top of the joint shall be pointed with joint mortar to a depth of 1½ inch, before the bedding mortar has set. Joints which cannot be so pointed, shall be prepared for pointing by raking them to a depth of 1½ inch before the mortar has set. Joints not pointed at the time the stone is laid shall be thoroughly wetted with clean water and filled with mortar. The mortar shall be well driven into the joint and finished with an approved pointing tool, flush with the pitch line of the stones.

609.08 Resetting Stone or Portland Cement Concrete Curb, Including Terminal Sections and Transitions

The curb shall be installed, backfilled and protected in accordance with Section 609.03, except as follows:

<u>a. Removal of Curbing</u> The Contractor shall carefully remove and store curb specified on the Plans or designated for resetting. Curb damaged or destroyed, because of the Contractor's operations or because of their failure to store and protect it in a manner that would prevent its loss or damage, shall be replaced with curbing of equal quality at the Contractor's expense.

<u>b. Cutting and Fitting</u> Cutting or fitting necessary in order to install the curbing at the locations directed shall be done by the Contractor.

Supersedes: February 16, 2024

609.09 Method of Measurement Curb, both new and reset, will be measured by the linear foot along the front face of the curb at the elevation of the finished pavement, complete in place and accepted. Curb inlets at catch basins, including doweling, will not be measured for payment but shall be considered included in the cost of the catch basin. New transition sections and terminal curb will be measured by the unit. Reset transition sections and terminal curb will be included in the measurement for resetting curb.

Concrete Slipform Curb and terminal ends will be measured by the linear foot along the front face of the curb at the elevation of the finished pavement, complete in place and accepted.

<u>609.10 Basis of Payment</u> The accepted quantities of curbing will be paid for at the contract unit price per linear foot for each kind and type of curbing as specified.

Payment for terminal curb shall include only that portion of the curbing modified for installation at ends of curb runs shown in the Standard Details. Curb adjacent to terminal ends shall be paid for at the contract unit price per linear foot for the type of curb installed.

Vertical Curb Type 1 is required to have a radius of 60 feet or less, will be paid for as Vertical Curb Type 1 - Circular.

Curb, Type 5 required to have a radius of 30 feet or less will be paid for as Curb Type 5 - Circular.

There will be no separate payment for concrete fill, mortar, reinforcing steel, anchors, tack coat, drilling for and grouting anchors, pointing and bedding of curbing, and for cutting and fitting, but these will be considered included in the work of the related curb.

Removal of existing curb and necessary excavation for installing new or reset curbing will not be paid for directly but shall be considered to be included in the appropriate new or reset curb pay item. Base and Subbase material will be paid for under Section 304 - Aggregate Base and Subbase Course. Backing up bituminous curb is incidental to the curb items. Loam, as directed, will be paid under 615 – Loam.

Payment will be made under:

	Pay Item	Pay Unit
609.11	Vertical Curb Type 1	Linear Foot
609.12	Vertical Curb Type 1 - Circular	Linear Foot
609.13	Vertical Bridge Curb Type 1	Linear Foot
609.131	Vertical Bridge Curb Type 1A	Linear Foot
609.132	Vertical Bridge Curb Type 1B	Linear Foot
609.142	Vertical Bridge Curb Type 1B - Circular	Linear Foot
609.15	Sloped Curb Type 1	Linear Foot
609.151	Sloped Curb Type 1 - Circular	Linear Foot
609.161	Concrete Slipform Curb – Vertical Type 2	Linear Foot
609.21	Concrete Slipform Curb Type 2	Linear Foot

609.219	Concrete Slipform Terminal End Type 2	Linear Foot
609.23	Terminal Curb Type 1	Each
609.234	Terminal Curb Type 1 - 4 foot	Each
609.237	Terminal Curb Type 1 - 7 foot	Each
609.2371	Terminal Curb Type 1 - 7 foot – Circular	Each
609.238	Terminal Curb Type 1 - 8 foot	Each
609.26	Curb Transition Section B Type 1	Each
609.31	Curb Type 3	Linear Foot
609.34	Curb Type 5	Linear Foot
609.35	Curb-Type 5 - Circular	Linear Foot
609.38	Reset Curb Type 1	Linear Foot
609.39	Reset Curb Type 2	Linear Foot
609.40	Reset Curb Type 5	Linear Foot

SECTION 610

STONE FILL, RIPRAP, STONE BLANKET, AND STONE DITCH PROTECTION

610.02 Materials Amend this subsection by adding the following to the end of the material list: "Stone Ditch Protection 703.29"

SECTION 618 SEEDING

618.08 Mulching Revise this Section so that the third sentence reads: "Mulch for Seeding Method Number 1 shall only be cellulous fiber mulch Section 619.04 (b) or straw mulch Section 619.04 (a)."

SECTION 619 MULCH

619.03 General Amend this Section by adding the following sentence to the end: "Straw mulch shall be used in all wetland areas."

SECTION 626

FOUNDATIONS, CONDUIT, AND JUNCTION BOXES FOR HIGHWAY SIGNING, LIGHTING, AND SIGNALS

<u>Section 626.021 Miscellaneous Materials</u> Revise this section by removing the fourth paragraph beginning with "All Concrete for concrete encasement..." and replace it with "All concrete for concrete encasement of conduit shall be Class S or Class Fill concrete in accordance with the applicable requirements of Section 502 – Structural Concrete, or a Prepackaged Concrete Mix from the Department's Qualified Products List (QPL)."

Section 626.031Conduit Revise the fifth paragraph beginning with "After the trench has been..." by removing the last sentence beginning with "Where concrete encasement..." and replacing it with "Where concrete encasement is required around the conduit, the concrete shall meet Class S, Class Fill in accordance with the applicable requirements of Section 502 – Structural Concrete, or a Prepackaged Concrete Mix from the Department's Qualified Products List (QPL)."

<u>626.034 Concrete Foundations</u> Revise this Section by changing '626.037' to '**626.036**' in the Second Paragraph which begins with "Foundations shall consist of cast-in-place...".

Revise the 10th paragraph beginning with "Before placing concrete, the required elbows..." by removing "...in accordance with Standard Specification 633."

626.036 Precast Foundations Revise the last sentence of paragraph one so that it reads: "Construction of precast foundations shall conform to the Standard Details and all requirements of 712.061."

SECTION 627 PAVEMENT MARKINGS

<u>627.02 Materials</u> Amend this section by adding the following to the existing Specification:

"When pavement marking paint must be applied on pavement with an air temperature between 35 °F and 50 °F, a low temperature waterborne paint may be used upon the Department's approval as noted below.

The Contractor shall submit the following information for Department review and approval at least 10 calendar days prior to application:

The manufacturer and product name of the low temperature waterborne paint

The manufacturer's technical product data sheets

The product's SDS sheets

All required and recommended application specifications for the product

The manufacturer's requirements for temperature, surface preparation, paint thickness and the bead application shall be followed. No additional payment will be made for the use of low temperature waterborne paint. "

<u>627.06 Application</u> Revise this subsection by replacing the paragraph beginning with "On other final pavement markings…" with the following:

"On other final pavement markings and on curb, where the paint is applied by hand painting or spraying, application shall be one uniform covering coat at least 16 mils thick. Before the paint has dried, the glass beads shall be applied by a pressure system that will force the glass beads onto the undried paint as uniformly as possible.

Supersedes: February 16, 2024

Painted lines and markings shall be applied in accordance with the manufacturer's published recommendations. These recommendations will be supplied to the Resident prior to installation."

Revise this subsection by replacing the paragraph beginning with "If the final reflectivety values are less..." with the following:

The final reflectivity will be acceptable if 90 percent or more of the painted pavement lines and markings meet the specified minimum value. If less than 90 percent of the painted pavement lines and markings meet the specified minimum final reflectivity values, the Contractor shall repaint those areas not meeting required reflectivity at no cost to the Department.

If, after repainting, analysis of the final reflectivity values results in the need for a second repainting, the Contractor will submit in writing a plan of action to meet the reflectivity minimums prior to continuing any work. Once the plan has been reviewed and approved by the Department, the Contractor shall reapply at no cost to the Department.

SECTION 637 DUST CONTROL

Revise this section by removing it in its entirety.

SECTION 643 TRAFFIC SIGNALS

<u>643.021 Materials</u> Amend this subsection by adding the following at the end:

"MaineDOT is transitioning to MASH2016 criteria for Work Zone Traffic Control Devices on the following schedule:

Temporary Traffic Control Signals will be crash tested and/or evaluated to MASH2016 criteria by January 1, 2030. Current Category 4 devices in useful serviceable condition that are successfully tested to NCHRP Report 350 or MASH2009 criteria may be utilized through December 31, 2029."

643.023 Traffic Signal Structures Remove the third paragraph and replace it with the following:

"Traffic signal support structures shall be classified as Fatigue Category III if they are located on roads with a speed limit of 35 mph or less, Fatigue Category II if they are located on roads with a speed limit of greater than 35 mph, and Fatigue Category I if noted on the Contract Plans. Fatigue Importance Factors shall be as specified in Table 11.6-1 (Fatigue Importance Factors). Fatigue analyses are not required for span-wire (strain) pole traffic signal support structures with heights of 55 feet or less unless required by the current edition of AASHTO "LRFD Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals".

643.09 Service Connection Revise this subsection by removing the paragraph that begins with "Traffic signal services shall have...".

And by removing the paragraphs beginning with "A service ground rod shall be installed..." and "A total of 4, 10' service..." and replace them with "A total of 4, 10' service ground rods shall be installed and properly connected together on the outside of the cabinet foundation. One ground rod shall be located at each corner and shall be either flush or slightly below finished grade. The connection between the ground rod and the ground wire shall be an exothermic connection such as a Cadweld. The ground wire from the interconnected ground rods shall be routed through a conduit in the foundation and into the base of the cabinet".

SECTION 645 HIGHWAY SIGNING

<u>Section 645.023 Sign Support Structures</u>. Under letter "c.", revise the fifth paragraph beginning with "In addition to the required details..." by removing the words "and foundation" from the 5th sentence.

<u>Section 645.08 Method of Measurement</u>. Revise the second paragraph beginning with "Bridge-type, cantilever and..." by removing the words "**including the foundation**".

<u>Section 645.09 Basis of Payment</u>. Revise the third paragraph beginning with "The accepted bridge-type, cantilever and..." by removing the word "**foundation**" from the second sentence. Add the following sentence to the end of the paragraph "**Conduits**, **Junction Boxes**, and **Foundations will be paid for under Section 626.**"

SECTION 652 MAINTENANCE OF TRAFFIC

652.2.5 Portable Changeable Message Sign Revise the fifth paragraph so it reads:

"The control system shall include a display screen upon which messages can be reviewed before being displayed on the message sign. The control system shall be capable of maintaining memory when power is unavailable. Messages must be changeable with either a portable electronic device like a notebook computer or an on-board keypad. The controller shall have the capability to store a minimum of 200 user-defined and 200 pre-programmed messages. Controller and battery compartments shall be enclosed in lockable, weather-tight boxes. The cabinet shall be locked at all times that the Contractor is not actively changing the message. The Contractor shall change the password for the controller prior to stationing the PCMS and shall provide the password to the Resident. The password shall be unique per PCMS and secure and shall not be written anywhere in, on, around, or stored in the PCMS."

August 2, 2024 Supersedes: February 16, 2024

Amend this Section by adding the following new subsection:

<u>"652.2.6 Device Crashworthiness</u> MaineDOT is transitioning to MASH2016 criteria for Work Zone Traffic Control Devices on the following schedule:

Category 1 (Cones, Drums, Tubular Markers, Flexible Delineators, and similar devices that have little chance if causing windshield penetration, tire damage, or other significant effect on the control or trajectory of a vehicle) – All Category 1 devices will be manufacturer self-certified as MASH2016 by January 1, 2025. Current Category 1 devices in useful serviceable condition that are not self-certified as MASH2016 compliant may be utilized through December 31, 2024.

Category 2 (Barricades, Portable Sign Supports, Category 1 devices with attachments, and similar devices that are not expected to produce significant vehicular velocity change but may be otherwise hazardous) – All Category 2 devices will be crash tested and/or evaluated to MASH2016 criteria by January 1, 2025. Current Category 2 devices in useful serviceable condition that are successfully tested to NCHRP Report 350 or MASH2009 criteria may be utilized through December 31, 2024.

Category 3 (Portable Concrete Barrier, Portable Crash Cushions, Truck Mounted Attenuators, Category 2 devices weighing more than 100 pounds, and similar devices that are expected to produce significant vehicular velocity change or other harmful reactions) – All Category 3 devices will be crash tested and/or evaluated to MASH2016 criteria by January 1, 2030. Current Category 3 devices in useful serviceable condition that are successfully tested to NCHRP Report 350 or MASH2009 criteria may be utilized through December 31, 2029. (See Standard Specification 526 for additional Portable Concrete Barrier information).

Category 4 (Trailer Mounted Devices: Arrow Boards, Temporary Traffic Control Signals, Area Lighting, Portable Changeable Message Sign, and other similar devices.) – All Category 4 devices will be crash tested and/or evaluated to MASH2016 criteria by January 1, 2030. Current Category 4 devices in useful serviceable condition that are successfully tested to NCHRP Report 350 or MASH2009 criteria may be utilized through December 31, 2029."

652.3.3 Submittal of Traffic Control Plan Amend this section by adding:

"n. A security plan for any PCMS shall be included. The Contractor shall provide a plan for secure access to the PCMS and protection from unauthorized users. The plan shall have details on securing the cabinets via a lock and password from unauthorized users, password changing protocols, and where the access information will be kept so it can be used in the event of emergency. The Contractor shall not Identify or store passwords in the TCP."

<u>652.4 Flaggers</u> Revise the first paragraph of this section so that it reads:

"The Contractor shall furnish flaggers as required by the TCP or as otherwise specified by the Resident. All flaggers must have successfully completed a flagger test approved by the Department and administered by a Department-approved Flagger-Certifier who is employing that flagger. All flaggers must carry an official certification card with them while flagging that has been issued by their employer."

<u>SECTION 681</u> PRECAST AGGREGATE-FILLED, CONCRETE BLOCK GRAVITY WALL

<u>681.08 Basis of Payment</u> Amend this section by adding the Item Number "**681.10**" in front of the item "Precast Aggregate-Filled Concrete Block Gravity Wall" at the end of the section.

SECTION 701 STRUCTURAL CONCRETE RELATED MATERIAL

701.01 Portland Cement and Portland Pozzolan Cement Amend the first sentence of Paragraph 3 by adding "or Type 1L Portland Limestone cement" so that it reads:

"A Type IP (MS) Portland-pozzolan cement (blended hydraulic cement with moderate sulfate resistance) or Type 1L Portland Limestone cement meeting the requirements of AASHTO M 240, may be used instead of Type II or where Type I Portland cement, meeting the requirements of AASHTO M 85, is allowed."

SECTION 703 AGGREGATES

Add the following to Section 703 - Aggregates

703.01 Fine Aggregate for Concrete Fine aggregate for concrete shall consist of natural sand or, when approved by the Resident, other inert materials with similar characteristics or combinations thereof, having strong, durable particles. Fine aggregate from different sources of supply shall not be mixed or stored in the same pile nor used alternately in the same class of construction or mix without permission of the Resident.

All fine aggregate shall be free from injurious amounts of organic impurities. Should the fine aggregate, when subjected to the colorimetric test for organic impurities, AASHTO T 21, produce a color darker than the reference standard color solution (laboratory designation Plate III), the fine aggregate shall be rejected.

Fine aggregate shall have a sand equivalent value of not less than 75 when tested in accordance with AASHTO T 176.

Fine aggregate sources shall meet the Alkali Silica Reactivity (ASR) requirements of Section 703.0201.

The fineness modulus shall not be less than 2.26 or more than 3.14. If this value is exceeded, the fine aggregate will be rejected unless suitable adjustments are made in proportions of coarse and fine aggregate. The fineness modulus of fine aggregate shall be determined by adding the cumulative percentages of material by weight retained on the following sieves: Nos. 4, 8, 16, 30, 50, 100 and dividing by 100.

Fine aggregate, from an individual source when tested for absorption as specified in AASHTO T 84, shall show an absorption of not more than 2.3 percent.

Sieve	Percentage by Weight
Designation	Passing Square Mesh Sieves
3/8 inch	100
No. 4	95-100
No. 8	80-100
No. 16	50-85
No. 30	25-60
No. 50	10-30
No. 100	2-10
No. 200	0-5.0

703.02 Coarse Aggregate for Concrete Coarse aggregate for concrete shall consist of crushed stone or gravel having hard, strong, durable pieces, free from adherent coatings and of which the composite blend retained on the 3/8 inch sieve shall contain no more than 15 percent, by weight of flat and elongated particles when performed in accordance with test method ASTM D 4791, Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate, using a dimensional ratio of 1:5.

The coarse aggregate from an individual source shall have an absorption no greater than 2.0 percent by weight determined in accordance with AASHTO T 85 modified for weight of sample.

The composite blend shall have a Micro-Deval value of 18.0 percent or less as determined by AASHTO T 327 or not exceed 40 percent loss as determined by AASHTO T 96.

Coarse aggregate sources shall meet the Alkali Silica Reactivity (ASR) requirements of Section 703.0201.

Coarse aggregate shall conform to the requirements of the following table for the size or sizes designated and shall be well graded between the limits specified.

Sieve		Percentage	by Weight	
Designation		Passing Squar	e Mesh Sieves	
Grading	A	AA	S	LATEX
Aggregate Size	1 inch	3/4 inch	1½ inch	½ inch
2 inch			100	
1½ inch	100		95-100	
1 inch	95-100	100	-	
³ / ₄ inch	1	90-100	35-70	100
½ inch	25-60	-	-	90-100
3/8 inch	1	20-55	10-30	40-70
No. 4	0-10	0-10	0-5	0-15
No. 8	0-5	0-5	-	0-5
No. 16	-	-	-	-
No. 50	-	-	-	-
No. 200	0 - 1.5	0 - 1.5	0 - 1.5	0 - 1.5

703.0201 Alkali Silica Reactive Aggregates All coarse and fine aggregates proposed for use in concrete shall be tested for Alkali Silica Reactivity (ASR) potential under AASHTO T 303 (ASTM C 1260), Accelerated Detection of Potentially Deleterious Expansion of Mortar Bars Due to Alkali-Silica Reaction, prior to being accepted for use. Acceptance will be based on testing performed by an accredited independent lab submitted to the Department. Aggregate submittals will be required on a 5-year cycle, unless the source or character of the aggregate in question has changed within 5 years from the last test date.

As per AASHTO T 303 (ASTM C 1260): Use of a particular coarse or fine aggregate will be allowed with no restrictions when the mortar bars made with this aggregate expand less than or equal to 0.10 percent at 30 days from casting. Use of a particular coarse or fine aggregate will be classified as potentially reactive when the mortar bars made with this aggregate expand greater than 0.10 percent at 30 days from casting. Use of this aggregate will only be allowed with the use of cement-pozzolan blends and/or chemical admixtures that result in mortar bar expansion of less than 0.10 percent at 30 days from casting as tested under ASTM C 1567.

Acceptable pozzolans and chemical admixtures that may be used when an aggregate is classified as potentially reactive include, but are not limited to the following:

- a. Class F Coal Fly Ash meeting the requirements of AASHTO M 295
- b. Ground Granulated Blast Furnace Slag (Grade 100 or 120) meeting the requirements of AASHTO M 302
- c. Densified Silica Fume meeting the requirements of AASHTO M 307
- d. Lithium-based admixtures
- e. Metakaolin

Pozzolans or chemical admixtures required to offset the effects of potentially reactive aggregates will be incorporated into the concrete at no additional cost to the Department.

703.05 Aggregate for Sand Leveling Aggregate for sand leveling shall be sand of hard durable particles free from vegetable matter, lumps or balls of clay and other deleterious substances. The aggregate shall meet the grading requirements of the following table.

Sieve	Percentage by Weight
Designation	Passing Square Mesh Sieves
3/8 inch	85-100
No. 200	0-5.0

703.06 Aggregate for Base and Subbase The following shall apply to Sections (a.) and (c.) below. The material shall have a Micro-Deval value of 25.0 or less as determined by AASHTO T 327. If the Micro- Deval value exceeds 25.0, the Washington State Degradation DOT Test Method T113, Method of Test for Determination of Degradation Value (January 2009 version) shall be performed, except that the test shall be performed on the portion of the sample that passes the ½ in sieve and is retained on the No. 10 sieve. If the material has a Washington Degradation value of less than 15, the material shall be rejected.

The material used in Section (b.) below shall have a Micro-Deval value of 25.0 or less as determined by AASHTO T 327. If the Micro-Deval value exceeds 25.0 the material may be used if it does not exceed 25 percent loss on AASHTO T 96, Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.

Recycled Asphalt Pavement (RAP) shall not be used for or blended with aggregate base or subbase.

a. Aggregate for base, Type A and B shall be crushed ledge or crushed gravel of hard durable particles free from vegetable matter, lumps or balls of clay and other deleterious substances. The gradation of the part that passes a 3 inch sieve shall meet the grading requirements of the following table:

Sieve	Percentage by Weight Passing Square Mesh Sieves	
Designation	Type A	Type B
½ inch	45-70	35-75
½ inch	30-55	25-60
No. 40	0-20	0-25
No. 200	0-6.0	0-6.0

At least 50 percent by weight of the material retained on the No. 4 sieve shall have at least one fractured face as tested by AASHTO T 335.

Type A aggregate for base shall only contain particles of rock that will pass the 2 inch square mesh sieve.

Type B aggregate for base shall only contain particles of rock that will pass the 4 inch square mesh sieve.

b. Aggregate for base, Type C shall be crushed ledge or crushed gravel of hard durable particles free from vegetable matter, lumps or balls of clay and other deleterious substances. The material shall meet the grading requirements of the following table:

Sieve Designation	Percentage by Weight Passing Square Mesh Sieves
Designation	Type C
4 inches	100
3 inches	90-100
2 inches	75-100
1 inch	50-80
½ inch	30-60
No. 4	15-40
No. 200	0-6.0

At least 50 percent by weight of the material coarser than the No. 4 sieve shall have at least one fractured face as tested by AASHTO T 335.

c. Aggregate for subbase shall be sand or gravel of hard durable particles free from vegetable matter, lumps or balls of clay and other deleterious substances. The gradation of the part that passes a 3 inch sieve shall meet the grading requirements of the following table:

Sieve Designation	Percentage by Weight Passing Square Mesh Sieves		
	Type D	Type E	
½ in	35-80		
½ inch	25-65	25-100	
No. 40	0-30	0-50	
No. 200	0-7.0	0-7.0	

Type D aggregate for subbase gravel may contain up to 50 percent by weight Recycled Concrete Aggregate (RCA). When RCA is used, the portion of the resulting blend of gravel and RCA retained on a ½" square mesh sieve shall contain a total of no more than 5 percent by weight of other recycled materials such as brick, concrete masonry block, or asphalt pavement as determined by visual inspection.

RCA shall be substantially free of wood, metal, plaster, and gypsum board as defined in Note 9 in Section 7.4 of AASHTO M 319. RCA shall also be free of all substances that fall under the category of solid waste or hazardous materials.

Aggregate for subbase shall not contain particles of rock which will not pass the 6 inch square mesh sieve.

703.08 Recycled Asphalt Pavement Recycled asphalt pavement shall consist of salvaged asphalt materials from milled pavements or production waste that has been processed before use to meet the requirements of the job mix formula. It shall be free of winter sand, granular fill, construction debris, or other materials not generally considered asphalt pavement.

<u>703.081 RAP for Asphalt Pavement</u> Recycled Asphalt Pavement (RAP) may be introduced into hot-mix asphalt pavement at percentages approved by the Department according to the MaineDOT Policies and Procedures for HMA Sampling and Testing.

If approved by the Department, the Contractor shall provide documentation stating the source, test results for average residual asphalt content, and stockpile gradations showing RAP materials have been sized to meet the maximum aggregate size requirements of each mix designation. The Department will obtain samples for verification and approval prior to its use.

The maximum allowable percent of RAP shall be determined by the asphalt content, the percent passing the 0.075 mm sieve, the ratio between the percent passing the 0.075 mm sieve and the asphalt content, and Coarse Micro-Deval loss values as tested by the Department.

The maximum percentage of RAP allowable shall be the lowest percentage as determined according to Table 4 below:

Classification	Maximum RAP Percentage Allowed	Asphalt content standard deviation	Percent passing 0.075 mm sieve standard deviation	Percent passing 0.075 mm sieve / asphalt content ratio	Residual aggregate M-D loss value
Class III	10%	≤ 1.0	N/A	≤ 4.0	≤ 18
Class II	20%	≤ 0.5	≤ 1.0	≤ 2.8	
Class I	30%	≤ 0.3	≤ 0.5	≤ 1.8	

Table 4: Maximum Percent RAP According to Test Results

The Department will monitor RAP asphalt content and gradation during production by testing samples from the stockpile at approximately 15,000 T intervals (in terms of mix production). The allowable variance limits (from the numerical average values used for mix designs) for this testing are determined based upon the maximum allowable RAP percentage and are shown below in Table 5.

Table 5: RAP Verification Limits

Classification	Asphalt content (compared to aim)	Percent passing 0.075 mm sieve (compared to aim)
Class III	± 1.5	± 2.0
Class II	± 1.0	± 1.5
Class I	± 0.5	± 0.7

For specification purposes, RAP will be categorized as follows:

Class III – A maximum of 10.0 percent of Class III RAP may be used in any base, intermediate base, surface, or shim mixture. A maximum of 20.0 percent of Class III RAP may be used in hand-placed mixes for item 403.209.

Class II – A maximum of 20.0 percent Class II RAP in any base, binder, surface, or shim course. Class I – A maximum of 20.0 percent Class I RAP may be used in any base, intermediate base, surface, or shim mixture without requiring a change to the specified asphalt binder. A maximum of 30.0 percent Class I RAP may be used in any base or intermediate base mixture provided that a PG 58-28 or PG 58-34 asphalt binder is used. A maximum of 30.0 percent Class I RAP may be used in any surface or shim mixture provided that PG 58-34 asphalt binder is used. Mixtures exceeding 20.0 percent Class I RAP must be evaluated and approved by the Department.

The Contractor may use up to two different RAP sources in any one mix design. The total RAP percentage of the mix shall not exceed the maximum allowed for the highest classification RAP source used (i.e. if a Class I & Class III used, total RAP must not exceed 30.0%). The blended RAP material must meet all the requirements of the classification for which the RAP is entered (i.e. 10% Class III with 20% Class I, blend must meet Class I criteria). The Department may take belt cuts of the blended RAP to verify the material meets these requirements. If the Contractor elects to use more than one RAP source in a design, the Contractor shall provide an acceptable point of sampling blended RAP material from the feed belt.

In the event that RAP source or properties change, the Contractor shall notify the Department of the change and submit new documentation stating the new source or properties a minimum of 72 hours prior to the change to allow for obtaining new samples and approval.

SECTION 709 REINFORCING STEEL AND WELDED STEEL WIRE FABRIC

709.01 Reinforcing Steel Remove the second paragraph of Section 709.01 of the standard specification beginning with "Low-Carbon, Chromium,..." and replace with the following:

"Low-carbon, chromium, reinforcing steel shall be deformed bars conforming to the requirements of ASTM A1035. Bars shall be Grade 100 and alloy Type CS unless otherwise specified on the Plans."

SECTION 710 FENCE AND GUARDRAIL

710.06 Fence Posts and Braces Revise the first Paragraph so that it reads:

"Wood posts shall be of cedar, white oak, or tamarack or other AWPA approved species, of the diameter or section and length shown on the plans."

Remove the fourth paragraph which starts "That portion of wood posts...".

Revise the paragraph beginning with "Braces shall be of spruce, eastern hemlock ... so that it now reads:

"Braces shall be of spruce, eastern hemlock, Norway pine, pitch pine, or tamarack timbers or other AWPA approved species, or spruce, cedar, tamarack or other AWPA approved species round posts of sufficient length to make a diagonal brace between adjacent posts. All wood posts and braces shall be pressure-treated in accordance with AASHTO M 133 and AWPA U1, UC4A Commodity Specification B: Posts. "

710.07 Guardrail Posts Revise this section so that the first sentence of section a. reads:

"a. Wood posts shall be of Norway pine, southern yellow pine, pitch pine, Douglas fir, red pine, white pine, or eastern hemlock or other AWPA approved species."

Revise the next paragraph so that it reads:

Wood posts and offset brackets shall be preservative treated in accordance with the requirements of AASHTO M 133 and AWPA U1, UC4A Commodity Specification B: Posts.

710.08 Guardrail Hardware Revise this subsection by replacing "AASHTO M 298" with "ASTM B695"

SECTION 711 MISCELLANEOUS BRIDGE MATERIAL

711.06 Stud Shear Connector Anchors and Fasteners Amend this section by deleting it in its entirety and replacing it with:

"Shear connectors shall meet the dimensional tolerances of Figure 9.1 of the ANSI/AASHTO/AWS D1.5 Bridge Welding Code (D1.5 Code). Shear connectors, anchors and fasteners shall meet the material requirements of Section 9 of the D1.5 Code. Shear connectors shall meet the mechanical property requirements of Table 9.1, Type B of the D1.5 Code. Anchors and fasteners shall meet the mechanical property requirements of Table 9.1 of the D1.5 Code, Type A."

SECTION 712 MISCELLANEOUS HIGHWAY MATERIAL

<u>712.061 Structural Precast Units</u> Amend this section by adding the following sentence to the end of the first paragraph of the <u>Construction</u> subsection:

"Facilities certified by NPCA or PCI shall provide to the Fabrication Engineer a copy of their annual audit to include deficiency reports and corrective actions."

Revise this section by changing the letter "b" of ASTM C1611 of the <u>Concrete Testing</u> subsection so that it reads:

"b. Air content shall be 5.0% to 8.0%."

SECTION 713 STRUCTURAL STEEL AND RELATED MATERIAL

Section 713.02 High Strength Bolts

Revise the second sentence of this subsection so that it reads "Nuts shall meet the requirement of ASTM A563". Revise the third sentence of this subsection so that it reads "Circular and beveled washers shall conform to the requirement of ASTM F436".

SECTION 718 TRAFFIC SIGNALS MATERIAL

718.03 Signal Mounting Amend the paragraph beginning with "All trunions, brackets and..." by adding "For polycarbonate signal heads with more than 3 sections or requiring mounting extensions greater than 12 inches in length, reinforcing plates shall be used to reinforce the housings at the point of attachment." to the end of the paragraph.

718.08 Controller Cabinet Revise this subsection by replacing the paragraph beginning with "The cabinet shall be supplied with LED light panels..." on or about page 7-66 with "The cabinet shall be supplied with white LED light panels which shall automatically illuminate via a door open switch whenever one of the four main cabinet doors are opened for the ground mount cabinet or two main doors for the side of pole cabinet. The ground mounted cabinet shall contain four LED light panels per side totaling eight panels for the cabinet; one panel each at the top and bottom portion of the front side and back side on the Control side and Power/Auxiliary side of the cabinet. Each light panel shall produce a minimum of 250 lumens for a total minimum lumen output of 2000 lumens with all eight panels illuminated. The minimum output per side would be 1000 lumens. The LED panels shall be protected by a clear shatterproof shield. The side of pole mounted cabinet shall contain four light panels; one at the top of the rack assembly and one at the bottom rack assembly on each side of the cabinet.

A second door open status switch per door shall activate a controller input to log a report event that one of the doors was opened. All door open status switches shall be connected to the same controller input. For the ground mount cabinet, there shall be two switches on each of the four main doors. For the side-of-pole mount cabinet, there shall be two switches on each of the two main doors."

Revise this subsection by replacing the paragraph beginning with "The cabinet shall be supplied with a generator panel ..." on or about page 7-68 with:

"The cabinet shall be supplied with a generator panel. The generator panel shall consist of a manual transfer switch and a twist-lock connector for generator hookup. The transfer switch knob and twist-lock connector shall be located inside a stainless steel enclosure with a separate lockable door accessed with a Corbin #2 key. The unit shall be mounted on the left, exterior of the control side wall of the ground mount cabinet a minimum of 36" above the surrounding grade and on the lower left side of the pole mounted cabinet. The generator transfer switch shall be a Reliance C30A1N Signa Series or approved equal. "

Revise this subsection by removing the following from the paragraph beginning with "The ground mounted cabinet shall be supplied and installed with an electric service meter socket trim and electrical service disconnect switch ..." on or about page 7-69: "(removed: thus preventing that space from being used either by equipment supplied as part of the project, or future equipment that would be installed in the rack system. Joe indicated that he would add this language to the detail so it is covered.)".

Revise this subsection by replacing the following in the paragraph beginning with "The Contractor shall reconfigure the default user name..." on or around page 7-70; "MaineDOT IT" with "MaineDOT Traffic Division".

In the paragraph beginning with "Tests shall be conducted by the contractor..." on or around page 7-73, amend this subsection by removing "in the state of Maine and" after "The facility shall be".

Supersedes: February 16, 2024

Amend this Section by adding the following subsection:

<u>718.13 Field Monitoring Unit (FMU)</u> This item of work shall conform to this specification. This item shall consist of furnishing and installing a Field Monitoring Unit (FMU) and software, as well as all needed accessories required for a full and complete installation, including but not limited to power adapters, Ethernet cables, and interface cables, as described herein.

Where applicable, communications from MaineDOT's cloud-based Central Management System (CMS) to the on-street traffic signal controllers shall be made through fiber optic interconnect cable connected back to existing internet connections and/or the Field Monitoring Unit (FMU). The Contractor shall furnish and install all materials necessary for a complete and operational fiber optic interconnection to all project intersections as shown on the plans. All connections to the CMS cloud-based system shall be via a secure VPN network.

The FMU shall be the only remote connection device used by isolated intersections to connect to the cloud-based system. All connections shall be encrypted VPN tunnels. The Contractor shall coordinate all configuration settings with MaineDOT IT and the Engineer.

The FMU central web based interface shall be a separate element from the CMS.

MATERIALS: The materials for this work shall conform to the following requirements:

- 1. The work under this item specifies the requirements for the FMU. The FMU shall operate independent of the brand/type of intersection controller deployed in the ATC traffic cabinet.
- 2. The FMU shall conform to the following requirements:
 - 2.1 The FMU shall function correctly between -34 degrees C and +74 degrees C.
 - 2.2 The FMU shall be provided with appropriately rated connectors that allows the FMU to be exchanged by unplugging connectors, without tools.
 - 2.3 The FMU shall monitor and log all ATC Controller and ATC cabinet faults and or alarms.
 - 2.4 The FMU shall be wired directly to the ATC cabinet.
 - 2.5 The FMU shall have an internal cellular modem running at 4G LTE.
 - 2.5.1 The Cellular modem shall be designed to be replaced / upgraded to 5G service when available.
 - 2.6 The FMU shall incorporate an integrated GPS and cell modem.
 - 2.7 The configuration of the FMU shall be accomplished by accessing the internal web server with a browser. It shall be possible to configure the FMU without any special software.

Supersedes: February 16, 2024

- 2.8 The FMU shall be powered via a standard 120V input power.
- 2.9 The FMU shall allow for the routing of the controller configuration packets to and from the controller (either by Ethernet or serial communications) for any type of controller utilized by the MaineDOT. In this way it shall be possible to configure the controller and utilize the controller specific software to interrogate the controller, and the FMU shall provide the communications pipe which allows this to be accomplished.
- 2.10 The FMU shall, within the size limitations above, include a battery and battery charging/monitoring circuit, to allow the FMU to function correctly even when all power to the intersection has failed. The battery shall continue to power the FMU for a minimum of 5 hours after all power has failed to the intersection.
- 2.11 The FMU shall incorporate an integrated GPS which will allow the FMU to geolocate itself on the FMU management software map, without configuration.
- 2.12 The FMU shall operate without requiring a static IP address. The only configuration required at the FMU is to enter the URL of where the FMU management software is hosted.
- 2.13 In the event that the cell service is interrupted or is not available, the FMU shall store any events that occur in internal memory and forward these events automatically to the FMU management software when the cell service is restored. In this way, a complete record of events at the device can be maintained even if cell service is interrupted for a period. The system will store 5000 events.
- 2.14 The FMU shall utilize HTTP and HTTPS protocols, and XML data structures, for communication with the FMU management software. In this way the data will be open for future expansion and competition. The use of secret proprietary protocols is not permitted.
- 2.15 The FMU shall include Ethernet communications via an Ethernet Port with RJ45 connector.
- 2.16 The FMU shall include weather proof antennas.

3. Map Display FMU Management Software

- 3.1 The FMU shall include a scrollable, zoomable map display, with the intersections and other monitored devices shown as representative icons on the map. The map shall include the ability to see the intersections using Google Streetview.
- 3.2 The alarm status of the intersection shall be clearly indicated on the icon on the map, so that the user can see at a glance which intersections are in alarm.

Supersedes: February 16, 2024

- 3.3 The map display shall also include a list of intersections, with the number and priority of alarms indicated on the list. Intersections in high priority alarm shall be moved to the top of the list, followed by medium priority, low priority and then finally by intersections not in alarm.
- 3.4 The icons shall change to be able to clearly indicate if an intersection is offline.
- 3.5 Clicking on the icon on the map shall expose a box with the current parameters of the intersection shown.
- 3.6 The default map display position and zoom shall be configurable by user, so that the user's view will default to show the intersections that the user is responsible for managing.
- 3.7 The map view shall have the ability to show Google traffic overlays on the map.

4. Intersection Detail Display FMU Management Software

- 4.1 It shall be possible to drill down, either from the map icon or from the list, to a device level detail for the intersection, which as a minimum shall display the following parameters:
 - 4.1.1 The alarm status, with priority indicated, and a text description of the alarm (if an alarm is present for this device).
 - 4.1.2 The time since the last communication with the device
 - 4.1.3 The following parameters (real time now values, minimum for the day values, maximum for the day values, and average for the day values)
 - 4.1.3.1 The AC mains voltage (value)
 - 4.1.3.2 The battery back-up voltage (value)
 - 4.1.3.3 The cabinet temperature (value)
 - 4.1.3.4 The cabinet humidity (value)
 - 4.1.3.5 The presence of AC power (OK or Fail)
 - 4.1.3.6 The flashing status of the intersection (OK or Flashing)
 - 4.1.3.7 Stop Time status (OK or Stop Time Active)
 - 4.1.3.8 The cabinet door status (Open or Closed)
 - 4.1.3.9 The intersection fan status (Fan On or Fan off)

Supersedes: February 16, 2024

- 4.1.4 It shall be possible to view graphs of each of the value parameters in graphical form, over the recent two-week period. This includes real time graphs of:
 - 4.1.4.1 The AC mains voltage
 - 4.1.4.2 The battery back-up voltage
 - 4.1.4.3 The cabinet temperature
 - 4.1.4.4 The cabinet humidity

5. Diagnostics and Log Display FMU Management Software

- 5.1 From the device level detail within the FMU management software, it shall be possible to drill down to get the raw data; the error logs; and the communications logs to allow a technician to fault-find problems.
- 5.2 It shall be possible to filter the logs by Device; by Device Type and/or by Group as well as between dates.
- 5.3 It shall be possible to print these selected logs to a local printer or a PDF file.
- 5.4 It shall be possible to export these logs to Excel on the local computer for further analysis.

6. Alarms FMU Management Software

- 6.1 The FMU management software shall have a comprehensive alarm generation capability
- 6.2 It shall be possible to configure alarms to be generated on any parameter becoming out of tolerance, including analog values, digital values and enumerated values.
- 6.3 Alarms shall be configurable to be of Low, High or Critical Priority.
- 6.4 The alarm priority shall be displayed throughout the FMU management software, on all displays, using color codes such as red-critical; yellow high; and amber-low to indicate the priority of the alarm.
- 6.5 The current active alarms shall be accessible for view via an expandable window, to see which alarms are active and when the alarm occurred. The highest priority alarms shall rise to the top of the list.

7. Alerts FMU Management Software

7.1 The FMU management software shall have comprehensive alerting capability, to enable the response personnel to be notified when an abnormal situation has occurred.

Supersedes: February 16, 2024

- 7.2 It shall be possible to configure alerts to one or more personnel for each alarm. This will cause, as selected, an SMS and/or an email to be sent to the person when an alarm occurs.
- 7.3 The alert shall be configurable to optionally send via email and/or via SMS a message when an alarm clears.
- 7.4 The intention is that the FMU management software provides the alerts to the user in near real time. The SMS and email shall be issued within 30 seconds of the occurrence of event which results in an alert being issued.

8. Hosting and Connectivity and Service FMU / FMU Management Software

- 8.1 The contractor shall supply the FMU with the FMU manufacturers 10 year options for Connectivity and Service, as part of the purchase price. The Connectivity and Service agreement shall include at a minimum:
 - 8.1.1 Cellular Connectivity
 - 8.1.2 No cellular overage charges
 - 8.1.3 Extended warranty on the hardware for the period of the Connectivity and Service Agreement
 - 8.1.4 Over-the-air software updates
 - 8.1.5 Over-the-air security updates
 - 8.1.6 Future Connected Vehicles Service

SECTION 720 STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS

720.12 Wood Sign Posts Revise the first sentence so that it reads:

Wood sign posts shall be rectangular, straight and sound timber, cut from live growing native spruce, red pine, hemlock, cedar trees or other AWPA approved species, free from loose knots or other structurally weakening defects of importance, such as shake or holes or heart rot.

Revise the third paragraph that starts with "When pressure treated..." so that it reads:

All sign posts shall be pressure-treated in accordance with AASHTO M 133 and AWPA Standard U1, UC4A, Commodity Specification A: Sawn Products.