

COUNTIE(S) : YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

COMPLETION DATE : 11/22/13

=====

PROJECT(S) : BR-1707(900)X

LOCATION(S) : CLAYHILL BRIDGE REPLACEMENT PLUSAOTHERINCIDENTALMWORK.F TRANSPORTATION

A TRUE COPY : \_\_\_\_\_

TITLE : \_\_\_\_\_

ATTEST : \_\_\_\_\_

CONTRACT DESCRIPTION : KENNEBUNK, BRIDGE REPLACEMENT. WORK INCLUDES CLAY HILL

NOTARY PUBLIC

RANK	VENDOR NO./NAME	TOTAL BID	% OVER LOW BID
1	001954 TECHNICAL CONSTRUCTION, INC.	\$ 1,872,275.00	100.0000%
2	000063 WYMAN & SIMPSON, INC.	\$ 2,014,651.44	107.6045%
3	000164 CPM CONSTRUCTORS	\$ 2,183,067.44	116.5997%
4	000032 REED & REED, INC.	\$ 2,193,605.00	117.1625%
5	000416 T. BUCK CONSTRUCTION, INC.	\$ 2,220,000.00	118.5723%
6	004202 NEW ENGLAND INFRASTRUCTURE INC.	\$ 2,792,321.00	149.1405%

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	( 1 ) 001954 TECHNICAL CONSTRUCTION, INC.		( 2 ) 000063 WYMAN & SIMPSON, INC.		( 3 ) 000164 CPM CONSTRUCTORS	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 PROJECT ITEMS							
0010 202.19 REMOVING EXISTING BRIDGE	1.000 LS	115000.00000	115000.00	100000.00000	100000.00	110000.00000	110000.00
0020 203.20 COMMON EXCAVATION	1810.000 CY	9.00000	16290.00	15.00000	27150.00	16.00000	28960.00
0030 203.25 GRANULAR BORROW	200.000 CY	33.00000	6600.00	20.00000	4000.00	18.00000	3600.00
0040 206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	140.000 CY	40.00000	5600.00	30.00000	4200.00	30.00000	4200.00
0050 304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2090.000 CY	12.00000	25080.00	21.00000	43890.00	22.00000	45980.00
0060 403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	285.000 T	90.00000	25650.00	126.00000	35910.00	126.00000	35910.00
0070 403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	17.000 T	145.00000	2465.00	170.00000	2890.00	170.00000	2890.00
0080 403.213 HOT MIX ASPHALT 12.5 MM BASE	520.000 T	95.00000	49400.00	115.00000	59800.00	105.00000	54600.00
0090 409.15 BITUMINOUS TACK COAT - APPLIED	172.000 G	12.00000	2064.00	11.00000	1892.00	11.00000	1892.00

COUNTIE(S): YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

=====

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	( 1 ) 001954 TECHNICAL CONSTRUCTION, INC.		( 2 ) 000063 WYMAN & SIMPSON, INC.		( 3 ) 000164 CPM CONSTRUCTORS	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0100 411.131 STONE DUST SURFACE COURSE	1040.000 SF	2.00000	2080.00	1.00000	1040.00	1.00000	1040.00
0110 430.25 COBBLESTONE PAVEMENT REMOVE AND RESET	10.000 SY	110.00000	1100.00	300.00000	3000.00	300.00000	3000.00
0120 501.231 DYNAMIC LOADING TEST	4.000 EA	4000.00000	16000.00	2500.00000	10000.00	2400.00000	9600.00
0130 501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	500.000 LF	70.00000	35000.00	75.00000	37500.00	85.00000	42500.00
0140 501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	500.000 LF	10.00000	5000.00	10.00000	5000.00	15.00000	7500.00
0150 501.70 STEEL PIPE PILES, DELIVERED	664.000 LF	200.00000	132800.00	150.00000	99600.00	275.00000	182600.00
0160 501.701 STEEL PIPE PILES, IN PLACE	664.000 LF	20.00000	13280.00	30.00000	19920.00	60.00000	39840.00
0170 501.90 PILE TIPS	22.000 EA	700.00000	15400.00	1000.00000	22000.00	1000.00000	22000.00
0180 501.91 PILE SPLICES	44.000 EA	10.00000	440.00	0.01000	0.44	0.01000	0.44
0190 501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	100000.00000	100000.00	100000.00000	100000.00	40000.00000	40000.00
0200 502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	70.000 LS	50000.00000	50000.00	50000.00000	50000.00	55000.00000	55000.00
0210 502.239 STRUCTURAL CONCRETE PIERS	55.000 LS	75000.00000	75000.00	60000.00000	60000.00	110000.00000	110000.00
0220 502.25 STRUCTURAL CONCRETE SUPERSTRUCTURE SLAB	108.000 LS	60000.00000	60000.00	100000.00000	100000.00	135000.00000	135000.00
0230 502.31 STRUCTURAL CONCRETE APPROACH SLABS	25.000 LS	10000.00000	10000.00	8000.00000	8000.00	7500.00000	7500.00
0240 502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	61.000 LS	20000.00000	20000.00	50000.00000	50000.00	22500.00000	22500.00
0250 503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	20000.000 LB	0.50000	10000.00	0.65000	13000.00	1.00000	20000.00
0260 503.13 REINFORCING STEEL, PLACING	20000.000 LB	0.60000	12000.00	0.65000	13000.00	0.70000	14000.00
0270 506.9105 POLYUREA ELASTOMER COATING ALLOWANCE	LUMP	46824.00000	46824.00	46824.00000	46824.00	46824.00000	46824.00
0280 507.0811 STEEL BRIDGE RAILING, 2 BAR	161.000 LS	20000.00000	20000.00	20000.00000	20000.00	24000.00000	24000.00
0290 507.0831 STEEL BRIDGE RAILING, 4 BAR	161.000 LS	26000.00000	26000.00	27000.00000	27000.00	35000.00000	35000.00

COUNTIE(S) : YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

=====

			( 1 ) 001954		( 2 ) 000063		( 3 ) 000164	
			TECHNICAL CONSTRUCTION, INC.		WYMAN & SIMPSON, INC.		CPM CONSTRUCTORS	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0300 508.14	HIGH PERFORMANCE WATERPROOFING MEMBRANE	630.000 LS	12000.00000	12000.00	13000.00000	13000.00	14000.00000	14000.00
0310 510.10	SPECIAL DETOUR ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 11'	LUMP	180000.00000	180000.00	250000.00000	250000.00	278000.00000	278000.00
0320 511.07	COFFERDAM: ABUT NO.1	LUMP	10000.00000	10000.00	1500.00000	1500.00	6500.00000	6500.00
0330 511.07	COFFERDAM: ABUT NO.2	LUMP	10000.00000	10000.00	1500.00000	1500.00	6500.00000	6500.00
0340 514.06	CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	1500.00000	1500.00	750.00000	750.00	1000.00000	1000.00
0350 515.20	PROTECTIVE COATING FOR CONCRETE SURFACE	385.000 SY	10.00000	3850.00	4.00000	1540.00	5.00000	1925.00
0360 526.301	TEMPORARY CONCRETE BARRIER TYPE I	100.000 LS	2000.00000	2000.00	5000.00000	5000.00	5000.00000	5000.00
0370 526.34	PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	2000.00000	8000.00	2500.00000	10000.00	2400.00000	9600.00
0380 527.303	ENERGY ABSORBING SYSTEM (ET-PLUS)	2.000 EA	2100.00000	4200.00	2500.00000	5000.00	2500.00000	5000.00
0390 527.34	WORK ZONE CRASH CUSHIONS	2.000 UN	3500.00000	7000.00	3500.00000	7000.00	1500.00000	3000.00
0400 535.60	PRESTRESSED STRUCTURAL CONCRETE SLAB	296.000 LS	400000.00000	400000.00	425000.00000	425000.00	420000.00000	420000.00
0410 606.1721	BRIDGE TRANSITION - TYPE 1	4.000 EA	1700.00000	6800.00	1500.00000	6000.00	1500.00000	6000.00
0420 606.23	GUARDRAIL TYPE 3C - SINGLE RAIL	425.000 LF	17.00000	7225.00	16.00000	6800.00	16.00000	6800.00
0430 606.231	GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	40.000 LF	25.00000	1000.00	16.00000	640.00	16.00000	640.00
0440 606.265	TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	54.00000	108.00	50.00000	100.00	50.00000	100.00
0450 606.353	REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA	47.00000	282.00	35.00000	210.00	35.00000	210.00
0460 608.08	REINFORCED CONCRETE SIDEWALK	48.000 SY	70.00000	3360.00	80.00000	3840.00	50.00000	2400.00
0470 608.26	CURB RAMP DETECTABLE WARNING FIELD	50.000 SF	50.00000	2500.00	50.00000	2500.00	50.00000	2500.00
0480 609.19	VERTICAL CURB TYPE 2	50.000 LF	30.00000	1500.00	32.00000	1600.00	28.00000	1400.00

COUNTIE(S): YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

=====

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		( 1 ) 001954 TECHNICAL CONSTRUCTION, INC.		( 2 ) 000063 WYMAN & SIMPSON, INC.		( 3 ) 000164 CPM CONSTRUCTORS	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0490 609.38 RESET CURB TYPE 1	100.000	LF	20.00000	2000.00	22.00000	2200.00	18.00000	1800.00
0500 610.08 PLAIN RIPRAP	570.000	CY	110.00000	62700.00	65.00000	37050.00	65.00000	37050.00
0510 613.319 EROSION CONTROL BLANKET	23.000	SY	4.00000	92.00	15.00000	345.00	12.00000	276.00
0520 615.07 LOAM	25.000	CY	45.00000	1125.00	34.00000	850.00	34.00000	850.00
0530 618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	4.000	UN	30.00000	120.00	75.00000	300.00	90.00000	360.00
0540 619.1201 MULCH - PLAN QUANTITY	4.000	UN	20.00000	80.00	25.00000	100.00	40.00000	160.00
0550 619.1401 EROSION CONTROL MIX	30.000	CY	45.00000	1350.00	50.00000	1500.00	40.00000	1200.00
0560 620.58 EROSION CONTROL GEOTEXTILE	425.000	SY	4.00000	1700.00	4.00000	1700.00	3.00000	1275.00
0570 627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2700.000	LF	0.30000	810.00	0.30000	810.00	0.30000	810.00
0580 629.05 HAND LABOR, STRAIGHT TIME	40.000	HR	40.00000	1600.00	40.00000	1600.00	30.00000	1200.00
0590 631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000	HR	135.00000	5400.00	115.00000	4600.00	120.00000	4800.00
0600 631.14 GRADER (INCLUDING OPERATOR)	40.000	HR	145.00000	5800.00	125.00000	5000.00	150.00000	6000.00
0610 631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	20.000	HR	110.00000	2200.00	65.00000	1300.00	80.00000	1600.00
0620 631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000	HR	75.00000	3000.00	70.00000	2800.00	60.00000	2400.00
0630 631.20 STUMP CHIPPER (INCLUDING OPERATOR)	4.000	HR	250.00000	1000.00	150.00000	600.00	250.00000	1000.00
0640 639.18 FIELD OFFICE TYPE A	1.000	EA	10000.00000	10000.00	10000.00000	10000.00	10000.00000	10000.00
0650 643.72 TEMPORARY TRAFFIC SIGNAL		LUMP	12000.00000	12000.00	15000.00000	15000.00	15000.00000	15000.00
0660 652.312 TYPE III BARRICADE	4.000	EA	200.00000	800.00	150.00000	600.00	250.00000	1000.00
0670 652.33 DRUM	20.000	EA	65.00000	1300.00	55.00000	1100.00	60.00000	1200.00

COUNTIE(S): YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

=====

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		( 1 ) 001954 TECHNICAL CONSTRUCTION, INC.		( 2 ) 000063 WYMAN & SIMPSON, INC.		( 3 ) 000164 CPM CONSTRUCTORS	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0680 652.34 CONE	40.000	EA	25.00000	1000.00	20.00000	800.00	25.00000	1000.00
0690 652.35 CONSTRUCTION SIGNS	200.000	SF	10.00000	2000.00	20.00000	4000.00	15.00000	3000.00
0700 652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000	LS	5000.00000	5000.00	5000.00000	5000.00	5000.00000	5000.00
0710 652.38 FLAGGER	300.000	HR	16.00000	4800.00	16.00000	4800.00	15.25000	4575.00
0720 656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL		LUMP	6000.00000	6000.00	5000.00000	5000.00	5000.00000	5000.00
0730 659.10 MOBILIZATION		LUMP	180000.00000	180000.00	200000.00000	200000.00	200000.00000	200000.00
SECTION TOTALS			\$	1,872,275.00	\$	2,014,651.44	\$	2,183,067.44
CONTRACT TOTALS			\$	1,872,275.00	\$	2,014,651.44	\$	2,183,067.44

COUNTIE(S) : YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

=====

=====			( 4 ) 000032		( 5 ) 000416		( 6 ) 004202	
=====			REED & REED, INC.		T. BUCK CONSTRUCTION, INC.		NEW ENGLAND INFRASTRUCTURE	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
-----								
SECTION 0001 PROJECT ITEMS								
0010 202.19	1.000	LS	125000.00000	125000.00	200000.00000	200000.00	250000.00000	250000.00
REMOVING EXISTING BRIDGE								
0020 203.20	1810.000	CY	13.00000	23530.00	9.00000	16290.00	21.00000	38010.00
COMMON EXCAVATION								
0030 203.25	200.000	CY	49.00000	9800.00	33.00000	6600.00	48.00000	9600.00
GRANULAR BORROW								
0040 206.082	140.000	CY	40.00000	5600.00	38.00000	5320.00	40.00000	5600.00
STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES								
0050 304.10	2090.000	CY	26.00000	54340.00	12.00000	25080.00	40.00000	83600.00
AGGREGATE SUBBASE COURSE - GRAVEL								
0060 403.208	285.000	T	126.00000	35910.00	92.00000	26220.00	135.00000	38475.00
HOT MIX ASPHALT 12.5 MM HMA SURFACE								
0070 403.209	17.000	T	170.00000	2890.00	145.00000	2465.00	180.00000	3060.00
HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)								
0080 403.213	520.000	T	105.00000	54600.00	92.00000	47840.00	115.00000	59800.00
HOT MIX ASPHALT 12.5 MM BASE								
0090 409.15	172.000	G	11.00000	1892.00	12.00000	2064.00	12.00000	2064.00
BITUMINOUS TACK COAT - APPLIED								
0100 411.131	1040.000	SF	1.50000	1560.00	2.00000	2080.00	2.00000	2080.00
STONE DUST SURFACE COURSE								
0110 430.25	10.000	SY	110.00000	1100.00	110.00000	1100.00	130.00000	1300.00
COBBLESTONE PAVEMENT REMOVE AND RESET								
0120 501.231	4.000	EA	3800.00000	15200.00	5000.00000	20000.00	5000.00000	20000.00
DYNAMIC LOADING TEST								
0130 501.50	500.000	LF	55.00000	27500.00	70.00000	35000.00	75.00000	37500.00
STEEL H-BEAM PILES 89 LBS/FT, DELIVERED								
0140 501.501	500.000	LF	15.00000	7500.00	10.00000	5000.00	11.00000	5500.00
STEEL H-BEAM PILES 89 LBS/FT, IN PLACE								
0150 501.70	664.000	LF	250.00000	166000.00	160.00000	106240.00	175.00000	116200.00
STEEL PIPE PILES, DELIVERED								
0160 501.701	664.000	LF	60.00000	39840.00	42.00000	27888.00	55.00000	36520.00
STEEL PIPE PILES, IN PLACE								
0170 501.90	22.000	EA	625.00000	13750.00	700.00000	15400.00	1000.00000	22000.00
PILE TIPS								
0180 501.91	44.000	EA	100.00000	4400.00	10.00000	440.00	1.00000	44.00
PILE SPLICES								
0190 501.92		LUMP	25000.00000	25000.00	170000.00000	170000.00	138000.00000	138000.00
PILE DRIVING EQUIPMENT MOBILIZATION								

COUNTIE(S) : YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

=====

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		( 4 ) 000032 REED & REED, INC.		( 5 ) 000416 T. BUCK CONSTRUCTION, INC.		( 6 ) 004202 NEW ENGLAND INFRASTRUCTURE	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0200 502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	70.000	LS	70000.00000	70000.00	35000.00000	35000.00	40000.00000	40000.00
0210 502.239 STRUCTURAL CONCRETE PIERS	55.000	LS	90000.00000	90000.00	50000.00000	50000.00	36000.00000	36000.00
0220 502.25 STRUCTURAL CONCRETE SUPERSTRUCTURE SLAB	108.000	LS	115000.00000	115000.00	85000.00000	85000.00	130000.00000	130000.00
0230 502.31 STRUCTURAL CONCRETE APPROACH SLABS	25.000	LS	10000.00000	10000.00	10000.00000	10000.00	10000.00000	10000.00
0240 502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	61.000	LS	40000.00000	40000.00	25000.00000	25000.00	34000.00000	34000.00
0250 503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	20000.000	LB	0.70000	14000.00	0.50000	10000.00	0.64000	12800.00
0260 503.13 REINFORCING STEEL, PLACING	20000.000	LB	0.52000	10400.00	0.50000	10000.00	0.40000	8000.00
0270 506.9105 POLYUREA ELASTOMER COATING ALLOWANCE		LUMP	46824.00000	46824.00	46824.00000	46824.00	46824.00000	46824.00
0280 507.0811 STEEL BRIDGE RAILING, 2 BAR	161.000	LS	19000.00000	19000.00	18500.00000	18500.00	19000.00000	19000.00
0290 507.0831 STEEL BRIDGE RAILING, 4 BAR	161.000	LS	26000.00000	26000.00	25000.00000	25000.00	26000.00000	26000.00
0300 508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	630.000	LS	13000.00000	13000.00	12000.00000	12000.00	12000.00000	12000.00
0310 510.10 SPECIAL DETOUR _____ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 11'		LUMP	325000.00000	325000.00	353000.00000	353000.00	449000.00000	449000.00
0320 511.07 COFFERDAM: ABUT NO.1		LUMP	20000.00000	20000.00	15000.00000	15000.00	46000.00000	46000.00
0330 511.07 COFFERDAM: ABUT NO.2		LUMP	20000.00000	20000.00	15000.00000	15000.00	46000.00000	46000.00
0340 514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000	EA	1500.00000	1500.00	1500.00000	1500.00	3000.00000	3000.00
0350 515.20 PROTECTIVE COATING FOR CONCRETE SURFACE	385.000	SY	5.00000	1925.00	4.00000	1540.00	4.00000	1540.00
0360 526.301 TEMPORARY CONCRETE BARRIER TYPE I	100.000	LS	5000.00000	5000.00	3000.00000	3000.00	15000.00000	15000.00
0370 526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000	EA	2800.00000	11200.00	2250.00000	9000.00	2700.00000	10800.00
0380 527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	2.000	EA	2400.00000	4800.00	2400.00000	4800.00	2500.00000	5000.00

COUNTIE(S) : YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

=====

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		( 4 ) 000032 REED & REED, INC.		( 5 ) 000416 T. BUCK CONSTRUCTION, INC.		( 6 ) 004202 NEW ENGLAND INFRASTRUCTURE	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0390 527.34 WORK ZONE CRASH CUSHIONS	2.000 UN		3500.00000	7000.00	2000.00000	4000.00	5000.00000	10000.00
0400 535.60 PRESTRESSED STRUCTURAL CONCRETE SLAB	296.000 LS		440000.00000	440000.00	390000.00000	390000.00	470000.00000	470000.00
0410 606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA		1500.00000	6000.00	1500.00000	6000.00	2000.00000	8000.00
0420 606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	425.000 LF		16.00000	6800.00	16.00000	6800.00	20.00000	8500.00
0430 606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	40.000 LF		16.00000	640.00	16.00000	640.00	28.00000	1120.00
0440 606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA		50.00000	100.00	50.00000	100.00	60.00000	120.00
0450 606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA		35.00000	210.00	35.00000	210.00	52.00000	312.00
0460 608.08 REINFORCED CONCRETE SIDEWALK	48.000 SY		80.00000	3840.00	70.00000	3360.00	55.00000	2640.00
0470 608.26 CURB RAMP DETECTABLE WARNING FIELD	50.000 SF		35.00000	1750.00	50.00000	2500.00	25.00000	1250.00
0480 609.19 VERTICAL CURB TYPE 2	50.000 LF		26.00000	1300.00	30.00000	1500.00	40.00000	2000.00
0490 609.38 RESET CURB TYPE 1	100.000 LF		22.00000	2200.00	20.00000	2000.00	28.00000	2800.00
0500 610.08 PLAIN RIPRAP	570.000 CY		70.00000	39900.00	110.00000	62700.00	55.00000	31350.00
0510 613.319 EROSION CONTROL BLANKET	23.000 SY		3.00000	69.00	4.00000	92.00	4.00000	92.00
0520 615.07 LOAM	25.000 CY		75.00000	1875.00	45.00000	1125.00	45.00000	1125.00
0530 618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	4.000 UN		75.00000	300.00	75.00000	300.00	30.00000	120.00
0540 619.1201 MULCH - PLAN QUANTITY	4.000 UN		25.00000	100.00	25.00000	100.00	15.00000	60.00
0550 619.1401 EROSION CONTROL MIX	30.000 CY		50.00000	1500.00	45.00000	1350.00	60.00000	1800.00
0560 620.58 EROSION CONTROL GEOTEXTILE	425.000 SY		2.00000	850.00	4.00000	1700.00	3.00000	1275.00
0570 627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2700.000 LF		0.30000	810.00	0.30000	810.00	0.60000	1620.00

COUNTIE(S): YORK

TABULATION OF BIDS

CONTRACT ID : 017079.00

=====

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		( 4 ) 000032 REED & REED, INC.		( 5 ) 000416 T. BUCK CONSTRUCTION, INC.		( 6 ) 004202 NEW ENGLAND INFRASTRUCTURE	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0580 629.05 HAND LABOR, STRAIGHT TIME	40.000	HR	45.00000	1800.00	45.00000	1800.00	40.00000	1600.00
0590 631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000	HR	130.00000	5200.00	115.00000	4600.00	120.00000	4800.00
0600 631.14 GRADER (INCLUDING OPERATOR)	40.000	HR	200.00000	8000.00	150.00000	6000.00	120.00000	4800.00
0610 631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	20.000	HR	90.00000	1800.00	100.00000	2000.00	100.00000	2000.00
0620 631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000	HR	75.00000	3000.00	70.00000	2800.00	70.00000	2800.00
0630 631.20 STUMP CHIPPER (INCLUDING OPERATOR)	4.000	HR	250.00000	1000.00	75.00000	300.00	80.00000	320.00
0640 639.18 FIELD OFFICE TYPE A	1.000	EA	9000.00000	9000.00	18000.00000	18000.00	38000.00000	38000.00
0650 643.72 TEMPORARY TRAFFIC SIGNAL		LUMP	12000.00000	12000.00	7500.00000	7500.00	85000.00000	85000.00
0660 652.312 TYPE III BARRICADE	4.000	EA	150.00000	600.00	250.00000	1000.00	150.00000	600.00
0670 652.33 DRUM	20.000	EA	75.00000	1500.00	30.00000	600.00	90.00000	1800.00
0680 652.34 CONE	40.000	EA	25.00000	1000.00	10.00000	400.00	25.00000	1000.00
0690 652.35 CONSTRUCTION SIGNS	200.000	SF	20.00000	4000.00	32.00000	6400.00	20.00000	4000.00
0700 652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000	LS	15000.00000	15000.00	1500.00000	1500.00	6000.00000	6000.00
0710 652.38 FLAGGER	300.000	HR	18.00000	5400.00	16.00000	4800.00	17.00000	5100.00
0720 656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL		LUMP	10000.00000	10000.00	12000.00000	12000.00	30000.00000	30000.00
0730 659.10 MOBILIZATION		LUMP	140000.00000	140000.00	219822.00000	219822.00	240000.00000	240000.00
SECTION TOTALS			\$	2,193,605.00	\$	2,220,000.00	\$	2,792,321.00
CONTRACT TOTALS			\$	2,193,605.00	\$	2,220,000.00	\$	2,792,321.00

=====