



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

David Bernhardt
COMMISSIONER

April 30, 2012
Subject: **Caribou Connector**
Federal Project No: HPP-6462(700)X
State PIN: 006462.70
Amendment No. 4

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 4 thru 9) **REMOVE** the "SCHEDULE OF ITEMS" 6 pages dated 120406 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 6 pages dated 120430.

In the Bid Book (page 32) "Construction Notes" Item 607.33; **CHANGE** the "NOTE" and the six stations that follow in pen and ink to read as follows:

Note: Line Posts and Intermediate Posts (1 per 660 LF if no corner/end post used).

Station	to	Station	Side	Intermediate Posts
4300+80		4337+87	RT	<u>6</u>
4305+25		4337+92	LT	<u>5</u>
4378+00		4419+42	RT	<u>4</u>
4378+55		4417+90	LT	<u>4</u>
4419+37		4492+72	LT	<u>9</u>
4420+50		4492+80	RT	<u>10</u>

In the Bid Book (page 35) "GENERAL NOTES" **DELETE** in its entirety Note 11) and **REPLACE** with the following in pen and ink;

"11) See "Construction Notes" page 29 to 32 for layout of:

Item 607.09 Woven Wire Fence – Metal Posts

Item 607.15 Driveway Gate 16 Foot – Metal

Item 607.32 Bracing Assembly Type I – Metal Posts

Item 607.33 Bracing Assembly Type II – Metal Posts"



PRINTED ON RECYCLED PAPER

The following questions have been received:

Question: On page 32 (Construction Notes) – Item 607.33 – note reads 1 Brace Assembly every 330 LF. On page 6-27 of the Standard Spec book, Item 607.04 w/w fence reads bracing will not be required except @ intervals of 660 FT – Please Clarify.

Response: Brace assembly spacing of 660' interval is correct. This will result in a reduction of Type II bracing assemblies. Please see the attached new Schedule of Items.

Question: On page 35 – General Note #11 refers to Special Provision 607.09. Can't find this in the book?

Response: General Note 11) has been replaced, please see the above pen and ink change.

Question: Please clarify; is Woven Wire, 1047-12-9/11, Class #1 or Class #3? Spec Book reads CL3, the Standard Detail Book reads CL1 – see 607(05), Note #3

Response: Class #3 is correct for woven wire fence specification for all locations except gates. At Gate locations, wire for gates shall conform to A.S.T.M. A116, Class 1, Design No. 1047-12-11.

Consider these changes and information prior to submitting your bid on May 2, 2012.

Sincerely,

A handwritten signature in blue ink, appearing to read "G. M. A. Macdougall", is written over the typed name. To the left of the signature, the letters "for" are handwritten in blue ink.

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.70

PROJECT(S): HPP-6462(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 Project Items						
0010	202.203 PAVEMENT BUTT JOINTS	130.000 SY				
0020	203.242 DIRTY BORROW	150.000 CY				
0030	304.13 DENSE GRADED CRUSHED AGGREGATE SUBBASE	160.000 CY				
0040	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	2250.000 T				
0050	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	80.000 T				
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	50.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	710.000 G				
0080	504.07 CONCRETE PIPE TIES	1.000 GP				
0090	603.209 30 INCH CULVERT PIPE OPTION III	140.000 LF				
0100	603.225 42 INCH REINFORCED CONCRETE PIPE CLASS III	8.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.70

PROJECT(S): HPP-6462(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	2450.000 LF				
0120	606.35 GUARDRAIL DELINEATOR POST	8.000 EA				
0130	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0140	607.09 WOVEN WIRE FENCE - METAL POSTS	32123.000 LF				
0150	607.15 DRIVE GATEWAY 16 FOOT - METAL	3.000 EA				
0160	607.32 BRACING ASSEMBLY TYPE I - METAL POSTS	28.000 EA				
0170	607.33 BRACING ASSEMBLY TYPE II - METAL POSTS	86.000 EA				
0180	609.34 CURB TYPE 5	500.000 LF				
0190	609.35 CURB TYPE 5 - CIRCULAR	9.000 LF				
0200	610.08 PLAIN RIPRAP	30.000 CY				
0210	612.06 BITUMINOUS SEALING - BLACK	110.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.70

PROJECT(S): HPP-6462(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	68.000 UN				
0230	619.1201 MULCH - PLAN QUANTITY	68.000 UN				
0240	620.58 EROSION CONTROL GEOTEXTILE	20.000 SY				
0250	621.026 EVERGREEN TREES (3 FOOT - 4 FOOT) GROUP B	300.000 EA				
0260	621.032 EVERGREEN TREES (4 FOOT - 5 FOOT) GROUP B	200.000 EA				
0270	621.038 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP B	400.000 EA				
0280	621.044 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP B	120.000 EA				
0290	621.047 EVERGREEN TREES (8 FOOT - 9 FOOT) GROUP B	40.000 EA				
0300	621.052 EVERGREEN TREES (10 FOOT - 12 FOOT) GROUP A	12.000 EA				
0310	621.202 MEDIUM DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP B	10.000 EA				
0320	621.256 LARGE DECIDUOUS TREES (8 FOOT - 10 FOOT) GROUP B	24.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.70

PROJECT(S): HPP-6462(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	621.273 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	20.000 EA				
0340	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	150.000 EA				
0350	621.552 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP A	450.000 EA				
0360	621.558 DECIDUOUS SHRUBS (4 FOOT - 5 FOOT) GROUP A	50.000 EA				
0370	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0380	626.11 PRECAST CONCRETE JUNCTION BOX	1.000 EA				
0390	626.21 METALLIC CONDUIT	50.000 LF				
0400	626.22 NON-METALLIC CONDUIT	530.000 LF				
0410	626.32 24 INCH FOUNDATION	6.000 EA				
0420	626.35 CONTROLLER CABINET FOUNDATION	1.000 EA				
0430	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	22100.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.70

PROJECT(S): HPP-6462(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	190.000 SF				
0450	627.77 REMOVING PAVEMENT MARKINGS	780.200 SF				
0460	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0470	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0480	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	10.000 HR				
0490	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				
0500	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0510	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0520	634.16 HIGHWAY LIGHTING	LUMP	LUMP			
0530	634.2042 LED LUMINARIES	6.000 EA				
0540	634.21 CONVENTIONAL LIGHT STANDARD	6.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.70

PROJECT(S): HPP-6462(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	652.33 DRUM	10.000				
	EA					
0560	652.34 CONE	20.000				
	EA					
0570	652.35 CONSTRUCTION SIGNS	180.000				
	SF					
0580	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	80.000				
	CD					
0590	652.38 FLAGGER	50.000				
	HR					
0600	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	720.000				
	SY					
0610	659.10 MOBILIZATION	LUMP	LUMP			
	TOTAL BID					