



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

August 5, 2011
Subject: **Newburgh**
State PIN: 017119.00
Amendment No. 1

David Bernhardt
COMMISSIONER

Dear Sir/Ms:

The following questions have been received:

Question: Does the Department have any geotechnical information to support the quantity of rock excavation estimated for this job?

Response: No geotechnical information work was done to support the excavation quantities. These are estimates based on land features.

Question: The cross culvert at approx. station 12+20 is new and has been installed recently. Is this pipe to be removed and replaced as indicated in the bid documents?

Response: The cross culvert will need to be removed and replaced in order to change the inlet elevations. The bid documents are accurate.

Question: The driveway pipe at approx. station 22+31 is on the right on the plan view. It shows as being on the left in the cross sections (12+31). In the intention to put a new driveway on the left side or the right or both?

Response: At STA 22+31 a driveway culvert will be replaced on the right. This is shown on the right side in both the plan view and in the cross sections at that station. At STA 12+33 the cross culvert inlet is shown on the left. Please contact us again if you still have questions regarding this issue.

Consider this information prior to submitting your bid on August 10, 2011.

Sincerely,



For Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER