



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Janet T. Mills  
GOVERNOR

Bruce A. Van Note  
COMMISSIONER

February 7, 2023  
Subject: Acadia Gateway  
State WIN: 017163.03  
Location: **Trenton**  
**Amendment No. 10**

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

**REMOVE** from Amendment No. 9, Proposal Schedule of Items, 13 pages, dated 3/6/2023 and **REPLACE** with the attached, revised Proposal Schedule of Items, 13 pages, dated 3/7/2023.

The following questions have been received:

**Question:** Is the intent that the new EV charger line items be priced only from the buried and divided junction boxes, which were part of the Div. 26 price from the start? Given the late notice of this change, this is the only reasonable request.

**Response:** The new line items for EV Chargers include purchasing and installing the chargers on the foundation. The charger foundations are paid under 502.311 associated with the chargers. The conduit and wire are included in Division 26.

**Question:** Related to Spec Section 11 11 36 Vehicle Charging Equipment Spec. In Amendment 7, Note 2 on C103 states that the Concrete Pad for a Level 3 EV Charger shall be 85"L x 50"W x 72"D. Please confirm the Depth required for this type of Concrete Pad. Level 2 charger foundations are only six inches thick and Level 3 foundations are six feet requiring deep excavations. Also, please revisit the bid item quantity of 5CY for 502.311 Site Concrete EV Charger Building & Charger Base. The spread footing and walls for the EV Charger Building is more than 5 CY's without even considering the EV Chargers.

**Response:** Level 3 EV Charger pad shall be by basis of design manufacturer's recommendation of 85"L x 50"W x 72"D (72" D is based on 5' frost depth + 12").

**Question:** On plan C103 it calls for Level 3 Charges to have an 85" x 50" x 72" foundation with only a top and bottom area to have steel, is this correct and what item covers the cost?

**Response:** Level 3 charger base is sized per basis of design manufacturer's recommendations. The charger foundations are paid under 502.311.

**Question:** Please confirm the dimensions of level III charger pads.

**Response:** Level 3 EV Charger pad shall be by basis of design manufacturer's recommendations of 85"L x 50"W x 72"D (72"D is based on 5' frost depth + 12").

Consider these changes and information prior to submitting your bid on **February 8, 2023**.

Sincerely,



George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	8.100 AC	_____	 _____	_____	 _____
0020	203.20 COMMON EXCAVATION	10,355.000 CY	_____	 _____	_____	 _____
0030	203.21 ROCK EXCAVATION	10.000 CY	_____	 _____	_____	 _____
0040	203.24 COMMON BORROW	5,737.000 CY	_____	 _____	_____	 _____
0050	203.25 GRANULAR BORROW	2,657.000 CY	_____	 _____	_____	 _____
0060	203.29 SELECTED GRANULAR MATERIAL	1,335.000 CY	_____	 _____	_____	 _____
0070	203.38 FILTER SAND	205.000 CY	_____	 _____	_____	 _____
0080	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	10.000 CY	_____	 _____	_____	 _____
0090	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	10.000 CY	_____	 _____	_____	 _____
0100	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	9,360.000 CY	_____	 _____	_____	 _____
0110	304.14 AGGREGATE BASE COURSE - TYPE A	3,095.000 CY	_____	 _____	_____	 _____
0120	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	1,529.000 T	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	134.000 T	_____	 _____	_____	 _____
0140	403.213 HOT MIX ASPHALT 12.5 MM BASE	3,266.000 T	_____	 _____	_____	 _____
0150	409.15 BITUMINOUS TACK COAT - APPLIED	2,682.000 G	_____	 _____	_____	 _____
0160	419.30 SAW CUTTING BITUMINOUS PAVEMENT	525.000 LF	_____	 _____	_____	 _____
0170	502.311 SITE CONCRETE BUS SHELTER	5.000 CY	_____	 _____	_____	 _____
0180	502.311 SITE CONCRETE EV CHARGER BUILDING & CHARGER BASE	62.000 CY	_____	 _____	_____	 _____
0190	502.311 SITE CONCRETE INFORMATION KIOSK	10.000 CY	_____	 _____	_____	 _____
0200	502.342 STRUCTURAL CONCRETE ROADWAY TRUCK APRON	3.000 CY	_____	 _____	_____	 _____
0210	502.602 STRUCTURAL CONCRETE, GENERATOR SLAB	LUMP SUM	_____	 LUMP SUM	_____	 _____
0220	502.603 STRUCTURAL CONCRETE, CONDENSER PAD	LUMP SUM	_____	 LUMP SUM	_____	 _____
0230	502.607 STRUCTURAL CONCRETE, STORAGE PAD DUMPSTER	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	525.19 GRANITE SEATING BLOCKS	37.000 EA	_____	 _____	_____	 _____
0250	603.142 10" CULV PIPE OPTION III	93.000 LF	_____	 _____	_____	 _____
0260	603.159 12 INCH CULVERT PIPE OPTION III	1,189.000 LF	_____	 _____	_____	 _____
0270	603.169 15 INCH CULVERT PIPE OPTION III	404.000 LF	_____	 _____	_____	 _____
0280	603.179 18 INCH CULVERT PIPE OPTION III	348.000 LF	_____	 _____	_____	 _____
0290	603.199 24 INCH CULVERT PIPE OPTION III	200.000 LF	_____	 _____	_____	 _____
0300	603.801 24" TRASH RACK	2.000 EA	_____	 _____	_____	 _____
0310	604.077 72 INCH CATCH BASIN TYPE A1-C	1.000 EA	_____	 _____	_____	 _____
0320	604.131 4' DIAMETER CATCH BASIN	12.000 EA	_____	 _____	_____	 _____
0330	604.15 MANHOLE	8.000 EA	_____	 _____	_____	 _____
0340	604.154 72 INCH MANHOLE	1.000 EA	_____	 _____	_____	 _____
0350	604.1542 72 INCH OUTLET CONTROL STRUCTURE	2.000 EA	_____	 _____	_____	 _____
0360	604.24 CATCH BASIN TYPE F	16.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	605.081 4" LINER UNDERDRAIN	386.000 LF	_____	 _____	_____	 _____
0380	605.082 4" FOUNDATION DRAIN	1,000.000 LF	_____	 _____	_____	 _____
0390	605.091 6" WET POND UNDERDRAIN	32.000 LF	_____	 _____	_____	 _____
0400	605.109 10" UNDERDRAIN TYPE C	505.000 LF	_____	 _____	_____	 _____
0410	605.11 12 INCH UNDERDRAIN TYPE C	910.000 LF	_____	 _____	_____	 _____
0420	605.12 15 INCH UNDERDRAIN TYPE C	127.000 LF	_____	 _____	_____	 _____
0430	605.19 6 INCH LONGITUDINAL UNDERDRAIN	630.000 LF	_____	 _____	_____	 _____
0440	605.31 UNDERDRAIN CLEANOUT	8.000 EA	_____	 _____	_____	 _____
0450	608.251 PRECAST CONCRETE PAVERS	3,000.000 SY	_____	 _____	_____	 _____
0460	608.26 CURB RAMP DETECTABLE WARNING FIELD	308.000 SF	_____	 _____	_____	 _____
0470	609.11 VERTICAL CURB TYPE 1	2,229.000 LF	_____	 _____	_____	 _____
0480	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	1,268.000 LF	_____	 _____	_____	 _____
0490	609.26 CURB TRANSITION SECTION B TYPE 1	2.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0500	610.08 PLAIN RIPRAP	20.000 CY	_____	 _____	_____	 _____
0510	610.21 RIVER STONES	27.000 CY	_____	 _____	_____	 _____
0520	610.61 NATURAL BOULDER TYPE A 36"X36" - 42"X42"	26.000 EA	_____	 _____	_____	 _____
0530	610.61 NATURAL BOULDER TYPE B 24"X24" - 36"X36"	33.000 EA	_____	 _____	_____	 _____
0540	610.61 NATURAL BOULDER TYPE C 18"X18" - 24"X24"	24.000 EA	_____	 _____	_____	 _____
0550	615.20 UNCOMPACTED SOIL FILTER MEDIUM	100.000 CY	_____	 _____	_____	 _____
0560	616.09 RHODORA SODDING	60.000 SY	_____	 _____	_____	 _____
0570	616.10 HUCKLEBERRY SODDING	160.000 SY	_____	 _____	_____	 _____
0580	616.11 HAY-SCENTED FERN SODDING	340.000 SY	_____	 _____	_____	 _____
0590	617.33 SUPERHUMUS TOPSOIL	2,292.000 CY	_____	 _____	_____	 _____
0600	618.14 SEEDING METHOD NUMBER 2	10.000 UN	_____	 _____	_____	 _____
0610	618.147 WETLAND SEEDING	6.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0620	618.149 SPECIAL SEED MIX LAWN	7.000 UN	_____	 _____	_____	 _____
0630	618.20 ANNUAL RYE GRASS SEED	200.000 LB	_____	 _____	_____	 _____
0640	618.27 MEADOW SEEDING MEADOW	21.000 UN	_____	 _____	_____	 _____
0650	618.29 RETENTION POND SEEDING	2.000 UN	_____	 _____	_____	 _____
0660	619.12 MULCH	10.000 UN	_____	 _____	_____	 _____
0670	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	10.000 SY	_____	 _____	_____	 _____
0680	621.037 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP A	6.000 EA	_____	 _____	_____	 _____
0690	621.043 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP A	43.000 EA	_____	 _____	_____	 _____
0700	621.046 EVERGREEN TR (8' - 10') GP A	33.000 EA	_____	 _____	_____	 _____
0710	621.052 EVERGREEN TREES (10 FOOT - 12 FOOT) GROUP A	32.000 EA	_____	 _____	_____	 _____
0720	621.201 MEDIUM DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	5.000 EA	_____	 _____	_____	 _____
0730	621.255 LARGE DECIDUOUS TREES (8 FOOT - 10 FOOT) GROUP A	21.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0740	621.263 LARGE DECIDUOUS TREES (10 FOOT - 12 FOOT) GROUP C	33.000 EA	_____	 _____	_____	 _____
0750	621.2641 MULTISTEM DECIDUOUS TREE (RIVER BIRCH) GROUP A	24.000 EA	_____	 _____	_____	 _____
0760	621.273 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	30.000 EA	_____	 _____	_____	 _____
0770	621.274 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP B	13.000 EA	_____	 _____	_____	 _____
0780	621.279 LARGE DECIDUOUS TREE (2.50 INCH - 3 INCH CALIPER) GROUP A	10.000 EA	_____	 _____	_____	 _____
0790	621.285 LARGE DECIDUOUS TREE (3 INCH - 3.50 INCH CALIPER) GROUP A	39.000 EA	_____	 _____	_____	 _____
0800	621.291 LARGE DECIDUOUS TREE (3.50 INCH - 4 INCH CALIPER) GROUP A	3.000 EA	_____	 _____	_____	 _____
0810	621.292 LARGE DECIDUOUS TREE (3.50 INCH - 4 INCH CALIPER) GROUP B	1.000 EA	_____	 _____	_____	 _____
0820	621.391 EVERGREENS (15 INCH - 18 INCH) GROUP C	204.000 EA	_____	 _____	_____	 _____
0830	621.50 BROADLEAF EVERGREEN (2.50 FOOT - 3 FOOT) GROUP C	3.000 EA	_____	 _____	_____	 _____
0840	621.525 BAYBERRY (2 FOOT - 3 FOOT)	64.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0850	621.542 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP C	3.000 EA	_____	 _____	_____	 _____
0860	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	450.000 EA	_____	 _____	_____	 _____
0870	621.547 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP B	336.000 EA	_____	 _____	_____	 _____
0880	621.548 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP C	13.000 EA	_____	 _____	_____	 _____
0890	621.552 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP A	4.000 EA	_____	 _____	_____	 _____
0900	621.553 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP B	3.000 EA	_____	 _____	_____	 _____
0910	621.554 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP C	6.000 EA	_____	 _____	_____	 _____
0920	621.558 DECIDUOUS SHRUBS (4 FOOT - 5 FOOT) GROUP A	11.000 EA	_____	 _____	_____	 _____
0930	621.662 VINES (18 INCH - 24 INCH) GROUP C	4.000 EA	_____	 _____	_____	 _____
0940	621.711 HERBACEOUS PERENNIALS GROUP B	200.000 EA	_____	 _____	_____	 _____
0950	621.98 METAL LANDSCAPE EDGING	1,600.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0960	625.23 IRRIGATION SYSTEM	LUMP SUM	LUMP SUM		_____	_____
0970	627.18 12 " SOLID WHITE PAVEMENT MARKING	160.000 LF	_____	_____	_____	_____
0980	627.71 4 INCH WHITE PAVEMENT MARKING LINE	2,792.000 LF	_____	_____	_____	_____
0990	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	9,070.000 SF	_____	_____	_____	_____
1000	634.228 CONCRETE TRANSFORMER PAD GENERATOR PAD	2.000 EA	_____	_____	_____	_____
1010	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	_____	_____	_____
1020	641.34 TRASH RECEPTACLE	4.000 EA	_____	_____	_____	_____
1030	641.35 ALUMINUM FLAG POLE	2.000 EA	_____	_____	_____	_____
1040	643.60 FLASHING BEACON AT: Gateway Drive / Bar harbor Road	LUMP SUM	LUMP SUM		_____	_____
1050	652.312 TYPE III BARRICADE	10.000 EA	_____	_____	_____	_____
1060	652.33 DRUM	25.000 EA	_____	_____	_____	_____
1070	652.34 CONE	100.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1080	652.35 CONSTRUCTION SIGNS	500.000 SF	_____	 _____	_____	 _____
1090	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
1100	652.38 FLAGGER	1,000.000 HR	_____	 _____	_____	 _____
1110	655.12 ELECTRIC VEHICLE CHARGING STATION - LEVEL 2 DUAL PORT	4.000 EA	_____	 _____	_____	 _____
1120	655.12 ELECTRIC VEHICLE CHARGING STATION - LEVEL 2 SINGLE PORT	1.000 EA	_____	 _____	_____	 _____
1130	655.13 ELECTRIC VEHICLE CHARGING STATION - LEVEL 3 SINGLE PORT	8.000 EA	_____	 _____	_____	 _____
1140	655.40 PHOTOVOLTAIC SYSTEM	LUMP SUM	LUMP SUM		_____	 _____
1150	656.71 LEVEL LIP SPREADER	86.000 CY	_____	 _____	_____	 _____
1160	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
1170	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
1180	801.014 PUMP STATION 8 FOOT DIAMETER	1.000 EA	_____	 _____	_____	 _____
1190	801.121 SEWER FORCE MAIN 2.5 INCH	1,120.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1200	801.17 8 INCH PVC SANITARY SEWER (SDR-35)	230.000 LF	_____	 _____	_____	 _____
1210	802.103 WATERLINE 2 INCH	LUMP SUM	LUMP SUM		_____	 _____
1220	802.20 SEPTIC TANKS - SEPTIC/DOSING TANK, 14,000 GAL	1.000 EA	_____	 _____	_____	 _____
1230	802.20 SEPTIC TANKS 10,000 GALLON	1.000 EA	_____	 _____	_____	 _____
1240	802.20 SEPTIC TANKS 20,000 GALLON	1.000 EA	_____	 _____	_____	 _____
1250	802.2011 STORAGE TANK	LUMP SUM	LUMP SUM		_____	 _____
1260	802.23 SUBSURFACE WASTEWATER DISPOSAL SYSTEM	LUMP SUM	LUMP SUM		_____	 _____
1270	803.01 TEST PITS	3.000 EA	_____	 _____	_____	 _____
1280	803.173 SEWER MANHOLE - 4 FOOT DIAMETER	4.000 EA	_____	 _____	_____	 _____
1290	803.173 SEWER MANHOLE - 4 FOOT DIAMETER CLEANOUT	3.000 EA	_____	 _____	_____	 _____
1300	822.301 PRE-INSULATED DUCTILE IRON PIPE	5.000 LF	_____	 _____	_____	 _____
1310	823.325 8 INCH GATE VALVE	1.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1320	823.33 6 INCH GATE VALVE WITH BOX	1.000 EA	_____	 _____	_____	 _____
1330	823.3351 4 INCH GATE VALVE AND BOX	1.000 EA	_____	 _____	_____	 _____
1340	824.50 FIRE SUPPRESSION TANK	LUMP SUM	LUMP SUM		_____	 _____
1350	832.071 CONTRACTOR ALLOWANCE Fiber Optic Service	LUMP SUM	LUMP SUM		5,000.00	
1360	832.071 CONTRACTOR ALLOWANCE Telephone Service	LUMP SUM	LUMP SUM		5,000.00	
1370	832.071 CONTRACTOR ALLOWANCE Versant Power	LUMP SUM	LUMP SUM		60,000.00	
1380	834.323 DRY HYDRANT	LUMP SUM	LUMP SUM		_____	 _____
1390	841.48 BOLLARDS	3.000 EA	_____	 _____	_____	 _____
1400	890.07 BIKE RACKS	20.000 EA	_____	 _____	_____	 _____
1410	910.30 SPECIAL WORK 20,000 GAL OXYPRO UNIT	2.000 EA	_____	 _____	_____	 _____
1420	DIV. 10 SPECIALTIES MISC SPECIALITIES	LUMP SUM	LUMP SUM		_____	 _____
1430	DIV. 12 FURNISHINGS	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 017163.03

Project(s): 017163.03

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1440	DIV. 21 FIRE SUPPRESSION	LUMP SUM	LUMP	SUM	_____	_____
1450	DIV. 22 PLUMBING	LUMP SUM	LUMP	SUM	_____	_____
1460	DIV. 23 HVAC	LUMP SUM	LUMP	SUM	_____	_____
1470	DIV. 26 ELECTRICAL	LUMP SUM	LUMP	SUM	_____	_____
1480	DIV. 3 CONCRETE	LUMP SUM	LUMP	SUM	_____	_____
1490	DIV. 4 MASONRY	LUMP SUM	LUMP	SUM	_____	_____
1500	DIV. 5 METALS	LUMP SUM	LUMP	SUM	_____	_____
1510	DIV. 6 WOOD & PLASTICS	LUMP SUM	LUMP	SUM	_____	_____
1520	DIV. 7 THERMAL & MOISTURE PROTECTION	LUMP SUM	LUMP	SUM	_____	_____
1530	DIV. 8 DOORS & WINDOWS	LUMP SUM	LUMP	SUM	_____	_____
1540	DIV. 9 FINISHES	LUMP SUM	LUMP	SUM	_____	_____
<b>Section: 1</b>			<b>Total:</b>		_____	_____
			<b>Total Bid:</b>		_____	_____