



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

December 13, 2011
Subject: **Arundel**
State PIN: 017867.00
Amendment No. 1

David Bernhardt
COMMISSIONER

Dear Sir/Ms:

Make the following changes to the Bid Document:

In the Bid Book (pages 4 thru7) **REMOVE** the "SCHEDULE OF ITEMS" 4 pages dated 111205 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 5 pages dated 111212.

In the Bid Book, after page 39, **ADD** the attached "SPECIAL PROVISION, SECTION 203, CRUSHED STONE", 1 page dated December 2011.

In the Plans, Sheet Number 2 of 18, "ESTIMATED QUANTITIES" **ADD** the following item in pen and ink;

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
<u>203.35</u>	<u>CRUSHED STONE</u>	<u>215.000</u>	<u>CY</u>


The following question has been received:

Question: The Transverse Section detail on sheet 15 of the project plans refers to Special Provision 203 for the crushed stone. I do not see the provision in the Contract Book.

Response: Special Provision 203 has been added, please see the above changes.

Consider this change and information prior to submitting your bid on January 11, 2012.

Sincerely,


Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 1

SCHEDULE OF ITEMS

DATE: 111212

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	CY 810.000				
0030	203.21 ROCK EXCAVATION	CY 10.000				
0040	203.25 GRANULAR BORROW	CY 480.000				
0050	203.35 CRUSHED STONE FILL	CY 215.000				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 695.000				
0070	403.210 HOT MIX ASPHALT 9.5 MM	T 207.000				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	T 138.000				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	G 32.000				
0100	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

SCHEDULE OF ITEMS

DATE: 111212

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0120	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0130	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP	LUMP			
0140	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0150	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0160	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	LF 275.000				
0170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 8.000				
0180	606.79 GUARDRAIL 350 FLARED TERMINAL	EA 4.000				
0190	610.07 STONE FILL	CY 215.000				
0200	610.08 PLAIN RIPRAP	CY 440.000				
0210	615.07 LOAM	CY 45.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 3

SCHEDULE OF ITEMS

DATE: 111212

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	UN 7.000				
0230	619.1201 MULCH - PLAN QUANTITY	UN 7.000				
0240	620.54 STABILIZATION GEOTEXTILE	SY 950.000				
0250	620.58 EROSION CONTROL GEOTEXTILE	SY 280.000				
0260	620.65 REINFORCEMENT GEOGRID	SY 180.000				
0270	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	LF 750.000				
0280	629.05 HAND LABOR, STRAIGHT TIME	HR 40.000				
0290	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR 20.000				
0300	631.14 GRADER (INCLUDING OPERATOR)	HR 20.000				
0310	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	HR 20.000				
0320	639.19 FIELD OFFICE TYPE B	EA 1.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 4

SCHEDULE OF ITEMS

DATE: 111212

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0340	652.31 TYPE I BARRICADE	EA 1.000				
0350	652.312 TYPE III BARRICADE	EA 4.000				
0360	652.33 DRUM	EA 10.000				
0370	652.34 CONE	EA 20.000				
0380	652.35 CONSTRUCTION SIGNS	SF 250.000				
0390	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	CD 30.000				
0400	652.38 FLAGGER	HR 150.000				
0410	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0420	659.10 MOBILIZATION	LUMP	LUMP			
0430	834.322 DRY HYDRANT - INSTALL ONLY	LUMP	LUMP			
	SECTION 0001 TOTAL					

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 5

SCHEDULE OF ITEMS

DATE: 111212

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
	TOTAL BID					

SPECIAL PROVISION
SECTION 203
CRUSHED STONE

Description This work shall consist of constructing a leveling pad of crushed stone in accordance with these specifications and in reasonably close conformity with the width, grade and thickness shown on the plans or established by the Resident.

MATERIALS

Aggregate Crushed stone material shall meet the requirements of ASTM Standard Specification C33, Standard Specification for Concrete Aggregates.

The aggregate shall meet the following gradation requirements:

Particle size	Percent by Weight Passing
1 inch	100
$\frac{3}{4}$ inch	90 – 100
$\frac{1}{2}$ inch	20 – 55
$\frac{3}{8}$ inch	0 – 15
No. 4	0 - 5

Construction Requirements The crushed stone shall be placed and graded as shown on the plans or as directed by the Resident. The crushed stone shall be compacted as required to ensure that all voids in the stone are filled, as approved by the Resident.

Method of Measurement Aggregate for crushed stone will be measured by the cubic yard complete in place.

Basis of Payment The accepted quantity of crushed stone will be paid for at the contract unit price per cubic yard of aggregate complete in place.

Payment will be under

<u>Pay Item</u>	<u>Unit</u>
203.35 Crushed Stone	Cubic Yard