



STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 16 STATE HOUSE STATION
 AUGUSTA, MAINE 04333-0016

Paul R. LePage
 GOVERNOR

David Bernhardt
 COMMISSIONER

December 16, 2011
 Subject: **Arundel**
 State PIN: 017867.00
Amendment No. 2

Dear Sir/Ms:

Make the following changes to the Bid Document:

In the Bid Book (page 1) "NOTICE TO CONTRACTORS", first paragraph **CHANGE** the third sentence that begins "The lowest responsive bidder ..." to read as follows; **"The lowest responsive bidder must have completed, or successfully complete, a bridge, a highway, or project specific prequalification to be considered for the award of this contract."**

In the Bid Book (pages 4 thru7) **REMOVE** the "SCHEDULE OF ITEMS" 5 pages dated 111212 (Replaced in Amendment #1) and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 4 pages dated 111213.

In the Plans, Sheet Number 2 of 18, "ESTIMATED QUANTITIES" **DELETE** the following item in pen and ink;

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
<u>610.07</u>	<u>STONE FILL</u>	<u>215.000</u>	<u>CY</u>

The following questions have been received:

Question: In the "Notice To Contractors" it restricts the bidders to "Bridge" prequalification status. Can this project be opened to "Highway" Contractors as well?

Response: Yes, please see the above pen and ink change.

Question: Where does item 610.07 "Stone Fill" get utilized?

Response: Item 610.07 has been replaced by Item 203.35 Crushed Stone, and the material will be used as foundation/bedding under the box culvert. Please see he above change.



PRINTED ON RECYCLED PAPER

Question: Is item 524.301 "Temporary Structural Support" the pay item for the sheeting as shown to maintain one lane of traffic? If no, please explain where the temporary structural support is required?


Response: Item 524.301 is to pay for the roadway support used in order to maintain one lane of alternating traffic.

Question: Can you tell us if the material being supplied for the dry hydrant is PVC or ductile iron?

Response: The dry hydrant pipe will be PVC.

Consider this change and information prior to submitting your bid on January 11, 2012.

Sincerely,



Scott Bickford

Contracts & Specifications Engineer

For

SCHEDULE OF ITEMS

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	CY	810.000			
0030	203.21 ROCK EXCAVATION	CY	10.000			
0040	203.25 GRANULAR BORROW	CY	480.000			
0050	203.35 CRUSHED STONE FILL	CY	215.000			
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY	695.000			
0070	403.210 HOT MIX ASPHALT 9.5 MM	T	207.000			
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	T	138.000			
0090	409.15 BITUMINOUS TACK COAT - APPLIED	G	32.000			
0100	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0120	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0130	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP	LUMP			
0140	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0150	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0160	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	LF 275.000				
0170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 8.000				
0180	606.79 GUARDRAIL 350 FLARED TERMINAL	EA 4.000				
0190	610.08 PLAIN RIPRAP	CY 440.000				
0200	615.07 LOAM	CY 45.000				
0210	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	UN 7.000				

SCHEDULE OF ITEMS

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	619.1201 MULCH - PLAN QUANTITY	7.000 UN				
0230	620.54 STABILIZATION GEOTEXTILE	950.000 SY				
0240	620.58 EROSION CONTROL GEOTEXTILE	280.000 SY				
0250	620.65 REINFORCEMENT GEOGRID	180.000 SY				
0260	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	750.000 LF				
0270	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0280	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0290	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0300	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0310	639.19 FIELD OFFICE TYPE B	1.000 EA				
0320	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	652.31 TYPE I BARRICADE	EA 1.000				
0340	652.312 TYPE III BARRICADE	EA 4.000				
0350	652.33 DRUM	EA 10.000				
0360	652.34 CONE	EA 20.000				
0370	652.35 CONSTRUCTION SIGNS	SF 250.000				
0380	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	CD 30.000				
0390	652.38 FLAGGER	HR 150.000				
0400	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0410	659.10 MOBILIZATION	LUMP	LUMP			
0420	834.322 DRY HYDRANT - INSTALL ONLY	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					