



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

David Bernhardt
COMMISSIONER

May 6, 2011
Subject: **Winthrop & Manchester**
Federal Project No: STP-1803(700)X
State PIN: 018037.00
Amendment No. 5

Dear Sir/Ms:

Make the following change to the Bid Document:

In the Bid Book (pages 4 thru 9) **REMOVE** the "SCHEDULE OF ITEMS" 6 pages dated 110504 (replaced in amendment #4) and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 6 pages dated 110506.

The following question has been received:

Question: Amendment #4 reduced the 403.207 quantity to 900 tons because you are now repairing the concrete instead of removal. According to the 403 Special Provision the only other area for 403.207 is Reconstruction of Existing Shoulder Areas. The construction notes – item 205.41 list one area from sta. 697+98 to 710+23 RT. The quantity of 403.207 required for this area does not come anywhere close to 900 tons. Can you tell me where the additional 403.207 will be used?

Response: The correct quantity of 403.207 is 250 tons. Please see the attached new Schedule Of Items.

Consider these changes and information prior to submitting your bid on **May 11, 2011**.

Sincerely,

Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018037.00

PROJECT(S): STP-1803(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	31300.000 SY				
0020	202.203 PAVEMENT BUTT JOINTS	3300.000 SY				
0030	205.41 RECONSTRUCTION OF EXISTING SHOULDER PLAN QUANTITY	1400.000 SY				
0040	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	10.000 CY				
0050	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	5.000 CY				
0060	403.207 HOT MIX ASPHALT 19.0 MM HMA	250.000 T				
0070	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	3000.000 T				
0080	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	200.000 T				
0090	403.210 HOT MIX ASPHALT 9.5 MM	14300.000 T				
0100	403.211 HOT MIX ASPHALT (SHIMMING)	5900.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018037.00

PROJECT(S): STP-1803(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	11300.000 G				
0120	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	60.000 CY				
0130	518.32 REHABILITATION OF STRUCTURAL CONCRETE SLAB - FULL DEPTH	3000.000 SF				
0140	604.161 ALTERING CATCH BASIN	3.000 EA				
0150	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	10.000 EA				
0160	604.247 CATCH BASIN TYPE F5-C	1.000 EA				
0170	605.11 12 INCH UNDERDRAIN TYPE C	40.000 LF				
0180	606.178 GUARDRAIL BEAM	562.500 LF				
0190	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	25.000 LF				
0200	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF				
0210	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	25.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018037.00

PROJECT(S): STP-1803(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	5.000 EA				
0230	606.352 REFLECTORIZED BEAM GUARDRAIL DELINEATORS	225.000 EA				
0240	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	77.000 EA				
0250	606.362 GUARDRAIL ADJUSTED	1350.000 LF				
0260	606.3651 GUARDRAIL-REMOVE, MODIFY, AND RESET EXISTING TO 3D	1088.000 LF				
0270	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	30.000 EA				
0280	606.47 SINGLE WOOD POST	2.000 EA				
0290	606.51 MULTIPLE MAILBOX SUPPORT	2.000 EA				
0300	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0310	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0320	609.31 CURB TYPE 3	1600.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018037.00

PROJECT(S): STP-1803(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	609.34 CURB TYPE 5	290.000 LF				
0340	609.38 RESET CURB TYPE 1	1617.000 LF				
0350	609.40 RESET CURB TYPE 5	1517.000 LF				
0360	613.319 EROSION CONTROL BLANKET	2400.000 SY				
0370	615.07 LOAM	135.000 CY				
0380	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	460.000 UN				
0390	619.1201 MULCH - PLAN QUANTITY	460.000 UN				
0400	627.18 12 " SOLID WHITE PAVEMENT MARKING	1285.000 LF				
0410	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	143000.000 LF				
0420	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	7760.000 SF				
0430	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018037.00

PROJECT(S): STP-1803(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	629.05 HAND LABOR, STRAIGHT TIME	250.000 HR				
0450	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	250.000 HR				
0460	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	500.000 HR				
0470	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	8.000 HR				
0480	639.19 FIELD OFFICE TYPE B	1.000 EA				
0490	643.86 TRAFFIC SIGNAL LOOP DETECTORS	13.000 EA				
0500	652.33 DRUM	160.000 EA				
0510	652.34 CONE	280.000 EA				
0520	652.35 CONSTRUCTION SIGNS	2212.000 SF				
0530	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	144.000 CD				
0540	652.38 FLAGGER	4000.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018037.00

PROJECT(S): STP-1803(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA				
0560	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0570	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					.

SECTION 0002 UTILITY ITEMS

0580	812.162 ADJUSTING SEWER MANHOLE TO GRADE	8.000 EA				
0590	812.164 REBUILDING SEWER MANHOLE	14.000 EA				
	SECTION 0002 TOTAL					
	TOTAL BID					