



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

David Bernhardt
COMMISSIONER

June 16, 2011
Subject: **Caribou Salt Storage Building**
State Pin: 018120.10
Location: Caribou
Amendment No. 4

Dear Sir/Ms:

Make the following change to the Bid Document:

In the Bid Book (page 69), "SPECIAL PROVISION, SECTION 07611, METAL ROOFING", **DELETE** in its entirety PART 3 – EXECUTION, and **REPLACE** with the following in pen and ink:

PART 3 – EXECUTION

3.1 Inspection

- A. Contractor shall inspect the substrate prior to installing metal roofing to insure that the surface is sound and uniform. Correct any irregularities prior to proceeding with the work.

3.2 Installation

- A. Fasten metal panels to structural substrate with movable clips that are seamed into the standing seam side lap
- B. Fasten clips to structural substrate in accordance with manufacturer's recommendations.
- C. Panel to panel connections shall be made with a positive, standing lock seam, continuously locked or crimped together by mechanical means during installation.
- D. All side lap sealant shall be factory applied.
- E. Install accessories such as penetration flashings and eave closures in accordance with manufacturer's recommendations, as approved by the Department.



PRINTED ON RECYCLED PAPER

3.3 Final Inspection

- A. A final inspection of the roofing system shall be made by the roofing manufacturer's representative as soon as construction is complete. Coordinate final manufacturer's inspection with the Department. Provide written certification that the metal roof system has been installed in accordance with the manufacturer's recommendations.

Consider this change and information prior to submitting your bid on June 22, 2011.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford", written in a cursive style.

Scott Bickford
Contracts & Specifications Engineer