



STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 16 STATE HOUSE STATION
 AUGUSTA, MAINE 04333-0016

Paul R. LePage
 GOVERNOR

David Bernhardt
 COMMISSIONER

April 2, 2012
 Subject: **Harrington**
 Federal Project No's: STP-1830(100)X &
 AC-STP-1918(900)X
 State PIN's: 018301.00 & 019189.00
Amendment No. 1

Dear Sir/Ms:

The following questions have been received:

Question: It is unclear where the quantity for items 403.209 Hot Mix Incidentals and the 409.10 Untreated Aggregate Surface Course are located. Please clarify where these items should be used.

Response: Item 403.209 will be placed at all the following locations unless directed differently by the resident. Item 411.10 will be used to back up driveway aprons at the following locations designated with a description of 'Apron'. It will also be used to back up pavement at the following locations as designated with a description of 'Paved' unless directed differently by the resident.

19189.00 Rte 1

Station	Side	Length	Width	Description
13+86	Left	25	3	Apron
42+90	Left	86	6	Paved
49+15	Left	25	3	Apron
51+05	Left	25	3	Apron
59+85	Left	35	6	Paved
60+68	Left	30	6	Paved
61+96	Left	25	6	Paved
69+06	Left	25	6	Paved
69+70	Left	25	3	Apron
72+98	Left	30	3	Apron
73+42	Left	30	3	Apron
80+85	Left	25	6	Paved
83+01	Left	30	3	Apron
83+97	Left	25	3	Apron
86+11	Left	25	3	Apron



PRINTED ON RECYCLED PAPER

10+00	Right	20	6	Paved
11+25	Right	25	3	Apron
12+28	Right	25	3	Apron
13+57	Right	25	3	Apron
16+40	Right	20	3	Apron
27+58	Right	30	3	Apron
43+50	Right	35	3	Apron
58+33	Right	25	3	Apron
59+66	Right	35	3	Apron
72+86	Right	35	3	Apron
74+16	Right	50	6	Paved
75+95	Right	50	3	Apron
80+32	Right	40	3	Apron
83+68	Right	25	3	Apron
83+97	Right	25	3	Apron

18301.00 Rte 1A

Station	Side	Length	Width	Description
17+43	Left	3	20	Apron
18+39	Left	6	25	Paved
20+66	Right	3	25	Apron
27+50	Left	3	25	Apron
39+39	Left	3	25	Apron
33+57	Left	3	30	Apron
34+80	Left	3	30	Apron
38+77	Left	3	25	Apron
42+35	Right	3	25	Apron
46+63	Right	3	40	Apron
46+92	Left	3	25	Apron
49+18	Left	3	25	Apron
52+10	Right	3	30	Apron
52+47	Left	3	30	Apron
55+70	Right	3	30	Apron
58+30	Left	3	30	Apron
63+00	Right	6	20	Paved
66+47	Left	6	25	Paved
67+26	Right	6	25	Paved
67+98	Right	6	25	Paved
72+15	Right	3	30	Apron


77+80	Left	3	30	Apron
79+78	Left	3	30	Apron
82+08	Left	3	25	Apron
86+32	Left	6	25	Paved
87+89	Left	3	30	Apron
88+73	Right	3	30	Apron
89+68	Left	3	25	Apron
91+85	Right	3	30	Apron
95+27	Left	3	25	Apron
107+95	Right	3	40	Apron
110+25	Left	3	30	Apron
116+75	Left	3	25	Apron
117+91	Right	6	85	Paved
125+56	Right	6	50	Paved
133+79	Right	3	25	Apron
138+15	Right	3	25	Apron
139+10	Left	3	25	Apron
139+86	Left	3	35	Apron
142+27	Right	3	25	Apron
143+27	Right	3	40	Apron
144+08	Right	3	40	Apron
144+65	Left	3	30	Apron
144+83	Right	6	35	Paved

Question: Where is Item 631.14 Grader to be used?

Response: Item 631.14 will be utilized to back up pavement along the shoulders where necessary or as directed by the resident.

Consider this information prior to submitting your bid on April 4, 2012.

Sincerely,



for George Macdougall
Acting Contracts & Specifications Engineer