



Paul R. LePage  
GOVERNOR

STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

January 6, 2012  
Subject: **Lubec**  
State PIN: 018317.00  
**Amendment No. 2**

David Bernhardt  
COMMISSIONER

Dear Sir/Ms:

Make the following changes to the Bid Document:

In the Bid Book (pages 4 and 5) **REMOVE** the "SCHEDULE OF ITEMS" 2 pages dated 111228 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 2 pages dated 120106.

In the Bid Book (page 21) "CONSTRUCTION NOTES" make the following **CHANGES** in pen and ink;

1. Under "ITEM 203.20 COMMON EXCAVATION" **CHANGE** the second station to read as follows;  
"14+00 to 15+50 Lt. Full Depth (Average 11 feet wide)"
2. **CHANGE** "ITEM 304.10 AGGR SUBB..." to read "**ITEM 304.103 AGGR SUBB...**"
3. After "ITEM 610.08 PLAIN RIP RAP" **ADD** the following:  
**ITEM 620.54 STABILIZATION GEOTEXTILE**  
**Note: This item is to be used under the temporary access road.**
4. Under "ITEM 620.58 EROSION CONTROL GEOTEXTILE" **CHANGE** the note to read as follows;  
**Note: This item is to be used under the Heavy Rip Rap.**

Note: Any references to 304.10 should read 304.103

The following questions have been received:

**Question:** Reference page 21 of the Bid Book, Construction Notes, Item 203.20 - Common Excavation. Under stationing, the second line gives the Full Depth work from Station 14+00 to 14+00. Should this be from Station 14+00 to 15+00?

**Response:** Yes. 14+00 to 15+50 is correct, please see the above change.

**Question:** Will the lane be closed until paving is complete? If the shoulder work is completed this winter and paving is not completed until spring will the area need to be maintained? Who will be responsible for maintaining the road?



PRINTED ON RECYCLED PAPER

**Response:** The westbound lane is to remain closed to traffic until the completion of this project. No additional maintenance of the road is expected between the construction operations this winter and those to occur in the spring.

**Question:** Who is responsible for traffic during the night when the Contractor is not on site?

**Response:** The contractor will be responsible for maintenance of traffic control in its entirety, day and night; from the time operations begin until winter operations cease, and again when subsequent operations resume.

**Question:** Under the General Notes, #15. It states that the MDOT will final stripe but the Contractor is responsible for transferring the existing striping pattern to the surface course. Will there be a temporary striping item added for this?

**Response:** Transferring the existing striping pattern to the surface course will be considered incidental to the contract.

**Question:** Erosion control geotextile is to be placed under the temporary access road. Stabilization geotextile is to be placed below the heavy rip rap. This is not the typical application for the fabrics, should they be reversed?

**Response:** Yes, application of the two fabrics should be reversed. Please see the above changes.

**Question:** Bid Item 304.10 ASCG – is specified as being truck measure in the Construction Notes. Item 304.10 is a plan quantity measure, should this item be 304.103?

**Response:** Item 304.10 is in-place measure not plan quantity. See new Schedule of Items changing item # Item 304.10 to 304.103 – Truck Measure.

**Question:** The Geotechnical Report states that the temporary access road will be built 550 feet East of the revetment area and all rock to be placed from the beach. It further states that excavation of peat and replacement with granular material will be required to build the access road. The Construction Notes say no grubbing will be done. Please clarify the method and area that DOT expects the Contractor to use.

**Response:** The Department will meet with the Contractor to mutually determine the most efficient method of construction and precise location of the temporary access road. Associated excavation, clearing and materials necessary for this construction will be paid for under contract items.

**Question:** The Geotechnical Report mentions a 110' x 70' staging area, is this area available for use on this project?

**Response:** This area will not be made expressly available to the contractor by the Department. The Contractor will be responsible for meeting with landowners to obtain permission to use any area not within the Department's right of way as a staging area.

**Question:** Is the Contractor able to work at night on this project? What are the hours of night time work allowed on this project?

**Response:** Night work will be allowed on this project, provided Contractor Submittals include provisions for such work. There will be no hourly restrictions.

Consider these changes and information prior to submitting your bid on January 11, 2012.

Sincerely,

  
for Scott Bickford  
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

CONTRACT ID: 018317.00

PROJECT(S): 18317.00

CONTRACTOR : \_\_\_\_\_

| LINE NO                    | ITEM DESCRIPTION  | APPROX. QUANTITY AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|----------------------------|---|----------------------------|------------|-----|------------|-----|
|                            |   |                            | DOLLARS    | CTS | DOLLARS    | CTS |
| SECTION 0001 PROJECT ITEMS |   |                            |            |     |            |     |
| 0010                       | 203.20 COMMON EXCAVATION  | 230.000<br>CY              |            |     |            |     |
| 0020                       | 203.25 GRANULAR BORROW  | 150.000<br>CY              |            |     |            |     |
| 0030                       | 203.35 CRUSHED STONE<br>FILL                                    | 30.000<br>CY               |            |     |            |     |
| 0040                       | 304.103 AGGREGATE<br>SUBBASE - GRAVEL (TRUCK<br>MEASURE)        | 100.000<br>CY              |            |     |            |     |
| 0050                       | 403.208 HOT MIX ASPHALT<br>12.5 MM HMA SURFACE                  | 35.000<br>T                |            |     |            |     |
| 0060                       | 403.213 HOT MIX ASPHALT<br>12.5 MM BASE                         | 35.000<br>T                |            |     |            |     |
| 0070                       | 409.15 BITUMINOUS TACK<br>COAT - APPLIED                        | 10.000<br>G                |            |     |            |     |
| 0080                       | 411.10 UNTREATED<br>AGGREGATE SURFACE COURSE<br>(TRUCK MEASURE) | 20.000<br>CY               |            |     |            |     |
| 0090                       | 610.16 HEAVY RIPRAP   | 400.000<br>CY              |            |     |            |     |
| 0100                       | 620.54 STABILIZATION<br>GEOTEXTILE                              | 100.000<br>SY              |            |     |            |     |

SCHEDULE OF ITEMS

CONTRACT ID: 018317.00

PROJECT(S): 18317.00

CONTRACTOR : \_\_\_\_\_

| LINE NO | ITEM DESCRIPTION  | APPROX. QUANTITY AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|---------|---|----------------------------|------------|-----|------------|-----|
|         |   |                            | DOLLARS    | CTS | DOLLARS    | CTS |
| 0110    | 620.58 EROSION CONTROL GEOTEXTILE                         | 100.000<br>SY              |            |     |            |     |
| 0120    | 629.05 HAND LABOR, STRAIGHT TIME                          | 10.000<br>HR               |            |     |            |     |
| 0130    | 631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)         | 10.000<br>HR               |            |     |            |     |
| 0140    | 631.172 TRUCK - LARGE (INCLUDING OPERATOR)                | 10.000<br>HR               |            |     |            |     |
| 0150    | 652.35 CONSTRUCTION SIGNS                                 | 224.000<br>SF              |            |     |            |     |
| 0160    | 652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES             | 42.000<br>CD               |            |     |            |     |
| 0170    | 652.38 FLAGGER  | 100.000<br>HR              |            |     |            |     |
| 0180    | 656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL | LUMP                       | LUMP       |     |            |     |
| 0190    | 659.10 MOBILIZATION                                       | LUMP                       | LUMP       |     |            |     |
|         | SECTION 0001 TOTAL  |                            |            |     |            |     |
|         | TOTAL BID   |                            |            |     |            |     |