



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

January 4, 2020
Subject: Intersection Improvements
State WINs: 018665.00
Location: **South Portland**
Amendment No. 3

Dear Sir/Ms.:

REMOVE page 86, SPECIAL PROVISION – SECTION 832-INSTALLATION OF INTERCONNECT – TRAFFIC SIGNALS – (Contractor Allowance/Interconnect wire by GWI), 1 page, dated November 23, 2020, and **REPLACE** with the attached, revised SPECIAL PROVISION – SECTION 832-INSTALLATION OF INTERCONNECT – TRAFFIC SIGNALS – (Contractor Allowance/Interconnect wire by GWI), 1 page, dated January 4, 2021.

The following question has been received:

Question: We were looking over the plans for South Portland STP-01866(500) and can't piece together where the majority of the contractor supplied fiber will be installed. The specs show 2650' of fiber optic cable for Pay Item 643.90, but the only 'non-GWI' fiber we see on the plans is about 500' for the cabinet drops at Rt 77 @ Highland Ave, Waterman @ Erskine, Broadway @ Anthoine. All other fiber looks to be existing GWI. Please clarify where the remaining fiber will be installed.

Response: See the attached, revised SPECIAL PROVISION – SECTION 832-INSTALLATION OF INTERCONNECT – TRAFFIC SIGNALS – (Contractor Allowance/Interconnect wire by GWI).

Consider these changes and information prior to submitting your bid on **January 6, 2021**.

Sincerely,

A handwritten signature in blue ink that reads "George Macdougall".

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

SPECIAL PROVISION
SECTION 832 – INSTALLATION OF INTERCONNECT
TRAFFIC SIGNALS

(Contractor Allowance/ Interconnect wire by GWI)

832.01 Description This work shall include providing Corning 12 strand single mode fiber optic cable (Item 643.90) for GWI to install to their splice points. The contractor shall coordinate with GWI (contact information in Utility Coordination Specification), to provide the cable on the day GWI will install and the contractor shall start the installation process by installing the cable into the cabinet and up the utility pole to utility lines, where GWI will complete installation. The following is a list of location and length of fiber required at each.

Broadway at Anthoine: 250 ft.

Waterman at Market: 950 ft.

Waterman at Erskine: 650 ft.

Highland at Ocean: 400 ft.

Broadway at Ocean: 400 ft.

832.02 Method of Measurement Installation of Interconnect wire by GWI will be measured by the Lump Sum, complete in place and accepted.

832.03 Basis of Payment The accepted quantities of Installation of Interconnect wire by GWI will be paid for at the contract unit price Lump Sum as specified. Payment for this work shall be made by force account. This work shall be treated in accordance with Section 109.7.5 – Force Account Work.

The 2650 feet of Fiber Optic Cable will be paid for separately under Item 643.90.

Payment for the Installation of Interconnect Wire by GWI will be a set contract price of \$4,500 that will be a pass through cost paid to GWI. For bid purposes a lump sum Contractor Allowance of \$4,500.00 has been included in the schedule of items. The Contractor Allowance will be paid as described in Section 109.7.5.

Payment will be made under:

	<u>Pay Item</u>	<u>Pay Unit</u>
832.071	Contractor Allowance	Lump Sum