



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

December 10, 2018
Subject: Bridge Replacement Projects,
Multi-Use Trail, Bridge Construction &
Traffic Signal Improvements
State WINs: 018735.00, 018736.00,
018736.10 & 022684.00
Location: **Gardiner**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 16 – 36, Proposal Schedule of Items, 21 pages, dated 10/30/2018, and **REPLACE** with the attached, revised Proposal Schedule of Items, 21 pages, dated 12/10/2018.

CHANGE on page 14, NOTICE TO CONTRACTORS, the bid opening date from “December 12, 2018” to read “**December 19, 2018**”. Make this change in pen and ink.

REMOVE page 71, SPECIAL PROVISION - SECTION 104 - GENERAL RIGHTS AND RESPONSIBILITIES - (Reserved Limits), 1 page, dated November 1, 2018, and **REPLACE** with the attached, revised SPECIAL PROVISION - SECTION 104 - GENERAL RIGHTS AND RESPONSIBILITIES - (Reserved Limits), 1 page, dated November 9, 2018.

ADD the attached - SPECIAL PROVISION - SECTION 105 - GENERAL SCOPE OF WORK - (Notices Required), 1 page, dated November 26, 2018.

ADD the attached - SPECIAL PROVISION - SECTION 652 – MAINTENANCE OF TRAFFIC - (Traffic Control Devices), 1 page, dated December 14, 2017.

The following questions have been received:

Question: On the bridge section view on sheet C9, the 10’ width appears to be defined between structural elements, however the special provision defines this width as between the railing. Please clarify.

Response: The 10’ width is the clear travel width between the railings.



PRINTED ON RECYCLED PAPER

Question: In special provision section 530.032, gusset plates are referenced. Are these required or can truss members be welded directly to one another without gussets?

Response: Gusset plates are not required. Truss members may be welded directly to each other without gusset plates as long as all connections are designed to adequately transfer all member forces at the panel points for all AASHTO limit states, including fatigue.

Question: Given that last week was a holiday week, the complexity of this project, and the number of projects bidding prior to this project we request the project bid date be moved to 12/19.

Response: See above changes.

Question: What length are the guardrail posts, 7' or 8'?

Response: Special Provision Section 606 Guardrail page 223 and Plan General Note #12 specify the use of 7 foot and 8 foot guardrail posts depending on the guardrail berm width. The only reduced berm width locations are in the area of STA 157+00 LT along the stream between the Maine Avenue Bridge and the Multi-Use Bridge location and at the intersection of Summer and Bridge Streets adjacent to Skehan's Tax.

Question: The 24" steel casing cast in the abutment shows as sch 40 steel, that is .688 wall which is very unusual and will be very expensive, I am suggesting to go with std. wall .375" or, xh wall .500" if needed, both options are readily available. Also what is the thickness of the 2" ring that is going in the middle of the casing pipes?


Response: Standard wall pipe (0.375") is acceptable. The welded restraint ring can be the same thickness (0.375").

Question: Will the department be willing to move the bid opening back a week seeing that all the lettings that were to be opened 12/5 have been moved to 12/12, overloading many contractors?

Response: See above changes.

Consider these changes and information prior to submitting your bid on **December 19, 2018**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	2.000 EA				
0020	201.24 REMOVING STUMP	4.000 EA				
0030	202.08 REMOVING BUILDING NO.: 1	LUMP SUM				
0040	202.08 REMOVING BUILDING NO.: 2	LUMP SUM				
0050	202.08 REMOVING BUILDING NO.: 3	LUMP SUM				
0060	202.15 REMOVING MANHOLE OR CATCH BASIN	6.000 EA				
0070	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0080	202.202 REMOVING PAVEMENT SURFACE	4,980.000 SY				
0090	203.20 COMMON EXCAVATION	5,020.000 CY				
0100	203.2312 HEALTH AND SAFETY PLAN	LUMP SUM				
0110	203.2318 DISPOSAL OF SPECIAL WASTE	150.000 T				
0120	203.2333 DISPOSAL TREATMENT OF SPECIAL EXCAVATION	1,100.000 T				

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	203.24 COMMON BORROW	77.000 CY	_____	_____	_____	_____
0140	203.25 GRANULAR BORROW	2,105.000 CY	_____	_____	_____	_____
0150	203.33 SPECIAL FILL	150.000 CY	_____	_____	_____	_____
0160	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	2,130.000 CY	_____	_____	_____	_____
0170	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	4,140.000 CY	_____	_____	_____	_____
0180	304.14 AGGREGATE BASE COURSE - TYPE A	120.000 CY	_____	_____	_____	_____
0190	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	957.000 T	_____	_____	_____	_____
0210	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	286.000 T	_____	_____	_____	_____
0220	403.213 HOT MIX ASPHALT 12.5 MM BASE	485.000 T	_____	_____	_____	_____
0230	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	931.000 T	_____	_____	_____	_____
0250	409.15 BITUMINOUS TACK COAT - APPLIED	739.000 G	_____	_____	_____	_____
0270	461.131 TEMPORARY PAVEMENT	90.000 T	_____	_____	_____	_____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0280	501.222 MICROPILES BR ST A1 RET WALL 7- 5/8" DIA	1,100.000 LF				
0290	501.222 MICROPILES BR ST ABUTMENTS 9- 5/8" DIA	3,900.000 LF				
0300	501.222 MICROPILES ME AVE NE RET WALL 9-5/8" DIA	260.000 LF				
0310	501.231 DYNAMIC LOADING TEST	4.000 EA				
0320	501.2331 MICROPILE VERIFICATION LOAD TEST	2.000 EA				
0330	501.2341 MICROPILE PROOF LOAD TEST	6.000 EA				
0340	501.25 STEEL CASING 24 INCH SCHED 40 GALV	52.000 LF				
0350	501.54 STEEL H-BEAM PILES 117 LBS/FT, DELIVERED	710.000 LF				
0360	501.541 STEEL H-BEAM PILES 117 LBS/FT, IN PLACE	710.000 LF				
0370	501.804 DRILLING EQUIPMENT MOBILIZATION MICROPILES	LUMP SUM	LUMP SUM			
0380	501.807 REMOVAL OF OBSTRUCTIONS PENETRATION	80.000 HOUR				

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0390	501.90 PILE TIPS	10.000 EA	_____	_____	_____	_____
0400	501.91 PILE SPLICES	20.000 EA	_____	_____	_____	_____
0410	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0420	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP SUM	_____	_____	_____
0430	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP SUM	_____	_____	_____
0440	502.48 LOW PERMEABILITY CONCRETE	7.000 CY	_____	_____	_____	_____
0450	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM	_____	_____	_____
0470	502.565 CONCRETE FILL	66.000 CY	_____	_____	_____	_____
0480	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: D	5.000 EA	_____	_____	_____	_____
0490	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	7,600.000 LB	_____	_____	_____	_____
0500	503.13 REINFORCING STEEL, PLACING	7,600.000 LB	_____	_____	_____	_____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0510	503.17 MECHANICAL WELDED SPLICE	207.000 EA	_____	 _____	_____	 _____
0520	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	127,300.000 LB	_____	 _____	_____	 _____
0530	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	127,300.000 LB	_____	 _____	_____	 _____
0540	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	 SUM	_____	 _____
0550	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	 SUM	_____	 _____
0560	504.96 METAL STAIRS	LUMP SUM	LUMP	 SUM	_____	 _____
0570	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	 SUM	_____	 _____
0580	506.9104 THERMAL SPRAY COATING - SHOP APPLIED	LUMP SUM	LUMP	 SUM	_____	 _____
0600	507.0834 WYOMING STEEL BRIDGE RAILING MODIFIED	LUMP SUM	LUMP	 SUM	_____	 _____
0610	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	 SUM	_____	 _____
0630	511.07 COFFERDAM: ABUT NO.1, ME AVE	LUMP SUM	LUMP	 SUM	_____	 _____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0640	511.07 COFFERDAM: ABUT NO.1, MULTI USE PATH	LUMP SUM	LUMP	SUM	_____	_____
0650	511.07 COFFERDAM: ABUT NO.2, ME AVE	LUMP SUM	LUMP	SUM	_____	_____
0660	511.07 COFFERDAM: ABUT NO.2, MULTI USE PATH	LUMP SUM	LUMP	SUM	_____	_____
0670	511.07 COFFERDAM: EX PIER NO.2 BR ST	LUMP SUM	LUMP	SUM	_____	_____
0680	511.07 COFFERDAM: EX PIER NO.3 BR ST	LUMP SUM	LUMP	SUM	_____	_____
0690	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0700	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	_____	_____	_____
0710	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0720	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	10.000 SF	_____	_____	_____	_____
0730	518.61 REPAIR OF VERTICAL SURFACES >= 8 IN.	4.000 CY	_____	_____	_____	_____
0740	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	177.000 LF	_____	_____	_____	_____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0750	523.52 BEARING INSTALLATION	14.000 EA	_____	 _____	_____	 _____
0760	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	14.000 EA	_____	 _____	_____	 _____
0770	524.301 TEMPORARY STRUCTURAL SUPPORT A1 DINER	LUMP SUM	LUMP	 SUM	_____	 _____
0780	524.301 TEMPORARY STRUCTURAL SUPPORT CONSOLIDATED COMM.	LUMP SUM	LUMP	 SUM	_____	 _____
0790	524.301 TEMPORARY STRUCTURAL SUPPORT HORIZ SLIDE	LUMP SUM	LUMP	 SUM	_____	 _____
0800	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	 SUM	_____	 _____
0810	526.304 TEMPORARY CONCRETE BARRIER, ANCHORED	LUMP SUM	LUMP	 SUM	_____	 _____
0820	526.3401 PERMANENT CONCRETE TRANSITION BARRIER - MODIFIED	7.000 EA	_____	 _____	_____	 _____
0830	527.34 WORK ZONE CRASH CUSHIONS	3.000 UN	_____	 _____	_____	 _____
0840	530.01 STEEL PEDESTRIAN BRIDGE	LUMP SUM	LUMP	 SUM	_____	 _____
0870	534.76 PRECAST ABUTMENT	LUMP SUM	LUMP	 SUM	_____	 _____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0880	534.7601 PRECAST APPROACH SLAB	LUMP SUM				
0890	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	32.000 LF				
0900	603.159 12 INCH CULVERT PIPE OPTION III	102.000 LF				
0910	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	40.000 LF				
0920	603.179 18 INCH CULVERT PIPE OPTION III	192.000 LF				
0930	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	77.000 LF				
0940	603.199 24 INCH CULVERT PIPE OPTION III	72.000 LF				
0950	604.072 CATCH BASIN TYPE A1-C	11.125 EA				
0960	604.092 CATCH BASIN TYPE B1-C	5.000 EA				
0970	604.15 MANHOLE	2.125 EA				
0980	604.154 72 INCH MANHOLE	1.000 EA				
0990	604.158 UTILITY VAULT	3.000 EA				

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1000	604.16 ALTERING CATCH BASIN TO MANHOLES	5.000 EA	_____	 _____	_____	 _____
1010	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	28.000 EA	_____	 _____	_____	 _____
1020	604.245 CATCH BASIN TYPE F4-C	1.000 EA	_____	 _____	_____	 _____
1030	604.247 CATCH BASIN TYPE F5-C	1.000 EA	_____	 _____	_____	 _____
1040	604.252 CATCH BASIN TYPE A5-C	2.625 EA	_____	 _____	_____	 _____
1050	604.2521 60" CATCH BASIN A5-C	1.000 EA	_____	 _____	_____	 _____
1060	604.30 SPECIAL CATCH BASIN	1.000 EA	_____	 _____	_____	 _____
1070	605.09 6 INCH UNDERDRAIN TYPE B	723.000 LF	_____	 _____	_____	 _____
1080	605.11 12 INCH UNDERDRAIN TYPE C	280.000 LF	_____	 _____	_____	 _____
1090	605.12 15 INCH UNDERDRAIN TYPE C	54.000 LF	_____	 _____	_____	 _____
1100	605.13 18 INCH UNDERDRAIN TYPE C	107.000 LF	_____	 _____	_____	 _____
1110	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	118.750 LF	_____	 _____	_____	 _____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 10 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1120	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	31.250 LF				
1130	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	2.000 EA				
1140	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1	4.000 EA				
1150	606.1721 BRIDGE TRANSITION - TYPE 1	2.000 EA				
1160	606.259 ANCHORAGE ASSEMBLY	3.000 EA				
1170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	16.000 EA				
1180	606.65 GUARDRAIL THRIE BEAM - SINGLE RAIL	37.500 LF				
1190	606.66 TERMINAL END THRIE BEAM	2.000 EA				
1200	607.22 CEDAR RAIL FENCE	550.000 LF				
1210	608.15 BRICK SIDEWALK WITH BITUMINOUS BASE	521.000 SY				
1220	608.171 CONCRETE SIDEWALK WITH BRICK BORDER	174.000 SY				

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 11 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1230	608.26 CURB RAMP DETECTABLE WARNING FIELD	596.000 SF	_____	_____	_____	_____
1240	609.11 VERTICAL CURB TYPE 1	1,658.000 LF	_____	_____	_____	_____
1250	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	547.000 LF	_____	_____	_____	_____
1260	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	4.000 EA	_____	_____	_____	_____
1270	609.2341 TERMINAL CURB TYPE 1 - 4 FOOT - CIRCULAR	2.000 EA	_____	_____	_____	_____
1280	609.238 TERMINAL CURB TYPE 1 - 8 FOOT	37.000 EA	_____	_____	_____	_____
1290	609.2381 TERMINAL CURB TYPE 1 - 8' CIRCULAR	35.000 EA	_____	_____	_____	_____
1300	609.26 CURB TRANSITION SECTION B TYPE 1	1.000 EA	_____	_____	_____	_____
1310	609.31 CURB TYPE 3	27.000 LF	_____	_____	_____	_____
1320	609.34 CURB TYPE 5	640.000 LF	_____	_____	_____	_____
1330	609.35 CURB TYPE 5 - CIRCULAR	95.000 LF	_____	_____	_____	_____
1340	610.08 PLAIN RIPRAP	49.000 CY	_____	_____	_____	_____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 12 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1350	610.16 HEAVY RIPRAP	1,910.000 CY				
1360	613.319 EROSION CONTROL BLANKET	126.000 SY				
1370	615.07 LOAM	442.000 CY				
1380	615.085 LOAM/WOODWASTE MULCH MIX	70.000 CY				
1390	618.13 SEEDING METHOD NUMBER 1	17.000 UN				
1400	618.14 SEEDING METHOD NUMBER 2	4.000 UN				
1410	618.143 SPECIAL SEED MIX:	11.000 UN				
1420	618.146 SEEDING HYDROMULCH MEDIUM	11.000 UN				
1430	619.12 MULCH	21.000 UN				
1440	619.14 EROSION CONTROL MIX	70.000 CY				
1450	620.58 EROSION CONTROL GEOTEXTILE	1,480.000 SY				
1460	620.66 DRAINAGE GEOCOMPOSITE	87.000 SY				
1470	621.126 SMALL DECIDUOUS TREES (6 FOOT - 8 FOOT) GROUP A	6.000 EA				

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 13 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1480	621.3851 EVERGREEN SHRUBS GP A 12" - 15" CONT	48.000 EA	_____	 _____	_____	 _____
1490	621.5351 DECIDUOUS SHRUBS (15 INCH - 18 INCH) GROUP A	60.000 EA	_____	 _____	_____	 _____
1500	621.54 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP A	12.000 EA	_____	 _____	_____	 _____
1510	621.71 HERBACEOUS PERENNIALS GROUP A 1 GAL CONT	114.000 EA	_____	 _____	_____	 _____
1520	621.715 HERBACEOUS PERENNIALS 1 QT CONT.	60.000 EA	_____	 _____	_____	 _____
1530	626.11 PRECAST CONCRETE JUNCTION BOX	18.000 EA	_____	 _____	_____	 _____
1540	626.21 METALLIC CONDUIT	390.000 LF	_____	 _____	_____	 _____
1550	626.22 NON-METALLIC CONDUIT	2,460.000 LF	_____	 _____	_____	 _____
1560	626.32 24 INCH FOUNDATION	17.000 EA	_____	 _____	_____	 _____
1570	626.332 30 INCH DIAMATER GREATER THAN 8 FEET LONG & 36 INCH DIAMETER, 42 INCH DIAMETER FOUNDATION	5.000 CY	_____	 _____	_____	 _____
1580	626.36 REMOVE OR MODIFY CONCRETE FOUNDATION	12.000 EA	_____	 _____	_____	 _____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 14 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1590	626.38 GROUND MOUNTED CABINET FOUNDATION	1.000 EA	_____	_____	_____	_____
1600	627.513 TEMPORARY PAVEMENT MARKING TAPE, YELLOW OR WHITE	75.000 SF	_____	_____	_____	_____
1610	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3,320.000 LF	_____	_____	_____	_____
1620	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	6,950.000 SF	_____	_____	_____	_____
1630	627.77 REMOVING PAVEMENT MARKINGS	840.000 SF	_____	_____	_____	_____
1640	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,600.000 LF	_____	_____	_____	_____
1650	629.05 HAND LABOR, STRAIGHT TIME	108.000 HR	_____	_____	_____	_____
1660	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	95.000 HR	_____	_____	_____	_____
1670	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	5.000 HR	_____	_____	_____	_____
1680	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	90.000 HR	_____	_____	_____	_____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 15 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1690	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	5.000 HR	_____	 _____	_____	 _____
1700	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	5.000 HR	_____	 _____	_____	 _____
1710	631.22 FRONT END LOADER (INCLUDING OPERATOR)	95.000 HR	_____	 _____	_____	 _____
1720	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
1730	634.160 HIGHWAY LIGHTING	LUMP SUM	LUMP SUM		_____	 _____
1740	634.2101 TYPE A LIGHT STANDARD	5.000 EA	_____	 _____	_____	 _____
1750	634.2102 TYPE B LIGHT STANDARD	5.000 EA	_____	 _____	_____	 _____
1760	634.2103 TYPE C LIGHT STANDARD	1.000 EA	_____	 _____	_____	 _____
1770	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
1780	643.62 RECTANGULAR RAPID FLASHING BEACON	2.000 EA	_____	 _____	_____	 _____
1790	643.64 FLASHING SIGN ASSEMBLY	1.000 EA	_____	 _____	_____	 _____
1800	643.71 TRAFFIC SIGNAL MODIFICATION	LUMP SUM	LUMP SUM		_____	 _____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 16 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1810	643.80 TRAFFIC SIGNALS AT BRIDGE & WATER STREETS	LUMP SUM	LUMP	SUM	_____	_____
1820	643.83 VIDEO DETECTION SYSTEM	LUMP SUM	LUMP	SUM	_____	_____
1830	643.91 MAST ARM POLE	1.000 EA	_____	_____	_____	_____
1840	643.92 PEDESTAL POLE	4.000 EA	_____	_____	_____	_____
1850	645.103 DEMOUNT GUIDE SIGN	2.000 EA	_____	_____	_____	_____
1860	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	39.000 EA	_____	_____	_____	_____
1870	645.1061 RELOCATE EXISTING SIGN ASSEMBLY AND POST	1.000 EA	_____	_____	_____	_____
1880	645.108 DEMOUNT POLE	19.000 EA	_____	_____	_____	_____
1890	645.113 REINSTALL GUIDE SIGN	2.000 EA	_____	_____	_____	_____
1900	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	37.000 EA	_____	_____	_____	_____
1910	645.118 REINSTALL POLE	17.000 EA	_____	_____	_____	_____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 17 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1920	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	153.000 SF				
1930	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	97.000 SF				
1940	645.51 SPECIAL SIGNING	LUMP SUM				
1950	652.311 TYPE II BARRICADE	4.000 EA				
1960	652.312 TYPE III BARRICADE	41.000 EA				
1970	652.313 TEMPORARY PEDESTRIAN BARRICADE, ADA COMPLIANT	370.000 LF				
1980	652.33 DRUM	125.000 EA				
1990	652.34 CONE	215.000 EA				
2000	652.35 CONSTRUCTION SIGNS	2,500.000 SF				
2010	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM				
2020	652.38 FLAGGER	5,574.000 HR				

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 18 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
2030	652.381 TRAFFIC OFFICER	484.000 HR				
2040	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	7.000 EA				
2050	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM		
2060	659.10 MOBILIZATION	LUMP SUM		LUMP SUM		
2070	660.21 ON-THE-JOB TRAINING (BID)	1,000.000 HR				
2080	802.10 12 INCH DUCTILE IRON WATERMAIN	170.000 LF				
2090	803.01 TEST PITS	16.000 EA				
2100	822.302 12 INCH DUCTILE IRON PIPE PREINSULATED	LUMP SUM		LUMP SUM		
2110	822.322 6 INCH DUCTILE IRON PIPE	30.000 LF				
2120	823.311 12 INCH GATE VALVE WITH BOX	2.000 EA				
2130	823.33 6 INCH GATE VALVE WITH BOX	1.000 EA				
2140	824.32 REMOVE/RESET HYDRANT	1.000 EA				

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 19 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 1 Main Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
2150	825.321 1 INCH CORPORATION	1.000 EA				
2160	825.331 1" CURB STOP	1.000 EA				
2170	825.90 1 INCH PREINSULATED HEAT TRACED WATER PIPE	LUMP SUM				
2180	841.49 BOLLARDS - COLLAPSIBLE	2.000 EA				
2190	845.10 STRUCTURAL STEEL UTILITY SUPPORT CONSOLIDATED COMM.	LUMP SUM				
2200	910.301 SPECIAL WORK SKEHANS TAX SIGN REMOVAL	LUMP SUM				
2210	910.301 SPECIAL WORK UTILITY CONDUIT	LUMP SUM				
Section: 1			Total:			

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 20 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 2 ME AVE PRECAST BR ALTERNATE

Alt Set ID: AL

Alt Mbr ID: 1

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0200	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT ALT 1	25.000 T	_____	_____	_____	_____
0240	403.2131 12.5 MM POLYMER MODIFIED HMA BASE ALT 1	25.000 T	_____	_____	_____	_____
0260	409.15 BITUMINOUS TACK COAT - APPLIED ALT 1	18.000 G	_____	_____	_____	_____
0460	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS ALT 1	LUMP SUM	LUMP	SUM	_____	_____
0590	506.9104 THERMAL SPRAY COATING - SHOP APPLIED ALT 1	LUMP SUM	LUMP	SUM	_____	_____
0620	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE ALT 1	LUMP SUM	LUMP	SUM	_____	_____
0850	530.04 PREFABRICATED BRIDGE STRUCTURE AND ASSEMBLY ALT 1	LUMP SUM	LUMP	SUM	_____	_____
Section: 2			Total:		_____	_____

12/10/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 21 of 21

Proposal ID: 018735.00

Project(s): 018735.00, 018736.00, 018736.10,
022684.00

SECTION: 3 ME AVE NEXT BEAM ALTERNATE

Alt Set ID: AL

Alt Mbr ID: 2

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0860	531.51 BRIDGE STRUCTURE - DETAIL BUILD	LUMP SUM		LUMP SUM		
	Section: 3		Total:			
			Total Bid:			

Gardiner
WINs 18735.00 &
22684.00
November 9, 2018

SPECIAL PROVISION
SECTION 104
GENERAL RIGHTS AND RESPONSIBILITIES
(Reserved Limits)

It is hereby brought to the Contractor's attention that use of the following areas will not become available to the Contractor until the stated dates below:

March 30, 2019: Building No. 1 (Chapman's Fuel) and the property it is on, depicted on the right of way map as parcel 2, at approximate Station 71+50 Left on Bridge Street.

December 4, 2018: All other property that immediately borders WIN 18735.00 and the Bridge Street/Water Street/Brunswick Avenue intersection portion of WIN 22684.00.

SPECIAL PROVISION
SECTION 105
GENERAL SCOPE OF WORK
(Notices Required)

Subsection 105.3.1 Notices Required is replaced in its entirety by the following:

105.3.1 Notices Required

The Contractor shall plan all operations so that the Resident will have sufficient advance notification to provide the necessary inspection and testing staff. Further, any changes to the Contractor's operations that affect the Department's staffing requirements will also require sufficient notification. Sufficient notification will be considered 48 hours. In the event that Work schedules are changed, a 48-hour notification shall be required again, unless otherwise agreed to by the Resident.

The Contractor shall plan granular material operations so that the Resident will have sufficient advance notification to provide a proctor for the material to be placed. Sufficient notification will be considered 7 days. Changes in source will also require this notification.

Failure to provide the above notifications will result in the following actions:

First offense - written warning

Second and subsequent - liquidated damages will be charged for one calendar day

SPECIAL PROVISION
SECTION 652
MAINTENANCE OF TRAFFIC
(Traffic Control Devices)

652.2.4 Other Devices

Add the following: “STOP / SLOW paddles shall also incorporate either white or red flashing lights on the STOP face and white or yellow on the SLOW face of the paddle.

Flashing lights on the STOP / SLOW paddle shall have a flash rate of at least 50, but not more than 60, flashes per minute.

Lighted paddles must conform to one of the options identified in the 2009 version of the MUTCD part 6E.03.”