



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

June 14, 2012
Subject: **North Yarmouth**
Federal Project No: STP-1911(100)X
State WIN: 019111.00
Amendment No. 2

David Bernhardt
COMMISSIONER

Dear Sir/Ms:

Make the following changes to the Bid Document:

In the Bid Book (pages 17 thru 19) **REMOVE** the "SCHEDULE OF ITEMS" 3 pages dated 120522 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 3 pages dated 120614.

In the Bid Book (page 35) **REMOVE** the "TYPICAL SECTIONS" sheet number 1 of 2 and **REPLACE** with the attached new "TYPICAL SECTIONS" sheet number 1 of 2.

In the Bid Book (page 46) **CHANGE** General Notes #10, 11 and 12 to read as follows:

10. Residential paved entrances shall be constructed with: 2" hot mix asphalt and 12" RAP material processed under Item 203.70. All work associated with hauling, placement, compaction, labor and other incidental work with the RAP for residential paved entrances shall be paid for under Item 204.21.

11. Commercial paved entrances shall be constructed with: 3" hot mix asphalt and 11" RAP material processed under Item 203.70. All work associated with hauling, placement, compaction, labor and other incidental work with the RAP for commercial paved entrances shall be paid for under Item 204.21.

12. Crushed stone entrances shall be constructed with 14" RAP material processed under Item 203.70. All work associated with hauling, placement, compaction, labor and other incidental work with the RAP for crushed stone entrances shall be paid for under Item 204.21.

Make this change in pen and ink.

The following questions have been received:

Question: The Typical drawing shows no shoulder. Is it the intent to back up the pavement on a 3 to 1 slope into the ditch?



PRINTED ON RECYCLED PAPER

Response: No, please see the revised Typical.

Question: General Note #10 states Residential paved drives shall be constructed with 12” of ASCG; please provide a pay item for this.

Response: Please see the above pen and ink change

Question: Item 204.21 Add Shoulder Aggregate, the Typical does not show a shoulder width, what is the shoulder width dimension?

Response: Please see the answer to Question #1 and refer to the new Typical Section.

Question: Will the Department supply the desired cross slope layout described in General Note #17?

Response: It is the responsibility of the Contractor to adhere to the Typical Sections.

Question: If the Contractor processes the rap and the project runs short of material, will the Department compensate the Contractor to move the screen or crusher to another location to process the remaining material to complete the project? How will this get paid?


Response: The Department has determined that there is sufficient material to complete the project. Also, please see the attached new Schedule of items.

Question: Referring to item 310.048, will the Contractor be held responsible for repairs?

Response: Yes

Consider these changes and information prior to submitting your bid on June 20, 2012.

Sincerely,


George Macdougall
Contracts & Specifications Engineer

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 1

SCHEDULE OF ITEMS

DATE: 120614

REVISED:

CONTRACT ID: 019111.00

PROJECT(S): STP- 1911(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.203 PAVEMENT BUTT JOINTS	840.000 SY				
0020	203.70 RECYCLED ASPHALT PAVEMENT - PROCESSING	5400.000 CY				
0030	204.21 ADD SHOULDER AGGREGATE - TRUCK MEASURE	1300.000 CY				
0040	310.21 PLANT MIXED RECYCLED ASPHALT PAVEMENT - MIXING AND TRUCKING	5330.000 T				
0050	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	80.000 T				
0060	403.2104 HOT MIX ASPHALT 9.5 MM - 3/4" SURFACE	1320.000 T				
0070	403.211 HOT MIX ASPHALT (SHIMMING)	1320.000 T				
0080	409.15 BITUMINOUS TACK COAT - APPLIED	2400.000 G				
0090	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	40.000 CY				

SCHEDULE OF ITEMS

CONTRACT ID: 019111.00

PROJECT(S): STP- 1911(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	502.47 PORTLAND CEMENT - SUPPLY AND INTRODUCTION	60.000 T				
0110	610.08 PLAIN RIPRAP	50.000 CY				
0120	613.319 EROSION CONTROL BLANKET	100.000 SY				
0130	620.58 EROSION CONTROL GEOTEXTILE	85.000 SY				
0140	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	24490.000 LF				
0150	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0160	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0170	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0180	631.161 PAVING CREW	100.000 HR				
0190	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR				
0200	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

CONTRACT ID: 019111.00

PROJECT(S): STP- 1911(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	639.19 FIELD OFFICE TYPE B	1.000 EA				
0220	652.33 DRUM	50.000 EA				
0230	652.34 CONE	130.000 EA				
0240	652.35 CONSTRUCTION SIGNS	940.000 SF				
0250	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	52.000 CD				
0260	652.38 FLAGGER	600.000 HR				
0270	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0280	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

