



Paul R. LePage  
GOVERNOR

STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

January 8, 2013  
Subject: **Edgecomb/Wiscasset**  
Federal Project No: NHS-1928(700)  
State WIN: 019287.00  
**Amendment No. 3**

David Bernhardt  
COMMISSIONER

Dear Sir/Ms:

The following question has been received:

**Question:** What material is to be placed in the 25' long section shown in the longitudinal approach transition section that has been grayed out? Is this the area that the common excavation line item is for?

**Response:** This material shall be hot mix asphalt. The bottom 7" shall be item 403.207, 19mm HMA. The next 1.5" layer shall be item 403.2131, 12.5 mm Polymer Modified HMA Base and the top 1.5" layer shall be item 403.2081, 12.5 mm Polymer Modified HMA. The depth of existing pavement is unknown in this area. Any material removed below the existing pavement shall be paid for under item 203.20 common excavation.

Consider this information prior to submitting your bid on **January 9, 2013**.

Sincerely,

  
for George M. A. Macdougall P.E.  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER