



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

November 30, 2012
Subject: **Scour Countermeasures**
Location: **Island Falls**
State WINS: **019322.00 & 019323.00**
Amendment No. 1

Dear Sir/Ms:

Make the following change to the Bid Documents:

In the Bid Book, make the following **CHANGES** to "SPECIAL PROVISION, SECTION 105, General Scope of Work, (Environmental Requirements)".

1. Page 33, **DELETE** in its entirety subparagraph "12.", which begins "12. In-Water work must be ...".
2. Pages 35 and 36, **DELETE** the content of these pages in their entirety.

Make the above changes in pen and ink.

The following question has been received:

Question: Is it the States intention to install the rip rap "in the dry" or can the rip rap be installed without cofferdams during the in stream work window?

Response: Containment of disturbed streambed material is required during streambed preparation and excavation as well as to allow for fish removal from the work area as described in Special Provisions Section 105 – General Scope of Work (Environmental Requirements) and 511 – Cofferdams. Please see the above changes.

Consider this change and information prior to submitting your bid on December 12, 2012.

Sincerely,

for 

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



100% RECYCLED PAPER