



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Paul R. LePage  
GOVERNOR

David Bernhardt  
COMMISSIONER

December 7, 2012  
Subject: **Scour Countermeasures**  
Location: **Island Falls**  
State WINS: **019322.00 & 019323.00**  
**Amendment No. 2**

Dear Sir/Ms:

The following questions have been received:

**Question:** The Schedule of Items in the book shows 606.365 Guardrail QTY as 100 LF. The book also shows 606.366 Guardrail QTY as 100 LF. Plans show 606.365 and 606.366 as 50 LF each. Please verify which is the correct LF?

**Response:** There are plans for both I-95 Northbound and I-95 Southbound bridges. Each plan set has estimated quantities associated with the work at that bridge. The bid book includes quantities to complete both bridge projects. For instance, the quantity of 606.365 and 606.366 is 50 LF per bridge for a total of 100 LF for the project.

**Question:** Is it safe to assume that the State will not allow round rock to be used as the large and plain riprap?

**Response:** Round rock will not be permitted per specification.

Consider this information prior to submitting your bid on December 12, 2012.

Sincerely,

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER