



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

December 10, 2012
Subject: **Scour Countermeasures**
Location: **Island Falls**
State WINS: **019322.00 & 019323.00**
Amendment No. 3

Dear Sir/Ms:

The following question has been received:

Question: Our suppliers are having no luck finding a supplier that makes anything remotely close to the Geocontainers that are spec'd out in Special Provision, Section 620, Option #1. Can you clarify MDOT's intentions with/for this product? Will MDOT provide a company that manufactures this product?

Response: If Option 1 of Special Provision 620 – Erosion Control Filter Layer is chosen, it is expected that the geocontainers may be fabricated (by the Contractor or suppliers). The materials necessary to fabricate the geocontainers are readily available.

Consider this information prior to submitting your bid on December 12, 2012.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER