



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

March 9, 2018
Subject: Pavement Milling, HMA
Overlay with Safety Improvements
State WIN: 020868.00
Location: **Lisbon**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

ADD the attached SPECIAL PROVISION - SECTION 401 - HOT MIX ASPHALT PAVEMENT - (HMA with Fine Micro-Deval Requirement), 1 page, dated January 19, 2017.

The following question has been received:

Question: In the 403 Special Provision, item number 403.2081 includes note 27 which says to refer to special provision 401 - HMA with fine micro Deval requirement for project specifics. There is no special provision 401 for fine micro Deval though. Was note 27 a misprint? Or could you provide the Special Provision 401?

Response: Note 27 as written in the 403SP applies to this contract. Please refer to the Special Provision 401 – Fine Micro Deval that is attached.

Consider these changes and information prior to submitting your bid on **March 14, 2018**.

Sincerely,

A handwritten signature in blue ink that reads "George M. A. Macdougall".

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SPECIAL PROVISION
SECTION 401 - HOT MIX ASPHALT PAVEMENT
(HMA with Fine Micro-Deval Requirement)

The following subsections of the most current version of Specification 401 – Hot Mix Asphalt Pavements have been revised and amended by the following:

401.01 Description The Contractor shall compose Hot Mix Asphalt (HMA) Pavement with aggregate, Performance Graded Asphalt Binder (PGAB), and mineral filler if required. If denoted in Special Provision 403 - Hot Mix Asphalt Pavement, the mixtures shall meet the additional aggregate requirements of this special provision.

401.02 Materials Materials shall meet the requirements specified in Section 700 – Materials, unless otherwise revised in this special provision:

| | |
|-----------------------------|--------|
| Aggregates for HMA Pavement | 703.07 |
| HMA Mixture Composition | 703.09 |

The HMA composite blend, minus any RAP used, shall have a Micro-Deval value of 18.0 or less as determined by AASHTO T327. The HMA composite blend, minus any RAP used, shall have a Fine Micro-Deval value of 14.0 or less as determined by ASTM D7428.