



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

April 30, 2018
Subject: HMA Overlay with Safety
Improvements
State WIN: 020875.00
Location: **Poland**
Amendment No. 2

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 17 – 19, Proposal Schedule of Items, 3 pages, dated 4/26/2018, and
REPLACE with the attached, revised Proposal Schedule of Items, 3 pages, dated 4/30/2018.

ADD the attached SPECIAL PROVISION - SECTION 606 – GUARDRAIL, 1 page, dated
February 10, 2016.

The following question has been received:

Question: Can plastic blocks be used, or do they have to be steel?

Response: See attached, revised Proposal Schedule of Items.

Consider these changes and information prior to submitting your bid on **May 2, 2018**.

Sincerely,

A handwritten signature in black ink, appearing to read 'George M. A. Macdougall'.

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020875.00

Project(s): 020875.00

SECTION: Not Assigned to a Section

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.203 PAVEMENT BUTT JOINTS	990.000 SY	_____	_____	_____	_____
0020	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	90.000 T	_____	_____	_____	_____
0030	403.210 HOT MIX ASPHALT 9.5 MM	3,710.000 T	_____	_____	_____	_____
0040	403.211 HOT MIX ASPHALT (SHIMMING)	2,210.000 T	_____	_____	_____	_____
0050	409.15 BITUMINOUS TACK COAT - APPLIED	5,400.000 G	_____	_____	_____	_____
0060	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	60.000 CY	_____	_____	_____	_____
0070	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	1,160.000 LF	_____	_____	_____	_____
0080	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	30.000 LF	_____	_____	_____	_____
0090	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0100	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA	_____	_____	_____	_____
0110	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020875.00

Project(s): 020875.00

SECTION: Not Assigned to a Section

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	613.319 EROSION CONTROL BLANKET	90.000 SY	_____	 _____	_____	 _____
0130	615.10 DIRTY BORROW	50.000 CY	_____	 _____	_____	 _____
0140	618.14 SEEDING METHOD NUMBER 2	121.000 UN	_____	 _____	_____	 _____
0150	619.12 MULCH	121.000 UN	_____	 _____	_____	 _____
0160	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	45,080.000 LF	_____	 _____	_____	 _____
0170	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	90,150.000 LF	_____	 _____	_____	 _____
0180	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0190	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR	_____	 _____	_____	 _____
0200	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	100.000 HR	_____	 _____	_____	 _____
0210	652.33 DRUM	80.000 EA	_____	 _____	_____	 _____
0220	652.34 CONE	80.000 EA	_____	 _____	_____	 _____
0230	652.35 CONSTRUCTION SIGNS	770.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020875.00

Project(s): 020875.00

SECTION: Not Assigned to a Section

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	34.000 CD	_____	 _____	_____	 _____
0250	652.38 FLAGGER	660.000 HR	_____	 _____	_____	 _____
0260	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM	_____	 _____
0270	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
	Section:			Total:	_____	 _____

SECTION: 1 Highway Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
	Section: 1			Total:	_____	 _____
				Total Bid:	_____	 _____

February 10, 2016

SPECIAL PROVISION
SECTION 606
GUARDRAIL

606.09 Basis of Payment: This section shall be amended with the addition of the following:

<u>Pay Item</u>	<u>Pay Unit</u>
606.1301 31" W-Beam Guardrail - Mid-Way Splice (Steel Post, 8" Offset Blocks, Single Faced)	Linear Foot
606.1302 31" W-Beam Guardrail - Mid-Way Splice (Steel Post, 8" Offset Blocks, Double Faced)	Linear Foot
606.1303 31" W-Beam Guardrail - Mid-Way Splice (Steel Post, 8" Offset Blocks, 15' Radius and Less)	Linear Foot
606.1304 31" W-Beam Guardrail - Mid-Way Splice (Steel Post, 8" Offset Blocks, Over 15' Radius)	Linear Foot
606.1305 31" W-Beam Guardrail - Mid-Way Splice Flared Terminal (31" Height)	Each
606.1306 31" W-Beam Guardrail - Mid-Way Splice Tangent Terminal (31" Height)	Each
606.1307 Bridge Transition (Asymmetrical) – Type 1	Each
606.1308 Buried-in-Slope Guardrail End, Mid-Way Splice	Each