



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

May 1, 2018
Subject: HMA Overlay with Safety
Improvements
State WIN: 020875.00
Location: **Poland**
Amendment No. 3

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 17 – 19, Proposal Schedule of Items, 3 pages, dated 4/30/2018, and
REPLACE with the attached, revised Proposal Schedule of Items, 3 pages, dated 4/30/2018.

REMOVE pages 35 - 36, CONSTRUCTION NOTES, 2 pages, dated March 28,2018, and
REPLACE with the attached, revised CONSTRUCTION NOTES, 2 pages, dated May 1,2018.

The following question has been received:

Question: Are the posts 7 feet or 8 feet?

Response: 8 feet.

Consider these changes and information prior to submitting your bid on **May 2, 2018**.

Sincerely,

A handwritten signature in blue ink that reads "George M. A. Macdougall".

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020875.00

Project(s): 020875.00

SECTION: 1 Highway Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.203 PAVEMENT BUTT JOINTS	990.000 SY	_____	_____	_____	_____
0020	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	90.000 T	_____	_____	_____	_____
0030	403.210 HOT MIX ASPHALT 9.5 MM	3,710.000 T	_____	_____	_____	_____
0040	403.211 HOT MIX ASPHALT (SHIMMING)	2,210.000 T	_____	_____	_____	_____
0050	409.15 BITUMINOUS TACK COAT - APPLIED	5,400.000 G	_____	_____	_____	_____
0060	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	60.000 CY	_____	_____	_____	_____
0070	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	1,160.000 LF	_____	_____	_____	_____
0080	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	30.000 LF	_____	_____	_____	_____
0090	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0100	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA	_____	_____	_____	_____
0110	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020875.00

Project(s): 020875.00

SECTION: 1 Highway Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	613.319 EROSION CONTROL BLANKET	90.000 SY	_____	 _____	_____	 _____
0130	615.10 DIRTY BORROW	50.000 CY	_____	 _____	_____	 _____
0140	618.14 SEEDING METHOD NUMBER 2	121.000 UN	_____	 _____	_____	 _____
0150	619.12 MULCH	121.000 UN	_____	 _____	_____	 _____
0160	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	45,080.000 LF	_____	 _____	_____	 _____
0170	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	90,150.000 LF	_____	 _____	_____	 _____
0180	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0190	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR	_____	 _____	_____	 _____
0200	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	100.000 HR	_____	 _____	_____	 _____
0210	652.33 DRUM	80.000 EA	_____	 _____	_____	 _____
0220	652.34 CONE	80.000 EA	_____	 _____	_____	 _____
0230	652.35 CONSTRUCTION SIGNS	770.000 SF	_____	 _____	_____	 _____

4/30/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 020875.00

Project(s): 020875.00

SECTION: 1 Highway Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	34.000 CD	_____	 _____	_____	 _____
0250	652.38 FLAGGER	660.000 HR	_____	 _____	_____	 _____
0260	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM	_____	 _____
0270	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
		Section: 1		Total:	_____	 _____
				Total Bid:	_____	 _____

CONSTRUCTION NOTES

202.203 PAVEMENT BUTT JOINTS

<u>Description</u>	<u>Station</u>
Begin Project	10+00
End Project	160+25
Paved Drives	20
Side Roads	3

606.1301 GUARDRAIL MD-WAY SPLICE Steel Post, 8" Offset Blocks, Single Faced

<u>Left Side</u>			<u>Right Side</u>		
<u>Station</u>	<u>To</u>	<u>Station</u>	<u>Station</u>	<u>To</u>	<u>Station</u>
61+22		71+73	69+75		70+81

606.1303 GUARDRAIL MID-WAY SPLICE Steel Post, 8" Offset Blocks, 15' Radius and Less

<u>Left Side</u>			<u>Right Side</u>		
<u>Station</u>	<u>To</u>	<u>Station</u>	<u>Station</u>	<u>To</u>	<u>Station</u>
			69+75		69+50

606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL

<u>Left Side</u>	<u>Right Side</u>
<u>Station</u>	<u>Station</u>
	69+50

606.1305 GUARDRAIL MID-WAY SPLICE FLARED TERMINAL

<u>Left Side</u>	<u>Right Side</u>
<u>Station</u>	<u>Station</u>
61+59	71+18
72+10	

CONSTRUCTION NOTES

627.733 4 INCH WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE

Final striping will not commence until 10 days have elapsed from the completion of surface pavement and must be completed within 20 days of the completion of surface pavement. Unless otherwise directed, failure to comply will result in a Traffic Control Violation.

Once Construction is Complete, Maintenance of Traffic Control Devices (652.36) will not be paid while waiting to final stripe.

Once Construction is Complete, Liquidated Damages will not be charged while waiting to final stripe

627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW

Temporary center lines shall be painted on all matched pavement within one week.

Temporary edge lines shall be painted on all pavement layers within four weeks.

All temporary lines shall be painted prior to final striping.

Multilane sections, truck lanes, and milled surfaces must be striped daily on all matched pavement layers.

TOMs must be used on all pavement layers until temporary paint is applied.

TOMs will be removed before final striping.

TOM removal will be addressed in the Traffic Control Plan.

Only painted temporary line will be paid under this item. TOMs will be considered incidental to the contract.

652.35 CONSTRUCTION SIGNS

Two “**Road Work Next 3 Miles**” will be required as part of this project.