



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

June 4, 2018
Subject: Sheepscot Bridge Wearing
Surface Replacement
State WIN: 021739.00
Location: **Palermo**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 16 – 19, Proposal Schedule of Items, 4 pages, dated 5/8/2018, and **REPLACE** with the attached, revised Proposal Schedule of Items, 4 pages, dated 6/1/2018.

In the Plan Set:

On SHEET NUMBER 2 OF 5, EST. QUANTITIES, GENERAL CONSTRUCTION NOTES AND SUPERSTRUCTURE NOTES, **ADD** Item No. 652.41 – Portable Changeable Message Sign – 2 – EA. Make this change in pen and ink.

The following questions have been received:

Question: Are wide load restriction signs required and how are they paid for?

Response: Wide load restriction signs will be paid for under 652.35 Construction Signs.

Question: Are changeable message boards required and how are they paid for?

Response: See above changes to Schedule of Items and Estimated Quantities sheet.

Consider these changes and information prior to submitting your bid on **June 6, 2018**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021739.00

Project(s): 021739.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.127 REMOVE EXISTING BITUMINOUS PAVEMENT	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	1,310.000 SY				
0030	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	110.000 T				
0040	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	123.000 T				
0050	409.15 BITUMINOUS TACK COAT - APPLIED	70.000 G				
0060	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM			26,500.00	
0070	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0080	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	344.000 SY				
0090	518.391 REPAIRING GRANITE CURB JOINT AND BEDDING MORTAR	170.000 LF				
0100	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	130.000 SF				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021739.00

Project(s): 021739.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0110	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 8 IN.	38.000 SF	_____	 _____	_____	 _____
0120	518.70 REPAIR OF OVERHEAD SURFACES < 8 IN.	10.000 SF	_____	 _____	_____	 _____
0130	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	41.000 LF	_____	 _____	_____	 _____
0140	520.243 BRIDGE JOINT MODIFICATION TYPE 3	1.000 EA	_____	 _____	_____	 _____
0150	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM		 LUMP SUM	_____	 _____
0160	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	 _____	_____	 _____
0170	627.51 6" TEMPORARY PAVEMENT TAPE, YELLOW OR WHITE	1,200.000 LF	_____	 _____	_____	 _____
0180	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	227.000 LF	_____	 _____	_____	 _____
0190	627.77 REMOVING PAVEMENT MARKINGS	367.000 SF	_____	 _____	_____	 _____
0200	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0210	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021739.00

Project(s): 021739.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0230	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	10.000 HR	_____	 _____	_____	 _____
0240	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0250	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0260	652.33 DRUM	40.000 EA	_____	 _____	_____	 _____
0270	652.34 CONE	40.000 EA	_____	 _____	_____	 _____
0280	652.35 CONSTRUCTION SIGNS	240.000 SF	_____	 _____	_____	 _____
0290	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0300	652.38 FLAGGER	200.000 HR	_____	 _____	_____	 _____
0305	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0310	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0320	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____

6/1/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 021739.00

Project(s): 021739.00

Section: 1

Total:

_____!

Total Bid:

_____!