



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

March 29, 2018
Subject: Large Culvert
Rehabilitation
State WIN: 021808.00
Location: **Owls Head**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 12 – 13, Proposal Schedule of Items, 2 pages, dated 3/1/2018, and **REPLACE** with the attached, revised Proposal Schedule of Items, 2 pages, dated 3/22/2018.

The following questions have been received:

Question: The plan shows 96' of existing pipe, with no extending of the liner pipe. Bid quantity is for 112'. Is the pipe being extended at the outlet?

Response: The proposed liner is not intended to extend past the existing structure. The correct quantity for item 509.201 is 96 LF.

Question: ADS N12 HDPE pipe meets material specification 706.06 and HP storm polypropylene pipe meets 706.10. Are these materials approved for us on this project?
Neither meet ASTM F894 and AASHTO M326

Response: AASHTO M326 applies only to outside diameter controlled polyethylene pipe and therefore is not applicable to the products mentioned above. Inside diameter controlled polyethylene pipe shall meet the requirements of ASTM F894. Polypropylene pipe will be allowed provided it meets the requirements of Standard Specification Section 706.10 and Special Provision 603 – Culvert Sliplining.

Consider these changes and information prior to submitting your bid on **April 4, 2018**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021808.00

Project(s): 021808.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	20.000 CY	_____	 _____	_____	 _____
0020	509.201 CULVERT SLIPLINING	96.000 LF	_____	 _____	_____	 _____
0030	511.07 COFFERDAM: UPSTREAM	LUMP SUM		 LUMP SUM	_____	 _____
0040	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM		 LUMP SUM	_____	 _____
0050	610.08 PLAIN RIPRAP	10.000 CY	_____	 _____	_____	 _____
0060	615.10 DIRTY BORROW	10.000 CY	_____	 _____	_____	 _____
0070	618.14 SEEDING METHOD NUMBER 2	1.000 UN	_____	 _____	_____	 _____
0080	619.12 MULCH	1.000 UN	_____	 _____	_____	 _____
0090	619.14 EROSION CONTROL MIX	10.000 CY	_____	 _____	_____	 _____
0100	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0110	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0120	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0130	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021808.00

Project(s): 021808.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0140	652.34 CONE	75.000 EA	_____	 _____	_____	 _____
0150	652.35 CONSTRUCTION SIGNS	300.000 SF	_____	 _____	_____	 _____
0160	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	30.000 CD	_____	 _____	_____	 _____
0170	652.38 FLAGGER	300.000 HR	_____	 _____	_____	 _____
0180	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0190	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____