



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Paul R. LePage  
GOVERNOR

David Bernhardt  
COMMISSIONER

April 17, 2018  
Subject: Highway Reconstruction &  
Improvements  
State WIN: 021843.00  
Location: **Wiscasset**  
**Amendment No. 1**

Dear Sir/Ms.:

The following question has been received:

**Question:** Could not find a detail of the 4' chain link fence, item #: 607.16. Is this going to have a PVC coating or galvanized finish? Are concrete footings going to be required or driven 2'6" embedment with drive anchors? Would the Department consider driving the posts to a 4' embedment in lieu of drive anchors? In areas around retaining walls, the extra post depth would help secure the posts.

**Response:** This fence will be PVC coated, black. As per the Standard Specifications, the foundations may be either concrete or metal drive anchors. Please refer to Standard Detail 607(06) for foundation depths. In areas around retaining walls, the Contractor may propose a different foundation design as part of their wall design submittal. Please refer to Retaining Wall Sheets and Standard Specification 673 – Wet Cast Small Landscape Block Wall.

Consider these changes and information prior to submitting your bid on **April 18, 2018**.

Sincerely,

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER